

## Problem 1.1

[Difficulty: 3]

---

**1.1** A number of common substances are

Tar	Sand
“Silly Putty”	Jello
Modeling clay	Toothpaste
Wax	Shaving cream

Some of these materials exhibit characteristics of both solid and fluid behavior under different conditions. Explain and give examples.

---

**Given:** Common Substances

Tar	Sand
“Silly Putty”	Jello
Modeling clay	Toothpaste
Wax	Shaving cream

Some of these substances exhibit characteristics of solids and fluids under different conditions.

**Find:** Explain and give examples.

**Solution:** Tar, Wax, and Jello behave as solids at room temperature or below at ordinary pressures. At high pressures or over long periods, they exhibit fluid characteristics. At higher temperatures, all three liquefy and become viscous fluids.

Modeling clay and silly putty show fluid behavior when sheared slowly. However, they fracture under suddenly applied stress, which is a characteristic of solids.

Toothpaste behaves as a solid when at rest in the tube. When the tube is squeezed hard, toothpaste “flows” out the spout, showing fluid behavior. Shaving cream behaves similarly.

Sand acts solid when in repose (a sand “pile”). However, it “flows” from a spout or down a steep incline.

## Problem 1.2

[Difficulty: 2]

---

**1.2** Give a word statement of each of the five basic conservation laws stated in Section 1.4, as they apply to a system.

---

**Given:** Five basic conservation laws stated in Section 1-4.

**Write:** A word statement of each, as they apply to a system.

**Solution:** Assume that laws are to be written for a *system*.

- a. Conservation of mass — The mass of a system is constant by definition.
- b. Newton's second law of motion — The net force acting on a system is directly proportional to the product of the system mass times its acceleration.
- c. First law of thermodynamics — The change in stored energy of a system equals the net energy added to the system as heat and work.
- d. Second law of thermodynamics — The entropy of any isolated system cannot decrease during any process between equilibrium states.
- e. Principle of angular momentum — The net torque acting on a system is equal to the rate of change of angular momentum of the system.

## Problem 1.3

[Difficulty: 3]

---

**1.3** The barrel of a bicycle tire pump becomes quite warm during use. Explain the mechanisms responsible for the temperature increase.

---

**Open-Ended Problem Statement:** The barrel of a bicycle tire pump becomes quite warm during use.

Explain the mechanisms responsible for the temperature increase.

**Discussion:** Two phenomena are responsible for the temperature increase: (1) friction between the pump piston and barrel and (2) temperature rise of the air as it is compressed in the pump barrel.

Friction between the pump piston and barrel converts mechanical energy (force on the piston moving through a distance) into thermal energy as a result of friction. Lubricating the piston helps to provide a good seal with the pump barrel and reduces friction (and therefore force) between the piston and barrel.

Temperature of the trapped air rises as it is compressed. The compression is not adiabatic because it occurs during a finite time interval. Heat is transferred from the warm compressed air in the pump barrel to the cooler surroundings. This raises the temperature of the barrel, making its outside surface warm (or even hot!) to the touch.

## Problem 1.4

[Difficulty: 3]

---

**1.4** Discuss the physics of skipping a stone across the water surface of a lake. Compare these mechanisms with a stone as it bounces after being thrown along a roadway.

---

**Open-Ended Problem Statement:** Consider the physics of “skipping” a stone across the water surface of a lake. Compare these mechanisms with a stone as it bounces after being thrown along a roadway.

**Discussion:** Observation and experience suggest two behaviors when a stone is thrown along a water surface:

1. If the angle between the path of the stone and the water surface is steep the stone may penetrate the water surface. Some momentum of the stone will be converted to momentum of the water in the resulting splash. After penetrating the water surface, the high drag\* of the water will slow the stone quickly. Then, because the stone is heavier than water it will sink.
2. If the angle between the path of the stone and the water surface is shallow the stone may not penetrate the water surface. The splash will be smaller than if the stone penetrated the water surface. This will transfer less momentum to the water, causing less reduction in speed of the stone. The only drag force on the stone will be from friction on the water surface. The drag will be momentary, causing the stone to lose only a portion of its kinetic energy. Instead of sinking, the stone may skip off the surface and become airborne again.

When the stone is thrown with speed and angle just right, it may skip several times across the water surface. With each skip the stone loses some forward speed. After several skips the stone loses enough forward speed to penetrate the surface and sink into the water.

Observation suggests that the shape of the stone significantly affects skipping. Essentially spherical stones may be made to skip with considerable effort and skill from the thrower. Flatter, more disc-shaped stones are more likely to skip, provided they are thrown with the flat surface(s) essentially parallel to the water surface; spin may be used to stabilize the stone in flight.

By contrast, no stone can ever penetrate the pavement of a roadway. Each collision between stone and roadway will be inelastic; friction between the road surface and stone will affect the motion of the stone only slightly. Regardless of the initial angle between the path of the stone and the surface of the roadway, the stone may bounce several times, then finally it will roll to a stop.

The shape of the stone is unlikely to affect trajectory of bouncing from a roadway significantly.

## Problem 1.5

[Difficulty: 1]

**1.5** Make a guess at the order of magnitude of the mass (e.g., 0.01, 0.1, 1.0, 10, 100, or 1000 lbm or kg) of standard air that is in a room 10 ft by 10 ft by 8 ft, and then compute this mass in lbm and kg to see how close your estimate was.

**Given:** Dimensions of a room

**Find:** Mass of air

**Solution:**

Basic equation:

$$\rho = \frac{p}{R_{\text{air}} \cdot T}$$

Given or available data

$$p = 14.7 \text{ psi}$$

$$T = (59 + 460) \text{ R}$$

$$R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$$

$$V = 10 \cdot \text{ft} \times 10 \cdot \text{ft} \times 8 \cdot \text{ft}$$

$$V = 800 \cdot \text{ft}^3$$

Then

$$\rho = \frac{p}{R_{\text{air}} \cdot T}$$

$$\rho = 0.076 \frac{\text{lbm}}{\text{ft}^3}$$

$$\rho = 0.00238 \frac{\text{slug}}{\text{ft}^3}$$

$$\rho = 1.23 \frac{\text{kg}}{\text{m}^3}$$

$$M = \rho \cdot V$$

$$M = 61.2 \cdot \text{lbm}$$

$$M = 1.90 \cdot \text{slug}$$

$$M = 27.8 \cdot \text{kg}$$

## Problem 1.6

[Difficulty: 1]

**1.6** A spherical tank of inside diameter 16 ft contains compressed oxygen at 1000 psia and 77°F. What is the mass of the oxygen?

**Given:** Data on oxygen tank.

**Find:** Mass of oxygen.

**Solution:** Compute tank volume, and then use oxygen density (Table A.6) to find the mass.

The given or available data is:  $D = 16\text{-ft}$        $p = 1000\text{-psi}$        $T = (77 + 460)\cdot R$        $T = 537\cdot R$

$$R_{O_2} = 48.29 \cdot \frac{\text{ft}\cdot\text{lbf}}{\text{lbm}\cdot R} \quad (\text{Table A.6})$$

For oxygen the critical temperature and pressure are:  $T_c = 279\cdot R$        $p_c = 725.2\cdot\text{psi}$       (data from NIST WebBook)

so the reduced temperature and pressure are:  $T_R = \frac{T}{T_c} = 1.925$        $p_R = \frac{p}{p_c} = 1.379$

Using a compressibility factor chart:  $Z = 0.948$       Since this number is close to 1, we can assume ideal gas behavior.

Therefore, the governing equation is the ideal gas equation  $p = \rho \cdot R_{O_2} \cdot T$       and       $\rho = \frac{M}{V}$

where  $V$  is the tank volume  $V = \frac{\pi \cdot D^3}{6}$        $V = \frac{\pi}{6} \times (16\text{-ft})^3$        $V = 2144.7\text{-ft}^3$

Hence  $M = V \cdot \rho = \frac{p \cdot V}{R_{O_2} \cdot T}$        $M = 1000 \cdot \frac{\text{lbf}}{\text{in}^2} \times 2144.7\text{-ft}^3 \times \frac{1}{48.29} \cdot \frac{\text{lbm}\cdot R}{\text{ft}\cdot\text{lbf}} \times \frac{1}{537} \cdot \frac{1}{R} \times \left(\frac{12\text{-in}}{\text{ft}}\right)^2$

$$M = 11910\text{-lbm}$$

## Problem 1.7

[Difficulty: 3]

**1.7** Very small particles moving in fluids are known to experience a drag force proportional to speed. Consider a particle of net weight  $W$  dropped in a fluid. The particle experiences a drag force,  $F_D = kV$ , where  $V$  is the particle speed. Determine the time required for the particle to accelerate from rest to 95 percent of its terminal speed,  $V_t$ , in terms of  $k$ ,  $W$ , and  $g$ .

**Given:** Small particle accelerating from rest in a fluid. Net weight is  $W$ , resisting force  $F_D = kV$ , where  $V$  is speed.

**Find:** Time required to reach 95 percent of terminal speed,  $V_t$ .

**Solution:** Consider the particle to be a system. Apply Newton's second law.

Basic equation:  $\sum F_y = ma_y$

Assumptions:

1.  $W$  is net weight
2. Resisting force acts opposite to  $V$

Then

$$\sum F_y = W - kV = ma_y = m \frac{dV}{dt} = \frac{W}{g} \frac{dV}{dt}$$

or

$$\frac{dV}{dt} = g \left( 1 - \frac{k}{W} V \right)$$

Separating variables,

$$\frac{dV}{1 - \frac{k}{W} V} = g dt$$

Integrating, noting that velocity is zero initially,

$$\int_0^V \frac{dV}{1 - \frac{k}{W} V} = -\frac{W}{k} \ln \left( 1 - \frac{k}{W} V \right) = \int_0^t g dt = gt$$


or

$$1 - \frac{k}{W} V = e^{-\frac{kg t}{W}}; \quad V = \frac{W}{k} \left( 1 - e^{-\frac{kg t}{W}} \right)$$

But  $V \rightarrow V_t$  as  $t \rightarrow \infty$ , so  $V_t = \frac{W}{k}$ . Therefore

$$\frac{V}{V_t} = 1 - e^{-\frac{kg t}{W}}$$

When  $\frac{V}{V_t} = 0.95$ , then  $e^{-\frac{kg t}{W}} = 0.05$  and  $\frac{kg t}{W} = 3$ . Thus  $t = 3W/gk$



## Problem 1.8

[Difficulty: 2]

**1.8** Consider again the small particle of Problem 1.7. Express the distance required to reach 95 percent of its terminal speed in percent terms of  $g$ ,  $k$ , and  $W$ .

**Given:** Small particle accelerating from rest in a fluid. Net weight is  $W$ , resisting force is  $F_D = kV$ , where  $V$  is speed.

**Find:** Distance required to reach 95 percent of terminal speed,  $V_t$ .

**Solution:** Consider the particle to be a system. Apply Newton's second law.

Basic equation:  $\sum F_y = ma_y$

Assumptions:

1.  $W$  is net weight.
2. Resisting force acts opposite to  $V$ .

Then,  $\sum F_y = W - kV = ma_y = m \frac{dV}{dt} = \frac{W}{g} V \frac{dV}{dy}$  or  $1 - \frac{k}{W} V = \frac{V}{g} \frac{dV}{dy}$

At terminal speed,  $a_y = 0$  and  $V = V_t = \frac{W}{k}$ . Then  $1 - \frac{V}{V_t} = \frac{1}{g} V \frac{dV}{dy}$

Separating variables  $\frac{V dV}{1 - \frac{V}{V_t}} = g dy$


Integrating, noting that velocity is zero initially

$$gy = \int_0^{0.95V_t} \frac{V dV}{1 - \frac{V}{V_t}} = \left[ -VV_t - V_t^2 \ln \left( 1 - \frac{V}{V_t} \right) \right]_0^{0.95V_t}$$

$$gy = -0.95V_t^2 - V_t^2 \ln(1 - 0.95) - V_t^2 \ln(1)$$

$$gy = -V_t^2 [0.95 + \ln 0.05] = 2.05 V_t^2$$

$$\therefore y = \frac{2.05}{g} V_t^2 = 2.05 \frac{W^2}{gt^2}$$





# Problem 1.10

[Difficulty: 4]

**1.10** In a combustion process, gasoline particles are to be dropped in air at 200°F. The particles must drop at least 10 in. in 1 s. Find the diameter  $d$  of droplets required for this. (The drag on these particles is given by  $F_D = \pi\mu Vd$ , where  $V$  is the particle speed and  $\mu$  is the air viscosity. To solve this problem, use *Excel's Goal Seek*.)


NOTE: Drag formula is in error: It should be:

$$F_D = 3 \cdot \pi \cdot V \cdot d$$

**Given:** Data on sphere and formula for drag.

**Find:** Diameter of gasoline droplets that take 1 second to fall 10 in.

**Solution:** Use given data and data in Appendices; integrate equation of motion by separating variables.



The data provided, or available in the Appendices, are:

$$\mu = 4.48 \times 10^{-7} \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \quad \rho_w = 1.94 \frac{\text{slug}}{\text{ft}^3} \quad SG_{\text{gas}} = 0.72 \quad \rho_{\text{gas}} = SG_{\text{gas}} \cdot \rho_w \quad \rho_{\text{gas}} = 1.40 \frac{\text{slug}}{\text{ft}^3}$$

Newton's 2nd law for the sphere (mass  $M$ ) is (ignoring buoyancy effects)

$$M \cdot \frac{dV}{dt} = M \cdot g - 3 \cdot \pi \cdot \mu \cdot V \cdot d$$

so

$$\frac{dV}{g - \frac{3 \cdot \pi \cdot \mu \cdot d}{M} \cdot V} = dt$$

Integrating twice and using limits



$$V(t) = \frac{M \cdot g}{3 \cdot \pi \cdot \mu \cdot d} \cdot \left( 1 - e^{\frac{-3 \cdot \pi \cdot \mu \cdot d}{M} \cdot t} \right) \quad x(t) = \frac{M \cdot g}{3 \cdot \pi \cdot \mu \cdot d} \cdot \left[ t + \frac{M}{3 \cdot \pi \cdot \mu \cdot d} \cdot \left( e^{\frac{-3 \cdot \pi \cdot \mu \cdot d}{M} \cdot t} - 1 \right) \right]$$

Replacing  $M$  with an expression involving diameter  $d$

$$M = \rho_{\text{gas}} \cdot \frac{\pi \cdot d^3}{6} \quad x(t) = \frac{\rho_{\text{gas}} \cdot d^2 \cdot g}{18 \cdot \mu} \cdot \left[ t + \frac{\rho_{\text{gas}} \cdot d^2}{18 \cdot \mu} \cdot \left( e^{\frac{-18 \cdot \mu}{\rho_{\text{gas}} \cdot d^2} \cdot t} - 1 \right) \right]$$

This equation must be solved for  $d$  so that  $x(1 \text{ s}) = 10 \text{ in.}$  The answer can be obtained from manual iteration, or by using *Excel's Goal Seek*.

$$d = 4.30 \times 10^{-3} \text{ in.}$$



Note That the particle quickly reaches terminal speed, so that a simpler approximate solution would be to solve  $Mg = 3\pi\mu Vd$  for  $d$ , with  $V = 0.25 \text{ m/s}$  (allowing for the fact that  $M$  is a function of  $d$ )!

## Problem 1.11

[Difficulty: 3]

**1.11** For a small particle of styrofoam ( $1 \text{ lbf/ft}^3$ ) (spherical, with diameter  $d = 0.3 \text{ mm}$ ) falling in standard air at speed  $V$ , the drag is given by  $F_D = 3\pi\mu Vd$ , where  $\mu$  is the air viscosity. Find the maximum speed starting from rest, and the time it takes to reach 95 percent of this speed. Plot the speed as a function of time.

**Given:** Data on sphere and formula for drag.

**Find:** Maximum speed, time to reach 95% of this speed, and plot speed as a function of time.

**Solution:** Use given data and data in Appendices, and integrate equation of motion by separating variables.

The data provided, or available in the Appendices, are:

$$\rho_{\text{air}} = 1.17 \frac{\text{kg}}{\text{m}^3} \quad \mu = 1.8 \times 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \quad \rho_w = 999 \frac{\text{kg}}{\text{m}^3} \quad SG_{\text{Sty}} = 0.016 \quad d = 0.3\text{-mm}$$

Then the density of the sphere is  $\rho_{\text{Sty}} = SG_{\text{Sty}} \cdot \rho_w$   $\rho_{\text{Sty}} = 16 \frac{\text{kg}}{\text{m}^3}$

The sphere mass is  $M = \rho_{\text{Sty}} \cdot \frac{\pi \cdot d^3}{6} = 16 \cdot \frac{\text{kg}}{\text{m}^3} \times \pi \times \frac{(0.0003 \cdot \text{m})^3}{6}$   $M = 2.26 \times 10^{-10} \text{kg}$

Newton's 2nd law for the steady state motion becomes (ignoring buoyancy effects)  $M \cdot g = 3 \cdot \pi \cdot V \cdot d$


so

$$V_{\text{max}} = \frac{M \cdot g}{3 \cdot \pi \cdot \mu \cdot d} = \frac{1}{3 \cdot \pi} \times 2.26 \times 10^{-10} \cdot \text{kg} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \frac{\text{m}^2}{1.8 \times 10^{-5} \cdot \text{N}\cdot\text{s}} \times \frac{1}{0.0003 \cdot \text{m}}$$
  $V_{\text{max}} = 0.0435 \frac{\text{m}}{\text{s}}$


Newton's 2nd law for the general motion is (ignoring buoyancy effects)  $M \cdot \frac{dV}{dt} = M \cdot g - 3 \cdot \pi \cdot \mu \cdot V \cdot d$

so  $\frac{dV}{g - \frac{3 \cdot \pi \cdot \mu \cdot d}{M} \cdot V} = dt$

Integrating and using limits  $V(t) = \frac{M \cdot g}{3 \cdot \pi \cdot \mu \cdot d} \cdot \left( 1 - e^{-\frac{3 \cdot \pi \cdot \mu \cdot d}{M} \cdot t} \right)$



Using the given data



The time to reach 95% of maximum speed is obtained from

$$\frac{M \cdot g}{3 \cdot \pi \cdot \mu \cdot d} \cdot \left( 1 - e^{\frac{-3 \cdot \pi \cdot \mu \cdot d}{M} \cdot t} \right) = 0.95 \cdot V_{\max}$$

so

$$t = -\frac{M}{3 \cdot \pi \cdot \mu \cdot d} \cdot \ln \left( 1 - \frac{0.95 \cdot V_{\max} \cdot 3 \cdot \pi \cdot \mu \cdot d}{M \cdot g} \right)$$

Substituting values

$$t = 0.0133 \text{ s}$$

The plot can also be done in *Excel*.

## Problem 1.12


[Difficulty: 3]

**1.12** In a pollution control experiment, minute solid particles (typical mass  $1 \times 10^{-13}$  slug) are dropped in air. The terminal speed of the particles is measured to be 0.2 ft/s. The drag of these particles is given by  $F_D = kV$ , where  $V$  is the instantaneous particle speed. Find the value of the constant  $k$ . Find the time required to reach 99 percent of terminal speed.

**Given:** Data on sphere and terminal speed.

**Find:** Drag constant  $k$ , and time to reach 99% of terminal speed.

**Solution:** Use given data; integrate equation of motion by separating variables.



The data provided are:  $M = 1 \times 10^{-13}$  slug  $V_t = 0.2 \frac{\text{ft}}{\text{s}}$

Newton's 2nd law for the general motion is (ignoring buoyancy effects)  $M \cdot \frac{dV}{dt} = M \cdot g - k \cdot V$  (1)

Newton's 2nd law for the steady state motion becomes (ignoring buoyancy effects)  $M \cdot g = k \cdot V_t$  so  $k = \frac{M \cdot g}{V_t}$

$$k = 1 \times 10^{-13} \cdot \text{slug} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{s}}{0.2 \cdot \text{ft}} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad k = 1.61 \times 10^{-11} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}}$$

To find the time to reach 99% of  $V_t$ , we need  $V(t)$ . From 1, separating variables  $\frac{dV}{g - \frac{k}{M} \cdot V} = dt$

Integrating and using limits  $t = -\frac{M}{k} \cdot \ln\left(1 - \frac{k}{M \cdot g} \cdot V\right)$

We must evaluate this when  $V = 0.99 \cdot V_t$   $V = 0.198 \cdot \frac{\text{ft}}{\text{s}}$

$$t = -1 \times 10^{-13} \cdot \text{slug} \times \frac{\text{ft}}{1.61 \times 10^{-11} \cdot \text{lb} \cdot \text{s}} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \cdot \ln\left(1 - 1.61 \times 10^{-11} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}} \times \frac{1}{1 \times 10^{-13} \cdot \text{slug}} \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \times \frac{0.198 \cdot \text{ft}}{\text{s}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb} \cdot \text{s}^2}\right)$$

$t = 0.0286 \text{ s}$

## Problem 1.13


[Difficulty: 5]

**1.13** For Problem 1.12, find the distance the particles travel before reaching 99 percent of terminal speed. Plot the distance traveled as a function of time.

**Given:** Data on sphere and terminal speed from Problem 1.12.

**Find:** Distance traveled to reach 99% of terminal speed; plot of distance versus time.

**Solution:** Use given data; integrate equation of motion by separating variables.



The data provided are:  $M = 1 \times 10^{-13} \cdot \text{slug}$   $V_t = 0.2 \cdot \frac{\text{ft}}{\text{s}}$

Newton's 2nd law for the general motion is (ignoring buoyancy effects)  $M \cdot \frac{dV}{dt} = M \cdot g - k \cdot V$  (1)

Newton's 2nd law for the steady state motion becomes (ignoring buoyancy effects)  $M \cdot g = k \cdot V_t$  so  $k = \frac{M \cdot g}{V_t}$

$$k = 1 \times 10^{-13} \cdot \text{slug} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{s}}{0.2 \cdot \text{ft}} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad k = 1.61 \times 10^{-11} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}}$$

To find the distance to reach 99% of  $V_t$ , we need  $V(y)$ . From 1:  $M \cdot \frac{dV}{dt} = M \cdot \frac{dy}{dt} \cdot \frac{dV}{dy} = M \cdot V \cdot \frac{dV}{dy} = M \cdot g - k \cdot V$

Separating variables  $\frac{V \cdot dV}{g - \frac{k}{M} \cdot V} = dy$

Integrating and using limits  $y = -\frac{M^2 \cdot g}{k^2} \cdot \ln\left(1 - \frac{k}{M \cdot g} \cdot V\right) - \frac{M}{k} \cdot V$

We must evaluate this when  $V = 0.99 \cdot V_t$   $V = 0.198 \cdot \frac{\text{ft}}{\text{s}}$

$$y = \left(1 \cdot 10^{-13} \cdot \text{slug}\right)^2 \cdot \frac{32.2 \cdot \text{ft}}{\text{s}^2} \cdot \left(\frac{\text{ft}}{1.61 \cdot 10^{-11} \cdot \text{lb} \cdot \text{s}}\right)^2 \cdot \left(\frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}\right)^2 \cdot \ln\left(1 - 1.61 \cdot 10^{-11} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}} \cdot \frac{1}{1 \cdot 10^{-13} \cdot \text{slug}} \cdot \frac{\text{s}^2}{32.2 \cdot \text{ft}} \cdot \frac{0.198 \cdot \text{ft}}{\text{s}} \cdot \frac{\text{slug} \cdot \text{ft}}{\text{lb} \cdot \text{s}^2}\right) \dots$$

$$+ 1 \cdot 10^{-13} \cdot \text{slug} \times \frac{\text{ft}}{1.61 \cdot 10^{-11} \cdot \text{lb} \cdot \text{s}} \times \frac{0.198 \cdot \text{ft}}{\text{s}} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$y = 4.49 \times 10^{-3} \cdot \text{ft}$$

Alternatively we could use the approach of Problem 1.12 and first find the time to reach terminal speed, and use this time in  $y(t)$  to find the above value of  $y$ :

From 1, separating variables  $\frac{dV}{g - \frac{k}{M} \cdot V} = dt$

Integrating and using limits  $t = -\frac{M}{k} \cdot \ln\left(1 - \frac{k}{M \cdot g} \cdot V\right)$  (2)

We must evaluate this when  $V = 0.99 \cdot V_t$   $V = 0.198 \cdot \frac{\text{ft}}{\text{s}}$

$$t = 1 \times 10^{-13} \cdot \text{slug} \times \frac{\text{ft}}{1.61 \times 10^{-11} \cdot \text{lb} \cdot \text{s}} \cdot \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \cdot \ln \left( 1 - 1.61 \times 10^{-11} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}} \times \frac{1}{1 \times 10^{-13} \cdot \text{slug}} \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \times \frac{0.198 \cdot \text{ft}}{\text{s}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb} \cdot \text{s}^2} \right)$$


$t = 0.0286 \text{ s}$

From 2, after rearranging  $V = \frac{dy}{dt} = \frac{M \cdot g}{k} \cdot \left( 1 - e^{-\frac{k}{M} \cdot t} \right)$

Integrating and using limits  $y = \frac{M \cdot g}{k} \cdot \left[ t + \frac{M}{k} \cdot \left( e^{-\frac{k}{M} \cdot t} - 1 \right) \right]$

$$y = 1 \times 10^{-13} \cdot \text{slug} \times \frac{32.2 \cdot \text{ft}}{\text{s}^2} \times \frac{\text{ft}}{1.61 \times 10^{-11} \cdot \text{lb} \cdot \text{s}} \cdot \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \cdot \left[ 0.0291 \cdot \text{s} \dots + 10^{-13} \cdot \text{slug} \cdot \frac{\text{ft}}{1.61 \times 10^{-11} \cdot \text{lb} \cdot \text{s}} \cdot \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \cdot \left( e^{-\frac{1.61 \times 10^{-11}}{1 \times 10^{-13}} \cdot 0.0291} - 1 \right) \right]$$

$$y = 4.49 \times 10^{-3} \cdot \text{ft}$$



This plot can also be presented in Excel.

## Problem 1.14

[Difficulty: 4]

**1.14** A sky diver with a mass of 70 kg jumps from an aircraft. The aerodynamic drag force acting on the sky diver is known to be  $F_D = kV^2$ , where  $k = 0.25 \text{ N}\cdot\text{s}^2/\text{m}^2$ . Determine the maximum speed of free fall for the sky diver and the speed reached after 100 m of fall. Plot the speed of the sky diver as a function of time and as a function of distance fallen.

**Given:** Data on sky diver:  $M = 70\text{ kg}$   $k = 0.25 \cdot \frac{\text{N}\cdot\text{s}^2}{\text{m}^2}$

**Find:** Maximum speed; speed after 100 m; plot speed as function of time and distance.

**Solution:** Use given data; integrate equation of motion by separating variables.


Treat the sky diver as a system; apply Newton's 2nd law:

Newton's 2nd law for the sky diver (mass  $M$ ) is (ignoring buoyancy effects):  $M \cdot \frac{dV}{dt} = M \cdot g - k \cdot V^2$  (1)

(a) For terminal speed  $V_t$ , acceleration is zero, so  $M \cdot g - k \cdot V_t^2 = 0$  so

$$V_t = \sqrt{\frac{M \cdot g}{k}}$$

$$V_t = \left( 70 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{m}^2}{0.25 \cdot \text{N} \cdot \text{s}^2} \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \times \text{m}} \right)^{\frac{1}{2}} = 52.4 \frac{\text{m}}{\text{s}}$$



(b) For  $V$  at  $y = 100$  m we need to find  $V(y)$ . From (1)  $M \cdot \frac{dV}{dt} = M \cdot \frac{dV}{dy} \cdot \frac{dy}{dt} = M \cdot V \cdot \frac{dV}{dt} = M \cdot g - k \cdot V^2$


Separating variables and integrating:

$$\int_0^V \frac{V}{1 - \frac{k \cdot V^2}{M \cdot g}} dV = \int_0^y g dy$$

so  $\ln\left(1 - \frac{k \cdot V^2}{M \cdot g}\right) = -\frac{2 \cdot k}{M} y$  or  $V^2 = \frac{M \cdot g}{k} \cdot \left(1 - e^{-\frac{2 \cdot k \cdot y}{M}}\right)$

Hence  $V(y) = V_t \cdot \left(1 - e^{-\frac{2 \cdot k \cdot y}{M}}\right)^{\frac{1}{2}}$

For  $y = 100$  m:  $V(100\text{ m}) = 52.4 \cdot \frac{\text{m}}{\text{s}} \cdot \left(1 - e^{-\frac{2 \times 0.25 \cdot \frac{\text{N} \cdot \text{s}^2}{\text{m}^2} \times 100 \cdot \text{m} \times \frac{1}{70 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}}}\right)^{\frac{1}{2}}$   $V(100\text{ m}) = 37.4 \cdot \frac{\text{m}}{\text{s}}$



(c) For  $V(t)$  we need to integrate (1) with respect to  $t$ :

$$M \cdot \frac{dV}{dt} = M \cdot g - k \cdot V^2$$

Separating variables and integrating:

$$\int_0^V \frac{V}{\frac{M \cdot g}{k} - V^2} dV = \int_0^t 1 dt$$

so


$$t = \frac{1}{2} \cdot \sqrt{\frac{M}{k \cdot g}} \cdot \ln \left( \frac{\sqrt{\frac{M \cdot g}{k}} + V}{\sqrt{\frac{M \cdot g}{k}} - V} \right) = \frac{1}{2} \cdot \sqrt{\frac{M}{k \cdot g}} \cdot \ln \left( \frac{|V_t + V|}{|V_t - V|} \right)$$

Rearranging

$$V(t) = V_t \cdot \frac{\left( e^{\frac{2 \cdot \sqrt{k \cdot g}}{M} \cdot t} - 1 \right)}{\left( e^{\frac{2 \cdot \sqrt{k \cdot g}}{M} \cdot t} + 1 \right)}$$

or

$$V(t) = V_t \cdot \tanh \left( V_t \cdot \frac{k}{M} \cdot t \right)$$



The two graphs can also be plotted in Excel.

## Problem 1.15

[Difficulty: 5]

**1.15** For Problem 1.14, the initial horizontal speed of the sky diver is 70 m/s. As she falls, the  $k$  value for the vertical drag remains as before, but the value for horizontal motion is  $k = 0.05 \text{ N} \cdot \text{s}/\text{m}^2$ . Compute and plot the 2D trajectory of the sky diver.

**Given:** Data on sky diver:  $M = 70 \cdot \text{kg}$      $k_{\text{vert}} = 0.25 \cdot \frac{\text{N} \cdot \text{s}^2}{\text{m}^2}$      $k_{\text{horiz}} = 0.05 \cdot \frac{\text{N} \cdot \text{s}^2}{\text{m}^2}$      $U_0 = 70 \cdot \frac{\text{m}}{\text{s}}$

**Find:** Plot of trajectory.

**Solution:** Use given data; integrate equation of motion by separating variables.

Treat the sky diver as a system; apply Newton's 2nd law in horizontal and vertical directions:

Vertical: Newton's 2nd law for the sky diver (mass  $M$ ) is (ignoring buoyancy effects):  $M \cdot \frac{dV}{dt} = M \cdot g - k_{\text{vert}} \cdot V^2$  (1)

For  $V(t)$  we need to integrate (1) with respect to  $t$ :

Separating variables and integrating: 
$$\int_0^V \frac{V}{\frac{M \cdot g}{k_{\text{vert}}} - V^2} dV = \int_0^t 1 dt$$

so 
$$t = \frac{1}{2} \cdot \sqrt{\frac{M}{k_{\text{vert}} \cdot g}} \cdot \ln \left( \frac{\sqrt{\frac{M \cdot g}{k_{\text{vert}}}} + V}{\sqrt{\frac{M \cdot g}{k_{\text{vert}}}} - V} \right)$$



Rearranging 
$$V(t) = \sqrt{\frac{M \cdot g}{k_{\text{vert}}}} \cdot \frac{\left( e^{\frac{2 \cdot \sqrt{k_{\text{vert}} \cdot g}}{M} \cdot t} - 1 \right)}{\left( e^{\frac{2 \cdot \sqrt{k_{\text{vert}} \cdot g}}{M} \cdot t} + 1 \right)}$$
 so 
$$V(t) = \sqrt{\frac{M \cdot g}{k_{\text{vert}}}} \cdot \tanh \left( \sqrt{\frac{k_{\text{vert}} \cdot g}{M}} \cdot t \right)$$

For  $y(t)$  we need to integrate again:  $\frac{dy}{dt} = V$  or  $y = \int V dt$

$$y(t) = \int_0^t V(t) dt = \int_0^t \sqrt{\frac{M \cdot g}{k_{\text{vert}}}} \cdot \tanh \left( \sqrt{\frac{k_{\text{vert}} \cdot g}{M}} \cdot t \right) dt = \sqrt{\frac{M \cdot g}{k_{\text{vert}}}} \cdot \ln \left( \cosh \left( \sqrt{\frac{k_{\text{vert}} \cdot g}{M}} \cdot t \right) \right)$$

$$y(t) = \sqrt{\frac{M \cdot g}{k_{\text{vert}}}} \cdot \ln \left( \cosh \left( \sqrt{\frac{k_{\text{vert}} \cdot g}{M}} \cdot t \right) \right)$$

After the first few seconds we reach steady state:



Horizontal: Newton's 2nd law for the sky diver (mass  $M$ ) is:

$$M \cdot \frac{dU}{dt} = -k_{\text{horiz}} \cdot U^2 \quad (2)$$

For  $U(t)$  we need to integrate (2) with respect to  $t$ :

Separating variables and integrating: 
$$\int_{U_0}^U \frac{1}{U^2} dU = \int_0^t -\frac{k_{\text{horiz}}}{M} dt \quad \text{so} \quad -\frac{k_{\text{horiz}}}{M} \cdot t = -\frac{1}{U} + \frac{1}{U_0}$$

Rearranging


$$U(t) = \frac{U_0}{1 + \frac{k_{\text{horiz}} \cdot U_0}{M} \cdot t}$$

For  $x(t)$  we need to integrate again:


$$\frac{dx}{dt} = U \quad \text{or} \quad x = \int U dt$$

$$x(t) = \int_0^t U(t) dt = \int_0^t \frac{U_0}{1 + \frac{k_{\text{horiz}} \cdot U_0}{M} \cdot t} dt = \frac{M}{k_{\text{horiz}}} \cdot \ln \left( \frac{k_{\text{horiz}} \cdot U_0}{M} \cdot t + 1 \right)$$

$$x(t) = \frac{M}{k_{\text{horiz}}} \cdot \ln \left( \frac{k_{\text{horiz}} \cdot U_0}{M} \cdot t + 1 \right)$$



Plotting the trajectory:



These plots can also be done in Excel.

## Problem 1.16

[Difficulty: 3]

**1.16** The English perfected the longbow as a weapon after the Medieval period. In the hands of a skilled archer, the longbow was reputed to be accurate at ranges to 100 m or more. If the maximum altitude of an arrow is less than  $h = 10$  m while traveling to a target 100 m away from the archer, and neglecting air resistance, estimate the speed and angle at which the arrow must leave the bow. Plot the required release speed and angle as a function of height  $h$ .

**Given:** Long bow at range,  $R = 100$  m. Maximum height of arrow is  $h = 10$  m. Neglect air resistance.

**Find:** Estimate of (a) speed, and (b) angle, of arrow leaving the bow.

**Plot:** (a) release speed, and (b) angle, as a function of  $h$

**Solution:** Let  $\vec{V}_0 = u_0\hat{i} + v_0\hat{j} = V_0(\cos\theta_0\hat{i} + \sin\theta_0\hat{j})$

$$\Sigma F_y = m \frac{dv}{dt} = -mg, \text{ so } v = v_0 - gt, \text{ and } t_f = 2t_{v=0} = 2v_0/g$$

Also, 
$$mv \frac{dv}{dy} = -mg, \text{ } v \, dv = -g \, dy, \text{ } 0 - \frac{v_0^2}{2} = -gh$$

Thus 
$$h = v_0^2/2g \tag{1}$$

$$\Sigma F_x = m \frac{du}{dt} = 0, \text{ so } u = u_0 = \text{const, and } R = u_0 t_f = \frac{2u_0 v_0}{g} \tag{2}$$


From Eq. 1: 
$$v_0^2 = 2gh \tag{3}$$

From Eq. 2: 
$$u_0 = \frac{gR}{2v_0} = \frac{gR}{2\sqrt{2gh}} \quad \therefore u_0^2 = \frac{gR^2}{8h}$$

Then 
$$V_0^2 = u_0^2 + v_0^2 = \frac{gR^2}{8h} + 2gh \quad \text{and} \quad V_0 = \left( 2gh + \frac{gR^2}{8h} \right)^{\frac{1}{2}} \tag{4}$$



$$V_0 = \left( 2 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 10 \text{ m} + \frac{9.81 \text{ m}}{8 \text{ s}^2} \times 100^2 \text{ m}^2 \times \frac{1}{10 \text{ m}} \right)^{\frac{1}{2}} = 37.7 \frac{\text{m}}{\text{s}}$$

From Eq. 3: 
$$v_0 = \sqrt{2gh} = V_0 \sin \theta, \theta = \sin^{-1} \frac{\sqrt{2gh}}{V_0} \tag{5}$$



$$\theta = \sin^{-1} \left[ \left( 2 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 10 \text{ m} \right)^{\frac{1}{2}} \times \frac{\text{s}}{37.7 \text{ m}} \right] = 21.8^\circ$$

Plots of  $V_0 = V_0(h)$  (Eq. 4) and  $\theta_0 = \theta_0(h)$  (Eq. 5) are presented below:



## Problem 1.17

[Difficulty: 2]

**1.17** For each quantity listed, indicate dimensions using mass as a primary dimension, and give typical SI and English units:

- (a) Power
- (b) Pressure
- (c) Modulus of elasticity
- (d) Angular velocity
- (e) Energy
- (f) Moment of a force
- (g) Momentum
- (h) Shear stress
- (i) Strain
- (j) Angular momentum

**Given:** Basic dimensions M, L, t and T.

**Find:** Dimensional representation of quantities below, and typical units in SI and English systems.

**Solution:**

(a) Power	$\text{Power} = \frac{\text{Energy}}{\text{Time}} = \frac{\text{Force} \times \text{Distance}}{\text{Time}} = \frac{F \cdot L}{t}$		
	From Newton's 2nd law    Force = Mass $\times$ Acceleration    so $F = \frac{M \cdot L}{t^2}$		
	Hence $\text{Power} = \frac{F \cdot L}{t} = \frac{M \cdot L \cdot L}{t^2 \cdot t} = \frac{M \cdot L^2}{t^3}$	$\frac{\text{kg} \cdot \text{m}^2}{\text{s}^3}$	$\frac{\text{slug} \cdot \text{ft}^2}{\text{s}^3}$
(b) Pressure	$\text{Pressure} = \frac{\text{Force}}{\text{Area}} = \frac{F}{L^2} = \frac{M \cdot L}{t^2 \cdot L^2} = \frac{M}{L \cdot t^2}$	$\frac{\text{kg}}{\text{m} \cdot \text{s}^2}$	$\frac{\text{slug}}{\text{ft} \cdot \text{s}^2}$
(c) Modulus of elasticity	$\text{Pressure} = \frac{\text{Force}}{\text{Area}} = \frac{F}{L^2} = \frac{M \cdot L}{t^2 \cdot L^2} = \frac{M}{L \cdot t^2}$	$\frac{\text{kg}}{\text{m} \cdot \text{s}^2}$	$\frac{\text{slug}}{\text{ft} \cdot \text{s}^2}$
(d) Angular velocity	$\text{AngularVelocity} = \frac{\text{Radians}}{\text{Time}} = \frac{1}{t}$	$\frac{1}{\text{s}}$	$\frac{1}{\text{s}}$
(e) Energy	$\text{Energy} = \text{Force} \times \text{Distance} = F \cdot L = \frac{M \cdot L \cdot L}{t^2} = \frac{M \cdot L^2}{t^2}$	$\frac{\text{kg} \cdot \text{m}^2}{\text{s}^2}$	$\frac{\text{slug} \cdot \text{ft}^2}{\text{s}^2}$
(f) Moment of a force	$\text{MomentOfForce} = \text{Force} \times \text{Length} = F \cdot L = \frac{M \cdot L \cdot L}{t^2} = \frac{M \cdot L^2}{t^2}$	$\frac{\text{kg} \cdot \text{m}^2}{\text{s}^2}$	$\frac{\text{slug} \cdot \text{ft}^2}{\text{s}^2}$
(g) Momentum	$\text{Momentum} = \text{Mass} \times \text{Velocity} = M \cdot \frac{L}{t} = \frac{M \cdot L}{t}$	$\frac{\text{kg} \cdot \text{m}}{\text{s}}$	$\frac{\text{slug} \cdot \text{ft}}{\text{s}}$
(h) Shear stress	$\text{ShearStress} = \frac{\text{Force}}{\text{Area}} = \frac{F}{L^2} = \frac{M \cdot L}{t^2 \cdot L^2} = \frac{M}{L \cdot t^2}$	$\frac{\text{kg}}{\text{m} \cdot \text{s}^2}$	$\frac{\text{slug}}{\text{ft} \cdot \text{s}^2}$
(i) Strain	$\text{Strain} = \frac{\text{LengthChange}}{\text{Length}} = \frac{L}{L}$	Dimensionless	
(j) Angular momentum	$\text{AngularMomentum} = \text{Momentum} \times \text{Distance} = \frac{M \cdot L}{t} \cdot L = \frac{M \cdot L^2}{t}$	$\frac{\text{kg} \cdot \text{m}^2}{\text{s}}$	$\frac{\text{slugs} \cdot \text{ft}^2}{\text{s}}$

## Problem 1.18

[Difficulty: 2]

**1.18** For each quantity listed, indicate dimensions using force as a primary dimension, and give typical SI and English units:

- (a) Power
- (b) Pressure
- (c) Modulus of elasticity
- (d) Angular velocity
- (e) Energy
- (f) Momentum
- (g) Shear stress
- (h) Specific heat
- (i) Thermal expansion coefficient
- (j) Angular momentum

**Given:** Basic dimensions F, L, t and T.

**Find:** Dimensional representation of quantities below, and typical units in SI and English systems.

**Solution:**

(a) Power	$\text{Power} = \frac{\text{Energy}}{\text{Time}} = \frac{\text{Force} \times \text{Distance}}{\text{Time}} = \frac{F \cdot L}{t}$	$\frac{N \cdot m}{s}$	$\frac{\text{lb} \cdot \text{ft}}{s}$
(b) Pressure	$\text{Pressure} = \frac{\text{Force}}{\text{Area}} = \frac{F}{L^2}$	$\frac{N}{m^2}$	$\frac{\text{lb} \cdot \text{f}}{\text{ft}^2}$
(c) Modulus of elasticity	$\text{Pressure} = \frac{\text{Force}}{\text{Area}} = \frac{F}{L^2}$	$\frac{N}{m^2}$	$\frac{\text{lb} \cdot \text{f}}{\text{ft}^2}$
(d) Angular velocity	$\text{AngularVelocity} = \frac{\text{Radians}}{\text{Time}} = \frac{1}{t}$	$\frac{1}{s}$	$\frac{1}{s}$
(e) Energy	$\text{Energy} = \text{Force} \times \text{Distance} = F \cdot L$	$N \cdot m$	$\text{lb} \cdot \text{ft}$
(f) Momentum	$\text{Momentum} = \text{Mass} \times \text{Velocity} = M \cdot \frac{L}{t}$		
	From Newton's 2nd law $\text{Force} = \text{Mass} \times \text{Acceleration}$ so $F = M \cdot \frac{L}{t^2}$ or $M = \frac{F \cdot t^2}{L}$		
	Hence $\text{Momentum} = M \cdot \frac{L}{t} = \frac{F \cdot t^2 \cdot L}{L \cdot t} = F \cdot t$	$N \cdot s$	$\text{lb} \cdot \text{s}$
(g) Shear stress	$\text{ShearStress} = \frac{\text{Force}}{\text{Area}} = \frac{F}{L^2}$	$\frac{N}{m^2}$	$\frac{\text{lb} \cdot \text{f}}{\text{ft}^2}$
(h) Specific heat	$\text{SpecificHeat} = \frac{\text{Energy}}{\text{Mass} \times \text{Temperature}} = \frac{F \cdot L}{M \cdot T} = \frac{F \cdot L}{\left(\frac{F \cdot t^2}{L}\right) \cdot T} = \frac{L^2}{t^2 \cdot T}$	$\frac{m^2}{s^2 \cdot K}$	$\frac{\text{ft}^2}{s^2 \cdot R}$
(i) Thermal expansion coefficient	$\text{ThermalExpansionCoefficient} = \frac{\text{LengthChange}}{\text{Length}} = \frac{1}{T}$	$\frac{1}{K}$	$\frac{1}{R}$
(j) Angular momentum	$\text{AngularMomentum} = \text{Momentum} \times \text{Distance} = F \cdot t \cdot L$	$N \cdot m \cdot s$	$\text{lb} \cdot \text{ft} \cdot \text{s}$

## Problem 1.19

[Difficulty: 1]

**1.19** Derive the following conversion factors:

- (a) Convert a viscosity of  $1 \text{ m}^2/\text{s}$  to  $\text{ft}^2/\text{s}$ .
- (b) Convert a power of  $100 \text{ W}$  to horsepower.
- (c) Convert a specific energy of  $1 \text{ kJ}/\text{kg}$  to  $\text{Btu}/\text{lbm}$ .

**Given:** Viscosity, power, and specific energy data in certain units

**Find:** Convert to different units

**Solution:**

Using data from tables (e.g. Table G.2)

$$(a) \quad 1 \cdot \frac{\text{m}^2}{\text{s}} = 1 \cdot \frac{\text{m}^2}{\text{s}} \times \left( \frac{\frac{1}{12} \cdot \text{ft}}{0.0254 \cdot \text{m}} \right)^2 = 10.76 \cdot \frac{\text{ft}^2}{\text{s}}$$

$$(b) \quad 100 \cdot \text{W} = 100 \cdot \text{W} \times \frac{1 \cdot \text{hp}}{746 \cdot \text{W}} = 0.134 \cdot \text{hp}$$

$$(c) \quad 1 \cdot \frac{\text{kJ}}{\text{kg}} = 1 \cdot \frac{\text{kJ}}{\text{kg}} \times \frac{1000 \cdot \text{J}}{1 \cdot \text{kJ}} \times \frac{1 \cdot \text{Btu}}{1055 \cdot \text{J}} \times \frac{0.454 \cdot \text{kg}}{1 \cdot \text{lbm}} = 0.43 \cdot \frac{\text{Btu}}{\text{lbm}}$$

## Problem 1.20

[Difficulty: 1]

**1.20** Derive the following conversion factors:

- (a) Convert a pressure of 1 psi to kPa.
- (b) Convert a volume of 1 liter to gallons.
- (c) Convert a viscosity of 1 lbf·s/ft<sup>2</sup> to N·s/m<sup>2</sup>.

**Given:** Pressure, volume and density data in certain units

**Find:** Convert to different units

**Solution:**

Using data from tables (e.g. Table G.2)

$$(a) \quad 1 \cdot \text{psi} = 1 \cdot \text{psi} \times \frac{6895 \text{ Pa}}{1 \cdot \text{psi}} \times \frac{1 \cdot \text{kPa}}{1000 \text{ Pa}} = 6.89 \text{ kPa}$$

$$(b) \quad 1 \cdot \text{liter} = 1 \cdot \text{liter} \times \frac{1 \cdot \text{quart}}{0.946 \text{ liter}} \times \frac{1 \cdot \text{gal}}{4 \cdot \text{quart}} = 0.264 \text{ gal}$$

$$(c) \quad 1 \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} = 1 \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \times \frac{4.448 \text{ N}}{1 \cdot \text{lbf}} \times \left( \frac{1 \cdot \text{ft}}{0.0254 \text{ m}} \right)^2 = 47.9 \frac{\text{N} \cdot \text{s}}{\text{m}^2}$$

## Problem 1.21

[Difficulty: 1]

**1.21** Derive the following conversion factors:

- (a) Convert a specific heat of  $4.18 \text{ kJ/kg} \cdot \text{K}$  to  $\text{Btu/lbm} \cdot ^\circ\text{R}$ .
- (b) Convert a speed of  $30 \text{ m/s}$  to  $\text{mph}$ .
- (c) Convert a volume of  $5.0 \text{ L}$  to  $\text{in}^3$ .

**Given:** Specific heat, speed, and volume data in certain units

**Find:** Convert to different units

**Solution:**

Using data from tables (e.g. Table G.2)

$$(a) \quad 4.18 \cdot \frac{\text{kJ}}{\text{kg} \cdot \text{K}} = 4.18 \cdot \frac{\text{kJ}}{\text{kg} \cdot \text{K}} \times \frac{1 \cdot \text{Btu}}{1.055 \cdot \text{kJ}} \times \frac{1 \cdot \text{kg}}{2.2046 \cdot \text{lbm}} \times \frac{1 \cdot \text{K}}{1.8 \cdot \text{R}} = 0.998 \cdot \frac{\text{Btu}}{\text{lbm} \cdot \text{R}}$$

$$(b) \quad 30 \cdot \frac{\text{m}}{\text{s}} = 30 \cdot \frac{\text{m}}{\text{s}} \times \frac{3.281 \cdot \text{ft}}{1 \cdot \text{m}} \cdot \frac{1 \cdot \text{mi}}{5280 \cdot \text{ft}} \cdot \frac{3600 \cdot \text{s}}{\text{hr}} = 67.1 \cdot \frac{\text{mi}}{\text{hr}}$$

$$(c) \quad 5 \cdot \text{L} = 5 \cdot \text{L} \times \frac{1 \cdot \text{m}^3}{1000 \cdot \text{L}} \times \left( \frac{100 \cdot \text{cm}}{1 \cdot \text{m}} \times \frac{1 \cdot \text{in}}{2.54 \cdot \text{cm}} \right)^3 = 305 \cdot \text{in}^3$$

## Problem 1.22

[Difficulty: 1]

**1.22** Express the following in SI units:

- (a) 5 acre · ft
- (b) 150 in<sup>3</sup>/s
- (c) 3 gpm
- (d) 3 mph/s

**Given:** Quantities in English Engineering (or customary) units.

**Find:** Quantities in SI units.

**Solution:** Use Table G.2 and other sources (e.g., Machinery's Handbook, Mark's Standard Handbook)

$$(a) \quad 3.7 \cdot \text{acre} \cdot \text{ft} = 3.7 \cdot \text{acre} \times \frac{4047 \cdot \text{m}^2}{1 \cdot \text{acre}} \times \frac{0.3048 \cdot \text{m}}{1 \cdot \text{ft}} = 4.56 \times 10^3 \cdot \text{m}^3$$

$$(b) \quad 150 \cdot \frac{\text{in}^3}{\text{s}} = 150 \cdot \frac{\text{in}^3}{\text{s}} \times \left( \frac{0.0254 \cdot \text{m}}{1 \cdot \text{in}} \right)^3 = 0.00246 \cdot \frac{\text{m}^3}{\text{s}}$$

$$(c) \quad 3 \cdot \text{gpm} = 3 \cdot \frac{\text{gal}}{\text{min}} \times \frac{231 \cdot \text{in}^3}{1 \cdot \text{gal}} \times \left( \frac{0.0254 \cdot \text{m}}{1 \cdot \text{in}} \right)^3 \cdot \frac{1 \cdot \text{min}}{60 \cdot \text{s}} = 0.000189 \cdot \frac{\text{m}^3}{\text{s}}$$

$$(d) \quad 3 \cdot \frac{\text{mph}}{\text{s}} = 3 \cdot \frac{\text{mile}}{\text{hr} \cdot \text{s}} \times \frac{1609 \cdot \text{m}}{1 \cdot \text{mile}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} = 1.34 \cdot \frac{\text{m}}{\text{s}^2}$$

## Problem 1.23

[Difficulty: 1]

**1.23** Express the following in SI units:

- (a) 100 cfm ( $\text{ft}^3/\text{min}$ )
- (b) 5 gal
- (c) 65 mph
- (d) 5.4 acres

**Given:** Quantities in English Engineering (or customary) units.

**Find:** Quantities in SI units.

**Solution:** Use Table G.2 and other sources (e.g., Google)

$$(a) \quad 100 \cdot \frac{\text{ft}^3}{\text{min}} = 100 \cdot \frac{\text{ft}^3}{\text{min}} \times \left( \frac{0.0254 \cdot \text{m}}{1 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^3 \times \frac{1 \cdot \text{min}}{60 \cdot \text{s}} = 0.0472 \cdot \frac{\text{m}^3}{\text{s}}$$

$$(b) \quad 5 \cdot \text{gal} = 5 \cdot \text{gal} \times \frac{231 \cdot \text{in}^3}{1 \cdot \text{gal}} \times \left( \frac{0.0254 \cdot \text{m}}{1 \cdot \text{in}} \right)^3 = 0.0189 \cdot \text{m}^3$$

$$(c) \quad 65 \cdot \text{mph} = 65 \cdot \frac{\text{mile}}{\text{hr}} \times \frac{1852 \cdot \text{m}}{1 \cdot \text{mile}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} = 29.1 \cdot \frac{\text{m}}{\text{s}}$$

$$(d) \quad 5.4 \cdot \text{acres} = 5.4 \cdot \text{acre} \times \frac{4047 \cdot \text{m}^2}{1 \cdot \text{acre}} = 2.19 \times 10^4 \cdot \text{m}^2$$

## Problem 1.24

[Difficulty: 1]

**1.24** Express the following in BG units:

- (a)  $50 \text{ m}^2$
- (b)  $250 \text{ cc}$
- (c)  $100 \text{ kW}$
- (d)  $5 \text{ kg/m}^2$

**Given:** Quantities in SI (or other) units.

**Find:** Quantities in BG units.

**Solution:** Use Table G.2.

$$(a) \quad 50 \cdot \text{m}^2 = 50 \cdot \text{m}^2 \times \left( \frac{1 \cdot \text{in}}{0.0254 \text{ m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 = 538 \cdot \text{ft}^2$$

$$(b) \quad 250 \cdot \text{cc} = 250 \cdot \text{cm}^3 \times \left( \frac{1 \cdot \text{m}}{100 \cdot \text{cm}} \times \frac{1 \cdot \text{in}}{0.0254 \text{ m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^3 = 8.83 \times 10^{-3} \cdot \text{ft}^3$$

$$(c) \quad 100 \cdot \text{kW} = 100 \cdot \text{kW} \times \frac{1000 \cdot \text{W}}{1 \cdot \text{kW}} \times \frac{1 \cdot \text{hp}}{746 \cdot \text{W}} = 134 \cdot \text{hp}$$

$$(d) \quad 5 \cdot \frac{\text{kg}}{\text{m}^2} = 5 \cdot \frac{\text{kg}}{\text{m}^2} \times \left( \frac{0.0254 \text{ m}}{1 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \times \frac{1 \cdot \text{slug}}{14.95 \cdot \text{kg}} = 0.0318 \frac{\text{slug}}{\text{ft}^2}$$

## Problem 1.25

[Difficulty: 1]

**1.25** Express the following in BG units:

- (a) 180 cc/min
- (b) 300 kW · hr
- (c) 50 N · s/m<sup>2</sup>
- (d) 40 m<sup>2</sup> · hr

**Given:** Quantities in SI (or other) units.

**Find:** Quantities in BG units.

**Solution:** Use Table G.2.

$$(a) \quad 180 \text{ cc} = 180 \text{ cm}^3 \times \left( \frac{1 \cdot \text{m}}{100 \text{ cm}} \times \frac{1 \cdot \text{in}}{0.0254 \text{ m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^3 = 6.36 \times 10^{-3} \cdot \text{ft}^3$$

$$(b) \quad 300 \text{ kW} = 300 \text{ kW} \times \frac{1000 \text{ W}}{1 \cdot \text{kW}} \times \frac{1 \cdot \text{hp}}{746 \text{ W}} = 402 \text{ hp}$$

$$(c) \quad 50 \frac{\text{N} \cdot \text{s}}{\text{m}^2} = 50 \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times \frac{1 \cdot \text{lbf}}{4.448 \text{ N}} \times \left( \frac{0.0254 \text{ m}}{1 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 = 1.044 \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$$

$$(d) \quad 40 \text{ m}^2 \cdot \text{hr} = 40 \text{ m}^2 \times \left( \frac{1 \cdot \text{in}}{0.0254 \text{ m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \cdot \text{hr} = 431 \cdot \text{ft}^2 \cdot \text{hr}$$

## Problem 1.26

[Difficulty: 2]

**1.26** While you're waiting for the ribs to cook, you muse about the propane tank of your barbecue. You're curious about the volume of propane versus the actual tank size. Find the liquid propane volume when full (the weight of the propane is specified on the tank). Compare this to the tank volume (take some measurements, and approximate the tank shape as a cylinder with a hemisphere on each end). Explain the discrepancy.

**Given:** Geometry of tank, and weight of propane.

**Find:** Volume of propane, and tank volume; explain the discrepancy.

**Solution:** Use Table G.2 and other sources (e.g., Google) as needed.

The author's tank is approximately 12 in in diameter, and the cylindrical part is about 8 in. The weight of propane specified is 17 lb.

The tank diameter is  $D = 12 \cdot \text{in}$

The tank cylindrical height is  $L = 8 \cdot \text{in}$

The mass of propane is  $m_{\text{prop}} = 17 \cdot \text{lbm}$

The specific gravity of propane is  $SG_{\text{prop}} = 0.495$

The density of water is  $\rho = 998 \frac{\text{kg}}{\text{m}^3}$

The volume of propane is given by  $V_{\text{prop}} = \frac{m_{\text{prop}}}{\rho_{\text{prop}}} = \frac{m_{\text{prop}}}{SG_{\text{prop}} \cdot \rho}$

$$V_{\text{prop}} = 17 \cdot \text{lbm} \times \frac{1}{0.495} \times \frac{\text{m}^3}{998 \cdot \text{kg}} \times \frac{0.454 \cdot \text{kg}}{1 \cdot \text{lbm}} \times \left( \frac{1 \cdot \text{in}}{0.0254 \cdot \text{m}} \right)^3 \quad V_{\text{prop}} = 953 \cdot \text{in}^3$$

The volume of the tank is given by a cylinder diameter  $D$  length  $L$ ,  $\pi D^2 L / 4$  and a sphere (two halves) given by  $\pi D^3 / 6$

$$V_{\text{tank}} = \frac{\pi \cdot D^2}{4} \cdot L + \frac{\pi \cdot D^3}{6}$$

$$V_{\text{tank}} = \frac{\pi \cdot (12 \cdot \text{in})^2}{4} \cdot 8 \cdot \text{in} + \pi \cdot \frac{(12 \cdot \text{in})^3}{6} \quad V_{\text{tank}} = 1810 \cdot \text{in}^3$$

The ratio of propane to tank volumes is  $\frac{V_{\text{prop}}}{V_{\text{tank}}} = 53\%$

This seems low, and can be explained by a) tanks are not filled completely, b) the geometry of the tank gave an overestimate of the volume (the ends are not really hemispheres, and we have not allowed for tank wall thickness).

## Problem 1.27

[Difficulty: 1]

---

**1.27** A farmer needs 4 cm of rain per week on his farm, with 10 hectares of crops. If there is a drought, how much water (L/min) will have to be supplied to maintain his crops?

---

**Given:** Acreage of land, and water needs.

**Find:** Water flow rate (L/min) to water crops.

**Solution:** Use Table G.2 and other sources (e.g., Machinery's Handbook, Mark's Standard Handbook) as needed.

The volume flow rate needed is  $Q = \frac{4 \text{ cm}}{\text{week}} \times 10 \text{ hectare}$

Performing unit conversions

$$Q = \frac{4 \text{ cm} \times 10 \text{ hectare}}{\text{week}} = \frac{0.04 \text{ m} \times 10 \text{ hectare}}{\text{week}} \times \frac{1 \times 10^4 \cdot \text{m}^2}{1 \text{ hectare}} \times \frac{1000 \text{ L}}{\text{m}^3} \times \frac{1 \cdot \text{week}}{7 \cdot \text{day}} \times \frac{1 \cdot \text{day}}{24 \cdot \text{hr}} \times \frac{1 \cdot \text{hr}}{60 \cdot \text{min}}$$
$$Q = 397 \cdot \frac{\text{L}}{\text{min}}$$

## Problem 1.28

[Difficulty: 1]

**1.28** Derive the following conversion factors:

- Convert a volume flow rate in cubic inches per minute to cubic millimeters per minute.
- Convert a volume flow rate in cubic meters per second to gallons per minute (gpm).
- Convert a volume flow rate in liters per minute to gpm.
- Convert a volume flow rate of air in standard cubic feet per minute (SCFM) to cubic meters per hour. A standard cubic foot of gas occupies one cubic foot at standard temperature and pressure ( $T=15^\circ\text{C}$  and  $p=101.3\text{ kPa}$  absolute).

**Given:** Data in given units

**Find:** Convert to different units

**Solution:**

$$(a) \quad 1 \cdot \frac{\text{in}^3}{\text{min}} = 1 \cdot \frac{\text{in}^3}{\text{min}} \times \left( \frac{0.0254\text{m}}{1 \cdot \text{in}} \times \frac{1000\text{mm}}{1 \cdot \text{m}} \right)^3 \times \frac{1 \cdot \text{min}}{60 \cdot \text{s}} = 273 \cdot \frac{\text{mm}^3}{\text{s}}$$

$$(b) \quad 1 \cdot \frac{\text{m}^3}{\text{s}} = 1 \cdot \frac{\text{m}^3}{\text{s}} \times \frac{1 \cdot \text{gal}}{4 \times 0.000946\text{m}^3} \times \frac{60 \cdot \text{s}}{1 \cdot \text{min}} = 15850 \text{ gpm}$$

$$(c) \quad 1 \cdot \frac{\text{liter}}{\text{min}} = 1 \cdot \frac{\text{liter}}{\text{min}} \times \frac{1 \cdot \text{gal}}{4 \times 0.946 \cdot \text{liter}} \times \frac{60 \cdot \text{s}}{1 \cdot \text{min}} = 0.264 \cdot \text{gpm}$$

$$(d) \quad 1 \cdot \text{SCFM} = 1 \cdot \frac{\text{ft}^3}{\text{min}} \times \left( \frac{0.0254 \cdot \text{m}}{\frac{1}{12} \cdot \text{ft}} \right)^3 \times \frac{60 \cdot \text{min}}{1 \cdot \text{hr}} = 1.70 \cdot \frac{\text{m}^3}{\text{hr}}$$

## Problem 1.29

[Difficulty: 1]

**1.29** The density of mercury is given as  $26.3 \text{ slug/ft}^3$ . Calculate the specific gravity and the specific volume in  $\text{m}^3/\text{kg}$  of the mercury. Calculate the specific weight in  $\text{lb/ft}^3$  on Earth and on the moon. Acceleration of gravity on the moon is  $5.47 \text{ ft/s}^2$ .

**Given:** Density of mercury.

**Find:** Specific gravity, volume and weight.

**Solution:** Use basic definitions

$$SG = \frac{\rho}{\rho_w} \quad \text{From Appendix A} \quad \rho_w = 1.94 \frac{\text{slug}}{\text{ft}^3} \quad \text{so} \quad SG = \frac{26.3}{1.94} \quad SG = 13.6$$

$$v = \frac{1}{\rho} \quad \text{so} \quad v = \frac{1}{26.3} \cdot \frac{\text{ft}^3}{\text{slug}} \times \left( \frac{0.3048 \text{ m}}{1 \cdot \text{ft}} \right)^3 \times \frac{1 \cdot \text{slug}}{32.2 \cdot \text{lbf}} \times \frac{1 \cdot \text{lbf}}{0.4536 \text{ kg}} \quad v = 7.37 \times 10^{-5} \frac{\text{m}^3}{\text{kg}}$$

$$\gamma = \rho \cdot g$$

$$\text{Hence on earth} \quad \gamma_E = 26.3 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{1 \cdot \text{lbf} \cdot \text{s}^2}{1 \cdot \text{slug} \cdot \text{ft}} \quad \gamma_E = 847 \frac{\text{lbf}}{\text{ft}^3}$$

$$\text{On the moon} \quad \gamma_M = 26.3 \cdot \frac{\text{slug}}{\text{ft}^3} \times 5.47 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{1 \cdot \text{lbf} \cdot \text{s}^2}{1 \cdot \text{slug} \cdot \text{ft}} \quad \gamma_M = 144 \frac{\text{lbf}}{\text{ft}^3}$$

Note that mass-based quantities are independent of gravity

## Problem 1.30

[Difficulty: 1]

**1.30** The kilogram force is commonly used in Europe as a unit of force. (As in the U.S. customary system, where 1 lbf is the force exerted by a mass of 1 lbm in standard gravity, 1 kgf is the force exerted by a mass of 1 kg in standard gravity.) Moderate pressures, such as those for auto or truck tires, are conveniently expressed in units of  $\text{kgf}/\text{cm}^2$ . Convert 32 psig to these units.

**Given:** Definition of kgf.

**Find:** Conversion from psig to  $\text{kgf}/\text{cm}^2$ .

**Solution:** Use Table G.2.

Define kgf  $\text{kgf} = 1 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2}$        $\text{kgf} = 9.81\text{N}$

Then  $32 \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{4.448\text{N}}{1 \cdot \text{lbf}} \times \frac{1 \cdot \text{kgf}}{9.81\text{N}} \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \times \frac{1 \cdot \text{ft}}{0.3048\text{m}} \times \frac{1 \cdot \text{m}}{100\text{cm}} \right)^2 = 2.25 \frac{\text{kgf}}{\text{cm}^2}$

## Problem 1.31

[Difficulty: 3]

**1.31** In Section 1.6 we learned that the Manning equation computes the flow speed  $V$  (m/s) in a canal made from unfinished concrete, given the hydraulic radius  $R_h$  (m), the channel slope  $S_0$ , and a Manning resistance coefficient constant value  $n \approx 0.014$ . For a canal with  $R_h = 7.5$  m and a slope of  $1/10$ , find the flow speed. Compare this result with that obtained using the same  $n$  value, but with  $R_h$  first converted to ft, with the answer assumed to be in ft/s. Finally, find the value of  $n$  if we wish to *correctly* use the equation for BG units (and compute  $V$  to check!).

**Given:** Information on canal geometry.

**Find:** Flow speed using the Manning equation, correctly and incorrectly!

**Solution:** Use Table G.2 and other sources (e.g., Google) as needed.

The Manning equation is 
$$V = \frac{R_h^{\frac{2}{3}} \cdot S_0^{\frac{1}{2}}}{n}$$
 which assumes  $R_h$  in meters and  $V$  in m/s.

The given data is  $R_h = 7.5 \text{ m}$        $S_0 = \frac{1}{10}$        $n = 0.014$

Hence 
$$V = \frac{7.5^{\frac{2}{3}} \cdot \left(\frac{1}{10}\right)^{\frac{1}{2}}}{0.014} \quad V = 86.5 \frac{\text{m}}{\text{s}}$$
 (Note that we don't cancel units; we just write m/s next to the answer! Note also this is a very high speed due to the extreme slope  $S_0$ .)

Using the equation incorrectly:  $R_h = 7.5 \text{ m} \times \frac{1 \cdot \text{in}}{0.0254 \cdot \text{m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}}$        $R_h = 24.6 \cdot \text{ft}$

Hence 
$$V = \frac{24.6^{\frac{2}{3}} \cdot \left(\frac{1}{10}\right)^{\frac{1}{2}}}{0.014} \quad V = 191 \frac{\text{ft}}{\text{s}}$$
 (Note that we again don't cancel units; we just write ft/s next to the answer!)

This incorrect use does not provide the correct answer  $V = 191 \frac{\text{ft}}{\text{s}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \times \frac{0.0254 \cdot \text{m}}{1 \cdot \text{in}} \quad V = 58.2 \frac{\text{m}}{\text{s}}$  which is wrong!

This demonstrates that for this "engineering" equation we must be careful in its use!

To generate a Manning equation valid for  $R_h$  in ft and  $V$  in ft/s, we need to do the following:

$$V\left(\frac{\text{ft}}{\text{s}}\right) = V\left(\frac{\text{m}}{\text{s}}\right) \times \frac{1 \cdot \text{in}}{0.0254 \cdot \text{m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} = \frac{R_h(\text{m})^{\frac{2}{3}} \cdot S_0^{\frac{1}{2}}}{n} \times \left(\frac{1 \cdot \text{in}}{0.0254 \cdot \text{m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right)$$

$$V\left(\frac{\text{ft}}{\text{s}}\right) = \frac{R_h(\text{ft})^{\frac{2}{3}} \cdot S_0^{\frac{1}{2}}}{n} \times \left(\frac{1 \cdot \text{in}}{0.0254 \cdot \text{m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right)^{-\frac{2}{3}} \times \left(\frac{1 \cdot \text{in}}{0.0254 \cdot \text{m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right) = \frac{R_h(\text{ft})^{\frac{2}{3}} \cdot S_0^{\frac{1}{2}}}{n} \times \left(\frac{1 \cdot \text{in}}{0.0254 \cdot \text{m}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right)^{\frac{1}{3}}$$

In using this equation, we ignore the units and just evaluate the conversion factor

$$\left(\frac{1}{0.0254} \cdot \frac{1}{12}\right)^{\frac{1}{3}} = 1.49$$

Hence 
$$V\left(\frac{\text{ft}}{\text{s}}\right) = \frac{1.49 \cdot R_h(\text{ft})^{\frac{2}{3}} \cdot S_0^{\frac{1}{2}}}{n}$$

Handbooks sometimes provide this form of the Manning equation for direct use with BG units. In our case we are asked to instead define a new value for n:

$$n_{\text{BG}} = \frac{n}{1.49} \quad n_{\text{BG}} = 0.0094 \quad \text{where} \quad V\left(\frac{\text{ft}}{\text{s}}\right) = \frac{R_h(\text{ft})^{\frac{2}{3}} \cdot S_0^{\frac{1}{2}}}{n_{\text{BG}}}$$

Using this equation with Rh = 24.6 ft: 
$$V = \frac{24.6^{\frac{2}{3}} \cdot \left(\frac{1}{10}\right)^{\frac{1}{2}}}{0.0094} \quad V = 284 \frac{\text{ft}}{\text{s}}$$

Converting to m/s: 
$$V = 284 \cdot \frac{\text{ft}}{\text{s}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \times \frac{0.0254 \cdot \text{m}}{1 \cdot \text{in}} \quad V = 86.6 \frac{\text{m}}{\text{s}} \quad \text{which is the correct answer!}$$

## Problem 1.32

[Difficulty: 2]

**1.32** From thermodynamics, we know that the coefficient of performance of an ideal air conditioner ( $COP_{ideal}$ ) is given by

$$COP_{ideal} = \frac{T_L}{T_H - T_L}$$

where  $T_L$  and  $T_H$  are the room and outside temperatures (absolute). If an AC is to keep a room at  $20^\circ\text{C}$  when it is  $40^\circ\text{C}$  outside, find the  $COP_{ideal}$ . Convert to an  $EER$  value, and compare this to a typical Energy Star-compliant  $EER$  value.

**Given:** Equation for  $COP_{ideal}$  and temperature data.

**Find:**  $COP_{ideal}$ ,  $EER$ , and compare to a typical Energy Star compliant  $EER$  value.

**Solution:** Use the COP equation. Then use conversions from Table G.2 or other sources (e.g., [www.energystar.gov](http://www.energystar.gov)) to find the EER.

The given data is  $T_L = (20 + 273)\cdot\text{K}$        $T_L = 293\text{-K}$        $T_H = (40 + 273)\cdot\text{K}$        $T_H = 313\text{-K}$

The  $COP_{ideal}$  is  $COP_{Ideal} = \frac{293}{313 - 293} = 14.65$

The EER is a similar measure to COP except the cooling rate (numerator) is in BTU/hr and the electrical input (denominator) is in W:

$$EER_{Ideal} = COP_{Ideal} \times \frac{\frac{\text{BTU}}{\text{hr}}}{\text{W}} \qquad EER_{Ideal} = 14.65 \times \frac{2545 \cdot \frac{\text{BTU}}{\text{hr}}}{746 \cdot \text{W}} = 50.0 \cdot \frac{\text{BTU}}{\text{hr} \cdot \text{W}}$$

This compares to Energy Star compliant values of about 15 BTU/hr/W! We have some way to go! We can define the isentropic efficiency as

$$\eta_{isen} = \frac{EER_{Actual}}{EER_{Ideal}}$$

Hence the isentropic efficiency of a very good AC is about 30%.

## Problem 1.33

[Difficulty: 2]

**1.33** The maximum theoretical flow rate (slug/s) through a supersonic nozzle is

$$\dot{m}_{\max} = 2.38 \frac{A_t p_0}{\sqrt{T_0}}$$

where  $A_t$  (ft<sup>2</sup>) is the nozzle throat area,  $p_0$  (psi) is the tank pressure, and  $T_0$  (°R) is the tank temperature. Is this equation dimensionally correct? If not, find the units of the 2.38 term. Write the equivalent equation in SI units.

**Given:** Equation for maximum flow rate.

**Find:** Whether it is dimensionally correct. If not, find units of 2.38 coefficient. Write a SI version of the equation

**Solution:** Rearrange equation to check units of 0.04 term. Then use conversions from Table G.2 or other sources (e.g., Google)

"Solving" the equation for the constant 2.38: 
$$2.38 = \frac{\dot{m}_{\max} \sqrt{T_0}}{A_t \cdot p_0}$$

Substituting the units of the terms on the right, the units of the constant are

$$\frac{\text{slug}}{\text{s}} \times \text{R}^{\frac{1}{2}} \times \frac{1}{\text{ft}^2} \times \frac{1}{\text{psi}} = \frac{\text{slug}}{\text{s}} \times \text{R}^{\frac{1}{2}} \times \frac{1}{\text{ft}^2} \times \frac{\text{in}^2}{\text{lbf}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} = \frac{\text{R}^{\frac{1}{2}} \cdot \text{in}^2 \cdot \text{s}}{\text{ft}^3}$$

$$c = 2.38 \frac{\text{R}^{\frac{1}{2}} \cdot \text{in}^2 \cdot \text{s}}{\text{ft}^3}$$

Hence the constant is actually

For BG units we could start with the equation and convert each term (e.g.,  $A_t$ ), and combine the result into a new constant, or simply convert  $c$  directly:

$$c = 2.38 \frac{\text{R}^{\frac{1}{2}} \cdot \text{in}^2 \cdot \text{s}}{\text{ft}^3} = 2.38 \frac{\text{R}^{\frac{1}{2}} \cdot \text{in}^2 \cdot \text{s}}{\text{ft}^3} \times \left( \frac{\text{K}}{1.8 \cdot \text{R}} \right)^{\frac{1}{2}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \times \frac{1 \cdot \text{ft}}{0.3048 \text{m}}$$

$$c = 0.04 \frac{\text{K}^{\frac{1}{2}} \cdot \text{s}}{\text{m}} \quad \text{so} \quad \dot{m}_{\max} = 0.04 \frac{A_t \cdot p_0}{\sqrt{T_0}} \quad \text{with } A_t \text{ in m}^2, p_0 \text{ in Pa, and } T_0 \text{ in K.}$$

## Problem 1.34

[Difficulty: 1]

**1.34** The mean free path  $\lambda$  of a molecule of gas is the average distance it travels before collision with another molecule. It is given by

$$\lambda = C \frac{m}{\rho d^2}$$

where  $m$  and  $d$  are the molecule's mass and diameter, respectively, and  $\rho$  is the gas density. What are the dimensions of constant  $C$  for a dimensionally consistent equation?

**Given:** Equation for mean free path of a molecule.

**Find:** Dimensions of  $C$  for a dimensionally consistent equation.

**Solution:** Use the mean free path equation. Then "solve" for  $C$  and use dimensions.

The mean free path equation is 
$$\lambda = C \cdot \frac{m}{\rho \cdot d^2}$$

"Solving" for  $C$ , and using dimensions 
$$C = \frac{\lambda \cdot \rho \cdot d^2}{m}$$

$$C = \frac{L \times \frac{M}{L^3} \times L^2}{M} = 0$$

The constant  $C$  is dimensionless.

## Problem 1.35

[Difficulty: 1]

**1.35** In Chapter 9 we will study aerodynamics and learn that the drag force  $F_D$  on a body is given by

$$F_D = \frac{1}{2} \rho V^2 A C_D$$

Hence the drag depends on speed  $V$ , fluid density  $\rho$ , and body size (indicated by frontal area  $A$ ) and shape (indicated by drag coefficient  $C_D$ ). What are the dimensions of  $C_D$ ?

**Given:** Equation for drag on a body.

**Find:** Dimensions of  $C_D$ .

**Solution:** Use the drag equation. Then "solve" for  $C_D$  and use dimensions.

The drag equation is 
$$F_D = \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D$$

"Solving" for  $C_D$ , and using dimensions 
$$C_D = \frac{2 \cdot F_D}{\rho \cdot V^2 \cdot A}$$

$$C_D = \frac{F}{\frac{M}{L^3} \times \left(\frac{L}{t}\right)^2 \times L^2}$$

But, From Newton's 2nd law

$$\text{Force} = \text{Mass} \cdot \text{Acceleration} \quad \text{or} \quad F = M \cdot \frac{L}{t^2}$$

Hence

$$C_D = \frac{F}{\frac{M}{L^3} \times \left(\frac{L}{t}\right)^2 \times L^2} = \frac{M \cdot L}{t^2} \times \frac{L^3}{M} \times \frac{t^2}{L^2} \times \frac{1}{L^2} = 0$$

The drag coefficient is dimensionless.

## Problem 1.36

[Difficulty: 1]

**1.36** A container weighs 3.5 lbf when empty. When filled with water at 90°F, the mass of the container and its contents is 2.5 slug. Find the weight of water in the container, and its volume in cubic feet, using data from Appendix A.

**Given:** Data on a container and added water.

**Find:** Weight and volume of water added.

**Solution:** Use Appendix A.

For the empty container  $W_c = 3.5 \text{ lbf}$

For the filled container  $M_{\text{total}} = 2.5 \text{ slug}$

The weight of water is then  $W_w = M_{\text{total}} \cdot g - W_c$

$$W_w = 2.5 \text{ slug} \times 32.2 \frac{\text{ft}}{\text{s}^2} \times \frac{1 \cdot \text{lbf} \cdot \text{s}^2}{1 \cdot \text{slug} \cdot \text{ft}} - 3.5 \text{ lbf} \qquad W_w = 77.0 \text{ lbf}$$

The temperature is  $90^\circ\text{F} = 32.2^\circ\text{C}$  and from Table A.7  $\rho = 1.93 \frac{\text{slug}}{\text{ft}^3}$

Hence  $V_w = \frac{M_w}{\rho}$  or  $V_w = \frac{W_w}{g \cdot \rho}$

$$V_w = 77.0 \text{ lbf} \times \frac{1}{32.2} \frac{\text{s}^2}{\text{ft}} \times \frac{1}{1.93} \frac{\text{ft}^3}{\text{slug}} \times \frac{1 \cdot \text{slug} \cdot \text{ft}}{1 \cdot \text{lbf} \cdot \text{s}^2} \qquad V_w = 1.24 \text{ ft}^3$$

## Problem 1.37

[Difficulty: 1]

**1.37** An important equation in the theory of vibrations is

$$m \frac{d^2x}{dt^2} + c \frac{dx}{dt} + kx = f(t)$$

where  $m$  (kg) is the mass and  $x$  (m) is the position at time  $t$  (s). For a dimensionally consistent equation, what are the dimensions of  $c$ ,  $k$ , and  $f$ ? What would be suitable units for  $c$ ,  $k$ , and  $f$  in the SI and BG systems?

**Given:** Equation for vibrations.

**Find:** Dimensions of  $c$ ,  $k$  and  $f$  for a dimensionally consistent equation. Also, suitable units in SI and BG systems.

**Solution:** Use the vibration equation to find the dimensions of each quantity

The first term of the equation is  $m \cdot \frac{d^2x}{dt^2}$

The dimensions of this are  $M \times \frac{L}{t^2}$

Each of the other terms must also have these dimensions.

Hence  $c \cdot \frac{dx}{dt} = \frac{M \cdot L}{t^2}$  so  $c \times \frac{L}{t} = \frac{M \cdot L}{t^2}$  and  $c = \frac{M}{t}$

$k \cdot x = \frac{M \cdot L}{t^2}$  so  $k \times L = \frac{M \cdot L}{t^2}$  and  $k = \frac{M}{t^2}$

$f = \frac{M \cdot L}{t^2}$

Suitable units for  $c$ ,  $k$ , and  $f$  are  $c: \frac{\text{kg}}{\text{s}} \quad \frac{\text{slug}}{\text{s}} \quad k: \frac{\text{kg}}{\text{s}^2} \quad \frac{\text{slug}}{\text{s}^2} \quad f: \frac{\text{kg} \cdot \text{m}}{\text{s}^2} \quad \frac{\text{slug} \cdot \text{ft}}{\text{s}^2}$

Note that  $c$  is a damping (viscous) friction term,  $k$  is a spring constant, and  $f$  is a forcing function. These are more typically expressed using  $F$  (force) rather than  $M$  (mass). From Newton's 2nd law:

$$F = M \cdot \frac{L}{t^2} \quad \text{or} \quad M = \frac{F \cdot t^2}{L}$$

Using this in the dimensions and units for  $c$ ,  $k$ , and  $f$  we find  $c = \frac{F \cdot t^2}{L \cdot t} = \frac{F \cdot t}{L}$   $k = \frac{F \cdot t^2}{L \cdot t^2} = \frac{F}{L}$   $f = F$

$c: \frac{\text{N} \cdot \text{s}}{\text{m}} \quad \frac{\text{lbf} \cdot \text{s}}{\text{ft}} \quad k: \frac{\text{N}}{\text{m}} \quad \frac{\text{lbf}}{\text{ft}} \quad f: \text{N} \quad \text{lbf}$

## Problem 1.38

[Difficulty: 1]

**1.38** A parameter that is often used in describing pump performance is the specific speed,  $N_{su}$ , given by

$$N_{su} = \frac{N(\text{rpm})[Q(\text{gpm})]^{1/2}}{[H(\text{ft})]^{3/4}}$$

What are the units of specific speed? A particular pump has a specific speed of 2000. What will be the specific speed in SI units (angular velocity in rad/s)?

**Given:** Specific speed in customary units

**Find:** Units; Specific speed in SI units

**Solution:**

The units are  $\frac{\text{rpm} \cdot \text{gpm}^{\frac{1}{2}}}{\text{ft}^{\frac{3}{4}}}$  or  $\frac{\text{ft}^{\frac{3}{4}}}{\text{s}^{\frac{3}{2}}}$

Using data from tables (e.g. Table G.2)

$$N_{Su} = 2000 \frac{\text{rpm} \cdot \text{gpm}^{\frac{1}{2}}}{\text{ft}^{\frac{3}{4}}}$$

$$N_{Su} = 2000 \times \frac{\text{rpm} \cdot \text{gpm}^{\frac{1}{2}}}{\text{ft}^{\frac{3}{4}}} \times \frac{2 \cdot \pi \cdot \text{rad}}{1 \cdot \text{rev}} \times \frac{1 \cdot \text{min}}{60 \cdot \text{s}} \times \left( \frac{4 \times 0.000946 \cdot \text{m}^3}{1 \cdot \text{gal}} \cdot \frac{1 \cdot \text{min}}{60 \cdot \text{s}} \right)^{\frac{1}{2}} \times \left( \frac{1}{12} \cdot \text{ft} \right)^{\frac{3}{4}}$$

$$N_{Su} = 4.06 \cdot \frac{\frac{\text{rad}}{\text{s}} \cdot \left( \frac{\text{m}^3}{\text{s}} \right)^{\frac{1}{2}}}{\text{m}^{\frac{3}{4}}}$$

## Problem 1.39

[Difficulty: 1]

**1.39** A particular pump has an "engineering" equation form of the performance characteristic equation given by  $H$  (ft) =  $1.5 - 4.5 \times 10^{-5} [Q$  (gpm)]<sup>2</sup>, relating the head  $H$  and flow rate  $Q$ . What are the units of the coefficients 1.5 and  $4.5 \times 10^{-5}$ ? Derive an SI version of this equation.

**Given:** "Engineering" equation for a pump

**Find:** SI version

**Solution:**

The dimensions of "1.5" are ft.

The dimensions of " $4.5 \times 10^{-5}$ " are ft/gpm<sup>2</sup>.

Using data from tables (e.g. Table G.2), the SI versions of these coefficients can be obtained

$$1.5 \cdot \text{ft} = 1.5 \cdot \text{ft} \times \frac{0.0254 \text{ m}}{1 \cdot \text{ft}} = 0.457 \text{ m}$$

$$4.5 \times 10^{-5} \cdot \frac{\text{ft}}{\text{gpm}^2} = 4.5 \cdot 10^{-5} \cdot \frac{\text{ft}}{\text{gpm}^2} \times \frac{0.0254 \text{ m}}{1 \cdot \text{ft}} \times \left( \frac{1 \cdot \text{gal}}{4 \cdot \text{quart}} \cdot \frac{1 \text{ quart}}{0.000946 \text{ m}^3} \cdot \frac{60 \cdot \text{s}}{1 \text{ min}} \right)^2$$

$$4.5 \cdot 10^{-5} \cdot \frac{\text{ft}}{\text{gpm}^2} = 3450 \cdot \frac{\text{m}}{\left( \frac{\text{m}^3}{\text{s}} \right)^2}$$

The equation is

$$H(\text{m}) = 0.457 - 3450 \cdot \left( Q \left( \frac{\text{m}^3}{\text{s}} \right) \right)^2$$

## Problem 1.40

[Difficulty: 2]

**1.40** Calculate the density of standard air in a laboratory from the ideal gas equation of state. Estimate the experimental uncertainty in the air density calculated for standard conditions (29.9 in. of mercury and 59°F) if the uncertainty in measuring the barometer height is  $\pm 0.1$  in. of mercury and the uncertainty in measuring temperature is  $\pm 0.5^\circ\text{F}$ . (Note that 29.9 in. of mercury corresponds to 14.7 psia.)

**Given:** Air at standard conditions –  $p = 29.9$  in Hg,  $T = 59^\circ\text{F}$

Uncertainty in  $p$  is  $\pm 0.1$  in Hg, in  $T$  is  $\pm 0.5^\circ\text{F}$

Note that 29.9 in Hg corresponds to 14.7 psia

**Find:** Air density using ideal gas equation of state; Estimate of uncertainty in calculated value.

**Solution:**

$$\rho = \frac{p}{RT} = 14.7 \frac{\text{lb}_f}{\text{in}^2} \times \frac{\text{lb} \cdot ^\circ\text{R}}{53.3 \text{ ft} \cdot \text{lb}_f} \times \frac{1}{519^\circ\text{R}} \times 144 \frac{\text{in}^2}{\text{ft}^2}$$

The uncertainty in density is given by

$$u_\rho = \left[ \left( \frac{p}{\rho} \frac{\partial \rho}{\partial p} u_p \right)^2 + \left( \frac{T}{\rho} \frac{\partial \rho}{\partial T} u_T \right)^2 \right]^{\frac{1}{2}}$$
$$\frac{p}{\rho} \frac{\partial \rho}{\partial p} = RT \frac{1}{RT} = \frac{RT}{RT} = 1; \quad u_p = \frac{\pm 0.1}{29.9} = \pm 0.334\%$$
$$\frac{T}{\rho} \frac{\partial \rho}{\partial T} = \frac{T}{\rho} \cdot -\frac{p}{RT^2} = -\frac{p}{\rho RT} = -1; \quad u_T = \frac{\pm 0.5}{460 + 59} = \pm 0.0963\%$$

Then

$$u_\rho = \left[ u_p^2 + (-u_T)^2 \right]^{\frac{1}{2}} = \pm \left[ 0.334\%^2 + (-0.0963\%)^2 \right]^{\frac{1}{2}}$$
$$u_\rho = \pm 0.348\% = \pm 2.66 \times 10^{-4} \frac{\text{lb}_m}{\text{ft}^3}$$

## Problem 1.41

[Difficulty: 2]

**1.41** Repeat the calculation of uncertainty described in Problem 1.40 for air in a hot air balloon. Assume the measured barometer height is 759 mm of mercury with an uncertainty of  $\pm 1$  mm of mercury and the temperature is  $60^\circ\text{C}$  with an uncertainty of  $\pm 1^\circ\text{C}$ . [Note that 759 mm of mercury corresponds to 101 kPa (abs).]

**Given:** Air in hot air balloon

$$p = 759 \pm 1 \text{ mm Hg} \quad T = 60 \pm 1^\circ\text{C}$$

**Find:** (a) Air density using ideal gas equation of state  
(b) Estimate of uncertainty in calculated value

**Solution:** We will apply uncertainty concepts.

**Governing Equations:**  $\rho = \frac{p}{R \cdot T}$  (Ideal gas equation of state)

$$u_R = \pm \left[ \left( \frac{x_1}{R} \frac{\partial R}{\partial x_1} u_{x_1} \right)^2 + \dots \right]^{\frac{1}{2}} \quad \text{(Propagation of Uncertainties)}$$

We can express density as:

$$\rho = 101 \cdot 10^3 \times \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{287 \cdot \text{N} \cdot \text{m}} \times \frac{1}{333 \cdot \text{K}} = 1.06 \frac{\text{kg}}{\text{m}^3} \quad \rho = 1.06 \frac{\text{kg}}{\text{m}^3}$$

So the uncertainty in the density is:

$$u_\rho = \pm \left[ \left( \frac{p}{\rho} \frac{\partial \rho}{\partial p} u_p \right)^2 + \left( \frac{T}{\rho} \frac{\partial \rho}{\partial T} u_T \right)^2 \right]^{\frac{1}{2}}$$

Solving each term separately:

$$\frac{p}{\rho} \frac{\partial \rho}{\partial p} = RT \frac{1}{RT} = 1 \quad u_p = \frac{1}{759} = 0.1318\%$$

$$\frac{T}{\rho} \frac{\partial \rho}{\partial T} = \frac{T}{\rho} \left( \frac{-p}{RT^2} \right) = -\frac{p}{RT} = -1 \quad u_T = \frac{1}{333} = 0.3003\%$$

Therefore:

$$u_\rho = \pm \left[ (u_p)^2 + (-u_T)^2 \right]^{\frac{1}{2}} = \pm \left[ (0.1318\%)^2 + (-0.3003\%)^2 \right]^{\frac{1}{2}}$$

$$u_\rho = \pm 0.328\% \left( \pm 3.47 \times 10^{-3} \frac{\text{kg}}{\text{m}^3} \right)$$

## Problem 1.42

[Difficulty: 2]

**1.42** The mass of the standard American golf ball is  $1.62 \pm 0.01$  oz and its mean diameter is  $1.68 \pm 0.01$  in. Determine the density and specific gravity of the American golf ball. Estimate the uncertainties in the calculated values.

**Given:** Standard American golf ball:  $m = 1.62 \pm 0.01 \text{ oz}$  (20 to 1)  
 $D = 1.68 \pm 0.01 \text{ in.}$  (20 to 1)

**Find:** Density and specific gravity; Estimate uncertainties in calculated values.

**Solution:** Density is mass per unit volume, so

$$\rho = \frac{m}{V} = \frac{m}{\frac{4}{3}\pi R^3} = \frac{3}{4\pi} \frac{m}{(D/2)^3} = \frac{6}{\pi} \frac{m}{D^3}$$

$$\rho = \frac{6}{\pi} \times 1.62 \text{ oz} \times \frac{1}{(1.68)^3 \text{ in.}^3} \times \frac{0.4536 \text{ kg}}{16 \text{ oz}} \times \frac{\text{in.}^3}{(0.0254)^3 \text{ m}^3} = 1130 \text{ kg/m}^3$$

and 
$$\text{SG} = \frac{\rho}{\rho_{\text{H}_2\text{O}}} = 1130 \frac{\text{kg}}{\text{m}^3} \times \frac{\text{m}^3}{1000 \text{ kg}} = 1.13$$

The uncertainty in density is given by 
$$u_\rho = \left[ \left( \frac{m}{\rho} \frac{\partial \rho}{\partial m} u_m \right)^2 + \left( \frac{D}{\rho} \frac{\partial \rho}{\partial D} u_D \right)^2 \right]^{\frac{1}{2}}$$

$$\frac{m}{\rho} \frac{\partial \rho}{\partial m} = \frac{m}{\rho} \frac{1}{V} = \frac{V}{V} = 1; \quad u_m = \frac{\pm 0.01}{1.62} = \pm 0.617\%$$

$$\frac{D}{\rho} \frac{\partial \rho}{\partial D} = \frac{D}{\rho} \cdot \left( -3 \frac{6m}{\pi D^4} \right) = -3 \frac{6}{\pi} \frac{m}{\rho D^4} = -3; \quad u_D = \frac{\pm 0.1}{1.68} = \pm 0.595\%$$

Thus

$$u_\rho = \pm \left[ u_m^2 + (-3u_D)^2 \right]^{\frac{1}{2}} = \pm \left[ 0.617\%^2 + (-3 \times 0.595\%)^2 \right]^{\frac{1}{2}} \quad u_\rho = \pm 1.89\% = \pm 21.4 \frac{\text{kg}}{\text{m}^3}$$

$$u_{\text{SG}} = u_\rho = \pm 1.89\% = \pm 0.0214$$

Finally, 
$$\rho = 1130 \pm 21.4 \text{ kg/m}^3 \quad (20 \text{ to } 1)$$

$$\text{SG} = 1.13 \pm 0.0214 \quad (20 \text{ to } 1)$$

## Problem 1.43

[Difficulty: 2]

**1.43** A can of pet food has the following internal dimensions: 102 mm height and 73 mm diameter (each  $\pm 1$  mm at odds of 20 to 1). The label lists the mass of the contents as 397 g. Evaluate the magnitude and estimated uncertainty of the density of the pet food if the mass value is accurate to  $\pm 1$  g at the same odds.

**Given:** Pet food can

$$H = 102 \pm 1 \text{ mm (20 to 1)}$$

$$D = 73 \pm 1 \text{ mm (20 to 1)}$$

$$m = 397 \pm 1 \text{ g (20 to 1)}$$

**Find:** Magnitude and estimated uncertainty of pet food density.

**Solution:** Density is

$$\rho = \frac{m}{\nabla} = \frac{m}{\pi R^2 H} = \frac{4}{\pi} \frac{m}{D^2 H} \quad \text{or} \quad \rho = \rho(m, D, H)$$

From uncertainty analysis: 
$$u_\rho = \pm \left[ \left( \frac{m}{\rho} \frac{\partial \rho}{\partial m} u_m \right)^2 + \left( \frac{D}{\rho} \frac{\partial \rho}{\partial D} u_D \right)^2 + \left( \frac{H}{\rho} \frac{\partial \rho}{\partial H} u_H \right)^2 \right]^{\frac{1}{2}}$$

Evaluating: 
$$\frac{m}{\rho} \frac{\partial \rho}{\partial m} = \frac{m}{\rho} \frac{4}{\pi} \frac{1}{D^2 H} = \frac{1}{\rho} \frac{4m}{\pi D^2 H} = 1; \quad u_m = \frac{\pm 1}{397} = \pm 0.252\%$$

$$\frac{D}{\rho} \frac{\partial \rho}{\partial D} = \frac{D}{\rho} (-2) \frac{4m}{\pi D^3 H} = (-2) \frac{1}{\rho} \frac{4m}{\pi D^2 H} = -2; \quad u_D = \frac{\pm 1}{73} = \pm 1.37\%$$

$$\frac{H}{\rho} \frac{\partial \rho}{\partial H} = \frac{H}{\rho} (-1) \frac{4m}{\pi D^2 H^2} = (-1) \frac{1}{\rho} \frac{4m}{\pi D^2 H} = -1; \quad u_H = \frac{\pm 1}{102} = \pm 0.980\%$$

Substituting: 
$$u_\rho = \pm \left[ (1 \times 0.252)^2 + (-2 \times 1.37)^2 + (-1 \times 0.980)^2 \right]^{\frac{1}{2}}$$

$$u_\rho = \pm 2.92\%$$

$$\nabla = \frac{\pi}{4} D^2 H = \frac{\pi}{4} \times (73)^2 \text{ mm}^2 \times 102 \text{ mm} \times \frac{\text{m}^3}{10^9 \text{ mm}^3} = 4.27 \times 10^{-4} \text{ m}^3$$

$$\rho = \frac{m}{\nabla} = \frac{397 \text{ g}}{4.27 \times 10^{-4} \text{ m}^3} \times \frac{\text{kg}}{1000 \text{ g}} = 930 \text{ kg/m}^3$$

Thus: 
$$\rho = 930 \pm 27.2 \text{ kg/m}^3 \text{ (20 to 1)}$$

## Problem 1.44

[Difficulty: 2]

**1.44** The mass flow rate in a water flow system determined by collecting the discharge over a timed interval is 0.2 kg/s. The scales used can be read to the nearest 0.05 kg and the stopwatch is accurate to 0.2 s. Estimate the precision with which the flow rate can be calculated for time intervals of (a) 10 s and (b) 1 min.

**Given:** Mass flow rate of water determine by collecting discharge over a timed interval is 0.2 kg/s.

Scales can be read to nearest 0.05 kg.

Stopwatch can be read to nearest 0.2 s.

**Find:** Estimate precision of flow rate calculation for time intervals of (a) 10 s, and (b) 1 min.

**Solution:** Apply methodology of uncertainty analysis, Appendix F:

$$\dot{m} = \frac{\Delta m}{\Delta t}$$

Computing equations:

$$u_{\dot{m}} = \pm \left[ \left( \frac{\Delta m}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta m} u_{\Delta m} \right)^2 + \left( \frac{\Delta t}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta t} u_{\Delta t} \right)^2 \right]^{\frac{1}{2}}$$

Thus 
$$\frac{\Delta m}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta m} = \Delta t \frac{1}{\Delta t} = 1 \quad \text{and} \quad \frac{\Delta t}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta t} = \frac{\Delta t^2}{\Delta m} \cdot -\frac{\Delta m}{\Delta t^2} = -1$$

The uncertainties are expected to be  $\pm$  half the least counts of the measuring instruments.

Tabulating results:

Time Interval, $\Delta t$ (s)	Error in $\Delta t$ (s)	Uncertainty in $\Delta t$ (%)	Water Collected, $\Delta m$ (kg)	Error in $\Delta m$ (kg)	Uncertainty in $\Delta m$ (%)	Uncertainty in $\dot{m}$ (%)
10	$\pm 0.10$	$\pm 1.0$	2.0	$\pm 0.025$	$\pm 1.25$	$\pm 1.60$
60	$\pm 0.10$	$\pm 0.167$	12.0	$\pm 0.025$	$\pm 0.208$	$\pm 0.267$

A time interval of about 15 seconds should be chosen to reduce the uncertainty in results to  $\pm 1$  percent.

## Problem 1.45

[Difficulty: 3]

**1.45** The mass flow rate of water in a tube is measured using a beaker to catch water during a timed interval. The nominal mass flow rate is 100 g/s. Assume that mass is measured using a balance with a least count of 1 g and a maximum capacity of 1 kg, and that the timer has a least count of 0.1 s. Estimate the time intervals and uncertainties in measured mass flow rate that would result from using 100, 500, and 1000 mL beakers. Would there be any advantage in using the largest beaker? Assume the tare mass of the empty 1000 mL beaker is 500 g.

**Given:** Nominal mass flow rate of water determined by collecting discharge (in a beaker) over a timed interval is  $\dot{m} = 100 \text{ g/s}$ ; Scales have capacity of 1 kg, with least count of 1 g; Timer has least count of 0.1 s; Beakers with volume of 100, 500, 1000 mL are available – tare mass of 1000 mL beaker is 500 g.

**Find:** Estimate (a) time intervals, and (b) uncertainties, in measuring mass flow rate from using each of the three beakers.

**Solution:** To estimate time intervals assume beaker is filled to maximum volume in case of 100 and 500 mL beakers and to maximum allowable mass of water (500 g) in case of 1000 mL beaker.

Then 
$$\dot{m} = \frac{\Delta m}{\Delta t} \quad \text{and} \quad \Delta t = \frac{\Delta m}{\dot{m}} = \frac{\rho \Delta V}{\dot{m}}$$

Tabulating results

$$\begin{aligned} \Delta V &= 100 \text{ mL} \quad 500 \text{ mL} \quad 1000 \text{ mL} \\ \Delta t &= 1 \text{ s} \quad 5 \text{ s} \quad 5 \text{ s} \end{aligned}$$

Apply the methodology of uncertainty analysis, Appendix E. Computing equation:

$$u_{\dot{m}} = \pm \left[ \left( \frac{\Delta m}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta m} u_{\Delta m} \right)^2 + \left( \frac{\Delta t}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta t} u_{\Delta t} \right)^2 \right]^{\frac{1}{2}}$$

The uncertainties are  $\pm$  half the least counts of the measuring instruments:  $\delta \Delta m = \pm 0.5 \text{ g}$        $\delta \Delta t = 0.05 \text{ s}$

$$\frac{\Delta m}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta m} = \Delta t \frac{1}{\Delta t} = 1 \quad \text{and} \quad \frac{\Delta t}{\dot{m}} \frac{\partial \dot{m}}{\partial \Delta t} = \frac{\Delta t^2}{\Delta m} \cdot -\frac{\Delta m}{\Delta t^2} = -1 \quad \therefore u_{\dot{m}} = \pm \left[ u_{\Delta m}^2 + (-u_{\Delta t})^2 \right]^{\frac{1}{2}}$$

Tabulating results:

Beaker Volume $\Delta V$ (mL)	Water Collected $\Delta m$ (g)	Error in $\Delta m$ (g)	Uncertainty in $\Delta m$ (%)	Time Interval $\Delta t$ (s)	Error in $\Delta t$ (s)	Uncertainty in $\Delta t$ (%)	Uncertainty in $\dot{m}$ (%)
100	100	$\pm 0.50$	$\pm 0.50$	1.0	$\pm 0.05$	$\pm 5.0$	$\pm 5.03$
500	500	$\pm 0.50$	$\pm 0.10$	5.0	$\pm 0.05$	$\pm 1.0$	$\pm 1.0$
1000	500	$\pm 0.50$	$\pm 0.10$	5.0	$\pm 0.05$	$\pm 1.0$	$\pm 1.0$

Since the scales have a capacity of 1 kg and the tare mass of the 1000 mL beaker is 500 g, there is no advantage in using the larger beaker. The uncertainty in  $\dot{m}$  could be reduced to  $\pm 0.50$  percent by using the large beaker if a scale with greater capacity the same least count were available

## Problem 1.46

[Difficulty: 2]

**1.46** The mass of the standard British golf ball is  $45.9 \pm 0.3$  g and its mean diameter is  $41.1 \pm 0.3$  mm. Determine the density and specific gravity of the British golf ball. Estimate the uncertainties in the calculated values.

**Given:** Standard British golf ball:

$$m = 45.9 \pm 0.3 \text{ g} \quad (20 \text{ to } 1)$$

$$D = 41.1 \pm 0.3 \text{ mm} \quad (20 \text{ to } 1)$$

**Find:** Density and specific gravity; Estimate of uncertainties in calculated values.

**Solution:** Density is mass per unit volume, so

$$\rho = \frac{m}{V} = \frac{m}{\frac{4}{3}\pi R^3} = \frac{3}{4\pi} \frac{m}{(D/2)^3} = \frac{6}{\pi} \frac{m}{D^3}$$

$$\rho = \frac{6}{\pi} \times 0.0459 \text{ kg} \times \frac{1}{(0.0411)^3} \text{ m}^3 = 1260 \text{ kg/m}^3$$

and

$$SG = \frac{\rho}{\rho_{H_2O}} = 1260 \frac{\text{kg}}{\text{m}^3} \times \frac{\text{m}^3}{1000 \text{ kg}} = 1.26$$

The uncertainty in density is given by

$$u_\rho = \pm \left[ \left( \frac{m}{\rho} \frac{\partial \rho}{\partial m} u_m \right)^2 + \left( \frac{D}{\rho} \frac{\partial \rho}{\partial D} u_D \right)^2 \right]^{1/2}$$

$$\frac{m}{\rho} \frac{\partial \rho}{\partial m} = \frac{m}{\rho} \frac{1}{V} = \frac{V}{V} = 1; \quad u_m = \pm \frac{0.3}{45.9} = \pm 0.654\%$$

$$\frac{D}{\rho} \frac{\partial \rho}{\partial D} = \frac{D}{\rho} \left( -3 \frac{6}{\pi} \frac{m}{D^4} \right) = -3 \left( \frac{6m}{\pi D^4} \right) = -3; \quad u_D = \pm \frac{0.3}{41.1} = \pm 0.730\%$$

Thus

$$u_\rho = \pm \left[ u_m^2 + (-3u_D)^2 \right]^{1/2} = \pm \left[ 0.654^2 + (-3 \times 0.730)^2 \right]^{1/2}$$

$$u_\rho = \pm 2.29\% = \pm 28.9 \text{ kg/m}^3$$

$$u_{SG} = u_\rho = \pm 2.29\% = \pm 0.0289$$

Summarizing

$$\rho = 1260 \pm 28.9 \text{ kg/m}^3 \quad (20 \text{ to } 1)$$

$$SG = 1.26 \pm 0.0289 \quad (20 \text{ to } 1)$$

## Problem 1.47

[Difficulty: 3]

**1.47** The estimated dimensions of a soda can are  $D = 66.0 \pm 0.5$  mm and  $H = 110 \pm 0.5$  mm. Measure the mass of a full can and an empty can using a kitchen scale or postal scale. Estimate the volume of soda contained in the can. From your measurements estimate the depth to which the can is filled and the uncertainty in the estimate. Assume the value of SG = 1.055, as supplied by the bottler.

**Given:** Soda can with estimated dimensions  $D = 66.0 \pm 0.5$  mm,  $H = 110 \pm 0.5$  mm. Soda has SG = 1.055

**Find:** Volume of soda in the can (based on measured mass of full and empty can); Estimate average depth to which the can is filled and the uncertainty in the estimate.

**Solution:** Measurements on a can of coke give

$$m_f = 386.5 \pm 0.50 \text{ g}, \quad m_e = 17.5 \pm 0.50 \text{ g} \therefore m = m_f - m_e = 369 \pm u_m \text{ g}$$

$$u_m = \left[ \left( \frac{m_f}{m} \frac{\partial m}{\partial m_f} u_{m_f} \right)^2 + \left( \frac{m_e}{m} \frac{\partial m}{\partial m_e} u_{m_e} \right)^2 \right]^{\frac{1}{2}}$$

$$u_{m_f} = \pm \frac{0.50 \text{ g}}{386.5 \text{ g}} = \pm 0.00129, \quad u_{m_e} = \pm \frac{0.50}{17.5} = 0.0286$$

$$u_m = \pm \left[ \left( \frac{386.5}{369} \times 1 \times 0.00129 \right)^2 + \left( \frac{17.5}{369} \times 1 \times 0.0286 \right)^2 \right]^{\frac{1}{2}} = \pm 0.0019$$

Density is mass per unit volume and SG =  $\rho/\rho_{\text{H}_2\text{O}}$  so

$$\forall = \frac{m}{\rho} = \frac{m}{\rho_{\text{H}_2\text{O}} \text{ SG}} = 369 \text{ g} \times \frac{\text{m}^3}{1000 \text{ kg}} \times \frac{1}{1.055} \times \frac{\text{kg}}{1000 \text{ g}} = 350 \times 10^{-6} \text{ m}^3$$

The reference value  $\rho_{\text{H}_2\text{O}}$  is assumed to be precise. Since SG is specified to three places beyond the decimal point, assume  $u_{\text{SG}} = \pm 0.001$ . Then

$$u_v = \left[ \left( \frac{m}{v} \frac{\partial v}{\partial m} u_m \right)^2 + \left( \frac{\text{SG}}{v} \frac{\partial v}{\partial \text{SG}} u_{\text{SG}} \right)^2 \right]^{\frac{1}{2}}$$

$$u_v = \pm \left[ (1 \times 0.0019)^2 + (-1 \times 0.001)^2 \right]^{\frac{1}{2}} = \pm 0.0021 = \pm 0.21\%$$

$$\forall = \frac{\pi D^2}{4} L \quad \text{or} \quad L = \frac{4\forall}{\pi D^2} = \frac{4}{\pi} \times \frac{350 \times 10^{-6} \text{ m}^3}{0.066^2 \text{ m}^2} \times \frac{10^3 \text{ mm}}{\text{m}} = 102 \text{ mm}$$

$$u_L = \left[ \left( \frac{\forall}{L} \frac{\partial L}{\partial \forall} u_{\forall} \right)^2 + \left( \frac{D}{L} \frac{\partial L}{\partial D} u_D \right)^2 \right]^{\frac{1}{2}}$$

$$\frac{\forall}{L} \frac{\partial L}{\partial \forall} = \frac{4}{\pi D^2} \frac{\pi D^2}{4} = 1$$

$$\frac{D}{L} \frac{\partial L}{\partial D} = \frac{D}{L} \cdot -2 \frac{4\forall}{\pi D^3} = -2 \frac{4\forall}{\pi D^2 L} = -2; \quad u_D = \pm \frac{0.5}{66} = \pm 0.0076$$

$$u_L = \pm \left[ (1 \times 0.0021)^2 + (-2 \times 0.0076)^2 \right]^{\frac{1}{2}} = \pm 0.0153 = \pm 1.53\%$$

Notes:

1. Printing on the can states the content as 355 ml. This suggests that the implied accuracy of the SG value may be over stated.
2. Results suggest that over seven percent of the can height is void of soda.

## Problem 1.48

[Difficulty: 3]

**1.48** From Appendix A, the viscosity  $\mu$  ( $\text{N}\cdot\text{s}/\text{m}^2$ ) of water at temperature  $T$  (K) can be computed from  $\mu = A10^{B/(T-C)}$ , where  $A = 2.414 \times 10^{-5} \text{ N}\cdot\text{s}/\text{m}^2$ ,  $B = 247.8 \text{ K}$ , and  $C = 140 \text{ K}$ . Determine the viscosity of water at  $30^\circ\text{C}$ , and estimate its uncertainty if the uncertainty in temperature measurement is  $\pm 0.5^\circ\text{C}$ .

**Given:** Data on water

**Find:** Viscosity; Uncertainty in viscosity

**Solution:**

The data is:  $A = 2.414 \times 10^{-5} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$        $B = 247.8 \text{ K}$        $C = 140 \cdot \text{K}$        $T = 303 \cdot \text{K}$

The uncertainty in temperature is  $u_T = \frac{0.5 \text{ K}}{293 \text{ K}}$        $u_T = 0.171\%$

Also  $\mu(T) = A \cdot 10^{\frac{B}{(T-C)}}$       Evaluating  $\mu(293 \text{ K}) = 1.005 \times 10^{-3} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

For the uncertainty  $\frac{d}{dT}\mu(T) = -\frac{A \cdot B \cdot \ln(10)}{10^{\frac{B}{C-T}} \cdot (C-T)^2}$

Hence  $u_{\mu(T)} = \left| \frac{T}{\mu(T)} \cdot \frac{d}{dT}\mu(T) \cdot u_T \right| = \frac{\ln(10) \cdot |B \cdot T \cdot u_T|}{(|C-T|)^2}$       Evaluating  $u_{\mu(T)} = 1.11\%$

## Problem 1.49


[Difficulty: 4]

**1.49** Using the nominal dimensions of the soda can given in Problem 1.47, determine the precision with which the diameter and height must be measured to estimate the volume of the can within an uncertainty of  $\pm 0.5$  percent.

**Given:** Dimensions of soda can:  $D = 66 \text{ mm}$ ,  $H = 110 \text{ mm}$

**Find:** Measurement precision needed to allow volume to be estimated with an uncertainty of  $\pm 0.5$  percent or less.

**Solution:** Use the methods of Appendix F:



Computing equations:

$$\mathcal{V} = \frac{\pi D^2 H}{4}$$

$$u_{\mathcal{V}} = \pm \left[ \left( \frac{H}{\mathcal{V}} \frac{\partial \mathcal{V}}{\partial H} u_H \right)^2 + \left( \frac{D}{\mathcal{V}} \frac{\partial \mathcal{V}}{\partial D} u_D \right)^2 \right]^{\frac{1}{2}}$$

Since  $\mathcal{V} = \frac{\pi D^2 H}{4}$ , then  $\frac{\partial \mathcal{V}}{\partial H} = \frac{\pi D^2}{4}$  and  $\frac{\partial \mathcal{V}}{\partial D} = \frac{\pi D H}{2}$ . Letting  $u_D = \pm \frac{\delta x}{D}$  and  $u_H = \pm \frac{\delta x}{H}$ , and substituting,

$$u_{\mathcal{V}} = \pm \left[ \left( \frac{4H}{\pi D^2 H} \frac{\pi D^2}{4} \frac{\delta x}{H} \right)^2 + \left( \frac{4D}{\pi D^2 H} \frac{\pi D H}{2} \frac{\delta x}{D} \right)^2 \right]^{\frac{1}{2}} = \pm \left[ \left( \frac{\delta x}{H} \right)^2 + \left( \frac{2\delta x}{D} \right)^2 \right]^{\frac{1}{2}}$$

Solving,

$$u_{\mathcal{V}}^2 = \left( \frac{\delta x}{H} \right)^2 + \left( \frac{2\delta x}{D} \right)^2 = (\delta x)^2 \left[ \left( \frac{1}{H} \right)^2 + \left( \frac{2}{D} \right)^2 \right]$$

$$\delta x = \pm \frac{u_{\mathcal{V}}}{\left[ \left( \frac{1}{H} \right)^2 + \left( \frac{2}{D} \right)^2 \right]^{\frac{1}{2}}} = \pm \frac{0.005}{\left[ \left( \frac{1}{110 \text{ mm}} \right)^2 + \left( \frac{2}{66 \text{ mm}} \right)^2 \right]^{\frac{1}{2}}} = \pm 0.158 \text{ mm}$$

Check:

$$u_H = \pm \frac{\delta x}{H} = \pm \frac{0.158 \text{ mm}}{110 \text{ mm}} = \pm 1.44 \times 10^{-3}$$

$$u_D = \pm \frac{\delta x}{D} = \pm \frac{0.158 \text{ mm}}{66 \text{ mm}} = \pm 2.39 \times 10^{-3}$$

$$u_{\mathcal{V}} = \pm [(u_H)^2 + (2u_D)^2]^{\frac{1}{2}} = \pm [(0.00144)^2 + (0.00478)^2]^{\frac{1}{2}} = \pm 0.00499$$

If  $\delta x$  represents half the least count, a minimum resolution of about  $2 \delta x \approx 0.32 \text{ mm}$  is needed.

## Problem 1.50

[Difficulty: 3]

**1.50** An enthusiast magazine publishes data from its road tests on the lateral acceleration capability of cars. The measurements are made using a 150-ft-diameter skid pad. Assume the vehicle path deviates from the circle by  $\pm 2$  ft and that the vehicle speed is read from a fifth-wheel speed-measuring system to  $\pm 0.5$  mph. Estimate the experimental uncertainty in a reported lateral acceleration of  $0.7 g$ . How would you improve the experimental procedure to reduce the uncertainty?

**Given:** Lateral acceleration,  $a = 0.70 g$ , measured on 150-ft diameter skid pad; Uncertainties in Path deviation  $\pm 2$  ft; vehicle speed  $\pm 0.5$  mph

**Find:** Estimate uncertainty in lateral acceleration; how could experimental procedure be improved?

**Solution:** Lateral acceleration is given by  $a = V^2/R$ .

From Appendix F,  $u_a = \pm[(2u_v)^2 + (u_R)^2]^{1/2}$

From the given data,  $V^2 = aR$ ;  $V = \sqrt{aR} = \sqrt{0.70 \times 32.2 \frac{\text{ft}}{\text{s}^2} \times 75 \text{ ft}} = 41.1 \frac{\text{ft}}{\text{s}}$

Then  $u_v = \pm \frac{\delta V}{V} = \pm 0.5 \frac{\text{mi}}{\text{hr}} \times \frac{\text{s}}{41.1 \text{ ft}} \times 5280 \frac{\text{ft}}{\text{mi}} \times \frac{\text{hr}}{3600 \text{ s}} = \pm 0.0178$

and  $u_R = \pm \frac{\delta R}{R} = \pm 2 \text{ ft} \times \frac{1}{75 \text{ ft}} = \pm 0.0267$

so

$$u_a = \pm [(2 \times 0.0178)^2 + (0.0267)^2]^{1/2} = \pm 0.0445$$

$$u_a = \pm 4.45 \text{ percent}$$

Experimental procedure could be improved by using a larger circle, assuming the absolute errors in measurement are constant.

For

$$D = 400 \text{ ft}; \quad R = 200 \text{ ft}$$

$$V^2 = aR; \quad V = \sqrt{aR} = \sqrt{0.70 \times 32.2 \frac{\text{ft}}{\text{s}^2} \times 200 \text{ ft}} = 67.1 \frac{\text{ft}}{\text{s}} = 45.8 \text{ mph}$$

$$u_v = \pm \frac{0.5}{45.8} = \pm 0.0109; \quad u_R = \pm \frac{2}{200} = \pm 0.0100$$

$$u_a = \pm [(2 \times 0.0109)^2 + 0.0100^2]^{1/2} = \pm 0.0240 = \pm 2.4\%$$

## Problem 1.51

[Difficulty: 4]

**1.51** The height of a building may be estimated by measuring the horizontal distance to a point on the ground and the angle from this point to the top of the building. Assuming these measurements are  $L = 100 \pm 0.5$  ft and  $\theta = 30 \pm 0.2^\circ$ , estimate the height  $H$  of the building and the uncertainty in the estimate. For the same building height and measurement uncertainties, use *Excel's Solver* to determine the angle (and the corresponding distance from the building) at which measurements should be made to minimize the uncertainty in estimated height. Evaluate and plot the optimum measurement angle as a function of building height for  $50 \leq H \leq 1000$  ft.

**Given:** Data on length and angle measurements

**Find:** Height; Angle for minimum uncertainty in height; Plot

**Solution:**

The data is:  $L = 100$ -ft       $\delta L = 0.5$ -ft       $\theta = 30$ -deg       $\delta\theta = 0.2$ -deg

Uncertainties:  $u_L = \frac{\delta L}{L}$        $u_L = 0.5\%$        $u_\theta = \frac{\delta\theta}{\theta}$        $u_\theta = 0.667\%$

The height is:  $H = L \cdot \tan(\theta)$        $H = 57.7$ -ft      with uncertainty       $u_H = \sqrt{\left(\frac{L}{H} \cdot \frac{\partial}{\partial L} H \cdot u_L\right)^2 + \left(\frac{\theta}{H} \cdot \frac{\partial}{\partial \theta} H \cdot u_\theta\right)^2}$

Hence with  $\frac{\partial}{\partial L} H = \tan(\theta)$        $\frac{\partial}{\partial \theta} H = L \cdot (1 + \tan(\theta)^2)$        $u_H = \sqrt{\left(\frac{L}{H} \cdot \tan(\theta) \cdot u_L\right)^2 + \left[\frac{L \cdot \theta}{H} \cdot (1 + \tan(\theta)^2) \cdot u_\theta\right]^2}$

Evaluating       $u_H = 0.949\%$       and       $\delta H = u_H \cdot H$        $\delta H = 0.548$ -ft

The height is then  $H = 57.7$ -ft +/-  $\delta H = 0.548$ -ft

To plot  $u_H$  versus  $\theta$  for a given  $H$  we need to replace  $L$ ,  $u_L$  and  $u_\theta$  with functions of  $\theta$ . Doing this and simplifying

$$u_H(\theta) = \sqrt{\left(\tan(\theta) \cdot \frac{\delta L}{H}\right)^2 + \left[\frac{\delta\theta}{\tan(\theta)} \cdot (1 + \tan(\theta)^2)\right]^2}$$


Given data:

$$\begin{aligned} H &= 57.7 && \text{ft} \\ \delta L &= 0.5 && \text{ft} \\ \delta\theta &= 0.2 && \text{deg} \end{aligned}$$

For this building height, we are to vary  $\theta$  (and therefore  $L$ ) to minimize the uncertainty  $u_H$ .

Plotting  $u_H$  vs  $\theta$

$\theta$ (deg)	$u_H$
5	4.02%
10	2.05%
15	1.42%
20	1.13%
25	1.00%
30	0.95%
35	0.96%
40	1.02%
45	1.11%
50	1.25%
55	1.44%
60	1.70%
65	2.07%
70	2.62%
75	3.52%
80	5.32%
85	10.69%




Optimizing using *Solver*

$\theta$ (deg)	$u_H$
31.4	0.947%

To find the optimum  $\theta$  as a function of building height  $H$  we need a more complex *Solver*

$H$ (ft)	$\theta$ (deg)	$u_H$
50	29.9	0.992%
75	34.3	0.877%
100	37.1	0.818%
125	39.0	0.784%
175	41.3	0.747%
200	42.0	0.737%
250	43.0	0.724%
300	43.5	0.717%
400	44.1	0.709%
500	44.4	0.705%
600	44.6	0.703%
700	44.7	0.702%
800	44.8	0.701%
900	44.8	0.700%
1000	44.9	0.700%



Use *Solver* to vary ALL  $\theta$ 's to minimize the total  $u_H$ !

Total  $u_H$ 's:

## Problem 1.52

[Difficulty: 4]

**1.52** An American golf ball is described in Problem 1.42. Assuming the measured mass and its uncertainty as given, determine the precision to which the diameter of the ball must be measured so the density of the ball may be estimated within an uncertainty of  $\pm 1$  percent.

**Given:** American golf ball,  $m = 1.62 \pm 0.01$  oz,  $D = 1.68$  in.

**Find:** Precision to which  $D$  must be measured to estimate density within uncertainty of  $\pm 1$  percent.

**Solution:** Apply uncertainty concepts

Definition: Density,  $\rho \equiv \frac{m}{V}$   $V = \frac{4}{3}\pi R^3 = \frac{\pi D^3}{6}$

Computing equation: 
$$u_R = \pm \left[ \left( \frac{x_1}{R} \frac{\partial R}{\partial x_1} u_{x_1} \right)^2 + \dots \right]^{\frac{1}{2}}$$

From the definition,

$$\rho = \frac{m}{\pi D^{3/6}} = \frac{6m}{\pi D^3} = \rho(m, D)$$

Thus  $\frac{m}{\rho} \frac{\partial \rho}{\partial m} = 1$  and  $\frac{D}{\rho} \frac{\partial \rho}{\partial D} = 3$ , so

$$u_\rho = \pm [(1 u_m)^2 + (3 u_D)^2]^{\frac{1}{2}}$$
$$u_\rho^2 = u_m^2 + 9 u_D^2$$

Solving,

$$u_D = \pm \frac{1}{3} [u_\rho^2 - u_m^2]^{\frac{1}{2}}$$

From the data given,

$$u_\rho = \pm 0.0100$$

$$u_m = \frac{\pm 0.01 \text{ oz}}{1.62 \text{ oz}} = \pm 0.00617$$

$$u_D = \pm \frac{1}{3} [(0.0100)^2 - (0.00617)^2]^{\frac{1}{2}} = \pm 0.00262 \text{ or } \pm 0.262\%$$

Since  $u_D = \pm \frac{\delta D}{D}$ , then

$$\delta D = \pm D u_D = \pm 1.68 \text{ in.} \cdot 0.00262 = \pm 0.00441 \text{ in.}$$

The ball diameter must be measured to a precision of  $\pm 0.00441$  in. ( $\pm 0.112$  mm) or better to estimate density within  $\pm 1$  percent. A micrometer or caliper could be used.

## Problem 1.53

[Difficulty: 5]

**1.53** A syringe pump is to dispense liquid at a flow rate of 100 mL/min. The design for the piston drive is such that the uncertainty of the piston speed is 0.001 in./min, and the cylinder bore diameter has a maximum uncertainty of 0.0005 in. Plot the uncertainty in the flow rate as a function of cylinder bore. Find the combination of piston speed and bore that minimizes the uncertainty in the flow rate.

**Given:** Syringe pump to deliver 100 mL/min       $\delta V = 0.001 \frac{\text{in}}{\text{min}}$        $\delta D = 0.0005 \cdot \text{in}$

**Find:** (a) Plot uncertainty in flow rate as a function of bore.  
 (b) Find combination of piston speed and bore resulting in minimum uncertainty in flow rate.

**Solution:** We will apply uncertainty concepts.

**Governing Equations:**  $Q = \frac{\pi}{4} \cdot D^2 \cdot V$  (Flow rate in syringe pump)

$$u_R = \pm \left[ \left( \frac{x_1}{R} \frac{\partial R}{\partial x_1} u_{x_1} \right)^2 + \dots \right]^{\frac{1}{2}} \quad \text{(Propagation of Uncertainties)}$$

Now solving for the piston speed in terms of the bore:  $V(D) = \frac{4 \cdot Q}{\pi \cdot D^2}$

So the uncertainty in the flow rate is:  $u_Q = \pm \left[ \left( \frac{D}{Q} \frac{\partial Q}{\partial D} u_D \right)^2 + \left( \frac{V}{Q} \frac{\partial Q}{\partial V} u_V \right)^2 \right]^{\frac{1}{2}} = \pm \left[ \left( \frac{D}{Q} \frac{2Q}{D} u_D \right)^2 + \left( \frac{V}{Q} \frac{Q}{V} u_V \right)^2 \right]^{\frac{1}{2}}$


$u_Q = \pm \left[ (2u_D)^2 + (u_V)^2 \right]^{\frac{1}{2}}$  where  $u_D = \frac{\delta D}{D}$      $u_V = \frac{\delta V}{V}$     The uncertainty is minimized when  $\frac{\partial u_Q}{\partial D} = 0$

Substituting expressions in terms of bore we get:  $D_{\text{opt}} = \left[ \frac{32}{\pi^2} \cdot \left( \frac{\delta D \cdot Q}{\delta V} \right)^2 \right]^{\frac{1}{6}}$

Substituting all known values yields  $D_{\text{opt}} = 1.76 \cdot \text{in}$

Plugging this into the expression for the piston speed yields  $V_{\text{opt}} = 2.50 \cdot \frac{\text{in}}{\text{min}}$  and the uncertainty is  $u_{\text{opt}} = 0.0694 \cdot \%$

Graphs of the piston speed and the uncertainty in the flowrate as a function of the bore are shown on the following page.



## Problem 2.1

[Difficulty: 1]

**2.1** For the velocity fields given below, determine:

a. whether the flow field is one-, two-, or three-dimensional, and why.

b. whether the flow is steady or unsteady, and why.

(The quantities  $a$  and  $b$  are constants.)

$$\begin{aligned} (1) \quad \vec{V} &= [(ax + t)e^{by}] \hat{i} & (2) \quad \vec{V} &= (ax - by) \hat{i} \\ (3) \quad \vec{V} &= ax \hat{i} + [e^{bx}] \hat{j} & (4) \quad \vec{V} &= ax \hat{i} + bx^2 \hat{j} + ax \hat{k} \\ (5) \quad \vec{V} &= ax \hat{i} + [e^{bx}] \hat{j} & (6) \quad \vec{V} &= ax \hat{i} + bx^2 \hat{j} + ay \hat{k} \\ (7) \quad \vec{V} &= ax \hat{i} + [e^{bx}] \hat{j} + ay \hat{k} & (8) \quad \vec{V} &= ax \hat{i} + [e^{by}] \hat{j} + az \hat{k} \end{aligned}$$

**Given:** Velocity fields

**Find:** Whether flows are 1, 2 or 3D, steady or unsteady.

**Solution:**

(1)	$\vec{V} = \vec{V}(x, y)$	2D	$\vec{V} = \vec{V}(t)$	Unsteady
(2)	$\vec{V} = \vec{V}(x, y)$	2D	$\vec{V} \neq \vec{V}(t)$	Steady
(3)	$\vec{V} = \vec{V}(x)$	1D	$\vec{V} \neq \vec{V}(t)$	Steady
(4)	$\vec{V} = \vec{V}(x)$	1D	$\vec{V} \neq \vec{V}(t)$	Steady
(5)	$\vec{V} = \vec{V}(x)$	1D	$\vec{V} = \vec{V}(t)$	Unsteady
(6)	$\vec{V} = \vec{V}(x, y)$	2D	$\vec{V} \neq \vec{V}(t)$	Steady
(7)	$\vec{V} = \vec{V}(x, y)$	2D	$\vec{V} = \vec{V}(t)$	Unsteady
(8)	$\vec{V} = \vec{V}(x, y, z)$	3D	$\vec{V} \neq \vec{V}(t)$	Steady

## Problem 2.2

[Difficulty: 1]

**2.2** For the velocity fields given below, determine:

a. whether the flow field is one-, two-, or three-dimensional, and why.

b. whether the flow is steady or unsteady, and why.

(The quantities  $a$  and  $b$  are constants.)

(1)  $\vec{V} = [ay^2e^{-bx}]i$       (2)  $\vec{V} = ax^2i + bxj + ck$

(3)  $\vec{V} = axyi - bytj$       (4)  $\vec{V} = axi - byj + ctk$

(5)  $\vec{V} = [ae^{-bx}]i + bt^2j$       (6)  $\vec{V} = a(x^2 + y^2)^{1/2}(1/z^3)k$

(7)  $\vec{V} = (ax + t)i - by^2j$       (8)  $\vec{V} = ax^2i + bxzj + cyk$

**Given:** Velocity fields

**Find:** Whether flows are 1, 2 or 3D, steady or unsteady.

**Solution:**

(1)	$\vec{V} = \vec{V}(y)$	1D	$\vec{V} = \vec{V}(t)$	Unsteady
(2)	$\vec{V} = \vec{V}(x)$	1D	$\vec{V} \neq \vec{V}(t)$	Steady
(3)	$\vec{V} = \vec{V}(x, y)$	2D	$\vec{V} = \vec{V}(t)$	Unsteady
(4)	$\vec{V} = \vec{V}(x, y)$	2D	$\vec{V} = \vec{V}(t)$	Unsteady
(5)	$\vec{V} = \vec{V}(x)$	1D	$\vec{V} = \vec{V}(t)$	Unsteady
(6)	$\vec{V} = \vec{V}(x, y, z)$	3D	$\vec{V} \neq \vec{V}(t)$	Steady
(7)	$\vec{V} = \vec{V}(x, y)$	2D	$\vec{V} = \vec{V}(t)$	Unsteady
(8)	$\vec{V} = \vec{V}(x, y, z)$	3D	$\vec{V} \neq \vec{V}(t)$	Steady

## Problem 2.3


[Difficulty: 2]

**2.3** A viscous liquid is sheared between two parallel disks; the upper disk rotates and the lower one is fixed. The velocity field between the disks is given by  $\vec{V} = \hat{e}_\theta r\omega z/h$ . (The origin of coordinates is located at the center of the lower disk; the upper disk is located at  $z = h$ .) What are the dimensions of this velocity field? Does this velocity field satisfy appropriate physical boundary conditions? What are they?

**Given:** Viscous liquid sheared between parallel disks.

Upper disk rotates, lower fixed.

Velocity field is: 
$$\vec{V} = \hat{e}_\theta \frac{r\omega z}{h}$$



**Find:**

- Dimensions of velocity field.
- Satisfy physical boundary conditions.

**Solution:** To find dimensions, compare to  $\vec{V} = \vec{V}(x, y, z)$  form.

The given field is  $\vec{V} = \vec{V}(r, z)$ . Two space coordinates are included, so the field is 2-D.

Flow must satisfy the no-slip condition:

- At lower disk,  $\vec{V} = 0$  since stationary.

$$z = 0, \text{ so } \vec{V} = \hat{e}_\theta \frac{r\omega 0}{h} = 0, \text{ so satisfied.}$$

- At upper disk,  $\vec{V} = \hat{e}_\theta r\omega$  since it rotates as a solid body.

$$z = h, \text{ so } \vec{V} = \hat{e}_\theta \frac{r\omega h}{h} = \hat{e}_\theta r\omega, \text{ so satisfied.}$$

## Problem 2.4

[Difficulty: 1]

**2.4** For the velocity field  $\vec{V} = Ax^2y\hat{i} + Bxy^2\hat{j}$ , where  $A = 2 \text{ m}^{-2}\text{s}^{-1}$  and  $B = 1 \text{ m}^{-2}\text{s}^{-1}$ , and the coordinates are measured in meters, obtain an equation for the flow streamlines. Plot several streamlines in the first quadrant.

**Given:** Velocity field

**Find:** Equation for streamlines

**Solution:**

For streamlines

$$\frac{v}{u} = \frac{dy}{dx} = \frac{B \cdot x \cdot y^2}{A \cdot x^2 \cdot y} = \frac{B \cdot y}{A \cdot x}$$

So, separating variables

$$\frac{dy}{y} = \frac{B}{A} \cdot \frac{dx}{x}$$


Integrating

$$\ln(y) = \frac{B}{A} \cdot \ln(x) + c = -\frac{1}{2} \cdot \ln(x) + c$$

The solution is

$$y = \frac{C}{\sqrt{x}}$$

The plot can be easily done in *Excel*.



## Problem 2.5

[Difficulty: 2]

**2.5** The velocity field  $\vec{V} = Ax\hat{i} - Ay\hat{j}$ , where  $A = 2 \text{ s}^{-1}$ , can be interpreted to represent flow in a corner. Find an equation for the flow streamlines. Explain the relevance of  $A$ . Plot several streamlines in the first quadrant, including the one that passes through the point  $(x, y) = (0, 0)$ .

**Given:** Velocity field

**Find:** Equation for streamlines; Plot several in the first quadrant, including one that passes through point  $(0,0)$

**Solution:**

**Governing equation:** For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence  $\frac{v}{u} = \frac{dy}{dx} = \frac{A \cdot y}{A \cdot x} = \frac{y}{x}$


So, separating variables  $\frac{dy}{y} = \frac{dx}{x}$

Integrating  $\ln(y) = -\ln(x) + c$

The solution is  $\ln(x \cdot y) = c$

or  $y = \frac{C}{x}$

The plot can be easily done in *Excel*.



The streamline passing through  $(0,0)$  is given by the vertical axis, then the horizontal axis.

The value of  $A$  is irrelevant to streamline shapes but IS relevant for computing the velocity at each point.

## Problem 2.6

[Difficulty: 1]

**2.6** A velocity field is specified as  $\vec{V} = axy\hat{i} + by^2\hat{j}$ , where  $a = 2 \text{ m}^{-1}\text{s}^{-1}$ ,  $b = -6 \text{ m}^{-1}\text{s}^{-1}$ , and the coordinates are measured in meters. Is the flow field one-, two-, or three-dimensional? Why? Calculate the velocity components at the point  $(2, \frac{1}{2})$ . Develop an equation for the streamline passing through this point. Plot several streamlines in the first quadrant including the one that passes through the point  $(2, \frac{1}{2})$ .

**Given:** Velocity field

**Find:** Whether field is 1D, 2D or 3D; Velocity components at  $(2, 1/2)$ ; Equation for streamlines; Plot

**Solution:**

The velocity field is a function of  $x$  and  $y$ . It is therefore 2D.

At point  $(2, 1/2)$ , the velocity components are

$$u = a \cdot x \cdot y = 2 \cdot \frac{1}{\text{m}\cdot\text{s}} \times 2 \cdot \text{m} \times \frac{1}{2} \cdot \text{m} \quad u = 2 \cdot \frac{\text{m}}{\text{s}}$$

$$v = b \cdot y^2 = -6 \cdot \frac{1}{\text{m}\cdot\text{s}} \times \left(\frac{1}{2} \cdot \text{m}\right)^2 \quad v = -\frac{3}{2} \cdot \frac{\text{m}}{\text{s}}$$

For streamlines

$$\frac{v}{u} = \frac{dy}{dx} = \frac{b \cdot y^2}{a \cdot x \cdot y} = \frac{b \cdot y}{a \cdot x}$$

So, separating variables

$$\frac{dy}{y} = \frac{b}{a} \cdot \frac{dx}{x}$$

Integrating


$$\ln(y) = \frac{b}{a} \cdot \ln(x) + c \quad y = C \cdot x^{\frac{b}{a}}$$

The solution is

$$y = C \cdot x^{-3}$$

The streamline passing through point  $(2, 1/2)$  is given by

$$\frac{1}{2} = C \cdot 2^{-3} \quad C = \frac{1}{2} \cdot 2^3 \quad C = 4 \quad y = \frac{4}{3x}$$



This can be plotted in *Excel*.

## Problem 2.7

[Difficulty: 2]

**2.7** A velocity field is given by  $\vec{V} = ax\hat{i} - bty\hat{j}$ , where  $a = 1 \text{ s}^{-1}$  and  $b = 1 \text{ s}^{-2}$ . Find the equation of the streamlines at any time  $t$ . Plot several streamlines in the first quadrant at  $t = 0 \text{ s}$ ,  $t = 1 \text{ s}$ , and  $t = 20 \text{ s}$ .

**Given:** Velocity field

**Find:** Equation for streamlines; Plot streamlines

**Solution:**

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{-b \cdot t \cdot y}{a \cdot x}$

So, separating variables  $\frac{dy}{y} = \frac{-b \cdot t}{a} \cdot \frac{dx}{x}$

Integrating  $\ln(y) = \frac{-b \cdot t}{a} \cdot \ln(x)$

The solution is  $y = c \cdot x^{\frac{-b}{a} \cdot t}$

For  $t = 0 \text{ s}$   $y = c$       For  $t = 1 \text{ s}$   $y = \frac{c}{x}$       For  $t = 20 \text{ s}$   $y = c \cdot x^{-20}$

**t = 0**

**t = 1 s**  
(### means too large to view)


**t = 20 s**

	c = 1	c = 2	c = 3
x	y	y	y
0.05	1.00	2.00	3.00
0.10	1.00	2.00	3.00
0.20	1.00	2.00	3.00
0.30	1.00	2.00	3.00
0.40	1.00	2.00	3.00
0.50	1.00	2.00	3.00
0.60	1.00	2.00	3.00
0.70	1.00	2.00	3.00
0.80	1.00	2.00	3.00
0.90	1.00	2.00	3.00
1.00	1.00	2.00	3.00
1.10	1.00	2.00	3.00
1.20	1.00	2.00	3.00
1.30	1.00	2.00	3.00
1.40	1.00	2.00	3.00
1.50	1.00	2.00	3.00
1.60	1.00	2.00	3.00
1.70	1.00	2.00	3.00
1.80	1.00	2.00	3.00
1.90	1.00	2.00	3.00
2.00	1.00	2.00	3.00


	c = 1	c = 2	c = 3
x	y	y	y
0.05	20.00	40.00	60.00
0.10	10.00	20.00	30.00
0.20	5.00	10.00	15.00
0.30	3.33	6.67	10.00
0.40	2.50	5.00	7.50
0.50	2.00	4.00	6.00
0.60	1.67	3.33	5.00
0.70	1.43	2.86	4.29
0.80	1.25	2.50	3.75
0.90	1.11	2.22	3.33
1.00	1.00	2.00	3.00
1.10	0.91	1.82	2.73
1.20	0.83	1.67	2.50
1.30	0.77	1.54	2.31
1.40	0.71	1.43	2.14
1.50	0.67	1.33	2.00
1.60	0.63	1.25	1.88
1.70	0.59	1.18	1.76
1.80	0.56	1.11	1.67
1.90	0.53	1.05	1.58
2.00	0.50	1.00	1.50

	c = 1	c = 2	c = 3
x	y	y	y
0.05	#####	#####	#####
0.10	#####	#####	#####
0.20	#####	#####	#####
0.30	#####	#####	#####
0.40	#####	#####	#####
0.50	#####	#####	#####
0.60	#####	#####	#####
0.70	#####	#####	#####
0.80	86.74	173.47	260.21
0.90	8.23	16.45	24.68
1.00	1.00	2.00	3.00
1.10	0.15	0.30	0.45
1.20	0.03	0.05	0.08
1.30	0.01	0.01	0.02
1.40	0.00	0.00	0.00
1.50	0.00	0.00	0.00
1.60	0.00	0.00	0.00
1.70	0.00	0.00	0.00
1.80	0.00	0.00	0.00
1.90	0.00	0.00	0.00
2.00	0.00	0.00	0.00


Streamline Plot (t = 0)



Streamline Plot (t = 1 s)



Streamline Plot (t = 20 s)



## Problem 2.8

[Difficulty: 2]

**2.8** A velocity field is given by  $\vec{V} = ax^3\hat{i} + bxy^3\hat{j}$ , where  $a = 1 \text{ m}^{-2}\text{s}^{-1}$  and  $b = 1 \text{ m}^{-3}\text{s}^{-1}$ . Find the equation of the streamlines. Plot several streamlines in the first quadrant.

**Given:** Velocity field

**Find:** Equation for streamlines; Plot streamlines

**Solution:**

Streamlines are given by 
$$\frac{v}{u} = \frac{dy}{dx} = \frac{b \cdot x \cdot y^3}{a \cdot x^3}$$

So, separating variables 
$$\frac{dy}{y^3} = \frac{b \cdot dx}{a \cdot x^2}$$

Integrating 
$$-\frac{1}{2 \cdot y^2} = \frac{b}{a} \cdot \left(-\frac{1}{x}\right) + C$$

The solution is 
$$y = \frac{1}{\sqrt{2 \cdot \left(\frac{b}{a \cdot x} + C\right)}}$$


Note: For convenience the sign of C is changed.

$a = 1$

$b = 1$

$C = \quad 0 \quad 2 \quad 4 \quad 6$

x	y	y	y	y
0.05	0.16	0.15	0.14	0.14
0.10	0.22	0.20	0.19	0.18
0.20	0.32	0.27	0.24	0.21
0.30	0.39	0.31	0.26	0.23
0.40	0.45	0.33	0.28	0.24
0.50	0.50	0.35	0.29	0.25
0.60	0.55	0.37	0.30	0.26
0.70	0.59	0.38	0.30	0.26
0.80	0.63	0.39	0.31	0.26
0.90	0.67	0.40	0.31	0.27
1.00	0.71	0.41	0.32	0.27
1.10	0.74	0.41	0.32	0.27
1.20	0.77	0.42	0.32	0.27
1.30	0.81	0.42	0.32	0.27
1.40	0.84	0.43	0.33	0.27
1.50	0.87	0.43	0.33	0.27
1.60	0.89	0.44	0.33	0.27
1.70	0.92	0.44	0.33	0.28
1.80	0.95	0.44	0.33	0.28
1.90	0.97	0.44	0.33	0.28
2.00	1.00	0.45	0.33	0.28



## Problem 2.9

[Difficulty: 2]

**2.9** A flow is described by the velocity field  $\vec{V} = (Ax + B)\hat{i} + (-Ay)\hat{j}$ , where  $A = 10$  ft/s/ft and  $B = 20$  ft/s. Plot a few streamlines in the  $xy$  plane, including the one that passes through the point  $(x, y) = (1, 2)$ .

**Given:** Velocity field

**Find:** Plot streamlines

**Solution:**

Streamlines are given by  $\frac{v}{u} = \frac{dy}{dx} = \frac{-A \cdot y}{A \cdot x + B}$

So, separating variables  $\frac{dy}{-A \cdot y} = \frac{dx}{A \cdot x + B}$

Integrating  $-\frac{1}{A} \ln(y) = \frac{1}{A} \cdot \ln\left(x + \frac{B}{A}\right)$


The solution is  $y = \frac{C}{x + \frac{B}{A}}$

For the streamline that passes through point  $(x,y) = (1,2)$   $C = y \cdot \left(x + \frac{B}{A}\right) = 2 \cdot \left(1 + \frac{20}{10}\right) = 6$   $y = \frac{6}{x + \frac{20}{10}}$

$y = \frac{6}{x + 2}$

A = 10  
B = 20  
C =

	1	2	4	6
x	y	y	y	y
0.00	0.50	1.00	2.00	3.00
0.10	0.48	0.95	1.90	2.86
0.20	0.45	0.91	1.82	2.73
0.30	0.43	0.87	1.74	2.61
0.40	0.42	0.83	1.67	2.50
0.50	0.40	0.80	1.60	2.40
0.60	0.38	0.77	1.54	2.31
0.70	0.37	0.74	1.48	2.22
0.80	0.36	0.71	1.43	2.14
0.90	0.34	0.69	1.38	2.07
1.00	0.33	0.67	1.33	2.00
1.10	0.32	0.65	1.29	1.94
1.20	0.31	0.63	1.25	1.88
1.30	0.30	0.61	1.21	1.82
1.40	0.29	0.59	1.18	1.76
1.50	0.29	0.57	1.14	1.71
1.60	0.28	0.56	1.11	1.67
1.70	0.27	0.54	1.08	1.62
1.80	0.26	0.53	1.05	1.58
1.90	0.26	0.51	1.03	1.54
2.00	0.25	0.50	1.00	1.50



## Problem 2.10

[Difficulty: 2]

**2.10** The velocity for a steady, incompressible flow in the  $xy$  plane is given by  $\vec{V} = \hat{i}A/x + \hat{j}Ay/x^2$ , where  $A = 2 \text{ m}^2/\text{s}$ , and the coordinates are measured in meters. Obtain an equation for the streamline that passes through the point  $(x, y) = (1, 3)$ . Calculate the time required for a fluid particle to move from  $x = 1 \text{ m}$  to  $x = 2 \text{ m}$  in this flow field.

**Given:** Velocity field

**Find:** Equation for streamline through (1,3)

**Solution:**

For streamlines

$$\frac{v}{u} = \frac{dy}{dx} = \frac{A \cdot \frac{y}{x^2}}{\frac{A}{x}} = \frac{y}{x}$$

So, separating variables

$$\frac{dy}{y} = \frac{dx}{x}$$

Integrating

$$\ln(y) = \ln(x) + c$$

The solution is

$$y = C \cdot x \quad \text{which is the equation of a straight line.}$$

For the streamline through point (1,3)

$$3 = C \cdot 1 \quad C = 3 \quad \text{and} \quad y = 3 \cdot x$$

For a particle

$$u_p = \frac{dx}{dt} = \frac{A}{x} \quad \text{or} \quad x \cdot dx = A \cdot dt \quad x = \sqrt{2 \cdot A \cdot t + c} \quad t = \frac{x^2}{2 \cdot A} - \frac{c}{2 \cdot A}$$

Hence the time for a particle to go from  $x = 1$  to  $x = 2 \text{ m}$  is

$$\Delta t = t(x = 2) - t(x = 1) \quad \Delta t = \frac{(2 \cdot \text{m})^2 - c}{2 \cdot A} - \frac{(1 \cdot \text{m})^2 - c}{2 \cdot A} = \frac{4 \cdot \text{m}^2 - 1 \cdot \text{m}^2}{2 \times 2 \cdot \frac{\text{m}^2}{\text{s}}} \quad \Delta t = 0.75 \cdot \text{s}$$

## Problem 2.11

[Difficulty: 3]

**2.11** The flow field for an atmospheric flow is given by

$$\vec{V} = -\frac{My}{2\pi}\hat{i} + \frac{Mx}{2\pi}\hat{j}$$

where  $M = 1 \text{ s}^{-1}$ , and the  $x$  and  $y$  coordinates are the parallel to the local latitude and longitude. Plot the velocity magnitude along the  $x$  axis, along the  $y$  axis, and along the line  $y = x$ , and discuss the velocity direction with respect to these three axes. For each plot use a range  $x$  or  $y = 0$  km to 1 km. Find the equation for the streamlines and sketch several of them. What does this flow field model?

**Given:** Flow field


**Find:** Plot of velocity magnitude along axes, and  $y = x$ ; Equation for streamlines

**Solution:**

On the  $x$  axis,  $y = 0$ , so

$$u = -\frac{M \cdot y}{2 \cdot \pi} = 0 \qquad v = \frac{M \cdot x}{2 \cdot \pi}$$

Plotting




The velocity is perpendicular to the axis and increases linearly with distance  $x$ .

This can also be plotted in Excel.

On the  $y$  axis,  $x = 0$ , so

$$u = -\frac{M \cdot y}{2 \cdot \pi} \qquad v = \frac{M \cdot x}{2 \cdot \pi} = 0$$

Plotting



The velocity is perpendicular to the axis and increases linearly with distance  $y$ .

This can also be plotted in Excel.

On the  $y = x$  axis

$$u = -\frac{M \cdot y}{2 \cdot \pi} = -\frac{M \cdot x}{2 \cdot \pi} \quad v = \frac{M \cdot x}{2 \cdot \pi}$$

The flow is perpendicular to line  $y = x$ :

Slope of line  $y = x$ :  $1$


Slope of trajectory of motion:  $\frac{u}{v} = -1$

If we define the radial position:

$$r = \sqrt{x^2 + y^2} \quad \text{then along } y = x \quad r = \sqrt{x^2 + x^2} = \sqrt{2} \cdot x$$

Then the magnitude of the velocity along  $y = x$  is  $V = \sqrt{u^2 + v^2} = \frac{M}{2 \cdot \pi} \cdot \sqrt{x^2 + x^2} = \frac{M \cdot \sqrt{2} \cdot x}{2 \cdot \pi} = \frac{M \cdot r}{2 \cdot \pi}$

Plotting



This can also be plotted in Excel.

For streamlines

$$\frac{v}{u} = \frac{dy}{dx} = \frac{\frac{M \cdot x}{2 \cdot \pi}}{\frac{-M \cdot y}{2 \cdot \pi}} = -\frac{x}{y}$$

So, separating variables

$$y \cdot dy = -x \cdot dx$$

Integrating

$$\frac{y^2}{2} = -\frac{x^2}{2} + c$$

The solution is

$$x^2 + y^2 = C \quad \text{which is the equation of a circle.}$$

The streamlines form a set of concentric circles.

This flow models a rigid body vortex flow. See Example 5.6 for streamline plots. Streamlines are circular, and the velocity approaches zero as we approach the center. In Problem 2.10, we see that the streamlines are also circular. In a real tornado, at large distances from the center, the velocities behave as in Problem 2.10; close to the center, they behave as in this problem.

## Problem 2.12

[Difficulty: 3]

**2.12** The flow field for an atmospheric flow is given by

$$\vec{V} = -\frac{Ky}{2\pi(x^2 + y^2)}\hat{i} + \frac{Kx}{2\pi(x^2 + y^2)}\hat{j}$$

where  $K = 10^5 \text{ m}^2/\text{s}$ , and the  $x$  and  $y$  coordinates are parallel to the local latitude and longitude. Plot the velocity magnitude along the  $x$  axis, along the  $y$  axis, and along the line  $y = x$ , and discuss the velocity direction with respect to these three axes. For each plot use a range  $x$  or  $y = -1 \text{ km}$  to  $1 \text{ km}$ , excluding  $|x|$  or  $|y| < 100 \text{ m}$ . Find the equation for the streamlines and sketch several of them. What does this flow field model?

**Given:** Flow field


**Find:** Plot of velocity magnitude along axes, and  $y = x$ ; Equation of streamlines

**Solution:**

On the  $x$  axis,  $y = 0$ , so

$$u = -\frac{K \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)} = 0 \qquad v = \frac{K \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)} = \frac{K}{2 \cdot \pi \cdot x}$$

Plotting




The velocity is perpendicular to the axis, is very high close to the origin, and falls off to zero.

This can also be plotted in Excel.

On the  $y$  axis,  $x = 0$ , so

$$u = -\frac{K \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)} = -\frac{K}{2 \cdot \pi \cdot y} \qquad v = \frac{K \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)} = 0$$

Plotting



The velocity is perpendicular to the axis, is very high close to the origin, and falls off to zero. This can also be plotted in Excel.

On the  $y = x$  axis

$$u = -\frac{K \cdot x}{2 \cdot \pi \cdot (x^2 + x^2)} = -\frac{K}{4 \cdot \pi \cdot x} \quad v = \frac{K \cdot x}{2 \cdot \pi \cdot (x^2 + x^2)} = \frac{K}{4 \cdot \pi \cdot x}$$

The flow is perpendicular to line  $y = x$ :  
 Slope of line  $y = x$ : 1  
 Slope of trajectory of motion:  $\frac{u}{v} = -1$


If we define the radial position:

$$r = \sqrt{x^2 + y^2} \quad \text{then along } y = x \quad r = \sqrt{x^2 + x^2} = \sqrt{2} \cdot x$$

Then the magnitude of the velocity along  $y = x$  is

$$V = \sqrt{u^2 + v^2} = \frac{K}{4 \cdot \pi} \cdot \sqrt{\frac{1}{x^2} + \frac{1}{x^2}} = \frac{K}{2 \cdot \pi \cdot \sqrt{2} \cdot x} = \frac{K}{2 \cdot \pi \cdot r}$$

Plotting



This can also be plotted in Excel.

For streamlines

$$\frac{v}{u} = \frac{dy}{dx} = \frac{\frac{K \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)}}{-\frac{K \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)}} = -\frac{x}{y}$$

So, separating variables

$$y \cdot dy = -x \cdot dx$$

Integrating

$$\frac{y^2}{2} = -\frac{x^2}{2} + c$$

The solution is  $x^2 + y^2 = C$  which is the equation of a circle.

Streamlines form a set of concentric circles.

This flow models a vortex flow. See Example 5.6 for streamline plots. Streamlines are circular, and the velocity approaches infinity as we approach the center. In Problem 2.11, we see that the streamlines are also circular. In a real tornado, at large distances from the center, the velocities behave as in this problem; close to the center, they behave as in Problem 2.11.

## Problem 2.13

[Difficulty: 3]

**2.13** A flow field is given by

$$\vec{V} = -\frac{qx}{2\pi(x^2 + y^2)}\hat{i} - \frac{qy}{2\pi(x^2 + y^2)}\hat{j}$$

where  $q = 5 \times 10^4 \text{ m}^2/\text{s}$ . Plot the velocity magnitude along the  $x$  axis, along the  $y$  axis, and along the line  $y = x$ , and discuss the velocity direction with respect to these three axes. For each plot use a range  $x$  or  $y = -1 \text{ km}$  to  $1 \text{ km}$ , excluding  $|x|$  or  $|y| < 100 \text{ m}$ . Find the equation for the streamlines and sketch several of them. What does this flow field model?

**Given:** Flow field


**Find:** Plot of velocity magnitude along axes, and  $y = x$ ; Equations of streamlines

**Solution:**

On the  $x$  axis,  $y = 0$ , so

$$u = -\frac{q \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)} = -\frac{q}{2 \cdot \pi \cdot x} \quad v = -\frac{q \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)} = 0$$

Plotting




The velocity is very high close to the origin, and falls off to zero. It is also along the axis. This can be plotted in *Excel*.

On the  $y$  axis,  $x = 0$ , so

$$u = -\frac{q \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)} = 0 \quad v = -\frac{q \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)} = -\frac{q}{2 \cdot \pi \cdot y}$$

Plotting



The velocity is again very high close to the origin, and falls off to zero. It is also along the axis.

This can also be plotted in *Excel*.

On the  $y = x$  axis

$$u = -\frac{q \cdot x}{2 \cdot \pi \cdot (x^2 + x^2)} = -\frac{q}{4 \cdot \pi \cdot x} \quad v = -\frac{q \cdot x}{2 \cdot \pi \cdot (x^2 + x^2)} = -\frac{q}{4 \cdot \pi \cdot x}$$

The flow is parallel to line  $y = x$ :

Slope of line  $y = x$ : 1

Slope of trajectory of motion:  $\frac{v}{u} = 1$


If we define the radial position:

$r = \sqrt{x^2 + y^2}$  then along  $y = x$   $r = \sqrt{x^2 + x^2} = \sqrt{2} \cdot x$

Then the magnitude of the velocity along  $y = x$  is

$$V = \sqrt{u^2 + v^2} = \frac{q}{4 \cdot \pi} \cdot \sqrt{\frac{1}{x^2} + \frac{1}{x^2}} = \frac{q}{2 \cdot \pi \cdot \sqrt{2} \cdot x} = \frac{q}{2 \cdot \pi \cdot r}$$

Plotting



This can also be plotted in Excel.

For streamlines

$$\frac{v}{u} = \frac{dy}{dx} = \frac{-\frac{q \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)}}{-\frac{q \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)}} = \frac{y}{x}$$

So, separating variables

$$\frac{dy}{y} = \frac{dx}{x}$$

Integrating

$$\ln(y) = \ln(x) + c$$

The solution is

$y = C \cdot x$  which is the equation of a straight line.

This flow field corresponds to a sink (discussed in Chapter 6).

## Problem 2.14

[Difficulty: 2]

**2.14** Beginning with the velocity field of Problem 2.5, show that the parametric equations for particle motion are given by  $x_p = c_1 e^{At}$  and  $y_p = c_2 e^{-At}$ . Obtain the equation for the pathline of the particle located at the point  $(x, y) = (2, 2)$  at the instant  $t = 0$ . Compare this pathline with the streamline through the same point.

**Given:** Velocity field

**Find:** Proof that the parametric equations for particle motion are  $x_p = c_1 e^{At}$  and  $y_p = c_2 e^{-At}$ ; pathline that was at  $(2,2)$  at  $t = 0$ ; compare to streamline through same point, and explain why they are similar or not.

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$        $v_p = \frac{dy}{dt}$       For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence for pathlines  $u_p = \frac{dx}{dt} = A \cdot x$        $v_p = \frac{dy}{dt} = -A \cdot y$

So, separating variables  $\frac{dx}{x} = A \cdot dt$        $\frac{dy}{y} = -A \cdot dt$

Integrating  $\ln(x) = A \cdot t + C_1$        $\ln(y) = -A \cdot t + C_2$   
 $x = e^{A \cdot t + C_1} = e^{C_1} \cdot e^{A \cdot t} = c_1 \cdot e^{A \cdot t}$        $y = e^{-A \cdot t + C_2} = e^{C_2} \cdot e^{-A \cdot t} = c_2 \cdot e^{-A \cdot t}$

The pathlines are  $x = c_1 \cdot e^{A \cdot t}$        $y = c_2 \cdot e^{-A \cdot t}$

Eliminating  $t$   $t = \frac{1}{A} \cdot \ln\left(\frac{x}{c_1}\right) = -\frac{1}{A} \cdot \ln\left(\frac{y}{c_2}\right)$        $\ln\left(\frac{1}{x} \cdot \frac{1}{y}\right) = \text{const}$     or     $\ln(x^A \cdot y^A) = \text{const}$

so  $x^A \cdot y^A = \text{const}$  or  $x \cdot y = 4$  for given data

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = -\frac{A \cdot y}{A \cdot x} = -\frac{y}{x}$

So, separating variables  $\frac{dy}{y} = -\frac{dx}{x}$

Integrating  $\ln(y) = -\ln(x) + c$

The solution is  $\ln(x \cdot y) = c$     or     $x \cdot y = \text{const}$     or     $x \cdot y = 4$  for given data

The streamline passing through  $(2,2)$  and the pathline that started at  $(2,2)$  coincide because the flow is steady!

## Problem 2.15

[Difficulty: 2]

**2.15** A flow field is given by  $\vec{V} = Ax\hat{i} + 2Ay\hat{j}$ , where  $A = 2 \text{ s}^{-1}$ . Verify that the parametric equations for particle motion are given by  $x_p = c_1 e^{At}$  and  $y_p = c_2 e^{2At}$ . Obtain the equation for the pathline of the particle located at the point  $(x, y) = (2, 2)$  at the instant  $t = 0$ . Compare this pathline with the streamline through the same point.

**Given:** Velocity field

**Find:** Proof that the parametric equations for particle motion are  $x_p = c_1 \cdot e^{A \cdot t}$  and  $y_p = c_2 \cdot e^{2 \cdot A \cdot t}$ ; pathline that was at  $(2, 2)$  at  $t = 0$ ; compare to streamline through same point, and explain why they are similar or not.

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence for pathlines  $u_p = \frac{dx}{dt} = A \cdot x$   $v_p = \frac{dy}{dt} = 2 \cdot A \cdot y$

So, separating variables  $\frac{dx}{x} = A \cdot dt$   $\frac{dy}{y} = 2 \cdot A \cdot dt$

Integrating  $\ln(x) = A \cdot t + C_1$   $\ln(y) = 2 \cdot A \cdot t + C_2$   
 $x = e^{A \cdot t + C_1} = e^{C_1} \cdot e^{A \cdot t} = c_1 \cdot e^{A \cdot t}$   $y = e^{2 \cdot A \cdot t + C_2} = e^{C_2} \cdot e^{2 \cdot A \cdot t} = c_2 \cdot e^{2 \cdot A \cdot t}$

The pathlines are  $x = c_1 \cdot e^{A \cdot t}$   $y = c_2 \cdot e^{2 \cdot A \cdot t}$

Eliminating t  $y = c_2 \cdot e^{2 \cdot A \cdot t} = c_2 \cdot \left(\frac{x}{c_1}\right)^2$  so  $y = c \cdot x^2$  or  $y = \frac{1}{2} \cdot x^2$  for given data

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{2 \cdot A \cdot y}{A \cdot x} = \frac{2 \cdot y}{x}$

So, separating variables  $\frac{dy}{y} = \frac{2 \cdot dx}{x}$  Integrating  $\ln(y) = 2 \cdot \ln(x) + c$

The solution is  $\ln\left(\frac{y}{x^2}\right) = c$

or  $y = C \cdot x^2$  or  $y = \frac{1}{2} \cdot x^2$  for given data

The streamline passing through  $(2, 2)$  and the pathline that started at  $(2, 2)$  coincide because the flow is steady!

## Problem 2.16

[Difficulty: 2]

**2.16** A velocity field is given by  $\vec{V} = ayt\hat{i} - bx\hat{j}$ , where  $a = 1 \text{ s}^{-2}$  and  $b = 4 \text{ s}^{-1}$ . Find the equation of the streamlines at any time  $t$ . Plot several streamlines at  $t = 0 \text{ s}$ ,  $t = 1 \text{ s}$ , and  $t = 20 \text{ s}$ .

**Given:** Velocity field

**Find:** Equation of streamlines; Plot streamlines

**Solution:**

Streamlines are given by  $\frac{v}{u} = \frac{dy}{dx} = \frac{-b \cdot x}{a \cdot y \cdot t}$

So, separating variables  $a \cdot t \cdot y \cdot dy = -b \cdot x \cdot dx$

Integrating  $\frac{1}{2} \cdot a \cdot t \cdot y^2 = -\frac{1}{2} \cdot b \cdot x^2 + C$

The solution is  $y = \sqrt{C - \frac{b \cdot x^2}{a \cdot t}}$

For  $t = 0 \text{ s}$   $x = c$       For  $t = 1 \text{ s}$   $y = \sqrt{C - 4x^2}$       For  $t = 20 \text{ s}$   $y = \sqrt{C - \frac{x^2}{5}}$

**t = 0**




	C=1	C=2	C=3
<b>x</b>	<b>y</b>	<b>y</b>	<b>y</b>
0.00	1.00	2.00	3.00
0.10	1.00	2.00	3.00
0.20	1.00	2.00	3.00
0.30	1.00	2.00	3.00
0.40	1.00	2.00	3.00
0.50	1.00	2.00	3.00
0.60	1.00	2.00	3.00
0.70	1.00	2.00	3.00
0.80	1.00	2.00	3.00
0.90	1.00	2.00	3.00
1.00	1.00	2.00	3.00
1.10	1.00	2.00	3.00
1.20	1.00	2.00	3.00
1.30	1.00	2.00	3.00
1.40	1.00	2.00	3.00
1.50	1.00	2.00	3.00
1.60	1.00	2.00	3.00
1.70	1.00	2.00	3.00
1.80	1.00	2.00	3.00
1.90	1.00	2.00	3.00
2.00	1.00	2.00	3.00

**t = 1 s**

	C=1	C=2	C=3
<b>x</b>	<b>y</b>	<b>y</b>	<b>y</b>
0.000	1.00	1.41	1.73
0.025	1.00	1.41	1.73
0.050	0.99	1.41	1.73
0.075	0.99	1.41	1.73
0.100	0.98	1.40	1.72
0.125	0.97	1.39	1.71
0.150	0.95	1.38	1.71
0.175	0.94	1.37	1.70
0.200	0.92	1.36	1.69
0.225	0.89	1.34	1.67
0.250	0.87	1.32	1.66
0.275	0.84	1.30	1.64
0.300	0.80	1.28	1.62
0.325	0.76	1.26	1.61
0.350	0.71	1.23	1.58
0.375	0.66	1.20	1.56
0.400	0.60	1.17	1.54
0.425	0.53	1.13	1.51
0.450	0.44	1.09	1.48
0.475	0.31	1.05	1.45
0.500	0.00	1.00	1.41

**t = 20 s**

	C=1	C=2	C=3
<b>x</b>	<b>y</b>	<b>y</b>	<b>y</b>
0.00	1.00	1.41	1.73
0.10	1.00	1.41	1.73
0.20	1.00	1.41	1.73
0.30	0.99	1.41	1.73
0.40	0.98	1.40	1.72
0.50	0.97	1.40	1.72
0.60	0.96	1.39	1.71
0.70	0.95	1.38	1.70
0.80	0.93	1.37	1.69
0.90	0.92	1.36	1.68
1.00	0.89	1.34	1.67
1.10	0.87	1.33	1.66
1.20	0.84	1.31	1.65
1.30	0.81	1.29	1.63
1.40	0.78	1.27	1.61
1.50	0.74	1.24	1.60
1.60	0.70	1.22	1.58
1.70	0.65	1.19	1.56
1.80	0.59	1.16	1.53
1.90	0.53	1.13	1.51
2.00	0.45	1.10	1.48



## Problem 2.17

[Difficulty: 4]

**2.17** Verify that  $x_p = -a\sin(\omega t)$ ,  $y_p = a\cos(\omega t)$  is the equation for the pathlines of particles for the flow field of Problem 2.12. Find the frequency of motion  $\omega$  as a function of the amplitude of motion,  $a$ , and  $K$ . Verify that  $x_p = -a\sin(\omega t)$ ,  $y_p = a\cos(\omega t)$  is also the equation for the pathlines of particles for the flow field of Problem 2.11, except that  $\omega$  is now a function of  $M$ . Plot typical pathlines for both flow fields and discuss the difference.

**Given:** Pathlines of particles

**Find:** Conditions that make them satisfy Problem 2.10 flow field; Also Problem 2.11 flow field; Plot pathlines

**Solution:**

The given pathlines are

$$x_p = -a \cdot \sin(\omega \cdot t) \qquad y_p = a \cdot \cos(\omega \cdot t)$$

The velocity field of Problem 2.12 is

$$u = -\frac{K \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)} \qquad v = \frac{K \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)}$$

If the pathlines are correct we should be able to substitute  $x_p$  and  $y_p$  into the velocity field to find the velocity as a function of time:

$$u = -\frac{K \cdot y}{2 \cdot \pi \cdot (x^2 + y^2)} = -\frac{K \cdot a \cdot \cos(\omega \cdot t)}{2 \cdot \pi \cdot (a^2 \cdot \sin^2(\omega \cdot t) + a^2 \cdot \cos^2(\omega \cdot t))} = -\frac{K \cdot \cos(\omega \cdot t)}{2 \cdot \pi \cdot a} \qquad (1)$$

$$v = \frac{K \cdot x}{2 \cdot \pi \cdot (x^2 + y^2)} = -\frac{K \cdot (-a \cdot \sin(\omega \cdot t))}{2 \cdot \pi \cdot (a^2 \cdot \sin^2(\omega \cdot t) + a^2 \cdot \cos^2(\omega \cdot t))} = -\frac{K \cdot \sin(\omega \cdot t)}{2 \cdot \pi \cdot a} \qquad (2)$$

We should also be able to find the velocity field as a function of time from the pathline equations (Eq. 2.9):

$$\frac{dx_p}{dt} = u \qquad \frac{dx_p}{dt} = v \qquad (2.9)$$

$$u = \frac{dx_p}{dt} = -a \cdot \omega \cdot \cos(\omega \cdot t) \qquad v = \frac{dy_p}{dt} = -a \cdot \omega \cdot \sin(\omega \cdot t) \qquad (3)$$


Comparing Eqs. 1, 2 and 3

$$u = -a \cdot \omega \cdot \cos(\omega \cdot t) = -\frac{K \cdot \cos(\omega \cdot t)}{2 \cdot \pi \cdot a} \qquad v = -a \cdot \omega \cdot \sin(\omega \cdot t) = -\frac{K \cdot \sin(\omega \cdot t)}{2 \cdot \pi \cdot a}$$

Hence we see that

$$a \cdot \omega = \frac{K}{2 \cdot \pi \cdot a} \qquad \text{or} \qquad \omega = \frac{K}{2 \cdot \pi \cdot a^2} \qquad \text{for the pathlines to be correct.}$$

The pathlines are



To plot this in Excel, compute  $x_p$  and  $y_p$  for  $t$  ranging from 0 to 60 s, with  $\omega$  given by the above formula. Plot  $y_p$  versus  $x_p$ . Note that outer particles travel much slower!

This is the free vortex flow discussed in Example 5.6

The velocity field of Problem 2.11 is

$$u = -\frac{M \cdot y}{2 \cdot \pi} \quad v = \frac{M \cdot x}{2 \cdot \pi}$$

If the pathlines are correct we should be able to substitute  $x_p$  and  $y_p$  into the velocity field to find the velocity as a function of time:

$$u = -\frac{M \cdot y}{2 \cdot \pi} = -\frac{M \cdot (a \cdot \cos(\omega \cdot t))}{2 \cdot \pi} = -\frac{M \cdot a \cdot \cos(\omega \cdot t)}{2 \cdot \pi} \quad (4)$$

$$v = \frac{M \cdot x}{2 \cdot \pi} = \frac{M \cdot (-a \cdot \sin(\omega \cdot t))}{2 \cdot \pi} = -\frac{M \cdot a \cdot \sin(\omega \cdot t)}{2 \cdot \pi} \quad (5)$$

Recall that

$$u = \frac{dx_p}{dt} = -a \cdot \omega \cdot \cos(\omega \cdot t) \quad v = \frac{dy_p}{dt} = -a \cdot \omega \cdot \sin(\omega \cdot t) \quad (3)$$


Comparing Eqs. 1, 4 and 5

$$u = -a \cdot \omega \cdot \cos(\omega \cdot t) = -\frac{M \cdot a \cdot \cos(\omega \cdot t)}{2 \cdot \pi} \quad v = -a \cdot \omega \cdot \sin(\omega \cdot t) = -\frac{M \cdot a \cdot \sin(\omega \cdot t)}{2 \cdot \pi}$$

Hence we see that

$$\omega = \frac{M}{2 \cdot \pi} \quad \text{for the pathlines to be correct.}$$

## The pathlines



To plot this in Excel, compute  $x_p$  and  $y_p$  for  $t$  ranging from 0 to 75 s, with  $\omega$  given by the above formula. Plot  $y_p$  versus  $x_p$ . Note that outer particles travel faster!

This is the forced vortex flow discussed in Example 5.6

Note that this is rigid body rotation!

## Problem 2.18

[Difficulty: 2]

**2.18** Air flows downward toward an infinitely wide horizontal flat plate. The velocity field is given by  $\vec{V} = (ax\hat{i} - ay\hat{j})(2 + \cos \omega t)$ , where  $a = 5 \text{ s}^{-1}$ ,  $\omega = 2\pi \text{ s}^{-1}$ ,  $x$  and  $y$  (measured in meters) are horizontal and vertically upward, respectively, and  $t$  is in s. Obtain an algebraic equation for a streamline at  $t=0$ . Plot the streamline that passes through point  $(x, y) = (3, 3)$  at this instant. Will the streamline change with time? Explain briefly. Show the velocity vector on your plot at the same point and time. Is the velocity vector tangent to the streamline? Explain.

**Given:** Time-varying velocity field

**Find:** Streamlines at  $t = 0$  s; Streamline through  $(3,3)$ ; velocity vector; will streamlines change with time

**Solution:**

For streamlines 
$$\frac{v}{u} = \frac{dy}{dx} = -\frac{a \cdot y \cdot (2 + \cos(\omega \cdot t))}{a \cdot x \cdot (2 + \cos(\omega \cdot t))} = -\frac{y}{x}$$

At  $t = 0$  (actually all times!) 
$$\frac{dy}{dx} = -\frac{y}{x}$$


So, separating variables 
$$\frac{dy}{y} = -\frac{dx}{x}$$

Integrating 
$$\ln(y) = -\ln(x) + c$$

The solution is 
$$y = \frac{C}{x}$$
 which is the equation of a hyperbola.

For the streamline through point  $(3,3)$  
$$C = \frac{3}{3} \quad C = 1 \quad \text{and} \quad y = \frac{1}{x}$$

The streamlines will not change with time since  $dy/dx$  does not change with time.



At  $t = 0$  
$$u = a \cdot x \cdot (2 + \cos(\omega \cdot t)) = 5 \cdot \frac{1}{s} \times 3 \cdot \text{m} \times 3$$

$$u = 45 \cdot \frac{\text{m}}{\text{s}}$$

$$v = -a \cdot y \cdot (2 + \cos(\omega \cdot t)) = 5 \cdot \frac{1}{s} \times 3 \cdot \text{m} \times 3$$

$$v = -45 \cdot \frac{\text{m}}{\text{s}}$$

The velocity vector is tangent to the curve;

Tangent of curve at  $(3,3)$  is 
$$\frac{dy}{dx} = -\frac{y}{x} = -1$$

Direction of velocity at  $(3,3)$  is 
$$\frac{v}{u} = -1$$

This curve can be plotted in Excel.

## Problem 2.19

[Difficulty: 3]

**2.19** Consider the flow described by the velocity field  $\vec{V} = A(1 + Bt)\hat{i} + Cty\hat{j}$ , with  $A = 1$  m/s,  $B = 1$  s<sup>-1</sup>, and  $C = 1$  s<sup>-2</sup>. Coordinates are measured in meters. Plot the pathline traced out by the particle that passes through the point (1, 1) at time  $t = 0$ . Compare with the streamlines plotted through the same point at the instants  $t = 0, 1$ , and 2 s.

**Given:** Velocity field

**Find:** Plot of pathline traced out by particle that passes through point (1,1) at  $t = 0$ ; compare to streamlines through same point at the instants  $t = 0, 1$  and 2s

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$      $v_p = \frac{dy}{dt}$     For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence for pathlines  $u_p = \frac{dx}{dt} = A \cdot (1 + B \cdot t)$      $A = 1 \cdot \frac{m}{s}$      $B = 1 \cdot \frac{1}{s}$      $v_p = \frac{dy}{dt} = C \cdot t \cdot y$      $C = 1 \cdot \frac{1}{s^2}$

So, separating variables  $dx = A \cdot (1 + B \cdot t) \cdot dt$      $\frac{dy}{y} = C \cdot t \cdot dt$

Integrating  $x = A \cdot \left( t + B \cdot \frac{t^2}{2} \right) + C_1$      $\ln(y) = \frac{1}{2} \cdot C \cdot t^2 + C_2$   
 $y = e^{\frac{1}{2} \cdot C \cdot t^2 + C_2} = e^{C_2} \cdot e^{\frac{1}{2} \cdot C \cdot t^2} = c_2 \cdot e^{\frac{1}{2} \cdot C \cdot t^2}$

The pathlines are  $x = A \cdot \left( t + B \cdot \frac{t^2}{2} \right) + C_1$      $y = c_2 \cdot e^{\frac{1}{2} \cdot C \cdot t^2}$

Using given data  $x = A \cdot \left( t + B \cdot \frac{t^2}{2} \right) + 1$      $y = e^{\frac{1}{2} \cdot C \cdot t^2}$


For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{C \cdot y \cdot t}{A \cdot (1 + B \cdot t)}$

So, separating variables  $(1 + B \cdot t) \cdot \frac{dy}{y} = \frac{C}{A} \cdot t \cdot dx$     which we can integrate for any given  $t$  ( $t$  is treated as a constant)

Integrating  $(1 + B \cdot t) \cdot \ln(y) = \frac{C}{A} \cdot t \cdot x + c$

The solution is  $y^{1+B \cdot t} = \frac{C}{A} \cdot t \cdot x + \text{const}$      $y = \left( \frac{C}{A} \cdot t \cdot x + \text{const} \right)^{\frac{1}{(1+B \cdot t)}}$

For particles at (1,1) at t = 0, 1, and 2s, using A, B, and C data:  $y = 1$        $y = x^{\frac{1}{2}}$        $y = (2 \cdot x - 1)^{\frac{1}{3}}$



## Problem 2.20

[Difficulty: 3]

**2.20** Consider the flow described by the velocity field  $\vec{V} = Bx(1 + At)\hat{i} + Cy\hat{j}$ , with  $A = 0.5 \text{ s}^{-1}$  and  $B = C = 1 \text{ s}^{-1}$ . Coordinates are measured in meters. Plot the pathline traced out by the particle that passes through the point (1, 1) at time  $t = 0$ . Compare with the streamlines plotted through the same point at the instants  $t = 0, 1$ , and  $2 \text{ s}$ .

**Given:** Velocity field

**Find:** Plot of pathline traced out by particle that passes through point (1,1) at  $t = 0$ ; compare to streamlines through same point at the instants  $t = 0, 1$  and  $2 \text{ s}$

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$      $v_p = \frac{dy}{dt}$     For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence for pathlines  $u_p = \frac{dx}{dt} = B \cdot x \cdot (1 + A \cdot t)$      $A = 0.5 \cdot \frac{1}{\text{s}}$      $B = 1 \cdot \frac{1}{\text{s}}$      $v_p = \frac{dy}{dt} = C \cdot y$      $C = 1 \cdot \frac{1}{\text{s}}$

So, separating variables  $\frac{dx}{x} = B \cdot (1 + A \cdot t) \cdot dt$      $\frac{dy}{y} = C \cdot dt$

Integrating  $\ln(x) = B \cdot \left( t + A \cdot \frac{t^2}{2} \right) + C_1$      $\ln(y) = C \cdot t + C_2$

$$x = e^{B \cdot \left( t + A \cdot \frac{t^2}{2} \right) + C_1} = e^{C_1} \cdot e^{B \cdot \left( t + A \cdot \frac{t^2}{2} \right)} = c_1 \cdot e^{B \cdot \left( t + A \cdot \frac{t^2}{2} \right)} \qquad y = e^{C \cdot t + C_2} = e^{C_2} \cdot e^{C \cdot t} = c_2 \cdot e^{C \cdot t}$$

The pathlines are  $x = c_1 \cdot e^{B \cdot \left( t + A \cdot \frac{t^2}{2} \right)}$      $y = c_2 \cdot e^{C \cdot t}$

Using given data  $x = e^{B \cdot \left( t + A \cdot \frac{t^2}{2} \right)}$      $y = e^{C \cdot t}$


For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{C \cdot y}{B \cdot x \cdot (1 + A \cdot t)}$

So, separating variables  $(1 + A \cdot t) \cdot \frac{dy}{y} = \frac{C}{B} \cdot \frac{dx}{x}$     which we can integrate for any given  $t$  ( $t$  is treated as a constant)

Integrating  $(1 + A \cdot t) \cdot \ln(y) = \frac{C}{B} \cdot \ln(x) + c$

The solution is  $y^{1+A \cdot t} = \text{const} \cdot x^{\frac{C}{B}}$  or  $y = \text{const} \cdot x$

For particles at (1,1) at  $t = 0, 1,$  and  $2\text{s}$   $y = x^{\frac{C}{B}}$   $y = x^{\frac{C}{(1+A)B}}$   $y = x^{\frac{C}{(1+2 \cdot A)B}}$



## Problem 2.21

[Difficulty: 3]

**2.21** Consider the flow field given in Eulerian description by the expression  $\vec{V} = A\hat{i} - Bt\hat{j}$ , where  $A = 2$  m/s,  $B = 2$  m/s<sup>2</sup>, and the coordinates are measured in meters. Derive the Lagrangian position functions for the fluid particle that was located at the point  $(x, y) = (1, 1)$  at the instant  $t = 0$ . Obtain an algebraic expression for the pathline followed by this particle. Plot the pathline and compare with the streamlines plotted through the same point at the instants  $t = 0, 1$ , and  $2$  s.

**Given:** Eulerian Velocity field

**Find:** Lagrangian position function that was at point (1,1) at  $t = 0$ ; expression for pathline; plot pathline and compare to streamlines through same point at the instants  $t = 0, 1$  and  $2$ s

**Solution:**

**Governing equations:** For pathlines (Lagrangian description)  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence for pathlines  $u_p = \frac{dx}{dt} = A$   $A = 2 \frac{m}{s}$   $v_p = \frac{dy}{dt} = -B \cdot t$   $B = 2 \frac{m}{s^2}$

So, separating variables  $dx = A \cdot dt$   $dy = -B \cdot t \cdot dt$

Integrating  $x = A \cdot t + x_0$   $x_0 = 1$  m  $y = -B \cdot \frac{t^2}{2} + y_0$   $y_0 = 1$  m

The Lagrangian description is  $x(t) = A \cdot t + x_0$   $y(t) = -B \cdot \frac{t^2}{2} + y_0$

Using given data  $x(t) = 2 \cdot t + 1$   $y(t) = 1 - t^2$

The pathlines are given by combining the equations  $t = \frac{x - x_0}{A}$   $y = -B \cdot \frac{t^2}{2} + y_0 = -B \cdot \frac{(x - x_0)^2}{2 \cdot A^2} + y_0$

Hence  $y(x) = y_0 - B \cdot \frac{(x - x_0)^2}{2 \cdot A^2}$  or, using given data  $y(x) = 1 - \frac{(x - 1)^2}{4}$

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{-B \cdot t}{A}$

So, separating variables  $dy = -\frac{B \cdot t}{A} \cdot dx$  which we can integrate for any given  $t$  ( $t$  is treated as a constant)


The solution is

$$y = -\frac{B \cdot t}{A} \cdot x + c \quad \text{and for the one through } (1,1) \quad 1 = -\frac{B \cdot t}{A} \cdot 1 + c \quad c = 1 + \frac{B \cdot t}{A}$$

$$y = -\frac{B \cdot t}{A} \cdot (x - 1) + 1 \quad y = 1 - t \cdot (x - 1)$$

$$x = 1, 1.1 \dots 20$$

Streamline Plots



## Problem 2.22

[Difficulty: 3]

**2.22** Consider the velocity field  $V = ax\hat{i} + by(1 + ct)\hat{j}$ , where  $a = b = 2 \text{ s}^{-1}$  and  $c = 0.4 \text{ s}^{-1}$ . Coordinates are measured in meters. For the particle that passes through the point  $(x, y) = (1, 1)$  at the instant  $t = 0$ , plot the pathline during the interval from  $t = 0$  to 1.5 s. Compare this pathline with the streamlines plotted through the same point at the instants  $t = 0, 1$ , and 1.5 s.

**Given:** Velocity field

**Find:** Plot of pathline of particle for  $t = 0$  to 1.5 s that was at point (1,1) at  $t = 0$ ; compare to streamlines through same point at the instants  $t = 0, 1$  and 1.5 s

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence for pathlines  $u_p = \frac{dx}{dt} = ax$   $a = 2 \frac{1}{s}$   $v_p = \frac{dy}{dt} = b \cdot y \cdot (1 + c \cdot t)$   $b = 2 \frac{1}{s^2}$   $c = 0.4 \frac{1}{s}$

So, separating variables  $\frac{dx}{x} = a \cdot dt$   $dy = b \cdot y \cdot (1 + c \cdot t) \cdot dt$   $\frac{dy}{y} = b \cdot (1 + c \cdot t) \cdot dt$

Integrating  $\ln\left(\frac{x}{x_0}\right) = a \cdot t$   $x_0 = 1 \text{ m}$   $\ln\left(\frac{y}{y_0}\right) = b \cdot \left(t + \frac{1}{2} \cdot c \cdot t^2\right)$   $y_0 = 1 \text{ m}$

Hence  $x(t) = x_0 \cdot e^{a \cdot t}$   $y(t) = e^{b \cdot \left(t + \frac{1}{2} \cdot c \cdot t^2\right)}$

Using given data  $x(t) = e^{2 \cdot t}$   $y(t) = e^{2 \cdot t + 0.4 \cdot t^2}$


For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{b \cdot y \cdot (1 + c \cdot t)}{a \cdot x}$

So, separating variables  $\frac{dy}{y} = \frac{b \cdot (1 + c \cdot t)}{a \cdot x} \cdot dx$  which we can integrate for any given  $t$  ( $t$  is treated as a constant)

Hence  $\ln\left(\frac{y}{y_0}\right) = \frac{b}{a} \cdot (1 + c \cdot t) \cdot \ln\left(\frac{x}{x_0}\right)$

The solution is  $y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a} \cdot (1 + c \cdot t)}$

$$\text{For } t = 0 \quad y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a} \cdot (1+c \cdot t)} = x \quad t = 1 \quad y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a} \cdot (1+c \cdot t)} = x^{1.4} \quad t = 1.5 \quad y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a} \cdot (1+c \cdot t)} = x^{1.6}$$



## Problem 2.23

[Difficulty: 3]

**2.23** Consider the flow field given in Eulerian description by the expression  $\vec{V} = ax\hat{i} + by\hat{j}$ , where  $a = 0.2 \text{ s}^{-1}$ ,  $b = 0.04 \text{ s}^{-2}$ , and the coordinates are measured in meters. Derive the Lagrangian position functions for the fluid particle that was located at the point  $(x, y) = (1, 1)$  at the instant  $t = 0$ . Obtain an algebraic expression for the pathline followed by this particle. Plot the pathline and compare with the streamlines plotted through the same point at the instants  $t = 0, 10,$  and  $20 \text{ s}$ .

**Given:** Velocity field

**Find:** Plot of pathline of particle for  $t = 0$  to  $1.5 \text{ s}$  that was at point  $(1,1)$  at  $t = 0$ ; compare to streamlines through same point at the instants  $t = 0, 1$  and  $1.5 \text{ s}$

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

**Assumption:** 2D flow

Hence for pathlines  $u_p = \frac{dx}{dt} = a \cdot x$   $a = \frac{1}{5} \frac{1}{\text{s}}$   $v_p = \frac{dy}{dt} = b \cdot y \cdot t$   $b = \frac{1}{25} \frac{1}{\text{s}^2}$

So, separating variables  $\frac{dx}{x} = a \cdot dt$   $dy = b \cdot y \cdot t \cdot dt$   $\frac{dy}{y} = b \cdot t \cdot dt$

Integrating  $\ln\left(\frac{x}{x_0}\right) = a \cdot t$   $x_0 = 1 \text{ m}$   $\ln\left(\frac{y}{y_0}\right) = b \cdot \frac{1}{2} \cdot t^2$   $y_0 = 1 \text{ m}$

Hence  $x(t) = x_0 \cdot e^{a \cdot t}$   $y(t) = y_0 \cdot e^{\frac{1}{2} \cdot b \cdot t^2}$

Using given data  $x(t) = e^{\frac{t}{5}}$   $y(t) = e^{\frac{t^2}{50}}$

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{b \cdot y \cdot t}{a \cdot x}$

So, separating variables  $\frac{dy}{y} = \frac{b \cdot t}{a \cdot x} \cdot dx$  which we can integrate for any given  $t$  ( $t$  is treated as a constant)


Hence  $\ln\left(\frac{y}{y_0}\right) = \frac{b}{a} \cdot t \cdot \ln\left(\frac{x}{x_0}\right)$

The solution is  $y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a} \cdot t}$   $\frac{b}{a} = 0.2$   $x_0 = 1$   $y_0 = 1$

For  $t = 0$   $y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a}} = 1$

$t = 5$   $y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a}} = x$   $\frac{b}{a} \cdot t = 1$

$t = 10$   $y = y_0 \cdot \left(\frac{x}{x_0}\right)^{\frac{b}{a}} = x^2$   $\frac{b}{a} \cdot t = 2$



## Problem 2.24

[Difficulty: 3]

**2.24** A velocity field is given by  $\vec{V} = ax\hat{i} - by\hat{j}$ , where  $a = 0.1 \text{ s}^{-2}$  and  $b = 1 \text{ s}^{-1}$ . For the particle that passes through the point  $(x, y) = (1, 1)$  at instant  $t = 0 \text{ s}$ , plot the pathline during the interval from  $t = 0$  to  $t = 3 \text{ s}$ . Compare with the streamlines plotted through the same point at the instants  $t = 0, 1$ , and  $2 \text{ s}$ .

**Given:** Velocity field

**Find:** Plot pathlines and streamlines

**Solution:**

Pathlines are given by  $\frac{dx}{dt} = u = a \cdot x \cdot t$   $\frac{dy}{dt} = v = -b \cdot y$

So, separating variables  $\frac{dx}{x} = a \cdot t \cdot dt$   $\frac{dy}{y} = -b \cdot dt$

Integrating  $\ln(x) = \frac{1}{2} \cdot a \cdot t^2 + c_1$   $\ln(y) = -b \cdot t + c_2$

For initial position  $(x_0, y_0)$   $x = x_0 \cdot e^{\frac{a}{2} \cdot t^2}$   $y = y_0 \cdot e^{-b \cdot t}$

Using the given data, and IC  $(x_0, y_0) = (1, 1)$  at  $t = 0$

$x = e^{0.05 \cdot t^2}$   $y = e^{-t}$

Streamlines are given by  $\frac{v}{u} = \frac{dy}{dx} = \frac{-b \cdot y}{a \cdot x \cdot t}$

So, separating variables  $\frac{dy}{y} = -\frac{b}{a \cdot t} \cdot \frac{dx}{x}$  Integrating  $\ln(y) = -\frac{b}{a \cdot t} \cdot \ln(x) + C$

The solution is  $y = C \cdot x^{-\frac{b}{a \cdot t}}$

For streamline at  $(1, 1)$  at  $t = 0 \text{ s}$   $x = c$

For streamline at  $(1, 1)$  at  $t = 1 \text{ s}$   $y = x^{-10}$

For streamline at  $(1, 1)$  at  $t = 2 \text{ s}$   $y = x^{-5}$

### Pathline


t	x	y
0.00	1.00	1.00
0.25	1.00	0.78
0.50	1.01	0.61
0.75	1.03	0.47
1.00	1.05	0.37
1.25	1.08	0.29
1.50	1.12	0.22
1.75	1.17	0.17
2.00	1.22	0.14
2.25	1.29	0.11
2.50	1.37	0.08
2.75	1.46	0.06
3.00	1.57	0.05
3.25	1.70	0.04
3.50	1.85	0.03
3.75	2.02	0.02
4.00	2.23	0.02
4.25	2.47	0.01
4.50	2.75	0.01
4.75	3.09	0.01
5.00	3.49	0.01

### Streamlines

t = 0	
x	y
1.00	1.00
1.00	0.78
1.00	0.61
1.00	0.47
1.00	0.37
1.00	0.29
1.00	0.22
1.00	0.17
1.00	0.14
1.00	0.11
1.00	0.08
1.00	0.06
1.00	0.05
1.00	0.04
1.00	0.03
1.00	0.02
1.00	0.02
1.00	0.01
1.00	0.01
1.00	0.01
1.00	0.01

t = 1 s	
x	y
1.00	1.00
1.00	0.97
1.01	0.88
1.03	0.75
1.05	0.61
1.08	0.46
1.12	0.32
1.17	0.22
1.22	0.14
1.29	0.08
1.37	0.04
1.46	0.02
1.57	0.01
1.70	0.01
1.85	0.00
2.02	0.00
2.23	0.00
2.47	0.00
2.75	0.00
3.09	0.00
3.49	0.00

t = 2 s	
x	y
1.00	1.00
1.00	0.98
1.01	0.94
1.03	0.87
1.05	0.78
1.08	0.68
1.12	0.57
1.17	0.47
1.22	0.37
1.29	0.28
1.37	0.21
1.46	0.15
1.57	0.11
1.70	0.07
1.85	0.05
2.02	0.03
2.23	0.02
2.47	0.01
2.75	0.01
3.09	0.00
3.49	0.00



## Problem 2.25

[Difficulty: 3]

**2.25** Consider the flow field  $\vec{V} = ax\hat{i} + b\hat{j}$ , where  $a = 0.1 \text{ s}^{-2}$  and  $b = 4 \text{ m/s}$ . Coordinates are measured in meters. For the particle that passes through the point  $(x, y) = (3, 1)$  at the instant  $t = 0$ , plot the pathline during the interval from  $t = 0$  to 3 s. Compare this pathline with the streamlines plotted through the same point at the instants  $t = 1, 2,$  and 3 s.

**Given:** Flow field

**Find:** Pathline for particle starting at (3,1); Streamlines through same point at  $t = 1, 2,$  and 3 s

**Solution:**

For particle paths  $\frac{dx}{dt} = u = a \cdot x \cdot t$       and       $\frac{dy}{dt} = v = b$

Separating variables and integrating  $\frac{dx}{x} = a \cdot t \cdot dt$       or       $\ln(x) = \frac{1}{2} \cdot a \cdot t^2 + c_1$

$dy = b \cdot dt$       or       $y = b \cdot t + c_2$

Using initial condition  $(x,y) = (3,1)$  and the given values for a and b

$c_1 = \ln(3 \cdot m)$       and       $c_2 = 1 \cdot m$

The pathline is then  $x = 3 \cdot e^{0.05 \cdot t^2}$       and       $y = 4 \cdot t + 1$

For streamlines (at any time t)  $\frac{v}{u} = \frac{dy}{dx} = \frac{b}{a \cdot x \cdot t}$


So, separating variables  $dy = \frac{b}{a \cdot t} \cdot \frac{dx}{x}$

Integrating  $y = \frac{b}{a \cdot t} \cdot \ln(x) + c$

We are interested in instantaneous streamlines at various times that always pass through point (3,1). Using a and b values:

$$c = y - \frac{b}{a \cdot t} \cdot \ln(x) = 1 - \frac{4}{0.1 \cdot t} \cdot \ln(3)$$

The streamline equation is  $y = 1 + \frac{40}{t} \cdot \ln\left(\frac{x}{3}\right)$



These curves can be plotted in Excel.

## Problem 2.26

[Difficulty: 4]

**2.26** Consider the garden hose of Fig. 2.5. Suppose the velocity field is given by  $\vec{V} = u_0\hat{i} + v_0\sin[\omega(t - x/u_0)]\hat{j}$ , where the  $x$  direction is horizontal and the origin is at the mean position of the hose,  $u_0 = 10$  m/s,  $v_0 = 2$  m/s, and  $\omega = 5$  cycle/s. Find and plot on one graph the instantaneous streamlines that pass through the origin at  $t = 0$  s, 0.05 s, 0.1 s, and 0.15 s. Also find and plot on one graph the pathlines of particles that left the origin at the same four times.

**Given:** Velocity field

**Find:** Plot streamlines that are at origin at various times and pathlines that left origin at these times

**Solution:**

For streamlines 
$$\frac{v}{u} = \frac{dy}{dx} = \frac{v_0 \cdot \sin\left[\omega \cdot \left(t - \frac{x}{u_0}\right)\right]}{u_0}$$

So, separating variables ( $t = \text{const}$ ) 
$$dy = \frac{v_0 \cdot \sin\left[\omega \cdot \left(t - \frac{x}{u_0}\right)\right]}{u_0} \cdot dx$$

Integrating 
$$y = \frac{v_0 \cdot \cos\left[\omega \cdot \left(t - \frac{x}{u_0}\right)\right]}{\omega} + c$$

Using condition  $y = 0$  when  $x = 0$  
$$y = \frac{v_0 \cdot \left[\cos\left[\omega \cdot \left(t - \frac{x}{u_0}\right)\right] - \cos(\omega \cdot t)\right]}{\omega}$$

This gives streamlines  $y(x)$  at each time  $t$

For particle paths, first find  $x(t)$  
$$\frac{dx}{dt} = u = u_0$$

Separating variables and integrating 
$$dx = u_0 \cdot dt \quad \int_0^x \quad \int_0^t \quad x = u_0 \cdot t + c_1$$

Using initial condition  $x = 0$  at  $t = \tau$  
$$c_1 = -u_0 \cdot \tau \quad x = u_0 \cdot (t - \tau)$$

For  $y(t)$  we have 
$$\frac{dy}{dt} = v = v_0 \cdot \sin\left[\omega \cdot \left(t - \frac{x}{u_0}\right)\right] \quad \text{so} \quad \frac{dy}{dt} = v = v_0 \cdot \sin\left[\omega \cdot \left[t - \frac{u_0 \cdot (t - \tau)}{u_0}\right]\right]$$


and 
$$\frac{dy}{dt} = v = v_0 \cdot \sin(\omega \cdot \tau)$$

Separating variables and integrating 
$$dy = v_0 \cdot \sin(\omega \cdot \tau) \cdot dt \quad y = v_0 \cdot \sin(\omega \cdot \tau) \cdot t + c_2$$

Using initial condition  $y = 0$  at  $t = \tau$  
$$c_2 = -v_0 \cdot \sin(\omega \cdot \tau) \cdot \tau \quad y = v_0 \cdot \sin(\omega \cdot \tau) \cdot (t - \tau)$$

The pathline is then

$x(t, \tau) = u_0 \cdot (t - \tau) \quad y(t, \tau) = v_0 \cdot \sin(\omega \cdot \tau) \cdot (t - \tau)$  These terms give the path of a particle  $(x(t), y(t))$  that started at  $t = \tau$ .



- Streamline  $t = 0s$
- Streamline  $t = 0.05s$
- - - Streamline  $t = 0.1s$
- · - Streamline  $t = 0.15s$
- Pathline starting  $t = 0s$
- Pathline starting  $t = 0.05s$
- - - Pathline starting  $t = 0.1s$
- · - Pathline starting  $t = 0.15s$

The streamlines are sinusoids; the pathlines are straight (once a water particle is fired it travels in a straight line).

These curves can be plotted in *Excel*.

## Problem 2.27

[Difficulty: 5]

**2.27** Using the data of Problem 2.26, find and plot the streakline shape produced after the first second of flow.

**Given:** Velocity field

**Find:** Plot streakline for first second of flow

**Solution:**

Following the discussion leading up to Eq. 2.10, we first find equations for the pathlines in form

$$x_p(t) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_p(t) = y(t, x_0, y_0, t_0)$$

where  $x_0, y_0$  is the position of the particle at  $t = t_0$ , and re-interpret the results as streaklines

$$x_{st}(t_0) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_{st}(t_0) = y(t, x_0, y_0, t_0)$$

which gives the streakline at  $t$ , where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

For particle paths, first find  $x(t)$   $\frac{dx}{dt} = u = u_0$

Separating variables and integrating  $dx = u_0 \cdot dt$   $x = x_0 + u_0 \cdot (t - t_0)$

For  $y(t)$  we have  $\frac{dy}{dt} = v = v_0 \cdot \sin\left[\omega \cdot \left(t - \frac{x}{u_0}\right)\right]$  so  $\frac{dy}{dt} = v = v_0 \cdot \sin\left[\omega \cdot \left[t - \frac{x_0 + u_0 \cdot (t - t_0)}{u_0}\right]\right]$

and  $\frac{dy}{dt} = v = v_0 \cdot \sin\left[\omega \cdot \left(t_0 - \frac{x_0}{u_0}\right)\right]$


Separating variables and integrating  $dy = v_0 \cdot \sin\left[\omega \cdot \left(t_0 - \frac{x_0}{u_0}\right)\right] \cdot dt$   $y = y_0 + v_0 \cdot \sin\left[\omega \cdot \left(t_0 - \frac{x_0}{u_0}\right)\right] \cdot (t - t_0)$

The streakline is then  $x_{st}(t_0) = x_0 + u_0(t - t_0)$   $y_{st}(t_0) = y_0 + v_0 \cdot \sin\left[\omega \cdot \left(t_0 - \frac{x_0}{u_0}\right)\right] \cdot (t - t_0)$

With  $x_0 = y_0 = 0$

$$x_{st}(t_0) = u_0 \cdot (t - t_0) \quad y_{st}(t_0) = v_0 \cdot \sin[\omega \cdot (t_0)] \cdot (t - t_0)$$

**Streakline for First Second**



This curve can be plotted in *Excel*. For  $t = 1$ ,  $t_0$  ranges from 0 to  $t$ .

## Problem 2.28

[Difficulty: 4]

**2.28** Consider the velocity field of Problem 2.20. Plot the streakline formed by particles that passed through the point (1, 1) during the interval from  $t = 0$  to  $t = 3$  s. Compare with the streamlines plotted through the same point at the instants  $t = 0, 1,$  and  $2$  s.

**Given:** Velocity field

**Find:** Plot of streakline for  $t = 0$  to  $3$  s at point (1,1); compare to streamlines through same point at the instants  $t = 0, 1,$  and  $2$  s

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

Following the discussion leading up to Eq. 2.10, we first find equations for the pathlines in form

$$x_p(t) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_p(t) = y(t, x_0, y_0, t_0)$$

$$x_{st}(t_0) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_{st}(t_0) = y(t, x_0, y_0, t_0)$$

which gives the streakline at  $t$ , where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

**Assumption:** 2D flow

For pathlines  $u_p = \frac{dx}{dt} = B \cdot x \cdot (1 + A \cdot t)$   $A = 0.5 \frac{1}{s}$   $B = 1 \frac{1}{s}$   $v_p = \frac{dy}{dt} = C \cdot y$   $C = 1 \frac{1}{s}$

So, separating variables  $\frac{dx}{x} = B \cdot (1 + A \cdot t) \cdot dt$   $\frac{dy}{y} = C \cdot dt$

Integrating  $\ln\left(\frac{x}{x_0}\right) = B \cdot \left(t - t_0 + A \cdot \frac{t^2 - t_0^2}{2}\right)$   $\ln\left(\frac{y}{y_0}\right) = C \cdot (t - t_0)$

$$x = x_0 \cdot e^{B \cdot \left(t - t_0 + A \cdot \frac{t^2 - t_0^2}{2}\right)} \quad y = y_0 \cdot e^{C \cdot (t - t_0)}$$

The pathlines are  $x_p(t) = x_0 \cdot e^{B \cdot \left(t - t_0 + A \cdot \frac{t^2 - t_0^2}{2}\right)}$   $y_p(t) = y_0 \cdot e^{C \cdot (t - t_0)}$

where  $x_0, y_0$  is the position of the particle at  $t = t_0$ . Re-interpreting the results as streaklines:

The streaklines are then  $x_{st}(t_0) = x_0 \cdot e^{B \cdot \left(t - t_0 + A \cdot \frac{t^2 - t_0^2}{2}\right)}$   $y_{st}(t_0) = y_0 \cdot e^{C \cdot (t - t_0)}$

where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )


For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{C \cdot y}{B \cdot x \cdot (1 + A \cdot t)}$

So, separating variables  $(1 + A \cdot t) \cdot \frac{dy}{y} = \frac{C}{B} \cdot \frac{dx}{x}$  which we can integrate for any given t (t is treated as a constant)

Integrating  $(1 + A \cdot t) \cdot \ln(y) = \frac{C}{B} \cdot \ln(x) + \text{const}$

The solution is  $y^{1+A \cdot t} = \text{const} \cdot x^{\frac{C}{B}}$

For particles at (1,1) at t = 0, 1, and 2s  $y = x$   $y = x^{\frac{2}{3}}$   $y = x^{\frac{1}{2}}$



## Problem 2.29

[Difficulty: 4]

**2.29** Streaklines are traced out by neutrally buoyant marker fluid injected into a flow field from a fixed point in space. A particle of the marker fluid that is at point  $(x, y)$  at time  $t$  must have passed through the injection point  $(x_0, y_0)$  at some earlier instant  $t = \tau$ . The time history of a marker particle may be found by solving the pathline equations for the initial conditions that  $x = x_0, y = y_0$  when  $t = \tau$ . The present locations of particles on the streakline are obtained by setting  $\tau$  equal to values in the range  $0 \leq \tau \leq t$ . Consider the flow field  $\vec{V} = ax(1 + bt)\hat{i} + cy\hat{j}$ , where  $a = c = 1 \text{ s}^{-1}$  and  $b = 0.2 \text{ s}^{-1}$ . Coordinates are measured in meters. Plot the streakline that passes through the initial point  $(x_0, y_0) = (1, 1)$ , during the interval from  $t = 0$  to  $t = 3 \text{ s}$ . Compare with the streamline plotted through the same point at the instants  $t = 0, 1,$  and  $2 \text{ s}$ .

**Given:** Velocity field

**Find:** Plot of streakline for  $t = 0$  to  $3 \text{ s}$  at point  $(1,1)$ ; compare to streamlines through same point at the instants  $t = 0, 1$  and  $2 \text{ s}$

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

Following the discussion leading up to Eq. 2.10, we first find equations for the pathlines in form

$$x_p(t) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_p(t) = y(t, x_0, y_0, t_0)$$

$$x_{st}(t_0) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_{st}(t_0) = y(t, x_0, y_0, t_0)$$

which gives the streakline at  $t$ , where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

**Assumption:** 2D flow

For pathlines  $u_p = \frac{dx}{dt} = a \cdot x \cdot (1 + b \cdot t)$   $a = 1 \frac{1}{s}$   $b = \frac{1}{5} \frac{1}{s}$   $v_p = \frac{dy}{dt} = c \cdot y$   $c = 1 \frac{1}{s}$

So, separating variables  $\frac{dx}{x} = a \cdot (1 + b \cdot t) \cdot dt$   $\frac{dy}{y} = c \cdot dt$

Integrating  $\ln\left(\frac{x}{x_0}\right) = a \cdot \left( t - t_0 + b \cdot \frac{t^2 - t_0^2}{2} \right)$   $\ln\left(\frac{y}{y_0}\right) = c \cdot (t - t_0)$

$$x = x_0 \cdot e^{a \cdot \left( t - t_0 + b \cdot \frac{t^2 - t_0^2}{2} \right)} \quad y = y_0 \cdot e^{c \cdot (t - t_0)}$$

The pathlines are 
$$x_p(t) = x_0 \cdot e^{a \cdot \left( t - t_0 + b \cdot \frac{t^2 - t_0^2}{2} \right)} \quad y_p(t) = y_0 \cdot e^{c \cdot (t - t_0)}$$

where  $x_0, y_0$  is the position of the particle at  $t = t_0$ . Re-interpreting the results as streaklines:

The streaklines are then 
$$x_{st}(t_0) = x_0 \cdot e^{a \cdot \left( t - t_0 + b \cdot \frac{t^2 - t_0^2}{2} \right)} \quad y_{st}(t_0) = y_0 \cdot e^{c \cdot (t - t_0)}$$

where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

For streamlines 
$$\frac{v}{u} = \frac{dy}{dx} = \frac{c \cdot y}{a \cdot x \cdot (1 + b \cdot t)}$$


So, separating variables 
$$(1 + b \cdot t) \cdot \frac{dy}{y} = \frac{c}{a} \cdot \frac{dx}{x} \quad \text{which we can integrate for any given } t \text{ (} t \text{ is treated as a constant)}$$

Integrating 
$$(1 + b \cdot t) \cdot \ln(y) = \frac{c}{a} \cdot \ln(x) + \text{const}$$

The solution is 
$$y^{1+b \cdot t} = \text{const} \cdot x^{\frac{c}{a}}$$

For particles at (1,1) at  $t = 0, 1, \text{ and } 2\text{s}$  
$$y = x \quad y = x^{\frac{2}{3}} \quad y = x^{\frac{1}{2}}$$

Streamline and Pathline Plots



## Problem 2.30

[Difficulty: 4]

**2.30** Consider the flow field  $\vec{V} = ax\hat{i} + b\hat{j}$ , where  $a = 1/4 \text{ s}^{-2}$  and  $b = 1/3 \text{ m/s}$ . Coordinates are measured in meters. For the particle that passes through the point  $(x, y) = (1, 2)$  at the instant  $t = 0$ , plot the pathline during the time interval from  $t = 0$  to  $3 \text{ s}$ . Compare this pathline with the streakline through the same point at the instant  $t = 3 \text{ s}$ .

**Given:** Velocity field

**Find:** Plot of pathline for  $t = 0$  to  $3 \text{ s}$  for particle that started at point  $(1, 2)$  at  $t = 0$ ; compare to streakline through same point at the instant  $t = 3$

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$        $v_p = \frac{dy}{dt}$

Following the discussion leading up to Eq. 2.10, we first find equations for the pathlines in form

$$x_p(t) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_p(t) = y(t, x_0, y_0, t_0)$$

$$x_{st}(t_0) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_{st}(t_0) = y(t, x_0, y_0, t_0)$$

which gives the streakline at  $t$ , where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

**Assumption:** 2D flow

For pathlines  $u_p = \frac{dx}{dt} = a \cdot x \cdot t$        $a = \frac{1}{4} \frac{1}{\text{s}^2}$        $b = \frac{1}{3} \frac{\text{m}}{\text{s}}$        $v_p = \frac{dy}{dt} = b$

So, separating variables  $\frac{dx}{x} = a \cdot t \cdot dt$        $dy = b \cdot dt$

Integrating  $\ln\left(\frac{x}{x_0}\right) = \frac{a}{2} \cdot (t^2 - t_0^2)$        $y - y_0 = b \cdot (t - t_0)$

$$x = x_0 \cdot e^{\frac{a}{2} \cdot (t^2 - t_0^2)} \quad y = y_0 + b \cdot (t - t_0)$$


The pathlines are  $x_p(t) = x_0 \cdot e^{\frac{a}{2} \cdot (t^2 - t_0^2)}$        $y_p(t) = y_0 + b \cdot (t - t_0)$

where  $x_0, y_0$  is the position of the particle at  $t = t_0$ . Re-interpreting the results as streaklines:

The pathlines are then  $x_{st}(t_0) = x_0 \cdot e^{\frac{a}{2} \cdot (t^2 - t_0^2)}$        $y_{st}(t_0) = y_0 + b \cdot (t - t_0)$

where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

Streakline and Pathline Plots



## Problem 2.31

[Difficulty: 4]

**2.31** A flow is described by velocity field  $\vec{V} = ay^2\hat{i} + b\hat{j}$ , where  $a = 1 \text{ m}^{-1}\text{s}^{-1}$  and  $b = 2 \text{ m/s}$ . Coordinates are measured in meters. Obtain the equation for the streamline passing through point (6, 6). At  $t = 1 \text{ s}$ , what are the coordinates of the particle that passed through point (1, 4) at  $t = 0$ ? At  $t = 3 \text{ s}$ , what are the coordinates of the particle that passed through point (-3, 0) 2 s earlier? Show that pathlines, streamlines, and streaklines for this flow coincide.

**Given:** 2D velocity field

**Find:** Streamlines passing through (6,6); Coordinates of particle starting at (1,4); that pathlines, streamlines and streaklines coincide

**Solution:**

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{b}{a \cdot y^2}$  or  $\int a \cdot y^2 dy = \int b dx$

Integrating  $\frac{a \cdot y^3}{3} = b \cdot x + c$

For the streamline through point (6,6)  $c = 60$  and  $y^3 = 6 \cdot x + 180$

For particle that passed through (1,4) at  $t = 0$   $u = \frac{dx}{dt} = a \cdot y^2$   $\int 1 dx = x - x_0 = \int a \cdot y^2 dt$  We need  $y(t)$

$v = \frac{dy}{dt} = b$   $\int 1 dy = \int b dt$   $y = y_0 + b \cdot t = y_0 + 2 \cdot t$

Then  $x - x_0 = \int_0^t a \cdot (y_0 + b \cdot t)^2 dt$   $x = x_0 + a \cdot \left( y_0^2 \cdot t + b \cdot y_0 \cdot t^2 + \frac{b^2 \cdot t^3}{3} \right)$

Hence, with  $x_0 = 1$   $y_0 = 4$   $x = 1 + 16 \cdot t + 8 \cdot t^2 + \frac{4}{3} \cdot t^3$  At  $t = 1 \text{ s}$   $x = 26.3 \cdot \text{m}$

$y = 4 + 2 \cdot t$   $y = 6 \cdot \text{m}$

For particle that passed through (-3,0) at  $t = 1$   $\int 1 dy = \int b dt$   $y = y_0 + b \cdot (t - t_0)$

$x - x_0 = \int_{t_0}^t a \cdot (y_0 + b \cdot t)^2 dt$   $x = x_0 + a \cdot \left[ y_0^2 \cdot (t - t_0) + b \cdot y_0 \cdot (t^2 - t_0^2) + \frac{b^2}{3} \cdot (t^3 - t_0^3) \right]$

Hence, with  $x_0 = -3$ ,  $y_0 = 0$  at  $t_0 = 1$   $x = -3 + \frac{4}{3} \cdot (t^3 - 1) = \frac{1}{3} \cdot (4 \cdot t^3 - 13)$   $y = 2 \cdot (t - 1)$

Evaluating at  $t = 3$   $x = 31.7 \cdot \text{m}$   $y = 4 \cdot \text{m}$

This is a steady flow, so pathlines, streamlines and streaklines always coincide

### Problem 2.32

[Difficulty: 3]

**2.32** Tiny hydrogen bubbles are being used as tracers to visualize a flow. All the bubbles are generated at the origin ( $x=0, y=0$ ). The velocity field is unsteady and obeys the equations:

$$\begin{aligned} u &= 1 \text{ m/s} & v &= 2 \text{ m/s} & 0 \leq t < 2 \text{ s} \\ u &= 0 & v &= -1 \text{ m/s} & 0 \leq t \leq 4 \text{ s} \end{aligned}$$


Plot the pathlines of bubbles that leave the origin at  $t=0, 1, 2, 3,$  and  $4$  s. Mark the locations of these five bubbles at  $t=4$  s. Use a dashed line to indicate the position of a streakline at  $t=4$  s.

#### Solution

The particle starting at  $t=3$  s follows the particle starting at  $t=2$  s;  
The particle starting at  $t=4$  s doesn't move!

Pathlines:      Starting at  $t=0$       Starting at  $t=1$  s      Starting at  $t=2$  s      Streakline at  $t=4$  s

t	x	y	x	y	x	y	x	y
0.00	0.00	0.00					2.00	2.00
0.20	0.20	0.40					1.80	1.60
0.40	0.40	0.80					1.60	1.20
0.60	0.60	1.20					1.40	0.80
0.80	0.80	1.60					1.20	0.40
1.00	1.00	2.00	0.00	0.00			1.00	0.00
1.20	1.20	2.40	0.20	0.40			0.80	-0.40
1.40	1.40	2.80	0.40	0.80			0.60	-0.80
1.60	1.60	3.20	0.60	1.20			0.40	-1.20
1.80	1.80	3.60	0.80	1.60			0.20	-1.60
2.00	2.00	4.00	1.00	2.00	0.00	0.00	0.00	-2.00
2.20	2.00	3.80	1.00	1.80	0.00	-0.20	0.00	-1.80
2.40	2.00	3.60	1.00	1.60	0.00	-0.40	0.00	-1.60
2.60	2.00	3.40	1.00	1.40	0.00	-0.60	0.00	-1.40
2.80	2.00	3.20	1.00	1.20	0.00	-0.80	0.00	-1.20
3.00	2.00	3.00	1.00	1.00	0.00	-1.00	0.00	-1.00
3.20	2.00	2.80	1.00	0.80	0.00	-1.20	0.00	-0.80
3.40	2.00	2.60	1.00	0.60	0.00	-1.40	0.00	-0.60
3.60	2.00	2.40	1.00	0.40	0.00	-1.60	0.00	-0.40
3.80	2.00	2.20	1.00	0.20	0.00	-1.80	0.00	-0.20
4.00	2.00	2.00	1.00	0.00	0.00	-2.00	0.00	0.00



## Problem 2.33

[Difficulty: 3]

**2.33** A flow is described by velocity field  $\vec{V} = ax\hat{i} + b\hat{j}$ , where  $a = 1/5 \text{ s}^{-1}$  and  $b = 1 \text{ m/s}$ . Coordinates are measured in meters. Obtain the equation for the streamline passing through point (1, 1). At  $t = 5 \text{ s}$ , what are the coordinates of the particle that initially (at  $t = 0$ ) passed through point (1, 1)? What are its coordinates at  $t = 10 \text{ s}$ ? Plot the streamline and the initial, 5 s, and 10 s positions of the particle. What conclusions can you draw about the pathline, streamline, and streakline for this flow?

**Given:** Velocity field

**Find:** Equation for streamline through point (1,1); coordinates of particle at  $t = 5 \text{ s}$  and  $t = 10 \text{ s}$  that was at (1,1) at  $t = 0$ ; compare pathline, streamline, streakline

**Solution:**

**Governing equations:** For streamlines  $\frac{v}{u} = \frac{dy}{dx}$  For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$

**Assumption:** 2D flow

Given data  $a = \frac{1}{5} \frac{1}{\text{s}}$   $b = 1 \frac{\text{m}}{\text{s}}$   $x_0 = 1$   $y_0 = 1$   $t_0 = 0$

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{b}{a \cdot x}$

So, separating variables  $\frac{a}{b} \cdot dy = \frac{dx}{x}$

Integrating  $\frac{a}{b} \cdot (y - y_0) = \ln\left(\frac{x}{x_0}\right)$

The solution is then  $y = y_0 + \frac{b}{a} \cdot \ln\left(\frac{x}{x_0}\right) = 5 \cdot \ln(x) + 1$

Hence for pathlines  $u_p = \frac{dx}{dt} = a \cdot x$   $v_p = \frac{dy}{dt} = b$

Hence  $\frac{dx}{x} = a \cdot dt$   $dy = b \cdot dt$

Integrating  $\ln\left(\frac{x}{x_0}\right) = a \cdot (t - t_0)$   $y - y_0 = b \cdot (t - t_0)$

The pathlines are  $x = x_0 \cdot e^{a \cdot (t - t_0)}$   $y = y_0 + b \cdot (t - t_0)$  or  $y = y_0 + \frac{b}{a} \cdot \ln\left(\frac{x}{x_0}\right)$

For a particle that was at  $x_0 = 1$  m,  $y_0 = 1$  m at  $t_0 = 0$  s, at time  $t = 1$  s we find the position is

$$x = x_0 \cdot e^{a \cdot (t-t_0)} = e^{\frac{1}{5}} \text{ m} \quad y = y_0 + b \cdot (t - t_0) = 2 \text{ m}$$


For a particle that was at  $x_0 = 1$  m,  $y_0 = 1$  m at  $t_0 = 0$  s, at time  $t = 5$  s we find the position is

$$x = x_0 \cdot e^{a \cdot (t-t_0)} = e \text{ m} \quad y = y_0 + b \cdot (t - t_0) = 6 \text{ m}$$

For a particle that was at  $x_0 = 1$  m,  $y_0 = 1$  at  $t_0 = 0$  s, at time  $t = 10$  s we find the position is

$$x = x_0 \cdot e^{a \cdot (t-t_0)} = e^2 \text{ m} \quad y = y_0 + b \cdot (t - t_0) = 11 \text{ m}$$

For this steady flow streamlines, streaklines and pathlines coincide



## Problem 2.34

[Difficulty: 3]

**2.34** A flow is described by velocity field  $\vec{V} = a\hat{i} + bx\hat{j}$ , where  $a = 2 \text{ m/s}$  and  $b = 1 \text{ s}^{-1}$ . Coordinates are measured in meters. Obtain the equation for the streamline passing through point (2, 5). At  $t = 2 \text{ s}$ , what are the coordinates of the particle that passed through point (0, 4) at  $t = 0$ ? At  $t = 3 \text{ s}$ , what are the coordinates of the particle that passed through point (1, 4.25) 2 s earlier? What conclusions can you draw about the pathline, streamline, and streakline for this flow?

**Given:** Velocity field

**Find:** Equation for streamline through point (2.5); coordinates of particle at  $t = 2 \text{ s}$  that was at (0,4) at  $t = 0$ ; coordinates of particle at  $t = 3 \text{ s}$  that was at (1,4.25) at  $t = 1 \text{ s}$ ; compare pathline, streamline, streakline

**Solution:**

**Governing equations:** For streamlines  $\frac{v}{u} = \frac{dy}{dx}$  For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$

**Assumption:** 2D flow

Given data  $a = 2 \frac{\text{m}}{\text{s}}$   $b = 1 \frac{1}{\text{s}}$   $x_0 = 2$   $y_0 = 5$   $x = 1$   $x = x$

For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{b \cdot x}{a}$

So, separating variables  $\frac{a}{b} \cdot dy = x \cdot dx$

Integrating  $\frac{a}{b} \cdot (y - y_0) = \frac{1}{2} \cdot (x^2 - x_0^2)$

The solution is then  $y = y_0 + \frac{b}{2 \cdot a} \cdot (x^2 - x_0^2) = \frac{x^2}{4} + 4$

Hence for pathlines  $u_p = \frac{dx}{dt} = a$   $v_p = \frac{dy}{dt} = b \cdot x$

Hence  $dx = a \cdot dt$   $dy = b \cdot x \cdot dt$

Integrating  $x - x_0 = a \cdot (t - t_0)$   $dy = b \cdot [x_0 + a \cdot (t - t_0)] \cdot dt$

$$y - y_0 = b \cdot \left[ x_0 \cdot (t - t_0) + \frac{a}{2} \cdot (t^2 - t_0^2) \right] - a \cdot t_0 \cdot (t - t_0)$$

The pathlines are  $x = x_0 + a \cdot (t - t_0)$   $y = y_0 + b \cdot \left[ x_0 \cdot (t - t_0) + \frac{a}{2} \cdot (t^2 - t_0^2) \right] - a \cdot t_0 \cdot (t - t_0)$


For a particle that was at  $x_0 = 0$  m,  $y_0 = 4$  m at  $t_0 = 0$  s, at time  $t = 2$  s we find the position is

$$x = x_0 + a \cdot (t - t_0) = 4 \text{ m} \quad y = y_0 + b \cdot \left[ x_0 \cdot (t - t_0) + \frac{a}{2} \cdot \left( (t - t_0)^2 \right) - a \cdot t_0 \cdot (t - t_0) \right] = 10 \text{ m}$$

For a particle that was at  $x_0 = 1$  m,  $y_0 = 4.25$  m at  $t_0 = 1$  s, at time  $t = 3$  s we find the position is

$$x = x_0 + a \cdot (t - t_0) = 5 \text{ m} \quad y = y_0 + b \cdot \left[ x_0 \cdot (t - t_0) + \frac{a}{2} \cdot \left( (t - t_0)^2 \right) - a \cdot t_0 \cdot (t - t_0) \right] = 10.5 \text{ m}$$

For this steady flow streamlines, streaklines and pathlines coincide; the particles referred to are the same particle!



## Problem 2.35

[Difficulty: 4]

**2.35** A flow is described by velocity field  $\vec{V} = ay\hat{i} + b\hat{j}$ , where  $a = 0.2 \text{ s}^{-1}$  and  $b = 0.4 \text{ m/s}^2$ . At  $t = 2 \text{ s}$ , what are the coordinates of the particle that passed through point (1, 2) at  $t = 0$ ? At  $t = 3 \text{ s}$ , what are the coordinates of the particle that passed through point (1, 2) at  $t = 2 \text{ s}$ ? Plot the pathline and streakline through point (1, 2), and plot the streamlines through the same point at the instants  $t = 0, 1, 2$ , and  $3 \text{ s}$ .

**Given:** Velocity field

**Find:** Coordinates of particle at  $t = 2 \text{ s}$  that was at (1,2) at  $t = 0$ ; coordinates of particle at  $t = 3 \text{ s}$  that was at (1,2) at  $t = 2 \text{ s}$ ; plot pathline and streakline through point (1,2) and compare with streamlines through same point at  $t = 0, 1$  and  $2 \text{ s}$

### Solution

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

Following the discussion leading up to Eq. 2.10, we first find equations for the pathlines in form

$$x_p(t) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_p(t) = y(t, x_0, y_0, t_0)$$

$$x_{st}(t_0) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_{st}(t_0) = y(t, x_0, y_0, t_0)$$

which gives the streakline at  $t$ , where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

**Assumption:** 2D flow

Given data  $a = 0.2 \frac{1}{\text{s}} \quad b = 0.4 \frac{\text{m}}{\text{s}^2}$

Hence for pathlines  $u_p = \frac{dx}{dt} = a \cdot y \quad v_p = \frac{dy}{dt} = b \cdot t$

Hence  $dx = a \cdot y \cdot dt \quad dy = b \cdot t \cdot dt \quad y - y_0 = \frac{b}{2} \cdot (t^2 - t_0^2)$

For x  $dx = \left[ a \cdot y_0 + a \cdot \frac{b}{2} \cdot (t^2 - t_0^2) \right] \cdot dt$

Integrating  $x - x_0 = a \cdot y_0 \cdot (t - t_0) + a \cdot \frac{b}{2} \cdot \left[ \frac{t^3}{3} - \frac{t_0^3}{3} - t_0^2 \cdot (t - t_0) \right]$

The pathlines are  $x(t) = x_0 + a \cdot y_0 \cdot (t - t_0) + a \cdot \frac{b}{2} \cdot \left[ \frac{t^3}{3} - \frac{t_0^3}{3} - t_0^2 \cdot (t - t_0) \right] \quad y(t) = y_0 + \frac{b}{2} \cdot (t^2 - t_0^2)$

These give the position (x,y) at any time  $t$  of a particle that was at  $(x_0, y_0)$  at time  $t_0$

Note that streaklines are obtained using the logic of the Governing equations, above

The streaklines are 
$$x(t_0) = x_0 + a \cdot y_0 \cdot (t - t_0) + a \cdot \frac{b}{2} \cdot \left[ \frac{t^3}{3} - \frac{t_0^3}{3} - t_0^2 \cdot (t - t_0) \right] \quad y(t_0) = y_0 + \frac{b}{2} \cdot (t^2 - t_0^2)$$

These gives the streakline at t, where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to t)

For a particle that was at  $x_0 = 1$  m,  $y_0 = 2$  m at  $t_0 = 0$  s, at time  $t = 2$  s we find the position is (from pathline equations)

$$x = x_0 + a \cdot y_0 \cdot (t - t_0) + a \cdot \frac{b}{2} \cdot \left[ \frac{t^3}{3} - \frac{t_0^3}{3} - t_0^2 \cdot (t - t_0) \right] = 1.9 \text{ m} \quad y = y_0 + \frac{b}{2} \cdot (t^2 - t_0^2) = 2.8 \text{ m}$$

For a particle that was at  $x_0 = 1$  m,  $y_0 = 2$  m at  $t_0 = 2$  s, at time  $t = 3$  s we find the position is

$$x = x_0 + a \cdot y_0 \cdot (t - t_0) + a \cdot \frac{b}{2} \cdot \left[ \frac{t^3}{3} - \frac{t_0^3}{3} - t_0^2 \cdot (t - t_0) \right] = 1.4 \text{ m} \quad y = y_0 + \frac{b}{2} \cdot (t^2 - t_0^2) = 3.0 \text{ m}$$


For streamlines 
$$\frac{v}{u} = \frac{dy}{dx} = \frac{b \cdot t}{a \cdot y}$$

So, separating variables 
$$y \cdot dy = \frac{b}{a} \cdot t \cdot dx \quad \text{where we treat } t \text{ as a constant}$$


Integrating 
$$\frac{y^2 - y_0^2}{2} = \frac{b \cdot t}{a} \cdot (x - x_0) \quad \text{and we have } x_0 = 1 \text{ m } y_0 = 2 \text{ m}$$

The streamlines are then 
$$y = \sqrt{y_0^2 + \frac{2 \cdot b \cdot t}{a} \cdot (x - x_0)} = \sqrt{4 \cdot t \cdot (x - 1) + 4}$$

Pathline Plots



Streamline Plots



## Problem 2.36

[Difficulty: 4]

**2.36** A flow is described by velocity field  $\vec{V} = at\hat{i} + b\hat{j}$ , where  $a = 0.4 \text{ m/s}^2$  and  $b = 2 \text{ m/s}$ . At  $t = 2 \text{ s}$ , what are the coordinates of the particle that passed through point  $(2, 1)$  at  $t = 0$ ? At  $t = 3 \text{ s}$ , what are the coordinates of the particle that passed through point  $(2, 1)$  at  $t = 2 \text{ s}$ ? Plot the pathline and streakline through point  $(2, 1)$  and compare with the streamlines through the same point at the instants  $t = 0, 1,$  and  $2 \text{ s}$ .

**Given:** Velocity field

**Find:** Coordinates of particle at  $t = 2 \text{ s}$  that was at  $(2,1)$  at  $t = 0$ ; coordinates of particle at  $t = 3 \text{ s}$  that was at  $(2,1)$  at  $t = 2 \text{ s}$ ; plot pathline and streakline through point  $(2,1)$  and compare with streamlines through same point at  $t = 0, 1$  and  $2 \text{ s}$

**Solution:**

**Governing equations:** For pathlines  $u_p = \frac{dx}{dt}$   $v_p = \frac{dy}{dt}$  For streamlines  $\frac{v}{u} = \frac{dy}{dx}$

Following the discussion leading up to Eq. 2.10, we first find equations for the pathlines in form

$$x_p(t) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_p(t) = y(t, x_0, y_0, t_0)$$

$$x_{st}(t_0) = x(t, x_0, y_0, t_0) \quad \text{and} \quad y_{st}(t_0) = y(t, x_0, y_0, t_0)$$

which gives the streakline at  $t$ , where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

**Assumption:** 2D flow

Given data  $a = 0.4 \frac{\text{m}}{\text{s}^2}$   $b = 2 \frac{\text{m}}{\text{s}}$

Hence for pathlines  $u_p = \frac{dx}{dt} = a \cdot t$   $v_p = \frac{dy}{dt} = b$

Hence  $dx = a \cdot t \cdot dt$   $dy = b \cdot dt$

Integrating  $x - x_0 = \frac{a}{2} \cdot (t^2 - t_0^2)$   $y - y_0 = b \cdot (t - t_0)$

The pathlines are  $x(t) = x_0 + \frac{a}{2} \cdot (t^2 - t_0^2)$   $y(t) = y_0 + b \cdot (t - t_0)$

These give the position  $(x,y)$  at any time  $t$  of a particle that was at  $(x_0,y_0)$  at time  $t_0$

Note that streaklines are obtained using the logic of the Governing equations, above

The streaklines are  $x(t_0) = x_0 + \frac{a}{2} \cdot (t^2 - t_0^2)$   $y(t_0) = y_0 + b \cdot (t - t_0)$

These gives the streakline at  $t$ , where  $x_0, y_0$  is the point at which dye is released ( $t_0$  is varied from 0 to  $t$ )

For a particle that was at  $x_0 = 2$  m,  $y_0 = 1$  m at  $t_0 = 0$ s, at time  $t = 2$  s we find the position is (from pathline equations)

$$x = x_0 + \frac{a}{2} \cdot (t^2 - t_0^2) = 2.8 \text{ m} \qquad y = y_0 + b \cdot (t - t_0) = 5 \text{ m}$$

For a particle that was at  $x_0 = 2$  m,  $y_0 = 1$  m at  $t_0 = 2$  s, at time  $t = 3$  s we find the position is

$$x = x_0 + \frac{a}{2} \cdot (t^2 - t_0^2) = 3 \text{ m} \qquad y = y_0 + b \cdot (t - t_0) = 3 \text{ m}$$


For streamlines  $\frac{v}{u} = \frac{dy}{dx} = \frac{b}{a \cdot t}$

So, separating variables  $dy = \frac{b}{a \cdot t} \cdot dx$  where we treat  $t$  as a constant


Integrating  $y - y_0 = \frac{b}{a \cdot t} \cdot (x - x_0)$  and we have  $x_0 = 2$  m  $y_0 = 1$  m

The streamlines are then  $y = y_0 + \frac{b}{a \cdot t} \cdot (x - x_0) = \frac{5 \cdot (x - 2)}{t} + 1$

Pathline Plots



Streamline Plots



## Problem 2.37

[Difficulty: 2]

**2.37** The variation with temperature of the viscosity of air is represented well by the empirical Sutherland correlation

$$\mu = \frac{bT^{1/2}}{1 + S/T}$$

Best-fit values of  $b$  and  $S$  are given in Appendix A. Develop an equation in SI units for kinematic viscosity versus temperature for air at atmospheric pressure. Assume ideal gas behavior. Check by using the equation to compute the kinematic viscosity of air at  $0^\circ\text{C}$  and at  $100^\circ\text{C}$  and comparing to the data in Appendix 10 (Table A.10); plot the kinematic viscosity for a temperature range of  $0^\circ\text{C}$  to  $100^\circ\text{C}$ , using the equation and the data in Table A.10.

**Given:** Sutherland equation

**Find:** Corresponding equation for kinematic viscosity

**Solution:**

**Governing equation:**  $\mu = \frac{b \cdot T^{\frac{1}{2}}}{1 + \frac{S}{T}}$  Sutherland equation       $p = \rho \cdot R \cdot T$  Ideal gas equation

**Assumptions:** Sutherland equation is valid; air is an ideal gas

The given data is       $b = 1.458 \times 10^{-6} \cdot \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^{\frac{1}{2}}}$        $S = 110.4 \cdot \text{K}$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $p = 101.3 \cdot \text{kPa}$

The kinematic viscosity is       $\nu = \frac{\mu}{\rho} = \frac{\mu \cdot R \cdot T}{p} = \frac{R \cdot T}{p} \cdot \frac{b \cdot T^{\frac{1}{2}}}{1 + \frac{S}{T}} = \frac{R \cdot b}{p} \cdot \frac{T^{\frac{3}{2}}}{1 + \frac{S}{T}} = \frac{b' \cdot T^{\frac{3}{2}}}{1 + \frac{S}{T}}$

where       $b' = \frac{R \cdot b}{p}$        $b' = 4.129 \times 10^{-9} \cdot \frac{\text{m}^2}{\text{K}^{1.5} \cdot \text{s}}$

$$b' = 286.9 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 1.458 \times 10^{-6} \cdot \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^{\frac{1}{2}}} \times \frac{\text{m}^2}{101.3 \times 10^3 \cdot \text{N}} = 4.129 \times 10^{-9} \cdot \frac{\text{m}^2}{\text{s} \cdot \text{K}^{\frac{3}{2}}}$$


Hence       $\nu = \frac{b' \cdot T^{\frac{3}{2}}}{1 + \frac{S}{T}}$  with       $b' = 4.129 \times 10^{-9} \cdot \frac{\text{m}^2}{\text{s} \cdot \text{K}^{\frac{3}{2}}}$        $S = 110.4 \text{ K}$

Check with Appendix A, Table A.10. At  $T = 0^\circ\text{C}$  we find  $T = 273.1\text{ K}$   $\nu = 1.33 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$

$$\nu = \frac{4.129 \times 10^{-9} \frac{\text{m}^2}{\text{s} \cdot \text{K}^{\frac{3}{2}}} \times (273.1 \cdot \text{K})^{\frac{3}{2}}}{1 + \frac{110.4}{273.1}} \quad \nu = 1.33 \times 10^{-5} \frac{\text{m}^2}{\text{s}} \quad \text{Check!}$$

At  $T = 100^\circ\text{C}$  we find  $T = 373.1\text{ K}$   $\nu = 2.29 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$

$$\nu = \frac{4.129 \times 10^{-9} \frac{\text{m}^2}{\text{s} \cdot \text{K}^{\frac{3}{2}}} \times (373.1 \cdot \text{K})^{\frac{3}{2}}}{1 + \frac{110.4}{373.1}} \quad \nu = 2.30 \times 10^{-5} \frac{\text{m}^2}{\text{s}} \quad \text{Check!}$$



## Problem 2.38

[Difficulty: 2]

**2.38** The variation with temperature of the viscosity of air is correlated well by the empirical Sutherland equation

$$\mu = \frac{bT^{1/2}}{1 + S/T}$$

Best-fit values of  $b$  and  $S$  are given in Appendix A for use with SI units. Use these values to develop an equation for calculating air viscosity in British Gravitational units as a function of absolute temperature in degrees Rankine. Check your result using data from Appendix A.

**Given:** Sutherland equation with SI units

**Find:** Corresponding equation in BG units

**Solution:**

**Governing equation:** 
$$\mu = \frac{b \cdot T^{\frac{1}{2}}}{1 + \frac{S}{T}} \quad \text{Sutherland equation}$$

**Assumption:** Sutherland equation is valid

The given data is 
$$b = 1.458 \times 10^{-6} \cdot \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^{\frac{1}{2}}} \quad S = 110.4 \cdot \text{K}$$

Converting constants 
$$b = 1.458 \times 10^{-6} \cdot \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^{\frac{1}{2}}} \times \frac{\text{lbm}}{0.454 \cdot \text{kg}} \times \frac{\text{slug}}{32.2 \cdot \text{lbm}} \times \frac{0.3048 \cdot \text{m}}{\text{ft}} \times \left( \frac{5 \cdot \text{K}}{9 \cdot \text{R}} \right)^{\frac{1}{2}} \quad b = 2.27 \times 10^{-8} \cdot \frac{\text{slug}}{\text{ft} \cdot \text{s} \cdot \text{R}^{\frac{1}{2}}}$$

Alternatively 
$$b = 2.27 \times 10^{-8} \cdot \frac{\text{slug}}{\text{ft} \cdot \text{s} \cdot \text{R}^{\frac{1}{2}}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad b = 2.27 \times 10^{-8} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2 \cdot \text{R}^{\frac{1}{2}}}$$

Also 
$$S = 110.4 \cdot \text{K} \times \frac{9 \cdot \text{R}}{5 \cdot \text{K}} \quad S = 198.7 \cdot \text{R}$$

and 
$$\mu = \frac{b \cdot T^{\frac{1}{2}}}{1 + \frac{S}{T}} \quad \text{with } T \text{ in Rankine, } \mu \text{ in } \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$$

Check with Appendix A, Table A.9. At  $T = 68^\circ\text{F}$  we find  $T = 527.7 \cdot \text{R}$   $\mu = 3.79 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2}$

$$\mu = \frac{2.27 \times 10^{-8} \frac{\text{lb} \cdot \text{s}}{\text{ft}^2 \cdot \text{R}} \times (527.7 \cdot \text{R})^{\frac{1}{2}}}{1 + \frac{198.7}{527.7}} \quad \mu = 3.79 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \quad \text{Check!}$$

At  $T = 200^\circ\text{F}$  we find  $T = 659.7 \cdot \text{R}$   $\mu = 4.48 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2}$

$$\mu = \frac{2.27 \times 10^{-8} \frac{\text{lb} \cdot \text{s}}{\text{ft}^2 \cdot \text{R}} \times (659.7 \cdot \text{R})^{\frac{1}{2}}}{1 + \frac{198.7}{659.7}} \quad \mu = 4.48 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \quad \text{Check!}$$

## Problem 2.39

[Difficulty: 3]

**2.39** Some experimental data for the viscosity of helium at 1 atm are

$T, ^\circ\text{C}$	0	100	200	300	400
$\mu, \text{N} \cdot \text{s}/\text{m}^2 (\times 10^5)$	1.86	2.31	2.72	3.11	3.46

Using the approach described in Appendix A.3, correlate these data to the empirical Sutherland equation

$$\mu = \frac{bT^{1/2}}{1 + S/T}$$

(where  $T$  is in kelvin) and obtain values for constants  $b$  and  $S$ .

**Given:** Viscosity data

**Find:** Obtain values for coefficients in Sutherland equation

**Solution:**

**Data:** Using procedure of Appendix A.3:

$T (^{\circ}\text{C})$	$T (\text{K})$	$\mu (\times 10^5)$
0	273	1.86E-05
100	373	2.31E-05
200	473	2.72E-05
300	573	3.11E-05
400	673	3.46E-05

$T (\text{K})$	$T^{3/2}/\mu$
273	2.43E+08
373	3.12E+08
473	3.78E+08
573	4.41E+08
673	5.05E+08

The equation to solve for coefficients  $S$  and  $b$  is


$$\frac{T^{3/2}}{\mu} = \left(\frac{1}{b}\right)T + \frac{S}{b}$$

From the built-in *Excel* *Linear Regression* functions:

Slope = 6.534E+05  
 Intercept = 6.660E+07  
 $R^2 = 0.9996$

Hence:

$b = 1.531\text{E-}06 \text{ kg/m}\cdot\text{s}\cdot\text{K}^{1/2}$   
 $S = 101.9 \text{ K}$



## Problem 2.40

[Difficulty: 2]

**2.40** The velocity distribution for laminar flow between parallel plates is given by

$$\frac{u}{u_{\max}} = 1 - \left(\frac{2y}{h}\right)^2$$

where  $h$  is the distance separating the plates and the origin is placed midway between the plates. Consider a flow of water at  $15^\circ\text{C}$ , with  $u_{\max} = 0.10 \text{ m/s}$  and  $h = 0.1 \text{ mm}$ . Calculate the shear stress on the upper plate and give its direction. Sketch the variation of shear stress across the channel.

**Given:** Velocity distribution between flat plates

**Find:** Shear stress on upper plate; Sketch stress distribution

**Solution:**

Basic equation  $\tau_{yx} = \mu \frac{du}{dy}$        $\frac{du}{dy} = \frac{d}{dy} u_{\max} \left[ 1 - \left(\frac{2y}{h}\right)^2 \right] = u_{\max} \left( -\frac{4}{h^2} \right) \cdot 2y = -\frac{8 \cdot u_{\max} \cdot y}{h^2}$


$$\tau_{yx} = -\frac{8 \cdot \mu \cdot u_{\max} \cdot y}{h^2}$$

At the upper surface  $y = \frac{h}{2}$     and     $h = 0.1 \text{ mm}$        $u_{\max} = 0.1 \frac{\text{m}}{\text{s}}$        $\mu = 1.14 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$  (Table A.8)

Hence  $\tau_{yx} = -8 \times 1.14 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times 0.1 \frac{\text{m}}{\text{s}} \times \frac{0.1}{2} \text{ mm} \times \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \times \left( \frac{1}{0.1 \cdot \text{mm}} \times \frac{1000 \cdot \text{mm}}{1 \cdot \text{m}} \right)^2$        $\tau_{yx} = -4.56 \frac{\text{N}}{\text{m}^2}$

The upper plate is a minus  $y$  surface. Since  $\tau_{yx} < 0$ , the shear stress on the upper plate must act in the plus  $x$  direction.

The shear stress varies linearly with  $y$        $\tau_{yx}(y) = -\left( \frac{8 \cdot \mu \cdot u_{\max}}{h^2} \right) \cdot y$



Shear Stress (Pa)

## Problem 2.41

[Difficulty: 2]

**2.41** The velocity distribution for laminar flow between parallel plates is given by

$$\frac{u}{u_{\max}} = 1 - \left(\frac{2y}{h}\right)^2$$

where  $h$  is the distance separating the plates and the origin is placed midway between the plates. Consider a flow of water at  $15^\circ\text{C}$  with maximum speed of  $0.05\text{ m/s}$  and  $h = 0.1\text{ mm}$ . Calculate the force on a  $1\text{ m}^2$  section of the lower plate and give its direction.

**Given:** Velocity distribution between parallel plates

**Find:** Force on lower plate

**Solution:**

Basic equations

$$F = \tau_{yx} \cdot A \quad \tau_{yx} = \mu \cdot \frac{du}{dy}$$
$$\frac{du}{dy} = \frac{d}{dy} u_{\max} \left[ 1 - \left(\frac{2y}{h}\right)^2 \right] = u_{\max} \left( -\frac{4}{h^2} \right) \cdot 2 \cdot y = -\frac{8 \cdot u_{\max} \cdot y}{h^2}$$

so

$$\tau_{yx} = -\frac{8 \cdot \mu \cdot u_{\max} \cdot y}{h^2} \quad \text{and} \quad F = -\frac{8 \cdot A \cdot \mu \cdot u_{\max} \cdot y}{h^2}$$

At the lower surface

$$y = -\frac{h}{2} \quad \text{and} \quad h = 0.1 \cdot \text{mm} \quad A = 1 \cdot \text{m}^2$$
$$u_{\max} = 0.05 \cdot \frac{\text{m}}{\text{s}} \quad \mu = 1.14 \times 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \quad (\text{Table A.8})$$

Hence

$$F = -8 \times 1 \cdot \text{m}^2 \times 1.14 \times 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times 0.05 \cdot \frac{\text{m}}{\text{s}} \times \frac{-0.1}{2} \cdot \text{mm} \times \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \times \left( \frac{1}{0.1} \cdot \frac{1}{\text{mm}} \times \frac{1000 \cdot \text{mm}}{1 \cdot \text{m}} \right)^2$$

$$F = 2.28 \cdot \text{N} \quad (\text{to the right})$$

## Problem 2.42

[Difficulty: 2]

---

**2.42** Explain how an ice skate interacts with the ice surface.  
What mechanism acts to reduce sliding friction between skate and ice?

---

**Open-Ended Problem Statement:** Explain how an ice skate interacts with the ice surface.  
What mechanism acts to reduce sliding friction between skate and ice?

**Discussion:** The normal freezing and melting temperature of ice is  $0^{\circ}\text{C}$  ( $32^{\circ}\text{F}$ ) at atmospheric pressure. The melting temperature of ice decreases as pressure is increased. Therefore ice can be caused to melt at a temperature below the normal melting temperature when the ice is subjected to increased pressure. A skater is supported by relatively narrow blades with a short contact against the ice. The blade of a typical skate is less than 3 mm wide. The length of blade in contact with the ice may be just ten or so millimeters. With a 3 mm by 10 mm contact patch, a 75 kg skater is supported by a pressure between skate blade and ice on the order of tens of megaPascals (hundreds of atmospheres). Such a pressure is enough to cause ice to melt rapidly.

When pressure is applied to the ice surface by the skater, a thin surface layer of ice melts to become liquid water and the skate glides on this thin liquid film. Viscous friction is quite small, so the effective friction coefficient is much smaller than for sliding friction.

The magnitude of the viscous drag force acting on each skate blade depends on the speed of the skater, the area of contact, and the thickness of the water layer on top of the ice.

The phenomenon of static friction giving way to viscous friction is similar to the hydroplaning of a pneumatic tire caused by a layer of water on the road surface.

## Problem 2.43

[Difficulty: 2]

**2.43** Crude oil, with specific gravity  $SG = 0.85$  and viscosity  $\mu = 2.15 \times 10^{-3} \text{ lbf} \cdot \text{s}/\text{ft}^2$ , flows steadily down a surface inclined  $\theta = 45$  degrees below the horizontal in a film of thickness  $h = 0.1$  in. The velocity profile is given by

$$u = \frac{\rho g}{\mu} \left( h y - \frac{y^2}{2} \right) \sin \theta$$

(Coordinate  $x$  is along the surface and  $y$  is normal to the surface.) Plot the velocity profile. Determine the magnitude and direction of the shear stress that acts on the surface.


**Given:** Velocity profile

**Find:** Plot of velocity profile; shear stress on surface

**Solution:**

The velocity profile is  $u = \frac{\rho \cdot g}{\mu} \cdot \left( h \cdot y - \frac{y^2}{2} \right) \cdot \sin(\theta)$  so the maximum velocity is at  $y = h$   $u_{\max} = \frac{\rho \cdot g}{\mu} \cdot \frac{h^2}{2} \cdot \sin(\theta)$

Hence we can plot  $\frac{u}{u_{\max}} = 2 \cdot \left[ \frac{y}{h} - \frac{1}{2} \cdot \left( \frac{y}{h} \right)^2 \right]$



This graph can be plotted in *Excel*

The given data is  $h = 0.1 \cdot \text{in}$   $\mu = 2.15 \times 10^{-3} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$   $\theta = 45 \cdot \text{deg}$

Basic equation  $\tau_{yx} = \mu \cdot \frac{du}{dy}$   $\tau_{yx} = \mu \cdot \frac{du}{dy} = \mu \cdot \frac{d}{dy} \left( \frac{\rho \cdot g}{\mu} \cdot \left( h \cdot y - \frac{y^2}{2} \right) \cdot \sin(\theta) \right) = \rho \cdot g \cdot (h - y) \cdot \sin(\theta)$

At the surface  $y = 0$   $\tau_{yx} = \rho \cdot g \cdot h \cdot \sin(\theta)$

Hence  $\tau_{yx} = 0.85 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 0.1 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \times \sin(45 \cdot \text{deg}) \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$   $\tau_{yx} = 0.313 \cdot \frac{\text{lbf}}{\text{ft}^2}$

The surface is a positive  $y$  surface. Since  $\tau_{yx} > 0$ , the shear stress on the surface must act in the plus  $x$  direction.

## Problem 2.44

[Difficulty: 2]


**2.44** A female freestyle ice skater, weighing 100 lbf, glides on one skate at speed  $V = 20$  ft/s. Her weight is supported by a thin film of liquid water melted from the ice by the pressure of the skate blade. Assume the blade is  $L = 11.5$  in. long and  $w = 0.125$  in. wide, and that the water film is  $h = 0.0000575$  in. thick. Estimate the deceleration of the skater that results from viscous shear in the water film, if end effects are neglected.

**Given:** Ice skater and skate geometry

**Find:** Deceleration of skater

**Solution:**

**Governing equation:**  $\tau_{yx} = \mu \frac{du}{dy}$        $\Sigma F_x = M \cdot a_x$



**Assumptions:** Laminar flow

The given data is       $W = 100 \cdot \text{lbf}$        $V = 20 \cdot \frac{\text{ft}}{\text{s}}$        $L = 11.5 \cdot \text{in}$        $w = 0.125 \cdot \text{in}$        $h = 0.0000575 \cdot \text{in}$

$$\mu = 3.68 \times 10^{-5} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \quad \text{Table A.7 @32}^\circ\text{F}$$

Then

$$\tau_{yx} = \mu \frac{du}{dy} = \mu \cdot \frac{V}{h} = 3.68 \times 10^{-5} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \times 20 \cdot \frac{\text{ft}}{\text{s}} \times \frac{1}{0.0000575 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{\text{ft}}$$

$$\tau_{yx} = 154 \cdot \frac{\text{lbf}}{\text{ft}^2}$$

Equation of motion       $\Sigma F_x = M \cdot a_x$       or       $\tau_{yx} \cdot A = \frac{-W}{g} \cdot a_x$

$$a_x = -\frac{\tau_{yx} \cdot A \cdot g}{W} = -\frac{\tau_{yx} \cdot L \cdot w \cdot g}{W}$$

$$a_x = -154 \cdot \frac{\text{lbf}}{\text{ft}^2} \times 11.5 \cdot \text{in} \times 0.125 \cdot \text{in} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{1}{100 \cdot \text{lbf}} \times \frac{\text{ft}^2}{(12 \cdot \text{in})^2}$$

$$a_x = -0.495 \cdot \frac{\text{ft}}{\text{s}^2}$$

## Problem 2.45

[Difficulty: 2]

**2.45** A block weighing 10 lbf and having dimensions 10 in. on each edge is pulled up an inclined surface on which there is a film of SAE 10W oil at 100°F. If the speed of the block is 2 ft/s and the oil film is 0.001 in. thick, find the force required to pull the block. Assume the velocity distribution in the oil film is linear. The surface is inclined at an angle of 25° from the horizontal.

**Given:** Block pulled up incline on oil layer



**Find:** Force required to pull the block

**Solution:**

**Governing equations:**

$$\tau_{yx} = \mu \cdot \frac{du}{dy}$$

$$\Sigma F_x = M \cdot a_x$$



**Assumptions:** Laminar flow

The given data is  $W = 10 \cdot \text{lbf}$        $U = 2 \cdot \frac{\text{ft}}{\text{s}}$        $w = 10 \cdot \text{in}$        $d = 0.001 \cdot \text{in}$        $\theta = 25 \cdot \text{deg}$

$$\mu = 3.7 \times 10^{-2} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \quad \text{Fig. A.2 @100°F (38°C)}$$

Equation of motion  $\Sigma F_x = M \cdot a_x = 0$        $F - f - W \cdot \sin(\theta) = 0$

The friction force is  $f = \tau_{yx} \cdot A = \mu \cdot \frac{du}{dy} \cdot A = \mu \cdot \frac{U}{d} \cdot w^2$

Hence  $F = f + W \cdot \sin(\theta) = \mu \cdot \frac{U}{d} \cdot w^2 + W \cdot \sin(\theta)$

$$F = 3.7 \times 10^{-2} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times 0.0209 \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \cdot \frac{\text{m}^2}{\text{N} \cdot \text{s}} \times 2 \cdot \frac{\text{ft}}{\text{s}} \times \frac{1}{0.001 \cdot \text{in}} \times (10 \cdot \text{in})^2 \times \frac{\text{ft}}{12 \cdot \text{in}} + 10 \cdot \text{lbf} \cdot \sin(25 \cdot \text{deg})$$

$$F = 17.1 \cdot \text{lbf}$$

## Problem 2.46

[Difficulty: 2]

**2.46** A block of mass 10 kg and measuring 250 mm on each edge is pulled up an inclined surface on which there is a film of SAE 10W-30 oil at 30°F (the oil film is 0.025 mm thick). Find the steady speed of the block if it is released. If a force of 75 N is applied to pull the block up the incline, find the steady speed of the block. If the force is now applied to push the block down the incline, find the steady speed of the block. Assume the velocity distribution in the oil film is linear. The surface is inclined at an angle of 30° from the horizontal.

**Given:** Block moving on incline on oil layer



**Find:** Speed of block when free, pulled, and pushed

**Solution:**

**Governing equations:**

$$\tau_{yx} = \mu \cdot \frac{du}{dy}$$

$$\Sigma F_x = M \cdot a_x$$



**Assumptions:** Laminar flow

The given data is  $M = 10\text{-kg}$        $W = M \cdot g$        $W = 98.066\text{ N}$        $w = 250\text{-mm}$

$d = 0.025\text{-mm}$        $\theta = 30\text{-deg}$        $F = 75\text{-N}$

$\mu = 10^{-1} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$       Fig. A.2 SAE 10-39 @30°C

Equation of motion  $\Sigma F_x = M \cdot a_x = 0$       so       $F - f - W \cdot \sin(\theta) = 0$

The friction force is  $f = \tau_{yx} \cdot A = \mu \cdot \frac{du}{dy} \cdot A = \mu \cdot \frac{U}{d} \cdot w^2$

Hence for uphill motion  $F = f + W \cdot \sin(\theta) = \mu \cdot \frac{U}{d} \cdot w^2 + W \cdot \sin(\theta)$        $U = \frac{d \cdot (F - W \cdot \sin(\theta))}{\mu \cdot w^2}$       (For downpush change sign of W)

For no force:  $U = \frac{d \cdot W \cdot \sin(\theta)}{\mu \cdot w^2}$        $U = 0.196 \frac{\text{m}}{\text{s}}$

Pushing up:  $U = \frac{d \cdot (F - W \cdot \sin(\theta))}{\mu \cdot w^2}$        $U = 0.104 \frac{\text{m}}{\text{s}}$       Pushing down:  $U = \frac{d \cdot (F + W \cdot \sin(\theta))}{\mu \cdot w^2}$        $U = 0.496 \frac{\text{m}}{\text{s}}$

## Problem 2.47

[Difficulty: 2]

**2.47** Tape is to be coated on both sides with glue by drawing it through a narrow gap. The tape is 0.015 in. thick and 1.00 in. wide. It is centered in the gap with a clearance of 0.012 in. on each side. The glue, of viscosity  $\mu = 0.02 \text{ slug}/(\text{ft} \cdot \text{s})$ , completely fills the space between the tape and gap. If the tape can withstand a maximum tensile force of 25 lbf, determine the maximum gap region through which it can be pulled at a speed of 3 ft/s.

**Given:** Data on tape mechanism

**Find:** Maximum gap region that can be pulled without breaking tape

**Solution:**

Basic equation  $\tau_{yx} = \mu \cdot \frac{du}{dy}$  and  $F = \tau_{yx} \cdot A$


Here  $F$  is the force on each side of the tape; the total force is then  $F_T = 2 \cdot F = 2 \cdot \tau_{yx} \cdot A$

The velocity gradient is linear as shown  $\frac{du}{dy} = \frac{V - 0}{c} = \frac{V}{c}$

The area of contact is  $A = w \cdot L$

Combining these results  $F_T = 2 \cdot \mu \cdot \frac{V}{c} \cdot w \cdot L$

Solving for  $L$   $L = \frac{F_T \cdot c}{2 \cdot \mu \cdot V \cdot w}$




The given data is  $F_T = 25 \cdot \text{lbf}$      $c = 0.012 \cdot \text{in}$      $\mu = 0.02 \cdot \frac{\text{slug}}{\text{ft} \cdot \text{s}}$      $V = 3 \cdot \frac{\text{ft}}{\text{s}}$      $w = 1 \cdot \text{in}$

Hence  $L = 25 \cdot \text{lbf} \times 0.012 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \times \frac{1}{2} \times \frac{1}{0.02 \cdot \frac{\text{slug}}{\text{ft} \cdot \text{s}}} \times \frac{1 \cdot \text{s}}{3 \cdot \text{ft}} \times \frac{1}{1 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \times \frac{\text{slug} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}}$      $L = 2.5 \cdot \text{ft}$

## Problem 2.48

[Difficulty: 2]

**2.48** A 73-mm-diameter aluminum ( $SG = 2.64$ ) piston of 100-mm length resides in a stationary 75-mm-inner-diameter steel tube lined with SAE 10W-30 oil at 25°C. A mass  $m = 2$  kg is suspended from the free end of the piston. The piston is set into motion by cutting a support cord. What is the terminal velocity of mass  $m$ ? Assume a linear velocity profile within the oil.



**Given:** Flow data on apparatus

**Find:** The terminal velocity of mass  $m$

**Solution:**

Given data:  $D_{\text{piston}} = 73 \text{ mm}$      $D_{\text{tube}} = 75 \text{ mm}$      $\text{Mass} = 2 \text{ kg}$      $L = 100 \text{ mm}$      $SG_{\text{Al}} = 2.64$

Reference data:  $\rho_{\text{water}} = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$  (maximum density of water)

From Fig. A.2., the dynamic viscosity of SAE 10W-30 oil at 25°C is:  $\mu = 0.13 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

The terminal velocity of the mass  $m$  is equivalent to the terminal velocity of the piston. At that terminal speed, the acceleration of the piston is zero. Therefore, all forces acting on the piston must be balanced. This means that the force driving the motion (i.e. the weight of mass  $m$  and the piston) balances the viscous forces acting on the surface of the piston. Thus, at  $r = R_{\text{piston}}$ :

$$\left[ \text{Mass} + SG_{\text{Al}} \rho_{\text{water}} \cdot \left( \frac{\pi \cdot D_{\text{piston}}^2 \cdot L}{4} \right) \right] \cdot g = \tau_{rz} \cdot A = \left( \mu \cdot \frac{d}{dr} V_z \right) \cdot (\pi \cdot D_{\text{piston}} \cdot L)$$


The velocity profile within the oil film is linear ...

Therefore 
$$\frac{d}{dr} V_z = \frac{V}{\left( \frac{D_{\text{tube}} - D_{\text{piston}}}{2} \right)}$$

Thus, the terminal velocity of the piston,  $V$ , is:

$$V = \frac{g \cdot (SG_{\text{Al}} \rho_{\text{water}} \cdot \pi \cdot D_{\text{piston}}^2 \cdot L + 4 \cdot \text{Mass}) \cdot (D_{\text{tube}} - D_{\text{piston}})}{8 \cdot \mu \cdot \pi \cdot D_{\text{piston}} \cdot L}$$


or 
$$V = 10.2 \frac{\text{m}}{\text{s}}$$



## Problem 2.49

[Difficulty: 3]

**2.49** The piston in Problem 2.48 is traveling at terminal speed. The mass  $m$  now disconnects from the piston. Plot the piston speed vs. time. How long does it take the piston to come within 1 percent of its new terminal speed?



**Given:** Flow data on apparatus

**Find:** Sketch of piston speed vs time; the time needed for the piston to reach 99% of its new terminal speed.

**Solution:**

Given data:  $D_{\text{piston}} = 73\text{-mm}$        $D_{\text{tube}} = 75\text{-mm}$        $L = 100\text{-mm}$        $SG_{\text{Al}} = 2.64$        $V_0 = 10.2 \cdot \frac{\text{m}}{\text{s}}$

Reference data:  $\rho_{\text{water}} = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$  (maximum density of water) (From Problem 2.48)


From Fig. A.2, the dynamic viscosity of SAE 10W-30 oil at 25°C is:  $\mu = 0.13 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

The free body diagram of the piston after the cord is cut is:

Piston weight: 
$$W_{\text{piston}} = SG_{\text{Al}} \cdot \rho_{\text{water}} \cdot g \cdot \left( \frac{\pi \cdot D_{\text{piston}}^2}{4} \right) \cdot L$$

Viscous force: 
$$F_{\text{viscous}}(V) = \tau_{rz} \cdot A$$

or 
$$F_{\text{viscous}}(V) = \mu \cdot \left[ \frac{V}{\frac{1}{2} \cdot (D_{\text{tube}} - D_{\text{piston}})} \right] \cdot (\pi \cdot D_{\text{piston}} \cdot L)$$



Applying Newton's second law: 
$$m_{\text{piston}} \cdot \frac{dV}{dt} = W_{\text{piston}} - F_{\text{viscous}}(V)$$

Therefore 
$$\frac{dV}{dt} = g - a \cdot V \quad \text{where} \quad a = \frac{8 \cdot \mu}{SG_{\text{Al}} \cdot \rho_{\text{water}} \cdot D_{\text{piston}} \cdot (D_{\text{tube}} - D_{\text{piston}})}$$


If 
$$V = g - a \cdot V \quad \text{then} \quad \frac{dX}{dt} = -a \cdot \frac{dV}{dt}$$

The differential equation becomes 
$$\frac{dX}{dt} = -a \cdot X \quad \text{where} \quad X(0) = g - a \cdot V_0$$

The solution to this differential equation is: 
$$X(t) = X_0 \cdot e^{-a \cdot t} \quad \text{or} \quad g - a \cdot V(t) = (g - a \cdot V_0) \cdot e^{-a \cdot t}$$

Therefore 
$$V(t) = \left( V_0 - \frac{g}{a} \right) \cdot e^{(-a \cdot t)} + \frac{g}{a}$$

Plotting piston speed vs. time (which can be done in Excel)



The terminal speed of the piston,  $V_t$ , is evaluated as  $t$  approaches infinity

$$V_t = \frac{g}{a} \quad \text{or} \quad V_t = 3.63 \frac{\text{m}}{\text{s}}$$


The time needed for the piston to slow down to within 1% of its terminal velocity is:

$$t = \frac{1}{a} \cdot \ln \left( \frac{V_0 - \frac{g}{a}}{1.01 \cdot V_t - \frac{g}{a}} \right) \quad \text{or} \quad t = 1.93 \text{ s}$$

## Problem 2.50

[Difficulty: 3]

**2.50** A block of mass  $M$  slides on a thin film of oil. The film thickness is  $h$  and the area of the block is  $A$ . When released, mass  $m$  exerts tension on the cord, causing the block to accelerate. Neglect friction in the pulley and air resistance. Develop an algebraic expression for the viscous force that acts on the block when it moves at speed  $V$ . Derive a differential equation for the block speed as a function of time. Obtain an expression for the block speed as a function of time. The mass  $M = 5 \text{ kg}$ ,  $m = 1 \text{ kg}$ ,  $A = 25 \text{ cm}^2$ , and  $h = 0.5 \text{ mm}$ . If it takes 1 s for the speed to reach 1 m/s, find the oil viscosity  $\mu$ . Plot the curve for  $V(t)$ .




**Given:** Block on oil layer pulled by hanging weight

**Find:** Expression for viscous force at speed  $V$ ; differential equation for motion; block speed as function of time; oil viscosity

**Solution:**

**Governing equations:**  $\tau_{yx} = \mu \frac{du}{dy}$        $\Sigma F_x = M \cdot a_x$



**Assumptions:** Laminar flow; linear velocity profile in oil layer

The given data is       $M = 5 \cdot \text{kg}$        $W = m \cdot g = 9.81 \cdot \text{N}$        $A = 25 \cdot \text{cm}^2$        $h = 0.05 \cdot \text{mm}$

Equation of motion (block)       $\Sigma F_x = M \cdot a_x$       so       $F_t - F_v = M \cdot \frac{dV}{dt}$       (1)

Equation of motion (block)       $\Sigma F_y = m \cdot a_y$       so       $m \cdot g - F_t = m \cdot \frac{dV}{dt}$       (2)

Adding Eqs. (1) and (2)       $m \cdot g - F_v = (M + m) \cdot \frac{dV}{dt}$

The friction force is       $F_v = \tau_{yx} \cdot A = \mu \cdot \frac{du}{dy} \cdot A = \mu \cdot \frac{V}{h} \cdot A$

Hence       $m \cdot g - \frac{\mu \cdot A}{h} \cdot V = (M + m) \cdot \frac{dV}{dt}$

To solve separate variables       $dt = \frac{M + m}{m \cdot g - \frac{\mu \cdot A}{h} \cdot V} \cdot dV$

$$t = -\frac{(M + m) \cdot h}{\mu \cdot A} \cdot \left( \ln \left( m \cdot g - \frac{\mu \cdot A}{h} \cdot V \right) - \ln(m \cdot g) \right) = -\frac{(M + m) \cdot h}{\mu \cdot A} \cdot \ln \left( 1 - \frac{\mu \cdot A}{m \cdot g \cdot h} \cdot V \right)$$

Hence taking antilogarithms       $1 - \frac{\mu \cdot A}{m \cdot g \cdot h} \cdot V = e^{-\frac{\mu \cdot A}{(M+m) \cdot h} \cdot t}$

Finally 
$$V = \frac{m \cdot g \cdot h}{\mu \cdot A} \cdot \left[ 1 - e^{-\frac{\mu \cdot A}{(M+m) \cdot h} \cdot t} \right]$$
 The maximum velocity is  $V = \frac{m \cdot g \cdot h}{\mu \cdot A}$

In Excel:


The data is

M = 5.00 kg  
 m = 1.00 kg  
 g = 9.81 m/s<sup>2</sup>  
 0 = 1.30 N.s/m<sup>2</sup>  
 A = 25 cm<sup>2</sup>  
 h = 0.5 mm

To find the viscosity for which the speed is 1 m/s after 1 s use *Goal Seek* with the velocity targeted to be 1 m/s by varying the viscosity in the set of cell below:

t (s)	V (m/s)
1.00	1.000


t (s)	V (m/s)
0.00	0.000
0.10	0.155
0.20	0.294
0.30	0.419
0.40	0.531
0.50	0.632
0.60	0.722
0.70	0.803
0.80	0.876
0.90	0.941
1.00	1.00
1.10	1.05
1.20	1.10
1.30	1.14
1.40	1.18
1.50	1.21
1.60	1.25
1.70	1.27
1.80	1.30
1.90	1.32
2.00	1.34
2.10	1.36
2.20	1.37
2.30	1.39
2.40	1.40
2.50	1.41
2.60	1.42
2.70	1.43
2.80	1.44
2.90	1.45
3.00	1.46



## Problem 2.51

[Difficulty: 4]

**2.51** A block 0.1 m square, with 5 kg mass, slides down a smooth incline, 30° below the horizontal, on a film of SAE 30 oil at 20°C that is 0.20 mm thick. If the block is released from rest at  $t=0$ , what is its initial acceleration? Derive an expression for the speed of the block as a function of time. Plot the curve for  $V(t)$ . Find the speed after 0.1 s. If we want the mass to instead reach a speed of 0.3 m/s at this time, find the viscosity  $\mu$  of the oil we would have to use.



**Given:** Data on the block and incline

**Find:** Initial acceleration; formula for speed of block; plot; find speed after 0.1 s. Find oil viscosity if speed is 0.3 m/s after 0.1 s

**Solution:**

Given data             $M = 5 \cdot \text{kg}$              $A = (0.1 \cdot \text{m})^2$              $d = 0.2 \cdot \text{mm}$              $\theta = 30 \cdot \text{deg}$

From Fig. A.2             $\mu = 0.4 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$

Applying Newton's 2nd law to initial instant (no friction)             $M \cdot a = M \cdot g \cdot \sin(\theta) - F_f = M \cdot g \cdot \sin(\theta)$

so             $a_{\text{init}} = g \cdot \sin(\theta) = 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \sin(30 \cdot \text{deg})$              $a_{\text{init}} = 4.9 \frac{\text{m}}{\text{s}^2}$

Applying Newton's 2nd law at any instant             $M \cdot a = M \cdot g \cdot \sin(\theta) - F_f$             and             $F_f = \tau \cdot A = \mu \cdot \frac{du}{dy} \cdot A = \mu \cdot \frac{V}{d} \cdot A$

so             $M \cdot a = M \cdot \frac{dV}{dt} = M \cdot g \cdot \sin(\theta) - \frac{\mu \cdot A}{d} \cdot V$

Separating variables             $\frac{dV}{g \cdot \sin(\theta) - \frac{\mu \cdot A}{M \cdot d} \cdot V} = dt$


Integrating and using limits             $-\frac{M \cdot d}{\mu \cdot A} \cdot \ln\left(1 - \frac{\mu \cdot A}{M \cdot g \cdot d \cdot \sin(\theta)} \cdot V\right) = t$

or             $V(t) = \frac{M \cdot g \cdot d \cdot \sin(\theta)}{\mu \cdot A} \cdot \left(1 - e^{-\frac{\mu \cdot A}{M \cdot d} \cdot t}\right)$

At  $t = 0.1 \text{ s}$              $V = 5 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.0002 \cdot \text{m} \cdot \sin(30 \cdot \text{deg}) \times \frac{\text{m}^2}{0.4 \cdot \text{N} \cdot \text{s} \cdot (0.1 \cdot \text{m})^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times \left[1 - e^{-\left(\frac{0.4 \cdot 0.01}{5 \cdot 0.0002} \cdot 0.1\right)}\right]$

$V(0.1 \cdot \text{s}) = 0.404 \cdot \frac{\text{m}}{\text{s}}$

The plot looks like



To find the viscosity for which  $V(0.1 \text{ s}) = 0.3 \text{ m/s}$ , we must solve

$$V(t = 0.1 \text{ s}) = \frac{M \cdot g \cdot d \cdot \sin(\theta)}{\mu \cdot A} \cdot \left[ 1 - e^{-\frac{\mu \cdot A}{M \cdot d} \cdot (t=0.1 \text{ s})} \right]$$

The viscosity  $\mu$  is implicit in this equation, so solution must be found by manual iteration, or by any of a number of classic root-finding numerical methods, or by using *Excel's Goal Seek*

Using *Excel*:

$$\mu = 1.08 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$$

## Problem 2.52

[Difficulty: 3]


**2.52** A block that is  $a$  mm square slides across a flat plate on a thin film of oil. The oil has viscosity  $\mu$  and the film is  $h$  mm thick. The block of mass  $M$  moves at steady speed  $U$  under the influence of constant force  $F$ . Indicate the magnitude and direction of the shear stresses on the bottom of the block and the plate. If the force is removed suddenly and the block begins to slow, sketch the resulting speed versus time curve for the block. Obtain an expression for the time required for the block to lose 95 percent of its initial speed.

**Given:** Block sliding on oil layer

**Find:** Direction of friction on bottom of block and on plate; expression for speed  $U$  versus time; time required to lose 95% of initial speed

**Solution:**

**Governing equations:**  $\tau_{yx} = \mu \cdot \frac{du}{dy}$        $\Sigma F_x = M \cdot a_x$



**Assumptions:** Laminar flow; linear velocity profile in oil layer

The bottom of the block is a  $-y$  surface, so  $\tau_{yx}$  acts to the left; The plate is a  $+y$  surface, so  $\tau_{xy}$  acts to the right

Equation of motion       $\Sigma F_x = M \cdot a_x$       so       $F_v = M \cdot \frac{dU}{dt}$

The friction force is       $F_v = \tau_{yx} \cdot A = \mu \cdot \frac{du}{dy} \cdot A = \mu \cdot \frac{U}{h} \cdot a^2$

Hence       $-\frac{\mu \cdot a^2}{h} \cdot U = M \cdot \frac{dU}{dt}$


To solve separate variables       $\frac{1}{U} \cdot dU = -\frac{\mu \cdot a^2}{M \cdot h} \cdot dt$

$$\ln\left(\frac{U}{U_0}\right) = -\frac{\mu \cdot a^2}{M \cdot h} \cdot t$$

Hence taking antilogarithms       $U = U_0 \cdot e^{-\frac{\mu \cdot a^2}{M \cdot h} \cdot t}$

Solving for  $t$        $t = -\frac{M \cdot h}{\mu \cdot a^2} \cdot \ln\left(\frac{U}{U_0}\right)$

Hence for  $\frac{U}{U_0} = 0.05$        $t = 3.0 \cdot \frac{M \cdot h}{\mu \cdot a^2}$



## Problem 2.53

[Difficulty: 2]


**2.53** Magnet wire is to be coated with varnish for insulation by drawing it through a circular die of 1.0 mm diameter. The wire diameter is 0.9 mm and it is centered in the die. The varnish ( $\mu = 20$  centipoise) completely fills the space between the wire and the die for a length of 50 mm. The wire is drawn through the die at a speed of 50 m/s. Determine the force required to pull the wire.

**Given:** Varnish-coated wire drawn through die

**Find:** Force required to pull wire

**Solution:**

**Governing equations:**  $\tau_{yx} = \mu \cdot \frac{du}{dy}$        $\Sigma F_x = M \cdot a_x$



**Assumptions:** Laminar flow; linear velocity profile in varnish layer

The given data is       $D = 1 \cdot \text{mm}$        $d = 0.9 \cdot \text{mm}$        $L = 50 \cdot \text{mm}$        $V = 50 \cdot \frac{\text{m}}{\text{s}}$        $\mu = 20 \times 10^{-2} \text{poise}$

Equation of motion       $\Sigma F_x = M \cdot a_x$       so       $F - F_v = 0$       for steady speed

The friction force is       $F_v = \tau_{yx} \cdot A = \mu \cdot \frac{du}{dr} \cdot A = \mu \cdot \frac{V}{\left(\frac{D-d}{2}\right)} \cdot \pi \cdot d \cdot L$

Hence       $F - F_v = 0$

so       $F = \frac{2 \cdot \pi \cdot \mu \cdot V \cdot d \cdot L}{D - d}$

$$F = 2 \cdot \pi \times 20 \times 10^{-2} \text{poise} \times \frac{0.1 \cdot \text{kg}}{\text{m} \cdot \text{s} \cdot \text{poise}} \times 50 \cdot \frac{\text{m}}{\text{s}} \times 0.9 \cdot \text{mm} \times 50 \cdot \text{mm} \times \frac{1}{(1 - 0.9) \cdot \text{mm}} \times \frac{\text{m}}{1000 \cdot \text{mm}}$$


$$F = 2.83 \text{ N}$$

## Problem 2.54

[Difficulty: 3]

**2.54** In a food-processing plant, honey is pumped through an annular tube. The tube is  $L = 2$  m long, with inner and outer radii of  $R_i = 5$  mm and  $R_o = 25$  mm, respectively. The applied pressure difference is  $\Delta p = 125$  kPa, and the honey viscosity is  $\mu = 5 \text{ N} \cdot \text{s}/\text{m}^2$ . The theoretical velocity profile for laminar flow through an annulus is:

$$u_z(r) = \frac{1}{4\mu} \left( \frac{\Delta p}{L} \right) \left[ R_i^2 - r^2 - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \ln\left(\frac{r}{R_i}\right) \right]$$



Show that the no-slip condition is satisfied by this expression. Find the location at which the shear stress is zero. Find the viscous forces acting on the inner and outer surfaces, and compare these to the force  $\Delta p \pi (R_o^2 - R_i^2)$ . Explain.

**Given:** Data on annular tube

**Find:** Whether no-slip is satisfied; location of zeroshear stress; viscous forces

**Solution:**

The velocity profile is

$$u_z(r) = \frac{1}{4\mu} \cdot \frac{\Delta p}{L} \cdot \left( R_i^2 - r^2 - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \ln\left(\frac{r}{R_i}\right) \right)$$

Check the no-slip condition. When  $r = R_o$

$$u_z(R_o) = \frac{1}{4\mu} \cdot \frac{\Delta p}{L} \cdot \left( R_i^2 - R_o^2 - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \ln\left(\frac{R_o}{R_i}\right) \right)$$

$$u_z(R_o) = \frac{1}{4\mu} \cdot \frac{\Delta p}{L} \cdot \left[ R_i^2 - R_o^2 + \left( R_o^2 - R_i^2 \right) \right] = 0$$

When  $r = R_i$

$$u_z(R_i) = \frac{1}{4\mu} \cdot \frac{\Delta p}{L} \cdot \left( R_i^2 - R_i^2 - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \ln\left(\frac{R_i}{R_i}\right) \right) = 0$$

The no-slip condition is satisfied.


The given data is

$$R_i = 5 \text{ mm} \qquad R_o = 25 \text{ mm} \qquad \Delta p = 125 \text{ kPa} \qquad L = 2 \text{ m}$$

The viscosity of the honey is

$$\mu = 5 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$$

The plot looks like



For each, shear stress is given by

$$\tau_{rx} = \mu \cdot \frac{du}{dr}$$

$$\tau_{rx} = \mu \cdot \frac{du_z(r)}{dr} = \mu \cdot \frac{d}{dr} \left[ \frac{1}{4 \cdot \mu} \cdot \frac{\Delta p}{L} \cdot \left( R_1^2 - r^2 - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \ln\left(\frac{r}{R_i}\right) \right) \right]$$

Hence

$$\tau_{rx} = \frac{1}{4} \cdot \frac{\Delta p}{L} \cdot \left( -2 \cdot r - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \frac{1}{r} \right)$$

For zero stress

$$-2 \cdot r - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \frac{1}{r} = 0 \quad \text{or} \quad r = \sqrt{\frac{R_i^2 - R_o^2}{2 \cdot \ln\left(\frac{R_i}{R_o}\right)}} \quad r = 13.7 \text{ mm}$$

On the outer surface

$$F_o = \tau_{rx} \cdot A = \frac{1}{4} \cdot \frac{\Delta p}{L} \cdot \left( -2 \cdot R_o - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \frac{1}{R_o} \right) \cdot 2 \cdot \pi \cdot R_o \cdot L$$

$$F_o = \Delta p \cdot \pi \cdot \left( -R_o^2 - \frac{R_o^2 - R_i^2}{2 \cdot \ln\left(\frac{R_i}{R_o}\right)} \right)$$

$$F_o = 125 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \pi \times \left[ - \left( 25 \cdot \text{mm} \times \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \right)^2 - \frac{[(25 \cdot \text{mm})^2 - (5 \cdot \text{mm})^2] \times \left( \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \right)}{2 \cdot \ln\left(\frac{5}{25}\right)} \right]$$

$$F_o = -172 \text{ N}$$

On the inner surface

$$F_i = \tau_{rx} \cdot A = \frac{1}{4} \cdot \frac{\Delta p}{L} \cdot \left( -2 \cdot R_i - \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right) \cdot R_i} \right) \cdot 2 \cdot \pi \cdot R_i \cdot L$$

$$F_i = \Delta p \cdot \pi \cdot \left( -R_i^2 - \frac{R_o^2 - R_i^2}{2 \cdot \ln\left(\frac{R_i}{R_o}\right)} \right)$$

Hence

$$F_i = 125 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \pi \times \left[ - \left( 5 \cdot \text{mm} \times \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \right)^2 - \frac{[(25 \cdot \text{mm})^2 - (5 \cdot \text{mm})^2] \times \left( \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \right)}{2 \cdot \ln\left(\frac{5}{25}\right)} \right]$$

$$F_i = 63.4 \text{ N}$$

Note that

$$F_o - F_i = -236 \text{ N} \quad \text{and} \quad \Delta p \cdot \pi \cdot (R_o^2 - R_i^2) = 236 \text{ N}$$

The net pressure force just balances the net viscous force!

## Problem 2.55

[Difficulty: 3]

**2.55** SAE 10W-30 oil at 100°C is pumped through a tube  $L = 10$  m long, diameter  $D = 20$  mm. The applied pressure difference is  $\Delta p = 5$  kPa. On the centerline of the tube is a metal filament of diameter  $d = 1 \mu\text{m}$ . The theoretical velocity profile for laminar flow through the tube is:

$$V(r) = \frac{1}{16\mu} \left( \frac{\Delta p}{L} \right) \left[ d^2 - 4r^2 - \frac{D^2 - d^2}{\ln\left(\frac{d}{D}\right)} \cdot \ln\left(\frac{2r}{d}\right) \right]$$

Show that the no-slip condition is satisfied by this expression. Find the location at which the shear stress is zero, and the stress on the tube and on the filament. Plot the velocity distribution and the stress distribution. (For the stress curve, set an upper limit on stress of 5 Pa.) Discuss the results.

**Given:** Data on flow through a tube with a filament

**Find:** Whether no-slip is satisfied; location of zero stress; stress on tube and filament

**Solution:**

The velocity profile is

$$V(r) = \frac{1}{16\mu} \cdot \frac{\Delta p}{L} \cdot \left( d^2 - 4r^2 - \frac{D^2 - d^2}{\ln\left(\frac{d}{D}\right)} \cdot \ln\left(\frac{2r}{d}\right) \right)$$

Check the no-slip condition.  
When

$$r = \frac{D}{2} \qquad V\left(\frac{D}{2}\right) = \frac{1}{16\mu} \cdot \frac{\Delta p}{L} \cdot \left( d^2 - D^2 - \frac{D^2 - d^2}{\ln\left(\frac{d}{D}\right)} \cdot \ln\left(\frac{D}{d}\right) \right)$$

$$V(D) = \frac{1}{16\mu} \cdot \frac{\Delta p}{L} \cdot [d^2 - D^2 + (D^2 - d^2)] = 0$$

When

$$r = \frac{d}{2} \qquad V(d) = \frac{1}{16\mu} \cdot \frac{\Delta p}{L} \cdot \left( d^2 - d^2 - \frac{D^2 - d^2}{\ln\left(\frac{d}{D}\right)} \cdot \ln\left(\frac{d}{d}\right) \right) = 0$$

The no-slip condition is satisfied.


The given data is

$d = 1 \mu\text{m}$	$D = 20 \text{ mm}$	$\Delta p = 5 \text{ kPa}$	$L = 10 \text{ m}$
---------------------	---------------------	----------------------------	--------------------

The viscosity of SAE 10-30 oil at 100°C is (Fig. A.2)

$$\mu = 1 \times 10^{-2} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$$

The plot looks like



For each, shear stress is given by


$$\tau_{rx} = \mu \cdot \frac{du}{dr}$$

$$\tau_{rx} = \mu \cdot \frac{dV(r)}{dr} = \mu \cdot \frac{d}{dr} \left[ \frac{1}{16 \cdot \mu} \cdot \frac{\Delta p}{L} \cdot \left( d^2 - 4 \cdot r^2 - \frac{D^2 - d^2}{\ln\left(\frac{d}{D}\right)} \cdot \ln\left(\frac{2 \cdot r}{D_i}\right) \right) \right]$$

$$\tau_{rx}(r) = \frac{1}{16} \cdot \frac{\Delta p}{L} \cdot \left( -8 \cdot r - \frac{D^2 - d^2}{\ln\left(\frac{d}{D}\right)} \cdot r \right)$$

For the zero-stress point

$$-8 \cdot r - \frac{D^2 - d^2}{\ln\left(\frac{d}{D}\right)} \cdot r = 0 \quad \text{or} \quad r = \sqrt{\frac{d^2 - D^2}{8 \cdot \ln\left(\frac{d}{D}\right)}} \quad r = 2.25 \cdot \text{mm}$$



Using the stress formula


$$\tau_{rx}\left(\frac{D}{2}\right) = -2.374 \text{ Pa}$$

$$\tau_{rx}\left(\frac{d}{2}\right) = 2.524 \cdot \text{kPa}$$

## Problem 2.56

[Difficulty: 2]

**2.56** Fluids of viscosities  $\mu_1 = 0.1 \text{ N} \cdot \text{s}/\text{m}^2$  and  $\mu_2 = 0.15 \text{ N} \cdot \text{s}/\text{m}^2$  are contained between two plates (each plate is  $1 \text{ m}^2$  in area). The thicknesses are  $h_1 = 0.5 \text{ mm}$  and  $h_2 = 0.3 \text{ mm}$ , respectively. Find the force  $F$  to make the upper plate move at a speed of  $1 \text{ m/s}$ . What is the fluid velocity at the interface between the two fluids?



**Given:** Flow between two plates

**Find:** Force to move upper plate; Interface velocity

**Solution:**

The shear stress is the same throughout (the velocity gradients are linear, and the stresses in the fluid at the interface must be equal and opposite).

Hence 
$$\tau = \mu_1 \cdot \frac{du_1}{dy} = \mu_2 \cdot \frac{du_2}{dy} \quad \text{or} \quad \mu_1 \cdot \frac{V_i}{h_1} = \mu_2 \cdot \frac{(V - V_i)}{h_2}$$
 where  $V_i$  is the interface velocity

Solving for the interface velocity  $V_i$

$$V_i = \frac{V}{1 + \frac{\mu_1 h_2}{\mu_2 h_1}} = \frac{1 \cdot \frac{\text{m}}{\text{s}}}{1 + \frac{0.1}{0.15} \cdot \frac{0.3}{0.5}} \quad V_i = 0.714 \frac{\text{m}}{\text{s}}$$


Then the force required is

$$F = \tau \cdot A = \mu_1 \cdot \frac{V_i}{h_1} \cdot A = 0.1 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times 0.714 \cdot \frac{\text{m}}{\text{s}} \times \frac{1}{0.5 \cdot \text{mm}} \times \frac{1000 \cdot \text{mm}}{1 \cdot \text{m}} \times 1 \cdot \text{m}^2 \quad F = 143 \text{ N}$$

## Problem 2.57

[Difficulty: 2]

**2.57** Fluids of viscosities  $\mu_1 = 0.15 \text{ N}\cdot\text{s}/\text{m}^2$ ,  $\mu_2 = 0.5 \text{ N}\cdot\text{s}/\text{m}^2$ , and  $\mu_3 = 0.2 \text{ N}\cdot\text{s}/\text{m}^2$  are contained between two plates (each plate is  $1 \text{ m}^2$  in area). The thicknesses are  $h_1 = 0.5 \text{ mm}$ ,  $h_2 = 0.25 \text{ mm}$ , and  $h_3 = 0.2 \text{ mm}$ , respectively. Find the steady speed  $V$  of the upper plate and the velocities at the two interfaces due to a force  $F = 100 \text{ N}$ . Plot the velocity distribution.



**Given:** Flow of three fluids between two plates

**Find:** Upper plate velocity; Interface velocities; plot velocity distribution

**Solution:**

The shear stress is the same throughout (the velocity gradients are linear, and the stresses in the fluids at the interfaces must be equal and opposite).

Given data	$F = 100 \cdot \text{N}$	$h_1 = 0.5 \cdot \text{mm}$	$h_2 = 0.25 \cdot \text{mm}$	$h_3 = 0.2 \cdot \text{mm}$
	$A = 1 \cdot \text{m}^2$	$\mu_1 = 0.15 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$	$\mu_2 = 0.5 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$	$\mu_3 = 0.2 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$


The (constant) stress is  $\tau = \frac{F}{A} = 100 \text{ Pa}$

For each fluid  $\tau = \mu \cdot \frac{\Delta V}{\Delta y}$  or  $\Delta V = \frac{\tau \cdot \Delta y}{\mu}$  where  $\Delta V$  is the overall change in velocity over distance  $\Delta y$


Hence  $V_{12} = \frac{\tau \cdot h_1}{\mu_1} = 0.333 \frac{\text{m}}{\text{s}}$  where  $V_{12}$  is the velocity at the 1 - 2 interface

Hence  $V_{23} = \frac{\tau \cdot h_2}{\mu_2} + V_{12} = 0.383 \frac{\text{m}}{\text{s}}$  where  $V_{23}$  is the velocity at the 2 - 3 interface

Hence  $V = \frac{\tau \cdot h_3}{\mu_3} + V_{23} = 0.483 \frac{\text{m}}{\text{s}}$  where  $V$  is the velocity at the upper plate



2.58 A concentric cylinder viscometer may be formed by rotating the inner member of a pair of closely fitting cylinders. The annular gap is small so that a linear velocity profile will exist in the liquid sample. Consider a viscometer with an inner cylinder of 4 in. diameter and 8 in. height, and a clearance gap width of 0.001 in., filled with castor oil at 90°F. Determine the torque required to turn the inner cylinder at 400 rpm.



Solution:

The required torque must balance the resisting torque of the shear force.

The shear force is given by  $F = \tau A$  where  $A = 2\pi R h$

For a Newtonian fluid  $\tau = \mu \frac{du}{dy}$

For small gap (linear profile)  $\tau = \mu \frac{v}{d}$

where  $v =$  tangential velocity of inner cylinder  $= R\omega$

Hence 
$$F = \tau A = \mu \frac{R\omega}{d} 2\pi R h = \frac{2\pi \mu R^2 \omega h}{d}$$

and the torque 
$$T = RF = \frac{2\pi \mu R^3 \omega h}{d}$$

From Fig A.2, for castor oil at 90°F (32°C),  $\mu = 3.80 \times 10^{-1} \text{ N}\cdot\text{s}/\text{m}^2$

Substituting numerical values.

$$T = \frac{2\pi \mu R^3 \omega h}{d} = 2\pi \times 3.80 \times 10^{-1} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times 2.09 \times 10^{-2} \frac{\text{lb}\cdot\text{s}}{\text{ft}^2 \cdot \text{N}\cdot\text{s}} \times (2.0)^3 \text{ in}^3 \times \frac{400 \text{ rev}}{\text{min}} \times 8 \text{ in} \times \frac{1}{10^{-3} \text{ in}}$$

$$\times 2\pi \frac{\text{rad}}{\text{rev}} \times \frac{\text{min}}{60 \text{ s}} \times \frac{\text{ft}^3}{1728 \text{ in}^3}$$


$T = 77.4 \text{ ft}\cdot\text{lb}$

Torqu.

## Problem 2.59

[Difficulty: 2]

**2.59** A concentric cylinder viscometer may be formed by rotating the inner member of a pair of closely fitting cylinders. For small clearances, a linear velocity profile may be assumed in the liquid filling the annular clearance gap. A viscometer has an inner cylinder of 75 mm diameter and 150 mm height, with a clearance gap width of 0.02 mm. A torque of 0.021 N·m is required to turn the inner cylinder at 100 rpm. Determine the viscosity of the liquid in the clearance gap of the viscometer.



### Solution

The imposed torque must balance the resisting torque of the shear force.

The shear force is given by  $F = \tau A$  where  $A = 2\pi R_i h$

For a Newtonian fluid  $\tau = \mu \frac{du}{dy}$

Since the velocity profile is assumed to be linear,  $\tau = \mu \frac{v}{d}$   
 where  $v$  is the tangential velocity of the inner cylinder,  $v = R_i \omega$

Thus,  $F = \tau A = \mu \frac{v}{d} 2\pi R_i h = \frac{2\pi \mu R_i^2 \omega h}{d}$

and the torque  $T = R_i F = \frac{2\pi \mu R_i^3 \omega h}{d}$

Solving for  $\mu$ ,

$$\mu = \frac{T d}{2\pi R_i^3 \omega h} = 0.021 \text{ N}\cdot\text{m} \times 0.02 \text{ mm} \times \frac{1}{2\pi} \times \frac{1}{(37.5)^3} \text{ mm}^3 \times \frac{\text{min}}{100 \text{ rev}} \times \frac{1}{150 \text{ mm}}$$


$$\times \frac{\text{rev}}{2\pi \text{ rad}} \times \frac{60 \text{ s}}{\text{min}} \times (1000)^3 \frac{\text{mm}^3}{\text{m}^3}$$

$$\mu = 8.07 \times 10^{-4} \text{ N}\cdot\text{s}/\text{m}^2$$

## Problem 2.60

[Difficulty: 2]

**2.60** A concentric cylinder viscometer is driven by a falling mass  $M$  connected by a cord and pulley to the inner cylinder, as shown. The liquid to be tested fills the annular gap of width  $a$  and height  $H$ . After a brief starting transient, the mass falls at constant speed  $V_m$ . Develop an algebraic expression for the viscosity of the liquid in the device in terms of  $M$ ,  $g$ ,  $V_m$ ,  $r$ ,  $R$ ,  $a$ , and  $H$ . Evaluate the viscosity of the liquid using:



$$M = 0.10 \text{ kg}$$

$$r = 25 \text{ mm}$$

$$R = 50 \text{ mm}$$

$$a = 0.20 \text{ mm}$$

$$H = 80 \text{ mm}$$

$$V_m = 30 \text{ mm/s}$$

Solution: Apply Newton's law of viscosity.

Basic equations:  $\tau = \mu \frac{du}{dy}$      $\Sigma M = 0$      $T = \tau A R$


Assumptions: (1) Newtonian liquid  
 (2) Narrow gap, so linear velocity profile  
 (3) Steady angular speed

Summing torques on the rotor

$$\Sigma M = Mgr - \tau A R = I \dot{\phi} = 0 \quad ; \quad A = 2\pi R H$$

Because  $a \ll R$ , treat the gap as plane. Then

$$\tau = \mu \frac{du}{dy} = \mu \frac{\Delta u}{\Delta y} = \mu \frac{U - 0}{a - 0} = \mu \frac{U}{a} = \frac{\mu V_m R}{a r}$$



Substituting,

$$Mgr - \frac{\mu V_m R}{a r} 2\pi R H R = Mgr - \frac{2\pi \mu V_m R^3 H}{a r} = 0$$

so

$$\mu = \frac{Mgr^2 a}{2\pi V_m R^3 H}$$

Evaluating for the given data

$$\mu = \frac{1}{2\pi} \times 0.10 \text{ kg} \times 9.81 \frac{\text{m}}{\text{s}^2} \times (0.025)^2 \text{ m}^2 \times 0.0002 \text{ m} \times \frac{\text{s}}{0.030 \text{ m}}$$


$$\times \frac{1}{(0.050)^3 \text{ m}^3} \times \frac{1}{0.080 \text{ m}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\mu = 0.0651 \text{ N} \cdot \text{s} / \text{m}^2 \quad (65.1 \text{ mPa} \cdot \text{s})$$

## Problem 2.61

[Difficulty: 3]

**2.61** The viscometer of Problem 2.60 is being used to verify that the viscosity of a particular fluid is  $\mu = 0.1 \text{ N}\cdot\text{s}/\text{m}^2$ . Unfortunately the cord snaps during the experiment. How long will it take the cylinder to lose 99% of its speed? The moment of inertia of the cylinder/pulley system is  $0.0273 \text{ kg}\cdot\text{m}^2$ .



**Given:** Data on the viscometer

**Find:** Time for viscometer to lose 99% of speed

**Solution:**

The given data is  $R = 50\text{-mm}$   $H = 80\text{-mm}$   $a = 0.20\text{-mm}$   $I = 0.0273\text{-kg}\cdot\text{m}^2$   $\mu = 0.1\cdot\frac{\text{N}\cdot\text{s}}{\text{m}^2}$

The equation of motion for the slowing viscometer is  $I\cdot\alpha = \text{Torque} = -\tau\cdot A\cdot R$

where  $\alpha$  is the angular acceleration and  $\tau$  is the viscous stress, and  $A$  is the surface area of the viscometer

The stress is given by 
$$\tau = \mu\cdot\frac{du}{dy} = \mu\cdot\frac{V-0}{a} = \frac{\mu\cdot V}{a} = \frac{\mu\cdot R\cdot\omega}{a}$$

where  $V$  and  $\omega$  are the instantaneous linear and angular velocities.

Hence 
$$I\cdot\alpha = I\cdot\frac{d\omega}{dt} = -\frac{\mu\cdot R\cdot\omega}{a}\cdot A\cdot R = -\frac{\mu\cdot R^2\cdot A}{a}\cdot\omega$$

Separating variables 
$$\frac{d\omega}{\omega} = -\frac{\mu\cdot R^2\cdot A}{a\cdot I}\cdot dt$$

Integrating and using IC  $\omega = \omega_0$  
$$\omega(t) = \omega_0\cdot e^{-\frac{\mu\cdot R^2\cdot A}{a\cdot I}\cdot t}$$

The time to slow down by 99% is obtained from solving  $0.01\cdot\omega_0 = \omega_0\cdot e^{-\frac{\mu\cdot R^2\cdot A}{a\cdot I}\cdot t}$  so  $t = -\frac{a\cdot I}{\mu\cdot R^2\cdot A}\cdot\ln(0.01)$


Note that  $A = 2\cdot\pi\cdot R\cdot H$  so  $t = -\frac{a\cdot I}{2\cdot\pi\cdot\mu\cdot R^3\cdot H}\cdot\ln(0.01)$

$$t = -\frac{0.0002\cdot\text{m}\cdot 0.0273\cdot\text{kg}\cdot\text{m}^2}{2\cdot\pi}\cdot\frac{\text{m}^2}{0.1\cdot\text{N}\cdot\text{s}}\cdot\frac{1}{(0.05\cdot\text{m})^3}\cdot\frac{1}{0.08\cdot\text{m}}\cdot\frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}}\cdot\ln(0.01) \quad t = 4.00 \text{ s}$$

## Problem 2.62

Difficulty: [2]


**2.62** A shaft with outside diameter of 18 mm turns at 20 revolutions per second inside a stationary journal bearing 60 mm long. A thin film of oil 0.2 mm thick fills the concentric annulus between the shaft and journal. The torque needed to turn the shaft is 0.0036 N·m. Estimate the viscosity of the oil that fills the gap.



Solution: Basic equation  $\tau_{yx} = \mu \frac{du}{dy}$

Assumptions: (1) Newtonian fluid

(2) Gap is narrow, so velocity profile is linear,  $\frac{du}{dy} \approx \frac{\Delta u}{\Delta y}$



Shear stress is

$$\tau_{yx} \approx \mu \frac{\Delta u}{\Delta y} = \mu \frac{U}{t} = \frac{\mu \omega D}{2t}$$

Neglecting end effects, torque is

$$T = FR = \tau_{yx} A R = \tau_{yx} (\pi D L) \frac{D}{2} = \frac{\mu \pi \omega D^3 L}{4t}$$

Solving for viscosity

$$\mu = \frac{4tT}{\pi \omega D^3 L}$$

$$= \frac{4}{\pi} \times 0.2 \text{ mm} \times 0.0036 \text{ N}\cdot\text{m} \times \frac{\text{s}}{20 \text{ rev}} \times \frac{1}{(18)^3 \text{ mm}^3} \times \frac{1}{60 \text{ mm}} \times \frac{1}{2\pi \text{ rad}} \times \frac{\text{rev}}{\text{s}} \times \frac{(1000)^3 \text{ mm}^3}{\text{m}^3}$$

$$\mu = 0.0208 \text{ N}\cdot\text{s} / \text{m}^2$$

{ From Fig. A.2, this oil appears somewhat less viscous than SAE 10W, }  
 assuming the oil is at room temperature.



**2.63** The thin outer cylinder (mass  $m_2$  and radius  $R$ ) of a small portable concentric cylinder viscometer is driven by a falling mass,  $m_1$ , attached to a cord. The inner cylinder is stationary. The clearance between the cylinders is  $a$ . Neglect bearing friction, air resistance, and the mass of liquid in the viscometer. Obtain an algebraic expression for the torque due to viscous shear that acts on the cylinder at angular speed  $\omega$ . Derive and solve a differential equation for the angular speed of the outer cylinder as a function of time. Obtain an expression for the maximum angular speed of the cylinder.

Solution:

Basic equations:  $\tau = \mu \frac{du}{dy}$



$\Sigma F = ma$ ,  $\Sigma M = I\alpha$

Assume: (1) Newtonian fluid  
(2) linear velocity profile



In the gap,  $\tau = \mu \frac{du}{dy} = \mu \frac{u}{a} = \frac{\mu R \omega}{a}$   
 $T = \tau A R = \frac{\mu R \omega}{a} (2\pi R h) R$   
 $T = \frac{2\pi R^3 \mu h}{a} \omega$

During acceleration, let the tension in the cord be  $F_c$



For the cylinder  $\Sigma M = F_c R - T = I\alpha = m_2 R^2 \frac{d\omega}{dt}$  ... (1)  
 For the mass  $\Sigma F_y = m_1 g - F_c = m_1 a = m_1 \frac{d^2x}{dt^2} = m_1 R \frac{d^2\omega}{dt^2}$  ... (2)  
 $\therefore F_c = m_1 g - m_1 R \frac{d\omega}{dt}$

Substituting into eq. (1)

$m_1 g R - \frac{2\pi R^3 \mu h}{a} \omega = (m_1 + m_2) R^2 \frac{d\omega}{dt}$   
 Let  $m_1 g R = b$ ,  $-\frac{2\pi R^3 \mu h}{a} = c$ ,  $(m_1 + m_2) R^2 = f$

Then,  $b + c\omega = f \frac{d\omega}{dt}$  or  $\int \frac{1}{f} dt = \int \frac{d\omega}{(b+c\omega)}$

Integrating,  $\frac{1}{f} t = \frac{1}{c} \ln(b+c\omega) \Big|_0^\omega = \frac{1}{c} \ln \frac{(b+c\omega)}{b} = \frac{1}{c} \ln(1 + \frac{c}{b}\omega)$

$\frac{c}{f} t = \ln(1 + \frac{c}{b}\omega) \Rightarrow e^{\frac{c}{f} t} = (1 + \frac{c}{b}\omega) \Rightarrow \omega = \frac{c}{b} (e^{\frac{c}{f} t} - 1)$

Substituting for b, c, and f  
 $\omega = \frac{m_1 g R a}{2\pi R^3 \mu h} (1 - e^{-\frac{2\pi R^3 \mu h}{a(m_1+m_2)R^2} t}) = \frac{m_1 g a}{2\pi R^2 \mu h} [1 - e^{-\frac{2\pi R^3 \mu h}{a(m_1+m_2)R^2} t}]$


Maximum  $\omega$  occurs at  $t \rightarrow \infty$

$\omega_{max} = \frac{m_1 g a}{2\pi R^2 \mu h}$

## Problem 2.64

[Difficulty: 3]

**2.64** A shock-free coupling for a low-power mechanical drive is to be made from a pair of concentric cylinders. The annular space between the cylinders is to be filled with oil. The drive must transmit power,  $\mathcal{P} = 10 \text{ W}$ . Other dimensions and properties are as shown. Neglect any bearing friction and end effects. Assume the minimum practical gap clearance  $\delta$  for the device is  $\delta = 0.25 \text{ mm}$ . Dow manufactures silicone fluids with viscosities as high as  $10^6$  centipoise. Determine the viscosity that should be specified to satisfy the requirement for this device.



**Given:** Shock-free coupling assembly


**Find:** Required viscosity

**Solution:**

Basic equation  $\tau_{r\theta} = \mu \frac{du}{dr}$       Shear force  $F = \tau \cdot A$       Torque  $T = F \cdot R$       Power  $P = T \cdot \omega$

Assumptions: Newtonian fluid, linear velocity profile

$$\tau_{r\theta} = \mu \frac{du}{dr} = \mu \frac{\Delta V}{\Delta r} = \mu \frac{[\omega_1 \cdot R - \omega_2 \cdot (R + \delta)]}{\delta}$$



$$\tau_{r\theta} = \mu \frac{(\omega_1 - \omega_2) \cdot R}{\delta} \quad \text{Because } \delta \ll R$$

Then 
$$P = T \cdot \omega_2 = F \cdot R \cdot \omega_2 = \tau \cdot A_2 \cdot R \cdot \omega_2 = \frac{\mu \cdot (\omega_1 - \omega_2) \cdot R}{\delta} \cdot 2 \cdot \pi \cdot R \cdot L \cdot R \cdot \omega_2$$

$$P = \frac{2 \cdot \pi \cdot \mu \cdot \omega_2 \cdot (\omega_1 - \omega_2) \cdot R^3 \cdot L}{\delta}$$

Hence

$$\mu = \frac{P \cdot \delta}{2 \cdot \pi \cdot \omega_2 \cdot (\omega_1 - \omega_2) \cdot R^3 \cdot L}$$


$$\mu = \frac{10 \cdot \text{W} \times 2.5 \times 10^{-4} \cdot \text{m}}{2 \cdot \pi} \times \frac{1}{9000} \cdot \frac{\text{min}}{\text{rev}} \times \frac{1}{1000} \cdot \frac{\text{min}}{\text{rev}} \times \frac{1}{(.01 \cdot \text{m})^3} \times \frac{1}{0.02 \cdot \text{m}} \times \frac{\text{N} \cdot \text{m}}{\text{s} \cdot \text{W}} \times \left( \frac{\text{rev}}{2 \cdot \pi \cdot \text{rad}} \right)^2 \times \left( \frac{60 \cdot \text{s}}{\text{min}} \right)^2$$

$$\mu = 0.202 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \quad \mu = 2.02 \cdot \text{poise} \quad \text{which corresponds to SAE 30 oil at } 30^\circ\text{C}.$$

### Problem 2.65

[Difficulty: 4] Part 1/2

**2.65** A circular aluminum shaft mounted in a journal is shown. The symmetric clearance gap between the shaft and journal is filled with SAE 10W-30 oil at  $T = 30^\circ\text{C}$ . The shaft is caused to turn by the attached mass and cord. Develop and solve a differential equation for the angular speed of the shaft as a function of time. Calculate the maximum angular speed of the shaft and the time required to reach 95 percent of this speed.



Solution: Apply summation of torques and Newton's second law.

Basic equations:  $\Sigma T = I \frac{d\omega}{dt}$        $\Sigma F = m \frac{dv}{dt}$        $v = R\omega$

For the mass:

$$\Sigma F_y = mg - t = m \frac{dv}{dt} = mR \frac{d\omega}{dt} \quad (1)$$

For the shaft:

$$\Sigma T = tR - T_{\text{viscous}} = I \frac{d\omega}{dt} \quad (2)$$

$$T_{\text{viscous}} = \tau A = \mu \frac{v}{a} R 2\pi RL = \frac{2\pi\mu WR^3 L}{a}$$

Assume: (1) Newtonian liquid, (2) small gap, (3) linear profile

Then Eq. 2 becomes  $tR - \frac{2\pi\mu R^3 L}{a} \omega = I \frac{d\omega}{dt}$  ; ;  $I = \frac{1}{2} MR^2$       (3)

Multiplying Eq. 1 by R and combining with Eq. 3 gives

$$mgR - mR^2 \frac{d\omega}{dt} - \frac{2\pi\mu R^3 L}{a} \omega = I \frac{d\omega}{dt} \quad \text{or} \quad mgR - \frac{2\pi\mu R^3 L}{a} \omega = (I + mR^2) \frac{d\omega}{dt} \quad (4)$$

This may be written  $A - B\omega = C \frac{d\omega}{dt}$  where  $A = mgR$ ,  $B = \frac{2\pi\mu R^3 L}{a}$ ,  $C = I + mR^2$

Separating variables  $\frac{d\omega}{A - B\omega} = \frac{dt}{C}$

Integrating  $\int_0^\omega \frac{d\omega}{A - B\omega} = -\frac{1}{B} \ln(A - B\omega) \Big|_0^\omega = -\frac{1}{B} \ln\left(1 - \frac{B\omega}{A}\right) = \int_0^t \frac{dt}{C} = \frac{t}{C}$

Simplifying  $1 - \frac{B\omega}{A} = e^{-Bt/C}$  or  $\omega = \frac{A}{B} \left[1 - e^{-Bt/C}\right]$       (5)  $\omega(t)$

The maximum angular speed ( $t \rightarrow \infty$ ) is  $\omega = A/B$ .

$$A = mgR = 0.010 \text{ kg} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.025 \text{ m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 2.45 \times 10^{-3} \text{ N} \cdot \text{m}$$

$$B = \frac{2\pi\mu R^3 L}{a} = 2\pi \times 0.095 \frac{\text{kg}}{\text{m} \cdot \text{s}} \times (0.025)^3 \text{ m}^3 \times 0.050 \text{ m} \times \frac{1}{0.0005 \text{ m}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 9.33 \times 10^{-4} \text{ N} \cdot \text{m} \cdot \text{s}$$

42 SHEETS 3 SQUARE  
43 SHEETS 3 SQUARE  
44 SHEETS 3 SQUARE  
45 SHEETS 3 SQUARE  
46 SHEETS 3 SQUARE  
47 SHEETS 3 SQUARE  
48 SHEETS 3 SQUARE  
49 SHEETS 3 SQUARE  
50 SHEETS 3 SQUARE  
51 SHEETS 3 SQUARE  
52 SHEETS 3 SQUARE  
53 SHEETS 3 SQUARE  
54 SHEETS 3 SQUARE  
55 SHEETS 3 SQUARE  
56 SHEETS 3 SQUARE  
57 SHEETS 3 SQUARE  
58 SHEETS 3 SQUARE  
59 SHEETS 3 SQUARE  
60 SHEETS 3 SQUARE  
61 SHEETS 3 SQUARE  
62 SHEETS 3 SQUARE  
63 SHEETS 3 SQUARE  
64 SHEETS 3 SQUARE  
65 SHEETS 3 SQUARE  
66 SHEETS 3 SQUARE  
67 SHEETS 3 SQUARE  
68 SHEETS 3 SQUARE  
69 SHEETS 3 SQUARE  
70 SHEETS 3 SQUARE  
71 SHEETS 3 SQUARE  
72 SHEETS 3 SQUARE  
73 SHEETS 3 SQUARE  
74 SHEETS 3 SQUARE  
75 SHEETS 3 SQUARE  
76 SHEETS 3 SQUARE  
77 SHEETS 3 SQUARE  
78 SHEETS 3 SQUARE  
79 SHEETS 3 SQUARE  
80 SHEETS 3 SQUARE  
81 SHEETS 3 SQUARE  
82 SHEETS 3 SQUARE  
83 SHEETS 3 SQUARE  
84 SHEETS 3 SQUARE  
85 SHEETS 3 SQUARE  
86 SHEETS 3 SQUARE  
87 SHEETS 3 SQUARE  
88 SHEETS 3 SQUARE  
89 SHEETS 3 SQUARE  
90 SHEETS 3 SQUARE  
91 SHEETS 3 SQUARE  
92 SHEETS 3 SQUARE  
93 SHEETS 3 SQUARE  
94 SHEETS 3 SQUARE  
95 SHEETS 3 SQUARE  
96 SHEETS 3 SQUARE  
97 SHEETS 3 SQUARE  
98 SHEETS 3 SQUARE  
99 SHEETS 3 SQUARE  
100 SHEETS 3 SQUARE  
NATIONAL  
MADE IN U.S.A.

### Problem 2.65

[Difficulty: 4] Part 2/2

Evaluating,  $\omega_{max} = \frac{A}{B} = 2.45 \times 10^{-5} \text{ N}\cdot\text{m} \times \frac{1}{9.33 \times 10^{-4} \text{ N}\cdot\text{m}\cdot\text{sec}} = 2.63 \text{ rad/s}$

Thus

$$\omega_{max} = 2.63 \frac{\text{rad}}{\text{s}} \times \frac{\text{rev}}{2\pi \text{ rad}} \times \frac{60 \text{ s}}{\text{min}} = 25.1 \text{ rpm}$$

$\omega_{max}$

From Eq. 5,  $\omega = 0.95 \omega_{max}$  when  $e^{-Bt/k} = 0.05$ , or  $Bt/k \approx 3$ ;  $t \approx \frac{3C}{B}$

$$C = I + mR^2 = \frac{1}{2}MR^2 + mR^2 = (\frac{1}{2}M + m)R^2$$

$$M = \pi R^2(1.5L + L)\rho = 2.5\pi R^2 L \rho$$

$$M = 2.5\pi \times (0.025)^2 \text{ m}^2 \times 0.050 \text{ m} \times (2.64)1000 \frac{\text{kg}}{\text{m}^3} = 0.648 \text{ kg}$$

$$C = (\frac{1}{2} \times 0.648 \text{ kg} + 0.010 \text{ kg})(0.025)^2 \text{ m}^2 = 2.09 \times 10^{-4} \text{ kg}\cdot\text{m}^2$$


Thus

$$t_{95} = 3 \times 2.09 \times 10^{-4} \text{ kg}\cdot\text{m}^2 \times \frac{1}{9.33 \times 10^{-4} \text{ N}\cdot\text{m}\cdot\text{s}} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} = 0.671 \text{ s}$$

$t_{95}$

{ The terminal speed could have been computed from Eq. 4 by }  
 { setting  $d\omega/dt \rightarrow 0$ , without solving the differential equation. }


**2.66** A proposal has been made to use a pair of parallel disks to measure the viscosity of a liquid sample. The upper disk rotates at height  $h$  above the lower disk. The viscosity of the liquid in the gap is to be calculated from measurements of the torque needed to turn the upper disk steadily. Obtain an algebraic expression for the torque needed to turn the disk. Could we use this device to measure the viscosity of a non-Newtonian fluid? Explain.



Solution: Use  $r, \theta, z$  coordinates at right:

Basic equations:  $\tau_{z\theta} = \mu \frac{dv_{\theta}}{dz}$

$dT = r dF = r \tau_{z\theta} dA$



- Assumptions: (1) Newtonian fluid  
 (2) No-slip condition  
 (3) Linear velocity profile (in narrow gap)

The velocity at any radial location on the rotating disk is  $v_{\theta} = \omega r$ .

Since the velocity profile is linear, then

$\tau_{z\theta} = \mu \frac{dv_{\theta}}{dz} = \mu \frac{\Delta v}{\Delta z} = \mu \frac{(\omega r - 0)}{(h - 0)} = \frac{\mu \omega r}{h}$

and

$dT = r \tau_{z\theta} dA = r \mu \frac{\omega r}{h} 2\pi r dr = \frac{2\pi \mu \omega r^3}{h} dr$

Integrating

$T = \int_A dT = \int_0^R \frac{2\pi \mu \omega r^3}{h} dr = \left. \frac{\pi \mu \omega r^4}{2h} \right|_0^R$


$T = \frac{\pi \mu \omega R^4}{2h}$

The device could not be used to measure the viscosity of a non-Newtonian fluid because the applied shear stress is not uniform. It varies from zero at the center of the disks to  $\mu \omega R/h$  at the edge

### Problem 2.67

[Difficulty: 4]

**2.67** The cone and plate viscometer shown is an instrument used frequently to characterize non-Newtonian fluids. It consists of a flat plate and a rotating cone with a very obtuse angle (typically  $\theta$  is less than 0.5 degrees). The apex of the cone just touches the plate surface and the liquid to be tested fills the narrow gap formed by the cone and plate. Derive an expression for the shear rate in the liquid that fills the gap in terms of the geometry of the system. Evaluate the torque on the driven cone in terms of the shear stress and geometry of the system.




Solution:

Since the angle  $\theta$  is very small, the average gap width is also very small.

It is reasonable to assume a linear velocity profile across the gap and to neglect end effects.

The shear (deformation) rate is given by

$$\dot{\gamma} = \frac{du}{dy} = \frac{\Delta u}{\Delta y}$$


At any radius,  $r$ ,

the velocity  $U = \omega r$  and

the gap width  $h = r \tan \theta$

$$\therefore \dot{\gamma} = \frac{\omega r}{r \tan \theta} = \frac{\omega}{\tan \theta}$$

Since  $\theta$  is very small,  $\tan \theta = \theta$  and

$$\dot{\gamma} = \frac{\omega}{\theta}$$

Note: The shear rate is independent of  $r$ . The entire sample is subjected to the same shear rate.

The torque on the driven cone is given by

$$T = \int r \cdot dF \quad \text{where } dF = \tau_{yz} dA$$

Since  $\dot{\gamma}$  is a constant (for a given  $\omega$ ) then  $\tau_{yz} = \text{constant}$

and

$$T = \int r dF = \int_A r \tau_{yz} dA = \tau_{yz} \int_0^R r 2\pi r dr$$


$$T = \frac{2\pi}{3} R^3 \tau_{yz}$$

## Problem 2.68

[Difficulty: 4]

**2.68** The viscometer of Problem 2.67 is used to measure the apparent viscosity of a fluid. The data below are obtained. What kind of non-Newtonian fluid is this? Find the values of  $k$  and  $n$  used in Eqs. 2.16 and 2.17 in defining the apparent viscosity of a fluid. (Assume  $\theta$  is 0.5 degrees.) Predict the viscosity at 90 and 100 rpm.

Speed (rpm)	10	20	30	40	50	60	70	80
$\mu$ ( $\text{N} \cdot \text{s}/\text{m}^2$ )	0.121	0.139	0.153	0.159	0.172	0.172	0.183	0.185



**Given:** Data on the viscometer

**Find:** The values of coefficients  $k$  and  $n$ ; determine the kind of non-Newtonian fluid it is; estimate viscosity at 90 and 100 rpm

**Solution:**

The velocity gradient at any radius  $r$  is

$$\frac{du}{dy} = \frac{r \cdot \omega}{r \cdot \tan(\theta)}$$

where  $\omega$  (rad/s) is the angular velocity

$$\omega = \frac{2 \cdot \pi \cdot N}{60} \quad \text{where } N \text{ is the speed in rpm}$$

For small  $\theta$ ,  $\tan(\theta)$  can be replaced with  $\theta$ , so

$$\frac{du}{dy} = \frac{\omega}{\theta}$$

From Eq 2.11.

$$k \cdot \left( \frac{du}{dy} \right)^{n-1} \frac{du}{dy} = \eta \cdot \frac{du}{dy}$$

where  $\eta$  is the apparent viscosity. Hence

$$\eta = k \cdot \left( \frac{du}{dy} \right)^{n-1} = k \cdot \left( \frac{\omega}{\theta} \right)^{n-1}$$

The data is

N (rpm)	$\mu$ ( $\text{N s}/\text{m}^2$ )
10	0.121
20	0.139
30	0.153
40	0.159
50	0.172
60	0.172
70	0.183
80	0.185

The computed data is


$\omega$ (rad/s)	$\omega/\theta$ (1/s)	$\eta$ (N s/m <sup>2</sup> x10 <sup>3</sup> )
1.047	120	121
2.094	240	139
3.142	360	153
4.189	480	159
5.236	600	172
6.283	720	172
7.330	840	183
8.378	960	185

From the *Trendline* analysis

$k = 0.0449$   
 $n - 1 = 0.2068$   
 $n = 1.21$       The fluid is dilatant

The apparent viscosities at 90 and 100 rpm can now be computed

N (rpm)	$\omega$ (rad/s)	$\omega/\theta$ (1/s)	$\eta$ (N s/m <sup>2</sup> x10 <sup>3</sup> )
90	9.42	1080	191
100	10.47	1200	195



**Problem 2.69**

[Difficulty: 4]

**2.69** An insulation company is examining a new material for extruding into cavities. The experimental data is given below for the speed  $U$  of the upper plate, which is separated from a fixed lower plate by a 1-mm-thick sample of the material, when a given shear stress is applied. Determine the type of material. If a replacement material with a minimum yield stress of 250 Pa is needed, what viscosity will the material need to have the same behavior as the current material at a shear stress of 450 Pa?

$\tau$ (Pa)	50	100	150	163	171	170	202	246	349	444
$U$ (m/s)	0	0	0	0.005	0.01	0.025	0.05	0.1	0.2	0.3

- Given:** Data on insulation material  
**Find:** Type of material; replacement material  
**Solution:**

The velocity gradient is

$$du/dy = U/\delta \quad \text{where } \delta = 0.001 \text{ m}$$

Data and computations

$\tau$ (Pa)	$U$ (m/s)	$du/dy$ ( $s^{-1}$ )
50	0.000	0
100	0.000	0
150	0.000	0
163	0.005	5
171	0.01	10
170	0.03	25
202	0.05	50
246	0.1	100
349	0.2	200
444	0.3	300


Hence we have a Bingham plastic, with  $\tau_y = 154$  Pa  
 $\mu_p = 0.963$  N s/m<sup>2</sup>

At  $\tau = 450$  Pa, based on the linear fit  $du/dy = 307$  s<sup>-1</sup>

For a fluid with  $\tau_y = 250$  Pa

we can use the Bingham plastic formula to solve for  $\mu_p$  given  $\tau$ ,  $\tau_y$  and  $du/dy$  from above

$$\mu_p = 0.652 \text{ N s/m}^2$$




## Problem 2.70

[Difficulty: 3]

**2.70** A viscometer is used to measure the viscosity of a patient's blood. The deformation rate (shear rate)—shear stress data is shown below. Plot the apparent viscosity versus deformation rate. Find the value of  $k$  and  $n$  in Eq. 2.17, and from this examine the aphorism "Blood is thicker than water."

$du/dy$ ( $s^{-1}$ )	5	10	25	50	100	200	300	400
$\tau$ (Pa)	0.0457	0.119	0.241	0.375	0.634	1.06	1.46	1.78




**Given:** Viscometer data

**Find:** Value of  $k$  and  $n$  in Eq. 2.17

**Solution:**

The data is

$\tau$ (Pa)	$du/dy$ ( $s^{-1}$ )
0.0457	5
0.119	10
0.241	25
0.375	50
0.634	100
1.06	200
1.46	300
1.78	400



Hence we have

$$k = 0.0162$$

$$n = 0.7934$$

Blood is pseudoplastic (shear thinning)

The apparent viscosity from

$$\eta = k (du/dy)^{n-1}$$

$du/dy$ ( $s^{-1}$ )	$\eta$ ( $N \cdot s/m^2$ )
5	0.0116
10	0.0101
25	0.0083
50	0.0072
100	0.0063
200	0.0054
300	0.0050
400	0.0047


$$\mu_{\text{water}} = 0.001 \text{ N s/m}^2 \text{ at } 20^\circ\text{C}$$

Hence, blood is "thicker" than water!

## Problem 2.71

[Difficulty: 5]

**2.71** A viscous clutch is to be made from a pair of closely spaced parallel disks enclosing a thin layer of viscous liquid. Develop algebraic expressions for the torque and the power transmitted by the disk pair, in terms of liquid viscosity,  $\mu$ , disk radius,  $R$ , disk spacing,  $a$ , and the angular speeds:  $\omega_i$  of the input disk and  $\omega_o$  of the output disk. Also develop expressions for the slip ratio,  $s = \Delta\omega/\omega_i$ , in terms of  $\omega_i$  and the torque transmitted. Determine the efficiency,  $\eta$ , in terms of the slip ratio.




Solution: Apply Newton's law of viscosity

Basic equations:  $\tau = \mu \frac{du}{dy}$      $dF = \tau dA$      $dT = r dF$

Assumptions: (1) Newtonian liquid  
(2) Narrow gap so velocity profile is linear

Consider a segment of plates:

$$\tau = \mu \frac{du}{dy} = \mu \frac{\Delta u}{\Delta y} = \mu \frac{r(\omega_i - \omega_o)}{a}$$



$$dA = r dr d\theta$$

End View

Bottom View

$$dF = \tau dA = \frac{\mu r \Delta\omega}{a} r dr d\theta = \frac{\mu \Delta\omega}{a} r^2 dr d\theta ; dT = r dF = \frac{\mu \Delta\omega}{a} r^3 dr d\theta$$

Integrating

$$T = \int_0^{2\pi} \int_0^R dT = \frac{\mu \Delta\omega}{a} \int_0^{2\pi} \int_0^R r^3 dr d\theta = \frac{2\pi \mu \Delta\omega}{a} \int_0^R r^3 dr = \frac{\pi \mu \Delta\omega R^4}{2a} \quad \leftarrow T$$

$$P_o = T \omega_o = \frac{\pi \mu \omega_o \Delta\omega R^4}{2a} \quad (\text{power transmitted}) \quad \leftarrow P$$

$$s = \frac{\Delta\omega}{\omega_i} = \frac{2aT}{\pi \mu R^4 \omega_i} \quad \leftarrow s$$


Efficiency is  $\eta = \frac{\text{Power out}}{\text{Power in}} = \frac{T \omega_o}{T \omega_i} = \frac{\omega_o}{\omega_i}$ . But  $\omega_o = \omega_i - \Delta\omega$ , so

$$\eta = \frac{\omega_i - \Delta\omega}{\omega_i} = 1 - \frac{\Delta\omega}{\omega_i} = 1 - s \quad \leftarrow \eta$$

## Problem 2.72

[Difficulty: 5]

**2.72** A concentric-cylinder viscometer is shown. Viscous torque is produced by the annular gap around the inner cylinder. Additional viscous torque is produced by the flat bottom of the inner cylinder as it rotates above the flat bottom of the stationary outer cylinder. Obtain an algebraic expression for the viscous torque due to flow in the annular gap of width  $a$ . Obtain an algebraic expression for the viscous torque due to flow in the bottom clearance gap of height  $b$ . Prepare a plot showing the ratio,  $b/a$ , required to hold the bottom torque to 1 percent or less of the annulus torque, versus the other geometric variables. What are the design implications? What modifications to the design can you recommend?



Solution: Basic equation  $\tau_{yx} = \mu \frac{du}{dy}$   
 Assumptions: (1) linear velocity profile, (2) Newtonian liquid

(a) in annular gap

$$\tau = \mu \frac{du}{dr} = \mu \frac{\Delta u}{\Delta r} = \mu \frac{U}{a} = \mu \frac{\omega R}{a}$$

$$\text{Torque} = R F_r = R \tau A = R \mu \frac{\omega R}{a} (2\pi R H) = \frac{2\pi \mu \omega R^3 H}{a} \quad (a)$$

(b) in bottom gap

$$\tau = \mu \frac{du}{dz} = \mu \frac{\Delta u}{\Delta z} = \mu \frac{U}{b} = \mu \frac{\omega R}{b}$$

(varies with r)

$$\text{Torque} = \int dT = \int r dF = \int r \tau dA = \int_0^R r \mu \frac{\omega R}{b} 2\pi r dr$$


$$\text{Torque} = \frac{2\pi \mu \omega}{b} \int_0^R r^3 dr = \frac{2\pi \mu \omega}{b} \left[ \frac{r^4}{4} \right]_0^R = \frac{\pi \mu \omega}{2b} R^4 \quad (b)$$

(c) For  $T_{\text{bottom}} / T_{\text{annulus}} \leq \frac{1}{100}$ , then

$$\frac{T_{\text{bot}}}{T_{\text{an}}} = \frac{\pi \mu \omega}{2b} R^4 \times \frac{a}{2\pi \mu \omega R^3 H} \leq \frac{1}{100}$$

$$\frac{aR}{4bH} \leq \frac{1}{100}$$

or  $\frac{b}{a} \geq 25 \frac{R}{H}$



(d) The plot shows the operating range. Specific design would depend on other constraints.


For  $a = 1 \text{ mm}$  with  $R/H = 1/2$  gives  $b = 12.5 \text{ mm}$

(e) For a given value of  $R/H$ , the dimension  $b$  could be effectively increased by "hollowing out" the inner cylinder as shown by the dashed lines in the diagram above.

## Problem 2.73

[Difficulty: 4]

**2.73** A viscometer is built from a conical pointed shaft that turns in a conical bearing, as shown. The gap between shaft and bearing is filled with a sample of the test oil. Obtain an algebraic expression for the viscosity  $\mu$  of the oil as a function of viscometer geometry ( $H$ ,  $a$ , and  $\theta$ ), turning speed  $\omega$ , and applied torque  $T$ . For the data given, find by referring to Figure A.2 in Appendix A, the type of oil for which the applied torque is  $0.325 \text{ N}\cdot\text{m}$ . The oil is at  $20^\circ\text{C}$ . *Hint:* First obtain an expression for the shear stress on the surface of the conical shaft as a function of  $z$ .



**Given:** Conical bearing geometry

**Find:** Expression for shear stress; Viscous torque on shaft


**Solution:**

Basic equation  $\tau = \mu \cdot \frac{du}{dy}$   $dT = r \cdot \tau \cdot dA$  Infinitesimal shear torque

Assumptions: Newtonian fluid, linear velocity profile (in narrow clearance gap), no slip condition

$$\tan(\theta) = \frac{r}{z} \quad \text{so} \quad r = z \cdot \tan(\theta)$$

Then 
$$\tau = \mu \cdot \frac{du}{dy} = \mu \cdot \frac{\Delta u}{\Delta y} = \mu \cdot \frac{(\omega \cdot r - 0)}{(a - 0)} = \frac{\mu \cdot \omega \cdot z \cdot \tan(\theta)}{a}$$



As we move up the device, shear stress increases linearly (because rate of shear strain does)

But from the sketch  $dz = ds \cdot \cos(\theta)$   $dA = 2 \cdot \pi \cdot r \cdot ds = 2 \cdot \pi \cdot r \cdot \frac{dz}{\cos(\theta)}$

The viscous torque on the element of area is 
$$dT = r \cdot \tau \cdot dA = r \cdot \frac{\mu \cdot \omega \cdot z \cdot \tan(\theta)}{a} \cdot 2 \cdot \pi \cdot r \cdot \frac{dz}{\cos(\theta)}$$
 
$$dT = \frac{2 \cdot \pi \cdot \mu \cdot \omega \cdot z^3 \cdot \tan(\theta)^3}{a \cdot \cos(\theta)} \cdot dz$$

Integrating and using limits  $z = H$  and  $z = 0$  
$$T = \frac{\pi \cdot \mu \cdot \omega \cdot \tan(\theta)^3 \cdot H^4}{2 \cdot a \cdot \cos(\theta)}$$

Solving for  $\mu$  
$$\mu = \frac{2 \cdot a \cdot \cos(\theta) \cdot T}{\pi \cdot \omega \cdot \tan(\theta)^3 \cdot H^4}$$

Using given data  $H = 25 \cdot \text{mm}$   $\theta = 30\text{-deg}$   $a = 0.2 \cdot \text{mm}$   $\omega = 75 \cdot \frac{\text{rev}}{\text{s}}$   $T = 0.325 \cdot \text{N}\cdot\text{m}$

$$\mu = \frac{2 \cdot a \cdot \cos(\theta) \cdot T}{\pi \cdot \omega \cdot \tan(\theta)^3 \cdot H^4} \quad \mu = 1.012 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$$

From Fig. A.2, at  $20^\circ\text{C}$ , CASTOR OIL has this viscosity!

## Problem 2.74


[Difficulty: 5]

**2.74** Design a concentric-cylinder viscometer to measure the viscosity of a liquid similar to water. The goal is to achieve a measurement accuracy of  $\pm 1$  percent. Specify the configuration and dimensions of the viscometer. Indicate what measured parameter will be used to infer the viscosity of the liquid sample.

Solution: Apply definition of Newtonian fluid

Computing equation:  $\tau = \mu \frac{du}{dy}$

- Assumptions:
- (1) Steady
  - (2) Newtonian liquid
  - (3) Narrow gap, so "unroll" it
  - (4) Linear velocity profile in gap
  - (5) Neglect end effects



Flow model:  $\frac{V}{a} = \frac{u}{y} = \frac{\omega R}{a}$        $u = V \frac{y}{a} = \omega R \frac{y}{a}$  ;  $\frac{du}{dy} = \frac{\omega R}{a}$

Thus  $\tau = \mu \frac{du}{dy} = \mu \frac{\omega R}{a}$  and torque on rotor is  $T = \tau A$ , where  $A = 2\pi R H$

Consequently  $T = R \mu \frac{\omega R}{a} 2\pi R H = \frac{2\pi \mu \omega R^3 H}{a}$ , or

$$\mu = \frac{Ta}{2\pi \omega R^3 H}$$

From this equation the uncertainty in  $\mu$  is (see Appendix F),

$$\frac{\Delta \mu}{\mu} = \pm \left[ \frac{\Delta T^2}{T^2} + \frac{\Delta a^2}{a^2} + \frac{\Delta \omega^2}{\omega^2} + \frac{\Delta H^2}{H^2} \right]^{\frac{1}{2}} = \pm [13 u^2]^{\frac{1}{2}} = \pm 3.61 u$$

if the uncertainty of each parameter equals  $u$ . Thus

$$u = \pm \frac{\frac{\Delta \mu}{\mu}}{3.61} = \pm \frac{1 \text{ percent}}{3.61} = \pm 0.277 \text{ percent}$$

Typical dimensions for a bench-top unit might be

$$H = 200 \text{ mm}, R = 75 \text{ mm}, a = 0.02 \text{ mm}, \text{ and } \omega = 10.5 \text{ rad/s (100 rpm)}$$

From Appendix A, Table A.8, water has  $\mu = 1.00 \times 10^{-3} \text{ N}\cdot\text{s/m}^2$  at  $T = 20^\circ\text{C}$ .

The corresponding torque would be

$$T = 2\pi \times 1.00 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times \frac{10.5}{\text{s}} \times (0.075)^3 \text{ m}^3 \times 0.2 \text{ m} \times \frac{1}{0.0002 \text{ m}} = 0.278 \text{ N}\cdot\text{m}$$


It should be possible to measure this torque quite accurately.

{ Many details would need to be considered (e.g. bearings, temperature rise, etc.) to produce a workable device. }

## Problem 2.75

[Difficulty: 5]

**2.75** A spherical thrust bearing is shown. The gap between the spherical member and the housing is of constant width  $h$ . Obtain and plot an algebraic expression for the nondimensional torque on the spherical member, as a function of angle  $\alpha$ .



Solution: Apply definitions

Computing equations:  $\tau = \mu \frac{du}{dy}$        $T = \int_A r \tau dA$

Assumptions: (1) Newtonian fluid, (2) narrow gap, (3) laminar flow

From the figure,  $r = R \sin \theta$        $u = \omega r = \omega R \sin \theta$

$$\tau = \mu \frac{du}{dy} = \mu \left( \frac{u-0}{h} \right) = \mu \frac{u}{h} = \frac{\mu \omega R \sin \theta}{h}$$


$$dA = 2\pi r R d\theta = 2\pi R^2 \sin \theta d\theta$$

Thus

$$T = \int_0^\alpha R \sin \theta \left( \frac{\mu \omega R \sin \theta}{h} \right) 2\pi R^2 \sin \theta d\theta = \frac{2\pi \mu \omega R^4}{h} \int_0^\alpha \sin^3 \theta d\theta$$

$$T = \frac{2\pi \mu \omega R^4}{h} \left[ \frac{\cos^3 \theta}{3} - \cos \theta \right]_0^\alpha = \frac{2\pi \mu \omega R^4}{h} \left[ \frac{\cos^3 \alpha}{3} - \cos \alpha + \frac{2}{3} \right]$$

To plot, normalize to  $\left[ \frac{T}{2\pi \mu \omega R^4} \right] = \left[ \frac{\cos^3 \alpha}{3} - \cos \alpha + \frac{2}{3} \right]$




{ Check dimensions:  $\left[ \frac{\mu \omega R^4}{h} \right] = \frac{Ft}{L^2} \times \frac{1}{t} \times L^4 \times \frac{1}{L} = FL^2 \checkmark \checkmark$  }

## Problem 2.76

[Difficulty: 5]

**2.76** A cross section of a rotating bearing is shown. The spherical member rotates with angular speed  $\omega$ , a small distance,  $a$ , above the plane surface. The narrow gap is filled with viscous oil, having  $\mu = 1250$  cp. Obtain an algebraic expression for the shear stress acting on the spherical member. Evaluate the maximum shear stress that acts on the spherical member for the conditions shown. (Is the maximum necessarily located at the maximum radius?) Develop an algebraic expression (in the form of an integral) for the total viscous shear torque that acts on the spherical member. Calculate the torque using the dimensions shown.



**Given:** Geometry of rotating bearing

**Find:** Expression for shear stress; Maximum shear stress; Expression for total torque; Total torque

**Solution:**

Basic equation  $\tau = \mu \cdot \frac{du}{dy}$   $dT = r \cdot \tau \cdot dA$

Assumptions: Newtonian fluid, narrow clearance gap, laminar motion

From the figure  $r = R \cdot \sin(\theta)$   $u = \omega \cdot r = \omega \cdot R \cdot \sin(\theta)$   $\frac{du}{dy} = \frac{u - 0}{h} = \frac{u}{h}$

$h = a + R \cdot (1 - \cos(\theta))$   $dA = 2 \cdot \pi \cdot r \cdot dr = 2 \cdot \pi \cdot R \cdot \sin(\theta) \cdot R \cdot \cos(\theta) \cdot d\theta$

Then  $\tau = \mu \cdot \frac{du}{dy} = \frac{\mu \cdot \omega \cdot R \cdot \sin(\theta)}{a + R \cdot (1 - \cos(\theta))}$

To find the maximum  $\tau$  set  $\frac{d}{d\theta} \left[ \frac{\mu \cdot \omega \cdot R \cdot \sin(\theta)}{a + R \cdot (1 - \cos(\theta))} \right] = 0$  so  $\frac{R \cdot \mu \cdot \omega \cdot (R \cdot \cos(\theta) - R + a \cdot \cos(\theta))}{(R + a - R \cdot \cos(\theta))^2} = 0$

$R \cdot \cos(\theta) - R + a \cdot \cos(\theta) = 0$   $\theta = \text{acos} \left( \frac{R}{R + a} \right) = \text{acos} \left( \frac{75}{75 + 0.5} \right)$   $\theta = 6.6 \cdot \text{deg}$

$\tau = 12.5 \cdot \text{poise} \times 0.1 \cdot \frac{\text{kg}}{\text{m} \cdot \text{s}} \times 2 \cdot \pi \cdot \frac{70}{60} \cdot \frac{\text{rad}}{\text{s}} \times 0.075 \cdot \text{m} \times \sin(6.6 \cdot \text{deg}) \times \frac{1}{[0.0005 + 0.075 \cdot (1 - \cos(6.6 \cdot \text{deg}))]} \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{m} \cdot \text{kg}}$

$\tau = 79.2 \cdot \frac{\text{N}}{\text{m}^2}$

The torque is  $T = \int_0^{\theta_{\max}} r \cdot \tau \cdot A \, d\theta = \int_0^{\theta_{\max}} \frac{\mu \cdot \omega \cdot R^4 \cdot \sin^2(\theta) \cdot \cos(\theta)}{a + R \cdot (1 - \cos(\theta))} \, d\theta$  where  $\theta_{\max} = \text{asin} \left( \frac{R_0}{R} \right)$   $\theta_{\max} = 15.5 \cdot \text{deg}$

This integral is best evaluated numerically using Excel, Mathcad, or a good calculator  $T = 1.02 \times 10^{-3} \cdot \text{N} \cdot \text{m}$

## Problem 2.77

[Difficulty: 2]


**2.77** Small gas bubbles form in soda when a bottle or can is opened. The average bubble diameter is about 0.1 mm. Estimate the pressure difference between the inside and outside of such a bubble.

Solution: Consider a free-body diagram of half a bubble:

Two forces act:

Pressure:  $F_p = \Delta p \frac{\pi D^2}{4}$

Surface tension:  $F_s = \sigma \pi D$



Summing forces for equilibrium

$$\sum F_x = F_p - F_s = \Delta p \frac{\pi D^2}{4} - \sigma \pi D = 0$$

$$\text{so } \frac{\Delta p D}{4} - \sigma = 0 \quad \text{or } \Delta p = \frac{4\sigma}{D}$$

Assuming soda-gas interface is similar to water-air, then  $\sigma = 72.8 \text{ mN/m}$ , and

$$\Delta p = 4 \times 72.8 \times 10^{-3} \frac{\text{N}}{\text{m}} \times \frac{1}{0.1 \times 10^{-3} \text{ m}} = 2.91 \times 10^3 \frac{\text{N}}{\text{m}^2} = 2.91 \text{ kPa}$$

$\Delta p$

## Problem 2.78

[Difficulty: 2]

**2.78** You intend to gently place several steel needles on the free surface of the water in a large tank. The needles come in two lengths: Some are 5 cm long, and some are 10 cm long. Needles of each length are available with diameters of 1 mm, 2.5 mm, and 5 mm. Make a prediction as to which needles, if any, will float.

**Given:** Data on size of various needles

**Find:** Which needles, if any, will float

**Solution:**

For a steel needle of length  $L$ , diameter  $D$ , density  $\rho_s$ , to float in water with surface tension  $\sigma$  and contact angle  $\theta$ , the vertical force due to surface tension must equal or exceed the weight

$$2 \cdot L \cdot \sigma \cdot \cos(\theta) \geq W = m \cdot g = \frac{\pi \cdot D^2}{4} \cdot \rho_s \cdot L \cdot g \quad \text{or} \quad D \leq \sqrt{\frac{8 \cdot \sigma \cdot \cos(\theta)}{\pi \cdot \rho_s \cdot g}}$$

From Table A.4  $\sigma = 72.8 \times 10^{-3} \frac{\text{N}}{\text{m}}$   $\theta = 0 \text{ deg}$  and for water  $\rho = 1000 \frac{\text{kg}}{\text{m}^3}$

From Table A.1, for steel  $\text{SG} = 7.83$

Hence 
$$\sqrt{\frac{8 \cdot \sigma \cdot \cos(\theta)}{\pi \cdot \text{SG} \cdot \rho \cdot g}} = \sqrt{\frac{8}{\pi \cdot 7.83} \times 72.8 \times 10^{-3} \frac{\text{N}}{\text{m}} \times \frac{\text{m}^3}{999 \cdot \text{kg}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}} = 1.55 \times 10^{-3} \cdot \text{m} = 1.55 \cdot \text{mm}$$

Hence  $D < 1.55 \text{ mm}$ . Only the 1 mm needles float (needle length is irrelevant)

## Problem 2.79

[Difficulty: 3]

2.79 According to Folsom [6], the capillary rise  $\Delta h$  (in.) of a water-air interface in a tube is correlated by the following empirical expression:

$$\Delta h = Ae^{-bD}$$

where  $D$  (in.) is the tube diameter,  $A = 0.400$ , and  $b = 4.37$ . You do an experiment to measure  $\Delta h$  versus  $D$  and obtain:

$D$ (in.)	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1	1.1
$\Delta h$ (in.)	0.232	0.183	0.09	0.059	0.052	0.033	0.017	0.01	0.006	0.004	0.003

What are the values of  $A$  and  $b$  that best fit this data using *Excel's Trendline* feature? Do they agree with Folsom's values? How good is the data?

**Given:** Capillary rise data

**Find:** Values of  $A$  and  $b$


**Solution:**

$D$ (in.)	$\Delta h$ (in.)
0.1	0.232
0.2	0.183
0.3	0.090
0.4	0.059
0.5	0.052
0.6	0.033
0.7	0.017
0.8	0.010
0.9	0.006
1.0	0.004
1.1	0.003

$$A = 0.403$$
$$b = 4.530$$

The fit is a good one ( $R^2 = 0.9919$ )

Capillary Rise vs. Tube Diameter



## Problem 2.80

[Difficulty: 2]

---

**2.80** Slowly fill a glass with water to the maximum possible level. Observe the water level closely. Explain how it can be higher than the rim of the glass.

---

**Open-Ended Problem Statement:** Slowly fill a glass with water to the maximum possible level before it overflows. Observe the water level closely. Explain how it can be higher than the rim of the glass.

**Discussion:** Surface tension can cause the maximum water level in a glass to be higher than the rim of the glass. The same phenomenon causes an isolated drop of water to “bead up” on a smooth surface. Surface tension between the water/air interface and the glass acts as an invisible membrane that allows trapped water to rise above the level of the rim of the glass. The mechanism can be envisioned as forces that act in the surface of the liquid above the rim of the glass. Thus the water appears to defy gravity by attaining a level higher than the rim of the glass.

To experimentally demonstrate that this phenomenon is the result of surface tension, set the liquid level nearly as far above the glass rim as you can get it, using plain water. Add a drop of liquid detergent (the detergent contains additives that reduce the surface tension of water). Watch as the excess water runs over the side of the glass.

## Problem 2.81

[Difficulty: 5]

---

**2.81** Plan an experiment to measure the surface tension of a liquid similar to water. If necessary, review the NCFMF video *Surface Tension* for ideas. Which method would be most suitable for use in an undergraduate laboratory? What experimental precision could be expected?

---

**Open-Ended Problem Statement:** Plan an experiment to measure the surface tension of a liquid similar to water. If necessary, review the NCFMF video *Surface Tension* for ideas. Which method would be most suitable for use in an undergraduate laboratory? What experimental precision could be expected?

**Discussion:** Two basic kinds of experiment are possible for an undergraduate laboratory:

1. Using a clear small-diameter tube, compare the capillary rise of the unknown liquid with that of a known liquid (compare with water, because it is similar to the unknown liquid).

This method would be simple to set up and should give fairly accurate results. A vertical traversing optical microscope could be used to increase the precision of measuring the liquid height in each tube.

A drawback to this method is that the specific gravity and contact angle of the two liquids must be the same to allow the capillary rises to be compared.

The capillary rise would be largest and therefore easiest to measure accurately in a tube with the smallest practical diameter. Tubes of several diameters could be used if desired.

2. Dip an object into a pool of test liquid and measure the vertical force required to pull the object from the liquid surface.

The object might be made rectangular (e.g., a sheet of plastic material) or circular (e.g., a metal ring). The net force needed to pull the same object from each liquid should be proportional to the surface tension of each liquid.

This method would be simple to set up. However, the force magnitudes to be measured would be quite small.

A drawback to this method is that the contact angles of the two liquids must be the same.

The first method is probably best for undergraduate laboratory use. A quantitative estimate of experimental measurement uncertainty is impossible without knowing details of the test setup. It might be reasonable to expect results accurate to within  $\pm 10\%$  of the true surface tension.

---

\*Net force is the total vertical force minus the weight of the object. A buoyancy correction would be necessary if part of the object were submerged in the test liquid.



## Problem 2.83

[Difficulty: 2]

**2.83** The viscous boundary layer velocity profile shown in Fig. 2.15 can be approximated by a parabolic equation,

$$u(y) = a + b\left(\frac{y}{\delta}\right) + c\left(\frac{y}{\delta}\right)^2$$

The boundary condition is  $u = U$  (the free stream velocity) at the boundary edge  $\delta$  (where the viscous friction becomes zero). Find the values of  $a$ ,  $b$ , and  $c$ .

**Given:** Boundary layer velocity profile in terms of constants  $a$ ,  $b$  and  $c$

**Find:** Constants  $a$ ,  $b$  and  $c$

**Solution:**

Basic equation 
$$u = a + b\left(\frac{y}{\delta}\right) + c\left(\frac{y}{\delta}\right)^2$$

Assumptions: No slip, at outer edge  $u = U$  and  $\tau = 0$

At  $y = 0$   $0 = a$   $a = 0$


At  $y = \delta$   $U = a + b + c$   $b + c = U$  (1)

At  $y = \delta$   $\tau = \mu \cdot \frac{du}{dy} = 0$

$$0 = \frac{d}{dy} a + b\left(\frac{y}{\delta}\right) + c\left(\frac{y}{\delta}\right)^2 = \frac{b}{\delta} + 2 \cdot c \cdot \frac{y}{\delta^2} = \frac{b}{\delta} + 2 \cdot \frac{c}{\delta} \quad b + 2 \cdot c = 0 \quad (2)$$

From 1 and 2  $c = -U$   $b = 2 \cdot U$

Hence 
$$u = 2 \cdot U \cdot \left(\frac{y}{\delta}\right) - U \cdot \left(\frac{y}{\delta}\right)^2 \quad \frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$$



## Problem 2.84

[Difficulty: 2]

**2.84** The viscous boundary layer velocity profile shown in Fig. 2.15 can be approximated by a cubic equation,

$$u(y) = a + b\left(\frac{y}{\delta}\right) + c\left(\frac{y}{\delta}\right)^3$$

The boundary condition is  $u = U$  (the free stream velocity) at the boundary edge  $\delta$  (where the viscous friction becomes zero). Find the values of  $a$ ,  $b$ , and  $c$ .

**Given:** Boundary layer velocity profile in terms of constants  $a$ ,  $b$  and  $c$

**Find:** Constants  $a$ ,  $b$  and  $c$

**Solution:**

Basic equation 
$$u = a + b\left(\frac{y}{\delta}\right) + c\left(\frac{y}{\delta}\right)^3$$

Assumptions: No slip, at outer edge  $u = U$  and  $\tau = 0$

At  $y = 0$   $0 = a$   $a = 0$


At  $y = \delta$   $U = a + b + c$   $b + c = U$  (1)

At  $y = \delta$   $\tau = \mu \cdot \frac{du}{dy} = 0$

$$0 = \frac{d}{dy} a + b\left(\frac{y}{\delta}\right) + c\left(\frac{y}{\delta}\right)^3 = \frac{b}{\delta} + 3 \cdot c \cdot \frac{y^2}{\delta^3} = \frac{b}{\delta} + 3 \cdot \frac{c}{\delta} \quad b + 3 \cdot c = 0 \quad (2)$$

From 1 and 2  $c = -\frac{U}{2}$   $b = \frac{3}{2} \cdot U$

Hence 
$$u = \frac{3 \cdot U}{2} \cdot \left(\frac{y}{\delta}\right) - \frac{U}{2} \cdot \left(\frac{y}{\delta}\right)^3 \quad \frac{u}{U} = \frac{3}{2} \cdot \left(\frac{y}{\delta}\right) - \frac{1}{2} \cdot \left(\frac{y}{\delta}\right)^3$$



## Problem 2.85

[Difficulty: 1]

**2.85** At what minimum speed (in mph) would an automobile have to travel for compressibility effects to be important? Assume the local air temperature is 60°F.

**Given:** Local temperature

**Find:** Minimum speed for compressibility effects

**Solution:**

Basic equation  $V = M \cdot c$  and  $M = 0.3$  for compressibility effects

$c = \sqrt{k \cdot R \cdot T}$  For air at STP,  $k = 1.40$  and  $R = 286.9 \text{ J/kg}\cdot\text{K}$  ( $53.33 \text{ ft}\cdot\text{lbf/lbm}\cdot\text{R}$ ).

Hence  $V = M \cdot c = M \cdot \sqrt{k \cdot R \cdot T}$

$$V = 0.3 \times \left[ 1.4 \times 53.33 \cdot \frac{\text{ft}\cdot\text{lbf}}{\text{lbm}\cdot\text{R}} \times \frac{32.2 \cdot \text{lbm}\cdot\text{ft}}{\text{lbf}\cdot\text{s}^2} \times (60 + 460) \cdot \text{R} \right]^{\frac{1}{2}} \cdot \frac{60 \cdot \text{mph}}{88 \cdot \frac{\text{ft}}{\text{s}}} \quad V = 229 \cdot \text{mph}$$



## Problem 2.87

[Difficulty: 2]

**2.87** What is the Reynolds number of water at 20°C flowing at 0.25 m/s through a 5-mm-diameter tube? If the pipe is now heated, at what mean water temperature will the flow transition to turbulence? Assume the velocity of the flow remains constant.

**Given:** Data on water tube

**Find:** Reynolds number of flow; Temperature at which flow becomes turbulent

**Solution:**

Basic equation For pipe flow (Section 2-6) 
$$\text{Re} = \frac{\rho \cdot V \cdot D}{\mu} = \frac{V \cdot D}{\nu}$$

At 20°C, from Fig. A.3  $\nu = 9 \times 10^{-7} \frac{\text{m}^2}{\text{s}}$  and so 
$$\text{Re} = 0.25 \frac{\text{m}}{\text{s}} \times 0.005 \cdot \text{m} \times \frac{1}{9 \times 10^{-7} \frac{\text{m}^2}{\text{s}}} \cdot \frac{\text{s}}{\text{m}^2} \quad \text{Re} = 1389$$

For the heated pipe 
$$\text{Re} = \frac{V \cdot D}{\nu} = 2300 \quad \text{for transition to turbulence}$$

Hence 
$$\nu = \frac{V \cdot D}{2300} = \frac{1}{2300} \times 0.25 \frac{\text{m}}{\text{s}} \times 0.005 \cdot \text{m} \quad \nu = 5.435 \times 10^{-7} \frac{\text{m}^2}{\text{s}}$$

From Fig. A.3, the temperature of water at this viscosity is approximately  $T = 52 \cdot \text{C}$

## Problem 2.88

[Difficulty: 3]

**2.88** A supersonic aircraft travels at 2700 km/hr at an altitude of 27 km. What is the Mach number of the aircraft? At what approximate distance measured from the leading edge of the aircraft's wing does the boundary layer change from laminar to turbulent?

**Given:** Data on supersonic aircraft

**Find:** Mach number; Point at which boundary layer becomes turbulent

**Solution:**

Basic equation  $V = M \cdot c$  and  $c = \sqrt{k \cdot R \cdot T}$  For air at STP,  $k = 1.40$  and  $R = 286.9 \text{ J/kg}\cdot\text{K}$  (53.33 ft.lbf/lbm $^\circ\text{R}$ ).

Hence 
$$M = \frac{V}{c} = \frac{V}{\sqrt{k \cdot R \cdot T}}$$

At 27 km the temperature is approximately (from Table A.3)  $T = 223.5 \cdot \text{K}$

$$M = \left( 2700 \times 10^3 \cdot \frac{\text{m}}{\text{hr}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} \right) \cdot \left( \frac{1}{1.4} \times \frac{1}{286.9} \cdot \frac{\text{kg} \cdot \text{K}}{\text{N} \cdot \text{m}} \times \frac{1 \cdot \text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times \frac{1}{223.5} \cdot \frac{1}{\text{K}} \right)^{\frac{1}{2}} \quad M = 2.5$$

For boundary layer transition, from Section 2-6  $Re_{\text{trans}} = 500000$

Then 
$$Re_{\text{trans}} = \frac{\rho \cdot V \cdot x_{\text{trans}}}{\mu} \quad \text{so} \quad x_{\text{trans}} = \frac{\mu \cdot Re_{\text{trans}}}{\rho \cdot V}$$

We need to find the viscosity and density at this altitude and pressure. The viscosity depends on temperature only, but at 223.5 K = -50°C, it is off scale of Fig. A.3. Instead we need to use formulas as in Appendix A

At this altitude the density is (Table A.3)  $\rho = 0.02422 \times 1.225 \frac{\text{kg}}{\text{m}^3} \quad \rho = 0.0297 \frac{\text{kg}}{\text{m}^3}$

For  $\mu$  
$$\mu = \frac{b \cdot T^2}{1 + \frac{S}{T}} \quad \text{where} \quad b = 1.458 \times 10^{-6} \cdot \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^2} \quad S = 110.4 \cdot \text{K}$$

$$\mu = 1.459 \times 10^{-5} \frac{\text{kg}}{\text{m} \cdot \text{s}} \quad \mu = 1.459 \times 10^{-5} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$$

Hence 
$$x_{\text{trans}} = 1.459 \times 10^{-5} \cdot \frac{\text{kg}}{\text{m} \cdot \text{s}} \times 500000 \times \frac{1}{0.0297} \cdot \frac{\text{m}^3}{\text{kg}} \times \frac{1}{2700} \times \frac{1}{10^3} \cdot \frac{\text{hr}}{\text{m}} \times \frac{3600 \text{ s}}{1 \cdot \text{hr}} \quad x_{\text{trans}} = 0.327 \text{ m}$$

## Problem 2.89

[Difficulty: 2]

**2.89** SAE 30 oil at 100°C flows through a 12-mm-diameter stainless-steel tube. What is the specific gravity and specific weight of the oil? If the oil discharged from the tube fills a 100-mL graduated cylinder in 9 seconds, is the flow laminar or turbulent?

**Given:** Type of oil, flow rate, and tube geometry

**Find:** Whether flow is laminar or turbulent

**Solution:**

Data on SAE 30 oil SG or density is limited in the Appendix. We can Google it or use the following  $\nu = \frac{\mu}{\rho}$  so  $\rho = \frac{\mu}{\nu}$

At 100°C, from Figs. A.2 and A.3  $\mu = 9 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$   $\nu = 1 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$

$$\rho = 9 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times \frac{1}{1 \times 10^{-5} \frac{\text{m}^2}{\text{s}}} \times \frac{\text{kg}\cdot\text{m}}{\text{s}^2\cdot\text{N}} \quad \rho = 900 \frac{\text{kg}}{\text{m}^3}$$

Hence  $\text{SG} = \frac{\rho}{\rho_{\text{water}}}$   $\rho_{\text{water}} = 1000 \frac{\text{kg}}{\text{m}^3}$   $\text{SG} = 0.9$

The specific weight is  $\gamma = \rho \cdot g$   $\gamma = 900 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}}$   $\gamma = 8.829 \times 10^3 \frac{\text{N}}{\text{m}^3}$

For pipe flow (Section 2-6)  $Q = \frac{\pi \cdot D^2}{4} \cdot V$  so  $V = \frac{4 \cdot Q}{\pi \cdot D^2}$

$$Q = 100 \cdot \text{mL} \times \frac{10^{-6} \cdot \text{m}^3}{1 \cdot \text{mL}} \times \frac{1}{9} \frac{1}{\text{s}} \quad Q = 1.111 \times 10^{-5} \frac{\text{m}^3}{\text{s}}$$

Then  $V = \frac{4}{\pi} \times 1.11 \times 10^{-5} \frac{\text{m}^3}{\text{s}} \times \left( \frac{1}{12} \frac{1}{\text{mm}} \times \frac{1000 \cdot \text{mm}}{1 \cdot \text{m}} \right)^2$   $V = 0.0981 \frac{\text{m}}{\text{s}}$

Hence  $\text{Re} = \frac{\rho \cdot V \cdot D}{\mu}$

$$\text{Re} = 900 \frac{\text{kg}}{\text{m}^3} \times 0.0981 \frac{\text{m}}{\text{s}} \times 0.012 \cdot \text{m} \times \frac{1}{9 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{kg}\cdot\text{m}}} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} \quad \text{Re} = 118$$

Flow is laminar

## Problem 2.90

[Difficulty: 2]

**2.90** A seaplane is flying at 100 mph through air at 45°F. At what distance from the leading edge of the underside of the fuselage does the boundary layer transition to turbulence? How does this boundary layer transition change as the underside of the fuselage touches the water during landing? Assume the water temperature is also 45°F.

**Given:** Data on seaplane

**Find:** Transition point of boundary layer

**Solution:**

For boundary layer transition, from Section 2-6  $Re_{trans} = 500000$

Then 
$$Re_{trans} = \frac{\rho \cdot V \cdot x_{trans}}{\mu} = \frac{V \cdot x_{trans}}{\nu} \quad \text{so} \quad x_{trans} = \frac{\nu \cdot Re_{trans}}{V}$$

At 45°F = 7.2°C (Fig A.3) 
$$\nu = 0.8 \times 10^{-5} \frac{\text{m}^2}{\text{s}} \times \frac{10.8 \frac{\text{ft}^2}{\text{s}}}{1 \cdot \frac{\text{m}^2}{\text{s}}} \quad \nu = 8.64 \times 10^{-5} \frac{\text{ft}^2}{\text{s}}$$

$$x_{trans} = 8.64 \times 10^{-5} \frac{\text{ft}^2}{\text{s}} \cdot 500000 \times \frac{1}{100 \cdot \text{mph}} \times \frac{60 \cdot \text{mph}}{88 \frac{\text{ft}}{\text{s}}} \quad x_{trans} = 0.295 \cdot \text{ft}$$

As the seaplane touches down:

At 45°F = 7.2°C (Fig A.3) 
$$\nu = 1.5 \times 10^{-5} \frac{\text{m}^2}{\text{s}} \times \frac{10.8 \frac{\text{ft}^2}{\text{s}}}{1 \cdot \frac{\text{m}^2}{\text{s}}} \quad \nu = 1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}$$

$$x_{trans} = 1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \cdot 500000 \times \frac{1}{100 \cdot \text{mph}} \times \frac{60 \cdot \text{mph}}{88 \frac{\text{ft}}{\text{s}}} \quad x_{trans} = 0.552 \cdot \text{ft}$$

**Problem 2.91**

[Difficulty: 3]

**2.91** An airliner is cruising at an altitude of 5.5 km with a speed of 700 km/hr. As the airliner increases its altitude, it adjusts its speed so that the Mach number remains constant. Provide a sketch of speed vs. altitude. What is the speed of the airliner at an altitude of 8 km?

**Given:** Data on airliner  
**Find:** Sketch of speed versus altitude ( $M = \text{const}$ )

**Solution:**  
 Data on temperature versus height can be obtained from Table A.3

At 5.5 km the temperature is approximately 252 K

The speed of sound is obtained from  $c = \sqrt{k \cdot R \cdot T}$

where  $k = 1.4$   
 $R = 286.9 \text{ J/kg K}$  (Table A.6)  
 $c = 318 \text{ m/s}$

We also have  $V = 700 \text{ km/hr}$

or  $V = 194 \text{ m/s}$

Hence  $M = V/c$  or


$$M = 0.611$$

To compute  $V$  for constant  $M$ , we use  $V = M \cdot c = 0.611 c$

At a height of 8 km:  $V = 677 \text{ km/hr}$

NOTE: Realistically, the airplane will fly to a maximum height of about 10 km!

z (km)	T (K)	c (m/s)	V (km/hr)
4	262	325	713
5	259	322	709
5	256	320	704
6	249	316	695
7	243	312	686
8	236	308	677
9	230	304	668
10	223	299	658
11	217	295	649
12	217	295	649
13	217	295	649
14	217	295	649
15	217	295	649
16	217	295	649
17	217	295	649
18	217	295	649
19	217	295	649
20	217	295	649
22	219	296	651
24	221	298	654
26	223	299	657
28	225	300	660
30	227	302	663
40	250	317	697
50	271	330	725
60	256	321	705
70	220	297	653
80	181	269	592
90	181	269	592




## Problem 2.92

[Difficulty: 4]

2.92 How does an airplane wing develop lift?

**Open-Ended Problem Statement:** How does an airplane wing develop lift?

**Discussion:** The sketch shows the cross-section of a typical airplane wing. The airfoil section is rounded at the front, curved across the top, reaches maximum thickness about a third of the way back, and then tapers slowly to a fine trailing edge. The bottom of the airfoil section is relatively flat. (The discussion below also applies to a symmetric airfoil at an angle of incidence that produces lift.)



NACA 2412 Wing Section

It is both a popular expectation and an experimental fact that air flows more rapidly over the curved top surface of the airfoil section than along the relatively flat bottom. In the NCFMF video *Flow Visualization*, timelines placed in front of the airfoil indicate that fluid flows more rapidly along the top of the section than along the bottom.

In the absence of viscous effects (this is a valid assumption outside the boundary layers on the airfoil) pressure falls when flow speed increases. Thus the pressures on the top surface of the airfoil where flow speed is higher are lower than the pressures on the bottom surface where flow speed does not increase. (Actual pressure profiles measured for a lifting section are shown in the NCFMF video *Boundary Layer Control*.) The unbalanced pressures on the top and bottom surfaces of the airfoil section create a net force that tends to develop lift on the profile.

## Problem 3.1

[Difficulty: 2]

**3.1** Compressed nitrogen (140 lbm) is stored in a spherical tank of diameter  $D = 2.5$  ft at a temperature of  $77^\circ\text{F}$ . What is the pressure inside the tank? If the maximum allowable stress in the tank is 30 ksi, find the minimum theoretical wall thickness of the tank.

**Given:** Data on nitrogen tank

**Find:** Pressure of nitrogen; minimum required wall thickness

**Assumption:** Ideal gas behavior

**Solution:**

Ideal gas equation of state:  $p \cdot V = M \cdot R \cdot T$

where, from Table A.6, for nitrogen  $R = 55.16 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}}$

Then the pressure of nitrogen is  $p = \frac{M \cdot R \cdot T}{V} = M \cdot R \cdot T \cdot \left( \frac{6}{\pi \cdot D^3} \right)$

$$p = 140 \cdot \text{lbm} \times 55.16 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \times (77 + 460) \cdot \text{R} \times \left[ \frac{6}{\pi \times (2.5 \cdot \text{ft})^3} \right] \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2$$

$$p = 3520 \frac{\text{lb}_f}{\text{in}^2}$$

To determine wall thickness, consider a free body diagram for one hemisphere:


$$\Sigma F = 0 = p \cdot \frac{\pi \cdot D^2}{4} - \sigma_c \cdot \pi \cdot D \cdot t$$

where  $\sigma_c$  is the circumferential stress in the container

Then  $t = \frac{p \cdot \pi \cdot D^2}{4 \cdot \pi \cdot D \cdot \sigma_c} = \frac{p \cdot D}{4 \cdot \sigma_c}$

$$t = 3520 \frac{\text{lb}_f}{\text{in}^2} \times \frac{2.5 \cdot \text{ft}}{4} \times \frac{\text{in}^2}{30 \times 10^3 \cdot \text{lb}_f}$$

$$t = 0.0733 \cdot \text{ft} \qquad t = 0.880 \cdot \text{in}$$



## Problem 3.2

[Difficulty: 2]

**3.2** Because the pressure falls, water boils at a lower temperature with increasing altitude. Consequently, cake mixes and boiled eggs, among other foods, must be cooked different lengths of time. Determine the boiling temperature of water at 1000 and 2000 m elevation on a standard day, and compare with the sea-level value.

**Given:** Pure water on a standard day

**Find:** Boiling temperature at (a) 1000 m and (b) 2000 m, and compare with sea level value.

**Solution:**

We can determine the atmospheric pressure at the given altitudes from table A.3, Appendix A

The data are

Elevation (m)	$p/p_o$	$p$ (kPa)
0	1.000	101.3
1000	0.887	89.9
2000	0.785	79.5


We can also consult steam tables for the variation of saturation temperature with pressure:

$p$ (kPa)	$T_{sat}$ ( $^{\circ}\text{C}$ )
70	90.0
80	93.5
90	96.7
101.3	100.0

We can interpolate the data from the steam tables to correlate saturation temperature with altitude:

Elevation (m)	$p/p_o$	$p$ (kPa)	$T_{sat}$ ( $^{\circ}\text{C}$ )
0	1.000	101.3	100.0
1000	0.887	89.9	96.7
2000	0.785	79.5	93.3

The data are plotted here. They show that the saturation temperature drops approximately  $3.4^{\circ}\text{C}/1000$  m.



### Problem 3.3

[Difficulty: 2]

**3.3** Ear “popping” is an unpleasant phenomenon sometimes experienced when a change in pressure occurs, for example in a fast-moving elevator or in an airplane. If you are in a two-seater airplane at 3000 m and a descent of 100 m causes your ears to “pop,” what is the pressure change that your ears “pop” at, in millimeters of mercury? If the airplane now rises to 8000 m and again begins descending, how far will the airplane descend before your ears “pop” again? Assume a U.S. Standard Atmosphere.

**Given:** Data on flight of airplane

**Find:** Pressure change in mm Hg for ears to “pop”; descent distance from 8000 m to cause ears to “pop.”

#### Solution:

Assume the air density is approximately constant constant from 3000 m to 2900 m.  
From table A.3

$$\rho_{SL} = 1.225 \cdot \frac{\text{kg}}{\text{m}^3} \qquad \rho_{\text{air}} = 0.7423 \cdot \rho_{SL} \qquad \rho_{\text{air}} = 0.909 \frac{\text{kg}}{\text{m}^3}$$

We also have from the manometer equation, Eq. 3.7

$$\Delta p = -\rho_{\text{air}} \cdot g \cdot \Delta z \qquad \text{and also} \qquad \Delta p = -\rho_{\text{Hg}} \cdot g \cdot \Delta h_{\text{Hg}}$$

Combining  $\Delta h_{\text{Hg}} = \frac{\rho_{\text{air}}}{\rho_{\text{Hg}}} \cdot \Delta z = \frac{\rho_{\text{air}}}{SG_{\text{Hg}} \cdot \rho_{\text{H}_2\text{O}}} \cdot \Delta z$   $SG_{\text{Hg}} = 13.55$  from Table A.2

$$\Delta h_{\text{Hg}} = \frac{0.909}{13.55 \times 999} \times 100 \cdot \text{m} \qquad \Delta h_{\text{Hg}} = 6.72 \cdot \text{mm}$$

For the ear popping descending from 8000 m, again assume the air density is approximately constant constant, this time at 8000 m.  
From table A.3

$$\rho_{\text{air}} = 0.4292 \cdot \rho_{SL} \qquad \rho_{\text{air}} = 0.526 \frac{\text{kg}}{\text{m}^3}$$

We also have from the manometer equation

$$\rho_{\text{air}8000} \cdot g \cdot \Delta z_{8000} = \rho_{\text{air}3000} \cdot g \cdot \Delta z_{3000}$$

where the numerical subscripts refer to conditions at 3000m and 8000m.  
Hence

$$\Delta z_{8000} = \frac{\rho_{\text{air}3000} \cdot g}{\rho_{\text{air}8000} \cdot g} \cdot \Delta z_{3000} = \frac{\rho_{\text{air}3000}}{\rho_{\text{air}8000}} \cdot \Delta z_{3000} \qquad \Delta z_{8000} = \frac{0.909}{0.526} \times 100 \cdot \text{m} \qquad \Delta z_{8000} = 173 \text{ m}$$

## Problem 3.4

[Difficulty: 3]

**3.4** When you are on a mountain face and boil water, you notice that the water temperature is 195°F. What is your approximate altitude? The next day, you are at a location where it boils at 185°F. How high did you climb between the two days? Assume a U.S. Standard Atmosphere.

**Given:** Boiling points of water at different elevations

**Find:** Change in elevation

**Solution:**

From the steam tables, we have the following data for the boiling point (saturation temperature) of water

$T_{\text{sat}}$ (°F)	$p$ (psia)
195	10.39
185	8.39

The sea level pressure, from Table A.3, is


$$p_{\text{SL}} = 14.696 \text{ psia}$$

Hence

$T_{\text{sat}}$ (°F)	$p/p_{\text{SL}}$
195	0.707
185	0.571

From Table A.3

$p/p_{\text{SL}}$	Altitude (m)	Altitude (ft)
0.7372	2500	8203
0.6920	3000	9843
0.6492	3500	11484
0.6085	4000	13124
0.5700	4500	14765



Then, any one of a number of *Excel* functions can be used to interpolate (Here we use *Excel's* *Trendline* analysis)

$p/p_{\text{SL}}$	Altitude (ft)
0.707	9303
0.571	14640

Current altitude is approximately 9303 ft

The change in altitude is then 5337 ft

Alternatively, we can interpolate for each altitude by using a linear regression between adjacent data points

For

$p/p_{\text{SL}}$	Altitude (m)	Altitude (ft)
0.7372	2500	8203
0.6920	3000	9843

$p/p_{\text{SL}}$	Altitude (m)	Altitude (ft)
0.6085	4000	13124
0.5700	4500	14765

Then

0.7070	2834	9299
--------	------	------


0.5730	4461	14637
--------	------	-------

The change in altitude is then 5338 ft

## Problem 3.5

[Difficulty: 2]

**3.5** A 125-mL cube of solid oak is held submerged by a tether as shown. Calculate the actual force of the water on the bottom surface of the cube and the tension in the tether.



**Given:** Data on system

**Find:** Force on bottom of cube; tension in tether

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot h$  where  $h$  is measured downwards

The absolute pressure at the interface is  $p_{\text{interface}} = p_{\text{atm}} + SG_{\text{oil}} \cdot \rho \cdot g \cdot h_{\text{oil}}$

Then the pressure on the lower surface is  $p_L = p_{\text{interface}} + \rho \cdot g \cdot h_L = p_{\text{atm}} + \rho \cdot g \cdot (SG_{\text{oil}} \cdot h_{\text{oil}} + h_L)$

For the cube  $V = 125 \cdot \text{mL}$   $V = 1.25 \times 10^{-4} \cdot \text{m}^3$

Then the size of the cube is  $d = V^{\frac{1}{3}}$   $d = 0.05 \text{ m}$  and the depth in water to the upper surface is  $h_U = 0.3 \cdot \text{m}$

Hence  $h_L = h_U + d$   $h_L = 0.35 \text{ m}$  where  $h_L$  is the depth in water to the lower surface

The force on the lower surface is  $F_L = p_L \cdot A$  where  $A = d^2$   $A = 0.0025 \text{ m}^2$

$$F_L = [p_{\text{atm}} + \rho \cdot g \cdot (SG_{\text{oil}} \cdot h_{\text{oil}} + h_L)] \cdot A$$

$$F_L = \left[ 101 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} + 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (0.8 \times 0.5 \cdot \text{m} + 0.35 \cdot \text{m}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right] \times 0.0025 \cdot \text{m}^2$$

$$F_L = 270.894 \text{ N} \quad \text{Note: Extra decimals needed for computing T later!}$$

For the tension in the tether, an FBD gives  $\Sigma F_y = 0$   $F_L - F_U - W - T = 0$  or  $T = F_L - F_U - W$

$$\text{where } F_U = [p_{\text{atm}} + \rho \cdot g \cdot (SG_{\text{oil}} \cdot h_{\text{oil}} + h_U)] \cdot A$$

Note that we could instead compute

$$\Delta F = F_L - F_U = \rho \cdot g \cdot SG_{oil} \cdot (h_L - h_U) \cdot A \quad \text{and} \quad T = \Delta F - W$$

Using  $F_U$

$$F_U = \left[ 101 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} + 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (0.8 \times 0.5 \cdot \text{m} + 0.3 \cdot \text{m}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right] \times 0.0025 \cdot \text{m}^2$$

$$F_U = 269.668 \text{ N}$$

Note: Extra decimals needed for computing T later!

For the oak block (Table A.1)

$$SG_{oak} = 0.77 \quad \text{so} \quad W = SG_{oak} \cdot \rho \cdot g \cdot V$$


$$W = 0.77 \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1.25 \times 10^{-4} \cdot \text{m}^3 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad W = 0.944 \text{ N}$$

$$T = F_L - F_U - W \quad T = 0.282 \text{ N}$$

### Problem 3.6

[Difficulty: 2]

3.6 The tube shown is filled with mercury at 20°C. Calculate the force applied to the piston.



**Given:** Data on system before and after applied force

**Find:** Applied force

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $p = p_{atm} - \rho \cdot g \cdot (y - y_0)$  with  $p(y_0) = p_{atm}$

For initial state  $p_1 = p_{atm} + \rho \cdot g \cdot h$  and  $F_1 = p_1 \cdot A = \rho \cdot g \cdot h \cdot A$  (Gage;  $F_1$  is hydrostatic upwards force)

For the initial FBD  $\Sigma F_y = 0$   $F_1 - W = 0$   $W = F_1 = \rho \cdot g \cdot h \cdot A$

For final state  $p_2 = p_{atm} + \rho \cdot g \cdot H$  and  $F_2 = p_2 \cdot A = \rho \cdot g \cdot H \cdot A$  (Gage;  $F_2$  is hydrostatic upwards force)

For the final FBD  $\Sigma F_y = 0$   $F_2 - W - F = 0$   $F = F_2 - W = \rho \cdot g \cdot H \cdot A - \rho \cdot g \cdot h \cdot A = \rho \cdot g \cdot A \cdot (H - h)$

$$F = \rho_{H_2O} \cdot SG \cdot g \cdot \frac{\pi \cdot D^2}{4} \cdot (H - h)$$

From Fig. A.1  $SG = 13.54$

$$F = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 13.54 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\pi}{4} \times (0.05 \cdot \text{m})^2 \times (0.2 - 0.025) \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$F = 45.6 \text{ N}$$

### Problem 3.7

[Difficulty: 1]

**3.7** The following pressure and temperature measurements were taken by a meteorological balloon rising through the lower atmosphere:

$p$ (psia)	14.71	14.62	14.53	14.45	14.36	14.27	14.18	14.1	14.01	13.92	13.84
$T$ (°F)	53.6	52	50.9	50.4	50.2	50	50.5	51.4	52.9	54	53.8

The initial values (top of table) correspond to ground level. Using the ideal gas law ( $p = \rho RT$  with  $R = 53.3 \text{ ft} \cdot \text{lb}/\text{lbm} \cdot ^\circ\text{R}$ ), compute and plot the variation of air density (in  $\text{lbm}/\text{ft}^3$ ) with height.

**Given:** Pressure and temperature data from balloon


**Find:** Plot density change as a function of elevation

**Assumption:** Ideal gas behavior

**Solution:**

Using the ideal gas equation,  $\rho = p/RT$

$p$ (psia)	$T$ (°F)	$\rho$ ( $\text{lbm}/\text{ft}^3$ )
14.71	53.6	0.07736
14.62	52.0	0.07715
14.53	50.9	0.07685
14.45	50.4	0.07647
14.36	50.2	0.07604
14.27	50.0	0.07560
14.18	50.5	0.07506
14.10	51.4	0.07447
14.01	52.9	0.07380
13.92	54.0	0.07319
13.84	53.8	0.07276



## Problem 3.8

[Difficulty: 2]

**3.8** A hollow metal cube with sides 100 mm floats at the interface between a layer of water and a layer of SAE 10W oil such that 10% of the cube is exposed to the oil. What is the pressure difference between the upper and lower horizontal surfaces? What is the average density of the cube?

**Given:** Properties of a cube floating at an interface

**Find:** The pressures difference between the upper and lower surfaces; average cube density

**Solution:**

The pressure difference is obtained from two applications of Eq. 3.7

$$p_U = p_0 + \rho_{\text{SAE10}} \cdot g \cdot (H - 0.1 \cdot d)$$

$$p_L = p_0 + \rho_{\text{SAE10}} \cdot g \cdot H + \rho_{\text{H}_2\text{O}} \cdot g \cdot 0.9 \cdot d$$

where  $p_U$  and  $p_L$  are the upper and lower pressures,  $p_0$  is the oil free surface pressure,  $H$  is the depth of the interface, and  $d$  is the cube size

Hence the pressure difference is

$$\Delta p = p_L - p_U = \rho_{\text{H}_2\text{O}} \cdot g \cdot 0.9 \cdot d + \rho_{\text{SAE10}} \cdot g \cdot 0.1 \cdot d$$

$$\Delta p = \rho_{\text{H}_2\text{O}} \cdot g \cdot d \cdot (0.9 + SG_{\text{SAE10}} \cdot 0.1)$$

From Table A.2  $SG_{\text{SAE10}} = 0.92$

$$\Delta p = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.1 \cdot \text{m} \times (0.9 + 0.92 \times 0.1) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \Delta p = 972 \text{ Pa}$$

For the cube density, set up a free body force balance for the cube

$$\Sigma F = 0 = \Delta p \cdot A - W$$

Hence

$$W = \Delta p \cdot A = \Delta p \cdot d^2$$

$$\rho_{\text{cube}} = \frac{m}{d^3} = \frac{W}{d^3 \cdot g} = \frac{\Delta p \cdot d^2}{d^3 \cdot g} = \frac{\Delta p}{d \cdot g}$$

$$\rho_{\text{cube}} = 972 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{0.1 \cdot \text{m}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad \rho_{\text{cube}} = 991 \frac{\text{kg}}{\text{m}^3}$$

## Problem 3.9

[Difficulty: 2]

**3.9** Your pressure gage indicates that the pressure in your cold tires is 0.25 MPa (gage) on a mountain at an elevation of 3500 m. What is the absolute pressure? After you drive down to sea level, your tires have warmed to 25°C. What pressure does your gage now indicate? Assume a U.S. Standard Atmosphere.

**Given:** Data on tire at 3500 m and at sea level

**Find:** Absolute pressure at 3500 m; pressure at sea level

**Solution:**

At an elevation of 3500 m, from Table A.3:

$$p_{\text{SL}} = 101 \cdot \text{kPa} \quad p_{\text{atm}} = 0.6492 \cdot p_{\text{SL}} \quad p_{\text{atm}} = 65.6 \cdot \text{kPa}$$

and we have

$$p_{\text{g}} = 0.25 \cdot \text{MPa} \quad p_{\text{g}} = 250 \cdot \text{kPa} \quad p = p_{\text{g}} + p_{\text{atm}} \quad p = 316 \cdot \text{kPa}$$

At sea level

$$p_{\text{atm}} = 101 \cdot \text{kPa}$$

Meanwhile, the tire has warmed up, from the ambient temperature at 3500 m, to 25°C.

At an elevation of 3500 m, from Table A.3

$$T_{\text{cold}} = 265.4 \cdot \text{K} \quad \text{and} \quad T_{\text{hot}} = (25 + 273) \cdot \text{K} \quad T_{\text{hot}} = 298 \text{ K}$$

Hence, assuming ideal gas behavior,  $pV = mRT$ , and that the tire is approximately a rigid container, the absolute pressure of the hot tire is

$$p_{\text{hot}} = \frac{T_{\text{hot}}}{T_{\text{cold}}} \cdot p \quad p_{\text{hot}} = 354 \cdot \text{kPa}$$

Then the gage pressure is

$$p_{\text{g}} = p_{\text{hot}} - p_{\text{atm}} \quad p_{\text{g}} = 253 \cdot \text{kPa}$$

## Problem 3.10

[Difficulty: 2]

**3.10** An air bubble, 0.3 in. in diameter, is released from the regulator of a scuba diver swimming 100 ft below the sea surface. (The water temperature is 86°F.) Estimate the diameter of the bubble just before it reaches the water surface.

**Given:** Data on air bubble

**Find:** Bubble diameter as it reaches surface

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho_{\text{sea}} \cdot g$  and the ideal gas equation  $p = \rho \cdot R \cdot T = \frac{M}{V} \cdot R \cdot T$

We assume the temperature is constant, and the density of sea water is constant

For constant sea water density  $p = p_{\text{atm}} + SG_{\text{sea}} \cdot \rho \cdot g \cdot h$  where  $p$  is the pressure at any depth  $h$

Then the pressure at the initial depth is  $p_1 = p_{\text{atm}} + SG_{\text{sea}} \cdot \rho \cdot g \cdot h_1$

The pressure as it reaches the surface is  $p_2 = p_{\text{atm}}$

For the bubble  $p = \frac{M \cdot R \cdot T}{V}$  but  $M$  and  $T$  are constant  $M \cdot R \cdot T = \text{const} = p \cdot V$

Hence  $p_1 \cdot V_1 = p_2 \cdot V_2$  or  $V_2 = V_1 \cdot \frac{p_1}{p_2}$  or  $D_2^3 = D_1^3 \cdot \frac{p_1}{p_2}$

Then the size of the bubble at the surface is  $D_2 = D_1 \cdot \left(\frac{p_1}{p_2}\right)^{\frac{1}{3}} = D_1 \cdot \left[\frac{(p_{\text{atm}} + \rho_{\text{sea}} \cdot g \cdot h_1)}{p_{\text{atm}}}\right]^{\frac{1}{3}} = D_1 \cdot \left(1 + \frac{\rho_{\text{sea}} \cdot g \cdot h_1}{p_{\text{atm}}}\right)^{\frac{1}{3}}$

From Table A.2  $SG_{\text{sea}} = 1.025$  (This is at 68°F)

$$D_2 = 0.3 \cdot \text{in} \times \left[ 1 + 1.025 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \times \frac{\text{ft}}{\text{s}^2} \times 100 \cdot \text{ft} \times \frac{\text{in}^2}{14.7 \cdot \text{lbf}} \times \left(\frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \right]^{\frac{1}{3}}$$

$$D_2 = 0.477 \cdot \text{in}$$

## Problem 3.11

[Difficulty: 2]

**3.11** A cube with 6 in. sides is suspended in a fluid by a wire. The top of the cube is horizontal and 8 in. below the free surface. If the cube has a mass of 2 slugs and the tension in the wire is  $T = 50.7$  lbf, compute the fluid specific gravity, and from this determine the fluid. What are the gage pressures on the upper and lower surfaces?

**Given:** Properties of a cube suspended by a wire in a fluid

**Find:** The fluid specific gravity; the gage pressures on the upper and lower surfaces

**Solution:**

From a free body analysis of the cube:  $\Sigma F = 0 = T + (p_L - p_U) \cdot d^2 - M \cdot g$

where  $M$  and  $d$  are the cube mass and size and  $p_L$  and  $p_U$  are the pressures on the lower and upper surfaces

For each pressure we can use Eq. 3.7  $p = p_0 + \rho \cdot g \cdot h$

Hence 
$$p_L - p_U = [p_0 + \rho \cdot g \cdot (H + d)] - (p_0 + \rho \cdot g \cdot H) = \rho \cdot g \cdot d = SG \cdot \rho_{H_2O} \cdot d$$

where  $H$  is the depth of the upper surface

Hence the force balance gives 
$$SG = \frac{M \cdot g - T}{\rho_{H_2O} \cdot g \cdot d^3} \quad SG = \frac{2 \cdot \text{slug} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} - 50.7 \cdot \text{lbf}}{1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times (0.5 \cdot \text{ft})^3} \quad SG = 1.75$$

From Table A.1, the fluid is Meriam blue.

The individual pressures are computed from Eq 3.7

$$p = p_0 + \rho \cdot g \cdot h \quad \text{or} \quad p_g = \rho \cdot g \cdot h = SG \cdot \rho_{H_2O} \cdot h$$

For the upper surface 
$$p_g = 1.754 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{2}{3} \cdot \text{ft} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_g = 0.507 \cdot \text{psi}$$

For the lower surface 
$$p_g = 1.754 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \left( \frac{2}{3} + \frac{1}{2} \right) \cdot \text{ft} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_g = 0.888 \cdot \text{psi}$$

Note that the SG calculation can also be performed using a buoyancy approach (discussed later in the chapter):

Consider a free body diagram of the cube:  $\Sigma F = 0 = T + F_B - M \cdot g$

where  $M$  is the cube mass and  $F_B$  is the buoyancy force 
$$F_B = SG \cdot \rho_{H_2O} \cdot L^3 \cdot g$$

Hence 
$$T + SG \cdot \rho_{H_2O} \cdot L^3 \cdot g - M \cdot g = 0 \quad \text{or} \quad SG = \frac{M \cdot g - T}{\rho_{H_2O} \cdot g \cdot L^3} \quad \text{as before} \quad SG = 1.75$$

## Problem 3.12

[Difficulty: 4]

**3.12** Assuming the bulk modulus is constant for seawater, derive an expression for the density variation with depth,  $h$ , below the surface. Show that the result may be written

$$\rho \approx \rho_0 + bh$$

where  $\rho_0$  is the density at the surface. Evaluate the constant  $b$ . Then, using the approximation, obtain an equation for the variation of pressure with depth below the surface. Determine the depth in feet at which the error in pressure predicted by the approximate solution is 0.01 percent.

**Given:** Model behavior of seawater by assuming constant bulk modulus

- Find:**
- Expression for density as a function of depth  $h$ .
  - Show that result may be written as  $\rho = \rho_0 + bh$
  - Evaluate the constant  $b$
  - Use results of (b) to obtain equation for  $p(h)$
  - Determine depth at which error in predicted pressure is 0.01%

**Solution:** From Table A.2, App. A:  $SG_O = 1.025$   $E_V = 2.42 \cdot \text{GPa} = 3.51 \times 10^5 \cdot \text{psi}$

**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure -  $h$  is positive downwards)

$$E_V = \frac{dp}{\frac{d\rho}{\rho}} \quad \text{(Definition of Bulk Modulus)}$$

Then  $dp = \rho \cdot g \cdot dh = E_V \cdot \frac{d\rho}{\rho}$  or  $\frac{d\rho}{\rho^2} = \frac{g}{E_V} dh$  Now if we integrate:  $\int_{\rho_0}^{\rho} \frac{1}{\rho^2} d\rho = \int_0^h \frac{g}{E_V} dh$

After integrating:  $\frac{\rho - \rho_0}{\rho \cdot \rho_0} = \frac{g \cdot h}{E_V}$  Therefore:  $\rho = \frac{E_V \cdot \rho_0}{E_V - g \cdot h \cdot \rho_0}$  and  $\frac{\rho}{\rho_0} = \frac{1}{1 - \frac{\rho_0 \cdot g \cdot h}{E_V}}$

Now for  $\frac{\rho_0 \cdot g \cdot h}{E_V} \ll 1$ , the binomial expansion may be used to approximate the density:  $\frac{\rho}{\rho_0} = 1 + \frac{\rho_0 \cdot g \cdot h}{E_V}$  (Binomial expansion may be found in a host of sources, e.g. *CRC Handbook of Mathematics*)

In other words,  $\rho = \rho_0 + b \cdot h$  where  $b = \frac{\rho_0^2 \cdot g}{E_V}$

Since  $dp = \rho \cdot g \cdot dh$  then an approximate expression for the pressure as a function of depth is:

$$p_{\text{approx}} - p_{\text{atm}} = \int_0^h (\rho_0 + b \cdot h) \cdot g \cdot dh \rightarrow p_{\text{approx}} - p_{\text{atm}} = \frac{g \cdot h \cdot (2 \cdot \rho_0 + b \cdot h)}{2} \quad \text{Solving for } p_{\text{approx}} \text{ we get:}$$

$$P_{\text{approx}} = P_{\text{atm}} + \frac{g \cdot h \cdot (2 \cdot \rho_0 + b \cdot h)}{2} = P_{\text{atm}} + \rho_0 \cdot g \cdot h + \frac{b \cdot g \cdot h^2}{2} = P_{\text{atm}} + \left( \rho_0 \cdot h + \frac{b \cdot h^2}{2} \right) \cdot g$$

Now if we substitute in the expression for b and simplify, we get:

$$P_{\text{approx}} = P_{\text{atm}} + \left( \rho_0 \cdot h + \frac{\rho_0 \cdot g \cdot h^2}{E_v} \cdot \frac{h^2}{2} \right) \cdot g = P_{\text{atm}} + \rho_0 \cdot g \cdot h \cdot \left( 1 + \frac{\rho_0 \cdot g \cdot h}{2 \cdot E_v} \right) \quad P_{\text{approx}} = P_{\text{atm}} + \rho_0 \cdot g \cdot h \cdot \left( 1 + \frac{\rho_0 \cdot g \cdot h}{2 E_v} \right)$$

The exact solution for p(h) is obtained by utilizing the exact solution for ρ(h). Thus:

$$P_{\text{exact}} - P_{\text{atm}} = \int_{\rho_0}^{\rho} \frac{E_v}{\rho} d\rho = E_v \cdot \ln\left(\frac{\rho}{\rho_0}\right) \quad \text{Substituting for } \frac{\rho}{\rho_0} \text{ we get:} \quad P_{\text{exact}} = P_{\text{atm}} + E_v \cdot \ln\left(1 - \frac{\rho_0 \cdot g \cdot h}{E_v}\right)^{-1}$$

$$\text{If we let } x = \frac{\rho_0 \cdot g \cdot h}{E_v} \text{ For the error to be 0.01\%: } \frac{\Delta P_{\text{exact}} - \Delta P_{\text{approx}}}{\Delta P_{\text{exact}}} = 1 - \frac{\rho_0 \cdot g \cdot h \cdot \left(1 + \frac{x}{2}\right)}{E_v \cdot \ln\left[(1-x)^{-1}\right]} = 1 - \frac{x \cdot \left(1 + \frac{x}{2}\right)}{\ln\left[(1-x)^{-1}\right]} = 0.0001$$

This equation requires an iterative solution, e.g. Excel's Goal Seek. The result is:  $x = 0.01728$  Solving x for h:

$$h = \frac{x \cdot E_v}{\rho_0 \cdot g} \quad h = 0.01728 \times 3.51 \times 10^5 \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{\text{ft}^3}{1.025 \times 1.94 \cdot \text{slug}} \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \times \left(\frac{12 \cdot \text{in}}{\text{ft}}\right)^2 \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} \quad h = 1.364 \times 10^4 \cdot \text{ft}$$

This depth is over 2.5 miles, so the incompressible fluid approximation is a reasonable one at all but the lowest depths of the ocean.

## Problem 3.13

[Difficulty: 3]

**3.13** Oceanographic research vessels have descended to 6.5 mi below sea level. At these extreme depths, the compressibility of seawater can be significant. One may model the behavior of seawater by assuming that its bulk modulus remains constant. Using this assumption, evaluate the deviations in density and pressure compared with values computed using the incompressible assumption at a depth,  $h$ , of 6.5 mi in seawater. Express your answers as a percentage. Plot the results over the range  $0 \leq h \leq 7$  mi.

**Given:** Model behavior of seawater by assuming constant bulk modulus

**Find:** The percent deviations in (a) density and (b) pressure at depth  $h = 6.5$  mi, as compared to values assuming constant density. Plot results over the range of 0 mi - 7 mi.

**Solution:** From Table A.2, App. A:  $SG_O = 1.025$   $E_V = 2.42 \cdot \text{GPa} = 3.51 \times 10^5 \cdot \text{psi}$   $h = 6.5 \cdot \text{mi}$

**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure -  $h$  is positive downwards)

$$E_V = \frac{dp}{\frac{d\rho}{\rho}} \quad (\text{Definition of Bulk Modulus})$$

Then  $dp = \rho \cdot g \cdot dh = E_V \cdot \frac{d\rho}{\rho}$  or  $\frac{d\rho}{\rho} = \frac{g}{E_V} \cdot dh$  Now if we integrate:  $\int_{\rho_0}^{\rho} \frac{1}{\rho^2} d\rho = \int_0^h \frac{g}{E_V} dh$

After integrating:  $\frac{\rho - \rho_0}{\rho \cdot \rho_0} = \frac{g \cdot h}{E_V}$  Therefore:  $\rho = \frac{E_V \cdot \rho_0}{E_V - \rho_0 \cdot g \cdot h}$  and  $\frac{\rho}{\rho_0} = \frac{1}{1 - \frac{\rho_0 \cdot g \cdot h}{E_V}}$

$$\frac{\Delta\rho}{\rho_0} = \frac{\rho - \rho_0}{\rho_0} = \frac{\rho}{\rho_0} - 1 = \frac{1}{1 - \frac{\rho_0 \cdot g \cdot h}{E_V}} - 1 = \frac{1 - \left(1 - \frac{\rho_0 \cdot g \cdot h}{E_V}\right)}{1 - \frac{\rho_0 \cdot g \cdot h}{E_V}} = \frac{\frac{\rho_0 \cdot g \cdot h}{E_V}}{1 - \frac{\rho_0 \cdot g \cdot h}{E_V}} \quad \frac{\Delta\rho}{\rho_0} = \frac{\frac{\rho_0 \cdot g \cdot h}{E_V}}{1 - \frac{\rho_0 \cdot g \cdot h}{E_V}}$$

To determine an expression for the percent deviation in pressure, we find  $p - p_{atm}$  for variable  $\rho$ , and then for constant  $\rho$ .

For variable density and constant bulk modulus:  $p - p_{atm} = \int_{\rho_0}^{\rho} \frac{E_V}{\rho} d\rho = E_V \cdot \ln\left(\frac{\rho}{\rho_0}\right)$

For constant density:  $p_{const\rho} - p_{atm} = \int_0^h \rho_0 g dh = \rho_0 \cdot g \cdot h$

$$\frac{\Delta p}{p_{\text{constp}}} = \frac{p - p_{\text{constp}}}{p_{\text{constp}}} = \frac{E_v \cdot \ln\left(\frac{\rho}{\rho_0}\right) - \rho_0 \cdot g \cdot h}{\rho_0 \cdot g \cdot h} = \frac{E_v}{\rho_0 \cdot g \cdot h} \cdot \ln\left(\frac{\rho}{\rho_0}\right) - 1 \qquad \frac{\Delta p}{p_{\text{constp}}} = \frac{E_v}{\rho_0 \cdot g \cdot h} \cdot \ln\left[\left(1 - \frac{\rho_0 \cdot g \cdot h}{E_v}\right)^{-1}\right] - 1$$

If we let  $x = \frac{E_v}{\rho_0 \cdot g}$   $x = 3.51 \times 10^5 \frac{\text{lbf}}{\text{in}^2} \times \frac{1}{1.025} \times \frac{1}{1.94} \frac{\text{ft}^3}{\text{slug}} \times \frac{1}{32.2} \frac{\text{s}^2}{\text{ft}} \times \left(\frac{12 \cdot \text{in}}{\text{ft}}\right)^2 \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} \times \frac{\text{mi}}{5280 \cdot \text{ft}}$   $x = 149.5 \cdot \text{mi}$

Substituting into the expressions for the deviations we get:

$$\text{dev}_\rho = \frac{\Delta \rho}{\rho_0} = \frac{\frac{h}{x}}{1 - \frac{h}{x}} = \frac{h}{x - h} = \frac{h}{149.5 \cdot \text{mi} - h}$$


$$\text{dev}_p = \frac{\Delta p}{p_{\text{constp}}} = \frac{x}{h} \cdot \ln\left[\left(1 - \frac{h}{x}\right)^{-1}\right] - 1 = \frac{149.5 \cdot \text{mi}}{h} \cdot \ln\left[\left(1 - \frac{h}{149.5 \cdot \text{mi}}\right)^{-1}\right] - 1$$

For  $h = 6.5 \text{ mi}$  we get:

$$\text{dev}_\rho = 4.55\%$$

$$\text{dev}_p = 2.24\%$$

The plot below shows the deviations in density and pressure as a function of depth from 0 mi to 7 mi:



## Problem 3.14


[Difficulty: 3]

**3.14** An inverted cylindrical container is lowered slowly beneath the surface of a pool of water. Air trapped in the container is compressed isothermally as the hydrostatic pressure increases. Develop an expression for the water height,  $y$ , inside the container in terms of the container height,  $H$ , and depth of submersion,  $h$ . Plot  $y/H$  versus  $h/H$ .

**Given:** Cylindrical cup lowered slowly beneath pool surface

**Find:** Expression for  $y$  in terms of  $h$  and  $H$ .  
Plot  $y/H$  vs.  $h/H$ .

**Solution:**



**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure -  $h$  is positive downwards)

$$p \cdot V = M \cdot R \cdot T \quad (\text{Ideal Gas Equation})$$

**Assumptions:**

- (1) Constant temperature compression of air inside cup
- (2) Static liquid
- (3) Incompressible liquid

First we apply the ideal gas equation (at constant temperature) for the pressure of the air in the cup:  $p \cdot V = \text{constant}$

$$\text{Therefore: } p \cdot V = p_a \cdot \frac{\pi}{4} \cdot D^2 \cdot H = p \cdot \frac{\pi}{4} \cdot D^2 \cdot (H - y) \quad \text{and upon simplification: } p_a \cdot H = p \cdot (H - y)$$

Now we look at the hydrostatic pressure equation for the pressure exerted by the water. Since  $\rho$  is constant, we integrate:

$$p - p_a = \rho \cdot g \cdot (h - y) \quad \text{at the water-air interface in the cup.}$$

Since the cup is submerged to a depth of  $h$ , these pressures must be equal:

$$p_a \cdot H = [p_a + \rho \cdot g \cdot (h - y)] \cdot (H - y) = p_a \cdot H - p_a \cdot y + \rho \cdot g \cdot (h - y) \cdot (H - y)$$

Expanding out the right hand side of this expression:

$$0 = -p_a \cdot y + \rho \cdot g \cdot (h - y) \cdot (H - y) = \rho \cdot g \cdot h \cdot H - \rho \cdot g \cdot h \cdot y - \rho \cdot g \cdot H \cdot y + \rho \cdot g \cdot y^2 - p_a \cdot y$$

$$\rho \cdot g \cdot y^2 - [p_a + \rho \cdot g \cdot (h + H)] \cdot y + \rho \cdot g \cdot h \cdot H = 0 \quad y^2 - \left[ \frac{p_a}{\rho \cdot g} + (h + H) \right] \cdot y + h \cdot H = 0$$

$$\text{We now use the quadratic equation: } y = \frac{\left[ \frac{p_a}{\rho \cdot g} + (h + H) \right] - \sqrt{\left[ \frac{p_a}{\rho \cdot g} + (h + H) \right]^2 - 4 \cdot h \cdot H}}{2}$$

we only use the minus sign because  $y$  can never be larger than  $H$ .


Now if we divide both sides by H, we get an expression for y/H:

$$\frac{y}{H} = \frac{\left(\frac{p_a}{\rho \cdot g \cdot H} + \frac{h}{H} + 1\right) - \sqrt{\left(\frac{p_a}{\rho \cdot g \cdot H} + \frac{h}{H} + 1\right)^2 - 4 \cdot \frac{h}{H}}}{2}$$

The exact shape of this curve will depend upon the height of the cup. The plot below was generated assuming:

$$p_a = 101.3 \cdot \text{kPa}$$

$$H = 1 \cdot \text{m}$$



## Problem 3.15

[Difficulty: 1]

**3.15** You close the top of your straw with your thumb and lift the straw out of your glass containing Coke. Holding it vertically, the total length of the straw is 45 cm, but the Coke held in the straw is in the bottom 15 cm. What is the pressure in the straw just below your thumb? Ignore any surface tension effects.

**Given:** Geometry of straw

**Find:** Pressure just below the thumb

**Assumptions:** (1) Coke is incompressible  
(2) Pressure variation within the air column is negligible  
(3) Coke has density of water

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot h$  where h is measured downwards

This equation only applies in the 15 cm of coke in the straw - in the other 30 cm of air the pressure is essentially constant.

The gage pressure at the coke surface is  $p_{\text{coke}} = \rho \cdot g \cdot h_{\text{coke}}$

Hence, with  $h_{\text{coke}} = -15 \cdot \text{cm}$  because h is measured downwards

$$p_{\text{coke}} = -1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 15 \cdot \text{cm} \times \frac{\text{m}}{100 \cdot \text{cm}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times \frac{\text{kPa} \cdot \text{m}^2}{1000 \cdot \text{N}}$$

$$p_{\text{coke}} = -1.471 \cdot \text{kPa} \quad \text{gage}$$

$$p_{\text{coke}} = 99.9 \cdot \text{kPa}$$

## Problem 3.16

[Difficulty: 2]


**3.16** A water tank filled with water to a depth of 16 ft has an inspection cover (1 in. × 1 in.) at its base, held in place by a plastic bracket. The bracket can hold a load of 9 lbf. Is the bracket strong enough? If it is, what would the water depth have to be to cause the bracket to break?

**Given:** Data on water tank and inspection cover

**Find:** If the support bracket is strong enough; at what water depth would it fail

**Assumptions:** Water is incompressible and static

**Solution:**



Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot h$  where  $h$  is measured downwards

The absolute pressure at the base is  $p_{\text{base}} = p_{\text{atm}} + \rho \cdot g \cdot h$  where  $h = 16 \cdot \text{ft}$

The gage pressure at the base is  $p_{\text{base}} = \rho \cdot g \cdot h$  This is the pressure to use as we have  $p_{\text{atm}}$  on the outside of the cover.

The force on the inspection cover is  $F = p_{\text{base}} \cdot A$  where  $A = 1 \cdot \text{in} \times 1 \cdot \text{in}$   $A = 1 \cdot \text{in}^2$

$$F = \rho \cdot g \cdot h \cdot A$$

$$F = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 16 \cdot \text{ft} \times 1 \cdot \text{in}^2 \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$F = 6.94 \cdot \text{lbf}$$

The bracket is strong enough (it can take 9 lbf).

To find the maximum depth we start with  $F = 9.00 \cdot \text{lbf}$

$$h = \frac{F}{\rho \cdot g \cdot A}$$


$$h = 9 \cdot \text{lbf} \times \frac{1}{1.94 \cdot \text{slug}} \cdot \frac{\text{ft}^3}{\text{slug}} \times \frac{1}{32.2 \cdot \text{ft}} \cdot \frac{\text{s}^2}{\text{ft}} \times \frac{1}{\text{in}^2} \times \left( \frac{12 \cdot \text{in}}{\text{ft}} \right)^2 \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2}$$

$$h = 20.7 \cdot \text{ft}$$

### Problem 3.17

[Difficulty: 4]

**3.17** A container with two circular vertical tubes of diameters  $d_1 = 39.5$  mm and  $d_2 = 12.7$  mm is partially filled with mercury. The equilibrium level of the liquid is shown in the left diagram. A cylindrical object made from solid brass is placed in the larger tube so that it floats, as shown in the right diagram. The object is  $D = 37.5$  mm in diameter and  $H = 76.2$  mm high. Calculate the pressure at the lower surface needed to float the object. Determine the new equilibrium level,  $h$ , of the mercury with the brass cylinder in place.



**Given:** Container of mercury with vertical tubes of known diameter, brass cylinder of known dimensions introduced into larger tube, where it floats.

$$d_1 = 39.5 \cdot \text{mm} \quad d_2 = 12.7 \cdot \text{mm} \quad D = 37.5 \cdot \text{mm} \quad H = 76.2 \cdot \text{mm} \quad SG_{\text{Hg}} = 13.55 \quad SG_{\text{b}} = 8.55$$

**Find:** (a) Pressure on the bottom of the cylinder  
(b) New equilibrium level,  $h$ , of the mercury

**Solution:** We will analyze a free body diagram of the cylinder, and apply the hydrostatics equation.


**Governing equations:**  $\Sigma F_z = 0$  (Vertical Equilibrium)  
 $\frac{dp}{dz} = -\rho \cdot g$  (Hydrostatic Pressure -  $z$  is positive upwards)  
 $\rho = SG \cdot \rho_{\text{water}}$  (Definition of Specific Gravity)

**Assumptions:** (1) Static liquid  
(2) Incompressible liquid

If we take a free body diagram of the cylinder:

$$\Sigma F_z = p \cdot \frac{\pi}{4} \cdot D^2 - \rho_{\text{b}} \cdot g \cdot \frac{\pi}{4} \cdot D^2 \cdot H = 0 \quad \text{thus: } p = \rho_{\text{b}} \cdot g \cdot H = SG_{\text{b}} \cdot \rho_{\text{water}} \cdot g \cdot H$$

$$p = 8.55 \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 76.2 \cdot \text{mm} \times \frac{\text{m}}{10^3 \cdot \text{mm}} \quad p = 6.39 \cdot \text{kPa} \quad (\text{gage})$$



This pressure must be generated by a column of mercury  $h+x$  in height. Thus:

$$p = \rho_{\text{Hg}} \cdot g \cdot (h+x) = SG_{\text{Hg}} \cdot \rho_{\text{water}} \cdot g \cdot (h+x) = SG_{\text{b}} \cdot \rho_{\text{water}} \cdot g \cdot H \quad \text{Thus: } h+x = \frac{SG_{\text{b}}}{SG_{\text{Hg}}} \cdot H$$

The value of  $x$  can be found by realizing that the volume of mercury in the system remains constant. Therefore:

$$\frac{\pi}{4} \cdot D^2 \cdot x = \frac{\pi}{4} \cdot (d_1^2 - D^2) \cdot h + \frac{\pi}{4} \cdot d_2^2 \cdot h \quad \text{Now if we solve for } x: \quad x = \left[ \left( \frac{d_1}{D} \right)^2 - 1 + \left( \frac{d_2}{D} \right)^2 \right] \cdot h$$


These expressions now allow us to solve for  $h$ :  $h = \frac{SG_{\text{b}}}{SG_{\text{Hg}}} \cdot \frac{D^2}{d_1^2 + d_2^2} \cdot H$  Substituting in values:

$$h = \frac{8.55}{13.55} \times \frac{(37.5 \cdot \text{mm})^2}{(39.5 \cdot \text{mm})^2 + (12.7 \cdot \text{mm})^2} \times 76.2 \cdot \text{mm} \quad h = 39.3 \cdot \text{mm}$$

### Problem 3.18

[Difficulty: 2]

**3.18** A partitioned tank as shown contains water and mercury. What is the gage pressure in the air trapped in the left chamber? What pressure would the air on the left need to be pumped to in order to bring the water and mercury free surfaces level?



**Given:** Data on partitioned tank

**Find:** Gage pressure of trapped air; pressure to make water and mercury levels equal

**Solution:**

The pressure difference is obtained from repeated application of Eq. 3.7, or in other words, from Eq. 3.8. Starting from the right air chamber

$$p_{\text{gage}} = SG_{\text{Hg}} \times \rho_{\text{H}_2\text{O}} \times g \times (3 \cdot \text{m} - 2.9 \cdot \text{m}) - \rho_{\text{H}_2\text{O}} \times g \times 1 \cdot \text{m}$$

$$p_{\text{gage}} = \rho_{\text{H}_2\text{O}} \times g \times (SG_{\text{Hg}} \times 0.1 \cdot \text{m} - 1.0 \cdot \text{m})$$

$$p_{\text{gage}} = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (13.55 \times 0.1 \cdot \text{m} - 1.0 \cdot \text{m}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad p_{\text{gage}} = 3.48 \cdot \text{kPa}$$

If the left air pressure is now increased until the water and mercury levels are now equal, Eq. 3.8 leads to

$$p_{\text{gage}} = SG_{\text{Hg}} \times \rho_{\text{H}_2\text{O}} \times g \times 1.0 \cdot \text{m} - \rho_{\text{H}_2\text{O}} \times g \times 1.0 \cdot \text{m}$$


$$p_{\text{gage}} = \rho_{\text{H}_2\text{O}} \times g \times (SG_{\text{Hg}} \times 1 \cdot \text{m} - 1.0 \cdot \text{m})$$

$$p_{\text{gage}} = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (13.55 \times 1 \cdot \text{m} - 1.0 \cdot \text{m}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad p_{\text{gage}} = 123 \cdot \text{kPa}$$

## Problem 3.19

[Difficulty: 2]

**3.19** In the tank of Problem 3.18, if the opening to atmosphere on the right chamber is first sealed, what pressure would the air on the left now need to be pumped to in order to bring the water and mercury free surfaces level? (Assume the air trapped in the right chamber behaves isothermally.)



**Given:** Data on partitioned tank

**Find:** Pressure of trapped air required to bring water and mercury levels equal if right air opening is sealed

**Solution:**

First we need to determine how far each free surface moves.

In the tank of Problem 3.18, the ratio of cross section areas of the partitions is  $0.75/3.75$  or  $1:5$ . Suppose the water surface (and therefore the mercury on the left) must move down distance  $x$  to bring the water and mercury levels equal. Then by mercury volume conservation, the mercury free surface (on the right) moves up  $(0.75/3.75)x = x/5$ . These two changes in level must cancel the original discrepancy in free surface levels, of  $(1\text{ m} + 2.9\text{ m}) - 3\text{ m} = 0.9\text{ m}$ . Hence  $x + x/5 = 0.9\text{ m}$ , or  $x = 0.75\text{ m}$ . The mercury level thus moves up  $x/5 = 0.15\text{ m}$ .

Assuming the air (an ideal gas,  $pV=RT$ ) in the right behaves isothermally, the new pressure there will be

$$P_{\text{right}} = \frac{V_{\text{rightold}}}{V_{\text{rightnew}}} \cdot P_{\text{atm}} = \frac{A_{\text{right}} \cdot L_{\text{rightold}}}{A_{\text{right}} \cdot L_{\text{rightnew}}} \cdot P_{\text{atm}} = \frac{L_{\text{rightold}}}{L_{\text{rightnew}}} \cdot P_{\text{atm}}$$

where  $V$ ,  $A$  and  $L$  represent volume, cross-section area, and vertical length

Hence

$$P_{\text{right}} = \frac{3}{3 - 0.15} \times 101 \cdot \text{kPa} \qquad P_{\text{right}} = 106 \cdot \text{kPa}$$

When the water and mercury levels are equal application of Eq. 3.8 gives:

$$P_{\text{left}} = P_{\text{right}} + SG_{\text{Hg}} \times \rho_{\text{H}_2\text{O}} \times g \times 1.0 \cdot \text{m} - \rho_{\text{H}_2\text{O}} \times g \times 1.0 \cdot \text{m}$$

$$P_{\text{left}} = P_{\text{right}} + \rho_{\text{H}_2\text{O}} \times g \times (SG_{\text{Hg}} \times 1.0 \cdot \text{m} - 1.0 \cdot \text{m})$$


$$P_{\text{left}} = 106 \cdot \text{kPa} + 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (13.55 \cdot 1.0 \cdot \text{m} - 1.0 \cdot \text{m}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \qquad P_{\text{left}} = 229 \cdot \text{kPa}$$

$$P_{\text{gage}} = P_{\text{left}} - P_{\text{atm}} \qquad P_{\text{gage}} = 229 \cdot \text{kPa} - 101 \cdot \text{kPa} \qquad P_{\text{gage}} = 128 \cdot \text{kPa}$$

### Problem 3.20

[Difficulty: 2]

**3.20** Consider the two-fluid manometer shown. Calculate the applied pressure difference.



**Given:** Two-fluid manometer as shown

$$l = 10.2\text{-mm} \quad SG_{\text{ct}} = 1.595 \quad (\text{From Table A.1, App. A})$$

**Find:** Pressure difference

**Solution:** We will apply the hydrostatics equation.

**Governing equations:**

$$\frac{dp}{dh} = \rho \cdot g$$

(Hydrostatic Pressure - h is positive downwards)

$$\rho = SG \cdot \rho_{\text{water}}$$

(Definition of Specific Gravity)

**Assumptions:**

- (1) Static liquid
- (2) Incompressible liquid

Starting at point 1 and progressing to point 2 we have:


$$p_1 + \rho_{\text{water}} \cdot g \cdot (d + l) - \rho_{\text{ct}} \cdot g \cdot l - \rho_{\text{water}} \cdot g \cdot d = p_2$$

Simplifying and solving for  $p_2 - p_1$  we have:

$$\Delta p = p_2 - p_1 = \rho_{\text{ct}} \cdot g \cdot l - \rho_{\text{water}} \cdot g \cdot l = (SG_{\text{ct}} - 1) \cdot \rho_{\text{water}} \cdot g \cdot l$$

Substituting the known data:


$$\Delta p = (1.591 - 1) \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 10.2 \cdot \text{mm} \times \frac{\text{m}}{10^3 \cdot \text{mm}} \quad \Delta p = 59.1 \text{ Pa}$$



## Problem 3.21

[Difficulty: 2]

**3.21** A manometer is formed from glass tubing with uniform inside diameter,  $D = 6.35$  mm, as shown. The U-tube is partially filled with water. Then  $V = 3.25$  cm<sup>3</sup> of Meriam red oil is added to the left side. Calculate the equilibrium height,  $H$ , when both legs of the U-tube are open to the atmosphere.



**Given:** U-tube manometer, partially filled with water, then a given volume of Meriam red oil is added to the left side

$$D = 6.35 \cdot \text{mm} \quad V_{\text{oil}} = 3.25 \cdot \text{cm}^3 \quad SG_{\text{oil}} = 0.827 \quad (\text{From Table A.1, App. A})$$

**Find:** Equilibrium height,  $H$ , when both legs are open to atmosphere.

**Solution:** We will apply the basic pressure-height relation.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards})$$

$$\rho = SG \cdot \rho_{\text{water}} \quad (\text{Definition of Specific Gravity})$$

**Assumptions:**

- (1) Static liquid
- (2) Incompressible liquid

Integration of the pressure equation gives:  $p_2 - p_1 = \rho \cdot g \cdot (h_2 - h_1)$

Thus:  $p_B - p_A = \rho_{\text{oil}} \cdot g \cdot L$  and  $p_D - p_C = \rho_{\text{water}} \cdot g \cdot (L - H)$

Since  $p_A = p_C = p_{\text{atm}}$  and  $p_B = p_D$  since they are at the same height:


$$\rho_{\text{oil}} \cdot g \cdot L = \rho_{\text{water}} \cdot g \cdot (L - H) \quad \text{or} \quad SG_{\text{oil}} \cdot L = L - H$$

Solving for  $H$ :  $H = L \cdot (1 - SG_{\text{oil}})$

The value of  $L$  comes from the volume of the oil:  $V_{\text{oil}} = \frac{\pi}{4} \cdot D^2 \cdot L$

Solving for  $L$ :  $L = \frac{4 \cdot V_{\text{oil}}}{\pi \cdot D^2} \quad L = \frac{4 \times 3.25 \cdot \text{cm}^3}{\pi \times (6.35 \cdot \text{mm})^2} \times \left( \frac{10 \cdot \text{mm}}{\text{cm}} \right)^3 \quad L = 102.62 \cdot \text{mm}$


We can now calculate  $H$ :  $H = 102.62 \cdot \text{mm} \cdot (1 - 0.827) \quad H = 17.75 \cdot \text{mm}$



## Problem 3.22

[Difficulty: 2]

**3.22** The manometer shown contains water and kerosene. With both tubes open to the atmosphere, the free-surface elevations differ by  $H_0 = 20.0$  mm. Determine the elevation difference when a pressure of 98.0 Pa (gage) is applied to the right tube.



**Given:** Two fluid manometer contains water and kerosene. With both tubes open to atmosphere, the difference in free surface elevations is known

$$H_0 = 20\text{-mm} \quad SG_k = 0.82 \quad (\text{From Table A.1, App. A})$$

**Find:** The elevation difference,  $H$ , between the free surfaces of the fluids when a gage pressure of 98.0 Pa is applied to the right tube.

**Solution:** We will apply the hydrostatics equation.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - h is positive downwards})$$

$$\rho = SG \cdot \rho_{\text{water}} \quad (\text{Definition of Specific Gravity})$$

**Assumptions:** (1) Static liquid  
(2) Incompressible liquid

When the gage pressure  $\Delta p$  is applied to the right tube, the water in the right tube is displaced downward by a distance,  $l$ . The kerosene in the left tube is displaced upward by the same distance,  $l$ .

Under the applied gage pressure  $\Delta p$ , the elevation difference,  $H$ , is:

$$H = H_0 + 2 \cdot l$$

Since points A and B are at the same elevation in the same fluid, their pressures are the same. Initially:

$$p_A = \rho_k \cdot g \cdot (H_0 + H_1) \quad p_B = \rho_{\text{water}} \cdot g \cdot H_1$$

Setting these pressures equal:


$$\rho_k \cdot g \cdot (H_0 + H_1) = \rho_{\text{water}} \cdot g \cdot H_1$$

Solving for  $H_1$

$$H_1 = \frac{\rho_k \cdot H_0}{\rho_{\text{water}} - \rho_k} = \frac{SG_k \cdot H_0}{1 - SG_k} \quad H_1 = \frac{0.82 \times 20\text{-mm}}{1 - 0.82} \quad H_1 = 91.11\text{-mm}$$

Now under the applied gage pressure:

$$p_A = \rho_k \cdot g \cdot (H_0 + H_1) + \rho_{\text{water}} \cdot g \cdot l \quad p_B = \Delta p + \rho_{\text{water}} \cdot g \cdot (H_1 - l)$$



Setting these pressures equal:

$$SG_k \cdot (H_0 + H_1) + l = \frac{\Delta p}{\rho_{\text{water}} \cdot g} + (H_1 - l) \quad l = \frac{1}{2} \left[ \frac{\Delta p}{\rho_{\text{water}} \cdot g} + H_1 - SG_k \cdot (H_0 + H_1) \right]$$

Substituting in known values we get:

$$l = \frac{1}{2} \times \left[ 98.0 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{999} \frac{\text{m}^3}{\text{kg}} \times \frac{1}{9.81} \frac{\text{s}^2}{\text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} + [91.11 \cdot \text{mm} - 0.82 \times (20 \cdot \text{mm} + 91.11 \cdot \text{mm})] \times \frac{\text{m}}{10^3 \cdot \text{mm}} \right] \quad l = 5.000 \cdot \text{mm}$$

Now we solve for H:


$$H = 20 \cdot \text{mm} + 2 \times 5.000 \cdot \text{mm}$$

$$H = 30.0 \cdot \text{mm}$$

### Problem 3.23

[Difficulty: 2]

**3.23** The manometer shown contains two liquids. Liquid A has  $SG = 0.88$  and liquid B has  $SG = 2.95$ . Calculate the deflection,  $h$ , when the applied pressure difference is  $p_1 - p_2 = 18 \text{ lbf/ft}^2$ .



**Given:** Data on manometer

**Find:** Deflection due to pressure difference

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot \Delta h$  where  $h$  is measured downwards

Starting at  $p_1$   $p_A = p_1 + SG_A \cdot \rho \cdot g \cdot (h + l)$  where  $l$  is the (unknown) distance from the level of the right interface

Next, from A to B  $p_B = p_A - SG_B \cdot \rho \cdot g \cdot h$

Finally, from A to the location of  $p_2$   $p_2 = p_B - SG_A \cdot \rho \cdot g \cdot l$

Combining the three equations  $p_2 = (p_A - SG_B \cdot \rho \cdot g \cdot h) - SG_A \cdot \rho \cdot g \cdot l = [p_1 + SG_A \cdot \rho \cdot g \cdot (h + l) - SG_B \cdot \rho \cdot g \cdot h] - SG_A \cdot \rho \cdot g \cdot l$

$$p_2 - p_1 = (SG_A - SG_B) \cdot \rho \cdot g \cdot h$$

$$h = \frac{p_1 - p_2}{(SG_B - SG_A) \cdot \rho \cdot g}$$

$$h = 18 \cdot \frac{\text{lbf}}{\text{ft}^2} \times \frac{1}{(2.95 - 0.88)} \times \frac{1}{1.94} \cdot \frac{\text{ft}^3}{\text{slug}} \times \frac{1}{32.2} \cdot \frac{\text{s}^2}{\text{ft}} \times \frac{\text{slug} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}}$$


$$h = 0.139 \cdot \text{ft}$$

$$h = 1.67 \cdot \text{in}$$

### Problem 3.24

[Difficulty: 2]

**3.24** Determine the gage pressure in kPa at point *a*, if liquid *A* has  $SG = 1.20$  and liquid *B* has  $SG = 0.75$ . The liquid surrounding point *a* is water, and the tank on the left is open to the atmosphere.



**Given:** Data on manometer


**Find:** Gage pressure at point *a*

**Assumption:** Water, liquids *A* and *B* are static and incompressible

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot \Delta h$

where  $\Delta h$  is height difference



Starting at point *a*  $p_1 = p_a - \rho_{H_2O} \cdot g \cdot h_1$  where  $h_1 = 0.125 \cdot m + 0.25 \cdot m$   $h_1 = 0.375 \text{ m}$

Next, in liquid *A*  $p_2 = p_1 + SG_A \cdot \rho_{H_2O} \cdot g \cdot h_2$  where  $h_2 = 0.25 \cdot m$

Finally, in liquid *B*  $p_{atm} = p_2 - SG_B \cdot \rho_{H_2O} \cdot g \cdot h_3$  where  $h_3 = 0.9 \cdot m - 0.4 \cdot m$   $h_3 = 0.5 \text{ m}$

Combining the three equations

$$p_{atm} = (p_1 + SG_A \cdot \rho_{H_2O} \cdot g \cdot h_2) - SG_B \cdot \rho_{H_2O} \cdot g \cdot h_3 = p_a - \rho_{H_2O} \cdot g \cdot h_1 + SG_A \cdot \rho_{H_2O} \cdot g \cdot h_2 - SG_B \cdot \rho_{H_2O} \cdot g \cdot h_3$$

$$p_a = p_{atm} + \rho_{H_2O} \cdot g \cdot (h_1 - SG_A \cdot h_2 + SG_B \cdot h_3)$$

or in gage pressures  $p_a = \rho_{H_2O} \cdot g \cdot (h_1 - SG_A \cdot h_2 + SG_B \cdot h_3)$


$$p_a = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times [0.375 - (1.20 \times 0.25) + (0.75 \times 0.5)] \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$p_a = 4.41 \times 10^3 \text{ Pa} \quad p_a = 4.41 \cdot \text{kPa} \quad (\text{gage})$$

## Problem 3.25

[Difficulty: 2]

**3.25** An engineering research company is evaluating using a sophisticated \$80,000 laser system between two large water storage tanks. You suggest that the job can be done with a \$200 manometer arrangement. Oil less dense than water can be used to give a significant amplification of meniscus movement; a small difference in level between the tanks will cause a much larger deflection in the oil levels in the manometer. If you set up a rig using Meriam red oil as the manometer fluid, determine the amplification factor that will be seen in the rig.



**Given:** Two fluid manometer, Meriam red oil is the second fluid  $SG_{oil} = 0.827$  from Table A.1

**Find:** The amplification factor which will be seen in this demonstrator

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g$$

(Hydrostatic Pressure - h is positive downwards)

$$\rho = SG \cdot \rho_{water}$$

(Definition of Specific Gravity)

**Assumptions:**

- (1) Static liquid
- (2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:

$$p = p_0 + \rho \cdot g \cdot h$$

For the left leg of the manometer:  $p_a = p_{atm} + \rho_{water} \cdot g \cdot h_A$

$$p_b = p_a - \rho_{water} \cdot g \cdot l = p_{atm} + \rho_{water} \cdot g \cdot (h_A - l)$$

For the right leg:

$$p_a = p_{atm} + \rho_{water} \cdot g \cdot h_B$$

$$p_b = p_a - \rho_{oil} \cdot g \cdot l = p_{atm} + \rho_{water} \cdot g \cdot (h_B - SG_{oil} \cdot l)$$

Combining the right hand sides of these two equations:

$$p_{atm} + \rho_{water} \cdot g \cdot (h_A - l) = p_{atm} + \rho_{water} \cdot g \cdot (h_B - SG_{oil} \cdot l)$$

Upon simplification:


$$h_A - l = h_B - SG_{oil} \cdot l$$

$$\Delta h = h_A - h_B = l \cdot (1 - SG_{oil}) \quad \text{so the amplification factor would be:}$$

$$AF = \frac{l}{\Delta h} = \frac{1}{1 - SG_{oil}}$$

For Meriam red  $AF = \frac{1}{1 - 0.827} = 5.78$


$$AF = 5.78$$



### Problem 3.26

[Difficulty: 2]

**3.26** Water flows downward along a pipe that is inclined at  $30^\circ$  below the horizontal, as shown. Pressure difference  $p_A - p_B$  is due partly to gravity and partly to friction. Derive an algebraic expression for the pressure difference. Evaluate the pressure difference if  $L = 5$  ft and  $h = 6$  in.



**Given:** Water flow in an inclined pipe as shown. The pressure difference is measured with a two-fluid manometer  
 $L = 5$  ft       $h = 6$  in       $SG_{Hg} = 13.55$  (From Table A.1, App. A)

**Find:** Pressure difference between A and B

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad \text{(Hydrostatic Pressure - h is positive downwards)}$$

$$\rho = SG \cdot \rho_{\text{water}} \quad \text{(Definition of Specific Gravity)}$$

**Assumptions:**

- (1) Static liquid
- (2) Incompressible liquid
- (3) Gravity is constant

Integrating the hydrostatic pressure equation we get:

$$\Delta p = \rho \cdot g \cdot \Delta h$$

Progressing through the manometer from A to B:

$$p_A + \rho_{\text{water}} \cdot g \cdot L \cdot \sin(30 \cdot \text{deg}) + \rho_{\text{water}} \cdot g \cdot a + \rho_{\text{water}} \cdot g \cdot h - \rho_{Hg} \cdot g \cdot h - \rho_{\text{water}} \cdot g \cdot a = p_B$$

Simplifying terms and solving for the pressure difference:

$$\Delta p = p_A - p_B = \rho_{\text{water}} \cdot g \cdot \left[ h \cdot (SG_{Hg} - 1) - L \cdot \sin(30 \cdot \text{deg}) \right]$$


Substituting in values:

$$\Delta p = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \frac{\text{ft}}{\text{s}^2} \times \left[ 6 \cdot \text{in} \times \frac{\text{ft}}{12 \cdot \text{in}} \times (13.55 - 1) - 5 \cdot \text{ft} \times \sin(30 \cdot \text{deg}) \right] \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad \Delta p = 1.638 \cdot \text{psi}$$

### Problem 3.27

[Difficulty: 2]

**3.27** Consider a tank containing mercury, water, benzene, and air as shown. Find the air pressure (gage). If an opening is made in the top of the tank, find the equilibrium level of the mercury in the manometer.



**Given:** Data on fluid levels in a tank

**Find:** Air pressure; new equilibrium level if opening appears

**Solution:**

Using Eq. 3.8, starting from the open side and working in gage pressure

$$p_{\text{air}} = \rho_{\text{H}_2\text{O}} \times g \times \left[ SG_{\text{Hg}} \times (0.3 - 0.1) \cdot m - 0.1 \cdot m - SG_{\text{Benzene}} \times 0.1 \cdot m \right]$$

Using data from Table A.2

$$p_{\text{air}} = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (13.55 \times 0.2 \cdot m - 0.1 \cdot m - 0.879 \times 0.1 \cdot m) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad p_{\text{air}} = 24.7 \cdot \text{kPa}$$

To compute the new level of mercury in the manometer, assume the change in level from 0.3 m is an increase of  $x$ . Then, because the volume of mercury is constant, the tank mercury level will fall by distance  $(0.025/0.25)^2 x$ . Hence, the gage pressure at the bottom of the tank can be computed from the left and the right, providing a formula for  $x$

$$SG_{\text{Hg}} \times \rho_{\text{H}_2\text{O}} \times g \times (0.3 \cdot m + x) = SG_{\text{Hg}} \times \rho_{\text{H}_2\text{O}} \times g \times \left[ 0.1 \cdot m - x \cdot \left( \frac{0.025}{0.25} \right)^2 \right] \cdot m \dots$$

$$+ \rho_{\text{H}_2\text{O}} \times g \times 0.1 \cdot m + SG_{\text{Benzene}} \times \rho_{\text{H}_2\text{O}} \times g \times 0.1 \cdot m$$

Hence

$$x = \frac{[0.1 \cdot m + 0.879 \times 0.1 \cdot m + 13.55 \times (0.1 - 0.3) \cdot m]}{\left[ 1 + \left( \frac{0.025}{0.25} \right)^2 \right] \times 13.55} \quad x = -0.184 \text{ m}$$


(The negative sign indicates the manometer level actually fell)

The new manometer height is  $h = 0.3 \cdot m + x$   $h = 0.116 \text{ m}$

## Problem 3.28

[Difficulty: 2]

**3.28** A reservoir manometer has vertical tubes of diameter  $D = 18$  mm and  $d = 6$  mm. The manometer liquid is Meriam red oil. Develop an algebraic expression for liquid deflection  $L$  in the small tube when gage pressure  $\Delta p$  is applied to the reservoir. Evaluate the liquid deflection when the applied pressure is equivalent to 25 mm of water (gage).



**Given:** Reservoir manometer with vertical tubes of known diameter. Gage liquid is Meriam red oil

$$D = 18\text{-mm} \quad d = 6\text{-mm}$$

$$SG_{\text{oil}} = 0.827 \quad (\text{From Table A.1, App. A})$$

**Find:** The manometer deflection,  $L$  when a gage pressure equal to 25 mm of water is applied to the reservoir.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - h is positive downwards})$$

$$\rho = SG \cdot \rho_{\text{water}} \quad (\text{Definition of Specific Gravity})$$

**Assumptions:**

- (1) Static liquid
- (2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:

$$\Delta p = \rho \cdot g \cdot \Delta h$$

Beginning at the free surface of the reservoir, and accounting for the changes in pressure with elevation:

$$p_{\text{atm}} + \Delta p + \rho_{\text{oil}} \cdot g \cdot (x + L) = p_{\text{atm}}$$

Upon simplification:  $x + L = \frac{\Delta p}{\rho_{\text{oil}} \cdot g}$  The gage pressure is defined as:  $\Delta p = \rho_{\text{water}} \cdot g \cdot \Delta h$  where  $\Delta h = 25\text{-mm}$

Combining these two expressions:  $x + L = \frac{\rho_{\text{water}} \cdot g \cdot h}{\rho_{\text{oil}} \cdot g} = \frac{\Delta h}{SG_{\text{oil}}}$

$x$  and  $L$  are related through the manometer dimensions:  $\frac{\pi}{4} \cdot D^2 \cdot x = \frac{\pi}{4} \cdot d^2 \cdot L \quad x = \left(\frac{d}{D}\right)^2 L$

Therefore:  $L = \frac{\Delta h}{SG_{\text{oil}} \cdot \left[1 + \left(\frac{d}{D}\right)^2\right]}$  Substituting values into the expression:  $L = \frac{25\text{-mm}}{0.827 \cdot \left[1 + \left(\frac{6\text{-mm}}{18\text{-mm}}\right)^2\right]}$


(Note:  $s = \frac{L}{\Delta h}$  which yields  $s = 1.088$  for this manometer.)

$$L = 27.2\text{-mm}$$

## Problem 3.29

[Difficulty: 2]

**3.29** A rectangular tank, open to the atmosphere, is filled with water to a depth of 2.5 m as shown. A U-tube manometer is connected to the tank at a location 0.7 m above the tank bottom. If the zero level of the Meriam blue manometer fluid is 0.2 m below the connection, determine the deflection  $l$  after the manometer is connected and all air has been removed from the connecting leg.



**Given:** A U-tube manometer is connected to the open tank filled with water as shown (manometer fluid is Meriam blue)  
 $D_1 = 2.5\text{ m}$   $D_2 = 0.7\text{ m}$   $d = 0.2\text{ m}$   $SG_{\text{oil}} = 1.75$  (From Table A.1, App. A)

**Find:** The manometer deflection,  $l$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure -  $h$  is positive downwards)  
 $\rho = SG \cdot \rho_{\text{water}}$  (Definition of Specific Gravity)

**Assumptions:** (1) Static liquid  
 (2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:

$$\Delta p = \rho \cdot g \cdot \Delta h$$

When the tank is filled with water, the oil in the left leg of the manometer is displaced downward by  $l/2$ . The oil in the right leg is displaced upward by the same distance,  $l/2$ .


Beginning at the free surface of the tank, and accounting for the changes in pressure with elevation:

$$p_{\text{atm}} + \rho_{\text{water}} \cdot g \cdot \left( D_1 - D_2 + d + \frac{l}{2} \right) - \rho_{\text{oil}} \cdot g \cdot l = p_{\text{atm}}$$

Upon simplification:

$$\rho_{\text{water}} \cdot g \cdot \left( D_1 - D_2 + d + \frac{l}{2} \right) = \rho_{\text{oil}} \cdot g \cdot l \quad D_1 - D_2 + d + \frac{l}{2} = SG_{\text{oil}} \cdot l \quad l = \frac{D_1 - D_2 + d}{SG_{\text{oil}} - \frac{1}{2}}$$

$$l = \frac{2.5\text{ m} - 0.7\text{ m} + 0.2\text{ m}}{1.75 - \frac{1}{2}} \quad l = 1.600\text{ m}$$



## Problem 3.30

[Difficulty: 2]

**3.30** A reservoir manometer is calibrated for use with a liquid of specific gravity 0.827. The reservoir diameter is 5/8 in. and the (vertical) tube diameter is 3/16 in. Calculate the required distance between marks on the vertical scale for 1 in. of water pressure difference.

**Given:** Reservoir manometer with dimensions shown. The manometer fluid specific gravity is given.

$$D = \frac{5}{8} \cdot \text{in} \quad d = \frac{3}{16} \cdot \text{in} \quad SG_{\text{oil}} = 0.827$$

**Find:** The required distance between vertical marks on the scale corresponding to  $\Delta p$  of 1 in water.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dz} = -\rho \cdot g \quad (\text{Hydrostatic Pressure - } z \text{ is positive upwards})$$

$$\rho = SG \cdot \rho_{\text{water}} \quad (\text{Definition of Specific Gravity})$$


**Assumptions:** (1) Static liquid  
(2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:

$$\Delta p = -\rho \cdot g \cdot \Delta z$$

Beginning at the free surface of the tank, and accounting for the changes in pressure with elevation:

$$p_{\text{atm}} + \Delta p - \rho_{\text{oil}} \cdot g \cdot (x + h) = p_{\text{atm}}$$



Upon simplification:  $\Delta p = \rho_{\text{oil}} \cdot g \cdot (x + h)$  The applied pressure is defined as:  $\Delta p = \rho_{\text{water}} \cdot g \cdot l$  where  $l = 1 \cdot \text{in}$

Therefore:  $\rho_{\text{water}} \cdot g \cdot l = \rho_{\text{oil}} \cdot g \cdot (x + h)$   $x + h = \frac{l}{SG_{\text{oil}}}$

x and h are related through the manometer dimensions:  $\frac{\pi}{4} \cdot D^2 \cdot x = \frac{\pi}{4} \cdot d^2 \cdot h$   $x = \left(\frac{d}{D}\right)^2 h$


Solving for h:  $h = \frac{l}{SG_{\text{oil}} \cdot \left[1 + \left(\frac{d}{D}\right)^2\right]}$  Substituting values into the expression:  $h = \frac{1 \cdot \text{in}}{0.827 \cdot \left[1 + \left(\frac{0.1875 \cdot \text{in}}{0.625 \cdot \text{in}}\right)^2\right]}$

$$h = 1.109 \cdot \text{in}$$

### Problem 3.31

[Difficulty: 2]

**3.31** The manometer fluid of Problem 3.29 is replaced with mercury (same zero level). The tank is sealed and the air pressure is increased to a gage pressure of 0.5 atm. Determine the deflection  $l$ .



**Given:** A U-tube manometer is connected to the open tank filled with water as shown (manometer fluid is mercury). The tank is sealed and pressurized.

$$D_1 = 2.5\text{ m} \quad D_2 = 0.7\text{ m} \quad d = 0.2\text{ m} \quad p_0 = 0.5\text{ atm} \quad SG_{\text{Hg}} = 13.55 \quad (\text{From Table A.1, App. A})$$

**Find:** The manometer deflection,  $l$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - h is positive downwards})$$

$$\rho = SG \cdot \rho_{\text{water}} \quad (\text{Definition of Specific Gravity})$$

**Assumptions:**


- (1) Static liquid
- (2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:

$$\Delta p = \rho \cdot g \cdot \Delta h$$

When the tank is filled with water and pressurized, the mercury in the left leg of the manometer is displaced downward by  $l/2$ . The mercury in the right leg is displaced upward by the same distance,  $l/2$ .

Beginning at the free surface of the tank, and accounting for the changes in pressure with elevation:



$$p_{\text{atm}} + p_0 + \rho_{\text{water}} \cdot g \cdot \left( D_1 - D_2 + d + \frac{1}{2} \right) - \rho_{\text{Hg}} \cdot g \cdot l = p_{\text{atm}}$$

Upon simplification:

$$p_0 + \rho_{\text{water}} \cdot g \cdot \left( D_1 - D_2 + d + \frac{1}{2} \right) = \rho_{\text{Hg}} \cdot g \cdot l$$

$$l = \frac{\frac{p_0}{\rho_{\text{water}} \cdot g} + D_1 - D_2 + d}{SG_{\text{Hg}} - \frac{1}{2}}$$


Substituting values into the expression:

$$l = \frac{\left( 0.5 \cdot \text{atm} \times \frac{1.013 \times 10^5 \cdot \text{N}}{\text{m}^2 \cdot \text{atm}} \times \frac{1}{1000} \cdot \frac{\text{m}^3}{\text{kg}} \times \frac{1}{9.8} \cdot \frac{\text{s}^2}{\text{m}} \right) + 2.5 \cdot \text{m} - 0.7 \cdot \text{m} + 0.2 \cdot \text{m}}{13.55 - \frac{1}{2}} \quad l = 0.549 \text{ m}$$

### Problem 3.32

[Difficulty: 3]

**3.32** The inclined-tube manometer shown has  $D = 96$  mm and  $d = 8$  mm. Determine the angle,  $\theta$ , required to provide a 5 : 1 increase in liquid deflection,  $L$ , compared with the total deflection in a regular U-tube manometer. Evaluate the sensitivity of this inclined-tube manometer.



**Given:**

Inclined manometer as shown.

$D = 96 \text{ mm}$   $d = 8 \text{ mm}$

Angle  $\theta$  is such that the liquid deflection  $L$  is five times that of a regular U-tube manometer.

**Find:**

Angle  $\theta$  and manometer sensitivity.

**Solution:**

We will apply the hydrostatics equations to this system.

**Governing Equation:**

$$\frac{dp}{dz} = -\rho \cdot g$$

(Hydrostatic Pressure -  $z$  is positive upwards)

**Assumptions:**


- (1) Static liquid
- (2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:

$$\Delta p = -\rho \cdot g \cdot \Delta z$$

Applying this equation from point 1 to point 2:

$$p_1 - \rho \cdot g \cdot (x + L \cdot \sin(\theta)) = p_2$$



Upon simplification:

$$p_1 - p_2 = \rho \cdot g \cdot (x + L \cdot \sin(\theta))$$

Since the volume of the fluid must remain constant:  $\frac{\pi}{4} \cdot D^2 \cdot x = \frac{\pi}{4} \cdot d^2 \cdot L$   $x = \left(\frac{d}{D}\right)^2 \cdot L$

Therefore:  $p_1 - p_2 = \rho \cdot g \cdot L \cdot \left[ \left(\frac{d}{D}\right)^2 + \sin(\theta) \right]$

Now for a U-tube manometer:  $p_1 - p_2 = \rho \cdot g \cdot h$  Hence:  $\frac{p_{1\text{incl}} - p_{2\text{incl}}}{p_{1\text{U}} - p_{2\text{U}}} = \frac{\rho \cdot g \cdot L \cdot \left[ \left(\frac{d}{D}\right)^2 + \sin(\theta) \right]}{\rho \cdot g \cdot h}$

For equal applied pressures:  $L \cdot \left[ \left(\frac{d}{D}\right)^2 + \sin(\theta) \right] = h$  Since  $L/h = 5$ :  $\sin(\theta) = \frac{h}{L} - \left(\frac{d}{D}\right)^2 = \frac{1}{5} - \left(\frac{8 \cdot \text{mm}}{96 \cdot \text{mm}}\right)^2$

$$\theta = 11.13 \cdot \text{deg}$$

The sensitivity of the manometer:  $s = \frac{L}{\Delta h_e} = \frac{L}{SG \cdot h}$

$$s = \frac{5}{SG}$$

### Problem 3.33

[Difficulty: 3]

**3.33** The inclined-tube manometer shown has  $D = 76$  mm and  $d = 8$  mm, and is filled with Meriam red oil. Compute the angle,  $\theta$ , that will give a 15-cm oil deflection along the inclined tube for an applied pressure of 25 mm of water (gage). Determine the sensitivity of this manometer.

**Given:** Data on inclined manometer

**Find:** Angle  $\theta$  for given data; find sensitivity

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot \Delta h$  where  $\Delta h$  is height difference

Under applied pressure  $\Delta p = SG_{\text{Mer}} \cdot \rho \cdot g \cdot (L \cdot \sin(\theta) + x)$  (1)

From Table A.1  $SG_{\text{Mer}} = 0.827$

and  $\Delta p = 1$  in. of water, or  $\Delta p = \rho \cdot g \cdot h$  where  $h = 25\text{-mm}$   $h = 0.025\text{ m}$

$$\Delta p = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.025 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \Delta p = 245 \text{ Pa}$$

The volume of liquid must remain constant, so  $x \cdot A_{\text{res}} = L \cdot A_{\text{tube}}$   $x = L \cdot \frac{A_{\text{tube}}}{A_{\text{res}}} = L \cdot \left(\frac{d}{D}\right)^2$  (2)

Combining Eqs 1 and 2  $\Delta p = SG_{\text{Mer}} \cdot \rho \cdot g \cdot \left[ L \cdot \sin(\theta) + L \cdot \left(\frac{d}{D}\right)^2 \right]$

Solving for  $\theta$   $\sin(\theta) = \frac{\Delta p}{SG_{\text{Mer}} \cdot \rho \cdot g \cdot L} - \left(\frac{d}{D}\right)^2$

$$\sin(\theta) = 245 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{0.827} \times \frac{1}{1000 \cdot \frac{\text{m}^3}{\text{kg}}} \times \frac{1}{9.81 \cdot \frac{\text{s}^2}{\text{m}}} \times \frac{1}{0.15 \cdot \frac{1}{\text{m}}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} - \left(\frac{8}{76}\right)^2 = 0.186$$

$$\theta = 11 \cdot \text{deg}$$

The sensitivity is the ratio of manometer deflection to a vertical water manometer

$$s = \frac{L}{h} = \frac{0.15 \cdot \text{m}}{0.025 \cdot \text{m}} \quad s = 6$$

## Problem 3.34

[Difficulty: 4]

**3.34** A barometer accidentally contains 6.5 inches of water on top of the mercury column (so there is also water vapor instead of a vacuum at the top of the barometer). On a day when the temperature is 70°F, the mercury column height is 28.35 inches (corrected for thermal expansion). Determine the barometric pressure in psia. If the ambient temperature increased to 85°F and the barometric pressure did not change, would the mercury column be longer, be shorter, or remain the same length? Justify your answer.

**Given:** Barometer with water on top of the mercury column, Temperature is known:

$$h_2 = 6.5\text{-in} \quad h_1 = 28.35\text{-in} \quad SG_{\text{Hg}} = 13.55 \quad (\text{From Table A.2, App. A}) \quad T = 70^\circ\text{F}$$

$$p_v = 0.363\text{-psi} \quad (\text{From Table A.7, App. A})$$

**Find:** (a) Barometric pressure in psia  
 (b) Effect of increase in ambient temperature on length of mercury column for the same barometric pressure:  $T_f = 85^\circ\text{F}$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = -\rho \cdot g$  (Hydrostatic Pressure - h is positive downwards)

$$\rho = SG \cdot \rho_{\text{water}} \quad (\text{Definition of Specific Gravity})$$

**Assumptions:** (1) Static liquid  
 (2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:


$$\Delta p = \rho \cdot g \cdot \Delta h$$

Start at the free surface of the mercury and progress through the barometer to the vapor pressure of the water:

$$P_{\text{atm}} - \rho_{\text{Hg}} \cdot g \cdot h_1 - \rho_{\text{water}} \cdot g \cdot h_2 = p_v$$

$$P_{\text{atm}} = p_v + \rho_{\text{water}} \cdot g \cdot (SG_{\text{Hg}} \cdot h_1 + h_2)$$

$$P_{\text{atm}} = 0.363 \cdot \frac{\text{lbf}}{\text{in}^2} + 1.93 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times (13.55 \times 28.35\text{-in} + 6.5\text{-in}) \times \left(\frac{\text{ft}}{12\text{-in}}\right)^3 \quad P_{\text{atm}} = 14.41 \cdot \frac{\text{lbf}}{\text{in}^2}$$




At the higher temperature, the vapor pressure of water increases to 0.60 psi. Therefore, if the atmospheric pressure were to remain constant, the length of the mercury column would have to decrease - the increased water vapor would push the mercury out of the tube!

### Problem 3.35

[Difficulty: 3]

**3.35** A student wishes to design a manometer with better sensitivity than a water-filled U-tube of constant diameter. The student's concept involves using tubes with different diameters and two liquids, as shown. Evaluate the deflection  $h$  of this manometer, if the applied pressure difference is  $\Delta p = 250 \text{ N/m}^2$ . Determine the sensitivity of this manometer. Plot the manometer sensitivity as a function of the diameter ratio  $d_2/d_1$ .



**Given:** U-tube manometer with tubes of different diameter and two liquids, as shown.

$$d_1 = 10 \cdot \text{mm} \quad d_2 = 15 \cdot \text{mm} \quad \text{SG}_{\text{oil}} = 0.85$$

**Find:** (a) the deflection,  $h$ , corresponding to  
(b) the sensitivity of the manometer

$$\Delta p = 250 \cdot \frac{\text{N}}{\text{m}^2}$$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dz} = -\rho \cdot g$$

(Hydrostatic Pressure -  $z$  is positive upwards)

$$\rho = \text{SG} \cdot \rho_{\text{water}}$$

(Definition of Specific Gravity)

**Assumptions:**

- (1) Static liquid
- (2) Incompressible liquid

Integrating the hydrostatic pressure equation we get:

$$p - p_0 = -\rho \cdot g \cdot (z - z_0) = \rho \cdot g \cdot (z_0 - z)$$


From the left diagram:

$$p_A - p_{\text{atm}} = \rho_{\text{water}} \cdot g \cdot l_1 = \rho_{\text{oil}} \cdot g \cdot l_2 \quad (1)$$

From the right diagram:

$$p_B - (p_{\text{atm}} + \Delta p) = \rho_{\text{water}} \cdot g \cdot l_3 \quad (2)$$

$$p_B - p_{\text{atm}} = \rho_{\text{water}} \cdot g \cdot l_4 + \rho_{\text{oil}} \cdot g \cdot l_2 \quad (3)$$



Combining these three equations:  $\Delta p = \rho_{\text{water}} \cdot g \cdot (l_4 - l_3) + \rho_{\text{oil}} \cdot g \cdot l_2 = \rho_{\text{water}} \cdot g \cdot (l_4 + l_1 - l_3)$

From the diagram we can see  $l_w = l_1 - l_3$  and  $h = l_4$  Therefore:

$$\Delta p = \rho_{\text{water}} \cdot g \cdot (h + l_w) \quad (4)$$

We can relate  $l_w$  to  $h$  since the volume of water in the manometer is constant:  $\frac{\pi}{4} \cdot d_1^2 \cdot l_w = \frac{\pi}{4} \cdot d_2^2 \cdot h$   $l_w = \left(\frac{d_2}{d_1}\right)^2 \cdot h$

Substituting this into (4) yields:  $\Delta p = \rho_{\text{water}} \cdot g \cdot h \cdot \left[ 1 + \left( \frac{d_2}{d_1} \right)^2 \right]$  Solving for h:  $h = \frac{\Delta p}{\rho_{\text{water}} \cdot g \cdot \left[ 1 + \left( \frac{d_2}{d_1} \right)^2 \right]}$


Substituting values into the equation:  $h = 250 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{999} \cdot \frac{\text{m}^3}{\text{kg}} \times \frac{1}{9.81} \frac{\text{s}^2}{\text{m}} \times \frac{1}{1 + \left( \frac{15 \cdot \text{mm}}{10 \cdot \text{mm}} \right)^2} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \times \frac{10^3 \cdot \text{mm}}{\text{m}}$   $h = 7.85 \cdot \text{mm}$

The sensitivity for the manometer is defined as:  $s = \frac{h}{\Delta h_e}$  where  $\Delta p = \rho_{\text{water}} \cdot g \cdot \Delta h_e$

Therefore:  $s = \frac{1}{1 + \left( \frac{d_2}{d_1} \right)^2}$   $s = \frac{1}{1 + \left( \frac{15 \cdot \text{mm}}{10 \cdot \text{mm}} \right)^2}$   $s = 0.308$

The design is a poor one. The sensitivity could be improved by interchanging  $d_2$  and  $d_1$ , i.e., having  $d_2$  smaller than  $d_1$

A plot of the manometer sensitivity is shown below:



### Problem 3.36

[Difficulty: 3]

**3.36** A water column stands 50 mm high in a 2.5-mm diameter glass tube. What would be the column height if the surface tension were zero? What would be the column height in a 1.0-mm diameter tube?

**Given:** Water column standing in glass tube

$$\Delta h = 50 \cdot \text{mm} \quad D = 2.5 \cdot \text{mm} \quad \sigma = 72.8 \times 10^{-3} \frac{\text{N}}{\text{m}} \quad (\text{From Table A.4, App. A})$$

**Find:** (a) Column height if surface tension were zero.  
(b) Column height in 1 mm diameter tube

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards})$$

$$\Sigma F_z = 0 \quad (\text{Static Equilibrium})$$

**Assumptions:**

- (1) Static, incompressible liquid
- (2) Neglect volume under meniscus
- (3) Applied pressure remains constant
- (4) Column height is sum of capillary rise and pressure difference

Assumption #4 can be written as:  $\Delta h = \Delta h_c + \Delta h_p$

Choose a free-body diagram of the capillary rise portion of the column for analysis:

$$\Sigma F_z = \pi \cdot D \cdot \sigma \cdot \cos(\theta) - \frac{\pi}{4} \cdot D^2 \cdot \rho \cdot g \cdot \Delta h_c = 0 \quad \text{Therefore: } \Delta h_c = \frac{4 \cdot \sigma}{\rho \cdot g \cdot D} \cdot \cos(\theta)$$

Substituting values:

$$\Delta h_c = 4 \times 72.8 \times 10^{-3} \frac{\text{N}}{\text{m}} \times \frac{1}{999} \frac{\text{m}^3}{\text{kg}} \times \frac{1}{9.81} \frac{\text{s}^2}{\text{m}} \times \frac{1}{2.5} \frac{1}{\text{mm}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \times \left( \frac{10^3 \cdot \text{mm}}{\text{m}} \right)^2$$



$$\Delta h_c = 11.89 \cdot \text{mm}$$

Therefore:  $\Delta h_p = \Delta h - \Delta h_c \quad \Delta h_p = 50 \cdot \text{mm} - 11.89 \cdot \text{mm} \quad \Delta h_p = 38.1 \cdot \text{mm} \quad (\text{result for } \sigma = 0)$

For the 1 mm diameter tube:

$$\Delta h_c = 4 \times 72.8 \times 10^{-3} \frac{\text{N}}{\text{m}} \times \frac{1}{999} \frac{\text{m}^3}{\text{kg}} \times \frac{1}{9.81} \frac{\text{s}^2}{\text{m}} \times \frac{1}{1} \frac{1}{\text{mm}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \times \left( \frac{10^3 \cdot \text{mm}}{\text{m}} \right)^2 \quad \Delta h_c = 29.71 \cdot \text{mm}$$


$$\Delta h = 29.7 \cdot \text{mm} + 38.1 \cdot \text{mm} \quad \Delta h = 67.8 \cdot \text{mm}$$



### Problem 3.37

[Difficulty: 4]

**3.37** If the tank of Problem 3.29 is sealed tightly and water drains slowly from the bottom of the tank, determine the deflection,  $l$ , after the system has attained equilibrium.



**Given:** Sealed tank is partially filled with water. Water drains slowly from the tank until the system attains equilibrium. U-tube manometer is connected to the tank as shown. (Meriam blue in manometer)

$$L = 3\text{ m} \quad D_1 = 2.5\text{ m} \quad D_2 = 0.7\text{ m} \quad d = 0.2\text{ m} \quad SG_{\text{oil}} = 1.75 \quad (\text{From Table A.2, App. A})$$

**Find:** The manometer deflection,  $l$ , under equilibrium conditions

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards})$$

$$p \cdot V = M \cdot R \cdot T \quad (\text{Ideal gas equation of state})$$

$$\rho = SG \cdot \rho_{\text{water}} \quad (\text{Definition of Specific Gravity})$$

**Assumptions:**

- (1) Static liquid
- (2) Incompressible liquid
- (3) Air in tank behaves ideally

Integrating the hydrostatic pressure equation we get:

$$\Delta p = \rho \cdot g \cdot \Delta h$$

To determine the surface pressure  $p_0$  under equilibrium conditions


we assume that the air expands at constant temperature:

$$\frac{p_a \cdot V_a}{p_0 \cdot V_0} = \frac{M \cdot R \cdot T_a}{M \cdot R \cdot T_0} \quad \text{Thus, } p_0 = \frac{V_a}{V_0} \cdot p_a = \frac{(L - D_1) \cdot A}{(L - H) \cdot A} \cdot p_a$$

Simplifying:  $p_0 = \frac{(L - D_1)}{(L - H)} \cdot p_a$  Now under equilibrium conditions:  $p_0 + \rho_{\text{water}} \cdot g \cdot H = p_a$  Combining these expressions:

$$\frac{(L - D_1)}{(L - H)} \cdot p_a + \rho_{\text{water}} \cdot g \cdot H = p_a \quad \text{Upon rearranging: } \rho_{\text{water}} \cdot g \cdot H^2 - (p_a + \rho_{\text{water}} \cdot g \cdot L) \cdot H + D_1 \cdot p_a = 0$$

Now we apply the quadratic formula to solve for  $H$ :



$$a = \rho_{\text{water}} \cdot g \quad a = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \quad a = 9.8 \times 10^3 \cdot \frac{\text{Pa}}{\text{m}}$$

$$b = -(\rho_a + \rho_{\text{water}} \cdot g \cdot L) \quad b = -\left(1.013 \times 10^5 \cdot \frac{\text{N}}{\text{m}^2} + 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 3 \cdot \text{m}\right) \quad b = -1.307 \times 10^5 \text{ Pa}$$

$$c = D_1 \cdot \rho_a \quad c = 2.5 \cdot \text{m} \times 1.013 \times 10^5 \cdot \frac{\text{N}}{\text{m}^2} \quad c = 2.532 \times 10^5 \cdot \text{Pa} \cdot \text{m}$$

$$H_{\text{upper}} = \frac{-b + \sqrt{b^2 - 4 \cdot a \cdot c}}{2 \cdot a} \quad H_{\text{upper}} = \frac{-(-1.307 \times 10^5 \cdot \text{Pa}) + \sqrt{(-1.307 \times 10^5 \cdot \text{Pa})^2 - 4 \times 9.8 \times 10^3 \cdot \frac{\text{Pa}}{\text{m}} \times 2.532 \times 10^5 \cdot \text{Pa} \cdot \text{m}}}{2 \times 9.8 \times 10^3 \cdot \frac{\text{Pa}}{\text{m}}}$$

$$H_{\text{upper}} = 10.985 \text{ m}$$

$$H_{\text{lower}} = \frac{-b - \sqrt{b^2 - 4 \cdot a \cdot c}}{2 \cdot a} \quad H_{\text{lower}} = \frac{-(-1.307 \times 10^5 \cdot \text{Pa}) - \sqrt{(-1.307 \times 10^5 \cdot \text{Pa})^2 - 4 \times 9.8 \times 10^3 \cdot \frac{\text{Pa}}{\text{m}} \times 2.532 \times 10^5 \cdot \text{Pa} \cdot \text{m}}}{2 \times 9.8 \times 10^3 \cdot \frac{\text{Pa}}{\text{m}}}$$

$$H_{\text{lower}} = 2.352 \text{ m}$$

Since H can not be greater than 3 m (otherwise the tank would overflow!), we must select the lower value for H:  $H = 2.352 \text{ m}$

$$\text{Solving for the pressure inside the tank: } p_0 = \frac{(3 \cdot \text{m} - 2.5 \cdot \text{m})}{(3 \cdot \text{m} - 2.352 \cdot \text{m})} \times 1.013 \times 10^5 \cdot \text{Pa} \quad p_0 = 7.816 \times 10^4 \text{ Pa}$$

$$\text{Applying the hydrostatic pressure equation to the manometer: } p_0 + \rho_{\text{water}} \cdot g \cdot \left(H - D_2 + d - \frac{1}{2}\right) + \rho_{\text{oil}} \cdot g \cdot l = p_a$$


$$\text{Solving for the manometer deflection: } l = \left( \frac{p_a - p_0}{\rho_{\text{water}} \cdot g} - H + D_2 - d \right) \cdot \frac{1}{SG_{\text{oil}} - \frac{1}{2}}$$

$$l = \left[ \left( 1.013 \times 10^5 \cdot \frac{\text{N}}{\text{m}^2} - 7.816 \times 10^4 \cdot \frac{\text{N}}{\text{m}^2} \right) \times \frac{1}{999} \cdot \frac{\text{m}^3}{\text{kg}} \times \frac{1}{9.81} \cdot \frac{\text{s}^2}{\text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - 2.352 \cdot \text{m} + 0.7 \cdot \text{m} - 0.2 \cdot \text{m} \right] \cdot \frac{1}{1.75 - \frac{1}{2}} \quad l = 0.407 \text{ m}$$

### Problem 3.38

[Difficulty :2]

**3.38** Consider a small-diameter open-ended tube inserted at the interface between two immiscible fluids of different densities. Derive an expression for the height difference  $\Delta h$  between the interface level inside and outside the tube in terms of tube diameter  $D$ , the two fluid densities  $\rho_1$  and  $\rho_2$ , and the surface tension  $\sigma$  and angle  $\theta$  for the two fluids' interface. If the two fluids are water and mercury, find the height difference if the tube diameter is 40 mils (1 mil = 0.001 in.).




**Given:** Two fluids inside and outside a tube

**Find:** (a) An expression for height  $\Delta h$   
 (b) Height difference when  $D = 0.040$  in for water/mercury

**Assumptions:** (1) Static, incompressible fluids  
 (2) Neglect meniscus curvature for column height and volume calculations

**Solution:**

A free-body vertical force analysis for the section of fluid 1 height  $\Delta h$  in the tube below the "free surface" of fluid 2 leads to



$$\sum F = 0 = \Delta p \cdot \frac{\pi \cdot D^2}{4} - \rho_1 \cdot g \cdot \Delta h \cdot \frac{\pi \cdot D^2}{4} + \pi \cdot D \cdot \sigma \cdot \cos(\theta)$$

where  $\Delta p$  is the pressure difference generated by fluid 2 over height  $\Delta h$ ,  $\Delta p = \rho_2 \cdot g \cdot \Delta h$

Hence

$$\Delta p \cdot \frac{\pi \cdot D^2}{4} - \rho_1 \cdot g \cdot \Delta h \cdot \frac{\pi \cdot D^2}{4} = \rho_2 \cdot g \cdot \Delta h \cdot \frac{\pi \cdot D^2}{4} - \rho_1 \cdot g \cdot \Delta h \cdot \frac{\pi \cdot D^2}{4} = -\pi \cdot D \cdot \sigma \cdot \cos(\theta)$$

Solving for  $\Delta h$

$$\Delta h = -\frac{4 \cdot \sigma \cdot \cos(\theta)}{g \cdot D \cdot (\rho_2 - \rho_1)}$$

For fluids 1 and 2 being water and mercury (for mercury  $\sigma = 375$  mN/m and  $\theta = 140^\circ$ , from Table A.4), solving for  $\Delta h$  when  $D = 0.040$  in


$$\Delta h = -4 \times 0.375 \cdot \frac{\text{N}}{\text{m}} \times \frac{\text{lbf}}{4.448 \cdot \text{N}} \times \frac{0.0254 \text{m}}{\text{in}} \times \cos(140 \cdot \text{deg}) \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \times \frac{1}{0.040 \cdot \text{in}} \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \left(\frac{12 \cdot \text{in}}{\text{ft}}\right)^3 \times \frac{1}{(13.6 - 1)} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2}$$

$$\Delta h = 0.360 \cdot \text{in}$$

### Problem 3.39

[Difficulty: 2]

**3.39** You have a manometer consisting of a tube that is 0.5 in. inner diameter (ID). On one side, the manometer leg contains mercury, 0.6 in.<sup>3</sup> of an oil (SG = 1.4), and 0.2 in.<sup>3</sup> of air as a bubble in the oil. The other leg contains only mercury. Both legs are open to the atmosphere and are in a static condition. An accident occurs in which 0.2 in.<sup>3</sup> of the oil and the air bubble are removed from one leg. How much do the mercury height levels change?



**Given:** Data on manometer before and after an "accident"

**Find:** Change in mercury level

**Assumptions:** (1) Liquids are incompressible and static  
 (2) Pressure change across air in bubble is negligible  
 (3) Any curvature of air bubble surface can be neglected in volume calculations

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot \Delta h$  where  $\Delta h$  is height difference

For the initial state, working from right to left  $p_{\text{atm}} = p_{\text{atm}} + SG_{\text{Hg}} \cdot \rho \cdot g \cdot h_3 - SG_{\text{oil}} \cdot \rho \cdot g \cdot (h_1 + h_2)$

$$SG_{\text{Hg}} \cdot \rho \cdot g \cdot h_3 = SG_{\text{oil}} \cdot \rho \cdot g \cdot (h_1 + h_2) \quad (1)$$

Note that the air pocket has no effect!

For the final state, working from right to left  $p_{\text{atm}} = p_{\text{atm}} + SG_{\text{Hg}} \cdot \rho \cdot g \cdot (h_3 - x) - SG_{\text{oil}} \cdot \rho \cdot g \cdot h_4$

$$SG_{\text{Hg}} \cdot \rho \cdot g \cdot (h_3 - x) = SG_{\text{oil}} \cdot \rho \cdot g \cdot h_4 \quad (2)$$

The two unknowns here are the mercury levels before and after (i.e.,  $h_3$  and  $x$ )

Combining Eqs. 1 and 2  $SG_{\text{Hg}} \cdot \rho \cdot g \cdot x = SG_{\text{oil}} \cdot \rho \cdot g \cdot (h_1 + h_2 - h_4) \quad x = \frac{SG_{\text{oil}}}{SG_{\text{Hg}}} \cdot (h_1 + h_2 - h_4) \quad (3)$

From Table A.1  $SG_{\text{Hg}} = 13.55$

The term  $h_1 + h_2 - h_4$  is the difference between the total height of oil before and after the accident


$$h_1 + h_2 - h_4 = \frac{\Delta V}{\left(\frac{\pi \cdot d^2}{4}\right)} = \frac{4}{\pi} \times \left(\frac{1}{0.5 \cdot \text{in}}\right)^2 \times 0.2 \cdot \text{in}^3 = 1.019 \cdot \text{in}$$

Then from Eq. 3  $x = \frac{1.4}{13.55} \times 1.019 \cdot \text{in} \quad x = 0.1053 \cdot \text{in}$

### Problem 3.40

[Difficulty: 2]

**3.40** Compare the height due to capillary action of water exposed to air in a circular tube of diameter  $D = 0.5$  mm, and between two infinite vertical parallel plates of gap  $a = 0.5$  mm.



**Given:** Water in a tube or between parallel plates

**Find:** Height  $\Delta h$  for each system

**Solution:**

a) Tube: A free-body vertical force analysis for the section of water height  $\Delta h$  above the "free surface" in the tube, as shown in the figure, leads to

$$\sum F = 0 = \pi \cdot D \cdot \sigma \cdot \cos(\theta) - \rho \cdot g \cdot \Delta h \cdot \frac{\pi \cdot D^2}{4}$$

Assumption: Neglect meniscus curvature for column height and volume calculations

Solving for  $\Delta h$

$$\Delta h = \frac{4 \cdot \sigma \cdot \cos(\theta)}{\rho \cdot g \cdot D}$$

b) Parallel Plates: A free-body vertical force analysis for the section of water height  $\Delta h$  above the "free surface" between plates arbitrary width  $w$  (similar to the figure above), leads to

$$\sum F = 0 = 2 \cdot w \cdot \sigma \cdot \cos(\theta) - \rho \cdot g \cdot \Delta h \cdot w \cdot a$$

Solving for  $\Delta h$

$$\Delta h = \frac{2 \cdot \sigma \cdot \cos(\theta)}{\rho \cdot g \cdot a}$$

For water  $\sigma = 72.8$  mN/m and  $\theta = 0^\circ$  (Table A.4), so

a) Tube

$$\Delta h = \frac{4 \times 0.0728 \cdot \frac{\text{N}}{\text{m}}}{999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.005 \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad \Delta h = 5.94 \times 10^{-3} \text{ m} \quad \Delta h = 5.94 \text{ mm}$$


b) Parallel Plates

$$\Delta h = \frac{2 \times 0.0728 \cdot \frac{\text{N}}{\text{m}}}{999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.005 \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad \Delta h = 2.97 \times 10^{-3} \text{ m} \quad \Delta h = 2.97 \text{ mm}$$

## Problem 3.41

[Difficulty: 3]

**3.41** Two vertical glass plates 12 in. × 12 in. are placed in an open tank containing water. At one end the gap between the plates is 0.004 in., and at the other it is 0.080 in. Plot the curve of water height between the plates from one end of the pair to the other.



**Given:** Geometry of vertical plates

**Find:** Curve of water height due to capillary action

**Assumption:** Water is static and incompressible

**Solution:**

Parallel Plates: A free-body vertical force analysis for the section of water height  $\Delta h$  above the "free surface" between plates arbitrary width  $w$  (similar to the figure above), leads to

$$\sum F = 0 = 2 \cdot w \cdot \sigma \cdot \cos(\theta) - \rho \cdot g \cdot \Delta h \cdot w \cdot a$$

Solving for  $\Delta h$

$$\Delta h = \frac{2 \cdot \sigma \cdot \cos(\theta)}{\rho \cdot g \cdot a}$$


For water  $\sigma = 72.8 \text{ mN/m} = 0.00537 \text{ lbf/ft}$  and  $\theta = 0^\circ$  (Table A.4), so

$$\sigma = 0.005 \text{ lbf/ft}$$

$$\rho = 1.94 \text{ slug/ft}^3$$

Using the formula above

$a$ (in)	$\Delta h$ (in)
0.004	0.0400
0.008	0.0200
0.012	0.0133
0.016	0.0100
0.020	0.0080
0.024	0.0067
0.028	0.0057
0.032	0.0050
0.036	0.0044
0.040	0.0040
0.044	0.0036
0.048	0.0033
0.052	0.0031
0.056	0.0029
0.060	0.0027
0.064	0.0025
0.068	0.0024
0.072	0.0022
0.080	0.0020



### Problem 3.42

[Difficulty: 3]

**3.42** Based on the atmospheric temperature data of the U.S. Standard Atmosphere of Fig. 3.3, compute and plot the pressure variation with altitude, and compare with the pressure data of Table A.3.

**Given:** Atmospheric temperature data

**Find:** Pressure variation; compare to Table A.3

**Solution:**


From Section 3-3:  $\frac{dp}{dz} = -\rho \cdot z$

For a linear temperature variation  $m = -\frac{dT}{dz} = \text{const}$   $p = p_0 \cdot \left(\frac{T}{T_0}\right)^{\frac{g}{m \cdot R}}$

For isothermal conditions (Example 3.4)  $p = p_0 \cdot e^{-\frac{g \cdot (z-z_0)}{R \cdot T}}$


In these equations  $p_0$ ,  $T_0$ , and  $z_0$  are reference conditions

$p_{SL} =$	101	kPa
$R =$	286.9	J/kg.K
$\rho =$	999	kg/m <sup>3</sup>



From Table A.3

The temperature can be computed from the data in the figure. The pressures are then computed from the appropriate equation.



Agreement between calculated and tabulated data is very good (as it should be, considering the table data are also computed!)

$z$ (km)	$T$ ( $^{\circ}\text{C}$ )	$T$ (K)		$\rho/\rho_{\text{SL}}$
0.0	15.0	288.0	$m =$ 0.0065 (K/m)	1.000
2.0	2.0	275.00		0.784
4.0	-11.0	262.0		0.608
6.0	-24.0	249.0		0.465
8.0	-37.0	236.0		0.351
11.0	-56.5	216.5		0.223
12.0	-56.5	216.5	$T = \text{const}$	0.190
14.0	-56.5	216.5		0.139
16.0	-56.5	216.5		0.101
18.0	-56.5	216.5		0.0738
20.1	-56.5	216.5		0.0530
22.0	-54.6	218.4	$m =$ -0.000991736 (K/m)	0.0393
24.0	-52.6	220.4		0.0288
26.0	-50.6	222.4		0.0211
28.0	-48.7	224.3		0.0155
30.0	-46.7	226.3		0.0115
32.2	-44.5	228.5		0.00824
34.0	-39.5	233.5		$m =$ -0.002781457 (K/m)
36.0	-33.9	239.1	0.00473	
38.0	-28.4	244.6	0.00356	
40.0	-22.8	250.2	0.00270	
42.0	-17.2	255.8	0.00206	
44.0	-11.7	261.3	0.00158	
46.0	-6.1	266.9	0.00122	
47.3	-2.5	270.5	0.00104	
50.0	-2.5	270.5	$T = \text{const}$	0.000736
52.4	-2.5	270.5		0.000544
54.0	-5.6	267.4	$m =$ 0.001956522 (K/m)	0.000444
56.0	-9.5	263.5		0.000343
58.0	-13.5	259.5		0.000264
60.0	-17.4	255.6		0.000202
61.6	-20.5	252.5		0.000163
64.0	-29.9	243.1	$m =$ 0.003913043 (K/m)	0.000117
66.0	-37.7	235.3		0.0000880
68.0	-45.5	227.5		0.0000655
70.0	-53.4	219.6		0.0000482
72.0	-61.2	211.8		0.0000351
74.0	-69.0	204.0		0.0000253
76.0	-76.8	196.2		0.0000180
78.0	-84.7	188.3		0.0000126
80.0	-92.5	180.5	$T = \text{const}$	0.00000861
82.0	-92.5	180.5		0.00000590
84.0	-92.5	180.5		0.00000404
86.0	-92.5	180.5		0.00000276
88.0	-92.5	180.5		0.00000189
90.0	-92.5	180.5		0.00000130

$z$ (km)	$\rho/\rho_{\text{SL}}$
0.0	1.000
0.5	0.942
1.0	0.887
1.5	0.835
2.0	0.785
2.5	0.737
3.0	0.692
3.5	0.649
4.0	0.609
4.5	0.570
5.0	0.533
6.0	0.466
7.0	0.406
8.0	0.352
9.0	0.304
10.0	0.262
11.0	0.224
12.0	0.192
13.0	0.164
14.0	0.140
15.0	0.120
16.0	0.102
17.0	0.0873
18.0	0.0747
19.0	0.0638
20.0	0.0546
22.0	0.0400
24.0	0.0293
26.0	0.0216
28.0	0.0160
30.0	0.0118
40.0	0.00283
50.0	0.000787
60.0	0.000222
70.0	0.0000545
80.0	0.0000102
90.0	0.00000162

## Problem 3.43

[Difficulty: 3]

**3.43** On a certain calm day, a mild inversion causes the atmospheric temperature to remain constant at 30°C between sea level and 5000-m altitude. Under these conditions, (a) calculate the elevation change for which a 3 percent reduction in air pressure occurs, (b) determine the change of elevation necessary to effect a 5 percent reduction in density, and (c) plot  $p_2/p_1$  and  $\rho_2/\rho_1$  as a function of  $\Delta z$ .

**Given:** Data on isothermal atmosphere

**Find:** Elevation changes for 3% pressure change and 5% density change; plot of pressure and density versus elevation

**Solution:**

**Assumptions:** Static, isothermal fluid,;  $g = \text{constant}$ ; ideal gas behavior

**Basic equations**

$$\frac{dp}{dz} = -\rho \cdot g \quad \text{and} \quad p = \rho \cdot R \cdot T$$

Then

$$\frac{dp}{dz} = -\rho \cdot g = -\frac{p \cdot g}{R_{\text{air}} \cdot T} \quad \text{and} \quad \frac{dp}{p} = -\frac{g}{R_{\text{air}} \cdot T} \cdot dz$$

Integrating

$$\Delta z = -\frac{R_{\text{air}} \cdot T_0}{g} \cdot \ln\left(\frac{p_2}{p_1}\right) \quad \text{where} \quad T = T_0$$

For an ideal gas with T constant

$$\frac{p_2}{p_1} = \frac{\rho_2 \cdot R_{\text{air}} \cdot T}{\rho_1 \cdot R_{\text{air}} \cdot T} = \frac{\rho_2}{\rho_1} \quad \text{so} \quad \Delta z = -\frac{R_{\text{air}} \cdot T_0}{g} \cdot \ln\left(\frac{\rho_2}{\rho_1}\right) = -C \cdot \ln\left(\frac{\rho_2}{\rho_1}\right) \quad (1)$$

From Table A.6

$$R_{\text{air}} = 287 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}}$$

Evaluating

$$C = \frac{R_{\text{air}} \cdot T_0}{g} = 287 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times (30 + 273) \cdot \text{K} \times \frac{1}{9.81} \cdot \frac{\text{s}^2}{\text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad C = 8865 \cdot \text{m}$$

For a 3% reduction in pressure


$$\frac{p_2}{p_1} = 0.97 \quad \text{so from Eq. 1} \quad \Delta z = -8865 \cdot \text{m} \cdot \ln(0.97) \quad \Delta z = 270 \cdot \text{m}$$

For a 5% reduction in density

$$\frac{\rho_2}{\rho_1} = 0.95 \quad \text{so from Eq. 1} \quad \Delta z = -8865 \cdot \text{m} \cdot \ln(0.95) \quad \Delta z = 455 \cdot \text{m}$$

To plot  $\frac{p_2}{p_1}$  and  $\frac{\rho_2}{\rho_1}$  we rearrange Eq. 1

$$\frac{p_2}{p_1} = \frac{\rho_2}{\rho_1} = e^{-\frac{\Delta z}{C}}$$



This plot can be plotted in Excel

## Problem 3.44

[Difficulty: 3]

**3.44** At ground level in Denver, Colorado, the atmospheric pressure and temperature are 83.2 kPa and 25°C. Calculate the pressure on Pike's Peak at an elevation of 2690 m above the city assuming (a) an incompressible and (b) an adiabatic atmosphere. Plot the ratio of pressure to ground level pressure in Denver as a function of elevation for both cases.

**Given:** Atmospheric conditions at ground level ( $z = 0$ ) in Denver, Colorado are  $p_0 = 83.2$  kPa,  $T_0 = 25^\circ\text{C}$ . Pike's peak is at elevation  $z = 2690$  m.

**Find:**  $p/p_0$  vs  $z$  for both cases.

**Solution:**

**Governing Equations:**  $\frac{dp}{dz} = -\rho \cdot g$        $p = \rho \cdot R \cdot T$

**Assumptions:** (1) Static fluid  
(2) Ideal gas behavior

(a) For an incompressible atmosphere:

$$\frac{dp}{dz} = -\rho \cdot g \quad \text{becomes} \quad p - p_0 = -\int_0^z \rho \cdot g \, dz \quad \text{or} \quad p = p_0 - \rho_0 \cdot g \cdot z = p_0 \cdot \left(1 - \frac{g \cdot z}{R \cdot T_0}\right) \quad (1)$$

At  $z = 2690$ -m  $p = 83.2 \cdot \text{kPa} \times \left(1 - 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2690 \cdot \text{m} \times \frac{\text{kg} \cdot \text{K}}{287 \cdot \text{N} \cdot \text{m}} \times \frac{1}{298 \cdot \text{K}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}\right)$   $p = 57.5 \cdot \text{kPa}$

(b) For an adiabatic atmosphere:  $\frac{p}{\rho^k} = \text{const}$        $\rho = \rho_0 \cdot \left(\frac{p}{p_0}\right)^{\frac{1}{k}}$


$$\frac{dp}{dz} = -\rho \cdot g \quad \text{becomes} \quad dp = -\rho_0 \cdot \left(\frac{p}{p_0}\right)^{\frac{1}{k}} \cdot g \cdot dz \quad \text{or} \quad \frac{1}{p^{\frac{1}{k}}} dp = -\frac{\rho_0 \cdot g}{p_0^{\frac{1}{k}}} \cdot dz$$

But  $\int_{p_0}^p \frac{1}{p^{\frac{1}{k}}} dp = \frac{k}{k-1} \cdot (p - p_0)^{\frac{k-1}{k}}$       hence  $\frac{k}{k-1} \cdot \left(p^{\frac{k-1}{k}} - p_0^{\frac{k-1}{k}}\right) = -\frac{\rho_0 \cdot g}{p_0^{\frac{1}{k}}} \cdot g \cdot z$

Solving for the pressure ratio  $\frac{p}{p_0} = \left(1 - \frac{k-1}{k} \cdot \frac{\rho_0}{p_0} \cdot g \cdot z\right)^{\frac{k}{k-1}}$       or  $\frac{p}{p_0} = \left(1 - \frac{k-1}{k} \cdot \frac{g \cdot z}{R \cdot T_0}\right)^{\frac{k}{k-1}} \quad (2)$

At  $z = 2690$ -m  $p = 83.2 \cdot \text{kPa} \times \left(1 - \frac{1.4-1}{1.4} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2690 \cdot \text{m} \times \frac{\text{kg} \cdot \text{K}}{287 \cdot \text{N} \cdot \text{m}} \times \frac{1}{298 \cdot \text{K}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}\right)^{\frac{1.4}{1.4-1}}$   $p = 60.2 \cdot \text{kPa}$

Equations 1 and 2 can be plotted:



## Problem 3.45

[Difficulty: 3]

**3.45** The Martian atmosphere behaves as an ideal gas with mean molecular mass of 32.0 and constant temperature of 200 K. The atmospheric density at the planet surface is  $\rho = 0.015 \text{ kg/m}^3$  and Martian gravity is  $3.92 \text{ m/s}^2$ . Calculate the density of the Martian atmosphere at height  $z = 20 \text{ km}$  above the surface. Plot the ratio of density to surface density as a function of elevation. Compare with that for data on the Earth's atmosphere.

**Given:** Martian atmosphere behaves as an ideal gas, constant temperature

$$M_m = 32.0 \quad T = 200 \cdot \text{K} \quad g = 3.92 \cdot \frac{\text{m}}{\text{s}^2} \quad \rho_0 = 0.015 \cdot \frac{\text{kg}}{\text{m}^3}$$

**Find:** Density at  $z = 20 \text{ km}$   
Plot the ratio of density to sea level density versus altitude, compare to that of earth.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dz} = -\rho \cdot g \quad (\text{Hydrostatic Pressure - } z \text{ is positive upwards})$$

$$p = \rho \cdot R \cdot T \quad (\text{Ideal Gas Equation of State})$$

$$R = \frac{R_u}{M_m} \quad (\text{Definition of Gas Constant})$$

**Assumptions:**

- (1) Static fluid
- (2) Constant gravitational acceleration
- (3) Ideal gas behavior

Taking the differential of the equation of state (constant temperature):  $dp = R \cdot T \cdot d\rho$

Substituting into the hydrostatic pressure equation:  $R \cdot T \cdot \frac{d\rho}{dz} = -\rho \cdot g$  Therefore:  $\frac{d\rho}{\rho} = -\frac{g}{R \cdot T} \cdot dz$

Integrating this expression:  $\int_{\rho_0}^{\rho} \frac{1}{\rho} d\rho = -\int_0^z \frac{g}{R \cdot T} dz$   $\ln\left(\frac{\rho}{\rho_0}\right) = -\frac{g \cdot z}{R \cdot T}$  or  $\frac{\rho}{\rho_0} = e^{-\frac{g \cdot z}{R \cdot T}}$  (1)


Evaluating:  $R = 8314.3 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{mol} \cdot \text{K}} \times \frac{1}{32.0} \cdot \frac{\text{kg} \cdot \text{mol}}{\text{kg}}$   $R = 259.822 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}}$

$$\rho = 0.015 \cdot \frac{\text{kg}}{\text{m}^3} \times e^{-\left(3.92 \cdot \frac{\text{m}}{\text{s}^2} \times 20 \times 10^3 \cdot \text{m} \times \frac{1}{259.822} \cdot \frac{\text{kg} \cdot \text{K}}{\text{N} \cdot \text{m}} \times \frac{1}{200} \cdot \frac{1}{\text{K}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}\right)}$$

$$\rho = 3.32 \times 10^{-3} \frac{\text{kg}}{\text{m}^3}$$

For the Martian atmosphere, let  $x = \frac{g}{R \cdot T}$   $x = 3.92 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{1}{259.822} \cdot \frac{\text{kg} \cdot \text{K}}{\text{N} \cdot \text{m}} \times \frac{1}{200} \cdot \frac{1}{\text{K}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $x = 0.07544 \cdot \frac{1}{\text{km}}$

Therefore:  $\frac{\rho}{\rho_0} = e^{-x \cdot z}$       These data are plotted along with the data for Earth's atmosphere from Table A.3.



## Problem 3.46

[Difficulty: 3]

**3.46** A door 1 m wide and 1.5 m high is located in a plane vertical wall of a water tank. The door is hinged along its upper edge, which is 1 m below the water surface. Atmospheric pressure acts on the outer surface of the door and at the water surface. (a) Determine the magnitude and line of action of the total resultant force from all fluids acting on the door. (b) If the water surface gage pressure is raised to 0.3 atm, what is the resultant force and where is its line of action? (c) Plot the ratios  $F/F_0$  and  $y'/y_c$  for different values of the surface pressure ratio  $p_s/p_{atm}$ . ( $F_0$  is the resultant force when  $p_s = p_{atm}$ .)

**Given:** Door located in plane vertical wall of water tank as shown

$$a = 1.5\text{ m} \quad b = 1\text{ m} \quad c = 1\text{ m}$$


Atmospheric pressure acts on outer surface of door.

**Find:** Resultant force and line of action:

(a) for  $p_s = p_{atm}$

(b) for  $p_{sg} = 0.3 \cdot \text{atm}$

Plot  $F/F_0$  and  $y'/y_c$  over range of  $p_s/p_{atm}$  ( $F_0$  is force determined in (a),  $y_c$  is y-coordinate of door centroid).



**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dy} = \rho \cdot g \quad \text{(Hydrostatic Pressure - } y \text{ is positive downwards)}$$

$$F_R = \int p \, dA \quad \text{(Hydrostatic Force on door)}$$

$$y' \cdot F_R = \int y \cdot p \, dA \quad \text{(First moment of force)}$$

**Assumptions:** (1) Static fluid  
(2) Incompressible fluid

We will obtain a general expression for the force and line of action, and then simplify for parts (a) and (b).

Since  $dp = \rho \cdot g \cdot dh$  it follows that  $p = p_s + \rho \cdot g \cdot y$

Now because  $p_{atm}$  acts on the outside of the door,  $p_{sg}$  is the surface gage pressure:  $p = p_{sg} + \rho \cdot g \cdot y$

$$F_R = \int p \, dA = \int_c^{c+a} p \cdot b \, dy = \int_c^{c+a} (p_{sg} + \rho \cdot g \cdot y) \cdot b \, dy = b \cdot \left[ p_{sg} \cdot a + \frac{\rho \cdot g}{2} \cdot (a^2 + 2 \cdot a \cdot c) \right] \quad (1)$$

$$y' \cdot F_R = \int y \cdot p \, dA \quad \text{Therefore:} \quad y' = \frac{1}{F_R} \int y \cdot p \, dA = \frac{1}{F_R} \cdot \int_c^{c+a} y \cdot (p_{sg} + \rho \cdot g \cdot y) \cdot b \, dy$$

$$\text{Evaluating the integral:} \quad y' = \frac{b}{F_R} \left[ \frac{p_{sg}}{2} [(c+a)^2 - c^2] + \frac{\rho \cdot g}{3} [(c+a)^3 - c^3] \right]$$

$$\text{Simplifying: } y' = \frac{b}{F_R} \cdot \left[ \frac{p_{sg}}{2} (a^2 + 2 \cdot a \cdot c) + \frac{\rho \cdot g}{3} \cdot [a^3 + 3 \cdot a \cdot c \cdot (a + c)] \right] \quad (2)$$

For part (a) we know  $p_{sg} = 0$  so substituting into (1) we get:  $F_o = \frac{\rho \cdot g \cdot b}{2} \cdot (a^2 + 2 \cdot a \cdot c)$

$$F_o = \frac{1}{2} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1 \cdot \text{m} \times [(1.5 \cdot \text{m})^2 + 2 \times 1.5 \cdot \text{m} \times 1 \cdot \text{m}] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_o = 25.7 \cdot \text{kN}$$

Substituting into (2) for the line of action we get:  $y' = \frac{\rho \cdot g \cdot b}{3 \cdot F_o} \cdot [a^3 + 3 \cdot a \cdot c \cdot (a + c)]$

$$y' = \frac{1}{3} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1 \cdot \text{m} \cdot \frac{1}{25.7 \times 10^3 \text{ N}} \cdot \frac{1}{\text{N}} \times [(1.5 \cdot \text{m})^3 + 3 \times 1.5 \cdot \text{m} \times 1 \cdot \text{m} \times (1.5 \cdot \text{m} + 1 \cdot \text{m})] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad y' = 1.9 \text{ m}$$

For part (b) we know  $p_{sg} = 0.3 \cdot \text{atm}$  . Substituting into (1) we get:

$$F_R = 1 \cdot \text{m} \times \left[ 0.3 \cdot \text{atm} \times \frac{1.013 \times 10^5 \cdot \text{N}}{\text{m}^2 \cdot \text{atm}} \times 1.5 \cdot \text{m} + \frac{1}{2} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times [(1.5 \cdot \text{m})^2 + 2 \times 1.5 \cdot \text{m} \times 1 \cdot \text{m}] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right]$$

$$F_R = 71.3 \cdot \text{kN}$$

$$y' = \frac{1 \cdot \text{m} \times \left[ \frac{0.3 \cdot \text{atm}}{2} \times \frac{1.013 \times 10^5 \cdot \text{N}}{\text{m}^2 \cdot \text{atm}} \times [(1.5)^2 + 2 \cdot 1.5 \cdot 1] \cdot \text{m}^2 + \frac{999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2}}{3} \times [(1.5)^3 + 3 \cdot 1.5 \cdot 1 \cdot (1.5 + 1)] \cdot \text{m}^3 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right]}{71.3 \times 10^3 \cdot \text{N}}$$

$$y' = 1.789 \text{ m}$$

The value of  $F/F_o$  is obtained from Eq. (1) and our result from part (a):

$$\frac{F}{F_o} = \frac{b \cdot \left[ p_{sg} \cdot a + \frac{\rho \cdot g}{2} \cdot (a^2 + 2 \cdot a \cdot c) \right]}{\frac{\rho \cdot g \cdot b}{2} \cdot (a^2 + 2 \cdot a \cdot c)} = 1 + \frac{2 \cdot p_{sg}}{\rho \cdot g \cdot (a + 2 \cdot c)}$$

For the gate  $y_c = c + \frac{a}{2}$  Therefore, the value of  $y'/y_c$  is obtained from Eqs. (1) and (2):



$$\frac{y'}{y_c} = \frac{2 \cdot b}{F_R \cdot (2 \cdot c + a)} \cdot \left[ \frac{p_{sg}}{2} (a^2 + 2 \cdot a \cdot c) + \frac{\rho \cdot g}{3} \cdot [a^3 + 3 \cdot a \cdot c \cdot (a + c)] \right] = \frac{2 \cdot b}{(2 \cdot c + a)} \cdot \frac{\left[ \frac{p_{sg}}{2} (a^2 + 2 \cdot a \cdot c) + \frac{\rho \cdot g}{3} \cdot [a^3 + 3 \cdot a \cdot c \cdot (a + c)] \right]}{\left[ b \cdot \left[ p_{sg} \cdot a + \frac{\rho \cdot g}{2} \cdot (a^2 + 2 \cdot a \cdot c) \right] \right]}$$

Simplifying this expression we get:

$$\frac{y'}{y_c} = \frac{2}{(2 \cdot c + a)} \cdot \frac{\frac{p_{sg}(a^2 + 2 \cdot a \cdot c)}{2} + \frac{\rho \cdot g}{3} \cdot [a^3 + 3 \cdot a \cdot c \cdot (a + c)]}{p_{sg} \cdot a + \frac{\rho \cdot g}{2} \cdot (a^2 + 2 \cdot a \cdot c)}$$

Based on these expressions we see that the force on the gate varies linearly with the increase in surface pressure, and that the line of action of the resultant is always below the centroid of the gate. As the pressure increases, however, the line of action moves closer to the centroid.

Plots of both ratios are shown below:



## Problem 3.47

[Difficulty: 2]

**3.47** A door 1 m wide and 1.5 m high is located in a plane vertical wall of a water tank. The door is hinged along its upper edge, which is 1 m below the water surface. Atmospheric pressure acts on the outer surface of the door. (a) If the pressure at the water surface is atmospheric, what force must be applied at the lower edge of the door in order to keep the door from opening? (b) If the water surface gage pressure is raised to 0.5 atm, what force must be applied at the lower edge of the door to keep the door from opening? (c) Find the ratio  $F/F_0$  as a function of the surface pressure ratio  $p_s/p_{atm}$ . ( $F_0$  is the force required when  $p_s = p_{atm}$ .)

**Given:** Door of constant width, located in plane vertical wall of water tank is hinged along upper edge.

$$b = 1 \cdot \text{m} \quad D = 1 \cdot \text{m} \quad L = 1.5 \cdot \text{m}$$


Atmospheric pressure acts on outer surface of door; force  $F$  is applied at lower edge to keep door closed.

**Find:** (a) Force  $F$ , if  $p_s = p_{atm}$

(b) Force  $F$ , if  $p_{sg} = 0.5 \cdot \text{atm}$

Plot  $F/F_0$  over range of  $p_s/p_{atm}$  ( $F_0$  is force determined in (a)).

**Solution:** We will apply the hydrostatics equations to this system.



**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards})$$

$$F_R = \int p \, dA \quad (\text{Hydrostatic Force on door})$$

$$\Sigma M_Z = 0 \quad (\text{Rotational Equilibrium})$$

**Assumptions:**

- (1) Static fluid
- (2) Constant density
- (3) Door is in equilibrium

Taking moments about the hinge: 
$$-F \cdot L + \int y \cdot p \, dA = 0 \quad dA = b \cdot dy$$

Solving for the force: 
$$F = \frac{1}{L} \cdot \int_0^L b \cdot y \cdot p \, dy \quad (1) \quad \text{We will obtain a general expression for } F \text{ and then simplify for parts (a) and (b).}$$

Since  $dp = \rho \cdot g \cdot dh$  it follows that  $p = p_s + \rho \cdot g \cdot h$  where  $h = D + y$

and hence  $p = p_s + \rho \cdot g \cdot (D + y)$  Now because  $p_{atm}$  acts on the outside of the door,  $p_{sg}$  is the surface gage pressure.

From Equation (1): 
$$F = \frac{1}{L} \cdot \int_0^L b \cdot y \cdot [p_{sg} + \rho \cdot g \cdot (D + y)] \, dy \quad F = \frac{b}{L} \cdot \int_0^L [(p_{sg} + \rho \cdot g \cdot D) \cdot y + \rho \cdot g \cdot y^2] \, dy$$

After integrating:  $F = \frac{b}{L} \left[ (p_{sg} + \rho \cdot g \cdot D) \cdot \frac{L^2}{2} + \rho \cdot g \cdot \frac{L^3}{3} \right]$  or  $F = b \cdot \left[ p_{sg} \cdot \frac{L}{2} + \rho \cdot g \cdot L \cdot \left( \frac{D}{2} + \frac{L}{3} \right) \right]$  (2)

(a) For  $p_s = p_{atm}$  it follows that  $p_{sg} = 0$  Therefore:  $F_o = \rho \cdot g \cdot b \cdot L \cdot \left( \frac{D}{2} + \frac{L}{3} \right)$  (3)


$$F_o = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1 \cdot \text{m} \times 1.5 \cdot \text{m} \times \left( \frac{1 \cdot \text{m}}{2} + \frac{1.5 \cdot \text{m}}{3} \right) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_o = 14.7 \cdot \text{kN}$$

(b) For  $p_{sg} = 0.5 \cdot \text{atm}$  we substitute variables:

$$F = 1 \cdot \text{m} \times \left[ 0.5 \cdot \text{atm} \times \frac{101 \cdot \text{kPa}}{\text{atm}} \times \frac{1.5 \cdot \text{m}}{2} + 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1.5 \cdot \text{m} \times \left( \frac{1 \cdot \text{m}}{2} + \frac{1.5 \cdot \text{m}}{3} \right) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right] \quad F = 52.6 \cdot \text{kN}$$

From Equations (2) and (3) we have:  $\frac{F}{F_o} = \frac{b \cdot \left[ p_{sg} \cdot \frac{L}{2} + \rho \cdot g \cdot L \cdot \left( \frac{D}{2} + \frac{L}{3} \right) \right]}{\rho \cdot g \cdot b \cdot L \cdot \left( \frac{D}{2} + \frac{L}{3} \right)} = 1 + \frac{p_{sg}}{2 \cdot \rho \cdot g \cdot \left( \frac{D}{2} + \frac{L}{3} \right)}$

Here is a plot of the force ratio as a function of the surface pressure:



## Problem 3.48

[Difficulty: 5]

**3.48** A hydropneumatic elevator consists of a piston-cylinder assembly to lift the elevator cab. Hydraulic oil, stored in an accumulator tank pressurized by air, is valved to the piston as needed to lift the elevator. When the elevator descends, oil is returned to the accumulator. Design the least expensive accumulator that can satisfy the system requirements. Assume the lift is 3 floors, the maximum load is 10 passengers, and the maximum system pressure is 800 kPa (gage). For column bending strength, the piston diameter must be at least 150 mm. The elevator cab and piston have a combined mass of 3000 kg, and are to be purchased. Perform the analysis needed to define, as a function of system operating pressure, the piston diameter, the accumulator volume and diameter, and the wall thickness. Discuss safety features that your company should specify for the complete elevator system. Would it be preferable to use a completely pneumatic design or a completely hydraulic design? Why?

**Discussion:** The design requirements are specified except that a typical floor height is about 12 ft, making the total required lift about 36 ft. A spreadsheet was used to calculate the system properties for various pressures. Results are presented on the next page, followed by a sample calculation. Total cost dropped quickly as system pressure was increased. A shallow minimum was reached in the 100-110 psig range. The lowest-cost solution was obtained at a system pressure of about 100 psig. At this pressure, the reservoir of 140 gal required a 3.30 ft diameter pressure sphere with a 0.250 in wall thickness. The welding cost was \$155 and the material cost \$433, for a total cost of \$588. Accumulator wall thickness was constrained at 0.250 in for pressures below 100 psi; it increased for higher pressures (this caused the discontinuity in slope of the curve at 100 psig). The mass of steel became constant above 110 psig. No allowance was made for the extra volume needed to pressurize the accumulator. Fail-safe design is essential for an elevator to be used by the public. The control circuitry should be redundant. Failures must be easy to spot. For this reason, hydraulic actuation is good: leaks will be readily apparent. The final design must be reviewed, approved, and stamped by a professional engineer since the design involves public safety. The terminology used in the solution is defined in the following table:

Symbol	Definition	Units
$p$	System pressure	psig
$A_p$	Area of lift piston	in <sup>2</sup>
$V_{oil}$	Volume of oil	gal
$D_s$	Diameter of spherical accumulator	ft
$t$	Wall thickness of accumulator	in
$A_w$	Area of weld	in <sup>2</sup>
$C_w$	Cost of weld	\$
$M_s$	Mass of steel accumulator	lbm
$C_s$	Cost of steel	\$
$C_t$	Total Cost	\$

A sample calculation and the results of the system simulation in Excel are presented below.


Sample calculation for a pressure of 20 psig:

$$W_t = p \cdot A_p \quad A_p = \frac{W_t}{p} \quad A_p = 7500 \cdot \text{lbf} \times \frac{1}{20} \cdot \frac{\text{in}^2}{\text{lbf}} \quad A_p = 375 \cdot \text{in}^2$$

$$V_{\text{oil}} = A_p \cdot L \quad V_{\text{oil}} = 375 \cdot \text{in}^2 \times 36 \cdot \text{ft} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \times \frac{7.48 \cdot \text{gal}}{\text{ft}^3} \quad V_{\text{oil}} = 701 \cdot \text{gal}$$

$$V_{\text{oil}} = V_s = \frac{4}{3} \cdot \pi \cdot R_s^3 = \frac{\pi}{6} \cdot D_s^3 \quad D_s = \left( \frac{6 \cdot V_{\text{oil}}}{\pi} \right)^{\frac{1}{3}} \quad D_s = \left( \frac{6}{\pi} \times 701 \cdot \text{gal} \times \frac{\text{ft}^3}{7.48 \cdot \text{gal}} \right)^{\frac{1}{3}} \quad D_s = 5.64 \cdot \text{ft}$$

From a force balance on the sphere:



$$\text{Thus: } p \cdot \pi \cdot \frac{D_s^2}{4} = \pi \cdot D_s \cdot t \cdot \sigma, \text{ so } t = \frac{p}{\sigma} \cdot \frac{D_s}{4} \quad t = 20 \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{1}{4000} \cdot \frac{\text{in}^2}{\text{lbf}} \times \frac{5.64 \cdot \text{ft}}{4} \times \frac{12 \cdot \text{in}}{\text{ft}} \quad t = 0.085 \cdot \text{in}$$

Since the minimum wall thickness is 0.250 in:

$$t = 0.250 \cdot \text{in}$$

$$A_w = \pi \cdot D_s \cdot t \quad A_w = \pi \cdot 5.64 \cdot \text{ft} \cdot 0.250 \cdot \text{in} \cdot \frac{12 \cdot \text{in}}{\text{ft}} \quad A_w = 53.2 \cdot \text{in}^2$$

$$C_w = 5.00 \cdot \frac{1}{\text{in}^2} \times 53.2 \cdot \text{in}^2 \quad (\text{cost in } \$) \quad C_w = 266$$

$$M_s = 4 \cdot \pi \cdot R_s^2 \cdot t \cdot \rho_s = \pi \cdot D_s^2 \cdot t \cdot SG_s \cdot \rho_{\text{water}}$$

$$M_s = \pi \times (5.64 \cdot \text{ft})^2 \times 0.250 \cdot \text{in} \times \frac{\text{ft}}{12 \cdot \text{in}} \times 7.8 \times 62.4 \cdot \frac{\text{lbm}}{\text{ft}^3} \quad M_s = 1013 \cdot \text{lbm}$$

$$C_s = 1.25 \cdot \frac{1}{\text{lbm}} \times 1013 \cdot \text{lbm} \quad (\text{cost in } \$) \quad C_s = 1266$$

Therefore the total cost is:


$$C_t = 266 + 1266 \quad (\text{cost in } \$) \quad C_t = 1532$$

### Results of system simulation:

<b>Input Data:</b>	Cab and piston weight:	$W_{cab} =$	6000	lbf
	Passenger weight:	$W_{pax} =$	1500	lbf
	Total weight:	$W_{tot} =$	7500	lbf
	Allowable stress:	$\sigma =$	4000	psi
	Minimum wall thickness:	$t =$	0.250	in
	Welding cost factor:	$cf_w =$	5.00	\$/in <sup>2</sup>
	Steel cost factor:	$cf_s =$	1.25	\$/pound

**Results:**


$p$ (psig)	$A_p$ (in <sup>2</sup> )	$V_{oil}$ (gal)	$D_s$ (ft)	$t$ (in)	$A_w$ (in <sup>2</sup> )	$C_w$	$M_s$ (lbm)	$C_s$	$C_t$
20	375	701	5.64	0.250	53.1	\$266	1012	\$1,265	\$1,531
30	250	468	4.92	0.250	46.4	\$232	772	\$965	\$1,197
40	187.5	351	4.47	0.250	42.2	\$211	638	\$797	\$1,008
50	150.0	281	4.15	0.250	39.1	\$196	549	\$687	\$882
60	125.0	234	3.91	0.250	36.8	\$184	487	\$608	\$792
70	107.1	200	3.71	0.250	35.0	\$175	439	\$549	\$724
80	93.8	175.3	3.55	0.250	33.5	\$167	402	\$502	\$669
90	83.3	155.8	3.41	0.250	32.2	\$161	371	\$464	\$625
100	75.0	140.3	3.30	0.250	31.1	\$155	346	\$433	\$588
110	68.2	127.5	3.19	0.263	31.7	\$159	342	\$428	\$586
120	62.5	116.9	3.10	0.279	32.6	\$163	342	\$428	\$591
130	57.7	107.9	3.02	0.294	33.5	\$168	342	\$428	\$595



## Problem 3.49

[Difficulty: 2]

**3.49** Find the pressures at points *A*, *B*, and *C*, as shown in the figure, and in the two air cavities.



**Given:** Geometry of chamber system

**Find:** Pressure at various locations

**Assumptions:** (1) Water and Meriam Blue are static and incompressible  
(2) Pressure gradients across air cavities are negligible

**Solution:**

Basic equation  $\frac{dp}{dy} = -\rho \cdot g$  or, for constant  $\rho$   $\Delta p = \rho \cdot g \cdot \Delta h$  where  $\Delta h$  is height difference

For point A  $p_A = p_{atm} + \rho_{H_2O} \cdot g \cdot h_1$  or in gage pressure  $p_A = \rho_{H_2O} \cdot g \cdot h_1$

Here we have  $h_1 = 8 \cdot \text{in}$   $h_1 = 0.667 \cdot \text{ft}$

$$p_A = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 0.667 \cdot \text{ft} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_A = 0.289 \cdot \text{psi} \quad (\text{gage})$$

For the first air cavity  $p_{air1} = p_A - SG_{MB} \cdot \rho_{H_2O} \cdot g \cdot h_2$  where  $h_2 = 4 \cdot \text{in}$   $h_2 = 0.333 \cdot \text{ft}$

From Table A.1  $SG_{MB} = 1.75$

$$p_{air1} = 0.289 \cdot \frac{\text{lb} \cdot \text{ft}}{\text{in}^2} - 1.75 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 0.333 \cdot \text{ft} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_{air1} = 0.036 \cdot \text{psi} \quad (\text{gage})$$

Note that  $p = \text{constant}$  throughout the air pocket

For point B  $p_B = p_{air1} + SG_{Hg} \cdot \rho_{H_2O} \cdot g \cdot h_3$  where  $h_3 = 6 \cdot \text{in}$   $h_3 = 0.5 \cdot \text{ft}$

$$p_B = 0.036 \cdot \frac{\text{lb} \cdot \text{ft}}{\text{in}^2} + 1.75 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 0.5 \cdot \text{ft} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_B = 0.416 \cdot \text{psi} \quad (\text{gage})$$

For point C  $p_C = p_{air2} + SG_{Hg} \cdot \rho_{H_2O} \cdot g \cdot h_4$  where  $h_4 = 10 \cdot \text{in}$   $h_4 = 0.833 \cdot \text{ft}$

$$p_C = 0.416 \cdot \frac{\text{lb} \cdot \text{ft}}{\text{in}^2} + 1.75 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 0.833 \cdot \text{ft} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_C = 1.048 \cdot \text{psi} \quad (\text{gage})$$


For the second air cavity  $p_{air2} = p_C - SG_{Hg} \cdot \rho_{H_2O} \cdot g \cdot h_5$  where  $h_5 = 6 \cdot \text{in}$   $h_5 = 0.5 \cdot \text{ft}$

$$p_{air2} = 1.048 \cdot \frac{\text{lb} \cdot \text{ft}}{\text{in}^2} - 1.75 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 0.5 \cdot \text{ft} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_{air2} = 0.668 \cdot \text{psi} \quad (\text{gage})$$

### Problem 3.50


[Difficulty: 3]

**3.50** Semicircular plane gate  $AB$  is hinged along  $B$  and held by horizontal force  $F_A$  applied at  $A$ . The liquid to the left of the gate is water. Calculate the force  $F_A$  required for equilibrium.



**Given:** Geometry of gate

**Find:** Force  $F_A$  for equilibrium



**Solution:**

Basic equation  $F_R = \int p \, dA$        $\frac{dp}{dh} = \rho \cdot g$        $\Sigma M_z = 0$

or, use computing equations  $F_R = p_c \cdot A$        $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$       where  $y$  would be measured from the free surface

Assumptions: static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side; door is in equilibrium

Instead of using either of these approaches, we note the following, using  $y$  as in the sketch

$$\Sigma M_z = 0 \quad F_A \cdot R = \int y \cdot p \, dA \quad \text{with} \quad p = \rho \cdot g \cdot h \quad \text{(Gage pressure, since } p = p_{\text{atm}} \text{ on other side)}$$

$$F_A = \frac{1}{R} \cdot \int y \cdot \rho \cdot g \cdot h \, dA \quad \text{with} \quad dA = r \cdot dr \cdot d\theta \quad \text{and} \quad y = r \cdot \sin(\theta) \quad h = H - y$$

Hence 
$$F_A = \frac{1}{R} \cdot \int_0^\pi \int_0^R \rho \cdot g \cdot r \cdot \sin(\theta) \cdot (H - r \cdot \sin(\theta)) \cdot r \, dr \, d\theta = \frac{\rho \cdot g}{R} \cdot \int_0^\pi \left( \frac{H \cdot R^3}{3} \cdot \sin(\theta) - \frac{R^4}{4} \cdot \sin(\theta)^2 \right) d\theta$$


$$F_R = \frac{\rho \cdot g}{R} \cdot \left( \frac{2 \cdot H \cdot R^3}{3} - \frac{\pi \cdot R^4}{8} \right) = \rho \cdot g \cdot \left( \frac{2 \cdot H \cdot R^2}{3} - \frac{\pi \cdot R^3}{8} \right)$$

Using given data 
$$F_R = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \left[ \frac{2}{3} \times 25 \cdot \text{ft} \times (10 \cdot \text{ft})^2 - \frac{\pi}{8} \times (10 \cdot \text{ft})^3 \right] \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_R = 7.96 \times 10^4 \cdot \text{lbf}$$

## Problem 3.51

[Difficulty: 2]

**3.51** A triangular access port must be provided in the side of a form containing liquid concrete. Using the coordinates and dimensions shown, determine the resultant force that acts on the port and its point of application.



**Given:** Geometry of access port

**Find:** Resultant force and location

**Solution:**

Basic equation  $F_R = \int p \, dA$        $\frac{dp}{dy} = \rho \cdot g$        $\Sigma M_S = y' \cdot F_R = \int y \, dF_R = \int y \cdot p \, dA$

or, use computing equations  $F_R = p_c \cdot A$        $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$

We will show both methods

**Assumptions:** Static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side

$$F_R = \int p \, dA = \int SG \cdot \rho \cdot g \cdot y \, dA \quad \text{but} \quad dA = w \cdot dy \quad \text{and} \quad \frac{w}{b} = \frac{y}{a} \quad w = \frac{b}{a} \cdot y$$

Hence 
$$F_R = \int_0^a SG \cdot \rho \cdot g \cdot y \cdot \frac{b}{a} \cdot y \, dy = \int_0^a SG \cdot \rho \cdot g \cdot \frac{b}{a} \cdot y^2 \, dy = \frac{SG \cdot \rho \cdot g \cdot b \cdot a^2}{3}$$

Alternatively  $F_R = p_c \cdot A$       and       $p_c = SG \cdot \rho \cdot g \cdot y_c = SG \cdot \rho \cdot g \cdot \frac{2}{3} \cdot a$       with       $A = \frac{1}{2} \cdot a \cdot b$

Hence 
$$F_R = \frac{SG \cdot \rho \cdot g \cdot b \cdot a^2}{3}$$

For  $y'$  
$$y' \cdot F_R = \int y \cdot p \, dA = \int_0^a SG \cdot \rho \cdot g \cdot \frac{b}{a} \cdot y^3 \, dy = \frac{SG \cdot \rho \cdot g \cdot b \cdot a^3}{4} \quad y' = \frac{SG \cdot \rho \cdot g \cdot b \cdot a^3}{4 \cdot F_R} = \frac{3}{4} \cdot a$$

Alternatively  $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$       and       $I_{xx} = \frac{b \cdot a^3}{36}$       (Google it!)       $y' = \frac{2}{3} \cdot a + \frac{b \cdot a^3}{36} \cdot \frac{2}{a \cdot b} \cdot \frac{3}{2 \cdot a} = \frac{3}{4} \cdot a$


Using given data, and  $SG = 2.5$  (Table A.1) 
$$F_R = \frac{2.5}{3} \cdot 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 1 \cdot \text{ft} \times (1.25 \cdot \text{ft})^2 \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_R = 81.3 \cdot \text{lb} \cdot \text{ft}$$

and 
$$y' = \frac{3}{4} \cdot a \quad y' = 0.938 \cdot \text{ft}$$

### Problem 3.52


[Difficulty: 3]

**3.52** A plane gate of uniform thickness holds back a depth of water as shown. Find the minimum weight needed to keep the gate closed.



**Given:** Geometry of plane gate

**Find:** Minimum weight to keep it closed



**Solution:**

Basic equation  $F_R = \int p \, dA$        $\frac{dp}{dh} = \rho \cdot g$        $\Sigma M_O = 0$

or, use computing equations  $F_R = p_c \cdot A$        $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$

**Assumptions:** static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side; door is in equilibrium

Instead of using either of these approaches, we note the following, using  $y$  as in the sketch

$$\Sigma M_O = 0 \quad W \cdot \frac{L}{2} \cdot \cos(\theta) = \int y \, dF$$

We also have  $dF = p \cdot dA$     with     $p = \rho \cdot g \cdot h = \rho \cdot g \cdot y \cdot \sin(\theta)$     (Gage pressure, since  $p = p_{\text{atm}}$  on other side)

Hence  $W = \frac{2}{L \cdot \cos(\theta)} \cdot \int y \cdot p \, dA = \frac{2}{L \cdot \cos(\theta)} \cdot \int y \cdot \rho \cdot g \cdot y \cdot \sin(\theta) \cdot w \, dy$

$$W = \frac{2}{L \cdot \cos(\theta)} \cdot \int y \cdot p \, dA = \frac{2 \cdot \rho \cdot g \cdot w \cdot \tan(\theta)}{L} \cdot \int_0^L y^2 \, dy = \frac{2}{3} \cdot \rho \cdot g \cdot w \cdot L^2 \cdot \tan(\theta)$$

Using given data  $W = \frac{2}{3} \cdot 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2 \cdot \text{m} \times (3 \cdot \text{m})^2 \times \tan(30 \cdot \text{deg}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$        $W = 68 \cdot \text{kN}$



To find the line of action of the force:

$$y' \cdot F_R = \int_{R-d}^R y \cdot p \cdot w \, dy = \int_{\alpha}^0 R \cdot \cos(\theta) \cdot \rho \cdot g \cdot R \cdot (\cos(\theta) - \cos(\alpha)) \cdot 2 \cdot R \cdot \sin(\theta) \cdot (-R \cdot \sin(\theta)) \, d\theta$$

Upon simplification:



$$y' \cdot F_R = 2 \cdot \rho \cdot g \cdot R^4 \cdot \int_0^{\alpha} [(\sin(\theta))^2 \cdot (\cos(\theta))^2 - \cos(\alpha) \cdot (\sin(\theta))^2 \cdot \cos(\theta)] \, d\theta = 2 \cdot \rho \cdot g \cdot R^4 \cdot \left[ \frac{1}{8} \cdot \left( \alpha - \frac{\sin(4 \cdot \alpha)}{4} \right) - \cos(\alpha) \cdot \frac{(\sin(\alpha))^3}{3} \right]$$

$$y' \cdot F_R = 2 \cdot \rho \cdot g \cdot R^4 \cdot \left[ \frac{1}{8} \cdot \left( \alpha - \frac{\sin(4 \cdot \alpha)}{4} \right) - \cos(\alpha) \cdot \frac{(\sin(\alpha))^3}{3} \right] \quad \text{and therefore} \quad y' = \frac{y' \cdot F_R}{F_R} \quad \text{or} \quad \frac{y'}{R} = \frac{y' \cdot F_R}{R \cdot F_R}$$

Simplifying the expression:

$$\frac{y'}{R} = \frac{\frac{1}{8} \cdot \left( \alpha - \frac{\sin(4 \cdot \alpha)}{4} \right) - \cos(\alpha) \cdot \frac{(\sin(\alpha))^3}{3}}{\frac{(\sin(\alpha))^3}{3} - \cos(\alpha) \cdot \left( \frac{\alpha}{2} - \frac{\sin(\alpha) \cdot \cos(\alpha)}{2} \right)}$$


Plots of the non-dimensionalized force and the line of action of the force are shown in the plots below:



## Problem 3.54

[Difficulty: 3]

**3.54** A rectangular gate (width  $w = 2$  m) is hinged as shown, with a stop on the lower edge. At what depth  $H$  will the gate tip?



**Given:** Gate geometry

**Find:** Depth  $H$  at which gate tips

**Solution:**

This is a problem with atmospheric pressure on both sides of the plate, so we can first determine the location of the center of pressure with respect to the free surface, using Eq.3.11c (assuming depth  $H$ )

$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} \quad \text{and} \quad I_{xx} = \frac{w \cdot L^3}{12} \quad \text{with} \quad y_c = H - \frac{L}{2}$$

where  $L = 1$  m is the plate height and  $w$  is the plate width

Hence

$$y' = \left( H - \frac{L}{2} \right) + \frac{w \cdot L^3}{12 \cdot w \cdot L \cdot \left( H - \frac{L}{2} \right)} = \left( H - \frac{L}{2} \right) + \frac{L^2}{12 \cdot \left( H - \frac{L}{2} \right)}$$

But for equilibrium, the center of force must always be at or below the level of the hinge so that the stop can hold the gate in place. Hence we must have

$$y' > H - 0.45 \cdot \text{m}$$

Combining the two equations

$$\left( H - \frac{L}{2} \right) + \frac{L^2}{12 \cdot \left( H - \frac{L}{2} \right)} \geq H - 0.45 \cdot \text{m}$$

Solving for  $H$

$$H \leq \frac{L}{2} + \frac{L^2}{12 \cdot \left( \frac{L}{2} - 0.45 \cdot \text{m} \right)} \quad H \leq \frac{1 \cdot \text{m}}{2} + \frac{(1 \cdot \text{m})^2}{12 \times \left( \frac{1 \cdot \text{m}}{2} - 0.45 \cdot \text{m} \right)} \quad H \leq 2.17 \cdot \text{m}$$

## Problem 3.55

[Difficulty: 1]

**3.55** For a mug of tea (65 mm diameter), imagine it cut symmetrically in half by a vertical plane. Find the force that each half experiences due to an 80-mm depth of tea.

**Given:** Geometry of cup

**Find:** Force on each half of cup

**Assumptions:** (1) Tea is static and incompressible  
(2) Atmospheric pressure on outside of cup

**Solution:**

Basic equation 
$$F_R = \int p \, dA \quad \frac{dp}{dh} = \rho \cdot g$$

or, use computing equation 
$$F_R = p_c \cdot A$$

The force on the half-cup is the same as that on a rectangle of size  $h = 8 \cdot \text{cm}$  and  $w = 6.5 \cdot \text{cm}$

$$F_R = \int p \, dA = \int \rho \cdot g \cdot y \, dA \quad \text{but} \quad dA = w \cdot dy$$

Hence 
$$F_R = \int_0^h \rho \cdot g \cdot y \cdot w \, dy = \frac{\rho \cdot g \cdot w \cdot h^2}{2}$$

Alternatively 
$$F_R = p_c \cdot A \quad \text{and} \quad F_R = p_c \cdot A = \rho \cdot g \cdot y_c \cdot A = \rho \cdot g \cdot \frac{h}{2} \cdot h \cdot w = \frac{\rho \cdot g \cdot w \cdot h^2}{2}$$


Using given data 
$$F_R = \frac{1}{2} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 6.5 \cdot \text{cm} \times (8 \cdot \text{cm})^2 \times \left( \frac{\text{m}}{100 \cdot \text{cm}} \right)^3 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_R = 2.04 \cdot \text{N}$$

Hence a teacup is being forced apart by about 2 N: not much of a force, so a paper cup works!

## Problem 3.56

[Difficulty: 3]

**3.56** Gates in the Poe Lock at Sault Ste. Marie, Michigan, close a channel  $W = 34$  m wide,  $L = 360$  m long, and  $D = 10$  m deep. The geometry of one pair of gates is shown; each gate is hinged at the channel wall. When closed, the gate edges are forced together at the center of the channel by water pressure. Evaluate the force exerted by the water on gate A. Determine the magnitude and direction of the force components exerted by the gate on the hinge. (Neglect the weight of the gate.)



**Given:** Geometry of lock system

**Find:** Force on gate; reactions at hinge

**Solution:**

Basic equation 
$$F_R = \int p \, dA \quad \frac{dp}{dh} = \rho \cdot g$$

or, use computing equation 
$$F_R = p_C \cdot A$$

**Assumptions:** static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side

The force on each gate is the same as that on a rectangle of size

$$h = D = 10 \cdot \text{m} \quad \text{and} \quad w = \frac{W}{2 \cdot \cos(15 \cdot \text{deg})}$$

$$F_R = \int p \, dA = \int \rho \cdot g \cdot y \, dA \quad \text{but} \quad dA = w \cdot dy$$

Hence 
$$F_R = \int_0^h \rho \cdot g \cdot y \cdot w \, dy = \frac{\rho \cdot g \cdot w \cdot h^2}{2}$$

Alternatively 
$$F_R = p_C \cdot A \quad \text{and} \quad F_R = p_C \cdot A = \rho \cdot g \cdot y_C \cdot A = \rho \cdot g \cdot \frac{h}{2} \cdot h \cdot w = \frac{\rho \cdot g \cdot w \cdot h^2}{2}$$

Using given data 
$$F_R = \frac{1}{2} \cdot 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{34 \cdot \text{m}}{2 \cdot \cos(15 \cdot \text{deg})} \times (10 \cdot \text{m})^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_R = 8.63 \cdot \text{MN}$$

For the force components  $R_x$  and  $R_y$  we do the following


$$\sum M_{\text{hinge}} = 0 = F_R \cdot \frac{w}{2} - F_n \cdot w \cdot \sin(15 \cdot \text{deg}) \quad F_n = \frac{F_R}{2 \cdot \sin(15 \cdot \text{deg})} \quad F_n = 16.7 \cdot \text{MN}$$

$$\sum F_x = 0 = F_R \cdot \cos(15 \cdot \text{deg}) - R_x = 0 \quad R_x = F_R \cdot \cos(15 \cdot \text{deg}) \quad R_x = 8.34 \cdot \text{MN}$$

$$\sum F_y = 0 = -R_y - F_R \cdot \sin(15 \cdot \text{deg}) + F_n = 0 \quad R_y = F_n - F_R \cdot \sin(15 \cdot \text{deg}) \quad R_y = 14.4 \cdot \text{MN}$$

$$R = (8.34 \cdot \text{MN}, 14.4 \cdot \text{MN})$$

$$R = 16.7 \cdot \text{MN}$$



## Problem 3.57

[Difficulty: 2]

**3.57** A section of vertical wall is to be constructed from ready-mix concrete poured between forms. The wall is to be 3 m high, 0.25 m thick, and 5 m wide. Calculate the force exerted by the ready-mix concrete on each form. Determine the line of application of the force.

**Given:** Liquid concrete poured between vertical forms as shown  
 $t = 0.25\text{-m}$   $H = 3\text{-m}$   $W = 5\text{-m}$   $SG_c = 2.5$  (From Table A.1, App. A)

**Find:** (a) Resultant force on form  
 (b) Line of application

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dy} = \rho \cdot g$  (Hydrostatic Pressure -  $y$  is positive downwards)

$F_R = p_c \cdot A$  (Hydrostatic Force)

$y' = y_c + \frac{I_{xx}}{A \cdot y_c}$  (Location of line of action)

$x' = x_c + \frac{I_{xy}}{A \cdot y_c}$

**Assumptions:** (1) Static fluid  
 (2) Incompressible fluid  
 (3) Atmospheric pressure acts at free surface and on the outside of the form.

For a rectangular plate:  $I_{xx} = \frac{W \cdot H^3}{12}$   $I_{xy} = 0$

$x_c = 2.5\text{-m}$   $y_c = 1.5\text{-m}$

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot y$   
 The density of concrete is:

$$\rho = 2.5 \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad \rho = 2.5 \times 10^3 \frac{\text{kg}}{\text{m}^3}$$


Therefore, the force is:  $F_R = \rho \cdot g \cdot y_c \cdot H \cdot W$

Substituting in values gives us:  $F_R = 2.5 \times 10^3 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1.5\text{-m} \times 3\text{-m} \times 5\text{-m}$   $F_R = 552\text{-kN}$

To find the line of action of the resultant force:

$$y' = y_c + \frac{W \cdot H^3}{12 \cdot W \cdot H \cdot y_c} = y_c + \frac{H^2}{12 \cdot y_c} \quad y' = 1.5\text{-m} + \frac{(3\text{-m})^2}{12 \cdot 1.5\text{-m}} \quad y' = 2.00\text{m}$$


Since  $I_{xy} = 0$  it follows that  $x' = x_c$   $x' = 2.50\text{-m}$



## Problem 3.58

[Difficulty: 4]

**3.58** A window in the shape of an isosceles triangle and hinged at the top is placed in the vertical wall of a form that contains liquid concrete. Determine the minimum force that must be applied at point  $D$  to keep the window closed for the configuration of form and concrete shown. Plot the results over the range of concrete depth  $0 \leq c \leq a$



**Given:** Window, in shape of isosceles triangle and hinged at the top is located in the vertical wall of a form that contains concrete.

$$a = 0.4\text{ m} \quad b = 0.3\text{ m} \quad c = 0.25\text{ m} \quad SG_c = 2.5 \quad (\text{From Table A.1, App. A})$$

**Find:** The minimum force applied at  $D$  needed to keep the window closed. Plot the results over the range of concrete depth between 0 and  $a$ .

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards})$$

$$F_R = \int p \, dA \quad (\text{Hydrostatic Force on door})$$

$$y' \cdot F_R = \int y \cdot p \, dA \quad (\text{First moment of force})$$

$$\Sigma M = 0 \quad (\text{Rotational equilibrium})$$

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts at free surface and on the outside of the window.

Integrating the pressure equation yields:  $p = \rho \cdot g \cdot (h - d)$  for  $h > d$

$$p = 0 \quad \text{for } h < d$$

$$\text{where} \quad d = a - c \quad d = 0.15\text{ m}$$



Summing moments around the hinge:  $-F_D \cdot a + \int h \cdot p \, dA = 0$

$$F_D = \frac{1}{a} \cdot \int h \cdot p \, dA = \frac{1}{a} \cdot \int_d^a h \cdot \rho \cdot g \cdot (h - d) \cdot w \, dh = \frac{\rho \cdot g}{a} \cdot \int_d^a h \cdot (h - d) \cdot w \, dh$$

From the law of similar triangles:

$$\frac{w}{b} = \frac{a - h}{a}$$

$$\text{Therefore:} \quad w = \frac{b}{a} (a - h)$$



Into the expression for the force at D: 
$$F_D = \frac{\rho \cdot g}{a} \cdot \int_d^a \frac{b}{a} \cdot h \cdot (h-d) \cdot (a-h) dh = \frac{\rho \cdot g \cdot b}{a^2} \cdot \int_d^a [-h^3 + (a+d) \cdot h^2 - a \cdot d \cdot h] dh$$

Evaluating this integral we get:

$$F_D = \frac{\rho \cdot g \cdot b}{a^2} \cdot \left[ -\frac{(a^4 - d^4)}{4} + \frac{(a+d) \cdot (a^3 - d^3)}{3} - \frac{a \cdot d \cdot (a^2 - d^2)}{2} \right] \quad \text{and after collecting terms:}$$

$$F_D = \rho \cdot g \cdot b \cdot a^2 \cdot \left[ -\frac{1}{4} \cdot \left[ 1 - \left( \frac{d}{a} \right)^4 \right] + \frac{1}{3} \cdot \left( 1 + \frac{d}{a} \right) \cdot \left[ 1 - \left( \frac{d}{a} \right)^3 \right] - \frac{1}{2} \cdot \frac{d}{a} \cdot \left[ 1 - \left( \frac{d}{a} \right)^2 \right] \right] \quad (1)$$

The density of the concrete is:  $\rho = 2.5 \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad \rho = 2.5 \times 10^3 \frac{\text{kg}}{\text{m}^3} \quad \frac{d}{a} = \frac{0.15}{0.4} = 0.375$


Substituting in values for the force at D:

$$F_D = 2.5 \times 10^3 \cdot \frac{\text{kg}}{\text{m}^3} \cdot 9.81 \cdot \frac{\text{m}}{\text{s}^2} \cdot 0.3 \cdot \text{m} \cdot (0.4 \cdot \text{m})^2 \cdot \left[ -\frac{1}{4} \cdot \left[ 1 - (0.375)^4 \right] + \frac{1}{3} \cdot (1 + 0.375) \cdot \left[ 1 - (0.375)^3 \right] - \frac{0.375}{2} \cdot \left[ 1 - (0.375)^2 \right] \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

To plot the results for different values of c/a, we use Eq. (1) and remember that  $d = a - c$   $F_D = 32.9 \text{ N}$

Therefore, it follows that  $\frac{d}{a} = 1 - \frac{c}{a}$  In addition, we can maximize the force by the maximum force (when c = a or d = 0):



$$F_{\max} = \rho \cdot g \cdot b \cdot a^2 \cdot \left( -\frac{1}{4} + \frac{1}{3} \right) = \frac{\rho \cdot g \cdot b \cdot a^2}{12} \quad \text{and so} \quad \frac{F_D}{F_{\max}} = 12 \cdot \left[ -\frac{1}{4} \cdot \left[ 1 - \left( \frac{d}{a} \right)^4 \right] + \frac{1}{3} \cdot \left( 1 + \frac{d}{a} \right) \cdot \left[ 1 - \left( \frac{d}{a} \right)^3 \right] - \frac{1}{2} \cdot \frac{d}{a} \cdot \left[ 1 - \left( \frac{d}{a} \right)^2 \right] \right]$$



### Problem 3.59

[Difficulty: 2]

**3.59** Solve Example 3.6 again using the two separate pressures method. Consider the distributed force to be the sum of a force  $F_1$  caused by the uniform gage pressure and a force  $F_2$  caused by the liquid. Solve for these forces and their lines of action. Then sum moments about the hinge axis to calculate  $F_t$ .




**Given:** Door as shown; Data from Example 3.6.

**Find:** Force to keep door shut using the two separate pressures method.

**Solution:** We will apply the computing equations to this system.

**Governing Equations:**  $F_R = p_c \cdot A$      $y' = y_c + \frac{I_{xx}}{y_c \cdot A}$      $I_{xx} = \frac{b \cdot L^3}{12}$



$$F_1 = p_0 \cdot A \quad F_1 = 100 \cdot \frac{\text{lb}}{\text{ft}^2} \times 3 \cdot \text{ft} \times 2 \cdot \text{ft}$$

$$F_1 = 600 \text{ lbf} \quad x' = 1 \cdot \text{ft} \quad z' = 1.5 \cdot \text{ft}$$

$$F_2 = p_c \cdot A = \rho \cdot g \cdot h_c \cdot L \cdot b = \gamma \cdot h_c \cdot L \cdot b$$


$$F_2 = 100 \cdot \frac{\text{lb}}{\text{ft}^3} \times 1.5 \cdot \text{ft} \times 3 \cdot \text{ft} \times 2 \cdot \text{ft} \quad F_2 = 900 \text{ lbf}$$

For the rectangular door  $I_{xx} = \frac{1}{12} \cdot b \cdot L^3$

$$h_2' = h_c + \frac{I_{xx}}{b \cdot L \cdot h_c} = h_c + \frac{1}{12} \cdot \frac{L^2}{h_c}$$

$$h_2' = 1.5 \cdot \text{m} + \frac{1}{12} \cdot \frac{(3 \cdot \text{m})^2}{1.5 \cdot \text{m}} \quad h_2' = 2 \text{ m}$$

The free body diagram of the door is then



$$\Sigma M_{Ax} = 0 = L \cdot F_t - F_1 \cdot (L - h_1') - F_2 \cdot (L - h_2')$$


$$F_t = F_1 \cdot \left(1 - \frac{h_1'}{L}\right) + F_2 \cdot \left(1 - \frac{h_2'}{L}\right)$$

$$F_t = 600 \cdot \text{lbf} \cdot \left(1 - \frac{1.5}{3}\right) + 900 \cdot \text{lbf} \cdot \left(1 - \frac{2}{3}\right) \quad F_t = 600 \text{ lbf}$$

## Problem 3.60

[Difficulty: 2]

**3.60** A large open tank contains water and is connected to a 6-ft-diameter conduit as shown. A circular plug is used to seal the conduit. Determine the magnitude, direction, and location of the force of the water on the plug.



**Given:** Plug is used to seal a conduit.  $\gamma = 62.4 \frac{\text{lb}}{\text{ft}^3}$

**Find:** Magnitude, direction and location of the force of water on the plug.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = \gamma$  (Hydrostatic Pressure -  $y$  is positive downwards)

$F_R = p_c \cdot A$  (Hydrostatic Force)

$y' = y_c + \frac{I_{xx}}{A \cdot y_c}$  (Location of line of action)

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts on the outside of the plug.

Integrating the hydrostatic pressure equation:  $p = \gamma \cdot h$   $F_R = p_c \cdot A = \gamma \cdot h_c \cdot \frac{\pi}{4} \cdot D^2$

$$F_R = 62.4 \frac{\text{lb}}{\text{ft}^3} \times 12 \cdot \text{ft} \times \frac{\pi}{4} \times (6 \cdot \text{ft})^2 \quad F_R = 2.12 \times 10^4 \cdot \text{lb}$$

For a circular area:  $I_{xx} = \frac{\pi}{64} \cdot D^4$  Therefore:  $y' = y_c + \frac{\frac{\pi}{64} \cdot D^4}{\frac{\pi}{4} \cdot D^2 \cdot y_c} = y_c + \frac{D^2}{16 \cdot y_c}$   $y' = 12 \cdot \text{ft} + \frac{(6 \cdot \text{ft})^2}{16 \times 12 \cdot \text{ft}}$

$$y' = 12.19 \cdot \text{ft}$$

The force of water is to the right and perpendicular to the plug.

## Problem 3.61

[Difficulty: 1]

**3.61** What holds up a car on its rubber tires? Most people would tell you that it is the air pressure inside the tires. However, the air pressure is the same all around the hub (inner wheel), and the air pressure inside the tire therefore pushes down from the top as much as it pushes up from below, having no net effect on the hub. Resolve this paradox by explaining where the force is that keeps the car off the ground.

**Given:** Description of car tire

**Find:** Explanation of lift effect

### **Solution:**

The explanation is as follows: It is true that the pressure in the entire tire is the same everywhere. However, the tire at the top of the hub will be essentially circular in cross-section, but at the bottom, where the tire meets the ground, the cross section will be approximately a flattened circle, or elliptical. Hence we can explain that the lower cross section has greater upward force than the upper cross section has downward force (providing enough lift to keep the car up) two ways. First, the horizontal projected area of the lower ellipse is larger than that of the upper circular cross section, so that net pressure times area is upwards. Second, any time you have an elliptical cross section that's at high pressure, that pressure will always try to force the ellipse to be circular (think of a round inflated balloon - if you squeeze it it will resist!). This analysis ignores the stiffness of the tire rubber, which also provides a little lift.

## Problem 3.62

[Difficulty: 2]

**3.62** The circular access port in the side of a water standpipe has a diameter of 0.6 m and is held in place by eight bolts evenly spaced around the circumference. If the standpipe diameter is 7 m and the center of the port is located 12 m below the free surface of the water, determine (a) the total force on the port and (b) the appropriate bolt diameter.

**Given:** Circular access port of known diameter in side of water standpipe of known diameter. Port is held in place by eight bolts evenly spaced around the circumference of the port. Center of the port is located at a know distance below the free surface of the water.

$$d = 0.6\text{ m} \quad D = 7\text{ m} \quad L = 12\text{ m}$$

**Find:** (a) Total force on the port  
(b) Appropriate bolt diameter

**Solution:** We will apply the hydrostatics equations to this system.


**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure - y is positive downwards)

$$F_R = p_c \cdot A \quad (\text{Hydrostatic Force})$$

$$\sigma = \frac{F}{A} \quad (\text{Normal Stress in bolt})$$

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Force is distributed evenly over all bolts
- (4) Appropriate working stress in bolts is 100 MPa
- (5) Atmospheric pressure acts at free surface of water and on outside of port.



Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

$$\text{The resultant force on the port is: } F_R = p_c \cdot A = \rho \cdot g \cdot L \cdot \frac{\pi}{4} \cdot d^2 \quad F_R = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 12 \cdot \text{m} \times \frac{\pi}{4} \times (0.6 \cdot \text{m})^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$F_R = 33.3 \cdot \text{kN}$$

To find the bolt diameter we consider:  $\sigma = \frac{F_R}{A}$  where A is the area of all of the bolts:  $A = 8 \times \frac{\pi}{4} \cdot d_b^2 = 2 \cdot \pi \cdot d_b^2$


$$\text{Therefore: } 2 \cdot \pi \cdot d_b^2 = \frac{F_R}{\sigma} \quad \text{Solving for the bolt diameter we get: } d_b = \left( \frac{F_R}{2 \cdot \pi \cdot \sigma} \right)^{\frac{1}{2}}$$

$$d_b = \left( \frac{1}{2 \times \pi} \times 33.3 \times 10^3 \cdot \text{N} \times \frac{1}{100 \times 10^6} \cdot \frac{\text{m}^2}{\text{N}} \right)^{\frac{1}{2}} \times \frac{10^3 \cdot \text{mm}}{\text{m}} \quad d_b = 7.28 \cdot \text{mm}$$

### Problem 3.63

[Difficulty: 3]

**3.63** As water rises on the left side of the rectangular gate, the gate will open automatically. At what depth above the hinge will this occur? Neglect the mass of the gate.




**Given:** Geometry of rectangular gate

**Find:** Depth for gate to open

**Solution:**

Basic equation  $\frac{dp}{dh} = \rho \cdot g$   $\Sigma M_Z = 0$

Computing equations  $F_R = p_c \cdot A$   $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$   $I_{xx} = \frac{b \cdot D^3}{12}$



**Assumptions:** Static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side; no friction in hinge

For incompressible fluid  $p = \rho \cdot g \cdot h$  where  $p$  is gage pressure and  $h$  is measured downwards

The force on the vertical gate (gate 1) is the same as that on a rectangle of size  $h = D$  and width  $w$

Hence  $F_1 = p_c \cdot A = \rho \cdot g \cdot y_c \cdot A = \rho \cdot g \cdot \frac{D}{2} \cdot D \cdot w = \frac{\rho \cdot g \cdot w \cdot D^2}{2}$

The location of this force is  $y' = y_c + \frac{I_{xx}}{A \cdot y_c} = \frac{D}{2} + \frac{w \cdot D^3}{12} \times \frac{1}{w \cdot D} \times \frac{2}{D} = \frac{2}{3} \cdot D$

The force on the horizontal gate (gate 2) is due to constant pressure, and is at the centroid

$$F_2 = p(y = D) \cdot A = \rho \cdot g \cdot D \cdot w \cdot L$$

Summing moments about the hinge

$$\Sigma M_{\text{hinge}} = 0 = -F_1 \cdot (D - y') + F_2 \cdot \frac{L}{2} = -F_1 \cdot \left( D - \frac{2}{3} \cdot D \right) + F_2 \cdot \frac{L}{2}$$

$$F_1 \cdot \frac{D}{3} = \frac{\rho \cdot g \cdot w \cdot D^2}{2} \cdot \frac{D}{3} = F_2 \cdot \frac{L}{2} = \rho \cdot g \cdot D \cdot w \cdot L \cdot \frac{L}{2}$$

$$\frac{\rho \cdot g \cdot w \cdot D^3}{6} = \frac{\rho \cdot g \cdot D \cdot w \cdot L^2}{2}$$


$$D = \sqrt{3} \cdot L = \sqrt{3} \times 5 \text{ ft}$$

$$D = 8.66 \text{ ft}$$

### Problem 3.64

[Difficulty: 3]

**3.64** The gate  $AOC$  shown is 6 ft wide and is hinged along  $O$ . Neglecting the weight of the gate, determine the force in bar  $AB$ . The gate is sealed at  $C$ .



**Given:** Gate  $AOC$ , hinged along  $O$ , has known width;  
Weight of gate may be neglected. Gate is sealed at  $C$ .

$$b = 6\text{-ft}$$

**Find:** Force in bar  $AB$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad \text{(Hydrostatic Pressure - h is positive downwards)}$$

$$F_R = p_c \cdot A \quad \text{(Hydrostatic Force)}$$

$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} \quad \text{(Location of line of action)}$$

$$\Sigma M_z = 0 \quad \text{(Rotational equilibrium)}$$

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts at free surface of water and on outside of gate
- (4) No resisting moment in hinge at  $O$
- (5) No vertical resisting force at  $C$

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$


The free body diagram of the gate is shown here:

$F_1$  is the resultant of the distributed force on  $AO$

$F_2$  is the resultant of the distributed force on  $OC$

$F_{AB}$  is the force of the bar

$C_x$  is the sealing force at  $C$



First find the force on  $AO$ :  $F_1 = p_c \cdot A_1 = \rho \cdot g \cdot h_{c1} \cdot b \cdot L_1$

$$F_1 = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 6 \cdot \text{ft} \times 6 \cdot \text{ft} \times 12 \cdot \text{ft} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$F_1 = 27.0 \cdot \text{kip}$$

$$h'_1 = h_{c1} + \frac{I_{xx}}{A \cdot h_{c1}} = h_{c1} + \frac{b \cdot L_1^3}{12 \cdot b \cdot L_1 \cdot h_{c1}} = h_{c1} + \frac{L_1^2}{12 \cdot h_{c1}} \quad h'_1 = 6 \cdot \text{ft} + \frac{(12 \cdot \text{ft})^2}{12 \times 6 \cdot \text{ft}} \quad h'_1 = 8 \cdot \text{ft}$$


Next find the force on OC:  $F_2 = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 12 \cdot \text{ft} \times 6 \cdot \text{ft} \times 6 \cdot \text{ft} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_2 = 27.0 \cdot \text{kip}$

Since the pressure is uniform over OC, the force acts at the centroid of OC, i.e.,  $x'_2 = 3 \cdot \text{ft}$

Summing moments about the hinge gives:  $F_{AB} \cdot (L_1 + L_3) - F_1 \cdot (L_1 - h'_1) + F_2 \cdot x'_2 = 0$

Solving for the force in the bar:  $F_{AB} = \frac{F_1 \cdot (L_1 - h'_1) - F_2 \cdot x'_2}{L_1 + L_3}$

Substituting in values:  $F_{AB} = \frac{1}{12 \cdot \text{ft} + 3 \cdot \text{ft}} \cdot [27.0 \times 10^3 \cdot \text{lb} \cdot \text{ft} \times (12 \cdot \text{ft} - 8 \cdot \text{ft}) - 27.0 \times 10^3 \cdot \text{lb} \cdot \text{ft} \times 3 \cdot \text{ft}]$




$$F_{AB} = 1800 \cdot \text{lb} \cdot \text{ft}$$

Thus bar AB is in compression

## Problem 3.65

[Difficulty: 3]

**3.65** The gate shown is 3 m wide and for analysis can be considered massless. For what depth of water will this rectangular gate be in equilibrium as shown?



**Given:** Gate shown with fixed width, base of gate is negligible.  
Gate is in equilibrium.

$$b = 3 \text{ m}$$

**Find:** Water depth,  $d$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$\frac{dp}{dh} = \rho \cdot g$	(Hydrostatic Pressure - $h$ is positive downwards)
$F_R = p_c \cdot A$	(Hydrostatic Force)
$y' = y_c + \frac{I_{xx}}{A \cdot y_c}$	(Location of line of action)
$\Sigma M_z = 0$	(Rotational equilibrium)

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts at free surface of water and on outside of gate


Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

$$F_R = p_c \cdot A = \rho \cdot g \cdot h_c \cdot A \quad h_c = \frac{d}{2} \quad A = b \cdot \frac{d}{\sin(\theta)}$$

Therefore,  $F_R = \frac{\rho \cdot g \cdot b \cdot d^2}{2 \cdot \sin(\theta)}$  To find the line of application of this force:


$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} \quad \text{Since } I_{xx} = \frac{b \cdot l^3}{12} \text{ and } A = b \cdot l \text{ it follows that}$$

$$y' = y_c + \frac{b \cdot l^3}{12 \cdot b \cdot l \cdot y_c} = y_c + \frac{l^2}{12 \cdot y_c} \quad \text{where } l \text{ is the length of the gate in contact with the water (as seen in diagram)}$$



l and d are related through:  $l = \frac{d}{\sin(\theta)}$  Therefore,  $y_c = \frac{l}{2} = \frac{d}{2 \cdot \sin(\theta)}$  and  $y' = \frac{d}{2 \cdot \sin(\theta)} + \frac{d^2}{(\sin(\theta))^2} \cdot \frac{2 \cdot \sin(\theta)}{12 \cdot d} = \frac{2 \cdot d}{3 \cdot \sin(\theta)}$

The free body diagram of the gate is shown here:



Summing moments about the hinge gives:

$$T \cdot L - (l - y') \cdot F_R = 0 \quad \text{where } T = M \cdot g$$

Solving for l:  $l = \frac{d}{\sin(\theta)} = \frac{M \cdot g \cdot L}{F_R} + y'$  So upon further substitution we get:

$$d = \left( \frac{2 \cdot M \cdot g \cdot L}{\rho \cdot g \cdot b \cdot d^2} \cdot \sin(\theta) + \frac{2 \cdot d}{3 \cdot \sin(\theta)} \right) \cdot \sin(\theta) \quad \text{or} \quad \frac{d}{3} = \frac{2 \cdot M \cdot L \cdot (\sin(\theta))^2}{\rho \cdot b \cdot d^2}$$


Solving for d:  $d = \left[ \frac{6 \cdot M \cdot L}{\rho \cdot b} \cdot (\sin(\theta))^2 \right]^{\frac{1}{3}}$  Substituting in values:  $d = \left[ 6 \times 2500 \cdot \text{kg} \times 5 \cdot \text{m} \times \frac{1}{999} \cdot \frac{\text{m}^3}{\text{kg}} \times \frac{1}{3\text{m}} \times (\sin(60 \cdot \text{deg}))^2 \right]^{\frac{1}{3}}$

$$d = 2.66 \text{ m}$$

### Problem 3.66

[Difficulty: 3]

**3.66** The gate shown is hinged at  $H$ . The gate is 3 m wide normal to the plane of the diagram. Calculate the force required at  $A$  to hold the gate closed.




**Given:** Geometry of gate

**Find:** Force at  $A$  to hold gate closed

**Solution:**

Basic equation  $\frac{dp}{dh} = \rho \cdot g$   $\Sigma M_z = 0$

Computing equations  $F_R = p_c \cdot A$   $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$   $I_{xx} = \frac{w \cdot L^3}{12}$



**Assumptions:** Static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side; no friction in hinge

For incompressible fluid  $p = \rho \cdot g \cdot h$  where  $p$  is gage pressure and  $h$  is measured downwards

The hydrostatic force on the gate is that on a rectangle of size  $L$  and width  $w$ .

Hence  $F_R = p_c \cdot A = \rho \cdot g \cdot h_c \cdot A = \rho \cdot g \cdot \left( D + \frac{L}{2} \cdot \sin(30\text{-deg}) \right) \cdot L \cdot w$

$$F_R = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \left( 1.5 + \frac{3}{2} \sin(30\text{-deg}) \right) \cdot \text{m} \times 3 \cdot \text{m} \times 3 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_R = 199 \cdot \text{kN}$$

The location of this force is given by  $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$  where  $y'$  and  $y_c$  are measured along the plane of the gate to the free surface

$$y_c = \frac{D}{\sin(30\text{-deg})} + \frac{L}{2} \quad y_c = \frac{1.5 \cdot \text{m}}{\sin(30\text{-deg})} + \frac{3 \cdot \text{m}}{2} \quad y_c = 4.5 \text{ m}$$

$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} = y_c + \frac{w \cdot L^3}{12} \cdot \frac{1}{w \cdot L} \cdot \frac{1}{y_c} = y_c + \frac{L^2}{12 \cdot y_c} = 4.5 \cdot \text{m} + \frac{(3 \cdot \text{m})^2}{12 \cdot 4.5 \cdot \text{m}} \quad y' = 4.67 \text{ m}$$


Taking moments about the hinge  $\Sigma M_H = 0 = F_R \cdot \left( y' - \frac{D}{\sin(30\text{-deg})} \right) - F_A \cdot L$

$$F_A = F_R \cdot \frac{\left( y' - \frac{D}{\sin(30\text{-deg})} \right)}{L} \quad F_A = 199 \cdot \text{kN} \cdot \frac{\left( 4.67 - \frac{1.5}{\sin(30\text{-deg})} \right)}{3} \quad F_A = 111 \cdot \text{kN}$$

### Problem 3.67

[Difficulty: 3]

**3.67** A long, square wooden block is pivoted along one edge. The block is in equilibrium when immersed in water to the depth shown. Evaluate the specific gravity of the wood, if friction in the pivot is negligible.



**Given:** Block hinged and floating

**Find:** SG of the wood

**Solution:**

Basic equation  $\frac{dp}{dh} = \rho \cdot g$   $\Sigma M_z = 0$

Computing equations  $F_R = p_c \cdot A$   $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$

**Assumptions:** Static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side; no friction in hinge

For incompressible fluid  $p = \rho \cdot g \cdot h$  where  $p$  is gage pressure and  $h$  is measured downwards


The force on the vertical section is the same as that on a rectangle of height  $d$  and width  $L$

Hence

$$F_1 = p_c \cdot A = \rho \cdot g \cdot y_c \cdot A = \rho \cdot g \cdot \frac{d}{2} \cdot d \cdot L = \frac{\rho \cdot g \cdot L \cdot d^2}{2}$$

The location of this force is

$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} = \frac{d}{2} + \frac{L \cdot d^3}{12} \times \frac{1}{L \cdot d} \times \frac{2}{d} = \frac{2}{3} \cdot d$$



The force on the horizontal section is due to constant pressure, and is at the centroid

$$F_2 = p(y = d) \cdot A = \rho \cdot g \cdot d \cdot L \cdot L$$

Summing moments about the hinge

$$\Sigma M_{\text{hinge}} = 0 = -F_1 \cdot (d - y') - F_2 \cdot \frac{L}{2} + M \cdot g \cdot \frac{L}{2}$$

Hence

$$F_1 \cdot \left( d - \frac{2}{3} \cdot d \right) + F_2 \cdot \frac{L}{2} = SG \cdot \rho \cdot L^3 \cdot g \cdot \frac{L}{2}$$

$$\frac{SG \cdot \rho \cdot g \cdot L^4}{2} = \frac{\rho \cdot g \cdot L \cdot d^2}{2} \cdot \frac{d}{3} + \rho \cdot g \cdot d \cdot L \cdot \frac{L}{2}$$

$$SG = \frac{1}{3} \cdot \left( \frac{d}{L} \right)^3 + \frac{d}{L}$$


$$SG = \frac{1}{3} \cdot \left( \frac{0.5}{1} \right)^3 + \frac{0.5}{1}$$

$$SG = 0.542$$

### Problem 3.68

[Difficulty: 4]

**3.68** A solid concrete dam is to be built to hold back a depth  $D$  of water. For ease of construction the walls of the dam must be planar. Your supervisor asks you to consider the following dam cross-sections: a rectangle, a right triangle with the hypotenuse in contact with the water, and a right triangle with the vertical in contact with the water. She wishes you to determine which of these would require the least amount of concrete. What will your report say? You decide to look at one more possibility: a nonright triangle, as shown. Develop and plot an expression for the cross-section area  $A$  as a function of  $a$ , and find the minimum cross-sectional area.



**Given:** Various dam cross-sections

**Find:** Which requires the least concrete; plot cross-section area  $A$  as a function of  $a$

**Solution:**

For each case, the dam width  $b$  has to be large enough so that the weight of the dam exerts enough moment to balance the moment due to fluid hydrostatic force(s). By doing a moment balance this value of  $b$  can be found

a) Rectangular dam

Straightforward application of the computing equations of Section 3-5 yields

$$F_H = p_c \cdot A = \rho \cdot g \cdot \frac{D}{2} \cdot w \cdot D = \frac{1}{2} \cdot \rho \cdot g \cdot D^2 \cdot w$$

$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} = \frac{D}{2} + \frac{w \cdot D^3}{12 \cdot w \cdot D \cdot \frac{D}{2}} = \frac{2}{3} \cdot D$$

so  $y = D - y' = \frac{D}{3}$

Also  $m = \rho_{\text{cement}} \cdot g \cdot b \cdot D \cdot w = SG \cdot \rho \cdot g \cdot b \cdot D \cdot w$


Taking moments about  $O$   $\sum M_O = 0 = -F_H \cdot y + \frac{b}{2} \cdot m \cdot g$

so  $\left(\frac{1}{2} \cdot \rho \cdot g \cdot D^2 \cdot w\right) \cdot \frac{D}{3} = \frac{b}{2} \cdot (SG \cdot \rho \cdot g \cdot b \cdot D \cdot w)$

Solving for  $b$   $b = \frac{D}{\sqrt{3 \cdot SG}}$

The minimum rectangular cross-section area is  $A = b \cdot D = \frac{D^2}{\sqrt{3 \cdot SG}}$


For concrete, from Table A.1,  $SG = 2.4$ , so  $A = \frac{D^2}{\sqrt{3 \cdot SG}} = \frac{D^2}{\sqrt{3 \times 2.4}} \quad A = 0.373 \cdot D^2$



b) Triangular dams

Instead of analysing right-triangles, a general analysis is made, at the end of which right triangles are analysed as special cases by setting  $\alpha = 0$  or 1.

Straightforward application of the computing equations of Section 3-5 yields



$$F_H = p_c \cdot A = \rho \cdot g \cdot \frac{D}{2} \cdot w \cdot D = \frac{1}{2} \cdot \rho \cdot g \cdot D^2 \cdot w$$

$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} = \frac{D}{2} + \frac{w \cdot D^3}{12 \cdot w \cdot D \cdot \frac{D}{2}} = \frac{2}{3} \cdot D$$

so 
$$y = D - y' = \frac{D}{3}$$

Also 
$$F_V = \rho \cdot V \cdot g = \rho \cdot g \cdot \frac{\alpha \cdot b \cdot D}{2} \cdot w = \frac{1}{2} \cdot \rho \cdot g \cdot \alpha \cdot b \cdot D \cdot w \quad x = (b - \alpha \cdot b) + \frac{2}{3} \cdot \alpha \cdot b = b \cdot \left(1 - \frac{\alpha}{3}\right)$$

For the two triangular masses

$$m_1 = \frac{1}{2} \cdot SG \cdot \rho \cdot g \cdot \alpha \cdot b \cdot D \cdot w \quad x_1 = (b - \alpha \cdot b) + \frac{1}{3} \cdot \alpha \cdot b = b \cdot \left(1 - \frac{2 \cdot \alpha}{3}\right)$$

$$m_2 = \frac{1}{2} \cdot SG \cdot \rho \cdot g \cdot (1 - \alpha) \cdot b \cdot D \cdot w \quad x_2 = \frac{2}{3} \cdot b \cdot (1 - \alpha)$$

Taking moments about O

$$\sum M_O = 0 = -F_H \cdot y + F_V \cdot x + m_1 \cdot g \cdot x_1 + m_2 \cdot g \cdot x_2$$

so 
$$-\left(\frac{1}{2} \cdot \rho \cdot g \cdot D^2 \cdot w\right) \cdot \frac{D}{3} + \left(\frac{1}{2} \cdot \rho \cdot g \cdot \alpha \cdot b \cdot D \cdot w\right) \cdot b \cdot \left(1 - \frac{\alpha}{3}\right) \dots = 0$$

$$+ \left(\frac{1}{2} \cdot SG \cdot \rho \cdot g \cdot \alpha \cdot b \cdot D \cdot w\right) \cdot b \cdot \left(1 - \frac{2 \cdot \alpha}{3}\right) + \left[\frac{1}{2} \cdot SG \cdot \rho \cdot g \cdot (1 - \alpha) \cdot b \cdot D \cdot w\right] \cdot \frac{2}{3} \cdot b \cdot (1 - \alpha)$$

Solving for  $b$  
$$b = \frac{D}{\sqrt{(3 \cdot \alpha - \alpha^2) + SG \cdot (2 - \alpha)}}$$

For a right triangle with the hypotenuse in contact with the water,  $\alpha = 1$ , and

$$b = \frac{D}{\sqrt{3 - 1 + SG}} = \frac{D}{\sqrt{3 - 1 + 2.4}} \quad b = 0.477 \cdot D$$

The cross-section area is 
$$A = \frac{b \cdot D}{2} = 0.238 \cdot D^2 \quad A = 0.238 \cdot D^2$$

For a right triangle with the vertical in contact with the water,  $\alpha = 0$ , and

$$b = \frac{D}{\sqrt{2 \cdot SG}} = \frac{D}{\sqrt{2 \cdot 2.4}}$$

$$b = 0.456 \cdot D$$

The cross-section area is

$$A = \frac{b \cdot D}{2} = 0.228 \cdot D^2$$

$$A = 0.228 \cdot D^2$$

For a general triangle

$$A = \frac{b \cdot D}{2} = \frac{D^2}{2 \cdot \sqrt{(3 \cdot \alpha - \alpha^2) + SG \cdot (2 - \alpha)}}$$

$$A = \frac{D^2}{2 \cdot \sqrt{(3 \cdot \alpha - \alpha^2) + 2.4 \cdot (2 - \alpha)}}$$

The final result is


$$A = \frac{D^2}{2 \cdot \sqrt{4.8 + 0.6 \cdot \alpha - \alpha^2}}$$

The dimensionless area,  $A/D^2$ , is plotted

Alpha	$A/D^2$
0.0	0.2282
0.1	0.2270
0.2	0.2263
0.3	0.2261
0.4	0.2263
0.5	0.2270
0.6	0.2282
0.7	0.2299
0.8	0.2321
0.9	0.2349
1.0	0.2384

*Solver* can be used to find the minimum area

Alpha	$A/D^2$
0.300	0.2261



From the Excel workbook, the minimum area occurs at  $\alpha = 0.3$

$$A_{\min} = \frac{D^2}{2 \cdot \sqrt{4.8 + 0.6 \times 0.3 - 0.3^2}}$$


$$A = 0.226 \cdot D^2$$

The final results are that a triangular cross-section with  $\alpha = 0.3$  uses the least concrete; the next best is a right triangle with the vertical in contact with the water; next is the right triangle with the hypotenuse in contact with the water; and the cross-section requiring the most concrete is the rectangular cross-section.

## Problem 3.69

[Difficulty: 2]

**3.69** For the geometry shown, what is the vertical force on the dam? The steps are 0.5 m high, 0.5 m deep, and 3 m wide.



**Given:** Geometry of dam

**Find:** Vertical force on dam

**Assumption:** Water is static and incompressible

**Solution:**

Basic equation:  $\frac{dp}{dh} = \rho \cdot g$

For incompressible fluid  $p = p_{\text{atm}} + \rho \cdot g \cdot h$  where  $h$  is measured downwards from the free surface

The force on each horizontal section (depth  $d = 0.5$  m and width  $w = 3$  m) is

$$F = p \cdot A = (p_{\text{atm}} + \rho \cdot g \cdot h) \cdot d \cdot w$$

Hence the total force is  $F_T = [p_{\text{atm}} + (p_{\text{atm}} + \rho \cdot g \cdot h) + (p_{\text{atm}} + \rho \cdot g \cdot 2 \cdot h) + (p_{\text{atm}} + \rho \cdot 3 \cdot g \cdot h) + (p_{\text{atm}} + \rho \cdot g \cdot 4 \cdot h)] \cdot d \cdot w$

where we have used  $h$  as the height of the steps

$$F_T = d \cdot w \cdot (5 \cdot p_{\text{atm}} + 10 \cdot \rho \cdot g \cdot h)$$


$$F_T = 0.5 \cdot \text{m} \times 3 \cdot \text{m} \times \left( 5 \times 101 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} + 10 \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.5 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right)$$

$$F_T = 831 \cdot \text{kN}$$

## Problem 3.70

[Difficulty: 2]

**3.70** For the dam shown, what is the vertical force of the water on the dam?



**Given:** Geometry of dam

**Find:** Vertical force on dam

**Assumptions:** (1) water is static and incompressible  
(2) since we are asked for the force of the water, all pressures will be written as gage

**Solution:**

Basic equation:  $\frac{dp}{dh} = \rho \cdot g$

For incompressible fluid  $p = \rho \cdot g \cdot h$  where  $p$  is gage pressure and  $h$  is measured downwards from the free surface

The force on each horizontal section (depth  $d$  and width  $w$ ) is

$$F = p \cdot A = \rho \cdot g \cdot h \cdot d \cdot w \quad (\text{Note that } d \text{ and } w \text{ will change in terms of } x \text{ and } y \text{ for each section of the dam!})$$

Hence the total force is (allowing for the fact that some faces experience an upwards (negative) force)

$$F_T = p \cdot A = \Sigma \rho \cdot g \cdot h \cdot d \cdot w = \rho \cdot g \cdot d \cdot \Sigma h \cdot w$$

Starting with the top and working downwards


$$F_T = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 3 \cdot \text{ft} \times [(3 \cdot \text{ft} \times 12 \cdot \text{ft}) + (3 \cdot \text{ft} \times 6 \cdot \text{ft}) - (9 \cdot \text{ft} \times 6 \cdot \text{ft}) - (12 \cdot \text{ft} \times 12 \cdot \text{ft})] \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$F_T = -2.70 \times 10^4 \cdot \text{lbf} \quad \text{The negative sign indicates a net upwards force (it's actually a buoyancy effect on the three middle sections)}$$

## Problem 3.71

[Difficulty: 3]

**3.71** The gate shown is 1.5 m wide and pivoted at  $O$ ;  $a = 1.0 \text{ m}^{-2}$ ,  $D = 1.20 \text{ m}$ , and  $H = 1.40 \text{ m}$ . Determine (a) the magnitude and moment of the vertical component of the force about  $O$ , and (b) the horizontal force that must be applied at point  $A$  to hold the gate in position.



**Given:** Parabolic gate, hinged at  $O$  has a constant width.

$$b = 1.5 \text{ m} \quad a = 1.0 \text{ m}^{-2} \quad D = 1.2 \text{ m} \quad H = 1.4 \text{ m}$$

**Find:** (a) Magnitude and moment of the vertical force on the gate due to water  
(b) Horizontal force applied at  $A$  required to maintain equilibrium

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards})$$

$$\Sigma M_z = 0 \quad (\text{Rotational equilibrium})$$

$$F_v = \int p \, dA_y \quad (\text{Vertical Hydrostatic Force})$$

$$x' \cdot F_v = \int x \, dF_v \quad (\text{Moment of vertical force})$$

$$y' \cdot F_H = \int y \, dF_H \quad (\text{Moment of Horizontal Hydrostatic Force})$$

**Assumptions:** (1) Static fluid  
(2) Incompressible fluid  
(3) Atmospheric pressure acts at free surface of water and on outside of gate


Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

(a) The magnitude and moment of the vertical component of hydrostatic force:

$$F_v = \int p \, dA_y = \int \rho \cdot g \cdot h \cdot b \, dx \quad \text{where } h = D - y \quad x = a \cdot y^3 \quad dx = 3 \cdot a \cdot y^2 \cdot dy$$

$$\text{Substituting back into the relation for the force: } F_v = \int_0^D \rho \cdot g \cdot (D - y) \cdot b \cdot 3 \cdot a \cdot y^2 \, dy = 3 \cdot \rho \cdot g \cdot b \cdot a \cdot \int_0^D (D \cdot y^2 - y^3) \, dy$$


$$\text{Evaluating the integral: } F_v = 3 \cdot \rho \cdot g \cdot b \cdot a \cdot \left( \frac{D^4}{3} - \frac{D^4}{4} \right) = \rho \cdot g \cdot b \cdot a \cdot \frac{D^4}{4}$$



Substituting values we calculate the force:

$$F_V = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1.5 \cdot \text{m} \times 1.0 \cdot \frac{1}{\text{m}^2} \times \frac{(1.2 \cdot \text{m})^4}{4} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$F_V = 7.62 \cdot \text{kN}$$



To find the associated moment:  $x' \cdot F_V = \int x \, dF_V = \int x \cdot p \, dA_y$  Using the derivation for the force:

$$x' \cdot F_V = \int_0^D a \cdot y^3 \cdot \rho \cdot g \cdot (D - y) \cdot b \cdot 3 \cdot a \cdot y^2 \, dy = 3 \cdot \rho \cdot g \cdot a^2 \cdot b \cdot \int_0^D (D \cdot y^5 - y^6) \, dy$$
 Evaluating the integral:

$$x' \cdot F_V = 3 \cdot \rho \cdot g \cdot a^2 \cdot b \cdot \left( \frac{D^7}{6} - \frac{D^7}{7} \right) = \frac{3}{42} \cdot \rho \cdot g \cdot a^2 \cdot b \cdot D^7 = \rho \cdot g \cdot a^2 \cdot b \cdot \frac{D^7}{14}$$
 Now substituting values into this equation:

$$x' \cdot F_V = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \left( \frac{1.0}{\text{m}^2} \right)^2 \times 1.5 \cdot \text{m} \times \frac{(1.20 \cdot \text{m})^7}{14} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$x' \cdot F_V = 3.76 \cdot \text{kN} \cdot \text{m} \quad (\text{positive indicates counterclockwise})$$

(b) Horizontal force at A to maintain equilibrium: we take moments at O:

$$x' \cdot F_V + y' \cdot F_H - H \cdot F_A = 0 \quad \text{Solving for the force at A:} \quad F_A = \frac{1}{H} \cdot (x' \cdot F_V + y' \cdot F_H)$$

To get the moment of the horizontal hydrostatic force:

$$y' \cdot F_H = \int y \, dF_H = \int y \cdot p \, dA_x = \int y \cdot \rho \cdot g \cdot h \cdot b \, dy = \rho \cdot g \cdot b \cdot \int_0^D y \cdot (D - y) \, dy = \rho \cdot g \cdot b \cdot \int_0^D (D \cdot y - y^2) \, dy$$

$$\text{Evaluating the integral: } y' \cdot F_H = \rho \cdot g \cdot b \cdot \left( \frac{D^3}{2} - \frac{D^3}{3} \right) = \rho \cdot g \cdot b \cdot \frac{D^3}{6}$$
 Now substituting values into this equation:

$$y' \cdot F_H = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1.5 \cdot \text{m} \times \frac{(1.20 \cdot \text{m})^3}{6} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$


$$y' \cdot F_H = 4.23 \cdot \text{kN} \cdot \text{m} \quad (\text{counterclockwise})$$

$$\text{Therefore: } F_A = \frac{1}{1.4 \, \text{m}} \cdot (3.76 \cdot \text{kN} \cdot \text{m} + 4.23 \cdot \text{kN} \cdot \text{m}) \quad F_A = 5.71 \cdot \text{kN}$$

## Problem 3.72

[Difficulty: 3]

**3.72** The parabolic gate shown is 2 m wide and pivoted at  $O$ ;  $c = 0.25 \text{ m}^{-1}$ ,  $D = 2 \text{ m}$ , and  $H = 3 \text{ m}$ . Determine (a) the magnitude and line of action of the vertical force on the gate due to the water, (b) the horizontal force applied at  $A$  required to maintain the gate in equilibrium, and (c) the vertical force applied at  $A$  required to maintain the gate in equilibrium.



**Given:** Parabolic gate, hinged at  $O$  has a constant width.

$$b = 2 \cdot \text{m} \quad c = 0.25 \cdot \text{m}^{-1} \quad D = 2 \cdot \text{m} \quad H = 3 \cdot \text{m}$$

**Find:** (a) Magnitude and line of action of the vertical force on the gate due to water  
 (b) Horizontal force applied at  $A$  required to maintain equilibrium  
 (c) Vertical force applied at  $A$  required to maintain equilibrium

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards})$$

$$\Sigma M_Z = 0 \quad (\text{Rotational equilibrium})$$

$$F_V = \int p \, dA_y \quad (\text{Vertical Hydrostatic Force})$$

$$x' \cdot F_V = \int x \, dF_V \quad (\text{Location of line of action})$$


$$F_H = p_c \cdot A \quad (\text{Horizontal Hydrostatic Force})$$

$$h' = h_c + \frac{I_{xx}}{A \cdot h_c} \quad (\text{Location of line of action})$$

**Assumptions:** (1) Static fluid  
 (2) Incompressible fluid  
 (3) Atmospheric pressure acts at free surface of water and on outside of gate

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

(a) The magnitude and line of action of the vertical component of hydrostatic force:



$$F_V = \int p \, dA_y = \int_0^{\sqrt{\frac{D}{c}}} \rho \cdot g \cdot h \cdot b \, dx = \int_0^{\sqrt{\frac{D}{c}}} \rho \cdot g \cdot (D - y) b \, dx = \int_0^{\sqrt{\frac{D}{c}}} \rho \cdot g \cdot (D - c \cdot x^2) b \, dx = \rho \cdot g \cdot b \cdot \int_0^{\sqrt{\frac{D}{c}}} (D - c \cdot x^2) \, dx$$

$$\text{Evaluating the integral: } F_V = \rho \cdot g \cdot b \cdot \left( \frac{D^{\frac{3}{2}}}{\frac{1}{c^{\frac{1}{2}}}} - \frac{1}{3} \cdot \frac{D^{\frac{3}{2}}}{\frac{1}{c^{\frac{1}{2}}}} \right) = \frac{2 \cdot \rho \cdot g \cdot b}{3} \cdot \frac{D^{\frac{3}{2}}}{\frac{1}{c^{\frac{1}{2}}}} \quad (1)$$

Substituting values:  $F_V = \frac{2}{3} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2 \cdot \text{m} \times (2 \cdot \text{m})^{\frac{3}{2}} \times \left(\frac{1}{0.25} \cdot \text{m}\right)^{\frac{1}{2}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $F_V = 73.9 \cdot \text{kN}$

To find the line of action of this force:  $x' \cdot F_V = \int x \, dF_V$  Therefore,  $x' = \frac{1}{F_V} \cdot \int x \, dF_V = \frac{1}{F_V} \cdot \int x \cdot p \, dA_y$

Using the derivation for the force:  $x' = \frac{1}{F_V} \cdot \int_0^{\sqrt{\frac{D}{c}}} x \cdot \rho \cdot g \cdot (D - c \cdot x^2) \cdot b \, dx = \frac{\rho \cdot g \cdot b}{F_V} \cdot \int_0^{\sqrt{\frac{D}{c}}} (D \cdot x - c \cdot x^3) \, dx$

Evaluating the integral:  $x' = \frac{\rho \cdot g \cdot b}{F_V} \cdot \left[ \frac{D}{2} \cdot \frac{D}{c} - \frac{c}{4} \cdot \left(\frac{D}{c}\right)^2 \right] = \frac{\rho \cdot g \cdot b}{F_V} \cdot \frac{D^2}{4 \cdot c}$  Now substituting values into this equation:

$x' = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2 \cdot \text{m} \times \frac{1}{73.9 \times 10^3 \text{ N}} \cdot \frac{1}{4} \times (2 \cdot \text{m})^2 \times \frac{1}{0.25} \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $x' = 1.061 \text{ m}$

To find the required force at A for equilibrium, we need to find the horizontal force of the water on the gate and its line of action as well. Once this force is known we take moments about the hinge (point O).

$F_H = p_c \cdot A = \rho \cdot g \cdot h_c \cdot b \cdot D = \rho \cdot g \cdot \frac{D}{2} \cdot b \cdot D = \rho \cdot g \cdot b \cdot \frac{D^2}{2}$  since  $h_c = \frac{D}{2}$  Therefore the horizontal force is:

$F_H = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2 \cdot \text{m} \times \frac{(2 \cdot \text{m})^2}{2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $F_H = 39.2 \cdot \text{kN}$

To calculate the line of action of this force:


$h' = h_c + \frac{I_{xx}}{A \cdot h_c} = \frac{D}{2} + \frac{b \cdot D^3}{12 \cdot b \cdot D} \cdot \frac{1}{D} = \frac{D}{2} + \frac{D}{6} = \frac{2}{3} \cdot D$   $h' = \frac{2}{3} \cdot 2 \cdot \text{m}$   $h' = 1.333 \text{ m}$

Now we have information to solve parts (b) and (c):

(b) Horizontal force applied at A for equilibrium: take moments about O:

$F_A \cdot H - F_V \cdot x' - F_H \cdot (D - h') = 0$  Solving for  $F_A$   $F_A = \frac{F_V \cdot x' + F_H \cdot (D - h')}{H}$


$F_A = \frac{1}{3} \cdot \frac{1}{\text{m}} \times [73.9 \cdot \text{kN} \times 1.061 \cdot \text{m} + 39.2 \cdot \text{kN} \times (2 \cdot \text{m} - 1.333 \cdot \text{m})]$   $F_A = 34.9 \cdot \text{kN}$



(c) Vertical force applied at A for equilibrium: take moments about O:

$F_A \cdot L - F_V \cdot x' - F_H \cdot (D - h') = 0$  Solving for  $F_A$   $F_A = \frac{F_V \cdot x' + F_H \cdot (D - h')}{L}$

L is the value of x at y = H. Therefore:  $L = \sqrt{\frac{H}{c}}$   $L = \sqrt{3 \cdot \text{m} \times \frac{1}{0.25} \cdot \text{m}}$   $L = 3.464 \text{ m}$




$F_A = \frac{1}{3.464} \cdot \frac{1}{\text{m}} \times [73.9 \cdot \text{kN} \times 1.061 \cdot \text{m} + 39.2 \cdot \text{kN} \times (2 \cdot \text{m} - 1.333 \cdot \text{m})]$   $F_A = 30.2 \cdot \text{kN}$

### Problem 3.73

[Difficulty: 2]

**3.73** Liquid concrete is poured into the form ( $R = 2$  ft). The form is  $w = 15$  ft wide normal to the diagram. Compute the magnitude of the vertical force exerted on the form by the concrete, and specify its line of action.



**Given:** Liquid concrete is poured into the form shown  
 $R = 2$  ft    $w = 15$  ft    $SG_c = 2.5$  (Table A.1, App. A)

**Find:** Magnitude and line of action of the vertical force on the form

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure -  $h$  is positive downwards)

$$F_V = \int p \, dA_y \quad \text{(Vertical Hydrostatic Force)}$$

$$x' \cdot F_V = \int x \, dF_V \quad \text{(Moment of vertical force)}$$

**Assumptions:** (1) Static fluid  
 (2) Incompressible fluid  
 (3) Atmospheric pressure acts at free surface of concrete and on outside of gate

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

$$F_V = \int p \, dA_y = \int \rho \cdot g \cdot h \cdot \sin(\theta) \, dA \quad \text{where} \quad dA = w \cdot R \cdot d\theta \quad \text{and} \quad h = R - y = R - R \cdot \sin(\theta)$$

$$\text{Therefore, } F_V = \int_0^{\frac{\pi}{2}} \rho \cdot g \cdot (R - R \cdot \sin(\theta)) \cdot w \cdot R \cdot \sin(\theta) \, d\theta = \rho \cdot g \cdot w \cdot R^2 \cdot \int_0^{\frac{\pi}{2}} [\sin(\theta) - (\sin(\theta))^2] \, d\theta$$

$$\text{Evaluating the integral: } F_V = \rho \cdot g \cdot w \cdot R^2 \cdot \left[ -(0 - 1) - \left( \frac{\pi}{4} - 0 \right) + (0 - 0) \right] = \rho \cdot g \cdot w \cdot R^2 \cdot \left( 1 - \frac{\pi}{4} \right)$$

$$\text{The density of concrete is: } \rho = 2.5 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \rho = 4.85 \cdot \frac{\text{slug}}{\text{ft}^3}$$

$$\text{Substituting values we calculate the force: } F_V = 4.85 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 15 \cdot \text{ft} \times (2 \cdot \text{ft})^2 \times \left( 1 - \frac{\pi}{4} \right) \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_V = 2011 \cdot \text{lb} \cdot \text{ft}$$

To find the line of action:  $x' \cdot F_V = \int x \, dF_V = \int x \cdot p \, dA_y$  Using the derivation for the force:

$$x' \cdot F_v = \int R \cdot \cos(\theta) \cdot \rho \cdot g \cdot (R - R \cdot \sin(\theta)) \cdot w \cdot R \cdot \sin(\theta) \, d\theta = \rho \cdot g \cdot w \cdot R^3 \cdot \int_0^{\frac{\pi}{2}} [\sin(\theta) \cdot \cos(\theta) - (\sin(\theta))^2 \cdot \cos(\theta)] \, d\theta$$

Evaluating the integral:  $x' \cdot F_v = \rho \cdot g \cdot w \cdot R^3 \cdot \left(\frac{1}{2} - \frac{1}{3}\right) = \rho \cdot g \cdot w \cdot \frac{R^3}{6}$  Therefore the line of action of the force is:

$$x' = \frac{x' \cdot F_v}{F_v} = \frac{\rho \cdot g \cdot w \cdot \frac{R^3}{6}}{\rho \cdot g \cdot w \cdot R^2 \cdot \left(1 - \frac{\pi}{4}\right)} = \frac{R}{6 \cdot \left(1 - \frac{\pi}{4}\right)}$$


Substituting values:  $x' = \frac{2 \cdot \text{ft}}{6 \cdot \left(1 - \frac{\pi}{4}\right)}$

$x' = 1.553 \cdot \text{ft}$

## Problem 3.74

[Difficulty: 2]

**3.74** An open tank is filled with water to the depth indicated. Atmospheric pressure acts on all outer surfaces of the tank. Determine the magnitude and line of action of the vertical component of the force of the water on the curved part of the tank bottom.



**Given:** Open tank as shown. Width of curved surface  $b = 10 \cdot \text{ft}$


**Find:** (a) Magnitude of the vertical force component on the curved surface  
(b) Line of action of the vertical component of the force

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = \gamma$  (Hydrostatic Pressure - h is positive downwards)

$$F_v = - \int p \, dA_y \quad (\text{Vertical Hydrostatic Force})$$

$$x' \cdot F_v = \int x \, dF_v \quad (\text{Moment of vertical force})$$



**Assumptions:** (1) Static fluid  
(2) Incompressible fluid  
(3) Atmospheric pressure acts at free surface of water and on outside of wall

Integrating the hydrostatic pressure equation:  $p = \gamma \cdot h$  We can define along the surface  $h = L - (R^2 - x^2)^{\frac{1}{2}}$

We also define the incremental area on the curved surface as:  $dA_y = b \cdot dx$  Substituting these into the force equation we get:

$$F_v = - \int p \, dA_y = - \int_0^R \gamma \cdot \left[ L - (R^2 - x^2)^{\frac{1}{2}} \right] \cdot b \, dx = -\gamma \cdot b \cdot \int_0^R (L - \sqrt{R^2 - x^2}) \, dx = -\gamma \cdot b \cdot R \cdot \left( L - R \cdot \frac{\pi}{4} \right)$$

$$F_v = - \left[ 62.4 \cdot \frac{\text{lb}}{\text{ft}^3} \times 10 \cdot \text{ft} \times 4 \cdot \text{ft} \times \left( 10 \cdot \text{ft} - 4 \cdot \text{ft} \times \frac{\pi}{4} \right) \right] \quad F_v = -17.12 \times 10^3 \cdot \text{lb} \cdot \text{ft} \quad (\text{negative indicates downward})$$

To find the line of action of the force:  $x' \cdot F_v = \int x \, dF_v$  where  $dF_v = -\gamma \cdot b \cdot (L - \sqrt{R^2 - x^2}) \cdot dx$

$$\text{Therefore:} \quad x' = \frac{x' \cdot F_v}{F_v} = \frac{1}{\gamma \cdot b \cdot R \cdot \left( L - R \cdot \frac{\pi}{4} \right)} \cdot \int_0^R x \cdot \gamma \cdot b \cdot (L - \sqrt{R^2 - x^2}) \, dx = \frac{1}{R \cdot \left( L - R \cdot \frac{\pi}{4} \right)} \cdot \int_0^R (L \cdot x - x \cdot \sqrt{R^2 - x^2}) \, dx$$


$$\text{Evaluating the integral:} \quad x' = \frac{4}{R \cdot (4 \cdot L - \pi \cdot R)} \cdot \left( \frac{1}{2} \cdot L \cdot R^2 - \frac{1}{3} \cdot R^3 \right) = \frac{4 \cdot R^2}{R \cdot (4 \cdot L - \pi \cdot R)} \cdot \left( \frac{L}{2} - \frac{R}{3} \right) = \frac{4 \cdot R}{4 \cdot L - \pi \cdot R} \cdot \left( \frac{L}{2} - \frac{R}{3} \right)$$

$$\text{Substituting known values:} \quad x' = \frac{4 \cdot 4 \cdot \text{ft}}{4 \cdot 10 \cdot \text{ft} - \pi \cdot 4 \cdot \text{ft}} \cdot \left( \frac{10 \cdot \text{ft}}{2} - \frac{4 \cdot \text{ft}}{3} \right) \quad x' = 2.14 \cdot \text{ft}$$

## Problem 3.75

[Difficulty: 2]

**3.75** A spillway gate formed in the shape of a circular arc is  $w$  m wide. Find the magnitude and line of action of the vertical component of the force due to all fluids acting on the gate.



**Given:** Gate formed in the shape of a circular arc has width  $w$ . Liquid is water; depth  $h = R$

**Find:** (a) Magnitude of the net vertical force component due to fluids acting on the gate  
(b) Line of action of the vertical component of the force

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dy} = \rho \cdot g$  (Hydrostatic Pressure -  $y$  is positive downwards)

$$F_v = - \int p \, dA_y \quad \text{(Vertical Hydrostatic Force)}$$

$$x' \cdot F_v = \int x \, dF_v \quad \text{(Moment of vertical force)}$$

**Assumptions:** (1) Static fluid  
(2) Incompressible fluid  
(3) Atmospheric pressure acts at free surface of water and on outside of gate

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot y$

Instead of  $y$ , we use  $\theta$  as our variable of integration:  $y = R \cdot \sin(\theta)$

Therefore,  $dy = R \cdot \cos(\theta) \cdot d\theta$  In addition,  $dA_y = w \cdot R \cdot \sin(\theta) \cdot d\theta$

$$\text{Therefore, } F_v = - \int_0^{\frac{\pi}{2}} \rho \cdot g \cdot R \cdot \sin(\theta) \cdot w \cdot R \cdot \sin(\theta) \, d\theta = -\rho \cdot g \cdot R^2 \cdot w \cdot \int_0^{\frac{\pi}{2}} (\sin(\theta))^2 \, d\theta = -\rho \cdot g \cdot R^2 \cdot w \cdot \frac{\pi}{4} \quad F_v = -\frac{\pi \cdot \rho \cdot g \cdot R^2 \cdot w}{4}$$

(negative indicates downward)

To find the line of action of the vertical component of the force:  $x' \cdot F_v = \int x \, dF_v$  where  $x = R \cdot \cos(\theta)$  and the elemental force is


$dF_v = -\rho \cdot g \cdot R^2 \cdot w \cdot (\sin(\theta))^2 \cdot d\theta$  Substituting into the above integral yields:

$$x' = \frac{x' \cdot F_v}{F_v} = -\frac{4}{\pi \cdot \rho \cdot g \cdot R^2 \cdot w} \cdot \int_0^{\frac{\pi}{2}} -(R \cdot \cos(\theta)) \cdot [\rho \cdot g \cdot R^2 \cdot w \cdot (\sin(\theta))^2] \, d\theta = \frac{4 \cdot R}{\pi} \cdot \int_0^{\frac{\pi}{2}} (\sin(\theta))^2 \cdot \cos(\theta) \, d\theta = \frac{4 \cdot R}{\pi} \cdot \frac{1}{3} \quad x' = \frac{4 \cdot R}{3 \cdot \pi}$$

## Problem 3.76

[Difficulty: 3]

**3.76** A dam is to be constructed using the cross-section shown. Assume the dam width is  $w = 160$  ft. For water height  $H = 9$  ft, calculate the magnitude and line of action of the vertical force of water on the dam face. Is it possible for water forces to overturn this dam? Under what circumstances will this happen?



**Given:** Dam with cross-section shown. Width of dam  $b = 160$  ft

**Find:** (a) Magnitude and line of action of the vertical force component on the dam  
(b) If it is possible for the water to overturn dam

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad (\text{Hydrostatic Pressure - } h \text{ is positive downwards from free surface})$$

$$F_V = \int p \, dA_y \quad (\text{Vertical Hydrostatic Force})$$

$$F_H = p_c \cdot A \quad (\text{Horizontal Hydrostatic Force})$$

$$x' \cdot F_V = \int x \, dF_V \quad (\text{Moment of vertical force})$$

$$h' = h_c + \frac{I_{xx}}{h_c \cdot A} \quad (\text{Line of action of vertical force})$$

$$\Sigma M_z = 0 \quad (\text{Rotational Equilibrium})$$


**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts at free surface of water and on outside of dam

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

Into the vertical force equation:  $F_V = \int p \, dA_y = \int_{x_A}^{x_B} \rho \cdot g \cdot h \cdot b \, dx = \rho \cdot g \cdot b \cdot \int_{x_A}^{x_B} (H - y) \, dx$

From the definition of the dam contour:  $x \cdot y - A \cdot y = B$  Therefore:  $y = \frac{B}{x - A}$  and  $x_A = \frac{10 \cdot \text{ft}^2}{9 \cdot \text{ft}} + 1 \cdot \text{ft}$   $x_A = 2.11$  ft



Into the force equation:  $F_v = \rho \cdot g \cdot b \cdot \int_{x_A}^{x_B} \left( H - \frac{B}{x-A} \right) dx = \rho \cdot g \cdot b \cdot \left[ H \cdot (x_B - x_A) - B \cdot \ln \left( \frac{x_B - A}{x_A - A} \right) \right]$  Substituting known values:

$$F_v = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 160 \cdot \text{ft} \times \left[ 9 \cdot \text{ft} \times (7.0 \cdot \text{ft} - 2.11 \cdot \text{ft}) - 10 \cdot \text{ft}^2 \times \ln \left( \frac{7.0 - 1}{2.11 - 1} \right) \right] \cdot \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_v = 2.71 \times 10^5 \cdot \text{lbf}$$

To find the line of action of the force:  $x' \cdot F_v = \int x dF_v$  where  $dF_v = \rho \cdot g \cdot b \cdot \left( H - \frac{B}{x-A} \right) \cdot dx$  Therefore:

$$x' = \frac{x' \cdot F_v}{F_v} = \frac{1}{F_v} \cdot \int_{x_A}^{x_B} x \cdot \rho \cdot g \cdot b \cdot \left( H - \frac{B}{x-A} \right) dx = \frac{1}{H \cdot (x_B - x_A) - B \cdot \ln \left( \frac{x_B - A}{x_A - A} \right)} \cdot \int_{x_A}^{x_B} \left( H \cdot x - \frac{B \cdot x}{x-A} \right) dx$$

Evaluating the integral:  $x' = \frac{\frac{H}{2} \cdot (x_B^2 - x_A^2) - B \cdot (x_B - x_A) - B \cdot A \cdot \ln \left( \frac{x_B - A}{x_A - A} \right)}{H \cdot (x_B - x_A) - B \cdot \ln \left( \frac{x_B - A}{x_A - A} \right)}$  Substituting known values we get:

$$x' = \frac{\frac{9 \cdot \text{ft}}{2} \times (7^2 - 2.11^2) \cdot \text{ft}^2 - 10 \cdot \text{ft}^2 \times (7 - 2.11) \cdot \text{ft} - 10 \cdot \text{ft}^2 \times 1 \cdot \text{ft} \times \ln \left( \frac{7 - 1}{2.11 - 1} \right)}{9 \cdot \text{ft} \times (7 - 2.11) \cdot \text{ft} - 10 \cdot \text{ft}^2 \times \ln \left( \frac{7 - 1}{2.11 - 1} \right)} \quad x' = 4.96 \cdot \text{ft}$$

To determine whether or not the water can overturn the dam, we need the horizontal force and its line of action:

$$F_H = p_c \cdot A = \rho \cdot g \cdot \frac{H}{2} \cdot H \cdot b = \frac{\rho \cdot g \cdot b \cdot H^2}{2}$$

Substituting values:  $F_H = \frac{1}{2} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 160 \cdot \text{ft} \times (9 \cdot \text{ft})^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$   $F_H = 4.05 \times 10^5 \cdot \text{lbf}$

For the line of action:  $h' = h_c + \frac{I_{xx}}{h_c \cdot A}$  where  $h_c = \frac{H}{2}$   $A = H \cdot b$   $I_{xx} = \frac{b \cdot H^3}{12}$

Therefore:  $h' = \frac{H}{2} + \frac{b \cdot H^3}{12} \cdot \frac{2}{H} \cdot \frac{1}{b \cdot H} = \frac{H}{2} + \frac{H}{6} = \frac{2}{3} \cdot H$   $h' = \frac{2}{3} \cdot 9 \cdot \text{ft}$   $h' = 6.00 \cdot \text{ft}$

Taking moments of the hydrostatic forces about the origin:

$$M_w = F_H \cdot (H - h') - F_v \cdot x' \quad M_w = 4.05 \times 10^5 \cdot \text{lbf} \times (9 - 6) \cdot \text{ft} - 2.71 \times 10^5 \cdot \text{lbf} \times 4.96 \cdot \text{ft} \quad M_w = -1.292 \times 10^5 \cdot \text{lbf} \cdot \text{ft}$$


The negative sign indicates that this is a clockwise moment about the origin. Since the weight of the dam will also contribute a clockwise moment about the origin, these two moments should not cause the dam to tip to the left.

Therefore, the water can not overturn the dam.

## Problem 3.77

[Difficulty: 3]

**3.77** A Tainter gate used to control water flow from the Uniontown Dam on the Ohio River is shown; the gate width is  $w = 35$  m. Determine the magnitude, direction, and line of action of the force from the water acting on the gate.



**Given:** Tainter gate as shown  $w = 35$  m

**Find:** Force of the water acting on the gate

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure - h is positive downwards from free surface)

$dF = p \cdot dA$  (Hydrostatic Force)

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts at free surface of water and on outside of gate

Integrating the hydrostatic pressure equation:

$$p = \rho \cdot g \cdot h = \rho \cdot g \cdot R \cdot \sin(\theta)$$

Resolving the hydrostatic force into horizontal and vertical components:

$$dF_H = dF \cdot \cos(\theta) = p \cdot dA \cdot \cos(\theta) = \rho \cdot g \cdot R \cdot \sin(\theta) \cdot w \cdot R \cdot d\theta \cdot \cos(\theta) \quad \text{since} \quad dA = w \cdot R \cdot d\theta$$

Integrating this expression:  $F_H = \int_0^{\theta_1} \rho \cdot g \cdot R^2 \cdot w \cdot \sin(\theta) \cdot \cos(\theta) \, d\theta$  where  $\theta_1 = \text{asin}\left(\frac{10 \cdot \text{m}}{20 \cdot \text{m}}\right) = 30\text{-deg}$

$$F_H = \rho \cdot g \cdot R^2 \cdot w \cdot \int_0^{30\text{-deg}} \sin(\theta) \cdot \cos(\theta) \, d\theta = \rho \cdot g \cdot R^2 \cdot w \cdot \frac{(\sin(30\text{-deg}))^2}{2} = \frac{\rho \cdot g \cdot R^2 \cdot w}{8} \quad \text{Substituting known values:}$$

$$F_H = \frac{1}{8} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (20 \cdot \text{m})^2 \times 35 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_H = 1.715 \times 10^7 \cdot \text{N}$$

Similarly, we can calculate the vertical component of the hydrostatic force:  $dF_V = dF \cdot \sin(\theta) = p \cdot dA \cdot \sin(\theta) = \rho \cdot g \cdot R^2 \cdot w \cdot (\sin(\theta))^2 \cdot d\theta$

$$F_V = \rho \cdot g \cdot R^2 \cdot w \cdot \int_0^{30\text{-deg}} (\sin(\theta))^2 \, d\theta = \rho \cdot g \cdot R^2 \cdot w \cdot \left(\frac{\pi}{12} - \frac{\sqrt{3}}{8}\right) \quad \text{Substituting known values:}$$

$$F_V = \left(\frac{\pi}{12} - \frac{\sqrt{3}}{8}\right) \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (20 \cdot \text{m})^2 \times 35 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_V = 6.21 \times 10^6 \cdot \text{N}$$

Now since the gate surface in contact with the water is a circular arc, all elements  $dF$  of the force, and hence the line of action of the resultant must pass through the pivot. Thus:

Magnitude of the resultant force:

$$F_R = \sqrt{F_H^2 + F_V^2} \quad F_R = \sqrt{(1.715 \times 10^7 \cdot \text{N})^2 + (6.21 \times 10^6 \cdot \text{N})^2} \quad F_R = 1.824 \times 10^7 \text{N}$$

The line of action of the force:


$$\alpha = \text{atan}\left(\frac{F_V}{F_H}\right) \quad \alpha = \text{atan}\left(\frac{6.21 \times 10^6 \cdot \text{N}}{1.715 \times 10^7 \cdot \text{N}}\right) \quad \alpha = 19.9 \cdot \text{deg}$$

The force passes through the pivot at an angle  $\alpha$  to the horizontal.

## Problem 3.78

[Difficulty: 4]

**3.78** A gate, in the shape of a quarter-cylinder, hinged at *A* and sealed at *B*, is 3 m wide. The bottom of the gate is 4.5 m below the water surface. Determine the force on the stop at *B* if the gate is made of concrete;  $R = 3$  m.




**Given:** Gate geometry

**Find:** Force on stop *B*

**Solution:**

Basic equations  $\frac{dp}{dh} = \rho \cdot g$   
 $\Sigma M_A = 0$



Assumptions: static fluid;  $\rho = \text{constant}$ ;  $p_{\text{atm}}$  on other side

For incompressible fluid  $p = \rho \cdot g \cdot h$  where  $p$  is gage pressure and  $h$  is measured downwards

We need to compute force (including location) due to water on curved surface and underneath. For curved surface we could integrate pressure, but here we use the concepts that  $F_V$  (see sketch) is equivalent to the weight of fluid above, and  $F_H$  is equivalent to the force on a vertical flat plate. Note that the sketch only shows forces that will be used to compute the moment at *A*

For  $F_V$   $F_V = W_1 - W_2$

with  $W_1 = \rho \cdot g \cdot w \cdot D \cdot R = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 3 \cdot \text{m} \times 4.5 \cdot \text{m} \times 3 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $W_1 = 397 \cdot \text{kN}$

$W_2 = \rho \cdot g \cdot w \cdot \frac{\pi \cdot R^2}{4} = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 3 \cdot \text{m} \times \frac{\pi}{4} \times (3 \cdot \text{m})^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $W_2 = 208 \cdot \text{kN}$

$F_V = W_1 - W_2$   $F_V = 189 \cdot \text{kN}$

with  $x$  given by  $F_V \cdot x = W_1 \cdot \frac{R}{2} - W_2 \cdot \frac{4 \cdot R}{3 \cdot \pi}$  or  $x = \frac{W_1}{F_V} \cdot \frac{R}{2} - \frac{W_2}{F_V} \cdot \frac{4 \cdot R}{3 \cdot \pi}$

$x = \frac{397}{189} \times \frac{3 \cdot \text{m}}{2} - \frac{208}{189} \times \frac{4}{3 \cdot \pi} \times 3 \cdot \text{m}$   $x = 1.75 \text{ m}$

For  $F_H$  Computing equations  $F_H = p_c \cdot A$   $y' = y_c + \frac{I_{xx}}{A \cdot y_c}$

Hence 
$$F_H = p_c \cdot A = \rho \cdot g \cdot \left(D - \frac{R}{2}\right) \cdot w \cdot R$$

$$F_H = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \left(4.5 \cdot \text{m} - \frac{3 \cdot \text{m}}{2}\right) \times 3 \cdot \text{m} \times 3 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_H = 265 \cdot \text{kN}$$

The location of this force is

$$y' = y_c + \frac{I_{xx}}{A \cdot y_c} = \left(D - \frac{R}{2}\right) + \frac{w \cdot R^3}{12} \times \frac{1}{w \cdot R \cdot \left(D - \frac{R}{2}\right)} = D - \frac{R}{2} + \frac{R^2}{12 \cdot \left(D - \frac{R}{2}\right)}$$

$$y' = 4.5 \cdot \text{m} - \frac{3 \cdot \text{m}}{2} + \frac{(3 \cdot \text{m})^2}{12 \times \left(4.5 \cdot \text{m} - \frac{3 \cdot \text{m}}{2}\right)} \quad y' = 3.25 \text{ m}$$

The force  $F_1$  on the bottom of the gate is  $F_1 = p \cdot A = \rho \cdot g \cdot D \cdot w \cdot R$

$$F_1 = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 4.5 \cdot \text{m} \times 3 \cdot \text{m} \times 3 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_1 = 397 \cdot \text{kN}$$

For the concrete gate (SG = 2.4 from Table A.2)

$$W_{\text{Gate}} = \text{SG} \cdot \rho \cdot g \cdot w \cdot \frac{\pi \cdot R^2}{4} = 2.4 \cdot 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 3 \cdot \text{m} \times \frac{\pi}{4} \times (3 \cdot \text{m})^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad W_{\text{Gate}} = 499 \cdot \text{kN}$$

Hence, taking moments about A 
$$F_B \cdot R + F_1 \cdot \frac{R}{2} - W_{\text{Gate}} \cdot \frac{4 \cdot R}{3 \cdot \pi} - F_V \cdot x - F_H \cdot [y' - (D - R)] = 0$$

$$F_B = \frac{4}{3 \cdot \pi} \cdot W_{\text{Gate}} + \frac{x}{R} \cdot F_V + \frac{[y' - (D - R)]}{R} \cdot F_H - \frac{1}{2} \cdot F_1$$


$$F_B = \frac{4}{3 \cdot \pi} \times 499 \cdot \text{kN} + \frac{1.75}{3} \times 189 \cdot \text{kN} + \frac{[3.25 - (4.5 - 3)]}{3} \times 265 \cdot \text{kN} - \frac{1}{2} \times 397 \cdot \text{kN}$$

$$F_B = 278 \cdot \text{kN}$$

## Problem 3.79

[Difficulty: 4]

**3.79** Consider the cylindrical weir of diameter 3 m and length 6 m. If the fluid on the left has a specific gravity of 1.6, and on the right has a specific gravity of 0.8, find the magnitude and direction of the resultant force.



**Given:** Sphere with different fluids on each side

**Find:** Resultant force and direction

### Solution:

The horizontal and vertical forces due to each fluid are treated separately. For each, the horizontal force is equivalent to that on a vertical flat plate; the vertical force is equivalent to the weight of fluid "above".

For horizontal forces, the computing equation of Section 3-5 is  $F_H = p_c \cdot A$  where  $A$  is the area of the equivalent vertical plate

For vertical forces, the computing equation of Section 3-5 is  $F_V = \rho \cdot g \cdot V$  where  $V$  is the volume of fluid above the curved surface.

The data is

	For water	$\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$	
	For the fluids	$SG_1 = 1.6$	$SG_2 = 0.8$
	For the weir	$D = 3\text{-m}$	$L = 6\text{-m}$

#### (a) Horizontal Forces

For fluid 1 (on the left)

$$F_{H1} = p_c \cdot A = \left( \rho_1 \cdot g \cdot \frac{D}{2} \right) \cdot D \cdot L = \frac{1}{2} \cdot SG_1 \cdot \rho \cdot g \cdot D^2 \cdot L$$

$$F_{H1} = \frac{1}{2} \cdot 1.6 \cdot 999 \cdot \frac{\text{kg}}{\text{m}^3} \cdot 9.81 \cdot \frac{\text{m}}{\text{s}^2} \cdot (3\text{-m})^2 \cdot 6\text{-m} \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_{H1} = 423\text{-kN}$$

For fluid 2 (on the right)


$$F_{H2} = p_c \cdot A = \left( \rho_2 \cdot g \cdot \frac{D}{4} \right) \cdot D \cdot L = \frac{1}{8} \cdot SG_2 \cdot \rho \cdot g \cdot D^2 \cdot L$$

$$F_{H2} = \frac{1}{8} \cdot 0.8 \cdot 999 \cdot \frac{\text{kg}}{\text{m}^3} \cdot 9.81 \cdot \frac{\text{m}}{\text{s}^2} \cdot (3\text{-m})^2 \cdot 6\text{-m} \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_{H2} = 52.9\text{-kN}$$

The resultant horizontal force is  $F_H = F_{H1} - F_{H2} \quad F_H = 370\text{-kN}$

#### (b) Vertical forces

For the left geometry, a "thought experiment" is needed to obtain surfaces with fluid "above"



Hence

$$F_{V1} = SG_1 \cdot \rho \cdot g \cdot \frac{\pi \cdot D^2}{4} \cdot L$$

$$F_{V1} = 1.6 \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\pi \cdot (3 \cdot \text{m})^2}{8} \times 6 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_{V1} = 333 \cdot \text{kN}$$

(Note: Use of buoyancy leads to the same result!)

For the right side, using a similar logic

$$F_{V2} = SG_2 \cdot \rho \cdot g \cdot \frac{\pi \cdot D^2}{4} \cdot L$$

$$F_{V2} = 0.8 \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\pi \cdot (3 \cdot \text{m})^2}{16} \times 6 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_{V2} = 83.1 \cdot \text{kN}$$

The resultant vertical force is  $F_V = F_{V1} + F_{V2}$   $F_V = 416 \cdot \text{kN}$

Finally the resultant force and direction can be computed


$$F = \sqrt{F_H^2 + F_V^2} \quad F = 557 \cdot \text{kN}$$

$$\alpha = \text{atan} \left( \frac{F_V}{F_H} \right) \quad \alpha = 48.3 \cdot \text{deg}$$

## Problem 3.80

[Difficulty: 3]

**3.80** A cylindrical weir has a diameter of 3 m and a length of 6 m. Find the magnitude and direction of the resultant force acting on the weir from the water.



**Given:** Cylindrical weir as shown; liquid is water

**Find:** Magnitude and direction of the resultant force of the water on the weir

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad \text{(Hydrostatic Pressure - h is positive downwards from free surface)}$$

$$\vec{dF}_R = -p \cdot dA \quad \text{(Hydrostatic Force)}$$

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts on free surfaces and on the first quadrant of the cylinder

Using the coordinate system shown in the diagram at the right:

$$F_{Rx} = \vec{F}_R \cdot \vec{i} = - \int p \, dA \cdot \vec{i} = - \int p \cdot \cos(\theta + 90 \cdot \text{deg}) \, dA = \int p \cdot \sin(\theta) \, dA$$

$$F_{Ry} = \vec{F}_R \cdot \vec{j} = - \int p \, dA \cdot \vec{j} = - \int p \cdot \cos(\theta) \, dA \quad \text{Now since } dA = L \cdot R \cdot d\theta \text{ it follows that}$$

$$F_{Rx} = \int_0^{\frac{3 \cdot \pi}{2}} p \cdot L \cdot R \cdot \sin(\theta) \, d\theta \quad \text{and} \quad F_{Ry} = - \int_0^{\frac{3 \cdot \pi}{2}} p \cdot L \cdot R \cdot \cos(\theta) \, d\theta$$


Next, we integrate the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$  Now over the range  $0 \leq \theta \leq \pi$   $h_1 = R(1 - \cos(\theta))$

Over the range  $\pi \leq \theta \leq \frac{3 \cdot \pi}{2}$   $h_2 = -R \cdot \cos(\theta)$

Therefore we can express the pressure in terms of  $\theta$  and substitute into the force equations:

$$F_{Rx} = \int_0^{\frac{3 \cdot \pi}{2}} p \cdot L \cdot R \cdot \sin(\theta) \, d\theta = \int_0^{\pi} \rho \cdot g \cdot R \cdot (1 - \cos(\theta)) \cdot L \cdot R \cdot \sin(\theta) \, d\theta - \int_{\pi}^{\frac{3 \cdot \pi}{2}} \rho \cdot g \cdot R \cdot \cos(\theta) \cdot L \cdot R \cdot \sin(\theta) \, d\theta$$

$$F_{Rx} = \rho \cdot g \cdot R^2 \cdot L \cdot \int_0^{\pi} (1 - \cos(\theta)) \cdot \sin(\theta) \, d\theta - \rho \cdot g \cdot R^2 \cdot L \cdot \int_{\pi}^{\frac{3 \cdot \pi}{2}} \cos(\theta) \cdot \sin(\theta) \, d\theta$$



$$F_{Rx} = \rho \cdot g \cdot R^2 \cdot L \cdot \left[ \int_0^{\pi} (1 - \cos(\theta)) \cdot \sin(\theta) \, d\theta - \int_{\pi}^{\frac{3 \cdot \pi}{2}} \cos(\theta) \cdot \sin(\theta) \, d\theta \right] = \rho \cdot g \cdot R^2 \cdot L \cdot \left( 2 - \frac{1}{2} \right) = \frac{3}{2} \cdot \rho \cdot g \cdot R^2 \cdot L$$

Substituting known values:  $F_{Rx} = \frac{3}{2} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (1.5 \cdot \text{m})^2 \times 6 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $F_{Rx} = 198.5 \cdot \text{kN}$

Similarly we can calculate the vertical force component:

$$F_{Ry} = - \int_0^{\frac{3 \cdot \pi}{2}} p \cdot L \cdot R \cdot \cos(\theta) \, d\theta = - \left[ \int_0^{\pi} \rho \cdot g \cdot R \cdot (1 - \cos(\theta)) \cdot L \cdot R \cdot \cos(\theta) \, d\theta - \int_{\pi}^{\frac{3 \cdot \pi}{2}} \rho \cdot g \cdot R \cdot \cos(\theta) \cdot L \cdot R \cdot \cos(\theta) \, d\theta \right]$$

$$F_{Ry} = -\rho \cdot g \cdot R^2 \cdot L \cdot \left[ \int_0^{\pi} (1 - \cos(\theta)) \cdot \cos(\theta) \, d\theta - \int_{\pi}^{\frac{3 \cdot \pi}{2}} (\cos(\theta))^2 \, d\theta \right] = \rho \cdot g \cdot R^2 \cdot L \cdot \left( \frac{\pi}{2} + \frac{3 \cdot \pi}{4} - \frac{\pi}{2} \right) = \frac{3 \cdot \pi}{4} \cdot \rho \cdot g \cdot R^2 \cdot L$$

Substituting known values:  $F_{Ry} = \frac{3 \cdot \pi}{4} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (1.5 \cdot \text{m})^2 \times 6 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $F_{Ry} = 312 \cdot \text{kN}$

Now since the weir surface in contact with the water is a circular arc, all elements  $dF$  of the force, and hence the line of action of the resultant force, must pass through the pivot. Thus:

Magnitude of the resultant force:  $F_R = \sqrt{(198.5 \cdot \text{kN})^2 + (312 \cdot \text{kN})^2}$   $F_R = 370 \cdot \text{kN}$

The line of action of the force:  $\alpha = \text{atan}\left(\frac{312 \cdot \text{kN}}{198.5 \cdot \text{kN}}\right)$   $\alpha = 57.5 \cdot \text{deg}$

## Problem 3.81

[Difficulty: 3]

**3.81** A cylindrical log of diameter  $D$  rests against the top of a dam. The water is level with the top of the log and the center of the log is level with the top of the dam. Obtain expressions for (a) the mass of the log per unit length and (b) the contact force per unit length between the log and dam.

**Given:** Cylindrical log floating against dam

**Find:** (a) Mass per unit length of the log (b) Contact force per unit length between log and dam

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**


$$\frac{dp}{dh} = \rho \cdot g \quad \text{(Hydrostatic Pressure - } h \text{ is positive downwards from free surface)}$$

$$\rightarrow \quad \rightarrow$$

$$dF = p \cdot dA \quad \text{(Hydrostatic Force)}$$

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts on free surfaces and on the first quadrant of the log



Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h = \rho \cdot g \cdot R \cdot (1 - \cos(\theta))$

Resolving the incremental force into horizontal and vertical components:

$$dF = p \cdot dA = p \cdot w \cdot R \cdot d\theta = \rho \cdot g \cdot R \cdot (1 - \cos(\theta)) \cdot w \cdot R \cdot d\theta = \rho \cdot g \cdot R^2 \cdot w \cdot (1 - \cos(\theta))$$

$$dF_H = dF \cdot \sin(\theta) = \rho \cdot g \cdot R^2 \cdot w \cdot (1 - \cos(\theta)) \cdot \sin(\theta) \quad dF_V = dF \cdot \cos(\theta) = \rho \cdot g \cdot R^2 \cdot w \cdot (1 - \cos(\theta)) \cdot \cos(\theta)$$

Integrating the expression for the horizontal force will provide us with the contact force per unit length:

$$F_H = \int_0^{\frac{3 \cdot \pi}{2}} \rho \cdot g \cdot R^2 \cdot w \cdot (1 - \cos(\theta)) \cdot \sin(\theta) \, d\theta = \rho \cdot g \cdot R^2 \cdot w \cdot \int_0^{\frac{3 \cdot \pi}{2}} (\sin(\theta) - \sin(\theta) \cdot \cos(\theta)) \, d\theta = \rho \cdot g \cdot R^2 \cdot w \cdot \left( -\frac{1}{2} + 1 \right) = \frac{\rho \cdot g \cdot R^2 \cdot w}{2}$$

$$\text{Therefore: } \frac{F_H}{w} = \frac{\rho \cdot g \cdot R^2}{2}$$

Integrating the expression for the vertical force will provide us with the mass per unit length of the log:

$$F_V = \int_0^{\frac{3 \cdot \pi}{2}} \rho \cdot g \cdot R^2 \cdot w \cdot (1 - \cos(\theta)) \cdot \cos(\theta) \, d\theta = \rho \cdot g \cdot R^2 \cdot w \cdot \int_0^{\frac{3 \cdot \pi}{2}} (1 - \cos(\theta)) \cdot \cos(\theta) \, d\theta = \rho \cdot g \cdot R^2 \cdot w \cdot \left( -1 - \frac{3 \cdot \pi}{4} \right)$$


$$\text{Therefore: } \frac{F_V}{w} = -\rho \cdot g \cdot R^2 \cdot \left( 1 + \frac{3 \cdot \pi}{4} \right) \quad \text{From a free-body diagram for the log: } \Sigma F_y = 0 \quad -\frac{m}{w} \cdot g - \frac{F_V}{w} = 0 \quad \frac{m}{w} = -\frac{F_V}{w \cdot g}$$

$$\text{Solving for the mass of the log: } \frac{m}{w} = \rho \cdot R^2 \cdot \left( 1 + \frac{3 \cdot \pi}{4} \right)$$

## Problem 3.82

[Difficulty: 3]

**3.82** A curved surface is formed as a quarter of a circular cylinder with  $R = 0.750$  m as shown. The surface is  $w = 3.55$  m wide. Water stands to the right of the curved surface to depth  $H = 0.650$  m. Calculate the vertical hydrostatic force on the curved surface. Evaluate the line of action of this force. Find the magnitude and line of action of the horizontal force on the surface.



**Given:** Curved surface, in shape of quarter cylinder, with given radius  $R$  and width  $w$ ; water stands to depth  $H$ .  
 $R = 0.750\text{-m}$     $w = 3.55\text{-m}$     $H = 0.650\text{-m}$

**Find:** Magnitude and line of action of (a) vertical force and (b) horizontal force on the curved surface

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad \text{(Hydrostatic Pressure - h is positive downwards from free surface)}$$

$$F_V = \int p \, dA_y \quad \text{(Vertical Hydrostatic Force)}$$


$$F_H = p_c \cdot A \quad \text{(Horizontal Hydrostatic Force)}$$

$$x' \cdot F_V = \int x \, dF_v \quad \text{(Moment of vertical force)}$$

$$h' = h_c + \frac{I_{xx}}{h_c \cdot A} \quad \text{(Line of action of horizontal force)}$$

**Assumptions:**


- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts on free surface of the water and on the left side of the curved surface



Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

From the geometry:  $h = H - R \cdot \sin(\theta)$     $y = R \cdot \sin(\theta)$     $x = R \cdot \cos(\theta)$     $dA = w \cdot R \cdot d\theta$

$$\theta_1 = \text{asin}\left(\frac{H}{R}\right) \quad \theta_1 = \text{asin}\left(\frac{0.650}{0.750}\right) \quad \theta_1 = 1.048\text{-rad}$$



Therefore the vertical component of the hydrostatic force is:

$$F_V = \int p \, dA_y = \int \rho \cdot g \cdot h \cdot \sin(\theta) \, dA = \int_0^{\theta_1} \rho \cdot g \cdot (H - R \cdot \sin(\theta)) \cdot \sin(\theta) \cdot w \cdot R \, d\theta$$

$$F_V = \rho \cdot g \cdot w \cdot R \cdot \int_0^{\theta_1} \left[ H \cdot \sin(\theta) - R \cdot (\sin(\theta))^2 \right] d\theta = \rho \cdot g \cdot w \cdot R \cdot \left[ H \cdot (1 - \cos(\theta_1)) - R \cdot \left( \frac{\theta_1}{2} - \frac{\sin(2 \cdot \theta_1)}{4} \right) \right]$$

$$F_V = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 3.55 \cdot \text{m} \times 0.750 \cdot \text{m} \times \left[ 0.650 \cdot \text{m} \times (1 - \cos(1.048 \cdot \text{rad})) - 0.750 \cdot \text{m} \times \left( \frac{1.048}{2} - \frac{\sin(2 \times 1.048 \cdot \text{rad})}{4} \right) \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$F_V = 2.47 \cdot \text{kN}$$

To calculate the line of action of this force:

$$x' \cdot F_V = \int R \cdot \cos(\theta) \cdot \rho \cdot g \cdot h \cdot \sin(\theta) \, dA = \rho \cdot g \cdot w \cdot R^2 \cdot \int_0^{\theta_1} [H \cdot \sin(\theta) \cdot \cos(\theta) - R \cdot (\sin(\theta))^2 \cdot \cos(\theta)] \, d\theta$$

Evaluating the integral:  $x' \cdot F_V = \rho \cdot g \cdot w \cdot R^2 \cdot \left[ \frac{H}{2} \cdot (\sin(\theta_1))^2 - \frac{R}{3} \cdot (\sin(\theta_1))^3 \right]$  Therefore we may find the line of action:

$$x' = \frac{x' \cdot F_V}{F_V} = \frac{\rho \cdot g \cdot w \cdot R^2}{F_V} \cdot \left[ \frac{H}{2} \cdot (\sin(\theta_1))^2 - \frac{R}{3} \cdot (\sin(\theta_1))^3 \right] \quad \text{Substituting in known values: } \sin(\theta_1) = \frac{0.650}{0.750}$$

$$x' = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 3.55 \cdot \text{m} \times (0.750 \cdot \text{m})^2 \times \frac{1}{2.47 \times 10^3 \, \text{N}} \cdot \frac{1}{\text{m}} \times \left[ \frac{0.650 \cdot \text{m}}{2} \times \left( \frac{0.650}{0.750} \right)^2 - \frac{0.750 \cdot \text{m}}{3} \times \left( \frac{0.650}{0.750} \right)^3 \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$x' = 0.645 \, \text{m}$$

$$\text{For the horizontal force: } F_H = p_c \cdot A = \rho \cdot g \cdot h_c \cdot H \cdot w = \rho \cdot g \cdot \frac{H}{2} \cdot H \cdot w = \frac{\rho \cdot g \cdot H^2 \cdot w}{2}$$

$$F_H = \frac{1}{2} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (0.650 \cdot \text{m})^2 \times 3.55 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$F_H = 7.35 \cdot \text{kN}$$

For the line of action of the horizontal force:  $h' = h_c + \frac{I_{xx}}{h_c \cdot A}$  where  $I_{xx} = \frac{w \cdot H^3}{12}$   $A = w \cdot H$  Therefore:

$$h' = h_c + \frac{I_{xx}}{h_c \cdot A} = \frac{H}{2} + \frac{w \cdot H^3}{12} \cdot \frac{2}{H} \cdot \frac{1}{w \cdot H} = \frac{H}{2} + \frac{H}{6} = \frac{2}{3} \cdot H$$

$$h' = \frac{2}{3} \times 0.650 \cdot \text{m}$$

$$h' = 0.433 \, \text{m}$$

## Problem 3.83

[Difficulty: 2]

**3.83** If you throw an anchor out of your canoe but the rope is too short for the anchor to rest on the bottom of the pond, will your canoe float higher, lower, or stay the same? Prove your answer.

**Given:** Canoe floating in a pond

**Find:** What happens when an anchor with too short of a line is thrown from canoe

**Solution:**

**Governing equation:**

$$F_B = \rho_w g V_{disp} = W$$

Before the anchor is thrown from the canoe the buoyant force on the canoe balances out the weight of the canoe and anchor:

$$F_{B_1} = W_{canoe} + W_{anchor} = \rho_w g V_{canoe_1}$$

The anchor weight can be expressed as

$$W_{anchor} = \rho_a g V_a$$

so the initial volume displaced by the canoe can be written as

$$V_{canoe_1} = \frac{W_{canoe}}{\rho_w g} + \frac{\rho_a}{\rho_w} V_a$$

After throwing the anchor out of the canoe there will be buoyant forces acting on the canoe and the anchor. Combined, these buoyant forces balance the canoe weight and anchor weight:

$$F_{B_2} = W_{canoe} + W_{anchor} = \rho_w g V_{canoe_2} + \rho_w g V_a$$

$$V_{canoe_2} = \frac{W_{canoe}}{\rho_w g} + \frac{W_a}{\rho_w g} - V_a$$

Using the anchor weight,


$$V_{canoe_2} = \frac{W_{canoe}}{\rho_w g} + \frac{\rho_a}{\rho_w} V_a - V_a$$

Hence the volume displaced by the canoe after throwing the anchor in is less than when the anchor was in the canoe, meaning that the canoe is floating higher.

## Problem 3.84

[Difficulty: 3]

**3.84** A curved submerged surface, in the shape of a quarter cylinder with radius  $R = 1.0$  ft is shown. The form can withstand a maximum vertical load of 350 lbf before breaking. The width is  $w = 4$  ft. Find the maximum depth  $H$  to which the form may be filled. Find the line of action of the vertical force for this condition. Plot the results over the range of concrete depth  $0 \leq H \leq R$ .



**Given:** Curved surface, in shape of quarter cylinder, with given radius  $R$  and width  $w$ ; liquid concrete stands to depth  $H$ .

$$R = 1 \cdot \text{ft} \quad w = 4 \cdot \text{ft} \quad F_{v\text{max}} = 350 \cdot \text{lbf} \quad \text{SG} = 2.50 \quad \text{From Table A.1, App A}$$

**Find:** (a) Maximum depth of concrete to avoid cracking  
 (b) Line of action on the form.  
 (c) Plot the vertical force and line of action over  $H$  ranging from 0 to  $R$ .


**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure -  $h$  is positive downwards from free surface)

$$F_v = \int p \, dA_y \quad (\text{Vertical Hydrostatic Force})$$

$$x' \cdot F_v = \int x \, dF_v \quad (\text{Moment of vertical force})$$

**Assumptions:** (1) Static fluid  
 (2) Incompressible fluid  
 (3) Atmospheric pressure acts on free surface of the concrete



Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

From the geometry:  $y = R \cdot \sin(\theta)$   $x = R \cdot \cos(\theta)$   $h = y - d$   $d = R - H$   $dA = w \cdot R \cdot d\theta$

Therefore the vertical component of the hydrostatic force is:

$$F_v = \int p \, dA_y = \int \rho \cdot g \cdot h \cdot \sin(\theta) \, dA = \int_{\theta_1}^{\frac{\pi}{2}} \rho \cdot g \cdot (R \cdot \sin(\theta) - d) \cdot \sin(\theta) \cdot w \cdot R \, d\theta \quad \text{where} \quad \theta_1 = \text{asin}\left(\frac{d}{R}\right)$$

$$F_v = \rho \cdot g \cdot w \cdot R \cdot \int_{\theta_1}^{\frac{\pi}{2}} [R \cdot (\sin(\theta))^2 - d \cdot (\sin(\theta))] \, d\theta = \rho \cdot g \cdot w \cdot R \cdot \left[ R \cdot \left( \frac{\pi}{4} - \frac{\theta_1}{2} + \frac{\sin(2 \cdot \theta_1)}{4} \right) - d \cdot \cos(\theta_1) \right] \quad \text{In terms of H:}$$

$$\sin(\theta_1) = \frac{R - H}{R} \quad \cos(\theta_1) = \frac{\sqrt{R^2 - (R - H)^2}}{R} = \frac{\sqrt{2 \cdot R \cdot H - H^2}}{R} \quad \sin(2 \cdot \theta_1) = 2 \cdot \sin(\theta_1) \cdot \cos(\theta_1) = \frac{2 \cdot (R - H) \cdot \sqrt{2 \cdot R \cdot H - H^2}}{R^2}$$

$$F_v = \rho \cdot g \cdot w \cdot R \cdot \left[ R \cdot \left[ \frac{\pi}{4} - \frac{\arcsin\left(1 - \frac{H}{R}\right)}{2} + \frac{(R-H) \cdot \sqrt{2 \cdot R \cdot H - H^2}}{2R^2} \right] - (R-H) \cdot \frac{\sqrt{2 \cdot R \cdot H - H^2}}{R} \right]$$

This equation can be solved iteratively for H:

$$H = 0.773 \cdot \text{ft}$$

To calculate the line of action of this force:

$$x' \cdot F_v = \int x \cdot \rho \cdot g \cdot h \cdot \sin(\theta) \, dA = \rho \cdot g \cdot R^2 \cdot w \cdot \int_{\theta_1}^{\frac{\pi}{2}} \left[ R \cdot (\sin(\theta))^2 \cdot \cos(\theta) - d \cdot \sin(\theta) \cdot \cos(\theta) \right] d\theta$$

Evaluating the integral:

$$x' \cdot F_v = \rho \cdot g \cdot R^2 \cdot w \cdot \left[ \frac{R}{3} \cdot \left[ 1 - (\sin(\theta_1))^3 \right] - \frac{d}{2} \cdot (\cos(\theta_1))^2 \right]$$



Therefore we may find the line of action:

$$x' = \frac{x' \cdot F_v}{F_v} = \frac{\rho \cdot g \cdot R^2 \cdot w}{F_v} \cdot \left[ \frac{R}{3} \cdot \left[ 1 - (\sin(\theta_1))^3 \right] - \frac{d}{2} \cdot (\cos(\theta_1))^2 \right]$$

Substituting in known values:  $\sin(\theta_1) = \frac{1 - 0.773}{1} = 0.227$      $\cos(\theta_1) = \sqrt{1 - 0.227^2} = 0.9739$

$$x' = \left( 2.5 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \right) \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times (1 \cdot \text{ft})^2 \times 4 \cdot \text{ft} \times \frac{1}{350} \cdot \frac{1}{\text{lbf}} \times \left[ \frac{1 \cdot \text{ft}}{3} \times \left[ 1 - (0.227)^3 \right] - \frac{0.227 \cdot \text{ft}}{2} \times (0.9739)^2 \right] \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad x' = 0.396 \cdot \text{ft}$$


We may use the equations we developed above to plot the vertical force and line of action as a function of the height of the concrete in the



## Problem 3.85

[Difficulty: 3]

**3.85** The cross-sectional shape of a canoe is modeled by the curve  $y = ax^2$ , where  $a = 1.2 \text{ ft}^{-1}$  and the coordinates are in feet. Assume the width of the canoe is constant at  $w = 2 \text{ ft}$  over its entire length  $L = 18 \text{ ft}$ . Set up a general algebraic expression relating the total mass of the canoe and its contents to distance  $d$  between the water surface and the gunwale of the floating canoe. Calculate the maximum total mass allowable without swamping the canoe.



**Given:** Model cross section of canoe as a parabola. Assume constant width  $W$  over entire length  $L$

$$y = a \cdot x^2 \quad a = 1.2 \cdot \text{ft}^{-1} \quad W = 2 \cdot \text{ft} \quad L = 18 \cdot \text{ft}$$

**Find:** Expression relating the total mass of canoe and contents to distance  $d$ . Determine maximum allowable total mass without swamping the canoe.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $\frac{dp}{dh} = \rho \cdot g$  (Hydrostatic Pressure -  $h$  is positive downwards from free surface)

$$F_V = \int p \, dA_y \quad \text{(Vertical Hydrostatic Force)}$$

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts on free surface of the water and inner surface of the canoe.

At any value of  $d$  the weight of the canoe and its contents is balanced by the net vertical force of the water on the canoe.

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

$$F_V = \int p \, dA_y = \int \rho \cdot g \cdot h \cdot L \, dx \quad \text{where } h = (H - d) - y$$

To determine the upper limit of integration we remember that  $y = a \cdot x^2$  At the surface

$y = H - d$  Therefore,  $x = \sqrt{\frac{H-d}{a}}$  and so the vertical force is:

$$F_V = 2 \cdot \int_0^{\sqrt{\frac{H-d}{a}}} \rho \cdot g \cdot [(H-d) - a \cdot x^2] \cdot L \, dx = 2 \cdot \rho \cdot g \cdot L \cdot \int_0^{\sqrt{\frac{H-d}{a}}} [(H-d) - a \cdot x^2] \, dx = 2 \cdot \rho \cdot g \cdot L \cdot \left[ \frac{(H-d)^2}{\sqrt{a}} - \frac{a}{3} \cdot \left[ \frac{(H-d)}{a} \right]^{\frac{3}{2}} \right]$$

Upon simplification:  $F_V = 2 \cdot \rho \cdot g \cdot L \cdot \frac{(H-d)^2}{\sqrt{a}} \cdot \left( 1 - \frac{1}{3} \right) = \frac{4 \cdot \rho \cdot g \cdot L}{3 \sqrt{a}} \cdot (H-d)^{\frac{3}{2}} = M \cdot g$  or  $M = \frac{4 \cdot \rho \cdot L}{3 \sqrt{a}} \cdot (H-d)^{\frac{3}{2}}$  where  $M$  is the mass of the canoe.

The limit for no swamping is  $d=0$ , and so:  $M = \frac{4}{3} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 18 \cdot \text{ft} \times \sqrt{\frac{\text{ft}}{1.2}} \times (2.4 \cdot \text{ft})^{\frac{3}{2}} \times \frac{32.174 \cdot \text{lb}}{\text{slug}}$   $M = 5.08 \times 10^3 \cdot \text{lb}$


This leaves us no margin, so if we set  $d=0.2 \text{ ft}$  we get  $M = \frac{4}{3} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 18 \cdot \text{ft} \times \sqrt{\frac{\text{ft}}{1.2}} \times (2.2 \cdot \text{ft})^{\frac{3}{2}} \cdot \frac{32.174 \cdot \text{lb}}{\text{slug}}$   $M = 4.46 \times 10^3 \cdot \text{lb}$

Clearly the answer is highly dependent upon the allowed risk of swamping!

## Problem 3.86

[Difficulty: 4]

**3.86** The cylinder shown is supported by an incompressible liquid of density  $\rho$ , and is hinged along its length. The cylinder, of mass  $M$ , length  $L$ , and radius  $R$ , is immersed in liquid to depth  $H$ . Obtain a general expression for the cylinder specific gravity versus the ratio of liquid depth to cylinder radius,  $\alpha = H/R$ , needed to hold the cylinder in equilibrium for  $0 \leq \alpha < 1$ . Plot the results.



**Given:** Cylinder of mass  $M$ , length  $L$ , and radius  $R$  is hinged along its length and immersed in an incompressible liquid to depth  $H$ .

**Find:** General expression for the cylinder specific gravity as a function of  $\alpha = H/R$  needed to hold the cylinder in equilibrium for  $\alpha$  ranging from 0 to 1.

**Solution:** We will apply the hydrostatics equations to this system.


**Governing Equations:**

$$\frac{dp}{dh} = \rho \cdot g \quad \text{(Hydrostatic Pressure - } h \text{ is positive downwards from free surface)}$$

$$F_V = \int p \, dA_y \quad \text{(Vertical Hydrostatic Force)}$$

$$\Sigma M = 0 \quad \text{(Rotational Equilibrium)}$$

- Assumptions:**
- (1) Static fluid
  - (2) Incompressible fluid
  - (3) Atmospheric pressure acts on free surface of the liquid.



The moments caused by the hydrostatic force and the weight of the cylinder about the hinge need to balance each other.

Integrating the hydrostatic pressure equation:  $p = \rho \cdot g \cdot h$

$$dF_V = dF \cdot \cos(\theta) = p \cdot dA \cdot \cos(\theta) = \rho \cdot g \cdot h \cdot w \cdot R \cdot d\theta \cdot \cos(\theta)$$

Now the depth to which the cylinder is submerged is  $H = h + R \cdot (1 - \cos(\theta))$

Therefore  $h = H - R \cdot (1 - \cos(\theta))$  and into the vertical force equation:

$$dF_V = \rho \cdot g \cdot [H - R \cdot (1 - \cos(\theta))] \cdot w \cdot R \cdot \cos(\theta) \cdot d\theta = \rho \cdot g \cdot w \cdot R^2 \cdot \left[ \frac{H}{R} - (1 - \cos(\theta)) \right] \cdot \cos(\theta) \cdot d\theta$$

$$dF_V = \rho \cdot g \cdot w \cdot R^2 \cdot [(\alpha - 1) \cdot \cos(\theta) + (\cos(\theta))^2] \cdot d\theta = \rho \cdot g \cdot w \cdot R^2 \cdot \left[ (\alpha - 1) \cdot \cos(\theta) + \frac{1 + \cos(2 \cdot \theta)}{2} \right] \cdot d\theta$$

Now as long as  $\alpha$  is not greater than 1, the net horizontal hydrostatic force will be zero due to symmetry, and the vertical force is:

$$F_V = \int_{-\theta_{\max}}^{\theta_{\max}} 1 \, dF_V = \int_0^{\theta_{\max}} 2 \, dF_V \quad \text{where} \quad \cos(\theta_{\max}) = \frac{R - H}{R} = 1 - \alpha \quad \text{or} \quad \theta_{\max} = \arccos(1 - \alpha)$$

$$F_v = 2\rho \cdot g \cdot w \cdot R^2 \cdot \int_0^{\theta_{\max}} \left[ (\alpha - 1) \cdot \cos(\theta) + \frac{1}{2} + \frac{1}{2} \cdot \cos(2\theta) \right] d\theta \quad \text{Now upon integration of this expression we have:}$$

$$F_v = \rho \cdot g \cdot w \cdot R^2 \cdot \left[ \alpha \cos(1 - \alpha) - (1 - \alpha) \cdot \sqrt{\alpha \cdot (2 - \alpha)} \right]$$


The line of action of the vertical force due to the liquid is through the centroid of the displaced liquid, i.e., through the center of the cylinder

The weight of the cylinder is given by:  $W = M \cdot g = \rho_c \cdot V \cdot g = SG \cdot \rho \cdot \pi \cdot R^2 \cdot w \cdot g$  where  $\rho$  is the density of the fluid and  $SG = \frac{\rho_c}{\rho}$

The line of action of the weight is also through the center of the cylinder. Taking moment about the hinge we get:

$$\Sigma M_o = W \cdot R - F_v \cdot R = 0 \quad \text{or in other words} \quad W = F_v \quad \text{and therefore:}$$

$$SG \cdot \rho \cdot \pi \cdot R^2 \cdot w \cdot g = \rho \cdot g \cdot w \cdot R^2 \cdot \left[ \alpha \cos(1 - \alpha) - (1 - \alpha) \cdot \sqrt{\alpha \cdot (2 - \alpha)} \right] \quad SG = \frac{1}{\pi} \cdot \left[ \alpha \cos(1 - \alpha) - (1 - \alpha) \cdot \sqrt{\alpha \cdot (2 - \alpha)} \right]$$



## Problem 3.87

[Difficulty: 4]

**3.87** A canoe is represented by a right semicircular cylinder, with  $R = 1.2$  ft and  $L = 17$  ft. The canoe floats in water that is  $d = 1$  ft deep. Set up a general algebraic expression for the total mass (canoe and contents) that can be floated, as a function of depth. Evaluate for the given conditions. Plot the results over the range of water depth  $0 \leq d \leq R$ .

**Given:** Canoe, modeled as a right semicircular cylindrical shell, floats in water of depth  $d$ . The shell has outer radius  $R$  and length

$$R = 1.2 \cdot \text{ft} \quad L = 17 \cdot \text{ft} \quad d = 1 \cdot \text{ft}$$

**Find:** (a) General expression for the maximum total mass that can be floated, as a function of depth,  
 (b) evaluate for the given conditions  
 (c) plot for range of water depth between 0 and  $R$ .

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$\frac{dp}{dy} = \rho \cdot g$$

(Hydrostatic Pressure -  $y$  is positive downwards from free surface)

$$F_v = \int p \, dA_y$$


(Vertical Hydrostatic Force)

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts on free surface of the liquid.

$y$  is a function of  $\theta$  for a given depth  $d$ :  $y = d - (R - R \cdot \cos(\theta)) = d - R + R \cdot \cos(\theta)$

The maximum value of  $\theta$ :  $\theta_{\max} = \arccos\left[\frac{(R-d)}{R}\right]$



A free-body diagram of the canoe gives:  $\Sigma F_y = 0 = M \cdot g - F_v$  where  $F_v$  is the vertical force of the water on the canoe.

$$F_v = \int p \, dA_y = \int p \cdot \cos(\theta) \, dA = \int_{-\theta_{\max}}^{\theta_{\max}} \rho \cdot g \cdot y \cdot L \cdot R \cdot \cos(\theta) \, d\theta = 2 \cdot \rho \cdot g \cdot L \cdot R \cdot \int_0^{\theta_{\max}} (d - R + R \cdot \cos(\theta)) \cdot \cos(\theta) \, d\theta$$

$$F_v = 2 \cdot \rho \cdot g \cdot L \cdot R \cdot \int_0^{\theta_{\max}} [(d - R) \cdot \cos(\theta) + R \cdot (\cos(\theta))^2] \, d\theta = 2 \cdot \rho \cdot g \cdot L \cdot R \cdot \left[ (d - R) \cdot \sin(\theta_{\max}) + R \cdot \left( \frac{\theta_{\max}}{2} + \frac{\sin(2 \cdot \theta_{\max})}{4} \right) \right]$$


Since  $M = \frac{F_v}{g}$  it follows that  $M = 2 \cdot \rho \cdot L \cdot R \cdot \left[ (d - R) \cdot \sin(\theta_{\max}) + R \cdot \left( \frac{\theta_{\max}}{2} + \frac{\sin(2 \cdot \theta_{\max})}{4} \right) \right]$

For  $R = 1.2 \cdot \text{ft}$   $L = 17 \cdot \text{ft}$  and  $d = 1 \cdot \text{ft}$  we can determine the mass:  $\theta_{\max} = \arccos\left[\frac{(1.2 - 1)}{1.2}\right]$   $\theta_{\max} = 1.403 \cdot \text{rad}$

$$M = 2 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 17 \cdot \text{ft} \times 1.2 \cdot \text{ft} \times \left[ (1 \cdot \text{ft} - 1.2 \cdot \text{ft}) \times \sin(1.403 \cdot \text{rad}) + 1.2 \cdot \text{ft} \times \left( \frac{1.403 \cdot \text{rad}}{2} + \frac{\sin(2 \times 1.403 \cdot \text{rad})}{4} \right) \right] \times \frac{32.2 \cdot \text{lbm}}{\text{slug}}$$

$$M = 1895 \cdot \text{lbm}$$

When we enter the values of  $d/R$  into the expressions for  $\theta_{\max}$  and  $M$ , we get the following graph:



## Problem 3.88

[Difficulty: 4]

**3.88** A glass observation room is to be installed at the corner of the bottom of an aquarium. The aquarium is filled with seawater to a depth of 35 ft. The glass is a segment of a sphere, radius 5 ft, mounted symmetrically in the corner. Compute the magnitude and direction of the net force on the glass structure.

**Given:** Geometry of glass observation room

**Find:** Resultant force and direction

**Assumptions:** Water in aquarium is static and incompressible

### Solution:

The  $x$ ,  $y$  and  $z$  components of force due to the fluid are treated separately. For the  $x$ ,  $y$  components, the horizontal force is equivalent to that on a vertical flat plate; for the  $z$  component, (vertical force) the force is equivalent to the weight of fluid above.

For horizontal forces, the computing equation of Section 3-5 is  $F_H = p_c \cdot A$  where  $A$  is the area of the equivalent vertical plate.

For the vertical force, the computing equation of Section 3-5 is  $F_V = \rho \cdot g \cdot V$  where  $V$  is the volume of fluid above the curved surface.

The data are For water  $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$

For the fluid (Table A.2)  $SG = 1.025$

For the aquarium  $R = 5 \cdot \text{ft}$   $H = 35 \cdot \text{ft}$

#### (a) Horizontal Forces

Consider the  $x$  component

The center of pressure of the glass is  $y_c = H - \frac{4 \cdot R}{3 \cdot \pi}$   $y_c = 32.88 \cdot \text{ft}$

Hence  $F_{Hx} = p_c \cdot A = (SG \cdot \rho \cdot g \cdot y_c) \cdot \frac{\pi \cdot R^2}{4}$

$$F_{Hx} = 1.025 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 32.88 \cdot \text{ft} \times \frac{\pi \cdot (5 \cdot \text{ft})^2}{4} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_{Hx} = 4.13 \times 10^4 \cdot \text{lbf}$$

The  $y$  component is of the same magnitude as the  $x$  component

$$F_{Hy} = F_{Hx} \quad F_{Hy} = 4.13 \times 10^4 \cdot \text{lbf}$$

The resultant horizontal force (at  $45^\circ$  to the  $x$  and  $y$  axes) is

$$F_H = \sqrt{F_{Hx}^2 + F_{Hy}^2} \quad F_H = 5.85 \times 10^4 \cdot \text{lbf}$$

(b) Vertical forces

The vertical force is equal to the weight of fluid above (a volume defined by a rectangular column minus a segment of a sphere)

$$\text{The volume is } V = \frac{\pi \cdot R^2}{4} \cdot H - \frac{4 \cdot \pi \cdot R^3}{3} \quad V = 621.8 \cdot \text{ft}^3$$

$$\text{Then } F_V = SG \cdot \rho \cdot g \cdot V \quad F_V = 1.025 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 621.8 \cdot \text{ft}^3 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$
$$F_V = 3.98 \times 10^4 \cdot \text{lbf}$$

Finally the resultant force and direction can be computed

$$F = \sqrt{F_H^2 + F_V^2} \quad F = 7.07 \times 10^4 \cdot \text{lbf}$$

$$\alpha = \text{atan} \left( \frac{F_V}{F_H} \right) \quad \alpha = 34.3 \cdot \text{deg}$$

Note that  $\alpha$  is the angle the resultant force makes with the horizontal

## Problem \*3.89

[Difficulty: 2]

**3.89** A hydrometer is a specific gravity indicator, the value being indicated by the level at which the free surface intersects the stem when floating in a liquid. The 1.0 mark is the level when in distilled water. For the unit shown, the immersed volume in distilled water is  $15 \text{ cm}^3$ . The stem is 6 mm in diameter. Find the distance,  $h$ , from the 1.0 mark to the surface when the hydrometer is placed in a nitric acid solution of specific gravity 1.5.


**Given:** Hydrometer as shown, submerged in nitric acid. When submerged in water,  $h = 0$  and the immersed volume is 15 cubic cm.  
 $SG = 1.5 \quad d = 6\text{-mm}$

**Find:** The distance  $h$  when immersed in nitric acid.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $F_{\text{buoy}} = \rho \cdot g \cdot V_d$  (Buoyant force is equal to weight of displaced fluid)

**Assumptions:** (1) Static fluid  
 (2) Incompressible fluid



Taking a free body diagram of the hydrometer:  $\Sigma F_z = 0 \quad -M \cdot g + F_{\text{buoy}} = 0$

Solving for the mass of the hydrometer:  $M = \frac{F_{\text{buoy}}}{g} = \rho \cdot V_d$

When immersed in water:  $M = \rho_w \cdot V_w$  When immersed in nitric acid:  $M = \rho_n \cdot V_n$

Since the mass of the hydrometer is the same in both cases:  $\rho_w \cdot V_w = \rho_n \cdot V_n$

When the hydrometer is in the nitric acid:  $V_n = V_w - \frac{\pi}{4} \cdot d^2 \cdot h \quad \rho_n = SG \cdot \rho_w$

Therefore:  $\rho_w \cdot V_w = SG \cdot \rho_w \cdot \left( V_w - \frac{\pi}{4} \cdot d^2 \cdot h \right)$  Solving for the height  $h$ :


$V_w = SG \cdot \left( V_w - \frac{\pi}{4} \cdot d^2 \cdot h \right) \quad V_w \cdot (1 - SG) = -SG \cdot \frac{\pi}{4} \cdot d^2 \cdot h$

$h = V_w \cdot \left( \frac{SG - 1}{SG} \right) \cdot \frac{4}{\pi \cdot d^2} \quad h = 15 \cdot \text{cm}^3 \times \left( \frac{1.5 - 1}{1.5} \right) \times \frac{4}{\pi \times (6\text{-mm})^2} \times \left( \frac{10\text{-mm}}{\text{cm}} \right)^3 \quad h = 177\text{-mm}$

### Problem \*3.90

[Difficulty: 3]

**3.90** Find the specific weight of the sphere shown if its volume is  $0.025\text{m}^3$ . State all assumptions. What is the equilibrium position of the sphere if the weight is removed?



**Given:** Data on sphere and weight

**Find:** SG of sphere; equilibrium position when freely floating

**Solution:**


Basic equation  $F_B = \rho \cdot g \cdot V$  and  $\Sigma F_z = 0$   $\Sigma F_z = 0 = T + F_B - W$

where  $T = M \cdot g$   $M = 10 \cdot \text{kg}$   $F_B = \rho \cdot g \cdot \frac{V}{2}$   $W = SG \cdot \rho \cdot g \cdot V$

Hence  $M \cdot g + \rho \cdot g \cdot \frac{V}{2} - SG \cdot \rho \cdot g \cdot V = 0$   $SG = \frac{M}{\rho \cdot V} + \frac{1}{2}$

$$SG = 10 \cdot \text{kg} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{1}{0.025 \cdot \text{m}^3} + \frac{1}{2} \quad SG = 0.9$$

The specific weight is  $\gamma = \frac{\text{Weight}}{\text{Volume}} = \frac{SG \cdot \rho \cdot g \cdot V}{V} = SG \cdot \rho \cdot g$   $\gamma = 0.9 \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $\gamma = 8829 \cdot \frac{\text{N}}{\text{m}^3}$



For the equilibrium position when floating, we repeat the force balance with  $T = 0$

$$F_B - W = 0 \quad W = F_B \quad \text{with} \quad F_B = \rho \cdot g \cdot V_{\text{submerged}}$$

From references (trying Googling "partial sphere volume")  $V_{\text{submerged}} = \frac{\pi \cdot h^2}{3} \cdot (3 \cdot R - h)$

where  $h$  is submerged depth and  $R$  is the sphere radius  $R = \left(\frac{3 \cdot V}{4 \cdot \pi}\right)^{\frac{1}{3}}$   $R = \left(\frac{3}{4 \cdot \pi} \cdot 0.025 \cdot \text{m}^3\right)^{\frac{1}{3}}$   $R = 0.181\text{ m}$

Hence  $W = SG \cdot \rho \cdot g \cdot V = F_B = \rho \cdot g \cdot \frac{\pi \cdot h^2}{3} \cdot (3 \cdot R - h)$   $h^2 \cdot (3 \cdot R - h) = \frac{3 \cdot SG \cdot V}{\pi}$

$$h^2 \cdot (3 \cdot 0.181 \cdot \text{m} - h) = \frac{3 \cdot 0.9 \cdot 0.025 \cdot \text{m}^3}{\pi} \quad h^2 \cdot (0.544 - h) = 0.0215$$

This is a cubic equation for  $h$ . We can keep guessing  $h$  values, manually iterate, or use Excel's Goal Seek to find  $h = 0.292 \cdot \text{m}$

## Problem \*3.91

[Difficulty: 2]

**3.91** The fat-to-muscle ratio of a person may be determined from a specific gravity measurement. The measurement is made by immersing the body in a tank of water and measuring the net weight. Develop an expression for the specific gravity of a person in terms of their weight in air, net weight in water, and  $SG = f(T)$  for water.

**Given:** Specific gravity of a person is to be determined from measurements of weight in air and the net weight when totally immersed in water.

**Find:** Expression for the specific gravity of a person from the measurements.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equation:**  $F_{buoy} = \rho \cdot g \cdot V_d$  (Buoyant force is equal to weight of displaced fluid)


**Assumptions:** (1) Static fluid  
(2) Incompressible fluid

Taking a free body diagram of the body:  $\Sigma F_y = 0 \quad F_{net} - M \cdot g + F_{buoy} = 0$

$F_{net}$  is the weight measurement for the immersed body.

$F_{net} = M \cdot g - F_{buoy} = M \cdot g - \rho_w \cdot g \cdot V_d$  However in air:  $F_{air} = M \cdot g$

Therefore the weight measured in water is:  $F_{net} = F_{air} - \rho_w \cdot g \cdot V_d$  and  $V_d = \frac{F_{air} - F_{net}}{\rho_w \cdot g}$



Now in order to find the specific gravity of the person, we need his/her density:

$F_{air} = M \cdot g = \rho \cdot g \cdot V_d = \rho \cdot g \cdot \frac{(F_{air} - F_{net})}{\rho_w \cdot g}$  Simplifying this expression we get:  $F_{air} = \frac{\rho}{\rho_w} (F_{air} - F_{net})$

Now if we call the density of water at 4 deg C  $\rho_{w4C}$  then:  $F_{air} = \frac{\left(\frac{\rho}{\rho_{w4C}}\right)}{\left(\frac{\rho_w}{\rho_{w4C}}\right)} (F_{air} - F_{net}) = \frac{SG}{SG_w} \cdot (F_{air} - F_{net})$

Solving this expression for the specific gravity of the person  $SG$ , we get:  $SG = SG_w \cdot \frac{F_{air}}{F_{air} - F_{net}}$

## Problem \*3.92

[Difficulty: 2]

**3.92** Quantify the statement, "Only the tip of an iceberg shows (in seawater)."

**Given:** Iceberg floating in seawater

**Find:** Quantify the statement, "Only the tip of an iceberg shows (in seawater)."

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $F_{\text{buoy}} = \rho \cdot g \cdot V_d$  (Buoyant force is equal to weight of displaced fluid)

**Assumptions:** (1) Static fluid  
(2) Incompressible fluid

Taking a free body diagram of the iceberg:  $\Sigma F_z = 0 \quad -M \cdot g + F_{\text{buoy}} = 0$


$M \cdot g = F_{\text{buoy}} = \rho_{\text{sw}} \cdot g \cdot V_d$  But the mass of the iceberg is also:  $M = \rho_{\text{ice}} \cdot V_{\text{tot}}$

Combining these expressions:  $\rho_{\text{ice}} \cdot V_{\text{tot}} \cdot g = \rho_{\text{sw}} \cdot g \cdot V_d \quad V_d = V_{\text{tot}} \cdot \frac{\rho_{\text{ice}}}{\rho_{\text{sw}}} = V_{\text{tot}} \cdot \frac{SG_{\text{ice}}}{SG_{\text{sw}}}$

The volume of the iceberg above the water is:  $V_{\text{show}} = V_{\text{tot}} - V_d = V_{\text{tot}} \cdot \left( 1 - \frac{SG_{\text{ice}}}{SG_{\text{sw}}} \right)$

Therefore we may define a volume fraction:  $VF = \frac{V_{\text{show}}}{V_{\text{tot}}} = 1 - \frac{SG_{\text{ice}}}{SG_{\text{sw}}}$

Substituting in data from Tables A.1 and A.2 we get:  $VF = 1 - \frac{0.917}{1.025} \quad VF = 0.1054$  Only 10% of the iceberg is above water!



## Problem \*3.93

[Difficulty: 2]

**3.93** An open tank is filled to the top with water. A steel cylindrical container, wall thickness  $\delta = 1$  mm, outside diameter  $D = 100$  mm, and height  $H = 1$  m, with an open top, is gently placed in the water. What is the volume of water that overflows from the tank? How many 1 kg weights must be placed in the container to make it sink? Neglect surface tension effects.

**Given:** Geometry of steel cylinder

**Find:** Volume of water displaced; number of 1 kg wts to make it sink

**Solution:**

The data is For water  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$

For steel (Table A.1)  $SG = 7.83$

For the cylinder  $D = 100\text{-mm}$   $H = 1\text{-m}$   $\delta = 1\text{-mm}$

The volume of the cylinder is  $V_{\text{steel}} = \delta \cdot \left( \frac{\pi \cdot D^2}{4} + \pi \cdot D \cdot H \right)$   $V_{\text{steel}} = 3.22 \times 10^{-4} \cdot \text{m}^3$

The weight of the cylinder is  $W = SG \cdot \rho \cdot g \cdot V_{\text{steel}}$

$$W = 7.83 \times 999 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 3.22 \times 10^{-4} \cdot \text{m}^3 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad W = 24.7 \text{ N}$$

At equilibrium, the weight of fluid displaced is equal to the weight of the cylinder

$$W_{\text{displaced}} = \rho \cdot g \cdot V_{\text{displaced}} = W$$

$$V_{\text{displaced}} = \frac{W}{\rho \cdot g} = 24.7 \cdot \text{N} \times \frac{\text{m}^3}{999 \cdot \text{kg}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad V_{\text{displaced}} = 2.52 \text{ L}$$

To determine how many 1 kg wts will make it sink, we first need to find the extra volume that will need to be displaced

Distance cylinder sank  $x_1 = \frac{V_{\text{displaced}}}{\left( \frac{\pi \cdot D^2}{4} \right)}$   $x_1 = 0.321 \text{ m}$

Hence, the cylinder must be made to sink an additional distance  $x_2 = H - x_1$   $x_2 = 0.679 \text{ m}$

We need to add  $n$  weights so that  $1 \cdot \text{kg} \cdot n \cdot g = \rho \cdot g \cdot \frac{\pi \cdot D^2}{4} \cdot x_2$

$$n = \frac{\rho \cdot \pi \cdot D^2 \cdot x_2}{4 \times 1 \cdot \text{kg}} = 999 \frac{\text{kg}}{\text{m}^3} \times \frac{\pi}{4} \times (0.1 \cdot \text{m})^2 \times 0.679 \cdot \text{m} \times \frac{1}{1 \cdot \text{kg}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad n = 5.33$$

Hence we need  $n = 6$  weights to sink the cylinder

## Problem \*3.94

[Difficulty: 2]

**3.94** Quantify the experiment performed by Archimedes to identify the material content of King Hiero's crown. Assume you can measure the weight of the king's crown in air,  $W_a$ , and the weight in water,  $W_w$ . Express the specific gravity of the crown as a function of these measured values.

**Given:** Experiment performed by Archimedes to identify the material content of King Hiero's crown. The crown was weighed in air and in water.

**Find:** Expression for the specific gravity of the crown as a function of the weights in water and air.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $F_b = \rho \cdot g \cdot V_d$  (Buoyant force is equal to weight of displaced fluid)

**Assumptions:** (1) Static fluid  
(2) Incompressible fluid

Taking a free body diagram of the body:  $\Sigma F_z = 0$   $W_w - M \cdot g + F_b = 0$

$W_w$  is the weight of the crown in water.


$W_w = M \cdot g - F_{\text{buoy}} = M \cdot g - \rho_w \cdot g \cdot V_d$  However in air:  $W_a = M \cdot g$

Therefore the weight measured in water is:  $W_w = W_a - \rho_w \cdot g \cdot V_d$

so the volume is:  $V_d = \frac{W_a - W_w}{\rho_w \cdot g}$  Now the density of the crown is:  $\rho_c = \frac{M}{V_d} = \frac{M \cdot \rho_w \cdot g}{W_a - W_w} = \frac{W_a}{W_a - W_w} \cdot \rho_w$

Therefore, the specific gravity of the crown is:  $SG = \frac{\rho_c}{\rho_w} = \frac{W_a}{W_a - W_w}$   $SG = \frac{W_a}{W_a - W_w}$

Note: by definition specific gravity is the density of an object divided by the density of water at 4 degrees Celsius, so the measured temperature of the water in the experiment and the data from tables A.7 or A.8 may be used to correct for the variation in density of the water with temperature.



## Problem \*3.95

[Difficulty: 2]

---

**3.95** Gas bubbles are released from the regulator of a submerged scuba diver. What happens to the bubbles as they rise through the seawater? Explain.

---

**Open-Ended Problem Statement:** Gas bubbles are released from the regulator of a submerged Scuba diver. What happens to the bubbles as they rise through the seawater?

**Discussion:** Air bubbles released by a submerged diver should be close to ambient pressure at the depth where the diver is swimming. The bubbles are small compared to the depth of submersion, so each bubble is exposed to essentially constant pressure. Therefore the released bubbles are nearly spherical in shape.

The air bubbles are buoyant in water, so they begin to rise toward the surface. The bubbles are quite light, so they reach terminal speed quickly. At low speeds the spherical shape should be maintained. At higher speeds the bubble shape may be distorted.

As the bubbles rise through the water toward the surface, the hydrostatic pressure decreases. Therefore the bubbles expand as they rise. As the bubbles grow larger, one would expect the tendency for distorted bubble shape to be exaggerated.

## Problem \*3.96

[Difficulty: 2]

**3.96** Hot-air ballooning is a popular sport. According to a recent article, “hot-air volumes must be large because air heated to 150°F over ambient lifts only 0.018 lbf/ft<sup>3</sup> compared to 0.066 and 0.071 for helium and hydrogen, respectively.” Check these statements for sea-level conditions. Calculate the effect of increasing the hot-air maximum temperature to 250°F above ambient.

**Given:** Balloons with hot air, helium and hydrogen. Claim lift per cubic foot of 0.018, 0.066, and 0.071 pounds force per cubic foot for respective gases, with the air heated to 150 deg. F over ambient.

**Find:** (a) evaluate the claims of lift per unit volume  
(b) determine change in lift when air is heated to 250 deg. F over ambient.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $L = \rho_a \cdot g \cdot V - \rho_g \cdot g \cdot V$  (Net lift force is equal to difference in weights of air and gas)

$$p = \rho \cdot R \cdot T \quad \text{(Ideal gas equation of state)}$$

**Assumptions:** (1) Static fluid  
(2) Incompressible fluid  
(3) Ideal gas behavior

The lift per unit volume may be written as:  $LV = \frac{L}{V} = g \cdot (\rho_a - \rho_g) = \rho_a \cdot g \cdot \left(1 - \frac{\rho_g}{\rho_a}\right)$  now if we take the ideal gas equation and

we take into account that the pressure inside and outside the balloon are equal:  $\frac{L}{V} = \rho_a \cdot g \cdot \left(1 - \frac{R_a \cdot T_a}{R_g \cdot T_g}\right) = \gamma_a \cdot \left(1 - \frac{R_a \cdot T_a}{R_g \cdot T_g}\right)$

At standard conditions the specific weight of air is:  $\gamma_a = 0.0765 \cdot \frac{\text{lbf}}{\text{ft}^3}$  the gas constant is:  $R_a = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$  and  $T_a = 519 \cdot \text{R}$

For helium:  $R_g = 386.1 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$   $T_g = T_a$  and therefore:  $LV_{\text{He}} = 0.0765 \cdot \frac{\text{lbf}}{\text{ft}^3} \times \left(1 - \frac{53.33}{386.1}\right)$   $LV_{\text{He}} = 0.0659 \cdot \frac{\text{lbf}}{\text{ft}^3}$

For hydrogen:  $R_g = 766.5 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$   $T_g = T_a$  and therefore:  $LV_{\text{H}_2} = 0.0765 \cdot \frac{\text{lbf}}{\text{ft}^3} \times \left(1 - \frac{53.33}{766.5}\right)$   $LV_{\text{H}_2} = 0.0712 \cdot \frac{\text{lbf}}{\text{ft}^3}$

For hot air at 150 degrees above ambient:

$$R_g = R_a \quad T_g = T_a + 150 \cdot \text{R} \quad \text{and therefore:} \quad LV_{\text{air150}} = 0.0765 \cdot \frac{\text{lbf}}{\text{ft}^3} \times \left(1 - \frac{519}{519 + 150}\right) \quad LV_{\text{air150}} = 0.0172 \cdot \frac{\text{lbf}}{\text{ft}^3}$$

The agreement with the claims stated above is good.

For hot air at 250 degrees above ambient:


$$R_g = R_a \quad T_g = T_a + 250 \cdot \text{R} \quad \text{and therefore:} \quad LV_{\text{air250}} = 0.0765 \cdot \frac{\text{lbf}}{\text{ft}^3} \times \left(1 - \frac{519}{519 + 250}\right) \quad LV_{\text{air250}} = 0.0249 \cdot \frac{\text{lbf}}{\text{ft}^3}$$

$$\frac{LV_{\text{air250}}}{LV_{\text{air150}}} = 1.450 \quad \text{Air at } \Delta T \text{ of 250 deg. F gives 45\% more lift than air at } \Delta T \text{ of 150 deg. F!}$$

## Problem \*3.97

[Difficulty: 2]

**3.97** Hydrogen bubbles are used to visualize water flow streaklines in the video, *Flow Visualization*. A typical hydrogen bubble diameter is  $d = 0.001$  in. The bubbles tend to rise slowly in water because of buoyancy; eventually they reach terminal speed relative to the water. The drag force of the water on a bubble is given by  $F_D = 3\pi\mu Vd$ , where  $\mu$  is the viscosity of water and  $V$  is the bubble speed relative to the water. Find the buoyancy force that acts on a hydrogen bubble immersed in water. Estimate the terminal speed of a bubble rising in water.



**Given:** Data on hydrogen bubbles

**Find:** Buoyancy force on bubble; terminal speed in water

**Solution:**

Basic equation  $F_B = \rho \cdot g \cdot V = \rho \cdot g \cdot \frac{\pi}{6} \cdot d^3$  and  $\Sigma F_y = M \cdot a_y$   $\Sigma F_y = 0 = F_B - F_D - W$  for terminal speed

$$F_B = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\pi}{6} \times \left( 0.001 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^3 \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_B = 1.89 \times 10^{-11} \cdot \text{lb} \cdot \text{f}$$

For terminal speed  $F_B - F_D - W = 0$   $F_D = 3 \cdot \pi \cdot \mu \cdot V \cdot d = F_B$  where we have ignored  $W$ , the weight of the bubble (at STP most gases are about 1/1000 the density of water)

Hence  $V = \frac{F_B}{3 \cdot \pi \cdot \mu \cdot d}$  with  $\mu = 2.10 \times 10^{-5} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2}$  from Table A.7 at 68°F

$$V = 1.89 \times 10^{-11} \cdot \text{lb} \cdot \text{f} \times \frac{1}{3 \cdot \pi} \times \frac{1}{2.10 \times 10^{-5} \cdot \text{lb} \cdot \text{s}} \cdot \frac{\text{ft}^2}{\text{ft}^2} \times \frac{1}{0.001 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}}$$

$$V = 1.15 \times 10^{-3} \cdot \frac{\text{ft}}{\text{s}} \quad V = 0.825 \cdot \frac{\text{in}}{\text{min}}$$

As noted by Professor Kline in the film "Flow Visualization", bubbles rise slowly!

## Problem \*3.98

[Difficulty: 3]

**3.98** It is desired to use a hot air balloon with a volume of  $320,000 \text{ ft}^3$  for rides planned in summer morning hours when the air temperature is about  $48^\circ\text{F}$ . The torch will warm the air inside the balloon to a temperature of  $160^\circ\text{F}$ . Both inside and outside pressures will be “standard” ( $14.7 \text{ psia}$ ). How much mass can be carried by the balloon (basket, fuel, passengers, personal items, and the component of the balloon itself) if neutral buoyancy is to be assured? What mass can be carried by the balloon to ensure vertical takeoff acceleration of  $2.5 \text{ ft/s}^2$ ? For this, consider that both balloon and inside air have to be accelerated, as well as some of the surrounding air (to make way for the balloon). The rule of thumb is that the total mass subject to acceleration is the mass of the balloon, all its appurtenances, and twice its volume of air. Given that the volume of hot air is fixed during the flight, what can the balloonists do when they want to go down?




**Given:** Data on hot air balloon

**Find:** Maximum mass of balloon for neutral buoyancy; mass for initial acceleration of  $2.5 \text{ ft/s}^2$ .

**Assumptions:** Air is treated as static and incompressible, and an ideal gas

**Solution:**

Basic equation  $F_B = \rho_{\text{atm}} \cdot g \cdot V$  and  $\Sigma F_y = M \cdot a_y$



Hence  $\Sigma F_y = 0 = F_B - W_{\text{hotair}} - W_{\text{load}} = \rho_{\text{atm}} \cdot g \cdot V - \rho_{\text{hotair}} \cdot g \cdot V - M \cdot g$  for neutral buoyancy

$$M = V \cdot (\rho_{\text{atm}} - \rho_{\text{hotair}}) = \frac{V \cdot p_{\text{atm}}}{R} \cdot \left( \frac{1}{T_{\text{atm}}} - \frac{1}{T_{\text{hotair}}} \right)$$

$$M = 320000 \cdot \text{ft}^3 \times 14.7 \cdot \frac{\text{lbf}}{\text{in}^2} \times \left( \frac{12 \cdot \text{in}}{\text{ft}} \right)^2 \times \frac{\text{lbf} \cdot \text{R}}{53.33 \cdot \text{ft} \cdot \text{lbf}} \times \left[ \frac{1}{(48 + 460) \cdot \text{R}} - \frac{1}{(160 + 460) \cdot \text{R}} \right] \quad M = 4517 \cdot \text{lbm}$$

Initial acceleration  $\Sigma F_y = F_B - W_{\text{hotair}} - W_{\text{load}} = (\rho_{\text{atm}} - \rho_{\text{hotair}}) \cdot g \cdot V - M_{\text{new}} \cdot g = M_{\text{accel}} \cdot a = (M_{\text{new}} + 2 \cdot \rho_{\text{hotair}} \cdot V) \cdot a$

Solving for  $M_{\text{new}}$   $(\rho_{\text{atm}} - \rho_{\text{hotair}}) \cdot g \cdot V - M_{\text{new}} \cdot g = (M_{\text{new}} + 2 \cdot \rho_{\text{hotair}} \cdot V) \cdot a$

$$M_{\text{new}} = V \cdot \frac{(\rho_{\text{atm}} - \rho_{\text{hotair}}) \cdot g - 2 \cdot \rho_{\text{hotair}} \cdot a}{a + g} = \frac{V \cdot p_{\text{atm}}}{a + g} \cdot \left[ g \cdot \left( \frac{1}{T_{\text{atm}}} - \frac{1}{T_{\text{hotair}}} \right) - \frac{2 \cdot a}{T_{\text{hotair}}} \right]$$

$$M_{\text{new}} = 320000 \cdot \text{ft}^3 \cdot 14.7 \cdot \frac{\text{lbf}}{\text{in}^2} \cdot \left( \frac{12 \cdot \text{in}}{\text{ft}} \right)^2 \cdot \frac{\text{lbf} \cdot \text{R}}{53.33 \cdot \text{ft} \cdot \text{lbf}} \cdot \frac{\text{s}^2}{(2.5 + 32.2) \cdot \text{ft}} \cdot \left[ 32.2 \cdot \left[ \frac{1}{(48 + 460)} - \frac{1}{(160 + 460)} \right] - 2 \cdot 2.5 \cdot \frac{1}{(160 + 460)} \right] \cdot \frac{\text{ft}}{\text{s}^2 \cdot \text{R}}$$

$$M_{\text{new}} = 1239 \cdot \text{lbm}$$

To make the balloon move up or down during flight, the air needs to be heated to a higher temperature, or let cool (or let in ambient air).

## Problem \*3.99

[Difficulty: 4]

**3.99** Scientific balloons operating at pressure equilibrium with the surroundings have been used to lift instrument packages to extremely high altitudes. One such balloon, filled with helium, constructed of polyester with a skin thickness of 0.013 mm and a diameter of 120 m, lifted a payload of 230 kg. The specific gravity of the skin material is 1.28. Determine the altitude to which the balloon would rise. Assume that the helium used in the balloon is in thermal equilibrium with the ambient air, and that the balloon is a perfect sphere.

**Given:** Spherical balloon filled with helium lifted a payload of mass  $M=230$  kg. At altitude, helium and air were in thermal equilibrium. Balloon diameter is 120 m and specific gravity of the skin material is 1.28.


**Find:** The altitude to which the balloon rose.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $F_{buoy} = \rho \cdot g \cdot V_d$  (Buoyant force is equal to mass of displaced fluid)

$p = \rho \cdot R \cdot T$  (Ideal gas equation of state)

**Assumptions:** (1) Static, incompressible fluid  
(2) Static equilibrium at 49 km altitude  
(3) Ideal gas behavior



Taking a free body diagram of the balloon and payload:  $\Sigma F_z = F_{buoy} - M_{He} \cdot g - M_s \cdot g - M \cdot g = 0$

Substituting for the buoyant force and knowing that mass is density times volume:

$$\rho_{air} \cdot g \cdot V_b - \rho_{He} \cdot g \cdot V_b - \rho_s \cdot g \cdot V_s - M \cdot g = 0 \quad \rho_{air} \cdot V_b - \rho_{He} \cdot V_b - \rho_s \cdot V_s - M = 0$$

The volume of the balloon:  $V_b = \frac{\pi}{6} \cdot D^3$  The volume of the skin:  $V_s = \pi \cdot D^2 \cdot t$  Substituting these into the force equation:

$\rho_{air} - \rho_{He} = \frac{6}{\pi \cdot D^3} \cdot (\pi \cdot \rho_s \cdot t \cdot D^2 + M)$  From the ideal gas equation of state and remembering that pressure and temperature of the air and helium are equal:

$\frac{p}{T} = \frac{6}{\pi \cdot D^3} \cdot (\pi \cdot \rho_s \cdot t \cdot D^2 + M) \cdot \frac{1}{\left(\frac{1}{R_{air}} - \frac{1}{R_{He}}\right)}$  Substituting known values and consulting Appendix A for gas constants:

$$\frac{p}{T} = \frac{6}{\pi} \times \frac{1}{(120\text{-m})^3} \times \left[ \pi \times 1280 \cdot \frac{\text{kg}}{\text{m}^3} \times 0.013 \cdot 10^{-3} \cdot \text{m} \times (120\text{-m})^2 + 230 \cdot \text{kg} \right] \times \frac{1}{\frac{1}{287} - \frac{1}{2080}} \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times \frac{\text{Pa} \cdot \text{m}^2}{\text{N}} = 3.616 \times 10^{-4} \cdot \frac{\text{kPa}}{\text{K}}$$

To determine the altitude, we need to check this ratio against data from Table A.3. We find that the ratio of pressure to temperature matches the result above at:

$$h = 48.3 \cdot \text{km}$$

### Problem \*3.100

[Difficulty: 3]

**3.100** A helium balloon is to lift a payload to an altitude of 40 km, where the atmospheric pressure and temperature are 3.0 mbar and  $-25^{\circ}\text{C}$ , respectively. The balloon skin is polyester with specific gravity of 1.28 and thickness of 0.015 mm. To maintain a spherical shape, the balloon is pressurized to a gage pressure of 0.45 mbar. Determine the maximum balloon diameter if the allowable tensile stress in the skin is limited to  $62\text{ MN/m}^2$ . What payload can be carried?

**Given:** A pressurized balloon is to be designed to lift a payload of mass  $M$  to an altitude of 40 km, where  $p = 3.0\text{ mbar}$  and  $T = -25\text{ deg C}$ . The balloon skin has a specific gravity of 1.28 and thickness 0.015 mm. The gage pressure of the helium is 0.45 mbar. The allowable tensile stress in the balloon is  $62\text{ MN/m}^2$

**Find:** (a) The maximum balloon diameter  
(b) The maximum payload mass

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$F_{\text{buoy}} = \rho \cdot g \cdot V_d \quad (\text{Buoyant force is equal to mass of displaced fluid})$$

$$p = \rho \cdot R \cdot T \quad (\text{Ideal gas equation of state})$$

**Assumptions:**

- (1) Static, incompressible fluid
- (2) Static equilibrium at 40 km altitude
- (3) Ideal gas behavior

The diameter of the balloon is limited by the allowable tensile stress in the skin:

$$\Sigma F = \frac{\pi}{4} \cdot D^2 \cdot \Delta p - \pi \cdot D \cdot t \cdot \sigma = 0 \quad \text{Solving this expression for the diameter:} \quad D_{\text{max}} = \frac{4 \cdot t \cdot \sigma}{\Delta p}$$

$$D_{\text{max}} = 4 \times 0.015 \times 10^{-3} \cdot \text{m} \times 62 \times 10^6 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{0.45 \cdot 10^{-3} \cdot \text{bar}} \times \frac{\text{bar} \cdot \text{m}^2}{10^5 \cdot \text{N}} \quad D_{\text{max}} = 82.7\text{m}$$

To find the maximum allowable payload we perform a force balance on the system:

$$\Sigma F_z = F_{\text{buoy}} - M_{\text{He}} \cdot g - M_b \cdot g - M \cdot g = 0 \quad \rho_a \cdot g \cdot V_b - \rho_{\text{He}} \cdot g \cdot V_b - \rho_s \cdot g \cdot V_s - M \cdot g = 0$$

Solving for  $M$ :  $M = (\rho_a - \rho_{\text{He}}) \cdot V_b - \rho_s \cdot V_s$  The volume of the balloon is:  $V_b = \frac{\pi}{6} \cdot D^3$




The volume of the skin is:  $V_s = \pi \cdot D^2 \cdot t$  Therefore, the mass is:  $M = \frac{\pi}{6} \cdot (\rho_a - \rho_{\text{He}}) \cdot D^3 - \pi \cdot \rho_s \cdot D^2 \cdot t$

The air density:  $\rho_a = \frac{p_a}{R_a \cdot T} \quad \rho_a = 3.0 \times 10^{-3} \cdot \text{bar} \times \frac{\text{kg} \cdot \text{K}}{287 \cdot \text{N} \cdot \text{m}} \times \frac{1}{(273 - 25) \cdot \text{K}} \times \frac{10^5 \cdot \text{N}}{\text{bar} \cdot \text{m}^2} \quad \rho_a = 4.215 \times 10^{-3} \frac{\text{kg}}{\text{m}^3}$

Repeating for helium:  $\rho_{\text{He}} = \frac{p}{R \cdot T} \quad \rho_{\text{He}} = 6.688 \times 10^{-4} \frac{\text{kg}}{\text{m}^3}$

The payload mass is:  $M = \frac{\pi}{6} \times (4.215 - 0.6688) \times 10^{-3} \cdot \frac{\text{kg}}{\text{m}^3} \times (82.7\text{m})^3 - \pi \times 1.28 \times 10^3 \cdot \frac{\text{kg}}{\text{m}^3} \times (82.7\text{m})^2 \times 0.015 \times 10^{-3} \cdot \text{m}$


$$M = 638\text{ kg}$$



### Problem \*3.101

[Difficulty: 3]

**3.101** A block of volume  $0.025 \text{ m}^3$  is allowed to sink in water as shown. A circular rod  $5 \text{ m}$  long and  $20 \text{ cm}^2$  in cross-section is attached to the weight and also to the wall. If the rod mass is  $1.25 \text{ kg}$  and the rod makes an angle of  $12^\circ$  with the horizontal at equilibrium, what is the mass of the block?




**Given:** Geometry of block and rod

**Find:** Angle for equilibrium

**Assumptions:** Water is static and incompressible

**Solution:**

Basic equations  $\Sigma M_{\text{Hinge}} = 0$   $F_B = \rho \cdot g \cdot V$  (Buoyancy)



The free body diagram is as shown.  $F_{BB}$  and  $F_{BR}$  are the buoyancy of the block and rod, respectively;  $c$  is the (unknown) exposed length of the rod

Taking moments about the hinge

$$(W_B - F_{BB}) \cdot L \cdot \cos(\theta) - F_{BR} \cdot \frac{(L+c)}{2} \cdot \cos(\theta) + W_R \cdot \frac{L}{2} \cdot \cos(\theta) = 0$$

with  $W_B = M_B \cdot g$   $F_{BB} = \rho \cdot g \cdot V_B$   $F_{BR} = \rho \cdot g \cdot (L-c) \cdot A$   $W_R = M_R \cdot g$

Combining equations  $(M_B - \rho \cdot V_B) \cdot L - \rho \cdot A \cdot (L-c) \cdot \frac{(L+c)}{2} + M_R \cdot \frac{L}{2} = 0$

We can solve for  $M_B$   $\rho \cdot A \cdot (L^2 - c^2) = 2 \cdot \left( M_B - \rho \cdot V_B + \frac{1}{2} \cdot M_R \right) \cdot L$

$$M_B = \frac{\rho \cdot A}{2 \cdot L} \cdot (L^2 - c^2) + \rho \cdot V_B - \frac{1}{2} \cdot M_R \quad \text{and since} \quad c = \frac{a}{\sin(\theta)} \quad M_B = \frac{\rho \cdot A}{2 \cdot L} \cdot \left[ L^2 - \left( \frac{a}{\sin(\theta)} \right)^2 \right] + \rho \cdot V_B - \frac{1}{2} \cdot M_R$$

$$M_B = \frac{1}{2} \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 20 \cdot \text{cm}^2 \times \left( \frac{\text{m}}{100 \cdot \text{cm}} \right)^2 \times \frac{1}{5 \cdot \text{m}} \cdot \left[ (5 \cdot \text{m})^2 - \left( \frac{0.25 \cdot \text{m}}{\sin(12 \cdot \text{deg})} \right)^2 \right] + 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 0.025 \cdot \text{m}^3 - \frac{1}{2} \times 1.25 \cdot \text{kg}$$

$$M_B = 29.1 \text{ kg}$$

## Problem \*3.102

[Difficulty: 3]

**3.102** The stem of a glass hydrometer used to measure specific gravity is 5 mm in diameter. The distance between marks on the stem is 2 mm per 0.1 increment of specific gravity. Calculate the magnitude and direction of the error introduced by surface tension if the hydrometer floats in kerosene. (Assume the contact angle between kerosene and glass is  $0^\circ$ .)

**Given:** Glass hydrometer used to measure SG of liquids. Stem has diameter  $D=5$  mm, distance between marks on stem is  $d=2$  mm per 0.1 SG. Hydrometer floats in kerosene (Assume zero contact angle between glass and kerosene).

**Find:** Magnitude of error introduced by surface tension.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $F_{\text{buoy}} = \rho \cdot g \cdot V_d$  (Buoyant force is equal to weight of displaced fluid)

**Assumptions:** (1) Static fluid  
(2) Incompressible fluid  
(3) Zero contact angle between ethyl alcohol and glass

The surface tension will cause the hydrometer to sink  $\Delta h$  lower into the liquid. Thus for this change:

$$\Sigma F_z = \Delta F_{\text{buoy}} - F_\sigma = 0$$

The change in buoyant force is:  $\Delta F_{\text{buoy}} = \rho \cdot g \cdot \Delta V = \rho \cdot g \cdot \frac{\pi}{4} \cdot D^2 \cdot \Delta h$

The force due to surface tension is:  $F_\sigma = \pi \cdot D \cdot \sigma \cdot \cos(\theta) = \pi \cdot D \cdot \sigma$


Thus,  $\rho \cdot g \cdot \frac{\pi}{4} \cdot D^2 \cdot \Delta h = \pi \cdot D \cdot \sigma$  Upon simplification:  $\frac{\rho \cdot g \cdot D \cdot \Delta h}{4} = \sigma$

Solving for  $\Delta h$ :  $\Delta h = \frac{4 \cdot \sigma}{\rho \cdot g \cdot D}$  From Table A.2,  $SG = 1.43$  and from Table A.4,  $\sigma = 26.8$  mN/m

Therefore,  $\Delta h = 4 \times 26.8 \times 10^{-3} \frac{\text{N}}{\text{m}} \times \frac{\text{m}^3}{1430 \cdot \text{kg}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \frac{1}{5 \times 10^{-3} \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} \Delta h = 1.53 \times 10^{-3} \text{ m}$

So the change in specific gravity will be:  $\Delta SG = 1.53 \times 10^{-3} \cdot \text{m} \times \frac{0.1}{2 \times 10^{-3} \cdot \text{m}} \quad \Delta SG = 0.0765$

From the diagram, surface tension acts to cause the hydrometer to float lower in the liquid. Therefore, surface tension results in an indicated specific gravity smaller than the actual specific gravity.



## Problem \*3.103

[Difficulty:4]

**3.103** A sphere, of radius  $R$ , is partially immersed, to depth  $d$ , in a liquid of specific gravity  $SG$ . Obtain an algebraic expression for the buoyancy force acting on the sphere as a function of submersion depth  $d$ . Plot the results over the range of water depth  $0 \leq d \leq 2R$ .

**Given:** Sphere partially immersed in a liquid of specific gravity  $SG$ .

**Find:** (a) Formula for buoyancy force as a function of the submersion depth  $d$   
 (b) Plot of results over range of liquid depth


**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $F_{\text{buoy}} = \rho \cdot g \cdot V_d$  (Buoyant force is equal to weight of displaced fluid)

**Assumptions:** (1) Static fluid  
 (2) Incompressible fluid  
 (3) Atmospheric pressure acts everywhere

We need an expression for the displaced volume of fluid at an arbitrary depth  $d$ . From the diagram we see that:

$$d = R(1 - \cos(\theta_{\text{max}})) \quad \text{at an arbitrary depth } h: \quad h = d - R \cdot (1 - \cos(\theta)) \quad r = R \cdot \sin(\theta)$$



So if we want to find the volume of the submerged portion of the sphere we calculate:

$$V_d = \int_0^{\theta_{\text{max}}} \pi r^2 dh = \pi \int_0^{\theta_{\text{max}}} R^2 \cdot (\sin(\theta))^2 \cdot R \cdot \sin(\theta) d\theta = \pi \cdot R^3 \cdot \int_0^{\theta_{\text{max}}} (\sin(\theta))^3 d\theta$$

Evaluating the integral we get:

$$V_d = \pi \cdot R^3 \cdot \left[ \frac{(\cos(\theta_{\text{max}}))^3}{3} - \cos(\theta_{\text{max}}) + \frac{2}{3} \right]$$


Now since:  $\cos(\theta_{\text{max}}) = 1 - \frac{d}{R}$  we get:  $V_d = \pi \cdot R^3 \cdot \left[ \frac{1}{3} \left( 1 - \frac{d}{R} \right)^3 - \left( 1 - \frac{d}{R} \right) + \frac{2}{3} \right]$

Thus the buoyant force is:  $F_{\text{buoy}} = \rho_w \cdot SG \cdot g \cdot \pi \cdot R^3 \cdot \left[ \frac{1}{3} \left( 1 - \frac{d}{R} \right)^3 - \left( 1 - \frac{d}{R} \right) + \frac{2}{3} \right]$

If we non-dimensionalize by the force on a fully submerged sphere:

$$F_d = \frac{F_{\text{buoy}}}{\rho_w \cdot SG \cdot g \cdot \frac{4}{3} \cdot \pi \cdot R^3} = \frac{3}{4} \left[ \frac{1}{3} \left( 1 - \frac{d}{R} \right)^3 - \left( 1 - \frac{d}{R} \right) + \frac{2}{3} \right]$$

$$F_d = \frac{3}{4} \left[ \frac{1}{3} \left( 1 - \frac{d}{R} \right)^3 - \left( 1 - \frac{d}{R} \right) + \frac{2}{3} \right]$$



## Problem 3.104

[Difficulty: 2]

**3.104** If the mass  $M$  in Problem 3.101 is released from the rod, at equilibrium how much of the rod will remain submerged? What will be the minimum required upward force at the tip of the rod to just lift it out of the water?

**Given:** Geometry of rod

**Find:** How much of rod is submerged; force to lift rod out of water

**Solution:**

Basic equations  $\Sigma M_{\text{Hinge}} = 0$   $F_B = \rho \cdot g \cdot V$  (Buoyancy)

The free body diagram is as shown.  $F_{BR}$  is the buoyancy of the rod;  $c$  is the (unknown) exposed length of the rod

Taking moments about the hinge

$$-F_{BR} \cdot \frac{(L+c)}{2} \cdot \cos(\theta) + W_R \cdot \frac{L}{2} \cdot \cos(\theta) = 0$$

with  $F_{BR} = \rho \cdot g \cdot (L-c) \cdot A$   $W_R = M_R \cdot g$

Hence  $-\rho \cdot A \cdot (L-c) \cdot \frac{(L+c)}{2} + M_R \cdot \frac{L}{2} = 0$

We can solve for  $c$   $\rho \cdot A \cdot (L^2 - c^2) = M_R \cdot L$

$$c = \sqrt{L^2 - \frac{L \cdot M_R}{\rho \cdot A}}$$


$$c = \sqrt{(5 \cdot \text{m})^2 - 5 \cdot \text{m} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{1}{20} \cdot \frac{1}{\text{cm}^2} \times \left(\frac{100 \cdot \text{cm}}{1 \cdot \text{m}}\right)^2 \times 1.25 \cdot \text{kg}}$$

$$c = 4.68 \text{ m}$$

Then the submerged length is  $L - c = 0.323 \text{ m}$

To lift the rod out of the water requires a force equal to half the rod weight (the reaction also takes half the weight)


$$F = \frac{1}{2} \cdot M_R \cdot g = \frac{1}{2} \times 1.25 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F = 6.1 \text{ N}$$



## Problem \*3.105

[Difficulty: 2]

**3.105** In a logging operation, timber floats downstream to a lumber mill. It is a dry year, and the river is running low, as low as 60 cm in some locations. What is the largest diameter log that may be transported in this fashion (leaving a minimum 5 cm clearance between the log and the bottom of the river)? For the wood,  $SG = 0.8$ .



**Given:** Data on river

**Find:** Largest diameter of log that will be transported

**Solution:**

Basic equation  $F_B = \rho \cdot g \cdot V_{\text{sub}}$  and  $\Sigma F_y = 0$   $\Sigma F_y = 0 = F_B - W$

where  $F_B = \rho \cdot g \cdot V_{\text{sub}} = \rho \cdot g \cdot A_{\text{sub}} \cdot L$   $W = SG \rho \cdot g \cdot V = SG \rho \cdot g \cdot A \cdot L$

From references (e.g. CRC Mathematics Handbook)  $A_{\text{sub}} = \frac{R^2}{2} \cdot (\theta - \sin(\theta))$  where R is the radius and  $\theta$  is the included angle

Hence  $\rho \cdot g \cdot \frac{R^2}{2} \cdot (\theta - \sin(\theta)) \cdot L = SG \rho \cdot g \cdot \pi \cdot R^2 \cdot L$

$$\theta - \sin(\theta) = 2 \cdot SG \cdot \pi = 2 \times 0.8 \times \pi$$

This equation can be solved by manually iterating, or by using a good calculator, or by using Excel's Goal Seek

$$\theta = 239 \cdot \text{deg}$$

From geometry the submerged amount of a log is  $H - h$  and also  $R + R \cdot \cos\left(\pi - \frac{\theta}{2}\right)$

Hence  $H - h = R + R \cdot \cos\left(\pi - \frac{\theta}{2}\right)$


Solving for R  $R = \frac{H - h}{1 + \cos\left(180\text{deg} - \frac{\theta}{2}\right)}$   $R = \frac{(0.6 - 0.05) \cdot \text{m}}{1 + \cos\left[\left(180 - \frac{239}{2}\right) \cdot \text{deg}\right]}$   $R = 0.369 \text{ m}$

$D = 2 \cdot R$   $D = 0.737 \text{ m}$

### Problem \*3.106

[Difficulty: 4]

**3.106** A sphere of radius 1 in., made from material of specific gravity of  $SG = 0.95$ , is submerged in a tank of water. The sphere is placed over a hole of radius 0.075 in., in the tank bottom. When the sphere is released, will it stay on the bottom of the tank or float to the surface?



**Given:** Data on sphere and tank bottom

**Find:** Expression for SG of sphere at which it will float to surface; minimum SG to remain in position

**Assumptions:** (1) Water is static and incompressible  
(2) Sphere is much larger than the hole at the bottom of the tank


**Solution:**

Basic equations  $F_B = \rho \cdot g \cdot V$  and  $\Sigma F_y = F_L - F_U + F_B - W$

where  $F_L = p_{atm} \cdot \pi \cdot a^2$   $F_U = [p_{atm} + \rho \cdot g \cdot (H - 2 \cdot R)] \cdot \pi \cdot a^2$

$F_B = \rho \cdot g \cdot V_{net}$   $V_{net} = \frac{4}{3} \cdot \pi \cdot R^3 - 2 \cdot \pi \cdot R \cdot a^2$

$W = SG \cdot \rho \cdot g \cdot V$  with  $V = \frac{4}{3} \cdot \pi \cdot R^3$



Now if the sum of the vertical forces is positive, the sphere will float away, while if the sum is zero or negative the sphere will stay at the bottom of the tank (its weight and the hydrostatic force are greater than the buoyant force).

Hence  $\Sigma F_y = p_{atm} \cdot \pi \cdot a^2 - [p_{atm} + \rho \cdot g \cdot (H - 2 \cdot R)] \cdot \pi \cdot a^2 + \rho \cdot g \cdot \left( \frac{4}{3} \cdot \pi \cdot R^3 - 2 \cdot \pi \cdot R \cdot a^2 \right) - SG \cdot \rho \cdot g \cdot \frac{4}{3} \cdot \pi \cdot R^3$

This expression simplifies to  $\Sigma F_y = \pi \cdot \rho \cdot g \cdot \left[ (1 - SG) \cdot \frac{4}{3} \cdot R^3 - H \cdot a^2 \right]$

$$\Sigma F_y = \pi \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \left[ \frac{4}{3} \times (1 - 0.95) \times \left( 1 \cdot \text{in} \times \frac{\text{ft}}{12 \cdot \text{in}} \right)^3 - 2.5 \cdot \text{ft} \times \left( 0.075 \cdot \text{in} \times \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \right] \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$\Sigma F_y = -0.012 \cdot \text{lbf}$  Therefore, the sphere stays at the bottom of the tank.

### Problem \*3.107

[Difficulty: 4]

**3.107** A cylindrical timber, with  $D = 1$  ft and  $L = 15$  ft, is weighted on its lower end so that it floats vertically with 10 ft submerged in seawater. When displaced vertically from its equilibrium position, the timber oscillates or “heaves” in a vertical direction upon release. Estimate the frequency of oscillation in this heave mode. Neglect viscous effects and water motion.

**Given:** Cylindrical timber,  $D = 1$  ft and  $L = 15$  ft, is weighted on the lower end so that it floats vertically with 10 ft submerged in sea water. When displaced vertically from equilibrium, the timber oscillates in a vertical direction upon release.

**Find:** Estimate the frequency of the oscillation. Neglect viscous forces or water motion.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $F_{\text{buoy}} = \rho \cdot g \cdot V_d$  (Buoyant force is equal to weight of displaced fluid)

**Assumptions:**

- (1) Static fluid
- (2) Incompressible fluid
- (3) Atmospheric pressure acts everywhere
- (4) Viscous effects and water motion are negligible.

At equilibrium:  $\Sigma F_y = F_{\text{buoy}} - M \cdot g = 0$   $M = \rho \cdot V_d = \rho \cdot A \cdot d$

Once the timber is displaced:  $\Sigma F_y = F_{\text{buoy}} - M \cdot g = M \cdot \frac{d^2 y}{dt^2}$

$$\rho \cdot g \cdot A \cdot (d - y) - M \cdot g = M \cdot \frac{d^2 y}{dt^2} \quad \rho \cdot g \cdot A \cdot d - \rho \cdot g \cdot A \cdot y - \rho \cdot A \cdot d \cdot g = M \cdot \frac{d^2 y}{dt^2}$$

Thus we have the equation:  $M \cdot \frac{d^2 y}{dt^2} + \rho \cdot g \cdot A \cdot y = 0$  or:  $\frac{d^2 y}{dt^2} + \frac{\rho \cdot g \cdot A}{\rho \cdot A \cdot d} \cdot y = 0$   $\frac{d^2 y}{dt^2} + \frac{g}{d} \cdot y = 0$

This ODE describes simple harmonic motion with the natural frequency  $\omega$  described by:

$$\omega^2 = \frac{g}{d}$$

Solving for  $\omega$ :  $\omega = \sqrt{\frac{g}{d}}$

$$\omega = \sqrt{\frac{32.2 \text{ ft}}{\text{s}^2} \times \frac{1}{10 \text{ ft}}}$$


$$\omega = 1.7944 \frac{\text{rad}}{\text{s}}$$

To express this as a frequency:

$$f = \frac{\omega}{2 \cdot \pi}$$

$$f = \frac{1.7944 \frac{1}{\text{s}}}{2 \cdot \pi}$$


$$f = 0.286 \text{ Hz}$$



### Problem \*3.108

[Difficulty: 3]

**3.108** You are in the Bermuda Triangle when you see a bubble plume eruption (a large mass of air bubbles, similar to a foam) off to the side of the boat. Do you want to head toward it and be part of the action? What is the effective density of the water and air bubbles in the drawing on the right that will cause the boat to sink? Your boat is 10 ft long, and weight is the same in both cases.




**Given:** Data on boat

**Find:** Effective density of water/air bubble mix if boat sinks

**Solution:**

Basic equations  $F_B = \rho \cdot g \cdot V$  and

$$\Sigma F_y = 0$$



We can apply the sum of forces for the "floating" free body

$$\Sigma F_y = 0 = F_B - W \quad \text{where}$$

$$F_B = SG_{\text{sea}} \cdot \rho \cdot g \cdot V_{\text{subfloat}}$$

$$V_{\text{subfloat}} = \frac{1}{2} \cdot h \cdot \left( \frac{2 \cdot h}{\tan \theta} \right) \cdot L = \frac{L \cdot h^2}{\tan(\theta)}$$

$$SG_{\text{sea}} = 1.024 \quad (\text{Table A.2})$$

Hence 
$$W = \frac{SG_{\text{sea}} \cdot \rho \cdot g \cdot L \cdot h^2}{\tan(\theta)} \quad (1)$$

We can apply the sum of forces for the "sinking" free body

$$\Sigma F_y = 0 = F_B - W \quad \text{where}$$

$$F_B = SG_{\text{mix}} \cdot \rho \cdot g \cdot V_{\text{sub}} \quad V_{\text{subsink}} = \frac{1}{2} \cdot H \cdot \left( \frac{2 \cdot H}{\tan \theta} \right) \cdot L = \frac{L \cdot H^2}{\tan(\theta)}$$

Hence 
$$W = \frac{SG_{\text{mix}} \cdot \rho \cdot g \cdot L \cdot H^2}{\tan(\theta)} \quad (2)$$

Comparing Eqs. 1 and 2 
$$W = \frac{SG_{\text{sea}} \cdot \rho \cdot g \cdot L \cdot h^2}{\tan(\theta)} = \frac{SG_{\text{mix}} \cdot \rho \cdot g \cdot L \cdot H^2}{\tan(\theta)}$$


$$SG_{\text{mix}} = SG_{\text{sea}} \cdot \left( \frac{h}{H} \right)^2 \quad SG_{\text{mix}} = 1.024 \times \left( \frac{7}{8} \right)^2 \quad SG_{\text{mix}} = 0.784$$

The density is 
$$\rho_{\text{mix}} = SG_{\text{mix}} \cdot \rho \quad \rho_{\text{mix}} = 0.784 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \rho_{\text{mix}} = 1.52 \cdot \frac{\text{slug}}{\text{ft}^3}$$

### Problem \*3.109

[Difficulty: 2]

**3.109** A bowl is inverted symmetrically and held in a dense fluid,  $SG = 15.6$ , to a depth of 200 mm measured along the centerline of the bowl from the bowl rim. The bowl height is 80 mm, and the fluid rises 20 mm inside the bowl. The bowl is 100 mm inside diameter, and it is made from an old clay recipe,  $SG = 6.1$ . The volume of the bowl itself is about 0.9 L. What is the force required to hold it in place?



**Given:** Data on inverted bowl and dense fluid

**Find:** Force to hold in place

**Assumption:** Fluid is static and incompressible

**Solution:**

Basic equations  $F_B = \rho \cdot g \cdot V$  and  $\Sigma F_y = 0$   $\Sigma F_y = 0 = F_B - F - W$

Hence  $F = F_B - W$

For the buoyancy force  $F_B = SG_{\text{fluid}} \cdot \rho_{\text{H}_2\text{O}} \cdot g \cdot V_{\text{sub}}$  with  $V_{\text{sub}} = V_{\text{bowl}} + V_{\text{air}}$

For the weight  $W = SG_{\text{bowl}} \cdot \rho_{\text{H}_2\text{O}} \cdot g \cdot V_{\text{bowl}}$

Hence  $F = SG_{\text{fluid}} \cdot \rho_{\text{H}_2\text{O}} \cdot g \cdot (V_{\text{bowl}} + V_{\text{air}}) - SG_{\text{bowl}} \cdot \rho_{\text{H}_2\text{O}} \cdot g \cdot V_{\text{bowl}}$

$$F = \rho_{\text{H}_2\text{O}} \cdot g \cdot \left[ SG_{\text{fluid}} (V_{\text{bowl}} + V_{\text{air}}) - SG_{\text{bowl}} V_{\text{bowl}} \right]$$

$$F = 999 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \left[ 15.6 \times \left[ 0.9 \text{ L} \times \frac{\text{m}^3}{1000 \text{ L}} + (0.08 - 0.02) \cdot \text{m} \cdot \frac{\pi \cdot (0.1 \text{ m})^2}{4} \right] - 5.7 \times \left( 0.9 \text{ L} \times \frac{\text{m}^3}{1000 \text{ L}} \right) \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$F = 159.4 \text{ N}$$

## Problem \*3.110

[Difficulty: 4]

---

**3.110** In the “Cartesian diver” child’s toy, a miniature “diver” is immersed in a column of liquid. When a diaphragm at the top of the column is pushed down, the diver sinks to the bottom. When the diaphragm is released, the diver again rises. Explain how the toy might work.

---

**Open-Ended Problem Statement:** In the “Cartesian diver” child’s toy, a miniature “diver” is immersed in a column of liquid. When a diaphragm at the top of the column is pushed down, the diver sinks to the bottom. When the diaphragm is released, the diver again rises. Explain how the toy might work.

**Discussion:** A possible scenario is for the toy to have a flexible bladder that contains air. Pushing down on the diaphragm at the top of the liquid column would increase the pressure at any point in the liquid. The air in the bladder would be compressed slightly as a result. The volume of the bladder, and therefore its buoyancy, would decrease, causing the diver to sink to the bottom of the liquid column.

Releasing the diaphragm would reduce the pressure in the water column. This would allow the bladder to expand again, increasing its volume and therefore the buoyancy of the diver. The increased buoyancy would permit the diver to rise to the top of the liquid column and float in a stable, partially submerged position, on the surface of the liquid.

## Problem \*3.111

[Difficulty: 4]

---

**3.111** Consider a conical funnel held upside down and submerged slowly in a container of water. Discuss the force needed to submerge the funnel if the spout is open to the atmosphere. Compare with the force needed to submerge the funnel when the spout opening is blocked by a rubber stopper.

---

**Open-Ended Problem Statement:** Consider a conical funnel held upside down and submerged slowly in a container of water. Discuss the force needed to submerge the funnel if the spout is open to the atmosphere. Compare with the force needed to submerge the funnel when the spout opening is blocked by a rubber stopper.

**Discussion:** Let the weight of the funnel in air be  $W_a$ . Assume the funnel is held with its spout vertical and the conical section down. Then  $W_a$  will also be vertical.

Two possible cases are with the funnel spout open to atmosphere or with the funnel spout sealed. With the funnel spout open to atmosphere, the pressures inside and outside the funnel are equal, so no net pressure force acts on the funnel. The force needed to support the funnel will remain constant until it first contacts the water. Then a buoyancy force will act vertically upward on every element of volume located beneath the water surface.

The first contact of the funnel with the water will be at the widest part of the conical section. The buoyancy force will be caused by the volume formed by the funnel thickness and diameter as it begins to enter the water. The buoyancy force will reduce the force needed to support the funnel. The buoyancy force will increase as the depth of submergence of the funnel increases until the funnel is fully submerged. At that point the buoyancy force will be constant and equal to the weight of water displaced by the volume of the material from which the funnel is made.

If the funnel material is less dense than water, it would tend to float partially submerged in the water. The force needed to support the funnel would decrease to zero and then become negative (i.e., down) to fully submerge the funnel.

If the funnel material were denser than water it would not tend to float even when fully submerged. The force needed to support the funnel would decrease to a minimum when the funnel became fully submerged, and then would remain constant at deeper submersion depths.

With the funnel spout sealed, air will be trapped inside the funnel. As the funnel is submerged gradually below the water surface, it will displace a volume equal to the volume of the funnel material plus the volume of trapped air. Thus its buoyancy force will be much larger than when the spout is open to atmosphere. Neglecting any change in air volume (pressures caused by submersion should be small compared to atmospheric pressure) the buoyancy force would be from the entire volume encompassed by the outside of the funnel. Finally, when fully submerged, the volume of the rubber stopper (although small) will also contribute to the total buoyancy force acting on the funnel.

## Problem \*3.112

[Difficulty: 2]

**3.112** Three steel balls (each about half an inch in diameter) lie at the bottom of a plastic shell floating on the water surface in a partially filled bucket. Someone removes the steel balls from the shell and carefully lets them fall to the bottom of the bucket, leaving the plastic shell to float empty. What happens to the water level in the bucket? Does it rise, go down, or remain unchanged? Explain.

**Given:** Steel balls resting in floating plastic shell in a bucket of water

**Find:** What happens to water level when balls are dropped in water

**Solution:** Basic equation  $F_B = \rho \cdot V_{\text{disp}} \cdot g = W$  for a floating body weight  $W$

When the balls are in the plastic shell, the shell and balls displace a volume of water equal to their own weight - a large volume because the balls are dense. When the balls are removed from the shell and dropped in the water, the shell now displaces only a small volume of water, and the balls sink, displacing only their own volume. Hence the difference in displaced water before and after moving the balls is the difference between the volume of water that is equal to the weight of the balls, and the volume of the balls themselves. The amount of water displaced is significantly reduced, so the water level in the bucket drops.

$$\text{Volume displaced before moving balls: } V_1 = \frac{W_{\text{plastic}} + W_{\text{balls}}}{\rho \cdot g}$$

$$\text{Volume displaced after moving balls: } V_2 = \frac{W_{\text{plastic}}}{\rho \cdot g} + V_{\text{balls}}$$

$$\text{Change in volume displaced } \Delta V = V_2 - V_1 = V_{\text{balls}} - \frac{W_{\text{balls}}}{\rho \cdot g} = V_{\text{balls}} - \frac{SG_{\text{balls}} \cdot \rho \cdot g \cdot V_{\text{balls}}}{\rho \cdot g}$$

$$\Delta V = V_{\text{balls}} \cdot (1 - SG_{\text{balls}})$$

Hence initially a large volume is displaced; finally a small volume is displaced ( $\Delta V < 0$  because  $SG_{\text{balls}} > 1$ )

## Problem \*3.113

[Difficulty: 4]

---

**3.113** A proposed ocean salvage scheme involves pumping air into “bags” placed within and around a wrecked vessel on the sea bottom. Comment on the practicality of this plan, supporting your conclusions with analyses.

---

**Open-Ended Problem Statement:** A proposed ocean salvage scheme involves pumping air into “bags” placed within and around a wrecked vessel on the sea bottom. Comment on the practicality of this plan, supporting your conclusions with analyses.

**Discussion:** This plan has several problems that render it impractical. First, pressures at the sea bottom are very high. For example, *Titanic* was found in about 12,000 ft of seawater. The corresponding pressure is nearly 6,000 psi. Compressing air to this pressure is possible, but would require a multi-stage compressor and very high power.

Second, it would be necessary to manage the buoyancy force after the bag and object are broken loose from the sea bed and begin to rise toward the surface. Ambient pressure would decrease as the bag and artifact rise toward the surface. The air would tend to expand as the pressure decreases, thereby tending to increase the volume of the bag. The buoyancy force acting on the bag is directly proportional to the bag volume, so it would increase as the assembly rises. The bag and artifact thus would tend to accelerate as they approach the sea surface. The assembly could broach the water surface with the possibility of damaging the artifact or the assembly.


If the bag were of constant volume, the pressure inside the bag would remain essentially constant at the pressure of the sea floor, e.g., 6,000 psi for *Titanic*. As the ambient pressure decreases, the pressure differential from inside the bag to the surroundings would increase. Eventually the difference would equal sea floor pressure. This probably would cause the bag to rupture.

If the bag permitted some expansion, a control scheme would be needed to vent air from the bag during the trip to the surface to maintain a constant buoyancy force just slightly larger than the weight of the artifact in water. Then the trip to the surface could be completed at low speed without danger of broaching the surface or damaging the artifact.

## Problem \*3.114

[Difficulty: 3]

**3.114** A cylindrical container, similar to that analyzed in Example 3.10 (on the Web), is rotated at a constant rate of 2 Hz about its axis. The cylinder is 0.5 m in diameter and initially contains water that is 0.3 m deep. Determine the height of the liquid free surface at the center of the container. Does your answer depend on the density of the liquid? Explain.



**Given:** Cylindrical container rotating as in Example 3.10

$$R = 0.25 \cdot \text{m} \quad h_0 = 0.3 \cdot \text{m} \quad f = 2 \cdot \text{Hz}$$

**Find:** (a) height of free surface at the entrance  
(b) if solution depends on  $\rho$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $-\nabla p + \rho \vec{g} = \rho \vec{a}$  (Hydrostatic equation)

**Assumptions:** (1) Incompressible fluid  
(2) Atmospheric pressure acts everywhere

In order to obtain the solution we need an expression for the shape of the free surface in terms of  $\omega$ ,  $r$ , and  $h_0$ . The required expression was derived in Example 3.10. The equation is:

$$z = h_0 - \frac{(\omega \cdot R)^2}{2 \cdot g} \cdot \left[ \frac{1}{2} - \left( \frac{r}{R} \right)^2 \right]$$

The angular velocity  $\omega$  is related to the frequency of rotation through:  $\omega = 2 \cdot \pi \cdot f$   $\omega = 2 \cdot \pi \times 2 \cdot \frac{\text{rad}}{\text{s}} = 12.57 \cdot \frac{\text{rad}}{\text{s}}$

Now since  $h_1$  is the  $z$  value which corresponds to  $r = 0$ :  $h_1 = h_0 - \frac{(\omega \cdot R)^2}{4 \cdot g}$


Substituting known values:  $h_1 = 0.3 \cdot \text{m} - \frac{1}{4} \times \left( 12.57 \cdot \frac{\text{rad}}{\text{s}} \times 0.25 \cdot \text{m} \right)^2 \times \frac{\text{s}^2}{9.81 \cdot \text{m}}$   $h_1 = 0.05 \text{ m}$

The solution is independent of  $\rho$  because the equation of the free surface is independent of  $\rho$  as well.

## Problem \*3.115

[Difficulty: 2]

**3.115** A crude accelerometer can be made from a liquid-filled U-tube as shown. Derive an expression for the liquid level difference  $h$  caused by an acceleration  $\vec{a}$ , in terms of the tube geometry and fluid properties.



**Given:** U-tube accelerometer

**Find:** Acceleration in terms of  $h$  and  $L$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$-\frac{\partial p}{\partial x} + \rho g_x = \rho a_x$$

(Hydrostatic equation in x-direction)

$$-\frac{\partial p}{\partial y} + \rho g_y = \rho a_y$$

(Hydrostatic equation in y-direction)

**Assumptions:**

- (1) Incompressible fluid
- (2) Neglect sloshing
- (3) Ignore corners
- (4) Both ends of U-tube are open to atmosphere

In the coordinate system we are using, we can see that:  $a_x = a$   $a_y = 0$   $g_x = 0$   $g_y = -g$

Thus,  $\frac{\partial p}{\partial x} = -\rho a$   $\frac{\partial p}{\partial y} = -\rho g$  Now if we evaluate  $\Delta p$  from left to right in the U-tube:  $dp = \frac{\partial p}{\partial x} dx + \frac{\partial p}{\partial y} dy$


We may also write this expression as:  $\Delta p = \frac{\partial p}{\partial x} \Delta x + \frac{\partial p}{\partial y} \Delta y$   $\Delta p = (-\rho \cdot g) \cdot (-b) + (-\rho \cdot a) \cdot (-L) + (-\rho \cdot g) \cdot (b + h) = 0$

Simplifying this expression:  $\Delta p = \rho \cdot a \cdot L - \rho \cdot g \cdot h = 0$  Solving for  $h$ :  $h = \frac{a \cdot L}{g}$

### Problem \*3.116

[Difficulty: 2]

**3.116** A rectangular container of water undergoes constant acceleration down an incline as shown. Determine the slope of the free surface using the coordinate system shown.



**Given:** Rectangular container with constant acceleration

**Find:** Slope of free surface

**Solution:** Basic equation  $-\nabla p + \rho \bar{g} = \rho \bar{a}$

In components  $\frac{\partial}{\partial x} p + \rho \cdot g_x = \rho \cdot a_x$        $\frac{\partial}{\partial y} p + \rho \cdot g_y = \rho \cdot a_y$        $\frac{\partial}{\partial z} p + \rho \cdot g_z = \rho \cdot a_z$

We have  $a_y = a_z = 0$        $g_x = g \cdot \sin(\theta)$        $g_y = -g \cdot \cos(\theta)$        $g_z = 0$

Hence  $\frac{\partial}{\partial x} p + \rho \cdot g \cdot \sin(\theta) = \rho \cdot a_x$     (1)     $\frac{\partial}{\partial y} p - \rho \cdot g \cdot \cos(\theta) = 0$     (2)     $\frac{\partial}{\partial z} p = 0$     (3)

From Eq. 3 we can simplify from  $p = p(x, y, z)$  to  $p = p(x, y)$

Hence a change in pressure is given by  $dp = \frac{\partial}{\partial x} p \cdot dx + \frac{\partial}{\partial y} p \cdot dy$

At the free surface  $p = \text{const.}$ , so  $dp = 0 = \frac{\partial}{\partial x} p \cdot dx + \frac{\partial}{\partial y} p \cdot dy$  or  $\frac{dy}{dx} = -\frac{\frac{\partial}{\partial x} p}{\frac{\partial}{\partial y} p}$  at the free surface

Hence at the free surface, using Eqs 1 and 2  $\frac{dy}{dx} = -\frac{\frac{\partial}{\partial x} p}{\frac{\partial}{\partial y} p} = \frac{\rho \cdot g \cdot \sin(\theta) - \rho \cdot a_x}{\rho \cdot g \cdot \cos(\theta)} = \frac{g \cdot \sin(\theta) - a_x}{g \cdot \cos(\theta)}$


$$\frac{dy}{dx} = \frac{9.81 \cdot (0.5) \cdot \frac{\text{m}}{\text{s}^2} - 3 \cdot \frac{\text{m}}{\text{s}^2}}{9.81 \cdot (0.866) \cdot \frac{\text{m}}{\text{s}^2}}$$

At the free surface, the slope is  $\frac{dy}{dx} = 0.224$

### Problem \*3.117

[Difficulty: 2]

**3.117** The U-tube shown is filled with water at  $T = 68^\circ\text{F}$ . It is sealed at  $A$  and open to the atmosphere at  $D$ . The tube is rotated about vertical axis  $AB$  at 1600 rpm. For the dimensions shown, would cavitation occur in the tube?



**Given:** Spinning U-tube sealed at one end

**Find:** Maximum angular speed for no cavitation

**Assumptions:** (1) water is incompressible  
(2) constant angular velocity

**Solution:** Basic equation  $-\nabla p + \rho \bar{g} = \rho \bar{a}$

In components  $-\left(\frac{\partial p}{\partial r}\right) = \rho \cdot a_r = -\rho \cdot \frac{V^2}{r} = -\rho \cdot \omega^2 \cdot r$   $\frac{\partial p}{\partial z} = -\rho \cdot g$

Between D and C,  $r = \text{constant}$ , so  $\frac{\partial p}{\partial z} = -\rho \cdot g$  and so  $p_D - p_C = -\rho \cdot g \cdot H$  (1)

Between B and A,  $r = \text{constant}$ , so  $\frac{\partial p}{\partial z} = -\rho \cdot g$  and so  $p_A - p_B = -\rho \cdot g \cdot H$  (2)

Between B and C,  $z = \text{constant}$ , so  $\frac{\partial p}{\partial r} = \rho \cdot \omega^2 \cdot r$  and so  $\int_{p_B}^{p_C} 1 dp = \int_0^L \rho \cdot \omega^2 \cdot r dr$

Integrating  $p_C - p_B = \rho \cdot \omega^2 \cdot \frac{L^2}{2}$  (3)

Since  $p_D = p_{\text{atm}}$ , then from Eq 1  $p_C = p_{\text{atm}} + \rho \cdot g \cdot H$

From Eq. 3  $p_B = p_C - \rho \cdot \omega^2 \cdot \frac{L^2}{2}$  so  $p_B = p_{\text{atm}} + \rho \cdot g \cdot H - \rho \cdot \omega^2 \cdot \frac{L^2}{2}$

From Eq. 2  $p_A = p_B - \rho \cdot g \cdot H$  so  $p_A = p_{\text{atm}} - \rho \cdot \omega^2 \cdot \frac{L^2}{2}$

Thus the minimum pressure occurs at point A (not B). Substituting known data to find the pressure at A:

$$p_A = 14.7 \cdot \frac{\text{lb}_f}{\text{in}^2} - 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 1600 \cdot \frac{\text{rev}}{\text{min}} \times \frac{2 \cdot \pi \cdot \text{rad}}{\text{rev}} \times \frac{\text{min}}{60 \cdot \text{s}} \right)^2 \times \frac{1}{2} \times \left( 3 \cdot \text{in} \times \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \times \frac{\text{lb}_f \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 = 2.881 \cdot \frac{\text{lb}_f}{\text{in}^2}$$

At  $68^\circ\text{F}$  from steam tables, the vapor pressure of water is


$$p_v = 0.339 \cdot \text{psi}$$

which is less than the pressure at A.  
Therefore, cavitation does not occur.

### Problem \*3.118

[Difficulty: 2]

**3.118** If the U-tube of Problem 3.117 is spun at 300 rpm, what will the pressure be at *A*? If a small leak appears at *A*, how much water will be lost at *D*?



- Given:** Spinning U-tube sealed at one end
- Find:** Pressure at *A*; water loss due to leak
- Assumption:** Water is incompressible; centripetal acceleration is constant
- Solution:** Basic equation  $-\nabla p + \rho \bar{g} = \rho \bar{a}$

From the analysis of Example Problem 3.10, solving the basic equation, the pressure  $p$  at any point  $(r, z)$  in a continuous rotating fluid is given by

$$p = p_0 + \frac{\rho \cdot \omega^2}{2} \cdot (r^2 - r_0^2) - \rho \cdot g \cdot (z - z_0) \quad (1) \quad \text{where } p_0 \text{ is a reference pressure at point } (r_0, z_0)$$

In this case  $p = p_A$        $p_0 = p_D$        $z = z_A = z_D = z_0 = H$        $r = 0$        $r_0 = r_D = L$

The speed of rotation is  $\omega = 300 \cdot \text{rpm}$        $\omega = 31.4 \cdot \frac{\text{rad}}{\text{s}}$

The pressure at *D* is  $p_D = 0 \cdot \text{kPa}$  (gage)

Hence 
$$p_A = \frac{\rho \cdot \omega^2}{2} \cdot (-L^2) - \rho \cdot g \cdot (0) = -\frac{\rho \cdot \omega^2 \cdot L^2}{2} = -\frac{1}{2} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(31.4 \cdot \frac{\text{rad}}{\text{s}}\right)^2 \times (3 \cdot \text{in})^2 \times \left(\frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right)^4 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$p_A = -0.42 \cdot \text{psi}$  (gage)

When the leak appears, the water level at *A* will fall, forcing water out at point *D*. Once again, from the analysis of Example Problem 3.10, we can use Eq 1

In this case  $p = p_A = 0$        $p_0 = p_D = 0$        $z = z_A$        $z_0 = z_D = H$        $r = 0$        $r_0 = r_D = L$

Hence 
$$0 = \frac{\rho \cdot \omega^2}{2} \cdot (-L^2) - \rho \cdot g \cdot (z_A - H)$$


$$z_A = H - \frac{\omega^2 \cdot L^2}{2 \cdot g} = 12 \text{ in} - \frac{1}{2} \times \left(31.4 \cdot \frac{\text{rad}}{\text{s}}\right)^2 \times (3 \cdot \text{in})^2 \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \quad z_A = 0.52 \cdot \text{in}$$

The amount of water lost is  $\Delta h = H - z_A = 12 \cdot \text{in} - 0.52 \cdot \text{in}$        $\Delta h = 11.48 \cdot \text{in}$

## Problem \*3.119

[Difficulty: 2]

**3.119** A centrifugal micromanometer can be used to create small and accurate differential pressures in air for precise measurement work. The device consists of a pair of parallel disks that rotate to develop a radial pressure difference. There is no flow between the disks. Obtain an expression for pressure difference in terms of rotation speed, radius, and air density. Evaluate the speed of rotation required to develop a differential pressure of  $8 \mu\text{m}$  of water using a device with a 50 mm radius.



**Given:** Centrifugal manometer consists of pair of parallel disks that rotate to develop a radial pressure difference. There is no flow between the disks.

**Find:** (a) an expression for the pressure difference,  $\Delta p$ , as a function of  $\omega$ ,  $R$ , and  $\rho$ .  
 (b) find  $\omega$  if  $\Delta p = 8 \mu\text{m H}_2\text{O}$  and  $R = 50 \text{ mm}$

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$-\nabla p + \rho \vec{g} = \rho \vec{a} \quad \text{(Hydrostatic equation)}$$

$$-\frac{\partial p}{\partial r} + \rho g_r = \rho a_r \quad \text{(Hydrostatic equation in radial direction)}$$

**Assumptions:**

- (1) Incompressible fluid
- (2) Standard air between disks
- (3) Rigid body motion
- (4) Radial direction is horizontal

For rigid body motion:  $a_r = -\frac{V^2}{r} = -\frac{(r \cdot \omega)^2}{r} = -r \cdot \omega^2$  In addition, since  $r$  is horizontal:  $g_r = 0$

Thus, the hydrostatic equation becomes:  $\frac{\partial p}{\partial r} = \rho r \omega^2$

We can solve this expression by separating variables and integrating:

$$\Delta p = \rho \cdot \omega^2 \cdot \int_0^R r \, dr \quad \text{Evaluating the integral on the right hand side:} \quad \Delta p = \frac{\rho \cdot \omega^2 \cdot R^2}{2}$$

Solving for the rotational frequency:  $\omega = \sqrt{\frac{2 \cdot \Delta p}{\rho \cdot R^2}}$  The pressure differential can be expressed as:  $\Delta p = \rho \cdot g \cdot \Delta h$


Therefore: 
$$\omega = \sqrt{2 \cdot \frac{\rho_w}{\rho_{air}} \cdot \frac{g \cdot \Delta h}{R^2}}$$

Substituting in values: 
$$\omega = \sqrt{2 \times \frac{999}{1.225} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 8 \times 10^{-6} \cdot \text{m} \times \frac{1}{(50 \times 10^{-3} \cdot \text{m})^2}} \quad \omega = 7.16 \cdot \frac{\text{rad}}{\text{s}}$$

### Problem \*3.120

[Difficulty: 2]

**3.120** A test tube is spun in a centrifuge. The tube support is mounted on a pivot so that the tube swings outward as rotation speed increases. At high speeds, the tube is nearly horizontal. Find (a) an expression for the radial component of acceleration of a liquid element located at radius  $r$ , (b) the radial pressure gradient  $dp/dr$ , and (c) the required angular velocity to generate a pressure of 250 MPa in the bottom of a test tube containing water. (The free surface and bottom radii are 50 and 130 mm, respectively.)



**Given:** Test tube with water

**Find:** (a) Radial acceleration  
(b) Radial pressure gradient  
(c) Rotational speed needed to generate 250 MPa pressure at the bottom of the tube

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $-\nabla p + \rho \vec{g} = \rho \vec{a}$  (Hydrostatic equation)

$$-\frac{\partial p}{\partial r} + \rho g_r = \rho a_r \quad \text{(Hydrostatic equation in radial direction)}$$

**Assumptions:** (1) Incompressible fluid  
(2) Rigid body motion  
(3) Radial direction is horizontal

For rigid body motion:  $a_r = -\frac{V^2}{r} = -\frac{(r \cdot \omega)^2}{r} = -r \cdot \omega^2$   $a_r = -r \cdot \omega^2$

In addition, since  $r$  is horizontal:  $g_r = 0$  Thus, the hydrostatic equation becomes:  $\frac{\partial p}{\partial r} = \rho r \omega^2$

We can solve this expression by separating variables and integrating:  $\Delta p = \rho \cdot \omega^2 \cdot \int_{r_1}^{r_2} r \, dr$

Evaluating the integral on the right hand side:  $\Delta p = \frac{\rho \cdot \omega^2}{2} \cdot (r_2^2 - r_1^2)$  Solving for  $\omega$ :  $\omega = \sqrt{\frac{2 \cdot \Delta p}{\rho \cdot (r_2^2 - r_1^2)}}$

Substituting in values:  $\omega = \sqrt{2 \times 250 \times 10^6 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \cdot \text{kg}} \times \frac{1}{(130 \times 10^{-3} \cdot \text{m})^2 - (50 \times 10^{-3} \cdot \text{m})^2} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \times \frac{\text{rev}}{2 \cdot \pi \cdot \text{rad}}}$

$$\omega = 938 \cdot \text{Hz}$$

### Problem \*3.121

[Difficulty: 3]

**3.121** A rectangular container, of base dimensions  $0.4 \text{ m} \times 0.2 \text{ m}$  and height  $0.4 \text{ m}$ , is filled with water to a depth of  $0.2 \text{ m}$ ; the mass of the empty container is  $10 \text{ kg}$ . The container is placed on a plane inclined at  $30^\circ$  to the horizontal. If the coefficient of sliding friction between the container and the plane is  $0.3$ , determine the angle of the water surface relative to the horizontal.

**Given:** Rectangular container of base dimensions  $0.4 \text{ m} \times 0.2 \text{ m}$  and a height of  $0.4 \text{ m}$  is filled with water to a depth of  $d = 0.2 \text{ m}$ . Mass of empty container is  $M_c = 10 \text{ kg}$ . The container slides down an incline of  $\theta = 30^\circ$  with respect to the horizontal. The coefficient of sliding friction is  $0.30$ .

**Find:** The angle of the water surface relative to the horizontal.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**  $-\nabla p + \rho \vec{g} = \rho \vec{a}$  (Hydrostatic equation)

$$\vec{F} = M\vec{a} \quad (\text{Newton's Second Law})$$

**Assumptions:** (1) Incompressible fluid  
(2) Rigid body motion

Writing the component relations:  $-\frac{\partial p}{\partial x} = \rho a_x$     $\frac{\partial p}{\partial x} = -\rho a_x$     $-\frac{\partial p}{\partial y} - \rho g = \rho a_y$     $\frac{\partial p}{\partial y} = -\rho(g + a_y)$

We write the total differential of pressure as:  $dp = \frac{\partial p}{\partial x} dx + \frac{\partial p}{\partial y} dy$  Now along the free surface of the water  $dp = 0$ . Thus:

$\frac{dy}{dx} = -\frac{\partial p / \partial x}{\partial p / \partial y} = -\frac{a_x}{g + a_y}$  and  $\alpha = \text{atan}\left(-\frac{dy}{dx}\right)$  To determine the acceleration components we analyze a free-body diagram:

$$M = M_c + M_w = M_c + \rho_w \cdot V_w \quad M = 10 \cdot \text{kg} + 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 0.4 \cdot \text{m} \times 0.2 \cdot \text{m} \times 0.2 \cdot \text{m} \quad M = 25.98 \text{ kg}$$

$$\Sigma F_y' = 0 = N - M \cdot g \cdot \cos(\theta) \quad N = M \cdot g \cdot \cos(\theta) \quad N = 25.98 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \cos(30 \cdot \text{deg}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad N = 220.7 \text{ N}$$



$$\Sigma F_x' = M \cdot a_{x'} = M \cdot g \cdot \sin(\theta) - F_f = M \cdot g \cdot \sin(\theta) - \mu \cdot N \quad a_{x'} = g \cdot \sin(\theta) - \mu \cdot \frac{N}{M}$$

$$a_{x'} = 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \sin(30 \cdot \text{deg}) - 0.30 \times 220.7 \cdot \text{N} \times \frac{1}{25.98 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad a_{x'} = 2.357 \frac{\text{m}}{\text{s}^2}$$

Now that we have the acceleration in the  $x'$ - $y'$  system, we transform it to the  $x$ - $y$  system:  $a_x = a_{x'} \cdot \cos(\theta)$     $a_y = -a_{x'} \cdot \sin(\theta)$

$$a_x = 2.357 \cdot \frac{\text{m}}{\text{s}^2} \times \cos(30 \cdot \text{deg}) \quad a_x = 2.041 \frac{\text{m}}{\text{s}^2} \quad a_y = -2.357 \cdot \frac{\text{m}}{\text{s}^2} \times \sin(30 \cdot \text{deg}) \quad a_y = -1.178 \frac{\text{m}}{\text{s}^2}$$

Thus,  $\alpha = \text{atan}\left(\frac{2.041}{9.81 - 1.178}\right)$     $\alpha = 13.30 \cdot \text{deg}$



## Problem \*3.122

[Difficulty: 3]

**3.122** If the container of Problem 3.121 slides without friction, determine the angle of the water surface relative to the horizontal. What is the slope of the free surface for the same acceleration up the plane?

**Given:** Rectangular container of base dimensions 0.4 m x 0.2 m and a height of 0.4 m is filled with water to a depth of  $d = 0.2$  m. Mass of empty container is  $M_c = 10$  kg. The container slides down an incline of  $\theta = 30$  deg with respect to the horizontal without friction.


**Find:** (a) The angle of the water surface relative to the horizontal.  
(b) The slope of the free surface for the same acceleration up the plane.

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$-\nabla p + \rho \vec{g} = \rho \vec{a} \quad (\text{Hydrostatic equation})$$

$$\vec{F} = M\vec{a} \quad (\text{Newton's Second Law})$$



**Assumptions:** (1) Incompressible fluid  
(2) Rigid body motion

Writing the component relations:

$$-\frac{\partial p}{\partial x} = \rho a_x \quad \frac{\partial p}{\partial x} = -\rho a_x \quad -\frac{\partial p}{\partial y} - \rho g = \rho a_y \quad \frac{\partial p}{\partial y} = -\rho(g + a_y)$$

We write the total differential of pressure as:  $dp = \frac{\partial p}{\partial x} dx + \frac{\partial p}{\partial y} dy$  Now along the free surface of the water  $dp = 0$ . Thus:

$$\frac{dy}{dx} = -\frac{\partial p / \partial x}{\partial p / \partial y} = -\frac{a_x}{g + a_y} \quad \text{and} \quad \alpha = \text{atan}\left(-\frac{dy}{dx}\right)$$

To determine the acceleration components we analyze a free-body diagram:


$$M = M_c + M_w = M_c + \rho_w \cdot V_w \quad M = 10 \cdot \text{kg} + 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 0.4 \cdot \text{m} \times 0.2 \cdot \text{m} \times 0.2 \cdot \text{m} \quad M = 25.98 \text{ kg}$$

$$\Sigma F_{x'} = M \cdot a_{x'} = M \cdot g \cdot \sin(\theta) \quad a_{x'} = g \cdot \sin(\theta) \quad a_x = a_{x'} \cdot \cos(\theta) = g \cdot \sin(\theta) \cdot \cos(\theta)$$

$$a_y = -a_{x'} \cdot \sin(\theta) = g \cdot (\sin(\theta))^2$$

Thus,

$$\frac{dy}{dx} = -\frac{g \cdot \sin(\theta) \cdot \cos(\theta)}{g[1 - (\sin(\theta))^2]} = -\frac{\sin(\theta) \cdot \cos(\theta)}{(\cos(\theta))^2} = -\frac{\sin(\theta)}{\cos(\theta)} = -\tan(\theta) \quad \alpha = 30 \cdot \text{deg}$$



For the acceleration up the incline:  $a_x = -g \cdot \sin(\theta) \cdot \cos(\theta) \quad a_y = g \cdot (\sin(\theta))^2$

Thus,

$$\text{slope} = \frac{g \cdot \sin(\theta) \cdot \cos(\theta)}{g[1 + (\sin(\theta))^2]} = -\frac{\sin(\theta) \cdot \cos(\theta)}{1 + (\sin(\theta))^2} \quad \text{slope} = \frac{\sin(30 \cdot \text{deg}) \cdot \cos(30 \cdot \text{deg})}{1 + (\sin(30 \cdot \text{deg}))^2} \quad \text{slope} = 0.346$$

### Problem \*3.123

[Difficulty: 3]

**3.123** A cubical box, 80 cm on a side, half-filled with oil (SG = 0.80), is given a constant horizontal acceleration of 0.25 g parallel to one edge. Determine the slope of the free surface and the pressure along the horizontal bottom of the box.

**Given:** Cubical box with constant acceleration

**Find:** Slope of free surface; pressure along bottom of box

**Solution:** Basic equation  $-\nabla p + \rho \vec{g} = \rho \vec{a}$

In components  $\frac{\partial}{\partial x} p + \rho \cdot g_x = \rho \cdot a_x$   $\frac{\partial}{\partial y} p + \rho \cdot g_y = \rho \cdot a_y$   $\frac{\partial}{\partial z} p + \rho \cdot g_z = \rho \cdot a_z$

We have  $a_x = a_x$   $g_x = 0$   $a_y = 0$   $g_y = -g$   $a_z = 0$   $g_z = 0$

Hence  $\frac{\partial}{\partial x} p = -SG \cdot \rho \cdot a_x$  (1)  $\frac{\partial}{\partial y} p = -SG \cdot \rho \cdot g$  (2)  $\frac{\partial}{\partial z} p = 0$  (3)

From Eq. 3 we can simplify from  $p = p(x, y, z)$  to  $p = p(x, y)$

Hence a change in pressure is given by  $dp = \frac{\partial}{\partial x} p \cdot dx + \frac{\partial}{\partial y} p \cdot dy$  (4)

At the free surface  $p = \text{const.}$ , so  $dp = 0 = \frac{\partial}{\partial x} p \cdot dx + \frac{\partial}{\partial y} p \cdot dy$  or  $\frac{dy}{dx} = -\frac{\frac{\partial}{\partial x} p}{\frac{\partial}{\partial y} p} = -\frac{a_x}{g} = -\frac{0.25 \cdot g}{g}$

Hence at the free surface  $\frac{dy}{dx} = -0.25$

The equation of the free surface is then  $y = -\frac{x}{4} + C$  and through volume conservation the fluid rise in the rear balances the fluid fall in the front, so at the midpoint the free surface has not moved from the rest position

For size  $L = 80\text{-cm}$  at the midpoint  $x = \frac{L}{2}$   $y = \frac{L}{2}$  (box is half filled)  $\frac{L}{2} = -\frac{1}{4} \cdot \frac{L}{2} + C$   $C = \frac{5}{8} \cdot L$   $y = \frac{5}{8} \cdot L - \frac{x}{4}$

Combining Eqs 1, 2, and 4  $dp = -SG \cdot \rho \cdot a_x \cdot dx - SG \cdot \rho \cdot g \cdot dy$  or  $p = -SG \cdot \rho \cdot a_x \cdot x - SG \cdot \rho \cdot g \cdot y + c$

We have  $p = p_{\text{atm}}$  when  $x = 0$   $y = \frac{5}{8} \cdot L$  so  $p_{\text{atm}} = -SG \cdot \rho \cdot g \cdot \frac{5}{8} \cdot L + c$   $c = p_{\text{atm}} + SG \cdot \rho \cdot g \cdot \frac{5}{8} \cdot L$

$$p(x, y) = p_{\text{atm}} + SG \cdot \rho \cdot \left( \frac{5}{8} \cdot g \cdot L - a_x \cdot x - g \cdot y \right) = p_{\text{atm}} + SG \cdot \rho \cdot g \cdot \left( \frac{5}{8} \cdot L - \frac{x}{4} - y \right)$$

On the bottom  $y = 0$  so

$$p(x, 0) = p_{\text{atm}} + SG \cdot \rho \cdot g \cdot \left( \frac{5}{8} \cdot L - \frac{x}{4} \right) = 101 + 0.8 \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \left( \frac{5}{8} \times 0.8 \cdot \text{m} - \frac{x}{4} \right) \times \frac{\text{kPa}}{10^3 \cdot \text{Pa}}$$

$$p(x, 0) = 105 - 1.96 \cdot x \quad (p \text{ in kPa, } x \text{ in m})$$

### Problem \*3.124


[Difficulty: 3]

**3.124** Gas centrifuges are used in one process to produce enriched uranium for nuclear fuel rods. The maximum peripheral speed of a gas centrifuge is limited by stress considerations to about 950 ft/s. Assume a gas centrifuge containing uranium hexafluoride gas, with molecular gas  $M_m = 352$ , and ideal gas behavior. Develop an expression for the ratio of maximum pressure to pressure at the centrifuge axis. Evaluate the pressure ratio for a gas temperature of 620°F.

**Given:** Gas centrifuge, with maximum peripheral speed  $V_{\max} = 950$  ft/s contains uranium hexafluoride gas ( $M = 352$  lb/lbmol) at 620 deg F.

**Find:** (a) Ratio of maximum pressure to pressure at the centrifuge axis  
(b) Evaluate pressure ratio at 620 deg F.

**Solution:** We will apply the hydrostatics equations to this system.



**Governing Equations:**

$$-\nabla p + \rho \vec{g} = \rho \vec{a} \quad (\text{Hydrostatic equation})$$

$$-\frac{\partial p}{\partial r} + \rho g_r = \rho a_r \quad (\text{Hydrostatic equation radial component})$$

**Assumptions:** (1) Incompressible fluid  
(2) Rigid body motion  
(3) Ideal gas behavior, constant temperature

For rigid body motion:  $a_r = -\frac{V^2}{r} = -\frac{(r \cdot \omega)^2}{r} = -r \cdot \omega^2$

Thus:  $\frac{\partial p}{\partial r} = -\rho a_r = \frac{\rho}{R_g T} r \omega^2$

Separating variables and integrating:

$$\int_{p_1}^{p_2} \frac{1}{p} dp = \frac{\omega^2}{R_g \cdot T} \cdot \int_0^{r_2} r dr \quad \ln\left(\frac{p_2}{p_1}\right) = \frac{\omega^2}{R_g \cdot T} \cdot \frac{r_2^2}{2} \quad \text{where we define: } V_{\max} = \omega \cdot r_2 \quad \text{therefore: } \ln\left(\frac{p_2}{p_1}\right) = \frac{V_{\max}^2}{2 \cdot R_g \cdot T}$$

Solving for the pressure ratio:  $p_{\text{rat}} = \frac{p_2}{p_1} = e^{\left(\frac{V_{\max}^2}{2 \cdot R_g \cdot T}\right)}$

The gas constant:  $R_g = \frac{1545}{352} \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \quad R_g = 4.39 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}}$

Substituting in all known values:  $p_{\text{rat}} = e^{\left[\left(950 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{1}{2} \times \frac{1}{4.39 \cdot \text{ft} \cdot \text{lb}_f} \times \frac{1}{(620+460) \cdot \text{R}} \times \frac{\text{lb}_f \cdot \text{s}^2}{32.2 \cdot \text{lbm} \cdot \text{ft}}\right]}$   $p_{\text{rat}} = 19.2$

### Problem \*3.125


[Difficulty: 3]

**3.125** A pail, 400 mm in diameter and 400 mm deep, weighs 15 N and contains 200 mm of water. The pail is swung in a vertical circle of 1-m radius at a speed of 5 m/s. Assume the water moves as a rigid body. At the instant when the pail is at the top of its trajectory, compute the tension in the string and the pressure on the bottom of the pail from the water.

**Given:** Pail is swung in a vertical circle. Water moves as a rigid body.  
Point of interest is the top of the trajectory.

**Find:** (a) Tension in the string  
(b) Pressure on pail bottom from the water.

**Solution:** We will apply the hydrostatics equations to this system.



**Governing Equations:**  $-\nabla p + \rho \vec{g} = \rho \vec{a}$  (Hydrostatic equation)

$$-\frac{\partial p}{\partial r} + \rho g_r = \rho a_r \quad \text{(Hydrostatic equation radial component)}$$

**Assumptions:** (1) Incompressible fluid  
(2) Rigid body motion  
(3) Center of mass of bucket and water are located at a radius of 1 m where  $V = r\omega = 5 \text{ m/s}$

Summing the forces in the radial direction:  $-T - (M_b + M_w) \cdot g = (M_b + M_w) a_r$  where  $a_r = -\frac{V^2}{r}$

Thus the tension is:  $T = (M_b + M_w) \cdot \left( \frac{V^2}{r} - g \right)$  where:  $M_b = 15 \cdot \text{N} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}$   $M_b = 1.529 \cdot \text{kg}$

and:  $M_w = \rho \cdot V = \rho \cdot \frac{\pi}{4} \cdot d^2 \cdot h$   $M_w = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \frac{\pi}{4} \times (0.4 \cdot \text{m})^2 \times 0.2 \cdot \text{m}$   $M_w = 25.11 \cdot \text{kg}$

Now we find T:  $T = (1.529 + 25.11) \cdot \text{kg} \times \left[ \left( 5 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{1}{1 \cdot \text{m}} - 9.81 \cdot \frac{\text{m}}{\text{s}^2} \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $T = 405 \cdot \text{N}$

If we apply this information to the radial hydrostatic equation we get:  $-\frac{\partial p}{\partial r} - \rho g = -\rho \frac{V^2}{r}$  Thus:  $\frac{\partial p}{\partial r} = \rho \left( \frac{V^2}{r} - g \right)$

If we assume that the radial pressure gradient is constant throughout the water, then the pressure gradient is equal to:


$$p_r = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ \left( 5 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{1}{1 \cdot \text{m}} - 9.81 \cdot \frac{\text{m}}{\text{s}^2} \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad p_r = 15.17 \cdot \frac{\text{kPa}}{\text{m}}$$

and we may calculate the pressure at the bottom of the bucket:  $\Delta p = p_r \cdot \Delta r$   $\Delta p = 15.17 \cdot \frac{\text{kPa}}{\text{m}} \times 0.2 \cdot \text{m}$   $\Delta p = 3.03 \cdot \text{kPa}$

### Problem \*3.126

[Difficulty: 3]

**3.126** A partially full can of soda is placed at the outer edge of a child's merry-go-round, located  $R = 5$  ft from the axis of rotation. The can diameter and height are 2.5 in. and 5 in., respectively. The can is half full, and the soda has specific gravity  $SG = 1.05$ . Evaluate the slope of the liquid surface in the can if the merry-go-round spins at 20 rpm. Calculate the spin rate at which the can would spill, assuming no slippage between the can bottom and the merry-go-round. Would the can most likely spill or slide off the merry-go-round?



**Given:** Half-filled soft drink can at the outer edge of a merry-go-round

$$\omega = 0.3 \cdot \frac{\text{rev}}{\text{s}}$$

**Find:** (a) Slope of free surface  
(b) Spin rate necessary for spillage  
(c) Likelihood of spilling versus slipping

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$-\nabla p + \rho \vec{g} = \rho \vec{a} \quad (\text{Hydrostatic equation})$$

$$-\frac{\partial p}{\partial r} + \rho g_r = \rho a_r \quad (\text{Hydrostatic equation radial component})$$

$$-\frac{\partial p}{\partial z} + \rho g_z = \rho a_z \quad (\text{Hydrostatic equation z component})$$

**Assumptions:** (1) Incompressible fluid  
(2) Rigid body motion  
(3) Merry-go-round is horizontal

$$a_r = -\frac{V^2}{r} = -\frac{(r\omega)^2}{r} = -r\omega^2 \quad a_z = 0 \quad g_r = 0 \quad g_z = -g \quad \text{Thus:} \quad \frac{\partial p}{\partial r} = \rho r \omega^2 \quad \frac{\partial p}{\partial z} = -\rho g \quad \text{So } p = p(r, z)$$

$$dp = \frac{\partial p}{\partial r} dr + \frac{\partial p}{\partial z} dz \quad \text{For the free surface the pressure is constant. Therefore:} \quad \frac{dz}{dr} = -\frac{\partial p / \partial r}{\partial p / \partial z} = -\frac{\rho r \omega^2}{-\rho g} = \frac{r \omega^2}{g}$$

So the slope at the free surface is  $\text{slope} = 5 \cdot \text{ft} \times \left( 20 \cdot \frac{\text{rev}}{\text{min}} \times \frac{\text{min}}{60 \cdot \text{s}} \times \frac{2 \cdot \pi \cdot \text{rad}}{\text{rev}} \right)^2 \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \quad \text{slope} = 0.681$

To spill, the slope must be  $\frac{H}{D}$   $\text{slope}_{\text{sp}} = \frac{H}{D} \quad \text{slope}_{\text{sp}} = \frac{5}{2.5} \quad \text{slope}_{\text{sp}} = 2.000$

Thus,  $\omega_{\text{sp}} = \sqrt{\frac{g}{r} \cdot \frac{dz}{dr}} \quad \omega_{\text{sp}} = \sqrt{32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{1}{5 \cdot \text{ft}} \times 2} \quad \omega_{\text{sp}} = 3.59 \cdot \frac{\text{rad}}{\text{s}}$

This is nearly double the original speed (2.09 rad/s). Now the coefficient of static friction between the can and the surface of the merry-go-round is probably less than 0.5. Thus the can would not likely spill or tip; it would slide off!

## Problem \*3.127

[Difficulty: 2]

**3.127** When a water polo ball is submerged below the surface in a swimming pool and released from rest, it is observed to pop out of the water. How would you expect the height to which it rises above the water to vary with depth of submersion below the surface? Would you expect the same results for a beach ball? For a table-tennis ball?

**Discussion:** Separate the problem into two parts: (1) the motion of the ball in water below the pool surface, and (2) the motion of the ball in air above the pool surface.

Below the pool water surface the motion of each ball is controlled by buoyancy force and inertia. For small depths of submersion ball speed upon reaching the surface will be small. As depth is increased, ball speed will increase until terminal speed in water is approached. For large depths, the actual depth will be irrelevant because the ball will reach terminal speed before reaching the pool water surface. All three balls are relatively light for their diameters, so terminal speed in water should be reached quickly. The depth of submersion needed to reach terminal speed should be fairly small, perhaps 1 meter or less (The initial water depth required to reach terminal speed may be calculated using the methods of Chapter 9).

Buoyancy is proportional to volume and inertia is proportional to mass. The ball with the largest volume per unit mass should accelerate most quickly to terminal speed. This will probably be the beach ball, followed by the table-tennis ball and the water polo ball.

The ball with the largest diameter has the smallest frontal area per unit volume; the terminal speed should be highest for this ball. Therefore, the beach ball should have the highest terminal speed, followed by the water polo ball and the table-tennis ball.

Above the pool water surface the motion of each ball is controlled by aerodynamic drag force, gravity force, and inertia (see the equation below). Without aerodynamic drag, the height above the pool water surface reached by each ball will depend only on its initial speed (The maximum height reached by a ball in air with aerodynamic drag may be calculated using the methods of Chapter 9). Aerodynamic drag reduces the height reached by the ball.

Aerodynamic drag is proportional to frontal area. The heaviest ball per unit frontal area (probably the water polo ball) should reach the maximum height and the lightest ball per unit area (probably the beach ball) should reach the minimum height.

$$\Sigma F_y = -F_D - m \cdot g = m \cdot a_y = m \cdot \frac{dV}{dt} = -C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot V^2 - m \cdot g \quad \text{since} \quad F_D = C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot V^2$$

Thus, 
$$-\frac{C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot V^2}{m} - g = \frac{dV}{dt} = V \cdot \frac{dV}{dy} \quad (1)$$

We solve this by separating variables:

$$\frac{V \cdot dV}{1 + \frac{C_D \cdot A \cdot \rho}{m \cdot g} \cdot \frac{V^2}{2}} = -g \cdot dy$$

Integrating this expression over the flight of the ball yields:

$$-\frac{m \cdot g}{\rho \cdot C_D \cdot A} \cdot \ln \left( 1 + \frac{\rho \cdot C_D \cdot A}{m \cdot g} \cdot \frac{V_0^2}{2} \right) = -g \cdot y_{\max}$$

Solving for the maximum height: 
$$y_{\max} = -\frac{m}{\rho \cdot C_D \cdot A} \cdot \ln \left( 1 + \frac{\rho \cdot C_D \cdot A}{m \cdot g} \cdot \frac{V_0^2}{2} \right)$$
 Simplifying: 
$$y_{\max} = -\frac{m}{\rho \cdot C_D \cdot A} \cdot \ln \left( 1 + \frac{F_{D0}}{m \cdot g} \right) \quad (2)$$

If we neglect drag, equation (1) becomes:  $-g \cdot dy = V \cdot dV$  Integrating and solving for the maximum height: 
$$y_{\max} = -\frac{V_0^2}{2 \cdot g} \quad (3)$$

Checking the limiting value predicted by Eq (2) as  $C_D \rightarrow 0$  : we remember that for small x that  $\ln(1+x) = -x$ . Thus:

$$\lim_{C_D \rightarrow 0} y_{\max} = \lim_{C_D \rightarrow 0} \left( -\frac{m}{\rho C_D A} \cdot \frac{\rho C_D A}{m g} \cdot \frac{V_0^2}{2} \right) = \frac{V_0^2}{2g} \quad \text{which is the result in Equation (3).}$$


## Problem \*3.128

[Difficulty: 4]

**3.128** Cast iron or steel molds are used in a horizontal-spindle machine to make tubular castings such as liners and tubes. A charge of molten metal is poured into the spinning mold. The radial acceleration permits nearly uniformly thick wall sections to form. A steel liner, of length  $L = 6$  ft, outer radius  $r_o = 6$  in., and inner radius  $r_i = 4$  in., is to be formed by this process. To attain nearly uniform thickness, the angular velocity should be at least 300 rpm. Determine (a) the resulting radial acceleration on the inside surface of the liner and (b) the maximum and minimum pressures on the surface of the mold.

**Given:** A steel liner is to be formed in a spinning horizontal mold. To insure uniform thickness the minimum angular velocity should be at least 300 rpm. For steel,  $SG = 7.8$

**Find:** (a) The resulting radial acceleration on the inside surface of the liner  
(b) the maximum and minimum pressures on the surface of the mold



(gravity is downward in this diagram)

**Solution:** We will apply the hydrostatics equations to this system.

**Governing Equations:**

$$-\nabla p + \rho \vec{g} = \rho \vec{a} \quad (\text{Hydrostatic equation})$$

$$-\frac{\partial p}{\partial r} + \rho g_r = \rho a_r \quad (\text{Hydrostatic equation radial component})$$

$$-\frac{1}{r} \frac{\partial p}{\partial \theta} + \rho g_\theta = \rho a_\theta \quad (\text{Hydrostatic equation transverse component})$$

$$-\frac{\partial p}{\partial z} + \rho g_z = \rho a_z \quad (\text{Hydrostatic equation z component})$$

**Assumptions:** (1) Incompressible fluid  
(2) Rigid body motion

$$a_r = -\frac{V^2}{r} = -\frac{(r\omega)^2}{r} = -r\omega^2 \quad a_\theta = 0 \quad a_z = 0 \quad g_r = -g \cdot \cos(\theta) \quad g_\theta = g \cdot \sin(\theta) \quad g_z = 0$$

Hence:  $a_r = 4 \cdot \text{in} \times \left( 300 \times \frac{\text{rev}}{\text{min}} \times \frac{2 \cdot \pi \cdot \text{rad}}{\text{rev}} \times \frac{\text{min}}{60 \cdot \text{s}} \right)^2 \times \frac{\text{ft}}{12 \cdot \text{in}} \quad a_r = 329 \cdot \frac{\text{ft}}{\text{s}^2} \quad a_r = 10.23 \cdot g$

Thus:  $\frac{\partial p}{\partial r} = \rho g_r - \rho a_r = \rho r \omega^2 - \rho g \cos \theta \quad \frac{\partial p}{\partial \theta} = \rho r g_\theta - \rho r a_\theta = \rho r g \sin \theta \quad \frac{\partial p}{\partial z} = \rho g_z - \rho a_z = 0$

$$dp = \frac{\partial p}{\partial r} dr + \frac{\partial p}{\partial \theta} d\theta = (\rho r \omega^2 - \rho g \cos \theta) dr + (\rho r g \sin \theta) d\theta$$

We can integrate to find pressure as a function of  $r$  and  $\theta$ .  $p(r_i, \theta) = p_{\text{atm}} \quad \left. \frac{\partial p}{\partial r} \right|_\theta = \rho r \omega^2 - \rho g \cos \theta$

Therefore, we integrate:  $p - p_{\text{atm}} = \int_{r_i}^r (\rho \cdot r \cdot \omega^2 - \rho \cdot g \cdot \cos(\theta)) dr + f(\theta)$

$$p = p_{atm} + \rho \cdot \omega^2 \cdot \frac{(r^2 - r_i^2)}{2} - \rho \cdot g \cdot \cos(\theta) \cdot (r - r_i) + f(\theta) \quad \text{Taking the derivative of pressure with respect to } \theta:$$

$$\left. \frac{\partial p}{\partial \theta} \right)_r = \rho(r - r_i)g \sin \theta + \frac{df}{d\theta} = \rho r g \sin \theta \quad \text{Thus, the integration function } f(\theta) \text{ is:} \quad f(\theta) = -\rho \cdot g \cdot r_i \cdot \cos(\theta) + C$$

$$\text{Therefore, the pressure is:} \quad p = p_{atm} + \rho \cdot \omega^2 \cdot \frac{(r^2 - r_i^2)}{2} - \rho \cdot g \cdot (r - r_i) \cdot \cos(\theta) - \rho \cdot g \cdot r_i \cdot \cos(\theta) + C$$

$$\text{The integration constant is determined from the boundary condition:} \quad p(r_i, \theta) = p_{atm}$$

$$p_{atm} = p_{atm} + \rho \cdot \omega^2 \cdot \frac{(r_i^2 - r_i^2)}{2} - \rho \cdot g \cdot (r_i - r_i) \cdot \cos(\theta) - \rho \cdot g \cdot r_i \cdot \cos(\theta) + C \quad -\rho \cdot g \cdot r_i \cdot \cos(\theta) + C = 0 \quad C = \rho \cdot g \cdot r_i \cdot \cos(\theta)$$

$$\text{Therefore, the pressure is:} \quad p = p_{atm} + \rho \cdot \omega^2 \cdot \frac{(r^2 - r_i^2)}{2} - \rho \cdot g \cdot (r - r_i) \cdot \cos(\theta)$$

The maximum pressure should occur on the mold surface at  $\theta = \pi$ :

$$p_{maxgage} = \left[ \left( 7.8 \cdot 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \right) \times \left( 31.42 \cdot \frac{\text{rad}}{\text{s}} \right)^2 \times \frac{1}{2} \cdot \left( \frac{6^2 - 4^2}{12^2} \right) \cdot \text{ft}^2 - \left( 7.8 \cdot 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \right) \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \left( \frac{6 - 4}{12} \right) \cdot \text{ft} \cdot \cos(\pi) \right] \cdot \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$p_{maxgage} = 1119 \cdot \text{psf}$$

$$p_{maxgage} = 7.77 \cdot \text{psi}$$

The minimum pressure should occur on the mold surface at  $\theta = 0$ :

$$p_{mingage} = \left[ \left( 7.8 \cdot 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \right) \times \left( 31.42 \cdot \frac{\text{rad}}{\text{s}} \right)^2 \times \frac{1}{2} \cdot \left( \frac{6^2 - 4^2}{12^2} \right) \cdot \text{ft}^2 - \left( 7.8 \cdot 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \right) \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \left( \frac{6 - 4}{12} \right) \cdot \text{ft} \cdot \cos(0) \right] \cdot \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$p_{mingage} = 956 \cdot \text{psf}$$

$$p_{mingage} = 6.64 \cdot \text{psi}$$

(In both results we divided by 144 to convert from psf to psi.)

## Problem \*3.129

[Difficulty: 4]


**3.129** The analysis of Problem 3.121 suggests that it may be possible to determine the coefficient of sliding friction between two surfaces by measuring the slope of the free surface in a liquid-filled container sliding down an inclined surface. Investigate the feasibility of this idea.

**Discussion:** A certain minimum angle of inclination would be needed to overcome static friction and start the container into motion down the incline. Once the container is in motion, the retarding force would be provided by sliding (dynamic) friction. The coefficient of dynamic friction usually is smaller than the static friction coefficient. Thus the container would continue to accelerate as it moved down the incline. This acceleration would provide a non-zero slope to the free surface of the liquid in the container.

In principle the slope could be measured and the coefficient of dynamic friction calculated. In practice several problems would arise.

To calculate dynamic friction coefficient one must assume the liquid moves as a solid body, i.e., that there is no sloshing. This condition could only be achieved if there were a minimum initial disturbance and the sliding distance were long.

It would be difficult to measure the slope of the free surface of liquid in the moving container. Images made with a video camera or a digital still camera might be processed to obtain the required slope information.



$$\Sigma F_y = 0 = N - M \cdot g \cdot \cos(\theta) \quad N = M \cdot g \cdot \cos(\theta)$$

$$\Sigma F_x = M \cdot a_x = M \cdot g \cdot \sin(\theta) - F_f \quad F_f = \mu_k \cdot N = \mu_k \cdot M \cdot g \cdot \cos(\theta)$$

Thus the acceleration is:

$$a_x = g \cdot \sin(\theta) - \mu_k \cdot g \cdot \cos(\theta) \quad \text{Now for a static liquid:} \quad -\nabla p + \rho \vec{g} = \rho \vec{a}$$

$$-\frac{\partial p}{\partial x} + \rho g \sin \theta = \rho a_x = \rho (g \sin \theta - \mu_k g \cos \theta) \quad \frac{\partial p}{\partial x} = \rho g \mu_k \cos \theta$$

$$-\frac{\partial p}{\partial y} - \rho g \cos \theta = \rho a_y = 0 \quad \frac{\partial p}{\partial y} = -\rho g \cos \theta$$

$$dp = \frac{\partial p}{\partial x} dx + \frac{\partial p}{\partial y} dy$$

For the free surface the pressure is constant. Therefore:  $\frac{dy}{dx} = -\frac{\partial p / \partial x}{\partial p / \partial y} = -\frac{\rho g \mu_k \cos \theta}{-\rho g \cos \theta} = \mu_k$

So the free surface angle is:  $\alpha = \text{atan}(\mu_k)$  Now since it is necessary to make the container slip along the surface,

$$\theta > \text{atan}(\mu_s) > \text{atan}(\mu_k) = \alpha$$

Thus,  $\alpha < \theta$ , as shown in the sketch above.

## Problem 4.1

[Difficulty: 2]

**4.1** A mass of 5 lbm is released when it is just in contact with a spring of stiffness 25 lbf/ft that is attached to the ground. What is the maximum spring compression? Compare this to the deflection if the mass was just resting on the compressed spring. What would be the maximum spring compression if the mass was released from a distance of 5 ft above the top of the spring?

**Given:** Data on mass and spring

**Find:** Maximum spring compression

**Solution:**

The given data is  $M = 5 \cdot \text{lb}$   $h = 5 \cdot \text{ft}$   $k = 25 \cdot \frac{\text{lbf}}{\text{ft}}$

Apply the First Law of Thermodynamics: for the system consisting of the mass and the spring (the spring has gravitational potential energy and the spring elastic potential energy)

Total mechanical energy at initial state  $E_1 = 0$

Note: The datum for zero potential is the top of the uncompressed spring

Total mechanical energy at instant of maximum compression  $x$   $E_2 = M \cdot g \cdot (-x) + \frac{1}{2} \cdot k \cdot x^2$

But  $E_1 = E_2$

so  $0 = M \cdot g \cdot (-x) + \frac{1}{2} \cdot k \cdot x^2$

Solving for  $x$   $x = \frac{2 \cdot M \cdot g}{k}$   $x = 2 \times 5 \cdot \text{lb} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{ft}}{25 \cdot \text{lbf}} \times \frac{32.2 \cdot \text{lb} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}}$   $x = 0.401 \cdot \text{ft}$

When just resting on the spring  $x = \frac{M \cdot g}{k}$   $x = 0.200 \text{ ft}$

When dropped from height  $h$ :

Total mechanical energy at initial state  $E_1 = M \cdot g \cdot h$

Total mechanical energy at instant of maximum compression  $x$   $E_2 = M \cdot g \cdot (-x) + \frac{1}{2} \cdot k \cdot x^2$

Note: The datum for zero potential is the top of the uncompressed spring

But  $E_1 = E_2$

so  $M \cdot g \cdot h = M \cdot g \cdot (-x) + \frac{1}{2} \cdot k \cdot x^2$

Solving for x

$$x^2 - \frac{2 \cdot M \cdot g}{k} \cdot x - \frac{2 \cdot M \cdot g \cdot h}{k} = 0$$

$$x = \frac{M \cdot g}{k} + \sqrt{\left(\frac{M \cdot g}{k}\right)^2 + \frac{2 \cdot M \cdot g \cdot h}{k}}$$

$$x = 5 \cdot \text{lb} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{ft}}{25 \cdot \text{lbf}} \times \frac{32.2 \cdot \text{lb} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}} + \sqrt{\left(5 \cdot \text{lb} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{ft}}{25 \cdot \text{lbf}} \times \frac{32.2 \cdot \text{lb} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}}\right)^2 + 2 \times 5 \cdot \text{lb} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{ft}}{25 \cdot \text{lbf}} \times \frac{32.2 \cdot \text{lb} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}} \times 5 \cdot \text{ft}}$$

$$x = 1.63 \cdot \text{ft}$$

Note that ignoring the loss of potential of the mass due to spring compression x gives

$$x = \sqrt{\frac{2 \cdot M \cdot g \cdot h}{k}} \quad x = 1.41 \cdot \text{ft}$$

## Problem 4.2

[Difficulty: 2]

**4.2** An ice-cube tray containing 250 mL of freshwater at 15°C is placed in a freezer at -5°C. Determine the change in internal energy (kJ) and entropy (kJ/K) of the water when it has frozen.

**Given:** An ice-cube tray with water at 15°C is frozen at -5°C.

**Find:** Change in internal energy and entropy

**Solution:** Apply the Tds and internal energy equations

**Governing equations:**  $Tds = du + pdv$   $du = c_v dT$

**Assumption:** Neglect volume change  
Liquid properties similar to water

The given or available data is:

$$T_1 = (15 + 273) \text{ K} = 288 \text{ K} \quad T_2 = (-5 + 273) \text{ K} = 268 \text{ K}$$

$$c_v = 1 \frac{\text{kcal}}{\text{kg} \cdot \text{K}} \quad \rho = 999 \frac{\text{kg}}{\text{m}^3}$$

Then with the assumption:  $Tds = du + pdv = du = c_v dT$

or 
$$ds = c_v \frac{dT}{T}$$

Integrating 
$$s_2 - s_1 = c_v \ln\left(\frac{T_2}{T_1}\right) \quad \text{or} \quad \Delta S = m(s_2 - s_1) = \rho V c_v \ln\left(\frac{T_2}{T_1}\right)$$

$$\Delta S = 999 \frac{\text{kg}}{\text{m}^3} \times 250 \text{ mL} \times \frac{10^{-6} \text{ m}^3}{\text{mL}} \times 1 \frac{\text{kcal}}{\text{kg} \cdot \text{K}} \times \ln\left(\frac{268}{288}\right) \times 4190 \frac{\text{J}}{\text{kcal}}$$

$$\Delta S = -0.0753 \frac{\text{kJ}}{\text{K}}$$

Also 
$$u_2 - u_1 = c_v (T_2 - T_1) \quad \text{or} \quad \Delta U = m c_v (T_2 - T_1) = \rho V c_v \Delta T$$

$$\Delta U = 999 \frac{\text{kg}}{\text{m}^3} \times 250 \text{ mL} \times \frac{10^{-6} \text{ m}^3}{\text{mL}} \times 1 \frac{\text{kcal}}{\text{kg} \cdot \text{K}} \times (-268 - 288) \text{ K} \times 4190 \frac{\text{J}}{\text{kcal}}$$

$$\Delta U = -20.9 \text{ kJ}$$

### Problem 4.3

[Difficulty: 2]


**4.3** A small steel ball of radius  $r = 1$  mm is placed on top of a horizontal pipe of outside radius  $R = 50$  mm and begins to roll under the influence of gravity. Rolling resistance and air resistance are negligible. As the speed of the ball increases, it eventually leaves the surface of the pipe and becomes a projectile. Determine the speed and location at which the ball loses contact with the pipe.

**Given:** Data on ball and pipe

**Find:** Speed and location at which contact is lost

**Solution:**

The given data is  $r = 1$  mm  $R = 50$  mm



$$\sum F_n = F_n - m \cdot g \cdot \cos(\theta) = m \cdot a_n$$

$$a_n = -\frac{V^2}{R + r}$$

Contact is lost when  $F_n = 0$  or  $-m \cdot g \cdot \cos(\theta) = -m \cdot \frac{V^2}{R + r}$

$$V^2 = g \cdot (R + r) \cdot \cos(\theta) \quad (1)$$

For no resistance energy is conserved, so  $E = m \cdot g \cdot z + m \cdot \frac{V^2}{2} = m \cdot g \cdot (R + r) \cdot \cos(\theta) + m \cdot \frac{V^2}{2} = E_0 = m \cdot g \cdot (R + r)$

Hence from energy considerations  $V^2 = 2 \cdot g \cdot (R + r) \cdot (1 - \cos(\theta)) \quad (2)$

Combining 1 and 2,  $V^2 = 2 \cdot g \cdot (R + r) \cdot (1 - \cos(\theta)) = g \cdot (R + r) \cdot \cos(\theta)$  or  $2 \cdot (1 - \cos(\theta)) = \cos(\theta)$

Hence  $\theta = \arccos\left(\frac{2}{3}\right)$   $\theta = 48.2 \cdot \text{deg}$

Then from 1  $V = \sqrt{(R + r) \cdot g \cdot \cos(\theta)}$   $V = 0.577 \frac{\text{m}}{\text{s}}$

## Problem 4.4

[Difficulty: 2]

**4.4** A fully loaded Boeing 777-200 jet transport aircraft weighs 325,000 kg. The pilot brings the 2 engines to full takeoff thrust of 425 kN each before releasing the brakes. Neglecting aerodynamic and rolling resistance, estimate the minimum runway length and time needed to reach a takeoff speed of 225 kph. Assume engine thrust remains constant during ground roll.

**Given:** Data on Boeing 777-200 jet

**Find:** Minimum runway length for takeoff

**Solution:**

Basic equation  $\Sigma F_x = M \cdot \frac{dV}{dt} = M \cdot V \cdot \frac{dV}{dx} = F_t = \text{constant}$  Note that the "weight" is already in mass units!

Separating variables  $M \cdot V \cdot dV = F_t \cdot dx$

Integrating

$$x = \frac{M \cdot V^2}{2 \cdot F_t}$$

$$x = \frac{1}{2} \times 325 \times 10^3 \text{ kg} \times \left( 225 \frac{\text{km}}{\text{hr}} \times \frac{1 \cdot \text{km}}{1000 \cdot \text{m}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} \right)^2 \times \frac{1}{2 \times 425 \times 10^3 \text{ N}} \cdot \frac{1}{\text{kg} \cdot \text{m}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad x = 747 \text{ m}$$

For time calculation  $M \cdot \frac{dV}{dt} = F_t \quad dV = \frac{F_t}{M} \cdot dt$

Integrating

$$t = \frac{M \cdot V}{F_t}$$

$$t = 325 \times 10^3 \text{ kg} \times 225 \frac{\text{km}}{\text{hr}} \times \frac{1 \cdot \text{km}}{1000 \cdot \text{m}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} \times \frac{1}{2 \times 425 \times 10^3 \text{ N}} \cdot \frac{1}{\text{kg} \cdot \text{m}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad t = 23.9 \text{ s}$$

Aerodynamic and rolling resistances would significantly increase both these results

## Problem 4.5

[Difficulty: 2]

**4.5** A police investigation of tire marks showed that a car traveling along a straight and level street had skidded to a stop for a total distance of 200 ft after the brakes were applied. The coefficient of friction between tires and pavement is estimated to be  $\mu = 0.7$ . What was the probable minimum speed (mph) of the car when the brakes were applied? How long did the car skid?

**Given:** Car sliding to a stop

**Find:** Initial speed; skid time

**Solution:**

**Governing equations:**  $\Sigma F_x = M \cdot a_x$        $F_f = \mu \cdot W$

**Assumptions:** Dry friction; neglect air resistance

Given data       $L = 200 \cdot \text{ft}$        $\mu = 0.7$

$$\Sigma F_x = -F_f = -\mu \cdot W = M \cdot a_x = \frac{W}{g} \cdot a_x = \frac{W}{g} \cdot \frac{d^2}{dt^2}x$$

or

$$\frac{d^2}{dt^2}x = -\mu \cdot g$$

Integrating, and using I.C.  $V = V_0$  at  $t = 0$

Hence

$$\frac{dx}{dt} = -\mu \cdot g \cdot t + c_1 = -\mu \cdot g \cdot t + V_0 \quad (1)$$

Integrating again

$$x = -\frac{1}{2} \cdot g \cdot t^2 + V_0 \cdot t + c_2 = -\frac{1}{2} \cdot g \cdot t^2 + V_0 \cdot t \quad \text{since } x = 0 \text{ at } t = 0 \quad (2)$$

We have the final state, at which  $x_f = L$  and  $\frac{dx}{dt} = 0$  at  $t = t_f$

From Eq. 1

$$\frac{dx}{dt} = 0 = -\mu \cdot g \cdot t_f + V_0 \quad \text{so} \quad t_f = \frac{V_0}{\mu \cdot g}$$

Substituting into Eq. 2

$$x = x_f = L = -\frac{1}{2} \cdot g \cdot t_f^2 + V_0 \cdot t_f = -\frac{1}{2} \cdot g \cdot t_f^2 + V_0 \cdot t_f = -\frac{1}{2} \cdot g \cdot \left(\frac{V_0}{\mu \cdot g}\right)^2 + V_0 \cdot \frac{V_0}{\mu \cdot g} = \frac{V_0^2}{2 \cdot \mu \cdot g}$$

Solving

$$L = \frac{V_0^2}{2 \cdot \mu \cdot g} \quad \text{or} \quad V_0 = \sqrt{2 \cdot \mu \cdot g \cdot L}$$

Using the data

$$V_0 = 64.7 \cdot \text{mph} \quad \text{The skid time is} \quad t_f = \frac{V_0}{\mu \cdot g} \quad t_f = 4.21 \text{ s}$$

## Problem 4.6

[Difficulty: 2]

**4.6** A high school experiment consists of a block of mass 2 kg sliding across a surface (coefficient of friction  $\mu = 0.6$ ). If it is given an initial velocity of 5 m/s, how far will it slide, and how long will it take to come to rest? The surface is now roughened a little, so with the same initial speed it travels a distance of 2 m. What is the new coefficient of friction, and how long does it now slide?

**Given:** Block sliding to a stop

**Find:** Distance and time traveled; new coefficient of friction

**Solution:**

**Governing equations:**  $\Sigma F_x = M \cdot a_x$        $F_f = \mu \cdot W$

**Assumptions:** Dry friction; neglect air resistance

Given data                       $\mu = 0.6$                $V_0 = 5 \cdot \frac{\text{m}}{\text{s}}$                $M = 2 \cdot \text{kg}$                $L = 2 \cdot \text{m}$

$$\Sigma F_x = -F_f = -\mu \cdot W = M \cdot a_x = \frac{W}{g} \cdot a_x = \frac{W}{g} \cdot \frac{d^2}{dt^2}x \quad \text{or} \quad \frac{d^2}{dt^2}x = -\mu \cdot g$$

Integrating, and using I.C.  $V = V_0$  at  $t = 0$

Hence 
$$\frac{dx}{dt} = -\mu \cdot g \cdot t + c_1 = -\mu \cdot g \cdot t + V_0 \tag{1}$$

Integrating again 
$$x = -\frac{1}{2} \cdot g \cdot t^2 + V_0 \cdot t + c_2 = -\frac{1}{2} \cdot g \cdot t^2 + V_0 \cdot t \quad \text{since } x = 0 \text{ at } t = 0 \tag{2}$$

We have the final state, at which  $x_f = L$  and  $\frac{dx}{dt} = 0$  at  $t = t_f$

From Eq. 1 
$$\frac{dx}{dt} = 0 = -\mu \cdot g \cdot t_f + V_0 \quad \text{so} \quad t_f = \frac{V_0}{\mu \cdot g} \quad \text{Using given data} \quad t_f = 0.850 \text{ s}$$

Substituting into Eq. 2 
$$x = x_f = L = -\frac{1}{2} \cdot g \cdot t_f^2 + V_0 \cdot t_f = -\frac{1}{2} \cdot g \cdot t_f^2 + V_0 \cdot t_f = -\frac{1}{2} \cdot g \cdot \left(\frac{V_0}{\mu \cdot g}\right)^2 + V_0 \cdot \frac{V_0}{\mu \cdot g} = \frac{V_0^2}{2 \cdot \mu \cdot g}$$

Solving 
$$x = \frac{V_0^2}{2 \cdot \mu \cdot g} \tag{3} \quad \text{Using give data} \quad x = 2.12 \text{ m}$$

For rough surface, using Eq. 3 with  $x = L$  
$$\mu = \frac{V_0^2}{2 \cdot g \cdot L} \quad \mu = 0.637 \quad t_f = \frac{V_0}{\mu \cdot g} \quad t_f = 0.800 \text{ s}$$

## Problem 4.7

[Difficulty: 2]

**4.7** A car traveling at 30 mph encounters a curve in the road. The radius of the road curve is 100 ft. Find the maximum speeds (mph) before losing traction, if the coefficient of friction on a dry road is  $\mu_{\text{dry}} = 0.7$  and on a wet road is  $\mu_{\text{wet}} = 0.3$ .

**Given:** Car entering a curve

**Find:** Maximum speed

**Solution:**

**Governing equations:**  $\Sigma F_r = M \cdot a_r$        $F_f = \mu \cdot W$        $a_r = \frac{V^2}{r}$

**Assumptions:** Dry friction; neglect air resistance

Given data       $\mu_{\text{dry}} = 0.7$        $\mu_{\text{wet}} = 0.3$        $r = 100 \cdot \text{ft}$

$$\Sigma F_r = -F_f = -\mu \cdot W = -\mu \cdot M \cdot g = M \cdot a_x = M \cdot \frac{V^2}{r}$$

or       $V = \sqrt{\mu \cdot r \cdot g}$

Hence, using given data       $V = \sqrt{\mu_{\text{dry}} \cdot r \cdot g}$        $V = 32.4 \cdot \text{mph}$        $V = \sqrt{\mu_{\text{wet}} \cdot r \cdot g}$        $V = 21.2 \cdot \text{mph}$

## Problem 4.8

[Difficulty: 2]

**4.8** Air at 20°C and an absolute pressure of 1 atm is compressed adiabatically in a piston-cylinder device, without friction, to an absolute pressure of 4 atm in a piston-cylinder device. Find the work done (MJ).

**Given:** Data on air compression process

**Find:** Work done

**Solution:**

Basic equation  $\delta w = p \cdot dv$

Assumptions: 1) Adiabatic 2) Frictionless process  $\delta w = p dv$

Given data  $p_1 = 1 \cdot \text{atm}$   $p_2 = 4 \cdot \text{atm}$   $T_1 = 20^\circ\text{C}$   $T_1 = 293 \text{ K}$

From Table A.6  $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$  and  $k = 1.4$

Before integrating we need to relate  $p$  and  $v$ . An adiabatic frictionless (reversible) process is isentropic, which for an ideal gas gives

$$p \cdot v^k = C \quad \text{where} \quad k = \frac{c_p}{c_v}$$

$$\delta w = p \cdot dv = C \cdot v^{-k} \cdot dv$$

Integrating  $w = \frac{C}{k-1} \cdot (v_2^{1-k} - v_1^{1-k}) = \frac{1}{(k-1)} \cdot (p_2 \cdot v_2^k \cdot v_2^{1-k} - p_1 \cdot v_1^k \cdot v_1^{1-k})$

$$w = \frac{R}{(k-1)} \cdot (T_2 - T_1) = \frac{R \cdot T_1}{(k-1)} \cdot \left( \frac{T_2}{T_1} - 1 \right) \quad (1)$$

But  $p \cdot v^k = C$  means  $p_1 \cdot v_1^k = p_2 \cdot v_2^k$  or  $p_1 \cdot \left( \frac{R \cdot T_1}{p_1} \right)^k = p_2 \cdot \left( \frac{R \cdot T_2}{p_2} \right)^k$

Rearranging  $\frac{T_2}{T_1} = \left( \frac{p_2}{p_1} \right)^{\frac{k-1}{k}}$

Combining with Eq. 1  $w = \frac{R \cdot T_1}{k-1} \cdot \left[ \left( \frac{p_2}{p_1} \right)^{\frac{k-1}{k}} - 1 \right]$

$$w = \frac{1}{0.4} \times 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \times (20 + 273) \text{K} \times \left[ \left( \frac{4}{1} \right)^{\frac{1.4-1}{1.4}} - 1 \right] \quad w = 102 \frac{\text{kJ}}{\text{kg}}$$

## Problem 4.9

[Difficulty: 2]

**4.9** In an experiment with a can of soda, it took 2 hr to cool from an initial temperature of 80°F to 45°F in a 35°F refrigerator. If the can is now taken from the refrigerator and placed in a room at 72°F, how long will the can take to reach 60°F? You may assume that for both processes the heat transfer is modeled by  $\dot{Q} \approx k(T - T_{\text{amb}})$ , where  $T$  is the can temperature,  $T_{\text{amb}}$  is the ambient temperature, and  $k$  is a heat transfer coefficient.

**Given:** Data on cooling of a can of soda in a refrigerator

**Find:** How long it takes to warm up in a room

**Solution:**

The First Law of Thermodynamics for the can (either warming or cooling) is

$$M \cdot c \cdot \frac{dT}{dt} = -k \cdot (T - T_{\text{amb}}) \quad \text{or} \quad \frac{dT}{dt} = -k \cdot (T - T_{\text{amb}})$$

where  $M$  is the can mass,  $c$  is the average specific heat of the can and its contents,  $T$  is the temperature, and  $T_{\text{amb}}$  is the ambient temperature

Separating variables  $\frac{dT}{T - T_{\text{amb}}} = -A \cdot dt$

Integrating  $T(t) = T_{\text{amb}} + (T_{\text{init}} - T_{\text{amb}}) \cdot e^{-A t}$

where  $T_{\text{init}}$  is the initial temperature. The available data from the cooling can now be used to obtain a value for constant  $A$

Given data for cooling  $T_{\text{init}} = 80^\circ\text{F}$   $T_{\text{init}} = 540 \cdot \text{R}$   $T_{\text{amb}} = 35^\circ\text{F}$   $T_{\text{amb}} = 495 \cdot \text{R}$   
 $T = 45^\circ\text{F}$   $T = 505 \cdot \text{R}$  when  $\tau = 2 \cdot \text{hr}$

Hence  $k = \frac{1}{\tau} \cdot \ln\left(\frac{T_{\text{init}} - T_{\text{amb}}}{T - T_{\text{amb}}}\right) = \frac{1}{2 \cdot \text{hr}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} \times \ln\left(\frac{540 - 495}{505 - 495}\right)$   $k = 2.09 \times 10^{-4} \text{ s}^{-1}$

Then, for the warming up process

$T_{\text{init}} = 45^\circ\text{F}$   $T_{\text{init}} = 505 \cdot \text{R}$   $T_{\text{amb}} = 72^\circ\text{F}$   $T_{\text{amb}} = 532 \cdot \text{R}$   
 $T_{\text{end}} = 60^\circ\text{F}$   $T_{\text{end}} = 520 \cdot \text{R}$

with  $T_{\text{end}} = T_{\text{amb}} + (T_{\text{init}} - T_{\text{amb}}) \cdot e^{-k \tau}$

Hence the time  $\tau$  is  $\tau = \frac{1}{k} \cdot \ln\left(\frac{T_{\text{init}} - T_{\text{amb}}}{T_{\text{end}} - T_{\text{amb}}}\right) = \frac{\text{s}}{2.09 \cdot 10^{-4}} \cdot \ln\left(\frac{505 - 532}{520 - 532}\right)$   $\tau = 3.88 \times 10^3 \text{ s}$   $\tau = 1.08 \cdot \text{hr}$

## Problem 4.10

[Difficulty: 2]

**4.10** A block of copper of mass 5 kg is heated to 90°C and then plunged into an insulated container containing 4 L of water at 10°C. Find the final temperature of the system. For copper, the specific heat is 385 J/kg·K, and for water the specific heat is 4186 J/kg·K.

**Given:** Data on heating and cooling a copper block

**Find:** Final system temperature

**Solution:**

Basic equation  $Q - W = \Delta E$

Assumptions: 1) Stationary system  $\Delta E = \Delta U$  2) No work  $W = 0$  3) Adiabatic  $Q = 0$

Then for the system (water and copper)

$$\Delta U = 0 \quad \text{or} \quad M_{\text{copper}} \cdot c_{\text{copper}} \cdot T_{\text{copper}} + M_{\text{w}} \cdot c_{\text{w}} \cdot T_{\text{w}} = (M_{\text{copper}} \cdot c_{\text{copper}} + M_{\text{w}} \cdot c_{\text{w}}) \cdot T_{\text{f}} \quad (1)$$

where  $T_{\text{f}}$  is the final temperature of the water (<sub>w</sub>) and copper (<sub>copper</sub>)

The given data is  $M_{\text{copper}} = 5 \cdot \text{kg}$        $c_{\text{copper}} = 385 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $c_{\text{w}} = 4186 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $V = 4 \cdot \text{L}$

$$T_{\text{copper}} = (90 + 273) \cdot \text{K} \quad \quad \quad T_{\text{w}} = (10 + 273) \cdot \text{K}$$

Also, for the water  $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$       so       $M_{\text{w}} = \rho \cdot V$        $M_{\text{w}} = 4.00 \text{ kg}$

Solving Eq. 1 for  $T_{\text{f}}$

$$T_{\text{f}} = \frac{M_{\text{copper}} \cdot c_{\text{copper}} \cdot T_{\text{copper}} + M_{\text{w}} \cdot c_{\text{w}} \cdot T_{\text{w}}}{(M_{\text{copper}} \cdot c_{\text{copper}} + M_{\text{w}} \cdot c_{\text{w}})}$$

$$T_{\text{f}} = 291 \text{ K} \quad \quad \quad T_{\text{f}} = 18.1 \cdot ^\circ\text{C}$$

## Problem 4.11

[Difficulty: 2]

**4.11** The average rate of heat loss from a person to the surroundings when not actively working is about 85 W. Suppose that in an auditorium with volume of approximately  $3.5 \times 10^5 \text{ m}^3$ , containing 6000 people, the ventilation system fails. How much does the internal energy of the air in the auditorium increase during the first 15 min after the ventilation system fails? Considering the auditorium and people as a system, and assuming no heat transfer to the surroundings, how much does the internal energy of the system change? How do you account for the fact that the temperature of the air increases? Estimate the rate of temperature rise under these conditions.

**Given:** Data on heat loss from persons, and people-filled auditorium

**Find:** Internal energy change of air and of system; air temperature rise

**Solution:**

Basic equation  $Q - W = \Delta E$

Assumptions: 1) Stationary system  $\Delta E = \Delta U$  2) No work  $W = 0$

Then for the air 
$$\Delta U = Q = 85 \cdot \frac{\text{W}}{\text{person}} \times 6000 \cdot \text{people} \times 15 \cdot \text{min} \times \frac{60 \cdot \text{s}}{\text{min}} \quad \Delta U = 459 \cdot \text{MJ}$$

For the air and people  $\Delta U = Q_{\text{surroundings}} = 0$

The increase in air energy is equal and opposite to the loss in people energy

For the air  $\Delta U = Q$  but for air (an ideal gas)  $\Delta U = M \cdot c_v \cdot \Delta T$  with  $M = \rho \cdot V = \frac{p \cdot V}{R_{\text{air}} \cdot T}$

Hence 
$$\Delta T = \frac{Q}{M \cdot c_v} = \frac{R_{\text{air}} \cdot Q \cdot T}{c_v \cdot p \cdot V}$$

From Table A.6  $R_{\text{air}} = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$  and  $c_v = 717.4 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$


$$\Delta T = \frac{286.9}{717.4} \times 459 \times 10^6 \cdot \text{J} \times (20 + 273) \text{K} \times \frac{1}{101 \times 10^3} \cdot \frac{\text{m}^2}{\text{N}} \times \frac{1}{3.5 \times 10^5} \cdot \frac{1}{\text{m}^3} \Delta T = 1.521 \text{ K}$$

This is the temperature change in 15 min. The rate of change is then  $\frac{\Delta T}{15 \cdot \text{min}} = 6.09 \cdot \frac{\text{K}}{\text{hr}}$

## Problem 4.12

[Difficulty: 3]

**4.12** The velocity field in the region shown is given by  $\vec{V} = (aj + by\hat{k})$  where  $a = 10\text{m/s}$  and  $b = 5\text{s}^{-1}$ . For the  $1\text{m} \times 1\text{m}$  triangular control volume (depth  $w = 1\text{m}$  perpendicular to the diagram), an element of area ① may be represented by  $d\vec{A}_1 = wdz\hat{j} - wdy\hat{k}$  and an element of area ② by  $d\vec{A}_2 = -wdy\hat{k}$ .



- (a) Find an expression for  $\vec{V} \cdot dA_1$ .
- (b) Evaluate  $\int_{A_1} \vec{V} \cdot dA_1$ .
- (c) Find an expression for  $\vec{V} \cdot dA_2$ .
- (d) Find an expression for  $\vec{V}(\vec{V} \cdot dA_2)$ .
- (e) Evaluate  $\int_{A_2} \vec{V}(\vec{V} \cdot dA_2)$ .

**Given:** Data on velocity field and control volume geometry

**Find:** Several surface integrals

**Solution:**

$$d\vec{A}_1 = wdz\hat{j} - wdy\hat{k}$$


$$d\vec{A}_1 = dz\hat{j} - dy\hat{k}$$

$$d\vec{A}_2 = -wdy\hat{k}$$

$$d\vec{A}_2 = -dy\hat{k}$$

$$\vec{V} = (a\hat{j} + by\hat{k})$$

$$\vec{V} = (10\hat{j} + 5y\hat{k})$$



$$(a) \quad \vec{V} \cdot dA_1 = (10\hat{j} + 5y\hat{k}) \cdot (dz\hat{j} - dy\hat{k}) = 10dz - 5ydy$$

$$(b) \quad \int_{A_1} \vec{V} \cdot dA_1 = \int_0^1 10dz - \int_0^1 5ydy = 10z \Big|_0^1 - \frac{5}{2}y^2 \Big|_0^1 = 7.5$$

$$(c) \quad \vec{V} \cdot dA_2 = (10\hat{j} + 5y\hat{k}) \cdot (-dy\hat{k}) = -5ydy$$

$$(d) \quad \vec{V}(\vec{V} \cdot dA_2) = -(10\hat{j} + 5y\hat{k})5ydy$$

$$(e) \quad \int_{A_2} \vec{V}(\vec{V} \cdot dA_2) = -\int_0^1 (10\hat{j} + 5y\hat{k})5ydy = -25y^2\hat{j} \Big|_0^1 - \frac{25}{3}y^3\hat{k} \Big|_0^1 = -25\hat{j} - 8.33\hat{k}$$

## Problem 4.13

[Difficulty: 3]

**4.13** The shaded area shown is in a flow where the velocity field is given by  $\vec{V} = ax\hat{i} + by\hat{j}$ ;  $a = b = 1 \text{ s}^{-1}$ , and the coordinates are measured in meters. Evaluate the volume flow rate and the momentum flux through the shaded area ( $\rho = 1 \text{ kg/m}^3$ ).

**Given:** Data on velocity field and control volume geometry


**Find:** Volume flow rate and momentum flux

**Solution:**

First we define the area and velocity vectors

$$d\vec{A} = dydz\hat{i} + dxdy\hat{k}$$

$$\vec{V} = ax\hat{i} + by\hat{j} \quad \text{or} \quad \vec{V} = x\hat{i} + y\hat{j}$$



We will need the equation of the surface:  $z = 3 - \frac{3}{4}x$  or  $x = 4 - \frac{4}{3}z$

Then

a) Volume flow rate

$$Q = \int_A \vec{V} \cdot d\vec{A} = \int_A (x\hat{i} + y\hat{j}) \cdot (dydz\hat{i} + dxdy\hat{k}) = \int_0^3 \int_0^5 x dy dz = 5 \int_0^3 \left(4 - \frac{4}{3}z\right) dz = 5 \left(4z - \frac{2}{3}z^2\right) \Big|_0^3$$

$$Q = (60 - 30) \frac{\text{m}^3}{\text{s}} = 30 \frac{\text{m}^3}{\text{s}}$$

b) Momentum flux

$$\begin{aligned} \rho \int_A \vec{V} (\vec{V} \cdot d\vec{A}) &= \rho \int_A (x\hat{i} + y\hat{j})(x\hat{i} + y\hat{j}) \cdot (dydz\hat{i} + dxdy\hat{k}) = \rho \int_A (x\hat{i} + y\hat{j})(xdydz) \\ &= \rho \int_0^3 \int_0^5 x^2 dy dz \hat{i} + \rho \int_0^3 \int_0^5 xy dy dz \hat{j} = 5 \int_0^3 \left(4 - \frac{4}{3}z\right)^2 dz \hat{i} + \frac{y^2}{2} \Big|_0^5 \int_0^3 \left(4 - \frac{4}{3}z\right) dz \hat{j} \\ &= 5 \int_0^3 \left(16 - \frac{32}{3}z + \frac{16}{9}z^2\right) dz \hat{i} + \frac{25}{2} \left(4z - \frac{2}{3}z^2\right) \Big|_0^3 \hat{j} = 5 \left(16z - \frac{16}{3}z^2 + \frac{16}{27}z^3\right) \Big|_0^3 \hat{i} + \frac{25}{2}(12 - 6) \hat{j} \\ &= 5(48 - 48 + 16) \hat{i} + 75 \hat{j} \end{aligned}$$

Momentum flux =  $80\hat{i} + 75\hat{j}$  N

## Problem 4.14

[Difficulty: 3]

**4.14** The area shown shaded is in a flow where the velocity field is given by  $\vec{V} = ax\hat{i} + by\hat{j} + c\hat{k}$ ;  $a = b = 2 \text{ s}^{-1}$  and  $c = 1 \text{ m/s}$ . Write a vector expression for an element of the shaded area. Evaluate the integrals  $\int_A \vec{V} \cdot d\vec{A}$  and  $\int_A \vec{V}(\vec{V} \cdot d\vec{A})$  over the shaded area.

**Given:** Data on velocity field and control volume geometry

**Find:** Surface integrals

**Solution:**

First we define the area and velocity vectors

$$d\vec{A} = dydz\hat{i} + dx dz\hat{j} \quad \vec{V} = ax\hat{i} + by\hat{j} + c\hat{k} \quad \text{or} \quad \vec{V} = 2x\hat{i} + 2y\hat{j} + \hat{k}$$


We will need the equation of the surface:  $y = \frac{3}{2}x$  or  $x = \frac{2}{3}y$

Then

$$\begin{aligned} \int_A \vec{V} \cdot d\vec{A} &= \int_A (-ax\hat{i} + by\hat{j} + c\hat{k}) \cdot (dydz\hat{i} - dx dz\hat{j}) \\ &= \int_0^2 \int_0^3 -ax dy dz - \int_0^2 \int_0^2 by dx dz = -a \int_0^2 dz \int_0^{\frac{2}{3}y} y dy - b \int_0^2 dz \int_0^{\frac{3}{2}x} x dx = -2a \frac{1}{3} y^2 \Big|_0^3 - 2b \frac{3}{4} x^2 \Big|_0^2 \\ Q &= (-6a - 6b) = -24 \frac{\text{m}^3}{\text{s}} \end{aligned}$$

We will again need the equation of the surface:  $y = \frac{3}{2}x$  or  $x = \frac{2}{3}y$ , and also  $dy = \frac{3}{2}dx$  and  $a = b$


$$\begin{aligned} \int_A \vec{V}(\vec{V} \cdot d\vec{A}) &= \int_A (-ax\hat{i} + by\hat{j} + c\hat{k})(-ax\hat{i} + by\hat{j} + c\hat{k}) \cdot (dydz\hat{i} - dx dz\hat{j}) \\ &= \int_A (-ax\hat{i} + by\hat{j} + c\hat{k})(-ax dy dz - by dx dz) \\ &= \int_A \left(-ax\hat{i} + \frac{3}{2}ax\hat{j} + c\hat{k}\right) \left(-ax \frac{3}{2} dx dz - a \frac{3}{2} x dx dz\right) \\ &= \int_A \left(-ax\hat{i} + \frac{3}{2}ax\hat{j} + c\hat{k}\right) (-3ax dx dz) \\ &= 3 \int_0^2 \int_0^2 a^2 x^2 dx dz \hat{i} - \frac{9}{2} \int_0^2 \int_0^2 a^2 x^2 dx dz \hat{j} - 3 \int_0^2 \int_0^2 ac x dx dz \hat{k} \\ &= (6) \left( a^2 \frac{x^3}{3} \Big|_0^2 \right) \hat{i} - (9) \left( a^2 \frac{x^3}{3} \Big|_0^2 \right) \hat{j} - (6) \left( ac \frac{x^2}{2} \Big|_0^2 \right) = 16a^2 \hat{i} - 24a^2 \hat{j} - 12ac \hat{k} \\ &= 64\hat{i} - 96\hat{j} - 60\hat{k} \quad \frac{\text{m}^4}{\text{s}^2} \end{aligned}$$



## Problem 4.15

[Difficulty: 2]

**4.15** Obtain expressions for the volume flow rate and the momentum flux through cross section ① of the control volume shown in the diagram.



**Given:** Control Volume with linear velocity distribution

**Find:** Volume flow rate and momentum flux

**Solution:** Apply the expressions for volume and momentum flux

**Governing equations:**  $Q = \int_A \vec{V} \cdot d\vec{A}$        $mf = \rho \int_A \vec{V} (\vec{V} \cdot d\vec{A})$

**Assumption:** (1) Incompressible flow

For a linear velocity profile  $\vec{V} = \frac{V}{h} y \hat{i}$       and also  $d\vec{A} = -w dy \hat{i}$

For the volume flow rate:

$$Q = \int_{y=0}^h \frac{V}{h} \hat{i} \cdot (-w dy \hat{i}) = -\frac{Vw}{h} \int_{y=0}^h y dy = -\frac{Vw}{h} \frac{y^2}{2} \Big|_0^h$$

$$Q = -\frac{1}{2} Vhw$$

The momentum flux is


$$mf = \int_{y=0}^h \frac{V}{h} \hat{i} \cdot \left( -\rho \frac{Vw}{h} y dy \right) = -\rho \frac{V^2 w}{h^2} \hat{i} \int_{y=0}^h y^2 dy = -\rho \frac{V^2 w}{h^2} \hat{i} \frac{y^3}{3} \Big|_0^h$$

$$mf = -\frac{1}{3} \rho V^2 wh \hat{i}$$

## Problem 4.16

[Difficulty: 2]

**4.16** For the flow of Problem 4.15, obtain an expression for the kinetic energy flux,  $\int (V^2/2)\rho\vec{V} \cdot d\vec{A}$ , through cross section ① of the control volume shown.



**Given:** Control Volume with linear velocity distribution

**Find:** Kinetic energy flux

**Solution:** Apply the expression for kinetic energy flux

**Governing equation:**  $kef = \int_A \frac{V^2}{2} \rho \vec{V} \cdot d\vec{A}$

**Assumption:** (1) Incompressible flow

For a linear velocity profile  $\vec{V} = \frac{V}{h} y \hat{i}$   $V(y) = \frac{V}{h} y$  and also  $d\vec{A} = -w dy \hat{i}$

The kinetic energy flux is

$$kef = \int_{y=0}^h \frac{1}{2} \left( \frac{V}{h} y \right)^2 \left( -\rho \frac{Vw}{h} y dy \right) = -\rho \frac{V^3 w}{2h^3} \int_{y=0}^h y^3 dy = -\rho \frac{V^3 w}{2h^3} \frac{y^4}{4} \Big|_0^h$$

$$kef = -\frac{1}{8} \rho V^3 w h$$

## Problem 4.17

[Difficulty: 2]

**4.17** The velocity distribution for laminar flow in a long circular tube of radius  $R$  is given by the one-dimensional expression,

$$\vec{V} = u\hat{i} = u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i}$$

For this profile obtain expressions for the volume flow rate and the momentum flux through a section normal to the pipe axis.

**Given:** Control Volume with parabolic velocity distribution

**Find:** Volume flow rate and momentum flux

**Solution:** Apply the expressions for volume and momentum flux

**Governing equations:**  $Q = \int_A \vec{V} \cdot d\vec{A}$        $mf = \rho \int_A \vec{V} (\vec{V} \cdot d\vec{A})$

**Assumption:** (1) Incompressible flow

For a linear velocity profile  $\vec{V} = u\hat{i} = u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i}$  and also  $d\vec{A} = 2\pi r dr \hat{i}$

For the volume flow rate:

$$Q = \int_{r=0}^R u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i} \cdot (2\pi r dr \hat{i}) = 2\pi u_{\max} \int_{y=0}^R \left[ r - \frac{r^3}{R^2} \right] dy = 2\pi u_{\max} \left[ \frac{r^2}{2} - \frac{r^4}{4R^2} \right]_0^R = 2\pi u_{\max} \left[ \frac{R^2}{2} - \frac{R^2}{4} \right]$$

$$Q = \frac{1}{2} \pi u_{\max} R^2$$

The momentum flux is

$$\begin{aligned} mf &= \int_{r=0}^R u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i} \left\{ u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i} \cdot (2\pi r dr \hat{i}) \right\} = u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i} \left\{ 2\pi u_{\max} \int_{y=0}^R \left[ r - \frac{r^3}{R^2} \right] dr \right\} \\ &= 2\pi u_{\max}^2 \hat{i} \int_{y=0}^R \left[ r - \frac{2r^3}{R^2} + \frac{r^5}{R^4} \right] dr \\ &= 2\pi u_{\max}^2 \hat{i} \left[ \frac{r^2}{2} - \frac{r^4}{4R^2} + \frac{r^6}{6R^4} \right]_0^R \\ &= 2\pi u_{\max}^2 \hat{i} \left[ \frac{R^2}{2} - \frac{R^2}{4} + \frac{R^2}{6} \right] \end{aligned}$$

$$mf = \frac{1}{3} \pi u_{\max}^2 R^2 \hat{i}$$

## Problem 4.18

[Difficulty: 2]

**4.18** For the flow of Problem 4.17, obtain an expression for the kinetic energy flux,  $\int (V^2/2)\rho\vec{V} \cdot d\vec{A}$ , through a section normal to the pipe axis.

**Given:** Control Volume with parabolic velocity distribution

**Find:** Kinetic energy flux

**Solution:** Apply the expressions for kinetic energy flux

**Governing equation:**  $kef = \int_A \frac{V^2}{2} \rho \vec{V} \cdot d\vec{A}$

**Assumption:** (1) Incompressible flow

For a linear velocity profile  $\vec{V} = u\hat{i} = u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i}$   $V = u = u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right]$  and also  $d\vec{A} = 2\pi r dr \hat{i}$

For the volume flow rate:

$$\begin{aligned} kef &= \int_{r=0}^R \frac{1}{2} \left\{ u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \right\}^2 \rho \left\{ u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \hat{i} \cdot (2\pi r dr \hat{i}) \right\} \\ &= \int_{r=0}^R \frac{1}{2} u_{\max}^2 \left[ 1 - 2 \left( \frac{r}{R} \right)^2 + \left( \frac{r}{R} \right)^4 \right] \rho \left\{ 2\pi u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] r dr \right\} \\ &= \int_{r=0}^R \pi \rho u_{\max}^3 \left[ 1 - 3 \left( \frac{r}{R} \right)^2 + 3 \left( \frac{r}{R} \right)^4 - \left( \frac{r}{R} \right)^6 \right] r dr \\ &= \int_{r=0}^R \pi \rho u_{\max}^3 \left[ r - 3 \frac{r^3}{R^2} + 3 \frac{r^5}{R^4} - \frac{r^7}{R^6} \right] dr \\ &= \pi \rho u_{\max}^3 \left[ \frac{r^2}{2} - \frac{3r^4}{4R^2} + \frac{r^6}{2R^4} - \frac{r^8}{8R^6} \right]_0^R \end{aligned}$$

$$kef = \frac{1}{8} \pi \rho u_{\max}^3 R^2$$

## Problem 4.19

[Difficulty: 1]

**4.19** A shower head fed by a  $\frac{3}{4}$ -in. ID water pipe consists of 50 nozzles of  $\frac{1}{32}$ -in. ID. Assuming a flow rate of 2.2 gpm, what is the exit velocity (ft/s) of each jet of water? What is the average velocity (ft/s) in the pipe?

**Given:** Data on flow through nozzles

**Find:** Exit velocity in each jet; velocity in pipe

**Solution:**

Basic equation 
$$\sum_{CS} (\vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

The given data is  $Q = 2.2 \cdot \text{gpm}$        $d = \frac{1}{32} \cdot \text{in}$        $n = 50$       (Number of nozzles)       $D = \frac{3}{4} \cdot \text{in}$

Area of each nozzle  $A = \frac{\pi}{4} \cdot d^2$        $A = 7.67 \times 10^{-4} \text{in}^2$

Area of the pipe  $A_{\text{pipe}} = \frac{\pi}{4} \cdot D^2$        $A_{\text{pipe}} = 0.442 \text{in}^2$

Total area of nozzles  $A_{\text{total}} = n \cdot A$        $A_{\text{total}} = 0.0383 \text{in}^2$

The jet speeds are then  $V = \frac{Q}{A_{\text{total}}}$        $V = 18.4 \frac{\text{ft}}{\text{s}}$       (Note that gal = 231 in<sup>3</sup>)

Then for the pipe flow 
$$\sum_{CS} (\vec{V} \cdot \vec{A}) = -V_{\text{pipe}} \cdot A_{\text{pipe}} + n \cdot V \cdot A = 0$$

Hence 
$$V_{\text{pipe}} = V \cdot \frac{n \cdot A}{A_{\text{pipe}}} = V \cdot n \cdot \left(\frac{d}{D}\right)^2$$

$$V_{\text{pipe}} = 18.4 \cdot \frac{\text{ft}}{\text{s}} \times 50 \times \left(\frac{\frac{1}{32}}{\frac{3}{4}}\right)^2 \qquad V_{\text{pipe}} = 1.60 \cdot \frac{\text{ft}}{\text{s}}$$

## Problem 4.20

[Difficulty: 1]

**4.20** A farmer is spraying a liquid through 10 nozzles,  $\frac{1}{8}$ -in. ID, at an average exit velocity of 10 ft/s. What is the average velocity in the 1-in. ID head feeder? What is the system flow rate, in gpm?

**Given:** Data on flow through nozzles

**Find:** Average velocity in head feeder; flow rate

**Solution:**

Basic equation 
$$\sum_{CS} (\vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

Then for the nozzle flow 
$$\sum_{CS} (\vec{V} \cdot \vec{A}) = -V_{\text{feeder}} \cdot A_{\text{feeder}} + 10 \cdot V_{\text{nozzle}} \cdot A_{\text{nozzle}} = 0$$

Hence 
$$V_{\text{feeder}} = V_{\text{nozzle}} \cdot \frac{10 \cdot A_{\text{nozzle}}}{A_{\text{feeder}}} = V_{\text{nozzle}} \cdot 10 \cdot \left( \frac{D_{\text{nozzle}}}{D_{\text{feeder}}} \right)^2$$

$$V_{\text{feeder}} = 10 \cdot \frac{\text{ft}}{\text{s}} \times 10 \times \left( \frac{1}{8} \right)^2$$

$$V_{\text{feeder}} = 1.56 \cdot \frac{\text{ft}}{\text{s}}$$

The flow rate is 
$$Q = V_{\text{feeder}} \cdot A_{\text{feeder}} = V_{\text{feeder}} \cdot \frac{\pi \cdot D_{\text{feeder}}^2}{4}$$

$$Q = 1.56 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} \times \left( 1 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \times \frac{7.48 \cdot \text{gal}}{1 \cdot \text{ft}^3} \times \frac{60 \cdot \text{s}}{1 \cdot \text{min}}$$

$$Q = 3.82 \cdot \text{gpm}$$

## Problem 4.21

[Difficulty: 3]

**4.21** A cylindrical holding water tank has a 3 m ID and a height of 3 m. There is one inlet of diameter 10 cm, an exit of diameter 8 cm, and a drain. The tank is initially empty when the inlet pump is turned on, producing an average inlet velocity of 5 m/s. When the level in the tank reaches 0.7 m, the exit pump turns on, causing flow out of the exit; the exit average velocity is 3 m/s. When the water level reaches 2 m the drain is opened such that the level remains at 2 m. Find (a) the time at which the exit pump is switched on, (b) the time at which the drain is opened, and (c) the flow rate into the drain ( $\text{m}^3/\text{min}$ ).

**Given:** Data on flow into and out of tank

**Find:** Time at which exit pump is switched on; time at which drain is opened; flow rate into drain

**Solution:**

Basic equation 
$$\frac{\partial}{\partial t} M_{CV} + \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Uniform flow 2) Incompressible flow

After inlet pump is on 
$$\frac{\partial}{\partial t} M_{CV} + \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = \frac{\partial}{\partial t} M_{\text{tank}} - \rho \cdot V_{\text{in}} \cdot A_{\text{in}} = 0 \quad \frac{\partial}{\partial t} M_{\text{tank}} = \rho \cdot A_{\text{tank}} \cdot \frac{dh}{dt} = \rho \cdot V_{\text{in}} \cdot A_{\text{in}}$$

$$\frac{dh}{dt} = V_{\text{in}} \cdot \frac{A_{\text{in}}}{A_{\text{tank}}} = V_{\text{in}} \cdot \left( \frac{D_{\text{in}}}{D_{\text{tank}}} \right)^2 \quad \text{where } h \text{ is the level of water in the tank}$$

Hence the time to reach  $h_{\text{exit}} = 0.7 \text{ m}$  is 
$$t_{\text{exit}} = \frac{h_{\text{exit}}}{\frac{dh}{dt}} = \frac{h_{\text{exit}}}{V_{\text{in}} \cdot \left( \frac{D_{\text{in}}}{D_{\text{tank}}} \right)^2} \quad t_{\text{exit}} = 0.7 \cdot \text{m} \times \frac{1}{5 \cdot \frac{\text{s}}{\text{m}}} \times \left( \frac{3 \cdot \text{m}}{0.1 \cdot \text{m}} \right)^2 \quad t_{\text{exit}} = 126 \text{ s}$$

After exit pump is on 
$$\frac{\partial}{\partial t} M_{CV} + \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = \frac{\partial}{\partial t} M_{\text{tank}} - \rho \cdot V_{\text{in}} \cdot A_{\text{in}} + \rho \cdot V_{\text{exit}} \cdot A_{\text{exit}} = 0 \quad A_{\text{tank}} \cdot \frac{dh}{dt} = V_{\text{in}} \cdot A_{\text{in}} - V_{\text{exit}} \cdot A_{\text{exit}}$$

$$\frac{dh}{dt} = V_{\text{in}} \cdot \frac{A_{\text{in}}}{A_{\text{tank}}} - V_{\text{exit}} \cdot \frac{A_{\text{exit}}}{A_{\text{tank}}} = V_{\text{in}} \cdot \left( \frac{D_{\text{in}}}{D_{\text{tank}}} \right)^2 - V_{\text{exit}} \cdot \left( \frac{D_{\text{exit}}}{D_{\text{tank}}} \right)^2$$

Hence the time to reach  $h_{\text{drain}} = 2 \text{ m}$  is 
$$t_{\text{drain}} = t_{\text{exit}} + \frac{(h_{\text{drain}} - h_{\text{exit}})}{\frac{dh}{dt}} = \frac{(h_{\text{drain}} - h_{\text{exit}})}{V_{\text{in}} \cdot \left( \frac{D_{\text{in}}}{D_{\text{tank}}} \right)^2 - V_{\text{exit}} \cdot \left( \frac{D_{\text{exit}}}{D_{\text{tank}}} \right)^2}$$

$$t_{\text{drain}} = 126 \cdot \text{s} + (2 - 0.7) \cdot \text{m} \times \frac{1}{5 \cdot \frac{\text{m}}{\text{s}} \times \left( \frac{0.1 \cdot \text{m}}{3 \cdot \text{m}} \right)^2 - 3 \cdot \frac{\text{m}}{\text{s}} \times \left( \frac{0.08 \cdot \text{m}}{3 \cdot \text{m}} \right)^2} \quad t_{\text{drain}} = 506 \text{ s}$$

The flow rate into the drain is equal to the net inflow (the level in the tank is now constant)

$$Q_{\text{drain}} = V_{\text{in}} \cdot \frac{\pi \cdot D_{\text{in}}^2}{4} - V_{\text{exit}} \cdot \frac{\pi \cdot D_{\text{exit}}^2}{4} \quad Q_{\text{drain}} = 5 \cdot \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.1 \cdot \text{m})^2 - 3 \cdot \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.08 \cdot \text{m})^2 \quad Q_{\text{drain}} = 0.0242 \frac{\text{m}^3}{\text{s}}$$

## Problem 4.22

[Difficulty: 1]

**4.22** A university laboratory that generates  $15 \text{ m}^3/\text{s}$  of air flow at design condition wishes to build a wind tunnel with variable speeds. It is proposed to build the tunnel with a sequence of three circular test sections: section 1 will have a diameter of 1.5 m, section 2 a diameter of 1 m, and section 3 a diameter such that the average speed is 75 m/s.

- (a) What will be the speeds in sections 1 and 2?  
(b) What must the diameter of section 3 be to attain the desired speed at design condition?

**Given:** Data on wind tunnel geometry

**Find:** Average speeds in wind tunnel; diameter of section 3

**Solution:**

Basic equation  $Q = V \cdot A$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

Given data:  $Q = 15 \cdot \frac{\text{m}^3}{\text{s}}$   $D_1 = 1.5 \text{ m}$   $D_2 = 1 \text{ m}$   $V_3 = 75 \cdot \frac{\text{m}}{\text{s}}$

Between sections 1 and 2  $Q = V_1 \cdot A_1 = V_1 \cdot \frac{\pi \cdot D_1^2}{4} = V_2 \cdot A_2 = V_2 \cdot \frac{\pi \cdot D_2^2}{4}$


Hence  $V_1 = \frac{Q}{\frac{\pi \cdot D_1^2}{4}}$   $V_1 = 8.49 \frac{\text{m}}{\text{s}}$   $V_2 = \frac{Q}{\frac{\pi \cdot D_2^2}{4}}$   $V_2 = 19.1 \frac{\text{m}}{\text{s}}$

For section 3 we can use  $V_1 \cdot \frac{\pi \cdot D_1^2}{4} = V_3 \cdot \frac{\pi \cdot D_3^2}{4}$  or  $D_3 = D_1 \cdot \sqrt{\frac{V_1}{V_3}}$   $D_3 = 0.505 \text{ m}$

## Problem 4.23

Difficulty: 4]

**4.23** A wet cooling tower cools warm water by spraying it into a forced dry-air flow. Some of the water evaporates in this air and is carried out of the tower into the atmosphere; the evaporation cools the remaining water droplets, which are collected at the exit pipe (6 in. ID) of the tower. Measurements indicate the warm water mass flow rate is 250,000 lb/hr, and the cool water (70°F) flows at an average speed of 5 ft/s in the exit pipe. The moist air density is 0.065 lb/ft<sup>3</sup>. Find (a) the volume flow rate (ft<sup>3</sup>/s) and mass flow rate (lb/hr) of the cool water, (b) the mass flow rate (lb/hr) of the moist air, and (c) the mass flow rate (lb/hr) of the dry air. *Hint:* Google “density of moist air” for information on relating moist and dry air densities!



**Given:** Data on flow into and out of cooling tower

**Find:** Volume and mass flow rate of cool water; mass flow rate of moist and dry air

**Solution:**

Basic equation  $\sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = 0$  and at each inlet/exit  $Q = V \cdot A$

Assumptions: 1) Uniform flow 2) Incompressible flow

Given data:  $m_{\text{warm}} = 2.5 \cdot 10^5 \cdot \frac{\text{lb}}{\text{hr}}$        $D = 6 \cdot \text{in}$        $V = 5 \cdot \frac{\text{ft}}{\text{s}}$        $\rho_{\text{moist}} = 0.065 \cdot \frac{\text{lb}}{\text{ft}^3}$

At the cool water exit  $Q_{\text{cool}} = V \cdot A$        $Q_{\text{cool}} = 5 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} \times (0.5 \cdot \text{ft})^2$        $Q_{\text{cool}} = 0.982 \cdot \frac{\text{ft}^3}{\text{s}}$        $Q_{\text{cool}} = 441 \cdot \text{gpm}$

The mass flow rate is  $m_{\text{cool}} = \rho \cdot Q_{\text{cool}}$        $m_{\text{cool}} = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 0.982 \cdot \frac{\text{ft}^3}{\text{s}}$        $m_{\text{cool}} = 1.91 \cdot \frac{\text{slug}}{\text{s}}$        $m_{\text{cool}} = 2.21 \times 10^5 \cdot \frac{\text{lb}}{\text{hr}}$

NOTE: Software does not allow dots over terms, so m represents mass flow rate, not mass!

For the water flow we need  $\sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = 0$  to balance the water flow

We have  $-m_{\text{warm}} + m_{\text{cool}} + m_v = 0$        $m_v = m_{\text{warm}} - m_{\text{cool}}$        $m_v = 29341 \cdot \frac{\text{lb}}{\text{hr}}$

This is the mass flow rate of water vapor. To obtain air flow rates, from psychrometrics  $x = \frac{m_v}{m_{\text{air}}}$

where x is the relative humidity. It is also known (try Googling "density of moist air") that  $\frac{\rho_{\text{moist}}}{\rho_{\text{dry}}} = \frac{1 + x}{1 + x \cdot \frac{R_{\text{H}_2\text{O}}}{R_{\text{air}}}}$

We are given  $\rho_{\text{moist}} = 0.065 \cdot \frac{\text{lb}}{\text{ft}^3}$

For dry air we could use the ideal gas equation

$\rho_{\text{dry}} = \frac{p}{R \cdot T}$  but here we use atmospheric air density (Table A.3)

$$\rho_{\text{dry}} = 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3}$$

$$\rho_{\text{dry}} = 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{lb}}{\text{slug}}$$

$$\rho_{\text{dry}} = 0.0765 \cdot \frac{\text{lb}}{\text{ft}^3}$$

Note that moist air is less dense than dry air!

Hence 
$$\frac{0.065}{0.0765} = \frac{1 + x}{1 + x \cdot \frac{85.78}{53.33}}$$

using data from Table A.6

$$x = \frac{0.0765 - 0.065}{0.065 \cdot \frac{85.78}{53.33} - 0.0765}$$

$$x = 0.410$$

Hence 
$$\frac{m_v}{m_{\text{air}}} = x$$
 leads to

$$m_{\text{air}} = \frac{m_v}{x}$$

$$m_{\text{air}} = 29341 \cdot \frac{\text{lb}}{\text{hr}} \times \frac{1}{0.41}$$

$$m_{\text{air}} = 71563 \cdot \frac{\text{lb}}{\text{hr}}$$


Finally, the mass flow rate of moist air is

$$m_{\text{moist}} = m_v + m_{\text{air}} \quad m_{\text{moist}} = 1.01 \times 10^5 \cdot \frac{\text{lb}}{\text{hr}}$$

## Problem 4.24

[Difficulty: 1]

**4.24** Fluid with  $65 \text{ lbm/ft}^3$  density is flowing steadily through the rectangular box shown. Given  $A_1 = 0.5 \text{ ft}^2$ ,  $A_2 = 0.1 \text{ ft}^2$ ,  $A_3 = 0.6 \text{ ft}^2$ ,  $\vec{V}_1 = 10 \hat{i} \text{ ft/s}$ , and  $\vec{V}_2 = 20 \hat{j} \text{ ft/s}$ , determine velocity  $\vec{V}_3$ .



**Given:** Data on flow through box

**Find:** Velocity at station 3

**Solution:**

Basic equation 
$$\sum_{\text{CS}} (\vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

Then for the box 
$$\sum_{\text{CS}} (\vec{V} \cdot \vec{A}) = -V_1 \cdot A_1 + V_2 \cdot A_2 + V_3 \cdot A_3 = 0$$

Note that the vectors indicate that flow is in at location 1 and out at location 2; we assume outflow at location 3

Hence 
$$V_3 = V_1 \cdot \frac{A_1}{A_3} - V_2 \cdot \frac{A_2}{A_3} \quad V_3 = 10 \cdot \frac{\text{ft}}{\text{s}} \times \frac{0.5}{0.6} - 20 \cdot \frac{\text{ft}}{\text{s}} \times \frac{0.1}{0.6} \quad V_3 = 5 \cdot \frac{\text{ft}}{\text{s}}$$

Based on geometry 
$$V_x = V_3 \cdot \sin(60 \cdot \text{deg}) \quad V_x = 4.33 \cdot \frac{\text{ft}}{\text{s}}$$


$$V_y = -V_3 \cdot \cos(60 \cdot \text{deg}) \quad V_y = -2.5 \cdot \frac{\text{ft}}{\text{s}}$$

$$\vec{V}_3 = \left( 4.33 \cdot \frac{\text{ft}}{\text{s}}, -2.5 \cdot \frac{\text{ft}}{\text{s}} \right)$$

## Problem 4.25

[Difficulty: 1]

**4.25** Consider steady, incompressible flow through the device shown. Determine the magnitude and direction of the volume flow rate through port 3.



**Given:** Data on flow through device

**Find:** Volume flow rate at port 3

**Solution:**

Basic equation 
$$\sum_{\text{CS}} (\vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

Then for the box 
$$\sum_{\text{CS}} (\vec{V} \cdot \vec{A}) = -V_1 \cdot A_1 + V_2 \cdot A_2 + V_3 \cdot A_3 = -V_1 \cdot A_1 + V_2 \cdot A_2 + Q_3$$

Note we assume outflow at port 3

Hence 
$$Q_3 = V_1 \cdot A_1 - V_2 \cdot A_2 \quad Q_3 = 3 \cdot \frac{\text{m}}{\text{s}} \times 0.1 \cdot \text{m}^2 - 10 \cdot \frac{\text{m}}{\text{s}} \times 0.05 \cdot \text{m}^2 \quad Q_3 = -0.2 \cdot \frac{\text{m}^3}{\text{s}}$$

The negative sign indicates the flow at port 3 is inwards.

Flow rate at port 3 is  $0.2 \text{ m}^3/\text{s}$  inwards

## Problem 4.26

[Difficulty: 1]

**4.26** A rice farmer needs to fill her  $150\text{ m} \times 400\text{ m}$  field with water to a depth of  $7.5\text{ cm}$  in  $1\text{ hr}$ . How many  $37.5\text{-cm}$ -diameter supply pipes are needed if the average velocity in each must be less than  $2.5\text{ m/s}$ ?

**Given:** Water needs of farmer

**Find:** Number of supply pipes needed

**Solution:**

Basic equation  $Q = V \cdot A$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

The given data is:  $A = 150\text{ m} \cdot 400\text{ m}$   $A = 6 \times 10^4\text{ m}^2$   $h = 7.5\text{ cm}$   $t = 1\text{ hr}$   $D = 37.5\text{ cm}$   $V = 2.5\frac{\text{m}}{\text{s}}$

Then  $Q = \frac{A \cdot h}{t}$   $Q = 1.25\frac{\text{m}^3}{\text{s}}$

If  $n$  is the number of pipes  $Q = V \cdot \frac{\pi}{4} \cdot D^2 \cdot n$  or  $n = \frac{4 \cdot Q}{\pi \cdot V \cdot D^2}$   $n = 4.527$

The farmer needs 5 pipes.

## Problem 4.27

[Difficulty: 1]

**4.27** You are making beer. The first step is filling the glass carboy with the liquid wort. The internal diameter of the carboy is 15 in., and you wish to fill it up to a depth of 2 ft. If your wort is drawn from the kettle using a siphon process that flows at 3 gpm, how long will it take to fill?

**Given:** Data on filling of glass carboy

**Find:** Time to fill

**Solution:**

We can treat this as an unsteady problem if we choose the CS as the entire carboy

Basic equation 
$$\frac{\partial}{\partial t} M_{CV} + \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Incompressible flow 2) Uniform flow

Given data:  $Q = 3 \cdot \text{gpm}$        $D = 15 \cdot \text{in}$        $h = 2 \cdot \text{ft}$

Hence 
$$\frac{\partial}{\partial t} M_{CV} = \rho \cdot A \cdot \frac{dh}{dt} = \rho \cdot A \cdot \frac{h}{\tau} = \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = \rho \cdot Q$$

where  $Q$  is the fill rate,  $A$  is the carboy cross-section area,  $dh/dt$  is the rate of rise in the carboy, and  $\tau$  is the fill time

Hence 
$$\tau = \frac{\frac{\pi}{4} \cdot D^2 \cdot h}{Q} \quad \tau = 6.12 \cdot \text{min}$$

## Problem 4.28

[Difficulty: 1]

**4.28** In your kitchen, the sink is 2 ft by 18 in. by 12 in. deep. You are filling it with water at the rate of 4 gpm. How long will it take (in min) to half fill the sink? After this you turn off the faucet and open the drain slightly so that the tank starts to drain at 1 gpm. What is the rate (in./min) at which the water level drops?

**Given:** Data on filling of a sink

**Find:** Time to half fill; rate at which level drops

**Solution:**

This is an unsteady problem if we choose the CS as the entire sink

Basic equation 
$$\frac{\partial}{\partial t} M_{CV} + \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Incompressible flow

Given data:  $m_{\text{rate}} = 4 \cdot \text{gpm}$      $L = 2 \cdot \text{ft}$      $w = 18 \cdot \text{in}$      $d = 12 \cdot \text{in}$      $Q = 4 \cdot \text{gpm}$      $Q_{\text{drain}} = 1 \cdot \text{gpm}$

Hence 
$$\frac{\partial}{\partial t} M_{CV} = \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = \text{Inflow} - \text{Outflow} \quad (1)$$

To half fill:  $V = \frac{1}{2} \cdot L \cdot w \cdot d$      $V = 1.5 \text{ ft}^3$      $V = 11.2 \text{ gal}$

Then, using Eq 1  $\frac{V}{\tau} = Q$      $\tau = \frac{V}{Q}$      $\tau = 168 \text{ s}$      $\tau = 2.81 \text{ min}$

After the drain opens, Eq. 1 becomes  $\frac{dV}{dt} = L \cdot w \cdot V_{\text{level}} = -Q_{\text{drain}}$  where  $V_{\text{level}}$  is the speed of water level drop

$$V_{\text{level}} = -\frac{Q_{\text{drain}}}{L \cdot w} \quad V_{\text{level}} = -7.43 \times 10^{-4} \frac{\text{ft}}{\text{s}} \quad V_{\text{level}} = -0.535 \frac{\text{in}}{\text{min}}$$

## Problem 4.29

[Difficulty: 1]

**4.29** Ventilation air specifications for classrooms require that at least 8.0 L/s of fresh air be supplied for each person in the room (students and instructor). A system needs to be designed that will supply ventilation air to 6 classrooms, each with a capacity of 20 students. Air enters through a central duct, with short branches successively leaving for each classroom. Branch registers are 200 mm high and 500 mm wide. Calculate the volume flow rate and air velocity entering each room. Ventilation noise increases with air velocity. Given a supply duct 500 mm high, find the narrowest supply duct that will limit air velocity to a maximum of 1.75 m/s.

**Given:** Air flow system

**Find:** Flow rate and velocity into each room; narrowest supply duct

**Solution:**

Basic equation  $Q = V \cdot A$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

The given data is:  $Q_{\text{person}} = 8 \cdot \frac{\text{L}}{\text{s}}$   $n_{\text{rooms}} = 6$   $n_{\text{students}} = 20$

$h = 200 \cdot \text{mm}$   $w = 500 \cdot \text{mm}$   $V_{\text{max}} = 1.75 \cdot \frac{\text{m}}{\text{s}}$

Then for each room  $Q_{\text{room}} = n_{\text{students}} \cdot Q_{\text{person}}$   $Q_{\text{room}} = 160 \frac{\text{L}}{\text{s}}$   $Q_{\text{room}} = 0.16 \frac{\text{m}^3}{\text{s}}$

and  $V_{\text{room}} = \frac{Q_{\text{room}}}{w \cdot h}$   $V_{\text{room}} = 1.6 \frac{\text{m}}{\text{s}}$

For the supply duct  $Q = n_{\text{rooms}} \cdot Q_{\text{room}}$   $Q = 960 \frac{\text{L}}{\text{s}}$   $Q = 0.96 \frac{\text{m}^3}{\text{s}}$

and  $Q = V_{\text{max}} \cdot A = V_{\text{max}} \cdot w \cdot h$  where  $w$  and  $h$  are now the supply duct dimensions  $h = 500 \cdot \text{mm}$

$w = \frac{Q}{V_{\text{max}} \cdot h}$   $w = 1.097 \text{ m}$

## Problem 4.30

[Difficulty: 1]

**4.30** You are trying to pump storm water out of your basement during a storm. The pump can extract 27.5 gpm. The water level in the basement is now sinking by about 4 in./hr. What is the flow rate (gpm) from the storm into the basement? The basement is 30 ft × 20 ft.

**Given:** Data on filling of a basement during a storm

**Find:** Flow rate of storm into basement

**Solution:**

This is an unsteady problem if we choose the CS as the entire basement

Basic equation 
$$\frac{\partial}{\partial t} M_{CV} + \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Incompressible flow

Given data: 
$$Q_{\text{pump}} = 27.5 \cdot \text{gpm} \quad \frac{dh}{dt} = 4 \cdot \frac{\text{in}}{\text{hr}} \quad A = 30 \cdot \text{ft} \cdot 20 \cdot \text{ft}$$

Hence 
$$\frac{\partial}{\partial t} M_{CV} = \rho \cdot A \cdot \frac{dh}{dt} = \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = \rho \cdot Q_{\text{storm}} - \rho \cdot Q_{\text{pump}}$$

where A is the basement area and dh/dt is the rate at which the height of water in the basement changes.

or 
$$Q_{\text{storm}} = Q_{\text{pump}} - A \cdot \frac{dh}{dt}$$

$$Q_{\text{storm}} = 27.5 \cdot \frac{\text{gal}}{\text{min}} - 30 \cdot \text{ft} \times 20 \cdot \text{ft} \times \left( \frac{4}{12} \cdot \frac{\text{ft}}{\text{hr}} \right) \times \frac{7.48 \cdot \text{gal}}{\text{ft}^3} \times \frac{1 \cdot \text{hr}}{60 \cdot \text{min}}$$

Data on gals from Table G.2

$$Q_{\text{storm}} = 2.57 \cdot \text{gpm}$$

## Problem 4.31

[Difficulty: 1]

**4.31** In steady-state flow, downstream the density is  $1 \text{ kg/m}^3$ , the velocity is  $1000 \text{ m/sec}$ , and the area is  $0.1 \text{ m}^2$ . Upstream, the velocity is  $1500 \text{ m/sec}$ , and the area is  $0.25 \text{ m}^2$ . What is the density upstream?

**Given:** Data on compressible flow

**Find:** Downstream density

**Solution:**

Basic equation 
$$\sum_{\text{CS}} (\rho \cdot \vec{V} \cdot \vec{A}) = 0$$

Assumptions: 1) Steady flow 2) Uniform flow


Then for the box 
$$\sum_{\text{CS}} (\rho \cdot \vec{V} \cdot \vec{A}) = -\rho_u \cdot V_u \cdot A_u + \rho_d \cdot V_d \cdot A_d = 0$$

Hence 
$$\rho_u = \rho_d \cdot \frac{V_d \cdot A_d}{V_u \cdot A_u} \quad \rho_u = 1 \cdot \frac{\text{kg}}{\text{m}^3} \cdot \frac{1000 \frac{\text{m}}{\text{s}} \cdot 0.1 \text{m}^2}{1500 \frac{\text{m}}{\text{s}} \cdot 0.25 \text{m}^2} \quad \rho_u = 0.267 \frac{\text{kg}}{\text{m}^3}$$

### Problem 4.32

[Difficulty: 2]

**4.32** In the incompressible flow through the device shown, velocities may be considered uniform over the inlet and outlet sections. The following conditions are known:  $A_1 = 0.1 \text{ m}^2$ ,  $A_2 = 0.2 \text{ m}^2$ ,  $A_3 = 0.15 \text{ m}^2$ ,  $V_1 = 10e^{-t/2} \text{ m/s}$ , and  $V_2 = 2 \cos(2\pi t) \text{ m/s}$  ( $t$  in seconds). Obtain an expression for the velocity at section ③, and plot  $V_3$  as a function of time. At what instant does  $V_3$  first become zero? What is the total mean volumetric flow at section ③?



**Given:** Data on flow through device

**Find:** Velocity  $V_3$ ; plot  $V_3$  against time; find when  $V_3$  is zero; total mean flow

**Solution:**

Governing equation: For incompressible flow (Eq. 4.13) and uniform flow  $\int \vec{V} \cdot d\vec{A} = \sum \vec{V} \cdot \vec{A} = 0$

Applying to the device (assuming  $V_3$  is out)  $-V_1 \cdot A_1 - V_2 \cdot A_2 + V_3 \cdot A_3 = 0$

$$V_3 = \frac{V_1 \cdot A_1 + V_2 \cdot A_2}{A_3} = \frac{10 \cdot e^{-\frac{t}{2}} \cdot \frac{\text{m}}{\text{s}} \times 0.1 \cdot \text{m}^2 + 2 \cdot \cos(2 \cdot \pi \cdot t) \cdot \frac{\text{m}}{\text{s}} \times 0.2 \cdot \text{m}^2}{0.15 \cdot \text{m}^2}$$

The velocity at  $A_3$  is  $V_3 = 6.67 \cdot e^{-\frac{t}{2}} + 2.67 \cdot \cos(2 \cdot \pi \cdot t)$


The total mean volumetric flow at  $A_3$  is

$$Q = \int_0^{\infty} V_3 \cdot A_3 \, dt = \int_0^{\infty} \left( 6.67 \cdot e^{-\frac{t}{2}} + 2.67 \cdot \cos(2 \cdot \pi \cdot t) \right) \cdot 0.15 \, dt \cdot \left( \frac{\text{m}}{\text{s}} \cdot \text{m}^2 \right)$$

$$Q = \lim_{t \rightarrow \infty} \left( -2 \cdot e^{-\frac{t}{2}} + \frac{1}{5 \cdot \pi} \cdot \sin(2 \cdot \pi \cdot t) \right) - (-2) = 2 \cdot \text{m}^3 \quad Q = 2 \cdot \text{m}^3$$

The time at which  $V_3$  first is zero, and the plot of  $V_3$  is shown in the corresponding *Excel* workbook  $t = 2.39 \cdot \text{s}$

$t$ (s)	$V_3$ (m/s)
0.00	9.33
0.10	8.50
0.20	6.86
0.30	4.91
0.40	3.30
0.50	2.53
0.60	2.78
0.70	3.87
0.80	5.29
0.90	6.41
1.00	6.71
1.10	6.00
1.20	4.48
1.30	2.66
1.40	1.15
1.50	0.48
1.60	0.84
1.70	2.03
1.80	3.53
1.90	4.74
2.00	5.12
2.10	4.49
2.20	3.04
2.30	1.29
2.40	-0.15
2.50	-0.76



The time at which  $V_3$  first becomes zero can be found using *Goal Seek*

$t$ (s)	$V_3$ (m/s)
2.39	0.00


### Problem 4.33

[Difficulty: 2]

**4.33** Oil flows steadily in a thin layer down an inclined plane. The velocity profile is

$$u = \frac{\rho g \sin \theta}{\mu} \left[ hy - \frac{y^2}{2} \right]$$

Express the mass flow rate per unit width in terms of  $\rho$ ,  $\mu$ ,  $g$ ,  $\theta$ , and  $h$ .



**Given:** Data on flow down an inclined plane

**Find:** Find  $u_{\max}$

**Solution:**

Basic equation 
$$m_{\text{flow}} = \int \rho u \, dA$$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at 1 and 2 
$$m_{\text{flow}} = \int_0^h \rho \cdot \frac{\rho \cdot g \cdot \sin(\theta)}{\mu} \cdot \left( h \cdot y - \frac{y^2}{2} \right) \cdot w \, dy = \frac{\rho^2 \cdot g \cdot \sin(\theta) \cdot w}{\mu} \int_0^h \left( h \cdot y - \frac{y^2}{2} \right) dy$$

$$m_{\text{flow}} = \frac{\rho^2 \cdot g \cdot \sin(\theta) \cdot w}{\mu} \cdot \left( \frac{h^3}{2} - \frac{h^3}{6} \right)$$

Hence 
$$m_{\text{flow}} = \frac{\rho^2 \cdot g \cdot \sin(\theta) \cdot w \cdot h^3}{3 \cdot \mu}$$


## Problem 4.34

[Difficulty: 2]

**4.34** Water enters a wide, flat channel of height  $2h$  with a uniform velocity of  $2.5 \text{ m/s}$ . At the channel outlet the velocity distribution is given by

$$\frac{u}{u_{\max}} = 1 - \left(\frac{y}{h}\right)^2$$

where  $y$  is measured from the centerline of the channel. Determine the exit centerline velocity,  $u_{\max}$ .



**Given:** Data on flow at inlet and outlet of channel

**Find:** Find  $u_{\max}$

**Solution:**

Basic equation 
$$\int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at 1 and 2 
$$-\rho \cdot U \cdot 2 \cdot h \cdot w + \int_{-h}^h \rho \cdot u(y) \, dy = 0$$

$$u_{\max} \cdot \left[ [h - (-h)] - \left[ \frac{h^3}{3 \cdot h^2} - \left( -\frac{h^3}{3 \cdot h^2} \right) \right] \right] = 2 \cdot h \cdot U$$

$$\int_{-h}^h u_{\max} \cdot \left[ 1 - \left( \frac{y}{h} \right)^2 \right] dy = 2 \cdot h \cdot U$$

$$u_{\max} \cdot \frac{4}{3} \cdot h = 2 \cdot h \cdot U$$

Hence 
$$u_{\max} = \frac{3}{2} \cdot U = \frac{3}{2} \times 2.5 \cdot \frac{\text{m}}{\text{s}}$$

$$u_{\max} = 3.75 \cdot \frac{\text{m}}{\text{s}}$$


### Problem 4.35

[Difficulty: 2]

**4.35** Water flows steadily through a pipe of length  $L$  and radius  $R = 75$  mm. Calculate the uniform inlet velocity,  $U$ , if the velocity distribution across the outlet is given by

$$u = u_{\max} \left[ 1 - \frac{r^2}{R^2} \right]$$

and  $u_{\max} = 3$  m/s.



**Given:** Data on flow at inlet and outlet of pipe

**Find:** Find  $U$

**Solution:**

Basic equation 
$$\int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at inlet and exit 
$$-\rho \cdot U \cdot \pi \cdot R^2 + \int_0^R \rho \cdot u(r) \cdot 2 \cdot \pi \cdot r \, dr = 0$$

$$u_{\max} \cdot \left( R^2 - \frac{1}{2} \cdot R^2 \right) = R^2 \cdot U$$

Hence 
$$U = \frac{1}{2} \times 3 \cdot \frac{\text{m}}{\text{s}}$$

$$\int_0^R u_{\max} \cdot \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \cdot 2 \cdot r \, dr = R^2 \cdot U$$

$$U = \frac{1}{2} \cdot u_{\max}$$

$$U = 1.5 \cdot \frac{\text{m}}{\text{s}}$$


### Problem 4.36

[Difficulty: 2]

**4.36** Incompressible fluid flows steadily through a plane diverging channel. At the inlet, of height  $H$ , the flow is uniform with magnitude  $V_1$ . At the outlet, of height  $2H$ , the velocity profile is

$$V_2 = V_m \cos\left(\frac{\pi y}{2H}\right)$$

where  $y$  is measured from the channel centerline. Express  $V_m$  in terms of  $V_1$ .



**Given:** Data on flow at inlet and outlet of channel

**Find:** Find  $u_{\max}$

**Solution:**

Basic equation 
$$\int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at 1 and 2 
$$-\rho \cdot V_1 \cdot H \cdot w + \int_{-H}^H \rho \cdot V_2(y) \cdot w \, dy = 0$$

or 
$$V_1 \cdot H = \int_{-H}^H V_m \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot H}\right) \, dy = 2 \cdot \int_0^H V_m \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot H}\right) \, dy = 2 \cdot V_m \cdot \frac{2 \cdot H}{\pi} \cdot \left(\sin\left(\frac{\pi}{2}\right) - \sin(0)\right) = \frac{4 \cdot H \cdot V_m}{\pi}$$

Hence 
$$V_m = \frac{\pi}{4} \cdot V_1$$


## Problem 4.37

[Difficulty: 3]

**4.37** The velocity profile for laminar flow in an annulus is given by

$$u(r) = -\frac{\Delta p}{4\mu L} \left[ R_o^2 - r^2 + \frac{R_o^2 - R_i^2}{\ln(R_i/R_o)} \ln \frac{R_o}{r} \right]$$

where  $\Delta p/L = -10$  kPa/m is the pressure gradient,  $\mu$  is the viscosity (SAE 10 oil at 20°C), and  $R_o = 5$  mm and  $R_i = 1$  mm are the outer and inner radii. Find the volume flow rate, the average velocity, and the maximum velocity. Plot the velocity distribution.



**Given:** Velocity distribution in annulus

**Find:** Volume flow rate; average velocity; maximum velocity; plot velocity distribution

**Solution:**

Governing equation For the flow rate (Eq. 4.14a) and average velocity (Eq. 4.14b)  $Q = \int \vec{V} dA$   $V_{av} = \frac{Q}{A}$

The given data is  $R_o = 5 \text{ mm}$   $R_i = 1 \text{ mm}$   $\frac{\Delta p}{L} = -10 \frac{\text{kPa}}{\text{m}}$   $\mu = 0.1 \frac{\text{N}\cdot\text{s}}{\text{m}^2}$  (From Fig. A.2)

$$u(r) = \frac{-\Delta p}{4\mu L} \left( R_o^2 - r^2 + \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \ln\left(\frac{R_o}{r}\right) \right)$$

The flow rate is  $Q = \int_{R_i}^{R_o} u(r) \cdot 2\pi \cdot r \, dr$

Considerable mathematical manipulation leads to  $Q = \frac{\Delta p \cdot \pi}{8 \cdot \mu \cdot L} \cdot (R_o^2 - R_i^2) \cdot \left[ \frac{(R_o^2 - R_i^2)}{\ln\left(\frac{R_o}{R_i}\right)} - (R_i^2 + R_o^2) \right]$

Substituting values  $Q = \frac{\pi}{8} \cdot (-10 \cdot 10^3) \cdot \frac{\text{N}}{\text{m}^2 \cdot \text{m}} \cdot \frac{\text{m}^2}{0.1 \cdot \text{N}\cdot\text{s}} \cdot (5^2 - 1^2) \cdot \left(\frac{\text{m}}{1000}\right)^2 \cdot \left[ \frac{5^2 - 1^2}{\ln\left(\frac{5}{1}\right)} - (5^2 + 1^2) \right] \cdot \left(\frac{\text{m}}{1000}\right)^2$

$$Q = 1.045 \times 10^{-5} \frac{\text{m}^3}{\text{s}} \quad Q = 10.45 \cdot \frac{\text{mL}}{\text{s}}$$

The average velocity is  $V_{av} = \frac{Q}{A} = \frac{Q}{\pi \cdot (R_o^2 - R_i^2)}$   $V_{av} = \frac{1}{\pi} \times 1.045 \times 10^{-5} \frac{\text{m}^3}{\text{s}} \times \frac{1}{5^2 - 1^2} \cdot \left(\frac{1000}{\text{m}}\right)^2$   $V_{av} = 0.139 \frac{\text{m}}{\text{s}}$


The maximum velocity occurs when  $\frac{du}{dr} = 0 = \frac{d}{dx} \left[ \frac{-\Delta p}{4\mu L} \cdot \left( R_o^2 - r^2 + \frac{R_o^2 - R_i^2}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \ln\left(\frac{R_o}{r}\right) \right) \right] = -\frac{\Delta p}{4\mu L} \cdot \left[ -2 \cdot r - \frac{(R_o^2 - R_i^2)}{\ln\left(\frac{R_i}{R_o}\right)} \cdot \frac{1}{r} \right]$

Then 
$$r = \sqrt{\frac{R_i^2 - R_o^2}{2 \cdot \ln\left(\frac{R_i}{R_o}\right)}} \quad r = 2.73 \cdot \text{mm} \quad \text{Substituting in } u(r) \quad u_{\max} = u(2.73 \cdot \text{mm}) = 0.213 \cdot \frac{\text{m}}{\text{s}}$$

The maximum velocity using Solver instead, and the plot, are also shown in an *Excel* workbook

$R_o = 5 \text{ mm}$   
 $R_i = 1 \text{ mm}$   
 $-p/L = -10 \text{ kPa/m}$   
 $-\alpha\mu = 0.1 \text{ N.s/m}^2$

$r \text{ (mm)}$	$u \text{ (m/s)}$
1.00	0.000
1.25	0.069
1.50	0.120
1.75	0.157
2.00	0.183
2.25	0.201
2.50	0.210
2.75	0.213
3.00	0.210
3.25	0.200
3.50	0.186
3.75	0.166
4.00	0.142
4.25	0.113
4.50	0.079
4.75	0.042
5.00	0.000




The maximum velocity can be found using *Solver*

$r \text{ (mm)}$	$u \text{ (m/s)}$
2.73	0.213

## Problem 4.38

[Difficulty: 2]

**4.38** A two-dimensional reducing bend has a linear velocity profile at section ①. The flow is uniform at sections ② and ③. The fluid is incompressible and the flow is steady. Find the maximum velocity,  $V_{1,\max}$ , at section ①.



**Given:** Data on flow at inlet and outlet of a reducing elbow

**Find:** Find the maximum velocity at section 1

**Solution:**

Basic equation 
$$\int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at 1, 2 and 3 
$$-\int_0^{h_1} V_1(y) \cdot w \, dy + V_2 \cdot w \cdot h_2 + V_3 \cdot w \cdot h_3 = 0$$

or 
$$\frac{V_{1\max}}{h_1} \cdot \int_0^{h_1} y \, dy = \frac{V_{1\max}}{h_1} \cdot \frac{h_1^2}{2} = V_2 \cdot h_2 + V_3 \cdot h_3$$


Hence 
$$V_{1\max} = \frac{2}{h_1} \cdot (V_3 \cdot h_3 + V_2 \cdot h_2)$$

$$V_{1\max} = \frac{2}{0.5 \cdot \text{m}} \cdot \left( 5 \cdot \frac{\text{m}}{\text{s}} \times 0.15 \cdot \text{m} + 1 \cdot \frac{\text{m}}{\text{s}} \times 0.2 \cdot \text{m} \right) \quad V_{1\max} = 3.80 \frac{\text{m}}{\text{s}}$$

## Problem 4.39

[Difficulty: 2]

**4.39** Water enters a two-dimensional, square channel of constant width,  $h = 75.5$  mm, with uniform velocity,  $U$ . The channel makes a  $90^\circ$  bend that distorts the flow to produce the linear velocity profile shown at the exit, with  $v_{\max} = 2v_{\min}$ . Evaluate  $v_{\min}$ , if  $U = 7.5$  m/s.



**Given:** Data on flow at inlet and outlet of channel

**Find:** Find  $u_{\max}$

**Solution:**

Basic equation 
$$\int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at inlet and exit 
$$-U \cdot w \cdot h + \int_0^h V_{\text{exit}}(x) \cdot w \, dx = 0$$

Here we have 
$$V_{\text{exit}} = V_{\max} - (V_{\max} - V_{\min}) \cdot \frac{x}{h}$$
 But we also have 
$$V_{\max} = 2 \cdot V_{\min}$$

Hence 
$$V_{\text{exit}} = 2 \cdot V_{\min} - V_{\min} \cdot \frac{x}{h}$$

$$\int_0^h V_{\text{exit}}(x) \cdot w \, dx = \int_0^h \left( 2 \cdot V_{\min} - V_{\min} \cdot \frac{x}{h} \right) \cdot w \, dx = \left( 2 \cdot V_{\min} \cdot h - V_{\min} \cdot \frac{h^2}{2 \cdot h} \right) \cdot w = \frac{3}{2} \cdot V_{\min} \cdot h \cdot w$$

Hence 
$$\frac{3}{2} \cdot V_{\min} \cdot h \cdot w = U \cdot w \cdot h$$
 
$$V_{\min} = \frac{2}{3} \cdot U$$

$$V_{\min} = \frac{2}{3} \times 7.5 \cdot \frac{\text{m}}{\text{s}}$$

$$V_{\min} = 5.00 \cdot \frac{\text{m}}{\text{s}}$$



### Problem 4.41

[Difficulty: 2]

4.41 A porous round tube with  $D = 60$  mm carries water. The inlet velocity is uniform with  $V_1 = 7.0$  m/s. Water flows radially and axisymmetrically outward through the porous walls with velocity distribution


$$v = V_0 \left[ 1 - \left( \frac{x}{L} \right)^2 \right]$$

where  $V_0 = 0.03$  m/s and  $L = 0.950$  m. Calculate the mass flow rate inside the tube at  $x = L$ .

Solution:

Basic equation:  $0 = \frac{\partial}{\partial t} \int_V \rho dV + \int_{CS} \rho \vec{v} \cdot d\vec{A}$

Assumptions: (1) steady flow  
(2)  $\rho = \text{constant}$



Then

$$0 = \int_{A_1} \rho \vec{v} \cdot d\vec{A} + \int_{A_2} \rho \vec{v} \cdot d\vec{A} + \int_{A_{\text{arc}}} \rho \vec{v} \cdot d\vec{A}$$

$$= -\rho V_1 A_1 + \dot{m}_2 + \int_0^L \rho V_0 \left[ 1 - \left( \frac{x}{L} \right)^2 \right] 2\pi R dx$$

$$\dot{m}_2 = \rho V_1 A_1 - 2\pi R \rho V_0 \int_0^L \left[ 1 - \frac{x^2}{L^2} \right] dx$$

$$= \rho V_1 \frac{\pi D^2}{4} - 2\pi R \rho V_0 \left[ x - \frac{x^3}{3L^2} \right]_0^L$$

$$= \frac{\pi}{4} \rho V_1 D^2 - \frac{4}{3} \pi R \rho V_0 L$$


$$\dot{m}_2 = \frac{\pi}{4} \times 999 \frac{\text{kg}}{\text{m}^3} \times 7.0 \frac{\text{m}}{\text{s}} \times (0.06 \text{ m})^2 - \frac{4}{3} \pi \times 0.03 \text{ m} \times 999 \frac{\text{kg}}{\text{m}^3} \times 0.03 \text{ m} \times 0.95 \text{ m}$$

$$\dot{m}_2 = 19.8 \frac{\text{kg}}{\text{s}} - 3.6 \frac{\text{kg}}{\text{s}} = 16.2 \frac{\text{kg}}{\text{s}} \quad \leftarrow \dot{m}_{\text{out}}$$

### Problem 4.42

[Difficulty: 2]

4.42 A rectangular tank used to supply water for a Reynolds flow experiment is 230 mm deep. Its width and length are  $W = 150$  mm and  $L = 230$  mm. Water flows from the outlet tube (inside diameter  $D = 6.35$  mm) at Reynolds number  $Re = 2000$ , when the tank is half full. The supply valve is closed. Find the rate of change of water level in the tank at this instant.



Solution:

Apply conservation of mass to CV which includes tank and tube.

Basic equation:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{v} \cdot d\vec{A}$$

Definition:  $Re = \frac{\rho \bar{V} D}{\mu} = \frac{\rho \bar{V} D}{\nu}$

Assumptions: (1) uniform flow at exit of tube.

(2) incompressible flow

(3) neglect air entering the control volume

Then,

$$0 = \frac{\partial}{\partial t} \left[ \rho W L h + \rho \pi \frac{D^2}{4} L_1 \right] + \left\{ +1 \left( \rho \bar{V}_0 \frac{\pi D^2}{4} \right) \right\}$$

$$0 = W L \frac{dh}{dt} + \bar{V}_0 \pi \frac{D^2}{4} \quad (\text{note } L_1 = \text{constant})$$

$$\therefore \frac{dh}{dt} = - \frac{\bar{V}_0 \pi D^2}{4 W L}$$

To find  $\bar{V}$  use the definition of  $Re$

$$\bar{V}_0 = \frac{Re \nu}{D}$$

For water at 20C  $\nu = 1 \times 10^{-6} \text{ m}^2/\text{sec}$  (Table A.8)

$$\bar{V}_0 = 2000 \times 1 \times 10^{-6} \frac{\text{m}^2}{\text{sec}} \times \frac{1}{6.35 \times 10^{-3} \text{ m}} = 0.315 \text{ m/sec}$$

$$\frac{dh}{dt} = - \frac{\bar{V}_0 \pi D^2}{4 W L} = - \frac{0.315 \text{ m}}{4 \text{ sec}} \times \frac{\pi (6.35 \text{ mm})^2}{150 \text{ mm} \times 230 \text{ mm}} \times 10^3 \frac{\text{mm}}{\text{m}}$$

$$\frac{dh}{dt} = - 0.289 \text{ mm/sec (falling)}$$

$\frac{dh}{dt}$

### Problem 4.43

[Difficulty: 2]

**4.43** A hydraulic accumulator is designed to reduce pressure pulsations in a machine tool hydraulic system. For the instant shown, determine the rate at which the accumulator gains or loses hydraulic oil.

Solution:

Use the control volume shown

Basic equation:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho \mathbf{V} \cdot d\mathbf{A} + \int_{CS} \rho \mathbf{V} \cdot d\mathbf{A}$$

Assumptions: (1) uniform flow at section (2)  
(2)  $p = \text{constant}$

Then,

$$0 = \frac{\partial}{\partial t} (M_{CV}) + \int_{A_1} \{-1 p V_1 dA_1\} + \int_{A_2} \{1 p V_2 dA_2\}$$

But  $\int_{A_1} p V_1 dA_1 = p Q_1$  where  $Q = \text{volume flowrate}$   
and  $p = SG \rho_{H_2O}$

$$\text{So } 0 = \frac{\partial}{\partial t} M_{CV} - p Q_1 + p V_2 A_2$$

$$\frac{\partial M_{CV}}{\partial t} = p (Q_1 - V_2 A_2)$$

$$= SG \rho_{H_2O} (Q_1 - V_2 \pi \frac{D^2}{4}) \quad \text{where } SG = 0.88 \text{ (Table A.2)}$$

$$= 0.88 \cdot 1.94 \frac{\text{slug}}{\text{ft}^3} \left[ 5.75 \frac{\text{gal}}{\text{min}} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{\text{min}}{60 \text{ s}} - 4.35 \frac{\text{ft}}{\text{s}} \times \pi \times \frac{(1.25)^2}{4} \text{ft}^2 \right]$$

$$\frac{\partial M_{CV}}{\partial t} = -4.14 \times 10^{-2} \frac{\text{slug}}{\text{s}} \quad \text{or} \quad -1.33 \frac{\text{lbm}}{\text{s}} \quad \frac{\partial M_{CV}}{\partial t}$$

(mass is decreasing in the CV)

Since  $M_{CV} = \rho_{oil} V_{oil}$

$$\frac{\partial M_{CV}}{\partial t} = \frac{\partial}{\partial t} (\rho_{oil} V_{oil}) = \rho_{oil} \frac{\partial V_{oil}}{\partial t} = SG_{oil} \rho_{H_2O} \frac{\partial V_{oil}}{\partial t}$$


$$\frac{\partial V_{oil}}{\partial t} = \frac{1}{SG_{oil} \rho_{H_2O}} \frac{\partial M_{CV}}{\partial t} = \frac{1}{0.88 \cdot 1.94 \text{ slugs}} \times (-4.14) \times 10^{-2} \frac{\text{slug}}{\text{s}}$$

$$\frac{\partial V_{oil}}{\partial t} = -2.43 \times 10^{-2} \frac{\text{ft}^3}{\text{s}} \quad \text{or} \quad 0.181 \text{ gal/s} \quad \frac{\partial V_{oil}}{\partial t}$$

### Problem 4.44

[Difficulty: 2]

**4.44** A cylindrical tank, 0.3 m in diameter, drains through a hole in its bottom. At the instant when the water depth is 0.6 m, the flow rate from the tank is observed to be 4 kg/s. Determine the rate of change of water level at this instant.



Solution: Apply conservation of mass to CV shown. Note section ② cuts below free surface, so  $\vec{V}_2$  corresponds to free surface velocity; volume of CV is constant.

$$\text{Basic equation: } 0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

Assumptions: (1) Incompressible flow, so unsteady term is zero, since volume of CV is fixed  
 (2) Uniform flow at each section

Then

$$0 = \rho \vec{V}_1 \cdot \vec{A}_1 + \rho \vec{V}_2 \cdot \vec{A}_2 = \dot{m}_1 + \rho \vec{V}_2 \cdot \vec{A}_2$$

and

$$\vec{V}_2 \cdot \vec{A}_2 = -\frac{\dot{m}_1}{\rho} = -\frac{4.0 \text{ kg/s}}{999 \text{ kg/m}^3} = -0.004 \text{ m}^3/\text{s}$$

Since  $\vec{V}_2 \cdot \vec{A}_2 < 0$ , flow at section ② is into CV. Therefore

$$V_2 = \frac{|\vec{V}_2 \cdot \vec{A}_2|}{A_2} = \frac{0.004 \text{ m}^3/\text{s}}{\frac{4}{\pi} \times (0.3)^2 \text{ m}^2} = 0.0566 \text{ m/s}$$

The water level is falling at 56.6 mm/s.


$$\vec{V}_S = -V_2 \hat{j} = -56.6 \hat{j} \text{ mm/s}$$

$\vec{V}_S$

## Problem 4.45

[Difficulty: 2]

**4.45** A tank of  $0.4 \text{ m}^3$  volume contains compressed air. A valve is opened and air escapes with a velocity of  $250 \text{ m/s}$  through an opening of  $100 \text{ mm}^2$  area. Air temperature passing through the opening is  $-20^\circ\text{C}$  and the absolute pressure is  $300 \text{ kPa}$ . Find the rate of change of density of the air in the tank at this moment.



**Given:** Data on airflow out of tank

**Find:** Find rate of change of density of air in tank

**Solution:**

Basic equation 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Density in tank is uniform 2) Uniform flow 3) Air is an ideal gas

Hence 
$$V_{\text{tank}} \cdot \frac{d\rho_{\text{tank}}}{dt} + \rho_{\text{exit}} \cdot V \cdot A = 0 \quad \frac{d\rho_{\text{tank}}}{dt} = -\frac{\rho_{\text{exit}} \cdot V \cdot A}{V_{\text{tank}}} = -\frac{p_{\text{exit}} \cdot V \cdot A}{R_{\text{air}} \cdot T_{\text{exit}} \cdot V_{\text{tank}}}$$


$$\frac{d\rho_{\text{tank}}}{dt} = -300 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times 250 \cdot \frac{\text{m}}{\text{s}} \times 100 \cdot \text{mm}^2 \times \left( \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \right)^2 \times \frac{1}{286.9} \cdot \frac{\text{kg} \cdot \text{K}}{\text{N} \cdot \text{m}} \times \frac{1}{(-20 + 273) \cdot \text{K}} \times \frac{1}{0.4 \cdot \text{m}^3}$$

Hence 
$$\frac{d\rho_{\text{tank}}}{dt} = -0.258 \cdot \frac{\text{kg}}{\text{m}^3 \cdot \text{s}} \quad \text{The mass in the tank is decreasing, as expected}$$

### Problem 4.46

[Difficulty: 2]

**4.46** Air enters a tank through an area of  $0.2 \text{ ft}^2$  with a velocity of  $15 \text{ ft/s}$  and a density of  $0.03 \text{ slug/ft}^3$ . Air leaves with a velocity of  $5 \text{ ft/s}$  and a density equal to that in the tank. The initial density of the air in the tank is  $0.02 \text{ slug/ft}^3$ . The total tank volume is  $20 \text{ ft}^3$  and the exit area is  $0.4 \text{ ft}^2$ . Find the initial rate of change of density in the tank.



Solution: Apply conservation of mass, using CV shown.

$$\text{Basic equation: } 0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

Assumptions: (1) Density is uniform in tank, so  $\frac{\partial}{\partial t} \int_{CV} \rho dV = \frac{\partial}{\partial t} (\rho_0 V)$

(2) Flow is uniform at inlet and outlet sections.

Then

$$0 = \frac{\partial}{\partial t} (\rho_0 V) + \rho_1 \vec{V}_1 \cdot \vec{A}_1 + \rho_0 \vec{V}_2 \cdot \vec{A}_2$$

$$0 = \rho_0 \frac{\partial V}{\partial t} + V \frac{\partial \rho_0}{\partial t} - |\rho_1 V_1 A_1| + |\rho_0 V_2 A_2|$$

or

$$\frac{\partial \rho_0}{\partial t} = \frac{|\rho_1 V_1 A_1| - |\rho_0 V_2 A_2|}{V}$$

Substituting magnitudes

$$\frac{\partial \rho_0}{\partial t} = \frac{1}{20 \text{ ft}^3} \left[ \frac{0.03 \text{ slug}}{\text{ft}^3} \times \frac{15 \text{ ft}}{\text{s}} \times 0.2 \text{ ft}^2 - \frac{0.02 \text{ slug}}{\text{ft}^3} \times \frac{5 \text{ ft}}{\text{s}} \times 0.4 \text{ ft}^2 \right]$$

$$\frac{\partial \rho_0}{\partial t} = 2.50 \times 10^{-3} \text{ slug/ft}^3 \cdot \text{s}$$

$\frac{\partial \rho_0}{\partial t}$

{ Note since  $\frac{\partial \rho_0}{\partial t} > 0$ , mass in tank increases. }

### Problem 4.47

[Difficulty: 2]

4.47 A recent TV news story about lowering Lake Shafer near Monticello, Indiana, by increasing the discharge through the dam that impounds the lake, gave the following information for flow through the dam:

Normal flow rate	290 cfs
Flow rate during draining of lake	2000 cfs


(The flow rate during draining was stated to be equivalent to 16,000 gal/s.) The announcer also said that during draining the lake level was expected to fall at the rate of 1 ft every 8 hr. Calculate the actual flow rate during draining in gal/s.

Estimate the surface area of the lake.

Solution: Convert units

$$Q = 2000 \frac{\text{ft}^3}{\text{s}} = 2000 \frac{\text{ft}^3}{\text{s}} \times 7.48 \frac{\text{gal}}{\text{ft}^3} = 1.50 \times 10^4 \text{ gal/s}$$

Apply conservation of mass using CV shown:



Basic equation:  $0 = \frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

Assumption: (1)  $\rho = \text{constant}$

Then  $\frac{dV}{dt} = A \frac{dh}{dt} = - \int_{CS} \vec{V} \cdot d\vec{A} = -Q_o + Q_i$

$$A = - \frac{Q_o - Q_i}{dh/dt} = - \frac{\Delta Q}{dh/dt} ; \Delta Q = Q_o - Q_i$$

But  $\Delta Q = 1,710 \text{ ft}^3/\text{s}$  and  $dh/dt = -1 \text{ ft}/8 \text{ hr}$ , since decreasing.

Thus

$$A = -1,710 \frac{\text{ft}^3}{\text{s}} \times \frac{8 \text{ hr}}{-1 \text{ ft}} \times \frac{3600 \text{ s}}{\text{hr}} = 4.92 \times 10^7 \text{ ft}^2$$

Since 1 acre = 43,600 ft<sup>2</sup>,

$$A = 4.92 \times 10^7 \text{ ft}^2 \times \frac{\text{acre}}{43,600 \text{ ft}^2} \approx 1,130 \text{ acres}$$

Since 1 square mile = 640 acres, the lake surface area is slightly less than 2 square miles!

Q

A

## Problem 4.48

[Difficulty: 3]

**4.48** A cylindrical tank, of diameter  $D = 6$  in., drains through an opening,  $d = 0.25$  in., in the bottom of the tank. The speed of the liquid leaving the tank is approximately  $V = \sqrt{2gy}$  where  $y$  is the height from the tank bottom to the free surface. If the tank is initially filled with water to  $y_0 = 3$  ft, determine the water depths at  $t = 1$  min,  $t = 2$  min, and  $t = 3$  min. Plot  $y$  (ft) versus  $t$  for the first three min.

**Given:** Data on draining of a tank

**Find:** Depth at various times; Plot of depth versus time

**Solution:**

Basic equation 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Uniform flow 2) Incompressible flow 3) Neglect air density

Treating the tank as the CV the basic equation becomes


$$\frac{\partial}{\partial t} \int_0^y \rho \cdot A_{\text{tank}} dy + \rho \cdot V \cdot A_{\text{opening}} = 0 \quad \text{or} \quad \rho \cdot \frac{\pi}{4} \cdot D^2 \cdot \frac{dy}{dt} + \rho \cdot \frac{\pi}{4} \cdot d^2 \cdot V = 0$$

Using  $V = \sqrt{2 \cdot g \cdot y}$  and simplifying 
$$\frac{dy}{dt} = -\left(\frac{d}{D}\right)^2 \cdot \sqrt{2 \cdot g \cdot y}^{\frac{1}{2}}$$

Separating variables 
$$\frac{dy}{\frac{1}{y^{\frac{1}{2}}}} = \left(\frac{d}{D}\right)^2 \cdot \sqrt{2 \cdot g} \cdot dt$$
 and integrating 
$$2 \cdot \left(y^{\frac{1}{2}} - y_0^{\frac{1}{2}}\right) = -\left(\frac{d}{D}\right)^2 \cdot \sqrt{2 \cdot g} \cdot t$$

Solving for  $y$  
$$y(t) = y_0 \cdot \left[1 - \sqrt{\frac{g}{2 \cdot y_0}} \cdot \left(\frac{d}{D}\right)^2 \cdot t\right]^2$$

Using the given data  $y(1\text{-min}) = 1.73\text{-ft}$        $y(2\text{-min}) = 0.804\text{-ft}$        $y(3\text{-min}) = 0.229\text{-ft}$



## Problem 4.49

[Difficulty: 3]

**4.49** For the conditions of Problem 4.48, estimate the times required to drain the tank from initial depth to a depth  $y = 2$  ft (a change in depth of 1 ft), and from  $y = 2$  ft to  $y = 1$  ft (also a change in depth of 1 ft). Can you explain the discrepancy in these times? Plot the time to drain to a depth  $y = 1$  ft as a function of opening sizes ranging from  $d = 0.1$  in. to 0.5 in.

**Given:** Data on draining of a tank

**Find:** Times to a depth of 1 foot; Plot of drain time versus opening size

**Solution:**

Basic equation 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Uniform flow 2) Incompressible flow 3) Neglect air density

Treating the tank as the CV the basic equation becomes

$$\frac{\partial}{\partial t} \int_0^y \rho \cdot A_{\text{tank}} dy + \rho \cdot V \cdot A_{\text{opening}} = 0 \quad \text{or} \quad \rho \cdot \frac{\pi}{4} \cdot D^2 \cdot \frac{dy}{dt} + \rho \cdot \frac{\pi}{4} \cdot d^2 \cdot V = 0$$

Using  $V = \sqrt{2 \cdot g \cdot y}$  and simplifying 
$$\frac{dy}{dt} = -\left(\frac{d}{D}\right)^2 \cdot \sqrt{2 \cdot g} \cdot y^{\frac{1}{2}}$$


Separating variables 
$$\frac{dy}{y^{\frac{1}{2}}} = \left(\frac{d}{D}\right)^2 \cdot \sqrt{2 \cdot g} \cdot dt$$
 and integrating 
$$2 \cdot \left(y^{\frac{1}{2}} - y_0^{\frac{1}{2}}\right) = -\left(\frac{d}{D}\right)^2 \cdot \sqrt{2 \cdot g} \cdot t$$

Solving for t 
$$t = \sqrt{\frac{2 \cdot y_0}{g}} \cdot \left(\frac{D}{d}\right)^2 \cdot \left(1 - \sqrt{\frac{y}{y_0}}\right)$$
 Using the given data  $t(2 \cdot \text{ft}) = 45.6 \text{ s}$       $t(1 \cdot \text{ft}) = 105 \text{ s}$

Hence for the first drop of 1 foot  $\Delta t = t(2 \cdot \text{ft})$   $\Delta t = 45.6 \text{ s}$

For the second drop of 1 foot  $\Delta t = t(1 \cdot \text{ft}) - t(2 \cdot \text{ft})$   $\Delta t = 59.5 \text{ s}$

This is because as the level drops the exit speed, hence drain rate, decreases.



### Problem 4.50

[Difficulty: 3]

**4.50** A conical flask contains water to height  $H = 36.8$  mm, where the flask diameter is  $D = 29.4$  mm. Water drains out through a smoothly rounded hole of diameter  $d = 7.35$  mm at the apex of the cone. The flow speed at the exit is approximately  $V = \sqrt{2gy}$ , where  $y$  is the height of the liquid free surface above the hole. A stream of water flows into the top of the flask at constant volume flow rate,  $Q = 3.75 \times 10^{-7} \text{ m}^3/\text{hr}$ . Find the volume flow rate from the bottom of the flask. Evaluate the direction and rate of change of water surface level in the flask at this instant.

Solution: Apply continuity to the CV shown.

Basic eq.:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{v} \cdot d\vec{A}$

Assumptions: (1) uniform flow at each section  
(2) neglect mass of air.


Then

$$0 = \rho \frac{dV}{dt} + \rho Q_{out} - \rho Q_{in} \quad \dots (1)$$

$$Q_{out} = V_0 A_0 = (2gy)^{1/2} \frac{\pi d^2}{4}$$

$$Q_{out} = [2 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.0368 \text{ m}]^{1/2} \frac{\pi}{4} \times (0.00735)^2 \text{ m}^2$$

$$Q_{out} = 3.61 \times 10^{-5} \text{ m}^3/\text{s} \quad (0.130 \text{ m}^3/\text{hr})$$



From eq. (1)

$$\frac{dV}{dt} + Q_{out} = Q_{in}$$

$$V = \frac{1}{3} \text{ area of base} \times \text{altitude} = \frac{1}{3} \pi R^2 y$$

$$\text{Since } R = y \tan \theta, \quad V = \frac{1}{3} \pi y^3 \tan^2 \theta$$

$$\frac{dV}{dt} = \frac{1}{3} \pi \tan^2 \theta \times 3y^2 \frac{dy}{dt} = \pi y^2 \tan^2 \theta \frac{dy}{dt} = \pi R^2 \frac{dy}{dt}$$

$$\therefore \frac{dV}{dt} = \frac{Q_{in} - Q_{out}}{\pi R^2} = \frac{1}{\pi R^2} (Q_{in} - Q_{out})$$


$$= \frac{1}{\pi} \times (6.0294)^2 \text{ m}^2 \left( 3.75 \times 10^{-7} - 0.130 \right) \frac{\text{m}^3}{\text{hr}} \times \frac{\text{hr}}{3600 \text{ s}}$$

$$\frac{dy}{dt} = -0.0532 \text{ m/s} \quad (\text{surface moves downward})$$

### Problem 4.51

[Difficulty: 3]

**4.51** A conical funnel of half-angle  $\theta = 15^\circ$ , with maximum diameter  $D = 70$  mm and height  $H$ , drains through a hole (diameter  $d = 3.12$  mm) in its bottom. The speed of the liquid leaving the funnel is approximately  $V = \sqrt{2gy}$ , where  $y$  is the height of the liquid free surface above the hole. Find the rate of change of surface level in the funnel at the instant when  $y = H/2$ .



Solution: Apply conservation of mass.

(1) Choose CV with top just below surface level.

Basic equation:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

Assumptions: (1)  $\rho = \text{constant}$ ,  $\vec{v} = \text{const}$ , so  $\frac{\partial}{\partial t} = 0$   
 (2) Uniform flow at each section.

For CV(1):  $0 = \left\{ -\rho V_s A_s \right\} + \left\{ +\rho V_e A_e \right\}$  or  $V_s = V_e \frac{A_e}{A_s}$

Thus  $V_s = V_e \left(\frac{d}{D/2}\right)^2 = \sqrt{2gH} \cdot 4 \left(\frac{d}{D}\right)^2 = 4\sqrt{gH} \left(\frac{d}{D}\right)^2 = -\frac{dy}{dt}$  (since  $y$  decreases)

But  $\tan \theta = \frac{D/2}{H}$  so  $H = \frac{D}{2 \tan \theta} = \frac{0.070 \text{ m}}{2 \tan 15^\circ} = 0.131 \text{ m}$

Substituting,

$\frac{dy}{dt} = -4 \sqrt{9.81 \frac{\text{m}}{\text{s}^2} \times 0.131 \text{ m}} \left(\frac{0.00312 \text{ m}}{0.070 \text{ m}}\right)^2 \cdot 1000 \frac{\text{mm}}{\text{m}} = -9.01 \text{ mm/s}$

Alternate solution: Choose CV(2) enclosing entire funnel.

Basic equation:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

Assumptions: (1)  $\rho = \text{constant}$ , but  $\vec{v}$  changes (Note:  $\vec{v} = \frac{\pi}{3} r^2 h$  for a cone.)  
 (2) Neglect air  
 (3) Uniform flow at outlet section

Then  $0 = \rho \frac{\partial}{\partial t} V_{H2O} + \left\{ +\rho V_e A_e \right\}$  or  $\frac{dV}{dt} = -V_e A_e$

The volume of water is  $V = \frac{\pi}{3} r^2 h = \frac{\pi}{3} (y \tan \theta)^2 y = \frac{\pi y^3 \tan^2 \theta}{3}$

so  $\frac{dV}{dt} = \pi y^2 \tan^2 \theta \frac{dy}{dt} = \pi \left(\frac{D}{4}\right)^2 \frac{dy}{dt}$  and  $\frac{\pi D^2}{16} \frac{dy}{dt} = -V_e A_e = -\sqrt{2gy} \frac{\pi d^2}{4}$

Finally, since  $y = H/2$ ,  $\frac{dy}{dt} = -4\sqrt{2gH} \left(\frac{d}{D}\right)^2$  as before.

{ Note: Flow is not steady in either CV. The  $\frac{\partial}{\partial t}$  term vanishes for CV(1) because there is no change in mass inside the CV. }


### Problem 4.52

[Difficulty: 3]

4.52 Water flows steadily past a porous flat plate. Constant suction is applied along the porous section. The velocity profile at section  $cd$  is

$$\frac{u}{U_\infty} = 3\left[\frac{y}{\delta}\right] - 2\left[\frac{y}{\delta}\right]^{3/2}$$

Evaluate the mass flow rate across section  $bc$ .



Basic equation:

$$0 = \frac{\partial}{\partial t} \int_{cv} \rho dV + \int_{cs} \rho \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Steady flow  
 (2) Incompressible flow  
 (3)  $\vec{V} = -v_0 \hat{j}$  along  $da$

Then

$$0 = \int_{cs} \rho \vec{V} \cdot d\vec{A} = \int_{ab} \rho \vec{V} \cdot d\vec{A} + \dot{m}_{bc} + \int_{cd} \rho \vec{V} \cdot d\vec{A} + \int_{da} \rho \vec{V} \cdot d\vec{A}$$

or 
$$0 = -\rho U_\infty w \delta + \dot{m}_{bc} + \int_0^\delta \rho U_\infty \left[ 3\left(\frac{y}{\delta}\right) - 2\left(\frac{y}{\delta}\right)^{3/2} \right] w dy + \rho v_0 w L$$

Thus

$$\dot{m}_{bc} = \rho U_\infty w \delta - \rho U_\infty w \delta \int_0^1 \left[ 3\left(\frac{y}{\delta}\right) - 2\left(\frac{y}{\delta}\right)^{3/2} \right] d\left(\frac{y}{\delta}\right) - \rho v_0 w L$$

$$= \rho w \left\{ U_\infty \delta - U_\infty \delta \left[ \frac{3}{2} \left(\frac{y}{\delta}\right)^2 - \frac{2}{2.5} \left(\frac{y}{\delta}\right)^{5/2} \right]_0^1 - v_0 L \right\}$$

$$= \rho w \left[ U_\infty \delta - U_\infty \delta \left( \frac{3}{2} - \frac{2}{2.5} \right) - v_0 L \right] = \rho w (0.3 U_\infty \delta - v_0 L)$$

$$= \frac{999 \text{ kg}}{\text{m}^3} \times 1.5 \text{ m} \left( 0.3 \times 3 \frac{\text{m}}{\text{s}} \times 0.0015 \text{ m} - 0.0002 \frac{\text{m}}{\text{s}} \times 2 \text{ m} \right)$$

$$\dot{m}_{bc} = 1.42 \text{ kg/s} \quad (\dot{m} > 0, \text{ so out of cv})$$

$\dot{m}_{bc}$



### Problem 4.54

[Difficulty: 4]


4.54 A tank of fixed volume contains brine with initial density,  $\rho_i$ , greater than water. Pure water enters the tank steadily and mixes thoroughly with the brine in the tank. The liquid level in the tank remains constant. Derive expressions for (a) the rate of change of density of the liquid mixture in the tank and (b) the time required for the density to reach the value  $\rho_f$ , where  $\rho_i > \rho_f > \rho_{H_2O}$ .

Solution: Apply conservation of mass using the CV shown.

Basic equation:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

Assumptions: (1)  $V_{\text{tank}} = \text{constant}$   
 (2)  $\rho$  uniform in tank  
 (3) Uniform flows at inlet and outlet sections



Then  $V_1 A_1 = V_2 A_2$  since tank volume is constant, and

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \rho VA - \rho_{H_2O} VA = \frac{\partial}{\partial t} \rho V + (\rho - \rho_{H_2O}) VA = V \frac{d\rho}{dt} + (\rho - \rho_{H_2O}) VA$$

So that

$$\frac{d\rho}{dt} = - \frac{(\rho - \rho_{H_2O}) VA}{V}$$

$\frac{d\rho}{dt}$

Separating variables,

$$\frac{d\rho}{\rho - \rho_{H_2O}} = - \frac{VA}{V} dt$$

Integrating from  $\rho_i$  at  $t = 0$  to  $\rho_f$  at  $t$ ,

$$\int_{\rho_i}^{\rho_f} \frac{d\rho}{\rho - \rho_{H_2O}} = \ln(\rho - \rho_{H_2O}) \Big|_{\rho_i}^{\rho_f} = \ln\left(\frac{\rho_f - \rho_{H_2O}}{\rho_i - \rho_{H_2O}}\right) = \int_0^t - \frac{VA}{V} dt = - \frac{VA}{V} t$$

Finally,

$$t = - \frac{V}{VA} \ln\left(\frac{\rho_f - \rho_{H_2O}}{\rho_i - \rho_{H_2O}}\right)$$

$t$

{ Note that  $\rho_f \rightarrow \rho_{H_2O}$  asymptotically as  $t \rightarrow \infty$ . }

## Problem 4.55

[Difficulty: 4]

**4.55** A conical funnel of half-angle  $\theta = 30^\circ$  drains through a small hole of diameter  $d = 0.25$  in. at the vertex. The speed of the liquid leaving the funnel is approximately  $V = \sqrt{2gy}$ , where  $y$  is the height of the liquid free surface above the hole. The funnel initially is filled to height  $y_0 = 12$  in. Obtain an expression for the time,  $t$ , for the funnel to completely drain, and evaluate. Find the time to drain from 12 in. to 6 in. (a change in depth of 6 in.), and from 6 in. to completely empty (also a change in depth of 6 in.). Can you explain the discrepancy in these times? Plot the drain time  $t$  as a function diameter  $d$  for  $d$  ranging from 0.25 in. to 0.5 in.

**Given:** Data on draining of a funnel

**Find:** Formula for drain time; time to drain from 12 in to 6 in; plot drain time versus hole diameter

**Solution:**

Basic equation 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Uniform flow 2) Incompressible flow 3) Neglect air density

Treating the funnel as the CV the basic equation becomes

$$\frac{\partial}{\partial t} \int_0^y \rho \cdot A_{\text{funnel}} dy + \rho \cdot V \cdot A_{\text{opening}} = 0$$

For the funnel 
$$A_{\text{funnel}} = \pi \cdot r^2 = \pi \cdot (y \cdot \tan(\theta))^2$$

Hence 
$$\rho \cdot \pi \cdot (\tan(\theta))^2 \cdot \frac{\partial}{\partial t} \int_0^y y^2 dy + \rho \cdot V \cdot \frac{\pi}{4} \cdot d^2 = 0 \quad \text{or} \quad (\tan(\theta))^2 \cdot \frac{d}{dt} \left( \frac{y^3}{3} \right) = -\sqrt{2 \cdot g \cdot y} \cdot \frac{d^2}{4}$$

Then 
$$(\tan(\theta))^2 \cdot y^2 \cdot \frac{dy}{dt} = -\sqrt{2 \cdot g \cdot y} \cdot \frac{d^2}{4}$$

Separating variables 
$$y^{\frac{3}{2}} \cdot dy = -\frac{\sqrt{2 \cdot g \cdot d^2}}{4 \cdot \tan(\theta)^2} \cdot dt$$

Hence 
$$\int_{y_0}^0 y^{\frac{3}{2}} dy = -\frac{\sqrt{2 \cdot g \cdot d^2}}{4 \cdot \tan(\theta)^2} \cdot t \quad \text{or} \quad \frac{2}{5} \cdot y_0^{\frac{5}{2}} = \frac{\sqrt{2 \cdot g \cdot d^2}}{4 \cdot \tan(\theta)^2} \cdot t$$


Solving for  $t$  
$$t = \frac{8}{5} \cdot \frac{\tan(\theta)^2 \cdot y_0^{\frac{5}{2}}}{\sqrt{2 \cdot g \cdot d}} \quad \text{and using the given data} \quad t = 2.55 \cdot \text{min}$$

To find the time to drain from 12 in to 6 in., we use the time equation with the two depths; this finds the time to drain from 12 in and 6 in, so the difference is the time we want

$$y_1 = 6 \cdot \text{in} \quad \Delta t_1 = \frac{8}{5} \cdot \frac{\tan(\theta)^2 \cdot y_0^{\frac{5}{2}}}{\sqrt{2 \cdot g \cdot d^2}} - \frac{8}{5} \cdot \frac{\tan(\theta)^2 \cdot y_1^{\frac{5}{2}}}{\sqrt{2 \cdot g \cdot d^2}} \quad \Delta t_1 = 2.1 \cdot \text{min}$$

$$\Delta t_2 = \frac{8}{5} \cdot \frac{\tan(\theta)^2 \cdot y_1^{\frac{5}{2}}}{\sqrt{2 \cdot g \cdot d^2}} \quad \Delta t_2 = 0.451 \cdot \text{min} \quad \text{Note that} \quad \Delta t_1 + \Delta t_2 = 2.55 \cdot \text{min}$$

The second time is a bit longer because although the flow rate decreases, the area of the funnel does too.



## Problem 4.56

[Difficulty: 4]

**4.56** For the funnel of Problem 4.55, find the diameter  $d$  required if the funnel is to drain in  $t = 1$  min. from an initial depth  $y_0 = 12$  in. Plot the diameter  $d$  required to drain the funnel in 1 min as a function of initial depth  $y_0$ , for  $y_0$  ranging from 1 in. to 24 in.

**Given:** Data on draining of a funnel

**Find:** Diameter that will drain in 1 min.; plot diameter versus depth  $y_0$

**Solution:**

Basic equation 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: 1) Uniform flow 2) Incompressible flow 3) Neglect air density

Treating the funnel as the CV the basic equation becomes

$$\frac{\partial}{\partial t} \int_0^y \rho \cdot A_{\text{funnel}} dy + \rho \cdot V \cdot A_{\text{opening}} = 0$$


For the funnel 
$$A_{\text{funnel}} = \pi \cdot r^2 = \pi \cdot (y \cdot \tan(\theta))^2$$

Hence 
$$\rho \cdot \pi \cdot (\tan(\theta))^2 \cdot \frac{\partial}{\partial t} \int_0^y y^2 dy + \rho \cdot V \cdot \frac{\pi}{4} \cdot d^2 = 0 \quad \text{or} \quad (\tan(\theta))^2 \cdot \frac{d}{dt} \left( \frac{y^3}{3} \right) = -\sqrt{2 \cdot g \cdot y} \cdot \frac{d^2}{4}$$

Then 
$$(\tan(\theta))^2 \cdot y^2 \cdot \frac{dy}{dt} = -\sqrt{2 \cdot g \cdot y} \cdot \frac{d^2}{4} \quad \text{Separating variables} \quad y^{\frac{3}{2}} \cdot dy = -\frac{\sqrt{2 \cdot g} \cdot d^2}{4 \cdot \tan(\theta)^2} \cdot dt$$

Hence 
$$\int_{y_0}^0 y^{\frac{3}{2}} dy = -\frac{\sqrt{2 \cdot g} \cdot d}{4 \cdot \tan(\theta)^2} \cdot t \quad \text{or} \quad \frac{2}{5} \cdot y_0^{\frac{5}{2}} = \frac{\sqrt{2 \cdot g} \cdot d}{4 \cdot \tan(\theta)^2} \cdot t$$

Solving for  $d$  
$$d = \sqrt{\frac{8}{5} \cdot \frac{\tan(\theta)^2 \cdot y_0^{\frac{5}{2}}}{\sqrt{2 \cdot g} \cdot t}} \quad \text{and using the given data, for } t = 1 \text{ min} \quad d = 0.399 \text{ in}$$








## Problem 4.58

[Difficulty: 3]

**4.58** Evaluate the net rate of flux of momentum out through the control surface of Problem 4.24.



**Given:** Data on flow through a control surface

**Find:** Net rate of momentum flux

**Solution:**

Basic equation: We need to evaluate  $\int_{CS} \vec{V} \rho \vec{V} \cdot d\vec{A}$

Assumptions: 1) Uniform flow at each section

From Problem 4.24  $V_1 = 10 \cdot \frac{\text{ft}}{\text{s}}$   $A_1 = 0.5 \cdot \text{ft}^2$   $V_2 = 20 \cdot \frac{\text{ft}}{\text{s}}$   $A_2 = 0.1 \cdot \text{ft}^2$   $A_3 = 0.6 \cdot \text{ft}^2$   $V_3 = 5 \cdot \frac{\text{ft}}{\text{s}}$  It is an outlet

Then for the control surface

$$\begin{aligned} \int_{CS} \vec{V} \rho \vec{V} \cdot d\vec{A} &= \vec{V}_1 \rho \vec{V}_1 \cdot \vec{A}_1 + \vec{V}_2 \rho \vec{V}_2 \cdot \vec{A}_2 + \vec{V}_3 \rho \vec{V}_3 \cdot \vec{A}_3 \\ &= V_1 \hat{i} \rho (\vec{V}_1 \cdot \vec{A}_1) + V_2 \hat{j} \rho (\vec{V}_2 \cdot \vec{A}_2) + [V_3 \sin(60) \hat{i} - V_3 \cos(60) \hat{j}] \rho (\vec{V}_3 \cdot \vec{A}_3) \\ &= -V_1 \hat{i} \rho V_1 A_1 + V_2 \hat{j} \rho V_2 A_2 + [V_3 \sin(60) \hat{i} - V_3 \cos(60) \hat{j}] \rho V_3 A_3 \\ &= \rho [-V_1^2 A_1 + V_3^2 A_3 \sin(60)] \hat{i} + \rho [V_2^2 A_2 - V_3^2 A_3 \cos(60)] \hat{j} \end{aligned}$$

Hence the x component is

$$\rho [-V_1^2 A_1 + V_3^2 A_3 \sin(60)] = 65 \cdot \frac{\text{lbm}}{\text{ft}^3} \times (-10^2 \times 0.5 + 5^2 \times 0.6 \times \sin(60 \cdot \text{deg})) \cdot \frac{\text{ft}^4}{\text{s}^2} \times \frac{\text{lbm} \cdot \text{s}^2}{\text{lbm} \cdot \text{ft}} = -2406 \cdot \text{lbm} \cdot \text{ft} / \text{s}^2$$


and the y component is

$$\rho [V_2^2 A_2 - V_3^2 A_3 \cos(60)] = 65 \cdot \frac{\text{lbm}}{\text{ft}^3} \times (20^2 \times 0.1 - 5^2 \times 0.6 \times \cos(60 \cdot \text{deg})) \cdot \frac{\text{ft}^4}{\text{s}^2} \times \frac{\text{lbm} \cdot \text{s}^2}{\text{lbm} \cdot \text{ft}} = 2113 \cdot \text{lbm} \cdot \text{ft} / \text{s}^2$$

## Problem 4.59

[Difficulty: 3]

**4.59** For the conditions of Problem 4.34, evaluate the ratio of the  $x$ -direction momentum flux at the channel outlet to that at the inlet.



**Given:** Data on flow at inlet and outlet of channel

**Find:** Ratio of outlet to inlet momentum flux

**Solution:**

Basic equation: Momentum flux in  $x$  direction at a section

$$mf_x = \int_A u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at 1 and 2  $mf_{x1} = U \cdot \rho \cdot (-U \cdot 2 \cdot h) \cdot w$

$$|mf_{x1}| = 2 \cdot \rho \cdot w \cdot U^2 \cdot h$$

Hence

$$mf_{x2} = \int_{-h}^h \rho \cdot u^2 \cdot w \, dy = \rho \cdot w \cdot u_{\max}^2 \cdot \int_{-h}^h \left[ 1 - \left( \frac{y}{h} \right)^2 \right]^2 dy = \rho \cdot w \cdot u_{\max}^2 \cdot \int_{-h}^h \left[ 1 - 2 \cdot \left( \frac{y}{h} \right)^2 + \left( \frac{y}{h} \right)^4 \right] dy$$

$$|mf_{x2}| = \rho \cdot w \cdot u_{\max}^2 \cdot \left( 2 \cdot h - \frac{4}{3} \cdot h + \frac{2}{5} \cdot h \right) = \rho \cdot w \cdot u_{\max}^2 \cdot \frac{16}{15} \cdot h$$

Then the ratio of momentum fluxes is

$$\frac{|mf_{x2}|}{|mf_{x1}|} = \frac{\frac{16}{15} \cdot \rho \cdot w \cdot u_{\max}^2 \cdot h}{2 \cdot \rho \cdot w \cdot U^2 \cdot h} = \frac{8}{15} \cdot \left( \frac{u_{\max}}{U} \right)^2$$

But, from Problem 4.34


$$u_{\max} = \frac{3}{2} \cdot U \quad \frac{|mf_{x2}|}{|mf_{x1}|} = \frac{8}{15} \cdot \left( \frac{\frac{3}{2} \cdot U}{U} \right)^2 = \frac{6}{5} = 1.2$$

Hence the momentum increases as it flows in the entrance region of the channel. This appears to contradict common sense, as friction should reduce flow momentum. What happens is the pressure drops significantly along the channel so the net force on the CV is to the right.

## Problem 4.60

[Difficulty: 3]

**4.60** For the conditions of Problem 4.35, evaluate the ratio of the  $x$ -direction momentum flux at the pipe outlet to that at the inlet.



**Given:** Data on flow at inlet and outlet of pipe

**Find:** Ratio of outlet to inlet momentum flux

**Solution:**

Basic equation: Momentum flux in  $x$  direction at a section  $mf_x = \int_A u \rho \vec{V} \cdot dA$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating at 1 and 2  $mf_{x1} = U \cdot \rho \cdot (-U \cdot \pi \cdot R^2)$   $|mf_{x1}| = \rho \cdot \pi \cdot U^2 \cdot R^2$

Hence  $mf_{x2} = \int_0^R \rho \cdot u^2 \cdot 2 \cdot \pi \cdot r \, dr = 2 \cdot \rho \cdot \pi \cdot u_{\max}^2 \cdot \int_0^R r \cdot \left[ 1 - \left( \frac{r}{R} \right)^2 \right]^2 \, dr = 2 \cdot \rho \cdot \pi \cdot u_{\max}^2 \cdot \int_0^R \left( r - 2 \cdot \frac{r^3}{R^2} + \frac{r^5}{R^4} \right) \, dr$

$$|mf_{x2}| = 2 \cdot \rho \cdot \pi \cdot u_{\max}^2 \cdot \left( \frac{R^2}{2} - \frac{R^2}{2} + \frac{R^2}{6} \right) = \rho \cdot \pi \cdot u_{\max}^2 \cdot \frac{R^2}{3}$$

Then the ratio of momentum fluxes is

$$\frac{|mf_{x2}|}{|mf_{x1}|} = \frac{\frac{1}{3} \cdot \rho \cdot \pi \cdot u_{\max}^2 \cdot R^2}{\rho \cdot \pi \cdot U^2 \cdot R^2} = \frac{1}{3} \cdot \left( \frac{u_{\max}}{U} \right)^2$$


But, from Problem 4.35  $u_{\max} = 2 \cdot U$   $\frac{|mf_{x2}|}{|mf_{x1}|} = \frac{1}{3} \cdot \left( \frac{2 \cdot U}{U} \right)^2 = \frac{4}{3} = 1.33$

Hence the momentum increases as it flows in the entrance region of the pipe. This appears to contradict common sense, as friction should reduce flow momentum. What happens is the pressure drops significantly along the pipe so the net force on the CV is to the right.

## Problem 4.61

[Difficulty: 3]

**4.61** Evaluate the net momentum flux through the bend of Problem 4.38, if the depth normal to the diagram is  $w = 1$  m.



**Given:** Data on flow through a bend

**Find:** Find net momentum flux

**Solution:**

Basic equations  $\int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$       Momentum fluxes:  $mf_x = \int_{CS} u \rho \vec{V} \cdot d\vec{A}$        $mf_y = \int_{CS} v \rho \vec{V} \cdot d\vec{A}$

Assumptions: 1) Steady flow 2) Incompressible flow

Evaluating mass flux at 1, 2 and 3 
$$-\int_0^{h_1} V_1(y) \cdot w \, dy + V_2 \cdot w \cdot h_2 + V_3 \cdot w \cdot h_3 = 0$$

or 
$$V_3 \cdot h_3 = \int_0^{h_1} V_1(y) \, dy - V_2 \cdot h_2 = \int_0^{h_1} V_{1max} \cdot \frac{y}{h_1} \, dy - V_2 \cdot h_2 = \frac{V_{1max}}{h_1} \cdot \frac{h_1^2}{2} - V_2 \cdot h_2$$

Hence 
$$V_{1max} = \frac{2}{h_1} \cdot (V_3 \cdot h_3 + V_2 \cdot h_2) \quad \text{Using given data} \quad V_{1max} = 3.8 \frac{m}{s}$$

For the x momentum, evaluating at 1, 2 and 3

$$mf_x = -\int_0^{h_1} V_1(y) \cdot \rho \cdot V_1(y) \cdot w \, dy + V_3 \cdot \cos(\theta) \cdot \rho \cdot V_3 \cdot h_3 \cdot w$$

$$mf_x = -\int_0^{h_1} \left( V_{1max} \cdot \frac{y}{h_1} \right)^2 \cdot \rho \cdot w \, dy + V_3^2 \cdot \rho \cdot h_3 \cdot \cos(\theta) \cdot w = -\frac{V_{1max}^2}{h_1^2} \cdot \frac{h_1^3}{3} \cdot \rho \cdot w + V_3^2 \cdot \rho \cdot h_3 \cdot w \cdot \cos(\theta)$$

$$mf_x = \rho \cdot w \cdot \left( -V_{1max}^2 \cdot \frac{h_1}{3} + V_3^2 \cdot \cos(\theta) \cdot h_3 \right) \quad \text{Using given data} \quad mf_x = 841 \text{ N}$$

For the y momentum, evaluating at 1, 2 and 3


$$mf_y = -V_2 \cdot \rho \cdot V_2 \cdot h_2 \cdot w + V_3 \cdot \sin(\theta) \cdot \rho \cdot V_3 \cdot h_3 \cdot w$$

$$mf_y = \rho \cdot w \cdot \left( -V_2^2 \cdot h_2 - V_3^2 \cdot \sin(\theta) \cdot h_3 \right) \quad \text{Using given data} \quad mf_y = -2075 \text{ N}$$

### Problem 4.62

[Difficulty: 2]

4.62 Evaluate the net momentum flux through the channel of Problem 4.39. Would you expect the outlet pressure to be higher, lower, or the same as the inlet pressure? Why?



Solution:

The momentum flux is defined as  $m.f. = \int \vec{v} \cdot (p\vec{v} \cdot d\vec{A})$

The net momentum flux through the CV is

$$m.f. = \int_{A_1} \vec{v} \cdot (p\vec{v} \cdot d\vec{A}) + \int_{A_2} \vec{v} \cdot (p\vec{v} \cdot d\vec{A})$$

where  $\vec{v}_1 = U\hat{i}$ ,  $\vec{v}_2 = \left\{ U_{max} - (U_{max} - U_{min}) \frac{x}{h} \right\} \hat{j}$   
 $\vec{v}_2 = \left\{ 2U_{min} - U_{min} \frac{x}{h} \right\} \hat{j} = U_{min} \left( 2 - \frac{x}{h} \right) \hat{j}$

Assumptions: (1) incompressible flow  
 (2) uniform flow at  $\odot$  (given).

$$\int_{A_1} \vec{v} \cdot (p\vec{v} \cdot d\vec{A}) = \vec{v}_1 \cdot (-p\vec{v}_1 A) = -pU^2 h^2 \hat{i} \quad \dots (1)$$

$$\begin{aligned} \int_{A_2} \vec{v} \cdot (p\vec{v} \cdot d\vec{A}) &= \int_0^h U_{min} \left( 2 - \frac{x}{h} \right) \hat{j} \cdot p U_{min} \left( 2 - \frac{x}{h} \right) h dx \\ &= \hat{j} p U_{min}^2 h \int_0^h \left( 4 - 4 \frac{x}{h} + \frac{x^2}{h^2} \right) dx \\ &= \hat{j} p U_{min}^2 h \left[ 4x - 2 \frac{x^2}{h} + \frac{x^3}{3h^2} \right]_0^h = \hat{j} p U_{min}^2 h \left[ 4h - 2h + \frac{h}{3} \right] \\ &= \hat{j} \frac{7}{3} p U_{min}^2 h^2 \end{aligned}$$

$$\therefore m.f. = -pU^2 h^2 \hat{i} + \frac{7}{3} p U_{min}^2 h^2 \hat{j} = ph^2 \left[ -U^2 \hat{i} + \frac{7}{3} U_{min}^2 \hat{j} \right]$$

Evaluating

$$m.f. = 999 \frac{kg}{m^3} \times (0.0755)^2 m^2 \left[ -(1.5)^2 \frac{m^2}{s^2} \hat{i} + \frac{7}{3} (5)^2 \frac{m^2}{s^2} \hat{j} \right] \times \frac{N \cdot s^2}{kg \cdot m}$$

$$m.f. = -320 \hat{i} + 332 \hat{j} \text{ N} \quad \text{m.f.}$$

For viscous (real) flow friction causes a pressure drop in the direction of flow (Chapter 8)

For flow in a bend streamline curvature results in a pressure gradient normal to the flow (Chapter 6)

12-752  
 20-351  
 43-358  
 43-359  
 43-360  
 43-361  
 500 SHEETS FULLER 5 SQUARE  
 500 SHEETS FULLER 6 SQUARE  
 500 SHEETS FULLER 7 SQUARE  
 500 SHEETS FULLER 8 SQUARE  
 500 SHEETS FULLER 9 SQUARE  
 500 SHEETS FULLER 10 SQUARE  
 100 RECYCLED WHITE 5 SQUARE  
 100 RECYCLED WHITE 6 SQUARE  
 MADE IN U.S.A.



## Problem 4.63

[Difficulty: 2]

**4.63** Water jets are being used more and more for metal cutting operations. If a pump generates a flow of 1 gpm through an orifice of 0.01 in. diameter, what is the average jet speed? What force (lbf) will the jet produce at impact, assuming as an approximation that the water sprays sideways after impact?


**Given:** Water jet hitting object

**Find:** Jet speed; Force generated

**Solution:**

Basic equations: Continuity and Momentum flux in x direction

$$\int_{CS} \vec{V} \cdot d\vec{A} = 0 \quad F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$



Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure throughout 4) Uniform flow

Given data       $Q = 1 \cdot \text{gpm}$        $d = 0.01 \cdot \text{in}$        $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$

Using continuity       $Q = V \cdot A = U \cdot \frac{\pi}{4} \cdot d^2$       Using data       $U = \frac{Q}{\frac{\pi}{4} \cdot d^2}$        $U = 4085 \frac{\text{ft}}{\text{s}}$        $U = 2785 \cdot \text{mph}$       **FAST!**

Using momentum       $R_x = u_1 \cdot \rho \cdot (-u_1 \cdot A_1) = -\rho \cdot U^2 \cdot A = -\rho \cdot U^2 \cdot \frac{\pi \cdot D^2}{4}$

Hence       $R_x = -\rho \cdot U^2 \cdot \frac{\pi \cdot d^2}{4}$

$$R_x = -1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(4085 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{\pi \cdot \left(\frac{.01}{12} \cdot \text{ft}\right)^2}{4} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = -17.7 \cdot \text{lbf}$$

## Problem 4.64

[Difficulty: 1]

**4.64** Considering that in the fully developed region of a pipe, the integral of the axial momentum is the same at all cross sections, explain the reason for the pressure drop along the pipe.

**Given:** Fully developed flow in pipe

**Find:** Why pressure drops if momentum is constant

**Solution:**

Basic equation: Momentum flux in x direction

$$F_x = F_{\dot{m}} + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Fully developed flow

Hence 
$$F_x = \frac{\Delta p}{L} - \tau_w \cdot A_s = 0 \quad \Delta p = L \cdot \tau_w \cdot A_s$$


where  $\Delta p$  is the pressure drop over length  $L$ ,  $\tau_w$  is the wall friction and  $A_s$  is the pipe surface area

The sum of forces in the x direction is zero. The friction force on the fluid is in the negative x direction, so the net pressure force must be in the positive direction. Hence pressure drops in the x direction so that pressure and friction forces balance

## Problem 4.65

[Difficulty: 2]

**4.65** Find the force required to hold the plug in place at the exit of the water pipe. The flow rate is  $1.5 \text{ m}^3/\text{s}$ , and the upstream pressure is  $3.5 \text{ MPa}$ .



**Given:** Data on flow and system geometry

**Find:** Force required to hold plug

**Solution:**

Basic equation: 
$$F_x = F_{\dot{Q}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

The given data is  $D_1 = 0.25 \text{ m}$        $D_2 = 0.2 \text{ m}$        $Q = 1.5 \frac{\text{m}^3}{\text{s}}$        $p_1 = 3500 \text{ kPa}$        $\rho = 999 \frac{\text{kg}}{\text{m}^3}$

Then  $A_1 = \frac{\pi \cdot D_1^2}{4}$        $A_1 = 0.0491 \text{ m}^2$        $V_1 = \frac{Q}{A_1}$        $V_1 = 30.6 \frac{\text{m}}{\text{s}}$

$A_2 = \frac{\pi}{4} \cdot (D_1^2 - D_2^2)$        $A_2 = 0.0177 \text{ m}^2$        $V_2 = \frac{Q}{A_2}$        $V_2 = 84.9 \frac{\text{m}}{\text{s}}$

Applying the basic equation

$$-F + p_1 \cdot A_2 - p_2 \cdot A_2 = 0 + V_1 \cdot (-\rho \cdot V_1 \cdot A_1) + V_2 \cdot (\rho \cdot V_2 \cdot A_2) \quad \text{and} \quad p_2 = 0 \quad (\text{gage})$$


Hence 
$$F = p_1 \cdot A_1 + \rho \cdot (V_1^2 \cdot A_1 - V_2^2 \cdot A_2)$$

$$F = 3500 \times \frac{\text{kN}}{\text{m}^2} \cdot 0.0491 \cdot \text{m}^2 + 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ \left( 30.6 \cdot \frac{\text{m}}{\text{s}} \right)^2 \cdot 0.0491 \cdot \text{m}^2 - \left( 84.9 \cdot \frac{\text{m}}{\text{s}} \right)^2 \cdot 0.0177 \cdot \text{m}^2 \right] \quad F = 90.4 \cdot \text{kN}$$

## Problem 4.66

[Difficulty: 2]

**4.66** A jet of water issuing from a stationary nozzle at 10 m/s ( $A_j = 0.1 \text{ m}^2$ ) strikes a turning vane mounted on a cart as shown. The vane turns the jet through angle  $\theta = 40^\circ$ . Determine the value of  $M$  required to hold the cart stationary. If the vane angle  $\theta$  is adjustable, plot the mass,  $M$ , needed to hold the cart stationary versus  $\theta$  for  $0 \leq \theta \leq 180^\circ$ .



**Given:** Nozzle hitting stationary cart

**Find:** Value of  $M$  to hold stationary; plot  $M$  versus  $\theta$

**Solution:**


Basic equation: Momentum flux in x direction for the tank

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \sum_{CS} u \rho \vec{V} \cdot \vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure throughout 4) Uniform flow 5) Exit velocity is  $V$

Hence 
$$R_x = -M \cdot g = V \cdot \rho \cdot (-V \cdot A) + V \cdot \cos(\theta) \cdot (V \cdot A) = \rho \cdot V^2 \cdot A \cdot (\cos(\theta) - 1) \quad M = \frac{\rho \cdot V^2 \cdot A}{g} \cdot (1 - \cos(\theta))$$

When  $\theta = 40^\circ$  
$$M = \frac{\text{s}^2}{9.81 \cdot \text{m}} \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(10 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times 0.1 \cdot \text{m}^2 \times (1 - \cos(40 \cdot \text{deg})) \quad M = 238 \text{ kg}$$




This graph can be plotted in *Excel*

## Problem 4.67

[Difficulty: 2]

**4.67** A large tank of height  $h = 1$  m and diameter  $D = 0.75$  m is affixed to a cart as shown. Water issues from the tank through a nozzle of diameter  $d = 15$  mm. The speed of the liquid leaving the tank is approximately  $V = \sqrt{2gy}$ , where  $y$  is the height from the nozzle to the free surface. Determine the tension in the wire when  $y = 0.9$  m. Plot the tension in the wire as a function of water depth for  $0 \leq y \leq 0.9$  m.



**Given:** Large tank with nozzle and wire

**Find:** Tension in wire; plot for range of water depths

**Solution:**


Basic equation: Momentum flux in x direction for the tank

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \sum_{CS} u \rho \vec{V} \cdot \vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure throughout 4) Uniform flow

Hence 
$$R_x = T = V \cdot \rho \cdot (V \cdot A) = \rho \cdot V^2 \cdot A = \rho \cdot (2 \cdot g \cdot y) \cdot \frac{\pi \cdot d^2}{4} \quad T = \frac{1}{2} \cdot \rho \cdot g \cdot y \cdot \pi \cdot d^2 \quad T \text{ is linear with } y!$$

When  $y = 0.9$  m 
$$T = \frac{\pi}{2} \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.9 \cdot \text{m} \times (0.015 \cdot \text{m})^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad T = 3.12 \text{ N}$$




This graph can be plotted in *Excel*

## Problem 4.68

[Difficulty: 2]

**4.68** A circular cylinder inserted across a stream of flowing water deflects the stream through angle  $\theta$ , as shown. (This is termed the “Coanda effect.”) For  $a = 12.5$  mm,  $b = 2.5$  mm,  $V = 3$  m/s, and  $\theta = 20^\circ$ , determine the horizontal component of the force on the cylinder caused by the flowing water.



**Given:** Water flowing past cylinder

**Find:** Horizontal force on cylinder

**Solution:**

Basic equation: Momentum flux in x direction


$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \sum_{CS} u \rho \vec{V} \cdot \vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure throughout 4) Uniform flow

Hence  $R_x = u_1 \cdot \rho \cdot (-u_1 \cdot A_1) + u_2 \cdot \rho \cdot (u_2 \cdot A_2) = 0 + \rho \cdot (-V \cdot \sin(\theta)) \cdot (V \cdot a \cdot b)$   $R_x = -\rho \cdot V^2 \cdot a \cdot b \cdot \sin(\theta)$

For given data  $R_x = -1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(3 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times 0.0125 \cdot \text{m} \times 0.0025 \cdot \text{m} \times \sin(20 \cdot \text{deg}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $R_x = -0.0962 \text{ N}$


This is the force on the fluid (it is to the left). Hence the force on the cylinder is  $R_x = -R_x$   $R_x = 0.0962 \text{ N}$



## Problem 4.69

[Difficulty: 2]

**4.69** A vertical plate has a sharp-edged orifice at its center. A water jet of speed  $V$  strikes the plate concentrically. Obtain an expression for the external force needed to hold the plate in place, if the jet leaving the orifice also has speed  $V$ . Evaluate the force for  $V = 15$  ft/s,  $D = 4$  in., and  $d = 1$  in. Plot the required force as a function of diameter ratio for a suitable range of diameter  $d$ .




**Given:** Water jet hitting plate with opening

**Find:** Force generated on plate; plot force versus diameter  $d$

**Solution:**

Basic equation: Momentum flux in x direction

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \sum_{CS} u \rho \vec{V} \cdot \vec{A}$$



Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure throughout 4) Uniform flow


Hence

$$R_x = u_1 \cdot \rho \cdot (-u_1 \cdot A_1) + u_2 \cdot \rho \cdot (u_2 \cdot A_2) = -\rho \cdot V^2 \cdot \frac{\pi \cdot D^2}{4} + \rho \cdot V^2 \cdot \frac{\pi \cdot d^2}{4} \quad R_x = -\frac{\pi \cdot \rho \cdot V^2 \cdot D^2}{4} \cdot \left[ 1 - \left( \frac{d}{D} \right)^2 \right] \quad (1)$$

For given data

$$R_x = -\frac{\pi}{4} \cdot 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 15 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \left( \frac{1}{3} \cdot \text{ft} \right)^2 \times \left[ 1 - \left( \frac{1}{4} \right)^2 \right] \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = -35.7 \cdot \text{lb} \cdot \text{f}$$

From Eq 1 (using the absolute value of  $R_x$ )




This graph can be plotted in *Excel*

## Problem 4.70

[Difficulty: 4]

**4.70** In a laboratory experiment, the water flow rate is to be measured catching the water as it vertically exits a pipe into an empty open tank that is on a zeroed balance. The tank is 10 m directly below the pipe exit, and the pipe diameter is 50 mm. One student obtains a flow rate by noting that after 60 s the volume of water (at 4°C) in the tank was 2 m<sup>3</sup>. Another student obtains a flow rate by reading the instantaneous weight accumulated of 3150 kg indicated at the 60-s point. Find the mass flow rate each student computes. Why do they disagree? Which one is more accurate? Show that the magnitude of the discrepancy can be explained by any concept you may have.



**Given:** Water flowing into tank

**Find:** Mass flow rates estimated by students. Explain discrepancy

**Solution:**

Basic equation: Momentum flux in y direction 
$$F_y = F_S + F_B = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure throughout 4) Uniform flow

For the first student 
$$m_1 = \frac{\rho \cdot V}{t} \quad \text{where } m_1 \text{ represents mass flow rate (software cannot render a dot above it!)}$$

$$m_1 = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 2 \cdot \text{m}^3 \times \frac{1}{60 \cdot \text{s}} \quad m_1 = 50.0 \frac{\text{kg}}{\text{s}}$$

For the second student 
$$m_2 = \frac{M}{t} \quad \text{where } m_2 \text{ represents mass flow rate}$$

$$m_2 = 3150 \cdot \text{kg} \times \frac{1}{60 \cdot \text{s}} \quad m_2 = 52.5 \frac{\text{kg}}{\text{s}}$$

There is a discrepancy because the second student is measuring instantaneous weight PLUS the force generated as the pipe flow momentum is "killed".

There is a discrepancy because the second student is measuring instantaneous weight PLUS the force generated as the pipe flow momentum is "killed". To analyse this we first need to find the speed at which the water stream enters the tank, 10 m below the pipe exit. This would be a good place to use the Bernoulli equation, but this problem is in the set before Bernoulli is covered. Instead we use the simple concept that the fluid is falling under gravity (a conclusion supported by the Bernoulli equation). From the equations for falling under gravity:

$$V_{\text{tank}}^2 = V_{\text{pipe}}^2 + 2 \cdot g \cdot h$$

where  $V_{\text{tank}}$  is the speed entering the tank,  $V_{\text{pipe}}$  is the speed at the pipe, and  $h = 10 \text{ m}$  is the distance traveled.  $V_{\text{pipe}}$  is obtained from

$$V_{\text{pipe}} = \frac{m_1}{\rho \cdot \frac{\pi \cdot d_{\text{pipe}}^2}{4}} = \frac{4 \cdot m_1}{\pi \cdot \rho \cdot d_{\text{pipe}}^2}$$

$$V_{\text{pipe}} = \frac{4}{\pi} \times 50 \cdot \frac{\text{kg}}{\text{s}} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \left( \frac{1}{0.05 \cdot \text{m}} \right)^2 \quad V_{\text{pipe}} = 25.5 \frac{\text{m}}{\text{s}}$$

Then

$$V_{\text{tank}} = \sqrt{V_{\text{pipe}}^2 + 2 \cdot g \cdot h} \quad V_{\text{tank}} = \sqrt{\left( 25.5 \cdot \frac{\text{m}}{\text{s}} \right)^2 + 2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 10\text{m}} \quad V_{\text{tank}} = 29.1 \frac{\text{m}}{\text{s}}$$

We can now use the y momentum equation for the CS shown above

$$R_y - W = -V_{\text{tank}} \cdot \rho \cdot (-V_{\text{tank}} \cdot A_{\text{tank}})$$

where  $A_{\text{tank}}$  is the area of the water flow as it enters the tank. But for the water flow

$$V_{\text{tank}} \cdot A_{\text{tank}} = V_{\text{pipe}} \cdot A_{\text{pipe}}$$

Hence

$$\Delta W = R_y - W = \rho \cdot V_{\text{tank}} \cdot V_{\text{pipe}} \cdot \frac{\pi \cdot d_{\text{pipe}}^2}{4}$$

This equation indicate the instantaneous difference  $\Delta W$  between the scale reading ( $R_y$ ) and the actual weight of water ( $W$ ) in the tank

$$\Delta W = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 29.1 \cdot \frac{\text{m}}{\text{s}} \times 25.5 \cdot \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.05 \cdot \text{m})^2 \quad \Delta W = 1457 \text{ N}$$

Indicated as a mass, this is

$$\Delta m = \frac{\Delta W}{g} \quad \Delta m = 149 \text{ kg}$$

Hence the scale overestimates the weight of water by 1457 N, or a mass of 149 kg

For the second student

$$M = 3150 \cdot \text{kg} - 149 \cdot \text{kg} \quad M = 3001 \text{ kg}$$

Hence

$$m_2 = \frac{M}{t} \quad \text{where } m_2 \text{ represents mass flow rate}$$


$$m_2 = 3001 \cdot \text{kg} \times \frac{1}{60 \cdot \text{s}} \quad m_2 = 50.0 \frac{\text{kg}}{\text{s}}$$

Comparing with the answer obtained from student 1, we see the students now agree! The discrepancy was entirely caused by the fact that the second student was measuring the weight of tank water PLUS the momentum lost by the water as it entered the tank!

## Problem 4.71

[Difficulty: 3]

**4.71** A tank of water sits on a cart with frictionless wheels as shown. The cart is attached using a cable to a mass  $M = 10$  kg, and the coefficient of static friction of the mass with the ground is  $\mu = 0.55$ . If the gate blocking the tank exit is removed, will the resulting exit flow be sufficient to start the tank moving? (Assume the water flow is frictionless, and that the jet velocity is  $V = \sqrt{2gh}$ , where  $h = 2$  m is the water depth.) Find the mass  $M$  that is just sufficient to hold the tank in place.



**Given:** Water tank attached to mass

**Find:** Whether tank starts moving; Mass to just hold in place

**Solution:**

Basic equation: Momentum flux in x direction for the tank

$$F_x = F_{\dot{x}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure at exit 4) Uniform flow

Hence 
$$R_x = V \cdot \cos(\theta) \cdot \rho \cdot (V \cdot A) = \rho \cdot V^2 \cdot \frac{\pi \cdot D^2}{4} \cdot \cos(\theta)$$

We need to find V. We could use the Bernoulli equation, but here it is known that  $V = \sqrt{2 \cdot g \cdot h}$  where  $h = 2$  m is the height of fluid in the tank

$$V = \sqrt{2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2 \cdot \text{m}} \quad V = 6.26 \frac{\text{m}}{\text{s}}$$

Hence 
$$R_x = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(6.26 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times \frac{\pi}{4} \times (0.05 \cdot \text{m})^2 \times \cos(60\text{-deg}) \quad R_x = 38.5 \text{ N}$$

This force is equal to the tension T in the wire  $T = R_x \quad T = 38.5 \text{ N}$

For the block, the maximum friction force a mass of  $M = 10$  kg can generate is  $F_{\max} = M \cdot g \cdot \mu$  where  $\mu$  is static friction

$$F_{\max} = 10 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.55 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_{\max} = 54.0 \text{ N}$$

Hence the tension T created by the water jet is less than the maximum friction  $F_{\max}$ ; the tank is at rest


The mass that is just sufficient is given by  $M \cdot g \cdot \mu = R_x$

$$M = \frac{R_x}{g \cdot \mu} \quad M = 38.5 \cdot \text{N} \times \frac{1}{9.81 \cdot \frac{\text{m}}{\text{s}^2}} \times \frac{1}{0.55} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad M = 7.14 \text{ kg}$$

## Problem 4.72

[Difficulty: 4]

**4.72** A gate is 1 m wide and 1.2 m tall and hinged at the bottom. On one side the gate holds back a 1-m-deep body of water. On the other side, a 5-cm diameter water jet hits the gate at a height of 1 m. What jet speed  $V$  is required to hold the gate vertical? What will the required speed be if the body of water is lowered to 0.5 m? What will the required speed be if the water level is lowered to 0.25 m?



**Given:** Gate held in place by water jet

**Find:** Required jet speed for various water depths

**Solution:**

Basic equation: Momentum flux in x direction for the wall

$$F_x = F_S + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Note: We use this equation ONLY for the jet impacting the wall. For the hydrostatic force and location we use computing equations

$$F_R = p_c \cdot A \quad y' = y_c + \frac{I_{xx}}{A \cdot y_c}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

Hence 
$$R_x = V \cdot \rho \cdot (-V \cdot A_{jet}) = -\rho \cdot V^2 \cdot \frac{\pi \cdot D^2}{4}$$

This force is the force generated by the wall on the jet; the force of the jet hitting the wall is then

$$F_{jet} = -R_x = \rho \cdot V^2 \cdot \frac{\pi \cdot D^2}{4} \quad \text{where } D \text{ is the jet diameter}$$

For the hydrostatic force 
$$F_R = p_c \cdot A = \rho \cdot g \cdot \frac{h}{2} \cdot h \cdot w = \frac{1}{2} \cdot \rho \cdot g \cdot w \cdot h^2 \quad y' = y_c + \frac{I_{xx}}{A \cdot y_c} = \frac{h}{2} + \frac{\frac{w \cdot h^3}{12}}{w \cdot h \cdot \frac{h}{2}} = \frac{2}{3} \cdot h$$

where  $h$  is the water depth and  $w$  is the gate width

For the gate, we can take moments about the hinge to obtain 
$$-F_{jet} \cdot h_{jet} + F_R \cdot (h - y') = -F_{jet} \cdot h_{jet} + F_R \cdot \frac{h}{3} = 0$$

where  $h_{jet}$  is the height of the jet from the ground

Hence 
$$F_{jet} = \rho \cdot V^2 \cdot \frac{\pi \cdot D^2}{4} \cdot h_{jet} = F_R \cdot \frac{h}{3} = \frac{1}{2} \cdot \rho \cdot g \cdot w \cdot h^2 \cdot \frac{h}{3} \quad V = \sqrt{\frac{2 \cdot g \cdot w \cdot h^3}{3 \cdot \pi \cdot D^2 \cdot h_j}}$$

For the first case ( $h = 1$  m) 
$$V = \sqrt{\frac{2}{3 \cdot \pi} \times 9.81 \cdot \frac{m}{s^2} \times 1 \cdot m \times (1 \cdot m)^3 \times \left(\frac{1}{0.05 \cdot m}\right)^2 \times \frac{1}{1 \cdot m}} \quad V = 28.9 \frac{m}{s}$$

For the second case ( $h = 0.5$  m) 
$$V = \sqrt{\frac{2}{3 \cdot \pi} \times 9.81 \cdot \frac{m}{s^2} \times 1 \cdot m \times (0.5 \cdot m)^3 \times \left(\frac{1}{0.05 \cdot m}\right)^2 \times \frac{1}{1 \cdot m}} \quad V = 10.2 \frac{m}{s}$$


For the first case ( $h = 0.25$  m) 
$$V = \sqrt{\frac{2}{3 \cdot \pi} \times 9.81 \cdot \frac{m}{s^2} \times 1 \cdot m \times (0.25 \cdot m)^3 \times \left(\frac{1}{0.05 \cdot m}\right)^2 \times \frac{1}{1 \cdot m}} \quad V = 3.61 \frac{m}{s}$$

### Problem 4.73

[Difficulty: 2]

**4.73** A farmer purchases 675 kg of bulk grain from the local co-op. The grain is loaded into his pickup truck from a hopper with an outlet diameter of 0.3 m. The loading operator determines the payload by observing the indicated gross mass of the truck as a function of time. The grain flow from the hopper ( $\dot{m} = 40 \text{ kg/s}$ ) is terminated when the indicated scale reading reaches the desired gross mass. If the grain density is  $600 \text{ kg/m}^3$ , determine the true payload.

Solution: Apply the y component of momentum equation using CV shown.



Basic equation:

$$F_{sy} + F_{By} = \frac{d}{dt} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A} \approx 0 \quad (2)$$

Assumptions: (1) No net pressure force;  $F_{sy} = R_y$

(2) Neglect  $v$  inside CV

Then (3) Uniform flow of grain at inlet section ①

$$R_y - (M_t + M_g)g = v_i \{-|\dot{m}|\}$$

$$v_i = -v_i = -\frac{\dot{m}}{\rho A}$$

or

$$R_y = (M_t + M_g)g + \frac{\dot{m}^2}{\rho A} \quad (\text{indicated during grain flow})$$

Loading is terminated when

$$\frac{R_y}{g} - M_t = M_g + \frac{\dot{m}^2}{\rho g A} = 675 \text{ kg}$$

Thus


$$\begin{aligned} M_g &= 675 \text{ kg} - \frac{\dot{m}^2}{\rho g A} \\ &= 675 \text{ kg} - (40)^2 \frac{\text{kg}^2}{\text{s}^2} \times \frac{\text{m}^3}{600 \text{ kg}} \times \frac{\text{s}^2}{9.81 \text{ m}} \times \frac{4}{\pi} \frac{1}{(0.3)^2 \text{ m}^2} \end{aligned}$$

$$M_g = 671 \text{ kg}$$

### Problem 4.74

[Difficulty: 2]

**4.74** Water flows steadily through a fire hose and nozzle. The hose is 75 mm inside diameter, and the nozzle tip is 25 mm ID; water gage pressure in the hose is 510 kPa, and the stream leaving the nozzle is uniform. The exit speed and pressure are 32 m/s and atmospheric, respectively. Find the force transmitted by the coupling between the nozzle and hose. Indicate whether the coupling is in tension or compression.



Solution: Apply continuity and  $x$  component of momentum equation to inertial CV shown; use gage pressures to cancel  $p_{atm}$ .

$$= 0 \quad (1)$$

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

$$F_{sx} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Steady flow  
 (2) Uniform flow at each section  
 (3) Incompressible flow  
 (4)  $F_{Bx} = 0$

Then

$$0 = \{-\rho V_1 A_1\} + \{\rho V_2 A_2\} = -\rho V_1 A_1 + \rho V_2 A_2$$

$$V_1 = V_2 \frac{A_2}{A_1} = V_2 \left(\frac{D_2}{D_1}\right)^2 = \frac{32 \text{ m}}{\text{s}} \times \left(\frac{25 \text{ mm}}{75 \text{ mm}}\right)^2 = 3.56 \text{ m/s}$$

and

$$R_x + p_1 g A_1 = u_1 \{-\rho V_1 A_1\} + u_2 \{\rho V_2 A_2\}$$

$$u_1 = V_1 \quad u_2 = V_2$$

$$R_x = -p_1 g A_1 - V_1 \rho V_1 A_1 + V_2 \rho V_2 A_2 = -p_1 g A_1 + \rho V_2 A_2 (V_2 - V_1)$$

$$= -510 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\pi}{4} (0.075)^2 \text{ m}^2 + \frac{999 \text{ kg}}{\text{m}^3} \times \frac{32 \text{ m}}{\text{s}} \times \frac{\pi}{4} (0.025)^2 \text{ m}^2 (32.0 - 3.56) \frac{\text{m}}{\text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$


$$R_x = -1.81 \text{ kN} \quad (\text{ie. force on CV is to the left})$$

Thus the coupling must be in tension.

### Problem 4.75

[Difficulty: 2]

**4.75** A shallow circular dish has a sharp-edged orifice at its center. A water jet, of speed  $V$ , strikes the dish concentrically. Obtain an expression for the external force needed to hold the dish in place if the jet issuing from the orifice also has speed  $V$ . Evaluate the force for  $V = 5$  m/s,  $D = 100$  mm, and  $d = 25$  mm. Plot the required force as a function of the angle  $\theta$  ( $0 \leq \theta \leq 90^\circ$ ) with diameter ratio as a parameter for a suitable range of diameter  $d$ .



#### Solution:

Apply the  $x$  component of the momentum equation to the inertial CV shown.

$$\text{Basic equation: } F_{B_x} + \sum F_x = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u (\rho \vec{v} \cdot d\vec{A})$$

Assumptions: (1) atmospheric pressure acts on all CV surfaces

(2)  $F_{B_x} = 0$

(3) steady flow

(4) uniform flow at each section

(5) incompressible flow

(6) no change in jet speed on dish:  $V_1 = V_2 = V_3 = V$

Res.

$$R_x = u_1 \{ -\rho V_1 A_1 \} + u_2 \{ \rho V_2 A_2 \} + u_3 \{ \rho V_3 A_3 \}$$

$$u_1 = V \quad A_1 = \frac{\pi D^2}{4} \quad u_2 = V \quad A_2 = \frac{\pi d^2}{4} \quad u_3 = -V \sin \theta \quad A_3 = A_1 - A_2$$


$$R_x = -\rho V^2 \frac{\pi D^2}{4} + \rho V^2 \frac{\pi d^2}{4} - \rho V^2 \sin \theta \frac{\pi}{4} (D^2 - d^2) = \rho V^2 \frac{\pi}{4} (1 + \sin \theta) (d^2 - D^2)$$

$$R_x = -\rho V^2 \frac{\pi D^2}{4} (1 + \sin \theta) \left[ 1 - \left(\frac{d}{D}\right)^2 \right]$$

Evaluating for  $d = 25$  mm

$$R_x = -\frac{\pi}{4} \times 999 \frac{\text{kg}}{\text{m}^3} \times (5)^2 \frac{\text{m}^2}{\text{s}^2} \times (0.10)^2 \text{m}^2 (1 + \sin 45^\circ) \left[ 1 - \left(\frac{25}{100}\right)^2 \right] \frac{\text{N}}{\text{kg} \cdot \text{m}} = -214 \text{ N}$$


Since  $R_x < 0$ , it must be applied to the left.  $R_x$  is plotted as a function of  $\theta$  for different values of  $d/D$



## Problem 4.76

[Difficulty: 3]

**4.76** Obtain expressions for the rate of change in mass of the control volume shown, as well as the horizontal and vertical forces required to hold it in place, in terms of  $p_1, A_1, V_1, p_2, A_2, V_2, p_3, A_3, V_3, p_4, A_4, V_4,$  and the constant density  $\rho$ .



**Given:** Flow into and out of CV

**Find:** Expressions for rate of change of mass, and force

**Solution:**

Basic equations: Mass and momentum flux 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

$$F_x = F_S + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

$$F_y = F_S + F_B = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Incompressible flow 2) Uniform flow

For the mass equation 
$$\frac{dM_{CV}}{dt} + \sum_{CS} (\rho \cdot \vec{V} \cdot \vec{A}) = \frac{dM_{CV}}{dt} + \rho \cdot (-V_1 \cdot A_1 - V_2 \cdot A_2 + V_3 \cdot A_3 + V_4 \cdot A_4) = 0$$

$$\frac{dM_{CV}}{dt} = \rho \cdot (V_1 \cdot A_1 + V_2 \cdot A_2 - V_3 \cdot A_3 - V_4 \cdot A_4)$$

For the x momentum 
$$F_x + \frac{p_1 \cdot A_1}{\sqrt{2}} + \frac{5}{13} \cdot p_2 \cdot A_2 - \frac{4}{5} \cdot p_3 \cdot A_3 - \frac{5}{13} \cdot p_4 \cdot A_4 = 0 + \frac{V_1}{\sqrt{2}} \cdot (-\rho \cdot V_1 \cdot A_1) + \frac{5}{13} \cdot V_2 \cdot (-\rho \cdot V_2 \cdot A_2) \dots$$
  

$$+ \frac{4}{5} \cdot V_3 \cdot (\rho \cdot V_3 \cdot A_3) + \frac{5}{13} \cdot V_4 \cdot (\rho \cdot V_4 \cdot A_4)$$

$$F_x = -\frac{p_1 \cdot A_1}{\sqrt{2}} - \frac{5}{13} \cdot p_2 \cdot A_2 + \frac{4}{5} \cdot p_3 \cdot A_3 + \frac{5}{13} \cdot p_4 \cdot A_4 + \rho \cdot \left( -\frac{1}{\sqrt{2}} \cdot V_1^2 \cdot A_1 - \frac{5}{13} \cdot V_2^2 \cdot A_2 + \frac{4}{5} \cdot V_3^2 \cdot A_3 + \frac{5}{13} \cdot V_4^2 \cdot A_4 \right)$$

For the y momentum 
$$F_y + \frac{p_1 \cdot A_1}{\sqrt{2}} - \frac{12}{13} \cdot p_2 \cdot A_2 - \frac{3}{5} \cdot p_3 \cdot A_3 + \frac{12}{13} \cdot p_4 \cdot A_4 = 0 + \frac{V_1}{\sqrt{2}} \cdot (-\rho \cdot V_1 \cdot A_1) - \frac{12}{13} \cdot V_2 \cdot (-\rho \cdot V_2 \cdot A_2) \dots$$
  


$$+ \frac{3}{5} \cdot V_3 \cdot (\rho \cdot V_3 \cdot A_3) - \frac{12}{13} \cdot V_4 \cdot (\rho \cdot V_4 \cdot A_4)$$

$$F_y = -\frac{p_1 \cdot A_1}{\sqrt{2}} + \frac{12}{13} \cdot p_2 \cdot A_2 + \frac{3}{5} \cdot p_3 \cdot A_3 - \frac{12}{13} \cdot p_4 \cdot A_4 + \rho \cdot \left( -\frac{1}{\sqrt{2}} \cdot V_1^2 \cdot A_1 - \frac{12}{13} \cdot V_2^2 \cdot A_2 + \frac{3}{5} \cdot V_3^2 \cdot A_3 - \frac{12}{13} \cdot V_4^2 \cdot A_4 \right)$$

## Problem 4.77

[Difficulty: 2]

**4.77** A 180° elbow takes in water at an average velocity of 0.8 m/s and a pressure of 350 kPa (gage) at the inlet, where the diameter is 0.2 m. The exit pressure is 75 kPa, and the diameter is 0.04 m. What is the force required to hold the elbow in place?



**Given:** Water flow through elbow

**Find:** Force to hold elbow

**Solution:**

Basic equation: Momentum flux in x direction for the elbow  $F_x = F_x + F_R = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

$$\text{Hence } R_x + p_1 g \cdot A_1 + p_2 g \cdot A_2 = V_1 (-\rho \cdot V_1 \cdot A_1) - V_2 (\rho \cdot V_2 \cdot A_2) \quad R_x = -p_1 g \cdot A_1 - p_2 g \cdot A_2 - \rho \cdot (V_1^2 \cdot A_1 + V_2^2 \cdot A_2)$$

$$\text{From continuity } V_2 \cdot A_2 = V_1 \cdot A_1 \quad \text{so} \quad V_2 = V_1 \cdot \frac{A_1}{A_2} = V_1 \cdot \left( \frac{D_1}{D_2} \right)^2 \quad V_2 = 0.8 \frac{\text{m}}{\text{s}} \cdot \left( \frac{0.2}{0.04} \right)^2 \quad V_2 = 20 \frac{\text{m}}{\text{s}}$$


$$\begin{aligned} \text{Hence } R_x &= -350 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\pi \cdot (0.2 \cdot \text{m})^2}{4} - 75 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\pi \cdot (0.04 \cdot \text{m})^2}{4} \dots \\ &+ -1000 \frac{\text{kg}}{\text{m}^3} \times \left[ \left( 0.8 \frac{\text{m}}{\text{s}} \right)^2 \times \frac{\pi \cdot (0.2 \cdot \text{m})^2}{4} + \left( 20 \frac{\text{m}}{\text{s}} \right)^2 \times \frac{\pi \cdot (0.04 \cdot \text{m})^2}{4} \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad R_x = -11.6 \cdot \text{kN} \end{aligned}$$

The force is to the left: It is needed to hold the elbow on against the high pressures, plus it generates the large change in x momentum

## Problem 4.78

[Difficulty: 2]

**4.78** Water is flowing steadily through the 180° elbow shown. At the inlet to the elbow the gage pressure is 15 psi. The water discharges to atmospheric pressure. Assume properties are uniform over the inlet and outlet areas:  $A_1 = 4 \text{ in.}^2$ ,  $A_2 = 1 \text{ in.}^2$ , and  $V_1 = 10 \text{ ft/s}$ . Find the horizontal component of force required to hold the elbow in place.



**Given:** Water flow through elbow

**Find:** Force to hold elbow

**Solution:**

Basic equation: Momentum flux in x direction for the elbow

$$F_x = F_{\dot{x}} + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure at exit 4) Uniform flow

$$\text{Hence} \quad R_x + p_1 g \cdot A_1 = V_1 (-\rho \cdot V_1 \cdot A_1) - V_2 (\rho \cdot V_2 \cdot A_2) \quad R_x = -p_1 g \cdot A_1 - \rho \cdot (V_1^2 \cdot A_1 + V_2^2 \cdot A_2)$$

$$\text{From continuity } V_2 \cdot A_2 = V_1 \cdot A_1 \quad \text{so} \quad V_2 = V_1 \cdot \frac{A_1}{A_2} \quad V_2 = 10 \cdot \frac{\text{ft} \cdot 4}{\text{s} \cdot 1} \quad V_2 = 40 \cdot \frac{\text{ft}}{\text{s}}$$


$$\text{Hence} \quad R_x = -15 \cdot \frac{\text{lbf}}{\text{in}^2} \times 4 \cdot \text{in}^2 - 1.94 \frac{\text{slug}}{\text{ft}^3} \times \left[ \left( 10 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \cdot 4 \cdot \text{in}^2 + \left( 40 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \cdot 1 \cdot \text{in}^2 \right] \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = -86.9 \text{ lbf}$$

The force is to the left: It is needed to hold the elbow on against the high pressure, plus it generates the large change in x momentum

## Problem 4.79

[Difficulty: 2]

**4.79** Water flows steadily through the nozzle shown, discharging to atmosphere. Calculate the horizontal component of force in the flanged joint. Indicate whether the joint is in tension or compression.



**Given:** Water flow through nozzle

**Find:** Force to hold nozzle

**Solution:**

Basic equation: Momentum flux in x direction for the elbow

$$F_x = F_{\dot{x}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

$$\text{Hence } R_x + p_1 g \cdot A_1 + p_2 g \cdot A_2 = V_1 \cdot (-\rho \cdot V_1 \cdot A_1) + V_2 \cdot \cos(\theta) \cdot (\rho \cdot V_2 \cdot A_2) \quad R_x = -p_1 g \cdot A_1 + \rho \cdot (V_2^2 \cdot A_2 \cdot \cos(\theta) - V_1^2 \cdot A_1)$$

$$\text{From continuity } V_2 \cdot A_2 = V_1 \cdot A_1 \quad \text{s} \quad V_2 = V_1 \cdot \frac{A_1}{A_2} = V_1 \cdot \left( \frac{D_1}{D_2} \right)^2 \quad V_2 = 1.5 \cdot \frac{\text{m}}{\text{s}} \cdot \left( \frac{30}{15} \right)^2 \quad V_2 = 6 \cdot \frac{\text{m}}{\text{s}}$$


$$\text{Hence } R_x = -15 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\pi \cdot (0.3 \cdot \text{m})^2}{4} + 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ \left( 6 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{\pi \cdot (0.15 \cdot \text{m})^2}{4} \cdot \cos(30 \cdot \text{deg}) - \left( 1.5 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{\pi \cdot (.3 \cdot \text{m})^2}{4} \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$R_x = -668 \cdot \text{N}$  The joint is in tension: It is needed to hold the elbow on against the high pressure, plus it generates the large change in x momentum

### Problem 4.80

[Difficulty: 2]

**4.80** Assume the bend of Problem 4.39 is a segment of a larger channel and lies in a horizontal plane. The inlet pressure is 170 kPa (abs), and the outlet pressure is 130 kPa (abs). Find the force required to hold the bend in place.



Solution:

Basic equation:  $\vec{F}_s + \vec{F}_B = \frac{\partial}{\partial t} \int_{CV} \rho \vec{V} dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

- Assumptions:
- (1) steady flow
  - (2)  $F_{B_x} = F_{B_y} = 0$
  - (3) incompressible flow
  - (4) atmospheric pressure acts on outside surfaces.

The x-momentum equation becomes

$$R_x + P_1 A_1 + \cancel{F_{B_x}} = \int_{CS} u (\rho \vec{V} \cdot d\vec{A}) = U \int_{CS} \rho V dA$$

$$R_x = -P_1 A_1 - \rho U^2 A_1 = -h^2 (P_1 + \rho U^2)$$

$$R_x = -(0.075)^2 \text{ m}^2 \left[ (170 - 101) \frac{\text{N}}{\text{m}^2} + 999 \frac{\text{kg}}{\text{m}^3} \times (7.5)^2 \frac{\text{m}^2}{\text{s}^2} \right] = -714 \text{ N}$$

The y-momentum equation becomes

$$R_y - P_2 A_2 + \cancel{F_{B_y}} = \int_{CS} v (\rho \vec{V} \cdot d\vec{A})$$

$$v_2 = V_2 = v_{\text{max}} - (v_{\text{max}} - v_{\text{min}}) \frac{x}{h} = 2v_{\text{min}} - v_{\text{min}} \frac{x}{h} = v_{\text{min}} \left( 2 - \frac{x}{h} \right)$$

$$R_y - P_2 A_2 = \int_0^h v_{\text{min}} \left( 2 - \frac{x}{h} \right) \rho v_{\text{min}} \left( 2 - \frac{x}{h} \right) h dx$$

$$R_y = P_2 A_2 + \rho v_{\text{min}}^2 h \int_0^h \left( 4 - 4 \frac{x}{h} + \frac{x^2}{h^2} \right) dx$$

$$= P_2 A_2 + \rho v_{\text{min}}^2 h \left[ 4x - 2 \frac{x^2}{h} + \frac{x^3}{3h^2} \right]_0^h$$

$$R_y = P_2 A_2 + \rho v_{\text{min}}^2 h \left[ 4h - 2h + \frac{h}{3} \right] = P_2 A_2 + \frac{7}{3} \rho v_{\text{min}}^2 h^2$$

$$R_y = h^2 \left( P_2 + \frac{7}{3} \rho v_{\text{min}}^2 \right)$$

$$= (0.075)^2 \text{ m}^2 \left[ (130 - 101) \frac{\text{N}}{\text{m}^2} + \frac{7}{3} \times 999 \frac{\text{kg}}{\text{m}^3} \times (5.0)^2 \frac{\text{m}^2}{\text{s}^2} \right]$$

$$R_y = 498 \text{ N}$$


$$\therefore \vec{R} = -714 \hat{i} + 498 \hat{j} \text{ N}$$

pd

### Problem 4.81

[Difficulty: 2]

**4.81** A spray system is shown in the diagram. Water is supplied at  $p = 1.45$  psig, through the flanged opening of area  $A = 3$  in.<sup>2</sup>. The water leaves in a steady free jet at atmospheric pressure. The jet area and speed are  $a = 1.0$  in.<sup>2</sup> and  $V = 15$  ft/s. The mass of the spray system is  $M = 0.2$  lbm and it contains  $\mathcal{V} = 12$  in.<sup>3</sup> of water. Find the force exerted on the supply pipe by the spray system.



Solution:

Apply the y component of the momentum equation to the fixed control volume shown.

Basic Equation:

$$F_{xy} + F_{by} = \frac{\partial}{\partial t} \int_{cv} \rho v \, d\mathcal{V} + \int_{cs} \rho v \vec{v} \cdot d\vec{A} \quad (1)$$

- Assumptions: (1) steady flow  
 (2) incompressible flow  
 (3) uniform flow at each section  
 (4) calculation of surface forces is simplified through use of gage pressures.

From continuity,  $0 = \frac{\partial}{\partial t} \int_{cv} \rho v \, d\mathcal{V} + \int_{cs} \rho v \vec{v} \cdot d\vec{A}$ , for given conditions  
 $0 = -\rho v_1 A_1 + \rho v_2 A_2$  and  $v_1 = v_2 \frac{A_2}{A_1} = v \frac{a}{A}$

The momentum flux is

$$\int_{cs} \rho v \vec{v} \cdot d\vec{A} = v_1 \{-\rho v_1 A_1\} + v_2 \{\rho v_2 A_2\} = v_1 (-\rho v_1 A_1) + v_2 (\rho v_2 A_2)$$

$$= v \frac{a}{A} (-\rho v a) + v (\rho v a) = \rho v^2 a \left(1 - \frac{a}{A}\right)$$

Then from eq. (1) we can write

$$R_y + F_{ig} A - p \mathcal{V} g - Mg = \rho v^2 a \left(1 - \frac{a}{A}\right) \quad \text{Solving for } R_y,$$

$$R_y = -F_{ig} A + p \mathcal{V} g + Mg + \rho v^2 a \left(1 - \frac{a}{A}\right)$$

$$= -1.45 \frac{\text{lb}}{\text{in}^2} \times 3 \text{ in}^2 + 1.94 \frac{\text{slug}}{\text{ft}^3} \times 12 \text{ in}^3 \times 32.2 \frac{\text{ft}}{\text{s}^2} \times \frac{\text{ft}^3}{1728 \text{ in}^3} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$+ 0.2 \text{ lbn} \cdot 32.2 \frac{\text{ft}}{\text{s}^2} \times \frac{\text{slug}}{32.2 \text{ lb}} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$+ 1.94 \frac{\text{slug}}{\text{ft}^3} \times (15)^2 \frac{\text{ft}^2}{\text{s}^2} \times 1 \text{ in}^2 \times \frac{\text{ft}^2}{144 \text{ in}^2} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \left(1 - \frac{1 \text{ in}^2}{3 \text{ in}^2}\right)$$


$$R_y = -1.70 \text{ lbf}$$

The force of the spray system on the supply pipe is  
 $K_y = -R_y = 1.70 \text{ lbf}$  (upward)

## Problem 4.82

[Difficulty: 2]

**4.82** A flat plate orifice of 2 in. diameter is located at the end of a 4-in.-diameter pipe. Water flows through the pipe and orifice at 20 ft<sup>3</sup>/s. The diameter of the water jet downstream from the orifice is 1.5 in. Calculate the external force required to hold the orifice in place. Neglect friction on the pipe wall.



**Given:** Water flow through orifice plate

**Find:** Force to hold plate

**Solution:**

Basic equation: Momentum flux in x direction for the elbow 
$$F_x = F_x + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

Hence 
$$R_x + p_1 g \cdot A_1 - p_2 g \cdot A_2 = V_1 \cdot (-\rho \cdot V_1 \cdot A_1) + V_2 \cdot (\rho \cdot V_2 \cdot A_2) \quad R_x = -p_1 g \cdot A_1 + \rho \cdot (V_2^2 \cdot A_2 - V_1^2 \cdot A_1)$$

From continuity  $Q = V_1 \cdot A_1 = V_2 \cdot A_2$

so 
$$V_1 = \frac{Q}{A_1} = 20 \cdot \frac{\text{ft}^3}{\text{s}} \times \frac{4}{\pi \cdot \left(\frac{1}{3} \cdot \text{ft}\right)^2} = 229 \cdot \frac{\text{ft}}{\text{s}} \quad \text{and} \quad V_2 = V_1 \cdot \frac{A_1}{A_2} = V_1 \cdot \left(\frac{D}{d}\right)^2 = 229 \cdot \frac{\text{ft}}{\text{s}} \times \left(\frac{4}{1.5}\right)^2 = 1628 \cdot \frac{\text{ft}}{\text{s}}$$

NOTE: problem has an error: Flow rate should be 2 ft<sup>3</sup>/s not 20 ft<sup>3</sup>/s! We will provide answers to both

Hence 
$$R_x = -200 \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{\pi \cdot (4 \cdot \text{in})^2}{4} + 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left[ \left(1628 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{\pi \cdot (1.5 \cdot \text{in})^2}{4} - \left(229 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{\pi \cdot (4 \cdot \text{in})^2}{4} \right] \times \left(\frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$R_x = 51707 \cdot \text{lbf}$

With more realistic velocities


Hence 
$$R_x = -200 \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{\pi \cdot (4 \cdot \text{in})^2}{4} + 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left[ \left(163 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{\pi \cdot (1.5 \cdot \text{in})^2}{4} - \left(22.9 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{\pi \cdot (4 \cdot \text{in})^2}{4} \right] \times \left(\frac{1 \cdot \text{ft}}{12 \cdot \text{in}}\right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$R_x = -1970 \cdot \text{lbf}$

### Problem 4.83

[Difficulty: 2]

**4.83** The nozzle shown discharges a sheet of water through a  $180^\circ$  arc. The water speed is 15 m/s and the jet thickness is 30 mm at a radial distance of 0.3 m from the centerline of the supply pipe. Find (a) the volume flow rate of water in the jet sheet and (b) the y component of force required to hold the nozzle in place.



Solution: Choose CV and coordinates shown. Apply continuity and momentum equation in y-direction.

Basic equations:  $Q = \int_A \vec{V} \cdot d\vec{A}$

$$F_{sy} + F_{By} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

$= 0(2) \quad = 0(3)$

Assumptions: (1) Flow uniform across exit section

(2)  $F_{By} = 0$

(3) Steady flow

At section (2),  $\vec{V} \cdot d\vec{A} = V R t d\theta$ , since flow out of CV. Then

$$Q = \int_{-\pi/2}^{\pi/2} V R t d\theta = V R t [\theta]_{-\pi/2}^{\pi/2} = V R t \pi$$

$$Q = \frac{15 \text{ m}}{\text{s}} \times 0.3 \text{ m} \times 0.03 \text{ m} \times \pi = 0.424 \text{ m}^3/\text{s}$$

From momentum

$$R_y = \int_{CS} v \rho \vec{V} \cdot d\vec{A} = \int_{A_1} v_1 \{ -|\rho v_1 dA_1| \} + \int_{A_2} v_2 \{ +|\rho v_2 dA_2| \}$$

with

$$v_1 = 0$$

$$v_2 = V \cos \theta$$


$$R_y = \int_{-\pi/2}^{\pi/2} V \cos \theta \rho V R t d\theta = \rho V^2 R t [\sin \theta]_{-\pi/2}^{\pi/2} = 2 \rho V^2 R t$$

$$R_y = 2 \times \frac{999 \text{ kg}}{\text{m}^3} \times (15)^2 \frac{\text{m}^2}{\text{s}^2} \times 0.3 \text{ m} \times 0.03 \text{ m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 4.05 \text{ kN}$$

## Problem 4.84

[Difficulty: 2]

**4.84** At rated thrust, a liquid-fueled rocket motor consumes 80 kg/s of nitric acid as oxidizer and 32 kg/s of aniline as fuel. Flow leaves axially at 180 m/s relative to the nozzle and at 110 kPa. The nozzle exit diameter is  $D = 0.6$  m. Calculate the thrust produced by the motor on a test stand at standard sea-level pressure.



**Given:** Data on rocket motor

**Find:** Thrust produced

**Solution:**

Basic equation: Momentum flux in x direction for the elbow  $F_x = F_{\dot{x}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$

Assumptions: 1) Steady flow 2) Neglect change of momentum within CV 3) Uniform flow

Hence  $R_x - p_{eg} \cdot A_e = V_e \cdot (\rho_e \cdot V_e \cdot A_e) = m_e \cdot V_e$   $R_x = p_{eg} \cdot A_e + m_e \cdot V_e$

where  $p_{eg}$  is the exit pressure (gage),  $m_e$  is the mass flow rate at the exit (software cannot render dot over m!) and  $V_e$  is the exit velocity


For the mass flow rate  $m_e = m_{\text{nitricacid}} + m_{\text{aniline}} = 80 \cdot \frac{\text{kg}}{\text{s}} + 32 \cdot \frac{\text{kg}}{\text{s}}$   $m_e = 112 \cdot \frac{\text{kg}}{\text{s}}$

Hence  $R_x = (110 - 101) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\pi \cdot (0.6 \cdot \text{m})^2}{4} + 112 \cdot \frac{\text{kg}}{\text{s}} \times 180 \cdot \frac{\text{m}}{\text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $R_x = 22.7 \cdot \text{kN}$



4.86 Consider flow through the sudden expansion shown. If the flow is incompressible and friction is neglected, show that the pressure rise,  $\Delta p = p_2 - p_1$ , is given by

$$\frac{\Delta p}{\frac{1}{2}\rho V_1^2} = 2\left(\frac{d}{D}\right)^2 \left[1 - \left(\frac{d}{D}\right)^2\right]$$



Plot the nondimensional pressure rise versus diameter ratio to determine the optimum value of  $d/D$  and the corresponding value of the nondimensional pressure rise. *Hint:* Assume the pressure is uniform and equal to  $p_1$  on the vertical surface of the expansion.

Solution:

Apply x component of momentum equation, using fixed CV shown  
 Basic equation:  $F_{sx} + \sum F_{Bx} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u (\rho \vec{V} \cdot d\vec{A})$

- Assumptions: (1) no friction, so surface force due to pressure only  
 (2)  $F_{Bx} = 0$   
 (3) steady flow (4) incompressible flow (given).  
 (5) uniform flow at sections 1 and 2  
 (6) uniform pressure  $p_1$  on vertical surface of expansion.


Then,  $p_1 A_2 - p_2 A_2 = u_1 \int -(\rho \vec{V}_1 \cdot d\vec{A}) + u_2 \int (\rho \vec{V}_2 \cdot d\vec{A})$   $u_1 = \bar{V}_1, u_2 = \bar{V}_2$

From continuity for uniform flow,  $\dot{m} = \rho A_1 \bar{V}_1 = \rho A_2 \bar{V}_2$ ;  $\bar{V}_2 = \bar{V}_1 \frac{A_1}{A_2}$

Thus,  $p_2 - p_1 = \rho \bar{V}_1 \frac{A_1}{A_2} \bar{V}_1 - \rho \bar{V}_1 \frac{A_1}{A_2} \bar{V}_2 = \rho \bar{V}_1 \frac{A_1}{A_2} (\bar{V}_1 - \bar{V}_2)$   
 $p_2 - p_1 = \rho \bar{V}_1^2 \frac{A_1}{A_2} \left(1 - \frac{\bar{V}_2}{\bar{V}_1}\right) = \rho \bar{V}_1^2 \frac{A_1}{A_2} \left(1 - \frac{A_1}{A_2}\right)$

and  $\frac{p_2 - p_1}{\frac{1}{2}\rho \bar{V}_1^2} = 2 \frac{A_1}{A_2} \left(1 - \frac{A_1}{A_2}\right) = 2\left(\frac{d}{D}\right)^2 \left[1 - \left(\frac{d}{D}\right)^2\right]$  Q.E.D.

From the plot below we see that  $\frac{\Delta p}{\frac{1}{2}\rho V_1^2}$  has an optimum value of  $\approx 0.5$  at  $d/D = 0.70$



Note: As expected  
 • for  $d=D$ ,  $\Delta p = 0$  for straight pipe  
 • for  $\frac{d}{D} \rightarrow 0$ ,  $\Delta p = 0$  for free jet  
 Also note that the location of section 2 would have to be chosen with care to make assumption (5) reasonable.


2025 RELEASE UNDER E.O. 14176  
 NATIONAL ARCHIVES  
 COLLETSVILLE, PA 17015  
 48-3889  
 200 RELEASE UNDER E.O. 14176



## Problem 4.87

[Difficulty: 2]

**4.87** A free jet of water with constant cross-section area  $0.01 \text{ m}^2$  is deflected by a hinged plate of length  $2 \text{ m}$  supported by a spring with spring constant  $k = 500 \text{ N/m}$  and uncompressed length  $x_0 = 1 \text{ m}$ . Find and plot the deflection angle  $\theta$  as a function of jet speed  $V$ . What jet speed has a deflection of  $\theta = 5^\circ$ ?



**Given:** Data on flow and system geometry

**Find:** Deflection angle as a function of speed; jet speed for  $10^\circ$  deflection

**Solution:**

The given data is  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$      $A = 0.01 \text{ m}^2$      $L = 2 \text{ m}$      $k = 500 \frac{\text{N}}{\text{m}}$      $x_0 = 1 \text{ m}$

Basic equation (y momentum):  $F_y = F_{S_y} + F_{B_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$


Applying this to the current system in the vertical direction

$$F_{\text{spring}} = V \cdot \sin(\theta) \cdot (\rho \cdot V \cdot A) \quad \text{But} \quad F_{\text{spring}} = k \cdot x = k \cdot (x_0 - L \cdot \sin(\theta))$$

Hence  $k \cdot (x_0 - L \cdot \sin(\theta)) = \rho \cdot V^2 \cdot A \cdot \sin(\theta)$

Solving for  $\theta$   $\theta = \text{asin} \left( \frac{k \cdot x_0}{k \cdot L + \rho \cdot A \cdot V^2} \right)$

For the speed at which  $\theta = 10^\circ$ , solve  $V = \sqrt{\frac{k \cdot (x_0 - L \cdot \sin(\theta))}{\rho \cdot A \cdot \sin(\theta)}}$      $V = \sqrt{\frac{500 \cdot \frac{\text{N}}{\text{m}} \cdot (1 - 2 \cdot \sin(5 \cdot \text{deg})) \cdot \text{m}}{999 \cdot \frac{\text{kg}}{\text{m}^3} \cdot 0.01 \cdot \text{m}^2 \cdot \sin(5 \cdot \text{deg})}} \cdot \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}}$      $V = 21.8 \frac{\text{m}}{\text{s}}$






### Problem 4.89

[Difficulty: 3]

4.89 A reducer in a piping system is shown. The internal volume of the reducer is  $0.2 \text{ m}^3$  and its mass is  $25 \text{ kg}$ . Evaluate the total force that must be provided by the surrounding pipes to support the reducer. The fluid is gasoline.



Solution: Apply the  $x$  and  $y$  components of the momentum equation, using the CV and coordinates shown. cancel  $p_{atm}$ .

Basic equations:

$$F_{3x} + F_{6x} = 0$$

$$F_{3y} + F_{6y} = \frac{\partial}{\partial t} \int_{CV} \rho v \, dV + \int_{CS} \rho v \, v \cdot \vec{A}$$

- Assumptions: (1)  $F_{Bx} = 0$   
 (2) Steady flow  
 (3) Uniform flow at each section  
 (4) Incompressible flow,  $SG = 0.72$  {Table A.2, Appendix A}

From the  $x$  component of momentum,

$$R_x + p_{1g} A_1 - p_{2g} A_2 = u_1 \{-|\rho V_1 A_1|\} + u_2 \{+|\rho V_2 A_2|\} = (V_2 - V_1) \rho V_1 A_1$$

$$u_1 = V_1 \quad u_2 = V_2$$

$$R_x = p_{2g} A_2 - p_{1g} A_1 + (V_2 - V_1) \rho V_1 A_1 \quad \text{Note } \rho = SG \rho_{H_2O}$$

$$= (109 - 101) 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\pi}{4} (0.2)^2 \text{m}^2 - 58.7 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\pi}{4} (0.4)^2 \text{m}^2 \\ + (12 - 3) \frac{\text{m}}{\text{s}} \times (0.72) 1000 \frac{\text{kg}}{\text{m}^3} \times 3 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} (0.4)^2 \text{m}^2 \times \frac{\text{N} \cdot \text{s}}{\text{kg} \cdot \text{m}}$$

$$R_x = -4.68 \text{ kN (force must be applied to left)}$$

$R_x$

From the  $y$  component of momentum,

$$R_y - Mg - p_g v = \frac{\partial}{\partial t} \int_{CV} \rho v \, dV + \int_{CS} \rho v \, v \cdot \vec{A}$$

$$R_y = Mg + p_g v$$

$$= 25 \text{ kg} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} + (0.72) 1000 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.2 \text{ m}^3 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$


$$R_y = 1.66 \text{ kN (force must be applied up)}$$

$R_y$

## Problem 4.90

[Difficulty: 2]

**4.90** A curved nozzle assembly that discharges to the atmosphere is shown. The nozzle mass is 4.5 kg and its internal volume is 0.002 m<sup>3</sup>. The fluid is water. Determine the reaction force exerted by the nozzle on the coupling to the inlet pipe.



**Given:** Data on nozzle assembly

**Find:** Reaction force

**Solution:**

Basic equation: Momentum flux in x and y directions

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

$$F_y = F_{S_y} + F_{B_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow CV 3) Uniform flow

For x momentum 
$$R_x = V_2 \cdot \cos(\theta) \cdot (\rho \cdot V_2 \cdot A_2) = \rho \cdot V_2^2 \cdot \frac{\pi \cdot D_2^2}{4} \cdot \cos(\theta)$$

From continuity 
$$A_1 \cdot V_1 = A_2 \cdot V_2 \quad V_2 = V_1 \cdot \frac{A_1}{A_2} = V_1 \cdot \left( \frac{D_1}{D_2} \right)^2 \quad V_2 = 2 \cdot \frac{\text{m}}{\text{s}} \times \left( \frac{7.5}{2.5} \right)^2 \quad V_2 = 18 \frac{\text{m}}{\text{s}}$$

Hence 
$$R_x = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 18 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{\pi}{4} \times (0.025 \cdot \text{m})^2 \times \cos(30 \cdot \text{deg}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad R_x = 138 \cdot \text{N}$$

For y momentum 
$$R_y - p_1 \cdot A_1 - W - \rho \cdot \text{Vol} \cdot g = -V_1 \cdot (-\rho \cdot V_1 \cdot A_1) - V_2 \cdot \sin(\theta) \cdot (\rho \cdot V_2 \cdot A_2)$$

$$R_y = p_1 \cdot \frac{\pi \cdot D_1^2}{4} + W + \rho \cdot \text{Vol} \cdot g + \frac{\rho \cdot \pi}{4} \cdot \left( V_1^2 \cdot D_1^2 - V_2^2 \cdot D_2^2 \cdot \sin(\theta) \right)$$

where 
$$W = 4.5 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad W = 44.1 \text{ N} \quad \text{Vol} = 0.002 \cdot \text{m}^3$$

Hence 
$$R_y = 125 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\pi \cdot (0.075 \cdot \text{m})^2}{4} + 44.1 \cdot \text{N} + 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 0.002 \cdot \text{m}^3 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \dots$$


$$+ 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \frac{\pi}{4} \times \left[ \left( 2 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times (0.075 \cdot \text{m})^2 - \left( 18 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times (0.025 \cdot \text{m})^2 \times \sin(30 \cdot \text{deg}) \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$R_y = 554 \cdot \text{N}$$

## Problem 4.91

[Difficulty: 3]

**4.91** A water jet pump has jet area  $0.1 \text{ ft}^2$  and jet speed  $100 \text{ ft/s}$ . The jet is within a secondary stream of water having speed  $V_s = 10 \text{ ft/s}$ . The total area of the duct (the sum of the jet and secondary stream areas) is  $0.75 \text{ ft}^2$ . The water is thoroughly mixed and leaves the jet pump in a uniform stream. The pressures of the jet and secondary stream are the same at the pump inlet. Determine the speed at the pump exit and the pressure rise,  $p_2 - p_1$ .



**Given:** Data on water jet pump

**Find:** Speed at pump exit; pressure rise

**Solution:**

Basic equation: Continuity, and momentum flux in x direction

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \qquad F_x = F_S + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow CV 3) Uniform flow

From continuity  $-\rho \cdot V_s \cdot A_s - \rho \cdot V_j \cdot A_j + \rho \cdot V_2 \cdot A_2 = 0$   $V_2 = V_s \cdot \frac{A_s}{A_2} + V_j \cdot \frac{A_j}{A_2} = V_s \cdot \left( \frac{A_2 - A_j}{A_2} \right) + V_j \cdot \frac{A_j}{A_2}$

$$V_2 = 10 \cdot \frac{\text{ft}}{\text{s}} \times \left( \frac{0.75 - 0.1}{0.75} \right) + 100 \cdot \frac{\text{ft}}{\text{s}} \times \frac{0.1}{0.75} \qquad V_2 = 22 \cdot \frac{\text{ft}}{\text{s}}$$

For x momentum  $p_1 \cdot A_2 - p_2 \cdot A_2 = V_j \cdot (-\rho \cdot V_j \cdot A_j) + V_s \cdot (-\rho \cdot V_s \cdot A_s) + V_2 \cdot (\rho \cdot V_2 \cdot A_2)$

$$\Delta p = p_2 - p_1 = \rho \cdot \left( V_j^2 \cdot \frac{A_j}{A_2} + V_s^2 \cdot \frac{A_s}{A_2} - V_2^2 \right)$$

$$\Delta p = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left[ \left( 100 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{0.1}{0.75} + \left( 10 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{(0.75 - 0.1)}{0.75} - \left( 22 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \right] \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$


Hence  $\Delta p = 1816 \cdot \frac{\text{lb} \cdot \text{ft}}{\text{ft}^2}$   $\Delta p = 12.6 \text{ psi}$



## Problem 4.93

[Difficulty: 3]

**4.93** Consider the steady adiabatic flow of air through a long straight pipe with  $0.05 \text{ m}^2$  cross-sectional area. At the inlet, the air is at  $200 \text{ kPa}$  (gage),  $60^\circ\text{C}$ , and has a velocity of  $150 \text{ m/s}$ . At the exit, the air is at  $80 \text{ kPa}$  and has a velocity of  $300 \text{ m/s}$ . Calculate the axial force of the air on the pipe. (Be sure to make the direction clear.)



**Given:** Data on adiabatic flow of air

**Find:** Force of air on pipe

**Solution:**

Basic equation: Continuity, and momentum flux in x direction, plus ideal gas equation

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad F_x = F_x + F_R = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad p = \rho \cdot R \cdot T$$

Assumptions: 1) Steady flow 2) Ideal gas CV 3) Uniform flow

From continuity  $-\rho_1 \cdot V_1 \cdot A_1 + \rho_2 \cdot V_2 \cdot A_2 = 0 \quad \rho_1 \cdot V_1 \cdot A = \rho_2 \cdot V_2 \cdot A \quad \rho_1 \cdot V_1 = \rho_2 \cdot V_2$

For x momentum  $R_x + p_1 \cdot A - p_2 \cdot A = V_1 \cdot (-\rho_1 \cdot V_1 \cdot A) + V_2 \cdot (\rho_2 \cdot V_2 \cdot A) = \rho_1 \cdot V_1 \cdot A \cdot (V_2 - V_1)$

$$R_x = (p_2 - p_1) \cdot A + \rho_1 \cdot V_1 \cdot A \cdot (V_2 - V_1)$$

For the air  $\rho_1 = \frac{p_1}{R_{\text{air}} \cdot T_1} \quad \rho_1 = (200 + 101) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{286.9 \cdot \text{N} \cdot \text{m}} \times \frac{1}{(60 + 273) \cdot \text{K}} \quad \rho_1 = 3.15 \frac{\text{kg}}{\text{m}^3}$

$$R_x = (80 - 200) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times 0.05 \cdot \text{m}^2 + 3.15 \cdot \frac{\text{kg}}{\text{m}^3} \times 150 \cdot \frac{\text{m}}{\text{s}} \times 0.05 \cdot \text{m}^2 \times (300 - 150) \cdot \frac{\text{m}}{\text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

Hence  $R_x = -2456 \text{ N}$


This is the force of the pipe on the air; the pipe is opposing flow. Hence the force of the air on the pipe is  $F_{\text{pipe}} = -R_x$

$F_{\text{pipe}} = 2456 \text{ N}$       The air is dragging the pipe to the right

### Problem 4.94

[Difficulty: 3]

4.94 A monotube boiler consists of a 20 ft length of tubing with 0.375 in. inside diameter. Water enters at the rate of 0.3 lbm/s at 500 psia. Steam leaves at 400 psig with 0.024 slug/ft<sup>3</sup> density. Find the magnitude and direction of the force exerted by the flowing fluid on the tube.



Solution: Apply the x component of the momentum equation, using the CV and coordinates shown.

Basic equation:

$$F_{3x} + F_{px} = \frac{d}{dt} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

= 0(1)    = 0(2)

- Assumptions:
- (1)  $F_{Bx} = 0$
  - (2) Steady flow
  - (3) Uniform flow at each section
  - (4) Use gage pressures to cancel  $p_{atm}$

From continuity,

$$\dot{m} = \rho_1 V_1 A_1 = \rho_2 V_2 A_2; \quad A = \text{constant, so } \rho_1 V_1 = \rho_2 V_2. \quad \text{Thus}$$

$$V_1 = \frac{\dot{m}}{\rho_1 A} = \frac{0.3 \frac{\text{lbm}}{\text{s}}}{1.94 \frac{\text{slug}}{\text{ft}^3} \times \frac{\pi}{4} \times \frac{1}{(0.375)^2 \text{in}^2} \times \frac{\text{slug}}{32.2 \text{lbm}} \times \frac{144 \text{in}^2}{\text{ft}^2}} = 6.26 \text{ ft/s}$$

and

$$V_2 = V_1 \frac{\rho_1}{\rho_2} = 6.26 \frac{\text{ft}}{\text{s}} \times 1.94 \frac{\text{slug}}{\text{ft}^3} \times \frac{\text{ft}^3}{0.024 \text{ slug}} = 506 \text{ ft/s}$$

From momentum,

$$R_x + p_{2g} A_1 - p_{1g} A_2 = u_1 \{-\dot{m}\} + u_2 \{+\dot{m}\} = (V_2 - V_1) \dot{m}$$

$$u_1 = V_1 \quad u_2 = V_2$$

$$R_x = (p_{2g} - p_{1g}) A + (V_2 - V_1) \dot{m}$$

$$= [400 - (500 - 14.7)] \frac{\text{lb}_f}{\text{in}^2} \times \frac{\pi}{4} (0.375)^2 \text{in}^2 + (506 - 6.26) \frac{\text{ft}}{\text{s}} \times 0.3 \frac{\text{lbm}}{\text{s}} \times \frac{\text{slug}}{32.2 \text{lbm}}$$

$$\times \frac{\text{lb}_f \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$R_x = -4.77 \text{ lb}_f$$

But  $R_x$  is force on CV; force on pipe is  $K_x$ ,


$$K_x = -R_x = 4.77 \text{ lb}_f \text{ (to right)}$$

$K_x$

## Problem 4.95

[Difficulty: 3]

**4.95** A gas flows steadily through a heated porous pipe of constant  $0.15 \text{ m}^2$  cross-sectional area. At the pipe inlet, the absolute pressure is  $400 \text{ kPa}$ , the density is  $6 \text{ kg/m}^3$ , and the mean velocity is  $170 \text{ m/s}$ . The fluid passing through the porous wall leaves in a direction normal to the pipe axis, and the total flow rate through the porous wall is  $20 \text{ kg/s}$ . At the pipe outlet, the absolute pressure is  $300 \text{ kPa}$  and the density is  $2.75 \text{ kg/m}^3$ . Determine the axial force of the fluid on the pipe.



**Given:** Data on heated flow of gas

**Find:** Force of gas on pipe

**Solution:**

Basic equation: Continuity, and momentum flux in x direction

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad F_x = F_{R_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad p = \rho \cdot R \cdot T$$

Assumptions: 1) Steady flow 2) Uniform flow

From continuity  $-\rho_1 \cdot V_1 \cdot A_1 + \rho_2 \cdot V_2 \cdot A_2 + m_3 = 0 \quad V_2 = V_1 \cdot \frac{\rho_1}{\rho_2} - \frac{m_3}{\rho_2 \cdot A_2}$  where  $m_3 = 20 \text{ kg/s}$  is the mass leaving through the walls (the software does not allow a dot)

$$V_2 = 170 \cdot \frac{\text{m}}{\text{s}} \times \frac{6}{2.75} - 20 \cdot \frac{\text{kg}}{\text{s}} \times \frac{\text{m}^3}{2.75 \cdot \text{kg}} \times \frac{1}{0.15 \cdot \text{m}^2} \quad V_2 = 322 \frac{\text{m}}{\text{s}}$$

For x momentum  $R_x + p_1 \cdot A - p_2 \cdot A = V_1 \cdot (-\rho_1 \cdot V_1 \cdot A) + V_2 \cdot (\rho_2 \cdot V_2 \cdot A)$

$$R_x = \left[ (p_2 - p_1) + \rho_2 \cdot V_2^2 - \rho_1 \cdot V_1^2 \right] \cdot A$$


$$R_x = \left[ (300 - 400) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} + \left[ 2.75 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 322 \cdot \frac{\text{m}}{\text{s}} \right)^2 - 6 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 170 \cdot \frac{\text{m}}{\text{s}} \right)^2 \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right] \times 0.15 \cdot \text{m}^2$$

Hence  $R_x = 1760 \text{ N}$

## Problem 4.96

[Difficulty: 3]

**4.96** Water is discharged at a flow rate of  $0.3 \text{ m}^3/\text{s}$  from a narrow slot in a 200-mm-diameter pipe. The resulting horizontal two-dimensional jet is 1 m long and 20 mm thick, but of nonuniform velocity; the velocity at location ② is twice that at location ①. The pressure at the inlet section is 50 kPa (gage). Calculate (a) the velocity in the pipe and at locations ① and ② and (b) the forces required at the coupling to hold the spray pipe in place. Neglect the mass of the pipe and the water it contains.



**Given:** Data on flow out of pipe device

**Find:** Velocities at 1 and 2; force on coupling

**Solution:**

Basic equations (continuity and x and y mom.): 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad F_y = F_{S_y} + F_{B_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

The given data is  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$      $D = 20\text{-cm}$      $L = 1\text{-m}$      $t = 20\text{-mm}$      $p_{3g} = 50\text{-kPa}$      $Q = 0.3 \frac{\text{m}^3}{\text{s}}$

From continuity  $Q = A \cdot V_{\text{ave}}$     due to linear velocity distribution     $V_{\text{ave}} = \frac{1}{2} \cdot (V_1 + V_2)$

Note that at the exit  $V(x) = V_1 + \frac{(V_2 - V_1)}{L} \cdot x$

Hence  $Q = \frac{1}{2} \cdot (V_1 + V_2) \cdot L \cdot t = \frac{1}{2} \cdot (V_1 + 2 \cdot V_1) \cdot L \cdot t$

$$V_1 = \frac{2 \cdot Q}{3 \cdot L \cdot t} \quad V_1 = 10 \frac{\text{m}}{\text{s}} \quad V_2 = 2 \cdot V_1 \quad V_2 = 20 \frac{\text{m}}{\text{s}}$$

At the inlet (location 3)  $V_3 = \frac{Q}{\frac{\pi}{4} \cdot D^2}$      $V_3 = 9.549 \frac{\text{m}}{\text{s}}$

Applying x momentum  $R_x + p_{3g} \cdot \frac{\pi}{4} \cdot D^2 = -V_3 \cdot \rho \cdot Q$      $R_x = -p_{3g} \cdot \frac{\pi}{4} \cdot D^2 - V_3 \cdot \rho \cdot Q$      $R_x = -4.43\text{-kN}$

Applying y momentum  $R_y = - \int_0^L V(x) \cdot \rho \cdot V(x) \cdot t \, dx = -\rho \cdot t \cdot \int_0^L \left[ V_1 + \frac{(V_2 - V_1)}{L} \cdot x \right]^2 dx$

Expanding and integrating  $R_y = -\rho \cdot t \cdot \left[ V_1^2 \cdot L + 2 \cdot V_1 \cdot \left( \frac{V_2 - V_1}{L} \right) \cdot \frac{L^2}{2} + \left( \frac{V_2 - V_1}{L} \right)^2 \cdot \frac{L^3}{3} \right]$      $R_y = -4.66\text{-kN}$

4.97 Water flows steadily through the square bend of Problem 4.39. Flow at the inlet is at  $p_1 = 185 \text{ kPa (abs)}$ . Flow at the exit is nonuniform, vertical, and at atmospheric pressure. The mass of the channel structure is  $M_c = 2.05 \text{ kg}$ ; the internal volume of the channel is  $V = 0.00355 \text{ m}^3$ . Evaluate the force exerted by the channel assembly on the supply duct.

Solution: Apply conservation of mass + momentum equations to the CV shown.

Basic equations:


$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{v} \cdot d\vec{A} \quad (1)$$

$$F_{s_x} + F_{s_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{v} \cdot d\vec{A} \quad (2)$$

$$F_{s_y} + F_{s_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{v} \cdot d\vec{A} \quad (3)$$

Assumptions:

- (1) steady flow
- (2) incompressible flow
- (3) uniform flow at inlet.
- (4) use gage pressures.



From continuity,  $0 = \vec{V}_1 \cdot \vec{A}_1 + \int_{CS} \vec{V}_2 \cdot d\vec{A}_2 = -Uwh + \int_0^h v w dx$

$$\therefore U h = \int_0^h v dx = \int_0^h v_{min} (2 - \frac{x}{h}) dx = v_{min} [2x - \frac{x^2}{2h}]_0^h = \frac{3}{2} v_{min} h$$

and  $v_{min} = \frac{2}{3} U = \frac{2}{3} \times 7.5 \frac{m}{s} = 5.0 \text{ m/s}$

From Eq. 2,

$$R_x + p_1 g A_1 = u_1 \{-p_1 A_1\} + \int_0^h u_2 \{p v_{min} (2 - \frac{x}{h})\} w dx = -p U^2 A_1$$

$$R_x = -p_1 g A_1 - p U^2 A_1 = -(185 - 101) \frac{N}{m^2} (0.0755)^2 - 999 \frac{kg}{m^3} (7.5)^2 (0.0755)^2$$

$$R_x = -479 \text{ N} - 320 \frac{kg \cdot m}{s^2} \cdot \frac{N \cdot s^2}{kg \cdot m} = -479 \text{ N} - 320 \text{ N} = -799 \text{ N}$$

$$K_x = -R_x = 799 \text{ N (on supply duct to the right)}$$

From Eq. 3,

$$R_y - M_c g - p_1 t g = v_1 \{-p_1 A_1\} + \int_0^h v_2 \{p v_2 w dx\}$$

$$R_y - M_c g - p_1 t g = \int_0^h v_{min} (2 - \frac{x}{h}) p v_{min} (2 - \frac{x}{h}) w dx$$

$$= p v_{min}^2 w \int_0^h (4 - 4 \frac{x}{h} + \frac{x^2}{h^2}) dx$$

$$= p v_{min}^2 w [4x - 2 \frac{x^2}{h} + \frac{x^3}{3h^2}]_0^h = p v_{min}^2 w h \frac{7}{3}$$

$$\therefore R_y = [2.05 \frac{kg}{s^2} \cdot 9.81 \frac{m}{s^2} + 999 \frac{kg}{m^3} (0.00355 \text{ m}^3) 9.81 \frac{m}{s^2} + \frac{7}{3} \cdot 999 \frac{kg}{m^3} (5.0)^2 (0.0755)^2] \frac{N \cdot s^2}{kg \cdot m}$$


$$R_y = (20.1 + 34.8 + 332) \text{ N} = 387 \text{ N (on CV)}$$

$$K_y = -R_y = -387 \text{ N (on supply duct, down)}$$

### Problem 4.98

[Difficulty: 3]

**4.98** A nozzle for a spray system is designed to produce a flat radial sheet of water. The sheet leaves the nozzle at  $V_2 = 10 \text{ m/s}$ , covers  $180^\circ$  of arc, and has thickness  $t = 1.5 \text{ mm}$ . The nozzle discharge radius is  $R = 50 \text{ mm}$ . The water supply pipe is  $35 \text{ mm}$  in diameter and the inlet pressure is  $p_1 = 150 \text{ kPa}$  (abs). Evaluate the axial force exerted by the spray nozzle on the coupling.



Solution: Apply the  $x$  component of momentum, using CV and coordinates shown.

Basic equation:

$$F_{sx} + F_{px} = \frac{d}{dt} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

- Assumptions: (1)  $F_{Bx} = 0$   
 (2) Steady flow  
 (3) Uniform flow at each section  
 (4) Use gage pressure to cancel  $p_{atm}$

From continuity

$$Q = V_1 A_1 = V_2 A_2 = V_2 \pi R t = \pi \times 10 \frac{\text{m}}{\text{sec}} \times 0.05 \text{ m} \times 0.0015 \text{ m} = 0.00236 \text{ m}^3/\text{s}$$

$$V_1 = \frac{Q}{A_1} = \frac{4Q}{\pi D^2} = \frac{4}{\pi} \times 0.00236 \frac{\text{m}^3}{\text{sec}} \times \frac{1}{(0.035)^2 \text{ m}^2} = 2.45 \text{ m/s}$$

From momentum

{ Note  $A_1 = \frac{\pi D^2}{4} = 0.000962 \text{ m}^2$  }

$$R_x + p_1 g A_1 = u_1 \{-\rho Q\} + \int_{A_2} u_2 \rho V_2 dA_2$$

$$u_1 = V_1 \quad u_2 = V_2 \cos \theta; \quad dA_2 = R t d\theta$$

$$\int_{A_2} = \int_{-\pi/2}^{\pi/2} V_2 \cos \theta \rho V_2 R t d\theta = 2 \rho V_2^2 R t \int_0^{\pi/2} \cos \theta d\theta = 2 \rho V_2^2 R t$$

Thus

$$R_x = -p_1 g A_1 - V_1 \rho Q + 2 \rho V_2^2 R t$$

$$= - (150 - 101) \frac{\text{N}}{\text{m}^2} \times 0.000962 \text{ m}^2 - 2.45 \frac{\text{m}}{\text{sec}} \times 999 \frac{\text{kg}}{\text{m}^3} \times 0.00236 \frac{\text{m}^3}{\text{sec}} \times \frac{\text{N} \cdot \text{sec}^2}{\text{sec} \cdot \text{kg} \cdot \text{m}}$$

$$+ 2 \times 999 \frac{\text{kg}}{\text{m}^3} \times \frac{(10)^2 \text{ m}^2}{\text{sec}^2} \times 0.05 \text{ m} \times 0.0015 \text{ m} \times \frac{\text{N} \cdot \text{sec}^2}{\text{kg} \cdot \text{m}}$$

$$R_x = -37.9 \text{ N}$$

But  $R_x$  is force on CV; force on coupling is  $K_x$ ,


$$K_x = -R_x = 37.9 \text{ N (to right)}$$

$K_x$

## Problem 4.99

[Difficulty: 4]

**4.99** A small round object is tested in a 0.75-m diameter wind tunnel. The pressure is uniform across sections ① and ②. The upstream pressure is 30 mm H<sub>2</sub>O (gage), the downstream pressure is 15 mm H<sub>2</sub>O (gage), and the mean air speed is 12.5 m/s. The velocity profile at section ② is linear; it varies from zero at the tunnel centerline to a maximum at the tunnel wall. Calculate (a) the mass flow rate in the wind tunnel, (b) the maximum velocity at section ②, and (c) the drag of the object and its supporting vane. Neglect viscous resistance at the tunnel wall.



**Given:** Data on flow in wind tunnel

**Find:** Mass flow rate in tunnel; Maximum velocity at section 2; Drag on object

**Solution:** Basic equations: Continuity, and momentum flux in x direction; ideal gas equation

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad F_x = F_S + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad p = \rho \cdot R \cdot T$$

Assumptions: 1) Steady flow 2) Uniform density at each section

From continuity  $m_{\text{flow}} = \rho_1 \cdot V_1 \cdot A_1 = \rho_1 \cdot V_1 \cdot \frac{\pi \cdot D_1^2}{4}$  where  $m_{\text{flow}}$  is the mass flow rate

We take ambient conditions for the air density  $\rho_{\text{air}} = \frac{p_{\text{atm}}}{R_{\text{air}} \cdot T_{\text{atm}}}$   $\rho_{\text{air}} = 101000 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{286.9 \cdot \text{N} \cdot \text{m}} \times \frac{1}{293 \cdot \text{K}}$   $\rho_{\text{air}} = 1.2 \frac{\text{kg}}{\text{m}^3}$

$$m_{\text{flow}} = 1.2 \cdot \frac{\text{kg}}{\text{m}^3} \times 12.5 \cdot \frac{\text{m}}{\text{s}} \times \frac{\pi \cdot (0.75 \cdot \text{m})^2}{4} \quad m_{\text{flow}} = 6.63 \frac{\text{kg}}{\text{s}}$$

Also  $m_{\text{flow}} = \int \rho_2 \cdot u_2 dA_2 = \rho_{\text{air}} \cdot \int_0^R V_{\text{max}} \cdot \frac{r}{R} \cdot 2 \cdot \pi \cdot r dr = \frac{2 \cdot \pi \cdot \rho_{\text{air}} \cdot V_{\text{max}}}{R} \cdot \int_0^R r^2 dr = \frac{2 \cdot \pi \cdot \rho_{\text{air}} \cdot V_{\text{max}} \cdot R^2}{3}$

$$V_{\text{max}} = \frac{3 \cdot m_{\text{flow}}}{2 \cdot \pi \cdot \rho_{\text{air}} \cdot R^2} \quad V_{\text{max}} = \frac{3}{2 \cdot \pi} \times 6.63 \cdot \frac{\text{kg}}{\text{s}} \times \frac{\text{m}^3}{1.2 \cdot \text{kg}} \times \left( \frac{1}{0.375 \cdot \text{m}} \right)^2 \quad V_{\text{max}} = 18.8 \frac{\text{m}}{\text{s}}$$

For x momentum  $R_x + p_1 \cdot A - p_2 \cdot A = V_1 \cdot (-\rho_1 \cdot V_1 \cdot A) + \int \rho_2 \cdot u_2 \cdot u_2 dA_2$

$$R_x = (p_2 - p_1) \cdot A - V_1 \cdot m_{\text{flow}} + \int_0^R \rho_{\text{air}} \cdot \left( V_{\text{max}} \cdot \frac{r}{R} \right)^2 \cdot 2 \cdot \pi \cdot r dr = (p_2 - p_1) \cdot A - V_1 \cdot m_{\text{flow}} + \frac{2 \cdot \pi \cdot \rho_{\text{air}} \cdot V_{\text{max}}^2}{R^2} \cdot \int_0^R r^3 dr$$

$$R_x = (p_2 - p_1) \cdot A - V_1 \cdot m_{\text{flow}} + \frac{\pi}{2} \cdot \rho_{\text{air}} \cdot V_{\text{max}}^2 \cdot R^2$$

We also have  $p_1 = \rho \cdot g \cdot h_1$   $p_1 = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.03 \cdot \text{m}$   $p_1 = 294 \text{ Pa}$   $p_2 = \rho \cdot g \cdot h_2$   $p_2 = 147 \cdot \text{Pa}$

Hence  $R_x = (147 - 294) \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\pi \cdot (0.75 \cdot \text{m})^2}{4} + \left[ -6.63 \cdot \frac{\text{kg}}{\text{s}} \times 12.5 \cdot \frac{\text{m}}{\text{s}} + \frac{\pi}{2} \times 1.2 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 18.8 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times (0.375 \cdot \text{m})^2 \right] \times \frac{1}{4}$

$$R_x = -54 \text{ N} \quad \text{The drag on the object is equal and opposite} \quad F_{\text{drag}} = -R_x \quad F_{\text{drag}} = 54.1 \text{ N}$$

## Problem 4.100

[Difficulty: 2]

**4.100** The horizontal velocity in the wake behind an object in an air stream of velocity  $U$  is given by

$$u(r) = U \left[ 1 - \cos^2 \left( \frac{\pi r}{2} \right) \right] \quad |r| \leq 1$$

$$u(r) = U \quad |r| > 1$$

where  $r$  is the nondimensional radial coordinate, measured perpendicular to the flow. Find an expression for the drag on the object.

**Given:** Data on wake behind object

**Find:** An expression for the drag

**Solution:**

Basic equation:

Momentum 
$$F_x = F_{\dot{x}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Applying this to the horizontal motion

$$-F = U \cdot (-\rho \cdot \pi \cdot 1^2 \cdot U) + \int_0^1 u(r) \cdot \rho \cdot 2 \cdot \pi \cdot r \cdot u(r) dr \quad F = \pi \rho \cdot \left( U^2 - 2 \cdot \int_0^1 r \cdot u(r)^2 dr \right)$$

$$F = \pi \rho \cdot U^2 \cdot \left[ 1 - 2 \cdot \int_0^1 r \cdot \left( 1 - \cos^2 \left( \frac{\pi \cdot r}{2} \right) \right)^2 dr \right]$$

$$F = \pi \rho \cdot U^2 \cdot \left( 1 - 2 \cdot \int_0^1 r - 2 \cdot r \cdot \cos^2 \left( \frac{\pi \cdot r}{2} \right) + r \cdot \cos^4 \left( \frac{\pi \cdot r}{2} \right) dr \right)$$

Integrating and using the limits 
$$F = \pi \rho \cdot U^2 \cdot \left[ 1 - \left( \frac{3}{8} + \frac{2}{\pi^2} \right) \right] \quad F = \left( \frac{5 \cdot \pi}{8} - \frac{2}{\pi} \right) \cdot \rho \cdot U^2$$


## Problem 4.101

[Difficulty: 3]

**4.101** An incompressible fluid flows steadily in the entrance region of a two-dimensional channel of height  $2h = 100$  mm and width  $w = 25$  mm. The flow rate is  $Q = 0.025$  m<sup>3</sup>/s. Find the uniform velocity  $U_1$  at the entrance. The velocity distribution at a section downstream is

$$\frac{u}{u_{\max}} = 1 - \left(\frac{y}{h}\right)^2$$

Evaluate the maximum velocity at the downstream section. Calculate the pressure drop that would exist in the channel if viscous friction at the walls could be neglected.



**Given:** Data on flow in 2D channel

**Find:** Maximum velocity; Pressure drop

**Solution:**

Basic equations: Continuity, and momentum flux in x direction

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \qquad F_x = F_{\dot{x}} + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Neglect friction

Given data       $w = 25$  mm       $h = 50$  mm       $Q = 0.025 \frac{\text{m}^3}{\text{s}}$        $\rho = 750 \frac{\text{kg}}{\text{m}^3}$

From continuity       $Q = U_1 \cdot 2 \cdot h \cdot w$        $U_1 = \frac{Q}{2 \cdot w \cdot h}$        $U_1 = 10.0 \frac{\text{m}}{\text{s}}$

Also       $-\rho \cdot U_1 \cdot A_1 + \int \rho \cdot u_2 dA = 0$

$$U_1 \cdot 2 \cdot h \cdot w = w \cdot \int_{-h}^h u_{\max} \cdot \left(1 - \frac{y^2}{h^2}\right) dy = w \cdot u_{\max} \cdot \left[ h - (-h) - \left[ \frac{h}{3} - \left(-\frac{h}{3}\right) \right] \right] = w \cdot u_{\max} \cdot \frac{4}{3} \cdot h$$


Hence       $u_{\max} = \frac{3}{2} \cdot U_1$        $u_{\max} = 15 \frac{\text{m}}{\text{s}}$

For x momentum       $p_1 \cdot A - p_2 \cdot A = V_1 \cdot (-\rho_1 \cdot V_1 \cdot A) + \int \rho_2 \cdot u_2 \cdot u_2 dA_2$       Note that there is no  $R_x$  (no friction)

$$p_1 - p_2 = -\rho \cdot U_1^2 + \frac{w}{A} \cdot \int_{-h}^h \rho \cdot u_{\max}^2 \cdot \left(1 - \frac{y^2}{h^2}\right)^2 dy = -\rho \cdot U_1^2 + \frac{\rho \cdot u_{\max}^2}{h} \cdot \left[ 2 \cdot h - 2 \cdot \left(\frac{2}{3} \cdot h\right) + 2 \cdot \left(\frac{1}{5} \cdot h\right) \right]$$

$$\Delta p = p_1 - p_2 = -\rho \cdot U_1^2 + \frac{8}{15} \cdot \rho \cdot u_{\max}^2 = \rho \cdot U_1 \cdot \left[ \frac{8}{15} \cdot \left(\frac{3}{2}\right)^2 - 1 \right]$$

Hence       $\Delta p = \frac{1}{5} \cdot \rho \cdot U_1^2$        $\Delta p = 15.0 \cdot \text{kPa}$




## Problem 4.102

[Difficulty: 3]

**4.102** An incompressible fluid flows steadily in the entrance region of a circular tube of radius  $R = 75$  mm. The flow rate is  $Q = 0.1$  m<sup>3</sup>/s. Find the uniform velocity  $U_1$  at the entrance. The velocity distribution at a section downstream is

$$\frac{u}{u_{\max}} = 1 - \left(\frac{r}{R}\right)^2$$

Evaluate the maximum velocity at the downstream section. Calculate the pressure drop that would exist in the channel if viscous friction at the walls could be neglected.



**Given:** Data on flow in 2D channel

**Find:** Maximum velocity; Pressure drop

**Solution:**

Basic equations: Continuity, and momentum flux in x direction

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad F_x = F_{\dot{x}} + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Neglect friction

Given data  $R = 75$  mm  $Q = 0.1 \frac{\text{m}^3}{\text{s}}$   $\rho = 850 \frac{\text{kg}}{\text{m}^3}$

From continuity  $Q = U_1 \cdot \pi \cdot R^2$   $U_1 = \frac{Q}{\pi \cdot R^2}$   $U_1 = 5.66 \frac{\text{m}}{\text{s}}$

Also  $-\rho \cdot U_1 \cdot A_1 + \int \rho \cdot u_2 dA = 0$

$$U_1 \cdot \pi \cdot R^2 = \int_0^R u_{\max} \cdot \left(1 - \frac{r^2}{R^2}\right) \cdot 2 \cdot \pi \cdot r dr = 2 \cdot \pi \cdot u_{\max} \cdot \left(\frac{R^2}{2} - \frac{R^4}{4 \cdot R^2}\right) = 2 \cdot \pi \cdot u_{\max} \cdot \frac{R^2}{4} = \pi \cdot u_{\max} \cdot \frac{R^2}{2}$$


Hence  $u_{\max} = 2 \cdot U_1$   $u_{\max} = 11.3 \frac{\text{m}}{\text{s}}$

For x momentum  $p_1 \cdot A - p_2 \cdot A = V_1 \cdot (-\rho_1 \cdot V_1 \cdot A) + \int \rho_2 \cdot u_2 \cdot u_2 dA_2$  Note that there is no  $R_x$  (no friction)

$$(p_1 - p_2) \cdot \pi \cdot R^2 = -\rho \cdot \pi \cdot R^2 \cdot U_1^2 + \int_0^R \rho \cdot u_{\max}^2 \cdot \left(1 - \frac{r^2}{R^2}\right)^2 \cdot 2 \cdot \pi \cdot r dr = -\rho \cdot \pi \cdot R^2 \cdot U_1^2 + 2 \cdot \pi \cdot \rho \cdot u_{\max}^2 \cdot \left(\frac{R^2}{2} - 2 \cdot \frac{R^4}{4 \cdot R^2} + \frac{R^6}{6 \cdot R^4}\right)$$

$$\Delta p = p_1 - p_2 = -\rho \cdot U_1^2 + \frac{1}{3} \cdot \rho \cdot u_{\max}^2 = -\rho \cdot U_1^2 + \frac{1}{3} \cdot \rho \cdot (2 \cdot U_1)^2 = \rho \cdot U_1 \cdot \left[\frac{1}{3} \cdot (2)^2 - 1\right] = \frac{1}{3} \cdot \rho \cdot U_1^2$$

Hence  $\Delta p = \frac{1}{3} \times 850 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(5.66 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   $\Delta p = 9.08 \cdot \text{kPa}$




### Problem 4.103

[Difficulty: 3]

**4.103** Air enters a duct, of diameter  $D = 25.0$  mm, through a well-rounded inlet with uniform speed,  $U_1 = 0.870$  m/s. At a downstream section where  $L = 2.25$  m, the fully developed velocity profile is

$$\frac{u(r)}{U_c} = 1 - \left(\frac{r}{R}\right)^2$$

The pressure drop between these sections is  $p_1 - p_2 = 1.92$  N/m<sup>2</sup>. Find the total force of friction exerted by the tube on the air.



Solution: Apply continuity and momentum to CV, CS

Basic equations:  $\frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$  (1)

$F_{sx} + F_{Bx} = \frac{d}{dt} \int_{CV} \rho u dV + \int_{CS} \rho u \vec{V} \cdot d\vec{A}$  (2)

Assumptions: (1) Steady flow (2) Incompressible flow (3) Uniform flow at inlet (4)  $F_{Bx} = 0$

Then  $0 = \{-\rho U_1 A_1\} + \int \rho u dA = -\rho U_1 \pi R^2 + \int_0^R \rho U_c [1 - (\frac{r}{R})^2] 2\pi r dr$

$0 = -\rho U_1 \pi R^2 + 2\pi \rho U_c \int_0^R (1 - \lambda^2) \lambda d\lambda$  or  $0 = -U_1 + 2U_c [\frac{\lambda^2}{2} - \frac{\lambda^4}{4}]_0^R$

Thus  $0 = -U_1 + \frac{1}{2} U_c$  or  $U_c = 2U_1$  ( $\lambda = r/R$ )

From momentum  $R_x + p_1 A_1 - p_2 A_2 = u_1 \{-\rho U_1 A_1\} + \int u_2 \{+\rho u_2 dA_2\}$

$u_1 = U_1$        $u_2 = U_c [1 - (\frac{r}{R})^2]$

so  $\int_0^R U_c [1 - (\frac{r}{R})^2] \rho U_c [1 - (\frac{r}{R})^2] 2\pi r dr = 2\pi \rho U_c^2 R^2 \int_0^1 (1 - \lambda^2)(1 - \lambda^2) \lambda d\lambda$   
 $= 2\pi \rho U_c^2 R^2 \int_0^1 (1 - 2\lambda^2 + \lambda^4) \lambda d\lambda = 2\pi \rho U_c^2 R^2 [\frac{\lambda^2}{2} - \frac{\lambda^4}{2} + \frac{\lambda^6}{6}]_0^1 = \frac{1}{3} \pi \rho U_c^2 R^2$

Substituting,

$R_x + (p_1 - p_2) \pi R^2 = -\pi \rho U_1^2 R^2 + \frac{1}{3} \pi \rho U_c^2 R^2 = -\pi \rho U_1^2 R^2 + \frac{1}{3} \pi \rho (2U_1)^2 R^2$

$R_x = -(p_1 - p_2) \frac{\pi D^2}{4} + \frac{1}{3} \rho U_1^2 \frac{\pi D^2}{4}$

$= -1.92 \frac{N}{m^2} \times \frac{\pi}{4} (0.025)^2 m^2 + \frac{1}{3} \times 1.23 \frac{kg}{m^3} \times (0.870)^2 \frac{m^2}{s^2} \times \frac{\pi}{4} (0.025)^2 m^2 \times \frac{N \cdot s^2}{kg \cdot m}$

$R_x = -7.90 \times 10^{-4} N$  (to left on CV, since  $< 0$ )

$R_x$




## Problem 4.105

[Difficulty: 4]

**4.105** A fluid with density  $\rho = 750 \text{ kg/m}^3$  flows along a flat plate of width 1 m. The undisturbed freestream speed is  $U_0 = 10 \text{ m/s}$ . At  $L = 1 \text{ m}$  downstream from the leading edge of the plate, the boundary-layer thickness is  $\delta = 5 \text{ mm}$ . The velocity profile at this location is

$$\frac{u}{U_0} = \frac{3}{2} \frac{y}{\delta} - \frac{1}{2} \left(\frac{y}{\delta}\right)^3$$

Plot the velocity profile. Calculate the horizontal component of force required to hold the plate stationary.



**Given:** Data on flow of boundary layer

**Find:** Plot of velocity profile; force to hold plate


**Solution:**

Basic equations: Continuity, and momentum flux in x direction

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad F_x = F_{\dot{S}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible 3) No net pressure force

Given data  $\rho = 750 \cdot \frac{\text{kg}}{\text{m}^3}$   $w = 1 \cdot \text{m}$   $U_0 = 10 \cdot \frac{\text{m}}{\text{s}}$   $L = 1 \cdot \text{m}$   $\delta = 5 \cdot \text{mm}$



From continuity  $-\rho \cdot U_0 \cdot w \cdot \delta + m_{bc} + \int_0^\delta \rho \cdot u \cdot w \, dy = 0$  where  $m_{bc}$  is the mass flow rate across bc (Note: software cannot render a dot!)

Hence  $m_{bc} = \int_0^\delta \rho \cdot (U_0 - u) \cdot w \, dy$

For x momentum  $-F_f = U_0 \cdot (-\rho \cdot U_0 \cdot w \cdot \delta) + U_0 \cdot m_{bc} + \int_0^\delta u \cdot \rho \cdot u \cdot w \, dy = \int_0^\delta [-U_0^2 + u^2 + U_0 \cdot (U_0 - u)] \cdot w \, dy$

Then the drag force is  $F_f = \int_0^\delta \rho \cdot u \cdot (U_0 - u) \cdot w \, dy = \int_0^\delta \rho \cdot U_0^2 \cdot \frac{u}{U_0} \cdot \left(1 - \frac{u}{U_0}\right) \, dy$

But we have

$$\frac{u}{U_0} = \frac{3}{2} \cdot \eta - \frac{1}{2} \cdot \eta^3 \quad \text{where we have used substitution} \quad y = \delta \cdot \eta$$

$$\frac{F_f}{w} = \int_0^{\eta=1} \rho \cdot U_0^2 \cdot \delta \cdot \frac{u}{U_0} \cdot \left(1 - \frac{u}{U_0}\right) d\eta = \rho \cdot U_0^2 \cdot \delta \cdot \int_0^1 \left(\frac{3}{2} \cdot \eta - \frac{9}{4} \cdot \eta^2 - \frac{1}{2} \cdot \eta^3 + \frac{3}{2} \cdot \eta^4 - \frac{1}{4} \cdot \eta^6\right) d\eta$$

$$\frac{F_f}{w} = \rho \cdot U_0^2 \cdot \delta \cdot \left(\frac{3}{4} - \frac{3}{4} - \frac{1}{8} + \frac{3}{10} - \frac{1}{28}\right) = 0.139 \cdot \rho \cdot U_0^2 \cdot \delta$$

Hence


$$\frac{F_f}{w} = 0.139 \times 750 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(10 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times 0.05 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\frac{F_f}{w} = 52.1 \frac{\text{N}}{\text{m}}$$

## Problem 4.106

[Difficulty: 4]

**4.106** Air at standard conditions flows along a flat plate. The undisturbed freestream speed is  $U_0 = 20$  m/s. At  $L = 0.4$  m downstream from the leading edge of the plate, the boundary-layer thickness is  $\delta = 2$  mm. The velocity profile at this location is approximated as  $u/U_0 = y/\delta$ . Calculate the horizontal component of force per unit width required to hold the plate stationary.



**Given:** Data on flow of boundary layer

**Find:** Force on plate per unit width

**Solution:**

Basic equations: Continuity, and momentum flux in x direction

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

$$F_x = F_{\dot{M}_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible 3) No net pressure force

From continuity  $-\rho \cdot U_0 \cdot w \cdot \delta + m_{bc} + \int_0^\delta \rho \cdot u \cdot w dy = 0$  where  $m_{bc}$  is the mass flow rate across bc (Note: software cannot render a dot!)

Hence  $m_{bc} = \int_0^\delta \rho (U_0 - u) \cdot w dy$

For x momentum  $-F_f = U_0 \cdot (-\rho \cdot U_0 \cdot w \cdot \delta) + U_0 \cdot m_{bc} + \int_0^\delta u \cdot \rho \cdot u \cdot w dy = \int_0^\delta [-U_0^2 + u^2 + U_0 \cdot (U_0 - u)] \cdot w dy$

Then the drag force is  $F_f = \int_0^\delta \rho \cdot u \cdot (U_0 - u) \cdot w dy = \int_0^\delta \rho \cdot U_0^2 \cdot \frac{u}{U_0} \cdot \left(1 - \frac{u}{U_0}\right) dy$

But we have  $\frac{u}{U_0} = \frac{y}{\delta}$  where we have used substitution  $y = \delta \cdot \eta$

$$\frac{F_f}{w} = \int_0^{\eta=1} \rho \cdot U_0^2 \cdot \delta \cdot \frac{u}{U_0} \cdot \left(1 - \frac{u}{U_0}\right) d\eta = \rho \cdot U_0^2 \cdot \delta \cdot \int_0^1 \eta \cdot (1 - \eta) d\eta$$

$$\frac{F_f}{w} = \rho \cdot U_0^2 \cdot \delta \cdot \left(\frac{1}{2} - \frac{1}{3}\right) = \frac{1}{6} \cdot \rho \cdot U_0^2 \cdot \delta$$

Hence  $\frac{F_f}{w} = \frac{1}{6} \times 1.225 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(20 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times \frac{2}{1000} \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$  (using standard atmosphere density)

$$\frac{F_f}{w} = 0.163 \cdot \frac{\text{N}}{\text{m}}$$






# Problem 4.108


[Difficulty: 4]

**4.108** Gases leaving the propulsion nozzle of a rocket are modeled as flowing radially outward from a point upstream from the nozzle throat. Assume the speed of the exit flow,  $V_e$ , has constant magnitude. Develop an expression for the axial thrust,  $T_a$ , developed by flow leaving the nozzle exit plane. Compare your result to the one-dimensional approximation,  $T = \dot{m}V_e$ . Evaluate the percent error for  $\alpha = 15^\circ$ . Plot the percent error versus  $\alpha$  for  $0 \leq \alpha \leq 22.5^\circ$ .



Solution:

Apply definitions  $\dot{m} = \int_A \rho v dA$ ,  $T_a = \int_A u \rho v dA$ . Use spherically symmetric flow.



The mass flow rate is [assuming  $\rho_e \neq \rho_e(\theta)$ ]  
 $\dot{m} = \int_A \rho v dA = \int_0^\alpha \rho_e V_e (2\pi R \sin \theta) R d\theta = 2\pi \rho_e V_e R^2 [-\cos \theta]_0^\alpha = 2\pi \rho_e V_e R^2 (1 - \cos \alpha)$

The one-dimensional approximation for thrust is then

$$T = \dot{m}V_e = 2\pi \rho_e V_e^2 R^2 (1 - \cos \alpha) \quad \leftarrow T_{1-D}$$

The axial thrust is given by


$$T_a = \int u \rho v dA = \int_0^\alpha V_e \cos \theta \rho_e V_e (2\pi R \sin \theta) R d\theta = 2\pi \rho_e V_e^2 R^2 \int_0^\alpha \sin \theta \cos \theta d\theta$$

$$T_a = 2\pi \rho_e V_e^2 R^2 \left[ \frac{\sin^2 \theta}{2} \right]_0^\alpha = \pi \rho_e V_e^2 R^2 \sin^2 \alpha \quad \leftarrow T_a$$

The error in the one-dimensional approximation is

$$e = \frac{T_{1-D} - T_a}{T_a} = \frac{T_{1-D}}{T_a} - 1 = \frac{2\pi \rho_e V_e^2 R^2 (1 - \cos \alpha)}{\pi \rho_e V_e^2 R^2 \sin^2 \alpha} - 1 = \frac{2(1 - \cos \alpha)}{\sin^2 \alpha} - 1 \quad \dots (1)$$

The percent error is plotted as a function of  $\alpha$




For  $\alpha = 15^\circ$   
 $e_{15} = \frac{2(1 - \cos 15)}{\sin^2 15} - 1$

$e_{15} = 0.0173$  or 1.73%  $e_{15}$

### Problem 4.109

[Difficulty: 4]

**4.109** When a plane liquid jet strikes an inclined flat plate, it splits into two streams of equal speed but unequal thickness. For frictionless flow there can be no tangential force on the plate surface. Use this assumption to develop an expression for  $h_2/h$  as a function of plate angle,  $\theta$ . Plot your results and comment on the limiting cases,  $\theta = 0$  and  $\theta = 90^\circ$ .




Solution: Apply the x component of the momentum equation using the CV and coordinates shown.

Basic equation:

$$=0(1) \quad =0(2) \quad =0(3)$$

$$F_{\rho x} + F_{\theta x} = \frac{d}{dt} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$



Assumptions: (1) No surface force on CV

(2) Neglect body forces

(3) Steady flow

(4) No change in jet speed:  $V_1 = V_2 = V_3 = V$

(5) Uniform flow at each section

From continuity for uniform incompressible flow  $0 = -\rho V w h + \rho V w h_2 + \rho V w h_3$

or

$$h = h_2 + h_3 = h_1 \quad \text{or} \quad h_3 = h_1 - h_2$$

From momentum

$$0 = u_1 \{-\rho V w h_1\} + u_2 \{+\rho V w h_2\} + u_3 \{+\rho V w h_3\}$$


$$u_1 = V \sin \theta \quad u_2 = V \quad u_3 = -V$$

$$0 = -\rho V^2 \sin \theta w h_1 + \rho V^2 w h_2 - \rho V^2 w h_3$$

Substituting from continuity and simplifying

$$0 = -\sin \theta h_1 + h_2 - (h_1 - h_2) \quad \text{so} \quad \frac{h_2}{h} = \frac{h_2}{h_1} = \frac{1 + \sin \theta}{2}$$

Plot:




At  $\theta = 0$ ,  $\frac{h_2}{h} = 0.5$ ; flow is equally split when plate is  $\perp$  to jet.

At  $\theta = 90^\circ$ ,  $\frac{h_2}{h} = 1.0$ ; plate has no effect on flow.

### Problem \*4.110

[Difficulty: 4]

\*4.110 Two large tanks containing water have small smoothly contoured orifices of equal area. A jet of liquid issues from the left tank. Assume the flow is uniform and unaffected by friction. The jet impinges on a vertical flat plate covering the opening of the right tank. Determine the minimum value for the height,  $h$ , required to keep the plate in place over the opening of the right tank.



Solution: Apply Bernoulli and momentum equations, use CV enclosing plate, as shown.

Basic equations:  $\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{constant}$

$$F_{sx} + F_{bx} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

$= 0(5) \quad = 0(1)$

- Assumptions:
- (1) Steady flow
  - (2) Incompressible flow
  - (3) Flow along a streamline
  - (4) No friction
  - (5)  $F_{bx} = 0$

Apply Bernoulli from water surface to jet

$$\frac{p}{\rho} + \frac{V^2}{2} + gh = \frac{p}{\rho} + \frac{V^2}{2} + g(0) \quad \text{so that } V^2 = 2gh \text{ or } V = \sqrt{2gh}$$

$\ll V^2$

From fluid statics,  $p_{3g} = \rho g H$

From momentum

$$-p_{3g} A = -\rho g H A = u_1 \{-\rho V A\} + u_2 \{+\rho V A\} = -\rho V^2 A$$

$$u_1 = V \quad u_2 = 0$$

Thus, using Bernoulli,

$$\rho g H A = \rho V^2 A = \rho (2gh) A = 2\rho g h A$$

and


$$h = \frac{H}{2}$$

$h$

## Problem \*4.111

[Difficulty: 4]

**\*4.111** A horizontal axisymmetric jet of air with 0.5 in. diameter strikes a stationary vertical disk of 8 in. diameter. The jet speed is 225 ft/s at the nozzle exit. A manometer is connected to the center of the disk. Calculate (a) the deflection,  $h$ , if the manometer liquid has  $SG = 1.75$  and (b) the force exerted by the jet on the disk.



**Given:** Air jet striking disk

**Find:** Manometer deflection; Force to hold disk

**Solution:**

Basic equations: Hydrostatic pressure, Bernoulli, and momentum flux in x direction

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant}$$

$$F_x = F_{\dot{S}} + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible 3) No friction 4) Flow along streamline 5) Uniform flow 6) Horizontal flow ( $g_x = 0$ )

Applying Bernoulli between jet exit and stagnation point

$$\frac{p}{\rho_{\text{air}}} + \frac{V^2}{2} = \frac{p_0}{\rho_{\text{air}}} + 0$$

$$p_0 - p = \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2$$

But from hydrostatics

$$p_0 - p = SG \cdot \rho \cdot g \cdot \Delta h \quad \text{so}$$

$$\Delta h = \frac{\frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2}{SG \cdot \rho \cdot g} = \frac{\rho_{\text{air}} \cdot V^2}{2 \cdot SG \cdot \rho \cdot g}$$

$$\Delta h = 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(225 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{1}{2 \cdot 1.75} \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \quad \Delta h = 0.55 \cdot \text{ft} \quad \Delta h = 6.6 \cdot \text{in}$$

For x momentum

$$R_x = V \cdot (-\rho_{\text{air}} \cdot A \cdot V) = -\rho_{\text{air}} \cdot V^2 \cdot \frac{\pi \cdot D^2}{4}$$

$$R_x = -0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(225 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{\pi \cdot \left(\frac{0.5 \cdot \text{ft}}{12}\right)^2}{4} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = -0.164 \cdot \text{lbf}$$

The force of the jet on the plate is then


$$F = -R_x$$

$$F = 0.164 \cdot \text{lbf}$$

## Problem \*4.112

[Difficulty: 3]

**\*4.112** Students are playing around with a water hose. When they point it straight up, the water jet just reaches one of the windows of Professor Pritchard's office, 10 m above. If the hose diameter is 1 cm, estimate the water flow rate (L/min). Professor Pritchard happens to come along and places his hand just above the hose to make the jet spray sideways axisymmetrically. Estimate the maximum pressure, and the total force, he feels. The next day the students again are playing around, and this time aim at Professor Fox's window, 15 m above. Find the flow rate (L/min) and the total force and maximum pressure when he, of course, shows up and blocks the flow.



**Given:** Water jet shooting upwards; striking surface

**Find:** Flow rate; maximum pressure; Force on hand

### Solution:

Basic equations: Bernoulli and momentum flux in x direction

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad F_x = F_{\dot{x}} + F_{R_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure throughout 4) Uniform flow

Given data  $h = 10\text{-m}$   $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$   $D = 1\text{-cm}$

Using Bernoulli between the jet exit and its maximum height h  $\frac{p_{\text{atm}}}{\rho} + \frac{V^2}{2} = \frac{p_{\text{atm}}}{\rho} + g \cdot h$

or  $V = \sqrt{2 \cdot g \cdot h}$   $V = 14.0 \frac{\text{m}}{\text{s}}$

Then  $Q = \frac{\pi}{4} \cdot D^2 \cdot V$   $Q = 66.0 \frac{\text{L}}{\text{min}}$

For Dr. Pritchard the maximum pressure is obtained from Bernoulli  $\frac{p_{\text{atm}}}{\rho} + \frac{V^2}{2} = \frac{p_{\text{max}}}{\rho}$   $p = \frac{1}{2} \cdot \rho \cdot V^2$   $p = 98.1 \cdot \text{kPa}$  (gage)

For Dr. Pritchard blocking the jet, from x momentum applied to the CV  $R_x = u_1 \cdot (-\rho \cdot u_1 \cdot A_1) = -\rho \cdot V^2 \cdot A$

Hence  $F = \rho \cdot V^2 \cdot \frac{\pi}{4} \cdot D^2$   $F = 15.4 \text{ N}$

Repeating for Dr. Fox  $h = 15\text{-m}$   $V = \sqrt{2 \cdot g \cdot h}$   $V = 17.2 \frac{\text{m}}{\text{s}}$   $Q = \frac{\pi}{4} \cdot D^2 \cdot V$   $Q = 80.8 \frac{\text{L}}{\text{min}}$


$p = \frac{1}{2} \cdot \rho \cdot V^2$   $p = 147.1 \cdot \text{kPa}$  (gage)

$F = \rho \cdot V^2 \cdot \frac{\pi}{4} \cdot D^2$   $F = 23.1 \text{ N}$

### Problem \*4.113

[Difficulty: 3]

\*4.113 A uniform jet of water leaves a 15-mm-diameter nozzle and flows directly downward. The jet speed at the nozzle exit plane is 2.5 m/s. The jet impinges on a horizontal disk and flows radially outward in a flat sheet. Obtain a general expression for the velocity the liquid stream would reach at the level of the disk. Develop an expression for the force required to hold the disk stationary, neglecting the mass of the disk and water sheet. Evaluate for  $h = 3$  m.



Solution: Apply Bernoulli and momentum equations. Use CV shown.

Basic equations:  $\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{constant} \quad (5)$

$$F_{Bz} + F_{Pz} = \frac{\partial}{\partial t} \int_{CV} w \rho dV + \int_{CS} w \rho \vec{V} \cdot d\vec{A}$$

$\uparrow = 0(6)$        $\uparrow = 0(1)$

Assumptions: (1) Steady flow

(2) Incompressible flow

(3) Flow along a streamline

(4) Frictionless flow

(5) Atmospheric pressure along jet

(6) Neglect water on plate;  $F_{Bz} = 0$

(7) Uniform flow at each section

The Bernoulli equation becomes

$$\frac{V_0^2}{2} + gh = \frac{V^2}{2} + g(0) \quad \text{or} \quad V^2 = V_0^2 + 2gh; \quad V = \sqrt{V_0^2 + 2gh}$$

From the momentum equation

$$R_z = w_1 \{-\rho V A\} + w_2 \{+\rho V_0 A_0\} = +\rho V^2 A$$

$$w_1 = -V \quad w_2 = 0$$

But from continuity,  $\dot{m} = \rho V_0 A_0 = \rho V A$ . Thus  $VA = V_0 A_0$ , and

$$R_z = \rho V_0 A_0 V = \rho V_0 A_0 \sqrt{V_0^2 + 2gh}$$

At  $h = 3.0$  m,


$$R_z = \frac{999 \text{ kg}}{\text{m}^3} \times \frac{2.5 \text{ m}}{\text{s}} \times \frac{\pi}{4} (0.015)^2 \text{ m}^2 \left[ (2.5)^2 \frac{\text{m}^2}{\text{s}^2} + 2 \times \frac{9.81 \text{ m}}{\text{s}^2} \times 3.0 \text{ m} \right]^{1/2} \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$R_z = 3.56 \text{ N (upward force)}$$

## Problem \*4.114

[Difficulty: 3]

**\*4.114** A 2-kg disk is constrained horizontally but is free to move vertically. The disk is struck from below by a vertical jet of water. The speed and diameter of the water jet at the nozzle exit are 10 m/s and 25 mm. Obtain a general expression for the speed of the water jet as a function of height,  $h$ . Find the height to which the disk will rise and remain stationary.



**Given:** Water jet striking disk

**Find:** Expression for speed of jet as function of height; Height for stationary disk

**Solution:**

Basic equations: Bernoulli; Momentum flux in z direction

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \qquad F_x = F_{\dot{V}} + F_B = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow

The Bernoulli equation becomes  $\frac{V_0^2}{2} + g \cdot 0 = \frac{V^2}{2} + g \cdot h \qquad V^2 = V_0^2 - 2 \cdot g \cdot h \qquad V = \sqrt{V_0^2 - 2 \cdot g \cdot h}$

Hence  $-M \cdot g = w_1 \cdot (-\rho \cdot w_1 \cdot A_1) = -\rho \cdot V^2 \cdot A$

But from continuity  $\rho \cdot V_0 \cdot A_0 = \rho \cdot V \cdot A \qquad \text{so} \qquad V \cdot A = V_0 \cdot A_0$

Hence we get  $M \cdot g = \rho \cdot V \cdot V \cdot A = \rho \cdot V_0 \cdot A_0 \cdot \sqrt{V_0^2 - 2 \cdot g \cdot h}$

Solving for h  $h = \frac{1}{2 \cdot g} \cdot \left[ V_0^2 - \left( \frac{M \cdot g}{\rho \cdot V_0 \cdot A_0} \right)^2 \right]$

$$h = \frac{1}{2} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \left[ \left( 10 \cdot \frac{\text{m}}{\text{s}} \right)^2 - \left[ 2 \cdot \text{kg} \times \frac{9.81 \cdot \text{m}}{\text{s}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{s}}{10 \cdot \text{m}} \times \frac{4}{\pi \cdot \left( \frac{25}{1000} \cdot \text{m} \right)^2} \right]^2 \right]$$

$h = 4.28 \text{ m}$


\*4.115 Water from a jet of diameter  $D$  is used to support the cone-shaped object shown. Derive an expression for the combined mass of the cone and water,  $M$ , that can be supported by the jet, in terms of parameters associated with a suitably chosen control volume. Use your expression to calculate  $M$  when  $V_0 = 10 \text{ m/s}$ ,  $H = 1 \text{ m}$ ,  $h = 0.8 \text{ m}$ ,  $D = 50 \text{ mm}$ , and  $\theta = 30^\circ$ . Estimate the mass of water in the control volume.

Solution: Apply continuity, Bernoulli, and momentum equations using CV shown.

Basic equations:  $0 = \frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

$$\frac{\rho_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{\rho_2}{\rho} + \frac{V_2^2}{2} + gz_2$$

$$F_{S_3} + F_{B_3} = \frac{d}{dt} \int_{CV} \omega \rho dV + \int_{CS} \omega \rho \vec{V} \cdot d\vec{A}$$



- Assumptions: (1) steady flow  
 (2) No friction  
 (3) Flow along a streamline } required for Bernoulli  
 (4) Incompressible flow  
 (5) Uniform flow at each cross-section  
 (6)  $F_{S_3} = 0$  since  $p_{atm}$  acts everywhere

Then  $0 = \{-\rho V_1 A_1\} + \{\rho V_2 A_2\}$  so  $V_1 A_1 = V_2 A_2$

From Bernoulli  
 $\frac{V_1^2}{2} + gz_1 = \frac{V_2^2}{2} + gz_2 = \frac{V_0^2}{2} = \frac{V_2^2}{2} + gH$ ;  $V_2^2 = V_0^2 - 2gH$

From momentum

$$F_{B_3} = \int_{CS} \omega \rho \vec{V} \cdot d\vec{A} = -Mg = \omega_1 \{-\rho V_1 A_1\} + \omega_2 \{\rho V_2 A_2\}$$

$$\omega_1 = V_0 \quad \omega_2 = V_2 \cos \theta$$

or  $-Mg = -V_0 \rho V_1 A_1 + V_2 \cos \theta \rho V_2 A_2 = \rho V_0 A_1 (V_2 \cos \theta - V_0)$

so  $M = \frac{(V_0 - V_2 \cos \theta) \rho V_0 A_1}{g}$

From Bernoulli

$$V_2 = (V_0^2 - 2gH)^{1/2} = \left[ (10)^2 \frac{\text{m}^2}{\text{s}^2} - 2 \times 9.81 \frac{\text{m}}{\text{s}^2} \cdot 1 \text{m} \right]^{1/2} = 8.97 \text{ m/s}$$

Substituting

$$M = \left( 10.0 \frac{\text{m}}{\text{s}} - 8.97 \frac{\text{m}}{\text{s}} \cdot \cos 30^\circ \right) \frac{999 \frac{\text{kg}}{\text{m}^3} \times 10 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} (0.050)^2 \text{m}^2 \cdot \text{s}^2}{9.81 \text{ m}}$$

$M = 4.46 \text{ kg}$  ← (total mass in CV: water + object)

To find mass of water in CV, we have 3 options:

(1) assume area of jet is constant

$$M = \rho V = \rho A_1 H = \frac{999 \text{ kg}}{\text{m}^3} \times \frac{\pi (0.05)^2 \text{ m}^2}{4} \times 1 \text{ m} = 1.96 \text{ kg}$$


(2) use a CV that encloses the free jet only

Continuity  $V_1 A_1 = V_2 A_2$

Bernoulli  $V_2 = (V_1^2 - 2gH)^{1/2}$

Momentum  $-M_w g = \dot{w}_1 \{-\rho V_1 A_1\} + \dot{w}_2 \{+\rho V_2 A_2\}$

$$\dot{w}_1 = V_1 = V_0 \quad \dot{w}_2 = V_2$$



Substituting in momentum

$$-M_w g = V_0 (-\rho V_0 A_1) + V_2 (+\rho V_0 A_1) = \rho V_0 A_1 (V_2 - V_0)$$

$$M_w = \frac{\rho V_0 A_1 (V_0 - V_2)}{g}$$

$$= \frac{999 \text{ kg}}{\text{m}^3} \times \frac{10 \text{ m}}{\text{s}} \times \frac{\pi (0.05)^2 \text{ m}^2}{4} (10 - 8.97) \frac{\text{m}}{\text{s}} \times \frac{1}{9.81 \text{ m/s}^2}$$

$$M_w = 2.06 \text{ kg}$$

$M_w$

(3) Evaluate the area at each cross-section using Bernoulli and continuity, then integrate to find  $V$ .

$$VA = V_0 A_1 = (V_0^2 - 2gz)^{1/2} A = V_0 A_1 \quad \text{so} \quad A = \frac{V_0 A_1}{(V_0^2 - 2gz)^{1/2}}$$

$$V = \int_0^H A dz = \int_0^H \frac{V_0 A_1}{(V_0^2 - 2gz)^{1/2}} dz = A_1 \int_0^H \frac{V_0}{2g} \frac{1}{(1 - \frac{2gz}{V_0^2})^{1/2}} d(\frac{2gz}{V_0^2})$$

This can be integrated. Let  $u = 1 - \frac{2gz}{V_0^2}$ , so  $\int = \int \frac{-du}{u^{1/2}}$

$$\text{Then } V = A_1 \frac{V_0}{2g} \left[ -2(1 - \frac{2gz}{V_0^2})^{1/2} \right]_{z=0}^{z=H} = \frac{A_1}{g} [V_0^2 - V_0(V_0^2 - 2gH)^{1/2}]$$

and  $M_w = \rho V = \frac{\rho A_1 V_0 (V_0 - V_2)}{g} = 2.06 \text{ kg}$  (same as (2) above)

Thus the mass of the cone is  $M_c = M - M_w = 2.40 \text{ kg}$ .


$M_c$

{ Note: If  $V_0$  were smaller or  $H$  larger,  $V_2$  would differ more from  $V_0$  and the jet area would increase significantly. Option (2) would still give the correct result with little effort. }

## Problem \*4.116

[Difficulty: 3]

**\*4.116** A stream of water from a 50-mm-diameter nozzle strikes a curved vane, as shown. A stagnation tube connected to a mercury-filled U-tube manometer is located in the nozzle exit plane. Calculate the speed of the water leaving the nozzle. Estimate the horizontal component of force exerted on the vane by the jet. Comment on each assumption used to solve this problem.



**Given:** Stream of water striking a vane

**Find:** Water speed; horizontal force on vane

**Solution:**

Basic equations: Bernoulli; Momentum flux in x direction

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad F_x = F_{\vec{x}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow

Given or available data  $D = 50 \text{ mm}$   $\rho_{\text{water}} = 1000 \frac{\text{kg}}{\text{m}^3}$   $\rho_{\text{Hg}} = 13.6 \rho_{\text{water}}$   $\theta = 30 \text{ deg}$   $\Delta h = 0.75 \text{ m}$

From Bernoulli  $p_0 = p + \frac{1}{2} \cdot \rho_{\text{water}} \cdot V^2$  and for the manometer  $p_0 - p = \rho_{\text{Hg}} \cdot g \cdot \Delta h$

Combining  $\frac{1}{2} \cdot \rho_{\text{water}} \cdot V^2 = \rho_{\text{Hg}} \cdot g \cdot \Delta h$  or  $V = \sqrt{\frac{2 \cdot \rho_{\text{Hg}} \cdot g \cdot \Delta h}{\rho_{\text{water}}}}$   $V = 14.1 \frac{\text{m}}{\text{s}}$

Applying x momentum to the vane  $R_x = \rho_{\text{water}} \cdot V \cdot \left( -V \cdot \frac{\pi}{4} \cdot D^2 \right) + \rho_{\text{water}} \cdot (-V \cdot \cos(\theta)) \cdot \left( V \cdot \frac{\pi}{4} \cdot D^2 \right)$

$$R_x = -\rho_{\text{water}} \cdot V^2 \cdot \frac{\pi}{4} \cdot D^2 \cdot (1 + \cos(\theta)) \quad R_x = -733 \text{ N}$$

Assuming frictionless, incompressible flow with no net pressure force is realistic, except along the vane where friction will reduce flow momentum at the exit.

## Problem \*4.117

[Difficulty: 2]

**\*4.117** A Venturi meter installed along a water pipe consists of a convergent section, a constant-area throat, and a divergent section. The pipe diameter is  $D = 100$  mm, and the throat diameter is  $d = 50$  mm. Find the net fluid force acting on the convergent section if the water pressure in the pipe is 200 kPa (gage) and the flow rate is 1000 L/min. For this analysis, neglect viscous effects.

**Given:** Data on flow and venturi geometry

**Find:** Force on convergent section; water pressure

**Solution:**

Basic equations:

Bernoulli equation and x momentum  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const} \quad F_x = F_{\vec{x}} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$

The given data is  $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$        $D = 100 \cdot \text{mm}$        $d = 50 \cdot \text{mm}$        $p_1 = 200 \cdot \text{kPa}$        $Q = 1000 \cdot \frac{\text{L}}{\text{min}}$

For pressure we first need the velocities

$$A_1 = \frac{\pi \cdot D^2}{4} \quad A_1 = 0.00785 \text{ m}^2 \quad A_2 = \frac{\pi}{4} \cdot d^2 \quad A_2 = 0.00196 \text{ m}^2$$

Then  $V_1 = \frac{Q}{\frac{\pi}{4} \cdot D^2} \quad V_1 = 2.12 \frac{\text{m}}{\text{s}} \quad V_2 = \frac{Q}{A_2} \quad V_2 = 8.49 \frac{\text{m}}{\text{s}}$

Applying Bernoulli between inlet and throat  $\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2}$

Solving for  $p_2$   $p_2 = p_1 + \frac{\rho}{2} \cdot (V_1^2 - V_2^2)$

$$p_2 = 200 \cdot \text{kPa} + \frac{1}{2} \cdot 999 \cdot \frac{\text{kg}}{\text{m}^3} \times (2.12^2 - 8.49^2) \cdot \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times \frac{\text{kN}}{1000 \cdot \text{N}} \quad p_2 = 166 \cdot \text{kPa}$$

Applying the horizontal component of momentum

$$-F + p_1 \cdot A_2 - p_2 \cdot A_2 = V_1 \cdot (-\rho \cdot V_1 \cdot A_1) + V_2 \cdot (\rho \cdot V_2 \cdot A_2)$$

or  $F = p_1 \cdot A_1 - p_2 \cdot A_2 + \rho \cdot (V_1^2 \cdot A_1 - V_2^2 \cdot A_2)$


$$F = 200 \cdot \frac{\text{kN}}{\text{m}^2} \times 0.00785 \cdot \text{m}^2 - 166 \cdot \frac{\text{kN}}{\text{m}^2} \times 0.00196 \cdot \text{m}^2 + 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ \left( 2.12 \cdot \frac{\text{m}}{\text{s}} \right)^2 \cdot 0.00785 \cdot \text{m}^2 - \left( 8.49 \cdot \frac{\text{m}}{\text{s}} \right)^2 \cdot 0.00196 \cdot \text{m}^2 \right] \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \times \text{m}}$$

$$F = 1.14 \text{ kN}$$

## Problem \*4.118

[Difficulty: 3]

**\*4.118** A plane nozzle discharges vertically 1200 L/s per unit width downward to atmosphere. The nozzle is supplied with a steady flow of water. A stationary, inclined, flat plate, located beneath the nozzle, is struck by the water stream. The water stream divides and flows along the inclined plate; the two streams leaving the plate are of unequal thickness. Frictional effects are negligible in the nozzle and in the flow along the plate surface. Evaluate the minimum gage pressure required at the nozzle inlet.



**Given:** Nozzle flow striking inclined plate

**Find:** Minimum gage pressure

**Solution:**

Basic equations: Bernoulli and y momentum

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const} \quad F_y = F_S + F_B = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

The given data is  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$   $q = 1200 \frac{\text{L}}{\text{s} \cdot \text{m}}$   $W = 80 \text{ mm}$   $h = 0.25 \text{ m}$   $w = 20 \text{ mm}$   $H = 7.5 \text{ m}$   $\theta = 30 \text{ deg}$

For the exit velocity and nozzle velocity  $V_2 = \frac{q}{W}$   $V_2 = 15.0 \frac{\text{m}}{\text{s}}$   $V_1 = V_2 \cdot \frac{w}{W}$   $V_1 = 3.75 \frac{\text{m}}{\text{s}}$

Then from Bernoulli  $p_1 + \frac{\rho}{2} \cdot V_1^2 = p_{\text{atm}} + \frac{\rho}{2} \cdot V_2^2$  or  $p_1 = \frac{\rho}{2} \cdot (V_2^2 - V_1^2) - \rho \cdot g \cdot h$   $p_1 = 103 \cdot \text{kPa}$  (gage)

Applying Bernoulli between 2 and the plate (state 3)

$$p_{\text{atm}} + \frac{\rho}{2} \cdot V_2^2 = p_{\text{atm}} + \frac{\rho}{2} \cdot V_3^2 - \rho \cdot g \cdot H \quad V_3 = \sqrt{V_2^2 + 2 \cdot g \cdot H} \quad V_3 = 19.3 \frac{\text{m}}{\text{s}}$$

For the plate there is no force along the plate (x momentum) as there is no friction. For the force normal to the plate (y momentum) we have

$$R_y = -V_3 \cdot \cos(\theta) \cdot (-\rho \cdot V_3 \cdot A_3) = -V_3 \cdot \cos(\theta) \cdot (-\rho \cdot q) \quad R_y = V_3 \cdot \cos(\theta) \cdot \rho \cdot q \quad R_y = 20.0 \cdot \frac{\text{kN}}{\text{m}}$$

## Problem \*4.119

[Difficulty: 3]

**\*4.119** You turn on the kitchen faucet very slightly, so that a very narrow stream of water flows into the sink. You notice that it is “glassy” (laminar flow) and gets narrower and remains “glassy” for about the first 50 mm of descent. When you measure the flow, it takes three min to fill a 1-L bottle, and you estimate the stream of water is initially 5 mm in diameter. Assuming the speed at any cross section is uniform and neglecting viscous effects, derive expressions for and plot the variations of stream speed and diameter as functions of  $z$  (take the origin of coordinates at the faucet exit). What are the speed and diameter when it falls to the 50-mm point?

**Given:** Water faucet flow

**Find:** Expressions for stream speed and diameter; plot

**Solution:**

Basic equation: Bernoulli 
$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$$

Assumptions: Laminar, frictionless, uniform flow



The given data is  $D_0 = 5 \cdot \text{mm}$        $h = 50 \cdot \text{mm}$        $Q = \frac{1 \cdot \text{L}}{3 \cdot \text{min}}$        $Q = 0.333 \frac{\text{L}}{\text{min}}$

The initial velocity is  $V_0 = \frac{Q}{\frac{\pi}{4} \cdot D_0^2}$        $V_0 = 0.283 \frac{\text{m}}{\text{s}}$


Then applying Bernoulli between the exit and any other location 
$$\frac{p_{\text{atm}}}{\rho} + \frac{V_0^2}{2} = \frac{p_{\text{atm}}}{\rho} + \frac{V^2}{2} - g \cdot z \quad (z \text{ downwards})$$

Then  $V(z) = \sqrt{V_0^2 + 2 \cdot g \cdot z}$       Also  $V_0 \cdot \frac{\pi}{4} \cdot D_0^2 = V \cdot \frac{\pi}{4} \cdot D^2$       so  $D(z) = \frac{D_0}{\left(1 + \frac{2 \cdot g \cdot z}{V_0^2}\right)^{\frac{1}{4}}}$

Evaluating at  $h$        $V(h) = 1.03 \frac{\text{m}}{\text{s}}$        $D(h) = 2.62 \cdot \text{mm}$



\*4.120 In ancient Egypt, circular vessels filled with water sometimes were used as crude clocks. The vessels were shaped in such a way that, as water drained from the bottom, the surface level dropped at constant rate,  $s$ . Assume that water drains from a small hole of area  $A$ . Find an expression for the radius of the vessel,  $r$ , as a function of the water level,  $h$ . Obtain an expression for the volume of water needed so that the clock will operate for  $n$  hours.



Solution: Apply conservation of mass and the Bernoulli equation.

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

$$\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{constant}$$

- Assumptions: (1) Quasi-steady flow;  $\frac{\partial}{\partial t}$  small  
 (2) Incompressible flow  
 (3) Uniform flow at each cross section  
 (4) Flow along a streamline  
 (5) No friction  
 (6)  $p_{air} \ll p_{H_2O}$

Writing Bernoulli from the liquid surface to the jet exit,

$$\frac{p_{atm}}{\rho} + \frac{s^2}{2} + gh = \frac{p_{atm}}{\rho} + \frac{V^2}{2} + g(0);$$

For  $s \ll V$ , then  $V = \sqrt{2gh}$ .

For the CV,

$$0 = \frac{\partial}{\partial t} \int_{V_{air}} \rho_{air} dV + \frac{\partial}{\partial t} \int_{V_{H_2O}} \rho_{H_2O} dV + \left\{ -\rho_{air} V_1 A_1 \right\} + \left\{ \rho_{H_2O} V A \right\}$$

or

$$0 = \rho \frac{dV}{dt} + \rho V A = \rho \pi r^2 \frac{dh}{dt} + \rho \sqrt{2gh} A = 0$$

But  $h$  decreases, so  $\frac{dh}{dt} = -s$ . Thus

$$\pi r^2 s = \sqrt{2gh} A \quad \text{or} \quad r = \sqrt{2g} \sqrt{\frac{A}{s}} h^{1/4}$$

For  $n$  hours' operation,  $H = ns$ , and

$$V = \int_0^H \pi r^2 dh = \int_0^{ns} \sqrt{2gh} \frac{A}{s} dh = \frac{2A}{3s} \sqrt{2g} (ns)^{3/2}$$

or

$$V = \frac{2A \sqrt{2g} n^{3/2} s^{1/2}}{3}$$

Check dimensions:


$$[V] = L^3 = \left[ A \sqrt{g} n^{3/2} s^{1/2} \right] = L^2 L^{1/2} t^{3/2} L^{1/2} t^{1/2} = L^3 \checkmark$$

# Problem \*4.121

[Difficulty: 4]

\*4.121 A stream of incompressible liquid moving at low speed leaves a nozzle pointed directly downward. Assume the speed at any cross section is uniform and neglect viscous effects. The speed and area of the jet at the nozzle exit are  $V_0$  and  $A_0$ , respectively. Apply conservation of mass and the momentum equation to a differential control volume of length  $dz$  in the flow direction. Derive expressions for the

variations of jet speed and area as functions of  $z$ . Evaluate the distance at which the jet area is half its original value. (Take the origin of coordinates at the nozzle exit.)



Solution: Apply continuity and momentum equations using CV shown.

Basic equations:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

$$F_B = \frac{\partial}{\partial t} \int_{CV} \rho \vec{r} dV + \int_{CS} \rho \vec{r} \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Steady flow  
 (2) Incompressible flow  
 (3) Uniform flow at each section  
 (4)  $p_{atm}$  acts everywhere }  $F_{Bz} = 0$   
 (5) No friction

Then  $0 = \int_{CS} \vec{V} \cdot d\vec{A} = \{-VA\} + \{+(V+dV)(A+dA)\}$ ;  $VA = V_0 A_0 = \text{constant}$

From momentum,

$$\rho g \left(A + \frac{dA}{2}\right) dz = V \{-pVA\} + (V+dV) \{-p(V+dV)(A+dA)\} = pVA dV$$

since  $dVdA \ll dA$ . Also, since  $dAdz \ll dz$ , the left side is  $\rho g A dz$ .

Thus  $\rho g A dz = pVA dV$  or  $V dV = g dz$

Integrating from  $V_0$  at  $z_0 = 0$  to  $V$  at  $z$ ,

$$\int_{V_0}^V V dV = \left[ \frac{V^2}{2} \right]_{V_0}^V = \frac{V^2}{2} - \frac{V_0^2}{2} = \int_{z_0}^z g dz = g(z - z_0) = gz$$

Thus  $V^2 = V_0^2 + 2gz$  or  $V(z) = \sqrt{V_0^2 + 2gz}$   $V(z)$

Since  $VA = V_0 A_0$ ,  $A = A_0 \frac{V_0}{V}$

$$A(z) = A_0 \frac{V_0}{\sqrt{V_0^2 + 2gz}} = \frac{A_0}{\sqrt{1 + 2gz/V_0^2}}$$
  $A(z)$

Solving for  $z$ ,


$$z = \frac{V_0^2}{2g} \left[ \left( \frac{A_0}{A} \right)^2 - 1 \right]$$

for  $\frac{A}{A_0} = \frac{1}{2}$ ,  $\frac{A_0}{A} = 2$ , and  $z_{1/2} = \frac{3V_0^2}{2g}$   $z_{1/2}$


### Problem \*4.122

[Difficulty: 4]

\*4.122 Incompressible fluid of negligible viscosity is pumped, at total volume flow rate  $Q$ , through a porous surface into the small gap between closely spaced parallel plates as shown. The fluid has only horizontal motion in the gap. Assume uniform flow across any vertical section. Obtain an expression for the pressure variation as a function of  $x$ . *Hint:* Apply conservation of mass and the momentum equation to a differential control volume of thickness  $dx$ , located at position  $x$ .



Solution: Apply continuity and  $x$  component of momentum equation.



Basic equations:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} (\vec{V} \cdot d\vec{A})$$

$$F_{Bx} + F_{px} = \frac{\partial}{\partial t} \int_{CV} \rho u dV + \int_{CS} \rho u \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Steady flow  
 (2) Incompressible flow  
 (3) Uniform flow at each section  
 (4) Neglect friction  
 (5)  $F_{Bx} = 0$

Then

$$0 = \int_{CS} \vec{V} \cdot d\vec{A} = \{-Vwh\} + \{-\frac{Q}{wh} wh dx\} + \{(V+dV)wh\}; wh dV = \frac{Q}{L} dx$$

$$V = \frac{Q}{wh} \frac{x}{L} + C; C=0 \text{ since } V(0)=0; V(x) = \frac{Q}{wh} \frac{x}{L}$$

From momentum,

$$pwh - (p+dp)wh = u_x \{-pVwh\} + u_{dx} \{-p \frac{Q}{wh} wh dx\} + u_{x+dx} \{p(V+dV)wh\}$$

$$u_x = V \quad u_{dx} = 0 \quad u_{x+dx} = V+dV$$

From continuity,  $(V+dV)wh = Vwh + Q \frac{dx}{L}$ , so

$$-dpwh = -pV^2wh + 0 + (V+dV)(Vwh + Q \frac{dx}{L})p$$

$$= -pV^2wh + pV^2wh + pVwh dV + VpQ \frac{dx}{L} + pQ dV \frac{dx}{L}$$

Neglecting products of differentials ( $dVdx \ll dx$ ), and with  $dV = \frac{Q}{wh} \frac{dx}{L}$

$$-dp = pVdV + \frac{VpQ}{wh} \frac{dx}{L} = pV \frac{Q}{wh} \frac{dx}{L} + \frac{VpQ}{wh} \frac{dx}{L} = 2p \frac{Q}{wh} \frac{x}{L} \frac{Q}{wh} \frac{dx}{L}$$

$$-dp = 2p \left(\frac{Q}{whL}\right)^2 x dx \quad p(x) = -p \left(\frac{Q}{whL}\right)^2 x^2 + C$$



If  $p(0) = p_0$ , then  $p(x) = p_0 - p \left(\frac{Q}{whL}\right)^2 \left(\frac{x}{L}\right)^2$

$p(x)$

## Problem \*4.123

[Difficulty: 4] Part 1/2

**\*4.123** Incompressible liquid of negligible viscosity is pumped, at total volume flow rate  $Q$ , through two small holes into the narrow gap between closely spaced parallel disks as shown. The liquid flowing away from the holes has only radial motion. Assume uniform flow across any vertical section and discharge to atmospheric pressure at  $r = R$ . Obtain an expression for the pressure variation and plot as a function of radius. *Hint:* Apply conservation of mass and the momentum equation to a differential control volume of thickness  $dr$  located at radius  $r$ .



Solution: Apply continuity and momentum equations to the differential CV shown.

Basic equations:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} \quad = 0(1)$$

$$F_{Sr} + F_{Br} = \frac{\partial}{\partial t} \int_{CV} V_r \rho dV + \int_{CS} V_r \rho \vec{V} \cdot d\vec{A} \quad = 0(5) \quad = 0(1)$$

Assumptions: (1) Steady flow

(2) Incompressible flow

(3) Uniform flow at each section

(4) Neglect friction

(5)  $F_{Br} = 0$

(6) No flow in  $\theta$  direction

(7)  $\sin \frac{d\theta}{2} = \frac{d\theta}{2}$

Then

$$0 = \int_{CS} \vec{V} \cdot d\vec{A} = \{-\rho V h r d\theta\} + \{\rho (V + dV) h (r + dr) d\theta\}; \quad V_r = \text{constant}$$

From momentum, For  $r = R$ ,  $Q = V_R 2\pi R h$ , so  $V_R = Q / 2\pi R h$

$$p h r d\theta + 2(p + \frac{dp}{2}) h dr \sin \frac{d\theta}{2} - (p + dp) h (r + dr) d\theta$$

$$= V \{-\rho V h r d\theta\} + (V + dV) \{\rho (V + dV) h (r + dr) d\theta\}$$

$$p h r d\theta + p h \frac{dr}{r} d\theta + \frac{1}{2} dp h dr d\theta - (p r + p \frac{dr}{r} + r dp + dr dp) h d\theta$$

$$= dV (\rho V h r d\theta) \quad \{\text{Note terms in braces are equal.}\}$$

Assuming products of differentials are much smaller than single differentials,

$$-r dp h d\theta = dV (\rho V h r d\theta) \quad \text{or} \quad dp = -\rho V dV$$

$$\text{Integrating, } p(r) - p(R) = -\rho \frac{V^2}{2} + \frac{\rho V_R^2}{2} \quad \text{or} \quad p(r) - p_{atm} = \frac{\rho}{2} (V_R^2 - V^2)$$

$$\text{Since } V_R = \frac{Q}{2\pi R h}, \text{ and } V_r = \text{constant, } \frac{V}{V_R} = \frac{R}{r}, \text{ so} \quad = \frac{\rho V_R^2}{2} \left[ 1 - \left( \frac{V}{V_R} \right)^2 \right]$$

$$p(r) - p_{atm} = \frac{\rho}{2} \left( \frac{Q}{2\pi R h} \right)^2 \left[ 1 - \left( \frac{R}{r} \right)^2 \right]$$


Note since  $r < R$ , that  $p(r) < p_{atm}$  between the disks.

# Problem \*4.123

[Difficulty: 4] Part 2/2

The pressure distribution is computed and plotted in Excel:

$r/R$	$P$
0.15	-43.4
0.20	-24.0
0.25	-15.0
0.30	-10.1
0.35	-7.16
0.40	-5.25
0.45	-3.94
0.50	-3.00
0.55	-2.31
0.60	-1.78
0.65	-1.37
0.70	-1.04
0.75	-0.78
0.80	-0.563
0.85	-0.384
0.90	-0.235
0.95	-0.108
1.00	0.000



## Problem \*4.124


[Difficulty: 5]

**\*4.124** The narrow gap between two closely spaced circular plates initially is filled with incompressible liquid. At  $t = 0$  the upper plate, initially  $h_0$  above the lower plate, begins to move downward toward the lower plate with constant speed,  $V_0$ , causing the liquid to be squeezed from the narrow gap. Neglecting viscous effects and assuming uniform flow in the radial direction, develop an expression for the velocity field between the parallel plates. *Hint:* Apply conservation of mass to a control volume with the outer surface located at radius  $r$ . Note that even though the speed of the upper plate is constant, the flow is unsteady. For  $V_0 = 0.01$  m/s and  $h_0 = 2$  mm, find the velocity at the exit radius  $R = 100$  mm at  $t = 0$  and  $t = 0.1$  s. Plot the exit velocity as a function of time, and explain the trend.

**Given:** Plates coming together

**Find:** Expression for velocity field; exit velocity; plot

**Solution:** Apply continuity using deformable CV as shown



Basic equation: 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Assumptions: Incompressible, uniform flow


Given data:  $V_0 = 0.01 \cdot \frac{m}{s}$        $h_0 = 2 \cdot mm$        $R = 100 \cdot mm$

Continuity becomes 
$$\frac{\partial V}{\partial t} + \int_{CS} \vec{V} \cdot d\vec{A} = 0 \quad \text{or} \quad \frac{\partial}{\partial t} (\pi \cdot r^2 \cdot h) + V \cdot 2 \cdot \pi \cdot r \cdot h = 0$$

or 
$$\pi \cdot r^2 \cdot \frac{dh}{dt} + V \cdot 2 \cdot \pi \cdot r \cdot h = \pi \cdot r^2 \cdot V_0 + V \cdot 2 \cdot \pi \cdot r \cdot h = 0$$
      Hence 
$$V(r) = V_0 \cdot \frac{r}{2 \cdot h}$$

If  $V_0$  is constant  $h = h_0 - V_0 \cdot t$       so 
$$V(r, t) = \frac{V_0 \cdot r}{2 \cdot (h_0 - V_0 \cdot t)}$$
      Note that  $t_{max} = \frac{h_0}{V_0}$        $t_{max} = 0.200$  s

Evaluating  $V(R, 0) = 0.250 \frac{m}{s}$        $V(R, 0.1 \cdot s) = 0.500 \frac{m}{s}$



The velocity greatly increases as the constant flow rate exits through a gap that becomes narrower with time.


\*4.125 Liquid falls vertically into a short horizontal rectangular open channel of width  $b$ . The total volume flow rate,  $Q$ , is distributed uniformly over area  $bL$ . Neglect viscous effects. Obtain an expression for  $h_1$  in terms of  $h_2$ ,  $Q$ , and  $b$ . Hint: Choose a control volume with outer boundary located at  $x = L$ . Sketch the surface profile,  $h(x)$ . Hint: Use a differential control volume of width  $dx$ .

Solution: Apply continuity and momentum equations to (i) finite CV, and (ii) differential CV, as shown.

Basic equations:

$$0 = \frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

$$F_{3x} + F_{px} = \frac{d}{dt} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$



Assumptions: (1) Steady flow

(2) Incompressible flow

(3) Uniform flow at each section

(4) Hydrostatic pressure distribution;  $F_p(h) = \rho g b \frac{h^2}{2}$

(5) No friction on bed

(6) Horizontal bed;  $F_{bx} = 0$

Then for finite CV shown,

$$0 = \int_{CS} \vec{V} \cdot d\vec{A} = -Q + V_2 b h_2; \quad V_2 = \frac{Q}{b h_2}$$

From momentum

$$\rho g b \frac{h_1^2}{2} - \rho g b \frac{h_2^2}{2} = u_1 \{0\} + u_2 \{+PQ\} + u_3 \{-PQ\}$$

$$u_2 = V_2 \quad u_3 = 0$$

$$\frac{\rho g b}{2} (h_1^2 - h_2^2) = V_2 P Q = \frac{Q}{b h_2} P Q = \frac{P Q^2}{b h_2}; \quad h_1 = \sqrt{h_2^2 + \frac{2Q^2}{g b^2 h_2}} \leftarrow h_1$$

For differential CV shown,

$$0 = \int_{CS} \vec{V} \cdot d\vec{A} = \{-Vbh\} + \{-\frac{Q}{bL} b dx\} + \{(V+dV)b(h+dh)\}$$

$$0 = -\frac{Q}{L} dx + b(hdV + Vdh) = -\frac{Q}{L} dx + b d(hV); \quad \frac{d(hV)}{dx} = \frac{Q}{L}$$

From momentum,

$$\rho g b \frac{h^2}{2} - \rho g b \frac{(h+dh)^2}{2} = V \{-P V b h\} + 0 \{-\frac{P Q}{L} dx\} + (V+dV) \{P(V+dV)b(h+dh)\}$$

Using continuity,

$$\frac{\rho g b}{2} (-2h dh + d^2 h^2) = -P V^2 b h + (V+dV) \{P V b h + \frac{P Q}{L} dx\}$$

Cont'd. →

$$-\rho g b h dh = -\rho \cancel{V^2} b h + \rho \cancel{V^2} b h + \rho V b h dV + \frac{\rho Q}{L} V dx + \frac{\rho Q}{L} dV \ll dx$$

or

$$-gh dh = V h dV + \frac{Q}{bL} V dx$$

From continuity,  $V h dV = -V^2 dh + \frac{Q}{bL} V dx$ , so

$$-gh dh = -V^2 dh + \frac{2Q}{bL} V dx$$

Solving,


$$\frac{dh}{dx} (V^2 - gh) = \frac{2Q}{bL} V$$

$$\frac{dh}{dx} = \frac{2QV}{bL(V^2 - gh)} = \frac{2QV}{bLgh(V^2/gh - 1)}$$

From finite CV analysis,  $h_1 > h_2$ , so  $\frac{dh}{dx} < 0$ . Thus  $V^2/gh < 1$ . As  $x$  increases,  $V \uparrow$  and  $h \uparrow$ . Therefore

$$\frac{V^2}{gh} \uparrow, \frac{V}{h} \uparrow, \text{ and } \left| \frac{dh}{dx} \right| \uparrow.$$

Sketch:



## Problem \*4.126

[Difficulty: 4] Part 1/2


**\*4.126** Design a clepsydra (Egyptian water clock)—a vessel from which water drains by gravity through a hole in the bottom and which indicates time by the level of the remaining water. Specify the dimensions of the vessel and the size of the drain hole; indicate the amount of water needed to fill the vessel and the interval at which it must be filled. Plot the vessel radius as a function of elevation.

**Discussion:** The original Egyptian water clock was an open water-filled vessel with an orifice in the bottom. The vessel shape was designed so that the water level dropped at a constant rate during use.

Water leaves the orifice at higher speed when the water level within the vessel is high, and at lower speed when the water level within the vessel is low. The size of the orifice is constant. Thus the instantaneous volume flow rate depends on the water level in the vessel.

The rate at which the water level falls in the vessel depends on the volume flow rate and the area of the water surface. The surface area at each water level must be chosen so that the water level within the vessel decreases at a constant rate. The continuity and Bernoulli equations can be applied to determine the required vessel shape so that the water surface level drops at a constant rate.

Use the CV and notation shown (Problem 4.97):



Solution: Basic equations are

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho d\mathcal{V} + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

$$\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{constant}$$

- Assumptions:
- (1) Quasi-steady flow
  - (2) Incompressible flow
  - (3) Uniform flow at each cross-section
  - (4) Flow along a streamline
  - (5) No friction
  - (6)  $p_{air} \ll p_{H_2O}$

Writing Bernoulli from the liquid surface to the jet exit,

$$\frac{p_{atm}}{\rho} + \frac{0^2}{2} + gh = \frac{p_{atm}}{\rho} + \frac{V^2}{2} + g(0)$$

For  $z \ll V$ , then  $V = \sqrt{2gh}$

For the CV,

$$0 = \frac{\partial}{\partial t} \int_{\mathcal{V}_{air}} \rho_{air} d\mathcal{V} + \frac{\partial}{\partial t} \int_{\mathcal{V}_{H_2O}} \rho_{H_2O} d\mathcal{V} + \left\{ -\rho_{air} V_1 A_1 \right\} + \left\{ \rho_{H_2O} V A \right\}$$

# Problem \*4.126

[Difficulty: 4] Part 2/2

$$\text{or } 0 = \rho \frac{dV}{dt} + \rho VA = \rho \pi r^2 \frac{dh}{dt} + \rho \sqrt{2gh} A$$

But  $h$  decreases, so  $\frac{dh}{dt} = -\Delta$ . Thus

$$\pi r^2 \Delta = \sqrt{2gh} A \quad \text{or} \quad r = \sqrt[4]{2g} \sqrt{\frac{A}{\pi \Delta}} h^{1/4}$$

For  $n$  hours operation,  $H = n\Delta$ , and

$$V = \int_0^H \pi r^2 dh = \int_0^{n\Delta} \sqrt{2gh} \frac{A}{\Delta} dh = \frac{2A}{3\Delta} \sqrt{2g} (n\Delta)^{3/2}$$

$$\text{or } V = \frac{2A\sqrt{2g}}{3} n^{3/2} \Delta^{1/2}$$

Evaluating and plotting:


**Input Parameters:**

Maximum water height:  $H = 0.5$  m  
 Number of hours' duration:  $n = 24$  hr

**Dimensionless Shape**

**Actual Shape**


$r/R$	$h/H$	$r$ (m)	$h$ (m)
-1	1.00	-0.309	0.500
-0.9	0.656	-0.278	0.328
-0.8	0.410	-0.247	0.205
-0.7	0.240	-0.216	0.120
-0.6	0.130	-0.185	0.065
-0.5	0.063	-0.155	0.031
-0.4	0.026	-0.124	0.013
-0.3	0.008	-0.093	0.004
-0.2	0.002	-0.062	0.001
-0.1	0.000	-0.031	0.000
0	0	0	0
0.1	0.000	0.031	0.000
0.2	0.002	0.062	0.001
0.3	0.008	0.093	0.004
0.4	0.026	0.124	0.013
0.5	0.063	0.155	0.031
0.6	0.130	0.185	0.065
0.7	0.240	0.216	0.120
0.8	0.410	0.247	0.205
0.9	0.656	0.278	0.328
1	1.000	0.309	0.500



## Problem \*4.127

[Difficulty: 3]

**4.127** A jet of water is directed against a vane, which could be a blade in a turbine or in any other piece of hydraulic machinery. The water leaves the stationary 40-mm-diameter nozzle with a speed of 25 m/s and enters the vane tangent to the surface at A. The inside surface of the vane at B makes angle  $\theta = 150^\circ$  with the x direction. Compute the force that must be applied to maintain the vane speed constant at  $U = 5$  m/s.



**Given:** Water jet striking moving vane

**Find:** Force needed to hold vane to speed  $U = 5$  m/s

**Solution:**

Basic equations: Momentum flux in x and y directions

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad F_y = F_{S_y} + F_{B_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Jet relative velocity is constant

Then 
$$R_x = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2) = -(V - U) \cdot [\rho \cdot (V - U) \cdot A] + (V - U) \cdot \cos(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$

$$R_x = \rho(V - U)^2 \cdot A \cdot (\cos(\theta) - 1) \quad A = \frac{\pi}{4} \cdot \left( \frac{40}{1000} \cdot \text{m} \right)^2 \quad A = 1.26 \times 10^{-3} \text{ m}^2$$

Using given data

$$R_x = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ (25 - 5) \cdot \frac{\text{m}}{\text{s}} \right]^2 \times 1.26 \times 10^{-3} \cdot \text{m}^2 \times (\cos(150 \cdot \text{deg}) - 1) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad R_x = -940 \text{ N}$$

Then 
$$R_y = v_1 \cdot (-\rho \cdot V_1 \cdot A_1) + v_2 \cdot (\rho \cdot V_2 \cdot A_2) = -0 + (V - U) \cdot \sin(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$


$$R_y = \rho(V - U)^2 \cdot A \cdot \sin(\theta) \quad R_y = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ (25 - 5) \cdot \frac{\text{m}}{\text{s}} \right]^2 \times 1.26 \times 10^{-3} \cdot \text{m}^2 \times \sin(150 \cdot \text{deg}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad R_y = 252 \text{ N}$$

Hence the force required is 940 N to the left and 252 N upwards to maintain motion at 5 m/s

## Problem 4.128

[Difficulty: 3]

**4.128** Water from a stationary nozzle impinges on a moving vane with turning angle  $\theta = 120^\circ$ . The vane moves away from the nozzle with constant speed,  $U = 10$  m/s, and receives a jet that leaves the nozzle with speed  $V = 30$  m/s. The nozzle has an exit area of  $0.004$  m<sup>2</sup>. Find the force that must be applied to maintain the vane speed constant.



**Given:** Water jet striking moving vane

**Find:** Force needed to hold vane to speed  $U = 10$  m/s

**Solution:**

Basic equations: Momentum flux in x and y directions

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad F_y = F_{S_y} + F_{B_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Jet relative velocity is constant

$$\text{Then } R_x = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2) = -(V - U) \cdot [\rho \cdot (V - U) \cdot A] + (V - U) \cdot \cos(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$

$$R_x = \rho(V - U)^2 \cdot A \cdot (\cos(\theta) - 1)$$

Using given data

$$R_x = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ (30 - 10) \cdot \frac{\text{m}}{\text{s}} \right]^2 \times 0.004 \cdot \text{m}^2 \times (\cos(120 \cdot \text{deg}) - 1) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad R_x = -2400 \text{ N}$$

$$\text{Then } R_y = v_1 \cdot (-\rho \cdot V_1 \cdot A_1) + v_2 \cdot (\rho \cdot V_2 \cdot A_2) = -0 + (V - U) \cdot \sin(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$


$$R_y = \rho(V - U)^2 \cdot A \cdot \sin(\theta) \quad R_y = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ (30 - 10) \cdot \frac{\text{m}}{\text{s}} \right]^2 \times 0.004 \cdot \text{m}^2 \times \sin(120 \cdot \text{deg}) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad R_y = 1386 \text{ N}$$

Hence the force required is 2400 N to the left and 1390 N upwards to maintain motion at 10 m/s

### Problem 4.129

[Difficulty: 2]

4.129 The circular dish, whose cross section is shown, has an outside diameter of 0.20 m. A water jet with speed of 35 m/s strikes the dish concentrically. The dish moves to the left at 15 m/s. The jet diameter is 20 mm. The dish has a hole at its center that allows a stream of water 10 mm in diameter to pass through without resistance. The remainder of the jet is deflected and flows along the dish. Calculate the force required to maintain the dish motion.



Solution: Apply continuity and x momentum equation to CV moving with dish as shown.

Basic equations:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

$$F_{sx} + F_{bx} = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V} \cdot d\vec{A}$$

- Assumptions:
- (1) Steady flow w.r.t. CV
  - (2) No pressure forces on CV
  - (3) Horizontal;  $F_{bx} = 0$
  - (4) Uniform flow at each section
  - (5) No change in speed of jet relative to vane
  - (6) Incompressible flow

Then

$$0 = \int_{CS} \vec{V}_{xyz} \cdot d\vec{A} = (V-U) \left( -\frac{\pi D^2}{4} + \frac{\pi d^2}{4} + A_{3,4} \right)$$

$$A_{3,4} = \frac{\pi}{4} (D^2 - d^2) = \frac{\pi}{4} [(0.020)^2 - (0.010)^2] \text{ m}^2 = 2.36 \times 10^{-4} \text{ m}^2$$

From the momentum equation

$$R_x = u_1 \left\{ -\rho(V-U) \frac{\pi D^2}{4} \right\} + u_2 \left\{ +\rho(V-U) \frac{\pi d^2}{4} \right\} + u_3 \left\{ +\rho(V-U) A_{3,4} \right\}$$

$$u_1 = V-U \quad u_2 = V-U \quad u_3 = -(V-U) \cos 40^\circ$$

$$R_x = -\rho(V-U)^2 \frac{\pi D^2}{4} + \rho(V-U)^2 \frac{\pi d^2}{4} - \rho(V-U)^2 \frac{\pi}{4} (D^2 - d^2) \cos 40^\circ$$

$$= -\rho(V-U)^2 \frac{\pi}{4} (D^2 - d^2) (1 + \cos 40^\circ)$$

$$= -999 \frac{\text{kg}}{\text{m}^3} \times (35 - 15)^2 \frac{\text{m}^2}{\text{s}^2} \times 2.36 \times 10^{-4} \text{ m}^2 (1 + \cos 40^\circ) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$R_x = -167 \text{ N (force must be applied to right)}$$


{ Note:  $R_y = Mg$ , since there is no net momentum flux in the y-direction. }

## Problem 4.130

[Difficulty: 3]

- 4.130** A freshwater jet boat takes in water through side vents and ejects it through a nozzle of diameter  $D = 75$  mm; the jet speed is  $V_j$ . The drag on the boat is given by  $F_{\text{drag}} \propto kV^2$ , where  $V$  is the boat speed. Find an expression for the steady speed,  $V$ , in terms of water density  $\rho$ , flow rate through the system of  $Q$ , constant  $k$ , and jet speed  $V_j$ . A jet speed  $V_j = 15$  m/s produces a boat speed of  $V = 10$  m/s.
- Under these conditions, what is the new flow rate  $Q$ ?
  - Find the value of the constant  $k$ .
  - What speed  $V$  will be produced if the jet speed is increased to  $V_j = 25$  m/s?
  - What will be the new flow rate?

**Given:** Data on jet boat  
**Find:** Formula for boat speed; flow rate; value of  $k$ ; new speed and flow rate



**Solution:**

Basic equation:

Momentum 
$$\vec{F} = \vec{F}_S + \vec{F}_B = \frac{\partial}{\partial t} \int_{CV} \vec{V}_{xyz} \rho dV + \int_{CS} \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Given data 
$$D = 75\text{-mm} \quad V_j = 15 \cdot \frac{\text{m}}{\text{s}} \quad V = 10 \cdot \frac{\text{m}}{\text{s}} \quad \rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$$

Applying the horizontal component of momentum

$$F_{\text{drag}} = V \cdot (-\rho \cdot Q) + V_j \cdot (\rho \cdot Q) \quad \text{or, with} \quad F_{\text{drag}} = k \cdot V^2 \quad k \cdot V^2 = \rho \cdot Q \cdot V_j - \rho \cdot Q \cdot V$$

$$k \cdot V^2 + \rho \cdot Q \cdot V - \rho \cdot Q \cdot V_j = 0$$

Solving for  $V$  
$$V = -\frac{\rho \cdot Q}{2 \cdot k} + \sqrt{\left(\frac{\rho \cdot Q}{2 \cdot k}\right)^2 + \frac{\rho \cdot Q \cdot V_j}{k}} \quad (1)$$

For the flow rate 
$$Q = V_j \cdot \frac{\pi}{4} \cdot D^2 \quad Q = 0.0663 \frac{\text{m}^3}{\text{s}}$$

To find  $k$  from Eq 1, let  $\alpha = \frac{\rho \cdot Q}{2 \cdot k}$  then 
$$V = -\alpha + \sqrt{\alpha^2 + 2 \cdot \alpha \cdot V_j}$$

$$(V + \alpha)^2 = V^2 + 2 \cdot \alpha \cdot V + \alpha^2 = \alpha^2 + 2 \cdot \alpha \cdot V_j \quad \text{or} \quad \alpha = \frac{V^2}{2 \cdot (V_j - V)} \quad \alpha = 10 \frac{\text{m}}{\text{s}}$$


Hence 
$$k = \frac{\rho \cdot Q}{2 \cdot \alpha} \quad k = 3.31 \frac{\text{N}}{\left(\frac{\text{m}}{\text{s}}\right)^2}$$

For 
$$V_j = 25 \cdot \frac{\text{m}}{\text{s}} \quad Q = V_j \cdot \frac{\pi}{4} \cdot D^2 \quad Q = 0.11 \frac{\text{m}^3}{\text{s}} \quad V = \left[ -\frac{\rho \cdot Q}{2 \cdot k} + \sqrt{\left(\frac{\rho \cdot Q}{2 \cdot k}\right)^2 + \frac{\rho \cdot Q \cdot V_j}{k}} \right] \quad V = 16.7 \frac{\text{m}}{\text{s}}$$

### Problem 4.131

[Difficulty: 2]

4.131 A jet of oil ( $SG = 0.8$ ) strikes a curved blade that turns the fluid through angle  $\theta = 180^\circ$ . The jet area is  $1200 \text{ mm}^2$  and its speed relative to the stationary nozzle is  $20 \text{ m/s}$ . The blade moves toward the nozzle at  $10 \text{ m/s}$ . Determine the force that must be applied to maintain the blade speed constant.



Find: Force needed to maintain vane speed constant.

Solution: Apply  $x$  component of momentum equation to moving CV shown.

$$\text{Basic equation: } F_{Sx} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

$= 0(2) \quad = 0(2)$

- Assumptions:
- (1) No net pressure force on CV;  $F_{Sx} = R_x$
  - (2)  $F_{Bx} = 0$
  - (3) Steady flow
  - (4) Flow uniform at each section
  - (5) Jet area and speed relative to vane are constant

The subscript  $xyz$  is a reminder that all velocities must be evaluated relative to the CV. Then

$$R_x = u_1 \{ -\rho(V+U)A \} + u_2 \{ \rho(V+U)A \}$$

$$u_1 = V+U \quad u_2 = -(V+U)$$

$$\text{and } R_x = -\rho(V+U)^2 A - \rho(V+U)^2 A = -2\rho(V+U)^2 A = -2SG \rho_{H_2O} (V+U)^2 A$$

$$R_x = -2(0.8) 999 \frac{\text{kg}}{\text{m}^3} (20+10)^2 \frac{\text{m}^2}{\text{s}^2} \times 1200 \text{ mm}^2 \times \frac{\text{m}^2}{10^6 \text{ mm}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = -1.73 \text{ kN}$$

This force must be applied to the left on the vane.


{ Note  $R_y = mg$ , since there are no vertical components of velocity. }



## Problem 4.133

[Difficulty: 3]

**4.133** Consider a single vane, with turning angle  $\theta$ , moving horizontally at constant speed,  $U$ , under the influence of an impinging jet as in Problem 4.128. The absolute speed of the jet is  $V$ . Obtain general expressions for the resultant force and power that the vane could produce. Show that the power is maximized when  $U = V/3$ .



**Given:** Water jet striking moving vane

**Find:** Expressions for force and power; Show that maximum power is when  $U = V/3$

**Solution:**

Basic equation: Momentum flux for inertial CV 
$$\vec{F} = \vec{F}_S + \vec{F}_B = \frac{\partial}{\partial t} \int_{CV} \vec{V}_{xyz} \rho dV + \int_{CS} \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow  
5) Jet relative velocity is constant

Then 
$$R_x = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2) = -(V - U) \cdot [\rho \cdot (V - U) \cdot A] + (V - U) \cdot \cos(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$

$$R_x = \rho(V - U)^2 \cdot A \cdot (\cos(\theta) - 1)$$

This is force on vane; Force exerted by vane is equal and opposite

$$F_x = \rho(V - U)^2 \cdot A \cdot (1 - \cos(\theta))$$

The power produced is then

$$P = U \cdot F_x = \rho \cdot U \cdot (V - U)^2 \cdot A \cdot (1 - \cos(\theta))$$

To maximize power wrt to U

$$\frac{dP}{dU} = \rho \cdot (V - U)^2 \cdot A \cdot (1 - \cos(\theta)) + \rho \cdot (2) \cdot (-1) \cdot (V - U) \cdot U \cdot A \cdot (1 - \cos(\theta)) = 0$$


Hence 
$$V - U - 2 \cdot U = V - 3 \cdot U = 0 \quad U = \frac{V}{3} \quad \text{for maximum power}$$

Note that there is a vertical force, but it generates no power

## Problem 4.134

[Difficulty: 3]

**4.134** Water, in a 4-in. diameter jet with speed of 100 ft/s to the right, is deflected by a cone that moves to the left at 45 ft/s. Determine (a) the thickness of the jet sheet at a radius of 9 in. and (b) the external horizontal force needed to move the cone.



**Given:** Water jet striking moving cone

**Find:** Thickness of jet sheet; Force needed to move cone

**Solution:**

Basic equations: Mass conservation; Momentum flux in x direction

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad F_x = F_{\dot{m}} + F_{R_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Jet relative velocity is constant

Then  $-\rho \cdot V_1 \cdot A_1 + \rho \cdot V_2 \cdot A_2 = 0 \quad -\rho \cdot (V_j + V_c) \cdot \frac{\pi \cdot D_j^2}{4} + \rho \cdot (V_j + V_c) \cdot 2 \cdot \pi \cdot R \cdot t = 0$  (Refer to sketch)

Hence  $t = \frac{D_j^2}{8 \cdot R} \quad t = \frac{1}{8} \times (4 \cdot \text{in})^2 \times \frac{1}{9 \cdot \text{in}} \quad t = 0.222 \cdot \text{in}$

Using relative velocities, x momentum is

$$R_x = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2) = -(V_j + V_c) \cdot [\rho \cdot (V_j + V_c) \cdot A_j] + (V_j + V_c) \cdot \cos(\theta) \cdot [\rho \cdot (V_j + V_c) \cdot A_j]$$

$$R_x = \rho (V_j + V_c)^2 \cdot A_j \cdot (\cos(\theta) - 1)$$

Using given data


$$R_x = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left[ (100 + 45) \cdot \frac{\text{ft}}{\text{s}} \right]^2 \times \frac{\pi \cdot \left( \frac{4}{12} \cdot \text{ft} \right)^2}{4} \times (\cos(60 \cdot \text{deg}) - 1) \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = -1780 \cdot \text{lbf}$$

Hence the force is 1780 lbf to the left; the upwards equals the weight

### Problem 4.135

[Difficulty: 3]

4.135 The circular dish, whose cross section is shown, has an outside diameter of 0.15 m. A water jet strikes the dish concentrically and then flows outward along the surface of the dish. The jet speed is 45 m/s and the dish moves to the left at 10 m/s. Find the thickness of the jet sheet at a radius of 75 mm from the jet axis. What horizontal force on the dish is required to maintain this motion?



Solution: Apply the momentum equation to a CV moving with the dish, as shown.

Basic equation:

$$F_{Sx} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} u_x \rho \, dV + \int_{CS} u_x \rho \, \vec{V}_{rel} \cdot d\vec{A}$$

- Assumptions:
- (1) No pressure forces
  - (2) Horizontal;  $F_{Bx} = 0$
  - (3) Steady flow w.r.t. CV
  - (4) Uniform flow at each section
  - (5) Use relative velocities
  - (6) No change in relative velocity on the dish

Then

$$R_x = u_1 \{ -\rho(V-U)A \} + u_2 \{ +\rho(V-U)A \}$$

$$u_1 = V-U \quad u_2 = -(V-U)\cos\theta$$

$$R_x = -\rho(V-U)^2 A - \rho(V-U)^2 A \cos\theta = -\rho(V-U)^2 A (1 + \cos\theta)$$

$$= -999 \frac{\text{kg}}{\text{m}^3} \times (45-10)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\pi}{4} (0.050)^2 \text{m}^2 (1 + \cos 40^\circ) \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$R_x = -4.24 \text{ kN (force must act to right)}$$

$R_x$

Apply conservation of mass to determine the jet sheet thickness:

Basic equation:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho \, dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

Using the above assumptions, then

$$0 = -\rho V_1 A_1 + \rho V_2 A_2$$

$$V_1 = V-U ; V_2 = V-U ; A_1 = \frac{\pi d^2}{4} ; A_2 = 2\pi R t$$

Therefore  $A_1 = A_2 = \frac{\pi d^2}{4} = 2\pi R t$ , and  $t = \frac{d^2}{8R}$


$$t = \frac{1}{8} \times (0.050)^2 \text{m}^2 \times \frac{1}{0.075 \text{m}} = 4.17 \times 10^{-3} \text{m or } 4.17 \text{ mm}$$

$t$

### Problem 4.136

[Difficulty: 3]

4.136 Consider a series of turning vanes struck by a continuous jet of water that leaves a 50-mm diameter nozzle at constant speed,  $V = 86.6$  m/s. The vanes move with constant speed,  $U = 50$  m/s. Note that all the mass flow leaving the jet crosses the vanes. The curvature of the vanes is described by angles  $\theta_1 = 30^\circ$  and  $\theta_2 = 45^\circ$ , as shown. Evaluate the nozzle angle,  $\alpha$ , required to ensure that the jet enters tangent to the leading edge of each vane. Calculate the force that must be applied to maintain the vane speed constant.



Solution: Apply momentum equation using CV moving with vanes, as shown.

Basic equation:  $\frac{d}{dt} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A} = 0(x) = 0(z)$

$$F_{Bx} + F_{Px} = \frac{d}{dt} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$$


- Assumptions:
- (1) No pressure forces
  - (2) Horizontal;  $F_{Bx} = 0$
  - (3) Steady flow w.r.t. CV
  - (4) Uniform flow at each section
  - (5) No change in relative velocity on vane
  - (6) Flow enters and leaves tangent to vanes

The nozzle angle may be obtained from trigonometry. The inlet velocity relationship is shown in the sketch:

From the law of sines,

$$\frac{\sin \alpha}{V_{rb}} = \frac{\sin(90 + \theta_1)}{V} = \frac{\sin \beta}{U}$$

$$\beta = \sin^{-1} \left[ \frac{U}{V} \sin(90 + \theta_1) \right] = \sin^{-1} \left[ \frac{50}{86.6} \sin(120^\circ) \right] = 30^\circ$$



From the sketch,  $90^\circ = \alpha + \beta + \theta_1$ , so  $\alpha = 90^\circ - \beta - \theta_1 = 90^\circ - 30^\circ - 30^\circ = 30^\circ$

Also  $V_{rb} \cos \theta_1 = V \sin \alpha$ ;  $V_{rb} = V \frac{\sin \alpha}{\cos \theta_1} = 86.6 \frac{\text{m}}{\text{s}} \cdot \frac{\sin 30^\circ}{\cos 30^\circ} = 50.0 \text{ m/s}$

From momentum equation (note all of  $\dot{m}$  flows across vanes)

$$R_x = u_1 \{-\dot{m}\} + u_2 \{\dot{m}\} = V_{rb} \sin \theta_1 (-\dot{m}) - V_{rb} \sin \theta_2 (\dot{m}) = V_{rb} \dot{m} (-\sin \theta_1 - \sin \theta_2)$$

$$u_1 = V_{rb} \sin \theta_1, \quad u_2 = -V_{rb} \sin \theta_2; \quad R_y = \dot{m} V_{rb} (-\cos \theta_1 + \cos \theta_2)$$

Thus, since  $\dot{m} = \rho Q$ ,


$$R_x = V_{rb} \rho Q (-\sin \theta_1 - \sin \theta_2)$$

$$= \frac{50 \text{ m}}{\text{s}} \cdot \frac{999 \text{ kg}}{\text{m}^3} \cdot \frac{0.170 \text{ m}^3}{\text{s}} (-\sin 30^\circ - \sin 45^\circ) \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$R_x = -10.3 \text{ kN (to left)}$$

{ Note: The net force on the CV in the y-direction is  $R_y = -1.35 \text{ kN}$ . }

4.137 Consider again the moving multiple-vane system described in Problem 4.136. Assuming that a way could be found to make  $\alpha$  nearly zero (and thus,  $\theta_1$  nearly  $90^\circ$ ), evaluate the vane speed,  $U$ , that would result in maximum power output from the moving vane system.



Solution: Apply momentum equation using CV moving with vanes, as shown.

Basic equation:

$$F_{3x} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} u_{x13} \rho dV + \int_{CS} u_{x13} \rho \vec{V}_{x13} \cdot d\vec{A}$$

$= 0(t) = 0(s)$

- Assumptions:
- (1) No pressure forces
  - (2) Horizontal;  $F_{Bx} = 0$
  - (3) Steady flow w.r.t. CV
  - (4) Uniform flow at each section
  - (5) No change in relative velocity on vane
  - (6) Flow enters and leaves tangent to vanes

For  $\alpha \approx 0$ ,  $V_{r1} \approx V - U$ ; the momentum equation becomes

$$R_x = u_1 \{-\dot{m}\} + u_2 \{+\dot{m}\} = -\dot{m}(V-U) - \dot{m}(V-U) \sin \theta_2 = -\dot{m}(V-U)(1 + \sin \theta_2)$$

$$u_1 \approx V_{r1} \approx V - U; u_2 \approx -V_{r1} \sin \theta_2 \approx -(V-U) \sin \theta_2$$

The vane system produces force,  $K_x = -R_x$ , and power  $\dot{P} = K_x U$ . Thus

$$\dot{P} = K_x U = -R_x U = \dot{m}(V-U)U(1 + \sin \theta_2) \tag{1}$$

To find maximum power, set  $\frac{d\dot{P}}{dU} = 0$

$$\frac{d\dot{P}}{dU} = \dot{m}(-1)U(1 + \sin \theta_2) + \dot{m}(V-U)(1)(1 + \sin \theta_2) = \dot{m}(V - 2U)(1 + \sin \theta_2)$$

Thus, power is maximized when  $V - 2U = 0$ , or  $U = \frac{V}{2}$  (for  $\dot{P}_{max}$ )


{ Note from Eq. 1 that  $\theta_2 \rightarrow 90^\circ$  increases power also. }

{ Note also that  $K_y = -R_y = -\dot{m} V_{r1} \cos \theta_2$  but this force does not produce power. }

### Problem 4.138

[Difficulty: 2]

**4.138** A steady jet of water is used to propel a small cart along a horizontal track as shown. Total resistance to motion of the cart assembly is given by  $F_D = kU^2$ , where  $k = 0.92 \text{ N} \cdot \text{s}^2/\text{m}^2$ . Evaluate the acceleration of the cart at the instant when its speed is  $U = 10 \text{ m/s}$ .



Solution: Apply the momentum equation using CV and CS shown.

Basic equation:  $F_{sx} + F_{bx} - \int_{cv} \rho u_x dV = \frac{d}{dt} \int_{cv} u_x \rho dV + \int_{cs} u_x \rho \vec{V} \cdot d\vec{A}$

- Assumptions: (1) Only resistance is  $F_D$ ;  $F_{sx} = -F_D = -kU^2$   
 (2) Horizontal;  $F_{bx} = 0$   
 (3) Neglect inlet of mass of water in CV  
 (4) No change in speed w.r. to vane  
 (5) Uniform flow at each cross-section

Then

$$-kU^2 - \rho u_x M_{cv} = u_1 \{-\rho(V-U)A\} + u_2 \{+\rho(V-U)A\}$$

Measure  $u$  w.r. to CV:

$$u_1 = V-U \quad u_2 = -(V-U) \sin \theta$$

$$-kU^2 - \rho u_x M_{cv} = -\rho(V-U)^2 A - \rho(V-U)^2 A \sin \theta = -\rho(V-U)^2 A (1 + \sin \theta)$$

so

$$\rho u_x = \frac{1}{M} [\rho(V-U)^2 A (1 + \sin \theta) - kU^2]$$

$$= \frac{1}{15 \text{ kg}} \left[ \frac{999 \text{ kg}}{\text{m}^3} \frac{(30-10)^2 \text{ m}^2}{\text{s}^2} \frac{\pi (0.025)^2 \text{ m}^2}{4} (1 + \sin 30^\circ) - 0.92 \frac{\text{N} \cdot \text{s}^2}{\text{m}^2} \times \frac{(10)^2 \text{ m}^2}{\text{sec}^2} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]$$


$$\rho u_x = 13.5 \text{ m/s}^2 \quad (\text{to right})$$

$\rho u_x$

## Problem 4.139

[Difficulty: 4]

**4.139** A plane jet of water strikes a splitter vane and divides into two flat streams, as shown. Find the mass flow rate ratio,  $\dot{m}_2/\dot{m}_3$ , required to produce zero net vertical force on the splitter vane. If there is a resistive force of 16 N applied to the splitter vane, find the steady speed  $U$  of the vane.



**Given:** Jet impacting a splitter vane

**Find:** Mass flow rate ratio; new speed  $U$

**Solution:** Apply momentum equation to inertial CV

Assumptions: No pressure force; neglect water mass on vane; steady flow wrt vane; uniform flow; no change of speed wrt the vane

Basic equation 
$$\vec{F} = \vec{F}_S + \vec{F}_B = \frac{\partial}{\partial t} \int_{CV} \vec{V}_{xyz} \rho dV + \int_{CS} \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Given data  $V = 25 \frac{m}{s}$      $A = 7.85 \cdot 10^{-5} \cdot m^2$      $U = 10 \frac{m}{s}$      $\theta = 30\text{-deg}$      $\rho = 999 \frac{kg}{m^3}$

For constant speed wrt the vane, the jet velocity at each location is  $V - U$

For no vertical force, y momentum becomes  $0 = v_1 \cdot (-m_1) + v_2 \cdot m_2 + v_3 \cdot m_3$  where  $v_i$  and  $m_i$  are the vertical components of velocity and mass flow rates, respectively, at the inlet and exits, wrt the vane coordinates

Hence  $0 = 0 + (V - U) \cdot m_2 - (V - U) \cdot \sin(\theta) \cdot m_3$  or  $m_2 = m_3 \cdot \sin(\theta)$      $\frac{m_2}{m_3} = \sin(\theta) = \frac{1}{2}$

Note that  $m_1 = \rho \cdot A \cdot (V - U)$      $m_1 = 1.18 \frac{kg}{s}$

and  $m_1 = m_2 + m_3$  so  $m_1 = m_3 \cdot \sin(\theta) + m_3$      $\frac{m_3}{m_1} = \frac{1}{1 + \sin(\theta)}$      $\frac{m_3}{m_1} = \frac{2}{3}$      $m_3 = 0.784 \frac{kg}{s}$      $m_2 = 0.392 \frac{kg}{s}$

and using x momentum  $R_x = u_1 \cdot (-m_1) + u_2 \cdot m_2 + u_3 \cdot m_3 = (V - U) \cdot (-m_1) + 0 + (V - U) \cdot \cos(\theta) \cdot m_3$

Writing in terms of  $m_1$   $R_x = (V - U) \cdot m_1 \cdot \left( \frac{\cos(\theta)}{1 + \sin(\theta)} - 1 \right)$      $R_x = -7.46 \text{ N}$

Instead, the force is now  $R_x = -16 \cdot \text{N}$  but  $R_x = (V - U) \cdot m_1 \cdot \left( \frac{\cos(\theta)}{1 + \sin(\theta)} - 1 \right)$  and  $m_1 = \rho \cdot A \cdot (V - U)$


Hence  $R_x = (V - U)^2 \cdot \rho \cdot A \cdot \left( \frac{\cos(\theta)}{1 + \sin(\theta)} - 1 \right)$

Solving for  $U$  
$$U = V - \sqrt{\frac{R_x}{\rho \cdot A \cdot \left( \frac{\cos(\theta)}{1 + \sin(\theta)} - 1 \right)}}$$
     $U = 3.03 \frac{m}{s}$

### Problem 4.140

[Difficulty: 3]

**4.140** The hydraulic catapult of Problem 4.138 is accelerated by a jet of water that strikes the curved vane. The cart moves along a level track with negligible resistance. At any time its speed is  $U$ . Calculate the time required to accelerate the cart from rest to  $U = V/2$ .



Solution: Apply  $x$  component of momentum equation to accelerating CV.

Basic equation:  $F_x = 0(1) = 0(2) \approx 0(3)$

$$F_x + F_x - \int_{CV} \rho u_x dV = \frac{\partial}{\partial t} \int_{CV} \rho u_x dV + \int_{CS} \rho u_x \vec{V} \cdot d\vec{A}$$

- Assumptions:
- (1)  $F_{sx} = 0$ , since no pressure forces, no resistance
  - (2)  $F_{bx} = 0$ , since horizontal
  - (3) Neglect mass of water on vane
  - (4) Uniform flow in jet
  - (5) No change in relative velocity on vane

Then

$$-\rho u_x M_{CV} = u_1 \{-\rho(V-U)A\} + u_2 \{+\rho(V-U)A\} = -(1 + \sin\theta) \rho(V-U)^2 A$$

$$u_1 = V-U \quad u_2 = -(V-U) \sin\theta$$

so  $\frac{dU}{dt} = \frac{\rho A (1 + \sin\theta)}{M} (V-U)^2$

To integrate, note since  $V = \text{constant}$ ,  $d(V-U) = -dU$ , so

$$-\int_0^{V/2} \frac{d(V-U)}{(V-U)^2} = \int_0^t \frac{\rho A (1 + \sin\theta)}{M} dt$$

or  $\frac{1}{V-U} \Big|_{U=0}^{U=V/2} = \frac{2}{V} - \frac{1}{V} = \frac{1}{V} = \frac{\rho A (1 + \sin\theta)}{M} t$

Thus

$$t = \frac{M}{\rho V A (1 + \sin\theta)}$$

$$= 15.0 \text{ kg} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{s}}{30.0 \text{ m}} \times \frac{4}{\pi (0.025)^2 \text{ m}^2} \times \frac{1}{(1 + \sin 30^\circ)}$$


$$t = 0.680 \text{ s}$$

t

### Problem 4.141

[Difficulty: 2]

**4.141** A vane/slider assembly moves under the influence of a liquid jet as shown. The coefficient of kinetic friction for motion of the slider along the surface is  $\mu_k = 0.30$ . Calculate the terminal speed of the slider.



Solution: Apply x momentum equation to linearly accelerating CV.

Basic equation:

$$F_{Sx} + F_{Bx} - \int_{CV} a_{fx} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_x y_3 \rho dV + \int_{CS} u_x y_3 \rho \vec{V}_{xy_3} \cdot d\vec{A}$$

$= 0(1) \qquad \approx 0(2)$

- Assumptions: (1) Horizontal motion, so  $F_{Bx} = 0$   
 (2) Neglect mass of liquid on vane,  $u \approx 0$  on vane  
 (3) Uniform flow at each section  
 (4) Measure velocities relative to CV

Then

$$-Mg\mu_k - a_{fx} M = u_1 \{-\rho(V-U)A\} + u_2 \{+\dot{m}_2\} + u_3 \{+\dot{m}_3\}$$

$$u_1 = V-U \qquad u_2 = 0 \qquad u_3 = 0$$

$$-Mg\mu_k - M \frac{dU}{dt} = -\rho(V-U)^2 A$$

or

$$\frac{dU}{dt} = \frac{\rho(V-U)^2 A}{M} - g\mu_k$$

At terminal speed,  $dU/dt = 0$  and  $U = U_t$ , so

$$0 = \frac{\rho(V-U_t)^2 A}{M} - g\mu_k \quad \text{or} \quad V-U_t = \sqrt{\frac{Mg\mu_k}{\rho A}}$$

and

$$U_t = V - \sqrt{\frac{Mg\mu_k}{\rho A}}$$

$$= 20 \frac{m}{s} - \left[ 30 \text{ kg} \times 9.81 \frac{m}{s^2} \times 0.3 \times \frac{m^3}{999 \text{ kg} \times 0.005 \text{ m}^2} \right]^{1/2}$$



$$U_t = 15.8 \text{ m/s}$$

$U_t$

### Problem 4.142

[Difficulty: 3]

4.142 A cart is propelled by a liquid jet issuing horizontally from a tank as shown. The track is horizontal; resistance to motion may be neglected. The tank is pressurized so that the jet speed may be considered constant. Obtain a general expression for the speed of the cart as it accelerates from rest. If  $M_0 = 100$  kg,  $\rho = 999$  kg/m<sup>3</sup>, and  $A = 0.005$  m<sup>2</sup>, find the jet speed  $V$  required for the cart to reach a speed of 1.5 m/s after 30 seconds. For this condition, plot the cart speed  $U$  as a function of time. Plot the cart speed after 30 seconds as a function of jet speed.



Solution:

a) Apply x component of momentum equation using linearly accelerating CV shown.

$$\text{Basic equation: } \overset{=0(1)}{F_{\rho x}} + \overset{=0(2)}{F_{\rho x}} - \int_{CV} a_{rfx} \rho dV = \overset{=0(3)}{\frac{\partial}{\partial t} \int_{CV} u_{xy3} \rho dV} + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$$

Assumptions: (1) No resistance

(2)  $F_{Bx} = 0$  since track is horizontal

(3) Neglect  $u_{xy3}$  within CV

(4) Uniform flow at jet exit

Then

$$-a_{rfx} M = u \{ \rho V A \} = -\rho V^2 A$$

$$u = -V$$

From continuity,  $M = M_0 - \rho V A t = M_0 - \rho V A t$ . Using  $a_{rfx} = \frac{dU}{dt}$ ,

$$\frac{dU}{dt} = \frac{\rho V^2 A}{M_0 - \rho V A t}$$

Separating variables and integrating,

$$\int_0^U dU = U = \int_0^t \frac{\rho V^2 A dt}{M_0 - \rho V A t} = -V \ln(M_0 - \rho V A t) \Big|_0^t = V \ln \left( \frac{M_0}{M_0 - \rho V A t} \right)$$

or

$$\frac{U}{V} = \ln \left( \frac{M_0}{M_0 - \rho V A t} \right)$$

$$\frac{U}{V}$$


Check dimensions:  $[\rho V A t] = \frac{M}{L^3} \frac{L}{t} L^2 t = M$

b) Using the given data in Excel (with Solver) the jet speed for  $U = 1.5$  m/s @  $t = 30$  s is  $V = 0.61$  m/s

## Problem 4.143

[Difficulty: 4]

**4.143** For the vane/slider problem of Problem 4.141, find and plot expressions for the acceleration and speed of the slider as a function of time.



**Given:** Data on vane/slider

**Find:** Formula for acceleration and speed; plot

**Solution:**

The given data is  $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$      $M = 30 \cdot \text{kg}$      $A = 0.005 \cdot \text{m}^2$      $V = 20 \cdot \frac{\text{m}}{\text{s}}$      $\mu_k = 0.3$

The equation of motion, from Problem 4.141, is  $\frac{dU}{dt} = \frac{\rho \cdot (V - U)^2 \cdot A}{M} - g \cdot \mu_k$

The acceleration is thus  $a = \frac{\rho \cdot (V - U)^2 \cdot A}{M} - g \cdot \mu_k$     Separating variables  $\frac{dU}{\frac{\rho \cdot (V - U)^2 \cdot A}{M} - g \cdot \mu_k} = dt$

Substitute  $u = V - U$      $dU = -du$      $\frac{du}{\frac{\rho \cdot A \cdot u^2}{M} - g \cdot \mu_k} = -dt$

But  $\int \frac{1}{\left(\frac{\rho \cdot A \cdot u^2}{M} - g \cdot \mu_k\right)} du = -\sqrt{\frac{M}{g \cdot \mu_k \cdot \rho \cdot A}} \cdot \operatorname{atanh}\left(\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot u\right)$

and  $u = V - U$  so  $-\sqrt{\frac{M}{g \cdot \mu_k \cdot \rho \cdot A}} \cdot \operatorname{atanh}\left(\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot u\right) = -\sqrt{\frac{M}{g \cdot \mu_k \cdot \rho \cdot A}} \cdot \operatorname{atanh}\left[\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot (V - U)\right]$

Using initial conditions  $-\sqrt{\frac{M}{g \cdot \mu_k \cdot \rho \cdot A}} \cdot \operatorname{atanh}\left[\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot (V - U)\right] + \sqrt{\frac{M}{g \cdot \mu_k \cdot \rho \cdot A}} \cdot \operatorname{atanh}\left(\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot V\right) = -t$

$$V - U = \sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}} \cdot \operatorname{tanh}\left(\sqrt{\frac{g \cdot \mu_k \cdot \rho \cdot A}{M}} \cdot t + \operatorname{atanh}\left(\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot V\right)\right)$$

$$U = V - \sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}} \cdot \operatorname{tanh}\left(\sqrt{\frac{g \cdot \mu_k \cdot \rho \cdot A}{M}} \cdot t + \operatorname{atanh}\left(\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot V\right)\right)$$

Note that  $\operatorname{atanh}\left(\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot V\right) = 0.213 - \frac{\pi}{2} \cdot i$

which is complex and difficult to handle in *Excel*, so we use the identity  $\operatorname{atanh}(x) = \operatorname{atanh}\left(\frac{1}{x}\right) - \frac{\pi}{2} \cdot i$  for  $x > 1$

so

$$U = V - \sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}} \cdot \tanh \left( \sqrt{\frac{g \cdot \mu_k \cdot \rho \cdot A}{M}} \cdot t + \operatorname{atanh} \left( \frac{1}{\sqrt{\frac{\rho \cdot A}{g \cdot \mu_k \cdot M}} \cdot V} \right) - \frac{\pi}{2} \cdot i \right)$$

and finally the identity

$$\tanh \left( x - \frac{\pi}{2} \cdot i \right) = \frac{1}{\tanh(x)}$$

to obtain

$$U(t) = V - \frac{\sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}}}{\tanh \left( \sqrt{\frac{g \cdot \mu_k \cdot \rho \cdot A}{M}} \cdot t + \operatorname{atanh} \left( \sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}} \cdot \frac{1}{V} \right) \right)}$$



Note that

$$a = \frac{\rho \cdot (V - U)^2 \cdot A}{M} - g \cdot \mu_k \quad \text{and} \quad V - U = \frac{\sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}}}{\tanh \left( \sqrt{\frac{g \cdot \mu_k \cdot \rho \cdot A}{M}} \cdot t + \operatorname{atanh} \left( \sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}} \cdot \frac{1}{V} \right) \right)}$$


Hence

$$a(t) = \frac{g \cdot \mu_k}{\tanh \left( \sqrt{\frac{g \cdot \mu_k \cdot \rho \cdot A}{M}} \cdot t + \operatorname{atanh} \left( \sqrt{\frac{g \cdot \mu_k \cdot M}{\rho \cdot A}} \cdot \frac{1}{V} \right) \right)^2} - g \cdot \mu_k$$

The plots are presented below



4.144 If the cart of Problem 4.138 is released at  $t = 0$ , when would you expect the acceleration to be maximum? Sketch what you would expect for the curve of acceleration versus time. What value of  $\theta$  would maximize the acceleration at any time? Why? Will the cart speed ever equal the jet speed? Explain briefly.



Solution: Apply  $x$  component of momentum equation to accelerating CV

Basic equation:  $F_{sx} + F_{bx} - \int_{CV} a_{rx} \rho dV = \frac{d}{dt} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$

- Assumptions: (1)  $F_{sx} = -F_D = -kU^2$ , where  $k = 0.92 \text{ N}\cdot\text{s}^2/\text{m}^2$   
 (2)  $F_{bx} = 0$ , since horizontal  
 (3) Neglect mass of water on vane  
 (4) Uniform flow in jet  
 (5) No change in relative velocity on vane

Then


$$-kU^2 - a_{rx} M_{CV} = u_1 \{-\rho(V-U)A\} + u_2 \{+\rho(V-U)A\} = -(1+\sin\theta)\rho(V-U)^2 A$$

$$u_1 = V-U \quad u_2 = -(V-U)\sin\theta$$

so

$$\frac{dU}{dt} = \frac{\rho A (1+\sin\theta)}{M} (V-U)^2 - kU^2/M \tag{1}$$

(a) Acceleration is maximum at  $t=0$ , when  $U=0$

(b) Acceleration vs. time will be 

(c) From Eq. 1,  $dU/dt$  is maximum when  $\theta = \pi/2$  and  $\sin\theta = 1$

(d) From Eq. 1,  $\frac{dU}{dt}$  will go to zero when  $U < V$ ; this will be the terminal speed for the cart,  $U_t$ . From Eq. 1,  $\frac{dU}{dt} = 0$  when

$$\rho A (1+\sin\theta) (V-U)^2 = kU^2$$


$$\text{or } U = \frac{\left[ \frac{\rho A (1+\sin\theta)}{k} \right]^{1/2}}{1 + \left[ \frac{\rho A (1+\sin\theta)}{k} \right]^{1/2}} V = 0.472V$$

$U$  will be asymptotic to  $V$ .

## Problem 4.145

[Difficulty: 4]

**4.145** The acceleration of the vane/cart assembly of Problem 4.128 is to be controlled as it accelerates from rest by changing the vane angle,  $\theta$ . A constant acceleration,  $a = 1.5 \text{ m/s}^2$ , is desired. The water jet leaves the nozzle of area  $A = 0.025 \text{ m}^2$ , with speed  $V = 15 \text{ m/s}$ . The vane/cart assembly has a mass of  $55 \text{ kg}$ ; neglect friction. Determine  $\theta$  at  $t = 5 \text{ s}$ . Plot  $\theta(t)$  for the given constant acceleration over a suitable range of  $t$ .



**Given:** Water jet striking moving vane/cart assembly

**Find:** Angle  $\theta$  at  $t = 5 \text{ s}$ ; Plot  $\theta(t)$

**Solution:**

Basic equation: Momentum flux in x direction for accelerating CV

$$F_{S_x} + F_{B_x} - \int_{CV} a_{rfx} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) No changes in CV 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Constant jet relative velocity

Then 
$$-M \cdot a_{rfx} = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2) = -(V - U) \cdot [\rho \cdot (V - U) \cdot A] + (V - U) \cdot \cos(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$


$$-M \cdot a_{rfx} = \rho(V - U)^2 \cdot A \cdot (\cos(\theta) - 1) \quad \text{or} \quad \cos(\theta) = 1 - \frac{M \cdot a_{rfx}}{\rho \cdot (V - U)^2 \cdot A}$$

Since  $a_{rfx} = \text{constant}$  then  $U = a_{rfx} \cdot t$  
$$\cos(\theta) = 1 - \frac{M \cdot a_{rfx}}{\rho \cdot (V - a_{rfx} \cdot t)^2 \cdot A}$$

$$\theta = \arccos \left[ 1 - \frac{M \cdot a_{rfx}}{\rho \cdot (V - a_{rfx} \cdot t)^2 \cdot A} \right]$$

Using given data

$$\theta = \arccos \left[ 1 - 55 \cdot \text{kg} \times 1.5 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{1}{\left( 15 \cdot \frac{\text{m}}{\text{s}} - 1.5 \cdot \frac{\text{m}}{\text{s}^2} \times 5 \cdot \text{s} \right)^2} \times \frac{1}{0.025 \cdot \text{m}^2} \right] \quad \theta = 19.7 \cdot \text{deg} \quad \text{at } t = 5 \text{ s}$$




The solution is only valid for  $\theta$  up to  $180^\circ$  (when  $t = 9.14 \text{ s}$ ). This graph can be plotted in *Excel*

## Problem 4.146

[Difficulty: 3]

**4.146** The wheeled cart shown rolls with negligible resistance. The cart is to accelerate to the right at a constant rate of  $2.5 \text{ m/s}^2$ . This is to be accomplished by “programming” the water jet speed,  $V(t)$ , that hits the cart. The jet area remains constant at  $50 \text{ mm}^2$ . Find the initial jet speed, and the jet speed and cart speeds after 2.5 s and 5 s. Theoretically, what happens to the value of  $(V - U)$  over time?



**Given:** Vaned cart with negligible resistance

**Find:** Initial jet speed; jet and cart speeds at 2.5 s and 5 s; what happens to  $V - U$ ?

**Solution:** Apply x momentum 
$$F_{S_x} + F_{B_x} - \int_{CV} a_{rf_x} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) All changes wrt CV 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Constant jet area

Given data  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$        $M = 5 \cdot \text{kg}$        $A = 50 \cdot \text{mm}^2$        $a = 2.5 \cdot \frac{\text{m}}{\text{s}^2}$        $\theta = 120 \cdot \text{deg}$

Then  $-a \cdot M = u_1 \cdot [-\rho \cdot (V - U) \cdot A] + u_1 \cdot [\rho \cdot (V - U) \cdot A]$     where     $u_1 = V - U$     and     $u_2 = (V - U) \cdot \cos(\theta)$

Hence  $a \cdot M = \rho \cdot (V - U)^2 \cdot (1 - \cos(\theta)) \cdot A$     From this equation we can see that for constant acceleration  $V$  and  $U$  must increase at the same rate!

Solving for  $V$      $V(t) = a \cdot t + \sqrt{\frac{M \cdot a}{\rho \cdot (1 - \cos(\theta)) \cdot A}}$


Hence, evaluating       $V(0) = 12.9 \frac{\text{m}}{\text{s}}$        $V(2.5 \cdot \text{s}) = 19.2 \frac{\text{m}}{\text{s}}$        $V(5 \cdot \text{s}) = 25.4 \frac{\text{m}}{\text{s}}$

Also, for constant acceleration     $U(t) = a \cdot t$     so     $V - U = \sqrt{\frac{M \cdot a}{\rho \cdot (1 - \cos(\theta)) \cdot A}} = \text{const!}$

### Problem 4.147

[Difficulty: 3] Part 1/2

**4.147** A rocket sled, weighing 10,000 lbf and traveling 600 mph, is to be braked by lowering a scoop into a water trough. The scoop is 6 in. wide. Determine the time required (after lowering the scoop to a depth of 3 in. into the water) to bring the sled to a speed of 20 mph. Plot the sled speed as a function of time.



Solution: Apply x component of momentum equation to linearly accelerating CV. Basic equation is

$$\overset{=0(1)}{F_{Bx}} + \overset{=0(2)}{F_{Bx}} - \int_{CV} a_{rfx} \rho dV = \overset{=0(3)}{\frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV} + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

- options:
- (1)  $F_{Bx} = 0$
  - (2)  $F_{Bx} = 0$
  - (3) Neglect  $u_{xyz}$  and its rate of change in CV
  - (4) Uniform flow at each section
  - (5) Speed of water relative to sled is constant

Then

$$-a_{rfx} M = u_1 \{-\rho U w h\} + u_2 \{\rho U w h\}; \quad u_1 = U, \quad u_2 = -U \cos \theta$$

$$-a_{rfx} \frac{W}{g} = -\rho U^2 w h (1 + \cos \theta), \quad \text{or} \quad a_{rfx} = \frac{\rho g U^2 w h (1 + \cos \theta)}{W}$$

Now  $a_{rfx} = -\frac{dU}{dt}$ , because of coordinate choice. Thus

$$\frac{dU}{U^2} = -\frac{\rho w h}{W} (1 + \cos \theta) dt$$

and

$$\int_{U_i}^U \frac{dU}{U^2} = -\frac{1}{U} + \frac{1}{U_i} = -\frac{\rho w h}{W} (1 + \cos \theta) t \quad (1)$$

Solving for  $t$ ,

$$t = \left[ \frac{1}{U} - \frac{1}{U_i} \right] \frac{W}{\rho w h (1 + \cos \theta)}$$

$$= \left[ \frac{1}{20} - \frac{1}{600} \right] \frac{\text{hr}}{\text{mi}} \times \frac{\text{mi}}{5280 \text{ ft}} \times \frac{3600 \text{ s}}{\text{hr}} \times \frac{\text{ft}^3}{62.4 \text{ lbf}} \times \frac{1}{6 \text{ in.}} \times \frac{1}{3 \text{ in.}} \times \frac{144 \text{ in.}^2}{\text{ft}^2} \times \frac{10,000 \text{ lbf}}{1 + \cos 30^\circ}$$

$$t = 22.6 \text{ s}$$

The plot is presented on the next page.

# Problem 4.147


[Difficulty: 3] Part 2/2

Solving Eq. 1 for  $U$ ,

$$\frac{1}{U} = \frac{1}{U_i} + \frac{\delta w h}{W} (1 + \cos \theta) t = \frac{W + \delta w h U_i (1 + \cos \theta) t}{W U_i}$$

or 
$$U = \frac{W U_i}{W + \delta w h U_i (1 + \cos \theta) t} \quad (2)$$

Plotting,





McGraw-Hill Education  
 1221 Avenue of the Americas  
 New York, NY 10020-1346  
 Copyright 2012 McGraw-Hill Education  
 All rights reserved.



### Problem 4.148

[Difficulty: 3]

4.148 A rocket sled is to be slowed from an initial speed of 300 m/s by lowering a scoop into a water trough. The scoop is 0.3 m wide; it deflects the water through 150°. The trough is 800 m long. The mass of the sled is 8000 kg. At the initial speed it experiences an aerodynamic drag force of 90 kN. The aerodynamic force is proportional to the square of the sled speed. It is desired to slow the sled to 100 m/s. Determine the depth  $D$  to which the scoop must be lowered into the water.



Solution: Apply  $x$  component of momentum equation using linearly accelerating CV shown.

$$\text{Basic equation: } F_{Sx} + F_{Bx} - \int_{CV} a_{rx} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} f \vec{V}_{xy3} \cdot d\vec{A}$$

Assumptions: (1)  $F_{Bx} = 0$

(2) Neglect rate of change of  $u$  in CV

(3) Uniform flow at each section

(4) No change in relative speed of liquid crossing scoop

Then

$$-F_D - M a_{rx} = u_1 \{-\rho U w h\} + u_2 \{\rho U w h\}; \quad h = \text{scoop immersion}$$

$$u_1 = -U$$

$$u_2 = U \cos \theta$$

$$\text{But } F_D = kU^2; \quad k = \frac{F_{D0}}{U_0^2} = \frac{90 \text{ kN}}{(300)^2 \text{ m}^2} \times \frac{10^3 \text{ N}}{\text{kN}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} = 1.00 \text{ kg/m}$$

$$-kU^2 - M \frac{dU}{dt} = \rho U^2 w h (1 + \cos \theta), \quad \text{since } a_{rx} = dU/dt,$$

$$\text{Thus } -M \frac{dU}{dt} = [k + \rho w h (1 + \cos \theta)] U^2 = -M U \frac{dU}{dX}$$

$$\text{or } \frac{dU}{U} = -C dX, \quad \text{where } C = \frac{k + \rho w h (1 + \cos \theta)}{M}$$

$$\text{Integrating, } \ln \frac{U}{U_0} = -CX, \quad \text{so } C = -\frac{1}{X} \ln \frac{U}{U_0}$$

$$C = -\frac{1}{800 \text{ m}} \ln \left( \frac{100}{300} \right) = 1.37 \times 10^{-3} \text{ m}^{-1}$$


$$\text{Solving for } h, \quad h = \frac{MC - k}{\rho w (1 + \cos \theta)}$$

$$h = \left[ 8000 \text{ kg} \times \frac{1.37 \times 10^{-3}}{\text{m}} - 1.00 \frac{\text{kg}}{\text{m}} \right] \frac{\text{m}^3}{999 \text{ kg}} \times \frac{1}{0.3 \text{ m}} \times \frac{1}{(1 + \cos 30^\circ)} = 0.0179 \text{ m}$$

$$h = 17.9 \text{ mm}$$

$h$

4.149 Starting from rest, the cart shown is propelled by a hydraulic catapult (liquid jet). The jet strikes the curved surface and makes a 180° turn, leaving horizontally. Air and rolling resistance may be neglected. If the mass of the cart is 100 kg and the jet of water leaves the nozzle (of area 0.001 m<sup>2</sup>) with a speed of 35 m/s, determine the speed of the cart 5 s after the jet is directed against the cart. Plot the cart speed as a function of time.



Solution: Apply x component of momentum equation using the linearly accelerating CV shown above.

$$\text{Basic equation: } \overset{\approx 0(1)}{F_{Ax}} + \overset{\approx 0(2)}{F_{Bx}} - \int_{CV} a_{rx} \rho dV = \frac{d}{dt} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$$

- Assumptions:
- (1)  $F_{Ax} = 0$
  - (2)  $F_{Bx} = 0$
  - (3) Neglect mass of liquid and rate of change of  $u$  in CV
  - (4) Uniform flow at each section
  - (5) Jet area and speed with respect to vehicle are constant

Then

$$-M a_{rx} = -M \frac{dU}{dt} = u_1 \{-\rho(V-U)A\} + u_2 \{\rho(V-U)A\}$$

$$u_1 = V-U \quad u_2 = -(V-U)$$

or

$$\frac{dU}{dt} = \frac{2\rho(V-U)^2 A}{M}$$

Note that  $dU = -d(V-U)$ , and separate variables to obtain

$$-\frac{d(V-U)}{(V-U)^2} = \frac{2\rho A}{M} dt$$

Integrate from  $U=0$  at  $t=0$  to  $U$  at  $t$ ,

$$\int_{V-U=V}^{V-U} -\frac{d(V-U)}{(V-U)^2} = \frac{1}{V-U} \Big|_V^{V-U} = \frac{1}{V-U} - \frac{1}{V} = \frac{V-(V-U)}{V(V-U)} = \frac{U}{V(V-U)} = \frac{2\rho A}{M} t$$

Solving,

$$U = (V-U) \frac{2\rho VA}{M} t \quad \text{or} \quad U = V \left[ \frac{\frac{2\rho VA}{M} t}{1 + \frac{2\rho VA}{M} t} \right] \quad (1)$$

For the given conditions at  $t = 5$  s,

$$\frac{2\rho VA}{M} t = 2 \times \frac{999 \text{ kg}}{\text{m}^3} \times \frac{30 \text{ m}}{\text{s}} \times 0.001 \text{ m}^2 \times 5 \text{ s} \times \frac{1}{100 \text{ kg}} = 3.00$$


$$U = \frac{30 \text{ m}}{\text{s}} \left[ \frac{3.00}{1 + 3.00} \right] = 22.5 \text{ m/s}$$

The plot is on the next page.

U



4.150 Consider the jet and cart of Problem 4.149 again, but include an aerodynamic drag force proportional to the square of cart speed,  $F_D = kU^2$ , with  $k = 2.0 \text{ N} \cdot \text{s}^2/\text{m}^2$ . Derive an expression for the cart acceleration as a function of cart speed and other given parameters. Evaluate the acceleration of the cart at  $U = 10 \text{ m/s}$ . What fraction is this speed of the terminal speed of the cart?



Solution: Apply x momentum for CV with linear acceleration.

Basic equation:

$$F_{sx} + F_{bx} - \int_{CV} \text{art}_x \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{x1j3} \rho dV + \int_{CS} u_{2j3} \rho \vec{V}_{2j3} \cdot d\vec{A}$$

- Assumptions:
- (1) Horizontal,  $F_{bx} = 0$
  - (2) Neglect mass of liquid in CV (components of  $u$  cancel)
  - (3) Uniform flow at each section
  - (4) Measure all velocities relative to the CV
  - (5) No change in stream area or speed on vane

Then

$$-kU^2 - \text{art}_x M = u_1 \{ -|\rho(V-U)A| \} + u_2 \{ +|\rho(V-U)A| \} = -2\rho(V-U)^2 A$$

$$u_1 = V-U \quad u_2 = -(V-U)$$

or

$$\text{art}_x = \frac{dU}{dt} = \frac{2\rho(V-U)^2 A - kU^2}{M} \quad \leftarrow a(U)$$

At  $U = 10 \text{ m/sec}$

$$\text{art}_x = \frac{2 \times 999 \frac{\text{kg}}{\text{m}^3} (30-10)^2 \frac{\text{m}^2}{\text{s}^2} \times 0.001 \text{ m}^2 - 2.0 \frac{\text{N} \cdot \text{s}^2}{\text{m}^2} \cdot (10)^2 \frac{\text{m}^2}{\text{s}^2} \cdot \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}}{100 \text{ kg}} = 5.99 \frac{\text{m}}{\text{s}^2} \quad \leftarrow \text{art}_x$$

At terminal speed,  $\text{art}_x = 0$ . Then  $2\rho(V-U_t)^2 A = kU_t^2$ , or

$$V - U_t = U_t \sqrt{\frac{k}{2\rho A}}$$

solving,  $U_t = \frac{V}{1 + \sqrt{k/2\rho A}}$

$$U_t = \frac{30 \frac{\text{m}}{\text{s}}}{1 + \left[ \frac{1}{2} \times 2.0 \frac{\text{N} \cdot \text{s}^2}{\text{m}^2} \cdot \frac{\text{m}^3}{999 \text{ kg}} \cdot \frac{1}{0.001 \text{ m}^2} \cdot \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]^{1/2}} = 15.0 \text{ m/s}$$


Finally,

$$\text{Fraction} = \frac{U}{U_t} = \frac{10.0 \text{ m/s}}{15.0 \text{ m/s}} = 0.667 \quad \leftarrow \text{Fraction}$$

## Problem 4.151

[Difficulty: 4]

**4.151** A small cart that carries a single turning vane rolls on a level track. The cart mass is  $M = 5 \text{ kg}$  and its initial speed is  $U_0 = 5 \text{ m/s}$ . At  $t = 0$ , the vane is struck by an opposing jet of water, as shown. Neglect any external forces due to air or rolling resistance. Determine the jet speed  $V$  required to bring the cart to rest in (a) 1 s and (b) 2 s. In each case find the total distance traveled.



**Given:** Vaned cart being hit by jet

**Find:** Jet speed to stop cart in 1 s and 2 s; distance traveled

**Solution:** Apply x momentum 
$$F_{S_x} + F_{B_x} - \int_{CV} a_{rf_x} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) All changes wrt CV 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Constant jet area

Given data  $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$      $M = 5 \cdot \text{kg}$      $D = 35 \cdot \text{mm}$      $\theta = 60 \cdot \text{deg}$      $U_0 = 5 \cdot \frac{\text{m}}{\text{s}}$

$A = \frac{\pi}{4} \cdot D^2$      $A = 962 \cdot \text{mm}^2$

Then  $-a_{rf} \cdot M = u_1 \cdot [-\rho \cdot (V + U) \cdot A] + u_2 \cdot [\rho \cdot (V + U) \cdot A]$

where  $a_{rf} = \frac{dU}{dt}$      $u_1 = -(V + U)$     and     $u_2 = -(V + U) \cdot \cos(\theta)$

Hence  $-\frac{dU}{dt} \cdot M = \rho \cdot (V + U)^2 \cdot A - \rho \cdot (V + U)^2 \cdot A \cdot \cos(\theta) = \rho \cdot (V + U)^2 \cdot A \cdot (1 - \cos(\theta))$

or  $-\frac{dU}{dt} \cdot M = \rho \cdot (V + U)^2 \cdot A \cdot (1 - \cos(\theta))$     (1)

Note that V is constant, so  $dU = d(V+U)$ , separating variables 
$$-\frac{d(V + U)}{(V + U)^2} = \frac{\rho \cdot (1 - \cos(\theta)) \cdot A}{M} \cdot dt$$

Integrating from  $U_0$  at  $t = 0$  to  $U = 0$  at  $t$  
$$\frac{1}{V} - \frac{1}{V + U_0} = \frac{\rho \cdot (1 - \cos(\theta)) \cdot A}{M} \cdot t$$

Solving for V 
$$\frac{U_0}{V \cdot (V + U_0)} = \frac{\rho \cdot (1 - \cos(\theta)) \cdot A \cdot t}{M}$$
    or     $V^2 + V \cdot U_0 - \frac{M \cdot U_0}{\rho \cdot (1 - \cos(\theta)) \cdot A \cdot t}$

Hence 
$$V = -\frac{U_0}{2} + \sqrt{\frac{U_0^2}{4} + \frac{U_0 \cdot M}{\rho \cdot A \cdot (1 - \cos(\theta)) \cdot t}}$$

To find distances note that  $\frac{dU}{dt} = \frac{dU}{dx} \cdot \frac{dx}{dt} = U \cdot \frac{dU}{dx}$

so Eq. 1 can be rewritten as  $-U \cdot \frac{dU}{dx} \cdot M = \rho \cdot (V + U)^2 \cdot A \cdot (1 - \cos(\theta))$

Separating variables  $\frac{U \cdot dU}{(V + U)^2} = -\frac{\rho \cdot A \cdot (1 - \cos(\theta))}{M} \cdot dx$

It can be shown that  $\int_{U_0}^0 \frac{U}{(V + U)^2} dU = \ln\left(\frac{V}{V + U_0}\right) + \frac{V}{V} - \frac{V}{V + U_0}$  (Remember that V is constant)

$$\ln\left(\frac{V}{V + U_0}\right) + 1 - \frac{V}{V + U_0} = -\frac{\rho \cdot A \cdot (1 - \cos(\theta))}{M} \cdot x$$

Solving for x  $x = -\frac{M}{\rho \cdot A \cdot (1 - \cos(\theta))} \cdot \left(\ln\left(\frac{V}{V + U_0}\right) + 1 - \frac{V}{V + U_0}\right)$

Substituting values:

To stop in  $t = 1 \cdot s$   $V = -\frac{U_0}{2} + \sqrt{\frac{U_0^2}{4} + \frac{U_0 \cdot M}{\rho \cdot A \cdot (1 - \cos(\theta)) \cdot t}}$   $V = 5.13 \frac{m}{s}$

and  $x = -\frac{M}{\rho \cdot A \cdot (1 - \cos(\theta))} \cdot \left(\ln\left(\frac{V}{V + U_0}\right) + 1 - \frac{V}{V + U_0}\right)$   $x = 1.94 m$


To stop in  $t = 2 \cdot s$   $V = -\frac{U_0}{2} + \sqrt{\frac{U_0^2}{4} + \frac{U_0 \cdot M}{\rho \cdot A \cdot (1 - \cos(\theta)) \cdot t}}$   $V = 3.18 \frac{m}{s}$

and  $x = -\frac{M}{\rho \cdot A \cdot (1 - \cos(\theta))} \cdot \left(\ln\left(\frac{V}{V + U_0}\right) + 1 - \frac{V}{V + U_0}\right)$   $x = 3.47 m$

### Problem 4.152

[Difficulty: 3]

- 4.152 Solve Problem 4.141 if the vane and slider ride on a film of oil instead of sliding in contact with the surface. Assume motion resistance is proportional to speed,  $F_R = kU$ , with  $k = 7.5 \text{ N} \cdot \text{s/m}$ .



Solution: Apply  $x$  momentum equation to linearly accelerating CV.

Basic equation:

$$F_{Bx} + F_{Px} - \int_{CV} a_{rx} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{x13} \rho dV + \int_{CS} u_{x13} \rho \vec{V}_{x13} \cdot d\vec{A}$$

- Assumptions: (1) Horizontal, so  $F_{Bx} = 0$   
 (2) Neglect mass of liquid on vane,  $u_{x13} = 0$  on vane  
 (3) Uniform flow at each section  
 (4) Measure velocities relative to CV

Then

$$-kU - a_{rx} M = u_1 \{-\rho(V-U)A\} + u_2 \{+m_2\} + u_3 \{+m_3\}$$

$$u_1 = V-U \quad u_2 = 0 \quad u_3 = 0$$

$$-kU - M \frac{dU}{dt} = -\rho(V-U)^2 A$$

or

$$\frac{dU}{dt} = \frac{\rho(V-U)^2 A}{M} - \frac{kU}{M}$$

$$= \frac{999 \text{ kg/m}^3 (20-10)^2 \text{ m}^2 \cdot 0.005 \text{ m}^2}{30 \text{ kg}} - \frac{7.5 \text{ N} \cdot \text{s}}{30 \text{ kg}} = \frac{10 \text{ m}}{\text{s}} - \frac{1}{30 \text{ kg}} \cdot \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}$$

$$\frac{dU}{dt} = 14.2 \text{ m/s}^2 \quad (\text{at } U = 10 \text{ m/s})$$

$\frac{dU}{dt}$

At terminal speed,  $U = U_t$  and  $dU/dt = 0$ , so

$$0 = \frac{\rho(V-U)^2 A}{M} - \frac{kU}{M} \quad \text{or} \quad V^2 - 2UV + U^2 - \frac{k}{\rho A} U = 0$$

$$U^2 - (2V + \frac{k}{\rho A}) U + V^2 = 0$$

$$U = \frac{2V + k/\rho A \pm \sqrt{(2V + k/\rho A)^2 - 4V^2}}{2} = V \left\{ \left(1 + \frac{k}{2\rho VA}\right) \pm \sqrt{\left(1 + \frac{k}{2\rho VA}\right)^2 - 1} \right\}$$

$$1 + \frac{k}{2\rho VA} = 1 + \frac{1}{2} \cdot \frac{7.5 \text{ N} \cdot \text{s}}{\text{m}} \cdot \frac{\text{m}^3}{999 \text{ kg}} \cdot \frac{\text{s}}{20 \text{ m}} \cdot \frac{1}{0.005 \text{ m}^2} \cdot \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} = 1.0375$$

$$U = V \left\{ 1.0375 \pm \sqrt{(1.0375)^2 - 1} \right\} = 0.761 V = 0.761 \cdot 20 \frac{\text{m}}{\text{s}} = 15.2 \text{ m/s}$$

$U_t$

{ The negative root was chosen so  $U_t < V$ , as required. }

## Problem 4.153

[Difficulty: 4]

**4.153** For the vane/slider problem of Problem 4.152, plot the acceleration, speed, and position of the slider as functions of time. (Consider numerical integration.)

**Given:** Data on vane/slider

**Find:** Formula for acceleration, speed, and position; plot

**Solution:** Apply x momentum 
$$F_{S_x} + F_{B_x} - \int_{CV} a_{rf_x} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) All changes wrt CV 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Constant jet area

The given data is  $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$        $M = 30 \text{ kg}$        $A = 0.005 \cdot \text{m}^2$        $V = 20 \cdot \frac{\text{m}}{\text{s}}$        $k = 7.5 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}}$

Then  $-kU - M \cdot a_{rf} = u_1 \cdot [-\rho \cdot (V - U) \cdot A] + u_2 \cdot m_2 + u_3 \cdot m_3$

where  $a_{rf} = \frac{dU}{dt}$        $u_1 = V - U$        $u_2 = 0$        $u_3 = 0$

Hence  $-k \cdot U - M \cdot \frac{dU}{dt} = -\rho \cdot (V - U)^2 \cdot A$

or 
$$\frac{dU}{dt} = \frac{\rho \cdot (V - U)^2 \cdot A}{M} - \frac{k \cdot U}{M}$$

The acceleration is thus 
$$a = \frac{\rho \cdot (V - U)^2 \cdot A}{M} - \frac{k \cdot U}{M}$$

The differential equation for  $U$  can be solved analytically, but is quite messy. Instead we use a simple numerical method - Euler's method

$$U(n+1) = U(n) + \left[ \frac{\rho \cdot (V - U(n))^2 \cdot A}{M} - \frac{k \cdot U(n)}{M} \right] \cdot \Delta t \quad \text{where } \Delta t \text{ is the time step}$$

For the position  $x$   $\frac{dx}{dt} = U$

so  $x(n+1) = x(n) + U(n) \cdot \Delta t$

The final set of equations is




$$U(n+1) = U(n) + \left[ \frac{\rho \cdot (V - U(n))^2 \cdot A}{M} - \frac{k \cdot U(n)}{M} \right] \cdot \Delta t$$

$$a(n) = \frac{\rho \cdot (V - U(n))^2 \cdot A}{M} - \frac{k \cdot U(n)}{M}$$

$$x(n+1) = x(n) + U(n) \cdot \Delta t$$

The results can be plotted in *Excel*


$t$ (s)	$x$ (m)	$U$ (m/s)	$a$ (m/s <sup>2</sup> )
0.0	0.0	0.0	66.6
0.1	0.0	6.7	28.0
0.2	0.7	9.5	16.1
0.3	1.6	11.1	10.5
0.4	2.7	12.1	7.30
0.5	3.9	12.9	5.29
0.6	5.2	13.4	3.95
0.7	6.6	13.8	3.01
0.8	7.9	14.1	2.32
0.9	9.3	14.3	1.82
1.0	10.8	14.5	1.43
1.1	12.2	14.6	1.14
1.2	13.7	14.7	0.907
1.3	15.2	14.8	0.727
1.4	16.6	14.9	0.585
1.5	18.1	15.0	0.472
1.6	19.6	15.0	0.381
1.7	21.1	15.1	0.309
1.8	22.6	15.1	0.250
1.9	24.1	15.1	0.203
2.0	25.7	15.1	0.165
2.1	27.2	15.1	0.134
2.2	28.7	15.2	0.109
2.3	30.2	15.2	0.0889
2.4	31.7	15.2	0.0724
2.5	33.2	15.2	0.0590
2.6	34.8	15.2	0.0481
2.7	36.3	15.2	0.0392
2.8	37.8	15.2	0.0319
2.9	39.3	15.2	0.0260
3.0	40.8	15.2	0.0212



### Problem 4.154

[Difficulty: 3]

4.154 A rectangular block of mass  $M$ , with vertical faces, rolls without resistance along a smooth horizontal plane as shown. The block travels initially at speed  $U_0$ . At  $t = 0$  the block is struck by a liquid jet and its speed begins to slow. Obtain an algebraic expression for the acceleration of the block for  $t > 0$ . Solve the equation to determine the time at which  $U = 0$ .



Solution: Apply  $x$  momentum equation to linearly accelerating CV.

Basic equation:

$$F_x + F_x - \int_{CV} \rho u_x v_x dV = \frac{d}{dt} \int_{CV} \rho u_x v_x dV + \int_{CS} \rho u_x v_x \cdot d\vec{A}$$

- Assumptions:
- (1) No pressure or friction forces, so  $F_{3x} = 0$
  - (2) Horizontal, so  $F_{2x} = 0$
  - (3) Neglect mass of liquid in CV,  $u \approx 0$  in CV
  - (4) Uniform flow at each section
  - (5) Measure velocities relative to CV

Then

$$-M a_x = -M \frac{dU}{dt} = u_1 \{-\rho(V+U)A\} + u_2 \{+m_2\} + u_3 \{+m_3\}$$

$$u_1 = -(V+U) \quad u_2 = 0 \quad u_3 = 0$$

or

$$\frac{dU}{dt} = -\frac{\rho(V+U)^2 A}{M}$$

$\frac{dU}{dt}$

But, since  $V = \text{constant}$ ,  $dU = d(V+U)$ , so

$$\frac{d(V+U)}{(V+U)^2} = -\frac{\rho A}{M} dt$$

Integrating from  $U_0$  at  $t=0$  to  $U=0$  at  $t$

$$\int_{V+U_0}^V \frac{d(V+U)}{(V+U)^2} = -\frac{1}{(V+U)} \Big|_{V+U_0}^V = -\frac{1}{V} + \frac{1}{V+U_0} = \frac{-U_0}{V(V+U_0)} = -\frac{\rho A t}{M}$$


Solving,  $t = \frac{M U_0}{\rho V A (V+U_0)} = \frac{M}{\rho V A (1+U_0/V)}$

$t$

### Problem 4.155

[Difficulty: 3]

**4.155** A rectangular block of mass  $M$ , with vertical faces, rolls on a horizontal surface between two opposing jets as shown. At  $t = 0$  the block is set into motion at speed  $U_0$ . Subsequently, it moves without friction parallel to the jet axes with speed  $U(t)$ . Neglect the mass of any liquid adhering to the block compared with  $M$ . Obtain general expressions for the acceleration of the block,  $a(t)$ , and the block speed,  $U(t)$ .



Solution: Apply  $x$  momentum to linearly accelerating CV.

Basic equation:  $\approx 0(1) \approx 0(2)$   $\approx 0(3)$

$$F_{3x} + F_{4x} - \int_{CV} \rho a_{rx} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$$

- Assumptions: (1) No pressure or friction forces, so  $F_{3x} = 0$   
 (2) Horizontal, so  $F_{4x} = 0$   
 (3) Neglect mass of liquid in CV;  $u_{xy3} = 0$  in CV  
 (4) Uniform flow at each section  
 (5) Measure velocities relative to CV

Then

$$-\rho a_{rx} M = -M \frac{dU}{dt} = u_1 \{-\rho(V-U)A\} + u_2 \{-\rho(V+U)A\} + u_3 \{m_3\} + u_4 \{m_4\}$$

$$u_1 = V-U \quad u_2 = -(V+U) \quad u_3 = 0 \quad u_4 = 0$$

or

$$-M \frac{dU}{dt} = \rho A [-(V-U)^2 + (V+U)^2] = \rho A [4UV] = 4\rho VAU$$

Thus  $\frac{dU}{U} = -\frac{4\rho VA}{M} dt$

Integrating  $\int_{U_0}^U \frac{dU}{U} = \ln U \Big|_{U_0}^U = \ln \frac{U}{U_0} = -\frac{4\rho VA}{M} t$

or

$$U(t) = U_0 e^{-\frac{4\rho VA}{M} t}$$

$U(t)$

Also


$$a(t) = \frac{dU}{dt} = -\frac{4\rho VA}{M} U_0 e^{-\frac{4\rho VA}{M} t}$$

$a(t)$

## Problem 4.156

[Difficulty: 3]

**4.156** Consider the diagram of Problem 4.154. If  $M = 100$  kg,  $\rho = 999$  kg/m<sup>3</sup>, and  $A = 0.01$  m<sup>2</sup>, find the jet speed  $V$  required for the cart to be brought to rest after one second if the initial speed of the cart is  $U_0 = 5$  m/s. For this condition, plot the speed  $U$  and position  $x$  of the cart as functions of time. What is the maximum value of  $x$ , and how long does the cart take to return to its initial position?



**Given:** Data on system

**Find:** Jet speed to stop cart after 1 s; plot speed & position; maximum  $x$ ; time to return to origin

**Solution:** Apply x momentum  $F_{S_x} + F_{B_x} - \int_{CV} a_{rf,x} \rho d\Psi = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho d\Psi + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$

Assumptions: 1) All changes wrt CV 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Constant jet area

The given data is  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$        $M = 100 \text{ kg}$        $A = 0.01 \text{ m}^2$        $U_0 = 5 \frac{\text{m}}{\text{s}}$

Then  $-a_{rf} \cdot M = u_1 \cdot [-\rho \cdot (V + U) \cdot A] + u_2 \cdot m_2 + u_3 \cdot m_3$

where  $a_{rf} = \frac{dU}{dt}$        $u_1 = -(V + U)$       and       $u_2 = u_3 = 0$

Hence  $-\frac{dU}{dt} \cdot M = \rho \cdot (V + U)^2 \cdot A$       or       $\frac{dU}{dt} = -\frac{\rho \cdot (V + U)^2 \cdot A}{M}$       which leads to       $\frac{d(V + U)}{(V + U)^2} = -\left(\frac{\rho \cdot A}{M}\right) \cdot dt$

Integrating and using the IC  $U = U_0$  at  $t = 0$        $U = -V + \frac{V + U_0}{1 + \frac{\rho \cdot A \cdot (V + U_0)}{M} \cdot t}$

To find the jet speed  $V$  to stop the cart after 1 s, solve the above equation for  $V$ , with  $U = 0$  and  $t = 1$  s. (The equation becomes a quadratic in  $V$ ). Instead we use *Excel's Goal Seek* in the associated workbook

From *Excel*       $V = 5 \frac{\text{m}}{\text{s}}$

For the position  $x$  we need to integrate  $\frac{dx}{dt} = U = -V + \frac{V + U_0}{1 + \frac{\rho \cdot A \cdot (V + U_0)}{M} \cdot t}$

The result is  $x = -V \cdot t + \frac{M}{\rho \cdot A} \cdot \ln \left[ 1 + \frac{\rho \cdot A \cdot (V + U_0)}{M} \cdot t \right]$

This equation (or the one for  $U$  with  $U = 0$ ) can be easily used to find the maximum value of  $x$  by differentiating, as well as the time for  $x$  to be zero again. Instead we use *Excel's Goal Seek* and *Solver* in the associated workbook

From *Excel*       $x_{\text{max}} = 1.93 \cdot \text{m}$        $t(x = 0) = 2.51 \cdot \text{s}$

The complete set of equations is  $U = -V + \frac{V + U_0}{1 + \frac{\rho \cdot A \cdot (V + U_0)}{M} \cdot t}$        $x = -V \cdot t + \frac{M}{\rho \cdot A} \cdot \ln \left[ 1 + \frac{\rho \cdot A \cdot (V + U_0)}{M} \cdot t \right]$

The plots are presented in the *Excel* workbook:

$t$ (s)	$x$ (m)	$U$ (m/s)
0.0	0.00	5.00
0.2	0.82	3.33
0.4	1.36	2.14
0.6	1.70	1.25
0.8	1.88	0.56
1.0	1.93	0.00
1.2	1.88	-0.45
1.4	1.75	-0.83
1.6	1.56	-1.15
1.8	1.30	-1.43
2.0	0.99	-1.67
2.2	0.63	-1.88
2.4	0.24	-2.06
2.6	-0.19	-2.22
2.8	-0.65	-2.37
3.0	-1.14	-2.50

To find  $V$  for  $U = 0$  in 1 s, use *Goal Seek*



$t$ (s)	$U$ (m/s)	$V$ (m/s)
1.0	0.00	5.00

To find the maximum  $x$ , use *Solver*

$t$ (s)	$x$ (m)
1.0	1.93

To find the time at which  $x = 0$  use *Goal Seek*


$t$ (s)	$x$ (m)
2.51	0.00



## Problem 4.157

[Difficulty: 2]

**4.157** Consider the statement and diagram of Problem 4.155. Assume that at  $t = 0$ , when the block of mass  $M = 5 \text{ kg}$  is at  $x = 0$ , it is set into motion at speed  $U_0 = 10 \text{ m/s}$ , to the right. The water jets have speed  $V = 20 \text{ m/s}$  and area  $A = 100 \text{ mm}^2$ . Calculate the time required to reduce the block speed to  $U = 2.5 \text{ m/s}$ . Plot the block position  $x$  versus time. Compute the final rest position of the block. Explain why it comes to rest.



**Given:** Mass moving between two jets

**Find:** Time to slow to 2.5 m/s; plot position; rest position; explain

**Solution:** Apply x momentum 
$$F_{S_x} + F_{B_x} - \int_{CV} a_{rf_x} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) All changes wrt CV 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow 5) Constant jet area

The given data is  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$      $M = 5 \text{ kg}$      $V = 20 \frac{\text{m}}{\text{s}}$      $U_0 = 10 \frac{\text{m}}{\text{s}}$      $U = 2.5 \frac{\text{m}}{\text{s}}$      $A = 100 \text{ mm}^2$

Then  $-a_{rf} \cdot M = u_1 \cdot [-\rho \cdot (V - U) \cdot A] + u_2 \cdot [-\rho \cdot (V + U) \cdot A] + u_3 \cdot m_3$

where  $a_{rf} = \frac{dU}{dt}$      $u_1 = V - U$      $u_2 = -(V + U)$     and     $u_3 = 0$

Hence  $-\frac{dU}{dt} \cdot M = \rho \cdot A \cdot [-(V - U)^2 + (V + U)^2] = 4 \cdot \rho \cdot A \cdot V \cdot U$


Separating and integrating  $\frac{dU}{U} = -\frac{4 \cdot \rho \cdot A \cdot V}{M} \cdot dt$     or     $\ln(U) - \ln(U_0) = -\frac{4 \cdot \rho \cdot A \cdot V}{M} \cdot t$      $U = U_0 \cdot e^{-\frac{4 \cdot \rho \cdot A \cdot V}{M} \cdot t}$     (1)

Solving for t  $t = -\frac{M}{4 \cdot \rho \cdot V \cdot A} \cdot \ln\left(\frac{U}{U_0}\right)$     and using given data     $t = 0.867 \text{ s}$     for     $U = 2.5 \frac{\text{m}}{\text{s}}$

For position x  $\frac{dx}{dt} = U = U_0 \cdot e^{-\frac{4 \cdot \rho \cdot A \cdot V}{M} \cdot t}$

and a straightforward integration leads to  $x(t) = \frac{M \cdot U_0}{4 \cdot \rho \cdot V \cdot A} \cdot \left(1 - e^{-\frac{4 \cdot \rho \cdot V \cdot A}{M} \cdot t}\right)$     For     $t = 0.867 \text{ s}$      $x(t) = 4.69 \text{ m}$


For large time  $x_{\text{final}} = \frac{M \cdot U_0}{4 \cdot \rho \cdot V \cdot A}$      $x_{\text{final}} = 6.26 \text{ m}$



## Problem \*4.158

[Difficulty: 3]

**\*4.158** A vertical jet of water impinges on a horizontal disk as shown. The disk assembly mass is 30 kg. When the disk is 3 m above the nozzle exit, it is moving upward at  $U = 5$  m/s. Compute the vertical acceleration of the disk at this instant.



**Given:** Water jet striking moving disk

**Find:** Acceleration of disk when at a height of 3 m

**Solution:**

Basic equations: Bernoulli; Momentum flux in z direction (treated as upwards) for linear accelerating CV

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad F_{S_z} + F_{B_z} - \int_{CV} a_{rfz} \rho dV = \frac{\partial}{\partial t} \int_{CV} w_{xyz} \rho dV + \int_{CS} w_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow (All in jet)

The Bernoulli equation becomes  $\frac{V_0^2}{2} + g \cdot 0 = \frac{V_1^2}{2} + g \cdot (z - z_0)$   $V_1 = \sqrt{V_0^2 + 2 \cdot g \cdot (z_0 - z)}$

$$V_1 = \sqrt{\left(15 \cdot \frac{\text{m}}{\text{s}}\right)^2 + 2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \cdot (0 - 3) \cdot \text{m}} \quad V_1 = 12.9 \frac{\text{m}}{\text{s}}$$

The momentum equation becomes

$$-W - M \cdot a_{rfz} = w_1 \cdot (-\rho \cdot V_1 \cdot A_1) + w_2 \cdot (\rho \cdot V_2 \cdot A_2) = (V_1 - U) \cdot [-\rho \cdot (V_1 - U) \cdot A_1] + 0$$


Hence  $a_{rfz} = \frac{\rho \cdot (V_1 - U)^2 \cdot A_1 - W}{M} = \frac{\rho \cdot (V_1 - U)^2 \cdot A_1}{M} - g = \frac{\rho \cdot (V_1 - U)^2 \cdot A_0 \cdot \frac{V_0}{V_1}}{M} - g$  using  $V_1 \cdot A_1 = V_0 \cdot A_0$

$$a_{rfz} = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ (12.9 - 5) \cdot \frac{\text{m}}{\text{s}} \right]^2 \times 0.005 \cdot \text{m}^2 \times \frac{15}{12.9} \times \frac{1}{30 \cdot \text{kg}} - 9.81 \cdot \frac{\text{m}}{\text{s}^2} \quad a_{rfz} = 2.28 \frac{\text{m}}{\text{s}^2}$$

## Problem 4.159

[Difficulty: 4]

**4.159** A vertical jet of water leaves a 75-mm diameter nozzle. The jet impinges on a horizontal disk (see Problem 4.158). The disk is constrained horizontally but is free to move vertically. The mass of the disk is 35 kg. Plot disk mass versus flow rate to determine the water flow rate required to suspend the disk 3 m above the jet exit plane.



**Given:** Water jet striking disk

**Find:** Plot mass versus flow rate to find flow rate for a steady height of 3 m

**Solution:**

Basic equations: Bernoulli; Momentum flux in z direction (treated as upwards)

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad F_z = F_{S_z} + F_{B_z} = \frac{\partial}{\partial t} \int_{CV} w \rho dV + \int_{CS} w \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow (All in jet)

The Bernoulli equation becomes  $\frac{V_0^2}{2} + g \cdot 0 = \frac{V_1^2}{2} + g \cdot h \quad V_1 = \sqrt{V_0^2 - 2 \cdot g \cdot h}$


The momentum equation becomes

$$-M \cdot g = w_1 \cdot (-\rho \cdot V_1 \cdot A_1) + w_2 \cdot (\rho \cdot V_2 \cdot A_2) = V_1 \cdot (-\rho \cdot V_1 \cdot A_1) + 0$$

Hence  $M = \frac{\rho \cdot V_1^2 \cdot A_1}{g}$  but from continuity  $V_1 \cdot A_1 = V_0 \cdot A_0$

$$M = \frac{\rho \cdot V_1 \cdot V_0 \cdot A_0}{g} = \frac{\pi}{4} \cdot \frac{\rho \cdot V_0 \cdot D_0^2}{g} \cdot \sqrt{V_0^2 - 2 \cdot g \cdot h} \quad \text{and also} \quad Q = V_0 \cdot A_0$$

This equation is difficult to solve for  $V_0$  for a given  $M$ . Instead we plot first:



Goal Seek or Solver in *Excel* feature can be used to find  $Q$  when  $M = 35$  kg  $Q = 0.0469 \cdot \frac{\text{m}^3}{\text{s}}$

### Problem 4.160

[Difficulty: 3]

**4.160** A rocket sled traveling on a horizontal track is slowed by a retro-rocket fired in the direction of travel. The initial speed of the sled is  $U_0 = 500$  m/s. The initial mass of the sled is  $M_0 = 1500$  kg. The retro-rocket consumes fuel at the rate of 7.75 kg/s, and the exhaust gases leave the nozzle at atmospheric pressure and a speed of 2500 m/s relative to the rocket. The retro-rocket fires for 20 s. Neglect aerodynamic drag and rolling resistance. Obtain and plot an algebraic expression for sled speed  $U$  as a function of firing time. Calculate the sled speed at the end of retro-rocket firing.


Solution: Apply  $x$ -component of momentum equation to the linearly accelerating CV shown.

From continuity,

$$M_{CV} = M_0 - \dot{m}t, \quad t < t_{b0}$$

Basic equation:  $F_{sx} + F_{Bx} - \int_{CV} a r_x \rho dV = \frac{d}{dt} \int_{CV} u_x \rho dV + \int_{CS} u_x \rho \vec{V} \cdot \vec{n} dA$

*Notes:*  $\approx 0(1)$  above  $F_{sx}$ ,  $\approx 0(2)$  above  $F_{Bx}$ ,  $\approx 0(3)$  above  $\frac{d}{dt}$ .



- Assumptions:
- (1) No pressure, drag, or rolling resistance, so  $F_{sx} = 0$
  - (2) Horizontal motion, so  $F_{Bx} = 0$
  - (3) Neglect unsteady effects within CV
  - (4) Uniform flow at nozzle exit plane
  - (5)  $p_e = p_{atm}$

Then  $-a r_x M_{CV} = u_e \{ + \dot{m} \} = + V_e \dot{m}$  or  $\frac{dU}{dt} = -\frac{V_e \dot{m}}{M_{CV}} = -\frac{V_e \dot{m}}{M_0 - \dot{m}t}$

$u_e = V_e$

Thus  $dU = V_e \left( \frac{-\dot{m} dt}{M_0 - \dot{m}t} \right)$  and  $U - U_0 = V_e \ln \left( M_0 - \dot{m}t \right)_0^t = V_e \ln \left( 1 - \frac{\dot{m}t}{M_0} \right)$

$$U(t) = U_0 + V_e \ln \left( 1 - \frac{\dot{m}t}{M_0} \right) ; \quad t < t_{b0}$$

$U(t)$

At  $t_{b0}$ ,  $U(t_{b0}) = 500 \frac{m}{s} + 2500 \frac{m}{s} \times \ln \left( 1 - \frac{7.75 \frac{kg}{s} \times 20.0 s}{1500 kg} \right)$


$$U(t_{b0}) = 227 \text{ m/s}$$

$U(t_{b0})$

### Problem 4.161

[Difficulty: 3]

**4.161** A manned space capsule travels in level flight above the Earth's atmosphere at initial speed  $U_0 = 8.00$  km/s. The capsule is to be slowed by a retro-rocket to  $U = 5.00$  km/s in preparation for a reentry maneuver. The initial mass of the capsule is  $M_0 = 1600$  kg. The rocket consumes fuel at  $\dot{m} = 8.0$  kg/s, and exhaust gases leave at  $V_e = 3000$  m/s relative to the capsule and at negligible pressure. Evaluate the duration of the retro-rocket firing needed to accomplish this. Plot the final speed as a function of firing duration for a time range  $\pm 10\%$  of this firing time.



Solution: Apply  $x$  component of momentum to CV with linear acceleration.

Basic equation:  $F_x^{(1)} = F_x^{(2)}$

$$F_{rx} + F_{bx} - \int_{CV} a_{rx} \rho dV = \frac{d}{dt} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

$\approx 0$  (4)

- Assumptions: (1) No resistance;  $F_{rx} = 0$   
 (2) Horizontal;  $F_{bx} = 0$   
 (3) Use velocities measured relative to CV  
 (4) Neglect velocity within CV  
 (5) Uniform flow at exit plane with negligible  $p_e$  (given)

From continuity,

$$\frac{dM}{dt} = \frac{d}{dt} \int_{CV} \rho dV = - \int_{CS} \rho \vec{V}_{xyz} \cdot d\vec{A} = -\dot{m}; \quad M(t) = M_0 - \dot{m}t$$

From momentum,

$$-a_{rx} M = - \frac{dU}{dt} (M_0 - \dot{m}t) = U_e \{ + \dot{m} \} = V_e \dot{m}$$

Thus

$$\frac{dU}{dt} = - \frac{V_e \dot{m}}{M_0 - \dot{m}t} \quad U_e = V_e$$

Integrating,  $U - U_0 = V_e \int_0^t \frac{-\dot{m} dt}{M_0 - \dot{m}t} = V_e \ln(M_0 - \dot{m}t) \Big|_0^t = V_e \ln \left( \frac{M_0 - \dot{m}t}{M_0} \right)$

Solving for  $t$ ,

$$\frac{M_0 - \dot{m}t}{M_0} = e^{-\frac{U - U_0}{V_e}}; \quad M_0 - \dot{m}t = M_0 e^{-\frac{U - U_0}{V_e}}$$

$$t = \frac{M_0}{\dot{m}} \left( 1 - e^{-\frac{U - U_0}{V_e}} \right)$$

$$= 1600 \text{ kg} \times \frac{\text{s}}{8 \text{ kg}} \left\{ 1 - e^{-\left[ \frac{(5.00 - 8.00) \text{ km}}{\text{s}} \times \frac{\text{s}}{3000 \text{ m}} \times \frac{1000 \text{ m}}{\text{km}} \right]} \right\}$$

$$t = 126 \text{ s}$$

**4.162** A rocket sled accelerates from rest on a level track with negligible air and rolling resistances. The initial mass of the sled is  $M_0 = 600$  kg. The rocket initially contains 150 kg of fuel. The rocket motor burns fuel at constant rate  $\dot{m} = 15$  kg/s. Exhaust gases leave the rocket nozzle uniformly and axially at  $V_e = 2900$  m/s relative to the nozzle, and the pressure is atmospheric. Find the maximum speed reached by the rocket sled. Calculate the maximum acceleration of the sled during the run.


Solution:

Apply the momentum equation to linearly accelerating CV shown.

Basic equation:  $\cancel{F_{sx}} + \cancel{F_{sx}} - \int_{CV} \rho \vec{u} \cdot d\vec{A} = \frac{d}{dt} \int_{CV} \rho \vec{u} \cdot d\vec{V} + \int_{CS} \rho \vec{u} \cdot \vec{n} \cdot dA$

- Assumptions: (1) no net pressure forces ( $p_e = p_{atm}$ , given)  
 (2) horizontal motion,  $F_{rx} = 0$   
 (3) neglected  $\frac{\partial}{\partial t}$  in CV  
 (4) uniform axial jet

From continuity,  $M = M_0 - \dot{m}t$ . Then  
 $-\dot{m} M = -\frac{dM}{dt} (M_0 - \dot{m}t) = u_e \dot{m} = -V_e \dot{m}$  ... (1)



Separating variables,  
 $dU = V_e \frac{\dot{m} dt}{M_0 - \dot{m}t}$

Integrating from  $U=0$  at  $t=0$  to  $U$  at  $t$  gives  
 $U = -V_e \ln(M_0 - \dot{m}t) \Big|_0^t = -V_e \ln \frac{(M_0 - \dot{m}t)}{M_0} = V_e \ln \frac{M_0}{(M_0 - \dot{m}t)}$  ... (2)

The speed is a maximum at burnout. At burnout  $M_f = 0$  and  $M = M_0 - \dot{m}t = 450$  kg

At burnout,  $t = \frac{M_f \text{ initial}}{\dot{m}_{\text{fuel}}} = \frac{150 \text{ kg}}{15 \text{ kg/s}} = 10 \text{ s}$

Then from Eq. 2

$U_{\text{max}} = 2900 \frac{\text{m}}{\text{s}} \ln \frac{600 \text{ kg}}{450 \text{ kg}} = 834 \text{ m/s}$  ←  $U_{\text{max}}$

From Eq. 1 the acceleration is  $\frac{dU}{dt} = \frac{\dot{m} V_e}{M_0 - \dot{m}t}$

The maximum acceleration occurs at the instant prior to burn out

$\left. \frac{dU}{dt} \right|_{\text{max}} = \frac{15 \text{ kg}}{\text{s}} \times \frac{2900 \text{ m}}{\text{s}} \times \frac{1}{450 \text{ kg}} = 96.7 \text{ m/s}^2$  ←  $\left. \frac{dU}{dt} \right|_{\text{max}}$

15, 20, 25, 30, 35, 40, 45, 50 SHEETS PER PAK  
 42, 50 SHEETS PER PAK  
 42, 50 SHEETS PER PAK  
 100 RECYCLED, WHITE  
 5 SQUARE  
 5 SQUARE  
 200 RECYCLED WHITE  
 5 SQUARE  
 MADE IN U.S.A.






## Problem 4.163

[Difficulty: 4]

**4.163** A rocket sled has mass of 5000 kg, including 1000 kg of fuel. The motion resistance in the track on which the sled rides and that of the air total  $kU$ , where  $k$  is 50 N·s/m and  $U$  is the speed of the sled in m/s. The exit speed of the exhaust gas relative to the rocket is 1750 m/s, and the exit pressure is atmospheric. The rocket burns fuel at the rate of 50 kg/s.



- (a) Plot the sled speed as a function of time.
- (b) Find the maximum speed.
- (c) What percentage increase in maximum speed would be obtained by reducing  $k$  by 10 percent?

**Given:** Rocket sled on track

**Find:** Plot speed versus time; maximum speed; effect of reducing  $k$

**Solution:**

Basic equation: Momentum flux in x direction

$$F_{S_x} + F_{B_x} - \int_{CV} a_{rf_x} \rho dV = \frac{\partial}{\partial t} \int_{CV} w_{xyz} \rho dV + \int_{CS} w_{xyz} \rho \bar{V}_{xyz} \cdot d\bar{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure in jet 4) Uniform flow (All in jet)

Given data  $M_0 = 5000 \cdot \text{kg}$      $k = 50 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}}$      $V_e = 1750 \cdot \frac{\text{m}}{\text{s}}$      $M_{\text{fuel}} = 1000 \cdot \text{kg}$      $m_{\text{rate}} = 50 \cdot \frac{\text{kg}}{\text{s}}$

The momentum equation becomes  $-F_R - a_{rf} \cdot M = u_e \cdot m_{\text{rate}} = -V_e \cdot m_{\text{rate}}$     and     $F_R = k \cdot U$

From continuity  $M = M_0 - m_{\text{rate}} \cdot t$

Hence, combining  $-k \cdot U - (M_0 - m_{\text{rate}} \cdot t) \cdot \frac{dU}{dt} = -V_e \cdot m_{\text{rate}}$     or     $\frac{dU}{dt} = \frac{V_e \cdot m_{\text{rate}} - k \cdot U}{M_0 - m_{\text{rate}} \cdot t}$

Separating variables  $\frac{dU}{V_e \cdot m_{\text{rate}} - k \cdot U} = \frac{dt}{(M_0 - m_{\text{rate}} \cdot t)}$

Integrating  $\frac{1}{k} \cdot ((\ln(V_e \cdot m_{\text{rate}} - k \cdot U) - \ln(V_e \cdot m_{\text{rate}}))) = \frac{1}{m_{\text{rate}}} \cdot (\ln(M_0 - m_{\text{rate}} \cdot t) - \ln(M_0))$

Simplifying  $\frac{1}{k} \cdot \ln\left(\frac{V_e \cdot m_{\text{rate}} - k \cdot U}{V_e \cdot m_{\text{rate}}}\right) = \frac{1}{k} \cdot \ln\left(1 - \frac{k \cdot U}{V_e \cdot m_{\text{rate}}}\right) = \frac{1}{m_{\text{rate}}} \cdot \ln\left(\frac{M_0 - m_{\text{rate}} \cdot t}{M_0}\right) = \frac{1}{m_{\text{rate}}} \cdot \ln\left(1 - \frac{m_{\text{rate}} \cdot t}{M_0}\right)$

Solving for U  $U(t) = \frac{V_e \cdot m_{\text{rate}}}{k} \cdot \left[ 1 - \left( 1 - \frac{m_{\text{rate}} \cdot t}{M_0} \right)^{\frac{k}{m_{\text{rate}}}} \right]$

Using given data  $U(10 \cdot \text{s}) = 175 \frac{\text{m}}{\text{s}}$     and fuel is used up when  $t_{\text{fuel}} = \frac{M_{\text{fuel}}}{m_{\text{rate}}} = 20 \text{ s}$


This is when the speed is maximum  $U_{\max} = U(t_{\text{fuel}}) \quad U_{\max} = 350 \frac{\text{m}}{\text{s}}$

With 10% reduction in k  $k_2 = 0.9 \cdot k \quad U_{\max 2} = \frac{V_e \cdot m_{\text{rate}}}{k_2} \cdot \left[ 1 - \left( 1 - \frac{m_{\text{rate}} \cdot t_{\text{fuel}}}{M_0} \right)^{\frac{k_2}{m_{\text{rate}}}} \right] \quad U_{\max 2} = 354 \frac{\text{m}}{\text{s}}$

The percent improvement is  $\frac{U_{\max 2} - U_{\max}}{U_{\max}} = 1.08\%$

When the fuel runs out the momentum equation simplifies from  $-k \cdot U - (M_0 - m_{\text{rate}} \cdot t) \cdot \frac{dU}{dt} = -V_e \cdot m_{\text{rate}}$  to  $-k \cdot U - \frac{dU}{dt} = 0$


The solution to this (with  $U = U_{\max}$  when  $t = t_{\text{fuel}}$ )  $U_{\text{empty}}(t) = U_{\max} \cdot e^{-\frac{k \cdot (t - t_{\text{fuel}})}{M_0 - M_{\text{fuel}}}}$



## Problem 4.164

[Difficulty: 3]

**4.164** A rocket sled with initial mass of 900 kg is to be accelerated on a level track. The rocket motor burns fuel at constant rate  $\dot{m} = 13.5$  kg/s. The rocket exhaust flow is uniform and axial. Gases leave the nozzle at 2750 m/s relative to the nozzle, and the pressure is atmospheric. Determine the minimum mass of rocket fuel needed to propel the sled to a speed of 265 m/s before burnout occurs. As a first approximation, neglect resistance forces.



**Given:** Data on rocket sled

**Find:** Minimum fuel to get to 265 m/s

**Solution:**

Basic equation: Momentum flux in x direction 
$$F_{S_x} + F_{B_x} - \int_{CV} a_{rfx} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) No resistance 2)  $p_e = p_{atm}$  3) Uniform flow 4) Use relative velocities

From continuity  $\frac{dM}{dt} = m_{rate} = \text{constant}$  so  $M = M_0 - m_{rate} \cdot t$  (Note: Software cannot render a dot!)

Hence from momentum 
$$-a_{rfx} \cdot M = -\frac{dU}{dt} \cdot (M_0 - m_{rate} \cdot t) = u_e \cdot (\rho_e \cdot V_e \cdot A_e) = -V_e \cdot m_{rate}$$

Separating variables 
$$dU = \frac{V_e \cdot m_{rate}}{M_0 - m_{rate} \cdot t} \cdot dt$$

Integrating 
$$U = V_e \cdot \ln\left(\frac{M_0}{M_0 - m_{rate} \cdot t}\right) = -V_e \cdot \ln\left(1 - \frac{m_{rate} \cdot t}{M_0}\right) \quad \text{or} \quad t = \frac{M_0}{m_{rate}} \cdot \left(1 - e^{-\frac{U}{V_e}}\right)$$


The mass of fuel consumed is 
$$m_f = m_{rate} \cdot t = M_0 \cdot \left(1 - e^{-\frac{U}{V_e}}\right)$$

Hence 
$$m_f = 900 \cdot \text{kg} \times \left(1 - e^{-\frac{265}{2750}}\right) \quad m_f = 82.7 \text{ kg}$$

## Problem 4.165

[Difficulty: 3]

**4.165** A rocket motor is used to accelerate a kinetic energy weapon to a speed of 3500 mph in horizontal flight. The exit stream leaves the nozzle axially and at atmospheric pressure with a speed of 6000 mph relative to the rocket. The rocket motor ignites upon release of the weapon from an aircraft flying horizontally at  $U_0 = 600$  mph. Neglecting air resistance, obtain an algebraic expression for the speed reached by the weapon in level flight. Determine the minimum fraction of the initial mass of the weapon that must be fuel to accomplish the desired acceleration.



**Given:** Data on rocket weapon

**Find:** Expression for speed of weapon; minimum fraction of mass that must be fuel

**Solution:**

Basic equation: Momentum flux in x direction 
$$F_{S_x} + F_{B_x} - \int_{CV} a_{rf_x} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) No resistance 2)  $p_e = p_{atm}$  3) Uniform flow 4) Use relative velocities 5) Constant mass flow rate

From continuity 
$$\frac{dM}{dt} = m_{rate} = \text{constant} \quad \text{so} \quad M = M_0 - m_{rate} \cdot t \quad (\text{Note: Software cannot render a dot!})$$

Hence from momentum 
$$-a_{rf_x} \cdot M = -\frac{dU}{dt} \cdot (M_0 - m_{rate} \cdot t) = u_e \cdot (\rho_e \cdot V_e \cdot A_e) = -V_e \cdot m_{rate}$$

Separating variables 
$$dU = \frac{V_e \cdot m_{rate}}{M_0 - m_{rate} \cdot t} \cdot dt$$

Integrating from  $U = U_0$  at  $t = 0$  to  $U = U$  at  $t = t$

$$U - U_0 = -V_e \cdot \left( \ln(M_0 - m_{rate} \cdot t) - \ln(M_0) \right) = -V_e \cdot \ln \left( 1 - \frac{m_{rate} \cdot t}{M_0} \right)$$

$$U = U_0 - V_e \cdot \ln \left( 1 - \frac{m_{rate} \cdot t}{M_0} \right)$$

Rearranging 
$$\text{MassFractionConsumed} = \frac{m_{rate} \cdot t}{M_0} = 1 - e^{-\frac{(U-U_0)}{V_e}} = 1 - e^{-\frac{(3500-600)}{6000}} = 0.383$$

Hence 38.3% of the mass must be fuel to accomplish the task. In reality, a much higher percentage would be needed due to drag effects





# Problem 4.167

[Difficulty: 3]


4.167 A daredevil considering a record attempt—for the world's longest motorcycle jump—asks for your consulting help: He must reach 875 km/hr (from a standing start on horizontal ground) to make the jump, so he needs rocket propulsion. The total mass of the motorcycle, the rocket

motor without fuel, and the rider is 375 kg. Gases leave the rocket nozzle horizontally, at atmospheric pressure, with a speed of 2510 m/s. Evaluate the minimum amount of rocket fuel needed to accelerate the motorcycle and rider to the required speed.

Solution: Apply x-component of momentum equation to linearly accelerating CV shown.

From continuity,

$$M_{cv} = M_0 - \dot{m}t$$



Basic equation: 
$$\sum F_x = \frac{d}{dt} \int_{CV} \rho u_x dV + \int_{CS} \rho u_x \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Neglect air and rolling resistance  
 (2) Level track, so  $F_{Bx} = 0$   
 (3) Neglect unsteady effects within CV  
 (4) Uniform flow at nozzle exit plane  
 (5)  $p_e = p_{atm}$

Then

$$-p_e A_e M_{cv} = u_e \{ \dot{m} \} = -V_e \dot{m} \quad \text{or} \quad \frac{dU}{dt} = \frac{V_e \dot{m}}{M_{cv}} = \frac{V_e \dot{m}}{M_0 - \dot{m}t}$$

$$u_e = -V_e$$

Separating variables and integrating,

$$dU = -V_e \left( \frac{-\dot{m} dt}{M_0 - \dot{m}t} \right) \quad \text{or} \quad U_j = -V_e \ln(M_0 - \dot{m}t)_0^t = V_e \ln \left( \frac{M_0}{M_0 - \dot{m}t} \right)$$

But  $M_0 = M_B + M_F$  and  $M_F = \dot{m}t$ , so

$$\frac{U_j}{V_e} = \ln \left( \frac{M_B + M_F}{M_B} \right) = \ln \left( 1 + \frac{M_F}{M_B} \right); \quad 1 + \frac{M_F}{M_B} = e^{U_j/V_e}; \quad \frac{M_F}{M_B} = e^{U_j/V_e} - 1$$

Finally,  $M_F = M_B (e^{U_j/V_e} - 1)$

$$M_F = 375 \text{ kg} \times \exp \left[ 875 \frac{\text{km}}{\text{hr}} \times \frac{5}{2510 \text{ m}} \times \frac{1000 \text{ m}}{\text{km}} \times \frac{\text{hr}}{3600 \text{ s}} - 1 \right]$$

$$M_F = 38.1 \text{ kg}$$


$M_F$

The fuel mass required is about 10 percent of the mass of the motorcycle and rider.

### Problem 4.168

[Difficulty: 3] Part 1/2

**4.168** A "home-made" solid propellant rocket has an initial mass of 20 lbm; 15 lbm of this is fuel. The rocket is directed vertically upward from rest, burns fuel at a constant rate of 0.5 lbm/s, and ejects exhaust gas at a speed of 6500 ft/s relative to the rocket. Assume that the pressure at the exit is atmospheric and that air resistance may be neglected. Calculate the rocket speed after 20 s and the distance traveled by the rocket in 20 s. Plot the rocket speed and the distance traveled as functions of time.



Solution: Apply  $y$ -component of momentum equation to accelerating CV using CS shown.

Basic equation:

$$F_{By} + F_{By} - \int_{CV} a r_{fy} \rho dV = \frac{d}{dt} \int_{CV} v_{xy} \rho dV + \int_{CS} v_{xy} \rho \vec{V}_{xy} \cdot d\vec{A}$$

$\approx 0(z)$

Assumptions: (1) Neglect air resistance;  $p_e = p_{atm}$  (given)  
 (2) Neglect  $v_{xy}$  and  $\frac{d}{dt}$  within CV  
 (3) Uniform flow at nozzle exit section

Then

$$F_{By} - a r_{fy} M = -Mg - M a r_{fy} = v_e \{ + \dot{m} \} = -v_e \dot{m}$$

and

$$v_e = -V_e$$

$$a r_{fy} = \frac{dV}{dt} = \frac{V_e \dot{m}}{M} - g$$

Introducing  $M = M_0 - \dot{m}t$  and separating variables,

$$dV = \left( \frac{V_e \dot{m}}{M_0 - \dot{m}t} - g \right) dt$$

Integrating from rest at  $t = 0$

$$V = \int_0^t \left( \frac{V_e \dot{m}}{M_0 - \dot{m}t} - g \right) dt = -V_e \ln(M_0 - \dot{m}t) \Big|_0^t - gt$$

or

$$V = V_e \ln \left( \frac{M_0}{M_0 - \dot{m}t} \right) - gt \quad (1)$$

At  $t = 20$  sec,

$$V = 6500 \frac{ft}{s} \ln \left( \frac{20 \text{ lbm}}{20 \text{ lbm} - 0.5 \frac{lbm}{s} \times 20 s} \right) - 32.2 \frac{ft}{s^2} \times 20 s$$

$$V(20 s) = 3,860 \text{ ft/s}$$

To find height, note  $V = \frac{dY}{dt}$ . Substitute into Eq. 1 to obtain

$V_{20}$

### Problem 4.168

[Difficulty: 3] Part 2/2

$$\frac{dY}{dt} = V_e \ln\left(\frac{M_0}{M_0 - \dot{m}t}\right) - gt = -V_e \ln\left(1 - \frac{\dot{m}t}{M_0}\right) - gt$$

Let  $r = 1 - \frac{\dot{m}t}{M_0}$ , and  $dr = -\frac{\dot{m}}{M_0} dt$ , then

$$dY = -V_e \ln r dr - gt dt = +\frac{V_e M_0}{\dot{m}} \ln r dr - gt dt$$

Integrating from  $Y=0$  at  $t=0$ ,

$$Y = \int_0^t \frac{V_e M_0}{\dot{m}} \ln r dr - \frac{1}{2} gt^2 = \frac{V_e M_0}{\dot{m}} \left[ r \ln r - r \right]_0^t - \frac{1}{2} gt^2$$

$$= \frac{V_e M_0}{\dot{m}} \left\{ \left(1 - \frac{\dot{m}t}{M_0}\right) \left[ \ln\left(1 - \frac{\dot{m}t}{M_0}\right) - 1 \right] \right\} \Big|_0^t - \frac{1}{2} gt^2$$

$$Y = \frac{V_e M_0}{\dot{m}} \left\{ \left(1 - \frac{\dot{m}t}{M_0}\right) \left[ \ln\left(1 - \frac{\dot{m}t}{M_0}\right) - 1 \right] + 1 \right\} - \frac{1}{2} gt^2$$

At  $t = 20$  s,



$$1 - \frac{\dot{m}t}{M_0} = 1 - 0.5 \frac{\text{lbm}}{\text{s}} \times 20 \text{ s} \times \frac{1}{20 \text{ lbm}} = \frac{1}{2}$$

so


$$Y = 6500 \frac{\text{ft}}{\text{s}} \times 20 \text{ lbm} \times \frac{\text{s}}{0.5 \text{ lbm}} \left\{ \left(\frac{1}{2}\right) \left[ \ln\left(\frac{1}{2}\right) - 1 \right] + 1 \right\} - \frac{1}{2} \times 32.2 \frac{\text{ft}}{\text{s}^2} (20)^2 \text{ s}^2$$

$$Y = 33,500 \text{ ft}$$

Y



4.169 A large two-stage liquid rocket with mass of 30,000 kg is to be launched from a sea-level launch pad. The main engine burns liquid hydrogen and liquid oxygen in a stoichiometric mixture at 2450 kg/s. The thrust nozzle has an exit diameter of 2.6 m. The exhaust gases exit the nozzle at 2270 m/s and an exit plane pressure of 66 kPa absolute. Calculate the acceleration of the rocket at liftoff. Obtain an expression for speed as a function of time, neglecting air resistance.



Solution: Apply y component of momentum equation to CV with linear acceleration

Basic equation:  $F_{Ay} + F_{By} - \int_{CV} a_{ry} \rho dV = \frac{d}{dt} \int_{CV} U_{ry} \rho dV + \int_{CS} U_{ry} \rho \vec{V} \cdot d\vec{A}$

- Assumptions: (1)  $F_{Ay}$  due to pressure,  $p_{atm}$  assumed constant, neglect air resistance  
 (2) neglect rate of change of momentum inside CV  
 (3) uniform flow at exit

Then,  $(p_e - p_{atm})A_e - Mg - a_{ry}M = U_e \{ \dot{m} \} = -\dot{m}U_e$

Solving for  $a_{ry}$ ,  $a_{ry} = \frac{dU}{dt} = \frac{1}{M} [ \dot{m}U_e + (p_e - p_{atm})A_e ] - g \dots (1)$

$M = M(t)$ . From conservation of mass  $\frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$

Then  $\frac{d}{dt} \int_{CV} \rho dV = \frac{dM}{dt} = - \int_{CS} \rho \vec{V} \cdot d\vec{A} = -\dot{m}_e$  (constant)

Hence  $M(t) = M_0 - \dot{m}t$ , and

$$a_{ry} = \frac{dU}{dt} = \frac{\dot{m}U_e}{M_0 - \dot{m}t} + \frac{(p_e - p_{atm})A_e}{M_0 - \dot{m}t} - g$$

$$U = \int_0^t dU = \int_0^t \frac{\dot{m}U_e}{M_0 - \dot{m}t} dt + \int_0^t \frac{(p_e - p_{atm})A_e}{M_0 - \dot{m}t} dt - \int_0^t g dt$$

$$U = -U_e \ln \left[ \frac{M_0 - \dot{m}t}{M_0} \right] - \frac{(p_e - p_{atm})A_e}{\dot{m}} \ln \left[ \frac{M_0 - \dot{m}t}{M_0} \right] - gt$$

$$U = - \left[ U_e + \frac{(p_e - p_{atm})A_e}{\dot{m}} \right] \ln \left[ \frac{M_0 - \dot{m}t}{M_0} \right] - gt \quad \leftarrow U(t)$$

At lift-off,  $t = 0$ ,  $M = M_0$

$$a_{ry} = \frac{1}{M} [ \dot{m}U_e + (p_e - p_{atm})A_e ] - g$$


$$= \frac{1}{3 \times 10^4 \text{ kg}} \left[ 2450 \frac{\text{kg}}{\text{s}} \cdot 2270 \frac{\text{m}}{\text{s}} + (66 - 101) \frac{\text{N}}{\text{m}^2} \cdot \frac{\pi}{4} (2.6)^2 \text{ m}^2 \cdot \frac{\text{kg}}{\text{m}^3} \right] - 9.81 \frac{\text{m}}{\text{s}^2}$$

$$a_{ry} = 169 \text{ m/s}^2 \quad \leftarrow a_{ry}$$

## Problem 4.170

[Difficulty: 3]

**4.170** Neglecting air resistance, what speed would a vertically directed rocket attain in 5 s if it starts from rest, has initial mass of 350 kg, burns 10 kg/s, and ejects gas at atmospheric pressure with a speed of 2500 m/s relative to the rocket? What would be the maximum velocity? Plot the rocket speed as a function of time for the first minute of flight.



**Given:** Data on rocket

**Find:** Speed after 5 s; Maximum velocity; Plot of speed versus time

**Solution:**

Basic equation: Momentum flux in y direction

$$F_{S_y} + F_{B_y} - \int_{CV} a_{rfy} \rho dV = \frac{\partial}{\partial t} \int_{CV} v_{xyz} \rho dV + \int_{CS} v_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) No resistance 2)  $p_e = p_{atm}$  3) Uniform flow 4) Use relative velocities 5) Constant mass flow rate

From continuity  $\frac{dM}{dt} = m_{rate} = \text{constant}$  so  $M = M_0 - m_{rate} \cdot t$  (Note: Software cannot render a dot!)

Hence from momentum  $-M \cdot g - a_{rfy} \cdot M = u_e \cdot (\rho_e \cdot V_e \cdot A_e) = -V_e \cdot m_{rate}$  or  $a_{rfy} = \frac{dV}{dt} = \frac{V_e \cdot m_{rate}}{M} - g = \frac{V_e \cdot m_{rate}}{M_0 - m_{rate} \cdot t} - g$


Separating variables  $dV = \left( \frac{V_e \cdot m_{rate}}{M_0 - m_{rate} \cdot t} - g \right) \cdot dt$

Integrating from  $V = 0$  at  $t = 0$  to  $V = V$  at  $t = t$

$$V = -V_e \cdot \left( \ln(M_0 - m_{rate} \cdot t) - \ln(M_0) \right) - g \cdot t = -V_e \cdot \ln \left( 1 - \frac{m_{rate} \cdot t}{M_0} \right) - g \cdot t \quad V = -V_e \cdot \ln \left( 1 - \frac{m_{rate} \cdot t}{M_0} \right) - g \cdot t$$

At  $t = 5$  s  $V_{max} = -2500 \cdot \frac{m}{s} \cdot \ln \left( 1 - 10 \cdot \frac{kg}{s} \times \frac{1}{350 \cdot kg} \times 5 \cdot s \right) - 9.81 \cdot \frac{m}{s^2} \times 5 \cdot s \quad V_{max} = 336 \frac{m}{s}$

For the motion after 5 s, assuming the fuel is used up, the equation of motion becomes  $a = -M \cdot g$



## Problem 4.171

[Difficulty: 3]

**4.171** Inflate a toy balloon with air and release it. Watch as the balloon darts about the room. Explain what causes the phenomenon you see.

**Discussion:** Air blown into a balloon to inflate it must be compressed to overcome the skin's resistance to stretching. (Remember how hard it is to create enough pressure to "start" the inflation process!) After decreasing briefly, the required pressure seems to increase as inflation of the balloon continues.

As the balloon is inflated, the skin stretches and stores energy. When the inflated balloon is released, the stored energy in the skin forces the compressed air out the open mouth of the balloon. The expansion of the compressed air to the lower surrounding atmospheric pressure creates a high-speed jet of air, which propels the relatively light balloon initially at a high speed.

The moving balloon is unstable because it has a poor aerodynamic shape. Therefore it darts about in a random pattern. The balloon keeps moving as long as it contains pressurized air to act as a propulsion jet. However, it is not long before the energy stored in the skin is exhausted and the air in the balloon is reduced to atmospheric pressure.


When the balloon reaches atmospheric pressure it is slowed by aerodynamic drag. Finally the empty, wrinkled balloon simply falls to the floor.

Some toys that use a balloon for propulsion are available. Most have stabilizing surfaces. It is instructive to study these toys carefully to understand how each works, and why each toy is shaped the way it is.

## Problem 4.172

[Difficulty: 4]

**4.172** The vane/cart assembly of mass  $M = 30$  kg, shown in Problem 4.128, is driven by a water jet. The water leaves the stationary nozzle of area  $A = 0.02$  m<sup>2</sup>, with a speed of 20 m/s. The coefficient of kinetic friction between the assembly and the surface is 0.10. Plot the terminal speed of the assembly as a function of vane turning angle,  $\theta$ , for  $0 \leq \theta \leq \pi/2$ . At what angle does the assembly begin to move if the coefficient of static friction is 0.15?



**Given:** Water jet striking moving vane

**Find:** Plot of terminal speed versus turning angle; angle to overcome static friction

**Solution:**

Basic equations: Momentum flux in x and y directions

$$F_{S_x} + F_{B_x} - \int_{CV} a_{rf_x} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xyz} \rho dV + \int_{CS} u_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

$$F_{S_y} + F_{B_y} - \int_{CV} a_{rf_y} \rho dV = \frac{\partial}{\partial t} \int_{CV} v_{xyz} \rho dV + \int_{CS} v_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) Incompressible flow 2) Atmospheric pressure in jet 3) Uniform flow 4) Jet relative velocity is constant

Then 
$$-F_f - M \cdot a_{rfx} = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2) = -(V - U) \cdot [\rho \cdot (V - U) \cdot A] + (V - U) \cdot \cos(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$

$$a_{rfx} = \frac{\rho(V - U)^2 \cdot A \cdot (1 - \cos(\theta)) - F_f}{M} \quad (1)$$

Also 
$$R_y - M \cdot g = v_1 \cdot (-\rho \cdot V_1 \cdot A_1) + v_2 \cdot \rho \cdot V_2 \cdot A_2 = 0 + (V - U) \cdot \sin(\theta) \cdot [\rho \cdot (V - U) \cdot A]$$


$$R_y = M \cdot g + \rho(V - U)^2 \cdot A \cdot \sin(\theta)$$

At terminal speed  $a_{rfx} = 0$  and  $F_f = \mu_k R_y$ . Hence in Eq 1

$$0 = \frac{\rho \cdot (V - U_t)^2 \cdot A \cdot (1 - \cos(\theta)) - \mu_k \cdot [M \cdot g + \rho \cdot (V - U_t)^2 \cdot A \cdot \sin(\theta)]}{M} = \frac{\rho \cdot (V - U_t)^2 \cdot A \cdot (1 - \cos(\theta) - \mu_k \cdot \sin(\theta))}{M} - \mu_k \cdot g$$

or 
$$V - U_t = \sqrt{\frac{\mu_k \cdot M \cdot g}{\rho \cdot A \cdot (1 - \cos(\theta) - \mu_k \cdot \sin(\theta))}} \quad U_t = V - \sqrt{\frac{\mu_k \cdot M \cdot g}{\rho \cdot A \cdot (1 - \cos(\theta) - \mu_k \cdot \sin(\theta))}}$$

The terminal speed as a function of angle is plotted below; it can be generated in *Excel*



For the static case  $F_f = \mu_s \cdot R_y$  and  $a_{rfx} = 0$  (the cart is about to move, but hasn't)

Substituting in Eq 1, with  $U = 0$

$$0 = \frac{\rho \cdot V^2 \cdot A \cdot \left[ 1 - \cos(\theta) - \mu_s \cdot (\rho \cdot V^2 \cdot A \cdot \sin(\theta) + M \cdot g) \right]}{M}$$

or

$$\cos(\theta) + \mu_s \cdot \sin(\theta) = 1 - \frac{\mu_s \cdot M \cdot g}{\rho \cdot V^2 \cdot A}$$

We need to solve this for  $\theta$ ! This can be done by hand or by using Excel's Goal Seek or Solver  $\theta = 19.0 \cdot \text{deg}$


Note that we need  $\theta = 19^\circ$ , but once started we can throttle back to about  $\theta = 12.5^\circ$  and still keep moving!

### Problem 4.173

[Difficulty: 3]

4.173 Consider the vehicle shown in Problem 4.149. Starting from rest, it is propelled by a hydraulic catapult (liquid jet). The jet strikes the curved surface and makes a 180° turn, leaving horizontally. Air and rolling resistance may be

neglected. Using the notation shown, obtain an equation for the acceleration of the vehicle at any time and determine the time required for the vehicle to reach  $U = V/2$ .



Solution: Apply  $x$  component of momentum equation using linearly accelerating CV shown above.

$$\text{Basic equation: } F_{3x} + F_{4x} - \int_{CV} \text{arf}_x \rho dV = \frac{d}{dt} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} \vec{F}_{xy3} \cdot d\vec{A}$$

- Assumptions: (1)  $F_{3x} = 0$   
 (2)  $F_{4x} = 0$   
 (3) Neglect mass of liquid and rate of change of  $u$  in CV  
 (4) Uniform flow at each section  
 (5) Jet area and speed with respect to vehicle are constant

Then

$$-M \text{arf}_x = -M \frac{dU}{dt} = u_1 \{-\rho(V-U)A\} + u_2 \{\rho(V-U)A\}$$

$$u_1 = V-U \quad u_2 = -(V-U)$$

or

$$\text{arf}_x = \frac{dU}{dt} = \frac{2\rho(V-U)^2 A}{M} \quad ; \quad \frac{dU}{(V-U)^2} = \frac{2\rho A}{M} dt \quad ; \quad -\frac{d(V-U)}{(V-U)^2} = \frac{2\rho A}{M} dt$$

To obtain  $\text{arf}_x(t)$ , we must first find  $U(t)$ . Integrating from  $U=0$  at  $t=0$  to  $U$  at  $t$ ,

$$\int_{V-U=V}^{V-U} -\frac{d(V-U)}{(V-U)^2} = \left[ \frac{1}{V-U} \right]_V^{V-U} = \frac{1}{V-U} - \frac{1}{V} = \frac{V-(V-U)}{V(V-U)} = \frac{2\rho A}{M} t \quad ; \quad \frac{U}{V-U} = \frac{2\rho A}{M} t$$

Solving,

$$U = (V-U) \frac{2\rho A}{M} t, \quad U = V \frac{2\rho A}{M} t \quad \text{and} \quad V-U = V \left[ 1 - \frac{2\rho A}{M} t \right]$$

Substituting,

$$\text{arf}_x = \frac{2\rho V^2 A}{M} \left[ 1 - \frac{2\rho A}{M} t \right]^2 = \frac{2\rho V^2 A}{M} \left[ \frac{1}{1 + \frac{2\rho A}{M} t} \right]^2 \quad \text{arf}_x(t)$$

The time to reach  $U = V/2$  is


$$\frac{U}{V} = \frac{1}{2} = \frac{2\rho A}{M} t \quad \text{or} \quad t = \frac{M}{2\rho A} \quad t(V/2)$$

$$\text{Check: } \left[ \frac{M}{\rho V A} \right] = \frac{M}{\rho} \frac{L^3}{L^2 L} = t \checkmark \quad ; \quad \left[ \frac{\rho V^2 A}{M} \right] = \frac{M}{L^3} \frac{L^2}{t^2} \frac{L^2}{M} = \frac{L}{t^2} \checkmark$$

### Problem 4.174

[Difficulty: 3]

4.174 The moving tank shown is to be slowed by lowering a scoop to pick up water from a trough. The initial mass and speed of the tank and its contents are  $M_0$  and  $U_0$ , respectively. Neglect external forces due to pressure or friction and assume that the track is horizontal. Apply the continuity and momentum equations to show that at any instant  $U = U_0 M_0 / M$ . Obtain a general expression for  $U/U_0$  as a function of time.



Solution: Apply continuity and momentum equations to linearly accelerating CV shown.

Basic equations:  $0 = \frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{V}_{xy3} \cdot d\vec{A}$

$\stackrel{=0(1)}{F_{sx}} + \stackrel{=0(2)}{F_{bx}} - \int_{CV} a r_{fx} \rho dV = \frac{d}{dt} \int_{CV} \stackrel{=0(3)}{u_{xy3}} \rho dV + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$

- Assumptions: (1)  $F_{sx} = 0$   
 (2)  $F_{bx} = 0$   
 (3) Neglect  $u$  within CV  
 (4) Uniform flow across inlet section

From continuity

$$0 = \frac{d}{dt} M_{CV} + \{-\rho U A\} \quad \text{or} \quad \frac{dM}{dt} = \rho U A$$

From momentum

$$-a r_{fx} M = -\frac{dU}{dt} M = u \{-\rho U A\} = U \rho U A, \text{ since } u = -U$$

But from continuity,  $\rho U A = \frac{dM}{dt}$ , so

$$M \frac{dU}{dt} + U \frac{dM}{dt} = 0 \quad \text{or} \quad UM = \text{constant} = U_0 M_0; \quad U = U_0 M_0 / M$$

Substituting  $M = M_0 U_0 / U$  into momentum,  $-\frac{dU}{dt} \frac{M_0 U_0}{U} = \rho U^2 A$ , or

$$\frac{dU}{U^3} = -\frac{\rho A}{U_0 M_0} dt$$

$$\text{Integrating, } \int_{U_0}^U \frac{dU}{U^3} = -\frac{1}{2} \left[ \frac{1}{U^2} \right]_{U_0}^U = -\frac{1}{2} \left( \frac{1}{U^2} - \frac{1}{U_0^2} \right) = -\int_0^t \frac{\rho A}{U_0 M_0} dt = -\frac{\rho A}{U_0 M_0} t$$

Solving for  $U$ ,


$$U = \frac{U_0}{\left[ 1 + \frac{2\rho U_0 A}{M_0} t \right]^{1/2}}$$

### Problem 4.175

[Difficulty: 3]

4.175 The tank shown rolls with negligible resistance along a horizontal track. It is to be accelerated from rest by a liquid jet that strikes the vane and is deflected into the tank. The initial mass of the tank is  $M_0$ . Use the continuity and

momentum equations to show that at any instant the mass of the vehicle and liquid contents is  $M = M_0 V / (V - U)$ . Obtain a general expression for  $U/V$  as a function of time.



Find: (a) Apply continuity and momentum to show  $M = M_0 V / (V - U)$   
 (b) General expression for  $U/V$  as a function of time.

Solution: Apply continuity and  $x$  component of momentum equation to linearly accelerating CV shown.

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V}_{xy3} \cdot d\vec{A}$

$$F_{fx} + F_{bx} - \int_{CV} a r_{fx} \rho dV = \frac{\partial}{\partial t} \int_{CV} u_{xy3} \rho dV + \int_{CS} u_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$$

Assumptions: (1)  $F_{fx} = 0$   
 (2)  $F_{bx} = 0$   
 (3) Neglect  $u$  within CV  
 (4) Uniform flow in jet

From continuity

$$0 = \frac{\partial}{\partial t} M_{cv} + \{-\rho(V-U)A\} \quad \text{or} \quad \frac{dM}{dt} = \rho(V-U)A$$

From momentum

$$-a r_{fx} M = -\frac{dU}{dt} M = u \{-\rho(V-U)A\} = (V-U)[- \rho(V-U)A]; \quad u = V-U$$

But from continuity,  $\rho(V-U)A = \frac{dM}{dt}$ , and  $dU = -d(V-U)$ , so

$$-\frac{dU}{dt} M = \frac{d(V-U)}{dt} M = -(V-U) \frac{dM}{dt} \quad \text{or} \quad M(V-U) = \text{constant} = M_0 V$$

Thus  $M = M_0 V / (V - U)$  M

Substituting into momentum,  $-\frac{dU}{dt} M = \frac{d(V-U)}{dt} \frac{M_0 V}{(V-U)} = -\rho(V-U)^2 A$ , or

$$\frac{d(V-U)}{(V-U)^2} = -\frac{\rho A}{VM_0} dt$$

Integrating,  $\int_V^{V-U} \frac{d(V-U)}{(V-U)^2} = -\frac{1}{2} \left[ \frac{1}{(V-U)^2} - \frac{1}{V^2} \right] = -\int_0^t \frac{\rho A}{VM_0} dt = -\frac{\rho A}{VM_0} t$


Solving,

$$\frac{U}{V} = \left\{ 1 - \frac{1}{\left[ 1 + \frac{2\rho VA}{M_0} t \right]^{1/2}} \right\}$$
U/V

## Problem 4.176

[Difficulty: 4]

**4.176** A model solid propellant rocket has a mass of 69.6 g, of which 12.5 g is fuel. The rocket produces 5.75 N of thrust for a duration of 1.7 s. For these conditions, calculate the maximum speed and height attainable in the absence of air resistance. Plot the rocket speed and the distance traveled as functions of time.



**Given:** Data on rocket

**Find:** Maximum speed and height; Plot of speed and distance versus time

**Solution:**

Basic equation: Momentum flux in y direction 
$$F_{S_y} + F_{B_y} - \int_{CV} a_{rfy} \rho dV = \frac{\partial}{\partial t} \int_{CV} v_{xyz} \rho dV + \int_{CS} v_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) No resistance 2)  $p_e = p_{atm}$  3) Uniform flow 4) Use relative velocities 5) Constant mass flow rate

From continuity 
$$\frac{dM}{dt} = m_{rate} = \text{constant} \quad \text{so} \quad M = M_0 - m_{rate} \cdot t \quad (\text{Note: Software cannot render a dot!})$$

Hence from momentum 
$$-M \cdot g - a_{rfy} \cdot M = u_e \cdot (\rho_e \cdot V_e \cdot A_e) = -V_e \cdot m_{rate}$$

Hence 
$$a_{rfy} = \frac{dV}{dt} = \frac{V_e \cdot m_{rate}}{M} - g = \frac{V_e \cdot m_{rate}}{M_0 - m_{rate} \cdot t} - g$$

Separating variables 
$$dV = \left( \frac{V_e \cdot m_{rate}}{M_0 - m_{rate} \cdot t} - g \right) \cdot dt$$

Integrating from  $V = 0$  at  $t = 0$  to  $V = V$  at  $t = t$

$$V = -V_e \cdot \left( \ln(M_0 - m_{rate} \cdot t) - \ln(M_0) \right) - g \cdot t = -V_e \cdot \ln \left( 1 - \frac{m_{rate} \cdot t}{M_0} \right) - g \cdot t$$

$$V = -V_e \cdot \ln \left( 1 - \frac{m_{rate} \cdot t}{M_0} \right) - g \cdot t \quad \text{for} \quad t \leq t_b \quad (\text{burn time}) \quad (1)$$

To evaluate at  $t_b = 1.7$  s, we need  $V_e$  and  $m_{rate}$  
$$m_{rate} = \frac{m_f}{t_b} \quad m_{rate} = \frac{12.5 \cdot \text{gm}}{1.7 \cdot \text{s}} \quad m_{rate} = 7.35 \times 10^{-3} \frac{\text{kg}}{\text{s}}$$

Also note that the thrust  $F_t$  is due to momentum flux from the rocket 
$$F_t = m_{rate} \cdot V_e \quad V_e = \frac{F_t}{m_{rate}} \quad V_e = \frac{5.75 \cdot \text{N}}{7.35 \times 10^{-3} \cdot \frac{\text{kg}}{\text{s}}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} \quad V_e = 782 \frac{\text{m}}{\text{s}}$$

Hence 
$$V_{\max} = -V_e \cdot \ln \left( 1 - \frac{m_{rate} \cdot t_b}{M_0} \right) - g \cdot t_b$$

$$V_{\max} = -782 \cdot \frac{\text{m}}{\text{s}} \cdot \ln \left( 1 - 7.35 \times 10^{-3} \cdot \frac{\text{kg}}{\text{s}} \times \frac{1}{0.0696 \cdot \text{kg}} \times 1.7 \cdot \text{s} \right) - 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1.7 \cdot \text{s} \quad V_{\max} = 138 \frac{\text{m}}{\text{s}}$$

To obtain  $Y(t)$  we set  $V = dY/dt$  in Eq 1, and integrate to find

$$Y = \frac{V_e \cdot M_0}{m_{\text{rate}}} \cdot \left[ \left( 1 - \frac{m_{\text{rate}} \cdot t}{M_0} \right) \cdot \left( \ln \left( 1 - \frac{m_{\text{rate}} \cdot t}{M_0} \right) - 1 \right) + 1 \right] - \frac{1}{2} \cdot g \cdot t^2 \quad t \leq t_b \quad t_b = 1.7 \cdot s \quad (2)$$

At  $t = t_b$

$$Y_b = 782 \cdot \frac{\text{m}}{\text{s}} \times 0.0696 \cdot \text{kg} \times \frac{\text{s}}{7.35 \times 10^{-3} \cdot \text{kg}} \cdot \left[ \left( 1 - \frac{0.00735 \cdot 1.7}{0.0696} \right) \left( \ln \left( 1 - \frac{0.00735 \cdot 1.7}{0.0696} \right) - 1 \right) + 1 \right] \dots$$



$$+ -\frac{1}{2} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (1.7 \cdot \text{s})^2$$

$$Y_b = 113 \text{ m}$$

After burnout the rocket is in free assent. Ignoring drag  $V(t) = V_{\text{max}} - g \cdot (t - t_b)$  (3)

$$Y(t) = Y_b + V_{\text{max}} \cdot (t - t_b) - \frac{1}{2} \cdot g \cdot (t - t_b)^2 \quad t > t_b \quad (4)$$

The speed and position as functions of time are plotted below. These are obtained from Eqs 1 through 4, and can be plotted in *Excel*




Using Solver, or by differentiating  $y(t)$  and setting to zero, or by setting  $V(t) = 0$ , we find for the maximum  $y$

$$t = 15.8 \text{ s} \quad y_{\text{max}} = 1085 \text{ m}$$

## Problem 4.177

[Difficulty: 3]

**4.177** A small rocket motor is used to power a "jet pack" device to lift a single astronaut above the Moon's surface. The rocket motor produces a uniform exhaust jet with constant speed,  $V_e = 3000$  m/s, and the thrust is varied by changing the jet size. The total initial mass of the astronaut and the jet pack is  $M_0 = 200$  kg, 100 kg of which is fuel and oxygen for the rocket motor. Find (a) the exhaust mass flow rate required to just lift off initially, (b) the mass flow rate just as the fuel and oxygen are used up, and (c) the maximum anticipated time of flight. Note that the Moon's gravity is about 17 percent of Earth's.



**Given:** Data on "jet pack" rocket

**Find:** Initial exhaust mass flow rate; mass flow rate at end; maximum time of flight

**Solution:**

Basic equation: Momentum flux in y direction 
$$F_{S_y} + F_{B_y} - \int_{CV} a_{rf_y} \rho dV = \frac{\partial}{\partial t} \int_{CV} v_{xyz} \rho dV + \int_{CS} v_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) Jet pack just hovers 2) Steady flow 3) Uniform flow 4) Use relative velocities

Given data  $V_e = 3000 \frac{m}{s}$        $M_0 = 200 \text{ kg}$        $M_{\text{fuel}} = 100 \text{ kg}$        $g_{\text{moon}} = 0.17g$        $g_{\text{moon}} = 1.67 \frac{m}{s^2}$

At all instants, the momentum becomes  $-M \cdot g_{\text{moon}} = -v_1 \cdot m_{\text{rate}} = -V_e \cdot m_{\text{rate}}$  or  $m_{\text{rate}} = \frac{M \cdot g_{\text{moon}}}{V_e}$

Hence, initially  $m_{\text{rateinit}} = \frac{M_0 \cdot g_{\text{moon}}}{V_e}$        $m_{\text{rateinit}} = 0.111 \frac{kg}{s}$

Finally, when all the fuel is just used up, the mass is  $M_f = M_0 - M_{\text{fuel}}$        $M_f = 100 \text{ kg}$

Then  $m_{\text{ratefinal}} = \frac{M_f \cdot g_{\text{moon}}}{V_e}$        $m_{\text{ratefinal}} = 0.0556 \frac{kg}{s}$

Flight ends as fuel is used up. To find this, from continuity  $\frac{dM}{dt} = m_{\text{rate}}$  but  $m_{\text{rate}} = \frac{M \cdot g_{\text{moon}}}{V_e}$

Hence  $\frac{dM}{dt} = \frac{M \cdot g_{\text{moon}}}{V_e}$  so  $\frac{dM}{M} = \frac{g_{\text{moon}}}{V_e} \cdot dt$

Integrating  $\ln\left(\frac{M_0}{M}\right) = \frac{g_{\text{moon}}}{V_e} \cdot t$  or  $M = M_0 \cdot e^{-\frac{g_{\text{moon}}}{V_e} \cdot t}$

Solving for t  $t = -\frac{V_e}{g_{\text{moon}}} \cdot \ln\left(\frac{M}{M_0}\right)$  so when  $M = M_f$        $t_{\text{final}} = -\frac{V_e}{g_{\text{moon}}} \cdot \ln\left(\frac{M_f}{M_0}\right)$        $t_{\text{final}} = 20.8 \text{ min}$

## Problem 4.178

[Difficulty: 5] Part 1/3

**4.178** Several toy manufacturers sell water “rockets” that consist of plastic tanks to be partially filled with water and then pressurized with air. Upon release, the compressed air forces water out of the nozzle rapidly, propelling the rocket. You are asked to help specify optimum conditions for this water-jet propulsion system. To simplify the analysis, consider horizontal motion only. Perform the analysis and

design needed to define the acceleration performance of the compressed air/water-propelled rocket. Identify the fraction of tank volume that initially should be filled with compressed air to achieve optimum performance (i.e., maximum speed from the water charge). Describe the effect of varying the initial air pressure in the tank.

**Discussion:** The process may be modeled as a polytropic expansion of the trapped air which forces water out the jet nozzle, causing the “rocket” to accelerate. The polytropic exponent may be varied to model anything from an isothermal expansion process ( $n = 1$ ) to an adiabatic expansion process ( $n = k$ ), which is more likely to be an accurate model for the sudden expansion of the air.

Speed of the water jet leaving the “rocket” is proportional to the square root of the pressure difference between the tank and atmosphere.

Qualitatively it is apparent that the smaller the initial volume fraction of trapped air, the larger will be the expansion ratio of the air, and the more rapid will be the pressure reduction as the air expands. This will cause the water jet speed to drop rapidly. The combination of low water jet speed and relatively large mass of water will produce sluggish acceleration.


Increasing the initial volume fraction of air will reduce the expansion ratio, so higher pressure will be maintained longer in the tank and the water jet will maintain higher speed longer. This combined with the relatively small mass of water in the tank will produce rapid acceleration.

If the initial volume fraction of air is too large, all water will be expended before the air pressure is reduced significantly. In this situation, some of the stored energy of the air will be dissipated in a relatively ineffective air jet. Consequently, for any initial pressure in the tank, there is an optimum initial air fraction.

This problem cannot be solved in closed form because of the varying air pressure, mass flow rate, and mass of water in the tank; it can only be solved numerically. One possible integration scheme is to increment time and solve for all properties of the system at each instant. The drawback to this scheme is that the water is unlikely to be exhausted at an even increment of time. A second scheme is to increment the volume of water remaining and solve for properties using the average flow rate during the interval. This scheme is outlined below.

*Model the air/water jet-propelled “rocket” using the CV and coordinates shown.*

*First choose dimensions and mass of “rocket” to be simulated:*



### Input Data:

Jet diameter:	$D_j =$	0.003	m
Tank diameter:	$D_t =$	0.035	m
Tank length:	$L =$	0.1	m
Tank mass:	$M_t =$	0.01	kg
Polytropic exponent:	$n =$	1.4	---

*Next choose initial conditions for the simulation (see sample calculations below):*

# Problem 4.178

[Difficulty: 5] Part 2/3

### Initial Conditions:

Air fraction in tank:	$\alpha =$	0.5	---
Tank pressure:	$p_0 =$	200	kPa (gage)
Volume increment:	$\Delta\alpha =$	0.02	---

Compute reference parameters:

### Calculated Parameters:

Jet area:	$A_j =$	7.07E-06	m <sup>2</sup>
Tank volume:	$V_t =$	9.62E-05	m <sup>3</sup>
Initial air volume:	$V_0 =$	4.81E-05	m <sup>3</sup>
Initial water mass:	$M_0 =$	0.0481	kg

(These are used in the spreadsheet below.)

Then decrease the water fraction in the tank by  $\Delta\alpha$ :

### Calculated Results:

Water Fraction, $V_w/V_t$ (---)	Gage Pressure, $p$ (kPa)	Water Mass, $M_w$ (kg)	Jet Speed, $V_j$ (m/s)	Flow Rate, $dm/dt$ (kg/s)	Time Interval, $\Delta t$ (s)	Current Time, $t$ (s)	"Rocket" Accel., $a$ (m/s <sup>2</sup> )	"Rocket" Speed, $U$ (m/s)
0.50	200	0.0481	20.0	0.141	0	0	48.7	0
0.48	184	0.0461	19.2	0.135	0.0139	0.0139	47.5	0.668

The computation is made as follows:

(1) Decrease  $\alpha$  by  $\Delta\alpha$

(2) Compute  $p$  from  $p = p_0 \left(\frac{V_0}{V}\right)^{\gamma}$

$$p = (200 + 101.325) \text{ kPa} \left(\frac{0.50}{0.52}\right)^{1.4} - 101.325 = 183.9 \text{ kPa (gage)}$$

(3) Use Bernoulli to calculate jet speed

$$V_j = \sqrt{\frac{2\Delta p}{\rho}} = \left[ 2 \times 183.9 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]^{1/2} = 19.10 \text{ m/s}^*$$

(4) Calculate water mass using  $\alpha$ .

(5) Use conservation of mass to compute mass flow rate

$$\dot{m} = \rho V_j A_j = 999 \frac{\text{kg}}{\text{m}^3} \times 19.10 \frac{\text{m}}{\text{s}} \times 7.07 \times 10^{-6} \text{ m}^2 = 0.1349 \text{ kg/s}$$

(6) Use the average mass flow rate during the interval to approximate  $\Delta t$ :

$$\Delta t = \frac{\Delta m}{dm/dt} = \frac{\Delta m}{\dot{m}} = (0.0481 - 0.0461) \text{ kg} \times \frac{\text{s}}{0.138 \text{ kg}} = 0.01449 \text{ s}^*$$

(7) Use momentum to compute acceleration (note  $M = M_w + M_b$ ):

$$a_{\text{avg}} = \frac{\dot{m} V_j}{M} = 0.135 \frac{\text{kg}}{\text{s}} \times 19.2 \frac{\text{m}}{\text{s}} \times \frac{1}{0.0461 + 0.0100 \text{ kg}} = 46.2 \text{ m/s}^2^*$$

(8) Finally, use average acceleration to get speed


$$U = U_0 + \bar{a} \Delta t = 0 + 48.1 \frac{\text{m}}{\text{s}^2} \times 0.0139 \text{ s} = 0.669 \text{ m/s}^*$$

\* Note effect of roundoff error.

42-3841 100% RECYCLED PAPER  
 42-3842 100% RECYCLED PAPER  
 42-3843 100% RECYCLED PAPER  
 42-3844 100% RECYCLED PAPER  
 42-3845 100% RECYCLED PAPER  
 42-3846 100% RECYCLED PAPER  
 42-3847 100% RECYCLED PAPER  
 42-3848 100% RECYCLED PAPER  
 42-3849 100% RECYCLED PAPER  
 42-3850 100% RECYCLED PAPER  
 42-3851 100% RECYCLED PAPER  
 42-3852 100% RECYCLED PAPER  
 42-3853 100% RECYCLED PAPER  
 42-3854 100% RECYCLED PAPER  
 42-3855 100% RECYCLED PAPER  
 42-3856 100% RECYCLED PAPER  
 42-3857 100% RECYCLED PAPER  
 42-3858 100% RECYCLED PAPER  
 42-3859 100% RECYCLED PAPER  
 42-3860 100% RECYCLED PAPER  
 42-3861 100% RECYCLED PAPER  
 42-3862 100% RECYCLED PAPER  
 42-3863 100% RECYCLED PAPER  
 42-3864 100% RECYCLED PAPER  
 42-3865 100% RECYCLED PAPER  
 42-3866 100% RECYCLED PAPER  
 42-3867 100% RECYCLED PAPER  
 42-3868 100% RECYCLED PAPER  
 42-3869 100% RECYCLED PAPER  
 42-3870 100% RECYCLED PAPER  
 42-3871 100% RECYCLED PAPER  
 42-3872 100% RECYCLED PAPER  
 42-3873 100% RECYCLED PAPER  
 42-3874 100% RECYCLED PAPER  
 42-3875 100% RECYCLED PAPER  
 42-3876 100% RECYCLED PAPER  
 42-3877 100% RECYCLED PAPER  
 42-3878 100% RECYCLED PAPER  
 42-3879 100% RECYCLED PAPER  
 42-3880 100% RECYCLED PAPER  
 42-3881 100% RECYCLED PAPER  
 42-3882 100% RECYCLED PAPER  
 42-3883 100% RECYCLED PAPER  
 42-3884 100% RECYCLED PAPER  
 42-3885 100% RECYCLED PAPER  
 42-3886 100% RECYCLED PAPER  
 42-3887 100% RECYCLED PAPER  
 42-3888 100% RECYCLED PAPER  
 42-3889 100% RECYCLED PAPER  
 42-3890 100% RECYCLED PAPER  
 42-3891 100% RECYCLED PAPER  
 42-3892 100% RECYCLED PAPER  
 42-3893 100% RECYCLED PAPER  
 42-3894 100% RECYCLED PAPER  
 42-3895 100% RECYCLED PAPER  
 42-3896 100% RECYCLED PAPER  
 42-3897 100% RECYCLED PAPER  
 42-3898 100% RECYCLED PAPER  
 42-3899 100% RECYCLED PAPER  
 42-3900 100% RECYCLED PAPER  
 42-3901 100% RECYCLED PAPER  
 42-3902 100% RECYCLED PAPER  
 42-3903 100% RECYCLED PAPER  
 42-3904 100% RECYCLED PAPER  
 42-3905 100% RECYCLED PAPER  
 42-3906 100% RECYCLED PAPER  
 42-3907 100% RECYCLED PAPER  
 42-3908 100% RECYCLED PAPER  
 42-3909 100% RECYCLED PAPER  
 42-3910 100% RECYCLED PAPER  
 42-3911 100% RECYCLED PAPER  
 42-3912 100% RECYCLED PAPER  
 42-3913 100% RECYCLED PAPER  
 42-3914 100% RECYCLED PAPER  
 42-3915 100% RECYCLED PAPER  
 42-3916 100% RECYCLED PAPER  
 42-3917 100% RECYCLED PAPER  
 42-3918 100% RECYCLED PAPER  
 42-3919 100% RECYCLED PAPER  
 42-3920 100% RECYCLED PAPER  
 42-3921 100% RECYCLED PAPER  
 42-3922 100% RECYCLED PAPER  
 42-3923 100% RECYCLED PAPER  
 42-3924 100% RECYCLED PAPER  
 42-3925 100% RECYCLED PAPER  
 42-3926 100% RECYCLED PAPER  
 42-3927 100% RECYCLED PAPER  
 42-3928 100% RECYCLED PAPER  
 42-3929 100% RECYCLED PAPER  
 42-3930 100% RECYCLED PAPER  
 42-3931 100% RECYCLED PAPER  
 42-3932 100% RECYCLED PAPER  
 42-3933 100% RECYCLED PAPER  
 42-3934 100% RECYCLED PAPER  
 42-3935 100% RECYCLED PAPER  
 42-3936 100% RECYCLED PAPER  
 42-3937 100% RECYCLED PAPER  
 42-3938 100% RECYCLED PAPER  
 42-3939 100% RECYCLED PAPER  
 42-3940 100% RECYCLED PAPER  
 42-3941 100% RECYCLED PAPER  
 42-3942 100% RECYCLED PAPER  
 42-3943 100% RECYCLED PAPER  
 42-3944 100% RECYCLED PAPER  
 42-3945 100% RECYCLED PAPER  
 42-3946 100% RECYCLED PAPER  
 42-3947 100% RECYCLED PAPER  
 42-3948 100% RECYCLED PAPER  
 42-3949 100% RECYCLED PAPER  
 42-3950 100% RECYCLED PAPER  
 42-3951 100% RECYCLED PAPER  
 42-3952 100% RECYCLED PAPER  
 42-3953 100% RECYCLED PAPER  
 42-3954 100% RECYCLED PAPER  
 42-3955 100% RECYCLED PAPER  
 42-3956 100% RECYCLED PAPER  
 42-3957 100% RECYCLED PAPER  
 42-3958 100% RECYCLED PAPER  
 42-3959 100% RECYCLED PAPER  
 42-3960 100% RECYCLED PAPER  
 42-3961 100% RECYCLED PAPER  
 42-3962 100% RECYCLED PAPER  
 42-3963 100% RECYCLED PAPER  
 42-3964 100% RECYCLED PAPER  
 42-3965 100% RECYCLED PAPER  
 42-3966 100% RECYCLED PAPER  
 42-3967 100% RECYCLED PAPER  
 42-3968 100% RECYCLED PAPER  
 42-3969 100% RECYCLED PAPER  
 42-3970 100% RECYCLED PAPER  
 42-3971 100% RECYCLED PAPER  
 42-3972 100% RECYCLED PAPER  
 42-3973 100% RECYCLED PAPER  
 42-3974 100% RECYCLED PAPER  
 42-3975 100% RECYCLED PAPER  
 42-3976 100% RECYCLED PAPER  
 42-3977 100% RECYCLED PAPER  
 42-3978 100% RECYCLED PAPER  
 42-3979 100% RECYCLED PAPER  
 42-3980 100% RECYCLED PAPER  
 42-3981 100% RECYCLED PAPER  
 42-3982 100% RECYCLED PAPER  
 42-3983 100% RECYCLED PAPER  
 42-3984 100% RECYCLED PAPER  
 42-3985 100% RECYCLED PAPER  
 42-3986 100% RECYCLED PAPER  
 42-3987 100% RECYCLED PAPER  
 42-3988 100% RECYCLED PAPER  
 42-3989 100% RECYCLED PAPER  
 42-3990 100% RECYCLED PAPER  
 42-3991 100% RECYCLED PAPER  
 42-3992 100% RECYCLED PAPER  
 42-3993 100% RECYCLED PAPER  
 42-3994 100% RECYCLED PAPER  
 42-3995 100% RECYCLED PAPER  
 42-3996 100% RECYCLED PAPER  
 42-3997 100% RECYCLED PAPER  
 42-3998 100% RECYCLED PAPER  
 42-3999 100% RECYCLED PAPER  
 42-4000 100% RECYCLED PAPER  
 42-4001 100% RECYCLED PAPER  
 42-4002 100% RECYCLED PAPER  
 42-4003 100% RECYCLED PAPER  
 42-4004 100% RECYCLED PAPER  
 42-4005 100% RECYCLED PAPER  
 42-4006 100% RECYCLED PAPER  
 42-4007 100% RECYCLED PAPER  
 42-4008 100% RECYCLED PAPER  
 42-4009 100% RECYCLED PAPER  
 42-4010 100% RECYCLED PAPER  
 42-4011 100% RECYCLED PAPER  
 42-4012 100% RECYCLED PAPER  
 42-4013 100% RECYCLED PAPER  
 42-4014 100% RECYCLED PAPER  
 42-4015 100% RECYCLED PAPER  
 42-4016 100% RECYCLED PAPER  
 42-4017 100% RECYCLED PAPER  
 42-4018 100% RECYCLED PAPER  
 42-4019 100% RECYCLED PAPER  
 42-4020 100% RECYCLED PAPER  
 42-4021 100% RECYCLED PAPER  
 42-4022 100% RECYCLED PAPER  
 42-4023 100% RECYCLED PAPER  
 42-4024 100% RECYCLED PAPER  
 42-4025 100% RECYCLED PAPER  
 42-4026 100% RECYCLED PAPER  
 42-4027 100% RECYCLED PAPER  
 42-4028 100% RECYCLED PAPER  
 42-4029 100% RECYCLED PAPER  
 42-4030 100% RECYCLED PAPER  
 42-4031 100% RECYCLED PAPER  
 42-4032 100% RECYCLED PAPER  
 42-4033 100% RECYCLED PAPER  
 42-4034 100% RECYCLED PAPER  
 42-4035 100% RECYCLED PAPER  
 42-4036 100% RECYCLED PAPER  
 42-4037 100% RECYCLED PAPER  
 42-4038 100% RECYCLED PAPER  
 42-4039 100% RECYCLED PAPER  
 42-4040 100% RECYCLED PAPER  
 42-4041 100% RECYCLED PAPER  
 42-4042 100% RECYCLED PAPER  
 42-4043 100% RECYCLED PAPER  
 42-4044 100% RECYCLED PAPER  
 42-4045 100% RECYCLED PAPER  
 42-4046 100% RECYCLED PAPER  
 42-4047 100% RECYCLED PAPER  
 42-4048 100% RECYCLED PAPER  
 42-4049 100% RECYCLED PAPER  
 42-4050 100% RECYCLED PAPER  
 42-4051 100% RECYCLED PAPER  
 42-4052 100% RECYCLED PAPER  
 42-4053 100% RECYCLED PAPER  
 42-4054 100% RECYCLED PAPER  
 42-4055 100% RECYCLED PAPER  
 42-4056 100% RECYCLED PAPER  
 42-4057 100% RECYCLED PAPER  
 42-4058 100% RECYCLED PAPER  
 42-4059 100% RECYCLED PAPER  
 42-4060 100% RECYCLED PAPER  
 42-4061 100% RECYCLED PAPER  
 42-4062 100% RECYCLED PAPER  
 42-4063 100% RECYCLED PAPER  
 42-4064 100% RECYCLED PAPER  
 42-4065 100% RECYCLED PAPER  
 42-4066 100% RECYCLED PAPER  
 42-4067 100% RECYCLED PAPER  
 42-4068 100% RECYCLED PAPER  
 42-4069 100% RECYCLED PAPER  
 42-4070 100% RECYCLED PAPER  
 42-4071 100% RECYCLED PAPER  
 42-4072 100% RECYCLED PAPER  
 42-4073 100% RECYCLED PAPER  
 42-4074 100% RECYCLED PAPER  
 42-4075 100% RECYCLED PAPER  
 42-4076 100% RECYCLED PAPER  
 42-4077 100% RECYCLED PAPER  
 42-4078 100% RECYCLED PAPER  
 42-4079 100% RECYCLED PAPER  
 42-4080 100% RECYCLED PAPER  
 42-4081 100% RECYCLED PAPER  
 42-4082 100% RECYCLED PAPER  
 42-4083 100% RECYCLED PAPER  
 42-4084 100% RECYCLED PAPER  
 42-4085 100% RECYCLED PAPER  
 42-4086 100% RECYCLED PAPER  
 42-4087 100% RECYCLED PAPER  
 42-4088 100% RECYCLED PAPER  
 42-4089 100% RECYCLED PAPER  
 42-4090 100% RECYCLED PAPER  
 42-4091 100% RECYCLED PAPER  
 42-4092 100% RECYCLED PAPER  
 42-4093 100% RECYCLED PAPER  
 42-4094 100% RECYCLED PAPER  
 42-4095 100% RECYCLED PAPER  
 42-4096 100% RECYCLED PAPER  
 42-4097 100% RECYCLED PAPER  
 42-4098 100% RECYCLED PAPER  
 42-4099 100% RECYCLED PAPER  
 42-4100 100% RECYCLED PAPER  
 42-4101 100% RECYCLED PAPER  
 42-4102 100% RECYCLED PAPER  
 42-4103 100% RECYCLED PAPER  
 42-4104 100% RECYCLED PAPER  
 42-4105 100% RECYCLED PAPER  
 42-4106 100% RECYCLED PAPER  
 42-4107 100% RECYCLED PAPER  
 42-4108 100% RECYCLED PAPER  
 42-4109 100% RECYCLED PAPER  
 42-4110 100% RECYCLED PAPER  
 42-4111 100% RECYCLED PAPER  
 42-4112 100% RECYCLED PAPER  
 42-4113 100% RECYCLED PAPER  
 42-4114 100% RECYCLED PAPER  
 42-4115 100% RECYCLED PAPER  
 42-4116 100% RECYCLED PAPER  
 42-4117 100% RECYCLED PAPER  
 42-4118 100% RECYCLED PAPER  
 42-4119 100% RECYCLED PAPER  
 42-4120 100% RECYCLED PAPER  
 42-4121 100% RECYCLED PAPER  
 42-4122 100% RECYCLED PAPER  
 42-4123 100% RECYCLED PAPER  
 42-4124 100% RECYCLED PAPER  
 42-4125 100% RECYCLED PAPER  
 42-4126 100% RECYCLED PAPER  
 42-4127 100% RECYCLED PAPER  
 42-4128 100% RECYCLED PAPER  
 42-4129 100% RECYCLED PAPER  
 42-4130 100% RECYCLED PAPER  
 42-4131 100% RECYCLED PAPER  
 42-4132 100% RECYCLED PAPER  
 42-4133 100% RECYCLED PAPER  
 42-4134 100% RECYCLED PAPER  
 42-4135 100% RECYCLED PAPER  
 42-4136 100% RECYCLED PAPER  
 42-4137 100% RECYCLED PAPER  
 42-4138 100% RECYCLED PAPER  
 42-4139 100% RECYCLED PAPER  
 42-4140 100% RECYCLED PAPER  
 42-4141 100% RECYCLED PAPER  
 42-4142 100% RECYCLED PAPER  
 42-4143 100% RECYCLED PAPER  
 42-4144 100% RECYCLED PAPER  
 42-4145 100% RECYCLED PAPER  
 42-4146 100% RECYCLED PAPER  
 42-4147 100% RECYCLED PAPER  
 42-4148 100% RECYCLED PAPER  
 42-4149 100% RECYCLED PAPER  
 42-4150 100% RECYCLED PAPER  
 42-4151 100% RECYCLED PAPER  
 42-4152 100% RECYCLED PAPER  
 42-4153 100% RECYCLED PAPER  
 42-4154 100% RECYCLED PAPER  
 42-4155 100% RECYCLED PAPER  
 42-4156 100% RECYCLED PAPER  
 42-4157 100% RECYCLED PAPER  
 42-4158 100% RECYCLED PAPER  
 42-4159 100% RECYCLED PAPER  
 42-4160 100% RECYCLED PAPER  
 42-4161 100% RECYCLED PAPER  
 42-4162 100% RECYCLED PAPER  
 42-4163 100% RECYCLED PAPER  
 42-4164 100% RECYCLED PAPER  
 42-4165 100% RECYCLED PAPER  
 42-4166 100% RECYCLED PAPER  
 42-4167 100% RECYCLED PAPER  
 42-4168 100% RECYCLED PAPER  
 42-4169 100% RECYCLED PAPER  
 42-4170 100% RECYCLED PAPER  
 42-4171 100% RECYCLED PAPER  
 42-4172 100% RECYCLED PAPER  
 42-4173 100% RECYCLED PAPER  
 42-4174 100% RECYCLED PAPER  
 42-4175 100% RECYCLED PAPER  
 42-4176 100% RECYCLED PAPER  
 42-4177 100% RECYCLED PAPER  
 42-4178 100% RECYCLED PAPER  
 42-4179 100% RECYCLED PAPER  
 42-4180 100% RECYCLED PAPER  
 42-4181 100% RECYCLED PAPER  
 42-4182 100% RECYCLED PAPER  
 42-4183 100% RECYCLED PAPER  
 42-4184 100% RECYCLED PAPER  
 42-4185 100% RECYCLED PAPER  
 42-4186 100% RECYCLED PAPER  
 42-4187 100% RECYCLED PAPER  
 42-4188 100% RECYCLED PAPER  
 42-4189 100% RECYCLED PAPER  
 42-4190 100% RECYCLED PAPER  
 42-4191 100% RECYCLED PAPER  
 42-4192 100% RECYCLED PAPER  
 42-4193 100% RECYCLED PAPER  
 42-4194 100% RECYCLED PAPER  
 42-4195 100% RECYCLED PAPER  
 42-4196 100% RECYCLED PAPER  
 42-4197 100% RECYCLED PAPER  
 42-4198 100% RECYCLED PAPER  
 42-4199 100% RECYCLED PAPER  
 42-4200 100% RECYCLED PAPER  
 42-4201 100% RECYCLED PAPER  
 42-4202 100% RECYCLED PAPER  
 42-4203 100% RECYCLED PAPER  
 42-4204 100% RECYCLED PAPER  
 42-4205 100% RECYCLED PAPER  
 42-4206 100% RECYCLED PAPER  
 42-4207 100% RECYCLED PAPER  
 42-4208 100% RECYCLED PAPER  
 42-4209 100% RECYCLED PAPER  
 42-4210 100% RECYCLED PAPER  
 42-4211 100% RECYCLED PAPER  
 42-4212 100% RECYCLED PAPER  
 42-4213 100% RECYCLED PAPER  
 42-4214 100% RECYCLED PAPER  
 42-4215 100% RECYCLED PAPER  
 42-4216 100% RECYCLED PAPER  
 42-4217 100% RECYCLED PAPER  
 42-4218 100% RECYCLED PAPER  
 42-4219 100% RECYCLED PAPER  
 42-4220 100% RECYCLED PAPER  
 42-4221 100% RECYCLED PAPER  
 42-4222 100% RECYCLED PAPER  
 42-4223 100% RECYCLED PAPER  
 42-4224 100% RECYCLED PAPER  
 42-4225 100% RECYCLED PAPER  
 42-4226 100% RECYCLED PAPER  
 42-4227 100% RECYCLED PAPER  
 42-4228 100% RECYCLED PAPER  
 42-4229 100% RECYCLED PAPER  
 42-4230 100% RECYCLED PAPER  
 42-4231 100% RECYCLED PAPER  
 42-4232 100% RECYCLED PAPER  
 42-4233 100% RECYCLED PAPER  
 42-4234 100% RECYCLED PAPER  
 42-4235 100% RECYCLED PAPER  
 42-4236 100% RECYCLED PAPER  
 42-4237 100% RECYCLED PAPER  
 42-4238 100% RECYCLED PAPER  
 42-4239 100% RECYCLED PAPER  
 42-4240 100% RECYCLED PAPER  
 42-4241 100% RECYCLED PAPER  
 42-4242 100% RECYCLED PAPER  
 42-4243 100% RECYCLED PAPER  
 42-4244 100% RECYCLED PAPER  
 42-4245 100% RECYCLED PAPER  
 42-4246 100% RECYCLED PAPER  
 42-4247 100% RECYCLED PAPER  
 42-4248 100% RECYCLED PAPER  
 42-4249 100% RECYCLED PAPER  
 42-4250 100% RECYCLED PAPER  
 42-4251 100% RECYCLED PAPER  
 42-4252 100% RECYCLED PAPER  
 42-4253 100% RECYCLED PAPER  
 42-4254 100% RECYCLED PAPER  
 42-4255 100% RECYCLED PAPER  
 42-4256 100% RECYCLED PAPER  
 42-4257 100% RECYCLED PAPER  
 42-4258 100% RECYCLED PAPER  
 42-4259 100% RECYCLED PAPER  
 42-4260 100% RECYCLED PAPER  
 42-4261 100% RECYCLED PAPER  
 42-4262 100% RECYCLED PAPER  
 42-4263 100% RECYCLED PAPER  
 42-4264 100% RECYCLED PAPER  
 42-4265 100% RECYCLED PAPER  
 42-4266 100% RECYCLED PAPER  
 42-4267 100% RECYCLED PAPER



4.179 A disk, of mass  $M$ , is constrained horizontally but is free to move vertically. A jet of water strikes the disk from below. The jet leaves the nozzle at initial speed  $V_0$ . Obtain a differential equation for the disk height,  $h(t)$ , above the jet exit plane if the disk is released from large height,  $H$ . (You will not be able to solve this ODE, as it is highly nonlinear!) Assume that when the disk reaches equilibrium, its height above the jet exit plane is  $h_0$ .



- (a) Sketch  $h(t)$  for the disk released at  $t = 0$  from  $H > h_0$ .  
 (b) Explain why the sketch is as you show it.

Solution: Apply Bernoulli equation to jet, then y momentum equation to CV with linear acceleration.

Basic equations:

$$\frac{p_1}{\rho} + \frac{V_0^2}{2} + g z_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g z_2$$

$$F_{py} + F_{ey} - \int_{CV} a_{ry} \rho dV = \frac{d}{dt} \int_{CV} u_{ry} \rho dV + \int_{CS} u_{ry} \rho \vec{V}_{r2} \cdot d\vec{A}$$

- Assumptions: (1) Steady flow  
 (2) Incompressible flow  
 (3) No friction  
 (4) Flow along a streamline  
 (5)  $p_1 = p_2 = p_{atm}$

- (6) No pressure force on CV, so  $F_{py} = 0$   
 (7) Neglect mass of liquid in CV and  $V \approx 0$  in CV  
 (8) Uniform flow at each section  
 (9) Measure velocities relative to CV

From momentum

$$-(M + \dot{m}_{ur})g - a_{ry}(M + \dot{m}_{ur}) = v_1 \{-\rho(V_1 - U)A_1\} + v_2 \{\dot{m}_2\}$$

$$v_1 = V_1 - U \quad v_2 \approx 0$$

With  $a_{ry} = \frac{d^2h}{dt^2}$ ,  $U = \frac{dh}{dt}$ , then

$$-Mg - M \frac{d^2h}{dt^2} = -\rho(V_1 - \frac{dh}{dt})^2 A_1$$

But from Bernoulli,  $\frac{V_1^2}{2} = \frac{V_0^2}{2} - g z_1$ , so  $V_1 = \sqrt{V_0^2 - 2gh}$ , since  $z_1 = h(t)$

Also from continuity,  $V_1 A_1 = V_0 A_0$ , so  $A_1 = A_0 V_0 / V_1$ . Substituting

$$\frac{d^2h}{dt^2} = \rho (\sqrt{V_0^2 - 2gh} - \frac{dh}{dt})^2 \frac{A_0 V_0}{M \sqrt{V_0^2 - 2gh}} - g$$

At equilibrium height,  $h = h_0$ ,  $\frac{dh}{dt} = 0$ , and  $\frac{d^2h}{dt^2} = 0$ . Then


$$\rho \sqrt{V_0^2 - 2gh_0} A_0 V_0 - Mg = 0$$

$$\text{Thus } V_0^2 - 2gh_0 = \left(\frac{Mg}{\rho V_0 A_0}\right)^2$$

This may be solved to obtain

$$h_0 = \frac{V_0^2}{2g} \left[ 1 - \left( \frac{Mg}{\rho V_0^2 A_0} \right)^2 \right] = \frac{V_0^2}{2g} \left[ 1 - \left( \frac{Mg}{mV_0} \right)^2 \right]$$

When released,  $H > h_0$ , and  $dh/dt = 0$ . Because the equation for  $d^2h/dt^2$  is nonlinear, oscillations will occur. The expected behavior is sketched below:




- Notes: (1) Expect oscillations  
 (2)  $\Delta h_3 < \Delta h_2 < \Delta h_1$ , due to nonlinear equation

## Problem 4.180

[Difficulty: 5]

**4.180** Consider the configuration of the vertical jet impinging on a horizontal disk shown in Problem 4.158. Assume the disk is released from rest at an initial height of 2 m above the jet exit plane. Using a numerical method such as the Euler method (see Section 5.5), solve for the subsequent motion of this disk. Identify the steady-state height of the disk.



**Given:** Water jet striking moving disk

**Find:** Motion of disk; steady state height

**Solution:**

Basic equations: Bernoulli; Momentum flux in z direction (treated as upwards) for linear accelerating CV

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad F_{S_z} + F_{B_z} - \int_{CV} a_{rfz} \rho d\Psi = \frac{\partial}{\partial t} \int_{CV} w_{xyz} \rho d\Psi + \int_{CS} w_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Atmospheric pressure 4) Uniform flow 5) velocities wrt CV (All in jet)

The Bernoulli equation becomes  $\frac{V_0^2}{2} + g \cdot 0 = \frac{V_1^2}{2} + g \cdot h$   $V_1 = \sqrt{V_0^2 - 2 \cdot g \cdot h}$  (1)

$$V_1 = \sqrt{\left(15 \cdot \frac{\text{m}}{\text{s}}\right)^2 + 2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \cdot (0 - 3) \cdot \text{m}} \quad V_1 = 12.9 \frac{\text{m}}{\text{s}}$$

The momentum equation becomes  $-M \cdot g - M \cdot a_{rfz} = w_1 \cdot (-\rho \cdot V_1 \cdot A_1) + w_2 \cdot (\rho \cdot V_2 \cdot A_2) = (V_1 - U) \cdot [-\rho \cdot (V_1 - U) \cdot A_1] + 0$

With  $a_{rfz} = \frac{d^2h}{dt^2}$  and  $U = \frac{dh}{dt}$  we get  $-M \cdot g - M \cdot \frac{d^2h}{dt^2} = -\rho \cdot \left(V_1 - \frac{dh}{dt}\right)^2 \cdot A_1$

Using Eq 1, and from continuity  $V_1 \cdot A_1 = V_0 \cdot A_0$   $\frac{d^2h}{dt^2} = \left(\sqrt{V_0^2 - 2 \cdot g \cdot h} - \frac{dh}{dt}\right)^2 \cdot \frac{\rho \cdot A_0 \cdot V_0}{M \cdot \sqrt{V_0^2 - 2 \cdot g \cdot h}} - g$  (2)

This must be solved numerically! One approach is to use Euler's method (see the *Excel* solution)

At equilibrium  $h = h_0$   $\frac{dh}{dt} = 0$   $\frac{d^2h}{dt^2} = 0$  so


$$\sqrt{(V_0^2 - 2 \cdot g \cdot h_0)} \cdot \rho \cdot A_0 \cdot V_0 - M \cdot g = 0 \quad \text{and} \quad h_0 = \frac{V_0^2}{2 \cdot g} \cdot \left[1 - \left(\frac{M \cdot g}{\rho \cdot V_0^2 \cdot A_0}\right)^2\right]$$

Hence  $h_0 = \frac{1}{2} \times \left(15 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \left[1 - \left[30 \cdot \text{kg} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \left(\frac{\text{s}}{15 \cdot \text{m}}\right)^2 \times \frac{1}{.005 \cdot \text{m}^2}\right]^2\right] h_0 = 10.7 \text{ m}$

In Excel:

$$\begin{aligned} \Xi t &= 0.05 \text{ s} \\ A_0 &= 0.005 \text{ m}^2 \\ g &= 9.81 \text{ m/s}^2 \\ V &= 15 \text{ m/s} \\ M &= 30 \text{ kg} \\ \Xi &= 1000 \text{ kg/m}^3 \end{aligned}$$

$t$ (s)	$h$ (m)	$dh/dt$ (m/s)	$d^2h/dt^2$ (m/s <sup>2</sup> )
0.000	2.000	0.000	24.263
0.050	2.000	1.213	18.468
0.100	2.061	2.137	14.311
0.150	2.167	2.852	11.206
0.200	2.310	3.412	8.811
0.250	2.481	3.853	6.917
0.300	2.673	4.199	5.391
0.350	2.883	4.468	4.140
0.400	3.107	4.675	3.100
0.450	3.340	4.830	2.227
0.500	3.582	4.942	1.486
0.550	3.829	5.016	0.854
0.600	4.080	5.059	0.309
0.650	4.333	5.074	-0.161
0.700	4.587	5.066	-0.570
0.750	4.840	5.038	-0.926
0.800	5.092	4.991	-1.236
0.850	5.341	4.930	-1.507
0.900	5.588	4.854	-1.744
0.950	5.830	4.767	-1.951
1.000	6.069	4.669	-2.130
1.050	6.302	4.563	-2.286
1.100	6.530	4.449	-2.420
1.150	6.753	4.328	-2.535
1.200	6.969	4.201	-2.631
1.250	7.179	4.069	-2.711
1.300	7.383	3.934	-2.776
1.350	7.579	3.795	-2.826
1.400	7.769	3.654	-2.864
1.450	7.952	3.510	-2.889
1.500	8.127	3.366	-2.902
1.550	8.296	3.221	-2.904
1.600	8.457	3.076	-2.896
1.650	8.611	2.931	-2.878
1.700	8.757	2.787	-2.850
1.750	8.896	2.645	-2.814
1.800	9.029	2.504	-2.769
1.850	9.154	2.365	-2.716
1.900	9.272	2.230	-2.655
1.950	9.384	2.097	-2.588
2.000	9.488	1.967	-2.514
2.050	9.587	1.842	-2.435
2.100	9.679	1.720	-2.350
2.150	9.765	1.602	-2.261
2.200	9.845	1.489	-2.167
2.250	9.919	1.381	-2.071
2.300	9.989	1.278	-1.972
2.350	10.052	1.179	-1.871
2.400	10.111	1.085	-1.769
2.450	10.166	0.997	-1.666




$t$ (s)	$h$ (m)	$dh/dt$ (m/s)	$d^2h/dt^2$ (m/s <sup>2</sup> )
2.950	10.506	0.380	-0.766
3.000	10.525	0.341	-0.698
3.050	10.542	0.307	-0.634
3.100	10.558	0.275	-0.574
3.150	10.571	0.246	-0.519
3.200	10.584	0.220	-0.469
3.250	10.595	0.197	-0.422
3.300	10.604	0.176	-0.380
3.350	10.613	0.157	-0.341
3.400	10.621	0.140	-0.306
3.450	10.628	0.124	-0.274
3.500	10.634	0.111	-0.245
3.550	10.640	0.098	-0.219
3.600	10.645	0.087	-0.195
3.650	10.649	0.078	-0.174
3.700	10.653	0.069	-0.155
3.750	10.656	0.061	-0.138
3.800	10.659	0.054	-0.123
3.850	10.662	0.048	-0.109
3.900	10.665	0.043	-0.097
3.950	10.667	0.038	-0.086
4.000	10.669	0.033	-0.077
4.050	10.670	0.030	-0.068
4.100	10.672	0.026	-0.060
4.150	10.673	0.023	-0.053
4.200	10.674	0.021	-0.047
4.250	10.675	0.018	-0.042
4.300	10.676	0.016	-0.037
4.350	10.677	0.014	-0.033
4.400	10.678	0.013	-0.029
4.450	10.678	0.011	-0.026
4.500	10.679	0.010	-0.023
4.550	10.679	0.009	-0.020

## Problem 4.181

[Difficulty: 5] Part 1/2

**4.181** A small solid-fuel rocket motor is fired on a test stand. The combustion chamber is circular, with 100 mm diameter. Fuel, of density  $1660 \text{ kg/m}^3$ , burns uniformly at the rate of  $12.7 \text{ mm/s}$ . Measurements show that the exhaust gases leave the rocket at ambient pressure, at a speed of  $2750 \text{ m/s}$ . The absolute pressure and temperature in the combustion chamber

are  $7.0 \text{ MPa}$  and  $3610 \text{ K}$ , respectively. Treat the combustion products as an ideal gas with molecular mass of  $25.8$ . Evaluate the rate of change of mass and of linear momentum within the rocket motor. Express the rate of change of linear momentum within the motor as a percentage of the motor thrust.



Treat combustion products as ideal gas with molecular mass,  $M_m = 25.8$ .

- Find: (a) Evaluate rate of change of mass and of linear momentum within rocket motor.  
 (b) Express rate of change of momentum as a percentage of thrust.

Solution: Apply continuity and  $x$  component of momentum equations using fixed CV shown.

Basic equations: 
$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

$$F_{Bx} + F_{Bx}^{(2)} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) No net pressure force;  $F_{Bx} = R_x$   
 (2)  $F_{Bx}^{(2)} = 0$   
 (3) All properties constant at each point, except at surface where combustion takes place  
 (4) Uniform flow at exit section

The continuity equation becomes

$$0 = \frac{\partial}{\partial t} \int_I \rho dV + \frac{\partial}{\partial t} \int_a^l \rho_g A dx + \frac{\partial}{\partial t} \int_l^b \rho_f A dx + \{ \rho_e V_e A_e \}$$

$$0 = \frac{\partial}{\partial t} [\rho_g A (l-a)] + \frac{\partial}{\partial t} [\rho_f A (b-l)] + \dot{m}_e = (\rho_g - \rho_f) A \frac{dl}{dt} + \dot{m}_e$$

or

$$\dot{m}_e = (\rho_f - \rho_g) A \frac{dl}{dt} = (\rho_f - \rho_g) A v_b$$

For an ideal gas,

$$\rho_g = \frac{p_g}{RT_g} = \frac{p_g M_m}{R_u T_g} = \frac{7.0 \times 10^6 \text{ N/m}^2}{\frac{8314 \text{ N}\cdot\text{m}}{\text{mol}} \times \frac{1}{3610 \text{ K}}} = 6.02 \text{ kg/m}^3$$

so

$$\dot{m}_e = (1660 - 6) \frac{\text{kg}}{\text{m}^3} \times \frac{\pi (0.1)^2 \text{ m}^2}{4} \times \frac{0.0127 \text{ m}}{\text{s}} = 0.165 \text{ kg/s}$$

Mass flow is out, so  $\frac{\partial M_{CV}}{\partial t} = -0.165 \text{ kg/s}$

$$\frac{\partial M_{CV}}{\partial t}$$

From the momentum equation,

$$R_x = \frac{\partial}{\partial t} \int_V u \rho dV + \frac{\partial}{\partial t} \int_a^L u_g \rho_g A dx + \frac{\partial}{\partial t} \int_L^b u_e \rho_e A dx + u_e \{ \rho_e V_e A_e \}$$

$$= \frac{\partial}{\partial t} [u_g \rho_g A (L-a)] + u_e \dot{m}_e \quad ; \quad u_g = -V_g \quad \text{and} \quad u_e = -V_e$$

$$R_x = -\rho_g V_g A \frac{dL}{dt} - V_e \dot{m}_e = -\rho_g V_g A \Delta - V_e \dot{m}_e$$

But, from continuity,  $\rho_g V_g A = \dot{m}_e$ , since no mass accumulates in region I of the CV. Thus

$$R_x = -\dot{m}_e (V_e + \Delta)$$

$R_x$  is the force on the CV. The thrust is

$$K_x = \text{Thrust} = -R_x = \dot{m}_e (V_e + \Delta)$$

$$K_x = 0.165 \frac{\text{kg}}{\text{s}} (2750 + 0.0127) \frac{\text{m}}{\text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 454 \text{ N}$$

The rate of change of linear momentum within the CV is

$$\frac{\partial P_{x,CV}}{\partial t} = -\dot{m}_e \Delta = -0.165 \frac{\text{kg}}{\text{s}} \times 0.0127 \frac{\text{m}}{\text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = -2.10 \text{ mN} \quad \frac{\partial P_{x,CV}}{\partial t}$$

The ratio of rate of change of linear momentum to thrust is

$$\frac{\frac{\partial P_{x,CV}}{\partial t}}{K_x} = \frac{-\dot{m}_e \Delta}{\dot{m}_e (V_e + \Delta)} = -\frac{\Delta}{(V_e + \Delta)} = -\frac{0.0127 \frac{\text{m}}{\text{s}}}{(2750 + 0.0127) \frac{\text{m}}{\text{s}}} = -4.62 \times 10^{-6}$$

or

$$\frac{\frac{\partial P_{x,CV}}{\partial t}}{K_x} = -4.62 \times 10^{-4} \text{ percent}$$

Ratio

{ Neglecting the unsteady momentum term in the analysis of this rocket motor would cause an error of approximately 1 part in 217,000. The assumption that  $\frac{\partial P_{x,CV}}{\partial t} \approx 0$  is certainly justified for engineering work. }

## Problem 4.182

[Difficulty: 5] Part 1/3

**4.182** The capability of the Aircraft Landing Loads and Traction Facility at NASA's Langley Research Center is to be upgraded. The facility consists of a rail-mounted carriage propelled by a jet of water issuing from a pressurized tank. (The setup is identical in concept to the hydraulic catapult of Problem 4.138.) Specifications require accelerating the car-

riage with 49,000 kg mass to a speed of 220 knots in a distance of 122 m. (The vane turning angle is  $170^\circ$ .) Identify a range of water jet sizes and speeds needed to accomplish this performance. Specify the recommended operating pressure for the water-jet system and determine the shape and estimated size of tankage to contain the pressurized water.

**Discussion:** The analysis of Example 4.11 forms the basis for the solution outlined below. Use a control volume attached to and moving with the carriage to analyze the motion. Neglect aerodynamic and rolling resistance to obtain a best-case solution. Solve the resulting differential equation of motion for carriage speed and position as functions of time, and for speed as a function of position along the rails.

Computing equations are summarized and results tabulated below. As shown in Example 4.11, analysis of the carriage motion results in the differential equation

$$\frac{dU}{dt} = \frac{\rho (V_j - U)^2 (1 - \cos \theta)}{M} \quad (1)$$

Integrating with respect to time gives carriage speed versus time

$$U = V_j \frac{bt}{1 + bt} \quad (2)$$

where parameter  $b$  is

$$b = \frac{\rho V_j A_j (1 - \cos \theta)}{M} \quad (3)$$

Equation 2 is integrated to obtain carriage position versus time

$$x = V_j \left[ t - \frac{\ln(1 + bt)}{b} \right] \quad (4)$$

Substitute  $dU/dt = U dU/dx$  and integrate Eq. 1 for distance traveled versus carriage speed

$$x = \frac{V_j}{b} \left[ \ln(1 - U/V_j) + \frac{1}{1 - U/V_j} - 1 \right] \quad (5)$$

Relate jet speed to water tank pressure using the Bernoulli equation

$$V_j = \sqrt{2\Delta P/\rho} \quad (6)$$

The required volume of water is computed as follows:

1. Assume a range of tank pressures.
2. Compute the jet speed corresponding to each tank pressure from Eq. 6.
3. Solve for parameter  $b$  from Eq. 5 using the known maximum speed and specified distance.
4. Obtain jet area from Eq. 3.
5. Compute the time required to accelerate the carriage from Eq. 2.
6. Calculate jet diameter from jet area.
7. Compute the required volume of water from the product of mass flow rate and acceleration time.

The optimum operating pressure requires the least costly tankage. (Assume the most efficient spherical shape for pressurized tankage and constant tank pressure during acceleration.) Tankage calculations are organized as follows:

1. Obtain tank diameter from tank volume.
2. Calculate wall thickness from a force balance on the thin wall of the tank.
3. Calculate steel volume from tank surface area and wall thickness.
4. Assume steel cost is proportional to steel volume.

Sample calculation: assume  $p = 6000$  psig

$$V_j = \left[ 2 \times 6000 \frac{\text{lb}}{\text{in}^2} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{\text{slug} \cdot \text{ft}}{16 \text{ lb} \cdot \text{s}^2} \right]^{\frac{1}{2}} = 944 \text{ ft/s} ; \frac{U}{V_j} = \frac{371}{944} = 0.393$$

$$b = 944 \frac{\text{ft}}{\text{s}} \times \frac{1}{400 \text{ ft}} \left[ 2 \ln(1 - 0.393) + \frac{1}{1 - 0.393} - 1 \right] = 0.350 \text{ s}^{-1}$$

$$A_j = \frac{bM}{\rho V_j (1 - \cos \theta)} = \frac{0.350}{\text{s}} \times 3350 \text{ slug} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{\text{s}}{944 \text{ ft}} \times \frac{1}{(1 - \cos 170^\circ)} = 0.323 \text{ ft}^2$$

$$D = \sqrt{\frac{4A}{\pi}} = \left[ \frac{4}{\pi} \times 0.323 \text{ ft}^2 \times \frac{144 \text{ in}^2}{\text{ft}^2} \right]^{\frac{1}{2}} = 7.69 \text{ in.}$$

$$t = \frac{1}{b} \left( \frac{U/V_j}{1 - U/V_j} \right) = \frac{\text{s}}{0.350} \times \frac{0.393}{1 - 0.393} = 1.85 \text{ s}$$

$$Q = V_j A = 944 \frac{\text{ft}}{\text{s}} \times 0.323 \text{ ft}^2 \times \frac{7.48 \text{ gal}}{\text{ft}^3} = 2280 \text{ gal/s}$$

$$V = Qt = 2280 \frac{\text{gal}}{\text{s}} \times 1.85 \text{ s} = 4220 \text{ gal}$$

$$D = (6V/\pi)^{\frac{1}{3}} = \left( \frac{6}{\pi} \times 4220 \text{ gal} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \right)^{\frac{1}{3}} = 10.3 \text{ ft}$$

$$\Delta p \frac{\pi D^2}{4} = \pi D t ; t = \frac{pD}{4\sigma} = \frac{1}{4} \times 6000 \frac{\text{lb}}{\text{in}^2} \times 10.3 \text{ ft} \times \frac{\text{in}^2}{40,000 \text{ lb}} \times \frac{12 \text{ in}}{\text{ft}} = 4.64 \text{ in.}$$

$$V_{\text{steel}} = \pi D^2 t = \pi \times (10.3 \text{ ft})^2 \times 4.64 \text{ in.} \times \frac{\text{ft}}{12 \text{ in.}} = 129 \text{ ft}^3$$

Discussion: The results show the steel volume plummets as tank pressure is raised, with a broad minimum between 3,000 and 4,000 psig.



## Problem 4.183

[Difficulty: 5] Part 1/2

**4.183** A classroom demonstration of linear momentum is planned, using a water-jet propulsion system for a cart traveling on a horizontal linear air track. The track is 5 m long, and the cart mass is 155 g. The objective of the design is to obtain the best performance for the cart, using 1 L of water contained in an open cylindrical tank made from plastic sheet with density of  $0.0819 \text{ g/cm}^3$ . For stability, the maximum height of the water tank cannot exceed 0.5 m. The diameter of the smoothly rounded water jet may not exceed 10 percent of the tank diameter. Determine the best dimensions for the tank

and the water jet by modeling the system performance. Using a numerical method such as the Euler method (see Section 5.5), plot acceleration, velocity, and distance as functions of time. Find the optimum dimensions of the water tank and jet opening from the tank. Discuss the limitations on your analysis. Discuss how the assumptions affect the predicted performance of the cart. Would the actual performance of the cart be better or worse than predicted? Why? What factors account for the difference(s)?

**Discussion:** This solution is an extension of Problem 4.184. The analyses for tank level, acceleration, and velocity are identical; please refer to the solution for Problem 4.184 for equations describing each of these variables as functions of time.

One new feature of this problem is computation of distance traveled. Equation 7 of Problem 4.184 could be integrated in closed form to provide an equation for distance traveled as a function of time. However, the integral would be messy, and it would provide little insight into the dependence on key parameters. Consequently, a numerical analysis has been chosen in this problem. The results are presented in the plots and spreadsheet on the next page.

We have chosen to define velocity as the output to be maximized.

A second new feature of this problem is the geometric constraints: the maximum track length is 5 m. Intuitively jet diameter should be chosen as the largest possible fraction of tank diameter for optimum performance. Using the spreadsheet to vary  $\beta = d/D$  verifies that this is the case. Therefore we have used the maximum allowable ratio,  $\beta = 0.1$ , for all computations.

Tank height should be a factor in performance. Intuition suggests that increasing tank height should improve performance. Using the spreadsheet shows a very weak dependence on tank height. Performance is best at smaller tank heights, corresponding to the minimum tank mass.

As tank height is decreased, diameter increases because tank volume is held constant. Since diameter ratio is constant, then jet diameter increases with decreasing tank height. This effect almost overshadows the effect of tank height.

The principal limitations on the analysis are the assumptions of negligible motion resistance and no slope to the free surface of water in the tank. Actual performance of the cart would likely be less than predicted because of motion resistance.

*Distance is modeled as*

$$x_{i+1} = x_i + U_i \Delta t + \frac{1}{2} a_{x,i} \Delta t^2$$

*The accuracy of this model for position is consistent with the accuracy of modeling the water-jet propulsion system.*



# Problem 4.184

[Difficulty: 5] Part 1/4

**4.184** Analyze the design and optimize the performance of a cart propelled along a horizontal track by a water jet that issues under gravity from an open cylindrical tank carried on board the cart. (A water-jet-propelled cart is shown in the diagram for Problem 4.142.) Neglect any change in slope of the liquid free surface in the tank during acceleration. Analyze the motion of the cart along a horizontal track, assuming it starts from rest and begins to accelerate when

water starts to flow from the jet. Derive algebraic equations or solve numerically for the acceleration and speed of the cart as functions of time. Present results as plots of acceleration and speed versus time, neglecting the mass of the tank. Determine the dimensions of a tank of minimum mass required to accelerate the cart from rest along a horizontal track to a specified speed in a specified time interval.

**Discussion:** This problem solution consists of two parts. The first is to analyze the acceleration and velocity of a cart propelled by a gravity-driven water jet. The second is to optimize the dimensions of the cart and jet to accelerate to a specified speed in a specified time interval.

To analyze the problem, apply conservation of mass and the Bernoulli equation to the draining of the tank, then apply the x component of the momentum equation for a control volume to analyze the resulting linear acceleration. A representative plot of the results is presented below.

To optimize the performance of the water-jet-propelled cart, manipulate the solution dimensions until the best performance is attained.

**Input Data:**


$d =$	10	mm	Diameter of water jet
$D =$	100	mm	Diameter of tank
$g =$	9.81	ft/s <sup>2</sup>	Acceleration of gravity
$H =$	150	mm	Height of tank
$M_t =$	0.001	kg	Mass of tank
$\rho =$	999	kg/m <sup>3</sup>	Density of water

**Calculated Parameters:**

$a =$	0.029	(--)	( $a^2 =$ ) Ratio of mass of tank to initial mass of water
$b =$	0.0572	s <sup>-1</sup>	Geometric parameter of solution
$M_0 =$	1.18	kg	Initial mass of water in tank
$\beta =$	0.1	(--)	Ratio of jet diameter to tank diameter

**Calculated Results:**

Time, $t$ (s)	Level Ratio, $y/H$ (--)	Accel., $a_x$ (m/s <sup>2</sup> )	Velocity, $U$ (m/s)
0	1	0.196	0
1	0.810	0.196	0.196
2	0.640	0.196	0.392
3	0.490	0.196	0.588
4	0.360	0.196	0.784
5	0.250	0.196	0.980
6	0.160	0.196	1.176
7	0.0900	0.196	1.37
8	0.0400	0.196	1.57
9	0.0100	0.196	1.76
10	0	0.195	1.96




17-289  
 40-283  
 42-286  
 47-392  
 47-399  
 200 SHEETS  
 100 RECYCLED  
 2001 RECYCLED  
 Made in U.S.A.  
 National Brand

Given: Cart, propelled by water jet, accelerates along horizontal track.

Find: (a) Analyze motion, derive algebraic equations for acceleration and speed of cart as functions of time  
 (b) Plot acceleration and speed vs. time.

Solution: Apply conservation of mass, Bernoulli, and momentum equations.

Basic equations:



$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{v} \cdot d\vec{A}$$

$$\frac{p_j}{\rho} + \frac{V_j^2}{2} + g y_j = \frac{p}{\rho} + \frac{V^2}{2} + g y \quad \text{--- (8)}$$

$M_t$  = mass of tank, cart

$$\beta = \frac{d}{D}$$

$$F_{p_x} + F_{\beta_x} - \int_{CV} a r_x \rho dV = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{v} \cdot d\vec{A} \quad \text{--- (11)}$$

Assumptions: (1) Uniform flow from exit jet (2) Neglect air in CV

$$0 = \frac{\partial}{\partial t} (\rho A_t y) + \{ \rho V_j A_j \} = \rho A_t \frac{dy}{dt} + \rho V_j A_j = -\rho A_t V + \rho V_j A_j \quad (1)$$

$$\text{Thus } V = V_j \frac{A_j}{A_t} = V_j \left(\frac{d}{D}\right)^2 = \beta^2 V_j \quad (2)$$

- (3) No slope to free surface (given)
- (4) Quasi-steady flow
- (5) Frictionless flow
- (6) Incompressible flow
- (7) Flow along a streamline
- (8)  $p = p_j = p_{atm}$
- (9)  $y_j = 0$

From Bernoulli,  $\frac{V_j^2}{2} = \frac{V^2}{2} + g y$  or  $V_j^2 - V^2 = 2g y$

Substituting from (2),  $V_j^2 - \beta^4 V_j^2 = V_j^2 (1 - \beta^4) = 2g y$ ;  $V_j^2 = \frac{2g y}{(1 - \beta^4)}$  (3)

Substituting into (1),  $\frac{dy}{dt} = -\beta^2 V_j = -\beta^2 \frac{\sqrt{2g y}}{(1 - \beta^4)}$  or  $\frac{dy}{y^{1/2}} = -\frac{\beta^2 \sqrt{2g}}{1 - \beta^4} dt$

Integrating,  $2y^{1/2} \Big|_{y_0}^y = -\frac{\beta^2 \sqrt{2g}}{(1 - \beta^4)} t$  or  $y^{1/2} - y_0^{1/2} = -\frac{\beta^2 \sqrt{2g}}{2(1 - \beta^4)} t$

Thus  $\left(\frac{y}{y_0}\right)^{1/2} = 1 - \left[\frac{g \beta^4}{2 y_0 (1 - \beta^4)}\right]^{1/2} t = 1 - b t$ ;  $b = \left[\frac{g \beta^4}{2 y_0 (1 - \beta^4)}\right]^{1/2}$  (4)



Given: cart, propelled by water jet, accelerating on horizontal track.

$$\frac{dU}{dt} = \frac{2g\beta^2}{1-\beta^4} \frac{(1-bt)^2}{a^2 + (1-bt)^2} \quad (1)$$

$$U(t) = \frac{2g\beta^2}{1-\beta^4} \left\{ t + \frac{a}{b} \left[ \tan^{-1}\left(\frac{1-bt}{a}\right) - \tan^{-1}\left(\frac{1}{a}\right) \right] \right\} \quad (2)$$

$$\beta = \frac{d}{D}, \quad a^2 = \frac{M_t}{M_0}, \quad b = \left[ \frac{g\beta^4}{2y_0(1-\beta^4)} \right]^{1/2}$$

Find: (a) Shape for tank of minimum mass for given volume.

(b) Minimum water volume to reach  $U = 2.5$  m/sec in  $t = 25$  sec.

Solution: mass of tank is  $M = \rho_t A_s t$ , where  $t$  = thickness of wall

$$A_s = A_{\text{bottom}} + A_{\text{cylinder}} = \frac{\pi D^2}{4} + \pi D H$$

Since volume is  $V = \frac{\pi D^2}{4} H$ , then  $H = \frac{4V}{\pi D^2}$ , and

$$A_s = \frac{\pi D^2}{4} + \pi D \left( \frac{4V}{\pi D^2} \right) = \frac{\pi D^2}{4} + \frac{4V}{D}$$

To minimize, set  $dA_s/dD = 0$

$$\frac{dA_s}{dD} = \frac{\pi D}{2} + (-1) \frac{4V}{D^2} = 0 \quad \text{so} \quad D^3 = \frac{8V}{\pi} \quad \text{or} \quad D = \left( \frac{8V}{\pi} \right)^{1/3} \quad (3) \quad D_{\text{opt}}$$

$$\text{Then } V = \frac{\pi D^2 H}{4} = \frac{\pi D^3}{8} \quad \text{so} \quad \frac{H}{D} = \frac{1}{2} \quad (4) \quad \left. \frac{H}{D} \right|_{\text{opt}}$$

The tank mass per volume for optimum  $H/D$  is

$$m = \frac{M}{V} = \frac{\rho_t \left( \frac{\pi D^2}{4} + \pi D H \right) t}{\frac{\pi D^2 H}{4}} = \rho_t \left( \frac{t}{H} + \frac{4t}{D} \right) = \rho_t \frac{t}{H} \left( 1 + 4 \frac{H}{D} \right) = 3 \rho_t \frac{t}{H}$$

Therefore mass depends on  $\rho_t t$  for a given volume. The minimum mass is achieved for the smallest combination of  $\rho_t$  and  $t$ .

$$a^2 = \frac{M_t}{M_0} = \frac{M_t}{\rho_t V} = \frac{3 \rho_t t}{\rho} \frac{t}{H} = 3 SG \left( \frac{t}{H} \right) \quad (5)$$

which still depends on volume, since it contains  $H$ .

The best solution strategy seems to be: pick  $V$ , calculate  $H, D, \beta, a$ , and  $b$ , then plot  $U(t)$ .



Evaluating,  $\dot{m}_2 = \rho A_2 V_2 = \rho \frac{\pi d^2}{4} V_2$

$$\dot{m}_2 = 999 \frac{\text{kg}}{\text{m}^3} \times \frac{\pi}{4} (0.05)^2 \text{m}^2 \times 40 \frac{\text{m}}{\text{s}} = 78.5 \text{ kg/s}$$

Then with  $V_2 = 40 \text{ m/s}$

Moment from jet =  $78.5 \frac{\text{kg}}{\text{s}} \times 40 \frac{\text{m}}{\text{s}} \times \frac{1.5^2}{5} \left[ 3 \text{m} \cos 30^\circ - \frac{1.5 \text{m}}{2} \sin 30^\circ \right]$

Moment<sub>jet</sub> =  $6.98 \text{ kN}\cdot\text{m}$  ← Moment<sub>jet</sub>

For the case of impending tipping (about point 3)

$N_4 \rightarrow 0$  and from Eq. 2

$$-\frac{W}{2} Mg + \dot{m}_2 V \left[ h \cos \theta - \frac{W}{2} \sin \theta \right] = 0$$

To solve for  $V_2$ , write  $\dot{m} = \rho A_2 V_2$

$$V_2^2 = \frac{W Mg}{2 \rho A_2 \left[ h \cos \theta - \frac{W}{2} \sin \theta \right]} \quad (3)$$

$$V_2^2 = \frac{1.5 \text{m} \cdot 350 \text{kg} \cdot 9.81 \frac{\text{m}}{\text{s}^2}}{2 \cdot 999 \frac{\text{kg}}{\text{m}^3} \cdot 1.96 \times 10^{-3} \text{m}^2 \cdot \left( 3 \cos 30^\circ - 0.75 \sin 30^\circ \right) \text{m}}$$

$$V_2^2 = 592 \text{ m}^2/\text{s}^2 \quad \therefore V_2 = 24.3 \text{ m/s} \quad V_2$$

Thus, the maximum speed allowable without tipping is less than the value suggested.

The impending motion will be tipping since  $f_3 < \mu N_3$

From the x momentum equation  $f_3 = \dot{m} V_2 \cos \theta$


From the y momentum equation  $N_3 = Mg + \dot{m} V_2 \sin \theta$

For tipping  $\mu > 0.377$

From Eq. 2 we see that as  $\theta$  increases the tendency to tip decreases

For impending motion from Eq. 3

$$V = \left\{ \frac{W Mg}{2 \rho A_2 \left[ h \cos \theta - \frac{W}{2} \sin \theta \right]} \right\}^{1/2}$$



### Problem 4.186


[Difficulty: 2]

**4.186** The 90° reducing elbow of Example 4.6 discharges to atmosphere. Section ② is located 0.3 m to the right of Section ①. Estimate the moment exerted by the flange on the elbow.

Solution: Apply moment of momentum, using the CV and CS shown.

From Example Problem 4.6  $\vec{V}_2 = -16\hat{j}$  m/s,  $A_1 = 0.01$  m<sup>2</sup>

Steady flow,  $A_2 = 0.0025$  m<sup>2</sup>



Basic equation (fixed CV):

$$\vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} = \frac{d}{dt} \int_{CV} \vec{r} \times \vec{V} \rho dV + \int_{CS} \vec{r} \times \vec{V} \rho \vec{V} \cdot d\vec{A}$$

$\vec{r} \times \vec{g} \approx 0(1)$        $\vec{T}_{shaft} = 0(2)$        $\frac{d}{dt} \int_{CV} \vec{r} \times \vec{V} \rho dV = 0(3)$

- Assumptions: (1) Neglect body forces (5) Incompressible flow  
 (2) No shafts, so  $\vec{T}_{shaft} = 0$   
 (3) Steady flow (given)  
 (4) Uniform flow at each cross section

Then

$$\vec{M}_{flange} = \vec{r} \times \vec{F}_s|_{flange} = \vec{r}_1 \times \vec{V}_1 \{-\rho V_1 A_1\} + \vec{r}_2 \times \vec{V}_2 \{+\rho V_2 A_2\} \quad (1)$$

$$\left. \begin{aligned} \vec{r}_1 &= 0 \\ \vec{r}_2 &= a\hat{i} - b\hat{j} \\ \vec{V}_2 &= -V_2\hat{j} \end{aligned} \right\} \vec{r}_2 \times \vec{V}_2 = -aV_2\hat{k} + 0$$

Substituting into Eq. 1,

$$\begin{aligned} \vec{M}_{flange} &= -aV_2\hat{k} \{+\rho V_2 A_2\} = -a\rho V_2^2 A_2 \hat{k} \\ &= 0.3 \text{ m} \times 999 \frac{\text{kg}}{\text{m}^3} \times (16)^2 \frac{\text{m}^2}{\text{s}^2} \times 0.0025 \text{ m}^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} (-\hat{k}) \end{aligned}$$

$$\vec{M}_{flange} = -192 \hat{k} \text{ N} \cdot \text{m}$$


This is the torque that must be exerted on the CV by the flange.

{ Since  $\vec{M}_{flange}$  is in the  $-\hat{k}$  direction, it must act cw in the xy-plane. }

### Problem 4.187

[Difficulty: 3]

**4.187** Crude oil (SG = 0.95) from a tanker dock flows through a pipe of 0.25 m diameter in the configuration shown. The flow rate is  $0.58 \text{ m}^3/\text{s}$ , and the gage pressures are shown in the diagram. Determine the force and torque that are exerted by the pipe assembly on its supports.



Solution: No momentum components exist in the  $y$  direction. Apply  $x$  component of linear momentum and the moment of momentum equations using the CV shown. Location of coordinates is arbitrary; for simplicity, choose as shown.

Basic equations:  $F_{Sx} + \overset{=0(1)}{F_{Bx}} = \overset{=0(2)}{\frac{\partial}{\partial t} \int_{CV} u \rho dV} + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$

$\vec{r} \times \vec{F}_S + \int_{CV} \vec{r} \times \vec{g} \rho dV + \overset{=0(4)}{\vec{T}_{shaft}} = \overset{=0(5)}{\frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{V} \rho dV} + \int_{CS} \vec{r} \times \vec{V} \rho \vec{V} \cdot d\vec{A}$

- Assumptions: (1)  $F_{Bx} = 0$ ;  $\vec{g}$  acts in  $z$  direction  
 (2) Steady flow  
 (3) Uniform flow at each section  
 (4) No  $z$  component of  $\vec{r} \times \vec{g}$   
 (5)  $\vec{T}_{shaft} = 0$

$A = \frac{\pi D^2}{4} = \frac{\pi}{4} (0.25)^2 \text{ m}^2 = 0.049 \text{ m}^2$

From momentum equation,

$R_{x1} + R_{x2} + p_1 A - p_2 A = u_1 \{-\dot{m}\} + u_2 \{\dot{m}\} = 0$ ;  $R_{x1} + R_{x2} = (p_2 - p_1) A$

From moment of momentum,

$\vec{r}_1 \times (R_{x1} + p_1 A) \hat{e} + \vec{r}_2 \times (R_{x2} - p_2 A) \hat{e} = \vec{r}_1 \times V_1 \hat{e} \{-\dot{m}\} + \vec{r}_2 \times V_2 \hat{e} \{\dot{m}\}$ ;  $\vec{r}_1 = L \hat{j}$ ,  $\vec{r}_1 \times \hat{e} = -L \hat{k}$

$-L(R_{x1} + p_1 A) \hat{k} = -LV_1(-\dot{m}) \hat{k} = LV_1 \dot{m} \hat{k} = L \frac{Q}{A} (\rho Q) \hat{k} = L \frac{\rho Q^2}{A} \hat{k}$

$R_{x1} = -\frac{\rho Q^2}{A} - p_1 A = -0.95 \times 999 \frac{\text{kg}}{\text{m}^3} \times \frac{(0.58)^2 \text{ m}^6}{\text{s}^2} \times \frac{1}{0.049 \text{ m}^2 \times \text{kg} \cdot \text{m}} - 3.45 \times 10^5 \frac{\text{N}}{\text{m}^2} \times 0.049 \text{ m}^2 = -23.4 \text{ kN}$

$R_{x2} = (p_2 - p_1) A - R_{x1} = p_2 A - p_1 A + \frac{\rho Q^2}{A} + p_1 A = p_2 A + \frac{\rho Q^2}{A}$   
 $= 3.32 \times 10^5 \frac{\text{N}}{\text{m}^2} \times 0.049 \text{ m}^2 + 0.95 \times 999 \frac{\text{kg}}{\text{m}^3} \times \frac{(0.58)^2 \text{ m}^6}{\text{s}^2} \times \frac{1}{0.049 \text{ m}^2 \times \text{kg} \cdot \text{m}} = 22.8 \text{ kN}$

$\vec{r} \times \vec{F}_S = \vec{r}_1 \times R_{x1} \hat{e} = L \hat{j} \times R_{x1} \hat{e} = -L R_{x1} \hat{k} = -20 \text{ m} \times (-46.0) \text{ kN} \hat{k} = 468 \hat{k} \text{ kN} \cdot \text{m}$

These are forces and torque on CV. The corresponding reactions are:

$K_{x1} = -R_{x1} = 23.4 \text{ kN}$ ,  $K_{x2} = -R_{x2} = -22.8 \text{ kN}$

$\vec{M} = -\vec{r} \times \vec{F}_S = -468 \hat{k} \text{ kN} \cdot \text{m}$  (i.e. clockwise)


Force

Torque

## Problem 4.188

[Difficulty: 3]

**4.188** The simplified lawn sprinkler shown rotates in the horizontal plane. At the center pivot,  $Q = 15 \text{ L/min}$  of water enters vertically. Water discharges in the horizontal plane from each jet. If the pivot is frictionless, calculate the torque needed to keep the sprinkler from rotating. Neglecting the inertia of the sprinkler itself, calculate the angular acceleration that results when the torque is removed.



**Given:** Data on rotating spray system

**Find:** Torque required to hold stationary; steady-state speed

**Solution:**

Basic equation: Rotating CV

$$\begin{aligned} \vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} \\ - \int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV \quad (4.52) \\ = \frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{V}_{xyz} \rho dV + \int_{CS} \vec{r} \times \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \end{aligned}$$

Assumptions: 1) No surface force; 2) Body torques cancel; 3) Sprinkler stationary; 4) Steady flow; 5) Uniform flow; 6)  $L \ll r$

The given data is  $Q = 15 \frac{\text{L}}{\text{min}}$        $R = 225 \text{ mm}$        $d = 5 \text{ mm}$        $\rho = 999 \frac{\text{kg}}{\text{m}^3}$

For each branch  $V = \frac{1}{2} \cdot \frac{Q}{\frac{\pi \cdot d^2}{4}}$        $V = 6.37 \frac{\text{m}}{\text{s}}$

The basic equation reduces to a single scalar equation (FOR EACH BRANCH)

$$T_{shaft} - \int \vec{r} \times (\vec{\alpha} \times \vec{r}) \cdot \rho dV = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA \quad \text{where } \alpha \text{ is the angular acceleration}$$

But  $\vec{r} \times (\vec{\alpha} \times \vec{r}) = r^2 \cdot \alpha$  ( $r$  and  $\alpha$  perpendicular); the volume integral is  $\int \vec{r} \times (\vec{\alpha} \times \vec{r}) \cdot \rho dV = \int r^2 \cdot \alpha \cdot \rho dV = \frac{R^3}{3} \cdot \alpha \cdot \frac{\pi}{4} \cdot d^2$

For the surface integral (FOR EACH BRANCH)  $\int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA = R \cdot V \cdot \rho \cdot \frac{Q}{2}$

Combining  $T_{shaft} - \frac{R^3}{3} \cdot \alpha \cdot \rho \cdot \frac{\pi}{4} \cdot d^2 = R \cdot V \cdot \rho \cdot \frac{Q}{2}$       (1)

When the sprayer is at rest,  $\alpha = 0$ , so  $T_{shaft} = R \cdot V \cdot \rho \cdot \frac{Q}{2}$        $T_{shaft} = 0.179 \text{ N}\cdot\text{m}$


The total torque is then  $T_{total} = 2 \cdot T_{shaft}$        $T_{total} = 0.358 \text{ N}\cdot\text{m}$

When the device is released is released ( $T_{shaft} = 0$  in Eq 1), we can solve for  $\alpha$        $\alpha = \frac{6 \cdot \rho \cdot Q \cdot V}{\rho \cdot \pi \cdot d^2 \cdot R^2}$        $\alpha = 2.402 \times 10^3 \frac{1}{\text{s}^2}$

## Problem 4.189

[Difficulty: 3]

**4.189** Consider the sprinkler of Problem 4.188 again. Derive a differential equation for the angular speed of the sprinkler as a function of time. Evaluate its steady-state speed of rotation if there is no friction in the pivot.



**Given:** Data on rotating spray system

**Find:** Differential equation for motion; steady speed

**Solution:**

Basic equation: Rotating CV

$$\begin{aligned} \vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} \\ - \int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV \quad (4.52) \\ = \frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{V}_{xyz} \rho dV + \int_{CS} \vec{r} \times \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \end{aligned}$$

Assumptions: 1) No surface force; 2) Body torques cancel; 3) Steady flow; 5) Uniform flow; 6)  $L \ll r$

The given data is

$$Q = 15 \frac{L}{min} \quad R = 225 \cdot mm \quad d = 5 \cdot mm \quad \rho = 999 \frac{kg}{m^3}$$

For each branch

$$V = \frac{1}{2} \cdot \frac{Q}{\frac{\pi}{4} \cdot d^2} \quad V = 6.37 \frac{m}{s} \quad A = \frac{\pi}{4} \cdot d^2 \quad A = 19.6 mm^2$$

The basic equation reduces to a single scalar equation (FOR EACH BRANCH)

$$-\int \vec{r} \times (2\vec{\omega} \times \vec{V} \times \vec{r} + \alpha \times \vec{r}) \cdot \rho dV = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA \quad \text{where } \alpha \text{ is the angular acceleration}$$

But  $\vec{r} \times (2\vec{\omega} \times \vec{V} \times \vec{r} + \alpha \times \vec{r}) = 2 \cdot \omega \cdot r \cdot V + \alpha \cdot r^2$  (r and  $\alpha$  perpendicular)

The volume integral is then

$$-\int \vec{r} \times (2\vec{\omega} \times \vec{V} \times \vec{r} + \alpha \times \vec{r}) \cdot \rho dV = -\left(\omega \cdot R^2 \cdot V + \alpha \cdot \frac{R^3}{3}\right) \cdot \rho \cdot A$$

For the surface integral (FOR EACH BRANCH)

$$\int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA = R \cdot V \cdot \rho \cdot \frac{Q}{2}$$

Combining

$$-\left(\omega \cdot R^2 \cdot V + \alpha \cdot \frac{R^3}{3}\right) \cdot \rho \cdot A = R \cdot V \cdot \rho \cdot \frac{Q}{2} \quad \text{or} \quad \alpha = \frac{3}{A \cdot R^2} \cdot \left(-\omega \cdot V \cdot A \cdot R - \frac{Q \cdot V}{2}\right) \quad (1)$$

The steady state speed ( $\alpha = 0$  in Eq 1) is then when

$$-\omega_{max} \cdot V \cdot A \cdot R - \frac{Q \cdot V}{2} = 0 \quad \text{or} \quad \omega_{max} = -\frac{Q}{2 \cdot A \cdot R}$$


$$\omega_{max} = -28.3 \frac{1}{s} \quad \omega_{max} = -270 \text{ rpm}$$

## Problem 4.190

[Difficulty: 3]

**4.190** Repeat Problem 4.189, but assume a constant retarding torque in the pivot of  $0.5 \text{ N}\cdot\text{m}$ . At what retarding torque would the sprinkler not be able to rotate?

NOTE ERROR: Retarding torque is  $0.05 \text{ N}\cdot\text{m}$ !



**Given:** Data on rotating spray system

**Find:** Differential equation for motion; steady speed; torque to stop

**Solution:**

Basic equation: Rotating CV

$$\begin{aligned} \vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} \\ - \int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV \quad (4.52) \\ = \frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{V}_{xyz} \rho dV + \int_{CS} \vec{r} \times \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \end{aligned}$$

Assumptions: 1) No surface force; 2) Body torques cancel; 3) Steady flow; 5) Uniform flow; 6)  $L \ll r$

The given data is  $Q = 15 \frac{\text{L}}{\text{min}}$        $R = 225 \text{ mm}$        $d = 5 \text{ mm}$        $\rho = 999 \frac{\text{kg}}{\text{m}^3}$        $T = 0.05 \text{ N}\cdot\text{m}$

For each branch  $V = \frac{1}{2} \frac{Q}{\frac{\pi}{4} d^2}$        $V = 6.37 \frac{\text{m}}{\text{s}}$        $A = \frac{\pi}{4} d^2$        $A = 19.6 \text{ mm}^2$

The basic equation reduces to a single scalar equation (FOR EACH BRANCH)

$$\frac{T}{2} - \int \vec{r} \times (2\vec{\omega} \times \vec{V} \times \vec{r} + \alpha \times \vec{r}) \cdot \rho dV = \int \vec{r} \times \vec{V}_{xyz} \rho \cdot \vec{V}_{xyz} dA \quad \text{where } T \text{ is the retarding torque } \alpha \text{ is the angular acceleration}$$

But  $\vec{r} \times (2\vec{\omega} \times \vec{V} \times \vec{r} + \alpha \times \vec{r}) = 2\omega \cdot r \cdot V + \alpha \cdot r^2$       ( $r$  and  $\alpha$  perpendicular)

The volume integral is then  $-\int \vec{r} \times (2\vec{\omega} \times \vec{V} \times \vec{r} + \alpha \times \vec{r}) \cdot \rho dV = -\left(\omega \cdot R^2 \cdot V + \alpha \cdot \frac{R^3}{3}\right) \cdot \rho \cdot A$

For the surface integral (FOR EACH BRANCH)  $\int \vec{r} \times \vec{V}_{xyz} \rho \cdot \vec{V}_{xyz} dA = R \cdot V \cdot \rho \cdot \frac{Q}{2}$

Combining  $\frac{T}{2} - \left(\omega \cdot R^2 \cdot V + \alpha \cdot \frac{R^3}{3}\right) \cdot \rho \cdot A = R \cdot V \cdot \rho \cdot \frac{Q}{2}$       or       $\alpha = \frac{3}{2 \cdot \rho \cdot A \cdot R^3} \cdot (T - 2 \cdot \rho \cdot A \cdot \omega \cdot R^2 \cdot V - \rho \cdot R \cdot Q \cdot V)$       (1)

The steady state speed ( $\alpha = 0$  in Eq 1) is then when  $T - 2 \cdot \rho \cdot A \cdot \omega_{max} \cdot R^2 \cdot V - \rho \cdot R \cdot Q \cdot V = 0$       or       $\omega_{max} = \frac{T - \rho \cdot R \cdot Q \cdot V}{2 \cdot \rho \cdot A \cdot R^2 \cdot V}$


$$\omega_{max} = -24.3 \frac{1}{\text{s}} \quad \omega_{max} = -232 \text{ rpm}$$

For no rotation use  $\alpha = \omega = 0$  in Eq 1, and solve for  $T_{max}$        $T_{max} = \rho \cdot Q \cdot R \cdot V$        $T_{max} = 0.358 \text{ N}\cdot\text{m}$

## Problem 4.191

[Difficulty: 4]

**4.191** Water flows in a uniform flow out of the 2.5-mm slots of the rotating spray system, as shown. The flow rate is 3 L/s. Find (a) the torque required to hold the system stationary and (b) the steady-state speed of rotation after it is released.



**Given:** Data on rotating spray system

**Find:** Torque required to hold stationary; steady-state speed

**Solution:**

Basic equation: Rotating CV

$$\begin{aligned} \vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} \\ - \int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV \quad (4.52) \\ = \frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{V}_{xyz} \rho dV + \int_{CS} \vec{r} \times \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \end{aligned}$$

The given data is  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$        $\delta = 2.5\text{-mm}$        $r_o = 300\text{-mm}$        $Q_{in} = 3 \frac{\text{L}}{\text{s}}$        $r_i = (300 - 250)\text{-mm}$

For no rotation ( $\omega = 0$ ) the basic equation reduces to a single scalar equation

$$T_{shaft} = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA \quad \text{or} \quad T_{shaft} = 2 \cdot \delta \cdot \int_{r_i}^{r_o} r \cdot V \cdot \rho \cdot V dr = 2 \cdot \rho \cdot V^2 \cdot \delta \cdot \int_{r_i}^{r_o} r dr = \rho \cdot V^2 \cdot \delta \cdot (r_o^2 - r_i^2)$$

where  $V$  is the exit velocity with respect to the CV  $V = \frac{Q_{in}}{2 \cdot \delta \cdot (r_o - r_i)}$        $V = 2.40 \frac{\text{m}}{\text{s}}$

Hence  $T_{shaft} = \rho \cdot \left[ \frac{Q_{in}}{2 \cdot \delta \cdot (r_o - r_i)} \right]^2 \cdot \delta \cdot (r_o^2 - r_i^2)$        $T_{shaft} = \frac{\rho \cdot Q_{in}^2}{4 \cdot \delta} \cdot \frac{(r_o + r_i)}{(r_o - r_i)}$

$$T_{shaft} = \frac{1}{4} \times \left( 3 \cdot \frac{\text{L}}{\text{s}} \times \frac{10^{-3} \cdot \text{m}^3}{\text{L}} \right)^2 \times \frac{999 \cdot \text{kg}}{\text{m}^3} \times \frac{1}{0.0025 \cdot \text{m}} \times \frac{(0.3 + 0.05)}{(0.3 - 0.05)} \quad T_{shaft} = 1.26 \cdot \text{N} \cdot \text{m}$$

For the steady rotation speed the equation becomes  $-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA$

The volume integral term  $-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV$  must be evaluated for the CV. The velocity in the CV varies with  $r$ . This

variation can be found from mass conservation

For an infinitesimal CV of length  $dr$  and cross-section  $A$  at radial position  $r$ , if the flow in is  $Q$ , the flow out is  $Q + dQ$ , and the loss through the slot is  $V\delta dr$ . Hence mass conservation leads to

$$(Q + dQ) + V \cdot \delta \cdot dr - Q = 0 \quad dQ = -V \cdot \delta \cdot dr \quad Q(r) = -V \cdot \delta \cdot r + \text{const}$$

At the inlet ( $r = r_i$ )  $Q = Q_i = \frac{Q_{in}}{2}$

Hence  $Q = Q_i + V \cdot \delta \cdot (r_i - r) = \frac{Q_{in}}{2} + \frac{Q_{in}}{2 \cdot \delta \cdot (r_o - r_i)} \cdot \delta \cdot (r_i - r)$   $Q = \frac{Q_{in}}{2} \cdot \left(1 + \frac{r_i - r}{r_o - r_i}\right) = \frac{Q_{in}}{2} \cdot \left(\frac{r_o - r}{r_o - r_i}\right)$

and along each rotor the water speed is  $v(r) = \frac{Q}{A} = \frac{Q_{in}}{2 \cdot A} \cdot \left(\frac{r_o - r}{r_o - r_i}\right)$

Hence the term  $\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV$  becomes

$$-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV = 4 \cdot \rho \cdot A \cdot \omega \cdot \int_{r_i}^{r_o} r \cdot v(r) dr = 4 \cdot \rho \cdot \omega \cdot \int_{r_i}^{r_o} r \cdot \frac{Q_{in}}{2} \cdot \left(\frac{r_o - r}{r_o - r_i}\right) dr$$

or  $-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV = 2 \cdot \rho \cdot Q_{in} \cdot \omega \cdot \int_{r_i}^{r_o} r \cdot \left(\frac{r_o - r}{r_o - r_i}\right) dr = \rho \cdot Q_{in} \cdot \omega \cdot \frac{r_o^3 + r_i^2 \cdot (2 \cdot r_i - 3 \cdot r_o)}{3 \cdot (r_o - r_i)}$

Recall that  $\int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA = \rho \cdot V^2 \cdot \delta \cdot (r_o^2 - r_i^2)$

Hence equation  $-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA$  becomes

$$\rho \cdot Q_{in} \cdot \omega \cdot \frac{r_o^3 + r_i^2 \cdot (2 \cdot r_i - 3 \cdot r_o)}{3 \cdot (r_o - r_i)} = \rho \cdot V^2 \cdot \delta \cdot (r_o^2 - r_i^2)$$

Solving for  $\omega$   $\omega = \frac{3 \cdot (r_o - r_i) \cdot V^2 \cdot \delta \cdot (r_o^2 - r_i^2)}{Q_{in} \cdot [r_o^3 + r_i^2 \cdot (2 \cdot r_i - 3 \cdot r_o)]}$   $\omega = 120 \cdot \text{rpm}$

## Problem 4.192

[Difficulty: 4]

**4.192** If the same flow rate in the rotating spray system of Problem 4.191 is not uniform but instead varies linearly from a maximum at the outer radius to zero at the inner radius, find (a) the torque required to hold it stationary and (b) the steady-state speed of rotation.

**Given:** Data on rotating spray system

**Find:** Torque required to hold stationary; steady-state speed

**Solution:**

Governing equation: Rotating CV

$$\begin{aligned} \vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho \, dV + \vec{T}_{shaft} \\ - \int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho \, dV \quad (4.52) \\ = \frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{V}_{xyz} \rho \, dV + \int_{CS} \vec{r} \times \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \end{aligned}$$

The given data is

$$\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad \delta = 2.5 \cdot \text{mm} \quad r_o = 300 \cdot \text{mm} \quad r_i = (300 - 250) \cdot \text{mm} \quad Q_{in} = 3 \cdot \frac{\text{L}}{\text{s}}$$

For no rotation ( $\omega = 0$ ) this equation reduces to a single scalar equation

$$T_{shaft} = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} \, dA \quad \text{or} \quad T_{shaft} = 2 \cdot \delta \cdot \int_{r_i}^{r_o} r \cdot V \cdot \rho \cdot V \, dr$$

where  $V$  is the exit velocity with respect to the CV. We need to find  $V(r)$ . To do this we use mass conservation, and the fact that the distribution is linear

$$V(r) = V_{max} \cdot \frac{(r - r_i)}{(r_o - r_i)} \quad \text{and} \quad 2 \cdot \frac{1}{2} \cdot V_{max} \cdot (r_o - r_i) \cdot \delta = Q_{in}$$

so

$$V(r) = \frac{Q_{in}}{\delta} \cdot \frac{(r - r_i)}{(r_o - r_i)^2}$$

Hence

$$T_{shaft} = 2 \cdot \rho \cdot \delta \cdot \int_{r_i}^{r_o} r \cdot V^2 \, dr = 2 \cdot \frac{\rho \cdot Q_{in}^2}{\delta} \cdot \int_{r_i}^{r_o} r \cdot \left[ \frac{(r - r_i)}{(r_o - r_i)^2} \right]^2 \, dr \quad T_{shaft} = \frac{\rho \cdot Q_{in}^2 \cdot (r_i + 3 \cdot r_o)}{6 \cdot \delta \cdot (r_o - r_i)}$$

$$T_{shaft} = \frac{1}{6} \times \left( 3 \cdot \frac{\text{L}}{\text{s}} \times \frac{10^{-3} \cdot \text{m}^3}{\text{L}} \right)^2 \times \frac{999 \cdot \text{kg}}{\text{m}^3} \times \frac{1}{0.0025 \cdot \text{m}} \times \frac{(0.05 + 3 \cdot 0.3)}{(0.3 - 0.05)} \quad T_{shaft} = 2.28 \cdot \text{N} \cdot \text{m}$$

For the steady rotation speed the equation becomes

$$- \int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho \, dV = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} \, dA$$

The volume integral term  $-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV$  must be evaluated for the CV. The velocity in the CV varies with  $r$ . This variation can be found from mass conservation

For an infinitesimal CV of length  $dr$  and cross-section  $A$  at radial position  $r$ , if the flow in is  $Q$ , the flow out is  $Q + dQ$ , and the loss through the slot is  $V \delta dr$ . Hence mass conservation leads to

$$(Q + dQ) + V \cdot \delta \cdot dr - Q = 0 \quad dQ = -V \cdot \delta \cdot dr \quad Q(r) = Q_i - \delta \cdot \int_{r_i}^r \frac{Q_{in}}{\delta} \cdot \frac{(r - r_i)}{(r_o - r_i)^2} dr = Q_i - \int_{r_i}^r Q_{in} \cdot \frac{(r - r_i)}{(r_o - r_i)^2} dr$$

At the inlet ( $r = r_i$ )  $Q = Q_i = \frac{Q_{in}}{2}$

Hence  $Q(r) = \frac{Q_{in}}{2} \cdot \left[ 1 - \frac{(r - r_i)^2}{(r_o - r_i)^2} \right]$

and along each rotor the water speed is  $v(r) = \frac{Q}{A} = \frac{Q_{in}}{2 \cdot A} \cdot \left[ 1 - \frac{(r - r_i)^2}{(r_o - r_i)^2} \right]$

Hence the term  $-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV$  becomes  $4 \cdot \rho \cdot A \cdot \omega \cdot \left( \int_{r_i}^{r_o} r \cdot v(r) dr \right) = 4 \cdot \rho \cdot \omega \cdot \int_{r_i}^{r_o} \frac{Q_{in}}{2} \cdot r \cdot \left[ 1 - \frac{(r - r_i)^2}{(r_o - r_i)^2} \right] dr$

or  $2 \cdot \rho \cdot Q_{in} \cdot \omega \cdot \int_{r_i}^{r_o} r \cdot \left[ 1 - \frac{(r - r_i)^2}{(r_o - r_i)^2} \right] dr = \rho \cdot Q_{in} \cdot \omega \cdot \left( \frac{1}{6} \cdot r_o^2 + \frac{1}{3} \cdot r_i \cdot r_o - \frac{1}{2} \cdot r_i^2 \right)$


Recall that  $\int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA = \frac{\rho \cdot Q_{in}^2 \cdot (r_i + 3 \cdot r_o)}{6 \cdot (r_o - r_i) \cdot \delta}$

Hence equation  $-\int \vec{r} \times (2 \cdot \vec{\omega} \times \vec{V}_{xyz}) \cdot \rho dV = \int \vec{r} \times \vec{V}_{xyz} \cdot \rho \cdot \vec{V}_{xyz} dA$

becomes  $\rho \cdot Q_{in} \cdot \omega \cdot \left( \frac{1}{6} \cdot r_o^2 + \frac{1}{3} \cdot r_i \cdot r_o - \frac{1}{2} \cdot r_i^2 \right) = \frac{\rho \cdot Q_{in}^2 \cdot (r_i + 3 \cdot r_o)}{6 \cdot (r_o - r_i) \cdot \delta}$

Solving for  $\omega$   $\omega = \frac{\rho \cdot Q_{in} \cdot (r_i + 3 \cdot r_o)}{\left( r_o^2 + 2 \cdot r_i \cdot r_o - 3 \cdot r_i^2 \right) \cdot (r_o - r_i) \cdot \rho \cdot \delta}$   $\omega = 387 \cdot \text{rpm}$

4.193 A single tube carrying water rotates at constant angular speed, as shown. Water is pumped through the tube at volume flow rate  $Q = 13.8 \text{ L/min}$ . Find the torque that must be applied to maintain the steady rotation of the tube using two methods of analysis: (a) a rotating control volume and (b) a fixed control volume.



Solution: Apply angular momentum principle.  $\left\{ \omega = 33 \frac{1}{3} \frac{\text{rev}}{\text{min}} = 3.49 \text{ rad/s} \right\}$

(a) Rotating CV: use relative velocities, Eq. 4.53:

$$\begin{aligned} \text{Basic equation: } \vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \frac{d\vec{v}}{dt} \rho dV + \vec{T}_{\text{shaft}} &= \int_{CV} \vec{r} \times [z\vec{\omega} \times \vec{v}_{xy3} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \frac{d\vec{v}}{dt} \times \vec{r}] \rho dV \\ &= \int_{CV} \vec{r} \times \vec{v}_{xy3} \rho dV + \int_{CS} \vec{r} \times \vec{v}_{xy3} \rho \vec{v}_{xy3} \cdot d\vec{A} \end{aligned}$$

Assumptions: (1)  $\vec{F}_s = 0$ , (2) Body torques cancel, (3) No  $\hat{k}$  in centrifugal accel, (4)  $\vec{\omega} = 0$ , (5) steady flow, (6)  $\vec{r} \times \vec{v} = 0$

Then

$$T_{\text{shaft}} \hat{k} = \int_{CV} \vec{r} \times (z\vec{\omega} \times \vec{v}) \rho dV = \int_0^R r \hat{i} \times (z\omega \hat{k} \times v \hat{i}) \rho A dr = \omega \rho V A R^2 \hat{k} = \omega \rho Q R^2 \hat{k}$$

$$T_{\text{shaft}} = 3.49 \frac{\text{rad}}{\text{s}} \times 999 \frac{\text{kg}}{\text{m}^3} \times 13.8 \times 10^{-6} \frac{\text{m}^3}{\text{min}} \times (0.3)^2 \text{m}^2 \times \frac{\text{min}}{60 \text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 0.0722 \text{ N} \cdot \text{m}$$

(b) Fixed control volume: use absolute velocities, Eq. 4.47:

$$\text{Basic equation: } \vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \frac{d\vec{v}}{dt} \rho dV + \vec{T}_{\text{shaft}} = \frac{d}{dt} \int_{CV} \vec{r} \times \vec{v} \rho dV + \int_{CS} \vec{r} \times \vec{v} \rho \vec{v}_{xy3} \cdot d\vec{A}$$

Relative to fixed coordinates  $XY$ ,  $\vec{r} = r(\cos\theta \hat{i} + \sin\theta \hat{j})$

$$\vec{v} = v(\cos\theta \hat{i} + \sin\theta \hat{j}) + r\omega(-\sin\theta \hat{i} + \cos\theta \hat{j})$$

$$\vec{r} \times \vec{v} = \begin{vmatrix} \hat{k} & & \\ r \cos\theta & r \sin\theta & 0 \\ v \cos\theta - r\omega \sin\theta & v \sin\theta + r\omega \cos\theta & 0 \end{vmatrix} = \hat{k} (rv \sin\theta \cos\theta + \omega r^2 \cos^2\theta - r v \sin\theta \cos\theta + \omega r^2 \sin^2\theta) = \omega r^2 \hat{k}$$

Thus  $\frac{d}{dt} = 0$  and  $\int_{CS} \vec{r} \times \vec{v} \rho \vec{v}_{xy3} \cdot d\vec{A} = \omega R^2 \hat{k} \{ \rho Q \} = \omega \rho Q R^2 \hat{k}$  and


$$T_{\text{shaft}} \hat{k} = \omega \rho Q R^2 \hat{k} \text{ (as before); } T = 0.0722 \text{ N} \cdot \text{m}$$

{ Note that when applied correctly, either choice of CV produces the same result. }

### Problem 4.194

[Difficulty: 3]

4.194 The lawn sprinkler shown is supplied with water at a rate of 68 L/min. Neglecting friction in the pivot, determine the steady-state angular speed for  $\theta = 30^\circ$ . Plot the steady-state angular speed of the sprinkler for  $0 \leq \theta \leq 90^\circ$ .



Solution: Choose rotating CV. Apply angular momentum principle, Eq. 4.53.

Basic equation:  $\vec{T} \times \vec{F}_S + \int_{CV} \vec{r} \times \frac{d}{dt} \rho dV + \vec{T}_{shaft}$

$$-\int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xy3} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV$$

$$= \frac{d}{dt} \int_{CV} \vec{r} \times \vec{V}_{xy3} \rho dV + \int_{CS} \vec{r} \times \vec{V}_{xy3} \rho \vec{V}_{xy3} \cdot d\vec{A}$$

Assumptions: (1)  $\vec{F}_S = 0$ , (2) Body torques cancel, (3)  $\vec{T}_{shaft} = 0$ , (4) Neglect aerodynamic drag, (5) No  $\hat{k}$  component of centripetal acceleration, (6) Steady flow, (7)  $L \ll R$

Analyze one arm of sprinkler. From geometry,  $\vec{r} = r\hat{r}$  in CV,  $\vec{r} = R\hat{r}$  at jet. Then

$$-\int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xy3}] \rho dV = R\hat{r} \times (-V \sin\theta \hat{j}) \frac{\rho Q}{3} = -\frac{\rho Q R V}{3} \sin\theta \hat{k}$$


$$r\hat{r} \times (2\omega\hat{k} \times V\hat{r}) = 2\omega V r \hat{k}; \quad -\int_{CV} = -\omega V R^2 \rho A \hat{k}$$

Dropping  $\hat{k}$ ,  $-\omega V R^2 \rho A = -\frac{\rho Q R V}{3} \sin\theta$ , so with  $VA = Q/3$ ,

$$\omega = \frac{V}{R} \sin\theta; \quad V = \frac{Q}{3A} = \frac{4Q}{3\pi d^2} = \frac{4}{3\pi} \times \frac{68 \times 10^{-3} \text{ m}^3}{\text{min}} \times \frac{1}{(0.00635)^2 \text{ m}^2} \times \frac{\text{min}}{60 \text{ s}} = 11.9 \text{ m/s}$$

$$\omega = 11.9 \frac{\text{m}}{\text{s}} \times \frac{1}{0.152 \text{ m}} \times \sin\theta = 78.3 \sin\theta \text{ rad/s}$$

Plotting:



For  $\theta = 30^\circ$ ,

$$\omega = 78.3 \sin 30^\circ$$

$$\omega = 39.1 \text{ rad/s}$$

ω


ω  
(θ = 30°)

Plot

### Problem 4.195

[Difficulty: 3]

**4.195** A small lawn sprinkler is shown. The sprinkler operates at a gage pressure of 140 kPa. The total flow rate of water through the sprinkler is 4 L/min. Each jet discharges at 17 m/s (relative to the sprinkler arm) in a direction inclined 30° above the horizontal. The sprinkler rotates about a vertical axis. Friction in the bearing causes a torque of 0.18 N · m opposing rotation. Evaluate the torque required to hold the sprinkler stationary.



Solution: Apply moment of momentum using fixed CV enclosing sprinkler arms.

Basic equation:

$$\vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} = \frac{d}{dt} \int_{CV} \vec{r} \times \vec{V} \rho dV + \int_{CS} \vec{r} \times \vec{V} \rho \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Neglect torque due to surface forces  
 (2) Torques due to body forces cancel by symmetry  
 (3) Steady flow  
 (4) Uniform flow leaving each jet

Then

$$-T_f \hat{k} = (\vec{r} \times \vec{V})_in \left\{ -\rho Q \right\} + 2(\vec{r} \times \vec{V})_jet \left\{ \frac{1}{2} \rho Q \right\}$$

$$(\vec{r} \times \vec{V})_in = 0$$

$$\vec{r} = R \hat{e}_r$$

$$\vec{V} = (R\omega - V_{rel} \cos \alpha) \hat{e}_\theta + V_{rel} \sin \alpha \hat{e}_z$$

The absolute velocity of the jet leaving sprinkler is  $\vec{V} = V_{rel} [\cos \alpha (-\hat{e}_\theta) + \sin \alpha (\hat{e}_z)]$

$$\text{Then } (\vec{r} \times \vec{V})_z = \{ R \hat{e}_r \times V_{rel} [\cos \alpha (-\hat{e}_\theta) + \sin \alpha (\hat{e}_z)] \}_z = \{ R V_{rel} \cos \alpha (-\hat{e}_z) + R V_{rel} \sin \alpha (-\hat{e}_\theta) \}_z$$

$$(\vec{r} \times \vec{V})_z = -R V_{rel} \cos \alpha$$

$$\text{Substituting, } T_{shaft} = T_{ext} - T_f = 2(-R V_{rel} \cos \alpha) \left( \frac{1}{2} \rho Q \right)$$

$$\text{Thus } T_{ext} = T_f - \rho Q R V_{rel} \cos \alpha$$

$$= 0.18 \text{ N} \cdot \text{m} - 999 \frac{\text{kg}}{\text{m}^3} \cdot \frac{4 \text{ L}}{\text{min}} \cdot 0.2 \text{ m} \cdot \frac{17 \text{ m}}{\text{s}} \cdot 0.866 \cdot \frac{\text{m}^3}{1000 \text{ L}} \cdot \frac{\text{min}}{60 \text{ s}} \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$


$$T_{ext} = -0.0161 \text{ N} \cdot \text{m} \text{ (to hold sprinkler stationary)}$$

{ Since  $T_{ext} < 0$ , it must be applied in the minus  $z$  direction to oppose motion. }

### Problem 4.196

[Difficulty: 3]

4.196 In Problem 4.195, calculate the initial acceleration of the sprinkler from rest if no external torque is applied and the moment of inertia of the sprinkler head is  $0.1 \text{ kg} \cdot \text{m}^2$  when filled with water.



Solution: Apply moment of momentum using fixed CV enclosing sprinkler arms.

Basic equation:

$$\vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} = \frac{d}{dt} \int_{CV} \vec{r} \times \vec{v} \rho dV + \int_{CS} \vec{r} \times \vec{v} \rho \vec{v} \cdot d\vec{n}$$

- Assumptions: (1) Neglect torque due to surface forces  
 (2) Torques due to body forces cancel by symmetry  
 (3) Steady flow  
 (4) Uniform flow leaving each jet

Then

$$-T_f \hat{k} = (\vec{r} \times \vec{v})_in \{-\rho Q\} + 2(\vec{r} \times \vec{v})_{jet} \left\{ \frac{1}{2} \rho Q \right\}$$

$$(\vec{r} \times \vec{v})_in \approx 0$$

$$\vec{r} = R \hat{e}_r$$

$$\vec{v} = (R\omega - V_{jet} \cos \alpha) \hat{e}_\theta + V_{jet} \sin \alpha \hat{e}_z$$

The jet leaves the sprinkler at  $\vec{v}(abs) = V_{jet} [\cos \alpha (-\hat{e}_\theta) + \sin \alpha (\hat{e}_z)]$

$$\text{Then } \vec{r} \times \vec{v} = R \hat{e}_r \times V_{jet} [\cos \alpha (-\hat{e}_\theta) + \sin \alpha (\hat{e}_z)] = R V_{jet} [\cos \alpha (-\hat{e}_z) + \sin \alpha (-\hat{e}_\theta)]$$

Summing moments on the rotor,  $\Sigma \vec{M} = I \vec{\omega}$ . Thus

$$\vec{\omega} = \frac{\Sigma T}{I} = \frac{\rho Q R V_{jet} \cos \alpha - T_f}{I}$$

$$= \left[ \frac{999 \text{ kg}}{\text{m}^3} \times \frac{4 \text{ L}}{\text{min}} \times 0.2 \text{ m} \times \frac{17 \text{ m}}{\text{s}} \times 0.866 \times \frac{\text{m}^3}{1000 \text{ L}} \times \frac{\text{min}}{60 \text{ s}} - 0.18 \text{ N} \cdot \text{m} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right] \frac{1}{0.1 \text{ kg} \cdot \text{m}^2}$$

$$\vec{\omega} = 0.161 \text{ rad/s}^2$$


$\vec{\omega}$

{ It is not necessary to use a rotating CV, because at the instant considered,  $\vec{\omega} = 0$  and  $I$  is known.

### Problem 4.197

[Difficulty: 4]

4.197 A small lawn sprinkler is shown (Problem 4.196). The sprinkler operates at an inlet gage pressure of 140 kPa. The total flow rate of water through the sprinkler is 4.0 L/min. Each jet discharges at 17 m/s (relative to the sprinkler arm) in a direction inclined 30° above the horizontal. The sprinkler rotates about a vertical axis. Friction in the bearing causes a torque of 0.18 N · m opposing rotation. Determine the steady speed of rotation of the sprinkler and the approximate area covered by the spray.



Solution: Apply moment of momentum using fixed CV enclosing sprinkler arms.

Basic equation:

$$\vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft} = \frac{d}{dt} \int_{CV} \vec{r} \times \vec{V} \rho dV + \int_{CS} \vec{r} \times \vec{V} \rho \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Neglect torque due to surface forces  
 (2) Torques due to body forces cancel by symmetry  
 (3) Steady flow  
 (4) Uniform flow leaving each jet

Then

$$-T_f \hat{k} = (\vec{r} \times \vec{V})_{in} \{-\rho Q\} + 2(\vec{r} \times \vec{V})_{jet} \left\{ \frac{1}{2} \rho Q \right\}$$

$$(\vec{r} \times \vec{V})_{in} \approx 0$$

$$\vec{r} = R \hat{e}_r$$

$$\vec{V} = (R\omega - V_{rel} \cos \alpha) \hat{e}_\theta + V_{rel} \sin \alpha \hat{e}_z$$

$$(\vec{r} \times \vec{V})_z = R(R\omega - V_{rel} \cos \alpha)$$

or

$$-T_f = R(R\omega - V_{rel} \cos \alpha) \rho Q$$


Thus

$$\omega = \frac{V_{rel} \cos \alpha}{R} - \frac{T_f}{\rho Q R^2}$$

$$= \frac{17 \text{ m/s} \times \cos 30^\circ}{0.2 \text{ m}} - \frac{0.18 \text{ N} \cdot \text{m}}{999 \text{ kg/m}^3 \times 4.0 \text{ L} \times (0.2 \text{ m})^2} \times \frac{1}{60 \text{ s/min}} \times \frac{10^3 \text{ L}}{\text{m}^3} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}$$

$$\omega = 6.04 \text{ rad/s} \text{ or } 57.7 \text{ rpm}$$

Treat the spray outside each nozzle as moving without air resistance:



For each particle,  $\frac{dV_z}{dt} = -g$ , so  $V_z = V_{z0} - gt$

At  $z_{max}$ ,  $V_z = 0$ , so  $t = \frac{V_{z0}}{g}$ ; flight time is  $2t$ .

$$L = 2t V_{abs} \cos \alpha = 2V_{abs} \cos \alpha \left( \frac{V_{abs} \sin \alpha}{g} \right) = \frac{2V_{rel} \sin \alpha (V_{rel} \cos \alpha - R\omega)}{g}$$

$$L = 2 \times \frac{17 \text{ m/s}}{9.81 \text{ m/s}^2} \times \sin 30^\circ \left( \frac{17 \text{ m/s} \times \cos 30^\circ}{9.81 \text{ m/s}^2} - 0.2 \text{ m} \times 6.04 \text{ rad/s} \right) = 23.4 \text{ m}$$

$$R_{spray} = \sqrt{R^2 + L^2} = 23.4 \text{ m}; \quad A_{spray} = \pi R_{spray}^2 = \pi (23.4)^2 \text{ m}^2 = 1720 \text{ m}^2$$

## Problem 4.198

[Difficulty: 4]

**4.198** When a garden hose is used to fill a bucket, water in the bucket may develop a swirling motion. Why does this happen? How could the amount of swirl be calculated approximately?

**Discussion:** Frequently when filling a bucket the hose is held so that the water stream entering the bucket is not vertical. If, in addition, the water stream is off-center in the bucket, then flow entering the bucket has a tangential component of velocity, a swirl component.

The tangential component of the water velocity entering the bucket has a moment-of-momentum (swirl) with respect to a control volume drawn around the stationary bucket. This entering swirl can only be reduced by a torque acting to oppose it. Viscous forces among fluid layers will tend to transfer swirl to other layers so that eventually all of the water in the bucket has a swirling motion.

Swirl in the bucket may be influenced by viscosity. The swirl may tend to nearly a rigid-body motion to minimize viscous forces between annular layers of water in the bucket. The rigid-body motion assumption may be a reasonable model to calculate the total angular momentum (moment-of-momentum) of the water in the bucket.




### Problem 4.199

[Difficulty: 4] Part 1/2

4.199 Water flows at the rate of  $0.15 \text{ m}^3/\text{s}$  through a nozzle assembly that rotates steadily at 30 rpm. The arm and nozzle masses are negligible compared with the water inside.

Determine the torque required to drive the device and the reaction torques at the flange.



Find: (a) Torque required to drive the nozzle assembly  
(b) Reaction torques at the flange.

Solution: Apply the moment of momentum equation to the rotating CV shown.

Basic equation:

$$\vec{r} \times \vec{F}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{\text{shaft}} \approx 0(2)$$

$$-\int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV = \frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{V}_{xyz} \rho dV + \int_{\Delta A} \vec{r} \times \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \approx 0(5)$$

$$\int_{\Delta A} \vec{r} \times \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} = 0(7)$$

- Assumptions: (1) Let  $\vec{T}_{cv}$  represent all torques acting on the CV  
(2) Neglect torque due to body force  
(3) Constant angular speed  
(4) Neglect mass of arm compared to water inside  
(5) Steady flow in CV  
(6) Neglect nozzle length compared to  $L$   
(7)  $\vec{r}$  colinear with  $\vec{V}$ , so  $\vec{r} \times \vec{V}_{xyz} = 0$

Then

$$\vec{T}_{cv} = \int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r})] \rho dV$$

Since  $\vec{\omega} = \omega \hat{k}$  and  $\vec{r} = L(\sin\theta \hat{i} + \cos\theta \hat{k})$ , then

$$\vec{\omega} \times \vec{r} = \omega L \sin\theta \hat{j}$$

$$\vec{\omega} \times (\vec{\omega} \times \vec{r}) = \omega \hat{k} \times \omega L \sin\theta \hat{j} = \omega^2 L \sin\theta (-\hat{i})$$

$$\text{and } \vec{r} \times [\vec{\omega} \times (\vec{\omega} \times \vec{r})] = L(\sin\theta \hat{i} + \cos\theta \hat{k}) \times \omega^2 L \sin\theta (-\hat{i}) = \omega^2 L^2 \sin\theta \cos\theta (-\hat{j})$$

Since  $\vec{V}_{xyz} = V_{cv}(\sin\theta \hat{i} + \cos\theta \hat{k})$ , then

$$2\vec{\omega} \times \vec{V}_{xyz} = 2\omega \hat{k} \times V_{cv}(\sin\theta \hat{i} + \cos\theta \hat{k}) = 2\omega V_{cv} \sin\theta \hat{j}$$

$$\text{and } \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz}] = L(\sin\theta \hat{i} + \cos\theta \hat{k}) \times 2\omega V_{cv} \sin\theta \hat{j} = 2\omega L V_{cv} \sin\theta \hat{k}$$

$$+ 2\omega L V_{cv} \sin\theta \cos\theta (-\hat{i})$$

Substituting and introducing  $d\theta = A d\ell$ ,

$$\vec{T}_{cv} = \int_0^L (-2\omega L V_{cv} \sin\theta \cos\theta \hat{i} - \omega^2 L^2 \sin\theta \cos\theta \hat{j} + 2\omega L V_{cv} \sin^2\theta \hat{k}) \rho A d\ell$$

$$\vec{T}_{cv} = \left[ -\omega L^2 V_{cv} \sin\theta \cos\theta \hat{i} - \frac{\omega^2 L^3}{3} \sin\theta \cos\theta \hat{j} + \omega L^2 V_{cv} \sin^2\theta \hat{k} \right] \rho A$$

The shaft torque needed to maintain steady rotation of the assembly is

$$\begin{aligned} T_{shaft} &= T_{cvz} = \omega L^2 V_{cv} \sin^2\theta \rho A = \omega L^2 \frac{\rho}{A} \sin^2\theta \rho A = \rho Q \omega L^2 \sin^2\theta \\ &= 999 \frac{\text{kg}}{\text{m}^3} \cdot 0.15 \frac{\text{m}^3}{\text{s}} \cdot \frac{30 \text{ rev}}{\text{min}} \cdot (0.5)^2 \text{m}^2 \cdot (0.5)^2 \cdot 2\pi \frac{\text{rad}}{\text{rev}} \cdot \frac{\text{min}}{60 \text{ s}} = \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \end{aligned}$$

$$T_{shaft} = 29.4 \text{ N} \cdot \text{m}$$

$T_{shaft}$

The reaction moments acting on the flange are

$$\begin{aligned} M_x &= -T_{cvx} = \omega L^2 V_{cv} \sin\theta \cos\theta \rho A = \rho Q \omega L^2 \sin\theta \cos\theta \\ &= 999 \frac{\text{kg}}{\text{m}^3} \cdot 0.15 \frac{\text{m}^3}{\text{s}} \cdot \frac{30 \text{ rev}}{\text{min}} \cdot (0.5)^2 \text{m}^2 \cdot (0.5) \cdot (0.866) \cdot 2\pi \frac{\text{rad}}{\text{rev}} \cdot \frac{\text{min}}{60 \text{ s}} = \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \end{aligned}$$

$$M_x = 51.0 \text{ N} \cdot \text{m} \text{ (applied to flange by cv)}$$

$M_x$

$$\begin{aligned} M_y &= -T_{cvy} = \frac{1}{3} \rho \omega^2 L^3 A \sin\theta \cos\theta \\ &= \frac{1}{3} \cdot 999 \frac{\text{kg}}{\text{m}^3} \left[ \frac{30 \text{ rev}}{\text{min}} \cdot 2\pi \frac{\text{rad}}{\text{rev}} \cdot \frac{\text{min}}{60 \text{ s}} \right]^2 \cdot (0.5)^3 \text{m}^3 \cdot \frac{\pi}{4} \cdot (0.1)^2 \text{m}^2 \cdot (0.5) \cdot (0.866) = \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \end{aligned}$$

$$M_y = 1.40 \text{ N} \cdot \text{m} \text{ (applied to flange by cv)}$$


$M_y$

{ Torques due to the masses of water, tube, and nozzle must be considered in the overall design. }

## Problem 4.200

[Difficulty: 4] Part 1/3

**4.200** A pipe branches symmetrically into two legs of length  $L$ , and the whole system rotates with angular speed  $\omega$  around its axis of symmetry. Each branch is inclined at angle  $\alpha$  to the axis of rotation. Liquid enters the pipe steadily, with zero angular momentum, at volume flow rate  $Q$ . The pipe diameter,  $D$ , is much smaller than  $L$ . Obtain an expression for the external torque required to turn the pipe. What additional torque would be required to impart angular acceleration  $\dot{\omega}$ ?



Solution: Apply moment of momentum equation using rotating CV.

Basic equation:  $\vec{r} \times \vec{f}_s + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft}$

$$-\int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV = \frac{d}{dt} \int_{CV} \vec{r} \times \vec{V}_{xyz} \rho dV + \int_{CS} \vec{r} \times \vec{V}_{xyz} (\vec{V}_{xyz} \cdot d\vec{A})$$

- Assumptions: (1) No surface forces  
 (2) Body forces produce no torque about axis (symmetry)  
 (3) Flow steady in rotating frame  
 (4)  $\vec{r}$  and  $\vec{V}_{xyz}$  are colinear:  $\vec{r} \times \vec{V}_{xyz} = 0$

Then 
$$\vec{T}_{shaft} = \int_{CV} \vec{r} \times [2\vec{\omega} \times \vec{V}_{xyz} + \vec{\omega} \times (\vec{\omega} \times \vec{r}) + \dot{\vec{\omega}} \times \vec{r}] \rho dV$$

Using the coordinates above,  $\vec{\omega} = \omega \hat{k}$   $\dot{\vec{\omega}} = \dot{\omega} \hat{k}$

$$\vec{r} = r(\cos\alpha \hat{k} + \sin\alpha \hat{i}) \quad (\text{upper tube})$$

$$\vec{V}_{xyz} = \frac{Q}{2A}(\cos\alpha \hat{k} + \sin\alpha \hat{i}) \quad (\text{upper tube}); \quad A = \frac{\pi D^2}{4}$$

and 
$$\dot{\vec{\omega}} \times \vec{r} = \dot{\omega} r \sin\alpha \hat{j}$$

$$\vec{\omega} \times (\vec{\omega} \times \vec{r}) = \omega \hat{k} \times \omega r \sin\alpha \hat{j} = -\omega^2 r \sin\alpha \hat{i}$$

$$2\vec{\omega} \times \vec{V}_{xyz} = 2\omega \frac{Q}{2A} \sin\alpha \hat{j} = \frac{\omega Q}{A} \sin\alpha \hat{j}$$

Thus for the upper tube,

$$\vec{T}_{shaft} = \int_0^L \left\{ r(\cos\alpha \hat{k} + \sin\alpha \hat{i}) \times \left[ \left( \frac{\omega Q}{A} + \dot{\omega} r \right) \sin\alpha \hat{j} - \omega^2 r \sin\alpha \hat{i} \right] \right\} \rho A dr$$

$$= \int_0^L \left[ \left( \frac{r\omega Q}{A} + \dot{\omega} r^2 \right) (\sin\alpha \cos\alpha) \hat{i} + \left( \frac{r\omega Q}{A} + \dot{\omega} r^2 \right) \sin^2\alpha \hat{k} + \omega^2 r^2 \sin\alpha \cos\alpha (-\hat{j}) \right] \rho A dr$$

$$\vec{T}_{shaft}(\text{upper}) = \left( \frac{L^2 \omega Q}{2A} + \frac{\dot{\omega} L^3}{3} \right) \sin\alpha \cos\alpha \hat{i} + \left( \frac{L^2 \omega Q}{2A} + \frac{\dot{\omega} L^3}{3} \right) \sin^2\alpha \hat{k} + \frac{\omega^2 L^3}{3} \sin\alpha \cos\alpha (-\hat{j}) \rho A$$

For the lower tube,  $\vec{\omega} = \omega \hat{k}$   $\dot{\omega} = \dot{\omega} \hat{k}$

$$\vec{r} = r(\cos\alpha \hat{k} - \sin\alpha \hat{i}) \text{ (lower tube)}$$

$$\vec{v}_{xyz} = \frac{\omega}{2A}(\cos\alpha \hat{k} - \sin\alpha \hat{j}) \text{ (lower tube)}$$

and  $\dot{\omega} \times \vec{r} = -r\dot{\omega} \sin\alpha \hat{j}$

$$\vec{\omega} \times (\vec{\omega} \times \vec{r}) = \omega \hat{k} \times (-r\omega \sin\alpha \hat{j}) = r\omega^2 \sin\alpha \hat{i}$$

$$2\vec{\omega} \times \vec{v}_{xyz} = 2\omega \frac{\omega}{2A}(-\sin\alpha) \left(\frac{\hat{j}}{2}\right) = -\frac{\omega^2}{A} \sin\alpha \hat{j}$$

Thus for the lower tube,

$$\vec{T}_{\text{shaft}} = \int_0^L \left\{ r(\cos\alpha \hat{k} - \sin\alpha \hat{i}) \times \left[ \left(\frac{r\omega}{A} + r\dot{\omega}\right) \sin\alpha (-\hat{j}) + r\omega^2 \sin\alpha \hat{i} \right] \right\} \rho A dr$$

$$= \int_0^L \left[ \left(\frac{r^2\omega}{A} + r^2\dot{\omega}\right) \sin\alpha \cos\alpha \hat{i} + \left(\frac{r\omega}{A} + r\dot{\omega}\right) \sin^2\alpha \hat{k} + r^2\omega^2 \sin\alpha \cos\alpha \hat{j} \right] \rho A dr$$

$$\vec{T}_{\text{shaft (lower)}} = \left[ \frac{L^2\omega}{2A} + \frac{L^3\dot{\omega}}{3} \right] \sin\alpha \cos\alpha \hat{i} + \left[ \frac{L^2\omega}{2A} + \frac{L^3\dot{\omega}}{3} \right] \sin^2\alpha \hat{k} + \frac{L^3\omega^2}{3} \sin\alpha \cos\alpha \hat{j} \quad (\rho A)$$

Summing these expressions gives

$$\vec{T}_{\text{shaft (total)}} = \left( \frac{L^2\omega}{A} + \frac{2L^3\dot{\omega}}{3} \right) \sin^2\alpha \rho A \hat{k}$$

Thus the steady-state portion of the torque is

$$\vec{T}_{\text{shaft (steady state)}} = \left( \frac{L^2\omega}{A} \right) \sin^2\alpha \rho A \hat{k} = L^2 \rho \omega \sin^2\alpha \hat{k}$$

Steady

The additional torque needed to provide angular acceleration,  $\dot{\omega}$ , is

$$\vec{T}_{\text{shaft (acceleration)}} = \frac{2L^3\rho\dot{\omega}A}{3} \sin^2\alpha \hat{k}$$


Acceler

{ Torques of individual tubes about the x and y axes are reacted internally; they must be considered in design of the tube. }

(b) Using fixed CV:

Basic equation:  $\vec{r} \times \vec{F}_3 + \int_{CV} \vec{r} \times \vec{g} \rho dV + \vec{T}_{shaft}$

$$= \frac{\partial}{\partial t} \int_{CV} \vec{r} \times \vec{v} \rho dV + \int_{CS} \vec{r} \times \vec{v} \rho \vec{v} \cdot d\vec{A}$$



- Assumptions:
- (1) No surface forces
  - (2) Body forces symmetric (no moment about X-axis)
  - (3) No change in angular momentum within CV w.r.to time
  - (4) Symmetry in two branches
  - (5) Uniform flow at each cross-section

Then  $\vec{T}_2 = T \hat{i} = \vec{r}_1 \times \vec{v}_1 \{-\rho A\} + \vec{r}_2 \times \vec{v}_2 \{+\rho \frac{Q}{2}\} + \vec{r}_3 \times \vec{v}_3 \{+\rho \frac{Q}{2}\} = 2\vec{r}_2 \times \vec{v}_2 \{+\rho \frac{Q}{2}\}$

or  $\vec{r}_1 = 0 \quad \vec{r}_2 = L \sin \alpha \hat{j}; \quad \vec{v}_2 = \omega L \hat{k}; \quad \vec{r}_2 \times \vec{v}_2 = \omega L^2 \sin^2 \alpha \hat{i}$

$T_{ss} = \rho \omega Q L^2 \sin^2 \alpha$  (steady-state torque)

$T_{ss}$

The torque required for acceleration is  $T_{acc} = I \dot{\omega}$ , where  $I = \int r^2 dm$

For one leg of the branch,  $I = \int r^2 dm = \int_0^L (L \sin \alpha)^2 \rho A ds = \frac{\rho A L^3}{3} \sin^2 \alpha$

(b) Neglect mass of pipe

For both sides,  $I = \frac{2 \rho A L^3}{3} \sin^2 \alpha$ .

Thus

$T_{acc} = \frac{2 \rho \dot{\omega} A L^3}{3} \sin^2 \alpha$  (torque required for angular acceleration)

$T_{acc}$

The total torque that must be applied is

$T = T_{ss} + T_{acc} = \rho \omega Q L^2 \sin^2 \alpha + \frac{2 \rho \dot{\omega} A L^3}{3} \sin^2 \alpha$

$T_{total}$



From y momentum,  $R_y = \rho V_1 \{-\rho V w h_1\} + \rho V_2 \{\rho V w h_2\} + \rho V_3 \{\rho V w h_3\}$

$$V_1 = -V \cos \theta \quad V_2 = 0 \quad V_3 = 0$$

$$R_y = \rho V^2 w h \cos \theta \quad (5) \quad R_y$$

From moment of momentum,

$$\vec{r}' \times \vec{F}_2 = \vec{r}_1 \times \vec{V}_1 \{-\rho V w h_1\} + \vec{r}_2 \times \vec{V}_2 \{\rho V w h_2\} + \vec{r}_3 \times \vec{V}_3 \{\rho V w h_3\}$$

$$\begin{aligned} \vec{r}' &= x' \hat{i} & \vec{r}_1 &= \vec{V}_1 = 0 & \vec{r}_2 &= \frac{h_2}{2} \hat{j} & \vec{r}_3 &= \frac{h_3}{2} \hat{j} \\ \vec{F}_2 &= R_y \hat{j} & & & \vec{V}_2 &= -V \hat{i} & \vec{V}_3 &= V \hat{i} \\ \vec{r}' \times \vec{F}_2 &= x' R_y \hat{k} & \vec{r}_2 \times \vec{V}_2 &= \frac{h_2 V}{2} \hat{k} & \vec{r}_3 \times \vec{V}_3 &= -\frac{h_3 V}{2} \hat{k} \end{aligned}$$

Combining and dropping  $\hat{k}$ ,

$$x' R_y = \frac{1}{2} \rho V^2 w h_2^2 - \frac{1}{2} \rho V^2 w h_3^2 = \frac{1}{2} \rho V^2 w (h_2^2 - h_3^2)$$

or

$$x' = \frac{\rho V^2 w (h_2^2 - h_3^2)}{2 R_y} = \frac{\rho V^2 w (h_2 + h_3)(h_2 - h_3)}{2 R_y}$$

Substituting from Eqs. 3, 4 and 5,

$$x' = \frac{\rho V^2 w h^2 \left(\frac{1 - \sin \theta}{2} + \frac{1 + \sin \theta}{2}\right) \left(\frac{1 - \sin \theta}{2} - \frac{1 + \sin \theta}{2}\right)}{2 \rho V^2 w h \cos \theta} = \frac{h(-\sin \theta)}{2 \cos \theta}$$

or

$$x' = -\frac{h}{2} \tan \theta \quad (6) \quad x'$$

Note that  $x' < 0$ . This means that  $R_y$  must be applied below point 0.

If  $R_y$  is applied at point 0, then  $x' = 0$ . For equilibrium, from Eq. 6,  $\theta = 0$ . Thus if force is applied at point 0, plate will be in equilibrium when perpendicular to jet.






### Problem 4.203

[Difficulty: 2]

4.203 Air at standard conditions enters a compressor at 75 m/s and leaves at an absolute pressure and temperature of 200 kPa and 345 K, respectively, and speed  $V = 125$  m/s. The flow rate is 1 kg/s. The cooling water circulating around the compressor casing removes 18 kJ/kg of air. Determine the power required by the compressor.



Solution: Apply first law of thermodynamics, using CV shown.

$$\text{B.E.} \quad \dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} (e + p\mathbf{v}) \rho \mathbf{v} \cdot d\mathbf{A}$$

$\begin{matrix} \nearrow 0(1) \\ \nearrow 0(2) \end{matrix}$

- Assume: (1)  $\dot{W}_{\text{shear}} = 0$   
 (2) Steady flow  
 (3) Uniform flow at each section  
 (4) Neglect  $\Delta z$   
 (5) Ideal gas,  $p = \rho RT$ ,  $\Delta h = c_p \Delta T$ ;  $c_p = 1.00 \text{ kJ/kg}\cdot\text{K}$   
 (6) From continuity,  $\dot{m}_1 = \dot{m}_2 = \dot{m}$

Then

$$\dot{Q} - \dot{W}_s = \left( u_2 + \frac{V_2^2}{2} + g\Delta z_2 + p_2 v_2 \right) \dot{m} + \left( u_1 + \frac{V_1^2}{2} + g\Delta z_1 + p_1 v_1 \right) \dot{m}$$

$\begin{matrix} \nearrow 0(4) \\ \nearrow 0(4) \end{matrix}$

Note that  $h = u + pv$ , and  $\dot{Q} = \dot{m} \frac{dq}{dm}$ , so

$$\dot{W}_{in} = -\dot{W}_s = \dot{m} \left( \frac{V_2^2 - V_1^2}{2} + h_2 - h_1 - \frac{dq}{dm} \right) = \dot{m} \left[ \frac{V_2^2 - V_1^2}{2} + c_p(T_2 - T_1) - \frac{dq}{dm} \right]$$

or

$$\begin{aligned} \dot{W}_{in} &= 1.0 \frac{\text{kg}}{\text{s}} \left\{ \frac{1}{2} \left[ (125)^2 - (75)^2 \right] \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} \times \frac{\text{kJ}}{1000 \text{ N}\cdot\text{m}} \right. \\ &\quad \left. + 1.00 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} (345 - 288) \text{ K} - (-18 \frac{\text{kJ}}{\text{kg}}) \right\} \frac{\text{kW}\cdot\text{s}}{\text{kJ}} \end{aligned}$$

$$\dot{W}_{in} = 80.0 \text{ kW}$$

$\dot{W}_{in}$

## Problem 4.204

[Difficulty: 3]

**4.204** Compressed air is stored in a pressure bottle with a volume of 100 L, at 500 kPa and 20°C. At a certain instant, a valve is opened and mass flows from the bottle at  $\dot{m} = 0.01$  kg/s. Find the rate of change of temperature in the bottle at this instant

**Given:** Compressed air bottle

**Find:** Rate of temperature change

**Solution:**

Basic equations: Continuity; First Law of Thermodynamics for a CV

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad \dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} \left( u + pv + \frac{V^2}{2} + gz \right) \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Adiabatic 2) No work 3) Neglect KE 4) Uniform properties at exit 5) Ideal gas

Given data  $p = 500 \text{ kPa}$      $T = 20^\circ\text{C}$      $T = 293\text{K}$      $V = 100\text{L}$      $m_{\text{exit}} = 0.01 \cdot \frac{\text{kg}}{\text{s}}$

Also  $R_{\text{air}} = \frac{286.9 \text{ N}\cdot\text{m}}{\text{kg}\cdot\text{K}}$      $c_v = 717.4 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}}$

From continuity  $\frac{\partial}{\partial t} M_{CV} + m_{\text{exit}} = 0$  where  $m_{\text{exit}}$  is the mass flow rate at the exit (Note: Software does not allow a dot!)

$$\frac{\partial}{\partial t} M_{CV} = -m_{\text{exit}}$$

From the 1st law  $0 = \frac{\partial}{\partial t} \int u dM + \left( u + \frac{p}{\rho} \right) \cdot m_{\text{exit}} = u \cdot \left( \frac{\partial}{\partial t} M \right) + M \cdot \left( \frac{\partial}{\partial t} u \right) + \left( u + \frac{p}{\rho} \right) \cdot m_{\text{exit}}$

Hence  $u \cdot (-m_{\text{exit}}) + M \cdot c_v \cdot \frac{dT}{dt} + u \cdot m_{\text{exit}} + \frac{p}{\rho} \cdot m_{\text{exit}} = 0$      $\frac{dT}{dt} = -\frac{m_{\text{exit}} \cdot p}{M \cdot c_v \cdot \rho}$

But  $M = \rho \cdot V$  (where V is volume) so  $\frac{dT}{dt} = -\frac{m_{\text{exit}} \cdot p}{V \cdot c_v \cdot \rho^2}$

For air  $\rho = \frac{p}{R_{\text{air}} \cdot T}$      $\rho = 500 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg}\cdot\text{K}}{286.9 \cdot \text{N}\cdot\text{m}} \times \frac{1}{(20 + 273) \cdot \text{K}}$      $\rho = 5.95 \frac{\text{kg}}{\text{m}^3}$

Hence  $\frac{dT}{dt} = -0.01 \cdot \frac{\text{kg}}{\text{s}} \times 500 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{100 \cdot \text{L}} \times \frac{\text{L}}{10^{-3} \cdot \text{m}^3} \times \frac{\text{kg}\cdot\text{K}}{717.4 \cdot \text{N}\cdot\text{m}} \times \left( \frac{\text{m}^3}{5.95 \cdot \text{kg}} \right)^2 = -1.97 \cdot \frac{\text{K}}{\text{s}} = -1.97 \cdot \frac{\text{C}}{\text{s}}$

## Problem 4.205

[Difficulty: 3]

**4.205** A centrifugal water pump with a 0.1-m-diameter inlet and a 0.1-m-diameter discharge pipe has a flow rate of  $0.02 \text{ m}^3/\text{s}$ . The inlet pressure is 0.2 m Hg vacuum and the exit pressure is 240 kPa. The inlet and outlet sections are located at the same elevation. The measured power input is 6.75 kW. Determine the pump efficiency.

**Given:** Data on centrifugal water pump

**Find:** Pump efficiency

**Solution:**

Basic equations:

$$\begin{aligned} \dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} \\ = \frac{\partial}{\partial t} \int_{\text{CV}} e \rho dV + \int_{\text{CS}} \left( u + pv + \frac{V^2}{2} + gz \right) \rho \vec{V} \cdot d\vec{A} \end{aligned} \quad (4.56)$$

$$\Delta p = SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h \quad \eta = \frac{W_s}{P_{\text{in}}}$$

Available data:

$D_1 = 0.1 \cdot \text{m}$	$D_2 = 0.1 \cdot \text{m}$	$Q = 0.02 \cdot \frac{\text{m}^3}{\text{s}}$	$P_{\text{in}} = 6.75 \cdot \text{kW}$
$\rho = 1000 \frac{\text{kg}}{\text{m}^3}$	$SG_{\text{Hg}} = 13.6$	$h_1 = -0.2 \cdot \text{m}$	$p_2 = 240 \cdot \text{kPa}$

Assumptions: 1) Adiabatic 2) Only shaft work 3) Steady 4) Neglect  $\Delta u$  5)  $\Delta z = 0$  6) Incompressible 7) Uniform flow

Then

$$-W_s = \left( p_1 \cdot v_1 + \frac{V_1^2}{2} \right) \cdot (-m_{\text{rate}}) + \left( p_2 \cdot v_2 + \frac{V_2^2}{2} \right) \cdot (m_{\text{rate}})$$

Since  $m_{\text{rate}} = \rho \cdot Q$  and  $V_1 = V_2$  (from continuity)

$$-W_s = \rho \cdot Q \cdot (p_2 \cdot v_2 - p_1 \cdot v_1) = Q \cdot (p_2 - p_1)$$

$$p_1 = \rho_{\text{Hg}} \cdot g \cdot h \quad \text{or} \quad p_1 = SG_{\text{Hg}} \cdot \rho \cdot g \cdot h_1 \quad p_1 = -26.7 \cdot \text{kPa}$$


$$W_s = Q \cdot (p_1 - p_2) \quad W_s = -5.33 \cdot \text{kW} \quad \text{The negative sign indicates work in}$$

$$\eta = \frac{|W_s|}{P_{\text{in}}} \quad \eta = 79.0\%$$

### Problem 4.206

[Difficulty: 2]

4.206 A turbine is supplied with  $0.6 \text{ m}^3/\text{s}$  of water from a  $0.3\text{-m}$ -diameter pipe; the discharge pipe has a  $0.4 \text{ m}$  diameter. Determine the pressure drop across the turbine if it delivers  $60 \text{ kW}$ .



Solution: Apply continuity, energy equations, using CV shown.

Basic equations: 
$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

$$\dot{Q} - \dot{W}_s - \dot{W}_{shear} - \dot{W}_{other} = \frac{\partial}{\partial t} \int_{CV} \rho p dV + \int_{CS} \left( p + \frac{\rho V^2}{2} + \rho g z \right) \rho \vec{V} \cdot d\vec{A}$$

- Assumptions:
- (1) Steady flow
  - (2) Uniform flow at each section
  - (3) Incompressible flow
  - (4)  $\dot{Q} = 0$
  - (5)  $\dot{W}_{shear} = 0$  by choice of CV;  $\dot{W}_{other} = 0$
  - (6) Neglect  $\Delta u$
  - (7) Neglect  $\Delta z$

Then

$$0 = \{-\rho V_1 A_1\} + \{\rho V_2 A_2\} \quad \text{or} \quad V_2 = V_1 \frac{A_1}{A_2} = V_1 \left( \frac{D_1}{D_2} \right)^2$$

and

$$-\dot{W}_s = \left( \frac{V_1^2}{2} + p_1 v \right) \{-\rho V_1 A_1\} + \left( \frac{V_2^2}{2} + p_2 v \right) \{\rho V_2 A_2\}$$

$$-\dot{W}_s = -\left[ \frac{V_1^2 - V_2^2}{2} + (p_1 - p_2)v \right] \rho Q = -\left\{ \frac{V_1^2}{2} \left[ 1 - \left( \frac{D_1}{D_2} \right)^4 \right] + (p_1 - p_2)v \right\} \rho Q$$

or

$$p_1 - p_2 = \frac{1}{v} \left\{ \frac{\dot{W}_s}{\rho Q} - \frac{V_1^2}{2} \left[ 1 - \left( \frac{D_1}{D_2} \right)^4 \right] \right\} = \frac{\dot{W}_s}{Q} - \frac{\rho V_1^2}{2} \left[ 1 - \left( \frac{D_1}{D_2} \right)^4 \right]$$

But  $V_1 = \frac{Q}{A_1} = \frac{0.6 \text{ m}^3/\text{s}}{\frac{\pi}{4} (0.3)^2 \text{ m}^2} = 8.49 \text{ m/s}$ , and  $\dot{W}_s = \dot{W}_{out} = 60 \text{ kW}$ , so

$$p_1 - p_2 = (60 \text{ kW}) \frac{10^3 \text{ N}\cdot\text{m}}{\text{kw}\cdot\text{s}} \cdot \frac{\text{s}}{0.6 \text{ m}^3} - \frac{1}{2} \cdot 999 \frac{\text{kg}}{\text{m}^3} \cdot \frac{(8.49)^2 \text{ m}^2}{\text{s}^2} \left[ 1 - \left( \frac{0.3}{0.4} \right)^4 \right] \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}}$$


$$p_1 - p_2 = 75.4 \text{ kPa}$$

$p_1 - p_2$

### Problem 4.207

[Difficulty: 2]

4.207 Air enters a compressor at 14 psia, 80°F with negligible speed and is discharged at 70 psia, 500°F with a speed of 500 ft/s. If the power input is 3200 hp and the flow rate is 20 lbm/s, determine the rate of heat transfer.



Find: Heat transfer, in Btu/lbm.

Solution: Apply energy equation to CV shown.

Basic equations:  $p = \rho RT$ ,  $\Delta h = c_p \Delta T$

$$\dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} (u + pv + \frac{V^2}{2} + gz) \rho \vec{V} \cdot d\vec{A}$$

$\begin{matrix} =0(2) & =0(2) & =0(2) & & =0(5) \\ \uparrow & \uparrow & \uparrow & & \uparrow \\ \dot{Q} & -\dot{W}_s & -\dot{W}_{\text{shear}} & -\dot{W}_{\text{other}} & \end{matrix}$

- Assumptions: (1) Ideal gas, constant specific heat  
 (2)  $\dot{W}_{\text{shear}} = 0$  by choice of CV;  $\dot{W}_{\text{other}} = 0$   
 (3) Steady flow  
 (4) Uniform flow at each section  
 (5) Neglect  $\Delta z$   
 (6)  $V_1 \approx 0$

By definition  $h \equiv u + pv$ , so

$$\dot{Q} - \dot{W}_s = (h_1 + \frac{V_1^2}{2}) \dot{m} + (h_2 + \frac{V_2^2}{2}) \dot{m} = \dot{m} \left[ \frac{V_2^2}{2} + c_p (T_2 - T_1) \right]$$

or

$$\frac{\delta Q}{dm} = \frac{\dot{Q}}{\dot{m}} = \frac{\dot{W}_s}{\dot{m}} + \frac{V_2^2}{2} + c_p (T_2 - T_1)$$

Noting  $\dot{W}_s = -3200 \text{ hp}$ , so

$$\frac{\delta Q}{dm} = -3200 \text{ hp} \times \frac{2545 \text{ Btu}}{\text{hp} \cdot \text{hr}} \times \frac{\text{s}}{20 \text{ lbm}} \times \frac{\text{hr}}{3600 \text{ s}} + 0.240 \frac{\text{Btu}}{\text{lbm} \cdot \text{F}} \times (500 - 80) \text{ F} \\ + \frac{(500)^2 \text{ ft}^2}{2 \text{ s}^2} \times \frac{\text{lb} \cdot \text{s}^{-2}}{\text{slug} \cdot \text{ft}} \times \frac{\text{slug}}{32.2 \text{ lbm}} \times \frac{\text{Btu}}{778 \text{ ft} \cdot \text{lb} \cdot \text{F}}$$

$$\frac{\delta Q}{dm} = -7.32 \text{ Btu/lbm}$$

$$\frac{\delta Q}{dm}$$

Therefore heat transfer is out of CV, since  $\delta Q/dm < 0$ . The rate of heat transfer is


$$\dot{Q} = -7.32 \frac{\text{Btu}}{\text{lbm}} \times \frac{20 \text{ lbm}}{\text{s}} = -146 \text{ Btu/s}$$

$$\dot{Q}$$

### Problem 4.208

[Difficulty: 2]

**4.208** Air is drawn from the atmosphere into a turbo-machine. At the exit, conditions are 500 kPa (gage) and 130°C. The exit speed is 100 m/s and the mass flow rate is 0.8 kg/s. Flow is steady and there is no heat transfer. Compute the shaft work interaction with the surroundings.



Solution: Apply energy equation, using CV shown.

Basic equations:  $p = \rho RT$ ,  $\Delta h = c_p \Delta T$

$$\overset{=0(1)}{\dot{q}} - \overset{=0(2)}{\dot{w}_s} - \overset{=0(2)}{\dot{w}_{shear}} - \overset{=0(3)}{\dot{w}_{other}} = \frac{\partial}{\partial t} \int_{CV} \rho e dV + \int_{CS} (u + pv + \frac{V^2}{2} + g\Delta z) \rho \vec{V} \cdot d\vec{A} \quad \approx 0(5)$$

- Assumptions:
- (1) Ideal gas, constant specific heat
  - (2)  $\dot{w}_{shear} = 0$  by choice of CV;  $\dot{w}_{other} = 0$
  - (3) Steady flow
  - (4) Uniform flow at each section
  - (5) Neglect  $\Delta z$
  - (6)  $V_1 = 0$
  - (7)  $\dot{q} = 0$

By definition,  $h \equiv u + pv$ , so

$$-\dot{w}_s = (h_1 + \frac{V_1^2}{2}) \{-\dot{m}\} + (h_2 + \frac{V_2^2}{2}) \{\dot{m}\} = \dot{m} (h_2 - h_1 + \frac{V_2^2}{2})$$

or

$$-\dot{w}_s = \dot{m} (h_2 - h_1 + \frac{V_2^2}{2}) = \dot{m} [c_p (T_2 - T_1) + \frac{V_2^2}{2}]$$

$$= 0.8 \frac{\text{kg}}{\text{s}} \left[ 1.00 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} (403 - 288) \text{K} \right]$$

$$+ \frac{(100)^2 \text{ m}^2}{\text{s}^2} \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \cdot \frac{\text{kJ}}{10^3 \text{ N} \cdot \text{m}} \left] \frac{\text{kW} \cdot \text{s}}{\text{kJ}}$$

$$-\dot{w}_s = 96.0 \text{ kW} \quad \text{or} \quad \dot{w}_s = -96.0 \text{ kW}$$


{Power is into CV because  $\dot{w}_s < 0$ .}

$\dot{w}_s$

## Problem 4.209

[Difficulty: 3]

**4.209** All major harbors are equipped with fire boats for extinguishing ship fires. A 3-in.-diameter hose is attached to the discharge of a 15-hp pump on such a boat. The nozzle attached to the end of the hose has a diameter of 1 in. If the nozzle discharge is held 10 ft above the surface of the water, determine the volume flow rate through the nozzle, the maximum height to which the water will rise, and the force on the boat if the water jet is directed horizontally over the stern.



**Given:** Data on fire boat hose system

**Find:** Volume flow rate of nozzle; Maximum water height; Force on boat

**Solution:**

Basic equation: First Law of Thermodynamics for a CV

$$\dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} = \frac{\partial}{\partial t} \int_{\text{CV}} e \rho dV + \int_{\text{CS}} \left( u + pv + \frac{V^2}{2} + gz \right) \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Neglect losses 2) No work 3) Neglect KE at 1 4) Uniform properties at exit 5) Incompressible 6)  $p_{\text{atm}}$  at 1 and 2

Hence for CV (a) 
$$-\dot{W}_s = \left( \frac{V_2^2}{2} + g \cdot z_2 \right) \cdot \dot{m}_{\text{exit}} \quad \dot{m}_{\text{exit}} = \rho \cdot V_2 \cdot A_2 \quad \text{where } \dot{m}_{\text{exit}} \text{ is mass flow rate (Note: Software cannot render a dot!)}$$

Hence, for  $V_2$  (to get the flow rate) we need to solve 
$$\left( \frac{1}{2} \cdot V_2^2 + g \cdot z_2 \right) \cdot \rho \cdot V_2 \cdot A_2 = -\dot{W}_s \quad \text{which is a cubic for } V_2!$$

To solve this we could ignore the gravity term, solve for velocity, and then check that the gravity term is in fact minor. Alternatively we could manually iterate, or use a calculator or Excel, to solve. The answer is

Hence the flow rate is 
$$Q = V_2 \cdot A_2 = V_2 \cdot \frac{\pi \cdot D_2^2}{4} \quad Q = 114 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} \times \left( \frac{1}{12} \cdot \text{ft} \right)^2 \quad Q = 0.622 \cdot \frac{\text{ft}^3}{\text{s}} \quad Q = 279 \cdot \text{gpm}$$

To find  $z_{\text{max}}$ , use the first law again to (to CV (b)) to get 
$$-\dot{W}_s = g \cdot z_{\text{max}} \cdot \dot{m}_{\text{exit}}$$

$$z_{\text{max}} = -\frac{\dot{W}_s}{g \cdot \dot{m}_{\text{exit}}} = -\frac{\dot{W}_s}{g \cdot \rho \cdot Q} \quad z_{\text{max}} = 15 \cdot \text{hp} \times \frac{550 \cdot \text{ft} \cdot \text{lbf}}{\text{s}} \times \frac{\text{s}^2}{1 \cdot \text{hp}} \times \frac{\text{ft}^3}{32.2 \cdot \text{ft}} \times \frac{1}{1.94 \cdot \text{slug}} \times \frac{\text{s}}{0.622 \cdot \text{ft}^3} \times \frac{\text{slug} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}} \quad z_{\text{max}} = 212 \cdot \text{ft}$$

For the force in the x direction when jet is horizontal we need x momentum

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{\text{CV}} u \rho dV + \int_{\text{CS}} u \rho \vec{V} \cdot d\vec{A}$$


Then 
$$R_x = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2) = 0 + V_2 \cdot \rho \cdot Q \quad R_x = \rho \cdot Q \cdot V_2$$

$$R_x = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 0.622 \cdot \frac{\text{ft}^3}{\text{s}} \times 114 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = 138 \cdot \text{lbf}$$

### Problem 4.210

[Difficulty: 3]

4.210 A pump draws water from a reservoir through a 150-mm-diameter suction pipe and delivers it to a 75-mm-diameter discharge pipe. The end of the suction pipe is 2 m below the free surface of the reservoir. The pressure gage on the discharge pipe (2 m above the reservoir surface) reads 170 kPa. The average speed in the discharge pipe is 3 m/s. If the pump efficiency is 75 percent, determine the power required to drive it.



Solution: Apply first law to cv shown, noting that flow enters with negligible velocity at section ①.

Basic equation:

$$\dot{Q} - \dot{W}_{\text{shaft}} - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} = \frac{\partial}{\partial t} \int_{cv} \rho \mathbf{v} \cdot d\mathbf{V} + \int_{cs} \left( e + \frac{P}{\rho} \right) \rho \mathbf{v} \cdot d\mathbf{A}$$

Assumptions: (1)  $\dot{W}_{\text{shear}} = \dot{W}_{\text{other}} = 0$

(2) steady flow

(3)  $V_1 = 0$

(4)  $z_1 = 0$

(5)  $P_1 = 0$  (gage)

(6) Uniform flow at each section

(7) Incompressible flow;  $V_1 A_1 = V_2 A_2$

$$e = u + \frac{V^2}{2} + gz$$

Then

$$\dot{Q} - \dot{W}_s = \left( u_1 + \frac{V_1^2}{2} + gz_1 + \frac{P_1}{\rho} \right) \{-\dot{m}\} + \left( u_2 + \frac{V_2^2}{2} + gz_2 + \frac{P_2}{\rho} \right) \{\dot{m}\}$$

or

$$-\dot{W}_s = \dot{m} \left[ \frac{P_2}{\rho} + \frac{V_2^2}{2} + gz_2 + (u_2 - u_1 - \frac{\delta Q}{dm}) \right]$$

Obtain the ideal or minimum power input by neglecting thermal effects.

Thus

$$-\dot{W}_{s, \text{ideal}} = \dot{m} \left[ \frac{P_2}{\rho} + \frac{V_2^2}{2} + gz_2 \right]$$

For the system,

$$\dot{m} = \rho V_2 A_2 = 999 \frac{\text{kg}}{\text{m}^3} \cdot \frac{3 \text{ m}}{\text{s}} \cdot \frac{\pi}{4} (0.075)^2 \text{ m}^2 = 13.2 \text{ kg/s}$$

and

$$-\dot{W}_{s, \text{ideal}} = 13.2 \frac{\text{kg}}{\text{s}} \left[ \frac{1.70 \times 10^5 \text{ N}}{\text{m}^2} \cdot \frac{\text{m}^3}{999 \text{ kg}} + \frac{1}{2} \left( \frac{3 \text{ m}}{\text{s}} \right)^2 \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} + \frac{9.81 \text{ m}}{\text{s}^2} \cdot 2 \text{ m} \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right]$$

$$\dot{W}_{s, \text{ideal}} = -2560 \frac{\text{N} \cdot \text{m}}{\text{s}} \cdot \frac{\text{kW} \cdot \text{s}}{10^3 \text{ N} \cdot \text{m}} = -2.56 \text{ kW}$$

Finally


$$\dot{W}_{s, \text{actual}} = \frac{\dot{W}_{s, \text{ideal}}}{\eta} = \frac{-2.56 \text{ kW}}{0.75} = -3.41 \text{ kW}$$

$\dot{W}_{s, \text{actual}}$

## Problem 4.211

[Difficulty: 4]

**4.211** The total mass of the helicopter-type craft shown is 1000 kg. The pressure of the air is atmospheric at the outlet. Assume the flow is steady and one-dimensional. Treat the air as incompressible at standard conditions and calculate, for a hovering position, the speed of the air leaving the craft and the minimum power that must be delivered to the air by the propeller.



**Given:** Data on helicopter-type craft

**Find:** Air speed; Minimum power needed

**Solution:**

Basic equation: Continuity, z momentum; First Law of Thermodynamics for a CV; Bernoulli; Ideal gas

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad F_z = F_{S_z} + F_{B_z} = \frac{\partial}{\partial t} \int_{CV} w \rho dV + \int_{CS} w \rho \vec{V} \cdot d\vec{A}$$

$$= \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} \left( u + pv + \frac{V^2}{2} + gz \right) \rho \vec{V} \cdot d\vec{A} \quad \frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const} \quad p = \rho \cdot R_{\text{air}} \cdot T \quad \Delta h = c_p \cdot \Delta T$$

Assumptions: 1) Atmospheric at exit 2) Standard air 3) Uniform properties at exit 4) Incompressible

Given data  $M = 1000 \cdot \text{kg}$      $p = 101 \cdot \text{kPa}$      $T = 15^\circ \text{C}$      $D_o = 4.5 \cdot \text{m}$      $D_i = 4.25 \cdot \text{m}$      $R_{\text{air}} = \frac{286.9 \cdot \text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}}$

Then  $A_1 = \frac{\pi}{4} \cdot D_o^2$      $A_1 = 15.9 \text{ m}^2$      $A_2 = \frac{\pi}{4} \cdot (D_o^2 - D_i^2)$      $A_2 = 1.72 \text{ m}^2$      $\rho = \frac{p}{R_{\text{air}} \cdot T}$      $\rho = 1.222 \frac{\text{kg}}{\text{m}^3}$

From continuity  $0 = (-\rho \cdot V_1 \cdot A_1) + (\rho \cdot V_2 \cdot A_2)$     or     $V_1 = \frac{A_2}{A_1} \cdot V_2$

From momentum  $-\rho_1 g \cdot A_1 - M \cdot g = w_1 \cdot (-\rho \cdot V_1 \cdot A_1) + w_2 \cdot (\rho \cdot V_2 \cdot A_2)$      $w_1 = -V_1$      $w_2 = -V_2$     and     $\rho \cdot V_1 \cdot A_1 = \rho \cdot V_2 \cdot A_2$

Then  $-\rho_1 g \cdot A_1 - M \cdot g = V_1 \cdot \rho \cdot V_1 \cdot A_1 - V_2 \cdot \rho \cdot V_2 \cdot A_2 = -\rho \cdot V_2 \cdot A_2 \cdot (V_2 - V_1)$

For this flow Bernoulli also applies between the atmosphere and location 1     $p_{\text{atm}} = p_1 + \frac{1}{2} \cdot \rho \cdot V_1^2$      $p_1 g = -\frac{1}{2} \cdot \rho \cdot V_1^2$

Using continuity  $p_1 g \cdot A_1 = -\frac{1}{2} \cdot \rho \cdot V_1^2 \cdot A_1 = -\frac{1}{2} \cdot \rho \cdot V_2 \cdot A_2 \cdot V_1 = -\frac{1}{2} \cdot \rho \cdot V_2^2 \cdot A_2 \cdot \frac{A_2}{A_1}$

Substituting into the momentum equation and using continuity

$$\frac{1}{2} \cdot \rho \cdot V_2^2 \cdot A_2 \cdot \frac{A_2}{A_1} - M \cdot g = -\rho \cdot V_2^2 \cdot A_2 \cdot \left(1 - \frac{V_1}{V_2}\right) = -\rho \cdot V_2^2 \cdot A_2 \cdot \left(1 - \frac{A_2}{A_1}\right) \text{ or } M \cdot g = \rho \cdot V_2^2 \cdot A_2 \cdot \left(1 - \frac{1}{2} \cdot \frac{A_2}{A_1}\right)$$

Hence

$$V_2 = \sqrt{\frac{M \cdot g}{\rho \cdot A_2 \cdot \left(1 - \frac{1}{2} \cdot \frac{A_2}{A_1}\right)}} \quad \text{Substituting values} \quad V_2 = 70.3 \frac{\text{m}}{\text{s}}$$

For power we use the First Law

$$\begin{aligned} & \dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} \\ &= \frac{\partial}{\partial t} \int_{\text{CV}} e \rho dV + \int_{\text{CS}} \left(u + pv + \frac{V^2}{2} + gz\right) \rho \vec{V} \cdot d\vec{A} \end{aligned}$$

We have additional assumptions 5)  $pv = \text{const}$  6) Neglect  $\Delta z$

Then

$$-W_s = m_{\text{rate}} \cdot \left(\frac{V_2^2 - V_1^2}{2}\right) + m_{\text{rate}} \cdot \left(u_2 - u_1 - \frac{dQ}{dm}\right)$$

The last term is non-mechanical energy; the minimum possible work is when this is zero. Hence

$$-W_s = -W_{\text{min}} = m_{\text{rate}} \cdot \left(\frac{V_2^2 - V_1^2}{2}\right) = m_{\text{rate}} \cdot \frac{V_2^2}{2} \cdot \left[1 - \left(\frac{V_1}{V_2}\right)^2\right] = \frac{\rho \cdot A_2 \cdot V_2^2}{2} \cdot \left[1 - \left(\frac{A_2}{A_1}\right)^2\right]$$


$$W_{\text{min}} = \frac{\rho \cdot A_2 \cdot V_2^3}{2} \cdot \left[1 - \left(\frac{A_2}{A_1}\right)^2\right] \quad \text{Using given data} \quad W_{\text{min}} = 360 \cdot \text{kW}$$

### Problem 4.212

[Difficulty: 4] Part 1/2

4.212 Liquid flowing at high speed in a wide, horizontal open channel under some conditions can undergo a hydraulic jump, as shown. For a suitably chosen control volume, the flows entering and leaving the jump may be considered uniform with

hydrostatic pressure distributions (see Example 4.7). Consider a channel of width  $w$ , with water flow at  $D_1 = 0.6$  m and  $V_1 = 5$  m/s. Show that in general,  $D_2 = D_1 \left[ \sqrt{1 + 8V_1^2/gD_1} - 1 \right] / 2$ .



Evaluate the change in mechanical energy through the hydraulic jump. If heat transfer to the surroundings is negligible, determine the change in water temperature through the jump.

Solution: Apply continuity, x component of momentum, and energy equations using CV shown.

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

$F_{3x} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} V_x \rho dV + \int_{CS} V_x \rho \vec{V} \cdot d\vec{A}$

$\dot{Q} - \dot{W}_s - \dot{W}_{shear} - \dot{W}_{other} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} (e + p\vec{r}) \rho \vec{V} \cdot d\vec{A}$

Assumptions: (1) Steady flow

(2) Incompressible flow

(3) Uniform flow at each section

(4) Hydrostatic pressure distribution at sections ①, ②.

so  $p = \rho g (D - z)$

(5) Neglect friction force,  $F_f$ , on CV

(6)  $\dot{Q} = 0$

(7)  $\dot{W}_s = \dot{W}_{shear} = \dot{W}_{other} = 0$

(8)  $F_{Bx} = 0$ , since channel is horizontal

$e = u + \frac{V^2}{2} + gz$

From continuity,

$0 = \{-\rho V_1 A_1\} + \{\rho V_2 A_2\} = -\rho V_1 w D_1 + \rho V_2 w D_2 ; V_1 D_1 = V_2 D_2$

From momentum,

$F_{3x} = \underbrace{\rho g \frac{D_1}{2} w D_1 - \rho g \frac{D_2}{2} w D_2}_{\text{hydrostatic forces}} = V_{x1} \{-\rho V_1 w D_1\} + V_{x2} \{\rho V_2 w D_2\}$

$V_{x1} = V_1 \qquad V_{x2} = V_2$

or

$\frac{\rho}{2} (D_1^2 - D_2^2) = V_1 D_1 (V_2 - V_1) = V_1^2 D_1 \left( \frac{V_2}{V_1} - 1 \right) = V_1^2 D_1 \left( \frac{D_1}{D_2} - 1 \right)$

or

$\frac{\rho}{2} (D_1 + D_2) (D_1 - D_2) = V_1^2 \frac{D_1}{D_2} (D_1 - D_2)$

Thus  $g \frac{D_1}{2} \left(1 + \frac{D_2}{D_1}\right) = V_1^2 \frac{D_1}{D_2}$  or  $\frac{D_2}{D_1} \left(1 + \frac{D_2}{D_1}\right) = \frac{2V_1^2}{g D_1}$  or  $\left(\frac{D_2}{D_1}\right)^2 + \frac{D_2}{D_1} - \frac{2V_1^2}{g D_1} = 0$

Using the quadratic equation,

$$\frac{D_2}{D_1} = \frac{1}{2} \left[ -1 \pm \sqrt{1 + \frac{8V_1^2}{g D_1}} \right] \quad \text{or} \quad D_2 = \frac{D_1}{2} \left[ \sqrt{1 + \frac{8V_1^2}{g D_1}} - 1 \right] \quad \leftarrow D_2$$

Solving for  $D_2$

$$D_2 = \frac{1}{2} \times 0.6 \text{ m} \left[ \sqrt{1 + \frac{8 \times (5)^2 \text{ m}^2/\text{s}^2}{9.81 \text{ m/s}^2 \times 0.6 \text{ m}}} - 1 \right] = 1.47 \text{ m}$$

$$V_2 = \frac{D_1}{D_2} V_1 = \frac{0.6}{1.47} \times 5 \text{ m/s} = 2.04 \text{ m/s}$$

From the energy equation, with  $e_{\text{mech}} = \frac{V^2}{2} + gz + \frac{p}{\rho}$ , and  $dA = w dz$ , the mechanical energy fluxes are

$$\text{mef}_1 = \int_0^{D_1} \left[ \frac{V_1^2}{2} + gz + \frac{1}{\rho} \rho g (D-z) \right] \rho V_1 w dz = \left( \frac{V_1^2}{2} + g D_1 \right) \rho V_1 w D_1$$

$$\text{mef}_2 = \int_0^{D_2} \left[ \frac{V_2^2}{2} + gz + \frac{1}{\rho} \rho g (D-z) \right] \rho V_2 w dz = \left( \frac{V_2^2}{2} + g D_2 \right) \rho V_2 w D_2$$

and

$$\Delta \text{mef} = \text{mef}_2 - \text{mef}_1 = \left[ \frac{V_2^2 - V_1^2}{2} + g (D_2 - D_1) \right] \rho V_1 w D_1, \text{ since } V_1 D_1 = V_2 D_2$$

Thus  $\frac{\Delta \text{mef}}{\dot{m}} = \frac{1}{2} [V_2^2 - V_1^2 + 2g(D_2 - D_1)]$

$$\frac{\Delta \text{mef}}{\dot{m}} = \frac{1}{2} \left[ (2.04)^2 \frac{\text{m}^2}{\text{s}^2} - (5)^2 \frac{\text{m}^2}{\text{s}^2} + 2 \times 9.81 \frac{\text{m}}{\text{s}^2} (1.47 - 0.6) \text{ m} \right] \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = -1.88 \text{ N} \cdot \text{m} / \text{kg} \quad \leftarrow \frac{\Delta \text{mef}}{\dot{m}}$$

From the energy equation,

$$0 = \left[ u_1 + \frac{V_1^2}{2} + gz + \frac{1}{\rho} \rho g (D-z) \right] \{-\rho V_1 w D_1\} + \left[ u_2 + \frac{V_2^2}{2} + gz + \frac{1}{\rho} \rho g (D-z) \right] \{\rho V_2 w D_2\}$$

or

$$0 = (u_2 - u_1) \dot{m} + \Delta \text{mef}$$

Thus

$$u_2 - u_1 = C_V (T_2 - T_1) = - \frac{\Delta \text{mef}}{\dot{m}}$$

$$\Delta T = T_2 - T_1 = - \frac{\Delta \text{mef}}{\dot{m} C_V} = - \left( -1.88 \frac{\text{N} \cdot \text{m}}{\text{kg}} \right) \frac{\text{kg} \cdot \text{K}}{1 \text{ kcal}} \times \frac{\text{kcal}}{4187 \text{ J}} = 4.49 \times 10^{-4} \text{ K} \quad \leftarrow \Delta T$$

{ This small temperature change would be almost impossible to measure. }

## Problem 5.1

[Difficulty: 1]

**5.1** Which of the following sets of equations represent possible two-dimensional incompressible flow cases?

(a)  $u = 2x^2 + y^2 - x^2y; v = x^3 + x(y^2 - 4y)$

(b)  $u = 2xy - x^2y; v = 2xy - y^2 + x^2$

(c)  $u = x^2t + 2y; v = xt^2 - yt$

(d)  $u = (2x + 4y)xt; v = -3(x + y)yt$

**Given:** The list of velocity fields provided above

**Find:** Which of these fields possibly represent two-dimensional, incompressible flow

**Solution:** We will check these flow fields against the continuity equation

**Governing Equations:** 
$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:** (1) Incompressible flow ( $\rho$  is constant)  
(2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to: 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$$

This is the criterion against which we will check all of the flow fields.

a)  $u(x, y, t) = 2x^2 + y^2 - x^2y$      $v(x, y, t) = x^3 + x(y^2 - 4y)$      $\frac{\partial}{\partial x} u(x, y, t) = 4x - 2xy$      $\frac{\partial}{\partial y} v(x, y, t) = x(2y - 4)$

Hence 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v \neq 0 \quad \text{INCOMPRESSIBLE}$$

b)  $u(x, y, t) = 2xy - x^2y$      $v(x, y, t) = 2xy - y^2 + x^2$      $\frac{\partial}{\partial x} u(x, y, t) = 2y - 2xy$      $\frac{\partial}{\partial y} v(x, y, t) = 2x - 2y$

Hence 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v \neq 0 \quad \text{NOT INCOMPRESSIBLE}$$

c)  $u(x, y, t) = x^2t + 2y$      $v(x, y, t) = xt^2 - yt$      $\frac{\partial}{\partial x} u(x, y, t) = 2tx$      $\frac{\partial}{\partial y} v(x, y, t) = -t$

Hence 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v \neq 0 \quad \text{NOT INCOMPRESSIBLE}$$

d)  $u(x, y, t) = (2x + 4y)xt$      $v(x, y, t) = -3(x + y)yt$

$$\frac{\partial}{\partial x} u(x, y, t) = t(2x + 4y) + 2tx$$
     $\frac{\partial}{\partial y} v(x, y, t) = -t(3x + 3y) - 3ty$

Hence 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v \neq 0 \quad \text{NOT INCOMPRESSIBLE}$$

## Problem 5.2

[Difficulty: 2]

**5.2** Which of the following sets of equations represent possible three-dimensional incompressible flow cases?

(a)  $u = 2y^2 + 2xz$ ;  $v = -2yz + 6x^2yz$ ;  $w = 3x^2z^2 + x^3y^4$

(b)  $u = xyz$ ;  $v = -xyz$ ;  $w = z^2(x^2 - y)$

(c)  $u = x^2 + 2y + z^2$ ;  $v = x - 2y + z$ ;  $w = -2xz + y^2 + 2z$

**Given:** Velocity fields

**Find:** Which are 3D incompressible

**Solution:** We will check these flow fields against the continuity equation

**Governing Equation:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumption:** Incompressible flow ( $\rho$  is constant)

Based on the assumption, the continuity equation reduces to: 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v + \frac{\partial}{\partial z}w = 0$$

This is the criterion against which we will check all of the flow fields.

a)  $u(x, y, z, t) = 2 \cdot y^2 + 2 \cdot x \cdot z$        $v(x, y, z, t) = -2 \cdot y \cdot z + 6 \cdot x^2 \cdot y \cdot z$        $w(x, y, z, t) = 3 \cdot x^2 \cdot z^2 + x^3 \cdot y^4$

$$\frac{\partial}{\partial x}u(x, y, z, t) = 2 \cdot z$$

$$\frac{\partial}{\partial y}v(x, y, z, t) = 6 \cdot x^2 \cdot z - 2 \cdot z$$

$$\frac{\partial}{\partial z}w(x, y, z, t) = 6 \cdot x^2 \cdot z$$

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v + \frac{\partial}{\partial z}w \neq 0$$
 **NOT INCOMPRESSIBLE**

b)  $u(x, y, z, t) = x \cdot y \cdot z \cdot t$        $v(x, y, z, t) = -x \cdot y \cdot z \cdot t^2$        $w(x, y, z, t) = z^2 \cdot (x \cdot t^2 - y \cdot t)$

$$\frac{\partial}{\partial x}u(x, y, z, t) = t \cdot y \cdot z$$

$$\frac{\partial}{\partial y}v(x, y, z, t) = -t^2 \cdot x \cdot z$$

$$\frac{\partial}{\partial z}w(x, y, z, t) = 2 \cdot z \cdot (t^2 \cdot x - t \cdot y)$$

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v + \frac{\partial}{\partial z}w \neq 0$$
 **NOT INCOMPRESSIBLE**

c)  $u(x, y, z, t) = x^2 + 2 \cdot y + z^2$        $v(x, y, z, t) = x - 2 \cdot y + z$        $w(x, y, z, t) = -2 \cdot x \cdot z + y^2 + 2 \cdot z$

$$\frac{\partial}{\partial x}u(x, y, z, t) = 2 \cdot x$$

$$\frac{\partial}{\partial y}v(x, y, z, t) = -2$$

$$\frac{\partial}{\partial z}w(x, y, z, t) = 2 - 2 \cdot x$$

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v + \frac{\partial}{\partial z}w = 0$$
 **INCOMPRESSIBLE**

### Problem 5.3

[Difficulty: 2]

**5.3** For a flow in the  $xy$  plane, the  $x$  component of velocity is given by  $u = Ax(y - B)$ , where  $A = 1 \text{ ft}^{-1} \cdot \text{s}^{-1}$ ,  $B = 6 \text{ ft}$ , and  $x$  and  $y$  are measured in feet. Find a possible  $y$  component for steady, incompressible flow. Is it also valid for unsteady, incompressible flow? Why? How many  $y$  components are possible?

**Given:**  $x$  component of velocity

**Find:**  $y$  component for incompressible flow; Valid for unsteady?; How many  $y$  components?

**Solution:**

Basic equation: 
$$\frac{\partial}{\partial x}(\rho \cdot u) + \frac{\partial}{\partial y}(\rho \cdot v) + \frac{\partial}{\partial z}(\rho \cdot w) + \frac{\partial}{\partial t}\rho = 0$$

Assumption: Incompressible flow; flow in  $x$ - $y$  plane

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0 \quad \text{or} \quad \frac{\partial}{\partial y}v = -\frac{\partial}{\partial x}u = -\frac{\partial}{\partial x}[A \cdot x \cdot (y - B)] = -A \cdot (y - B)$$

Integrating 
$$v(x, y) = -\int A \cdot (y - B) dy = -A \cdot \left( \frac{y^2}{2} - B \cdot y \right) + f(x)$$

This basic equation is valid for steady and unsteady flow ( $t$  is not explicit)

There are an infinite number of solutions, since  $f(x)$  can be any function of  $x$ . The simplest is  $f(x) = 0$

$$v(x, y) = -A \cdot \left( \frac{y^2}{2} - B \cdot y \right)$$

$$v(x, y) = 6 \cdot y - \frac{y^2}{2}$$

## Problem 5.4

[Difficulty: 1]

**5.4** The three components of velocity in a velocity field are given by  $u = Ax + By + Cz$ ,  $v = Dx + Ey + Fz$ , and  $w = Gx + Hy + Jz$ . Determine the relationship among the coefficients  $A$  through  $J$  that is necessary if this is to be a possible incompressible flow field.

**Given:** The velocity field provided above

**Find:** The conditions under which this fields could represent incompressible flow

**Solution:** We will check this flow field against the continuity equation

**Governing Equations:** 
$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:** (1) Incompressible flow ( $\rho$  is constant)

Based on the assumption listed, the continuity equation reduces to: 
$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0$$

Calculating the partial derivatives of the velocity components: 
$$\frac{\partial u}{\partial x} = A \quad \frac{\partial v}{\partial y} = E \quad \frac{\partial w}{\partial z} = J$$

Applying this information to the continuity equation we get the necessary condition for incompressible flow:

$$A + E + J = 0$$

(B, C, D, F, G, and H are arbitrary)

## Problem 5.5

[Difficulty: 2]

**5.5** For a flow in the  $xy$  plane, the  $x$  component of velocity is given by  $u = 3x^2y - y^3$ . Determine a possible  $y$  component for steady, incompressible flow. Is it also valid for unsteady, incompressible flow? Why? How many possible  $y$  components are there?

**Given:**  $x$  component of velocity

**Find:**  $y$  component for incompressible flow; Valid for unsteady? How many  $y$  components?

**Solution:**

**Basic Equation:** 
$$\frac{\partial}{\partial x}(\rho \cdot u) + \frac{\partial}{\partial y}(\rho \cdot v) + \frac{\partial}{\partial z}(\rho \cdot w) + \frac{\partial}{\partial t}\rho = 0$$

**Assumptions:** Incompressible flow ( $\rho$  is constant)  
Flow is only in the  $x$ - $y$  plane

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0 \quad \text{or} \quad \frac{\partial}{\partial y}v = -\frac{\partial}{\partial x}u = -\frac{\partial}{\partial x}(3 \cdot x^2 \cdot y - y^3) = -6 \cdot x \cdot y$$

Integrating 
$$v(x, y) = -\int 6 \cdot x \cdot y \, dy = -3 \cdot x \cdot y^2 + f(x)$$

This basic equation is valid for steady and unsteady flow ( $t$  is not explicit)

There are an infinite number of solutions, since  $f(x)$  can be any function of  $x$ . The simplest is  $f(x) = 0$   $v(x, y) = -3 \cdot x \cdot y^2$

## Problem 5.6

[Difficulty: 2]

**5.6** The  $x$  component of velocity in a steady, incompressible flow field in the  $xy$  plane is  $u = A/x$ , where  $A = 2 \text{ m}^2/\text{s}$ , and  $x$  is measured in meters. Find the simplest  $y$  component of velocity for this flow field.

**Given:** The  $x$ -component of velocity in a steady, incompressible flow field

**Find:** The simplest  $y$ -component of velocity for this flow field

**Solution:** We will check this flow field against the continuity equation

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:**

- (1) Incompressible flow ( $\rho$  is constant)
- (2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$

The partial of  $u$  with respect to  $x$  is:  $\frac{\partial u}{\partial x} = -\frac{A}{x^2}$  Therefore from continuity, we have  $\frac{\partial v}{\partial y} = -\frac{\partial u}{\partial x} = \frac{A}{x^2}$

Integrating this expression will yield the  $y$ -component of velocity:  $v = \int \frac{A}{x^2} dy + f(x) = \frac{A \cdot y}{x} + f(x)$

The simplest version of this velocity component would result when  $f(x) = 0$ :

$$v = \frac{A \cdot y}{x}$$

## Problem 5.7

[Difficulty: 2]

**5.7** The  $y$  component of velocity in a steady, incompressible flow field in the  $xy$  plane is  $v = Axy(x^2 - y^2)$ , where  $A = 3 \text{ m}^{-3}\text{s}^{-1}$  and  $x$  and  $y$  are measured in meters. Find the simplest  $x$  component of velocity for this flow field.

**Given:**  $y$  component of velocity

**Find:**  $x$  component for incompressible flow; Simplest  $x$  components?

**Solution:**

**Basic equation:** 
$$\frac{\partial}{\partial x}(\rho \cdot u) + \frac{\partial}{\partial y}(\rho \cdot v) + \frac{\partial}{\partial z}(\rho \cdot w) + \frac{\partial}{\partial t}\rho = 0$$

**Assumptions:** Incompressible flow ( $\rho$  is constant)  
Flow is only in the  $x$ - $y$  plane

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0 \quad \text{or} \quad \frac{\partial}{\partial x}u = -\frac{\partial}{\partial y}v = -\frac{\partial}{\partial y}[A \cdot x \cdot y \cdot (x^2 - y^2)] = -[A \cdot x \cdot (x^2 - y^2) - A \cdot x \cdot y \cdot 2 \cdot y]$$

Integrating 
$$u(x, y) = -\int A \cdot (x^3 - 3 \cdot x \cdot y^2) dx = -\frac{1}{4} \cdot A \cdot x^4 + \frac{3}{2} \cdot A \cdot x^2 \cdot y^2 + f(y)$$

This basic equation is valid for steady and unsteady flow ( $t$  is not explicit)

There are an infinite number of solutions, since  $f(y)$  can be any function of  $y$ . The simplest is  $f(y) = 0$

$$u(x, y) = \frac{3}{2} \cdot A \cdot x^2 \cdot y^2 - \frac{1}{4} \cdot A \cdot x^4$$

$$u(x, y) = \frac{9}{2} \cdot x^2 \cdot y^2 - \frac{3}{4} \cdot x^4$$

## Problem 5.8

[Difficulty: 3]

**5.8** The  $y$  component of velocity in a steady incompressible flow field in the  $xy$  plane is

$$v = \frac{2xy}{(x^2 + y^2)^2}$$

Show that the simplest expression for the  $x$  component of velocity is

$$u = \frac{1}{(x^2 + y^2)} - \frac{2y^2}{(x^2 + y^2)^2}$$

**Given:**  $y$  component of velocity

**Find:**  $x$  component for incompressible flow; Simplest  $x$  component

**Solution:**

Basic equation: 
$$\frac{\partial}{\partial x}(\rho \cdot u) + \frac{\partial}{\partial y}(\rho \cdot v) + \frac{\partial}{\partial z}(\rho \cdot w) + \frac{\partial}{\partial t}\rho = 0$$

Assumption: Incompressible flow; flow in  $x$ - $y$  plane

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0 \quad \text{or} \quad \frac{\partial}{\partial x}u = -\frac{\partial}{\partial y}v = -\frac{\partial}{\partial y}\left[\frac{2 \cdot x \cdot y}{(x^2 + y^2)^2}\right] = -\left[\frac{2 \cdot x \cdot (x^2 - 3 \cdot y^2)}{(x^2 + y^2)^3}\right]$$

Integrating 
$$u(x, y) = -\int \left[\frac{2 \cdot x \cdot (x^2 - 3 \cdot y^2)}{(x^2 + y^2)^3}\right] dx = \frac{x^2 - y^2}{(x^2 + y^2)^2} + f(y) = \frac{x^2 + y^2 - 2 \cdot y^2}{(x^2 + y^2)^2} + f(y)$$

$$u(x, y) = \frac{1}{x^2 + y^2} - \frac{2 \cdot y^2}{(x^2 + y^2)^2} + f(y)$$

The simplest form is 
$$u(x, y) = \frac{1}{x^2 + y^2} - \frac{2 \cdot y^2}{(x^2 + y^2)^2}$$

Note: Instead of this approach we could have verified that  $u$  and  $v$  satisfy continuity

$$\frac{\partial}{\partial x}\left[\frac{1}{x^2 + y^2} - \frac{2 \cdot y^2}{(x^2 + y^2)^2}\right] + \frac{\partial}{\partial y}\left[\frac{2 \cdot x \cdot y}{(x^2 + y^2)^2}\right] = 0 \quad \text{However, this does not verify the solution is the simplest.}$$

## Problem 5.9

[Difficulty: 2]

**5.9** The  $x$  component of velocity in a steady incompressible flow field in the  $xy$  plane is  $u = Ae^{x/b} \cos(y/b)$ , where  $A = 10$  m/s,  $b = 5$  m, and  $x$  and  $y$  are measured in meters. Find the simplest  $y$  component of velocity for this flow field.

**Given:**  $x$  component of velocity

**Find:**  $y$  component for incompressible flow; Valid for unsteady? How many  $y$  components?

**Solution:**

Basic equation: 
$$\frac{\partial}{\partial x}(\rho \cdot u) + \frac{\partial}{\partial y}(\rho \cdot v) + \frac{\partial}{\partial z}(\rho \cdot w) + \frac{\partial}{\partial t}\rho = 0$$

Assumption: Incompressible flow; flow in  $x$ - $y$  plane

Hence 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0 \quad \text{or} \quad \frac{\partial}{\partial y}v = -\frac{\partial}{\partial x}u = -\frac{\partial}{\partial x}\left(A \cdot e^{\frac{x}{b}} \cdot \cos\left(\frac{y}{b}\right)\right) = -\left(\frac{A}{b} \cdot e^{\frac{x}{b}} \cdot \cos\left(\frac{y}{b}\right)\right)$$

Integrating 
$$v(x, y) = -\int \frac{A}{b} \cdot e^{\frac{x}{b}} \cdot \cos\left(\frac{y}{b}\right) dy = -A \cdot e^{\frac{x}{b}} \cdot \sin\left(\frac{y}{b}\right) + f(x)$$

This basic equation is valid for steady and unsteady flow ( $t$  is not explicit)

There are an infinite number of solutions, since  $f(x)$  can be any function of  $x$ . The simplest is  $f(x) = 0$

$$v(x, y) = -A \cdot e^{\frac{x}{b}} \cdot \sin\left(\frac{y}{b}\right)$$

$$v(x, y) = -10 \cdot e^{\frac{x}{5}} \cdot \sin\left(\frac{y}{5}\right)$$

## Problem 5.10

[Difficulty: 2]

**5.10** A crude approximation for the  $x$  component of velocity in an incompressible laminar boundary layer is a linear variation from  $u = 0$  at the surface ( $y = 0$ ) to the freestream velocity,  $U$ , at the boundary-layer edge ( $y = \delta$ ). The equation for the profile is  $u = Uy/\delta$ , where  $\delta = cx^{1/2}$  and  $c$  is a constant. Show that the simplest expression for the  $y$  component of velocity is  $v = uy/4x$ . Evaluate the maximum value of the ratio  $v/U$ , at a location where  $x = 0.5$  m and  $\delta = 5$  mm.

**Given:** Approximate profile for a laminar boundary layer:

$$u = \frac{U \cdot y}{\delta} \quad \delta = c \cdot \sqrt{x} \quad (c \text{ is constant})$$

**Find:** (a) Show that the simplest form of  $v$  is

$$v = \frac{u}{4} \cdot \frac{y}{x}$$

(b) Evaluate maximum value of  $v/u$  where  $\delta = 5$  mm and  $x = 0.5$  m

**Solution:** We will check this flow field using the continuity equation

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:**

- (1) Incompressible flow ( $\rho$  is constant)
- (2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$

The partial of  $u$  with respect to  $x$  is:  $\frac{\partial u}{\partial x} = \frac{\partial u}{\partial \delta} \frac{d\delta}{dx} = -\frac{Uy}{\delta^2} \times \frac{1}{2} c x^{-\frac{1}{2}} = -\frac{Uy}{2c x^{\frac{3}{2}}}$  Therefore from continuity:  $\frac{\partial v}{\partial y} = -\frac{\partial u}{\partial x} = \frac{Uy}{2c x^{\frac{3}{2}}}$

Integrating this expression will yield the  $y$ -component of velocity: 
$$v = \int \frac{U \cdot y}{2 \cdot c \cdot x^{\frac{3}{2}}} dy + f(x) = \frac{U \cdot y^2}{4 \cdot c \cdot x^{\frac{3}{2}}} + f(x)$$

Now due to the no-slip condition at the wall ( $y = 0$ ) we get  $f(x) = 0$ . Thus: 
$$v = \frac{U \cdot y^2}{4 \cdot c \cdot x^{\frac{3}{2}}} = \frac{U \cdot y}{c \cdot x^{\frac{1}{2}}} \cdot \frac{y}{4 \cdot x} = \frac{u \cdot y}{4 \cdot x} \text{ (Q.E.D.)} \quad v = \frac{u}{4} \cdot \frac{y}{x}$$

The maximum value of  $v/U$  is where  $y = \delta$ : 
$$v_{\text{ratmax}} = \frac{v}{u} = \frac{\delta}{4 \cdot x} \quad v_{\text{ratmax}} = \frac{5 \times 10^{-3} \cdot \text{m}}{4 \times 0.5 \cdot \text{m}} \quad v_{\text{ratmax}} = 0.0025$$

## Problem 5.11

[Difficulty: 3]


**5.11** A useful approximation for the  $x$  component of velocity in an incompressible laminar boundary layer is a parabolic variation from  $u = 0$  at the surface ( $y = 0$ ) to the freestream velocity,  $U$ , at the edge of the boundary layer ( $y = \delta$ ). The equation for the profile is  $u/U = 2(y/\delta) - (y/\delta)^2$ , where  $\delta = cx^{1/2}$  and  $c$  is a constant. Show that the simplest expression for the  $y$  component of velocity is

$$\frac{v}{U} = \frac{\delta}{x} \left[ \frac{1}{2} \left( \frac{y}{\delta} \right)^2 - \frac{1}{3} \left( \frac{y}{\delta} \right)^3 \right]$$

Plot  $v/U$  versus  $y/\delta$  to find the location of the maximum value of the ratio  $v/U$ . Evaluate the ratio where  $\delta = 5$  mm and  $x = 0.5$  m.

**Given:** Approximate (parabolic) profile for a laminar boundary layer:

$$\frac{u}{U} = 2 \cdot \left( \frac{y}{\delta} \right) - \left( \frac{y}{\delta} \right)^2 \quad \delta = c \cdot \sqrt{x} \quad (c \text{ is constant})$$



**Find:** (a) Show that the simplest form of  $v$  for incompressible flow is

$$\frac{v}{U} = \frac{\delta}{x} \cdot \left[ \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{3} \cdot \left( \frac{y}{\delta} \right)^3 \right]$$

(b) Plot  $v/U$  versus  $y/\delta$

(c) Evaluate maximum value of  $v/U$  where  $\delta = 5$  mm and  $x = 0.5$  m

**Solution:** We will check this flow field using the continuity equation

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:**

- (1) Incompressible flow ( $\rho$  is constant)
- (2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$

The partial of  $u$  with respect to  $x$  is:  $\frac{\partial u}{\partial x} = \frac{\partial u}{\partial \delta} \frac{d\delta}{dx} = U \left[ -\frac{2y}{\delta^2} + \frac{2y^2}{\delta^3} \right] \times \frac{1}{2} c x^{-1/2}$  Now since  $\delta = c \cdot x^{1/2}$   $\frac{1}{x^{1/2}} = \frac{c}{\delta}$  and thus

$$\frac{\partial u}{\partial x} = \frac{Uc^2}{\delta} \left[ -\frac{y}{\delta^2} + \frac{y^2}{\delta^3} \right] = \frac{Uc^2}{\delta^2} \left[ -\left( \frac{y}{\delta} \right) + \left( \frac{y}{\delta} \right)^2 \right] \quad \text{Therefore from continuity: } \frac{\partial v}{\partial y} = -\frac{\partial u}{\partial x} = \frac{Uc^2}{\delta^2} \left[ \left( \frac{y}{\delta} \right) - \left( \frac{y}{\delta} \right)^2 \right]$$

Integrating this expression will yield the  $y$ -component of velocity:  $v = \int \frac{U \cdot c^2}{\delta} \cdot \left[ \left( \frac{y}{\delta} \right) - \left( \frac{y}{\delta} \right)^2 \right] dy + f(x)$  Evaluating:


$$v = \frac{U \cdot c^2}{\delta^2} \cdot \left( \frac{y^2}{2 \cdot \delta} - \frac{y^3}{3 \cdot \delta^2} \right) + f(x) = \frac{U \cdot c^2}{\delta} \cdot \left[ \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{3} \cdot \left( \frac{y}{\delta} \right)^3 \right] + f(x) \quad \text{Since } \delta = c \cdot x^{1/2} \quad c^2 = \frac{\delta^2}{x} \quad \text{Thus:}$$

$$v = U \cdot \frac{\delta}{x} \cdot \left[ \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{3} \cdot \left( \frac{y}{\delta} \right)^3 \right] + f(x) \quad \text{Now due to the no-slip condition at the wall (y = 0) we get } f(x) = 0. \text{ Therefore:}$$

$$\frac{v}{U} = \frac{\delta}{x} \cdot \left[ \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{3} \cdot \left( \frac{y}{\delta} \right)^3 \right] \quad (\text{Q.E.D.}) \quad \frac{v}{U} = \frac{\delta}{x} \cdot \left[ \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{3} \cdot \left( \frac{y}{\delta} \right)^3 \right]$$

Plotting this relationship shows:

Assuming  $x = 0.5 \text{ m}$  and  $\delta = 5 \text{ mm}$



The maximum value of  $v/U$  is where  $y = \delta$ :  $v_{\text{ratmax}} = \frac{v}{U} = \frac{\delta}{x} \cdot \left( \frac{1}{2} - \frac{1}{3} \right) = \frac{\delta}{6 \cdot x} \quad v_{\text{ratmax}} = \frac{5 \times 10^{-3} \cdot \text{m}}{6 \times 0.5 \cdot \text{m}} \quad v_{\text{ratmax}} = 0.00167$

## Problem 5.12

[Difficulty: 3]

**5.12** A useful approximation for the  $x$  component of velocity in an incompressible laminar boundary layer is a sinusoidal variation from  $u = 0$  at the surface ( $y = 0$ ) to the freestream velocity,  $U$ , at the edge of the boundary layer ( $y = \delta$ ). The equation for the profile is  $u = U \sin(\pi y/2\delta)$ , where  $\delta = cx^{1/2}$  and  $c$  is a constant. Show that the simplest expression for the  $y$  component of velocity is

$$\frac{v}{U} = \frac{1}{\pi} \frac{\delta}{x} \left[ \cos\left(\frac{\pi y}{2\delta}\right) + \left(\frac{\pi y}{2\delta}\right) \sin\left(\frac{\pi y}{2\delta}\right) - 1 \right]$$

Plot  $u/U$  and  $v/U$  versus  $y/\delta$ , and find the location of the maximum value of the ratio  $v/U$ . Evaluate the ratio where  $x = 0.5$  m and  $\delta = 5$  mm.

**Given:** Approximate (sinusoidal) profile for a laminar boundary layer:

$$\frac{u}{U} = \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \quad \delta = c \cdot \sqrt{x} \quad (c \text{ is constant})$$

**Find:** (a) Show that the simplest form of  $v$  for incompressible flow is

$$\frac{v}{U} = \frac{1}{\pi} \cdot \frac{\delta}{x} \cdot \left[ \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) - 1 \right]$$

(b) Plot  $v/U$  versus  $y/\delta$

(c) Evaluate maximum value of  $v/U$  where  $\delta = 5$  mm and  $x = 0.5$  m

**Solution:** We will check this flow field using the continuity equation

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:**

- (1) Incompressible flow ( $\rho$  is constant)
- (2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$

The partial of  $u$  with respect to  $x$  is:  $\frac{\partial u}{\partial x} = \frac{\partial u}{\partial \delta} \frac{d\delta}{dx} = U \left[ -\frac{\pi y}{2\delta^2} \cos\left(\frac{\pi y}{2\delta}\right) \right] \times \frac{1}{2} cx^{-1/2} = -\frac{\pi U c y}{4\delta^2} x^{-1/2} \cos\left(\frac{\pi y}{2\delta}\right)$

Now since  $\delta = c \cdot x^{1/2}$   $\frac{1}{x} \cdot \frac{1}{2} x^{-1/2} = \frac{c}{\delta}$  and thus  $\frac{\partial u}{\partial x} = -\frac{\pi U c^2 y}{4\delta^3} \cos\left(\frac{\pi y}{2\delta}\right)$  Therefore from continuity:  $\frac{\partial v}{\partial y} = \frac{\pi U c^2 y}{4\delta^3} \cos\left(\frac{\pi y}{2\delta}\right)$

Integrating this expression will yield the  $y$ -component of velocity:  $v = \int \frac{\pi \cdot U \cdot c^2 \cdot y}{4 \cdot \delta^3} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) dy + f(x)$  Evaluating:

$v = \frac{\pi \cdot U \cdot c^2}{4 \cdot \delta^3} \cdot \int y \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) dy + f(x) = \frac{\pi \cdot U \cdot c^2}{4 \cdot \delta^3} \cdot \left( \frac{2 \cdot \delta \cdot y}{\pi} \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \frac{4 \cdot \delta^2}{\pi^2} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \right) + f(x)$  Simplifying this expression:

$$v = \frac{U \cdot c^2}{2 \cdot \delta^2} \cdot \left( y \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \frac{2 \cdot \delta}{\pi} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \right) + f(x) \quad \text{Since } \delta = c \cdot x^{\frac{1}{2}} \quad c^2 = \frac{\delta^2}{x} \quad \text{Thus:}$$

$$v = \frac{U}{2} \cdot \frac{\delta}{x} \cdot \left( \frac{y}{\delta} \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \frac{2}{\pi} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \right) + f(x) \quad \text{Now due to the no-slip condition at the wall (y = 0) we get:}$$



$$0 = \frac{U}{2} \cdot \frac{\delta}{x} \cdot \left( \frac{2}{\pi} \cdot \cos(0) \right) + f(x) \quad f(x) = -\frac{U \cdot \delta}{\pi \cdot x} \quad \text{Therefore: } v = \frac{U}{2} \cdot \frac{\delta}{x} \cdot \left( \frac{y}{\delta} \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \frac{2}{\pi} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \right) - \frac{U \cdot \delta}{\pi \cdot x} \quad \text{Simplifying:}$$

$$v = \frac{U}{\pi} \cdot \frac{\delta}{x} \cdot \left( \frac{\pi \cdot y}{2 \cdot \delta} \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) - 1 \right) \quad \text{Thus: } \frac{v}{U} = \frac{\delta}{\pi \cdot x} \cdot \left( \frac{\pi \cdot y}{2 \cdot \delta} \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) - 1 \right) \quad (\text{Q.E.D.})$$

$$\frac{v}{U} = \frac{\delta}{\pi \cdot x} \cdot \left( \frac{\pi \cdot y}{2 \cdot \delta} \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) - 1 \right)$$

Plotting this relationship shows:

Assuming  $x = 0.5 \text{ m}$  and  $\delta = 5 \text{ mm}$



The maximum value of  $v/U$  is where  $y = \delta$ :  $v_{\text{ratmax}} = \frac{v}{U} = \frac{\delta}{\pi \cdot x} \cdot \left( \frac{\pi}{2} \cdot \sin\left(\frac{\pi}{2}\right) + \cos\left(\frac{\pi}{2}\right) - 1 \right) = \frac{\delta}{\pi \cdot x} \cdot \left( \frac{\pi}{2} - 1 \right)$

$$v_{\text{ratmax}} = \frac{5 \times 10^{-3} \cdot \text{m}}{\pi \times 0.5 \cdot \text{m}} \times \left( \frac{\pi}{2} - 1 \right) \quad v_{\text{ratmax}} = 0.00182$$

## Problem 5.13

[Difficulty: 3]

**5.13** A useful approximation for the  $x$  component of velocity in an incompressible laminar boundary layer is a cubic variation from  $u=0$  at the surface ( $y=0$ ) to the freestream velocity,  $U$ , at the edge of the boundary layer ( $y=\delta$ ). The equation for the profile is  $u/U = \frac{3}{2} (y/\delta) - \frac{1}{2} (y/\delta)^3$ , where  $\delta = cx^{1/2}$  and  $c$  is a constant. Derive the simplest expression for  $v/U$ , the  $y$  component of velocity ratio. Plot  $u/U$  and  $v/U$  versus  $y/\delta$ , and find the location of the maximum value of the ratio  $v/U$ . Evaluate the ratio where  $\delta = 5$  mm and  $x = 0.5$  m.

**Given:** Data on boundary layer

**Find:**  $y$  component of velocity ratio; location of maximum value; plot velocity profiles; evaluate at particular point

**Solution:**

$$u(x, y) = U \cdot \left[ \frac{3}{2} \cdot \left( \frac{y}{\delta(x)} \right) - \frac{1}{2} \cdot \left( \frac{y}{\delta(x)} \right)^3 \right] \quad \text{and} \quad \delta(x) = c \cdot \sqrt{x}$$

so

$$u(x, y) = U \cdot \left[ \frac{3}{2} \cdot \left( \frac{y}{c \cdot \sqrt{x}} \right) - \frac{1}{2} \cdot \left( \frac{y}{c \cdot \sqrt{x}} \right)^3 \right]$$

For incompressible flow  $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$

Hence

$$v(x, y) = - \int \frac{d}{dx} u(x, y) dy \quad \text{and} \quad \frac{du}{dx} = \frac{3}{4} \cdot U \cdot \left( \frac{y^3}{c^3 \cdot x^2} - \frac{y}{c \cdot x^2} \right)$$

so

$$v(x, y) = - \int \frac{3}{4} \cdot U \cdot \left( \frac{y^3}{c^3} \cdot \frac{x^5}{2} - \frac{y}{c} \cdot \frac{x^3}{2} \right) dy$$

$$v(x, y) = \frac{3}{8} \cdot U \cdot \left( \frac{y^2}{\frac{3}{c \cdot x^2}} - \frac{y^4}{\frac{5}{2 \cdot c^3 \cdot x^2}} \right) \quad v(x, y) = \frac{3}{8} \cdot U \cdot \frac{\delta}{x} \cdot \left[ \left( \frac{y}{\delta} \right)^2 - \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^4 \right]$$

The maximum occurs at  $y = \delta$  as seen in the *Excel* work shown below.

$$v_{\max} = \frac{3}{8} \cdot U \cdot \frac{\delta}{x} \cdot \left( 1 - \frac{1}{2} \cdot 1 \right)$$


At  $\delta = 5$  mm and  $x = 0.5$  m, the maximum vertical velocity is

$$\frac{v_{\max}}{U} = 0.00188$$

To find when  $v/U$  is maximum, use *Solver* in *Excel*

$v/U$	$y/\delta$
0.00188	1.0

$v/U$	$y/\delta$
0.000000	0.0
0.000037	0.1
0.000147	0.2
0.000322	0.3
0.000552	0.4
0.00082	0.5
0.00111	0.6
0.00139	0.7
0.00163	0.8
0.00181	0.9
0.00188	1.0



## Problem 5.14

[Difficulty: 3]

**5.14** For a flow in the  $xy$  plane, the  $x$  component of velocity is given by  $u = Ax^2y^2$ , where  $A = 0.3 \text{ m}^{-3} \cdot \text{s}^{-1}$ , and  $x$  and  $y$  are measured in meters. Find a possible  $y$  component for steady, incompressible flow. Is it also valid for unsteady, incompressible flow? Why? How many possible  $y$  components are there? Determine the equation of the streamline for the simplest  $y$  component of velocity. Plot the streamlines through points  $(1, 4)$  and  $(2, 4)$ .

**Given:** Steady, incompressible flow in  $x$ - $y$  plane:

$$u = A \cdot x^2 \cdot y^2 \quad A = 0.3 \cdot \text{m}^{-3} \cdot \text{s}^{-1}$$

**Find:**

- a possible  $y$  component of velocity for this flow field
- if the result is valid for unsteady, incompressible flow
- number of possible  $y$  components for velocity
- equation of the streamlines for the flow
- plot streamlines through points  $(1,4)$  and  $(2,4)$

**Solution:** We will check this flow field using the continuity equation

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:**

- Incompressible flow ( $\rho$  is constant)
- Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$

The partial of  $u$  with respect to  $x$  is:  $\frac{\partial u}{\partial x} = 2Axy^2$  Therefore from continuity:  $\frac{\partial v}{\partial y} = -\frac{\partial u}{\partial x} = -2Axy^2$

Integrating this expression will yield the  $y$ -component of velocity:  $v = \int -2 \cdot A \cdot x \cdot y^2 \, dx + f(x)$   $v = -\frac{2}{3} \cdot A \cdot x^2 \cdot y^3 + f(x)$

The basic equation reduces for the same form for unsteady flow. Hence The result is valid for unsteady, incompressible flow.

Since  $f(x)$  is arbitrary: There are an infinite number of possible  $y$ -components of velocity.

The simplest version of  $v$  is when  $f(x) = 0$ . Therefore, the equation of the corresponding streamline is:


$$\frac{dy}{dx} = \frac{v}{u} = \frac{-\frac{2}{3} A \cdot x^2 \cdot y^3}{A \cdot x^2 \cdot y^2} = -\frac{2}{3} \cdot \frac{y}{x} \quad \text{Separating variables and integrating:} \quad \frac{dy}{y} = -\frac{2}{3} \cdot \frac{dx}{x} \quad \ln(y) = -\frac{2}{3} \cdot \ln(x) \quad \text{Thus:} \quad x \cdot y^{\frac{3}{2}} = \text{constant}$$

are the equations of the streamlines of this flow field.

Plotting streamline for point  $(1, 4)$ :  $1 \times 4^{\frac{3}{2}} = 8 \quad x \cdot y^{\frac{3}{2}} = 8$

Plotting streamline for point  $(2, 4)$ :  $2 \times 4^{\frac{3}{2}} = 16 \quad x \cdot y^{\frac{3}{2}} = 16$

The two streamlines are plotted here in red  $(1,4)$  and blue  $(2,4)$ :



## Problem 5.15

[Difficulty: 3]

**5.15** The  $y$  component of velocity in a steady, incompressible flow field in the  $xy$  plane is  $v = -Bxy^3$ , where  $B = 0.2 \text{ m}^{-3} \cdot \text{s}^{-1}$ , and  $x$  and  $y$  are measured in meters. Find the simplest  $x$  component of velocity for this flow field. Find the equation of the streamlines for this flow. Plot the streamlines through points  $(1, 4)$  and  $(2, 4)$ .

**Given:** Steady, incompressible flow in  $x$ - $y$  plane:

$$v = -B \cdot x \cdot y^3 \quad B = 0.2 \cdot \text{m}^{-3} \cdot \text{s}^{-1}$$

**Find:** (a) the simplest  $x$  component of velocity for this flow field  
 (b) equation of the streamlines for the flow  
 (c) plot streamlines through points  $(1,4)$  and  $(2,4)$

**Solution:** We will check this flow field using the continuity equation

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:** (1) Incompressible flow ( $\rho$  is constant)  
 (2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$

The partial of  $v$  with respect to  $y$  is:  $\frac{\partial v}{\partial y} = -3Bxy^2$  Therefore from continuity:  $\frac{\partial u}{\partial x} = -\frac{\partial v}{\partial y} = 3Bxy^2$

Integrating this expression will yield the  $x$ -component of velocity:  $u = \int 3 \cdot B \cdot x \cdot y^2 \, dx + f(y)$  Evaluating the integral:

$$u = \frac{3}{2} \cdot B \cdot x^2 \cdot y^2 + f(y) \quad \text{The simplest version of this equation is obtained when } f(y) = 0: \quad u = \frac{3}{2} \cdot B \cdot x^2 \cdot y^2$$


The equation of a streamline is:  $\frac{dy}{dx} = \frac{v}{u} = \frac{-B \cdot x \cdot y^3}{\frac{3}{2} \cdot B \cdot x^2 \cdot y^2} = -\frac{2}{3} \cdot \frac{y}{x}$  Separating variables and integrating:  $\frac{dy}{y} = -\frac{2}{3} \cdot \frac{dx}{x}$

$\ln(y) = -\frac{2}{3} \cdot \ln(x)$  Thus:  $x \cdot y^{\frac{3}{2}} = \text{constant}$  are the equations of the streamlines of this flow field.  $x \cdot y^{\frac{3}{2}} = \text{constant}$

Plotting streamline for point  $(1, 4)$ :  $1 \times 4^{\frac{3}{2}} = 8 \quad x \cdot y^{\frac{3}{2}} = 8$

Plotting streamline for point  $(2, 4)$ :  $2 \times 4^{\frac{3}{2}} = 16 \quad x \cdot y^{\frac{3}{2}} = 16$

The two streamlines are plotted here in red  $(1,4)$  and blue  $(2,4)$ :



## Problem 5.16

[Difficulty: 5]

---

**5.16** Consider a water stream from a jet of an oscillating lawn sprinkler. Describe the corresponding pathline and streakline.

---

**Discussion:** Refer back to the discussion of streamlines, pathlines, and streaklines in Section 2-2.

Because the sprinkler jet oscillates, this is an unsteady flow. Therefore pathlines and streaklines need not coincide.

A *pathline* is a line tracing the path of an individual fluid particle. The path of each particle is determined by the jet angle and the speed at which the particle leaves the jet.

Once a particle leaves the jet it is subject to gravity and drag forces. If aerodynamic drag were negligible, the path of each particle would be parabolic. The horizontal speed of the particle would remain constant throughout its trajectory. The vertical speed would be slowed by gravity until reaching peak height, and then it would become increasingly negative until the particle strikes the ground. The effect of aerodynamic drag is to reduce the particle speed. With drag the particle will not rise as high vertically nor travel as far horizontally. At each instant the particle trajectory will be lower and closer to the jet compared to the no-friction case. The trajectory after the particle reaches its peak height will be steeper than in the no-friction case.

A *streamline* is a line drawn in the flow that is tangent everywhere to the velocity vectors of the fluid motion. It is difficult to visualize the streamlines for an unsteady flow field because they move laterally. However, the streamline pattern may be drawn at an instant.

A *streakline* is the locus of the present locations of fluid particles that passed a reference point at previous times. As an example, choose the exit of a jet as the reference point. Imagine marking particles that pass the jet exit at a given instant and at uniform time intervals later. The first particle will travel farthest from the jet exit and on the lowest trajectory; the last particle will be located right at the jet exit. The curve joining the present positions of the particles will resemble a spiral whose radius increases with distance from the jet opening.

## Problem 5.17

[Difficulty: 4]

**5.17** Derive the differential form of conservation of mass in rectangular coordinates by expanding the *products* of density and the velocity components,  $\rho u$ ,  $\rho v$ , and  $\rho w$ , in a Taylor series about a point  $O$ . Show that the result is identical to Eq. 5.1a.

**Given:** Conservation of mass in rectangular coordinates

**Find:** Identical result to Equation 5.1a by expanding products of density and velocity in a Taylor Series.

**Solution:** We will use the diagram in Figure 5.1 (shown here). We will apply the conservation of mass evaluating the derivatives at point  $O$ :

**Governing Equations:**


$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation - Eqn 5.1a})$$

**Assumptions:** Expansion of density and velocity via Taylor series is valid around point  $O$ .

In the x-direction, the mass flux is:  $\dot{m}_x = \rho u dA = \rho u dy dz$

At the right face:  $\dot{m}_{x+dx/2} = \left[ \rho u + \frac{\partial(\rho u)}{\partial x} \frac{dx}{2} \right] dy dz$  (out of the volume)

At the left face:  $\dot{m}_{x-dx/2} = \left[ \rho u + \frac{\partial(\rho u)}{\partial x} \left( -\frac{dx}{2} \right) \right] dy dz$  (into the volume)



The net mass flux out of the volume in the x-direction would then be:

$$\dot{m}_{x(net)} = \dot{m}_{x+dx/2} - \dot{m}_{x-dx/2} = \left[ \rho u + \frac{\partial(\rho u)}{\partial x} \frac{dx}{2} \right] dy dz - \left[ \rho u + \frac{\partial(\rho u)}{\partial x} \left( -\frac{dx}{2} \right) \right] dy dz = \frac{\partial(\rho u)}{\partial x} dx dy dz$$

Similarly, the net mass fluxes in the y-direction and z-direction are:  $\dot{m}_{y(net)} = \frac{\partial(\rho v)}{\partial x} dx dy dz$      $\dot{m}_{z(net)} = \frac{\partial(\rho w)}{\partial x} dx dy dz$

The rate of mass accumulation in the volume is:  $\left. \frac{dm}{dt} \right)_{vol} = \frac{\partial \rho}{\partial t} dx dy dz$     Now the net outflux must balance the accumulation:

$$\dot{m}_{(net)} + \left. \frac{dm}{dt} \right)_{vol} = 0 \quad \text{Therefore we may write: } \frac{\partial(\rho u)}{\partial x} dx dy dz + \frac{\partial(\rho v)}{\partial x} dx dy dz + \frac{\partial(\rho w)}{\partial x} dx dy dz + \frac{\partial \rho}{\partial t} dx dy dz = 0$$

We may divide the volume out of all terms:  $\frac{\partial(\rho u)}{\partial x} + \frac{\partial(\rho v)}{\partial x} + \frac{\partial(\rho w)}{\partial x} + \frac{\partial \rho}{\partial t} = 0$  (Q.E.D.)

$$\frac{\partial(\rho u)}{\partial x} + \frac{\partial(\rho v)}{\partial x} + \frac{\partial(\rho w)}{\partial x} + \frac{\partial \rho}{\partial t} = 0$$

## Problem 5.18

[Difficulty: 2]

**5.18** Which of the following sets of equations represent possible incompressible flow cases?

- (a)  $V_r = U \cos \theta$ ;  $V_\theta = -U \sin \theta$   
 (b)  $V_r = -q/2\pi r$ ;  $V_\theta = K/2\pi r$   
 (c)  $V_r = U \cos \theta [1 - (a/r)^2]$ ;  $V_\theta = -U \sin \theta [1 + (a/r)^2]$

**Given:** The list of velocity fields provided above

**Find:** Which of these fields possibly represent incompressible flow

**Solution:** We will check these flow fields against the continuity equation

**Governing Equations:**

$$\frac{1}{r} \frac{\partial}{\partial r} (r\rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:**

- (1) Incompressible flow ( $\rho$  is constant)  
 (2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial(rV_r)}{\partial r} + \frac{\partial V_\theta}{\partial \theta} = 0$

This is the criterion against which we will check all of the flow fields.

(a)  $V_r = U \cdot \cos(\theta)$   
 $V_\theta = -U \cdot \sin(\theta)$

$$\frac{\partial(rV_r)}{\partial r} + \frac{\partial V_\theta}{\partial \theta} = (U \cos \theta) + (-U \cos \theta) = 0$$

This could be an incompressible flow field.

(b)  $V_r = -\frac{q}{2 \cdot \pi \cdot r}$   
 $V_\theta = \frac{K}{2 \cdot \pi \cdot r}$

$$\frac{\partial(rV_r)}{\partial r} + \frac{\partial V_\theta}{\partial \theta} = 0 + 0 = 0$$

This could be an incompressible flow field.

(c)  $V_r = U \cdot \cos(\theta) \cdot \left[1 - \left(\frac{a}{r}\right)^2\right]$   
 $V_\theta = -U \cdot \sin(\theta) \cdot \left[1 + \left(\frac{a}{r}\right)^2\right]$

$$\frac{\partial(rV_r)}{\partial r} + \frac{\partial V_\theta}{\partial \theta} = U \cos \theta \left[1 + \left(\frac{a}{r}\right)^2\right] - U \cos \theta \left[1 + \left(\frac{a}{r}\right)^2\right] = 0$$

This could be an incompressible flow field.

## Problem 5.19

[Difficulty: 2]

**5.19** Which of the following sets of equations represent(s) possible incompressible flow cases?

- (a)  $V_r = -K/r; V_\theta = 0$
- (b)  $V_r = 0; V_\theta = K/r$
- (c)  $V_r = -K \cos \theta/r^2; V_\theta = -K \sin \theta/r^2$

**Given:** The list of velocity fields provided above  
**Find:** Which of these fields possibly represent incompressible flow  
**Solution:** We will check these flow fields against the continuity equation

**Governing Equations:** 
$$\frac{1}{r} \frac{\partial}{\partial r} (r \rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:** (1) Incompressible flow ( $\rho$  is constant)  
 (2) Two dimensional flow (velocity is not a function of  $z$ )

Based on the two assumptions listed above, the continuity equation reduces to: 
$$\frac{\partial}{\partial r} (r \cdot V_r) + \frac{\partial}{\partial \theta} V_\theta = 0$$

This is the criterion against which we will check all of the flow fields.

a)  $V_r(r, \theta, t) = -\frac{K}{r} \quad V_\theta(r, \theta, t) = 0 \quad \frac{\partial}{\partial r} (r \cdot V_r(r, \theta, t)) = 0 \quad \frac{\partial}{\partial \theta} V_\theta(r, \theta, t) = 0$

Hence 
$$\frac{\partial}{\partial r} (r \cdot V_r) + \frac{\partial}{\partial \theta} V_\theta = 0 \quad \text{INCOMPRESSIBLE}$$

b)  $V_r(r, \theta, t) = 0 \quad V_\theta(r, \theta, t) = \frac{K}{r} \quad \frac{\partial}{\partial r} (r \cdot V_r(r, \theta, t)) = 0 \quad \frac{\partial}{\partial \theta} V_\theta(r, \theta, t) = 0$

Hence 
$$\frac{\partial}{\partial r} (r \cdot V_r) + \frac{\partial}{\partial \theta} V_\theta = 0 \quad \text{INCOMPRESSIBLE}$$

b)  $V_r(r, \theta, t) = -\frac{K \cdot \cos(\theta)}{r^2} \quad V_\theta(r, \theta, t) = -\frac{K \cdot \sin(\theta)}{r^2}$

$$\frac{\partial}{\partial r} (r \cdot V_r(r, \theta, t)) = \frac{K \cdot \cos(\theta)}{r^2} \quad \frac{\partial}{\partial \theta} V_\theta(r, \theta, t) = -\frac{K \cdot \cos(\theta)}{r^2}$$

Hence 
$$\frac{\partial}{\partial r} (r \cdot V_r) + \frac{\partial}{\partial \theta} V_\theta = 0 \quad \text{INCOMPRESSIBLE}$$

## Problem 5.20

[Difficulty: 3]

**5.20** For an incompressible flow in the  $r\theta$  plane, the  $r$  component of velocity is given as  $V_r = U \cos \theta$ .

- (a) Determine a possible  $\theta$  component of velocity.  
(b) How many possible  $\theta$  components are there?

**Given:**  $r$  component of velocity

**Find:**  $\theta$  component for incompressible flow; How many  $\theta$  components

**Solution:**

**Basic equation:** 
$$\frac{1}{r} \cdot \frac{\partial}{\partial r}(\rho \cdot r \cdot V_r) + \frac{1}{r} \cdot \frac{\partial}{\partial \theta}(\rho \cdot V_\theta) + \frac{\partial}{\partial z}(\rho \cdot V_z) + \frac{\partial}{\partial t} \rho = 0$$

**Assumptions:** Incompressible flow  
Flow in  $r$ - $\theta$  plane

Hence 
$$\frac{1}{r} \cdot \frac{\partial}{\partial r}(r \cdot V_r) + \frac{1}{r} \cdot \frac{\partial}{\partial \theta}(V_\theta) = 0 \quad \text{or} \quad \frac{\partial}{\partial \theta} V_\theta = \frac{\partial}{\partial r}(r \cdot V_r) = \frac{\partial}{\partial r}(r \cdot U \cdot \cos(\theta)) = -U \cdot \cos(\theta)$$

Integrating 
$$V_\theta(r, \theta) = - \int U \cdot \cos(\theta) d\theta = -U \cdot \sin(\theta) + f(r)$$

$$V_\theta(r, \theta) = -U \cdot \sin(\theta) + f(r)$$

There are an infinite number of solutions as  $f(r)$  can be any function of  $r$

The simplest form is  $V_\theta(r, \theta) = -U \cdot \sin(\theta)$

## Problem 5.21

[Difficulty: 3]

**5.21** For an incompressible flow in the  $r\theta$  plane, the  $r$  component of velocity is given as  $V_r = -\Lambda \cos \theta / r^2$ . Determine a possible  $\theta$  component of velocity. How many possible  $\theta$  components are there?

**Given:**  $r$  component of velocity

**Find:**  $\theta$  component for incompressible flow; How many  $\theta$  components

**Solution:**

Basic equation: 
$$\frac{1}{r} \cdot \frac{\partial}{\partial r}(\rho \cdot r \cdot V_r) + \frac{1}{r} \cdot \frac{\partial}{\partial \theta}(\rho \cdot V_\theta) + \frac{\partial}{\partial z}(\rho \cdot V_z) + \frac{\partial}{\partial t} \rho = 0$$

Assumption: Incompressible flow; flow in  $r$ - $\theta$  plane

Hence 
$$\frac{1}{r} \cdot \frac{\partial}{\partial r}(r \cdot V_r) + \frac{1}{r} \cdot \frac{\partial}{\partial \theta}(V_\theta) = 0 \quad \circ \quad \frac{\partial}{\partial \theta} V_\theta = \frac{\partial}{\partial r}(r \cdot V_r) = \frac{\partial}{\partial r} \left( -\frac{\Lambda \cdot \cos(\theta)}{r} \right) = -\frac{\Lambda \cdot \cos(\theta)}{r^2}$$

Integrating 
$$V_\theta(r, \theta) = - \int \frac{\Lambda \cdot \cos(\theta)}{r^2} d\theta = -\frac{\Lambda \cdot \sin(\theta)}{r^2} + f(r)$$

$$V_\theta(r, \theta) = -\frac{\Lambda \cdot \sin(\theta)}{r^2} + f(r)$$

There are an infinite number of solutions as  $f(r)$  can be any function of  $r$

The simplest form is 
$$V_\theta(r, \theta) = -\frac{\Lambda \cdot \sin(\theta)}{r^2}$$

## Problem 5.22


[Difficulty: 2]

**5.22** A viscous liquid is sheared between two parallel disks of radius  $R$ , one of which rotates while the other is fixed. The velocity field is purely tangential, and the velocity varies linearly with  $z$  from  $V_\theta = 0$  at  $z = 0$  (the fixed disk) to the velocity of the rotating disk at its surface ( $z = h$ ). Derive an expression for the velocity field between the disks.

**Given:** Flow between parallel disks as shown. Velocity is purely tangential. No-slip condition is satisfied, so velocity varies linearly with  $z$ .

**Find:** An expression for the velocity field

**Solution:** We will apply the continuity equation to this system.



**Governing Equations:**

$$\frac{1}{r} \frac{\partial}{\partial r} (r \rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{V} = V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k} \quad (\text{Velocity flow field})$$

**Assumptions:**

- (1) Incompressible flow ( $\rho$  is constant)
- (2) Purely tangential flow
- (3) Linear velocity variation with  $z$

Based on the first two assumptions, the continuity equation reduces to:  $\frac{\partial V_\theta}{\partial \theta} = 0$  thus:  $V_\theta = V_\theta(r, z)$

Since the velocity is linear with  $z$ , we may write:  $V_\theta(r, z) = z \cdot f(r) + C$  Now we apply known boundary conditions:

$$1: \quad V_\theta(r, 0) = 0 \quad 0 \cdot f(r) + C = 0 \quad C = 0 \quad 2: \quad V_\theta(r, h) = r \cdot \omega \quad h \cdot f(r) = r \cdot \omega \quad f(r) = \frac{r \cdot \omega}{h}$$

Therefore the tangential velocity is:  $V_\theta = \omega \cdot r \cdot \frac{z}{h}$  Thus, the velocity field is:

$$\vec{V} = \omega r \frac{z}{h} \hat{e}_\theta$$

## Problem 5.23

[Difficulty: 4]

**5.23** Evaluate  $\nabla \cdot \rho \vec{V}$  in cylindrical coordinates. Use the definition of  $\nabla$  in cylindrical coordinates. Substitute the velocity vector and perform the indicated operations, using the hint in footnote 1 on page 178. Collect terms and simplify; show that the result is identical to Eq. 5.2c.

**Given:** Definition of "del" operator in cylindrical coordinates, velocity vector

**Find:** (a) An expression for  $\vec{\nabla} \cdot (\rho \vec{V})$  in cylindrical coordinates.  
 (b) Show result is identical to Equation 5.2c.

**Solution:** We will apply the velocity field to the del operator and simplify.

**Governing Equations:**

$$\vec{\nabla} = \hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{k} \frac{\partial}{\partial z} \quad \text{(Definition of "del" operator)}$$

$$\vec{V} = V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k} \quad \text{(Velocity flow field)}$$

$$\frac{1}{r} \frac{\partial}{\partial r} (r \rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) = 0 \quad \text{(Equation 5.2c)}$$

$$\frac{\partial \hat{e}_r}{\partial \theta} = \hat{e}_\theta \quad \frac{\partial \hat{e}_\theta}{\partial \theta} = -\hat{e}_r \quad \text{(Hints from footnote)}$$

Substituting  $\vec{\nabla} \cdot (\rho \vec{V})$  using the governing equations yields:

$$\begin{aligned} \vec{\nabla} \cdot (\rho \vec{V}) &= \left( \hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{k} \frac{\partial}{\partial z} \right) \cdot \rho (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) \\ &= \hat{e}_r \frac{\partial}{\partial r} \cdot \rho (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} \cdot \rho (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) + \hat{k} \frac{\partial}{\partial z} \cdot \rho (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) \\ &= \hat{e}_r \cdot \hat{e}_r \frac{\partial}{\partial r} (\rho V_r) + \hat{e}_\theta \cdot \hat{e}_r \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_r) + \hat{e}_\theta \cdot \frac{1}{r} \frac{\partial \hat{e}_r}{\partial \theta} (\rho V_r) \\ &\quad + \hat{e}_\theta \cdot \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \hat{e}_\theta \cdot \frac{1}{r} \frac{\partial \hat{e}_\theta}{\partial \theta} (\rho V_\theta) + \hat{k} \cdot \hat{k} \frac{\partial}{\partial z} (\rho V_z) \end{aligned}$$

Using the hints listed above, and knowing that:  $\hat{e}_\theta \cdot \hat{e}_\theta = \hat{e}_r \cdot \hat{e}_r = \hat{k} \cdot \hat{k} = 1$      $\hat{e}_\theta \cdot \hat{e}_r = \hat{e}_r \cdot \hat{e}_\theta = 0$

$$\begin{aligned} \vec{\nabla} \cdot (\rho \vec{V}) &= \frac{\partial}{\partial r} (\rho V_r) + \hat{e}_\theta \cdot \frac{1}{r} \frac{\partial \hat{e}_r}{\partial \theta} (\rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \hat{e}_\theta \cdot \frac{1}{r} \frac{\partial \hat{e}_\theta}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) \\ &= \frac{\partial}{\partial r} (\rho V_r) + \hat{e}_\theta \cdot \hat{e}_\theta \frac{1}{r} (\rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) - \hat{e}_\theta \cdot \hat{e}_r \frac{1}{r} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) \\ &= \frac{\partial}{\partial r} (\rho V_r) + \frac{1}{r} (\rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) \end{aligned}$$

Combining the first two terms:  $\frac{\partial}{\partial r} (\rho V_r) + \frac{1}{r} (\rho V_r) = \frac{1}{r} \frac{\partial}{\partial r} (r \rho V_r)$  which can be verified through differentiation. Thus:

$$\vec{\nabla} \cdot (\rho \vec{V}) = \frac{1}{r} \frac{\partial}{\partial r} (r \rho V_r) + \frac{1}{r} \frac{\partial}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) \quad \text{(Q.E.D.)}$$

## Problem 5.24

[Difficulty: 3]

**\*5.24** A velocity field in cylindrical coordinates is given as  $\vec{V} = \hat{e}_r A/r + \hat{e}_\theta B/r$ , where  $A$  and  $B$  are constants with dimensions of  $\text{m}^2/\text{s}$ . Does this represent a possible incompressible flow? Sketch the streamline that passes through the point  $r_0 = 1 \text{ m}$ ,  $\theta = 90^\circ$  if  $A = B = 1 \text{ m}^2/\text{s}$ , if  $A = 1 \text{ m}^2/\text{s}$  and  $B = 0$ , and if  $B = 1 \text{ m}^2/\text{s}$  and  $A = 0$ .

**Given:** The velocity field

**Find:** Whether or not it is a incompressible flow; sketch various streamlines

**Solution:**

$$V_r = \frac{A}{r} \qquad V_\theta = \frac{B}{r}$$

For incompressible flow  $\frac{1}{r} \cdot \frac{d}{dr}(r \cdot V_r) + \frac{1}{r} \cdot \frac{d}{d\theta} V_\theta = 0$        $\frac{1}{r} \cdot \frac{d}{dr}(r \cdot V_r) = 0$        $\frac{1}{r} \cdot \frac{d}{d\theta} V_\theta = 0$

Hence  $\frac{1}{r} \cdot \frac{d}{dr}(r \cdot V_r) + \frac{1}{r} \cdot \frac{d}{d\theta} V_\theta = 0$       Flow is incompressible

For the streamlines  $\frac{dr}{V_r} = \frac{r \cdot d\theta}{V_\theta}$        $\frac{r \cdot dr}{A} = \frac{r^2 \cdot d\theta}{B}$

so  $\int \frac{1}{r} dr = \int \frac{A}{B} d\theta$       Integrating       $\ln(r) = \frac{A}{B} \cdot \theta + \text{const}$

Equation of streamlines is  $r = C \cdot e^{\frac{A}{B} \cdot \theta}$

(a) For  $A = B = 1 \text{ m}^2/\text{s}$ , passing through point  $(1\text{m}, \pi/2)$


$$r = e^{\theta - \frac{\pi}{2}}$$

(b) For  $A = 1 \text{ m}^2/\text{s}$ ,  $B = 0 \text{ m}^2/\text{s}$ , passing through point  $(1\text{m}, \pi/2)$

$$\theta = \frac{\pi}{2}$$

(c) For  $A = 0 \text{ m}^2/\text{s}$ ,  $B = 1 \text{ m}^2/\text{s}$ , passing through point  $(1\text{m}, \pi/2)$

$$r = 1 \cdot \text{m}$$



- (a)
- - (b)
- · - (c)

## Problem \*5.25

[Difficulty: 2]

**\*5.25** The velocity field for the viscometric flow of Example 5.7 is  $\vec{V} = U(y/h)\hat{i}$ . Find the stream function for this flow. Locate the streamline that divides the total flow rate into two equal parts.

**Given:** Velocity field for viscometric flow of Example 5.7:  $\vec{V} = U \frac{y}{h} \hat{i}$

**Find:** (a) Stream function  
(b) Locate streamline that divides flow rate equally

**Solution:** The flow is incompressible, so the stream function may be derived

**Governing Equations:**  $u = \frac{\partial \psi}{\partial y} \quad v = -\frac{\partial \psi}{\partial x}$  (Definition of stream function)

Integrating the velocity will result in the stream function:  $\psi = \int u \, dy + f(x) = \int U \frac{y}{h} \, dy + f(x) = \frac{U \cdot y^2}{2 \cdot h} + f(x)$

Let  $\psi = 0$  at  $y = 0$ , so  $f(x) = 0$ :

$$\psi = \frac{U \cdot y^2}{2 \cdot h}$$

The stream function is a maximum value at  $y = h$ :  $\psi_{\max} = \frac{U \cdot h^2}{2 \cdot h} = \frac{U \cdot h}{2}$  The flow rate is:  $\frac{Q}{w} = \psi_{\max} - \psi_{\min} = \frac{U \cdot h}{2} - 0 = \frac{U \cdot h}{2}$

So the streamline which splits the flow rate into two equal parts is:  $\psi_{\text{half}Q} = \frac{1}{2} \cdot \psi_{\max} = \frac{1}{2} \cdot \frac{U \cdot h}{2} = \frac{U \cdot h}{4}$

Therefore, the equation of this streamline would be:  $\frac{U \cdot y^2}{2 \cdot h} = \frac{U \cdot h}{4}$  Simplifying this equation:  $y^2 = \frac{h^2}{2}$  or:  $y = \frac{h}{\sqrt{2}}$

$$y = \frac{h}{\sqrt{2}}$$

## Problem \*5.26

[Difficulty: 3]

**\*5.26** Determine the family of stream functions  $\psi$  that will yield the velocity field  $\vec{V} = 2y(2x + 1)\hat{i} + [x(x + 1) - 2y^2]\hat{j}$ .

**Given:** Velocity field

**Find:** Stream function  $\psi$

**Solution:**

**Basic equations:**  $\frac{\partial}{\partial x}(\rho \cdot u) + \frac{\partial}{\partial y}(\rho \cdot v) + \frac{\partial}{\partial z}(\rho \cdot w) + \frac{\partial}{\partial t}\rho = 0$        $u = \frac{\partial}{\partial y}\psi$        $v = -\frac{\partial}{\partial x}\psi$

**Assumptions:** Incompressible flow  
Flow in x-y plane

Hence  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$       or       $\frac{\partial}{\partial x}[2 \cdot y \cdot (2x + 1)] + \frac{\partial}{\partial y}[x \cdot (x + 1) - 2 \cdot y^2] = 0$

Hence  $u = 2 \cdot y \cdot (2 \cdot x + 1) = \frac{\partial}{\partial y}\psi$        $\psi(x, y) = \int 2 \cdot y \cdot (2 \cdot x + 1) dy = 2 \cdot x \cdot y^2 + y^2 + f(x)$

and  $v = x \cdot (x + 1) - 2 \cdot y^2 = -\frac{\partial}{\partial x}\psi$        $\psi(x, y) = -\int [x \cdot (x + 1) - 2 \cdot y^2] dx = -\frac{x^3}{3} - \frac{x^2}{2} + 2 \cdot x \cdot y^2 + g(y)$

Comparing these  $f(x) = -\frac{x^3}{3} - \frac{x^2}{2}$       and       $g(y) = y^2$

The stream function is  $\psi(x, y) = y^2 + 2 \cdot x \cdot y^2 - \frac{x^2}{2} - \frac{x^3}{3}$

Checking  $u(x, y) = \frac{\partial}{\partial y}\left(y^2 + 2 \cdot x \cdot y^2 - \frac{x^2}{2} - \frac{x^3}{3}\right) \rightarrow u(x, y) = 2 \cdot y + 4 \cdot x \cdot y$

$v(x, y) = -\frac{\partial}{\partial x}\left(y^2 + 2 \cdot x \cdot y^2 - \frac{x^2}{2} - \frac{x^3}{3}\right) \rightarrow v(x, y) = x^2 + x - 2 \cdot y^2$

## Problem \*5.27

[Difficulty: 3]

**\*5.27** Does the velocity field of Problem 5.24 represent a possible incompressible flow case? If so, evaluate and sketch the stream function for the flow. If not, evaluate the rate of change of density in the flow field.

**Given:** The velocity field

**Find:** Whether or not it is a incompressible flow; sketch stream function

**Solution:**

$$V_r = \frac{A}{r}$$

$$V_\theta = \frac{B}{r}$$

For incompressible flow

$$\frac{1}{r} \cdot \frac{d}{dr}(r \cdot V_r) + \frac{1}{r} \cdot \frac{d}{d\theta} V_\theta = 0 \qquad \frac{1}{r} \cdot \frac{d}{dr}(r \cdot V_r) = 0 \qquad \frac{1}{r} \cdot \frac{d}{d\theta} V_\theta = 0$$

Hence

$$\frac{1}{r} \cdot \frac{d}{dr}(r \cdot V_r) + \frac{1}{r} \cdot \frac{d}{d\theta} V_\theta = 0 \qquad \text{Flow is incompressible}$$


For the stream function

$$\frac{\partial}{\partial \theta} \psi = r \cdot V_r = A \qquad \psi = A \cdot \theta + f(r)$$

Integrating

$$\frac{\partial}{\partial r} \psi = -V_\theta = -\frac{B}{r} \qquad \psi = -B \cdot \ln(r) + g(\theta)$$

Comparing, stream function is  $\psi = A \cdot \theta - B \cdot \ln(r)$



ψ

## Problem \*5.28

[Difficulty: 2]

**\*5.28** The stream function for a certain incompressible flow field is given by the expression  $\psi = -Ur \sin \theta + q\theta/2\pi$ . Obtain an expression for the velocity field. Find the stagnation point(s) where  $|\vec{V}| = 0$ , and show that  $\psi = 0$  there.

**Given:** Stream function for an incompressible flow field:

$$\psi = -U \cdot r \cdot \sin(\theta) + \frac{q}{2 \cdot \pi} \cdot \theta$$

**Find:** (a) Expression for the velocity field  
(b) Location of stagnation points  
(c) Show that the stream function is equal to zero at the stagnation points.

**Solution:** We will generate the velocity field from the stream function.

**Governing Equations:** 
$$V_r = \frac{1}{r} \frac{\partial \psi}{\partial \theta} \quad V_\theta = -\frac{\partial \psi}{\partial r} \quad (\text{Definition of stream function})$$

Taking the derivatives of the stream function:  $V_r = -U \cdot \cos(\theta) + \frac{q}{2 \cdot \pi \cdot r} \quad V_\theta = U \cdot \sin(\theta)$

So the velocity field is:

$$\vec{V} = \left( -U \cos \theta + \frac{q}{2\pi R} \right) \hat{e}_r + U \sin \theta \hat{e}_\theta$$

To find the stagnation points we must find the places where both velocity components are zero. When  $V_r = 0 \quad r = \frac{q}{2 \cdot \pi \cdot U \cdot \cos(\theta)}$

When  $V_\theta = 0 \quad \sin(\theta) = 0$  therefore:  $\theta = 0, \pi$  Now we can apply these values of  $\theta$  to the above relation to find  $r$ :

For  $\theta = 0$ :  $r = \frac{q}{2 \cdot \pi \cdot U \cdot \cos(0)} = \frac{q}{2 \cdot \pi \cdot U}$  For  $\theta = \pi$ :  $r = \frac{q}{2 \cdot \pi \cdot \cos(\pi)} = -\frac{q}{2 \cdot \pi \cdot U}$  These represent the same point:

Stagnation point at:

$$(r, \theta) = \left( \frac{q}{2 \cdot \pi \cdot U}, 0 \right)$$

At the stagnation point:  $\psi_{\text{stagnation}} = -U \cdot \frac{q}{2 \cdot \pi \cdot U} \cdot \sin(0) + \frac{q}{2 \cdot \pi} \cdot 0 = 0$

$$\psi_{\text{stagnation}} = 0$$

## Problem \*5.29

[Difficulty: 3]

**\*5.29** Consider a flow with velocity components  $u = z(3x^2 - z^2)$ ,  $v = 0$ , and  $w = x(x^2 - 3z^2)$ .

- (a) Is this a one-, two-, or three-dimensional flow?  
 (b) Demonstrate whether this is an incompressible flow.  
 (c) If possible, derive a stream function for this flow.

**Given:** Velocity field

**Find:** Whether it's 1D, 2D or 3D flow; Incompressible or not; Stream function  $\psi$

**Solution:**

**Basic equation:**  $\frac{\partial}{\partial x}(\rho \cdot u) + \frac{\partial}{\partial y}(\rho \cdot v) + \frac{\partial}{\partial z}(\rho \cdot w) + \frac{\partial}{\partial t}\rho = 0$        $u = \frac{\partial}{\partial z}\psi$        $w = \frac{\partial}{\partial x}\psi$

Assumption: Incompressible flow; flow in x-z plane ( $v = 0$ )

Velocity field is a function of x and z only, so is 2D

Check for incompressible  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial z}w = 0$

$$\frac{\partial}{\partial x}[z \cdot (3x^2 - z^2)] \rightarrow 6 \cdot x \cdot z$$

$$\frac{\partial}{\partial z}[x \cdot (x^2 - 3z^2)] \rightarrow -6 \cdot x \cdot z$$

Hence  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial z}w = 0$

Flow is INCOMPRESSIBLE

Hence  $u = z \cdot (3x^2 - z^2) = \frac{\partial}{\partial z}\psi$

$$\psi(x, z) = \int z \cdot (3x^2 - z^2) dz = \frac{3}{2} \cdot x^2 \cdot z^2 - \frac{1}{4} \cdot z^4 + f(x)$$

and  $w = x \cdot (x^2 - 3z^2) = \frac{\partial}{\partial x}\psi$

$$\psi(x, z) = - \int [x \cdot (x^2 - 3z^2)] dx = -\frac{x^4}{4} + \frac{3}{2} \cdot x^2 \cdot z^2 + g(z)$$

Comparing these  $f(x) = -\frac{x^4}{4}$       and

$$g(z) = -\frac{z^4}{4}$$

The stream function is  $\psi(x, z) = -\frac{x^4}{4} + \frac{3}{2} \cdot x^2 \cdot z^2 - \frac{z^4}{4}$

Checking  $u(x, z) = \frac{\partial}{\partial z} \left( -\frac{x^4}{4} + \frac{3}{2} \cdot x^2 \cdot z^2 - \frac{z^4}{4} \right) \rightarrow u(x, z) = 3 \cdot x^2 \cdot z - z^3$

$$w(x, z) = \frac{\partial}{\partial x} (z \cdot y^3 - z^3 \cdot y) \rightarrow w(x, z) = z^3 - 3 \cdot y^2 \cdot z$$

## Problem \*5.30

[Difficulty: 3]

**\*5.30** An incompressible frictionless flow field is specified by the stream function  $\psi = -5Ax - 2Ay$ , where  $A = 2 \text{ m/s}$ , and  $x$  and  $y$  are coordinates in meters.

- (a) Sketch the streamlines  $\psi = 0$  and  $\psi = 5$ , and indicate the direction of the velocity vector at the point  $(0, 0)$  on the sketch.
- (b) Determine the magnitude of the flow rate between the streamlines passing through  $(2, 2)$  and  $(4, 1)$ .

**Given:** Stream function for an incompressible flow field:

$$\psi = -5 \cdot A \cdot x - 2 \cdot A \cdot y \quad A = 2 \cdot \frac{\text{m}}{\text{s}}$$

- Find:**
- (a) Sketch streamlines  $\psi = 0$  and  $\psi = 5$
  - (b) Velocity vector at  $(0, 0)$
  - (c) Flow rate between streamlines passing through points  $(2, 2)$  and  $(4, 1)$

**Solution:** We will generate the velocity field from the stream function.


**Governing Equations:**  $u = \frac{\partial \psi}{\partial y} \quad v = -\frac{\partial \psi}{\partial x}$  (Definition of stream function)

**Assumptions:** Incompressible flow ( $\rho$  is constant)  
Flow is only in the x-y plane

For  $\psi = 0$ :  $0 = -5 \cdot A \cdot x - 2 \cdot A \cdot y$  Solving for  $y$ :  $y = -\frac{5}{2} \cdot x$

For  $\psi = 5$ :  $5 = -5 \cdot A \cdot x - 2 \cdot A \cdot y$  Solving for  $y$ :  $y = -\frac{5}{2} \cdot x - \frac{5}{2} \cdot \frac{\text{m}^2}{\text{s}} \times \frac{\text{s}}{2 \cdot \text{m}} = -\frac{5}{2} \cdot x - \frac{5}{2} \cdot \text{m}$

Here is the plot of the two streamlines:  $\psi = 0$  is in red;  $\psi = 5$  is in blue



Generating the velocity components from the stream function derivatives:

$u = -2 \cdot A \quad v = 5 \cdot A$  Therefore, the velocity vector at  $(0, 0)$  is:

$$\vec{V} = -4\hat{i} + 10\hat{j}$$

At the point  $(2, 2)$  the stream function value is:  $\psi_a = -5 \times 2 \cdot \frac{\text{m}}{\text{s}} \times 2 \cdot \text{m} - 2 \times 2 \cdot \frac{\text{m}}{\text{s}} \times 2 \cdot \text{m} \quad \psi_a = -28 \frac{\text{m}^2}{\text{s}}$

At the point  $(4, 1)$  the stream function value is:  $\psi_b = -5 \times 2 \cdot \frac{\text{m}}{\text{s}} \times 4 \cdot \text{m} - 2 \times 2 \cdot \frac{\text{m}}{\text{s}} \times 1 \cdot \text{m} \quad \psi_b = -44 \frac{\text{m}^2}{\text{s}}$

The flow rate between these two streamlines is:  $Q = \psi_b - \psi_a \quad Q = \left(-44 \cdot \frac{\text{m}^2}{\text{s}}\right) - \left(-28 \cdot \frac{\text{m}^2}{\text{s}}\right) \quad Q = -16 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}}$

Flow rate is  $16 \text{ m}^3/\text{s}$  per meter of depth

## Problem \*5.31

[Difficulty: 3]

**\*5.31** A linear velocity profile was used to model flow in a laminar incompressible boundary layer in Problem 5.10. Derive the stream function for this flow field. Locate streamlines at one-quarter and one-half the total volume flow rate in the boundary layer.

**Given:** Approximate profile for a laminar boundary layer:

$$u = \frac{U \cdot y}{\delta} \quad \delta = c \cdot \sqrt{x} \quad (c \text{ is constant})$$

**Find:**

- (a) Stream function for the flow field
- (b) Location of streamlines at one-quarter and one-half the total flow rate in the boundary layer.

**Solution:** We will generate the stream function from the velocity field.

**Governing Equations:**

$$u = \frac{\partial \psi}{\partial y} \quad v = -\frac{\partial \psi}{\partial x} \quad (\text{Definition of stream function})$$

Integrating the x-component of velocity yields the stream function:  $\psi = \int \frac{U \cdot y}{\delta} dy + f(x) = \frac{U \cdot y^2}{2 \cdot \delta} + f(x)$

If we set  $\psi = 0$  at  $y = 0$  then the stream function would be:

$$\psi = \frac{U \cdot y^2}{2 \cdot \delta}$$

The total flow rate per unit depth within the boundary layer is:  $Q = \psi(\delta) - \psi(0) = \frac{U \cdot \delta^2}{2 \cdot \delta} - 0 = \frac{1}{2} \cdot U \cdot \delta$

At one-quarter of the flow rate in the boundary layer:  $Q = \frac{1}{4} \cdot \frac{1}{2} \cdot U \cdot \delta = \frac{1}{8} \cdot U \cdot \delta$  Therefore, the streamline would be located at:

$\frac{1}{8} \cdot U \cdot \delta = \frac{U \cdot y^2}{2 \cdot \delta}$  Solving for y:  $y^2 = \frac{1}{4} \delta^2$  So at one-quarter of the flow rate:

$$\frac{y}{\delta} = \frac{1}{2}$$

At one-half of the flow rate in the boundary layer:  $Q = \frac{1}{2} \cdot \frac{1}{2} \cdot U \cdot \delta = \frac{1}{4} \cdot U \cdot \delta$  Therefore, the streamline would be located at:

$\frac{1}{4} \cdot U \cdot \delta = \frac{U \cdot y^2}{2 \cdot \delta}$  Solving for y:  $y^2 = \frac{1}{2} \delta^2$  So at one-quarter of the flow rate:

$$\frac{y}{\delta} = \frac{1}{\sqrt{2}}$$

## Problem \*5.32

[3]

**\*5.32** A parabolic velocity profile was used to model flow in a laminar incompressible boundary layer in Problem 5.11. Derive the stream function for this flow field. Locate streamlines at one-quarter and one-half the total volume flow rate in the boundary layer.

**Given:** Approximate profile for a laminar boundary layer:

$$\frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2 \quad \delta = c \cdot \sqrt{x} \quad (c \text{ is constant})$$

**Find:** (a) Stream function for the flow field  
(b) Location of streamlines at one-quarter and one-half the total flow rate in the boundary layer.

**Solution:** We will generate the stream function from the velocity field.

**Governing Equations:**  $u = \frac{\partial \psi}{\partial y} \quad v = -\frac{\partial \psi}{\partial x}$  (Definition of stream function)

Integrating the x-component of velocity yields the stream function:

$$\psi = \int U \cdot \left[ 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2 \right] dy + f(x) = U \cdot \delta \cdot \left[ \left(\frac{y}{\delta}\right)^2 - \frac{1}{3} \cdot \left(\frac{y}{\delta}\right)^3 \right] + f(x)$$

If we set  $\psi = 0$  at  $y = 0$  the stream function would be:

$$\psi = U \cdot \delta \cdot \left[ \left(\frac{y}{\delta}\right)^2 - \frac{1}{3} \cdot \left(\frac{y}{\delta}\right)^3 \right]$$

The total flow rate per unit depth within the boundary layer is:  $Q = \psi(\delta) - \psi(0) = U \cdot \delta \cdot \left[ \left(\frac{\delta}{\delta}\right)^2 - \frac{1}{3} \cdot \left(\frac{\delta}{\delta}\right)^3 \right] - 0 = \frac{2}{3} \cdot U \cdot \delta$

At one-quarter of the flow rate in the boundary layer:  $Q = \frac{1}{4} \cdot \frac{2}{3} \cdot U \cdot \delta = \frac{1}{6} \cdot U \cdot \delta$  Therefore, the streamline would be located at:

$$\frac{1}{6} \cdot U \cdot \delta = U \cdot \delta \cdot \left[ \left(\frac{y}{\delta}\right)^2 - \frac{1}{3} \cdot \left(\frac{y}{\delta}\right)^3 \right] \quad \text{or} \quad 2 \cdot \left(\frac{y}{\delta}\right)^3 - 6 \cdot \left(\frac{y}{\delta}\right)^2 + 1 = 0$$

We may solve this cubic for  $y/\delta$  using several methods,

including Goal Seek in Excel or polyroots in Mathcad. Once the roots are determined, only one root would make physical sense.

So at one-quarter of the flow rate:

$$\frac{y}{\delta} = 0.442$$

At one-half of the flow rate in the boundary layer:  $Q = \frac{1}{2} \cdot \frac{2}{3} \cdot U \cdot \delta = \frac{1}{3} \cdot U \cdot \delta$  Therefore, the streamline would be located at:

$$\frac{1}{3} \cdot U \cdot \delta = U \cdot \delta \cdot \left[ \left(\frac{y}{\delta}\right)^2 - \frac{1}{3} \cdot \left(\frac{y}{\delta}\right)^3 \right] \quad \text{or} \quad \left(\frac{y}{\delta}\right)^3 - 3 \cdot \left(\frac{y}{\delta}\right)^2 + 1 = 0$$

We solve this cubic as we solved the previous one.

So at one-half of the flow rate:

$$\frac{y}{\delta} = 0.653$$

## Problem \*5.33

[Difficulty: 3]

**\*5.33** Derive the stream function that represents the sinusoidal approximation used to model the  $x$  component of velocity for the boundary layer of Problem 5.12. Locate streamlines at one-quarter and one-half the total volume flow rate in the boundary layer.

**Given:** Approximate profile for a laminar boundary layer:

$$\frac{u}{U} = \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \quad \delta = c \cdot \sqrt{x} \quad (c \text{ is constant})$$

**Find:** (a) Stream function for the flow field  
(b) Location of streamlines at one-quarter and one-half the total flow rate in the boundary layer.

**Solution:** We will generate the stream function from the velocity field.

**Governing Equations:**  $u = \frac{\partial \psi}{\partial y} \quad v = -\frac{\partial \psi}{\partial x}$  (Definition of stream function)

Integrating the  $x$ -component of velocity yields the stream function:  $\psi = \int U \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) dy + f(x) = -\frac{2 \cdot U \cdot \delta}{\pi} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) + f(x)$

If we set  $\psi = 0$  at  $y = 0$  the stream function would be:

$$\psi = -\frac{2 \cdot U \cdot \delta}{\pi} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right)$$

The total flow rate per unit depth within the boundary layer is:  $Q = \psi(\delta) - \psi(0) = -\frac{2 \cdot U \cdot \delta}{\pi} \cdot \left(\cos\left(\frac{\pi}{2}\right) - \cos(0)\right) = \frac{2 \cdot U \cdot \delta}{\pi}$

At one-quarter of the flow rate in the boundary layer:  $Q = \frac{1}{4} \cdot \frac{2 \cdot U \cdot \delta}{\pi} = \frac{U \cdot \delta}{2 \cdot \pi}$  Therefore, the streamline would be located at:

$$\frac{U \cdot \delta}{2 \cdot \pi} = \frac{2 \cdot U \cdot \delta}{\pi} \cdot \left(1 - \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right)\right) \quad \text{or} \quad \frac{1}{4} = 1 - \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \quad \text{solving for } y/\delta: \quad \frac{y}{\delta} = \frac{2}{\pi} \cdot \arccos\left(\frac{3}{4}\right)$$

So at one-quarter of the flow rate:  $\frac{y}{\delta} = 0.460$

At one-half of the flow rate in the boundary layer:  $Q = \frac{1}{2} \cdot \frac{2 \cdot U \cdot \delta}{\pi} = \frac{U \cdot \delta}{\pi}$  Therefore, the streamline would be located at:

$$\frac{U \cdot \delta}{\pi} = \frac{2 \cdot U \cdot \delta}{\pi} \cdot \left(1 - \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right)\right) \quad \text{or} \quad \frac{1}{2} = 1 - \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right) \quad \text{solving for } y/\delta: \quad \frac{y}{\delta} = \frac{2}{\pi} \cdot \arccos\left(\frac{1}{2}\right)$$

So at one-half of the flow rate:  $\frac{y}{\delta} = 0.667$

## Problem \*5.34

[Difficulty: 3]

**\*5.34** A cubic velocity profile was used to model flow in a laminar incompressible boundary layer in Problem 5.13. Derive the stream function for this flow field. Locate streamlines at one-quarter and one-half the total volume flow rate in the boundary layer.

**Given:** Data on boundary layer

**Find:** Stream function; locate streamlines at 1/4 and 1/2 of total flow rate

**Solution:**

$$u(x, y) = U \cdot \left[ \frac{3}{2} \cdot \left( \frac{y}{\delta} \right) - \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^3 \right] \quad \text{and} \quad \delta(x) = c \cdot \sqrt{x}$$

For the stream function  $u = \frac{\partial \psi}{\partial y} = U \cdot \left[ \frac{3}{2} \cdot \left( \frac{y}{\delta} \right) - \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^3 \right]$

Hence 
$$\psi = \int U \cdot \left[ \frac{3}{2} \cdot \left( \frac{y}{\delta} \right) - \frac{1}{2} \cdot \left( \frac{y}{\delta} \right)^3 \right] dy \quad \psi = U \cdot \left( \frac{3}{4} \cdot \frac{y^2}{\delta} - \frac{1}{8} \cdot \frac{y^4}{\delta^3} \right) + f(x)$$

Let  $\psi = 0 = 0$  along  $y = 0$ , so  $f(x) = 0$ , so 
$$\psi = U \cdot \delta \cdot \left[ \frac{3}{4} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{8} \cdot \left( \frac{y}{\delta} \right)^4 \right]$$

The total flow rate in the boundary layer is

$$\frac{Q}{W} = \psi(\delta) - \psi(0) = U \cdot \delta \cdot \left( \frac{3}{4} - \frac{1}{8} \right) = \frac{5}{8} \cdot U \cdot \delta$$

At 1/4 of the total 
$$\psi - \psi_0 = U \cdot \delta \cdot \left[ \frac{3}{4} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{8} \cdot \left( \frac{y}{\delta} \right)^4 \right] = \frac{1}{4} \cdot \left( \frac{5}{8} \cdot U \cdot \delta \right)$$

$$24 \cdot \left( \frac{y}{\delta} \right)^2 - 4 \cdot \left( \frac{y}{\delta} \right)^4 = 5 \quad \text{or} \quad 4 \cdot X^2 - 24 \cdot X + 5 = 0 \quad \text{where} \quad X^2 = \frac{y}{\delta}$$

The solution to the quadratic is 
$$X = \frac{24 - \sqrt{24^2 - 4 \cdot 4 \cdot 5}}{2 \cdot 4} \quad X = 0.216 \quad \text{Note that the other root is} \quad \frac{24 + \sqrt{24^2 - 4 \cdot 4 \cdot 5}}{2 \cdot 4} = 5.784$$

Hence 
$$\frac{y}{\delta} = \sqrt{X} = 0.465$$

At 1/2 of the total flow 
$$\psi - \psi_0 = U \cdot \delta \cdot \left[ \frac{3}{4} \cdot \left( \frac{y}{\delta} \right)^2 - \frac{1}{8} \cdot \left( \frac{y}{\delta} \right)^4 \right] = \frac{1}{2} \cdot \left( \frac{5}{8} \cdot U \cdot \delta \right)$$

$$12 \cdot \left( \frac{y}{\delta} \right)^2 - 2 \cdot \left( \frac{y}{\delta} \right)^4 = 5 \quad \text{or} \quad 2 \cdot X^2 - 12 \cdot X + 5 = 0 \quad \text{where} \quad X^2 = \frac{y}{\delta}$$

The solution to the quadratic is 
$$X = \frac{12 - \sqrt{12^2 - 4 \cdot 2 \cdot 5}}{2 \cdot 2} \quad X = 0.450 \quad \text{Note that the other root is} \quad \frac{12 + \sqrt{12^2 - 4 \cdot 2 \cdot 5}}{2 \cdot 2} = 5.55$$

Hence 
$$\frac{y}{\delta} = \sqrt{X} = 0.671$$

## Problem \*5.35

[Difficulty: 3]

**\*5.35** A rigid-body motion was modeled in Example 5.6 by the velocity field  $\vec{V} = r\omega\hat{e}_\theta$ . Find the stream function for this flow. Evaluate the volume flow rate per unit depth between  $r_1 = 0.10$  m and  $r_2 = 0.12$  m, if  $\omega = 0.5$  rad/s. Sketch the velocity profile along a line of constant  $\theta$ . Check the flow rate calculated from the stream function by integrating the velocity profile along this line.

**Given:** Rigid body motion in Example Problem 5.6

$$\vec{V} = r\omega\hat{e}_\theta \quad \omega = 0.5 \frac{\text{rad}}{\text{s}}$$

**Find:**

- Stream function for the flow field
- Volume flow rate per unit depth between  $r = 0.10$  m and  $0.12$  m
- Sketch velocity profiles along a line of constant  $\theta$
- Check the volume flow rate calculated from the stream function by integrating the velocity profile along this line.

**Solution:** We will generate the stream function from the velocity field.

**Governing Equations:** 
$$V_r = \frac{1}{r} \frac{\partial \psi}{\partial \theta} \quad V_\theta = -\frac{\partial \psi}{\partial r} \quad \text{(Definition of stream function)}$$

Integrating the  $\theta$ -component of velocity yields the stream function: 
$$\psi = -\int r \cdot \omega \, dr + f(\theta) = -\frac{\omega \cdot r^2}{2} + f(\theta)$$

Now take the derivative of the stream function: 
$$V_r = \frac{1}{r} \cdot \frac{df}{d\theta} = 0 \quad \text{Therefore, } f(\theta) = C$$

$$\psi = -\frac{\omega \cdot r^2}{2} + C$$

The volume flow rate per unit depth is: 
$$Q = \psi(r_2) - \psi(r_1) = \left( -\frac{\omega \cdot r_2^2}{2} + C \right) - \left( -\frac{\omega \cdot r_1^2}{2} + C \right) = \frac{\omega}{2} \cdot (r_1^2 - r_2^2)$$

Substituting in known values: 
$$Q = \frac{1}{2} \times 0.5 \cdot \frac{\text{rad}}{\text{s}} \times (0.10^2 - 0.12^2) \cdot \text{m}^2$$


$$Q = -0.001100 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}}$$

Because  $Q < 0$ , the flow is in the direction of  $-\hat{e}_\theta$

Along a line of constant  $\theta$ , the velocity varies linearly:

From the linear velocity variation,  $V_\theta = \omega \cdot r$ . Thus the flow rate is:

$$Q = \int_{r_1}^{r_2} V_\theta \, dr = \omega \cdot \int_{r_1}^{r_2} r \, dr = \frac{\omega}{2} \cdot (r_2^2 - r_1^2)$$



Substituting known values: 
$$Q = \frac{1}{2} \times 0.5 \cdot \frac{\text{rad}}{\text{s}} \times (0.12^2 - 0.10^2) \cdot \text{m}^2$$


$$Q = 0.001100 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}}$$

These two expressions are the same with the exception of the sign.

## Problem \*5.36

[Difficulty: 3]

**\*5.36** In a parallel one-dimensional flow in the positive  $x$  direction, the velocity varies linearly from zero at  $y = 0$  to 30 m/s at  $y = 1.5$  m. Determine an expression for the stream function,  $\psi$ . Also determine the  $y$  coordinate above which the volume flow rate is half the total between  $y = 0$  and  $y = 1.5$  m.



**Given:** Linear velocity profile

**Find:** Stream function  $\psi$ ;  $y$  coordinate for half of flow

**Solution:**

Basic equations:  $u = \frac{\partial}{\partial y} \psi$        $v = \frac{\partial}{\partial x} \psi$       and we have       $u = U \cdot \left( \frac{y}{h} \right)$        $v = 0$

Assumption: Incompressible flow; flow in  $x$ - $y$  plane

Check for incompressible       $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$

$$\frac{\partial}{\partial x} \left( U \cdot \frac{y}{h} \right) \rightarrow 0$$

$$\frac{\partial}{\partial y} 0 \rightarrow 0$$

Hence       $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$

Flow is INCOMPRESSIBLE

Hence       $u = U \cdot \frac{y}{h} = \frac{\partial}{\partial y} \psi$

$$\psi(x, y) = \int U \cdot \frac{y}{h} dy = \frac{U \cdot y^2}{2 \cdot h} + f(x)$$

and       $v = 0 = \frac{\partial}{\partial x} \psi$

$$\psi(x, y) = - \int 0 dx = g(y)$$

Comparing these       $f(x) = 0$       and

$$g(y) = \frac{U \cdot y^2}{2 \cdot h}$$

The stream function is       $\psi(x, y) = \frac{U \cdot y^2}{2 \cdot h}$

For the flow ( $0 < y < h$ )       $Q = \int_0^h u dy = \frac{U}{h} \cdot \int_0^h y dy = \frac{U \cdot h}{2}$

For half the flow rate       $\frac{Q}{2} = \int_0^{h_{\text{half}}} u dy = \frac{U}{h} \cdot \int_0^{h_{\text{half}}} y dy = \frac{U \cdot h_{\text{half}}^2}{2 \cdot h} = \frac{1}{2} \cdot \left( \frac{U \cdot h}{2} \right) = \frac{U \cdot h}{4}$

Hence       $h_{\text{half}}^2 = \frac{1}{2} \cdot h^2$        $h_{\text{half}} = \frac{1}{\sqrt{2}} \cdot h = \frac{1.5 \cdot \text{m}}{\sqrt{2}} = 1.06 \cdot \text{m}$

## Problem \*5.37

[Difficulty: 3]

**\*5.37** Example 5.6 showed that the velocity field for a free vortex in the  $r\theta$  plane is  $\vec{V} = \hat{e}_\theta C/r$ . Find the stream function for this flow. Evaluate the volume flow rate per unit depth between  $r_1 = 0.20$  m and  $r_2 = 0.24$  m, if  $C = 0.3$  m<sup>2</sup>/s. Sketch the velocity profile along a line of constant  $\theta$ . Check the flow rate calculated from the stream function by integrating the velocity profile along this line.

**Given:** Rigid body motion in Example Problem 5.6

$$\vec{V} = \frac{C}{r} \hat{e}_\theta \quad C = 0.3 \frac{\text{m}^2}{\text{s}}$$

**Find:**

- Stream function for the flow field
- Volume flow rate per unit depth between  $r = 0.20$  m and  $0.24$  m
- Sketch velocity profiles along a line of constant  $\theta$
- Check the volume flow rate calculated from the stream function by integrating the velocity profile along this line.

**Solution:** We will generate the stream function from the velocity field.

**Governing Equations:**  $V_r = \frac{1}{r} \frac{\partial \psi}{\partial \theta} \quad V_\theta = -\frac{\partial \psi}{\partial r}$  (Definition of stream function)

**Assumptions:** Incompressible flow  
Flow is in the  $r$ - $\theta$  plane only

Integrating the  $\theta$ -component of velocity yields the stream function:  $\psi = -\int \frac{C}{r} dr + f(\theta) = -C \cdot \ln(r) + f(\theta)$

Now take the derivative of the stream function:  $V_r = \frac{1}{r} \cdot \frac{d\psi}{d\theta} = 0$  Therefore,  $f(\theta) = C_1$   $\psi = -C \cdot \ln(r) + C_1$


The volume flow rate per unit depth is:  $Q = \psi(r_2) - \psi(r_1) = (-C \cdot \ln(r_2) + C_1) - (-C \cdot \ln(r_1) + C_1) = C \cdot \ln\left(\frac{r_1}{r_2}\right)$

Substituting in known values:  $Q = 0.3 \cdot \frac{\text{m}^2}{\text{s}} \times \ln\left(\frac{0.20}{0.24}\right)$   $Q = -0.0547 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}}$

Because  $Q < 0$ , the flow is in the direction of  $e_\theta$

Along a line of constant  $\theta$ , the velocity varies inversely with  $r$ :

From the velocity profile,  $V_\theta = \frac{C}{r}$  Thus the flow rate is:



$Q = \int_{r_1}^{r_2} V_\theta dr = \int_{r_1}^{r_2} \frac{C}{r} dr = C \cdot \ln\left(\frac{r_2}{r_1}\right)$  Substituting known values:  $Q = 0.3 \cdot \frac{\text{m}^2}{\text{s}} \times \ln\left(\frac{0.24}{0.20}\right)$   $Q = 0.0547 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}}$

These two expressions are the same with the exception of the sign.

## Problem 5.38

[Difficulty: 2]

**5.38** Consider the flow field given by  $\vec{V} = xy^2\hat{i} - \frac{1}{3}y^3\hat{j} + xy\hat{k}$ . Determine (a) the number of dimensions of the flow, (b) if it is a possible incompressible flow, and (c) the acceleration of a fluid particle at point  $(x, y, z) = (1, 2, 3)$ .

**Given:** The velocity field provided above

**Find:** (a) the number of dimensions of the flow  
 (b) if this describes a possible incompressible flow  
 (c) the acceleration of a fluid particle at point (1,2,3)

**Solution:** We will check this flow field against the continuity equation, and then apply the definition of acceleration

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:** (1) Incompressible flow ( $\rho$  is constant)  
 (2) Two dimensional flow (velocity is not a function of  $z$ )  
 (3) Steady flow (velocity is not a function of  $t$ )

Based on assumption (2), we may state that:

The flow is two dimensional.

Based on assumptions (1) and (3), the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$

This is the criterion against which we will check the flow field.

$$\begin{aligned} u &= x \cdot y^2 \\ v &= -\frac{1}{3} \cdot y^3 \end{aligned} \quad \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = y^2 - y^2 = 0$$

This could be an incompressible flow field.

Based on assumptions (2) and (3), the acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y}$  and the partial derivatives of velocity are:

$$\frac{\partial \vec{V}}{\partial x} = y^2\hat{i} + y\hat{k} \quad \text{and} \quad \frac{\partial \vec{V}}{\partial y} = 2xy\hat{i} - y^2\hat{j} + x\hat{k} \quad \text{Therefore the acceleration vector is equal to:}$$

$$\vec{a}_p = xy^2(y^2\hat{i} + y\hat{k}) - \frac{1}{3}y^3(2xy\hat{i} - y^2\hat{j} + x\hat{k}) = \frac{1}{3}xy^4\hat{i} + \frac{1}{3}y^5\hat{j} + \frac{2}{3}xy^3\hat{k} \quad \text{At point (1,2,3), the acceleration is:}$$

$$\vec{a}_p = \left(\frac{1}{3} \times 1 \times 2^4\right)\hat{i} + \left(\frac{1}{3} \times 2^5\right)\hat{j} + \left(\frac{2}{3} \times 1 \times 2^3\right)\hat{k} = \frac{16}{3}\hat{i} + \frac{32}{3}\hat{j} + \frac{16}{3}\hat{k}$$

$$\vec{a}_p = \frac{16}{3}\hat{i} + \frac{32}{3}\hat{j} + \frac{16}{3}\hat{k}$$

## Problem 5.39

[Difficulty: 3]

**5.39** Consider the velocity field  $\vec{V} = A(x^4 - 6x^2y^2 + y^4)\hat{i} + A(4xy^3 - 4x^3y)\hat{j}$  in the  $xy$  plane, where  $A = 0.25 \text{ m}^{-3} \cdot \text{s}^{-1}$ , and the coordinates are measured in meters. Is this a possible incompressible flow field? Calculate the acceleration of a fluid particle at point  $(x, y) = (2, 1)$ .

**Given:** Velocity field

**Find:** Whether flow is incompressible; Acceleration of particle at (2,1)

**Solution:**

**Basic equations:**

$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0 \qquad \bar{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u\frac{\partial\vec{V}}{\partial x} + v\frac{\partial\vec{V}}{\partial y} + w\frac{\partial\vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial\vec{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

$$u(x, y) = A \cdot (x^4 - 6 \cdot x^2 \cdot y^2 + y^4) \qquad v(x, y) = A \cdot (4 \cdot x \cdot y^3 - 4 \cdot x^3 \cdot y)$$

For incompressible flow  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$

Checking  $\frac{\partial}{\partial x}[A \cdot (x^4 - 6 \cdot x^2 \cdot y^2 + y^4)] \rightarrow A \cdot (4 \cdot x^3 - 12 \cdot x \cdot y^2) \quad \frac{\partial}{\partial y}[A \cdot (4 \cdot x \cdot y^3 - 4 \cdot x^3 \cdot y)] \rightarrow -A \cdot (4 \cdot x^3 - 12 \cdot x \cdot y^2)$

Hence  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$

For this flow  $a_x = u \cdot \frac{\partial}{\partial x}u + v \cdot \frac{\partial}{\partial y}u$

$$a_x = A \cdot (x^4 - 6 \cdot x^2 \cdot y^2 + y^4) \cdot \frac{\partial}{\partial x}[A \cdot (x^4 - 6 \cdot x^2 \cdot y^2 + y^4)] + A \cdot (4 \cdot x \cdot y^3 - 4 \cdot x^3 \cdot y) \cdot \frac{\partial}{\partial y}[A \cdot (x^4 - 6 \cdot x^2 \cdot y^2 + y^4)]$$

$$a_x = 4 \cdot A^2 \cdot x \cdot (x^2 + y^2)^3$$

$$a_y = u \cdot \frac{\partial}{\partial x}v + v \cdot \frac{\partial}{\partial y}v$$

$$a_y = A \cdot (x^4 - 6 \cdot x^2 \cdot y^2 + y^4) \cdot \frac{\partial}{\partial x}[A \cdot (4 \cdot x \cdot y^3 - 4 \cdot x^3 \cdot y)] + A \cdot (4 \cdot x \cdot y^3 - 4 \cdot x^3 \cdot y) \cdot \frac{\partial}{\partial y}[A \cdot (4 \cdot x \cdot y^3 - 4 \cdot x^3 \cdot y)]$$

$$a_y = 4 \cdot A^2 \cdot y \cdot (x^2 + y^2)^3$$

Hence at (2,1)  $a_x = 4 \times \left(\frac{1}{4} \cdot \frac{1}{\text{m}^3 \cdot \text{s}}\right)^2 \times 2 \cdot \text{m} \times [(2 \cdot \text{m})^2 + (1 \cdot \text{m})^2]^3 \qquad a_x = 62.5 \frac{\text{m}}{\text{s}^2}$

$$a_y = 4 \times \left(\frac{1}{4} \cdot \frac{1}{\text{m}^3 \cdot \text{s}}\right)^2 \times 1 \cdot \text{m} \times [(2 \cdot \text{m})^2 + (1 \cdot \text{m})^2]^3 \qquad a_y = 31.3 \frac{\text{m}}{\text{s}^2} \qquad a = \sqrt{a_x^2 + a_y^2} \qquad a = 69.9 \frac{\text{m}}{\text{s}^2}$$

## Problem 5.40

[Difficulty: 2]

**5.40** Consider the flow field given by  $\vec{V} = ax^2y\hat{i} - by\hat{j} + cz^2\hat{k}$ , where  $a = 2 \text{ m}^{-2}\cdot\text{s}^{-1}$ ,  $b = 2 \text{ s}^{-1}$ , and  $c = 1 \text{ m}^{-1}\cdot\text{s}^{-1}$ . Determine (a) the number of dimensions of the flow, (b) if it is a possible incompressible flow, and (c) the acceleration of a fluid particle at point  $(x, y, z) = (2, 1, 3)$ .

**Given:** The velocity field provided above

**Find:** (a) the number of dimensions of the flow  
 (b) if this describes a possible incompressible flow  
 (c) the acceleration of a fluid particle at point (2,1,3)

**Solution:** We will check this flow field against the continuity equation, and then apply the definition of acceleration

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:** (1) Incompressible flow ( $\rho$  is constant)  
 (2) Steady flow (velocity is not a function of t)

Since the velocity is a function of x, y, and z, we may state that:

The flow is three dimensional.

Based on assumptions (1) and (2), the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0$

This is the criterion against which we will check the flow field.

$$\begin{aligned} u &= a \cdot x^2 \cdot y \\ v &= -b \cdot y \\ w &= c \cdot z^2 \end{aligned} \quad \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 2axy - b + 2cz \neq 0$$

This can not be incompressible.

Based on assumption (2), the acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}$  and the partial derivatives of velocity are:

$$\frac{\partial \vec{V}}{\partial x} = 2axy\hat{i} \quad \frac{\partial \vec{V}}{\partial y} = ax^2\hat{i} - b\hat{j} \quad \text{and} \quad \frac{\partial \vec{V}}{\partial z} = 2cz\hat{k} \quad \text{Therefore the acceleration vector is equal to:}$$

$$\vec{a}_p = ax^2y(2axy\hat{i}) - by(ax^2\hat{i} - b\hat{j}) + cz^2(2cz\hat{k}) = (2a^2x^3y^2 - abx^2y)\hat{i} + (b^2y)\hat{j} + (2c^2z^3)\hat{k} \quad \text{At point (2,1,3):}$$

$$\begin{aligned} \vec{a}_p &= \left[ 2 \times \left( \frac{2}{\text{m}^2 \cdot \text{s}} \right)^2 \times (2 \text{ m})^3 \times (1 \text{ m})^2 - \frac{2}{\text{m}^2 \cdot \text{s}} \times \frac{2}{\text{s}} \times (2 \text{ m})^2 \times 1 \text{ m} \right] \hat{i} + \left[ \left( \frac{2}{\text{s}} \right)^2 \times 1 \text{ m} \right] \hat{j} + \left[ 2 \times \left( \frac{1}{\text{m} \cdot \text{s}} \right)^2 \times (3 \text{ m})^3 \right] \hat{k} \\ &= 48\hat{i} + 4\hat{j} + 54\hat{k} \frac{\text{m}}{\text{s}^2} \end{aligned}$$

$\vec{a}_p = 48\hat{i} + 4\hat{j} + 54\hat{k} \frac{\text{m}}{\text{s}^2}$

## Problem 5.41

[Difficulty: 3]

**5.41** The  $x$  component of velocity in a steady, incompressible flow field in the  $xy$  plane is  $u = A(x^5 - 10x^3y^2 + 5xy^4)$ , where  $A = 2 \text{ m}^{-4} \cdot \text{s}^{-1}$  and  $x$  is measured in meters. Find the simplest  $y$  component of velocity for this flow field. Evaluate the acceleration of a fluid particle at point  $(x, y) = (1, 3)$ .

**Given:**  $x$  component of velocity field

**Find:** Simplest  $y$  component for incompressible flow; Acceleration of particle at (1,3)

**Solution:**

Basic equations

$$u = \frac{\partial}{\partial y} \psi \quad v = \frac{\partial}{\partial x} \psi \quad \bar{a}_p = \frac{D\bar{V}}{Dt} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \bar{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

We are given 
$$u(x, y) = A \cdot (x^5 - 10x^3 \cdot y^2 + 5 \cdot x \cdot y^4)$$

Hence for incompressible flow 
$$\psi(x, y) = \int u \, dy = \int A \cdot (x^5 - 10x^3 \cdot y^2 + 5 \cdot x \cdot y^4) \, dy = A \cdot \left( x^5 \cdot y - \frac{10}{3} \cdot x^3 \cdot y^3 + x \cdot y^5 \right) + f(x)$$

$$v(x, y) = \frac{\partial}{\partial x} \psi(x, y) = \frac{\partial}{\partial x} \left[ A \cdot \left( x^5 \cdot y - \frac{10}{3} \cdot x^3 \cdot y^3 + x \cdot y^5 \right) + f(x) \right] = -A \cdot (5 \cdot x^4 \cdot y - 10 \cdot x^2 \cdot y^3 + y^5) + F(x)$$

Hence 
$$v(x, y) = -A \cdot (5 \cdot x^4 \cdot y - 10 \cdot x^2 \cdot y^3 + y^5) + F(x)$$
 where  $F(x)$  is an arbitrary function of  $x$

The simplest is 
$$v(x, y) = -A \cdot (5 \cdot x^4 \cdot y - 10 \cdot x^2 \cdot y^3 + y^5)$$

For this flow 
$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u$$

$$a_x = A \cdot (x^5 - 10x^3 \cdot y^2 + 5 \cdot x \cdot y^4) \cdot \frac{\partial}{\partial x} [A \cdot (x^5 - 10x^3 \cdot y^2 + 5 \cdot x \cdot y^4)] - A \cdot (5 \cdot x^4 \cdot y - 10 \cdot x^2 \cdot y^3 + y^5) \cdot \frac{\partial}{\partial y} [A \cdot (x^5 - 10x^3 \cdot y^2 + 5 \cdot x \cdot y^4)]$$

$$a_x = 5 \cdot A^2 \cdot x \cdot (x^2 + y^2)^4$$

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v$$

$$a_y = A \cdot (x^5 - 10x^3 \cdot y^2 + 5 \cdot x \cdot y^4) \cdot \frac{\partial}{\partial x} [-A \cdot (5 \cdot x^4 \cdot y - 10 \cdot x^2 \cdot y^3 + y^5)] - A \cdot (5 \cdot x^4 \cdot y - 10 \cdot x^2 \cdot y^3 + y^5) \cdot \frac{\partial}{\partial y} [-A \cdot (5 \cdot x^4 \cdot y - 10 \cdot x^2 \cdot y^3 + y^5)]$$

$$a_y = 5 \cdot A^2 \cdot y \cdot (x^2 + y^2)^4$$

Hence at (1,3) 
$$a_x = 5 \times \left( \frac{1}{2} \cdot \frac{1}{\text{m}^4 \cdot \text{s}} \right)^2 \times 1 \cdot \text{m} \times [(1 \cdot \text{m})^2 + (3 \cdot \text{m})^2]^4 \quad a_x = 1.25 \times 10^4 \frac{\text{m}}{\text{s}^2}$$

$$a_y = 5 \times \left( \frac{1}{2} \cdot \frac{1}{\text{m}^4 \cdot \text{s}} \right)^2 \times 3 \cdot \text{m} \times [(1 \cdot \text{m})^2 + (3 \cdot \text{m})^2]^4 \quad a_y = 3.75 \times 10^4 \frac{\text{m}}{\text{s}^2} \quad a = \sqrt{a_x^2 + a_y^2} \quad a = 3.95 \times 10^4 \frac{\text{m}}{\text{s}^2}$$

## Problem 5.42

[Difficulty: 2]

**5.42** The velocity field within a laminar boundary layer is approximated by the expression

$$\vec{V} = \frac{AUy}{x^{1/2}}\hat{i} + \frac{AUy^2}{4x^{3/2}}\hat{j}$$

In this expression,  $A = 141 \text{ m}^{-1/2}$ , and  $U = 0.240 \text{ m/s}$  is the freestream velocity. Show that this velocity field represents a possible incompressible flow. Calculate the acceleration of a fluid particle at point  $(x, y) = (0.5 \text{ m}, 5 \text{ mm})$ . Determine the slope of the streamline through the point.

**Given:** The velocity field provided above

**Find:** (a) if this describes a possible incompressible flow  
(b) the acceleration of a fluid particle at point  $(x, y) = (0.5 \text{ m}, 5 \text{ mm})$   
(c) the slope of the streamline through that point

**Solution:** We will check this flow field against the continuity equation, and then apply the definition of acceleration

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:**

- (1) Incompressible flow ( $\rho$  is constant)
- (2) Two-dimensional flow (velocity is not a function of  $z$ )
- (3) Steady flow (velocity is not a function of  $t$ )

Based on the assumptions above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$  This is the criterion against which we will check the flow field.

$$u = \frac{A \cdot U \cdot y}{x^{1/2}} \quad v = \frac{A \cdot U \cdot y^2}{4 \cdot x^{3/2}} \quad \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = -\frac{1}{2} \frac{AUy}{x^{3/2}} + 2 \frac{AUy}{4x^{3/2}} = 0 \quad \text{This represents a possible incompressible flow field.}$$

Based on assumptions (2) and (3), the acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y}$  and the partial derivatives of velocity are:

$$\frac{\partial \vec{V}}{\partial x} = -\frac{AUy}{2x^{3/2}}\hat{i} - \frac{3AUy^2}{8x^{5/2}}\hat{j} \quad \text{and} \quad \frac{\partial \vec{V}}{\partial y} = \frac{AU}{x^{1/2}}\hat{i} + \frac{AUy}{2x^{3/2}}\hat{j} \quad \text{Therefore the acceleration vector is equal to:}$$

$$\vec{a}_p = \frac{AUy}{x^{1/2}} \left( -\frac{AUy}{2x^{3/2}}\hat{i} - \frac{3AUy^2}{8x^{5/2}}\hat{j} \right) + \frac{AUy^2}{4x^{3/2}} \left( \frac{AU}{x^{1/2}}\hat{i} + \frac{AUy}{2x^{3/2}}\hat{j} \right) = -\frac{A^2U^2y^2}{4x^2}\hat{i} - \frac{A^2U^2y^3}{4x^3}\hat{j} \quad \text{At } (5 \text{ m}, 5 \text{ mm}):$$

$$\vec{a}_p = -\left[ \frac{1}{4} \times \left( \frac{141}{\text{m}^{1/2}} \right)^2 \times \left( 0.240 \frac{\text{m}}{\text{s}} \right)^2 \times \left( \frac{0.005}{0.5} \right)^2 \right] \hat{i} - \left[ \frac{1}{4} \times \left( \frac{141}{\text{m}^{1/2}} \right)^2 \times \left( 0.240 \frac{\text{m}}{\text{s}} \right)^2 \times \left( \frac{0.005}{0.5} \right)^3 \right] \hat{j}$$

$$\vec{a}_p = -2.86(10^{-2}\hat{i} + 10^{-4}\hat{j})\frac{\text{m}}{\text{s}^2}$$

The slope of the streamline is given by:  $\text{slope} = \frac{v}{u} = \frac{A \cdot U \cdot y^2}{4 \cdot x^2} \cdot \frac{\frac{1}{x}}{A \cdot U \cdot y} = \frac{y}{4 \cdot x}$

Therefore,  $\text{slope} = \frac{0.005}{4 \times 0.5}$

$$\text{slope} = 2.50 \times 10^{-3}$$

## Problem 5.43

[Difficulty: 2]

**5.43** Wave flow of an incompressible fluid into a solid surface follows a sinusoidal pattern. Flow is two-dimensional with the  $x$  axis normal to the surface and  $y$  axis along the wall. The  $x$  component of the flow follows the pattern

$$u = Ax \sin\left(\frac{2\pi t}{T}\right)$$

Determine the  $y$  component of flow ( $v$ ) and the convective and local components of the acceleration vector.

**Given:** X component of a 2-dimensional transient flow.

**Find:** Y component of flow and total acceleration.

**Solution:**

**Governing Equations:**  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0$  (Continuity Equation for an Incompressible Fluid)

$$\bar{a}_p = \frac{D\bar{V}}{Dt} = u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z} + \frac{\partial \bar{V}}{\partial t} \quad (\text{Material Derivative})$$

**Assumptions:** Incompressible fluid  
No motion along the wall ( $x = 0$ ) limited to two dimensions ( $w = 0$ ).

The given or available data is:  $u = Ax \cdot \sin\left(\frac{2\pi t}{T}\right)$   $w = 0$

Simplify the continuity equation to find  $v$ :  $\frac{\partial v}{\partial y} = -\frac{\partial u}{\partial x} = -A \cdot \sin\left(\frac{2\pi t}{T}\right)$

Integrate:  $v = Ay \cdot \sin\left(\frac{2\pi t}{T}\right) + C$

Use the boundary condition of no flow at the origin to solve for the constant of integration

$$v = Ay \cdot \sin\left(\frac{2\pi t}{T}\right)$$

Give the velocity in vector form:  $\bar{V} = A \cdot \sin\left(\frac{2\pi t}{T}\right) \times (x\hat{i} + y\hat{j})$

Use the material derivative to find the acceleration. Start with the convective terms.  $\bar{a}_{p,conv} = u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y}$

$$\bar{a}_{p,conv} = u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} = Ax \cdot \sin\left(\frac{2\pi t}{T}\right) \times A \cdot \sin\left(\frac{2\pi t}{T}\right) \hat{i} + Ay \cdot \sin\left(\frac{2\pi t}{T}\right) \times A \cdot \sin\left(\frac{2\pi t}{T}\right) \hat{j}$$

$$= A^2 \cdot \sin^2\left(\frac{2\pi t}{T}\right) \times (x\hat{i} + y\hat{j})$$

$$\bar{a}_{p,conv} = A^2 \cdot \sin^2\left(\frac{2\pi t}{T}\right) \times (x\hat{i} + y\hat{j})$$

Finish the local term:  $\bar{a}_{p,local} = \frac{\partial \bar{V}}{\partial t} = A \cdot \sin\left(\frac{2\pi t}{T}\right) \times (x\hat{i} + y\hat{j}) = \frac{2\pi}{T} A \cdot \cos\left(\frac{2\pi t}{T}\right)$

$$\bar{a}_{p,local} = \frac{2\pi A}{T} \cos\left(\frac{2\pi t}{T}\right)$$

## Problem 5.44

[Difficulty: 2]

**5.44** The  $y$  component of velocity in a two-dimensional, incompressible flow field is given by  $v = -Axy$ , where  $v$  is in m/s,  $x$  and  $y$  are in meters, and  $A$  is a dimensional constant. There is no velocity component or variation in the  $z$  direction. Determine the dimensions of the constant,  $A$ . Find the simplest  $x$  component of velocity in this flow field. Calculate the acceleration of a fluid particle at point  $(x, y) = (1, 2)$ .

**Given:** The 2-dimensional, incompressible velocity field provided above

**Find:** (a) dimensions of the constant  $A$   
 (b) simplest  $x$ -component of the velocity  
 (c) acceleration of a particle at  $(1, 2)$

**Solution:** We will check the dimensions against the function definition, check the flow field against the continuity equation, and then apply the definition of acceleration.

**Governing Equations:**

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:** (1) Incompressible flow ( $\rho$  is constant)  
 (2) Two-dimensional flow (velocity is not a function of  $z$ )  
 (3) Steady flow (velocity is not a function of  $t$ )

Since  $v = -A \cdot x \cdot y$  it follows that  $A = -\frac{v}{x \cdot y}$  and the dimensions of  $A$  are given by:  $[A] = \left[ \frac{v}{xy} \right] = \frac{L}{t} \cdot \frac{1}{L} \cdot \frac{1}{L} \quad [A] = \frac{1}{Lt}$

Based on the assumptions above, the continuity equation reduces to:  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$  Therefore:  $\frac{\partial v}{\partial y} = -Ax = -\frac{\partial u}{\partial x}$

Integrating with respect to  $x$  will yield the  $x$ -component of velocity:  $u = \int A \cdot x \, dx + f(y) = \frac{1}{2} \cdot A \cdot x^2 + f(y)$

The simplest  $x$ -component of velocity is obtained for  $f(y) = 0$ :

$$u = \frac{1}{2} \cdot A \cdot x^2$$

Based on assumptions (2) and (3), the acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y}$  and the partial derivatives of velocity are:

$\frac{\partial \vec{V}}{\partial x} = Ax\hat{i} - Ay\hat{j}$  and  $\frac{\partial \vec{V}}{\partial y} = -Ax\hat{j}$  Therefore the acceleration vector is equal to:

$$\vec{a}_p = \frac{1}{2} Ax^2 (Ax\hat{i} - Ay\hat{j}) - Axy(-Ax\hat{j}) = \frac{1}{2} A^2 x^3 \hat{i} + \frac{1}{2} A^2 x^2 y \hat{j} \quad \text{At } (1, 2):$$

$$\vec{a}_p = \left( \frac{1}{2} \times A^2 \times 1^3 \right) \hat{i} + \left( \frac{1}{2} \times A^2 \times 1^2 \times 2 \right) \hat{j}$$

$$\vec{a}_p = A^2 \left( \frac{1}{2} \hat{i} + \hat{j} \right)$$

## Problem 5.45

[Difficulty: 2]

**5.45** Consider the velocity field  $\vec{V} = Ax/(x^2 + y^2)\hat{i} + Ay/(x^2 + y^2)\hat{j}$  in the  $xy$  plane, where  $A = 10 \text{ m}^2/\text{s}$ , and  $x$  and  $y$  are measured in meters. Is this an incompressible flow field? Derive an expression for the fluid acceleration. Evaluate the velocity and acceleration along the  $x$  axis, the  $y$  axis, and along a line defined by  $y = x$ . What can you conclude about this flow field?

**Given:** Velocity field

**Find:** Whether flow is incompressible; expression for acceleration; evaluate acceleration along axes and along  $y = x$

**Solution:**

The given data is  $A = 10 \cdot \frac{\text{m}^2}{\text{s}}$   $u(x, y) = \frac{A \cdot x}{x^2 + y^2}$   $v(x, y) = \frac{A \cdot y}{x^2 + y^2}$

For incompressible flow  $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$

Hence, checking  $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = -A \cdot \frac{(x^2 - y^2)}{(x^2 + y^2)^2} + A \cdot \frac{(x^2 - y^2)}{(x^2 + y^2)^2} = 0$  Incompressible flow

The acceleration is given by  $\vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$   
total acceleration of a particle

For the present steady, 2D flow  $a_x = u \cdot \frac{du}{dx} + v \cdot \frac{dv}{dy} = \frac{A \cdot x}{x^2 + y^2} \cdot \left[ \frac{-A \cdot (x^2 - y^2)}{(x^2 + y^2)^2} \right] + \frac{A \cdot y}{x^2 + y^2} \cdot \left[ \frac{-2 \cdot A \cdot x \cdot y}{(x^2 + y^2)^2} \right]$   $a_x = -\frac{A^2 \cdot x}{(x^2 + y^2)^2}$

$a_y = u \cdot \frac{dv}{dx} + v \cdot \frac{dv}{dy} = \frac{A \cdot x}{x^2 + y^2} \cdot \left[ \frac{-2 \cdot A \cdot x \cdot y}{(x^2 + y^2)^2} \right] + \frac{A \cdot y}{x^2 + y^2} \cdot \left[ \frac{A \cdot (x^2 - y^2)}{(x^2 + y^2)^2} \right]$   $a_y = -\frac{A^2 \cdot y}{(x^2 + y^2)^2}$

Along the  $x$  axis  $a_x = -\frac{A^2}{x^3} = -\frac{100}{x^3}$   $a_y = 0$

Along the  $y$  axis  $a_x = 0$   $a_y = -\frac{A^2}{y^3} = -\frac{100}{y^3}$

Along the line  $x = y$   $a_x = -\frac{A^2 \cdot x}{r^4} = -\frac{100 \cdot x}{r^4}$   $a_y = -\frac{A^2 \cdot y}{r^4} = -\frac{100 \cdot y}{r^4}$

where  $r = \sqrt{x^2 + y^2}$

For this last case the acceleration along the line  $x = y$  is  $a = \sqrt{a_x^2 + a_y^2} = -\frac{A^2}{r^4} \cdot \sqrt{x^2 + y^2} = -\frac{A^2}{r^3} = -\frac{100}{r^3}$   $a = -\frac{A^2}{r^3} = -\frac{100}{r^3}$

In each case the acceleration vector points towards the origin, proportional to  $1/\text{distance}^3$ , so the flow field is a radial decelerating flow.


## Problem 5.46

[Difficulty: 2]

**5.46** An incompressible liquid with negligible viscosity flows steadily through a horizontal pipe of constant diameter. In a porous section of length  $L = 0.3$  m, liquid is removed at a constant rate per unit length, so the uniform axial velocity in the pipe is  $u(x) = U(1 - x/2L)$ , where  $U = 5$  m/s. Develop an expression for the acceleration of a fluid particle along the centerline of the porous section.

**Given:** Duct flow with incompressible, inviscid liquid

$$U = 5 \frac{\text{m}}{\text{s}} \quad L = 0.3 \text{ m} \quad u(x) = U \left( 1 - \frac{x}{2L} \right)$$



**Find:** Expression for acceleration along the centerline of the duct

**Solution:** We will apply the definition of acceleration to the velocity.

**Governing Equation:** 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

- Assumptions:**
- (1) Incompressible flow ( $\rho$  is constant)
  - (2) One-dimensional flow along centerline ( $u = u(x)$  only)
  - (3) Steady flow (velocity is not a function of  $t$ )


Based on assumptions (2) and (3), the acceleration reduces to: 
$$a_{px} = u \cdot \frac{\partial}{\partial x} u = \left[ U \left( 1 - \frac{x}{2L} \right) \right] \cdot \left( -\frac{U}{2L} \right) = -\frac{U^2}{2L} \cdot \left( 1 - \frac{x}{2L} \right)$$

$$a_{px} = -\frac{U^2}{2L} \cdot \left( 1 - \frac{x}{2L} \right)$$

## Problem 5.47

[Difficulty: 4]

**5.47** An incompressible liquid with negligible viscosity flows steadily through a horizontal pipe. The pipe diameter linearly varies from 4 in. to 1 in. over a length of 6 ft. Develop an expression for the acceleration of a fluid particle along the pipe centerline. Plot the centerline velocity and acceleration versus position along the pipe, if the inlet centerline velocity is 3 ft/s.



**Given:** Flow in a pipe with variable diameter

**Find:** Expression for particle acceleration; Plot of velocity and acceleration along centerline

**Solution:**

**Basic equations:**

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad \bar{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

**Assumptions:** 1) Incompressible flow  
2) Uniform flow

Continuity reduces to  $\sum_{CS} \vec{V} \cdot \vec{A} = 0$  and for the flow rate  $Q = V \cdot A = V \cdot \frac{\pi \cdot D^2}{4}$

But  $D = D_1 + \frac{(D_0 - D_1)}{L} \cdot x$  where  $D_1$  and  $D_0$  are the inlet and exit diameters, and  $x$  is distance along the pipe of length  $L$ :  $D(0) = D_1$ ,  $D(L) = D_0$ .

Hence  $V_1 \cdot \frac{\pi \cdot D_1^2}{4} = V \cdot \frac{\pi \cdot \left[ D_1 + \frac{(D_0 - D_1)}{L} \cdot x \right]^2}{4}$

$$V = V_1 \cdot \frac{D_1^2}{\left[ D_1 + \frac{(D_0 - D_1)}{L} \cdot x \right]^2} = \frac{V_1}{\left[ 1 + \frac{\left( \frac{D_0}{D_1} - 1 \right)}{L} \cdot x \right]^2} \quad V(x) = \frac{V_1}{\left[ 1 + \frac{\left( \frac{D_0}{D_1} - 1 \right)}{L} \cdot x \right]^2}$$

Some representative values are  $V(0 \cdot \text{ft}) = 3 \cdot \frac{\text{ft}}{\text{s}}$   $V\left(\frac{L}{2}\right) = 7.68 \cdot \frac{\text{ft}}{\text{s}}$   $V(L) = 48 \cdot \frac{\text{ft}}{\text{s}}$

The acceleration is given by  $\bar{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$

total acceleration of a particle

For this flow

$$a_x = V \cdot \frac{\partial}{\partial x} V \quad a_x = \frac{V_i}{\left[1 + \frac{\left(\frac{D_o}{D_i} - 1\right)}{L} \cdot x\right]^2} \cdot \frac{\partial}{\partial x} \left[ \frac{V_i}{\left[1 + \frac{\left(\frac{D_o}{D_i} - 1\right)}{L} \cdot x\right]^2} \right] = - \frac{2 \cdot V_i^2 \cdot \left(\frac{D_o}{D_i} - 1\right)}{L \cdot \left[ \frac{x \cdot \left(\frac{D_o}{D_i} - 1\right)}{L} + 1 \right]^5}$$



$$a_x(x) = - \frac{2 \cdot V_i^2 \cdot \left(\frac{D_o}{D_i} - 1\right)}{L \cdot \left[ \frac{x \cdot \left(\frac{D_o}{D_i} - 1\right)}{L} + 1 \right]^5}$$

Some representative values are  $a_x(0\text{-m}) = 2.25 \cdot \frac{\text{ft}}{\text{s}^2}$

$a_x\left(\frac{L}{2}\right) = 23.6 \cdot \frac{\text{ft}}{\text{s}^2}$

$a_x(L) = 2.30 \times 10^3 \cdot \frac{\text{ft}}{\text{s}^2}$


The following plots can be done in *Excel*



## Problem 5.48

[Difficulty: 2]

**5.48** Consider the low-speed flow of air between parallel disks as shown. Assume that the flow is incompressible and inviscid, and that the velocity is purely radial and uniform at any section. The flow speed is  $V = 15 \text{ m/s}$  at  $R = 75 \text{ mm}$ . Simplify the continuity equation to a form applicable to this flow field. Show that a general expression for the velocity field is  $\vec{V} = V(R/r)\hat{e}_r$  for  $r_i \leq r \leq R$ . Calculate the acceleration of a fluid particle at the locations  $r = r_i$  and  $r = R$ .



**Given:** Incompressible, inviscid flow of air between parallel disks

**Find:** (a) simplified version of continuity equation valid in this flow field  
 (b) show that the velocity is described by:  $\vec{V} = V(R/r)\hat{e}_r$   
 (c) acceleration of a particle at  $r = r_i$ ,  $r = R$

**Solution:** We will apply the conservation of mass and the definition of acceleration to the velocity.

**Governing Equations:** 
$$\frac{1}{r} \frac{\partial}{\partial r}(\rho r V_r) + \frac{1}{r} \frac{\partial \vec{V}}{\partial \theta}(\rho V_\theta) + \frac{\partial}{\partial z}(\rho V_z) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity Equation})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = (\vec{V} \cdot \nabla)\vec{V} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

- Assumptions:**
- (1) Incompressible flow ( $\rho$  is constant)
  - (2) One-dimensional flow (velocity not a function of  $\theta$  or  $z$ )
  - (3) Flow is only in the  $r$ -direction
  - (4) Steady flow (velocity is not a function of  $t$ )

Based on the above assumptions, the continuity equation reduces to:  $\frac{1}{r} \frac{\partial}{\partial r}(r V_r) = 0$  or  $r V_r = C$

Thus:  $V_r = \frac{C}{r}$  should be the form of the solution. Now since at  $r = R$ :  $R \cdot V = C$  it follows that:  $V_r = \frac{R}{r} \cdot V$  or:

$$\vec{V} = V(R/r)\hat{e}_r \quad (\text{Q.E.D.})$$

Based on assumptions (2) - (4), acceleration is radial only, and that acceleration is equal to:  $a_{pr} = V_r \frac{\partial}{\partial r} V_r$


$$a_{pr} = \left( V \cdot \frac{R}{r} \right) \cdot \left( -V \cdot \frac{R}{r^2} \right) = -\frac{V^2}{R} \cdot \left( \frac{R}{r} \right)^3 \quad \text{Therefore, at } r = r_i: \quad a_{pr} = -\left( 15 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{1}{0.075 \cdot \text{m}} \times \left( \frac{75}{25} \right)^3 \quad a_{pr} = -8.1 \times 10^4 \frac{\text{m}}{\text{s}^2}$$

$$\text{Therefore, at } r = R: \quad a_{pr} = -\left( 15 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{1}{0.075 \cdot \text{m}} \times \left( \frac{75}{75} \right)^3 \quad a_{pr} = -3 \times 10^3 \frac{\text{m}}{\text{s}^2}$$

## Problem 5.49

[Difficulty: 2]

**5.49** Solve Problem 4.123 to show that the radial velocity in the narrow gap is  $V_r = Q/2\pi rh$ . Derive an expression for the acceleration of a fluid particle in the gap.



**Given:** Incompressible flow between parallel plates as shown

**Find:** (a) Show that the radial component of velocity is:  $V_r = \frac{Q}{2 \cdot \pi \cdot r \cdot h}$   
 (b) Acceleration in the gap

**Solution:** We will apply the conservation of mass and the definition of acceleration to the velocity.

**Governing Equation:**

$$\frac{1}{r} \frac{\partial}{\partial r} (\rho r V_r) + \frac{1}{r} \frac{\partial \vec{V}}{\partial \theta} (\rho V_\theta) + \frac{\partial}{\partial z} (\rho V_z) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity Equation})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = (\vec{V} \cdot \nabla) \vec{V} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

- Assumptions:**
- (1) Incompressible flow ( $\rho$  is constant)
  - (2) One-dimensional flow (velocity not a function of  $\theta$  or  $z$ )
  - (3) Flow is only in the  $r$ -direction
  - (4) Steady flow (velocity is not a function of  $t$ )

Based on the above assumptions, the continuity equation reduces to:  $\frac{1}{r} \cdot \frac{\partial}{\partial r} (r \cdot V_r) = 0$  or  $r \cdot V_r = C$

Thus:  $V_r = \frac{C}{r}$  should be the form of the solution. Now since the volumetric flow rate is:  $Q = 2 \cdot \pi \cdot r \cdot h \cdot V_r$  it follows that:

$$V_r = \frac{Q}{2 \cdot \pi \cdot r \cdot h}$$

(Q.E.D.)

Based on assumptions (2) - (4), acceleration is radial only, and that acceleration is equal to:  $a_{pr} = V_r \cdot \frac{\partial}{\partial r} V_r$

$$a_{pr} = \frac{Q}{2 \cdot \pi \cdot r \cdot h} \cdot \frac{-Q}{2 \cdot \pi \cdot r^2 \cdot h} = -\left(\frac{Q}{2 \cdot \pi \cdot h}\right)^2 \cdot \frac{1}{r^3}$$

Therefore, the particle acceleration is:

$$\vec{a}_p = -\left(\frac{Q}{2\pi h}\right)^2 \frac{1}{r^3} \hat{e}_r$$

## Problem 5.50

[Difficulty: 4]

**5.50** As part of a pollution study, a model concentration  $c$  as a function of position  $x$  has been developed,

$$c(x) = A(e^{-x/2a} - e^{-x/a})$$

where  $A = 3 \times 10^{-5}$  ppm (parts per million) and  $a = 3$  ft. Plot this concentration from  $x = 0$  to  $x = 30$  ft. If a vehicle with a pollution sensor travels through the area at  $u = U = 70$  ft/s, develop an expression for the measured concentration rate of change of  $c$  with time, and plot using the given data.

- (a) At what location will the sensor indicate the most rapid rate of change?  
 (b) What is the value of this rate of change?

**Given:** Data on pollution concentration

**Find:** Plot of concentration; Plot of concentration over time for moving vehicle; Location and value of maximum rate change

**Solution:**

**Basic equation:** 
$$\frac{D}{Dt} = u \frac{\partial}{\partial x} + v \frac{\partial}{\partial y} + w \frac{\partial}{\partial z} + \frac{\partial}{\partial t} \quad (\text{Material Derivative})$$

**Assumption:** Concentration of pollution is a function of  $x$  only  
 Sensor travels in  $x$ -direction only


For this case we have  $u = U \quad v = 0 \quad w = 0 \quad c(x) = A \cdot \left( e^{-\frac{x}{2 \cdot a}} - e^{-\frac{x}{a}} \right)$


Hence 
$$\frac{Dc}{Dt} = u \cdot \frac{dc}{dx} = U \cdot \frac{d}{dx} \left[ A \cdot \left( e^{-\frac{x}{2 \cdot a}} - e^{-\frac{x}{a}} \right) \right] = \frac{U \cdot A}{a} \cdot \left( e^{-\frac{x}{a}} - \frac{1}{2} \cdot e^{-\frac{x}{2 \cdot a}} \right)$$

We need to convert this to a function of time. For this motion  $u = U$  so  $x = U \cdot t$

$$\frac{Dc}{Dt} = \frac{U \cdot A}{a} \cdot \left( e^{-\frac{U \cdot t}{a}} - \frac{1}{2} \cdot e^{-\frac{U \cdot t}{2 \cdot a}} \right)$$

The following plots can be done in *Excel*





The magnitude of the rate of change is maximized when

$$\frac{d}{dx} \left( \frac{Dc}{Dt} \right) = \frac{d}{dx} \left[ \frac{U \cdot A}{a} \cdot \left( e^{-\frac{x}{a}} - \frac{1}{2} \cdot e^{-\frac{x}{2 \cdot a}} \right) \right] = 0$$

$$\frac{U \cdot A}{\frac{a^2}{2}} \cdot \left( \frac{1}{4} \cdot e^{-\frac{x}{2 \cdot a}} - e^{-\frac{x}{a}} \right) = 0 \quad \text{or} \quad e^{\frac{x}{2 \cdot a}} = 4$$

$$x_{\max} = 2 \cdot a \cdot \ln(4) = 2 \times 3 \cdot \text{ft} \times \ln(4)$$

$$x_{\max} = 8.32 \cdot \text{ft}$$

$$t_{\max} = \frac{x_{\max}}{U} = 8.32 \cdot \text{ft} \times \frac{\text{s}}{70 \cdot \text{ft}}$$

$$t_{\max} = 0.119 \cdot \text{s}$$

$$\frac{Dc_{\max}}{Dt} = \frac{U \cdot A}{a} \cdot \left( e^{-\frac{x_{\max}}{a}} - \frac{1}{2} \cdot e^{-\frac{x_{\max}}{2 \cdot a}} \right)$$

$$\frac{Dc_{\max}}{Dt} = 70 \cdot \frac{\text{ft}}{\text{s}} \times 3 \times 10^{-5} \cdot \text{ppm} \times \frac{1}{3 \cdot \text{ft}} \times \left( e^{-\frac{8.32}{3}} - \frac{1}{2} \times e^{-\frac{8.32}{2 \cdot 3}} \right)$$

$$\frac{Dc_{\max}}{Dt} = -4.38 \times 10^{-5} \cdot \frac{\text{ppm}}{\text{s}}$$

Note that there is another maximum rate, at  $t = 0$  ( $x = 0$ )

$$\frac{Dc_{\max}}{Dt} = 70 \cdot \frac{\text{ft}}{\text{s}} \times 3 \times 10^{-5} \cdot \text{ppm} \times \frac{1}{3 \cdot \text{ft}} \cdot \left( 1 - \frac{1}{2} \right)$$

$$\frac{Dc_{\max}}{Dt} = 3.50 \times 10^{-4} \cdot \frac{\text{ppm}}{\text{s}}$$

## Problem 5.51

[Difficulty: 2]

**5.51** After a rainfall the sediment concentration at a certain point in a river increases at the rate of 100 parts per million (ppm) per hour. In addition, the sediment concentration increases with distance downstream as a result of influx from tributary streams; this rate of increase is 50 ppm per mile. At this point the stream flows at 0.5 mph. A boat is used to survey the sediment concentration. The operator is amazed to find three different apparent rates of change of sediment concentration when the boat travels upstream, drifts with the current, or travels downstream. Explain physically why the different rates are observed. If the speed of the boat is 2.5 mph, compute the three rates of change.

**Given:** Sediment concentration rates in a river after a rainfall are:

$$\frac{\partial c}{\partial t} = 100 \frac{\text{ppm}}{\text{hr}} \quad \frac{\partial c}{\partial x} = 50 \frac{\text{ppm}}{\text{mi}}$$

Stream speed is 0.5 mph, where a boat is used to survey the concentration.  
The boat speed is 2.5 mph.

**Find:** (a) rates of change of sediment concentration observed when boat travels upstream, drifts with the current, or travels downstream.  
(b) explain why the observed rates differ

**Solution:** We will apply the concept of substantial derivative

**Governing Equation:** 
$$\frac{Dc}{Dt} = u \frac{\partial c}{\partial x} + v \frac{\partial c}{\partial y} + w \frac{\partial c}{\partial z} + \frac{\partial c}{\partial t} \quad \text{(Substantial Derivative)}$$

**Assumptions:** (1) One-dimensional motion (velocity not a function of y or z)  
(2) Steady flow (velocity is not a function of t)

Based on the above assumptions, the substantial derivative reduces to: 
$$\frac{Dc}{Dt} = u \frac{\partial c}{\partial x} + \frac{\partial c}{\partial t}$$

To obtain the rates of change from the boat, we set  $u = u_B$

(i) For travel upstream,  $u_B = u_s - V_b$   $u_B = 0.5 \text{ mph} - 2.5 \text{ mph}$   $u_B = -2 \text{ mph}$

$$D_{\text{cup}} = -2.0 \frac{\text{mi}}{\text{hr}} \times 50 \frac{10^{-6}}{\text{mi}} + 100 \frac{10^{-6}}{\text{hr}}$$

$$D_{\text{cup}} = 0.00 \frac{10^{-6}}{\text{hr}}$$

(ii) For drifting,  $u_B = u_s$   $u_B = 0.5 \text{ mph}$

$$D_{\text{cdrift}} = 0.5 \frac{\text{mi}}{\text{hr}} \times 50 \frac{10^{-6}}{\text{mi}} + 100 \frac{10^{-6}}{\text{hr}}$$

$$D_{\text{cdrift}} = 125.0 \frac{10^{-6}}{\text{hr}}$$

(iii) For travel downstream,  $u_B = u_s + V_b$   $u_B = 0.5 \text{ mph} + 2.5 \text{ mph}$   $u_B = 3 \text{ mph}$

$$D_{\text{cdown}} = 3.0 \frac{\text{mi}}{\text{hr}} \times 50 \frac{10^{-6}}{\text{mi}} + 100 \frac{10^{-6}}{\text{hr}}$$

$$D_{\text{cdown}} = 250 \frac{10^{-6}}{\text{hr}}$$

Physically the observed rates of change differ because the observer is convected through the flow. The convective change may add to or subtract from the local rate of change.

## Problem 5.52

[Difficulty: 2]

**5.52** As an aircraft flies through a cold front, an onboard instrument indicates that ambient temperature drops at the rate of  $0.7^\circ\text{F}/\text{min}$ . Other instruments show an air speed of 400 knots and a 2500 ft/min rate of climb. The front is stationary and vertically uniform. Compute the rate of change of temperature with respect to horizontal distance through the cold front.

**Given:** Instruments on board an aircraft flying through a cold front show ambient temperature dropping at  $0.7^\circ\text{F}/\text{min}$ , air speed of 400 knots and 2500 ft/min rate of climb.

**Find:** Rate of temperature change with respect to horizontal distance through cold front.


**Solution:** We will apply the concept of substantial derivative

**Governing Equation:** 
$$\frac{DT}{Dt} = u \frac{\partial T}{\partial x} + v \frac{\partial T}{\partial y} + w \frac{\partial T}{\partial z} + \frac{\partial T}{\partial t} \quad (\text{Substantial Derivative})$$

- Assumptions:**
- (1) Two-dimensional motion (velocity not a function of  $z$ )
  - (2) Steady flow (velocity is not a function of  $t$ )
  - (3) Temperature is constant in  $y$  direction

Based on the above assumptions, the substantial derivative reduces to: 
$$\frac{DT}{Dt} = u \frac{\partial T}{\partial x}$$

Finding the velocity components: 
$$V = 400 \cdot \frac{\text{nmi}}{\text{hr}} \times \frac{6080 \cdot \text{ft}}{\text{nmi}} \times \frac{\text{hr}}{3600 \cdot \text{s}} \quad V = 675.56 \cdot \frac{\text{ft}}{\text{s}} \quad v = 2500 \cdot \frac{\text{ft}}{\text{min}} \times \frac{\text{min}}{60 \cdot \text{s}} \quad v = 41.67 \cdot \frac{\text{ft}}{\text{s}}$$



Therefore: 
$$u = \sqrt{\left(675.56 \cdot \frac{\text{ft}}{\text{s}}\right)^2 - \left(41.67 \cdot \frac{\text{ft}}{\text{s}}\right)^2} \quad u = 674.27 \cdot \frac{\text{ft}}{\text{s}}$$

So the rate of change of temperature through the cold front is: 
$$\delta T_x = \frac{-0.7 \cdot \Delta^\circ\text{F}}{\text{min}} \times \frac{\text{s}}{674.27 \cdot \text{ft}} \times \frac{\text{min}}{60 \cdot \text{s}} \times \frac{5280 \cdot \text{ft}}{\text{mi}}$$

$$\delta T_x = -0.0914 \cdot \frac{\Delta^\circ\text{F}}{\text{mi}}$$

## Problem 5.53

[Difficulty: 2]

**5-53** An aircraft flies due north at 300 mph ground speed. Its rate of climb is 3000 ft/min. The vertical temperature gradient is  $-3^\circ\text{F}$  per 1000 ft of altitude. The ground temperature varies with position through a cold front, falling at the rate of  $1^\circ\text{F}$  per mile. Compute the rate of temperature change shown by a recorder on board the aircraft.

**Given:** Aircraft flying north with speed of 300 mph with respect to ground, 3000 ft/min vertical. Rate of temperature change is  $-3$  deg F/1000 ft altitude. Ground temperature varied 1 deg F/mile.

**Find:** Rate of temperature change shown by on-board flight recorder

**Solution:** We will apply the concept of substantial derivative

**Governing Equation:** 
$$\frac{DT}{Dt} = u \frac{\partial T}{\partial x} + v \frac{\partial T}{\partial y} + w \frac{\partial T}{\partial z} + \frac{\partial T}{\partial t}$$
 (Substantial Derivative)

**Assumptions:** (1) Two-dimensional motion (velocity not a function of  $z$ )  
(2) Steady flow (velocity is not a function of  $t$ )

Based on the above assumptions, the substantial derivative reduces to: 
$$\frac{DT}{Dt} = u \frac{\partial T}{\partial x} + v \frac{\partial T}{\partial y}$$

Substituting numerical values: 
$$\delta T = \left( 300 \cdot \frac{\text{mi}}{\text{hr}} \times \frac{-1 \cdot \Delta^\circ\text{F}}{\text{mi}} \times \frac{\text{hr}}{60 \cdot \text{min}} \right) + \left( 3000 \cdot \frac{\text{ft}}{\text{min}} \times \frac{-3 \cdot \Delta^\circ\text{F}}{1000 \cdot \text{ft}} \right)$$

$$\delta T = -14 \cdot \frac{\Delta^\circ\text{F}}{\text{min}}$$

## Problem 5.54

[Difficulty: 4]

**5.54** Wave flow of an incompressible fluid into a solid surface follows a sinusoidal pattern. Flow is axisymmetric about the  $z$  axis, which is normal to the surface. The  $z$  component of the flow follows the pattern

$$V_z = Az \sin\left(\frac{2\pi t}{T}\right)$$

Determine (a) the radial component of flow ( $V_r$ ) and (b) the convective and local components of the acceleration vector.

**Given:**  $Z$  component of an axisymmetric transient flow.

**Find:** Radial component of flow and total acceleration.

**Solution:**

**Governing Equations:**  $\frac{1}{r} \frac{\partial(rV_r)}{\partial r} + \frac{1}{r} \frac{\partial V_\theta}{\partial \theta} + \frac{\partial V_z}{\partial z} = 0$  (Continuity Equation for an Incompressible Fluid)

$$a_{r,p} = V_r \frac{\partial V_r}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_r}{\partial \theta} - \frac{V_\theta^2}{r} + V_z \frac{\partial V_r}{\partial z} + \frac{\partial V_r}{\partial t} \quad \text{(Particle acceleration)}$$

$$a_{z,p} = V_r \frac{\partial V_z}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_z}{\partial \theta} + V_z \frac{\partial V_z}{\partial z} + \frac{\partial V_z}{\partial t}$$

**Assumptions:** Incompressible fluid  
No motion along the wall ( $z = 0$ ) limited to two dimensions ( $V_\theta = 0$  and all partials with respect to  $\theta$  are zero).

The given or available data is:  $V_z = Az \cdot \sin\left(\frac{2\pi t}{T}\right) \quad V_\theta = 0 \quad \frac{\partial(\quad)}{\partial \theta} = 0$

Simplify the continuity equation to find  $V_r$ :  $\frac{1}{r} \frac{\partial(rV_r)}{\partial r} = -\frac{\partial V_z}{\partial z} \Rightarrow \frac{\partial(rV_r)}{\partial r} = r \times -A \cdot \sin\left(\frac{2\pi t}{T}\right)$

Solve using separation of variables:  $rV_r = -\frac{r^2 A}{2} \cdot \sin\left(\frac{2\pi t}{T}\right) + C$

Use the boundary condition of no flow at the origin to solve for the constant of integration

$$V_r = -\frac{rA}{2} \cdot \sin\left(\frac{2\pi t}{T}\right)$$

Find the convective terms of acceleration.  $a_{r,conv} = V_r \frac{\partial V_r}{\partial r} + V_z \frac{\partial V_r}{\partial z} = -\frac{rA}{2} \sin\left(\frac{2\pi t}{T}\right) \times -\frac{A}{2} \sin\left(\frac{2\pi t}{T}\right) + Az \sin\left(\frac{2\pi t}{T}\right) \times 0$

$$a_{r,conv} = \frac{rA^2}{4} \sin^2\left(\frac{2\pi t}{T}\right)$$

$a_{z,conv} = V_r \frac{\partial V_z}{\partial r} + V_z \frac{\partial V_z}{\partial z} = -\frac{rA}{2} \sin\left(\frac{2\pi t}{T}\right) \times 0 + Az \cdot \sin\left(\frac{2\pi t}{T}\right) \times A \cdot \sin\left(\frac{2\pi t}{T}\right)$

$$a_{z,conv} = zA^2 \sin^2\left(\frac{2\pi t}{T}\right)$$

Find the local terms:

$$a_{r,local} = \frac{\partial V_r}{\partial t} = -\frac{2\pi}{T} \times \frac{rA}{2} \cos\left(\frac{2\pi t}{T}\right)$$

$$a_{r,local} = \frac{-\pi r A}{T} \cos\left(\frac{2\pi t}{T}\right)$$

$$a_{z,local} = \frac{\partial V_z}{\partial t} = -\frac{2\pi}{T} \times Az \cdot \cos\left(\frac{2\pi t}{T}\right)$$

$$a_{z,local} = \frac{2\pi z A}{T} \cos\left(\frac{2\pi t}{T}\right)$$

## Problem 5.55

[Difficulty: 3]

**5.55** Expand  $(\vec{V} \cdot \nabla)\vec{V}$  in rectangular coordinates by direct substitution of the velocity vector to obtain the convective acceleration of a fluid particle. Verify the results given in Eqs. 5.11.

**Given:** Definition of "del" operator

**Find:** an expression for the convective acceleration for a fluid particle.

**Solution:** We will directly substitute the velocity vector into the expression.

**Governing Equation:** 
$$\nabla = \frac{\partial}{\partial x} \hat{i} + \frac{\partial}{\partial y} \hat{j} + \frac{\partial}{\partial z} \hat{k}$$
 ("del" operator in rectangular coordinates)

$$\vec{V} = u\hat{i} + v\hat{j} + w\hat{k}$$
 (velocity vector)

**Assumptions:** None.

Directly substituting we get:

$$\begin{aligned} (\vec{V} \cdot \nabla)\vec{V} &= (u\hat{i} + v\hat{j} + w\hat{k}) \cdot \left( \frac{\partial}{\partial x} \hat{i} + \frac{\partial}{\partial y} \hat{j} + \frac{\partial}{\partial z} \hat{k} \right) (u\hat{i} + v\hat{j} + w\hat{k}) \\ &= \left( u \frac{\partial}{\partial x} + v \frac{\partial}{\partial y} + w \frac{\partial}{\partial z} \right) (u\hat{i} + v\hat{j} + w\hat{k}) \\ &= \left( u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) \hat{i} + \left( u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) \hat{j} + \left( u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) \hat{k} \end{aligned}$$

The components of this vector are the x-, y-, and z-components of the convective acceleration:

$$\begin{aligned} a_{xp} &= \left( u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) + \frac{\partial u}{\partial t} \\ a_{yp} &= \left( u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) + \frac{\partial v}{\partial t} \\ a_{zp} &= \left( u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) + \frac{\partial w}{\partial t} \end{aligned}$$

## Problem 5.56

[Difficulty: 3]

**5.56** A steady, two-dimensional velocity field is given by  $\vec{V} = Ax\hat{i} - Ay\hat{j}$ , where  $A = 1\text{ s}^{-1}$ . Show that the streamlines for this flow are rectangular hyperbolas,  $xy = C$ . Obtain a general expression for the acceleration of a fluid particle in this velocity field. Calculate the acceleration of fluid particles at the points  $(x, y) = (\frac{1}{2}, 2)$ ,  $(1, 1)$ , and  $(2, \frac{1}{2})$ , where  $x$  and  $y$  are measured in meters. Plot streamlines that correspond to  $C = 0, 1$ , and  $2\text{ m}^2$  and show the acceleration vectors on the streamline plot.

**Given:** Steady, two-dimensional velocity field represented above

**Find:** (a) proof that streamlines are hyperbolas ( $xy = C$ )  
 (b) acceleration of a particle in this field  
 (c) acceleration of particles at  $(x,y) = (1/2\text{m}, 2\text{m})$ ,  $(1\text{m}, 1\text{m})$ , and  $(2\text{m}, 1/2\text{m})$   
 (d) plot streamlines corresponding to  $C = 0, 1$ , and  $2\text{ m}^2$  and show accelerations

**Solution:** We will apply the acceleration definition, and determine the streamline slope.

**Governing Equations:** 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:** (1) Two-dimensional flow (velocity is not a function of  $z$ )  
 (2) Incompressible flow

Streamlines along the  $x$ - $y$  plane are defined by  $\frac{dy}{dx} = \frac{v}{u} = \frac{-A \cdot y}{A \cdot x}$  Thus:  $\frac{dx}{x} + \frac{dy}{y} = 0$


After integrating:  $\ln(x) + \ln(y) = \ln(C)$  which yields:  $xy = C$  (Q.E.D.)

Based on the above assumptions the particle acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y}$  Substituting in the field:

$$\vec{a}_p = (Ax)A\hat{i} + (-Ay)(-A)\hat{j} = A^2(x\hat{i} + y\hat{j}) \quad \text{which simplifies to} \quad \vec{a}_p = A^2(x\hat{i} + y\hat{j})$$

At  $(x,y) = (0.5\text{m}, 2\text{m})$   $\vec{a}_p = (0.5\hat{i} + 2\hat{j}) \frac{\text{m}}{\text{s}^2}$     At  $(x,y) = (1\text{m}, 1\text{m})$   $\vec{a}_p = (\hat{i} + \hat{j}) \frac{\text{m}}{\text{s}^2}$     At  $(x,y) = (2\text{m}, 0.5\text{m})$   $\vec{a}_p = (2\hat{i} + 0.5\hat{j}) \frac{\text{m}}{\text{s}^2}$

Here is the plot of the streamlines:  
 (When  $C = 0$  the streamline is on the  $x$ - and  $y$ -axes.)



## Problem 5.57

[Difficulty: 3]

**5.57** A velocity field is represented by the expression  $\vec{V} = (Ax - B)\hat{i} - Ay\hat{j}$ , where  $A = 0.2 \text{ s}^{-1}$ ,  $B = 0.6 \text{ m} \cdot \text{s}^{-1}$ , and the coordinates are expressed in meters. Obtain a general expression for the acceleration of a fluid particle in this velocity field. Calculate the acceleration of fluid particles at points  $(x, y) = (0, \frac{4}{3})$ ,  $(1, 2)$ , and  $(2, 4)$ . Plot a few streamlines in the  $xy$  plane. Show the acceleration vectors on the streamline plot.

**Given:** Steady, two-dimensional velocity field represented above

**Find:** (a) general acceleration of a particle in this field  
 (b) acceleration of particles at  $(x,y) = (0\text{m}, 4/3\text{m})$ ,  $(1\text{m}, 2\text{m})$ , and  $(2\text{m}, 4\text{m})$   
 (c) plot streamlines with acceleration vectors

**Solution:** We will apply the acceleration definition, and determine the streamline slope.

**Governing Equations:** 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:** (1) Two-dimensional flow (velocity is not a function of  $z$ )  
 (2) Incompressible flow

Based on the above assumptions the particle acceleration reduces to: 
$$\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} \quad \text{Substituting in the field:}$$

$$\vec{a}_p = (Ax - B)A\hat{i} + (-Ay)(-A)\hat{j} = (A^2x - AB)\hat{i} + (A^2y)\hat{j} \qquad \vec{a}_p = (A^2x - AB)\hat{i} + (A^2y)\hat{j}$$

At  $(x,y) = (0\text{m}, 4/3\text{m})$  
$$\vec{a}_p = (-0.12\hat{i} + 0.0533\hat{j}) \frac{\text{m}}{\text{s}^2}$$

At  $(x,y) = (1\text{m}, 1\text{m})$  
$$\vec{a}_p = (-0.08\hat{i} + 0.0800\hat{j}) \frac{\text{m}}{\text{s}^2}$$


At  $(x,y) = (2\text{m}, 0.5\text{m})$  
$$\vec{a}_p = (-0.04\hat{i} + 0.160\hat{j}) \frac{\text{m}}{\text{s}^2}$$

Streamlines along the  $x$ - $y$  plane are defined by  $\frac{dy}{dx} = \frac{v}{u} = \frac{-A \cdot y}{A \cdot x - B}$  Thus:  $\frac{dx}{A \cdot x - B} + \frac{dy}{A \cdot y} = 0$  After integrating:

$$\frac{1}{A} \cdot \ln(A \cdot x - B) + \frac{1}{A} \cdot \ln(y) = \frac{1}{A} \cdot \ln(C) \quad \text{which yields:}$$

Here is the plot of the streamlines:

$$(A \cdot x - B) \cdot y = C$$



## Problem 5.58

[Difficulty: 3]

**5.58** A velocity field is represented by the expression  $\vec{V} = (Ax - B)\hat{i} + Cy\hat{j} + Dt\hat{k}$ , where  $A = 2 \text{ s}^{-1}$ ,  $B = 4 \text{ m} \cdot \text{s}^{-1}$ ,  $D = 5 \text{ m} \cdot \text{s}^{-2}$ , and the coordinates are measured in meters. Determine the proper value for  $C$  if the flow field is to be incompressible. Calculate the acceleration of a fluid particle located at point  $(x, y) = (3, 2)$ . Plot a few flow streamlines in the  $xy$  plane.

**Given:** Velocity field represented above

**Find:** (a) the proper value for  $C$  if the flow field is incompressible  
 (b) acceleration of a particle at  $(x,y) = (3\text{m},2\text{m})$   
 (c) sketch the streamlines in the  $x$ - $y$  plane

**Solution:** We will check the velocity field against the continuity equation, apply the acceleration definition, and determine the streamline slope.

**Governing Equations:** 
$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:** (1) Two-dimensional flow (velocity is not a function of  $z$ )  
 (2) Incompressible flow

Based on the above assumptions the continuity equation reduces to:  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$  This is the criterion to check the velocity.

The partial derivatives are:  $\frac{\partial}{\partial x}u = A$  and  $\frac{\partial}{\partial y}v = C$  Thus from continuity:  $A + C = 0$  or  $C = -A$   $C = -2 \cdot \text{s}^{-1}$

Based on the above assumptions the particle acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + \frac{\partial \vec{V}}{\partial t}$  Substituting in the field:

$$\vec{a}_p = (Ax - B)A\hat{i} + (Cy)C\hat{j} + D\hat{k} = (A^2x - AB)\hat{i} + C^2y\hat{j} + D\hat{k} \quad \text{At } (x,y) = (3\text{m}, 2\text{m})$$


$$\vec{a}_p = \left[ \left(\frac{2}{\text{s}}\right)^2 \times 3 \text{ m} - \frac{2}{\text{s}} \times 4 \frac{\text{m}}{\text{s}} \right] \hat{i} + \left(-\frac{2}{\text{s}}\right)^2 \times 2 \text{ m} \hat{j} + 5 \frac{\text{m}}{\text{s}^2} \hat{k} \quad \vec{a}_p = (4\hat{i} + 8\hat{j} + 5\hat{k}) \frac{\text{m}}{\text{s}^2}$$

Streamlines along the  $x$ - $y$  plane are defined by  $\frac{dy}{dx} = \frac{v}{u} = \frac{C \cdot y}{A \cdot x - B}$  Thus:  $-\frac{1}{A} \cdot \frac{dy}{y} = \frac{dx}{A \cdot x - B}$  or  $\frac{dx}{x - \frac{B}{A}} + \frac{dy}{y} = 0$

Solving this ODE by integrating:  $\ln\left(x - \frac{B}{A}\right) + \ln(y) = \text{const}$

Therefore:  $y \cdot \left(x - \frac{B}{A}\right) = \text{constant}$

Here is a plot of the streamlines passing through  $(3, 2)$ :



## Problem 5.59

[Difficulty: 3]

**5.59** A linear approximate velocity profile was used in Problem 5.10 to model a laminar incompressible boundary layer on a flat plate. For this profile, obtain expressions for the  $x$  and  $y$  components of acceleration of a fluid particle in the boundary layer. Locate the maximum magnitudes of the  $x$  and  $y$  accelerations. Compute the ratio of the maximum  $x$  magnitude to the maximum  $y$  magnitude for the flow conditions of Problem 5.10.

**5.10** A crude approximation for the  $x$  component of velocity in an incompressible laminar boundary layer is a linear variation from  $u = 0$  at the surface ( $y = 0$ ) to the freestream velocity,  $U$ , at the boundary-layer edge ( $y = \delta$ ). The equation for the profile is  $u = Uy/\delta$ , where  $\delta = cx^{1/2}$  and  $c$  is a constant. Show that the simplest expression for the  $y$  component of velocity is  $v = uy/4x$ . Evaluate the maximum value of the ratio  $v/U$ , at a location where  $x = 0.5$  m and  $\delta = 5$  mm.

**Given:** Linear approximate profile for two-dimensional boundary layer

**Find:** (a)  $x$ - and  $y$ -components of acceleration of a fluid particle  
(b) locate the maximum values of acceleration  
(c) compute ratio of maximum acceleration components

**Solution:** We will apply the acceleration definition.

**Governing Equation:** 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

**Assumptions:** (1) Two-dimensional flow (velocity is not a function of  $z$ )  
(2) Incompressible flow  
(3) Steady flow

Based on the above assumptions the particle acceleration reduces to: 
$$\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y}$$
 The velocities and derivatives are:

$$u = \frac{U \cdot y}{\delta} \quad v = \frac{u \cdot y}{4 \cdot x} = \frac{U \cdot y^2}{4 \cdot \delta \cdot x} \quad \delta = c \cdot x^{\frac{1}{2}} \quad \frac{\partial u}{\partial x} = \frac{\partial}{\partial \delta} \left( \frac{U \cdot y}{\delta} \right) \cdot \left( \frac{d}{dx} \delta \right) = -\frac{U \cdot y}{\delta^2} \cdot \frac{\delta}{2 \cdot x} = -\frac{U \cdot y}{2 \cdot \delta \cdot x} \quad \frac{\partial u}{\partial y} = \frac{U}{\delta}$$

$$\frac{\partial v}{\partial x} = \frac{\partial}{\partial x} \left( \frac{U \cdot y^2}{4 \cdot \delta \cdot x} \right) + \frac{\partial}{\partial \delta} \left( \frac{U \cdot y^2}{4 \cdot \delta \cdot x} \right) \cdot \left( \frac{d}{dx} \delta \right) = -\frac{U \cdot y^2}{4 \cdot \delta \cdot x^2} - \frac{U \cdot y^2}{4 \cdot \delta^2 \cdot x} \cdot \frac{\delta}{2 \cdot x} = -\frac{3 \cdot U \cdot y^2}{8 \cdot \delta \cdot x^2} \quad \frac{\partial v}{\partial y} = \frac{U \cdot y}{2 \cdot \delta \cdot x}$$
 So the accelerations are:

$$a_{px} = u \cdot \frac{\partial u}{\partial x} + v \cdot \frac{\partial u}{\partial y} = -\frac{U \cdot y}{\delta} \cdot \frac{U \cdot y}{2 \cdot \delta \cdot x} + \frac{U \cdot y^2}{4 \cdot \delta \cdot x} \cdot \frac{U}{\delta} = -\frac{U^2 \cdot y^2}{4 \cdot \delta \cdot x}$$

$$a_{px} = -\frac{U^2}{4 \cdot x} \cdot \left( \frac{y}{\delta} \right)^2$$

$$a_{py} = u \cdot \frac{\partial v}{\partial x} + v \cdot \frac{\partial v}{\partial y} = -\frac{U \cdot y}{\delta} \cdot \frac{3 \cdot U \cdot y^2}{8 \cdot \delta \cdot x^2} + \frac{U \cdot y^2}{4 \cdot \delta \cdot x} \cdot \frac{U \cdot y}{2 \cdot \delta \cdot x} = -\frac{U \cdot y^3}{4 \cdot \delta^2 \cdot x^2}$$

$$a_{py} = -\frac{U^2}{4 \cdot x} \cdot \left( \frac{y}{\delta} \right)^2 \cdot \frac{y}{x}$$

The maximum values are when  $y = \delta$ :

The ratio of the accelerations is: 
$$\frac{a_{py\max}}{a_{px\max}} = \frac{U^2}{4 \cdot x} \cdot \frac{4 \cdot x}{U^2} \cdot \frac{\delta}{x} = \frac{\delta}{x}$$

$$a_{px\max} = -\frac{U^2}{4 \cdot x} \quad a_{py\max} = -\frac{U^2}{4 \cdot x} \cdot \frac{\delta}{x}$$


When  $x = 0.5$  m and  $\delta = 5$  mm: 
$$\text{ratio} = \frac{0.5 \cdot \text{m}}{0.005 \cdot \text{m}}$$

$$\text{ratio} = 100$$

## Problem 5.60

[Difficulty: 4]

**5.60** A parabolic approximate velocity profile was used in Problem 5.11 to model flow in a laminar incompressible boundary layer on a flat plate. For this profile, find the  $x$  component of acceleration,  $a_x$ , of a fluid particle within the boundary layer. Plot  $a_x$  at location  $x = 0.8$  m, where  $\delta = 1.2$  mm, for a flow with  $U = 6$  m/s. Find the maximum value of  $a_x$  at this  $x$  location.



**Given:** Flow in boundary layer

**Find:** Expression for particle acceleration  $a_x$ ; Plot acceleration and find maximum at  $x = 0.8$  m

**Solution:**

Basic equations 
$$\frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2 \quad \frac{v}{U} = \frac{\delta}{x} \cdot \left[ \frac{1}{2} \cdot \left(\frac{y}{\delta}\right) - \frac{1}{3} \cdot \left(\frac{y}{\delta}\right)^3 \right] \quad \delta = c \cdot \sqrt{x}$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

We need to evaluate 
$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u$$

First, substitute 
$$\lambda(x, y) = \frac{y}{\delta(x)} \quad \text{so} \quad \frac{u}{U} = 2 \cdot \lambda - \lambda^2 \quad \frac{v}{U} = \frac{\delta}{x} \cdot \left( \frac{1}{2} \cdot \lambda - \frac{1}{3} \cdot \lambda^3 \right)$$

Then 
$$\frac{\partial}{\partial x} u = \frac{du}{d\lambda} \cdot \frac{d\lambda}{dx} = U \cdot (2 - 2 \cdot \lambda) \cdot \left( -\frac{y}{\delta^2} \right) \cdot \frac{d\delta}{dx} \quad \frac{d\delta}{dx} = \frac{1}{2} \cdot c \cdot x^{-\frac{1}{2}}$$

$$\frac{\partial}{\partial x} u = U \cdot (2 - 2 \cdot \lambda) \cdot \left( -\frac{\lambda}{\delta} \right) \cdot \frac{1}{2} \cdot c \cdot x^{-\frac{1}{2}} = U \cdot (2 - 2 \cdot \lambda) \cdot \left( -\frac{\lambda}{\frac{1}{c \cdot x^{\frac{1}{2}}}} \right) \cdot \frac{1}{2} \cdot c \cdot x^{-\frac{1}{2}}$$

$$\frac{\partial}{\partial x} u = -U \cdot (2 - 2 \cdot \lambda) \cdot \frac{\lambda}{2 \cdot x} = -\frac{U \cdot (\lambda - \lambda^2)}{x}$$

$$\frac{\partial}{\partial y} u = U \cdot \left( \frac{2}{\delta} - 2 \cdot \frac{y}{\delta^2} \right) = \frac{2 \cdot U}{\delta} \cdot \left[ \frac{y}{\delta} - \left( \frac{y}{\delta} \right)^2 \right] = \frac{2 \cdot U \cdot (\lambda - \lambda^2)}{y}$$

Hence 
$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = U \cdot (2 \cdot \lambda - \lambda^2) \cdot \left[ \frac{U \cdot (\lambda - \lambda^2)}{x} \right] + U \cdot \frac{\delta}{x} \cdot \left( \frac{1}{2} \cdot \lambda - \frac{1}{3} \cdot \lambda^3 \right) \cdot \left[ \frac{2 \cdot U \cdot (\lambda - \lambda^2)}{y} \right]$$

Collecting terms 
$$a_x = \frac{U^2}{x} \cdot \left( -\lambda^2 + \frac{4}{3} \cdot \lambda^3 - \frac{1}{3} \cdot \lambda^4 \right) = \frac{U^2}{x} \cdot \left[ -\left( \frac{y}{\delta} \right)^2 + \frac{4}{3} \cdot \left( \frac{y}{\delta} \right)^3 - \frac{1}{3} \cdot \left( \frac{y}{\delta} \right)^4 \right]$$

To find the maximum 
$$\frac{da_x}{d\lambda} = 0 = \frac{U^2}{x} \cdot \left( -2 \cdot \lambda + 4 \cdot \lambda^2 - \frac{4}{3} \cdot \lambda^3 \right) \quad \text{or} \quad -1 + 2 \cdot \lambda - \frac{2}{3} \cdot \lambda^2 = 0$$

The solution of this quadratic ( $\lambda < 1$ ) is 
$$\lambda = \frac{3 - \sqrt{3}}{2} \quad \lambda = 0.634 \quad \frac{y}{\delta} = 0.634$$


At  $\lambda = 0.634$

$$a_x = \frac{U^2}{x} \cdot \left( -0.634^2 + \frac{4}{3} \cdot 0.634^3 - \frac{1}{3} \cdot 0.634^4 \right) = -0.116 \cdot \frac{U^2}{x}$$

$$a_x = -0.116 \times \left( 6 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \frac{1}{0.8 \cdot \text{m}}$$

$$a_x = -5.22 \frac{\text{m}}{\text{s}^2}$$

The following plot can be done in *Excel*



## Problem 5.61

[Difficulty: 3]

**5.61** Show that the velocity field of Problem 2.18 represents a possible incompressible flow field. Determine and plot the streamline passing through point  $(x, y) = (2, 4)$  at  $t = 1.5$  s. For the particle at the same point and time, show on the plot the velocity vector and the vectors representing the local, convective, and total accelerations.

**2.18** Air flows downward toward an infinitely wide horizontal flat plate. The velocity field is given by  $\vec{V} = (ax\hat{i} - ay\hat{j})(2 + \cos\omega t)$ , where  $a = 5 \text{ s}^{-1}$ ,  $\omega = 2\pi \text{ s}^{-1}$ ,  $x$  and  $y$  (measured in meters) are horizontal and vertically upward, respectively, and  $t$  is in s. Obtain an algebraic equation for a streamline at  $t = 0$ . Plot the streamline that passes through point  $(x, y) = (3, 3)$  at this instant. Will the streamline change with time? Explain briefly. Show the velocity vector on your plot at the same point and time. Is the velocity vector tangent to the streamline? Explain.

**Given:** Steady, two-dimensional velocity field represented above

**Find:** (a) prove velocity field represents a possible incompressible flow field  
 (b) expression for the streamline at  $t = 1.5$  s  
 (c) plot of the streamline through  $(x, y) = (2\text{m}, 4\text{m})$  at that instant  
 (d) local velocity vector  
 (e) vectors representing local, convective, and total accelerations

**Solution:** We will apply the acceleration definition, and determine the streamline slope.

**Governing Equations:**

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle acceleration})$$

$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

**Assumptions:** (1) Two-dimensional flow (velocity is not a function of  $z$ )  
 (2) Incompressible flow

Based on the two assumptions listed above, the continuity equation reduces to:  $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$

This is the criterion against which we will check all of the flow fields.

$$u = (2 + \cos(\omega \cdot t)) \cdot ax \quad \frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = (2 + \cos(\omega \cdot t)) \cdot (a - a) = 0$$

$$v = -(2 + \cos(\omega \cdot t)) \cdot ay$$

This could be an incompressible flow field.

Streamlines along the  $x$ - $y$  plane are defined by  $\frac{dy}{dx} = \frac{v}{u} = \frac{-a \cdot y \cdot (2 + \cos(\omega \cdot t))}{a \cdot x \cdot (2 + \cos(\omega \cdot t))} = -\frac{y}{x}$  Thus:  $\frac{dx}{x} + \frac{dy}{y} = 0$  After integrating:

$$\ln(x) + \ln(y) = \ln(C) \quad \text{which yields: } x \cdot y = C \quad \text{At } (x, y) = (2\text{m}, 4\text{m}) \quad C = 2 \cdot \text{m} \times 4 \cdot \text{m} \quad C = 8 \text{m}^2 \quad x \cdot y = 8 \cdot \text{m}^2 \quad (\text{plot shown below})$$

$$\text{At } (x, y, t) = (2\text{m}, 4\text{m}, 1.5\text{s}) \quad \vec{V} = \frac{5}{\text{s}} (2 \text{ m}\hat{i} - 4 \text{ m}\hat{j}) \left( 2 + \cos\left(\frac{2\pi}{\text{s}} \times 1.5 \text{ s}\right) \right) \quad \vec{V} = (10\hat{i} - 20\hat{j}) \frac{\text{m}}{\text{s}}$$

Based on the above assumptions the particle acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + \frac{\partial \vec{V}}{\partial t}$

$$\text{The local acceleration is: } \vec{a}_{p, \text{local}} = \frac{\partial \vec{V}}{\partial t} = a\omega(x\hat{i} - y\hat{j})(-\sin(\omega t)) = \frac{5}{\text{s}} \times \frac{2\pi}{\text{s}} (2 \text{ m}\hat{i} - 4 \text{ m}\hat{j}) \left( -\sin\left(\frac{2\pi}{\text{s}} \times 1.5 \text{ s}\right) \right)$$

$$\vec{a}_{p, \text{local}} = (0\hat{i} + 0\hat{j}) \frac{\text{m}}{\text{s}^2}$$

The convective acceleration is:


$$\vec{a}_{p,conv} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} = a(u\hat{i} - v\hat{j})(2 + \cos \omega t) = \frac{5}{s} \times \left( 10 \frac{\text{m}}{\text{s}} \hat{i} + 20 \frac{\text{m}}{\text{s}} \hat{j} \right) \left( 2 + \cos \left( \frac{2\pi}{s} \times 1.5 \text{ s} \right) \right)$$

$$\vec{a}_{p,conv} = (50\hat{i} + 100\hat{j}) \frac{\text{m}}{\text{s}^2}$$

The total acceleration is the sum of the two acceleration terms:

$$\vec{a}_p = (50\hat{i} + 100\hat{j}) \frac{\text{m}}{\text{s}^2}$$

Here is the plot of the streamline and the vectors:



## Problem 5.62

[Difficulty: 3]

**5.62** A sinusoidal approximate velocity profile was used in Problem 5.12 to model flow in a laminar incompressible boundary layer on a flat plate. For this profile, obtain an expression for the  $x$  and  $y$  components of acceleration of a fluid particle in the boundary layer. Plot  $a_x$  and  $a_y$  at location  $x = 3$  ft, where  $\delta = 0.04$  in., for a flow with  $U = 20$  ft/s. Find the maxima of  $a_x$  and  $a_y$  at this  $x$  location.

**5.12** A useful approximation for the  $x$  component of velocity in an incompressible laminar boundary layer is a sinusoidal variation from  $u = 0$  at the surface ( $y = 0$ ) to the freestream velocity,  $U$ , at the edge of the boundary layer ( $y = \delta$ ). The equation for the profile is  $u = U \sin(\pi y/2\delta)$ , where  $\delta = cx^{1/2}$  and  $c$  is a constant. Show that the simplest expression for the  $y$  component of velocity is

$$\frac{v}{U} = \frac{1}{\pi} \frac{\delta}{x} \left[ \cos\left(\frac{\pi y}{2\delta}\right) + \left(\frac{\pi y}{2\delta}\right) \sin\left(\frac{\pi y}{2\delta}\right) - 1 \right]$$

Plot  $u/U$  and  $v/U$  versus  $y/\delta$ , and find the location of the maximum value of the ratio  $v/U$ . Evaluate the ratio where  $x = 0.5$  m and  $\delta = 5$  mm.

**Given:** Sinusoidal profile for two-dimensional boundary layer

**Find:** (a)  $x$ - and  $y$ -components of acceleration of a fluid particle  
 (b) plot components as functions of  $y/\delta$  for  $U = 20$  ft/s,  $x = 3$  ft,  $\delta = 0.04$  in  
 (c) maximum values of acceleration at this  $x$  location

**Solution:** We will apply the acceleration definition.

**Governing Equation:**

(Particle acceleration)

**Assumptions:** (1) Two-dimensional flow (velocity is not a function of  $z$ )  
 (2) Incompressible flow  
 (3) Steady flow

Based on the above assumptions the particle acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y}$  To make this easier, define  $\eta$ :

$$\eta = \frac{\pi}{2} \cdot \frac{y}{\delta} = \eta(x, y) \quad \frac{\partial}{\partial y} \eta = \frac{\pi}{2 \cdot \delta} \quad \delta = c \cdot x^{\frac{1}{2}} \quad \frac{d}{dx} \delta = \frac{1}{2} \cdot c \cdot x^{-\frac{1}{2}} = \frac{\delta}{2 \cdot x}$$

$$\frac{\partial}{\partial x} \eta = \left( \frac{\partial}{\partial \delta} \eta \right) \cdot \left( \frac{d}{dx} \delta \right) = -\frac{\pi \cdot y}{2 \cdot \delta^2} \cdot \frac{\delta}{2 \cdot x} = -\frac{\pi}{4 \cdot x} \cdot \frac{y}{\delta}$$

The velocities and derivatives are:  $u = U \cdot \sin(\eta) \quad \frac{\partial}{\partial x} u = \frac{\partial}{\partial \eta} u \cdot \frac{\partial}{\partial x} \eta = U \cdot \cos(\eta) \cdot -\frac{\pi}{4 \cdot x} \cdot \frac{y}{\delta} = -\frac{U}{2 \cdot x} \cdot \eta \cdot \cos(\eta)$  (Eqn. 1)

$$\frac{\partial}{\partial y} u = \frac{\partial}{\partial \eta} u \cdot \frac{\partial}{\partial y} \eta = U \cdot \cos(\eta) \cdot \frac{\pi}{2 \cdot \delta} = \frac{U \cdot \pi}{2 \cdot \delta} \cdot \cos(\eta)$$
 (Eqn. 2)

$v = \frac{U}{\pi} \cdot \frac{\delta}{x} \cdot (\cos(\eta) + \eta \cdot \sin(\eta) - 1)$  We find the derivatives of  $v$  using product and chain rules:

$$\frac{\partial}{\partial x} v = \frac{U}{\pi} \cdot \left[ \left( \frac{1}{x} \cdot \frac{\delta}{2 \cdot x} - \frac{\delta}{x^2} \right) \cdot (\cos(\eta) + \eta \cdot \sin(\eta) - 1) + \frac{\delta}{x} \cdot (-\sin(\eta) + \sin(\eta) + \eta \cdot \cos(\eta)) \cdot -\frac{\pi}{4 \cdot x} \cdot \frac{y}{\delta} \right]$$
 Simplifying this expression:

$$\frac{\partial}{\partial x} v = -\frac{U \cdot \delta}{2 \cdot \pi \cdot x^2} \cdot [(\cos(\eta) + \eta \cdot \sin(\eta) - 1) + \eta^2 \cdot \cos(\eta)]$$
 (Eqn. 3)

$$\frac{\partial}{\partial y} v = \frac{\partial}{\partial \eta} v \cdot \frac{\partial \eta}{\partial y} = \frac{U}{\pi} \cdot \frac{\delta}{x} \cdot (-\sin(\eta) + \sin(\eta) + \eta \cdot \cos(\eta)) \cdot \frac{\pi}{2 \cdot \delta} = \frac{U}{2 \cdot x} \cdot \eta \cdot \cos(\eta) \quad (\text{Eqn. 4})$$

So the accelerations are:

$$a_{px} = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = U \cdot \sin(\eta) \cdot \frac{U}{2 \cdot x} \cdot \eta \cdot \cos(\eta) + \frac{U}{\pi} \cdot \frac{\delta}{x} \cdot (\cos(\eta) + \eta \cdot \sin(\eta) - 1) \cdot \frac{U \cdot \pi}{2 \cdot \delta} \cdot \cos(\eta) \quad \text{Simplifying this expression:}$$


$$a_{px} = \frac{U^2}{2 \cdot x} \cdot \cos(\eta) \cdot (\cos(\eta) - 1)$$

$$a_{py} = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = U \cdot \sin(\eta) \cdot \frac{U \cdot \delta}{2 \cdot \pi \cdot x^2} \cdot (\cos(\eta) + \eta \cdot \sin(\eta) - 1 + \eta^2 \cdot \cos(\eta)) + \frac{U}{\pi} \cdot \frac{\delta}{x} \cdot (\cos(\eta) + \eta \cdot \sin(\eta) - 1) \cdot \frac{U}{2 \cdot x} \cdot \eta \cdot \cos(\eta)$$

Simplifying this expression:

$$a_{py} = \frac{U^2 \cdot \delta}{2 \cdot \pi \cdot x^2} \cdot \left[ \eta \cdot \cos(\eta) \cdot (\cos(\eta) + \eta \cdot \sin(\eta) - 1) - \sin(\eta) \cdot \left[ (1 + \eta^2) \cdot \cos(\eta) + \eta \cdot \sin(\eta) - 1 \right] \right]$$

Here are the plots of the acceleration components:



The maximum values and their locations may be found using Excel or Mathcad:

$$a_{pxmax} = -16.7 \cdot \frac{\text{ft}}{\text{s}^2}$$

$$\frac{y}{\delta} = 0.667$$


$$a_{pymax} = -0.0178 \cdot \frac{\text{ft}}{\text{s}^2}$$

$$\frac{y}{\delta} = 0.839$$

## Problem 5.63


[Difficulty: 3]

**5.63** Air flows into the narrow gap, of height  $h$ , between closely spaced parallel disks through a porous surface as shown. Use a control volume, with outer surface located at position  $r$ , to show that the uniform velocity in the  $r$  direction is  $V = v_0 r / 2h$ . Find an expression for the velocity component in the  $z$  direction ( $v_0 \ll V$ ). Evaluate the components of acceleration for a fluid particle in the gap.



**Given:** Flow between parallel disks through porous surface

**Find:** (a) show that  $V_r = v_0 r / 2h$   
 (b) expression for the  $z$ -component of velocity ( $v_0 \ll V$ )  
 (c) expression for acceleration of fluid particle in the gap



**Solution:** We will apply the continuity equation to the control volume shown:

**Governing Equations:** 
$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} \quad (\text{Continuity})$$

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = (\vec{V} \cdot \nabla) \vec{V} + \frac{\partial \vec{V}}{\partial t} \quad (\text{Particle Acceleration})$$

- Assumptions:**
- (1) Steady flow
  - (2) Incompressible flow
  - (3) Uniform flow at every section
  - (4) Velocity in  $\theta$ -direction is zero

Based on the above assumptions the continuity equation reduces to:  $0 = -\rho \cdot v_0 \cdot \pi \cdot r^2 + \rho \cdot V_r \cdot 2 \cdot \pi \cdot r \cdot h$  Solving for  $V_r$ :  $V_r = v_0 \cdot \frac{r}{2 \cdot h}$

We apply the differential form of continuity to find  $V_z$ :  $\frac{1}{r} \cdot \frac{\partial}{\partial r} (r \cdot V_r) + \frac{\partial}{\partial z} V_z = 0$   $\frac{1}{r} \cdot \frac{\partial}{\partial r} (r \cdot V_r) = \frac{v_0}{h} = -\frac{\partial}{\partial z} V_z$  Therefore:

$$V_z = - \int \frac{v_0}{h} dz + f(r) = -v_0 \cdot \frac{z}{h} + f(r) \quad \text{Now at } z=0: V_z = v_0 \quad \text{Therefore we can solve for } f(r): v_0 = -v_0 \cdot \frac{0}{h} + f(r) \quad f(r) = v_0$$

So we find that the  $z$ -component of velocity is:  $V_z = v_0 \cdot \left(1 - \frac{z}{h}\right)$

Based on the above assumptions the particle acceleration reduces to:  $\vec{a}_p = V_r \frac{\partial \vec{V}}{\partial r} + V_z \frac{\partial \vec{V}}{\partial z}$

$$\frac{\partial}{\partial r} V_r = \frac{v_0}{2 \cdot h} \quad \frac{\partial}{\partial z} V_r = 0 \quad \frac{\partial}{\partial r} V_z = 0 \quad \frac{\partial}{\partial z} V_z = -\frac{v_0}{h}$$

So the accelerations are:

$$a_{pr} = V_r \cdot \frac{\partial}{\partial r} V_r + V_z \cdot \frac{\partial}{\partial z} V_r = v_0 \cdot \frac{r}{2 \cdot h} \cdot \frac{v_0}{2 \cdot h} + v_0 \cdot \left(1 - \frac{z}{h}\right) \cdot 0 \quad a_{pr} = \frac{v_0^2 \cdot r}{4 \cdot h^2}$$

$$a_{pz} = V_r \cdot \frac{\partial}{\partial r} V_z + V_z \cdot \frac{\partial}{\partial z} V_z = v_0 \cdot \frac{r}{2 \cdot h} \cdot 0 + v_0 \cdot \left(1 - \frac{z}{h}\right) \cdot -\frac{v_0}{h} \quad a_{pz} = \frac{v_0^2}{h} \cdot \left(\frac{z}{h} - 1\right)$$

## Problem 5.64

[Difficulty: 3]

**5.64** The velocity field for steady inviscid flow from left to right over a circular cylinder, of radius  $R$ , is given by

$$\vec{V} = U \cos \theta \left[ 1 - \left( \frac{R}{r} \right)^2 \right] \hat{e}_r - U \sin \theta \left[ 1 + \left( \frac{R}{r} \right)^2 \right] \hat{e}_\theta$$

Obtain expressions for the acceleration of a fluid particle moving along the stagnation streamline ( $\theta = \pi$ ) and for the acceleration along the cylinder surface ( $r = R$ ). Plot  $a_r$  as a function of  $r/R$  for  $\theta = \pi$ , and as a function of  $\theta$  for  $r = R$ ; plot  $a_\theta$  as a function of  $\theta$  for  $r = R$ . Comment on the plots. Determine the locations at which these accelerations reach maximum and minimum values.

**Given:** Steady inviscid flow over a circular cylinder of radius  $R$


- Find:**
- Expression for acceleration of particle moving along  $\theta = \pi$
  - Expression for acceleration of particle moving along  $r = R$
  - Locations at which accelerations in  $r$ - and  $\theta$ - directions reach maximum and minimum values
  - Plot  $a_r$  as a function of  $R/r$  for  $\theta = \pi$  and as a function of  $\theta$  for  $r = R$
  - Plot  $a_\theta$  as a function of  $\theta$  for  $r = R$

**Solution:** We will apply the particle acceleration definition to the velocity field

**Governing Equation:**

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = (\vec{V} \cdot \nabla) \vec{V} + \frac{\partial \vec{V}}{\partial t} \quad \text{(Particle Acceleration)}$$

- Assumptions:**
- Steady flow
  - Inviscid flow
  - No flow in  $z$ -direction, velocity is not a function of  $z$



Based on the above assumptions the particle acceleration reduces to:  $\vec{a}_p = V_r \frac{\partial \vec{V}}{\partial r} + \frac{V_\theta}{r} \frac{\partial \vec{V}}{\partial \theta}$  and the components are:

$$a_{pr} = V_r \frac{\partial}{\partial r} V_r + \frac{V_\theta}{r} \frac{\partial}{\partial \theta} V_r - \frac{V_\theta^2}{r} \quad a_{p\theta} = V_r \frac{\partial}{\partial r} V_\theta + \frac{V_\theta}{r} \frac{\partial}{\partial \theta} V_\theta + \frac{V_r \cdot V_\theta}{r}$$

When  $\theta = \pi$ :  $V_r = -U \cdot \left[ 1 - \left( \frac{R}{r} \right)^2 \right]$   $V_\theta = 0$   $\frac{\partial}{\partial r} V_r = -U \cdot -2 \cdot \frac{R^2}{r^3} = 2 \cdot U \cdot \frac{R^2}{r^3}$   $\frac{\partial}{\partial \theta} V_r = 0$   $\frac{\partial}{\partial r} V_\theta = 0$   $\frac{\partial}{\partial \theta} V_\theta = 0$

So the accelerations are:  $a_{pr} = -U \cdot \left[ 1 - \left( \frac{R}{r} \right)^2 \right] \cdot 2 \cdot U \cdot \frac{R^2}{r^3} = \frac{2 \cdot U^2}{R} \cdot \left( \frac{R}{r} \right)^3 \cdot \left[ 1 - \left( \frac{R}{r} \right)^2 \right]$

$$a_{pr} = \frac{2 \cdot U^2}{R} \cdot \left( \frac{R}{r} \right)^3 \cdot \left[ 1 - \left( \frac{R}{r} \right)^2 \right]$$

$$a_{p\theta} = 0$$

To find the maximum acceleration, we take the derivative of the acceleration and set it to zero: Let  $\eta = \frac{R}{r}$

$$\frac{d}{d\eta} a_{pr} = \frac{2 \cdot U^2}{R} \cdot \left[ 3 \cdot \eta^2 \cdot (1 - \eta^2) - \eta^3 \cdot 2 \cdot \eta \right] = \frac{2 \cdot U^2}{R} \cdot (-5 \cdot \eta^4 + 3 \eta^2) = 0 \quad \text{Therefore: } \eta = \sqrt{\frac{3}{5}} \quad \text{or} \quad r = 1.291 \cdot R$$

The maximum acceleration would then be:  $a_{prmax} = \frac{2 \cdot U^2}{R} \cdot \left( \frac{1}{1.291} \right)^3 \cdot \left[ 1 - \left( \frac{1}{1.291} \right)^2 \right]$

$$a_{prmax} = 0.372 \cdot \frac{U^2}{R}$$

When  $r = R$ :  $V_r = 0$   $V_\theta = -2 \cdot U \cdot \sin(\theta)$   $\frac{\partial}{\partial r} V_r = 0$   $\frac{\partial}{\partial \theta} V_r = 0$   $\frac{\partial}{\partial r} V_\theta = 0$   $\frac{\partial}{\partial \theta} V_\theta = -2 \cdot U \cdot \cos(\theta)$

So the accelerations are:  $a_{pr} = -\frac{(-2 \cdot U \cdot \cos(\theta))^2}{R} = -\frac{4 \cdot U^2}{R} \cdot (\sin(\theta))^2$

$$a_{pr} = -\frac{4 \cdot U^2}{R} \cdot (\sin(\theta))^2$$

$$a_{p\theta} = \frac{-2 \cdot U \cdot \sin(\theta)}{R} \cdot -2 \cdot U \cdot \cos(\theta) = \frac{4 \cdot U^2}{R} \cdot \sin(\theta) \cdot \cos(\theta)$$

$$a_{p\theta} = \frac{4 \cdot U^2}{R} \cdot \sin(\theta) \cdot \cos(\theta)$$

Radial acceleration is minimum at  $\theta = 180\text{-deg}$


Accelerations at this angle are:  $a_{rmin} = -4 \cdot \frac{U^2}{R}$   $a_\theta = 0$

Azimuthal acceleration is maximum at  $\theta = 45\text{-deg}$


Accelerations at this angle are:  $a_r = -2 \cdot \frac{U^2}{R}$   $a_{\theta max} = 2 \cdot \frac{U^2}{R}$

Azimuthal acceleration is minimum at  $\theta = 135\text{-deg}$

Accelerations at this angle are:  $a_r = -2 \cdot \frac{U^2}{R}$   $a_{\theta min} = -2 \cdot \frac{U^2}{R}$




The plots of acceleration along the stagnation streamline and the cylinder surface are shown here. In all cases the accelerations have been normalized by  $U^2/R$



## Problem 5.65

[Difficulty: 3]

**5.65** Air flows into the narrow gap, of height  $h$ , between closely spaced parallel plates through a porous surface as shown. Use a control volume, with outer surface located at position  $x$ , to show that the uniform velocity in the  $x$  direction is  $u = v_0 x/h$ . Find an expression for the velocity component in the  $y$  direction. Evaluate the acceleration of a fluid particle in the gap.



**Given:** Air flow through porous surface into narrow gap

**Find:** (a) show that  $u(x) = v_0 x/h$   
 (b) expression for the  $y$ -component of velocity  
 (c) expression for acceleration of fluid particle in the gap

**Solution:** We will apply the continuity equation to the control volume shown:


**Governing Equations:**

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

(Continuity)

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} + \frac{\partial \vec{V}}{\partial t}$$

(Particle Acceleration)



**Assumptions:** (1) Steady flow  
 (2) Incompressible flow  
 (3) Uniform flow at every section

Based on the above assumptions the continuity equation reduces to:  $0 = -x \cdot w \cdot v_0 + h \cdot w \cdot u(x)$  Solving for  $u$ :  $u(x) = v_0 \cdot \frac{x}{h}$

We apply the differential form of continuity to find  $v$ :  $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$   $\frac{\partial}{\partial x} u = \frac{v_0}{h} = \frac{\partial}{\partial y} v$  Therefore the  $y$ -velocity  $v$  is:

$$v = - \int \frac{v_0}{h} dy + f(x) = -v_0 \cdot \frac{y}{h} + f(x) \quad \text{Now at } y=0: \quad v = v_0 \quad \text{Therefore we can solve for } f(x): \quad v_0 = -v_0 \cdot \frac{0}{h} + f(x) \quad f(x) = v_0$$

So we find that the  $y$ -component of velocity is:  $v = v_0 \cdot \left(1 - \frac{y}{h}\right)$

Based on the above assumptions the particle acceleration reduces to:  $\vec{a}_p = u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y}$

$$\frac{\partial}{\partial x} u = \frac{v_0}{h} \quad \frac{\partial}{\partial y} u = 0 \quad \frac{\partial}{\partial x} v = 0 \quad \frac{\partial}{\partial y} v = -\frac{v_0}{h}$$

So the accelerations are:

$$a_{px} = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = v_0 \cdot \frac{x}{h} \cdot \frac{v_0}{h} + v_0 \cdot \left(1 - \frac{y}{h}\right) \cdot 0$$

$$a_{px} = \frac{v_0^2 \cdot x}{h^2}$$

$$a_{py} = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = v_0 \cdot \frac{x}{h} \cdot 0 + v_0 \cdot \left(1 - \frac{y}{h}\right) \cdot \left(-\frac{v_0}{h}\right)$$

$$a_{py} = \frac{v_0^2}{h} \cdot \left(\frac{y}{h} - 1\right)$$


The acceleration vector would be:

$$\vec{a}_p = \frac{v_0^2}{h} \left[ \frac{x}{h} \hat{i} + \left(\frac{y}{h} - 1\right) \hat{j} \right]$$

## Problem 5.66

[Difficulty: 3]

**5.66** Consider the incompressible flow of a fluid through a nozzle as shown. The area of the nozzle is given by  $A = A_0(1 - bx)$  and the inlet velocity varies according to  $U = U_0(0.5 + 0.5\cos \omega t)$  where  $A_0 = 5 \text{ ft}^2$ ,  $L = 20 \text{ ft}$ ,  $b = 0.02 \text{ ft}^{-1}$ ,  $\omega = 0.16 \text{ rad/s}$ , and  $U_0 = 20 \text{ ft/s}$ . Find and plot the acceleration on the centerline, with time as a parameter.



**Given:** Velocity field and nozzle geometry

**Find:** Acceleration along centerline; plot

**Solution:**

**Assumption:** Incompressible flow

The given data is  $A_0 = 5 \cdot \text{ft}^2$     $L = 20 \cdot \text{ft}$     $b = 0.02 \cdot \text{ft}^{-1}$     $U_0 = 20 \cdot \frac{\text{ft}}{\text{s}}$     $\omega = 0.16 \cdot \frac{\text{rad}}{\text{s}}$     $A(x) = A_0 \cdot (1 - b \cdot x)$

The velocity on the centerline is obtained from continuity  $u(x) \cdot A(x) = U_0 \cdot A_0$

so 
$$u(x,t) = \frac{A_0}{A(x)} \cdot U_0 \cdot (0.5 + 0.5 \cdot \cos(\omega \cdot t)) = \frac{U_0}{(1 - b \cdot x)} \cdot (0.5 + 0.5 \cdot \cos(\omega \cdot t))$$


The acceleration is given by

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

For the present 1D flow 
$$a_x = \frac{\partial}{\partial t} u + u \cdot \frac{\partial}{\partial x} u = -\frac{0.5 \cdot U_0 \cdot \omega \cdot \sin(\omega \cdot t)}{1 - b \cdot x} + \frac{U_0}{(1 - b \cdot x)} \cdot (0.5 + 0.5 \cdot \cos(\omega \cdot t)) \cdot \left[ \frac{U_0 \cdot b \cdot (0.5 \cdot \cos(\omega \cdot t) + 0.5)}{(1 - b \cdot x)^2} \right]$$

$$a_x = \frac{U_0}{(1 - b \cdot x)} \cdot \left[ -(0.5 \cdot \omega \cdot \sin(\omega \cdot t)) + (0.5 + 0.5 \cdot \cos(\omega \cdot t)) \cdot \left[ \frac{U_0 \cdot b \cdot (0.5 \cdot \cos(\omega \cdot t) + 0.5)}{(1 - b \cdot x)^2} \right] \right]$$
      The plot is shown here:



## Problem 5.67

[Difficulty: 4]

**5.67** Consider again the steady, two-dimensional velocity field of Problem 5.56. Obtain expressions for the particle coordinates,  $x_p = f_1(t)$  and  $y_p = f_2(t)$ , as functions of time and the initial particle position,  $(x_0, y_0)$  at  $t = 0$ . Determine the time required for a particle to travel from initial position,  $(x_0, y_0) = (\frac{1}{2}, 2)$  to positions  $(x, y) = (1, 1)$  and  $(2, \frac{1}{2})$ . Compare the particle accelerations determined by differentiating  $f_1(t)$  and  $f_2(t)$  with those obtained in Problem 5.56.

**5.56** A steady, two-dimensional velocity field is given by  $\vec{V} = Ax\hat{i} - Ay\hat{j}$ , where  $A = 1\text{ s}^{-1}$ . Show that the streamlines for this flow are rectangular hyperbolas,  $xy = C$ . Obtain a general expression for the acceleration of a fluid particle in this velocity field. Calculate the acceleration of fluid particles at the points  $(x, y) = (\frac{1}{2}, 2)$ ,  $(1, 1)$ , and  $(2, \frac{1}{2})$ , where  $x$  and  $y$  are measured in meters. Plot streamlines that correspond to  $C = 0, 1$ , and  $2\text{ m}^2$  and show the acceleration vectors on the streamline plot.

**Given:** Steady, two-dimensional velocity field of Problem 5.56

**Find:** (a) expressions for particle coordinates,  $x_p = f_1(t)$  and  $y_p = f_2(t)$   
 (b) Time requires for particle to travel from  $(0.5, 2)$  to  $(1, 1)$  and  $(2, 0.5)$   
 (c) compare acceleration determined from  $f_1(t)$  and  $f_2(t)$  to those found in Problem 5.56

**Solution:** We will apply the particle acceleration definition to the velocity field

**Governing Equation:** 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = (\vec{V} \cdot \nabla)\vec{V} + \frac{\partial\vec{V}}{\partial t} \quad \text{(Particle Acceleration)}$$

**Assumptions:** (1) Incompressible flow  
 (2) Two-dimensional flow  
 (3) Steady flow

For the given flow,  $u = A \cdot x$  and  $v = -A \cdot y$ . Thus  $u_p = \frac{d}{dt}f_1 = A \cdot x_p = A \cdot f_1$  or  $\frac{df_1}{f_1} = A \cdot dt$ . Integrating from  $x_0$  to  $f_1$  yields:

$$\int_{x_0}^{f_1} \frac{1}{f_1} df_1 = \ln\left(\frac{f_1}{x_0}\right) = A \cdot t \quad \text{Solving for } f_1 \text{ yields: } f_1(t) = x_0 \cdot e^{A \cdot t}$$

Similarly, we can find:  $v_p = \frac{d}{dt}f_2 = -A \cdot y_p = -A \cdot f_2$  or  $\frac{df_2}{f_2} = -A \cdot dt$ . Integrating from  $y_0$  to  $f_2$  yields:  $f_2(t) = y_0 \cdot e^{-A \cdot t}$

In this problem,  $x_0 = \frac{1}{2}\text{ m}$  and  $y_0 = 2\text{ m}$ . Knowing the final position, we can solve for the time required.

To reach  $(1, 1)$ :

$$x = 1.0\text{ m} \quad t = \ln(2) \times 1\text{ s} \quad t = 0.693\text{ s} \quad y = 1.0\text{ m} \quad t = -\ln\left(\frac{1}{2}\right) \times 1\text{ s} \quad t = 0.693\text{ s} \quad t = 0.693\text{ s}$$

To reach  $(2, 0.5)$ :

$$x = 2.0\text{ m} \quad t = \ln(4) \times 1\text{ s} \quad t = 1.386\text{ s} \quad y = 0.5\text{ m} \quad t = -\ln\left(\frac{1}{4}\right) \times 1\text{ s} \quad t = 1.386\text{ s} \quad t = 1.386\text{ s}$$

The acceleration components are:

$$a_x = \frac{d^2}{dt^2}f_1 = x_0 \cdot A^2 \cdot e^{A \cdot t} = A^2 \cdot f_1(t) \quad a_y = \frac{d^2}{dt^2}f_2 = x_0 \cdot (-A)^2 \cdot e^{-A \cdot t} = A^2 \cdot f_2(t) \quad \text{At } (x, y) = (1, 1): \quad \vec{a}_p = (\hat{i} + \hat{j}) \frac{\text{m}}{\text{s}^2}$$


$$\text{At } (x, y) = (2, 0.5): \quad \vec{a}_p = (2\hat{i} + 0.5\hat{j}) \frac{\text{m}}{\text{s}^2}$$

These results are identical to the accelerations calculated in Problem 5.56.

## Problem 5.68

[Difficulty: 3]

**5.68** Consider the one-dimensional, incompressible flow through the circular channel shown. The velocity at section ① is given by  $U = U_0 + U_1 \sin \omega t$ , where  $U_0 = 20$  m/s,  $U_1 = 2$  m/s, and  $\omega = 0.3$  rad/s. The channel dimensions are  $L = 1$  m,  $R_1 = 0.2$  m, and  $R_2 = 0.1$  m. Determine the particle acceleration at the channel exit. Plot the results as a function of time over a complete cycle. On the same plot, show the acceleration at the channel exit if the channel is constant area, rather than convergent, and explain the difference between the curves.



**Given:** One-dimensional, incompressible flow through circular channel.

**Find:** (a) the acceleration of a particle at the channel exit  
 (b) plot as a function of time for a complete cycle.  
 (c) plot acceleration if channel is constant area  
 (d) explain difference between the two acceleration cases

**Solution:** We will apply the particle acceleration definition to the velocity field

**Governing Equations:** 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = (\vec{V} \cdot \nabla)\vec{V} + \frac{\partial \vec{V}}{\partial t} \quad \text{(Particle Acceleration)}$$

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} \quad \text{(Continuity equation)}$$

**Assumptions:** (1) Incompressible flow  
 (2) One-dimensional flow

Based on the above assumptions the continuity equation can provide the velocity at any location:  $u = U \cdot \frac{A_1}{A} = \left(\frac{R_1}{r}\right)^2$

Now based on the geometry of the channel we can write  $r = R_1 - (R_1 - R_2) \cdot \frac{x}{L} = R_1 - \Delta R \cdot \frac{x}{L}$  Therefore the flow speed is:

$$u = U \cdot \frac{R_1^2}{\left(R_1 - \Delta R \cdot \frac{x}{L}\right)^2} = \frac{(U_0 + U_1 \cdot \sin(\omega \cdot t))}{\left[1 - \frac{\Delta R}{R_1} \cdot \left(\frac{x}{L}\right)\right]^2} \quad \text{Based on the above assumptions the particle acceleration reduces to:}$$

$\vec{a}_p = \left(u \frac{\partial u}{\partial x} + \frac{\partial u}{\partial t}\right) \hat{i}$  Substituting the velocity and derivatives into this expression we can get the acceleration in the x-direction:

$$a_x = \frac{(U_0 + U_1 \cdot \sin(\omega \cdot t)) \cdot (U_0 + U_1 \cdot \sin(\omega \cdot t))}{\left[1 - \frac{\Delta R}{R_1} \cdot \left(\frac{x}{L}\right)\right]^2} \cdot (-2) \cdot \left(-\frac{\Delta R}{R_1 \cdot L}\right) + \frac{\omega \cdot U_1 \cdot \cos(\omega \cdot t)}{\left[1 - \frac{\Delta R}{R_1} \cdot \left(\frac{x}{L}\right)\right]^2} \quad \text{When we simplify this expression we get:}$$

$$a_x = \frac{2 \cdot \Delta R}{R_1 \cdot L} \cdot \frac{(U_0 + U_1 \cdot \sin(\omega \cdot t))^2}{\left[1 - \frac{\Delta R}{R_1} \cdot \left(\frac{x}{L}\right)\right]^5} + \frac{\omega \cdot U_1 \cdot \cos(\omega \cdot t)}{\left[1 - \frac{\Delta R}{R_1} \cdot \left(\frac{x}{L}\right)\right]^2} \quad \text{Now we substitute the given values into this expression we get:}$$

$$a_x = 2 \times 0.1 \cdot m \times \frac{1}{0.2 \cdot m} \times \frac{1}{1 \cdot m} \times (20 + 2 \cdot \sin(\omega \cdot t))^2 \cdot \frac{m^2}{s^2} \times \frac{1}{\left(1 - \frac{0.1 \cdot m}{0.2 \cdot m} \times 1\right)^5} + 0.3 \cdot \frac{\text{rad}}{s} \times 2 \cdot \frac{m}{s} \times \cos(\omega \cdot t) \times \frac{1}{\left(1 - \frac{0.1 \cdot m}{0.2 \cdot m} \times 1\right)^2}$$



$$a_x = \left[ 32 \cdot \left( 20 + 2 \cdot \sin\left( 0.3 \cdot \frac{\text{rad}}{s} \cdot t \right) \right)^2 + 2.4 \cdot \cos\left( 0.3 \cdot \frac{\text{rad}}{s} \cdot t \right) \right] \cdot \frac{m}{s^2}$$

Here is a plot of the acceleration versus time.

For a constant area channel,  $\Delta R = 0$  and the acceleration becomes:

$$a_x = \left( 0.6 \cdot \cos\left( 0.3 \cdot \frac{\text{rad}}{s} \cdot t \right) \right) \cdot \frac{m}{s^2}$$

The plot of that acceleration is shown below.  
The acceleration is so much larger for the converging channel than in the constant area channel because the convective acceleration is generated by the converging channel - the constant area channel has only local acceleration.



## Problem 5.69

[Difficulty: 2]

**5.69** Which, if any, of the following flow fields are irrotational?

(a)  $u = 2x^2 + y^2 - x^2y; v = x^3 + x(y^2 - 2y)$

(b)  $u = 2xy - x^2 + y; v = 2xy - y^2 + x^2$

(c)  $u = xt + 2y; v = xt^2 - yt$

(d)  $u = (x + 2y)xt; v = -(2x + y)yt$

**Given:** Velocity components

**Find:** Which flow fields are irrotational

**Solution:**

For a 2D field, the irrotationality test is  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

a)  $u(x, y, t) = 2 \cdot x^2 + y^2$     $v(x, y, t) = x^3 + x \cdot (y^2 - 2 \cdot y)$     $\frac{\partial}{\partial x}v(x, y, t) = 3 \cdot x^2 + y^2 - 2 \cdot y$     $\frac{\partial}{\partial y}u(x, y, t) = 2 \cdot y$

Hence  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u \neq 0$

Not irrotational

b)  $u(x, y, t) = 2 \cdot x \cdot y - x^2 + y$     $v(x, y, t) = 2 \cdot x \cdot y - y^2 + x^2$     $\frac{\partial}{\partial x}v(x, y, t) = 2 \cdot x + 2 \cdot y$     $\frac{\partial}{\partial y}u(x, y, t) = 2 \cdot x + 1$

Hence  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u \neq 0$

Not irrotational

c)  $u(x, y, t) = x \cdot t + 2 \cdot y$     $v(x, y, t) = x \cdot t^2 - y \cdot t$     $\frac{\partial}{\partial x}v(x, y, t) = t^2$     $\frac{\partial}{\partial y}u(x, y, t) = 2$

Hence  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u \neq 0$

Not irrotational

d)  $u(x, y, t) = (x + 2 \cdot y) \cdot x \cdot t$     $v(x, y, t) = -(2 \cdot x + y) \cdot y \cdot t$     $\frac{\partial}{\partial x}v(x, y, t) = -2 \cdot t \cdot y$     $\frac{\partial}{\partial y}u(x, y, t) = 2 \cdot t \cdot x$

Hence  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u \neq 0$

Not irrotational

## Problem 5.70

[Difficulty: 4]

**5.70** Expand  $(\vec{V} \cdot \nabla)\vec{V}$  in cylindrical coordinates by direct substitution of the velocity vector to obtain the convective acceleration of a fluid particle. (Recall the hint in footnote 1 on page 178.) Verify the results given in Eqs. 5.12.

**Given:** Definition of "del" operator in cylindrical coordinates, velocity vector

**Find:** (a) An expression for  $(\vec{V} \cdot \nabla)\vec{V}$  in cylindrical coordinates.  
(b) Show result is identical to Equations 5.12.

**Solution:** We will apply the velocity field to the del operator and simplify.

**Governing Equations:**

$$\vec{\nabla} = \hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{k} \frac{\partial}{\partial z} \quad (\text{Definition of "del" operator})$$

$$\vec{V} = V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k} \quad (\text{Velocity flow field})$$

$$\frac{\partial \hat{e}_r}{\partial \theta} = \hat{e}_\theta \quad \frac{\partial \hat{e}_\theta}{\partial \theta} = -\hat{e}_r \quad (\text{Hints from footnote})$$

Substituting  $(\vec{V} \cdot \nabla)\vec{V}$  using the governing equations yields:

$$\begin{aligned} (\vec{V} \cdot \nabla)\vec{V} &= \left[ (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) \cdot \left( \hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{k} \frac{\partial}{\partial z} \right) \right] (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) \\ &= \left( V_r \frac{\partial}{\partial r} + \frac{V_\theta}{r} \frac{\partial}{\partial \theta} + V_z \frac{\partial}{\partial z} \right) (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) \\ &= V_r \frac{\partial}{\partial r} (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) + \frac{V_\theta}{r} \frac{\partial}{\partial \theta} (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) + V_z \frac{\partial}{\partial z} (V_r \hat{e}_r + V_\theta \hat{e}_\theta + V_z \hat{k}) \\ &= V_r \frac{\partial}{\partial r} V_r \hat{e}_r + V_r \frac{\partial}{\partial r} V_\theta \hat{e}_\theta + V_r \frac{\partial}{\partial r} V_z \hat{k} + \frac{V_\theta}{r} \frac{\partial}{\partial \theta} (V_r \hat{e}_r) + \frac{V_\theta}{r} \frac{\partial}{\partial \theta} (V_\theta \hat{e}_\theta) + \frac{V_\theta}{r} \frac{\partial}{\partial \theta} V_z \hat{k} + V_z \frac{\partial}{\partial z} V_r \hat{e}_r \\ &\quad + V_z \frac{\partial}{\partial z} V_\theta \hat{e}_\theta + V_z \frac{\partial}{\partial z} V_z \hat{k} \end{aligned}$$

Applying the product rule to isolate derivatives of the unit vectors:

$$\begin{aligned} (\vec{V} \cdot \nabla)\vec{V} &= V_r \frac{\partial V_r}{\partial r} \hat{e}_r + V_r \frac{\partial V_\theta}{\partial r} \hat{e}_\theta + V_r \frac{\partial V_z}{\partial r} \hat{k} + \frac{V_\theta}{r} \frac{\partial V_r}{\partial \theta} \hat{e}_r + \frac{V_\theta}{r} \frac{\partial \hat{e}_r}{\partial \theta} V_r + \frac{V_\theta}{r} \frac{\partial V_\theta}{\partial \theta} \hat{e}_\theta + \frac{V_\theta}{r} \frac{\partial \hat{e}_\theta}{\partial \theta} V_\theta + \frac{V_\theta}{r} \frac{\partial V_z}{\partial \theta} \hat{k} \\ &\quad + V_z \frac{\partial V_r}{\partial z} \hat{e}_r + V_z \frac{\partial V_\theta}{\partial z} \hat{e}_\theta + V_z \frac{\partial V_z}{\partial z} \hat{k} \end{aligned}$$

Collecting terms:

$$\begin{aligned} (\vec{V} \cdot \nabla)\vec{V} &= \left( V_r \frac{\partial V_r}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_r}{\partial \theta} - \frac{V_\theta^2}{r} + V_z \frac{\partial V_r}{\partial z} \right) \hat{e}_r + \left( V_r \frac{\partial V_\theta}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_\theta}{\partial \theta} + \frac{V_r V_\theta}{r} + V_z \frac{\partial V_\theta}{\partial z} \right) \hat{e}_\theta \\ &\quad + \left( V_r \frac{\partial V_z}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_z}{\partial \theta} + V_z \frac{\partial V_z}{\partial z} \right) \hat{k} \end{aligned}$$

The three terms in parentheses are the three components of convective acceleration given in Equations 5.12.

## Problem 5.71

[Difficulty: 4]

**5.71** Consider again the sinusoidal velocity profile used to model the  $x$  component of velocity for a boundary layer in Problem 5.12. Neglect the vertical component of velocity. Evaluate the circulation around the contour bounded by  $x = 0.4$  m,  $x = 0.6$  m,  $y = 0$ , and  $y = 8$  mm. What would be the results of this evaluation if it were performed 0.2 m further downstream? Assume  $U = 0.5$  m/s.

**Given:** Sinusoidal approximation to boundary-layer velocity profile:

$$u = U \cdot \sin\left(\frac{\pi}{2} \cdot \frac{y}{\delta}\right) \quad \text{where } \delta = 5 \cdot \text{mm at } x = 0.5 \cdot \text{m}$$


Neglect the vertical component of velocity.  $U = 0.5 \cdot \frac{\text{m}}{\text{s}}$

**Find:** (a) Circulation about a contour bounded by  $x = 0.4$  m,  $x = 0.6$  m,  $y = 0$ , and  $y = 8$  mm.  
 (b) Result if evaluated  $\Delta x = 0.2$  m further downstream

**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equation:**

$$\Gamma = \oint \vec{V} \cdot d\vec{s} \quad (\text{Definition of circulation})$$



From the definition of circulation we break up the integral:

$$\Gamma = \int \vec{V} \cdot d\vec{s} + \int \vec{V} \cdot d\vec{s} + \int \vec{V} \cdot d\vec{s} + \int \vec{V} \cdot d\vec{s}$$

Since the velocity is zero over  $ab$ , and since the velocity and path are perpendicular over  $bc$  and  $da$ :

$$\Gamma = \int_{x_c}^{x_d} U dx = -U \cdot (x_c - x_d) \quad \Gamma = -0.5 \cdot \frac{\text{m}}{\text{s}} \times (0.6 \cdot \text{m} - 0.4 \cdot \text{m})$$

$$\Gamma = -0.1 \frac{\text{m}^2}{\text{s}}$$

At the downstream location, since  $\delta = c \cdot x^{\frac{1}{2}}$   $\delta' = \delta \cdot \left(\frac{x}{x'}\right)^{\frac{1}{2}}$   $\delta' = 5 \cdot \text{mm} \cdot \left(\frac{0.8 \cdot \text{m}}{0.5 \cdot \text{m}}\right)^{\frac{1}{2}}$   $\delta' = 6.325 \cdot \text{mm}$


Now since the boundary layer is less than 8 mm thick at point  $c'$ , the integral along  $c'c$  will be the same as that along  $cd$ .

$$\Gamma_{bb'c'c} = \Gamma_{abcd}$$

## Problem 5.72

[Difficulty: 2]

**5.72** Consider the velocity field for flow in a rectangular “corner,”  $\vec{V} = Ax\hat{i} - Ay\hat{j}$ , with  $A = 0.3\text{ s}^{-1}$ , as in Example 5.8. Evaluate the circulation about the unit square of Example 5.8.



**Given:** Velocity field for flow in a rectangular corner as in Example 5.8.

**Find:** Circulation about the unit square shown above.

**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equation:**  $\Gamma = \oint \vec{V} \cdot d\vec{s}$  (Definition of circulation)

From the definition of circulation we break up the integral:  $\Gamma = \int_{ab} \vec{V} \cdot d\vec{s} + \int_{bc} \vec{V} \cdot d\vec{s} + \int_{cd} \vec{V} \cdot d\vec{s} + \int_{da} \vec{V} \cdot d\vec{s}$

The integrand is equal to:  $\vec{V} \cdot d\vec{s} = (Ax\hat{i} - Ay\hat{j}) \cdot (dx\hat{i} + dy\hat{j}) = Axdx - Ayydy$  Therefore, the circulation is equal to:

$$\Gamma = \int_{x_a}^{x_d} A \cdot x \, dx + \int_{y_d}^{y_c} -A \cdot y \, dy + \int_{x_c}^{x_b} A \cdot x \, dx + \int_{y_b}^{y_a} -A \cdot y \, dy = \frac{A}{2} \left[ (x_d^2 - x_a^2) - (y_c^2 - y_d^2) + (x_b^2 - x_c^2) - (y_a^2 - y_b^2) \right]$$

$$\Gamma = \frac{1}{2} \times 0.3 \cdot \frac{1}{s} \times \left[ (2^2 - 1^2) - (2^2 - 1^2) + (1^2 - 2^2) - (1^2 - 2^2) \right] \cdot \text{m}^2$$

$$\Gamma = 0 \frac{\text{m}^2}{\text{s}}$$

This result is to be expected since the flow is irrotational and by Stokes' theorem, the circulation is equal to the curl of the velocity over the bounded area (Eqn. 5.18).

## Problem 5.73

[Difficulty: 3]

**5.73** A flow is represented by the velocity field  $\vec{V} = (x^7 - 21x^5y^2 + 35x^3y^4 - 7xy^6)\hat{i} + (7x^6y - 35x^4y^3 + 21x^2y^5 - y^7)\hat{j}$ . Determine if the field is (a) a possible incompressible flow and (b) irrotational.

**Given:** Flow field

**Find:** If the flow is incompressible and irrotational

**Solution:**

Basic equations: Incompressibility  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$

Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

a)  $u(x,y) = x^7 - 21x^5y^2 + 35x^3y^4 - 7xy^6$

$v(x,y) = 7x^6y - 35x^4y^3 + 21x^2y^5 - y^7$

$$\frac{\partial}{\partial x}u(x,y) = 7x^6 - 105x^4y^2 + 105x^2y^4 - 7y^6$$

$$\frac{\partial}{\partial y}v(x,y) = 7x^6 - 105x^4y^2 + 105x^2y^4 - 7y^6$$

Hence  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v \neq 0$

COMPRESSIBLE

b)  $u(x,y) = x^7 - 21x^5y^2 + 35x^3y^4 - 7xy^6$

$v(x,y) = 7x^6y - 35x^4y^3 + 21x^2y^5 - y^7$

$$\frac{\partial}{\partial x}v(x,y) = 42x^5y - 140x^3y^3 + 42xy^5$$

$$\frac{\partial}{\partial y}u(x,y) = 42x^5y - 140x^3y^3 + 42xy^5$$

Hence  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u \neq 0$

ROTATIONAL

Note that if we define  $v(x,y) = -(7x^6y - 35x^4y^3 + 21x^2y^5 - y^7)$  then the flow is incompressible and irrotational!

## Problem 5.74

[Difficulty: 2]

**5.74** Consider the two-dimensional flow field in which  $u = Ax^2$  and  $v = Bxy$ , where  $A = 1/2 \text{ ft}^{-1}\cdot\text{s}^{-1}$ ,  $B = -1 \text{ ft}^{-1}\cdot\text{s}^{-1}$ , and the coordinates are measured in feet. Show that the velocity field represents a possible incompressible flow. Determine the rotation at point  $(x, y) = (1, 1)$ . Evaluate the circulation about the "curve" bounded by  $y = 0$ ,  $x = 1$ ,  $y = 1$ , and  $x = 0$ .

**Given:** Two-dimensional flow field

**Find:** (a) show that the velocity field represents a possible incompressible flow  
 (b) Rotation at  $(x, y) = (1, 1)$   
 (c) Circulation about the unit square shown above


**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equations:** 
$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{\omega} = \frac{1}{2} \nabla \times \vec{V} \quad (\text{Definition of rotation})$$

$$\Gamma = \oint \vec{V} \cdot d\vec{s} \quad (\text{Definition of circulation})$$

**Assumptions:** (1) Steady flow  
 (2) Incompressible flow  
 (3) Two dimensional flow (velocity is not a function of z)



Based on the assumptions listed above, the continuity equation reduces to: 
$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$$

This is the criterion against which we will check the flow field.

$$\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 2A \cdot x + B \cdot x = 2 \times \frac{1}{2 \cdot \text{ft} \cdot \text{s}} \cdot x + \frac{-1}{\text{ft} \cdot \text{s}} \cdot x = 0$$

This could be an incompressible flow field.

From the definition of rotation: 
$$\vec{\omega} = \frac{1}{2} \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ Ax^2 & Bxy & 0 \end{vmatrix} = \frac{1}{2} B y \hat{k} \quad \text{At } (x, y) = (1, 1)$$

$$\vec{\omega} = -0.5 \hat{k} \frac{\text{rad}}{\text{s}}$$

From the definition of circulation we break up the integral: 
$$\Gamma = \int_{ab} \vec{V} \cdot d\vec{s} + \int_{bc} \vec{V} \cdot d\vec{s} + \int_{cd} \vec{V} \cdot d\vec{s} + \int_{da} \vec{V} \cdot d\vec{s}$$

The integrand is equal to:  $\vec{V} \cdot d\vec{s} = (Ax^2\hat{i} + Bxy\hat{j}) \cdot (dx\hat{i} + dy\hat{j}) = Ax^2 dx + Bxy dy$  Therefore, the circulation is equal to:

$$\Gamma = \int_{x_a}^{x_b} A \cdot x^2 dx + \int_{y_b}^{y_c} B \cdot x \cdot y dy + \int_{x_c}^{x_d} A \cdot x^2 dx + \int_{y_d}^{y_a} B \cdot x \cdot y dy \quad \text{Evaluating the integrals:}$$

$$\Gamma = \frac{A}{3} \cdot (x_b^3 - x_a^3 + x_d^3 - x_c^3) + \frac{B}{2} [x_c \cdot (y_c^2 - y_b^2) + x_a \cdot (y_a^2 - y_d^2)] \quad \text{Since } x_a = x_d = 0 \text{ and } x_b = x_c \text{ we can simplify:}$$

$$\Gamma = \frac{B}{2} \cdot x_c \cdot (y_c^2 - y_b^2) \quad \text{Substituting given values:} \quad \Gamma = \frac{1}{2} \times \left( \frac{-1}{\text{ft} \cdot \text{s}} \right) \times 1 \cdot \text{ft} \times (1^2 - 0^2) \cdot \text{ft}^2$$

$$\Gamma = -0.500 \cdot \frac{\text{ft}^2}{\text{s}}$$

## Problem 5.75

[Difficulty: 2]

**5.75** Consider the two-dimensional flow field in which  $u = Axy$  and  $v = By^2$ , where  $A = 1\text{ m}^{-1} \cdot \text{s}^{-1}$ ,  $B = -\frac{1}{2}\text{ m}^{-1} \cdot \text{s}^{-1}$ , and the coordinates are measured in meters. Show that the velocity field represents a possible incompressible flow. Determine the rotation at point  $(x, y) = (1, 1)$ . Evaluate the circulation about the “curve” bounded by  $y = 0, x = 1, y = 1,$  and  $x = 0$ .

**Given:** Two-dimensional flow field

**Find:** (a) show that the velocity field represents a possible incompressible flow  
 (b) Rotation at  $(x, y) = (1, 1)$   
 (c) Circulation about the unit square shown above

**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equations:** 
$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\bar{\omega} = \frac{1}{2} \nabla \times \vec{V} \quad (\text{Definition of rotation})$$

$$\Gamma = \oint \vec{V} \cdot d\vec{s} \quad (\text{Definition of circulation})$$

**Assumptions:** (1) Steady flow  
 (2) Incompressible flow  
 (3) Two dimensional flow (velocity is not a function of z)

Based on the assumptions listed above, the continuity equation reduces to: 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$$

This is the criterion against which we will check the flow field.

$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = A \cdot y + 2 \cdot B \cdot y = \frac{1}{\text{m} \cdot \text{s}} \cdot y + 2 \times \frac{-1}{2 \cdot \text{m} \cdot \text{s}} \cdot y = 0$$

This could be an incompressible flow field.

From the definition of rotation: 
$$\bar{\omega} = \frac{1}{2} \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ Axy & By^2 & 0 \end{vmatrix} = -\frac{1}{2} Ax\hat{k} \quad \text{At } (x, y) = (1, 1)$$

$$\bar{\omega} = -0.5\hat{k} \frac{\text{rad}}{\text{s}}$$


From the definition of circulation we break up the integral: 
$$\Gamma = \int_{ab} \vec{V} \cdot d\vec{s} + \int_{bc} \vec{V} \cdot d\vec{s} + \int_{cd} \vec{V} \cdot d\vec{s} + \int_{da} \vec{V} \cdot d\vec{s}$$

The integrand is equal to:  $\vec{V} \cdot d\vec{s} = (Axy\hat{i} + By^2\hat{j}) \cdot (dx\hat{i} + dy\hat{j}) = Axydx + By^2dy$  Therefore, the circulation is equal to:

$$\Gamma = \int_{x_a}^{x_b} A \cdot x \cdot y \, dx + \int_{y_b}^{y_c} B \cdot y^2 \, dy + \int_{x_c}^{x_d} A \cdot x \cdot y \, dx + \int_{y_d}^{y_a} B \cdot y^2 \, dy = \frac{A}{2} \cdot (x_b^2 - x_a^2) \cdot (y_a - y_c) + \frac{B}{3} (y_c^3 - y_b^3 + y_a^3 - y_d^3)$$

Since  $y_a = y_d = 0$  and  $y_b = y_c$  we can simplify: 
$$\Gamma = -\frac{A}{2} \cdot (x_b^2 - x_a^2) \cdot y_c$$
 Substituting given values:

$$\Gamma = \frac{1}{2} \times \frac{1}{\text{m} \cdot \text{s}} \times (1^2 - 0^2) \cdot \text{m}^2 \times -1 \cdot \text{m} \quad \Gamma = -0.5 \frac{\text{m}^2}{\text{s}}$$



## Problem 5.76

[Difficulty: 3]

**\*5.76** Consider a flow field represented by the stream function  $\psi = 3x^5y - 10x^3y^3 + 3xy^5$ . Is this a possible two-dimensional incompressible flow? Is the flow irrotational?

**Given:** Stream function

**Find:** If the flow is incompressible and irrotational

**Solution:**

Basic equations: Incompressibility  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$       Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

Note: The fact that  $\psi$  exists means the flow is incompressible, but we check anyway

$$\psi(x, y) = 3 \cdot x^5 \cdot y - 10 \cdot x^3 \cdot y^3 + 3 \cdot x \cdot y^5$$

Hence  $u(x, y) = \frac{\partial}{\partial y}\psi(x, y) = 3 \cdot x^5 - 30 \cdot x^3 \cdot y^2 + 15 \cdot x \cdot y^4$        $v(x, y) = \frac{\partial}{\partial x}\psi(x, y) = 30 \cdot x^2 \cdot y^3 - 15 \cdot x^4 \cdot y - 3 \cdot y^5$

For incompressibility

$$\frac{\partial}{\partial x}u(x, y) = 15 \cdot x^4 - 90 \cdot x^2 \cdot y^2 + 15 \cdot y^4$$

$$\frac{\partial}{\partial y}v(x, y) = 90 \cdot x^2 \cdot y^2 - 15 \cdot x^4 - 15 \cdot y^4$$

Hence  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$

**INCOMPRESSIBLE**

For irrotationality

$$\frac{\partial}{\partial x}v(x, y) = 60 \cdot x \cdot y^3 - 60 \cdot x^3 \cdot y$$

$$\frac{\partial}{\partial y}u(x, y) = 60 \cdot x^3 \cdot y - 60 \cdot x \cdot y^3$$

Hence  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

**IRROTATIONAL**

## Problem 5.77

[Difficulty: 3]

**\*5.77** Consider the flow field represented by the stream function  $\psi = x^6 - 15x^4y^2 + 15x^2y^4 - y^6$ . Is this a possible two-dimensional, incompressible flow? Is the flow irrotational?

**Given:** Stream function

**Find:** If the flow is incompressible and irrotational

**Solution:**

Basic equations: Incompressibility  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$       Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

Note: The fact that  $\psi$  exists means the flow is incompressible, but we check anyway

$$\psi(x, y) = x^6 - 15x^4y^2 + 15x^2y^4 - y^6$$

Hence  $u(x, y) = \frac{\partial}{\partial y}\psi(x, y) = 60x^2y^3 - 30x^4y - 6y^5$        $v(x, y) = \frac{\partial}{\partial x}\psi(x, y) = 60x^3y^2 - 6x^5 - 30x \cdot y^4$

For incompressibility

$$\frac{\partial}{\partial x}u(x, y) = 120x \cdot y^3 - 120x^3 \cdot y$$

$$\frac{\partial}{\partial y}v(x, y) = 120x^3 \cdot y - 120x \cdot y^3$$

Hence  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$

**INCOMPRESSIBLE**

For irrotationality

$$\frac{\partial}{\partial x}v(x, y) = 180x^2 \cdot y^2 - 30x^4 - 30y^4$$

$$\frac{\partial}{\partial y}u(x, y) = 30x^4 - 180x^2 \cdot y^2 + 30y^4$$

Hence  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

**IRROTATIONAL**

## Problem 5.78

[Difficulty: 2]

**\*5.78** Consider a velocity field for motion parallel to the  $x$  axis with constant shear. The shear rate is  $du/dy = A$ , where  $A = 0.1 \text{ s}^{-1}$ . Obtain an expression for the velocity field,  $\vec{V}$ . Calculate the rate of rotation. Evaluate the stream function for this flow field.

**Given:** Velocity field for motion in the  $x$ -direction with constant shear

**Find:** (a) Expression for the velocity field  
(b) Rate of rotation  
(c) Stream function

**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equations:** 
$$\frac{\partial}{\partial x}(\rho u) + \frac{\partial}{\partial y}(\rho v) + \frac{\partial}{\partial z}(\rho w) + \frac{\partial \rho}{\partial t} = 0 \quad (\text{Continuity equation})$$

$$\vec{\omega} = \frac{1}{2} \nabla \times \vec{V} \quad (\text{Definition of rotation})$$

**Assumptions:** (1) Steady flow  
(2) Incompressible flow

The  $x$ -component of velocity is:  $u = \int A dy + f(x) = Ay + f(x)$  Since flow is parallel to the  $x$ -axis:

$$\vec{V} = [Ay + f(x)]\hat{i}$$

From the definition of rotation: 
$$\vec{\omega} = \frac{1}{2} \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ Ay + f(x) & 0 & 0 \end{vmatrix} = -\frac{1}{2} A\hat{k}$$

$$\vec{\omega} = -0.05\hat{k} \frac{\text{rad}}{\text{s}}$$

From the definition of the stream function  $\psi = \int u dy + g(x) = \int (A \cdot y + f(x)) dy + g(x) = \frac{1}{2} \cdot A \cdot y^2 + f(x) \cdot y + g(x)$

$v = \frac{\partial}{\partial x} \psi = \frac{d}{dx} f(x) \cdot y - \frac{d}{dx} g(x) = 0$  Therefore, the derivatives of both  $f$  and  $g$  are zero, and thus  $f$  and  $g$  are constants:

$$\psi = \frac{1}{2} \cdot A \cdot y^2 + c_1 \cdot y + c_2$$

## Problem 5.79

[Difficulty: 2]

**\*5.79** Consider a flow field represented by the stream function  $\psi = -A/2(x^2 + y^2)$ , where  $A = \text{constant}$ . Is this a possible two-dimensional incompressible flow? Is the flow irrotational?

**Given:** The stream function

**Find:** Whether or not the flow is incompressible; whether or not the flow is irrotational

**Solution:**

The stream function is 
$$\psi(x, y) = -\frac{A}{2 \cdot \pi \cdot (x^2 + y^2)}$$

The velocity components are 
$$u(x, y) = \frac{\partial}{\partial y} \psi(x, y) = \frac{A \cdot y}{\pi \cdot (x^2 + y^2)^2} \quad v(x, y) = \frac{\partial}{\partial x} \psi(x, y) = -\frac{A \cdot x}{\pi \cdot (x^2 + y^2)^2}$$

Because a stream function exists, the flow is:

Incompressible

Alternatively, we can check with

$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$$

$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = -\frac{4 \cdot A \cdot x \cdot y}{\pi (x^2 + y^2)^3} + \frac{4 \cdot A \cdot x \cdot y}{\pi (x^2 + y^2)^3} = 0$$

Incompressible

For a 2D field, the irrotationality the test is 
$$\frac{\partial}{\partial x} v - \frac{\partial}{\partial y} u = 0$$

$$\frac{\partial}{\partial x} v(x, y) - \frac{\partial}{\partial y} u(x, y) = \frac{4 \cdot A \cdot x^2}{\pi \cdot (x^2 + y^2)^3} - \frac{2 \cdot A}{\pi \cdot (x^2 + y^2)^2} + \frac{4 \cdot A \cdot y^2}{\pi \cdot (x^2 + y^2)^3} = \frac{2 \cdot A}{\pi \cdot (x^2 + y^2)^2} \text{Not irrotational}$$

## Problem 5.80

[Difficulty: 2]

**\*5.80** Consider the flow field represented by the stream function  $\psi = Axy + Ay^2$ , where  $A = 1 \text{ s}^{-1}$ . Show that this represents a possible incompressible flow field. Evaluate the rotation of the flow. Plot a few streamlines in the upper half plane.

**Given:** Flow field represented by a stream function.

**Find:** (a) Show that this represents an incompressible velocity field  
 (b) the rotation of the flow  
 (c) Plot several streamlines in the upper half plane

**Solution:** We will apply the definition of rotation to the given velocity field.

**Governing Equation:** 
$$\vec{\omega} = \frac{1}{2} \nabla \times \vec{V} \quad \text{(Definition of rotation)}$$


**Assumptions:** (1) Steady flow  
 (2) Incompressible flow

From the definition of the stream function:  $u = \frac{\partial}{\partial y} \psi = A \cdot x + 2 \cdot A \cdot y$      $v = -\frac{\partial}{\partial x} \psi = -A \cdot y$     Applying the continuity equation:

$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = A - A = 0 \quad \text{This could be an incompressible flow field}$$

From the definition of rotation: 
$$\vec{\omega} = \frac{1}{2} \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ A(x+2y) & -Ay & 0 \end{vmatrix} = \frac{1}{2} (-2A) \hat{k} = -A \hat{k} \quad \vec{\omega} = -A \hat{k}$$

The streamlines are curves where the stream function is constant, i.e.,  $\psi = \text{constant}$     Here is a plot of streamlines:



## Problem 5.81

[Difficulty: 3]

**\*5.81** A flow field is represented by the stream function  $\psi = x^2 - y^2$ . Find the corresponding velocity field. Show that this flow field is irrotational. Plot several streamlines and illustrate the velocity field.

**Given:** Flow field represented by a stream function.

**Find:** (a) Expression for the velocity field  
 (b) Show that flow field is irrotational  
 (c) Plot several streamlines and illustrate velocity field

**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equation:** 
$$\vec{\omega} = \frac{1}{2} \nabla \times \vec{V}$$
 (Definition of rotation)

**Assumptions:** (1) Steady flow  
 (2) Incompressible flow

From the definition of the stream function:  $u = \frac{\partial}{\partial y} \psi = -2 \cdot y$     $v = \frac{\partial}{\partial x} \psi = -2 \cdot x$  In vector notation:


$$\vec{V} = -2y\hat{i} - 2x\hat{j}$$

From the definition of rotation: 
$$\vec{\omega} = \frac{1}{2} \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ -2y & -2x & 0 \end{vmatrix} = \frac{1}{2} (-2 + 2)\hat{k} = \vec{0}$$

$$\vec{\omega} = \vec{0}$$

Flow is irrotational

The streamlines are curves where the stream function is constant, i.e.,  $\psi = \text{constant}$  Here is a plot of streamlines:



## Problem 5.82

[Difficulty: 2]

**\*5.82** Consider the velocity field given by  $\vec{V} = Ax^2\hat{i} + Bxy\hat{j}$ , where  $A = 1 \text{ ft}^{-1}\cdot\text{s}^{-1}$ ,  $B = -2 \text{ ft}^{-1}\cdot\text{s}^{-1}$ , and the coordinates are measured in feet.

- (a) Determine the fluid rotation.
- (b) Evaluate the circulation about the "curve" bounded by  $y=0$ ,  $x=1$ ,  $y=1$ , and  $x=0$ .
- (c) Obtain an expression for the stream function.
- (d) Plot several streamlines in the first quadrant.

**Given:** Flow field represented by a velocity function.

- Find:**
- (a) Fluid rotation
  - (b) Circulation about the curve shown
  - (c) Stream function
  - (d) Plot several streamlines in first quadrant

**Solution:** We will apply the definition of rotation and circulation to the given velocity field.

**Governing Equation:**

$$\vec{\omega} = \frac{1}{2} \nabla \times \vec{V} \quad (\text{Definition of rotation})$$

$$\Gamma = \oint \vec{V} \cdot d\vec{s} \quad (\text{Definition of circulation})$$

**Assumption:** Steady flow

From the definition of rotation:

$$\vec{\omega} = \frac{1}{2} \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ Ax^2 & Bxy & 0 \end{vmatrix} = \frac{1}{2} (By)\hat{k}$$

$$\vec{\omega} = -y\hat{k} \frac{\text{rad}}{\text{ft} \cdot \text{s}}$$

From the definition of circulation we break up the integral:  $\Gamma = \int_{ab} \vec{V} \cdot d\vec{s} + \int_{bc} \vec{V} \cdot d\vec{s} + \int_{cd} \vec{V} \cdot d\vec{s} + \int_{da} \vec{V} \cdot d\vec{s}$

The integrand is equal to:  $\vec{V} \cdot d\vec{s} = (Ax^2\hat{i} + Bxy\hat{j}) \cdot (dx\hat{i} + dy\hat{j}) = Ax^2 dx + Bxy dy$  Therefore, the circulation is equal to:

$$\Gamma = \int_{x_a}^{x_b} A \cdot x^2 dx + \int_{y_b}^{y_c} B \cdot x \cdot y dy + \int_{x_c}^{x_d} A \cdot x^2 dx + \int_{y_d}^{y_a} B \cdot x \cdot y dy \quad \text{Evaluating the integral:}$$

$$\Gamma = \frac{A}{3} \cdot (x_b^3 - x_a^3 + x_d^3 - x_c^3) + \frac{B}{2} [x_c \cdot (y_c^2 - y_b^2) + x_a \cdot (y_a^2 - y_d^2)] \quad \text{Since } x_a = x_d = 0 \text{ and } x_b = x_c \text{ we can simplify:}$$

$$\Gamma = \frac{B}{2} \cdot x_c \cdot (y_c^2 - y_b^2) \quad \text{Substituting given values:} \quad \Gamma = \frac{1}{2} \times -\frac{2}{\text{ft} \cdot \text{s}} \times 1 \cdot \text{ft} \times (1^2 - 0^2) \cdot \text{ft}^2$$


$$\Gamma = -1.000 \cdot \frac{\text{ft}^2}{\text{s}}$$

From the definition of the stream function:  $u = \frac{\partial}{\partial y} \psi \quad \psi = \int u dy + f(x) = \int Ax^2 dy + f(x) = Ax^2 \cdot y + f(x)$


In addition,  $v = \frac{\partial}{\partial x} \psi \quad \psi = - \int v dx + g(y) = - \int B \cdot x \cdot y dx + g(y) = -\frac{B}{2} \cdot x^2 \cdot y + g(y)$  Comparing the two stream functions:

$$\frac{1}{\text{ft} \cdot \text{s}} \cdot x^2 \cdot y + f(x) = \frac{1}{\text{ft} \cdot \text{s}} \cdot x^2 \cdot y + g(y) \quad \text{Thus, } f = g = \text{constant} \quad \text{Taking } f(x) = 0:$$

$$\psi = A \cdot x^2 \cdot y$$



The streamlines are curves where the stream function is constant, i.e.,  $\psi = \text{constant}$  Here is a plot of streamlines:



## Problem 5.83

[Difficulty: 2]

**\*5.83** Consider the flow represented by the velocity field  $\vec{V} = (Ay + B)\hat{i} + Ax\hat{j}$ , where  $A = 10 \text{ s}^{-1}$ ,  $B = 10 \text{ ft/s}$ , and the coordinates are measured in feet.

- (a) Obtain an expression for the stream function.
- (b) Plot several streamlines (including the stagnation streamline) in the first quadrant.
- (c) Evaluate the circulation about the "curve" bounded by  $y = 0$ ,  $x = 1$ ,  $y = 1$ , and  $x = 0$ .


**Given:** Flow field represented by a velocity function.

**Find:** (a) An expression for the stream function  
 (b) Circulation about the curve shown  
 (c) Plot several streamlines (including the stagnation streamline) in first quadrant

**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equation:**  $\Gamma = \oint \vec{V} \cdot d\vec{s}$  (Definition of circulation)

**Assumptions:** Steady flow



From the definition of the stream function:  $u = \frac{\partial}{\partial y} \psi$      $\psi = \int u \, dy + f(x) = \int (A \cdot y + B) \, dy + f(x) = \frac{A}{2} \cdot y^2 + B \cdot y + f(x)$

In addition,  $v = \frac{\partial}{\partial x} \psi$      $\psi = - \int v \, dx + g(y) = - \int A \cdot x \, dx + g(y) = -\frac{A}{2} \cdot x^2 + g(y)$     Comparing the two stream functions:

$\frac{A}{2} \cdot y^2 + B \cdot y + f(x) = -\frac{A}{2} \cdot x^2 + g(y)$     Thus,  $f(x) = -\frac{A}{2} \cdot x^2 + C$     Taking  $C = 0$ :

$$\psi = \frac{A}{2} \cdot (y^2 - x^2) + B \cdot y$$

From the definition of circulation we break up the integral:  $\Gamma = \int_{ab} \vec{V} \cdot d\vec{s} + \int_{bc} \vec{V} \cdot d\vec{s} + \int_{cd} \vec{V} \cdot d\vec{s} + \int_{da} \vec{V} \cdot d\vec{s}$

The integrand is equal to:  $\vec{V} \cdot d\vec{s} = ((Ay + B)\hat{i} + Ax\hat{j}) \cdot (dx\hat{i} + dy\hat{j}) = (Ay + B)dx + Ax \, dy$     Therefore, the circulation is:

$\Gamma = \int_{x_a}^{x_b} (A \cdot y + B) \, dx + \int_{y_b}^{y_c} A \cdot x \, dy + \int_{x_c}^{x_d} (A \cdot y + B) \, dx + \int_{y_d}^{y_a} A \cdot x \, dy$     Evaluating the integral:

$\Gamma = (A \cdot y_a + B) \cdot (x_b - x_a) + A \cdot x_b \cdot (y_c - y_b) + (A \cdot y_c + B) \cdot (x_d - x_c) + A \cdot x_d \cdot (y_a - y_d)$     Substituting known values:

$$\Gamma = \left( \frac{10}{s} \times 0 \cdot \text{ft} + 10 \cdot \frac{\text{ft}}{s} \right) \times (1 - 0) \cdot \text{ft} + \frac{10}{s} \times 1 \cdot \text{ft} \times (1 - 0) \cdot \text{ft} + \left( \frac{10}{s} \times 1 \cdot \text{ft} + 10 \cdot \frac{\text{ft}}{s} \right) \times (0 - 1) \cdot \text{ft} + \frac{10}{s} \times 0 \cdot \text{ft} \times (1 - 0) \cdot \text{ft}$$

$$\Gamma = 0 \cdot \frac{\text{ft}^2}{s}$$

The streamlines are curves where the stream function is constant, i.e.,  $\psi = \text{constant}$ . Here is a plot of streamlines:

The stagnation streamline is the one running through the point where the velocity vanishes:


$$A \cdot y_{\text{stag}} + B = 0 \quad y_{\text{stag}} = -\frac{B}{A} = -1 \cdot \text{ft}$$

$$A \cdot x_{\text{stag}} = 0 \quad x_{\text{stag}} = 0$$

Plugging this information in to find the stream function at the stagnation point yields:

$$\psi_{\text{stag}} = \frac{10}{2 \cdot \text{s}} \cdot [(-1 \cdot \text{ft})^2 - (0 \cdot \text{ft})^2] + 10 \cdot \frac{\text{ft}}{\text{s}} \cdot -1 \cdot \text{ft}$$


$$\psi_{\text{stag}} = -5 \cdot \frac{\text{ft}^2}{\text{s}}$$



## Problem 5.84

[Difficulty: 3]

**5.84** Consider again the viscometric flow of Example 5.7. Evaluate the average rate of rotation of a pair of perpendicular line segments oriented at  $\pm 45^\circ$  from the  $x$  axis. Show that this is the same as in the example.




**Given:** Viscometric flow of Example 5.7,  $V = U(y/h)i$ , where  $U = 4 \text{ mm/s}$  and  $h = 4 \text{ mm}$

**Find:** (a) Average rate of rotation of two line segments at  $\pm 45^\circ$  degrees  
(b) Show that this is the same as in the example

**Solution:** We will apply the definition of rotation to the given velocity field.

**Governing Equation:**  $\vec{\omega} = \frac{1}{2} \nabla \times \vec{V}$  (Definition of rotation)


**Assumptions:** (1) Steady flow  
(2) Incompressible flow



Considering the lines shown:  $u_c = u_a + \frac{\partial}{\partial y} u \cdot (1 \cdot \sin(\theta_1))$

$$-\omega_{ac} = \frac{(u_c - u_a) \cdot \sin(\theta_1)}{l} \quad \text{since the component normal to } l \text{ is } u \cdot \sin(\theta_1)$$

$$-\omega_{ac} = \frac{\partial}{\partial y} u \cdot \frac{(1 \cdot \sin(\theta_1)) \cdot \sin(\theta_1)}{1} = \frac{\partial}{\partial y} u \cdot (\sin(\theta_1))^2 = \frac{U}{h} \cdot (\sin(\theta_1))^2 \quad \text{Now consider this sketch:}$$



$$u_b = u_d + \frac{\partial}{\partial y} u \cdot (1 \cdot \sin(\theta_2)) \quad -\omega_{bd} = \frac{(u_d - u_b) \cdot \sin(\theta_2)}{l} \quad \text{since the component normal to } l \text{ is } u \cdot \sin(\theta_2)$$

$$-\omega_{bd} = \frac{\partial}{\partial y} u \cdot \frac{(1 \cdot \sin(\theta_2)) \cdot \sin(\theta_2)}{1} = \frac{\partial}{\partial y} u \cdot (\sin(\theta_2))^2 = \frac{U}{h} \cdot (\sin(\theta_2))^2 \quad \text{Now we sum these terms:}$$

$$\omega = \frac{1}{2} \cdot (\omega_{ac} + \omega_{bd}) = -\frac{1}{2} \cdot \frac{U}{h} \cdot [(\sin(\theta_1))^2 + (\sin(\theta_2))^2] \quad \text{When } \theta_1 = 45\text{-deg and } \theta_2 = 135\text{-deg}$$

$$\omega = -\frac{1}{2} \cdot \frac{U}{h} \cdot \left[ \left( \frac{1}{\sqrt{2}} \right)^2 + \left( \frac{1}{\sqrt{2}} \right)^2 \right]$$

$$\omega = -\frac{1}{2} \cdot \frac{U}{h}$$


$$\text{Substituting for } U \text{ and } h: \quad \omega = -\frac{1}{2} \times 4 \frac{\text{mm}}{\text{s}} \times \frac{1}{4 \text{ mm}}$$

$$\omega = -0.5 \frac{1}{\text{s}}$$

## Problem 5.85

[Difficulty: 3]

**5.85** Consider the pressure-driven flow between stationary parallel plates separated by distance  $b$ . Coordinate  $y$  is measured from the bottom plate. The velocity field is given by  $u = U(y/b)[1 - (y/b)]$ . Obtain an expression for the circulation about a closed contour of height  $h$  and length  $L$ . Evaluate when  $h = b/2$  and when  $h = b$ . Show that the same result is obtained from the area integral of the Stokes Theorem (Eq. 5.18).



**Given:** Velocity field for pressure-driven flow between stationary parallel plates

**Find:** (a) Expression for circulation about a closed contour of height  $h$  and length  $L$   
 (b) Evaluate part (a) for  $h = b/2$  and  $h = b$   
 (c) Show that the same result is obtained from area integral of Stokes Theorem (Eq. 5.14)

**Solution:** We will apply the definition of circulation to the given velocity field.

**Governing Equations:**  $\Gamma = \oint \vec{V} \cdot d\vec{s}$  (Definition of circulation)

$$\int_A (\nabla \times \vec{V}) dA = \oint \vec{V} \cdot d\vec{s} \quad (\text{Stokes Theorem})$$

**Assumptions:** (1) Steady flow

From the definition of circulation we break up the integral:  $\Gamma = \int_1 \vec{V} \cdot d\vec{s} + \int_2 \vec{V} \cdot d\vec{s} + \int_3 \vec{V} \cdot d\vec{s} + \int_4 \vec{V} \cdot d\vec{s}$

The integrand is equal to:  $\vec{V} \cdot d\vec{s} = U \frac{y}{b} \left(1 - \frac{y}{b}\right) \hat{i} \cdot (dx \hat{i} + dy \hat{j}) = U \frac{y}{b} \left(1 - \frac{y}{b}\right) dx$  Therefore, the circulation is equal to:

$$\Gamma = \int_0^L U \cdot \frac{0}{b} \cdot \left(1 - \frac{0}{b}\right) dx + \int_L^0 U \cdot \frac{h}{b} \cdot \left(1 - \frac{h}{b}\right) dx = -U \cdot L \cdot \frac{h}{b} \cdot \left(1 - \frac{h}{b}\right) \quad \Gamma = -U \cdot L \cdot \frac{h}{b} \cdot \left(1 - \frac{h}{b}\right)$$

For  $h = b/2$ :  $\Gamma = -U \cdot L \cdot \frac{1}{b} \cdot \frac{b}{2} \cdot \left(1 - \frac{1}{b} \cdot \frac{b}{2}\right) \quad \Gamma = -\frac{U \cdot L}{4}$  For  $h = b$ :  $\Gamma = -U \cdot L \cdot 1 \cdot (1 - 1) \quad \Gamma = 0$

From Stokes Theorem:  $\Gamma = \int_A (\nabla \times \vec{V}) dA = \int_A \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y}\right) dA = -U \int_A \left(\frac{1}{b} - \frac{2y}{b}\right) dA$  We define  $dA = L dy$ :

$$\Gamma = -U \cdot L \cdot \int_0^h \left(\frac{1}{b} - \frac{2}{b} \cdot y\right) dy = -U \cdot L \cdot \left(\frac{h}{b} - \frac{h^2}{b}\right) = -U \cdot L \cdot \frac{h}{b} \cdot \left(1 - \frac{h}{b}\right) \quad \Gamma = -U \cdot L \cdot \frac{h}{b} \cdot \left(1 - \frac{h}{b}\right)$$

## Problem 5.86

[Difficulty: 3]

**\*5.86** The velocity field near the core of a tornado can be approximated as

$$\vec{V} = -\frac{q}{2\pi r}\hat{e}_r + \frac{K}{2\pi r}\hat{e}_\theta$$

Is this an irrotational flow field? Obtain the stream function for this flow.

**Given:** Velocity field approximation for the core of a tornado

**Find:** (a) Whether or not this is an irrotational flow  
(b) Stream function for the flow

**Solution:** We will apply the definition of rotation to the given velocity field.

**Governing Equation:**

$$\vec{\omega} = \frac{1}{2}\nabla \times \vec{V} \quad (\text{Definition of rotation})$$

$$\vec{\nabla} = \hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{k} \frac{\partial}{\partial z} \quad (\text{Definition of "del" operator})$$

$$\frac{\partial \hat{e}_r}{\partial \theta} = \hat{e}_\theta \quad \frac{\partial \hat{e}_\theta}{\partial \theta} = -\hat{e}_r \quad (\text{Hints from text})$$

**Assumptions:** (1) Steady flow  
(2) Two-dimensional flow (no z velocity, velocity is not a function of  $\theta$  or  $z$ )

From the definition of rotation:  $\vec{\omega} = \frac{1}{2}\left(\hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{k} \frac{\partial}{\partial z}\right) \times (V_r \hat{e}_r + V_\theta \hat{e}_\theta)$  Employing assumption (2) yields:

$$\vec{\omega} = \frac{1}{2}\left(\hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta}\right) \times (V_r \hat{e}_r + V_\theta \hat{e}_\theta) = \frac{1}{2}\left[\hat{e}_r \times \left(\hat{e}_r \frac{\partial V_r}{\partial r} + \hat{e}_\theta \frac{\partial V_\theta}{\partial r}\right) + \hat{e}_\theta \frac{1}{r} \times \frac{\partial}{\partial \theta}(V_r \hat{e}_r + V_\theta \hat{e}_\theta)\right] \quad \text{From product rule:}$$

$$\vec{\omega} = \frac{1}{2}\left[\left(\hat{e}_r \times \hat{e}_r\right) \frac{\partial V_r}{\partial r} + \left(\hat{e}_r \times \hat{e}_\theta\right) \frac{\partial V_\theta}{\partial r} + \hat{e}_\theta \frac{1}{r} \times \left(\hat{e}_r \frac{\partial V_r}{\partial \theta} + V_r \frac{\partial \hat{e}_r}{\partial \theta} + \hat{e}_\theta \frac{\partial V_\theta}{\partial \theta} + V_\theta \frac{\partial \hat{e}_\theta}{\partial \theta}\right)\right] \quad \text{Using the hints from the text:}$$

$$\vec{\omega} = \frac{1}{2}\left[\left(\hat{e}_r \times \hat{e}_r\right) \frac{\partial V_r}{\partial r} + \left(\hat{e}_r \times \hat{e}_\theta\right) \left(\frac{\partial V_\theta}{\partial r} - \frac{1}{r} \frac{\partial V_r}{\partial \theta} + \frac{V_\theta}{r}\right) + \left(\hat{e}_\theta \times \hat{e}_\theta\right) \left(\frac{1}{r} \frac{\partial V_\theta}{\partial \theta} + \frac{V_r}{r}\right)\right] = \frac{1}{2}\left(\frac{\partial V_\theta}{\partial r} - \frac{1}{r} \frac{\partial V_r}{\partial \theta} + \frac{V_\theta}{r}\right) \hat{k}$$

Since  $V$  is only a function of  $r$ :  $\vec{\omega} = \frac{1}{2}\left(\frac{\partial V_\theta}{\partial r} + \frac{V_\theta}{r}\right) \hat{k} = \frac{1}{2}\left(-\frac{K}{2\pi r^2} + \frac{K}{2\pi r^2}\right) \hat{k} = \vec{0}$

Flow is irrotational.

To build the stream function:  $V_r = \frac{1}{r} \frac{\partial \psi}{\partial \theta}$   $\psi = \int r \cdot V_r d\theta + f(r) = -\int \frac{q}{2\pi} d\theta + f(r) = -\frac{q \cdot \theta}{2\pi} + f(r)$

$V_\theta = \frac{\partial \psi}{\partial r}$   $\psi = -\int V_\theta dr + g(\theta) = -\int \frac{K}{2\pi \cdot r} dr + g(\theta) = -\frac{K}{2\pi} \cdot \ln(r) + g(\theta)$  Comparing these two expressions:

$$-\frac{q \cdot \theta}{2\pi} + f(r) = -\frac{K}{2\pi} \cdot \ln(r) + g(\theta) \quad f(r) = -\frac{K}{2\pi} \cdot \ln(r)$$

$\psi = -\frac{K}{2\pi} \cdot \ln(r) - \frac{q \cdot \theta}{2\pi}$

## Problem 5.87

[Difficulty: 2]

**5.87** The velocity profile for fully developed flow in a circular tube is  $V_z = V_{\max}[1 - (r/R)^2]$ . Evaluate the rates of linear and angular deformation for this flow. Obtain an expression for the vorticity vector,  $\vec{\zeta}$ .

**Given:** Velocity field for fully-developed flow in a circular tube

**Find:** (a) Rates of linear and angular deformation for this flow  
(b) Expression for the vorticity vector

**Solution:** We will apply the definition of vorticity to the given velocity field.

**Governing Equation:**  $\vec{\zeta} = \nabla \times \vec{V}$  (Definition of vorticity)

**Assumptions:** (1) Steady flow

The volume dilation rate of the flow is:  $\nabla \cdot \vec{V} = \frac{1}{r} \frac{\partial(rV_r)}{\partial r} + \frac{1}{r} \frac{\partial V_\theta}{\partial \theta} + \frac{\partial V_z}{\partial z} = 0$

Rates of linear deformation in all three directions is zero.

The angular deformations are: r- $\theta$  plane:  $\frac{1}{r} \cdot \frac{\partial}{\partial r} \left( \frac{V_\theta}{r} \right) + \frac{\partial}{\partial \theta} V_r = 0$

$\theta$ -z plane:  $\frac{\partial}{\partial z} V_\theta + \frac{1}{r} \cdot \frac{\partial}{\partial \theta} V_z = 0$

z-r plane:  $\frac{\partial}{\partial z} V_r + \frac{\partial}{\partial r} V_z = -V_{\max} \cdot \frac{2 \cdot r}{R^2}$

angdef =  $-V_{\max} \cdot \frac{2 \cdot r}{R^2}$

The vorticity in cylindrical coordinates is:  $\vec{\zeta} = \nabla \times \vec{V} = \left( \frac{1}{r} \frac{\partial V_z}{\partial \theta} - \frac{\partial V_\theta}{\partial z} \right) \hat{e}_r + \left( \frac{\partial V_r}{\partial z} - \frac{\partial V_z}{\partial r} \right) \hat{e}_\theta + \left( \frac{1}{r} \frac{\partial r V_\theta}{\partial r} - \frac{1}{r} \frac{\partial V_r}{\partial \theta} \right) \hat{k}$

$\vec{\zeta} = -V_{\max} \frac{2r}{R^2} \hat{e}_\theta$

## Problem 5.88

[Difficulty: 3]

**5.88** Consider the pressure-driven flow between stationary parallel plates separated by distance  $2b$ . Coordinate  $y$  is measured from the channel centerline. The velocity field is given by  $u = u_{\max}[1 - (y/b)^2]$ . Evaluate the rates of linear and angular deformation. Obtain an expression for the vorticity vector,  $\vec{\zeta}$ . Find the location where the vorticity is a maximum.

**Given:** Velocity field for pressure-driven flow between stationary parallel plates

**Find:** (a) Rates of linear and angular deformation for this flow  
 (b) Expression for the vorticity vector  
 (c) Location of maximum vorticity

**Solution:** We will apply the definition of vorticity to the given velocity field.

**Governing Equation:**  $\vec{\zeta} = \nabla \times \vec{V}$  (Definition of vorticity)

**Assumptions:** (1) Steady flow

The volume dilation rate of the flow is:  $\nabla \cdot \vec{V} = \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0$

Rates of linear deformation in all three directions is zero.

The angular deformations are: x-y plane:  $\frac{\partial}{\partial x} v + \frac{\partial}{\partial y} u = -u_{\max} \cdot \frac{2 \cdot y}{b^2}$

y-z plane:  $\frac{\partial}{\partial y} w + \frac{\partial}{\partial z} v = 0$

z-x plane:  $\frac{\partial}{\partial z} u + \frac{\partial}{\partial x} w = 0$

angdef =  $-u_{\max} \cdot \frac{2 \cdot y}{b^2}$

The vorticity is:  $\vec{\zeta} = \nabla \times \vec{V} = \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ u_{\max} \left[ 1 - \left( \frac{y}{b} \right)^2 \right] & 0 & 0 \end{vmatrix} = u_{\max} \frac{2y}{b^2} \hat{k}$


$\vec{\zeta} = u_{\max} \frac{2y}{b^2} \hat{k}$

The vorticity is a maximum at  $y=b$  and  $y=-b$

## Problem 5.89

[Difficulty: 2]

**5.89** Consider a steady, laminar, fully developed, incompressible flow between two infinite plates, as shown. The flow is due to the motion of the left plate as well as a pressure gradient that is applied in the  $y$  direction. Given the conditions that  $\vec{V} \neq \vec{V}(z)$ ,  $w=0$ , and that gravity points in the negative  $y$  direction, prove that  $u=0$  and that the pressure gradient in the  $y$  direction must be constant.



**Given:** Flow between infinite plates

**Find:** Prove that  $u=0$ ,  $dP/dy = \text{constant}$

**Solution:**

**Governing Equations:** 
$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad (\text{Continuity Equation})$$

$$\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial P}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right)$$

$$\rho \left( \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) = \rho g_y - \frac{\partial P}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} + \frac{\partial^2 v}{\partial z^2} \right) \quad (\text{Navier-Stokes Equations})$$

$$\rho \left( \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) = \rho g_z - \frac{\partial P}{\partial z} + \mu \left( \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} \right)$$

**Assumptions:** Incompressible fluid  
No motion along the wall ( $x=0$ ) limited to two dimensions ( $w=0$ ).

**Prove that  $u=0$ :**

Given that  $\vec{V} \neq \vec{V}(z)$  this means that 
$$\frac{\partial u}{\partial z} = \frac{\partial v}{\partial z} = \frac{\partial w}{\partial z} = 0$$

Also given that the flow is fully developed which means that  $\vec{V} \neq \vec{V}(y)$  so that 
$$\frac{\partial u}{\partial y} = \frac{\partial v}{\partial y} = \frac{\partial w}{\partial y} = 0$$

And steady flow implies that  $\vec{V} \neq \vec{V}(t)$

The continuity equation becomes  $\frac{\partial u}{\partial x} = 0$ , but because  $u \neq u(y, z, t)$  then  $u = u(x)$  meaning that the partial derivative here

becomes an ordinary derivative: 
$$\frac{du}{dx} = 0$$

Integrating the ordinary derivative gives:  $u = \text{constant}$

By the no-slip boundary condition  $u=0$  at the surface of either plate meaning the constant must be zero.

Hence:  $u=0$

**Prove that**  $\frac{\partial P}{\partial y} = \text{constant}$  :

Due to the fact that  $u = 0$ , and gravity is in the negative y-direction the x-component of the Navier-Stokes Equation becomes:

$$\frac{\partial P}{\partial x} = 0 \quad \text{hence } P \neq P(x)$$

Due to the fact that  $w = 0$ , and gravity is in the negative y-direction the z-component of the Navier-Stokes Equation becomes:

$$\frac{\partial P}{\partial z} = 0 \quad \text{hence } P \neq P(z)$$

The y-component of the Navier-Stokes Equation reduces to:

$$0 = -\frac{\partial P}{\partial y} - \rho g + \mu \left( \frac{\partial^2 v}{\partial x^2} \right)$$

So then

$$\frac{\partial P}{\partial y} = -\rho g + \mu \left( \frac{\partial^2 v}{\partial x^2} \right) \quad [1]$$

It has been shown that  $P \neq P(x, z)$  and because the flow is steady  $P \neq P(t)$  meaning that  $P = P(y)$ . This means that the left hand side of [1] can only be a function of y or a constant. Additionally, by the fully developed, steady flow, and  $\vec{V} \neq \vec{V}(z)$  conditions it is shown that  $v = v(x)$ . For this reason the right hand side of [1] can only be a function of x or a constant.

Mathematically speaking it is impossible for:  $f(y) = g(x)$  so each side of [1] must be a constant.

Hence,  $\frac{\partial P}{\partial y} = \text{constant}$

## Problem 5.90

[Difficulty: 3]


**5.90** Assume the liquid film in Example 5.9 is not isothermal, but instead has the following distribution:

$$T(y) = T_0 + (T_w - T_0)\left(1 - \frac{y}{h}\right)$$

where  $T_0$  and  $T_w$  are, respectively, the ambient temperature and the wall temperature. The fluid viscosity decreases with increasing temperature and is assumed to be described by

$$\mu = \frac{\mu_0}{1 + a(T - T_0)}$$

with  $a > 0$ . In a manner similar to Example 5.9, derive an expression for the velocity profile.



**Given:** temperature profile and temperature-dependent viscosity expression

**Find:** Velocity Profile

**Solution:**

**Governing Equations:**

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad (\text{Continuity Equation})$$

$$\begin{aligned} \rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) &= \rho g_x - \frac{\partial P}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right) \\ \rho \left( \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) &= \rho g_y - \frac{\partial P}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} + \frac{\partial^2 v}{\partial z^2} \right) \\ \rho \left( \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) &= \rho g_z - \frac{\partial P}{\partial z} + \mu \left( \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} \right) \end{aligned} \quad (\text{Navier-Stokes Equations})$$

**Assumptions:** Incompressible fluid

Similar to the Example 5.9, the x-component momentum equation can be simplified to

$$\frac{d\tau_{yx}}{dy} = -\rho g \sin \theta \quad (1)$$

Integrating once, one has

$$\tau_{yx} = -\rho g y \sin \theta + C_1 \quad (2)$$

Using the boundary condition:  $\tau_{yx}(y = h) = 0$

$$c_1 = \rho g h \sin \theta \quad (3)$$

Substituting  $c_1$  into eq. (2),

$$\tau_{yx} = \mu \frac{du}{dy} = \rho g (h - y) \sin \theta \quad (4)$$

Here, the fluid viscosity depends on the temperature,

$$\mu = \frac{\mu_0}{1 + a(T_w - T_0)(1 - y/h)} \quad (5)$$

Substituting equation (5) into equation (4), we have

$$\frac{du}{dy} = \frac{\rho g h (1 - y/h) \sin \theta}{\mu_0} (1 + a(T_w - T_0)(1 - y/h)) \quad (6)$$

Integrating equation (6) once

$$u = \frac{\rho g h \sin \theta}{\mu_0} \left( y \left( 1 - \frac{y}{2h} \right) + a(T_w - T_0) y \left( 1 - \frac{y}{h} + \frac{y^2}{3h^2} \right) \right) + C_2 \quad (7)$$

At  $y=0$ ,  $u=0$ :  $c_2=0$ .

Substituting  $c_2=0$  into eq. (7), one obtains

$$u = \frac{\rho g h \sin \theta}{\mu_0} \left( y \left( 1 - \frac{y}{2h} \right) + a(T_w - T_0) y \left( 1 - \frac{y}{h} + \frac{y^2}{3h^2} \right) \right) \quad (8)$$

When  $a=0$ , eq. (8) can be simplified to

$$u = \frac{\rho g h \sin \theta}{\mu_0} y \left( 1 - \frac{y}{2h} \right), \text{ and it is exactly the same velocity profile in Example 5.9.}$$

## Problem 5.91

[Difficulty: 2]


**5.91** The  $x$  component of velocity in a laminar boundary layer in water is approximated as  $u = U \sin(\pi y/2\delta)$ , where  $U = 3$  m/s and  $\delta = 2$  mm. The  $y$  component of velocity is much smaller than  $u$ . Obtain an expression for the net shear force per unit volume in the  $x$  direction on a fluid element. Calculate its maximum value for this flow.

**Given:** Sinusoidal approximation for velocity profile in laminar boundary layer

**Find:** (a) Express shear force per unit volume in the  $x$ -direction  
(b) Maximum value at these conditions

**Solution:** We will evaluate a differential volume of fluid in this flow field

**Assumptions:** (1) Steady flow



The differential of shear force would be:  $dF_{\text{shear}} = (\tau + d\tau) \cdot dx \cdot dz - \tau \cdot dx \cdot dz = d\tau \cdot dx \cdot dz$  and  $\frac{dF_{\text{sx}}}{dV} = \frac{d\tau}{dy} = \frac{d}{dy} \left( \mu \cdot \frac{du}{dy} \right) = \mu \cdot \frac{d^2}{dy^2} u$

From the given profile:  $\frac{d}{dy} u = \frac{\pi \cdot U}{2 \cdot \delta} \cdot \cos\left(\frac{\pi \cdot y}{2 \cdot \delta}\right)$  and  $\frac{d^2}{dy^2} u = -U \cdot \left(\frac{\pi}{2 \cdot \delta}\right)^2 \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right)$  Thus,  $\frac{dF_{\text{sx}}}{dV} = -\mu \cdot U \cdot \left(\frac{\pi}{2 \cdot \delta}\right)^2 \cdot \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right)$

The maximum magnitude for this shear force is when  $y = \delta$ :

$$F_{\text{vmax}} = \frac{dF_{\text{sxmax}}}{dV} = -\mu \cdot U \cdot \left(\frac{\pi}{2 \cdot \delta}\right)^2$$

For water:  $\mu = 0.001 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$   $U = 3 \cdot \frac{\text{m}}{\text{s}}$   $\delta = 2 \cdot \text{mm}$  Substituting these values:

$$F_{\text{vmax}} = -0.001 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times 3 \cdot \frac{\text{m}}{\text{s}} \times \left(\frac{\pi}{2} \times \frac{1}{0.002 \cdot \text{m}}\right)^2 \quad F_{\text{vmax}} = -1.851 \cdot \frac{\text{kN}}{\text{m}^3}$$



## Problem 5.92


[Difficulty: 3]

**5.92** A linear velocity profile was used to model flow in a laminar incompressible boundary layer in Problem 5.10. Express the rotation of a fluid particle. Locate the maximum rate of rotation. Express the rate of angular deformation for a fluid particle. Locate the maximum rate of angular deformation. Express the rates of linear deformation for a fluid particle. Locate the maximum rates of linear deformation. Express the shear force per unit volume in the  $x$  direction. Locate the maximum shear force per unit volume; interpret this result.

**5.10** A crude approximation for the  $x$  component of velocity in an incompressible laminar boundary layer is a linear variation from  $u = 0$  at the surface ( $y = 0$ ) to the freestream velocity,  $U$ , at the boundary-layer edge ( $y = \delta$ ). The equation for the profile is  $u = Uy/\delta$ , where  $\delta = cx^{1/2}$  and  $c$  is a constant. Show that the simplest expression for the  $y$  component of velocity is  $v = uy/4x$ . Evaluate the maximum value of the ratio  $v/U$ , at a location where  $x = 0.5$  m and  $\delta = 5$  mm.

**Given:** Linear approximation for velocity profile in laminar boundary layer

- Find:**
- Express rotation, find maximum
  - Express angular deformation, locate maximum
  - Express linear deformation, locate maximum
  - Express shear force per unit volume, locate maximum



**Solution:** We will apply the definition of rotation to the given velocity field.

**Governing Equation:** 
$$\vec{\omega} = \frac{1}{2} \nabla \times \vec{V} \quad (\text{Definition of rotation})$$

**Assumptions:** (1) Steady flow

The rotation is: 
$$\vec{\omega} = \frac{1}{2} \begin{vmatrix} \hat{i} & \hat{j} & \hat{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ U \frac{y}{\delta} & \frac{U y y}{4 x \delta} & 0 \end{vmatrix} = \frac{1}{2} \left[ \frac{\partial}{\partial x} \left( \frac{U y y}{4 x \delta} \right) - \frac{\partial}{\partial y} \left( U \frac{y}{\delta} \right) \right] \hat{k}$$
 Computing the partial derivatives:

$$\omega_z = -\frac{1}{2} \cdot \frac{1}{4} \cdot \frac{3}{2} \cdot \frac{U \cdot y^2}{c \cdot x^2} - \frac{1}{2} \cdot \frac{U}{c \cdot x^2} = -\frac{1}{2} \left( \frac{3}{8} \cdot \frac{U \cdot y^2}{c \cdot x^2} + \frac{U}{c \cdot x^2} \right) = -\frac{U}{2 \cdot c \cdot x^2} \left[ 1 + \frac{3}{8} \cdot \left( \frac{y}{x} \right)^2 \right]$$

$$\omega_z = -\frac{U}{2 \cdot \delta} \left[ 1 + \frac{3}{8} \cdot \left( \frac{y}{x} \right)^2 \right]$$

Maximum value at  $y = \delta$

The angular deformation is: 
$$\frac{\partial v}{\partial x} + \frac{\partial u}{\partial y} = \frac{\partial}{\partial x} \left( \frac{U}{4} \cdot \frac{y^2}{c \cdot x^2} \right) + \frac{\partial}{\partial y} \left( U \cdot \frac{y}{c \cdot x^2} \right) = \frac{U}{c} \left( -\frac{1}{4} \cdot \frac{3}{2} \cdot \frac{y^2}{x^2} + \frac{1}{x^2} \right) = \frac{U}{c \cdot x^2} \left[ 1 - \frac{3}{8} \cdot \left( \frac{y}{x} \right)^2 \right]$$

$$\text{angdef} = \frac{U}{\delta} \left[ 1 - \frac{3}{8} \cdot \left( \frac{y}{x} \right)^2 \right]$$

Maximum value at  $y = 0$

Linear deformation: 
$$\frac{\partial u}{\partial x} = \frac{\partial}{\partial x} \left( U \cdot \frac{y}{c \cdot x^2} \right) = -\frac{1}{2} \cdot \frac{U \cdot y}{c \cdot x^2}$$

$$\frac{\partial u}{\partial x} = -\frac{U}{2\delta} \cdot \frac{y}{x}$$


Maximum value at  $y = \delta$

$$\frac{\partial v}{\partial y} = \frac{\partial}{\partial y} \left( \frac{U}{4} \cdot \frac{y^2}{c \cdot x^2} \right) = \frac{2}{4} \cdot \frac{U \cdot y}{c \cdot x^2}$$

$$\frac{\partial v}{\partial y} = \frac{U}{2\delta} \cdot \frac{y}{x}$$

Maximum value at  $y = \delta$

The shear stress is  $\tau_{yx} = \mu \cdot \left( \frac{\partial v}{\partial x} + \frac{\partial u}{\partial y} \right) = \frac{\mu \cdot U}{\delta} \cdot \left[ 1 - \frac{3}{8} \cdot \left( \frac{y}{x} \right)^2 \right]$



The net shear force on a fluid element is  $d\tau \, dx \, dz$ :  $d\tau = \frac{\partial \tau}{\partial y} \cdot dy = \frac{\mu \cdot U}{\delta} \cdot \left( -\frac{3}{8} \cdot \frac{2 \cdot y}{x^2} \right) \cdot dy = -\frac{3 \cdot \mu \cdot U \cdot y}{4 \cdot \delta \cdot x^2} \cdot dy$

Therefore the shear stress per unit volume is:  $\frac{d}{dV} F = -\frac{3 \cdot \mu \cdot U}{4 \cdot \delta \cdot x} \cdot \frac{y}{x}$  Maximum value at  $y = \delta$

## Problem 5.93

[Difficulty: 2]


**5.93** Problem 4.35 gave the velocity profile for fully developed laminar flow in a circular tube as  $u = u_{\max}[1 - (r/R)^2]$ . Obtain an expression for the shear force per unit volume in the  $x$  direction for this flow. Evaluate its maximum value for the conditions of Problem 4.35.

**Given:** Velocity profile for fully developed laminar flow in a tube

**Find:** (a) Express shear force per unit volume in the  $x$ -direction  
(b) Maximum value at these conditions

**Solution:** We will evaluate a differential volume of fluid in this flow field

**Assumptions:** (1) Steady flow



The differential of shear force would be:  $dF_{\text{shear}} = (\tau + d\tau) \cdot 2 \cdot \pi \cdot r \cdot dz \cdot dr - \tau \cdot 2 \cdot \pi \cdot r \cdot dz \cdot dr = 2 \cdot \pi \cdot r \cdot d\tau \cdot dz \cdot dr$

and in cylindrical coordinates: 
$$\frac{dF_{sz}}{dV} = \frac{1}{2 \cdot \pi \cdot r \cdot dr \cdot dz} \cdot \frac{d}{dr} (r \cdot \tau) \cdot 2 \cdot \pi \cdot r \cdot dz = \frac{1}{r} \frac{d}{dr} \left( r \cdot \mu \cdot \frac{d}{dr} u \right)$$

From the given profile:  $\frac{d}{dr} u = -u_{\max} \cdot \frac{2 \cdot r}{R^2}$  Therefore: 
$$\frac{dF_{sz}}{dV} = -2 \cdot \frac{\mu \cdot u_{\max}}{r} \cdot \frac{d}{dr} \left( \frac{r^2}{R^2} \right) = -2 \cdot \frac{\mu \cdot u_{\max}}{r} \cdot \frac{2 \cdot r}{R^2} = -4 \cdot \frac{\mu \cdot u_{\max}}{R^2}$$

$$F_{v\max} = \frac{dF_{sz\max}}{dV} = -4 \cdot \frac{\mu \cdot u_{\max}}{R^2}$$


For water:  $\mu = 2.1 \times 10^{-5} \frac{\text{lb} \cdot \text{s}}{\text{ft}^2}$   $u_{\max} = 10 \frac{\text{ft}}{\text{s}}$   $R = 3 \cdot \text{in}$  Substituting these values:

$$F_{v\max} = -4 \times 2.1 \times 10^{-5} \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \times 10 \frac{\text{ft}}{\text{s}} \times \frac{1}{(3 \cdot \text{in})^2} \times \left( \frac{12 \cdot \text{in}}{\text{ft}} \right)^2 \quad F_{v\max} = -0.0134 \frac{\text{lb}}{\text{ft}^3}$$

## Problem 5.94

[Difficulty: 3]

**5.94** Assume the liquid film in Example 5.9 is horizontal (i.e.,  $\theta = 0^\circ$ ) and that the flow is driven by a constant shear stress on the top surface ( $y = h$ ),  $\tau_{yx} = C$ . Assume that the liquid film is thin enough and flat and that the flow is fully developed with zero net flow rate (flow rate  $Q = 0$ ). Determine the velocity profile  $u(y)$  and the pressure gradient  $dp/dx$ .



**Given:** Horizontal, fully developed flow

**Find:** Velocity Profile and pressure gradient

**Solution:**

**Governing Equations:**

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad (\text{Continuity Equation})$$

$$\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial P}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right)$$

$$\rho \left( \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) = \rho g_y - \frac{\partial P}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} + \frac{\partial^2 v}{\partial z^2} \right) \quad (\text{Navier-Stokes Equations})$$

$$\rho \left( \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) = \rho g_z - \frac{\partial P}{\partial z} + \mu \left( \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} \right)$$

**Assumptions:** (1) Incompressible fluid  
(2) Zero net flow rate

For fully developed flow

$$\frac{d^2 u}{dy^2} = \frac{1}{\mu} \frac{dp}{dx} \quad (1)$$

The general solution for equation (1) is

$$u = \frac{y^2}{2\mu} \frac{dp}{dx} + C_1 y + C_2 \quad (2)$$

where  $C_1$  and  $C_2$  are constants.

Apply the boundary conditions

$$u = 0 \text{ at } y = 0$$

$$\mu \frac{du}{dy} = C \text{ at } y = h$$

Then, we can get  $C_1 = \frac{1}{\mu} (C - h \frac{dp}{dx})$  and  $C_2 = 0$

$$u = -\frac{h^2}{\mu} \frac{dp}{dx} \left( y' - \frac{1}{2} y'^2 \right) + \frac{Ch}{\mu} y', \text{ where } y' = \frac{y}{h}$$

The net flow or flow rate is zero:


$$0 = -\frac{h^2}{\mu} \frac{dp}{dx} \int_0^l (y' - \frac{1}{2} y'^2) dy + \frac{Ch}{\mu} \int_0^l y' dy$$

Thus,  $\frac{dp}{dx} = \frac{3C}{2h}$

## Problem 5.95

[Difficulty: 3]

**5.95** Consider a planar microchannel of width  $h$ , as shown (it is actually very long in the  $x$  direction and open at both ends). A Cartesian coordinate system with its origin positioned at the center of the microchannel is used in the study. The microchannel is filled with a weakly conductive solution. When an electric current is applied across the two conductive walls, the current density,  $\vec{J}$ , transmitted through the solution is parallel to the  $y$  axis. The entire device is placed in a constant magnetic field,  $\vec{B}$ , which is pointed outward from the plane (the  $z$  direction), as shown. Interaction between the current density and the magnetic field induces a *Lorentz force* of density  $\vec{J} \times \vec{B}$ . Assume that the conductive solution is incompressible, and since the sample volume is very small in lab-on-a-chip applications, the gravitational body force is neglected. Under steady state, the flow driven by the Lorentz force is described by the continuity (Eq. 5.1a) and Navier–Stokes equations (Eqs. 5.27), except the  $x$ ,  $y$ , and  $z$  components of the latter have extra Lorentz force components on the right. Assuming that the flow is fully developed and the velocity field  $\vec{V}$  is a function of  $y$  only, find the three components of velocity.



**Given:** N-S equations and simplification assumptions

**Find:** Fluid Velocity

**Solution:**

**Governing Equations:**  $\nabla \cdot \mathbf{u} = 0$  (Continuity Equation)  
 $\rho \mathbf{u} \cdot \nabla \mathbf{u} = -\nabla p + \mu \nabla^2 \mathbf{u} + \mathbf{J} \times \mathbf{B}$  (Momentum Equation)

**Assumptions:** (1) Incompressible fluid  
 (2) Two dimensional, fully developed flow driven by Lorentz force  
 (2) Zero pressure gradient

Write the 2D continuity and momentum equations in Cartesian coordinates:

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0 \quad (1)$$

$$\rho \left( u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} \right) = -\frac{\partial p}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} \right) + JB \quad (2)$$

$$\rho(u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y}) = -\frac{\partial p}{\partial y} + \mu(\frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2}) \quad (3)$$

Simplify the above equations:

$$v = 0 \rightarrow \frac{\partial u}{\partial x} = 0 \rightarrow u = u(y)$$

Using the assumption of zero pressure gradient, equation (3) vanishes, and equation (2) can be simplified as

$$0 = \mu \frac{d^2 u}{dy^2} + JB \quad (4)$$

General solution for equation (4) is

$$u = -\frac{1}{2} \frac{JB}{\mu} y^2 + C_1 y + C_2 \quad (5)$$

Apply the no slip boundary conditions into equation (5), we get

$$\begin{cases} u(-\frac{h}{2}) = 0 = -\frac{1}{2} \frac{JB}{\mu} \frac{h^2}{4} - C_1 \frac{h}{2} + C_2 \\ u(\frac{h}{2}) = 0 = -\frac{1}{2} \frac{JB}{\mu} \frac{h^2}{4} + C_1 \frac{h}{2} + C_2 \end{cases}$$

Therefore,  $C_1=0$  and  $C_2 = \frac{JB}{8\mu} h^2$

The fluid velocity is given as

$$u(y) = \frac{JB}{8\mu} (h^2 - 4y^2)$$


## Problem 5.96

[Difficulty: 2]

**5.96** The common thermal polymerase chain reaction (PCR) process requires the cycling of reagents through three distinct temperatures for denaturation (90–94°C), annealing (50–55°C), and extension (72°C). In continuous-flow PCR reactors, the temperatures of the three thermal zones are maintained as fixed while the reagents are cycled continuously through these zones. These temperature variations induce significant variations in the fluid density, which under appropriate conditions can be used to generate fluid motion. The figure depicts a thermosiphon-based PCR device (Chen et al., 2004, *Analytical Chemistry*, 76, 3707–3715).

The closed loop is filled with PCR reagents. The plan of the loop is inclined at an angle  $\alpha$  with respect to the vertical. The loop is surrounded by three heaters and coolers that maintain different temperatures.

- Explain why the fluid automatically circulates in the closed loop along the counterclockwise direction.
- What is the effect of the angle  $\alpha$  on the fluid velocity?



**Given:** Temperature-dependent fluid density and the Navier-Stokes equations

**Find:** Explanation for the buoyancy-driven flow; effect of angle on fluid velocity

**Solution:**

**Governing Equations:**

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad (\text{Continuity Equation})$$

$$\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial P}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right)$$

$$\rho \left( \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) = \rho g_y - \frac{\partial P}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} + \frac{\partial^2 v}{\partial z^2} \right) \quad (\text{Navier-Stokes Equations})$$

$$\rho \left( \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) = \rho g_z - \frac{\partial P}{\partial z} + \mu \left( \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} \right)$$

**Assumption:** Incompressible fluid


- The first term in the right-hand-side of the momentum equations (5.27a)-(5.27c) represents the gravitational body force, which is proportional to the local fluid density. The fluid density in the region at temperature 72°C is higher than that in the region at temperature 90–94 °C, and meanwhile is lower than that in the region at temperature 50–55 °C. Thus, the net gravitational force induces counterclockwise fluid circulation within the loop.
- Since the fluid circulation is driven by buoyancy force which is proportional to  $g \times \cos \alpha$  where  $g$  is the gravitational acceleration, one can control the flow rate in the loop by adjusting the inclination angle  $\alpha$ . When the angle  $\alpha = 90^\circ$ , there is no fluid motion. When  $\alpha = 0$ , the flow rate is the maximum.

## Problem 5.97

[Difficulty: 3]

**5.97** Electro-osmotic flow (EOF) is the motion of liquid induced by an applied electric field across a charged capillary tube or microchannel. Assume the channel wall is negatively charged, a thin layer called the electric double layer (EDL) forms in the vicinity of the channel wall in which the number of positive ions is much larger than that of the negative ions. The net positively charged ions in the EDL then drag the electrolyte solution along with them and cause the fluid to flow toward the cathode. The thickness of the EDL is typically on the order of 10 nm. When the channel dimensions are much larger than the thickness of EDL, there is a slip velocity,  $y = \frac{\varepsilon \zeta}{\mu} \vec{E}$ , on the channel wall, where  $\varepsilon$  is the fluid permittivity,

$\zeta$  is the negative surface electric potential,  $\vec{E}$  is the electric field intensity, and  $\mu$  is the fluid dynamic viscosity. Consider a microchannel formed by two parallel plates. The walls of the channel have a negative surface electric potential of  $\zeta$ . The microchannel is filled with an electrolyte solution, and the microchannel ends are subjected to an electric potential difference that gives rise to a uniform electric field strength of  $E$  along the  $x$  direction. The pressure gradient in the channel is zero. Derive the velocity of the steady, fully developed electro-osmotic flow. Compare the velocity profile of the EOF to that of pressure-driven flow. Calculate the EOF velocity using  $\varepsilon = 7.08 \times 10^{-10} \text{ C}\cdot\text{V}^{-1}\text{m}^{-1}$ ,  $\zeta = -0.1 \text{ V}$ ,  $\mu = 10^{-3} \text{ Pa}\cdot\text{s}$ , and  $E = 1000 \text{ V/m}$ .



**Given:** N-S equations

**Find:** Fluid velocity

**Solution:**

**Governing Equations:**  $\nabla \cdot \mathbf{u} = 0$  (Continuity equation)  
 $\rho \mathbf{u} \cdot \nabla \mathbf{u} = -\nabla p + \mu \nabla^2 \mathbf{u}$  (Momentum equation)

**Assumptions:** (1) Two-dimensional fully developed flow  
 (2) Zero pressure gradient

(1) Write the continuity and momentum equations in Cartesian form:

$$\begin{cases} \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0 & (1) \\ \rho \left( u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} \right) = -\frac{\partial p}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} \right) & (2) \\ \rho \left( u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} \right) = -\frac{\partial p}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} \right) & (3) \end{cases}$$

Simplify the above equations:

$$v = 0 \rightarrow \frac{\partial u}{\partial x} = 0 \rightarrow u = u(y)$$

Using the assumption of zero pressure gradient, equation (3) vanishes, and equation (2) can be simplified as

$$0 = \mu \frac{d^2 u}{dy^2} \quad (4)$$

General solution for equation (4) is given as

$$u = C_1 y + C_2 \quad (5)$$

Apply the boundary condition into equation (5), we get

$$\begin{cases} u(-\frac{h}{2}) = -\frac{\varepsilon \zeta}{\mu} E = -C_1 \frac{h}{2} + C_2 \\ u(\frac{h}{2}) = -\frac{\varepsilon \zeta}{\mu} E = C_1 \frac{h}{2} + C_2 \end{cases}$$

Therefore,  $C_1=0$  and  $C_2 = -\frac{\varepsilon \zeta}{\mu} E$

The fluid velocity is given as

$$u(y) = -\frac{\varepsilon \zeta}{\mu} E \quad (6)$$

(2) Pressure-driven flow has a parabolic flow velocity profile; while EOF has a plug velocity profile and it is independent of the channel size.

(3) Substituting  $\varepsilon=7.08 \times 10^{-10} \text{ CV}^{-1} \text{ m}^{-1}$ ,  $\zeta=-0.1 \text{ V}$ ,  $\mu=10^{-3} \text{ Pa.s}$ , and  $E=1000 \text{ V/m}$  into equation (6), one obtains

$$\begin{aligned} u(y) &= -\frac{7.08 \times 10^{-10} \text{ C} \cdot \text{V}^{-1} \cdot \text{m}^{-1} \times -0.1 \text{ V}}{10^{-3} \text{ Pa} \cdot \text{s}} \times 1000 \text{ V/m} \\ &= 70.8 \times 10^{-6} \frac{\text{C} \cdot \text{V}}{\text{Pa} \cdot \text{s} \cdot \text{m}^2} = 70.8 \times 10^{-6} \frac{\text{N}}{\text{Pa} \cdot \text{s} \cdot \text{m}} = 70.8 \times 10^{-6} \text{ m/s} \end{aligned}$$

**Problem 5.98**

[Difficulty: 3]


**5.98** A tank contains water (20°C) at an initial depth  $y_0 = 1$  m. The tank diameter is  $D = 250$  mm, and a tube of diameter  $d = 3$  mm and length  $L = 4$  m is attached to the bottom of the tank. For laminar flow a reasonable model for the water level over time is

$$\frac{dy}{dt} = -\frac{d^4 \rho g}{32D^2 \mu L} y \quad y(0) = y_0$$

Using Euler methods with time steps of 12 min and 6 min:  
 (a) Estimate the water depth after 120 min, and compute the errors compared to the exact solution

$$y_{\text{exact}}(t) = y_0 e^{-\frac{d^4 \rho g}{32D^2 \mu L} t}$$

(b) Plot the Euler and exact results.



$d = 3$  mm  
 $D = 250$  mm  
 $y_0 = 1$  m  
 $L = 4$  m

$\rho = 999$  kg/m<sup>3</sup>  
 $\mu = 0.001$  N s/m<sup>2</sup>

$h = 12$  min                       $h = 6$  min

$$\frac{dy}{dt} = -\frac{d^4 \rho g}{32D^2 \mu L} y \quad y(0) = y_0$$

$$y_{\text{Exact}}(t) = y_0 e^{-\frac{d^4 \rho g}{32D^2 \mu L} t}$$

$$y_{n+1} = y_n + hky_n \quad k = -\frac{d^4 \rho g}{32D^2 \mu L} \quad t_{n+1} = t_n + h$$


$$k = 0.000099 \text{ s}^{-1}$$

$n$	$t_n$ (min)	$y_n$ (m)
0	0	1
1	12	0.929
2	24	0.862
3	36	0.801
4	48	0.743
5	60	0.690
6	72	0.641
7	84	0.595
8	96	0.553
9	108	0.513
10	120	0.477

Error:

$n$	$t_n$ (min)	$y_n$ (m)	$y_{\text{Exact}}(m)$
0	0.0	1	1
1	6.0	0.964	0.965
2	12.0	0.930	0.931
3	18.0	0.897	0.898
4	24.0	0.865	0.867
5	30.0	0.834	0.836
6	36.0	0.804	0.807
7	42.0	0.775	0.779
8	48.0	0.748	0.751
9	54.0	0.721	0.725
10	60.0	0.695	0.700
11	66.0	0.670	0.675
12	72.0	0.646	0.651
13	78.0	0.623	0.629
14	84.0	0.601	0.606
15	90.0	0.579	0.585
16	96.0	0.559	0.565
17	102.0	0.539	0.545
18	108.0	0.520	0.526
19	114.0	0.501	0.507
20	120.0	0.483	0.489

Error:



**Problem 5.99**

[Difficulty: 3]

**5.99** Use the Euler method to solve and plot

$$\frac{dy}{dx} = \cos(x) \quad y(0) = 0$$

from  $x = 0$  to  $x = \pi/2$ , using step sizes of  $\pi/48$ ,  $\pi/96$ , and  $\pi/144$ . Also plot the exact solution,


$$y(x) = \sin(x)$$

and compute the errors at  $x = \pi/2$  for the three Euler method solutions.

$$y_{n+1} = y_n + \Delta x \cos(x_n) \quad x_{n+1} = x_n + \Delta x$$

$\Delta x$ 0.06545			$\Delta x$ 0.032725			$\Delta x$ 0.021817			
$n$	$x$	$y$	$n$	$x$	$y$	$n$	$x$	$y$	$y_{\text{Exact}}$
0	0.000	0.000	0	0.000	0.000	0	0.000	0.000	0.000
1	0.065	0.065	1	0.033	0.033	1	0.022	0.022	0.022
2	0.131	0.131	2	0.065	0.065	2	0.044	0.044	0.044
3	0.196	0.196	3	0.098	0.098	3	0.065	0.065	0.065
4	0.262	0.260	4	0.131	0.131	4	0.087	0.087	0.087
5	0.327	0.323	5	0.164	0.163	5	0.109	0.109	0.109
6	0.393	0.385	6	0.196	0.195	6	0.131	0.131	0.131
7	0.458	0.446	7	0.229	0.227	7	0.153	0.152	0.152
8	0.524	0.504	8	0.262	0.259	8	0.175	0.174	0.174
9	0.589	0.561	9	0.295	0.291	9	0.196	0.195	0.195
10	0.654	0.615	10	0.327	0.322	10	0.218	0.217	0.216
11	0.720	0.667	11	0.360	0.353	11	0.240	0.238	0.238
12	0.785	0.716	12	0.393	0.384	12	0.262	0.259	0.259
13	0.851	0.763	13	0.425	0.414	13	0.284	0.280	0.280
14	0.916	0.806	14	0.458	0.444	14	0.305	0.301	0.301
15	0.982	0.846	15	0.491	0.473	15	0.327	0.322	0.321
16	1.047	0.882	16	0.524	0.502	16	0.349	0.343	0.342
17	1.113	0.915	17	0.556	0.530	17	0.371	0.363	0.362
18	1.178	0.944	18	0.589	0.558	18	0.393	0.383	0.383
19	1.244	0.969	19	0.622	0.585	19	0.415	0.404	0.403
20	1.309	0.990	20	0.654	0.612	20	0.436	0.424	0.423
21	1.374	1.007	21	0.687	0.638	21	0.458	0.443	0.442
22	1.440	1.020	22	0.720	0.663	22	0.480	0.463	0.462
23	1.505	1.028	23	0.753	0.688	23	0.502	0.482	0.481
24	1.571	1.032	24	0.785	0.712	24	0.524	0.501	0.500
			25	0.818	0.735	25	0.545	0.520	0.519
			26	0.851	0.757	26	0.567	0.539	0.537
			27	0.884	0.779	27	0.589	0.557	0.556

**Error 3.24%**



**Error 1.63%**

55	1.200	0.939	0.932
56	1.222	0.947	0.940
57	1.244	0.954	0.947
58	1.265	0.961	0.954
59	1.287	0.968	0.960
60	1.309	0.974	0.966
61	1.331	0.980	0.971
62	1.353	0.985	0.976
63	1.374	0.990	0.981
64	1.396	0.994	0.985
65	1.418	0.998	0.988
66	1.440	1.001	0.991
67	1.462	1.004	0.994
68	1.484	1.006	0.996
69	1.505	1.008	0.998
70	1.527	1.009	0.999
71	1.549	1.010	1.000
72	1.571	1.011	1.000

**Error 1.09%**

## Problem 5.100

[Difficulty: 3]

**\*5.100** Use *Excel* to generate the solution of Eq. 5.31 for  $m = 1$  shown in Fig. 5.18. To do so, you need to learn how to perform linear algebra in *Excel*. For example, for  $N = 4$  you will end up with the matrix equation of Eq. 5.37. To solve this equation for the  $u$  values, you will have to compute the inverse of the  $4 \times 4$  matrix, and then multiply this inverse into the  $4 \times 1$  matrix on the right of the equation. In *Excel*, to do *array operations*, you must use the following rules: Pre-select the cells that will contain the result; use the appropriate *Excel array function* (look at *Excel's Help* for details); press **Ctrl+Shift+Enter**, not just **Enter**. For example, to invert the  $4 \times 4$  matrix you would: Pre-select a blank  $4 \times 4$  array that will contain the inverse matrix; type =*minverse*([array containing matrix to be inverted]); press **Ctrl+Shift+Enter**. To multiply a  $4 \times 4$  matrix into a  $4 \times 1$  matrix you would: Pre-select a blank  $4 \times 1$  array that will contain the result; type =*mmult*([array containing  $4 \times 4$  matrix], [array containing  $4 \times 1$  matrix]); press **Ctrl+Shift+Enter**.

$$\frac{du}{dx} + u^m = 0; \quad 0 \leq x \leq 1; \quad u(0) = 1$$

$N = 4$   
 $\Delta x = 0.333$

Eq. 5.34 (LHS)	(RHS)
1.000    0.000    0.000    0.000	1
-1.000    1.333    0.000    0.000	0
0.000    -1.000    1.333    0.000	0
0.000    0.000    -1.000    1.333	0

$x$	Inverse Matrix	Result	Exact	Error
0.000	1.000    0.000    0.000    0.000	1.000	1.000	0.000
0.333	0.750    0.750    0.000    0.000	0.750	0.717	0.000
0.667	0.563    0.563    0.750    0.000	0.563	0.513	0.001
1.000	0.422    0.422    0.563    0.750	0.422	0.368	0.001
				<b>0.040</b>

$N = 8$   
 $\Delta x = 0.143$

Eq. 5.34 (LHS)

1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
-1.000	1.143	0.000	0.000	0.000	0.000	0.000	0.000	0.000
0.000	-1.000	1.143	0.000	0.000	0.000	0.000	0.000	0.000
0.000	0.000	-1.000	1.143	0.000	0.000	0.000	0.000	0.000
0.000	0.000	0.000	-1.000	1.143	0.000	0.000	0.000	0.000
0.000	0.000	0.000	0.000	-1.000	1.143	0.000	0.000	0.000
0.000	0.000	0.000	0.000	0.000	-1.000	1.143	0.000	0.000
0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.143	0.000

(RHS)

1
0
0
0
0
0
0
0

Inverse Matrix

$x$	1	2	3	4	5	6	7	8	Result	Exact	Error
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.000	1.000	0.000
0.143	0.875	0.875	0.000	0.000	0.000	0.000	0.000	0.000	0.875	0.867	0.000
0.286	0.766	0.766	0.875	0.000	0.000	0.000	0.000	0.000	0.766	0.751	0.000
0.429	0.670	0.670	0.766	0.875	0.000	0.000	0.000	0.000	0.670	0.651	0.000
0.571	0.586	0.586	0.670	0.766	0.875	0.000	0.000	0.000	0.586	0.565	0.000
0.714	0.513	0.513	0.586	0.670	0.766	0.875	0.000	0.000	0.513	0.490	0.000
0.857	0.449	0.449	0.513	0.586	0.670	0.766	0.875	0.000	0.449	0.424	0.000
1.000	0.393	0.393	0.449	0.513	0.586	0.670	0.766	0.875	0.393	0.368	0.000

**0.019**

$N = 16$

$\Delta x = 0.067$  Eq. 5.34 (LHS)

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	(RHS)
1	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1
2	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
3	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
4	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
5	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
6	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
7	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
8	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
9	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
10	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0
11	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0
12	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0
13	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0
14	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0
15	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0
16	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0

$x$	Inverse Matrix																Result	Exact	Error	
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.000	1.000	0.000
0.067	0.938	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.938	0.936	0.000
0.133	0.879	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.879	0.875	0.000
0.200	0.824	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.824	0.819	0.000
0.267	0.772	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.772	0.766	0.000
0.333	0.724	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.724	0.717	0.000
0.400	0.679	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.679	0.670	0.000
0.467	0.637	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.637	0.627	0.000
0.533	0.597	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.597	0.587	0.000
0.600	0.559	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.559	0.549	0.000
0.667	0.524	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.524	0.513	0.000
0.733	0.492	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.492	0.480	0.000
0.800	0.461	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.461	0.449	0.000
0.867	0.432	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.432	0.420	0.000
0.933	0.405	0.405	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.405	0.393	0.000
1.000	0.380	0.380	0.405	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.380	0.368	0.000

**0.009**

$N$	$\Delta x$	Error
4	0.333	0.040
8	0.143	0.019
16	0.067	0.009

## Problem 5.101

[Difficulty: 3]

**\*5.101** Following the steps to convert the differential equation Eq. 5.31 (for  $m=1$ ) into a difference equation (for example, Eq. 5.37 for  $N=4$ ), solve

$$\frac{du}{dx} + u = 2\cos(2x) \quad 0 \leq x \leq 1 \quad u(0) = 0$$

for  $N=4, 8,$  and  $16$  and compare to the exact solution

$$u_{\text{exact}} = \frac{2}{5}\cos(2x) + \frac{4}{5}\sin(2x) - \frac{2}{5}e^{-x}$$

*Hints:* Follow the rules for *Excel* array operations as described in Problem 5.100. Only the right side of the difference equations will change, compared to the solution method of Eq. 5.31 (for example, only the right side of Eq. 5.37 needs modifying).

New Eq. 5.37:  $-u_{i-1} + (1 + \Delta x)u_i = 2\Delta x \cdot \cos(2x_i)$

$N = 4$   
 $\Delta x = 0.333$

Eq. 5.34 (LHS)					(RHS)
1.000	0.000	0.000	0.000	0.000	0
-1.000	1.333	0.000	0.000	0.000	0.52392
0.000	-1.000	1.333	0.000	0.000	0.15683
0.000	0.000	-1.000	1.333	0.000	-0.2774

$x$	Inverse Matrix					Result	Exact	Error
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	
0.333	0.750	0.750	0.000	0.000	0.393	0.522	0.004	
0.667	0.563	0.563	0.750	0.000	0.412	0.666	0.016	
1.000	0.422	0.422	0.563	0.750	0.101	0.414	0.024	
<b>0.212</b>								

$N = 8$   
 $\Delta x = 0.143$

Eq. 5.34 (LHS)									(RHS)
1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
-1.000	1.143	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.27413
0.000	-1.000	1.143	0.000	0.000	0.000	0.000	0.000	0.000	0.24032
0.000	0.000	-1.000	1.143	0.000	0.000	0.000	0.000	0.000	0.18703
0.000	0.000	0.000	-1.000	1.143	0.000	0.000	0.000	0.000	0.11857
0.000	0.000	0.000	0.000	-1.000	1.143	0.000	0.000	0.000	0.0405
0.000	0.000	0.000	0.000	0.000	-1.000	1.143	0.000	0.000	-0.0409
0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.143	0.000	-0.1189

$x$	Inverse Matrix								Result	Exact	Error
	1	2	3	4	5	6	7	8			
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
0.143	0.875	0.875	0.000	0.000	0.000	0.000	0.000	0.000	0.240	0.263	0.000
0.286	0.766	0.766	0.875	0.000	0.000	0.000	0.000	0.000	0.420	0.469	0.000
0.429	0.670	0.670	0.766	0.875	0.000	0.000	0.000	0.000	0.531	0.606	0.001
0.571	0.586	0.586	0.670	0.766	0.875	0.000	0.000	0.000	0.569	0.668	0.001
0.714	0.513	0.513	0.586	0.670	0.766	0.875	0.000	0.000	0.533	0.653	0.002
0.857	0.449	0.449	0.513	0.586	0.670	0.766	0.875	0.000	0.431	0.565	0.002
1.000	0.393	0.393	0.449	0.513	0.586	0.670	0.766	0.875	0.273	0.414	0.002
											<b>0.094</b>

$N = 16$

$\Delta x = 0.067$  Eq. 5.34 (LHS)

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	(RHS)
<b>1</b>	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>2</b>	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.13215
<b>3</b>	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.12862
<b>4</b>	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.12281
<b>5</b>	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.11482
<b>6</b>	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.10478
<b>7</b>	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.09289
<b>8</b>	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.07935
<b>9</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.06441
<b>10</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.04831
<b>11</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.03137
<b>12</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.01386
<b>13</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	-0.0039
<b>14</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	-0.0216
<b>15</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	-0.0389
<b>16</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	-0.0555

$x$	Inverse Matrix																Result	Exact	Error	
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
0.067	0.938	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.124	0.129	0.000
0.133	0.879	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.237	0.247	0.000
0.200	0.824	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.337	0.352	0.000
0.267	0.772	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.424	0.445	0.000
0.333	0.724	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.495	0.522	0.000
0.400	0.679	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.552	0.584	0.000
0.467	0.637	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.591	0.630	0.000
0.533	0.597	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.615	0.659	0.000
0.600	0.559	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.622	0.671	0.000
0.667	0.524	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.612	0.666	0.000
0.733	0.492	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.587	0.645	0.000
0.800	0.461	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.547	0.608	0.000
0.867	0.432	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.492	0.557	0.000
0.933	0.405	0.405	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.425	0.491	0.000
1.000	0.380	0.380	0.405	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.346	0.414	0.000

**0.044**

$N$	$\Delta x$	Error
4	0.333	0.212
8	0.143	0.094
16	0.067	0.044

## Problem 5.102

[Difficulty: 3]

**\*5.102** Following the steps to convert the differential equation Eq. 5.31 (for  $m = 1$ ) into a difference equation (for example, Eq. 5.37 for  $N = 4$ ), solve

$$\frac{du}{dx} + u = 2x^2 + x \quad 0 \leq x \leq 1 \quad u(0) = 3$$

for  $N = 4, 8,$  and  $16$  and compare to the exact solution

$$u_{\text{exact}} = 2x^2 - 3x + 3$$

$$\text{New Eq. 5.37: } -u_{i-1} + (1 + \Delta x)u_i = \Delta x \cdot (2x_i^2 + x_i)$$

*Hint:* Follow the hints provided in Problem 5.101.

$N = 4$

$\Delta x = 0.333$

	Eq. 5.34 (LHS)				(RHS)			
	1.000	0.000	0.000	0.000	3			
	-1.000	1.333	0.000	0.000	0.18519			
	0.000	-1.000	1.333	0.000	0.51852			
	0.000	0.000	-1.000	1.333	1			
<b><math>x</math></b>	<b>Inverse Matrix</b>				<b>Result</b>	<b>Exact</b>	<b>Error</b>	
0.000	1.000	0.000	0.000	0.000	3.000	3.000	0.000	
0.333	0.750	0.750	0.000	0.000	2.389	2.222	0.007	
0.667	0.563	0.563	0.750	0.000	2.181	1.889	0.021	
1.000	0.422	0.422	0.563	0.750	2.385	2.000	0.037	<b>0.256</b>

$N = 8$

$\Delta x = 0.143$

	Eq. 5.34 (LHS)					(RHS)
	1.000	0.000	0.000	0.000	0.000	3
	-1.000	1.143	0.000	0.000	0.000	0.02624
	0.000	-1.000	1.143	0.000	0.000	0.06414
	0.000	0.000	-1.000	1.143	0.000	0.1137
	0.000	0.000	0.000	-1.000	1.143	0.17493
	0.000	0.000	0.000	0.000	-1.000	0.24781
	0.000	0.000	0.000	0.000	0.000	0.33236
	0.000	0.000	0.000	0.000	-1.000	0.42857

$x$	Inverse Matrix								Result	Exact	Error
	1	2	3	4	5	6	7	8			
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	3.000	3.000	0.000
0.143	0.875	0.875	0.000	0.000	0.000	0.000	0.000	0.000	2.648	2.612	0.000
0.286	0.766	0.766	0.875	0.000	0.000	0.000	0.000	0.000	2.373	2.306	0.001
0.429	0.670	0.670	0.766	0.875	0.000	0.000	0.000	0.000	2.176	2.082	0.001
0.571	0.586	0.586	0.670	0.766	0.875	0.000	0.000	0.000	2.057	1.939	0.002
0.714	0.513	0.513	0.586	0.670	0.766	0.875	0.000	0.000	2.017	1.878	0.002
0.857	0.449	0.449	0.513	0.586	0.670	0.766	0.875	0.000	2.055	1.898	0.003
1.000	0.393	0.393	0.449	0.513	0.586	0.670	0.766	0.875	2.174	2.000	0.004
											<b>0.113</b>

$N = 16$

$\Delta x = 0.067$  Eq. 5.34 (LHS)

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	(RHS)
<b>1</b>	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	3
<b>2</b>	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.00504
<b>3</b>	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.01126
<b>4</b>	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.01867
<b>5</b>	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.02726
<b>6</b>	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.03704
<b>7</b>	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.048
<b>8</b>	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.06015
<b>9</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.07348
<b>10</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.000	0.088
<b>11</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.000	0.1037
<b>12</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.000	0.12059
<b>13</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.000	0.13867
<b>14</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.000	0.15793
<b>15</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.000	0.17837
<b>16</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.067	0.2

$x$	Inverse Matrix																Result	Exact	Error	
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	3.000	3.000	0.000
0.067	0.938	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.817	2.809	0.000
0.133	0.879	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.652	2.636	0.000
0.200	0.824	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.503	2.480	0.000
0.267	0.772	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.373	2.342	0.000
0.333	0.724	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.259	2.222	0.000
0.400	0.679	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.163	2.120	0.000
0.467	0.637	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.084	2.036	0.000
0.533	0.597	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	2.023	1.969	0.000
0.600	0.559	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.979	1.920	0.000
0.667	0.524	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	0.000	1.952	1.889	0.000
0.733	0.492	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	0.000	1.943	1.876	0.000
0.800	0.461	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	0.000	1.952	1.880	0.000
0.867	0.432	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	0.000	1.978	1.902	0.000
0.933	0.405	0.405	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	0.000	2.022	1.942	0.000
1.000	0.380	0.380	0.405	0.432	0.461	0.492	0.524	0.559	0.597	0.637	0.679	0.724	0.772	0.824	0.879	0.938	0.000	2.083	2.000	0.000

**0.054**

$N$	$\Delta x$	Error
4	0.333	0.256
8	0.143	0.113
16	0.067	0.054

## Problem 5.103

[Difficulty: 3]

**\*5.103** A 50-mm cube of mass  $M = 3$  kg is sliding across an oiled surface. The oil viscosity is  $\mu = 0.45$  N·s/m<sup>2</sup>, and the thickness of the oil between the cube and surface is  $\delta = 0.2$  mm. If the initial speed of the block is  $u_0 = 1$  m/s, use the numerical method that was applied to the linear form of Eq. 5.31 to predict the cube motion for the first second of motion. Use  $N = 4, 8,$  and  $16$  and compare to the exact solution

$$u_{\text{exact}} = u_0 e^{-(A\mu/M\delta)t}$$

where  $A$  is the area of contact. *Hint:* Follow the hints provided in Problem 5.101.

Equation of motion:  $M \frac{du}{dt} = -\mu \frac{du}{dy} A = -\mu A \frac{u}{\delta}$

$$\frac{du}{dt} + \left( \frac{\mu A}{M \delta} \right) u = 0$$

$$\frac{du}{dt} + k \cdot u = 0$$

New Eq. 5.37:  $-u_{i-1} + (1 + k \cdot \Delta t)u_i = 0$

$N = 4$   
 $\Delta t = 0.333$

$A = 0.0025$  m<sup>2</sup>  
 $\delta = 0.5$  mm  
 $\mu = 0.45$  N·s/m<sup>2</sup>  
 $M = 3$  kg  
 $k = 0.75$  s<sup>-1</sup>

Eq. 5.34 (LHS)					(RHS)
1.000	0.000	0.000	0.000	0.000	1
-1.000	1.250	0.000	0.000	0.000	0
0.000	-1.000	1.250	0.000	0.000	0
0.000	0.000	-1.000	1.250	0.000	0

$t$	Inverse Matrix					Result	Exact	Error
0.000	1.000	0.000	0.000	0.000	1.000	1.000	0.0E+00	
0.333	0.800	0.800	0.000	0.000	0.800	0.779	1.1E-04	
0.667	0.640	0.640	0.800	0.000	0.640	0.607	2.8E-04	
1.000	0.512	0.512	0.640	0.800	0.512	0.472	3.9E-04	
<b>0.028</b>								

$N = 8$   
 $\Delta t = 0.143$

Eq. 5.34 (LHS)									(RHS)
1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1
-1.000	1.107	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
0.000	-1.000	1.107	0.000	0.000	0.000	0.000	0.000	0.000	0
0.000	0.000	-1.000	1.107	0.000	0.000	0.000	0.000	0.000	0
0.000	0.000	0.000	-1.000	1.107	0.000	0.000	0.000	0.000	0
0.000	0.000	0.000	0.000	-1.000	1.107	0.000	0.000	0.000	0
0.000	0.000	0.000	0.000	0.000	-1.000	1.107	0.000	0.000	0
0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.107	0.000	0

$t$	Inverse Matrix								Result	Exact	Error
	1	2	3	4	5	6	7	8			
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.000	1.000	0.0E+00
0.143	0.903	0.903	0.000	0.000	0.000	0.000	0.000	0.000	0.903	0.898	2.9E-06
0.286	0.816	0.816	0.903	0.000	0.000	0.000	0.000	0.000	0.816	0.807	9.5E-06
0.429	0.737	0.737	0.816	0.903	0.000	0.000	0.000	0.000	0.737	0.725	1.7E-05
0.571	0.666	0.666	0.737	0.816	0.903	0.000	0.000	0.000	0.666	0.651	2.5E-05
0.714	0.601	0.601	0.666	0.737	0.816	0.903	0.000	0.000	0.601	0.585	3.2E-05
0.857	0.543	0.543	0.601	0.666	0.737	0.816	0.903	0.000	0.543	0.526	3.7E-05
1.000	0.490	0.490	0.543	0.601	0.666	0.737	0.816	0.903	0.490	0.472	4.1E-05

**0.013**

$N = 16$

$\Delta t = 0.067$  Eq. 5.34 (LHS)

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	(RHS)
<b>1</b>	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1
<b>2</b>	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>3</b>	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>4</b>	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>5</b>	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>6</b>	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>7</b>	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>8</b>	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>9</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>10</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0.000	0
<b>11</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0.000	0
<b>12</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0.000	0
<b>13</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0.000	0
<b>14</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0.000	0
<b>15</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0.000	0
<b>16</b>	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	-1.000	1.050	0

$t$	Inverse Matrix																Result	Exact	Error	
0.000	1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	1.000	1.000	0.0E+00
0.067	0.952	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.952	0.951	8.3E-08
0.133	0.907	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.907	0.905	3.0E-07
0.200	0.864	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.864	0.861	6.1E-07
0.267	0.823	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.823	0.819	9.9E-07
0.333	0.784	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.784	0.779	1.4E-06
0.400	0.746	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.746	0.741	1.8E-06
0.467	0.711	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.711	0.705	2.2E-06
0.533	0.677	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.677	0.670	2.7E-06
0.600	0.645	0.645	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.645	0.638	3.0E-06
0.667	0.614	0.614	0.645	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.000	0.614	0.607	3.4E-06
0.733	0.585	0.585	0.614	0.645	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.000	0.585	0.577	3.7E-06
0.800	0.557	0.557	0.585	0.614	0.645	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.000	0.557	0.549	4.0E-06
0.867	0.530	0.530	0.557	0.585	0.614	0.645	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.000	0.530	0.522	4.3E-06
0.933	0.505	0.505	0.530	0.557	0.585	0.614	0.645	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.000	0.505	0.497	4.5E-06
1.000	0.481	0.481	0.505	0.530	0.557	0.585	0.614	0.645	0.677	0.711	0.746	0.784	0.823	0.864	0.907	0.952	0.000	0.481	0.472	4.7E-06

**0.006**

$N$	$\Delta t$	Error
4	0.333	0.028
8	0.143	0.013
16	0.067	0.006

# Problem 5.104

[Difficulty: 3]

**\*5.104** Use *Excel* to generate the solutions of Eq. 5.31 for  $m = 2$ , as shown in Fig. 5.21.



$$u_i = \frac{u_{g_{i-1}} + \Delta x u_{g_i}^2}{1 + 2\Delta x u_{g_i}}$$

$\Delta x = 0.333$

Iteration	$x$			
	0.000	0.333	0.667	1.000
0	1.000	1.000	1.000	1.000
1	1.000	0.800	0.800	0.800
2	1.000	0.791	0.661	0.661
3	1.000	0.791	0.650	0.560
4	1.000	0.791	0.650	0.550
5	1.000	0.791	0.650	0.550
6	1.000	0.791	0.650	0.550
<b>Exact</b>	<b>1.000</b>	<b>0.750</b>	<b>0.600</b>	<b>0.500</b>

### Residuals

0.204  
0.127  
0.068  
0.007  
0.000  
0.000



**Problem 5.105**


[Difficulty: 3]

\*5.105 Use Excel to generate the solutions of Eq. 5.31 for  $m = 2$ , as shown in Fig. 5.21, except use 16 points and as many iterations as necessary to obtain reasonable convergence.

$$u_i = \frac{u_{g,i-1} + \Delta x u_{g,i}^2}{1 + 2\Delta x u_{g,i}}$$

$\Delta x = 0.0667$

Iteration	x															
	0.000	0.067	0.133	0.200	0.267	0.333	0.400	0.467	0.533	0.600	0.667	0.733	0.800	0.867	0.933	1.000
0	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000	1.000
1	1.000	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941	0.941
2	1.000	0.941	0.889	0.889	0.889	0.889	0.889	0.889	0.889	0.889	0.889	0.889	0.889	0.889	0.889	0.889
3	1.000	0.941	0.888	0.842	0.842	0.842	0.842	0.842	0.842	0.842	0.842	0.842	0.842	0.842	0.842	0.842
4	1.000	0.941	0.888	0.841	0.799	0.799	0.799	0.799	0.799	0.799	0.799	0.799	0.799	0.799	0.799	0.799
5	1.000	0.941	0.888	0.841	0.799	0.761	0.761	0.761	0.761	0.761	0.761	0.761	0.761	0.761	0.761	0.761
6	1.000	0.941	0.888	0.841	0.799	0.760	0.726	0.726	0.726	0.726	0.726	0.726	0.726	0.726	0.726	0.726
7	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.694	0.694	0.694	0.694	0.694	0.694	0.694	0.694	0.694
8	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.664	0.664	0.664	0.664	0.664	0.664	0.664
9	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.637	0.637	0.637	0.637	0.637	0.637
10	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.612	0.612	0.612	0.612	0.612
11	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.589	0.589	0.589	0.589
12	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.568	0.568	0.568	0.568
13	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.548	0.548	0.548
14	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.529
15	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.512
16	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
17	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
18	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
19	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
20	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
21	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
22	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
23	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
24	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
25	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
26	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
27	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
28	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
29	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
30	1.000	0.941	0.888	0.841	0.799	0.760	0.725	0.693	0.664	0.637	0.612	0.589	0.567	0.547	0.529	0.511
Exact	1.000	0.938	0.882	0.833	0.789	0.750	0.714	0.682	0.652	0.625	0.600	0.577	0.556	0.536	0.517	0.500



### Problem 5.106

[Difficulty: 3]

**\*5.106** Use *Excel* to generate the solutions of Eq. 5.31 for  $m = -1$ , with  $u(0) = 3$ , using 4 and 16 points over the interval from  $x = 0$  to  $x = 3$ , with sufficient iterations, and compare to the exact solution

$$u_{\text{exact}} = \sqrt{9 - 2x}$$

To do so, follow the steps described in “Dealing with Non-linearity” section.

$$\Delta u_i = u_i - u_{g_i}$$

$$\frac{1}{u_i} = \frac{1}{u_{g_i} + \Delta u_i} \approx \frac{1}{u_{g_i}} \left( 1 - \frac{\Delta u_i}{u_{g_i}} \right)$$

$$\frac{u_i - u_{i-1}}{\Delta x} + \frac{1}{u_i} = 0$$

$$\frac{u_i - u_{i-1}}{\Delta x} + \frac{1}{u_{g_i}} \left( 1 - \frac{u_i - u_{g_i}}{u_{g_i}} \right) = 0$$

$$\frac{u_i - u_{i-1}}{\Delta x} + \frac{1}{u_{g_i}} \left( 2 - \frac{u_i}{u_{g_i}} \right) = 0$$

$$u_i \left( 1 - \frac{\Delta x}{u_{g_i}^2} \right) = u_{i-1} - \frac{2\Delta x}{u_{g_i}}$$

$$u_i = \frac{u_{i-1} - \frac{2\Delta x}{u_{g_i}}}{1 - \frac{\Delta x}{u_{g_i}^2}}$$

$\Delta x = 1.500$

Iteration	x			
	0.000	1.500	3.000	4.500
0	3.000	3.000	3.000	3.000
1	3.000	2.400	2.400	2.400
2	3.000	2.366	1.555	1.555
3	3.000	2.366	1.151	-0.986
4	3.000	2.366	1.816	-7.737
5	3.000	2.366	1.310	2.260
6	3.000	2.366	0.601	-0.025
Exact	<b>3.000</b>	<b>2.449</b>	<b>1.732</b>	<b>0.000</b>



$\Delta x = 0.300$

Iteration	x															
	0.000	0.300	0.600	0.900	1.200	1.500	1.800	2.100	2.400	2.700	3.000	3.300	3.600	3.900	4.200	4.500
0	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000	3.000
1	3.000	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897	2.897
2	3.000	2.896	2.789	2.789	2.789	2.789	2.789	2.789	2.789	2.789	2.789	2.789	2.789	2.789	2.789	2.789
3	3.000	2.896	2.789	2.677	2.677	2.677	2.677	2.677	2.677	2.677	2.677	2.677	2.677	2.677	2.677	2.677
4	3.000	2.896	2.789	2.677	2.560	2.560	2.560	2.560	2.560	2.560	2.560	2.560	2.560	2.560	2.560	2.560
5	3.000	2.896	2.789	2.677	2.560	2.438	2.438	2.438	2.438	2.438	2.438	2.438	2.438	2.438	2.438	2.438
6	3.000	2.896	2.789	2.677	2.560	2.436	2.308	2.308	2.308	2.308	2.308	2.308	2.308	2.308	2.308	2.308
7	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.170	2.170	2.170	2.170	2.170	2.170	2.170	2.170	2.170
8	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.023	2.023	2.023	2.023	2.023	2.023	2.023	2.023
9	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.862	1.862	1.862	1.862	1.862	1.862	1.862
10	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.686	1.686	1.686	1.686	1.686	1.686
11	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.487	1.487	1.487	1.487	1.487
12	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.254	1.254	1.254	1.254
13	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.958	0.958	0.958
14	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.901	0.493	0.493
15	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	1.349	3.091
16	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.544	1.192
17	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	14.403	0.051
18	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.859	-0.024
19	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.338	-0.051

20	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.538	-0.105
21	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	5.953	-0.239
22	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.805	-1.998
23	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.286	1.195
24	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.450	-0.273
25	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.900	-0.876
26	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.369	2.601
27	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.605	0.145
28	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.517	0.266
29	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-17.059	0.858
30	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.935	-29.971
31	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.392	0.955
32	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.663	-0.352
33	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.020	-1.662
34	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.041	0.383
35	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.088	1.534
36	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.204	-0.549
37	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.621	198.629
38	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	8.435	-0.624
39	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.831	41.087
40	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.313	0.817
41	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.494	-0.765
42	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	1.379	2.623
43	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.551	1.203
44	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-16.722	0.066
45	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.936	0.377
46	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.392	0.591
47	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.664	-4.391
48	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.014	0.813
49	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.029	-1.376
50	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.061	0.483
51	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.135	4.578
52	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.347	-0.270
53	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-1.765	-0.603
54	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	1.371	-4.389
55	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.549	1.532
56	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-40.363	0.180
57	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.914	5.316
58	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.379	0.810
59	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	0.627	-0.668
60	3.000	2.896	2.789	2.677	2.560	2.436	2.306	2.168	2.019	1.858	1.679	1.476	1.233	0.899	-0.243	4.652

<b>Exact</b>	<b>3.000</b>	<b>2.898</b>	<b>2.793</b>	<b>2.683</b>	<b>2.569</b>	<b>2.449</b>	<b>2.324</b>	<b>2.191</b>	<b>2.049</b>	<b>1.897</b>	<b>1.732</b>	<b>1.549</b>	<b>1.342</b>	<b>1.095</b>	<b>0.775</b>	<b>0.000</b>
--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------	--------------

Here are graphs comparing the numerical and exact solutions.



### Problem 5.107

[Difficulty: 3]

**\*5.107** An environmental engineer drops a pollution measuring probe with a mass of 0.3 slugs into a fast moving river (the speed of the water is  $U = 25$  ft/s). The equation of motion for your speed  $u$  is

$$M \frac{du}{dt} = k(U - u)^2$$

where  $k = 0.02$  lbf·s<sup>2</sup>/ft<sup>2</sup> is a constant indicating the drag of the water. Use *Excel* to generate and plot the probe speed versus time (for the first 10 s) using the same approach as the solutions of Eq. 5.31 for  $m = 2$ , as shown in Fig 5.21, except use 16 points and as many iterations as necessary to obtain reasonable convergence. Compare your results to the exact solution

$$u_{\text{exact}} = \frac{kU^2 t}{M + kUt}$$

*Hint:* Use a substitution for  $(U - u)$  so that the equation of motion looks similar to Eq. 5.31.

$$\begin{aligned} M \frac{du}{dt} &= k(U - u)^2 & v_i^2 &\approx 2v_{g_i} v_i - v_{g_i}^2 \\ v &= U - u & \frac{v_i - v_{i-1}}{\Delta t} + \frac{k}{M} (2v_{g_i} v_i - v_{g_i}^2) &= 0 \\ dv &= -du & v_i &= \frac{v_{g_{i-1}} + \frac{k}{M} \Delta t v_{g_i}^2}{1 + 2 \frac{k}{M} \Delta t v_{g_i}} \\ -M \frac{dv}{dt} &= kv^2 & \frac{dv}{dt} + \frac{k}{M} v^2 &= 0 \end{aligned}$$


$\Delta t = 1.000$        $k = 0.02$  lbf·s<sup>2</sup>/ft<sup>2</sup>  
 $M = 0.3$  slug

Iteration	$t$															
	0.000	1.000	2.000	3.000	4.000	5.000	6.000	7.000	8.000	9.000	10.000	11.000	12.000	13.000	14.000	15.000
0	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000	25.000
1	25.000	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385	15.385
2	25.000	13.365	10.213	10.213	10.213	10.213	10.213	10.213	10.213	10.213	10.213	10.213	10.213	10.213	10.213	10.213
3	25.000	13.267	8.603	7.269	7.269	7.269	7.269	7.269	7.269	7.269	7.269	7.269	7.269	7.269	7.269	7.269
4	25.000	13.267	8.477	6.158	5.480	5.480	5.480	5.480	5.480	5.480	5.480	5.480	5.480	5.480	5.480	5.480
5	25.000	13.267	8.476	6.043	4.715	4.323	4.323	4.323	4.323	4.323	4.323	4.323	4.323	4.323	4.323	4.323
6	25.000	13.267	8.476	6.042	4.621	3.781	3.533	3.533	3.533	3.533	3.533	3.533	3.533	3.533	3.533	3.533
7	25.000	13.267	8.476	6.042	4.620	3.706	3.136	2.967	2.967	2.967	2.967	2.967	2.967	2.967	2.967	2.967
8	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.668	2.547	2.547	2.547	2.547	2.547	2.547	2.547	2.547
9	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.314	2.224	2.224	2.224	2.224	2.224	2.224	2.224
10	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.274	2.039	1.970	1.970	1.970	1.970	1.970	1.970
11	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.006	1.820	1.765	1.765	1.765	1.765	1.765
12	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.792	1.641	1.597	1.597	1.597	1.597
13	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.493	1.457	1.457	1.457
14	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.473	1.369	1.338	1.338
15	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.263	1.237
16	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.172
17	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
18	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
19	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
20	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
21	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
22	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
23	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
24	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
25	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
26	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
27	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
28	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158

29	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
30	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
31	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
32	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
33	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
34	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
35	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
36	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
37	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
38	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
39	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158
40	25.000	13.267	8.476	6.042	4.620	3.705	3.075	2.618	2.273	2.005	1.791	1.617	1.472	1.351	1.247	1.158

Above values are for  $v!$  To get  $u$  we compute  $u = U - v$

Iteration																
10	0.000	11.733	16.524	18.958	20.380	21.295	21.925	22.382	22.726	22.961	23.030	23.030	23.030	23.030	23.030	23.030
20	0.000	11.733	16.524	18.958	20.380	21.295	21.925	22.382	22.727	22.995	23.209	23.383	23.528	23.649	23.753	23.842
40	0.000	11.733	16.524	18.958	20.380	21.295	21.925	22.382	22.727	22.995	23.209	23.383	23.528	23.649	23.753	23.842
<b>Exact</b>	<b>0.000</b>	<b>15.625</b>	<b>19.231</b>	<b>20.833</b>	<b>21.739</b>	<b>22.321</b>	<b>22.727</b>	<b>23.026</b>	<b>23.256</b>	<b>23.438</b>	<b>23.585</b>	<b>23.707</b>	<b>23.810</b>	<b>23.897</b>	<b>23.973</b>	<b>24.038</b>



## Problem 6.1

[Difficulty: 2]

**6.1** Consider the flow field with velocity given by  $\vec{V} = [A(y^2 - x^2) - Bx]\hat{i} + [2Axy + By]\hat{j}$ ;  $A = 1 \text{ ft}^{-1} \cdot \text{s}^{-1}$ ,  $B = 1 \text{ ft}^{-1} \cdot \text{s}^{-1}$ ; the coordinates are measured in feet. The density is  $2 \text{ slug/ft}^3$ , and gravity acts in the negative  $y$  direction. Calculate the acceleration of a fluid particle and the pressure gradient at point  $(x, y) = (1, 1)$ .

**Given:** Velocity field

**Find:** Acceleration of particle and pressure gradient at (1,1)

**Solution:**

NOTE: Units of B are  $\text{s}^{-1}$  not  $\text{ft}^{-1}\text{s}^{-1}$

Basic equations

$$\bar{a}_p = \frac{D\bar{V}}{Dt} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \frac{\partial \bar{V}}{\partial t}_{\text{local acceleration}} \quad \rho \frac{D\bar{V}}{Dt} = \rho \bar{g} - \nabla p$$

total acceleration of a particle

For this flow

$$u(x, y) = A \cdot (y^2 - x^2) - B \cdot x \quad v(x, y) = 2 \cdot A \cdot x \cdot y + B \cdot y$$

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = [A \cdot (y^2 - x^2) - B \cdot x] \cdot \frac{\partial}{\partial x} [A \cdot (y^2 - x^2) - B \cdot x] + (2 \cdot A \cdot x \cdot y + B \cdot y) \cdot \frac{\partial}{\partial y} [A \cdot (y^2 - x^2) - B \cdot x]$$

$$a_x = (B + 2 \cdot A \cdot x) \cdot (A \cdot x^2 + B \cdot x + A \cdot y^2)$$

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = [A \cdot (y^2 - x^2) - B \cdot x] \cdot \frac{\partial}{\partial x} (2 \cdot A \cdot x \cdot y + B \cdot y) + (2 \cdot A \cdot x \cdot y + B \cdot y) \cdot \frac{\partial}{\partial y} (2 \cdot A \cdot x \cdot y + B \cdot y)$$

$$a_y = (B + 2 \cdot A \cdot x) \cdot (B \cdot y + 2 \cdot A \cdot x \cdot y) - 2 \cdot A \cdot y \cdot [B \cdot x + A \cdot (x^2 - y^2)]$$

Hence at (1,1)

$$a_x = (1 + 2 \cdot 1 \cdot 1) \cdot \frac{1}{s} \times (1 \cdot 1^2 + 1 \cdot 1 + 1 \cdot 1^2) \cdot \frac{\text{ft}}{s} \quad a_x = 9 \cdot \frac{\text{ft}}{s^2}$$

$$a_y = (1 + 2 \cdot 1 \cdot 1) \cdot \frac{1}{s} \times (1 \cdot 1 + 2 \cdot 1 \cdot 1 \cdot 1) \cdot \frac{\text{ft}}{s} - 2 \cdot 1 \cdot 1 \cdot \frac{1}{s} \times [1 \cdot 1 + 1 \cdot (1^2 - 1^2)] \cdot \frac{\text{ft}}{s} \quad a_y = 7 \cdot \frac{\text{ft}}{s^2}$$

$$a = \sqrt{a_x^2 + a_y^2} \quad \theta = \text{atan} \left( \frac{a_y}{a_x} \right) \quad a = 11.4 \cdot \frac{\text{ft}}{s^2} \quad \theta = 37.9 \cdot \text{deg}$$

For the pressure gradient

$$\frac{\partial p}{\partial x} = \rho \cdot g_x - \rho \cdot a_x = -2 \cdot \frac{\text{slug}}{\text{ft}^3} \times 9 \cdot \frac{\text{ft}}{s^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad \frac{\partial p}{\partial x} = -18 \cdot \frac{\text{ft}^2}{\text{ft}} = -0.125 \cdot \frac{\text{psi}}{\text{ft}}$$

$$\frac{\partial p}{\partial y} = \rho \cdot g_y - \rho \cdot a_y = 2 \cdot \frac{\text{slug}}{\text{ft}^3} \times (-32.2 - 7) \cdot \frac{\text{ft}}{s^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad \frac{\partial p}{\partial y} = -78.4 \cdot \frac{\text{ft}^2}{\text{ft}} = -0.544 \cdot \frac{\text{psi}}{\text{ft}}$$

## Problem 6.2

[Difficulty: 2]

**6.2** An incompressible frictionless flow field is given by  $\vec{V} = (Ax + By)\hat{i} + (Bx - Ay)\hat{j}$ , where  $A = 2\text{ s}^{-1}$  and  $B = 3\text{ s}^{-1}$ , and the coordinates are measured in meters. Find the magnitude and direction of the acceleration of a fluid particle at point  $(x, y) = (2, 2)$ . Find the pressure gradient at the same point, if  $\vec{g} = -g\hat{j}$  and the fluid is water.

**Given:** Velocity field

**Find:** Acceleration of particle and pressure gradient at (2,2)

**Solution:**

Basic equations 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \frac{\partial \vec{V}}{\partial t}_{\text{local acceleration}} \quad \rho \frac{D\vec{V}}{Dt} = \rho \vec{g} - \nabla p$$

total acceleration of a particle

Given data 
$$A = 1 \cdot \frac{1}{\text{s}} \quad B = 3 \cdot \frac{1}{\text{s}} \quad x = 2 \cdot \text{m} \quad y = 2 \cdot \text{m} \quad \rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$$

For this flow 
$$u(x, y) = A \cdot x + B \cdot y \quad v(x, y) = B \cdot x - A \cdot y$$

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = (A \cdot x + B \cdot y) \cdot \frac{\partial}{\partial x} (A \cdot x + B \cdot y) + (B \cdot x - A \cdot y) \cdot \frac{\partial}{\partial y} (A \cdot x + B \cdot y) \quad a_x = (A^2 + B^2) \cdot x$$

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = (A \cdot x + B \cdot y) \cdot \frac{\partial}{\partial x} (B \cdot x - A \cdot y) + (B \cdot x - A \cdot y) \cdot \frac{\partial}{\partial y} (B \cdot x - A \cdot y) \quad a_y = (A^2 + B^2) \cdot y$$

Hence at (2,2) 
$$a_x = (1 + 9) \frac{1}{\text{s}} \times 2 \cdot \text{m} \quad a_x = 20 \frac{\text{m}}{\text{s}^2} \quad a_y = (1 + 9) \frac{1}{\text{s}} \times 2 \cdot \text{m} \quad a_y = 20 \frac{\text{m}}{\text{s}^2}$$

$$a = \sqrt{a_x^2 + a_y^2} \quad \theta = \text{atan} \left( \frac{a_y}{a_x} \right) \quad a = 28.28 \frac{\text{m}}{\text{s}^2} \quad \theta = 45 \cdot \text{deg}$$

For the pressure gradient

$$\frac{\partial}{\partial x} p = \rho \cdot g_x - \rho \cdot a_x = -999 \cdot \frac{\text{kg}}{\text{m}^3} \times 20 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \frac{\partial}{\partial x} p = -20000 \frac{\text{Pa}}{\text{m}} = -20.0 \frac{\text{kPa}}{\text{m}}$$

$$\frac{\partial}{\partial y} p = -\rho \cdot g_y - \rho \cdot a_y = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times (-9.81 - 20) \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \frac{\partial}{\partial y} p = -29800 \frac{\text{Pa}}{\text{m}} = -29.8 \frac{\text{kPa}}{\text{m}}$$

### Problem 6.3

[Difficulty: 2]

**6.3** A horizontal flow of water is described by the velocity field  $\vec{V} = (-Ax + Bt)\hat{i} + (Ay + Bt)\hat{j}$ , where  $A = 1 \text{ s}^{-1}$  and  $B = 2 \text{ m/s}^2$ ,  $x$  and  $y$  are in meters, and  $t$  is in seconds. Find expressions for the local acceleration, the convective acceleration, and the total acceleration. Evaluate these at point (1, 2) at  $t = 5$  seconds. Evaluate  $\nabla p$  at the same point and time.

**Given:** Velocity field

**Find:** Acceleration of particle and pressure gradient at (1,2)

**Solution:**

Basic equations

$$\bar{a}_p = \frac{D\bar{V}}{Dt} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \frac{\partial \bar{V}}{\partial t}_{\text{local acceleration}} \quad \rho \frac{D\bar{V}}{Dt} = \rho \bar{g} - \nabla p$$

total acceleration of a particle

Given data

$$A = 1 \cdot \frac{1}{\text{s}} \quad B = 2 \cdot \frac{\text{m}}{\text{s}^2} \quad x = 1 \cdot \text{m} \quad y = 2 \cdot \text{m} \quad t = 5 \cdot \text{s} \quad \rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$$

$$u(x, y, t) = -A \cdot x + B \cdot t \quad v(x, y, t) = A \cdot y + B \cdot t$$

The acceleration components and values are

$$a_{xt}(x, y, t) = \frac{\partial}{\partial t} u(x, y, t) = B \quad a_{xt}(x, y, t) = B \quad a_{xt}(x, y, t) = 2 \frac{\text{m}}{\text{s}^2}$$

$$a_{xc}(x, y, t) = u(x, y, t) \cdot \frac{\partial}{\partial x} u(x, y, t) + v(x, y, t) \cdot \frac{\partial}{\partial y} u(x, y, t) \quad a_{xc}(x, y, t) = A^2 \cdot x - A \cdot B \cdot t \quad a_{xc}(x, y, t) = -9 \frac{\text{m}}{\text{s}^2}$$

$$a_{yt}(x, y, t) = \frac{\partial}{\partial t} v(x, y, t) \quad a_{yt}(x, y, t) = B \quad a_{yt}(x, y, t) = 2 \frac{\text{m}}{\text{s}^2}$$

$$a_{yc}(x, y, t) = u(x, y, t) \cdot \frac{\partial}{\partial x} v(x, y, t) + v(x, y, t) \cdot \frac{\partial}{\partial y} v(x, y, t) \quad a_{yc}(x, y, t) = y \cdot A^2 + B \cdot t \cdot A \quad a_{yc}(x, y, t) = 12 \frac{\text{m}}{\text{s}^2}$$

$$a_x(x, y, t) = a_{xt}(x, y, t) + a_{xc}(x, y, t) \quad a_x(x, y, t) = x \cdot A^2 - B \cdot t \cdot A + B \quad a_x(x, y, t) = -7 \frac{\text{m}}{\text{s}^2}$$

$$a_y(x, y, t) = a_{yt}(x, y, t) + a_{yc}(x, y, t) \quad a_y(x, y, t) = y \cdot A^2 + B \cdot t \cdot A + B \quad a_y(x, y, t) = 14 \frac{\text{m}}{\text{s}^2}$$

For overall acceleration

$$a(x, y, t) = \sqrt{a_x(x, y, t)^2 + a_y(x, y, t)^2} \quad a(x, y, t) = \sqrt{(x \cdot A^2 - B \cdot t \cdot A + B)^2 + (y \cdot A^2 + B \cdot t \cdot A + B)^2} \quad a(x, y, t) = 15.7 \frac{\text{m}}{\text{s}^2}$$

$$\theta = \text{atan}\left(\frac{a_y(x, y, t)}{a_x(x, y, t)}\right) \quad \theta = -63.4 \cdot \text{deg}$$

For the pressure gradient we need

$$-\rho \cdot a_x(x, y, t) = 6.99 \cdot \frac{\text{kPa}}{\text{m}} \quad -\rho \cdot a_y(x, y, t) = -13.99 \cdot \frac{\text{kPa}}{\text{m}} \quad -\rho \cdot g = -9.80 \cdot \frac{\text{kPa}}{\text{m}}$$

Hence for the pressure gradient

$$\frac{\partial}{\partial x} p = \rho \cdot g_x - \rho \cdot a_x = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times 7 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\frac{\partial}{\partial x} p = 6990 \cdot \frac{\text{Pa}}{\text{m}} = 6.99 \cdot \frac{\text{kPa}}{\text{m}}$$

$$\frac{\partial}{\partial y} p = -\rho \cdot g_y - \rho \cdot a_y = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times (-9.81 - 14) \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\frac{\partial}{\partial y} p = -23800 \cdot \frac{\text{Pa}}{\text{m}} = -23.8 \cdot \frac{\text{kPa}}{\text{m}}$$

## Problem 6.4

[Difficulty: 2]

**6.4** A velocity field in a fluid with density of  $1000 \text{ kg/m}^3$  is given by  $\vec{V} = (-Ax + By)\hat{i} + (Ay + Bx)\hat{j}$ , where  $A = 2 \text{ s}^{-2}$  and  $B = 1 \text{ s}^{-2}$ ,  $x$  and  $y$  are in meters, and  $t$  is in seconds. Body forces are negligible. Evaluate  $\nabla p$  at point  $(x, y) = (1, 1)$  at  $t = 1 \text{ s}$ .

**Given:** Velocity field

**Find:** Pressure gradient at (1,1) at 1 s

**Solution:**

Basic equations 
$$\bar{a}_p = \frac{D\bar{V}}{Dt} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \frac{\partial \bar{V}}{\partial t} \quad \rho \frac{D\bar{V}}{Dt} = \rho \bar{g} - \nabla p$$

total acceleration of a particle local acceleration

Given data  $A = 2 \cdot \frac{1}{\text{s}^2}$        $B = 1 \cdot \frac{1}{\text{s}^2}$        $x = 1 \cdot \text{m}$        $y = 1 \cdot \text{m}$        $t = 1 \cdot \text{s}$        $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$

$u(x, y, t) = (-A \cdot x + B \cdot y) \cdot t$        $v(x, y, t) = (A \cdot y + B \cdot x) \cdot t$

The acceleration components and values are

$$a_{xt}(x, y, t) = \frac{\partial}{\partial t} u(x, y, t) = B \cdot y - A \cdot x \quad a_{xt}(x, y, t) = B \cdot y - A \cdot x \quad a_{xt}(x, y, t) = -1 \frac{\text{m}}{\text{s}^2}$$

$$a_{xc}(x, y, t) = u(x, y, t) \cdot \frac{\partial}{\partial x} u(x, y, t) + v(x, y, t) \cdot \frac{\partial}{\partial y} u(x, y, t) \quad a_{xc}(x, y, t) = t^2 \cdot x \cdot (A^2 + B^2) \quad a_{xc}(x, y, t) = 5 \frac{\text{m}}{\text{s}^2}$$

$$a_{yt}(x, y, t) = \frac{\partial}{\partial t} v(x, y, t) \quad a_{yt}(x, y, t) = A \cdot y + B \cdot x \quad a_{yt}(x, y, t) = 3 \frac{\text{m}}{\text{s}^2}$$

$$a_{yc}(x, y, t) = u(x, y, t) \cdot \frac{\partial}{\partial x} v(x, y, t) + v(x, y, t) \cdot \frac{\partial}{\partial y} v(x, y, t) \quad a_{yc}(x, y, t) = t^2 \cdot y \cdot (A^2 + B^2) \quad a_{yc}(x, y, t) = 5 \frac{\text{m}}{\text{s}^2}$$

$$a_x(x, y, t) = a_{xt}(x, y, t) + a_{xc}(x, y, t) \quad a_x(x, y, t) = x \cdot A^2 \cdot t^2 - x \cdot A + x \cdot B^2 \cdot t^2 + y \cdot B \quad a_x(x, y, t) = 4 \frac{\text{m}}{\text{s}^2}$$

$$a_y(x, y, t) = a_{yt}(x, y, t) + a_{yc}(x, y, t) \quad a_y(x, y, t) = y \cdot A^2 \cdot t^2 + y \cdot A + y \cdot B^2 \cdot t^2 + x \cdot B \quad a_y(x, y, t) = 8 \frac{\text{m}}{\text{s}^2}$$

Hence for the pressure gradient

$$\frac{\partial}{\partial x} p = -\rho \cdot a_x = -1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 4 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \frac{\partial}{\partial x} p = -4000 \cdot \frac{\text{Pa}}{\text{m}} = -4 \cdot \frac{\text{kPa}}{\text{m}}$$

$$\frac{\partial}{\partial y} p = -\rho \cdot a_y = -1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 8 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \frac{\partial}{\partial y} p = -8000 \cdot \frac{\text{Pa}}{\text{m}} = -8 \cdot \frac{\text{kPa}}{\text{m}}$$

## Problem 6.5

[Difficulty: 2]

**6.5** Consider the flow field with velocity given by  $\vec{V} = [A(x^2 - y^2) - 3Bx]\hat{i} - [2Axy - 3By]\hat{j}$ , where  $A = 1 \text{ ft}^{-1} \cdot \text{s}^{-1}$ ,  $B = 1 \text{ s}^{-1}$ , and the coordinates are measured in feet. The density is  $2 \text{ slug/ft}^3$  and gravity acts in the negative  $y$  direction. Determine the acceleration of a fluid particle and the pressure gradient at point  $(x, y) = (1, 1)$ .

**Given:** Velocity field

**Find:** Acceleration of particle and pressure gradient at (1,1)

**Solution:**

$$\text{Basic equations} \quad \bar{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}} \quad \rho \frac{D\vec{V}}{Dt} = \rho \bar{g} - \nabla p$$

total acceleration of a particle

$$\text{For this flow} \quad u(x, y) = A \cdot (x^2 - y^2) - 3 \cdot B \cdot x \quad v(x, y) = -2 \cdot A \cdot x \cdot y + 3 \cdot B \cdot y$$

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = [A \cdot (x^2 - y^2) - 3 \cdot B \cdot x] \cdot \frac{\partial}{\partial x} [A \cdot (x^2 - y^2) - 3 \cdot B \cdot x] + (-2 \cdot A \cdot x \cdot y + 3 \cdot B \cdot y) \cdot \frac{\partial}{\partial y} [A \cdot (x^2 - y^2) - 3 \cdot B \cdot x]$$

$$a_x = (2 \cdot A \cdot x - 3 \cdot B) \cdot (A \cdot x^2 - 3 \cdot B \cdot x + A \cdot y^2)$$

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = [A \cdot (x^2 - y^2) - 3 \cdot B \cdot x] \cdot \frac{\partial}{\partial x} (-2 \cdot A \cdot x \cdot y + 3 \cdot B \cdot y) + (-2 \cdot A \cdot x \cdot y + 3 \cdot B \cdot y) \cdot \frac{\partial}{\partial y} (-2 \cdot A \cdot x \cdot y + 3 \cdot B \cdot y)$$

$$a_y = (3 \cdot B \cdot y - 2 \cdot A \cdot x \cdot y) \cdot (3 \cdot B - 2 \cdot A \cdot x) - 2 \cdot A \cdot y \cdot [A \cdot (x^2 - y^2) - 3 \cdot B \cdot x]$$

$$\text{Hence at (1,1)} \quad a_x = (2 \cdot 1 \cdot 1 - 3 \cdot 1) \cdot \frac{1}{s} \times (1 \cdot 1^2 - 3 \cdot 1 \cdot 1 + 1 \cdot 1^2) \cdot \frac{\text{ft}}{s} \quad a_x = 1 \cdot \frac{\text{ft}}{s^2}$$

$$a_y = (3 \cdot 1 \cdot 1 - 2 \cdot 1 \cdot 1 \cdot 1) \cdot \frac{1}{s} \times (3 \cdot 1 - 2 \cdot 1 \cdot 1) \cdot \frac{\text{ft}}{s} - 2 \cdot 1 \cdot 1 \cdot \frac{1}{s} \times [1 \cdot (1^2 - 1^2) - 3 \cdot 1 \cdot 1] \cdot \frac{\text{ft}}{s} \quad a_y = 7 \cdot \frac{\text{ft}}{s^2}$$

$$a = \sqrt{a_x^2 + a_y^2} \quad \theta = \text{atan} \left( \frac{a_y}{a_x} \right) \quad a = 7.1 \cdot \frac{\text{ft}}{s^2} \quad \theta = 81.9 \cdot \text{deg}$$

For the pressure gradient

$$\frac{\partial}{\partial x} p = \rho \cdot g_x - \rho \cdot a_x = -2 \cdot \frac{\text{slug}}{\text{ft}^3} \times 1 \cdot \frac{\text{ft}}{s^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad \frac{\partial}{\partial x} p = -2 \cdot \frac{\text{lbf}}{\text{ft}^2} = -0.0139 \cdot \frac{\text{psi}}{\text{ft}}$$

$$\frac{\partial}{\partial y} p = \rho \cdot g_y - \rho \cdot a_y = 2 \cdot \frac{\text{slug}}{\text{ft}^3} \times (-32.2 - 7) \cdot \frac{\text{ft}}{s^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad \frac{\partial}{\partial y} p = -78.4 \cdot \frac{\text{lbf}}{\text{ft}^2} = -0.544 \cdot \frac{\text{psi}}{\text{ft}}$$

## Problem 6.6

[Difficulty: 2]

**6.6** The  $x$  component of velocity in an incompressible flow field is given by  $u = Ax$ , where  $A = 2 \text{ s}^{-1}$  and the coordinates are measured in meters. The pressure at point  $(x, y) = (0, 0)$  is  $p_0 = 190 \text{ kPa}$  (gage). The density is  $\rho = 1.50 \text{ kg/m}^3$  and the  $z$  axis is vertical. Evaluate the simplest possible  $y$  component of velocity. Calculate the fluid acceleration and determine the pressure gradient at point  $(x, y) = (2, 1)$ . Find the pressure distribution along the positive  $x$  axis.

**Given:** Velocity field

**Find:** Simplest  $y$  component of velocity; Acceleration of particle and pressure gradient at  $(2,1)$ ; pressure on  $x$  axis

**Solution:**

Basic equations 
$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0 \quad \bar{a}_p = \frac{D\bar{V}}{Dt} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \bar{V}}{\partial t}}_{\text{local acceleration}} \quad \rho \frac{D\bar{V}}{Dt} = \rho \bar{g} - \nabla p$$

For this flow 
$$u(x, y) = Ax \quad \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0 \quad \text{so} \quad v(x, y) = - \int \frac{\partial}{\partial x} u \, dy = - \int A \, dy = -A \cdot y + c$$

Hence  $v(x, y) = -A \cdot y$  is the simplest  $y$  component of velocity

For acceleration 
$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = A \cdot x \cdot \frac{\partial}{\partial x} (A \cdot x) + (-A \cdot y) \cdot \frac{\partial}{\partial y} (A \cdot x) = A^2 \cdot x \quad a_x = A^2 \cdot x$$

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = A \cdot x \cdot \frac{\partial}{\partial x} (-A \cdot y) + (-A \cdot y) \cdot \frac{\partial}{\partial y} (-A \cdot y) \quad a_y = A^2 \cdot y$$

Hence at  $(2,1)$  
$$a_x = \left(\frac{2}{s}\right)^2 \times 2 \cdot \text{m} \quad a_y = \left(\frac{2}{s}\right)^2 \times 1 \cdot \text{m} \quad a_x = 8 \frac{\text{m}}{\text{s}^2} \quad a_y = 4 \frac{\text{m}}{\text{s}^2}$$

$$a = \sqrt{a_x^2 + a_y^2} \quad \theta = \text{atan}\left(\frac{a_y}{a_x}\right) \quad a = 8.94 \frac{\text{m}}{\text{s}^2} \quad \theta = 26.6 \cdot \text{deg}$$

For the pressure gradient

$$\frac{\partial}{\partial x} p = \rho \cdot g_x - \rho \cdot a_x = -1.50 \cdot \frac{\text{kg}}{\text{m}^3} \times 8 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \frac{\partial}{\partial x} p = -12 \cdot \frac{\text{Pa}}{\text{m}}$$

$$\frac{\partial}{\partial y} p = \rho \cdot g_y - \rho \cdot a_y = -1.50 \cdot \frac{\text{kg}}{\text{m}^3} \times 4 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \frac{\partial}{\partial y} p = -6 \cdot \frac{\text{Pa}}{\text{m}}$$

$$\frac{\partial}{\partial z} p = \rho \cdot g_z - \rho \cdot a_z = 1.50 \times \frac{\text{kg}}{\text{m}^3} \times (-9.81) \cdot \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \frac{\partial}{\partial y} p = -14.7 \cdot \frac{\text{Pa}}{\text{m}}$$

For the pressure on the  $x$  axis 
$$dp = \frac{\partial}{\partial x} p \quad p - p_0 = \int_0^x (\rho \cdot g_x - \rho \cdot a_x) \, dx = \int_0^x (-\rho \cdot A^2 \cdot x) \, dx = -\frac{1}{2} \cdot \rho \cdot A^2 \cdot x^2$$

$$p(x) = p_0 - \frac{1}{2} \cdot \rho \cdot A^2 \cdot x^2 \quad p(x) = 190 \cdot \text{kPa} - \frac{1}{2} \cdot 1.5 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(\frac{2}{s}\right)^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times x^2 \quad p(x) = 190 - \frac{3}{1000} \cdot x^2 \quad (\text{p in kPa, x in m})$$



Evaluating at point (1,1) at

t = 0·s	Local	$12.6 \cdot \frac{\text{m}}{\text{s}^2}$	and	$-12.6 \cdot \frac{\text{m}}{\text{s}^2}$	Convective	$0 \cdot \frac{\text{m}}{\text{s}^2}$	and	$0 \cdot \frac{\text{m}}{\text{s}^2}$
	Total	$12.6 \cdot \frac{\text{m}}{\text{s}^2}$	and	$-12.6 \cdot \frac{\text{m}}{\text{s}^2}$				
t = 0.5·s	Local	$-12.6 \cdot \frac{\text{m}}{\text{s}^2}$	and	$12.6 \cdot \frac{\text{m}}{\text{s}^2}$	Convective	$0 \cdot \frac{\text{m}}{\text{s}^2}$	and	$0 \cdot \frac{\text{m}}{\text{s}^2}$
	Total	$-12.6 \cdot \frac{\text{m}}{\text{s}^2}$	and	$12.6 \cdot \frac{\text{m}}{\text{s}^2}$				
t = 1·s	Local	$12.6 \cdot \frac{\text{m}}{\text{s}^2}$	and	$-12.6 \cdot \frac{\text{m}}{\text{s}^2}$	Convective	$0 \cdot \frac{\text{m}}{\text{s}^2}$	and	$0 \cdot \frac{\text{m}}{\text{s}^2}$
	Total	$12.6 \cdot \frac{\text{m}}{\text{s}^2}$	and	$-12.6 \cdot \frac{\text{m}}{\text{s}^2}$				

The governing equation (assuming inviscid flow) for computing the pressure gradient is  $\rho \frac{D\vec{V}}{Dt} = \rho \vec{g} - \nabla p$

Hence, the components of pressure gradient (neglecting gravity) are

$$\frac{\partial p}{\partial x} = -\rho \cdot \frac{Du}{Dt} \quad \frac{\partial p}{\partial x} = -\rho \cdot \left( 2 \cdot \pi \cdot A \cdot \omega \cdot x \cdot \cos(2 \cdot \pi \cdot \omega \cdot t) + A^2 \cdot x \cdot \sin(2 \cdot \pi \cdot \omega \cdot t)^2 \right)$$

$$\frac{\partial p}{\partial y} = -\rho \cdot \frac{Dv}{Dt} \quad \frac{\partial p}{\partial y} = -\rho \cdot \left( -2 \cdot \pi \cdot A \cdot \omega \cdot y \cdot \cos(2 \cdot \pi \cdot \omega \cdot t) + A^2 \cdot y \cdot \sin(2 \cdot \pi \cdot \omega \cdot t)^2 \right)$$


Evaluated at (1,1) and time	t = 0·s	x comp.	$-25.1 \cdot \frac{\text{Pa}}{\text{m}}$	y comp.	$25.1 \cdot \frac{\text{Pa}}{\text{m}}$
	t = 0.5·s	x comp.	$25.1 \cdot \frac{\text{Pa}}{\text{m}}$	y comp.	$-25.1 \cdot \frac{\text{Pa}}{\text{m}}$
	t = 1·s	x comp.	$-25.1 \cdot \frac{\text{Pa}}{\text{m}}$	y comp.	$25.1 \cdot \frac{\text{Pa}}{\text{m}}$

## Problem 6.8

[Difficulty: 3]

**6.8** The velocity field for a plane source located distance  $h = 1$  m above an infinite wall aligned along the  $x$  axis is given by

$$\vec{V} = \frac{q}{2\pi[x^2 + (y-h)^2]} [x\hat{i} + (y-h)\hat{j}] + \frac{q}{2\pi[x^2 + (y+h)^2]} [x\hat{i} + (y+h)\hat{j}]$$



where  $q = 2 \text{ m}^3/\text{s}$ . The fluid density is  $1000 \text{ kg/m}^3$  and body forces are negligible. Derive expressions for the velocity and acceleration of a fluid particle that moves along the wall, and plot from  $x=0$  to  $x=+10h$ . Verify that the velocity and acceleration normal to the wall are zero. Plot the pressure gradient  $\partial p/\partial x$  along the wall. Is the pressure gradient along the wall adverse (does it oppose fluid motion) or not?

**Given:** Velocity field

**Find:** Expressions for velocity and acceleration along wall; plot; verify vertical components are zero; plot pressure gradient

**Solution:**

The given data is

$$q = 2 \cdot \frac{\text{m}^3}{\text{s}} \quad h = 1 \cdot \text{m} \quad \rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$$

$$u = \frac{q \cdot x}{2 \cdot \pi [x^2 + (y-h)^2]} + \frac{q \cdot x}{2 \cdot \pi [x^2 + (y+h)^2]} \quad v = \frac{q \cdot (y-h)}{2 \cdot \pi [x^2 + (y-h)^2]} + \frac{q \cdot (y+h)}{2 \cdot \pi [x^2 + (y+h)^2]}$$

The governing equation for acceleration is

$$\vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

For steady, 2D flow this reduces to (after considerable math!)

$$x\text{-component} \quad a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = - \frac{q^2 \cdot x \cdot [(x^2 + y^2)^2 - h^2 \cdot (h^2 - 4 \cdot y^2)]}{[x^2 + (y+h)^2]^2 \cdot [x^2 + (y-h)^2]^2 \cdot \pi^2}$$

$$y\text{-component} \quad a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = - \frac{q^2 \cdot y \cdot [(x^2 + y^2)^2 - h^2 \cdot (h^2 + 4 \cdot x^2)]}{\pi^2 \cdot [x^2 + (y+h)^2]^2 \cdot [x^2 + (y-h)^2]^2}$$

For motion along the wall  $y = 0 \cdot \text{m}$

$$u = \frac{q \cdot x}{\pi \cdot (x^2 + h^2)} \quad v = 0 \quad (\text{No normal velocity}) \quad a_x = - \frac{q^2 \cdot x \cdot (x^2 - h^2)}{\pi^2 \cdot (x^2 + h^2)^3} \quad a_y = 0 \quad (\text{No normal acceleration})$$

The governing equation (assuming inviscid flow) for computing the pressure gradient is

$$\rho \frac{D\vec{V}}{Dt} = \rho \vec{g} - \nabla p$$




Hence, the component of pressure gradient (neglecting gravity) along the wall is

$$\frac{\partial}{\partial x} p = -\rho \cdot \frac{Du}{Dt} \qquad \frac{\partial}{\partial x} p = \frac{\rho \cdot q^2 \cdot x \cdot (x^2 - h^2)}{\pi^2 \cdot (x^2 + h^2)^3}$$

The plots of velocity, acceleration, and pressure gradient are shown below, done in *Excel*. From the plots it is clear that the fluid experiences an adverse pressure gradient from the origin to  $x = 1$  m, then a negative one promoting fluid acceleration. If flow separates, it will likely be in the region  $x = 0$  to  $x = h$ .

$q = 2 \text{ m}^3/\text{s/m}$   
 $h = 1 \text{ m}$   
 $\rho = 1000 \text{ kg/m}^3$

$x$ (m)	$u$ (m/s)	$a$ (m/s <sup>2</sup> )	$dp/dx$ (Pa/m)
0.0	0.00	0.00000	0.00
1.0	0.32	0.00000	0.00
2.0	0.25	0.01945	-19.45
3.0	0.19	0.00973	-9.73
4.0	0.15	0.00495	-4.95
5.0	0.12	0.00277	-2.77
6.0	0.10	0.00168	-1.68
7.0	0.09	0.00109	-1.09
8.0	0.08	0.00074	-0.74
9.0	0.07	0.00053	-0.53
10.0	0.06	0.00039	-0.39



### Problem 6.9

[Difficulty: 2]

6.9 The velocity distribution in a two-dimensional steady flow field in the  $xy$  plane is  $\vec{V} = (Ax - B)\hat{i} + (C - Ay)\hat{j}$ , where  $A = 2 \text{ s}^{-1}$ ,  $B = 5 \text{ m} \cdot \text{s}^{-1}$ , and  $C = 3 \text{ m} \cdot \text{s}^{-1}$ ; the coordinates are measured in meters, and the body force distribution is  $\vec{g} = -g\hat{k}$ . Does the velocity field represent the flow of an incompressible fluid? Find the stagnation point of the flow field. Obtain an expression for the pressure gradient in the flow field. Evaluate the difference in pressure between point  $(x, y) = (1, 3)$  and the origin, if the density is  $1.2 \text{ kg/m}^3$ .

Solution:

(a) Apply the continuity equation,  $\frac{\partial \rho}{\partial t} + \nabla \cdot \rho \vec{V} = 0$ , for the given conditions. If  $\rho$  is constant, then

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0 = \frac{\partial}{\partial x}(2x - 5) + \frac{\partial}{\partial y}(3 - 2y) = 2 - 2 = 0 \quad \checkmark$$

$\therefore$  velocity field represents an incompressible flow

(b) At the stagnation point,  $\vec{V} = 0$ . For  $\vec{V} = 0$ , then

$$u = 2x - 5 = 0 \quad \text{and} \quad v = (3 - 2y) = 0$$

Thus stagnation point is at  $(x, y) = \left(\frac{5}{2}, \frac{3}{2}\right)$

(c) Euler's equation,  $\rho \vec{g} - \nabla P = \rho \frac{d\vec{V}}{dt}$ , can be used to obtain an expression for the pressure gradient

$$\nabla P = \rho \vec{g} - \rho \frac{d\vec{V}}{dt} = \rho \vec{g} - \rho \left[ \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{steady}} + u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z} \right]$$

$$\nabla P = \rho \left[ \vec{g} - u \frac{\partial \vec{V}}{\partial x} - v \frac{\partial \vec{V}}{\partial y} \right] = \rho \left[ -g\hat{k} - (2x - 5)2\hat{i} - (3 - 2y)(-2\hat{j}) \right]$$

$$\nabla P = -\rho \left[ (4x - 10)\hat{i} + (4y - 6)\hat{j} + g\hat{k} \right]$$

(d) Since  $P = P(x, y, z)$  we can write

$$dP = \frac{\partial P}{\partial x} dx + \frac{\partial P}{\partial y} dy + \frac{\partial P}{\partial z} dz = -\rho(4x - 10)dx - \rho(4y - 6)dy - \rho g dz$$

We can integrate to obtain  $\Delta P$  between any two points in the field if, and only if, the integral of the right hand side is independent of the path of integration. This is true for the present case.

$$\begin{aligned} \therefore P_{1,3} - P_{0,0} &= -\rho \left\{ \int_0^1 (4x - 10) dx + \int_0^3 (4y - 6) dy \right\} = -\rho \left\{ [2x^2 - 10x]_0^1 + [2y^2 - 6y]_0^3 \right\} \\ &= -\rho \{ -8 - 0 \} = 8\rho \end{aligned}$$

$$P_{1,3} - P_{0,0} = 8 \frac{\text{m}^2}{\text{s}^2} \cdot 1.2 \frac{\text{kg}}{\text{m}^3} = 9.6 \frac{\text{N}}{\text{m}^2}$$

## Problem 6.10

[Difficulty: 2]

**6.10** In a two-dimensional frictionless, incompressible ( $\rho = 1500 \text{ kg/m}^3$ ) flow, the velocity field in meters per second is given by  $\vec{V} = (Ax + By)\hat{i} + (Bx - Ay)\hat{j}$ ; the coordinates are measured in meters, and  $A = 4 \text{ s}^{-1}$  and  $B = 2 \text{ s}^{-1}$ . The pressure is  $p_0 = 200 \text{ kPa}$  at point  $(x, y) = (0, 0)$ . Obtain an expression for the pressure field,  $p(x, y)$  in terms of  $p_0, A$ , and  $B$ , and evaluate at point  $(x, y) = (2, 2)$ .

**Given:** Velocity field

**Find:** Expression for pressure field; evaluate at (2,2)

**Solution:**

Basic equations 
$$\bar{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \frac{\partial \vec{V}}{\partial t}_{\text{local acceleration}} \quad \rho \frac{D\vec{V}}{Dt} = \rho \bar{g} - \nabla p$$

total acceleration of a particle

Given data  $A = 4 \cdot \frac{1}{\text{s}} \quad B = 2 \cdot \frac{1}{\text{s}} \quad x = 2 \cdot \text{m} \quad y = 2 \cdot \text{m} \quad \rho = 1500 \cdot \frac{\text{kg}}{\text{m}^3} \quad p_0 = 200 \cdot \text{kPa}$

For this flow  $u(x, y) = A \cdot x + B \cdot y \quad v(x, y) = B \cdot x - A \cdot y$

Note that  $\frac{\partial}{\partial x} u(x, y) + \frac{\partial}{\partial y} v(x, y) = 0 \quad \frac{\partial}{\partial x} v(x, y) - \frac{\partial}{\partial y} u(x, y) = 0$

Then  $a_x(x, y) = u(x, y) \cdot \frac{\partial}{\partial x} u(x, y) + v(x, y) \cdot \frac{\partial}{\partial y} u(x, y) \quad a_x(x, y) = x \cdot (A^2 + B^2) \quad a_x(x, y) = 40 \frac{\text{m}}{\text{s}^2}$

$a_y(x, y) = u(x, y) \cdot \frac{\partial}{\partial x} v(x, y) + v(x, y) \cdot \frac{\partial}{\partial y} v(x, y) \quad a_y(x, y) = y \cdot (A^2 + B^2) \quad a_y(x, y) = 40 \frac{\text{m}}{\text{s}^2}$

The momentum equation becomes  $\frac{\partial}{\partial x} p = -\rho \cdot a_x \quad \frac{\partial}{\partial y} p = -\rho \cdot a_y \quad \text{and} \quad p = dx \cdot \frac{\partial}{\partial x} p + dy \cdot \frac{\partial}{\partial y} p$

Integrating

$$p(x, y) = p_0 - \rho \cdot \int_0^x a_x(x, y) dx - \rho \cdot \int_0^y a_y(x, y) dy$$

$$p(x, y) = p_0 - \frac{\rho \cdot (A^2 + B^2) \cdot y^2}{2} - \frac{\rho \cdot (A^2 + B^2) \cdot x^2}{2}$$

$p(x, y) = 80 \cdot \text{kPa}$

## Problem 6.11

[Difficulty: 2]

**6.11** An incompressible liquid with a density of  $1250 \text{ kg/m}^3$  and negligible viscosity flows steadily through a horizontal pipe of constant diameter. In a porous section of length  $L = 5 \text{ m}$ , liquid is removed at a constant rate per unit length so that the uniform axial velocity in the pipe is  $u(x) = U(1 - x/L)$ , where  $U = 15 \text{ m/s}$ . Develop expressions for and plot the pressure gradient along the centerline. Evaluate the outlet pressure if the pressure at the inlet to the porous section is  $100 \text{ kPa}$  (gage).

**Given:** Velocity field

**Find:** Expression for pressure gradient; plot; evaluate pressure at outlet

**Solution:**

Basic equations

$$\underbrace{\bar{a}_p = \frac{D\bar{V}}{Dt}}_{\text{total acceleration of a particle}} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \bar{V}}{\partial t}}_{\text{local acceleration}} \quad \rho \frac{D\bar{V}}{Dt} = \rho \bar{g} - \nabla p$$

Given data

$$U = 15 \frac{\text{m}}{\text{s}} \quad L = 5 \cdot \text{m} \quad p_{\text{in}} = 100 \cdot \text{kPa} \quad \rho = 1250 \cdot \frac{\text{kg}}{\text{m}^3}$$

Here

$$u(x) = U \cdot \left(1 - \frac{x}{L}\right) \quad u(0) = 15 \frac{\text{m}}{\text{s}} \quad u(L) = 0 \frac{\text{m}}{\text{s}}$$

The x momentum becomes

$$\rho \cdot u \cdot \frac{d}{dx} u = \rho \cdot a_a = \frac{d}{dx} p$$

Hence

$$a_x(x) = u(x) \cdot \frac{\partial}{\partial x} u(x) \quad a_x(x) = \frac{U^2 \cdot \left(\frac{x}{L} - 1\right)}{L}$$

The pressure gradient is then


$$\frac{dp}{dx} = -\rho \cdot \frac{U^2}{L} \cdot \left(\frac{x}{L} - 1\right)$$

Integrating momentum

$$p(x) = p_{\text{in}} - \rho \cdot \int_0^x a_x(x) dx \quad p(x) = p_{\text{in}} - \frac{U^2 \cdot \rho \cdot x \cdot (x - 2 \cdot L)}{2 \cdot L^2}$$

Hence

$$p(L) = \frac{\rho \cdot U^2}{2} + p_{\text{in}} \quad p(L) = 241 \cdot \text{kPa}$$



## Problem 6.12

[Difficulty: 2]

**6.12** An incompressible liquid with a density of  $900 \text{ kg/m}^3$  and negligible viscosity flows steadily through a horizontal pipe of constant diameter. In a porous section of length  $L = 2 \text{ m}$ , liquid is removed at a variable rate along the length so that the uniform axial velocity in the pipe is  $u(x) = Ue^{-x/L}$ , where  $U = 20 \text{ m/s}$ . Develop expressions for and plot the acceleration of a fluid particle along the centerline of the porous section and the pressure gradient along the centerline. Evaluate the outlet pressure if the pressure at the inlet to the porous section is  $50 \text{ kPa}$  (gage).

**Given:** Velocity field

**Find:** Expression for acceleration and pressure gradient; plot; evaluate pressure at outlet

**Solution:**

Basic equations

$$\bar{a}_p = \frac{D\bar{V}}{Dt} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \frac{\partial \bar{V}}{\partial t} \quad \rho \frac{D\bar{V}}{Dt} = \rho \bar{g} - \nabla p$$

total acceleration of a particle
convective acceleration
local acceleration

Given data

$$U = 20 \cdot \frac{\text{m}}{\text{s}} \quad L = 2 \cdot \text{m} \quad p_{\text{in}} = 50 \cdot \text{kPa} \quad \rho = 900 \cdot \frac{\text{kg}}{\text{m}^3}$$

Here

$$u(x) = U \cdot e^{-\frac{x}{L}} \quad u(0) = 20 \frac{\text{m}}{\text{s}} \quad u(L) = 7.36 \frac{\text{m}}{\text{s}}$$

The x component of acceleration is then

$$a_x(x) = u(x) \cdot \frac{\partial}{\partial x} u(x) \quad a_x(x) = -\frac{U^2 \cdot e^{-\frac{2 \cdot x}{L}}}{L}$$

The x momentum becomes

$$\rho \cdot u \cdot \frac{d}{dx} u = \rho \cdot a_a = \frac{d}{dx} p$$

The pressure gradient is then



$$\frac{dp}{dx} = \frac{\rho}{L} \cdot U^2 \cdot e^{-\frac{2 \cdot x}{L}}$$

Integrating momentum

$$p(x) = p_{\text{in}} - \rho \cdot \int_0^x a_x(x) dx \quad p(x) = p_{\text{in}} - \frac{U^2 \cdot \rho \cdot \left( e^{-\frac{2 \cdot x}{L}} - 1 \right)}{2}$$

Hence

$$p(L) = p_{\text{in}} - \frac{U^2 \cdot \rho \cdot \left( e^{-2} - 1 \right)}{2} \quad p(L) = 206 \cdot \text{kPa}$$



### Problem 6.13

[Difficulty: 2]

**6.13** For the flow of Problem 4.123 show that the uniform radial velocity is  $V_r = Q/2\pi rh$ . Obtain expressions for the  $r$  component of acceleration of a fluid particle in the gap and for the pressure variation as a function of radial distance from the central holes.

Solution:

Apply the conservation of mass to a CV with outer edge at  $r$ .



Basic equation:  $0 = \frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{v} \cdot d\vec{A}$

- Assumptions: (1) steady flow  
(2) incompressible flow  
(3) uniform flow at each section

Then  $0 = \int_{CS} \vec{v} \cdot d\vec{A} = -v_r \frac{d}{2} + v_r 2\pi rh$   
and  $v_r = \frac{Q}{2\pi rh}$

From Eq. 6.4a

$$g_r - \frac{1}{\rho} \frac{\partial p}{\partial r} = a_r = \frac{\partial v_r}{\partial t} + v_r \frac{\partial v_r}{\partial r} + \frac{v_\theta}{r} \frac{\partial v_r}{\partial \theta} + v_z \frac{\partial v_r}{\partial z} - \frac{v_\theta^2}{r}$$

Since  $v_r = v_r(r)$  and  $v_\theta = 0$ , then

$$a_r = v_r \frac{\partial v_r}{\partial r} = \frac{Q}{2\pi rh} \left[ \frac{Q}{2\pi rh} \left( -\frac{1}{r^2} \right) \right] = - \left( \frac{Q}{2\pi rh} \right)^2 \frac{1}{r}$$

$$a_r = - \frac{v_r^2}{r}$$

Since  $g_r = 0$ , then

$$-\frac{1}{\rho} \frac{\partial p}{\partial r} = a_r$$

$$\frac{\partial p}{\partial r} = -\rho a_r = \rho \frac{v_r^2}{r}$$

## Problem 6.14

[Difficulty: 3]

**6.14** The velocity field for a plane vortex sink is given by  $\vec{V} = (-q/2\pi r)\hat{e}_r + (K/2\pi r)\hat{e}_\theta$ , where  $q = 2 \text{ m}^3/\text{s}/\text{m}$  and  $K = 1 \text{ m}^3/\text{s}/\text{m}$ . The fluid density is  $1000 \text{ kg}/\text{m}^3$ . Find the acceleration at  $(1, 0)$ ,  $(1, \pi/2)$ , and  $(2, 0)$ . Evaluate  $\nabla p$  under the same conditions.

**Given:** Velocity field

**Find:** The acceleration at several points; evaluate pressure gradient

**Solution:**

The given data is  $q = 2 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}}$        $K = 1 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}}$        $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$        $V_r = -\frac{q}{2 \cdot \pi \cdot r}$        $V_\theta = \frac{K}{2 \cdot \pi \cdot r}$

The governing equations for this 2D flow are  $\rho a_r = \rho \left( \frac{\partial V_r}{\partial t} + V_r \frac{\partial V_r}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_r}{\partial \theta} + V_z \frac{\partial V_r}{\partial z} - \frac{V_\theta^2}{r} \right) = \rho g_r - \frac{\partial p}{\partial r}$  (6.3a)

$\rho a_\theta = \rho \left( \frac{\partial V_\theta}{\partial t} + V_r \frac{\partial V_\theta}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_\theta}{\partial \theta} + V_z \frac{\partial V_\theta}{\partial z} + \frac{V_r V_\theta}{r} \right) = \rho g_\theta - \frac{1}{r} \frac{\partial p}{\partial \theta}$  (6.3b)

The total acceleration for this steady flow is then

$r$  - component  $a_r = V_r \cdot \frac{\partial}{\partial r} V_r + \frac{V_\theta}{r} \cdot \frac{\partial}{\partial \theta} V_r - \frac{V_\theta^2}{r}$        $a_r = -\frac{q^2 + K^2}{4 \cdot \pi^2 \cdot r^3}$

$\theta$  - component  $a_\theta = V_r \cdot \frac{\partial}{\partial r} V_\theta + \frac{V_\theta}{r} \cdot \frac{\partial}{\partial \theta} V_\theta + \frac{V_r \cdot V_\theta}{r}$        $a_\theta = 0$

Evaluating at point  $(1,0)$        $a_r = -0.127 \frac{\text{m}}{\text{s}^2}$        $a_\theta = 0$

Evaluating at point  $(1, \pi/2)$        $a_r = -0.127 \frac{\text{m}}{\text{s}^2}$        $a_\theta = 0$

Evaluating at point  $(2,0)$        $a_r = -0.0158 \frac{\text{m}}{\text{s}^2}$        $a_\theta = 0$

From Eq. 6.3, pressure gradient is  $\frac{\partial}{\partial r} p = -\rho \cdot a_r$        $\frac{\partial}{\partial r} p = \frac{\rho \cdot (q^2 + K^2)}{4 \cdot \pi^2 \cdot r^3}$

$\frac{1}{r} \cdot \frac{\partial}{\partial \theta} p = -\rho \cdot a_\theta$        $\frac{1}{r} \cdot \frac{\partial}{\partial \theta} p = 0$

Evaluating at point  $(1,0)$        $\frac{\partial}{\partial r} p = 127 \cdot \frac{\text{Pa}}{\text{m}}$        $\frac{1}{r} \cdot \frac{\partial}{\partial \theta} p = 0$

Evaluating at point  $(1, \pi/2)$        $\frac{\partial}{\partial r} p = 127 \cdot \frac{\text{Pa}}{\text{m}}$        $\frac{1}{r} \cdot \frac{\partial}{\partial \theta} p = 0$

Evaluating at point  $(2,0)$        $\frac{\partial}{\partial r} p = 15.8 \cdot \frac{\text{Pa}}{\text{m}}$        $\frac{1}{r} \cdot \frac{\partial}{\partial \theta} p = 0$

### Problem 6.15

[Difficulty: 3]

**6.15** An incompressible, inviscid fluid flows into a horizontal round tube through its porous wall. The tube is closed at the left end and the flow discharges from the tube to the atmosphere at the right end. For simplicity, consider the  $x$  component of velocity in the tube uniform across any cross section. The density of the fluid is  $\rho$ , the tube diameter and length are  $D$  and  $L$ , respectively, and the uniform inflow velocity is  $v_0$ . The flow is steady. Obtain an algebraic expression for the  $x$  component of acceleration of a fluid particle located at position  $x$ , in terms of  $v_0$ ,  $x$ , and  $D$ . Find an expression for the pressure gradient,  $\partial p / \partial x$ , at position  $x$ . Integrate to obtain an expression for the gage pressure at  $x = 0$ .

Solution: Apply conservation of mass using the CV shown.

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{v} \cdot d\vec{A}$

$$a_{px} = u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} + \frac{\partial u}{\partial t} ; -\frac{\partial p}{\partial x} + \rho g_x = \rho a_{px}$$

- Assumptions: (1) Steady flow (4) Horizontal;  $g_x = 0$   
 (2) Incompressible flow (5)  $v \approx 0$  in channel ( $w \approx 0$  too)  
 (3) Uniform flow at each cross-section (6) Inviscid flow

Then  $\int \vec{v} \cdot d\vec{A} = \{-|v_0 \pi D x|\} + \{+|u \pi \frac{D^2}{4}|\} = 0$  or  $u(x) = 4 v_0 \frac{x}{D}$

and  $a_{px} = 4 v_0 \frac{x}{D} (4 v_0 \frac{1}{D}) = 16 v_0^2 \frac{x}{D^2}$

From the Euler equation,

$$-\frac{\partial p}{\partial x} = \rho a_{px} \text{ so } \frac{\partial p}{\partial x} = -\rho a_{px} = -16 \rho v_0^2 \frac{x}{D^2}$$

Since  $v \approx w \approx 0$ , then  $p(x)$  and  $dp = \frac{\partial p}{\partial x} dx$ . Integrating

$$\int_0^L dp = p_L - p(0) = \int_0^L -16 \rho v_0^2 \frac{x}{D^2} dx = -\left[ \frac{16 \rho v_0^2}{D^2} \frac{x^2}{2} \right]_0^L = -8 \frac{\rho v_0^2 L^2}{D^2}$$

Thus, since  $p_L = p_{atm}$ , the gage pressure at  $x = 0$  is

$$p(0) = 8 \rho v_0^2 \left(\frac{L}{D}\right)^2$$

## Problem 6.16

[Difficulty: 3]

**6.16** An incompressible liquid with negligible viscosity and density  $\rho = 1.75 \text{ slug/ft}^3$  flows steadily through a horizontal pipe. The pipe cross-section area linearly varies from  $15 \text{ in}^2$  to  $2.5 \text{ in}^2$  over a length of 10 feet. Develop an expression for and plot the pressure gradient and pressure versus position along the pipe, if the inlet centerline velocity is 5 ft/s and inlet pressure is 35 psi. What is the exit pressure? *Hint:* Use relation

$$u \frac{\partial u}{\partial x} = \frac{1}{2} \frac{\partial}{\partial x} (u^2)$$

**Given:** Flow in a pipe with variable area

**Find:** Expression for pressure gradient and pressure; Plot them; exit pressure

**Solution:**

Assumptions: 1) Incompressible flow 2) Flow profile remains unchanged so centerline velocity can represent average velocity

Basic equations  $Q = V \cdot A \quad \vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}} \quad \rho \frac{D\vec{V}}{Dt} = \rho \vec{g} - \nabla p$

total acceleration of a particle
convective acceleration
local acceleration

Given data  $\rho = 1.75 \cdot \frac{\text{slug}}{\text{ft}^3} \quad p_i = 35 \cdot \text{psi} \quad A_i = 15 \cdot \text{in}^2 \quad A_e = 2.5 \cdot \text{in}^2 \quad L = 10 \cdot \text{ft} \quad u_i = 5 \cdot \frac{\text{ft}}{\text{s}}$

For this 1D flow  $Q = u_i \cdot A_i = u \cdot A \quad A = A_i - \frac{(A_i - A_e)}{L} \cdot x \quad \text{so} \quad u(x) = u_i \cdot \frac{A_i}{A} = u_i \cdot \frac{A_i}{A_i - \left[ \frac{(A_i - A_e)}{L} \cdot x \right]}$

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = u_i \cdot \frac{A_i}{A_i - \left[ \frac{(A_i - A_e)}{L} \cdot x \right]} \cdot \frac{\partial}{\partial x} \left[ u_i \cdot \frac{A_i}{A_i - \left[ \frac{(A_i - A_e)}{L} \cdot x \right]} \right] = \frac{A_i^2 \cdot L^2 \cdot u_i^2 \cdot (A_e - A_i)}{(A_i \cdot L + A_e \cdot x - A_i \cdot x)^3}$$

For the pressure  $\frac{\partial}{\partial x} p = -\rho \cdot a_x - \rho \cdot g_x = -\frac{\rho \cdot A_i^2 \cdot L^2 \cdot u_i^2 \cdot (A_e - A_i)}{(A_i \cdot L + A_e \cdot x - A_i \cdot x)^3}$

and  $dp = \frac{\partial}{\partial x} p \cdot dx \quad p - p_i = \int_0^x \frac{\partial}{\partial x} p \, dx = \int_0^x -\frac{\rho \cdot A_i^2 \cdot L^2 \cdot u_i^2 \cdot (A_e - A_i)}{(A_i \cdot L + A_e \cdot x - A_i \cdot x)^3} \, dx$

This is a tricky integral, so instead consider the following:  $\frac{\partial}{\partial x} p = -\rho \cdot a_x = -\rho \cdot u \cdot \frac{\partial}{\partial x} u = -\frac{1}{2} \cdot \rho \cdot \frac{\partial}{\partial x} (u^2)$

Hence  $p - p_i = \int_0^x \frac{\partial}{\partial x} p \, dx = -\frac{\rho}{2} \cdot \int_0^x \frac{\partial}{\partial x} (u^2) \, dx = \frac{\rho}{2} \cdot (u(x=0)^2 - u(x)^2)$



$$p(x) = p_i + \frac{\rho}{2} \cdot (u_i^2 - u(x)^2) \quad \text{which we recognise as the Bernoulli equation!}$$

Hence

$$p(x) = p_i + \frac{\rho \cdot u_i^2}{2} \cdot \left[ 1 - \left[ \frac{A_i}{A_i - \left[ \frac{(A_i - A_e)}{L} \cdot x \right]} \right]^2 \right]$$

At the exit  $p(L) = 29.7 \text{ psi}$

The following plots can be done in *Excel*



## Problem 6.17

[Difficulty: 3]

**6.17** An incompressible liquid with negligible viscosity and density  $\rho = 1250 \text{ kg/m}^3$  flows steadily through a 5-m-long convergent-divergent section of pipe for which the area varies as

$$A(x) = A_0(1 + e^{-x/a} - e^{-x/2a})$$

where  $A_0 = 0.25 \text{ m}^2$  and  $a = 1.5 \text{ m}$ . Plot the area for the first 5 m. Develop an expression for and plot the pressure gradient and pressure versus position along the pipe, for the first 5 m, if the inlet centerline velocity is 10 m/s and inlet pressure is 300 kPa. *Hint:* Use relation

$$u \frac{\partial u}{\partial x} = \frac{1}{2} \frac{\partial}{\partial x} (u^2)$$

**Given:** Flow in a pipe with variable area

**Find:** Expression for pressure gradient and pressure; Plot them

**Solution:**

Assumptions: 1) Incompressible flow 2) Flow profile remains unchanged so centerline velocity can represent average velocity

Basic equations  $Q = V \cdot A \quad \vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}} \quad \rho \frac{D\vec{V}}{Dt} = \rho \vec{g} - \nabla p$

total acceleration of a particle

Given data  $\rho = 1250 \cdot \frac{\text{kg}}{\text{m}^3} \quad A_0 = 0.25 \cdot \text{m}^2 \quad a = 1.5 \cdot \text{m} \quad L = 5 \cdot \text{m} \quad u_0 = 10 \cdot \frac{\text{m}}{\text{s}} \quad p_0 = 300 \cdot \text{kPa}$

For this 1D flow  $Q = u_0 \cdot A_0 = u \cdot A \quad A(x) = A_0 \cdot \left( 1 + e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}} \right)$

so  $u(x) = u_0 \cdot \frac{A_0}{A} = \frac{u_0}{\left( 1 + e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}} \right)}$

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = \frac{u_0}{\left( 1 + e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}} \right)} \cdot \frac{\partial}{\partial x} \left[ \frac{u_0}{\left( 1 + e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}} \right)} \right] = \frac{u_0^2 \cdot e^{-\frac{x}{2 \cdot a}} \cdot \left( 2 \cdot e^{-\frac{x}{2 \cdot a}} - 1 \right)}{2 \cdot a \cdot \left( e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}} + 1 \right)^3}$$

For the pressure  $\frac{\partial}{\partial x} p = -\rho \cdot a_x - \rho \cdot g_x = -\frac{\rho \cdot u_0^2 \cdot e^{-\frac{x}{2 \cdot a}} \cdot \left( 2 \cdot e^{-\frac{x}{2 \cdot a}} - 1 \right)}{2 \cdot a \cdot \left( e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}} + 1 \right)^3}$

and

$$dp = \frac{\partial}{\partial x} p \cdot dx \quad p - p_i = \int_0^x \frac{\partial}{\partial x} p \, dx = \int_0^x \frac{\rho \cdot u_0^2 \cdot e^{-\frac{x}{2 \cdot a}} \cdot \left(2 \cdot e^{-\frac{x}{2 \cdot a}} - 1\right)}{2 \cdot a \cdot \left(e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}} + 1\right)^3} dx$$

This is a tricky integral, so instead consider the following:  $\frac{\partial}{\partial x} p = -\rho \cdot a_x = -\rho \cdot u \cdot \frac{\partial}{\partial x} u = -\frac{1}{2} \cdot \rho \cdot \frac{\partial}{\partial x} (u^2)$


Hence



$$p - p_i = \int_0^x \frac{\partial}{\partial x} p \, dx = -\frac{\rho}{2} \cdot \int_0^x \frac{\partial}{\partial x} (u^2) \, dx = \frac{\rho}{2} \cdot (u(x=0)^2 - u(x)^2)$$

$$p(x) = p_0 + \frac{\rho}{2} \cdot (u_0^2 - u(x)^2) \quad \text{which we recognise as the Bernoulli equation!}$$

$$p(x) = p_0 + \frac{\rho \cdot u_0^2}{2} \cdot \left[ 1 - \left[ \frac{1}{\left( \frac{1 + e^{-\frac{x}{a}} - e^{-\frac{x}{2 \cdot a}}}{2} \right)^2} \right] \right]$$

The following plots can be done in *Excel*





## Problem 6.18

[Difficulty: 3]

**6.18** A nozzle for an incompressible, inviscid fluid of density  $\rho = 1000 \text{ kg/m}^3$  consists of a converging section of pipe. At the inlet the diameter is  $D_i = 100 \text{ mm}$ , and at the outlet the diameter is  $D_o = 20 \text{ mm}$ . The nozzle length is  $L = 500 \text{ mm}$ , and the diameter decreases linearly with distance  $x$  along the nozzle. Derive and plot the acceleration of a fluid particle, assuming uniform flow at each section, if the speed at the inlet is  $V_i = 1 \text{ m/s}$ . Plot the pressure gradient through the nozzle, and find its maximum absolute value. If the pressure gradient must be no greater than  $5 \text{ MPa/m}$  in absolute value, how long would the nozzle have to be?

**Given:** Nozzle geometry

**Find:** Acceleration of fluid particle; Plot; Plot pressure gradient; find  $L$  such that pressure gradient  $< 5 \text{ MPa/m}$  in absolute value

**Solution:**

The given data is  $D_i = 0.1 \cdot \text{m}$        $D_o = 0.02 \cdot \text{m}$        $L = 0.5 \cdot \text{m}$        $V_i = 1 \cdot \frac{\text{m}}{\text{s}}$        $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$

For a linear decrease in diameter  $D(x) = D_i + \frac{D_o - D_i}{L} \cdot x$

From continuity  $Q = V \cdot A = V \cdot \frac{\pi}{4} \cdot D^2 = V_i \cdot \frac{\pi}{4} \cdot D_i^2$        $Q = 0.00785 \frac{\text{m}^3}{\text{s}}$

Hence  $V(x) \cdot \frac{\pi}{4} \cdot D(x)^2 = Q$        $V(x) = \frac{4 \cdot Q}{\pi \cdot \left( D_i + \frac{D_o - D_i}{L} \cdot x \right)^2}$

or  $V(x) = \frac{V_i}{\left( 1 + \frac{D_o - D_i}{L \cdot D_i} \cdot x \right)^2}$

The governing equation for this flow is  $\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial p}{\partial x}$       (6.2a)

or, for steady 1D flow, in the notation of the problem

$$a_x = V \cdot \frac{d}{dx} V = \frac{V_i}{\left( 1 + \frac{D_o - D_i}{L \cdot D_i} \cdot x \right)^2} \cdot \frac{d}{dx} \frac{V_i}{\left( 1 + \frac{D_o - D_i}{L \cdot D_i} \cdot x \right)^2} \quad a_x(x) = - \frac{2 \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot L \cdot \left[ 1 + \frac{(D_o - D_i)}{D_i \cdot L} \cdot x \right]^5}$$

This is plotted in the associated *Excel* workbook

From Eq. 6.2a, pressure gradient is

$$\frac{\partial p}{\partial x} = -\rho \cdot a_x \quad \frac{\partial p}{\partial x} = \frac{2 \cdot \rho \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot L \cdot \left[ 1 + \frac{(D_o - D_i)}{D_i \cdot L} \cdot x \right]^5}$$

This is also plotted in the associated *Excel* workbook. Note that the pressure gradient is always negative: separation is unlikely to occur in the nozzle

At the inlet  $\frac{\partial}{\partial x} p = -3.2 \cdot \frac{\text{kPa}}{\text{m}}$

At the exit  $\frac{\partial}{\partial x} p = -10 \cdot \frac{\text{MPa}}{\text{m}}$

To find the length  $L$  for which the absolute pressure gradient is no more than 5 MPa/m, we need to solve

$$\left| \frac{\partial}{\partial x} p \right| \leq 5 \cdot \frac{\text{MPa}}{\text{m}} = \frac{2 \cdot \rho \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot L \cdot \left[ 1 + \frac{(D_o - D_i)}{D_i \cdot L} \cdot x \right]^5}$$

with  $x = L$  m (the largest pressure gradient is at the outlet)

Hence  $L \geq \frac{2 \cdot \rho \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot \left( \frac{D_o}{D_i} \right)^5 \cdot \left| \frac{\partial}{\partial x} p \right|}$   $L \geq 1 \cdot \text{m}$

This result is also obtained using *Goal Seek* in the *Excel* workbook

From *Excel*


$x$ (m)	$a$ (m/s <sup>2</sup> )	$dp/dx$ (kPa/m)
0.000	3.20	-3.20
0.050	4.86	-4.86
0.100	7.65	-7.65
0.150	12.6	-12.6
0.200	22.0	-22.0
0.250	41.2	-41.2
0.300	84.2	-84.2
0.350	194	-194
0.400	529	-529
0.420	843	-843
0.440	1408	-1408
0.460	2495	-2495
0.470	3411	-3411
0.480	4761	-4761
0.490	6806	-6806
0.500	10000	-10000

For the length  $L$  required for the pressure gradient to be less than 5 MPa/m (abs) use *Goal Seek*


$L = 1.00$  m

$x$ (m)	$dp/dx$ (kPa/m)
1.00	-5000

### Acceleration Through A Nozzle



### Pressure Gradient Along A Nozzle



## Problem 6.19

[Difficulty: 3]

**6.19** A diffuser for an incompressible, inviscid fluid of density  $\rho = 1000 \text{ kg/m}^3$  consists of a diverging section of pipe. At the inlet the diameter is  $D_i = 0.25 \text{ m}$ , and at the outlet the diameter is  $D_o = 0.75 \text{ m}$ . The diffuser length is  $L = 1 \text{ m}$ , and the diameter increases linearly with distance  $x$  along the diffuser. Derive and plot the acceleration of a fluid particle, assuming uniform flow at each section, if the speed at the inlet is  $V_i = 5 \text{ m/s}$ . Plot the pressure gradient through the diffuser, and find its maximum value. If the pressure gradient must be no greater than  $25 \text{ kPa/m}$ , how long would the diffuser have to be?

**Given:** Diffuser geometry

**Find:** Acceleration of a fluid particle; plot it; plot pressure gradient; find  $L$  such that pressure gradient is less than  $25 \text{ kPa/m}$

**Solution:**

The given data is  $D_i = 0.25 \text{ m}$        $D_o = 0.75 \text{ m}$        $L = 1 \text{ m}$        $V_i = 5 \frac{\text{m}}{\text{s}}$        $\rho = 1000 \frac{\text{kg}}{\text{m}^3}$

For a linear increase in diameter  $D(x) = D_i + \frac{D_o - D_i}{L} \cdot x$

From continuity  $Q = V \cdot A = V \cdot \frac{\pi}{4} \cdot D^2 = V_i \cdot \frac{\pi}{4} \cdot D_i^2$        $Q = 0.245 \frac{\text{m}^3}{\text{s}}$

Hence  $V(x) \cdot \frac{\pi}{4} \cdot D(x)^2 = Q$        $V(x) = \frac{4Q}{\pi \cdot \left( D_i + \frac{D_o - D_i}{L} \cdot x \right)^2}$       or       $V(x) = \frac{V_i}{\left( 1 + \frac{D_o - D_i}{L \cdot D_i} \cdot x \right)^2}$

The governing equation for this flow is

$$\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial p}{\partial x} \quad (6.2a)$$

or, for steady 1D flow, in the notation of the problem  $a_x = V \cdot \frac{d}{dx} V = \frac{V_i}{\left( 1 + \frac{D_o - D_i}{L \cdot D_i} \cdot x \right)^2} \cdot \frac{d}{dx} \frac{V_i}{\left( 1 + \frac{D_o - D_i}{L \cdot D_i} \cdot x \right)^2}$

Hence  $a_x(x) = -\frac{2 \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot L \cdot \left[ 1 + \frac{(D_o - D_i)}{D_i \cdot L} \cdot x \right]^5}$

This can be plotted in *Excel* (see below)

From Eq. 6.2a, pressure gradient is  $\frac{\partial}{\partial x} p = -\rho \cdot a_x$        $\frac{\partial}{\partial x} p = \frac{2 \cdot \rho \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot L \cdot \left[ 1 + \frac{(D_o - D_i)}{D_i \cdot L} \cdot x \right]^5}$

This can also be plotted in *Excel*. Note that the pressure gradient is adverse: separation is likely to occur in the diffuser, and occur near the entrance

At the inlet  $\frac{\partial}{\partial x} p = 100 \cdot \frac{\text{kPa}}{\text{m}}$                       At the exit  $\frac{\partial}{\partial x} p = 412 \cdot \frac{\text{Pa}}{\text{m}}$

To find the length  $L$  for which the pressure gradient is no more than 25 kPa/m, we need to solve

$$\frac{\partial}{\partial x} p \leq 25 \cdot \frac{\text{kPa}}{\text{m}} = \frac{2 \cdot \rho \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot L \cdot \left[ 1 + \frac{(D_o - D_i)}{D_i \cdot L} \cdot x \right]^5}$$

with  $x = 0$  m (the largest pressure gradient is at the inlet)

Hence  $L \geq \frac{2 \cdot \rho \cdot V_i^2 \cdot (D_o - D_i)}{D_i \cdot \frac{\partial}{\partial x} p}$                        $L \geq 4 \cdot \text{m}$

This result is also obtained using *Goal Seek* in *Excel*.

In *Excel*:

$D_i = 0.25$  m  
 $D_o = 0.75$  m  
 $L = 1$  m  
 $V_i = 5$  m/s  
 $\rho = 1000$  kg/m<sup>3</sup>


$x$ (m)	$a$ (m/s <sup>2</sup> )	$dp/dx$ (kPa/m)
0.00	-100	100
0.05	-62.1	62.1
0.10	-40.2	40.2
0.15	-26.9	26.93
0.20	-18.59	18.59
0.25	-13.17	13.17
0.30	-9.54	9.54
0.40	-5.29	5.29
0.50	-3.125	3.125
0.60	-1.940	1.940
0.70	-1.256	1.256
0.80	-0.842	0.842
0.90	-0.581	0.581
1.00	-0.412	0.412

For the length  $L$  required for the pressure gradient to be less than 25 kPa/m use *Goal Seek*


$L = 4.00$  m

$x$ (m)	$dp/dx$ (kPa/m)
0.0	25.0

### Acceleration Through a Diffuser




### Pressure Gradient Along A Diffuser



## Problem 6.20

[Difficulty: 4]

**6.20** Consider the flow of Problem 5.48. Evaluate the magnitude and direction of the net pressure force that acts on the upper plate between  $r_i$  and  $R$ , if  $r_i = R/2$ .




Solution:

Basic equations:  $\vec{p}\vec{a} - \nabla p = \rho \frac{d\vec{v}}{dt}$   $\vec{F} = - \int p d\vec{A}$

- Assumptions: (1) incompressible flow  
 (2) steady flow  
 (3) frictionless flow  
 (4) uniform flow at each section.

To determine the pressure distribution  $p(r)$ , apply Eulers equation in the  $r$  direction



$$-\frac{\partial p}{\partial r} + \cancel{\rho \frac{dv_r}{dt}} = \rho a_r = \rho v_r \frac{dv_r}{dr}$$

$$\frac{\partial p}{\partial r} = -\rho v_r \frac{dv_r}{dr} = -\rho v \frac{R}{r} \frac{d}{dr} \left( v \frac{R}{r} \right) = \rho v \frac{R}{r} \frac{vR}{r^2}$$

$$\frac{dp}{dr} = \rho v^2 \frac{R}{r^3}$$

$$dp = \rho v^2 \frac{R}{r^3} dr$$

Integrating we obtain


$$p - p_{atm} = \int_{atm}^r dp = \rho v^2 R \int_R^r r^{-3} dr = \rho v^2 R \left[ -\frac{1}{2r^2} \right]_R^r = \frac{1}{2} \rho v^2 R^2 \left[ \frac{1}{R^2} - \frac{1}{r^2} \right]$$

$$\begin{aligned} F_z &= \int_{atm}^R (p - p_{atm}) dA = \int_{atm}^R \frac{1}{2} \rho v^2 R^2 \left[ \frac{1}{R^2} - \frac{1}{r^2} \right] 2\pi r dr = \rho v^2 R^2 \pi \left[ \frac{r^2}{2R^2} - \ln r \right]_{atm}^R \\ &= \rho v^2 R^2 \pi \left[ \frac{1}{2R^2} (R^2 - atm^2) - \ln \frac{R}{atm} \right] = \rho v^2 R^2 \pi [0.375 - \ln 2] = -0.318 \pi \rho v^2 R^2 \end{aligned}$$

$$= -0.318 \pi \times 1.23 \frac{kg}{m^3} \times (15 \frac{m}{s})^2 \times (0.075)^2 m^2 \times \frac{N \cdot s^2}{kg \cdot m}$$

$$F_z = -1.56 N \quad (F_z < 0, \text{ so force acts down})$$

6.21 Consider again the flow field of Problem 5.65. Assume the flow is incompressible with  $\rho = 1.23 \text{ kg/m}^3$  and friction is negligible. Further assume the vertical air flow velocity is  $v_0 = 15 \text{ mm/s}$ , the half-width of the cavity is  $L = 22 \text{ mm}$ , and its height is  $h = 1.2 \text{ mm}$ . Calculate the pressure gradient at  $(x, y) = (L, h)$ . Obtain an equation for the flow streamlines in the cavity.



Solution:

Euler's equation,  $\rho \vec{g} - \nabla p = \rho \frac{D\vec{v}}{Dt}$ , can be used to determine the pressure gradient for incompressible frictionless flow.

We need first to determine the velocity field. With  $u = v_0 \frac{x}{L}$ , for 2-D, incompressible flow we can use the continuity equation to determine  $v$ .

$$\text{Since } \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0, \text{ then } \frac{\partial v}{\partial y} = -\frac{\partial u}{\partial x} = -\frac{\partial}{\partial x} \left( \frac{v_0 x}{L} \right) = -\frac{v_0}{L}$$

$$\text{Then } v = \int \frac{\partial v}{\partial y} dy + f(x) = -\frac{v_0}{L} y + f(x)$$

$$\text{But } v = v_0 \text{ at } y=0 \text{ and hence } f(x) = v_0 \text{ and } v = v_0 \left( 1 - \frac{y}{L} \right)$$

$$\text{Then } \nabla p = \rho \vec{g} - \rho \frac{D\vec{v}}{Dt} = \rho \left[ \vec{g} - u \frac{\partial \vec{v}}{\partial x} - v \frac{\partial \vec{v}}{\partial y} \right] = \rho \left[ -g \hat{j} - \frac{v_0 x}{L} \left( \frac{v_0}{L} \hat{i} \right) - v_0 \left( 1 - \frac{y}{L} \right) \left( -\frac{v_0}{L} \hat{j} \right) \right]$$

$$\nabla p = \rho \left[ -g \hat{j} - \frac{v_0^2 x}{L^2} \hat{i} - \frac{v_0^2}{L} \left( 1 - \frac{y}{L} \right) \hat{j} \right]$$

At the point  $(x, y) = (L, h)$

$$\nabla p = \rho \left[ -\frac{v_0^2}{L} \hat{i} - g \hat{j} \right]$$

$$= 1.23 \frac{\text{kg}}{\text{m}^3} \left[ -(15)^2 \frac{\text{m}^2}{\text{s}^2} \cdot \frac{1}{0.022 \text{ m}} \hat{i} - 9.81 \frac{\text{m}}{\text{s}^2} \hat{j} \right] \cdot \frac{\text{N}}{\text{m}^3}$$

$$\nabla p|_{L,h} = -4.23 \hat{i} - 12.1 \hat{j} \text{ N/m}^3$$

(b) The slope of the streamlines is given by  $\frac{dy}{dx} = \frac{v}{u}$


$$\therefore \frac{dy}{dx} = \frac{v_0 \left( 1 - \frac{y}{L} \right)}{\frac{v_0 x}{L}} \text{ and separating variables, we can write}$$

$$\frac{d \left( \frac{y}{L} \right)}{\left( 1 - \frac{y}{L} \right)} = \frac{d \left( \frac{x}{L} \right)}{\frac{x}{L}} \text{ then integrating we obtain}$$

$$-\ln \left( 1 - \frac{y}{L} \right) = \ln \frac{x}{L} - \ln C$$

$$\text{or } \frac{x}{L} \left( 1 - \frac{y}{L} \right) = \text{constant}$$

6.22 A liquid layer separates two plane surfaces as shown. The lower surface is stationary; the upper surface moves downward at constant speed  $V$ . The moving surface has width  $w$ , perpendicular to the plane of the diagram, and  $w \gg L$ . The incompressible liquid layer, of density  $\rho$ , is squeezed from between the surfaces. Assume the flow is uniform at any cross section and neglect viscosity as a first approximation. Use a suitably chosen control volume to show that  $u = Vx/b$  within the gap, where  $b = b_0 - Vt$ . Obtain an algebraic expression for the acceleration of a fluid particle located at  $x$ . Determine the pressure gradient,  $\partial p/\partial x$ , in the liquid layer. Find the pressure distribution,  $p(x)$ . Obtain an expression for the net pressure force that acts on the upper (moving) flat surface.



Solution:

Basic equations :  $0 = \frac{\partial}{\partial t} \int_{\omega} \rho dV + \int_{\partial \omega} \rho \vec{v} \cdot d\vec{A}$   
 $-\nabla p + \rho \vec{g} = \rho \frac{D\vec{v}}{Dt}$        $\vec{F} = - \int p d\vec{A}$

(a) For the deformable CV shown

$$0 = \frac{\partial}{\partial t} \int_0^y \rho w x dy + \rho w x y = \rho w x \frac{dy}{dt} + \rho w x y$$

But  $dy/dt = -V$  and hence  $u = \frac{Vx}{b}$

If  $y = b_0$  at  $t=0$ , then  $y = b = b_0 - Vt$  at any time  $t$

$$\therefore u = \frac{Vx}{b} \quad u(t)$$

(b)  $a_x = \frac{Du}{Dt} = u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} + \frac{\partial u}{\partial t}$

Assumptions: (i)  $u = u(x)$ ,  $w = 0$

$$a_x = \frac{Vx}{b} \left( \frac{V}{b} \right) + \frac{\partial u}{\partial b} \frac{db}{dt} = \frac{V^2 x}{b^2} + \left( -\frac{Vx}{b^2} \right) (-V) = \frac{2V^2 x}{b^2} \quad a_x$$

(c) From Euler's equation in the  $x$  direction with  $g_x = 0$

$$\frac{\partial p}{\partial x} = -\rho a_x = -\frac{2\rho V^2 x}{b^2} \quad \frac{\partial p}{\partial x}$$

(d)  $p - p_{atm} = \int_x^L \frac{\partial p}{\partial x} dx = \int_x^L -\frac{2\rho V^2}{b^2} x dx = -\frac{\rho V^2 x^2}{b^2} \Big|_x^L = \frac{\rho V^2 L^2}{b^2} \left[ 1 - \left( \frac{x}{L} \right)^2 \right] \quad p(x)$


(e)  $F_{\text{net}} = \int (p - p_{atm}) dA = 2 \int_0^L \frac{\rho V^2 L^2}{b^2} \left[ 1 - \left( \frac{x}{L} \right)^2 \right] w dx$   
 $= 2 \int_0^L \frac{\rho V^2 L^3}{b^2} \left[ 1 - \left( \frac{x}{L} \right)^2 \right] w d\left( \frac{x}{L} \right) = \frac{2\rho V^2 L^3 w}{b^2} \left[ \left( \frac{x}{L} \right) - \frac{1}{3} \left( \frac{x}{L} \right)^3 \right]_0^L$

$$\vec{F}_{\text{net}} = \frac{4\rho V^2 L^3 w}{3b^2} \quad (\text{upward, since } F_y > 0) \quad \vec{F}_{\text{net}}$$

## Problem 6.23

[Difficulty: 4]

**6.23** A rectangular computer chip floats on a thin layer of air,  $h = 0.5$  mm thick, above a porous surface. The chip width is  $b = 40$  mm, as shown. Its length,  $L$ , is very long in the direction perpendicular to the diagram. There is no flow in the  $z$  direction. Assume flow in the  $x$  direction in the gap under the chip is uniform. Flow is incompressible, and frictional effects may be neglected. Use a suitably chosen control volume to show that  $U(x) = qx/h$  in the gap. Find a general expression for the (2D) acceleration of a fluid particle in the gap in terms of  $q, h, x,$  and  $y$ . Obtain an expression for the pressure gradient  $\partial p/\partial x$ . Assuming atmospheric pressure on the chip upper surface, find an expression for the net pressure force on the chip; is it directed upward or downward? Explain. Find the required flow rate  $q$  ( $\text{m}^3/\text{s}/\text{m}^2$ ) and the maximum velocity, if the mass per unit length of the chip is  $0.005$  kg/m. Plot the pressure distribution as part of your explanation of the direction of the net force.



**Given:** Rectangular chip flow

**Find:** Velocity field; acceleration; pressure gradient; net force; required flow rate; plot pressure

**Solution:**

Basic equations  $\sum_{CS} (\vec{V} \cdot \vec{A}) = 0$        $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$

$$\bar{a}_p = \frac{D\bar{V}}{Dt} = \underbrace{u \frac{\partial \bar{V}}{\partial x} + v \frac{\partial \bar{V}}{\partial y} + w \frac{\partial \bar{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \bar{V}}{\partial t}}_{\text{local acceleration}} \quad \rho \frac{D\bar{V}}{Dt} = \rho \bar{g} - \nabla p$$

total acceleration of a particle      convective acceleration      local acceleration

The given data is  $\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$        $p_{\text{atm}} = 101 \cdot \text{kPa}$        $h = 0.5 \cdot \text{mm}$        $b = 40 \cdot \text{mm}$        $M_{\text{length}} = 0.005 \cdot \frac{\text{kg}}{\text{m}}$

Assuming a CV that is from the centerline to any point  $x$ , and noting that  $q$  is inflow per unit area, continuity leads to

$$q \cdot x \cdot L = U \cdot h \cdot L \quad \text{or} \quad u(x) = U(x) = q \cdot \frac{x}{h}$$

For acceleration we will need the vertical velocity  $v$ ; we can use

$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0 \quad \text{or} \quad \frac{\partial}{\partial y} v = -\frac{\partial}{\partial x} u = -\frac{du}{dx} = -\frac{d}{dx} \left( q \cdot \frac{x}{h} \right) = -\frac{q}{h}$$

Hence  $v(y=y) - v(y=0) = -\int_0^y \frac{q}{h} dy = -q \cdot \frac{y}{h}$

But  $v(y=0) = q$  so  $v(y) = q \cdot \left( 1 - \frac{y}{h} \right)$

For the  $x$  acceleration  $a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u$        $a_x = q \cdot \frac{x}{h} \cdot \left( \frac{q}{h} \right) + q \cdot \left( 1 - \frac{y}{h} \right) \cdot (0)$        $a_x = \frac{q^2}{h^2} \cdot x$

For the y acceleration  $a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v$   $a_y = q \cdot \frac{x}{h} \cdot (0) + q \cdot \left(1 - \frac{y}{h}\right) \cdot \left(-\frac{q}{h}\right)$   $a_x = \frac{q^2}{h} \cdot \left(\frac{y}{h} - 1\right)$

For the pressure gradient we use x and y momentum (Euler equation)  $\rho \cdot \frac{Du}{Dx} = \rho \cdot \left(u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u\right) = \rho \cdot a_x = -\frac{\partial}{\partial x} p$

Hence  $\frac{\partial}{\partial x} p = -\rho \cdot \frac{q^2}{h^2} \cdot x$

Also  $\rho \cdot \frac{Dv}{Dx} = \rho \cdot \left(u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v\right) = \rho \cdot a_y = -\frac{\partial}{\partial y} p$   $\frac{\partial}{\partial y} p = \rho \cdot \frac{q^2}{h} \cdot \left(1 - \frac{y}{h}\right)$

For the pressure distribution, integrating from the outside edge ( $x = b/2$ ) to any point x

$$p(x = x) - p\left(x = \frac{b}{2}\right) = p(x) - p_{atm} = \int_{\frac{b}{2}}^x \frac{\partial}{\partial x} p \, dx = \int_{\frac{b}{2}}^x -\rho \cdot \frac{q^2}{h^2} \cdot x \, dx = -\rho \cdot \frac{q^2}{2 \cdot h^2} \cdot x^2 + \rho \cdot \frac{q^2}{8 \cdot h^2} \cdot b^2$$

$$p(x) = p_{atm} + \rho \cdot \frac{q^2 \cdot b^2}{8 \cdot h^2} \cdot \left[1 - 4 \cdot \left(\frac{x}{b}\right)^2\right]$$

For the net force we need to integrate this ... actually the gage pressure, as this pressure is opposed on the outer surface by  $p_{atm}$

$$p_g(x) = \frac{\rho \cdot q^2 \cdot b^2}{8 \cdot h^2} \cdot \left[1 - 4 \cdot \left(\frac{x}{b}\right)^2\right]$$

$$F_{net} = 2 \cdot L \cdot \int_0^{\frac{b}{2}} p_g(x) \, dx = 2 \cdot L \cdot \int_0^{\frac{b}{2}} \frac{\rho \cdot q^2 \cdot b^2}{8 \cdot h^2} \cdot \left[1 - 4 \cdot \left(\frac{x}{b}\right)^2\right] \, dx = \frac{\rho \cdot q^2 \cdot b^2 \cdot L}{4 \cdot h^2} \cdot \left(\frac{b}{2} - \frac{1}{3} \cdot \frac{b}{2}\right)$$


$$F_{net} = \frac{\rho \cdot q^2 \cdot b^3 \cdot L}{12 \cdot h^2}$$

The weight of the chip must balance this force  $M \cdot g = M_{length} \cdot L \cdot g = F_{net} = \frac{\rho \cdot q^2 \cdot b^3 \cdot L}{12 \cdot h^2}$  or  $M_{length} \cdot g = \frac{\rho \cdot q^2 \cdot b^3}{12 \cdot h^2}$

Solving for q for the given mass/length  $q = \sqrt{\frac{12 \cdot h^2 \cdot g \cdot M_{length}}{\rho \cdot b^3}}$   $q = 0.0432 \cdot \frac{m^3}{m^2}$

The maximum speed  $U_{max} = u\left(x = \frac{b}{2}\right) = q \cdot \frac{b}{2}$   $U_{max} = \frac{b \cdot q}{2 \cdot h}$   $U_{max} = 1.73 \frac{m}{s}$

The following plot can be done in *Excel*  $p_g(x) = \frac{\rho \cdot q^2 \cdot b^2}{8 \cdot h^2} \cdot \left[1 - 4 \cdot \left(\frac{x}{b}\right)^2\right]$




The net force is such that the chip is floating on air due to a Bernoulli effect: the speed is maximum at the edges and zero at the center; pressure has the opposite trend - pressure is minimum ( $p_{\text{atm}}$ ) at the edges and maximum at the center.

### Problem 6.24

[Difficulty: 3]

6.24 Heavy weights can be moved with relative ease on air cushions by using a load pallet as shown. Air is supplied from the plenum through porous surface  $AB$ . It enters the gap vertically at uniform speed,  $q$ . Once in the gap, all air flows in the positive  $x$  direction (there is no flow across the plane at  $x=0$ ). Assume air flow in the gap is incompressible and uniform at each cross section, with speed  $u(x)$ , as shown in the enlarged view. Although the gap is narrow ( $h \ll L$ ), neglect frictional effects as a first approximation. Use a suitably chosen control volume to show that  $u(x) = qx/h$  in the gap. Calculate the acceleration of a fluid particle in the gap. Evaluate the pressure gradient,  $\partial p/\partial x$ , and sketch the pressure distribution within the gap. Be sure to indicate the pressure at  $x=L$ .



Solution: Choose a CV in the gap, from 0 to  $x$ , as shown.

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

$$a_x = u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} + \frac{\partial u}{\partial t} - \frac{\partial p}{\partial x} + \rho g_x = \rho a_x$$

- Assumptions: (1) Steady flow  
 (2) Incompressible flow  
 (3) Uniform flow at each section  
 (4) No variation with  $z$   
 (5) Horizontal, so  $g_x = 0$


From continuity,

$$0 = \{-\rho q w(x)\} + \{\rho u(x) w h\} \text{ so } u(x) = q \frac{x}{h}$$

The acceleration is  $a_x = (q \frac{x}{h})(q \frac{1}{h}) = q \frac{x}{h^2}$

The pressure gradient is  $\frac{\partial p}{\partial x} = -\rho a_x = -\rho q \frac{x}{h^2}$

Sketching:



Sketch

## Problem 6.25

[Difficulty: 4]

**6.25** A velocity field is given by  $\vec{V} = [Ax^3 + Bxy^2]\hat{i} + [Ay^3 + Bx^2y]\hat{j}$ ;  $A = 0.2 \text{ m}^{-2} \cdot \text{s}^{-1}$ ,  $B$  is a constant, and the coordinates are measured in meters. Determine the value and units for  $B$  if this velocity field is to represent an incompressible flow. Calculate the acceleration of a fluid particle at point  $(x, y) = (2, 1)$ . Evaluate the component of particle acceleration normal to the velocity vector at this point.

**Given:** Velocity field

**Find:** Constant  $B$  for incompressible flow; Acceleration of particle at  $(2,1)$ ; acceleration normal to velocity at  $(2,1)$

**Solution:**

Basic equations

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0 \qquad \bar{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

For this flow

$$u(x, y) = A \cdot x^3 + B \cdot x \cdot y^2 \qquad v(x, y) = A \cdot y^3 + B \cdot x^2 \cdot y$$

$$\frac{\partial}{\partial x} u(x, y) + \frac{\partial}{\partial y} v(x, y) = \frac{\partial}{\partial x} (A \cdot x^3 + B \cdot x \cdot y^2) + \frac{\partial}{\partial y} (A \cdot y^3 + B \cdot x^2 \cdot y) = 0$$

$$\frac{\partial}{\partial x} u(x, y) + \frac{\partial}{\partial y} v(x, y) = (3 \cdot A + B) \cdot (x^2 + y^2) = 0 \qquad \text{Hence} \qquad B = -3 \cdot A \qquad B = -0.6 \frac{1}{\text{m}^2 \cdot \text{s}}$$

We can write

$$u(x, y) = A \cdot x^3 - 3 \cdot A \cdot x \cdot y^2 \qquad v(x, y) = A \cdot y^3 - 3 \cdot A \cdot x^2 \cdot y$$

Hence for  $a_x$

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = (A \cdot x^3 - 3 \cdot A \cdot x \cdot y^2) \cdot \frac{\partial}{\partial x} (A \cdot x^3 - 3 \cdot A \cdot x \cdot y^2) + (A \cdot y^3 - 3 \cdot A \cdot x^2 \cdot y) \cdot \frac{\partial}{\partial y} (A \cdot x^3 - 3 \cdot A \cdot x \cdot y^2)$$

$$a_x = 3 \cdot A^2 \cdot x \cdot (x^2 + y^2)^2$$

For  $a_y$

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = (A \cdot x^3 - 3 \cdot A \cdot x \cdot y^2) \cdot \frac{\partial}{\partial x} (A \cdot y^3 - 3 \cdot A \cdot x^2 \cdot y) + (A \cdot y^3 - 3 \cdot A \cdot x^2 \cdot y) \cdot \frac{\partial}{\partial y} (A \cdot y^3 - 3 \cdot A \cdot x^2 \cdot y)$$

$$a_y = 3 \cdot A^2 \cdot y \cdot (x^2 + y^2)^2$$

Hence at  $(2,1)$

$$a_x = 3 \cdot \left( \frac{0.2}{\text{m}^2 \cdot \text{s}} \right)^2 \times 2 \cdot \text{m} \times [(2 \cdot \text{m})^2 + (1 \cdot \text{m})^2]^2 \qquad a_x = 6.00 \frac{\text{m}}{\text{s}^2}$$

$$a_y = 3 \cdot \left( \frac{0.2}{\text{m}^2 \cdot \text{s}} \right)^2 \times 1 \cdot \text{m} \times [(2 \cdot \text{m})^2 + (1 \cdot \text{m})^2]^2 \qquad a_y = 3.00 \frac{\text{m}}{\text{s}^2}$$


$$a = \sqrt{a_x^2 + a_y^2} \qquad a = 6.71 \frac{\text{m}}{\text{s}^2}$$

We need to find the component of acceleration normal to the velocity vector

At (2,1) the velocity vector is at angle

$$\theta_{\text{vel}} = \text{atan}\left(\frac{v}{u}\right) = \text{atan}\left(\frac{A \cdot y^3 - 3 \cdot A \cdot x^2 \cdot y}{A \cdot x^3 - 3 \cdot A \cdot x \cdot y^2}\right)$$

$$\theta_{\text{vel}} = \text{atan}\left(\frac{1^3 - 3 \cdot 2^2 \cdot 1}{2^3 - 3 \cdot 2 \cdot 1^2}\right) \quad \theta_{\text{vel}} = -79.7 \cdot \text{deg}$$



At (1,2) the acceleration vector is at angle

$$\theta_{\text{accel}} = \text{atan}\left(\frac{a_y}{a_x}\right) \quad \theta_{\text{accel}} = \text{atan}\left(\frac{1}{2}\right)$$

$$\theta_{\text{accel}} = 26.6 \cdot \text{deg}$$

Hence the angle between the acceleration and velocity vectors is

$$\Delta\theta = \theta_{\text{accel}} - \theta_{\text{vel}}$$

$$\Delta\theta = 106 \cdot \text{deg}$$

The component of acceleration normal to the velocity is then

$$a_n = a \cdot \sin(\Delta\theta) = 6.71 \cdot \frac{\text{m}}{\text{s}^2} \cdot \sin(106 \cdot \text{deg}) \quad a_n = 6.45 \cdot \frac{\text{m}}{\text{s}^2}$$

**6.26** The  $y$  component of velocity in a two-dimensional incompressible flow field is given by  $v = -Axy$ , where  $v$  is in  $m/s$ , the coordinates are measured in meters, and  $A = 1 \text{ m}^{-1} \cdot \text{s}^{-1}$ . There is no velocity component or variation in the  $z$  direction. Calculate the acceleration of a fluid particle at point  $(x, y) = (1, 2)$ . Estimate the radius of curvature of the streamline passing through this point. Plot the streamline and show both the velocity vector and the acceleration vector on the plot. (Assume the simplest form of the  $x$  component of velocity.)

Solution:

For 2-D incompressible flow  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$ , so  $\frac{\partial u}{\partial x} = -\frac{\partial v}{\partial y}$

$$u = \int \frac{\partial u}{\partial x} dx + f(y) = \int -\frac{\partial v}{\partial y} dx + f(y) = \int (-Ay) dx + f(y) = \frac{A}{2}x^2 + f(y)$$

Choose the simplest solution,  $f(y) = 0$ , so  $u = \frac{A}{2}x^2$ . Here

$$\vec{v} = \frac{A}{2}x^2 \hat{i} - Axy \hat{j} = A \left( \frac{x^2}{2} \hat{i} - xy \hat{j} \right)$$

The acceleration of a fluid particle is

$$\vec{a}_p = u \frac{\partial \vec{v}}{\partial x} + v \frac{\partial \vec{v}}{\partial y} = \frac{A}{2}x^2 (Ax \hat{i} - Ay \hat{j}) - Axy(-Ax \hat{j})$$

$$\vec{a}_p = \frac{A^2}{2}x^3 \hat{i} + \frac{A^2}{2}xy^2 \hat{j} = \frac{A^2}{2} (x^3 \hat{i} + xy^2 \hat{j})$$

At the point  $(1, 2)$

$$\vec{a}_p = \frac{1}{2} \times (1) \frac{1}{1^2 \cdot 2^2} [ (1)^3 \text{ m}^3 \hat{i} + (1)^2 (2) \text{ m}^2 \hat{j} ] = 0.5 \hat{i} + \hat{j} \text{ m/s}^2 \leftarrow \vec{a}(1,2)$$

$$\vec{v} = \frac{1}{1 \cdot 2} \left[ \frac{1}{2} (1)^2 \text{ m}^2 \hat{i} - (1)(2) \text{ m}^2 \hat{j} \right] = 0.5 \hat{i} - 2 \hat{j} \text{ m/s}$$

The unit vector tangent to the streamline is

$$\hat{e}_t = \frac{\vec{v}}{|\vec{v}|} = \frac{0.5 \hat{i} - 2 \hat{j}}{[(0.5)^2 + (-2)^2]^{1/2}} = 0.243 \hat{i} - 0.970 \hat{j}$$

The unit vector normal to the streamline is

$$\hat{e}_n = \hat{e}_t \times \hat{k} = (0.243 \hat{i} - 0.970 \hat{j}) \times \hat{k} = -0.970 \hat{i} - 0.243 \hat{j}$$

The normal component of acceleration is

$$a_n = -\frac{v^2}{R} = \vec{a} \cdot \hat{e}_n = (0.5 \hat{i} + \hat{j}) \cdot (-0.970 \hat{i} - 0.243 \hat{j})$$

$$-\frac{v^2}{R} = -0.728 \text{ m/s}^2$$

$$R = \frac{v^2}{0.728} = \frac{4.25 \text{ m}^2/\text{s}^2}{0.728 \text{ m/s}^2} = 5.84 \text{ m} \leftarrow R(1,2)$$

The slope of the streamlines is given by

$$\left. \frac{dy}{dx} \right|_{se} = \frac{v}{u} = \frac{-Axy}{\frac{A}{2}x^2} = -\frac{2y}{x}$$

42-389 250 SHEETS PER CASE 5 SQUARE  
 42-389 100 RECYCLED WHITE 5 SQUARE  
 42-389 UNRECYCLED WHITE 5 SQUARE  
 MADE IN U.S.A.





## Problem 6.27

[Difficulty: 5]

**6.27** Consider the velocity field  $\vec{V} = A[x^4 - 6x^2y^2 + y^4]\hat{i} + B[x^3y - xy^3]\hat{j}$ ;  $A = 2 \text{ m}^{-3} \cdot \text{s}^{-1}$ ,  $B$  is a constant, and the coordinates are measured in meters. Find  $B$  for this to be an incompressible flow. Obtain the equation of the streamline through point  $(x, y) = (1, 2)$ . Derive an algebraic expression for the acceleration of a fluid particle. Estimate the radius of curvature of the streamline at  $(x, y) = (1, 2)$ .

**Given:** Velocity field

**Find:** Constant  $B$  for incompressible flow; Equation for streamline through  $(1,2)$ ; Acceleration of particle; streamline curvature

**Solution:**

Basic equations

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0 \qquad \bar{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$$

total acceleration of a particle

For this flow

$$u(x,y) = A \cdot (x^4 - 6x^2y^2 + y^4) \qquad v(x,y) = B \cdot (x^3y - xy^3)$$

$$\frac{\partial}{\partial x} u(x,y) + \frac{\partial}{\partial y} v(x,y) = \frac{\partial}{\partial x} [A \cdot (x^4 - 6x^2y^2 + y^4)] + \frac{\partial}{\partial y} [B \cdot (x^3y - xy^3)] = 0$$

$$\frac{\partial}{\partial x} u(x,y) + \frac{\partial}{\partial y} v(x,y) = B \cdot (x^3 - 3x \cdot y^2) + A \cdot (4x^3 - 12x \cdot y^2) = (4A + B) \cdot x \cdot (x^2 - 3y^2) = 0$$

Hence

$$B = -4A \qquad \qquad \qquad B = -8 \frac{1}{\text{m}^3 \cdot \text{s}}$$

Hence for  $a_x$

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u = A \cdot (x^4 - 6x^2y^2 + y^4) \cdot \frac{\partial}{\partial x} [A \cdot (x^4 - 6x^2y^2 + y^4)] + [-4A \cdot (x^3y - xy^3)] \cdot \frac{\partial}{\partial y} [A \cdot (x^4 - 6x^2y^2 + y^4)]$$

$$a_x = 4A^2 \cdot x \cdot (x^2 + y^2)^3$$

For  $a_y$

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v = A \cdot (x^4 - 6x^2y^2 + y^4) \cdot \frac{\partial}{\partial x} [-4A \cdot (x^3y - xy^3)] + [-4A \cdot (x^3y - xy^3)] \cdot \frac{\partial}{\partial y} [-4A \cdot (x^3y - xy^3)]$$

$$a_y = 4A^2 \cdot y \cdot (x^2 + y^2)^3$$

For a streamline

$$\frac{dy}{dx} = \frac{v}{u} \qquad \text{so} \qquad \frac{dy}{dx} = \frac{-4A \cdot (x^3y - xy^3)}{A \cdot (x^4 - 6x^2y^2 + y^4)} = -\frac{4 \cdot (x^3y - xy^3)}{(x^4 - 6x^2y^2 + y^4)}$$

Let

$$u = \frac{y}{x} \qquad \frac{du}{dx} = \frac{d\left(\frac{y}{x}\right)}{dx} = \frac{1}{x} \cdot \frac{dy}{dx} + y \cdot \frac{d\left(\frac{1}{x}\right)}{dx} = \frac{1}{x} \cdot \frac{dy}{dx} - \frac{y}{x^2} \qquad \text{so} \qquad \frac{dy}{dx} = x \cdot \frac{du}{dx} + u$$

Hence

$$\frac{dy}{dx} = x \cdot \frac{du}{dx} + u = -\frac{4 \cdot (x^3 \cdot y - x \cdot y^3)}{(x^4 - 6 \cdot x^2 \cdot y^2 + y^4)} = -\frac{4 \cdot (1 - u^2)}{\left(\frac{1}{u} - 6 \cdot u + \left(\frac{1}{u} - 6 \cdot u + u^3\right)\right)} u + \frac{4 \cdot (1 - u^2)}{\left(\frac{1}{u} - 6 \cdot u + u^3\right)}$$

$$x \cdot \frac{du}{dx} = \left[ u + \frac{4 \cdot (1 - u^2)}{\left(\frac{1}{u} - 6 \cdot u + u^3\right)} \right] = -\frac{u \cdot (u^4 - 10 \cdot u^2 + 5)}{u^4 - 6 \cdot u^2 + 1}$$

Separating variables

$$\frac{dx}{x} = -\frac{u^4 - 6 \cdot u^2 + 1}{u \cdot (u^4 - 10 \cdot u^2 + 5)} \cdot du \quad \ln(x) = -\frac{1}{5} \cdot \ln(u^5 - 10 \cdot u^3 + 5 \cdot u) + C$$

$$(u^5 - 10 \cdot u^3 + 5 \cdot u) \cdot x^5 = c \quad y^5 - 10 \cdot y^3 \cdot x^2 + 5 \cdot y \cdot x^4 = \text{const}$$

For the streamline through (1,2)  $y^5 - 10 \cdot y^3 \cdot x^2 + 5 \cdot y \cdot x^4 = -38$


Note that it would be MUCH easier to use the stream function method here!

To find the radius of curvature we use  $a_n = -\frac{V^2}{R}$  or  $|R| = \frac{V^2}{a_n}$

We need to find the component of acceleration normal to the velocity vector

At (1,2) the velocity vector is at angle  $\theta_{\text{vel}} = \text{atan}\left(\frac{v}{u}\right) = \text{atan}\left[-\frac{4 \cdot (x^3 \cdot y - x \cdot y^3)}{(x^4 - 6 \cdot x^2 \cdot y^2 + y^4)}\right]$

$$\theta_{\text{vel}} = \text{atan}\left[-\frac{4 \cdot (2 - 8)}{1 - 24 + 16}\right] \quad \theta_{\text{vel}} = -73.7 \cdot \text{deg}$$



At (1,2) the acceleration vector is at angle

$$\theta_{\text{accel}} = \text{atan}\left(\frac{a_y}{a_x}\right) = \text{atan}\left[\frac{4 \cdot A^2 \cdot y \cdot (x^2 + y^2)^3}{4 \cdot A^2 \cdot x \cdot (x^2 + y^2)^3}\right] = \text{atan}\left(\frac{y}{x}\right) \quad \theta_{\text{accel}} = \text{atan}\left(\frac{2}{1}\right) \quad \theta_{\text{accel}} = 63.4 \cdot \text{deg}$$

Hence the angle between the acceleration and velocity vectors is  $\Delta\theta = \theta_{\text{accel}} - \theta_{\text{vel}} \quad \Delta\theta = 137 \cdot \text{deg}$

The component of acceleration normal to the velocity is then  $a_n = a \cdot \sin(\Delta\theta)$  where  $a = \sqrt{a_x^2 + a_y^2}$

At (1,2)  $a_x = 4 \cdot A^2 \cdot x \cdot (x^2 + y^2)^3 = 500 \cdot \text{m}^7 \times A^2 = 500 \cdot \text{m}^7 \times \left(\frac{2}{\text{m}^3 \cdot \text{s}}\right)^2 = 2000 \cdot \frac{\text{m}}{\text{s}^2}$   $a_y = 4 \cdot A^2 \cdot y \cdot (x^2 + y^2)^3 = 4000 \cdot \frac{\text{m}}{\text{s}^2}$

$$a = \sqrt{2000^2 + 4000^2} \cdot \frac{\text{m}}{\text{s}^2} \quad a = 4472 \frac{\text{m}}{\text{s}^2} \quad a_n = a \cdot \sin(\Delta\theta) \quad a_n = 3040 \frac{\text{m}}{\text{s}^2}$$

$$u = A \cdot (x^4 - 6 \cdot x^2 \cdot y^2 + y^4) = -14 \cdot \frac{\text{m}}{\text{s}} \quad v = B \cdot (x^3 \cdot y - x \cdot y^3) = 48 \cdot \frac{\text{m}}{\text{s}} \quad V = \sqrt{u^2 + v^2} = 50 \cdot \frac{\text{m}}{\text{s}}$$

Then  $|R| = \frac{V^2}{a_n} \quad R = \left(50 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times \frac{1}{3040} \cdot \frac{\text{s}^2}{\text{m}} \quad R = 0.822 \text{ m}$

## Problem 6.28

[Difficulty: 2]

**6.28** The velocity field for a plane doublet is given in Table 6.2.  
Find an expression for the pressure gradient at any point  $(r, \theta)$ .

**Given:** Velocity field for doublet

**Find:** Expression for pressure gradient

**Solution:**

Basic equations

$$\rho a_r = \rho \left( \frac{\partial V_r}{\partial t} + V_r \frac{\partial V_r}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_r}{\partial \theta} + V_z \frac{\partial V_r}{\partial z} - \frac{V_\theta^2}{r} \right) = \rho g_r - \frac{\partial p}{\partial r}$$

$$\rho a_\theta = \rho \left( \frac{\partial V_\theta}{\partial t} + V_r \frac{\partial V_\theta}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_\theta}{\partial \theta} + V_z \frac{\partial V_\theta}{\partial z} + \frac{V_r V_\theta}{r} \right) = \rho g_\theta - \frac{1}{r} \frac{\partial p}{\partial \theta}$$

For this flow

$$V_r(r, \theta) = -\frac{\Lambda}{r^2} \cdot \cos(\theta) \quad V_\theta(r, \theta) = -\frac{\Lambda}{r^2} \cdot \sin(\theta) \quad V_z = 0$$

Hence for r momentum

$$\rho \cdot g_r - \frac{\partial p}{\partial r} = \rho \cdot \left( V_r \cdot \frac{\partial}{\partial r} V_r + \frac{V_\theta}{r} \cdot \frac{\partial}{\partial \theta} V_r - \frac{V_\theta^2}{r} \right)$$

Ignoring gravity

$$\frac{\partial p}{\partial r} = -\rho \cdot \left[ \left( -\frac{\Lambda}{r^2} \cdot \cos(\theta) \right) \cdot \frac{\partial}{\partial r} \left( -\frac{\Lambda}{r^2} \cdot \cos(\theta) \right) + \frac{\left( -\frac{\Lambda}{r^2} \cdot \sin(\theta) \right)}{r} \cdot \frac{\partial}{\partial \theta} \left( -\frac{\Lambda}{r^2} \cdot \cos(\theta) \right) - \frac{\left( -\frac{\Lambda}{r^2} \cdot \sin(\theta) \right)^2}{r} \right] \quad \frac{\partial p}{\partial r} = \frac{2 \cdot \Lambda^2 \cdot \rho}{r^5}$$

For  $\theta$  momentum

$$\rho \cdot g_\theta - \frac{1}{r} \cdot \frac{\partial p}{\partial \theta} = \rho \cdot \left( V_r \cdot \frac{\partial}{\partial r} V_\theta + \frac{V_\theta}{r} \cdot \frac{\partial}{\partial \theta} V_\theta + \frac{V_r \cdot V_\theta}{r} \right)$$

Ignoring gravity

$$\frac{\partial p}{\partial \theta} = -r \cdot \rho \cdot \left[ \left( -\frac{\Lambda}{r^2} \cdot \cos(\theta) \right) \cdot \frac{\partial}{\partial r} \left( -\frac{\Lambda}{r^2} \cdot \sin(\theta) \right) + \frac{\left( -\frac{\Lambda}{r^2} \cdot \sin(\theta) \right)}{r} \cdot \frac{\partial}{\partial \theta} \left( -\frac{\Lambda}{r^2} \cdot \sin(\theta) \right) + \frac{\left( -\frac{\Lambda}{r^2} \cdot \sin(\theta) \right) \cdot \left( -\frac{\Lambda}{r^2} \cdot \cos(\theta) \right)}{r} \right] \quad \frac{\partial p}{\partial \theta} = 0$$

The pressure gradient is purely radial

## Problem 6.29

[Difficulty: 4]

**6.29** Air flow over a stationary circular cylinder of radius  $a$  is modeled as a steady, frictionless, and incompressible flow from right to left, given by the velocity field

$$\vec{V} = U \left[ \left( \frac{a}{r} \right)^2 - 1 \right] \cos \theta \hat{e}_r + U \left[ \left( \frac{a}{r} \right)^2 + 1 \right] \sin \theta \hat{e}_\theta$$

Consider flow along the streamline forming the cylinder surface,  $r = a$ . Express the components of the pressure gradient in terms of angle  $\theta$ . Obtain an expression for the variation of pressure (gage) on the surface of the cylinder. For  $U = 75$  m/s and  $a = 150$  mm, plot the pressure distribution (gage) and explain, and find the minimum pressure. Plot the speed  $V$  as a function of  $r$  along the radial line  $\theta = \pi/2$  for  $r > a$  (that is, directly above the cylinder), and explain.

**Given:** Velocity field for flow over a cylinder

**Find:** Expression for pressure gradient; pressure variation; minimum pressure; plot velocity

**Solution:**

Basic equations

$$\rho a_r = \rho \left( \frac{\partial V_r}{\partial t} + V_r \frac{\partial V_r}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_r}{\partial \theta} + V_z \frac{\partial V_r}{\partial z} - \frac{V_\theta^2}{r} \right) = \rho g_r - \frac{\partial p}{\partial r}$$

$$\rho a_\theta = \rho \left( \frac{\partial V_\theta}{\partial t} + V_r \frac{\partial V_\theta}{\partial r} + \frac{V_\theta}{r} \frac{\partial V_\theta}{\partial \theta} + V_z \frac{\partial V_\theta}{\partial z} + \frac{V_r V_\theta}{r} \right) = \rho g_\theta - \frac{1}{r} \frac{\partial p}{\partial \theta}$$

Given data

$$\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \quad a = 150 \cdot \text{mm} \quad U = 75 \cdot \frac{\text{m}}{\text{s}}$$

For this flow

$$V_r = U \cdot \left[ \left( \frac{a}{r} \right)^2 - 1 \right] \cdot \cos(\theta) \quad V_\theta = U \cdot \left[ \left( \frac{a}{r} \right)^2 + 1 \right] \cdot \sin(\theta)$$

On the surface  $r = a$

$$V_r = 0 \quad V_\theta = 2 \cdot U \cdot \sin(\theta)$$

Hence on the surface:

For  $r$  momentum

$$\rho \cdot \left( V_r \cdot \frac{\partial}{\partial r} V_r + \frac{V_\theta}{r} \cdot \frac{\partial}{\partial \theta} V_r - \frac{V_\theta^2}{r} \right) = \rho \cdot \left( -\frac{V_\theta^2}{a} \right) = \frac{\partial}{\partial r} p \quad \frac{\partial}{\partial r} p = \rho \cdot \frac{V_\theta^2}{a} = \rho \cdot 4 \cdot U^2 \cdot \sin^2(\theta)$$

For  $\theta$  momentum


$$\rho \cdot \left( V_r \cdot \frac{\partial}{\partial r} V_\theta + \frac{V_\theta}{r} \cdot \frac{\partial}{\partial \theta} V_\theta + \frac{V_r \cdot V_\theta}{r} \right) = \rho \cdot \left( \frac{V_\theta}{a} \cdot \frac{\partial}{\partial \theta} V_\theta \right) = \rho \cdot \frac{2 \cdot U \cdot \sin(\theta)}{a} \cdot 2 \cdot U \cdot \cos(\theta) = -\frac{1}{r} \cdot \frac{\partial}{\partial \theta} p$$

$$\frac{\partial}{\partial \theta} p = -\frac{4 \cdot \rho \cdot U^2}{a} \cdot \sin(\theta) \cdot \cos(\theta) = -\frac{2 \cdot \rho \cdot U^2}{a} \cdot \sin(2 \cdot \theta)$$


For the pressure distribution we integrate from  $\theta = 0$  to  $\theta = \theta$ , assuming  $p(0) = p_{\text{atm}}$  (a stagnation point)

$$p(\theta) - p_{\text{atm}} = \int_0^\theta \frac{\partial}{\partial \theta} p \, d\theta = \int_0^\theta -\frac{4 \cdot \rho \cdot U^2}{a} \cdot \sin(\theta) \cdot \cos(\theta) \, d\theta$$

$$p(\theta) = -4 \cdot \rho \cdot U^2 \int_0^\theta \sin(\theta) \cdot \cos(\theta) d\theta \quad p(\theta) = -2 \cdot U^2 \cdot \rho \cdot \sin^2(\theta) \quad \text{Minimum } p: \quad p\left(\frac{\pi}{2}\right) = -13.8 \cdot \text{kPa}$$



For the velocity as a function of radial position at  $\theta = \pi/2$   $V_r = 0$  so  $V = V_\theta$   $V_\theta(r) = U \cdot \left[ \left( \frac{a}{r} \right)^2 + 1 \right]$




The velocity falls off to  $V = U$  as directly above the cylinder we have uniform horizontal as the effect of the cylinder decreases

$$V_\theta(100 \cdot a) = 75 \frac{\text{m}}{\text{s}}$$

## Problem 6.30

[Difficulty: 2]

**6.30** To model the velocity distribution in the curved inlet section of a water channel, the radius of curvature of the streamlines is expressed as  $R = LR_0/2y$ . As an approximation, assume the water speed along each streamline is  $V = 10$  m/s. Find an expression for and plot the pressure distribution from  $y = 0$  to the tunnel wall at  $y = L/2$ , if the centerline pressure (gage) is 50 kPa,  $L = 75$  mm, and  $R_0 = 0.2$  m. Find the value of  $V$  for which the wall static pressure becomes 35 kPa.



**Given:** Flow in a curved section

**Find:** Expression for pressure distribution; plot;  $V$  for wall static pressure of 35 kPa

**Solution:**


Basic equation 
$$\frac{\partial}{\partial n} p = \rho \cdot \frac{V^2}{R}$$

Assumptions: Steady; frictionless; no body force; constant speed along streamline

Given data 
$$\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad V = 10 \cdot \frac{\text{m}}{\text{s}} \quad L = 75 \cdot \text{mm} \quad R_0 = 0.2 \cdot \text{m} \quad p_c = 50 \cdot \text{kPa}$$

At the inlet section  $p = p(y)$  hence 
$$\frac{\partial}{\partial n} p = -\frac{dp}{dy} = \rho \cdot \frac{V^2}{R} = \rho \cdot V^2 \cdot \frac{2 \cdot y}{L \cdot R_0} \quad dp = -\rho \cdot V^2 \cdot \frac{2 \cdot y}{L \cdot R_0} \cdot dy$$

Integrating from  $y = 0$  to  $y = y$  
$$p(y) = p_c - \frac{\rho \cdot V^2}{R_0 \cdot L} \cdot y^2 \quad (1) \quad p(0) = 50 \cdot \text{kPa} \quad p\left(\frac{L}{2}\right) = 40.6 \cdot \text{kPa}$$




For a new wall pressure  $p_{\text{wall}} = 35 \cdot \text{kPa}$  solving Eq 1 for  $V$  gives 
$$V = \sqrt{\frac{4 \cdot R_0 \cdot (p_c - p_{\text{wall}})}{\rho \cdot L}} \quad V = 12.7 \frac{\text{m}}{\text{s}}$$

### Problem 6.31

[Difficulty: 2]

6.31 Air at 20 psia and 100°F flows around a smooth corner at the inlet to a diffuser. The air speed is 150 ft/s, and the radius of curvature of the streamlines is 3 in. Determine the magnitude of the centripetal acceleration experienced by a fluid particle rounding the corner. Express your answer in g's. Evaluate the pressure gradient,  $\partial p / \partial r$ .



Solution:

Basic equations:  $\rho \vec{g} - \nabla P = \rho \frac{d\vec{V}}{dt}$  ..... (1)

$\frac{d\vec{V}}{dt} = \vec{a}_p$  ..... (2)

$P = \rho R T$  ..... (3)

- Assumptions: (1)  $\rho = \text{constant}$   
 (2) frictionless flow  
 (3)  $\vec{g} = -g \hat{z}$

Writing the r component of equation (1)

$$\rho \frac{\partial p}{\partial r} = \rho a_r = \rho \left( \frac{\partial v_r}{\partial t} + v_r \frac{\partial v_r}{\partial r} + \frac{1}{r} \frac{\partial v_\theta}{\partial \theta} + v_\theta \frac{\partial v_\theta}{\partial r} \right) = \rho \frac{v^2}{r}$$

$$a_r = -\frac{v^2}{r}$$

$$\frac{\partial p}{\partial r} = -\frac{v^2}{r} = -\frac{(150)^2}{3 \text{ in}} = -\frac{(150)^2}{3 \times \frac{1}{12} \text{ ft}} = -2800 \frac{\text{ft}^2}{\text{ft}} = -2800 \text{ G's}$$

Also

$$\frac{\partial p}{\partial r} = \rho \frac{v^2}{r}$$

where  $\rho = \frac{P}{RT} = \frac{20 \text{ lbf}}{\text{ft}^2} \times \frac{1 \text{ lbf} \cdot \text{ft}}{32.2 \text{ lbf} \cdot \text{ft}} \times \frac{1}{53.3 \text{ ft} \cdot \text{lbf}} \times \frac{1}{530 \text{ R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{\text{slug}}{32.2 \text{ lbf}}$

$$\rho = 0.003 \text{ slug / ft}^3$$


$$\frac{\partial p}{\partial r} = \rho \frac{v^2}{r} = 0.003 \frac{\text{slug}}{\text{ft}^3} \times \frac{(150)^2 \text{ ft}^2}{\text{s}^2} \times \frac{1}{3 \text{ in}} \times \frac{12 \text{ in}}{\text{ft}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{ft} \cdot \text{slug}}$$

$$\frac{\partial p}{\partial r} = 270 \frac{\text{lbf}}{\text{ft}^2}$$

## Problem 6.32

[Difficulty: 3]

**6.32** Repeat Example 6.1, but with the somewhat more realistic assumption that the flow is similar to a free vortex (irrotational) profile,  $V_\theta = c/r$  (where  $c$  is a constant), as shown in Fig. P6.32. In doing so, prove that the flow rate is given by  $Q = k\sqrt{\Delta p}$ , where  $k$  is



$$k = w \ln\left(\frac{r_2}{r_1}\right) \sqrt{\frac{2r_1^2 r_2^2}{\rho(r_2^2 - r_1^2)}}$$

and  $w$  is the depth of the bend.

**Given:** Velocity field for free vortex flow in elbow

**Find:** Similar solution to Example 6.1; find  $k$  (above)

**Solution:**

Basic equation  $\frac{\partial p}{\partial r} = \frac{\rho \cdot V^2}{r}$  with  $V = V_\theta = \frac{c}{r}$

Assumptions: 1) Frictionless 2) Incompressible 3) free vortex

For this flow  $p \neq p(\theta)$  so  $\frac{\partial p}{\partial r} = \frac{d}{dr}p = \frac{\rho \cdot V^2}{r} = \frac{\rho \cdot c^2}{r^3}$

Hence 
$$\Delta p = p_2 - p_1 = \int_{r_1}^{r_2} \frac{\rho \cdot c^2}{r^3} dr = \frac{\rho \cdot c^2}{2} \cdot \left( \frac{1}{r_1^2} - \frac{1}{r_2^2} \right) = \frac{\rho \cdot c^2 \cdot (r_2^2 - r_1^2)}{2 \cdot r_1^2 \cdot r_2^2} \quad (1)$$

Next we obtain  $c$  in terms of  $Q$

$$Q = \int \vec{V} \cdot d\vec{A} = \int_{r_1}^{r_2} V \cdot w \, dr = \int_{r_1}^{r_2} \frac{w \cdot c}{r} \, dr = w \cdot c \cdot \ln\left(\frac{r_2}{r_1}\right)$$

Hence 
$$c = \frac{Q}{w \cdot \ln\left(\frac{r_2}{r_1}\right)}$$

Using this in Eq 1 
$$\Delta p = p_2 - p_1 = \frac{\rho \cdot c^2 \cdot (r_2^2 - r_1^2)}{2 \cdot r_1^2 \cdot r_2^2} = \frac{\rho \cdot Q^2 \cdot (r_2^2 - r_1^2)}{2 \cdot w^2 \cdot \ln\left(\frac{r_2}{r_1}\right)^2 \cdot r_1^2 \cdot r_2^2}$$

Solving for  $Q$  
$$Q = w \cdot \ln\left(\frac{r_2}{r_1}\right) \cdot \sqrt{\frac{2 \cdot r_1^2 \cdot r_2^2}{\rho \cdot (r_2^2 - r_1^2)}} \cdot \sqrt{\Delta p} \quad k = w \cdot \ln\left(\frac{r_2}{r_1}\right) \cdot \sqrt{\frac{2 \cdot r_1^2 \cdot r_2^2}{\rho \cdot (r_2^2 - r_1^2)}}$$



### Problem 6.33

[Difficulty: 4] Part 2/2

$$a_t = \vec{a}_p \cdot \hat{e}_t = (3\hat{i} + 2\hat{j}) \text{ m/s}^2 \cdot (0.832\hat{i} - 0.555\hat{j}) = 1.39 \text{ m/s}^2$$

$$\vec{a}_t = 1.39 \hat{e}_t = 1.16\hat{i} - 0.771\hat{j} \text{ m/s}^2 \quad \vec{a}_t(1,2)$$


For frictionless flow, Euler's equation along a streamline (neglecting gravity, i.e. assuming flow in horizontal plane) is

$$\frac{\partial p}{\partial s} = -\rho v \frac{\partial v}{\partial s} = -\rho a_t = -1.23 \frac{\text{kg}}{\text{m}^3} \times 1.39 \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\frac{\partial p}{\partial s} = -1.71 \text{ N/m}^2/\text{m} \quad \frac{\partial p}{\partial s}(1,2)$$

Looking at the streamline we would expect  $p(2,2)$  to be less than  $p(1,1)$  due to streamline curvature; Euler's equation normal to a streamline says

$$\frac{\partial p}{\partial n} = \frac{\rho v^2}{R}$$



## Problem 6.34

[Difficulty: 2]

**6.34** Using the analyses of Example 6.1 and Problem 6.32, plot the discrepancy (percent) between the flow rates obtained from assuming uniform flow and the free vortex (irrotational) profile as a function of inner radius  $r_1$ .

**Given:** Flow rates in elbow for uniform flow and free vortex

**Find:** Plot discrepancy


**Solution:**

For Example 6.1  $Q_{\text{Uniform}} = V \cdot A = w \cdot (r_2 - r_1) \cdot \sqrt{\frac{1}{\rho \cdot \ln\left(\frac{r_2}{r_1}\right)} \cdot \sqrt{\Delta p}}$  or  $\frac{Q_{\text{Uniform}} \cdot \sqrt{\rho}}{w \cdot r_1 \cdot \sqrt{\Delta p}} = \frac{\left(\frac{r_2}{r_1} - 1\right)}{\sqrt{\ln\left(\frac{r_2}{r_1}\right)}} \quad (1)$

For Problem 6.32  $Q = w \cdot \ln\left(\frac{r_2}{r_1}\right) \cdot \sqrt{\frac{2 \cdot r_1^2 \cdot r_2^2}{\rho \cdot (r_2^2 - r_1^2)} \cdot \sqrt{\Delta p}}$  or  $\frac{Q \cdot \sqrt{\rho}}{w \cdot r_1 \cdot \sqrt{\Delta p}} = \left(\frac{r_2}{r_1}\right) \cdot \ln\left(\frac{r_2}{r_1}\right) \cdot \sqrt{\frac{2}{\left[\left(\frac{r_2}{r_1}\right)^2 - 1\right]}} \quad (2)$

It is convenient to plot these as functions of  $r_2/r_1$

$r_2/r_1$	Eq. 1	Eq. 2	Error
1.01	0.100	0.100	0.0%
1.05	0.226	0.226	0.0%
1.10	0.324	0.324	0.1%
1.15	0.401	0.400	0.2%
1.20	0.468	0.466	0.4%
1.25	0.529	0.526	0.6%
1.30	0.586	0.581	0.9%
1.35	0.639	0.632	1.1%
1.40	0.690	0.680	1.4%
1.45	0.738	0.726	1.7%
1.50	0.785	0.769	2.1%
1.55	0.831	0.811	2.4%
1.60	0.875	0.851	2.8%
1.65	0.919	0.890	3.2%
1.70	0.961	0.928	3.6%
1.75	1.003	0.964	4.0%
1.80	1.043	1.000	4.4%
1.85	1.084	1.034	4.8%
1.90	1.123	1.068	5.2%
1.95	1.162	1.100	5.7%
2.00	1.201	1.132	6.1%
2.05	1.239	1.163	6.6%
2.10	1.277	1.193	7.0%
2.15	1.314	1.223	7.5%
2.20	1.351	1.252	8.0%
2.25	1.388	1.280	8.4%
2.30	1.424	1.308	8.9%
2.35	1.460	1.335	9.4%
2.40	1.496	1.362	9.9%
2.45	1.532	1.388	10.3%
2.50	1.567	1.414	10.8%






### Problem 6.35

[Difficulty: 4] Part 2/2

Thus  $\frac{dy}{y} + 2\frac{dx}{x} = 0$  and  $\ln y + \ln x^2 = \ln c$  or  
 $x^2 y = c$   
The equation of the streamline through (1, 2) is  $x^2 y = 2$ .



10 200  
11 200  
12 200  
13 200  
14 200  
15 200  
16 200  
17 200  
18 200  
19 200  
20 200  
21 200  
22 200  
23 200  
24 200  
25 200  
26 200  
27 200  
28 200  
29 200  
30 200  
31 200  
32 200  
33 200  
34 200  
35 200  
36 200  
37 200  
38 200  
39 200  
40 200  
41 200  
42 200  
43 200  
44 200  
45 200  
46 200  
47 200  
48 200  
49 200  
50 200  
51 200  
52 200  
53 200  
54 200  
55 200  
56 200  
57 200  
58 200  
59 200  
60 200  
61 200  
62 200  
63 200  
64 200  
65 200  
66 200  
67 200  
68 200  
69 200  
70 200  
71 200  
72 200  
73 200  
74 200  
75 200  
76 200  
77 200  
78 200  
79 200  
80 200  
81 200  
82 200  
83 200  
84 200  
85 200  
86 200  
87 200  
88 200  
89 200  
90 200  
91 200  
92 200  
93 200  
94 200  
95 200  
96 200  
97 200  
98 200  
99 200  
100 200



## Problem 6.36

[Difficulty: 4]

**6.36** The  $x$  component of velocity in a two-dimensional incompressible flow field is given by  $u = -\Lambda(x^2 - y^2)/(x^2 + y^2)^2$ , where  $u$  is in m/s, the coordinates are measured in meters, and  $\Lambda = 2 \text{ m}^3 \cdot \text{s}^{-1}$ . Show that the simplest form of the  $y$  component of velocity is given by  $v = -2\Lambda xy/(x^2 + y^2)^2$ . There is no velocity component or variation in the  $z$  direction. Calculate the acceleration of fluid particles at points  $(x, y) = (0, 1)$ ,  $(0, 2)$ , and  $(0, 3)$ . Estimate the radius of curvature of the streamlines passing through these points. What does the relation among the three points and their radii of curvature suggest to you about the flow field? Verify this by plotting these streamlines. [Hint: You will need to use an integrating factor.]

**Given:**  $x$  component of velocity field

**Find:**  $y$  component of velocity field; acceleration at several points; estimate radius of curvature; plot streamlines

**Solution:**

The given data is 
$$\Lambda = 2 \frac{\text{m}^3}{\text{s}} \qquad u = -\frac{\Lambda \cdot (x^2 - y^2)}{(x^2 + y^2)^2}$$

The basic equation (continuity) is 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$$

The basic equation for acceleration is 
$$\vec{a}_p = \frac{D\vec{V}}{Dt} = \underbrace{u \frac{\partial \vec{V}}{\partial x} + v \frac{\partial \vec{V}}{\partial y} + w \frac{\partial \vec{V}}{\partial z}}_{\text{convective acceleration}} + \underbrace{\frac{\partial \vec{V}}{\partial t}}_{\text{local acceleration}}$$
  
total acceleration of a particle

Hence 
$$v = - \int \frac{du}{dx} dy = - \int \frac{2 \cdot \Lambda \cdot x \cdot (x^2 - 3 \cdot y^2)}{(x^2 + y^2)^3} dy$$

Integrating (using an integrating factor) 
$$v = -\frac{2 \cdot \Lambda \cdot x \cdot y}{(x^2 + y^2)^2}$$

Alternatively, we could check that the given velocities  $u$  and  $v$  satisfy continuity

$$u = -\frac{\Lambda \cdot (x^2 - y^2)}{(x^2 + y^2)^2} \qquad \frac{\partial}{\partial x} u = \frac{2 \cdot \Lambda \cdot x \cdot (x^2 - 3 \cdot y^2)}{(x^2 + y^2)^3} \qquad v = -\frac{2 \cdot \Lambda \cdot x \cdot y}{(x^2 + y^2)^2} \qquad \frac{\partial}{\partial y} v = -\frac{2 \cdot \Lambda \cdot x \cdot (x^2 - 3 \cdot y^2)}{(x^2 + y^2)^3}$$

so 
$$\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$$

For steady, 2D flow the acceleration components reduce to (after considerable math!):

x - component

$$a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u$$

$$a_x = \left[ \frac{-\Lambda \cdot (x^2 - y^2)}{(x^2 + y^2)^2} \right] \cdot \left[ \frac{2 \cdot \Lambda \cdot x \cdot (x^2 - 3 \cdot y^2)}{(x^2 + y^2)^3} \right] + \left[ \frac{-2 \cdot \Lambda \cdot x \cdot y}{(x^2 + y^2)^2} \right] \cdot \left[ \frac{2 \cdot \Lambda \cdot y \cdot (3 \cdot x^2 - y^2)}{(x^2 + y^2)^3} \right] a_x = -\frac{2 \cdot \Lambda^2 \cdot x}{(x^2 + y^2)^3}$$

y - component

$$a_y = u \cdot \frac{\partial}{\partial x} v + v \cdot \frac{\partial}{\partial y} v$$

$$a_y = \left[ \frac{-\Lambda \cdot (x^2 - y^2)}{(x^2 + y^2)^2} \right] \cdot \left[ \frac{2 \cdot \Lambda \cdot y \cdot (3 \cdot x^2 - y^2)}{(x^2 + y^2)^3} \right] + \left[ \frac{-2 \cdot \Lambda \cdot x \cdot y}{(x^2 + y^2)^2} \right] \cdot \left[ \frac{2 \cdot \Lambda \cdot y \cdot (3 \cdot y^2 - x^2)}{(x^2 + y^2)^3} \right] a_y = -\frac{2 \cdot \Lambda^2 \cdot y}{(x^2 + y^2)^3}$$

Evaluating at point (0,1)

$$u = 2 \cdot \frac{\text{m}}{\text{s}}$$

$$v = 0 \cdot \frac{\text{m}}{\text{s}}$$

$$a_x = 0 \cdot \frac{\text{m}}{\text{s}^2}$$

$$a_y = -8 \cdot \frac{\text{m}}{\text{s}^2}$$

Evaluating at point (0,2)

$$u = 0.5 \cdot \frac{\text{m}}{\text{s}}$$

$$v = 0 \cdot \frac{\text{m}}{\text{s}}$$

$$a_x = 0 \cdot \frac{\text{m}}{\text{s}^2}$$

$$a_y = -0.25 \cdot \frac{\text{m}}{\text{s}^2}$$

Evaluating at point (0,3)

$$u = 0.222 \cdot \frac{\text{m}}{\text{s}}$$

$$v = 0 \cdot \frac{\text{m}}{\text{s}}$$

$$a_x = 0 \cdot \frac{\text{m}}{\text{s}^2}$$

$$a_y = -0.0333 \cdot \frac{\text{m}}{\text{s}^2}$$

The instantaneous radius of curvature is obtained from

$$a_{\text{radial}} = -a_y = -\frac{u^2}{r} \quad \text{or}$$

$$r = -\frac{u^2}{a_y}$$

For the three points

$$y = 1 \text{ m}$$

$$r = \frac{\left(2 \cdot \frac{\text{m}}{\text{s}}\right)^2}{8 \cdot \frac{\text{m}}{\text{s}^2}}$$

$$r = 0.5 \text{ m}$$

$$y = 2 \text{ m}$$

$$r = \frac{\left(0.5 \cdot \frac{\text{m}}{\text{s}}\right)^2}{0.25 \cdot \frac{\text{m}}{\text{s}^2}}$$

$$r = 1 \text{ m}$$

$$y = 3 \text{ m}$$

$$r = \frac{\left(0.2222 \cdot \frac{\text{m}}{\text{s}}\right)^2}{0.03333 \cdot \frac{\text{m}}{\text{s}^2}}$$

$$r = 1.5 \text{ m}$$

The radius of curvature in each case is 1/2 of the vertical distance from the origin. The streamlines form circles tangent to the x axis

The streamlines are given by

$$\frac{dy}{dx} = \frac{v}{u} = \frac{\frac{2 \cdot \Lambda \cdot x \cdot y}{(x^2 + y^2)^2}}{\frac{\Lambda \cdot (x^2 - y^2)}{(x^2 + y^2)^2}} = \frac{2 \cdot x \cdot y}{(x^2 - y^2)}$$

so

$$-2 \cdot x \cdot y \cdot dx + (x^2 - y^2) \cdot dy = 0$$

This is an inexact integral, so an integrating factor is needed

First we try

$$R = \frac{1}{-2 \cdot x \cdot y} \cdot \left[ \frac{d}{dx} (x^2 - y^2) - \frac{d}{dy} (-2 \cdot x \cdot y) \right] = -\frac{2}{y}$$

Then the integrating factor is

$$F = e^{\int -\frac{2}{y} dy} = \frac{1}{y^2}$$

The equation becomes an exact integral

$$-2 \cdot \frac{x}{y} \cdot dx + \frac{(x^2 - y^2)}{y^2} \cdot dy = 0$$

So

$$u = \int -2 \cdot \frac{x}{y} dx = -\frac{x^2}{y} + f(y) \quad \text{and} \quad u = \int \frac{(x^2 - y^2)}{y^2} dy = -\frac{x^2}{y} - y + g(x)$$

Comparing solutions


$$\psi = \frac{x^2}{y} + y \quad (1) \quad \text{or} \quad x^2 + y^2 = \psi \cdot y = \text{const} \cdot y$$

These form circles that are tangential to the x axis, as can be shown in *Excel*:

The stream function can be evaluated using Eq 1

		y values																				
		0.10	0.25	0.50	0.75	1.00	1.25	1.50	1.75	2.00	2.25	2.50	2.75	3.00	3.25	3.50	3.75	4.00	4.25	4.50	4.75	5.00
x values	2.50	62.6	25.3	13.0	9.08	7.25	6.25	5.67	5.32	5.13	5.03	5.00	5.02	5.08	5.17	5.29	5.42	5.56	5.72	5.89	6.07	6.25
	2.25	50.7	20.5	10.6	7.50	6.06	5.30	4.88	4.64	4.53	4.50	4.53	4.59	4.69	4.81	4.95	5.10	5.27	5.44	5.63	5.82	6.01
	2.00	40.1	16.3	8.50	6.08	5.00	4.45	4.17	4.04	4.00	4.03	4.10	4.20	4.33	4.48	4.64	4.82	5.00	5.19	5.39	5.59	5.80
	1.75	30.7	12.5	6.63	4.83	4.06	3.70	3.54	3.50	3.53	3.61	3.73	3.86	4.02	4.19	4.38	4.57	4.77	4.97	5.18	5.39	5.61
	1.50	22.6	9.25	5.00	3.75	3.25	3.05	3.00	3.04	3.13	3.25	3.40	3.57	3.75	3.94	4.14	4.35	4.56	4.78	5.00	5.22	5.45
	1.25	15.7	6.50	3.63	2.83	2.56	2.50	2.54	2.64	2.78	2.94	3.13	3.32	3.52	3.73	3.95	4.17	4.39	4.62	4.85	5.08	5.31
	1.00	10.1	4.25	2.50	2.08	2.00	2.05	2.17	2.32	2.50	2.69	2.90	3.11	3.33	3.56	3.79	4.02	4.25	4.49	4.72	4.96	5.20
	0.75	5.73	2.50	1.63	1.50	1.56	1.70	1.88	2.07	2.28	2.50	2.73	2.95	3.19	3.42	3.66	3.90	4.14	4.38	4.63	4.87	5.11
	0.50	2.60	1.25	1.00	1.08	1.25	1.45	1.67	1.89	2.13	2.36	2.60	2.84	3.08	3.33	3.57	3.82	4.06	4.31	4.56	4.80	5.05
	0.25	0.73	0.50	0.63	0.83	1.06	1.30	1.54	1.79	2.03	2.28	2.53	2.77	3.02	3.27	3.52	3.77	4.02	4.26	4.51	4.76	5.01
0.00	0.10	0.25	0.50	0.75	1.00	1.25	1.50	1.75	2.00	2.25	2.50	2.75	3.00	3.25	3.50	3.75	4.00	4.25	4.50	4.75	5.00	

See next page for plot:



## Problem 6.37

[Difficulty: 4] Part 1/2

**6.37** The  $x$  component of velocity in a two-dimensional, incompressible flow field is given by  $u = Axy$ ; the coordinates are measured in meters and  $A = 2 \text{ m}^{-1} \cdot \text{s}^{-1}$ . There is no velocity component or variation in the  $z$  direction. Calculate the acceleration of a fluid particle at point

$(x, y) = (2, 1)$ . Estimate the radius of curvature of the streamline passing through this point. Plot the streamline and show both the velocity vector and the acceleration vector on the plot. (Assume the simplest form of the  $y$  component of velocity.)

Solution: For two-d. incompressible flow,  $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$ , so

$$\frac{\partial v}{\partial y} = -\frac{\partial u}{\partial x} = -Ay; \text{ Integrating, } v = -\frac{1}{2}Ay^2; \vec{V} = Axy\hat{i} - \frac{1}{2}Ay^2\hat{j}.$$

The acceleration is

$$a_{px} = u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} = (Axy)(Ay) + (-\frac{1}{2}Ay^2)(Ax) = \frac{1}{2}A^2xy^2$$

$$a_{py} = u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} = (Axy)(0) + (-\frac{1}{2}Ay^2)(-Ay) = \frac{1}{2}Ay^3$$

$$\vec{a}_p = \frac{1}{2}A^2xy^2\hat{i} + \frac{1}{2}Ay^3\hat{j}; \text{ at } (2, 1) \quad \vec{a}_p = 4\hat{i} + 2\hat{j} \text{ (ft/s}^2\text{)}$$

Note  $a_n = \frac{V^2}{R}$ , so  $R = \frac{V^2}{a_n}$ , where  $a_n$  is acceleration normal to  $\vec{V}$

At  $(2, 1)$ ,  $\vec{V} = 4\hat{i} - 1\hat{j} \text{ ft/s}$ , so  $V^2 = (4)^2 + (1)^2 = 17 \text{ ft}^2/\text{s}^2$

To find  $a_n$ , dot  $\vec{a}_p$  with  $\hat{e}_n$ , the unit normal vector. To find  $\hat{e}_n$ , set

$$\hat{e}_n = -\frac{v}{V}\hat{i} + \frac{u}{V}\hat{j} = \frac{1}{\sqrt{17}}\hat{i} + \frac{4}{\sqrt{17}}\hat{j}$$

$$a_n = \hat{e}_n \cdot \vec{a}_p = \frac{4}{\sqrt{17}} + \frac{8}{\sqrt{17}} = \frac{12}{\sqrt{17}} = 2.91 \text{ ft/s}^2$$

Substituting

$$R = \frac{V^2}{a_n} = \frac{17 \text{ ft}^2/\text{s}^2}{2.91 \text{ ft/s}^2} = 5.84 \text{ ft}$$

The streamline is  $\frac{dx}{u} = \frac{dy}{v} = \frac{dx}{Axy} = \frac{dy}{-\frac{1}{2}Ay^2}$  or  $\frac{dx}{x} + 2\frac{dy}{y} = 0$

Integrating,  $\ln x + 2\ln y = \ln C$  or  $xy^2 = C$

For  $(x, y) = (2, 1)$ , then  $C = 2 \text{ ft}^3$ .

The plot and streamlines are on the following page.

# Problem 6.37

## Components of Velocity and Acceleration:

### Input Parameters:

$$A = 2 \text{ ft}^{-1}\text{s}^{-1}$$

### Calculated Values:

$$C = 2 \text{ ft}^3$$


Coord. x	Coord. y	Velocity, $V_x$	Velocity, $V_y$	Velocity, $V$	Accel., $a_x$	Accel., $a_y$	Accel., $a$	Normal Accel., $a_n$
0.08	5.00							
0.2	3.16							
0.4	2.24							
0.5	2.00	2.00	-4.00	4.47	2.00	16.0	16.1	8.94
0.6	1.83							
0.8	1.58							
1.0	1.41	2.83	-2.00	3.46	2.83	5.66	6.32	6.25
1.5	1.15	3.46	-1.33	3.71	3.46	3.08	4.63	4.12
2.0	1.00	4.00	-1.00	4.12	4.00	2.00	4.47	2.91
2.5	0.89	4.47	-0.80	4.54	4.47	1.43	4.70	2.20
3.0	0.82	4.90	-0.67	4.94	4.90	1.09	5.02	1.74
3.5	0.76	5.29	-0.57	5.32	5.29	0.86	5.36	1.43
4.0	0.71	5.66	-0.50	5.68	5.66	0.71	5.70	1.20
4.5	0.67	6.00	-0.44	6.02	6.00	0.59	6.03	1.03
5.0	0.63	6.32	-0.40	6.34	6.32	0.51	6.34	0.90

### Acceleration:

2	1
4	2

### Velocity:

2	1
4	0.5



11-2000  
 12-2000  
 13-2000  
 14-2000  
 15-2000  
 16-2000  
 17-2000  
 18-2000  
 19-2000  
 20-2000  
 21-2000  
 22-2000  
 23-2000  
 24-2000  
 25-2000  
 26-2000  
 27-2000  
 28-2000  
 29-2000  
 30-2000  
 31-2000  
 32-2000  
 33-2000  
 34-2000  
 35-2000  
 36-2000  
 37-2000  
 38-2000  
 39-2000  
 40-2000  
 41-2000  
 42-2000  
 43-2000  
 44-2000  
 45-2000  
 46-2000  
 47-2000  
 48-2000  
 49-2000  
 50-2000  
 51-2000  
 52-2000  
 53-2000  
 54-2000  
 55-2000  
 56-2000  
 57-2000  
 58-2000  
 59-2000  
 60-2000  
 61-2000  
 62-2000  
 63-2000  
 64-2000  
 65-2000  
 66-2000  
 67-2000  
 68-2000  
 69-2000  
 70-2000  
 71-2000  
 72-2000  
 73-2000  
 74-2000  
 75-2000  
 76-2000  
 77-2000  
 78-2000  
 79-2000  
 80-2000  
 81-2000  
 82-2000  
 83-2000  
 84-2000  
 85-2000  
 86-2000  
 87-2000  
 88-2000  
 89-2000  
 90-2000  
 91-2000  
 92-2000  
 93-2000  
 94-2000  
 95-2000  
 96-2000  
 97-2000  
 98-2000  
 99-2000  
 100-2000  
 101-2000  
 102-2000  
 103-2000  
 104-2000  
 105-2000  
 106-2000  
 107-2000  
 108-2000  
 109-2000  
 110-2000  
 111-2000  
 112-2000  
 113-2000  
 114-2000  
 115-2000  
 116-2000  
 117-2000  
 118-2000  
 119-2000  
 120-2000  
 121-2000  
 122-2000  
 123-2000  
 124-2000  
 125-2000  
 126-2000  
 127-2000  
 128-2000  
 129-2000  
 130-2000  
 131-2000  
 132-2000  
 133-2000  
 134-2000  
 135-2000  
 136-2000  
 137-2000  
 138-2000  
 139-2000  
 140-2000  
 141-2000  
 142-2000  
 143-2000  
 144-2000  
 145-2000  
 146-2000  
 147-2000  
 148-2000  
 149-2000  
 150-2000  
 151-2000  
 152-2000  
 153-2000  
 154-2000  
 155-2000  
 156-2000  
 157-2000  
 158-2000  
 159-2000  
 160-2000  
 161-2000  
 162-2000  
 163-2000  
 164-2000  
 165-2000  
 166-2000  
 167-2000  
 168-2000  
 169-2000  
 170-2000  
 171-2000  
 172-2000  
 173-2000  
 174-2000  
 175-2000  
 176-2000  
 177-2000  
 178-2000  
 179-2000  
 180-2000  
 181-2000  
 182-2000  
 183-2000  
 184-2000  
 185-2000  
 186-2000  
 187-2000  
 188-2000  
 189-2000  
 190-2000  
 191-2000  
 192-2000  
 193-2000  
 194-2000  
 195-2000  
 196-2000  
 197-2000  
 198-2000  
 199-2000  
 200-2000  
 201-2000  
 202-2000  
 203-2000  
 204-2000  
 205-2000  
 206-2000  
 207-2000  
 208-2000  
 209-2000  
 210-2000  
 211-2000  
 212-2000  
 213-2000  
 214-2000  
 215-2000  
 216-2000  
 217-2000  
 218-2000  
 219-2000  
 220-2000  
 221-2000  
 222-2000  
 223-2000  
 224-2000  
 225-2000  
 226-2000  
 227-2000  
 228-2000  
 229-2000  
 230-2000  
 231-2000  
 232-2000  
 233-2000  
 234-2000  
 235-2000  
 236-2000  
 237-2000  
 238-2000  
 239-2000  
 240-2000  
 241-2000  
 242-2000  
 243-2000  
 244-2000  
 245-2000  
 246-2000  
 247-2000  
 248-2000  
 249-2000  
 250-2000  
 251-2000  
 252-2000  
 253-2000  
 254-2000  
 255-2000  
 256-2000  
 257-2000  
 258-2000  
 259-2000  
 260-2000  
 261-2000  
 262-2000  
 263-2000  
 264-2000  
 265-2000  
 266-2000  
 267-2000  
 268-2000  
 269-2000  
 270-2000  
 271-2000  
 272-2000  
 273-2000  
 274-2000  
 275-2000  
 276-2000  
 277-2000  
 278-2000  
 279-2000  
 280-2000  
 281-2000  
 282-2000  
 283-2000  
 284-2000  
 285-2000  
 286-2000  
 287-2000  
 288-2000  
 289-2000  
 290-2000  
 291-2000  
 292-2000  
 293-2000  
 294-2000  
 295-2000  
 296-2000  
 297-2000  
 298-2000  
 299-2000  
 300-2000  
 301-2000  
 302-2000  
 303-2000  
 304-2000  
 305-2000  
 306-2000  
 307-2000  
 308-2000  
 309-2000  
 310-2000  
 311-2000  
 312-2000  
 313-2000  
 314-2000  
 315-2000  
 316-2000  
 317-2000  
 318-2000  
 319-2000  
 320-2000  
 321-2000  
 322-2000  
 323-2000  
 324-2000  
 325-2000  
 326-2000  
 327-2000  
 328-2000  
 329-2000  
 330-2000  
 331-2000  
 332-2000  
 333-2000  
 334-2000  
 335-2000  
 336-2000  
 337-2000  
 338-2000  
 339-2000  
 340-2000  
 341-2000  
 342-2000  
 343-2000  
 344-2000  
 345-2000  
 346-2000  
 347-2000  
 348-2000  
 349-2000  
 350-2000  
 351-2000  
 352-2000  
 353-2000  
 354-2000  
 355-2000  
 356-2000  
 357-2000  
 358-2000  
 359-2000  
 360-2000  
 361-2000  
 362-2000  
 363-2000  
 364-2000  
 365-2000  
 366-2000  
 367-2000  
 368-2000  
 369-2000  
 370-2000  
 371-2000  
 372-2000  
 373-2000  
 374-2000  
 375-2000  
 376-2000  
 377-2000  
 378-2000  
 379-2000  
 380-2000  
 381-2000  
 382-2000  
 383-2000  
 384-2000  
 385-2000  
 386-2000  
 387-2000  
 388-2000  
 389-2000  
 390-2000  
 391-2000  
 392-2000  
 393-2000  
 394-2000  
 395-2000  
 396-2000  
 397-2000  
 398-2000  
 399-2000  
 400-2000  
 401-2000  
 402-2000  
 403-2000  
 404-2000  
 405-2000  
 406-2000  
 407-2000  
 408-2000  
 409-2000  
 410-2000  
 411-2000  
 412-2000  
 413-2000  
 414-2000  
 415-2000  
 416-2000  
 417-2000  
 418-2000  
 419-2000  
 420-2000  
 421-2000  
 422-2000  
 423-2000  
 424-2000  
 425-2000  
 426-2000  
 427-2000  
 428-2000  
 429-2000  
 430-2000  
 431-2000  
 432-2000  
 433-2000  
 434-2000  
 435-2000  
 436-2000  
 437-2000  
 438-2000  
 439-2000  
 440-2000  
 441-2000  
 442-2000  
 443-2000  
 444-2000  
 445-2000  
 446-2000  
 447-2000  
 448-2000  
 449-2000  
 450-2000  
 451-2000  
 452-2000  
 453-2000  
 454-2000  
 455-2000  
 456-2000  
 457-2000  
 458-2000  
 459-2000  
 460-2000  
 461-2000  
 462-2000  
 463-2000  
 464-2000  
 465-2000  
 466-2000  
 467-2000  
 468-2000  
 469-2000  
 470-2000  
 471-2000  
 472-2000  
 473-2000  
 474-2000  
 475-2000  
 476-2000  
 477-2000  
 478-2000  
 479-2000  
 480-2000  
 481-2000  
 482-2000  
 483-2000  
 484-2000  
 485-2000  
 486-2000  
 487-2000  
 488-2000  
 489-2000  
 490-2000  
 491-2000  
 492-2000  
 493-2000  
 494-2000  
 495-2000  
 496-2000  
 497-2000  
 498-2000  
 499-2000  
 500-2000  
 501-2000  
 502-2000  
 503-2000  
 504-2000  
 505-2000  
 506-2000  
 507-2000  
 508-2000  
 509-2000  
 510-2000  
 511-2000  
 512-2000  
 513-2000  
 514-2000  
 515-2000  
 516-2000  
 517-2000  
 518-2000  
 519-2000  
 520-2000  
 521-2000  
 522-2000  
 523-2000  
 524-2000  
 525-2000  
 526-2000  
 527-2000  
 528-2000  
 529-2000  
 530-2000  
 531-2000  
 532-2000  
 533-2000  
 534-2000  
 535-2000  
 536-2000  
 537-2000  
 538-2000  
 539-2000  
 540-2000  
 541-2000  
 542-2000  
 543-2000  
 544-2000  
 545-2000  
 546-2000  
 547-2000  
 548-2000  
 549-2000  
 550-2000  
 551-2000  
 552-2000  
 553-2000  
 554-2000  
 555-2000  
 556-2000  
 557-2000  
 558-2000  
 559-2000  
 560-2000  
 561-2000  
 562-2000  
 563-2000  
 564-2000  
 565-2000  
 566-2000  
 567-2000  
 568-2000  
 569-2000  
 570-2000  
 571-2000  
 572-2000  
 573-2000  
 574-2000  
 575-2000  
 576-2000  
 577-2000  
 578-2000  
 579-2000  
 580-2000  
 581-2000  
 582-2000  
 583-2000  
 584-2000  
 585-2000  
 586-2000  
 587-2000  
 588-2000  
 589-2000  
 590-2000  
 591-2000  
 592-2000  
 593-2000  
 594-2000  
 595-2000  
 596-2000  
 597-2000  
 598-2000  
 599-2000  
 600-2000  
 601-2000  
 602-2000  
 603-2000  
 604-2000  
 605-2000  
 606-2000  
 607-2000  
 608-2000  
 609-2000  
 610-2000  
 611-2000  
 612-2000  
 613-2000  
 614-2000  
 615-2000  
 616-2000  
 617-2000  
 618-2000  
 619-2000  
 620-2000  
 621-2000  
 622-2000  
 623-2000  
 624-2000  
 625-2000  
 626-2000  
 627-2000  
 628-2000  
 629-2000  
 630-2000  
 631-2000  
 632-2000  
 633-2000  
 634-2000  
 635-2000  
 636-2000  
 637-2000  
 638-2000  
 639-2000  
 640-2000  
 641-2000  
 642-2000  
 643-2000  
 644-2000  
 645-2000  
 646-2000  
 647-2000  
 648-2000  
 649-2000  
 650-2000  
 651-2000  
 652-2000  
 653-2000  
 654-2000  
 655-2000  
 656-2000  
 657-2000  
 658-2000  
 659-2000  
 660-2000  
 661-2000  
 662-2000  
 663-2000  
 664-2000  
 665-2000  
 666-2000  
 667-2000  
 668-2000  
 669-2000  
 670-2000  
 671-2000  
 672-2000  
 673-2000  
 674-2000  
 675-2000  
 676-2000  
 677-2000  
 678-2000  
 679-2000  
 680-2000  
 681-2000  
 682-2000  
 683-2000  
 684-2000  
 685-2000  
 686-2000  
 687-2000  
 688-2000  
 689-2000  
 690-2000  
 691-2000  
 692-2000  
 693-2000  
 694-2000  
 695-2000  
 696-2000  
 697-2000  
 698-2000  
 699-2000  
 700-2000  
 701-2000  
 702-2000  
 703-2000  
 704-2000  
 705-2000  
 706-2000  
 707-2000  
 708-2000  
 709-2000  
 710-2000  
 711-2000  
 712-2000  
 713-2000  
 714-2000  
 715-2000  
 716-2000  
 717-2000  
 718-2000  
 719-2000  
 720-2000  
 721-2000  
 722-2000  
 723-2000  
 724-2000  
 725-2000  
 726-2000  
 727-2000  
 728-2000  
 729-2000  
 730-2000  
 731-2000  
 732-2000  
 733-2000  
 734-2000  
 735-2000  
 736-2000  
 737-2000  
 738-2000  
 739-2000  
 740-2000  
 741-2000  
 742-2000  
 743-2000  
 744-2000  
 745-2000  
 746-2000  
 747-2000  
 748-2000  
 749-2000  
 750-2000  
 751-2000  
 752-2000  
 753-2000  
 754-2000  
 755-2000  
 756-2000  
 757-2000  
 758-2000  
 759-2000  
 760-2000  
 761-2000  
 762-2000  
 763-2000  
 764-2000  
 765-2000  
 766-2000  
 767-2000  
 768-2000  
 769-2000  
 770-2000  
 771-2000  
 772-2000  
 773-2000  
 774-2000  
 775-2000  
 776-2000  
 777-2000  
 778-2000  
 779-2000  
 780-2000  
 781-2000  
 782-2000  
 783-2000  
 784-2000  
 785-2000  
 786-2000  
 787-2000  
 788-2000  
 789-2000  
 790-2000  
 791-2000  
 792-2000  
 793-2000  
 794-2000  
 795-2000  
 796-2000  
 797-2000  
 798-2000  
 799-2000  
 800-2000  
 801-2000  
 802-2000  
 803-2000  
 804-2000  
 805-2000  
 806-2000  
 807-2000  
 808-2000  
 809-2000  
 810-2000

## Problem 6.38

[Difficulty: 1]

**6.38** Water flows at a speed of 25 ft/s. Calculate the dynamic pressure of this flow. Express your answer in inches of mercury.

**Given:** Water at speed 25 ft/s

**Find:** Dynamic pressure in in. Hg

**Solution:**

Basic equations 
$$p_{\text{dynamic}} = \frac{1}{2} \cdot \rho \cdot V^2$$
 
$$p = \rho_{\text{Hg}} \cdot g \cdot \Delta h = SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h$$

Hence 
$$\Delta h = \frac{\rho \cdot V^2}{2 \cdot SG_{\text{Hg}} \cdot \rho \cdot g} = \frac{V^2}{2 \cdot SG_{\text{Hg}} \cdot g}$$

$$\Delta h = \frac{1}{2} \times \left( 25 \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{1}{13.6} \times \frac{\text{s}^2}{32.2 \text{ft}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \quad \Delta h = 8.56 \text{ in}$$

## Problem 6.39

[Difficulty: 1]

**6.39** Calculate the dynamic pressure that corresponds to a speed of 100 km/hr in standard air. Express your answer in millimeters of water.

**Given:** Air speed of 100 km/hr

**Find:** Dynamic pressure in mm water

**Solution:**

Basic equations 
$$p_{\text{dynamic}} = \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2$$
 
$$p = \rho_w \cdot g \cdot \Delta h$$

Hence 
$$\Delta h = \frac{\rho_{\text{air}}}{\rho_w} \cdot \frac{V^2}{2 \cdot g}$$

$$\Delta h = \frac{1.23 \cdot \frac{\text{kg}}{\text{m}^3}}{999 \cdot \frac{\text{kg}}{\text{m}^3}} \times \frac{1}{2} \times \left(100 \cdot \frac{\text{km}}{\text{hr}}\right)^2 \times \left(\frac{1000 \cdot \text{m}}{1 \cdot \text{km}}\right)^2 \times \left(\frac{1 \cdot \text{hr}}{3600 \cdot \text{s}}\right)^2 \times \frac{\text{s}^2}{9.81 \cdot \text{m}}$$

$\Delta h = 48.4 \cdot \text{mm}$

## Problem 6.40

[Difficulty: 2]

**6.40** Plot the speed of air versus the dynamic pressure (in millimeters of mercury), up to a dynamic pressure of 250 mm Hg.

**Given:** Air speed

**Find:** Plot dynamic pressure in mm Hg


**Solution:**

Basic equations  $p_{\text{dynamic}} = \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2$        $p = \rho_{\text{Hg}} \cdot g \cdot \Delta h = SG_{\text{Hg}} \cdot \rho_{\text{w}} \cdot g \cdot \Delta h$

Available data  $\rho_{\text{w}} = 999 \cdot \frac{\text{kg}}{\text{m}^3}$        $\rho_{\text{air}} = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$        $SG_{\text{Hg}} = 13.6$

Hence  $\frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2 = SG_{\text{Hg}} \cdot \rho_{\text{w}} \cdot g \cdot \Delta h$

Solving for V  $V(\Delta h) = \sqrt{\frac{2 \cdot SG_{\text{Hg}} \cdot \rho_{\text{w}} \cdot g \cdot \Delta h}{\rho_{\text{air}}}}$



## Problem 6.41

[Difficulty: 2]

**6.41** You present your open hand out of the window of an automobile perpendicular to the airflow. Assuming for simplicity that the air pressure on the entire front surface is stagnation pressure (with respect to automobile coordinates), with atmospheric pressure on the rear surface, estimate the net force on your hand when driving at (a) 30 mph and (b) 60 mph. Do these results roughly correspond with your experience? Do the simplifications tend to make the calculated force an over- or underestimate?

**Given:** Velocity of automobile

**Find:** Estimates of aerodynamic force on hand

**Solution:**

The basic equation is the Bernoulli equation (in coordinates attached to the vehicle)  $p_{\text{atm}} + \frac{1}{2} \cdot \rho \cdot V^2 = p_{\text{stag}}$

where  $V$  is the free stream velocity

For air  $\rho = 0.00238 \cdot \frac{\text{slug}}{\text{ft}^3}$

We need an estimate of the area of a typical hand. Personal inspection indicates that a good approximation is a square of sides 9 cm and 17 cm

$$A = 9 \cdot \text{cm} \times 17 \cdot \text{cm} \qquad A = 153 \cdot \text{cm}^2$$

Hence, for  $p_{\text{stag}}$  on the front side of the hand, and  $p_{\text{atm}}$  on the rear, by assumption,

$$F = (p_{\text{stag}} - p_{\text{atm}}) \cdot A = \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$$

(a)  $V = 30 \cdot \text{mph}$

$$F = \frac{1}{2} \cdot \rho \cdot V^2 \cdot A = \frac{1}{2} \times 0.00238 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 30 \cdot \text{mph} \cdot \frac{22 \cdot \frac{\text{ft}}{\text{s}}}{15 \cdot \text{mph}} \right)^2 \times 153 \cdot \text{cm}^2 \times \left( \frac{1}{2.54} \cdot \frac{\text{ft}}{\text{cm}} \right)^2 \qquad F = 0.379 \cdot \text{lbf}$$

(b)  $V = 60 \cdot \text{mph}$

$$F = \frac{1}{2} \cdot \rho \cdot V^2 \cdot A = \frac{1}{2} \times 0.00238 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 60 \cdot \text{mph} \cdot \frac{22 \cdot \frac{\text{ft}}{\text{s}}}{15 \cdot \text{mph}} \right)^2 \times 153 \cdot \text{cm}^2 \times \left( \frac{1}{2.54} \cdot \frac{\text{ft}}{\text{cm}} \right)^2 \qquad F = 1.52 \cdot \text{lbf}$$

These values pretty much agree with experience. However, they overestimate a bit as the entire front of the hand is not at stagnation pressure - there is flow around the had - so the pressure is less than stagnation over most of the surface.

## Problem 6.42

[Difficulty: 2]

**6.42** A jet of air from a nozzle is blown at right angles against a wall in which two pressure taps are located. A manometer connected to the tap directly in front of the jet shows a head of 25 mm of mercury above atmospheric. Determine the approximate speed of the air leaving the nozzle if it is at  $-10^\circ\text{C}$  and 200 kPa. At the second tap a manometer indicates a head of 5 mm of mercury above atmospheric; what is the approximate speed of the air there?

**Given:** Air jet hitting wall generating pressures

**Find:** Speed of air at two locations

**Solution:**

Basic equations  $\frac{p}{\rho_{\text{air}}} + \frac{V^2}{2} + g \cdot z = \text{const}$   $\rho_{\text{air}} = \frac{p}{R_{\text{air}} \cdot T}$   $\Delta p = \rho_{\text{Hg}} \cdot g \cdot \Delta h = SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data  $R = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$   $T = -10^\circ\text{C}$   $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$   $p = 200 \cdot \text{kPa}$   $SG_{\text{Hg}} = 13.6$

For the air  $\rho_{\text{air}} = \frac{p}{R \cdot T}$   $\rho_{\text{air}} = 2.65 \frac{\text{kg}}{\text{m}^3}$

Hence, applying Bernoulli between the jet and where it hits the wall directly

$$\frac{p_{\text{atm}}}{\rho_{\text{air}}} + \frac{V_j^2}{2} = \frac{p_{\text{wall}}}{\rho_{\text{air}}} \quad p_{\text{wall}} = \frac{\rho_{\text{air}} \cdot V_j^2}{2} \quad (\text{working in gage pressures})$$

Hence  $p_{\text{wall}} = SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h = \frac{\rho_{\text{air}} \cdot V_j^2}{2}$  so  $V_j = \sqrt{\frac{2 \cdot SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h}{\rho_{\text{air}}}}$

$\Delta h = 25 \cdot \text{mm}$  hence  $V_j = \sqrt{2 \times 13.6 \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \frac{1}{2.65} \cdot \frac{\text{m}^3}{\text{kg}} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 25 \cdot \text{mm} \times \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}}}$   $V_j = 50.1 \frac{\text{m}}{\text{s}}$

Repeating the analysis for the second point

$\Delta h = 5 \cdot \text{mm}$   $\frac{p_{\text{atm}}}{\rho_{\text{air}}} + \frac{V_j^2}{2} = \frac{p_{\text{wall}}}{\rho_{\text{air}}} + \frac{V^2}{2}$   $V = \sqrt{V_j^2 - \frac{2 \cdot p_{\text{wall}}}{\rho_{\text{air}}}} = \sqrt{V_j^2 - \frac{2 \cdot SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h}{\rho_{\text{air}}}}$

Hence  $V = \sqrt{\left(50.1 \cdot \frac{\text{m}}{\text{s}}\right)^2 - 2 \times 13.6 \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \frac{1}{2.65} \cdot \frac{\text{m}^3}{\text{kg}} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 5 \cdot \text{mm} \times \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}}}$   $V = 44.8 \frac{\text{m}}{\text{s}}$

### Problem 6.43

[Difficulty: 2]

**6.43** A pitot-static tube is used to measure the speed of air at standard conditions at a point in a flow. To ensure that the flow may be assumed incompressible for calculations of engineering accuracy, the speed is to be maintained at 100 m/s or less. Determine the manometer deflection, in millimeters of water, that corresponds to the maximum desirable speed.

Solution:

Manometer reads  $P_0 - P$  in mm of  $H_2O$ .

Basic equations:  $\frac{P}{\rho} + \frac{V^2}{2} + gz = \text{constant}$  for flow

$\frac{dP}{dz} = -\rho g$  for manometer

- Assumptions:
- (1) steady flow
  - (2) incompressible flow
  - (3) flow along a streamline
  - (4) frictionless deceleration to  $P_0$
  - (5)  $\rho = \text{constant}$  for manometer

From the Bernoulli equation

$$\frac{P_0}{\rho} = \frac{P}{\rho} + \frac{V^2}{2}$$

$$P_0 - P = \frac{\rho V^2}{2}$$

For the manometer,  $dP = -\rho g dz$


$$P_0 - P = \int_P^{P_0} dP = -\rho g (z_2 - z_1) = \rho g h$$

Then,

$$\rho_{H_2O} g h = \rho_{air} \frac{V^2}{2}$$

and


$$h = \frac{\rho_{air}}{\rho_{H_2O}} \frac{V^2}{2g} = \frac{1.23}{999} \times \frac{(100)^2}{9.81} \times \frac{1}{2} \times \frac{5^2}{9.81} \times \frac{10^3}{5} = 628 \text{ mm} \leftarrow h$$



## Problem 6.44

[Difficulty: 2]

**6.44** The inlet contraction and test section of a laboratory wind tunnel are shown. The air speed in the test section is  $U = 50$  m/s. A total-head tube pointed upstream indicates that the stagnation pressure on the test section centerline is 10 mm of water below atmospheric. The laboratory is maintained at atmospheric pressure and a temperature of  $-5^\circ\text{C}$ . Evaluate the dynamic pressure on the centerline of the wind tunnel test section. Compute the static pressure at the same point. Qualitatively compare the static pressure at the tunnel wall with that at the centerline. Explain why the two may not be identical.



**Given:** Wind tunnel with inlet section

**Find:** Dynamic and static pressures on centerline; compare with Speed of air at two locations

**Solution:**

Basic equations  $p_{\text{dyn}} = \frac{1}{2} \cdot \rho_{\text{air}} \cdot U^2$   $p_0 = p_s + p_{\text{dyn}}$   $\rho_{\text{air}} = \frac{p}{R_{\text{air}} \cdot T}$   $\Delta p = \rho_w \cdot g \cdot \Delta h$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data  $T = -5^\circ\text{C}$   $U = 50$   $R = 287 \frac{\text{J}}{\text{kg} \cdot \text{K}}$   $p_{\text{atm}} = 101 \text{ kPa}$   $h_0 = -10 \text{ mm}$   $\rho_w = 999 \frac{\text{kg}}{\text{m}^3}$

For air  $\rho_{\text{air}} = \frac{p_{\text{atm}}}{R \cdot T}$   $\rho_{\text{air}} = 1.31 \frac{\text{kg}}{\text{m}^3}$

$p_{\text{dyn}} = \frac{1}{2} \cdot \rho_{\text{air}} \cdot U^2$   $p_{\text{dyn}} = 1.64 \text{ kPa}$

Also  $p_0 = \rho_w \cdot g \cdot h_0$   $p_0 = -98.0 \text{ Pa}$  (gage)


and  $p_0 = p_s + p_{\text{dyn}}$  so  $p_s = p_0 - p_{\text{dyn}}$   $p_s = -1.738 \text{ kPa}$  (gage)  $h_s = \frac{p_s}{\rho_w \cdot g}$   $h_s = -177 \text{ mm}$

Streamlines in the test section are straight so  $\frac{\partial}{\partial n} p = 0$  and  $p_w = p_{\text{centerline}}$

In the curved section  $\frac{\partial}{\partial n} p = \rho_{\text{air}} \cdot \frac{V^2}{R}$  so  $p_w < p_{\text{centerline}}$



6.46 An open-circuit wind tunnel draws in air from the atmosphere through a well-contoured nozzle. In the test section, where the flow is straight and nearly uniform, a static pressure tap is drilled into the tunnel wall. A manometer connected to the tap shows that static pressure within the tunnel is 45 mm of water below atmospheric. Assume that the air is incompressible, and at 25°C, 100 kPa (abs). Calculate the air speed in the wind-tunnel test section.



Solution:

Basic equations:  $\frac{P}{\rho} + \frac{V^2}{2} + gz = \text{constant}$

- Assumptions:
- (1) steady flow
  - (2) incompressible flow
  - (3) frictionless flow
  - (4) flow along a streamline
  - (5) air behaves as an ideal gas
  - (6) stagnation pressure =  $P_{0in}$

From the Bernoulli equation,  $\frac{P_0}{\rho} = \frac{P_1}{\rho} + \frac{V_1^2}{2}$

$$P_0 - P_1 = P_{0in} - P_1 = \frac{1}{2} \rho V_1^2$$

$$V_1 = \left[ \frac{2(P_{0in} - P_1)}{\rho} \right]^{1/2}$$

From the manometer reading,  $P_{0in} - P_1 = \rho_{H_2O} g h$   $\rho_{H_2O}$

$$V_1 = \left[ \frac{2 \rho_{H_2O} g h}{\rho} \right]^{1/2}$$

From the ideal gas equation of state


$$\rho = \frac{P}{RT} = \frac{100 \times 10^3 \frac{N}{m^2} \times \frac{1 \text{ kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m}}}{298 \text{ K}} = 1.17 \frac{\text{kg}}{\text{m}^3}$$

$$V_1 = \left[ \frac{2 \rho_{H_2O} g h}{\rho} \right]^{1/2} = \left[ \frac{2 \times 999 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.045 \text{ m}}{1.17} \right]^{1/2} = 27.5 \text{ m/s} \leftarrow V_1$$

### Problem 6.47

[Difficulty: 4]

**6.47** The wheeled cart shown in Problem 4.128 rolls with negligible resistance. The cart is to accelerate to the right. The jet speed is  $V = 40$  m/s. The jet area remains constant at  $A = 25$  mm<sup>2</sup>. Neglect viscous forces between the water and vane. When the cart attains speed  $U = 15$  m/s, calculate the stagnation pressure of the water leaving the nozzle with respect to a fixed observer, the stagnation pressure of the water jet leaving the nozzle with respect to an observer on the vane, the absolute velocity of the jet leaving the vane with respect to a fixed observer, and the stagnation pressure of the jet leaving the vane with respect to a fixed observer. How would viscous forces affect the latter stagnation pressure, i.e., would viscous forces increase, decrease, or leave unchanged this stagnation pressure? Justify your answer.



Solution: Stagnation pressure is  $p_0 = p + \frac{1}{2}\rho V^2$  or  $p_0 - p = \frac{1}{2}\rho V^2$

$$\text{At jet, } p_{0j} = \frac{1}{2}\rho V^2 = \frac{1}{2} \times 999 \frac{\text{kg}}{\text{m}^3} \times (40)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 799 \text{ kPa (gage)}$$

$$\text{At cart, } p_{0rel} = \frac{1}{2}\rho (V-U)^2 = \frac{1}{2} \times 999 \frac{\text{kg}}{\text{m}^3} \times (40-15)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 312 \text{ kPa (gage)}$$

$$\text{Leaving vane, } \vec{V}_{abs} = U\hat{i} + (V-U)(\cos\theta\hat{i} + \sin\theta\hat{j})$$

$$\vec{V}_{abs} = [U + (V-U)\cos\theta]\hat{i} + (V-U)\sin\theta\hat{j}$$

$$= \left[ 15 \frac{\text{m}}{\text{s}} + (40-15) \frac{\text{m}}{\text{s}} \times \left(-\frac{1}{2}\right) \right] \hat{i} + (40-15) \frac{\text{m}}{\text{s}} \times 0.866 \hat{j}$$

$$\vec{V}_{abs} = 2.5\hat{i} + 21.7\hat{j} \text{ m/s}$$

$$\text{The magnitude } |\vec{V}_{abs}| = [(2.5)^2 + (21.7)^2]^{1/2} \text{ m/s} = 21.8 \text{ m/s}$$

Leaving vane,  $p_0 = \frac{1}{2}\rho |\vec{V}_{abs}|^2$ , relative to a fixed observer. Thus

$$p_{0, fixed} = \frac{1}{2} \times 999 \frac{\text{kg}}{\text{m}^3} \times (21.8)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 237 \text{ kPa (gage)}$$

{ The corresponding absolute pressures are 999, 413, and 338 kPa (abs). }


**Discussion:** Viscous forces would slow the jet speed relative to the vane. The jet would enter the vane with relative speed  $(V-U)$ ; it would leave the vane with speed  $\alpha(V-U)$ , where  $\alpha < 1$ .

Friction would reduce both components of relative velocity leaving the vane. The absolute velocity of the jet leaving the vane, as seen by a fixed observer, would decrease. Thus the stagnation pressure of the flow leaving the vane, relative to a fixed observer, would decrease.

## Problem 6.48

[Difficulty: 2]

**6.48** Water flows steadily up the vertical 1-in.-diameter pipe and out the nozzle, which is 0.5 in. in diameter, discharging to atmospheric pressure. The stream velocity at the nozzle exit must be 30 ft/s. Calculate the minimum gage pressure required at section ①. If the device were inverted, what would be the required minimum pressure at section ① to maintain the nozzle exit velocity at 30 ft/s?



**Given:** Flow in pipe/nozzle device

**Find:** Gage pressure needed for flow rate; repeat for inverted

**Solution:**

Basic equations  $Q = V \cdot A$   $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data  $D_1 = 1 \cdot \text{in}$   $D_2 = 0.5 \cdot \text{in}$   $V_2 = 30 \cdot \frac{\text{ft}}{\text{s}}$   $z_2 = 10 \cdot \text{ft}$   $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$

From continuity  $Q = V_1 \cdot A_1 = V_2 \cdot A_2$   $V_1 = V_2 \cdot \frac{A_2}{A_1}$  or  $V_1 = V_2 \cdot \left(\frac{D_2}{D_1}\right)^2$   $V_1 = 7.50 \cdot \frac{\text{ft}}{\text{s}}$

Hence, applying Bernoulli between locations 1 and 2

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + 0 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g \cdot z_2 = 0 + \frac{V_2^2}{2} + g \cdot z_2 \text{ working in gage pressures}$$

Solving for  $p_1$  (gage)  $p_1 = \rho \cdot \left( \frac{V_2^2 - V_1^2}{2} + g \cdot z_2 \right)$   $p_1 = 10.0 \cdot \text{psi}$

When it is inverted  $z_2 = -10 \cdot \text{ft}$

$$p_2 = \rho \cdot \left( \frac{V_2^2 - V_1^2}{2} + g \cdot z_2 \right)$$

$p_2 = 1.35 \cdot \text{psi}$



## Problem 6.50

[Difficulty: 2]

**6.50** You are on a date. Your date runs out of gas unexpectedly. You come to your own rescue by siphoning gas from another car. The height difference for the siphon is about 1 ft. The hose diameter is 0.5 in. What is your gasoline flow rate?

**Given:** Siphoning of gasoline

**Find:** Flow rate

**Solution:**

Basic equation 
$$\frac{p}{\rho_{\text{gas}}} + \frac{V^2}{2} + g \cdot z = \text{const}$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Hence, applying Bernoulli between the gas tank free surface and the siphon exit

$$\frac{p_{\text{atm}}}{\rho_{\text{gas}}} = \frac{p_{\text{atm}}}{\rho_{\text{gas}}} + \frac{V^2}{2} - g \cdot h \quad \text{where we assume the tank free surface is slowly changing so } V_{\text{tank}} \ll, \text{ and } h \text{ is the difference in levels}$$

Hence 
$$V = \sqrt{2 \cdot g \cdot h}$$

The flow rate is then 
$$Q = V \cdot A = \frac{\pi \cdot D^2}{4} \cdot \sqrt{2 \cdot g \cdot h}$$

$$Q = \frac{\pi}{4} \times (.5 \cdot \text{in})^2 \times \frac{1 \cdot \text{ft}^2}{144 \cdot \text{in}^2} \times \sqrt{2 \times 32.2 \frac{\text{ft}}{\text{s}^2} \times 1 \cdot \text{ft}} \quad Q = 0.0109 \cdot \frac{\text{ft}^3}{\text{s}} \quad Q = 4.91 \cdot \frac{\text{gal}}{\text{min}}$$

## Problem 6.51

[Difficulty: 2]

**6.51** You (a young person of legal drinking age) are making homemade beer. As part of the process you have to siphon the wort (the fermenting beer with sediment at the bottom) into a clean tank using a 5-mm ID tubing. Being a young engineer, you're curious about the flow you can produce. Find an expression for and plot the flow rate  $Q$  (liters per minute) versus the differential in height  $h$  (millimeters) between the wort free surface and the location of the hose exit. Find the value of  $h$  for which  $Q = 2$  L/min.

**Given:** Siphoning of wort

**Find:** Flow rate; plot; height for a flow of 2 L/min

**Solution:**

Basic equation 
$$\frac{p}{\rho_{\text{wort}}} + \frac{V^2}{2} + g \cdot z = \text{const}$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline


Hence, applying Bernoulli between the open surface of the full tank and tube exit to atmosphere

$$\frac{p_{\text{atm}}}{\rho_{\text{gas}}} = \frac{p_{\text{atm}}}{\rho_{\text{gas}}} + \frac{V^2}{2} - g \cdot h \quad \text{where we assume the tank free surface is slowly changing so } V_{\text{tank}} \ll, \text{ and } h \text{ is the difference in levels}$$

Hence 
$$V = \sqrt{2 \cdot g \cdot h}$$

The flow rate is then 
$$Q = V \cdot A = \frac{\pi \cdot D^2}{4} \cdot \sqrt{2 \cdot g \cdot h}$$

For  $D = 5 \cdot \text{mm}$



For a flow rate of  $Q = 2 \cdot \frac{\text{L}}{\text{min}}$   $Q = 3.33 \times 10^{-5} \frac{\text{m}^3}{\text{s}}$  solving for  $h$   $h = \frac{8 \cdot Q^2}{\pi^2 \cdot D^4 \cdot g}$   $h = 147 \cdot \text{mm}$

## Problem 6.52

[Difficulty: 2]

**6.52** A tank at a pressure of 50 kPa (gage) gets a pinhole rupture and benzene shoots into the air. Ignoring losses, to what height will the benzene rise?

**Given:** Ruptured pipe

**Find:** Height benzene rises from tank

**Solution:**

Basic equation 
$$\frac{p}{\rho_{\text{ben}}} + \frac{V^2}{2} + g \cdot z = \text{const}$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data 
$$\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad p_{\text{ben}} = 50 \cdot \text{kPa} \quad (\text{gage}) \quad \text{From Table A.2} \quad SG_{\text{ben}} = 0.879$$

Hence, applying Bernoulli between the pipe and the rise height of the benzene

$$\frac{p_{\text{ben}}}{\rho_{\text{ben}}} = \frac{p_{\text{atm}}}{\rho_{\text{ben}}} + g \cdot h \quad \text{where we assume } V_{\text{pipe}} \ll, \text{ and } h \text{ is the rise height}$$

Hence 
$$h = \frac{p_{\text{ben}}}{SG_{\text{ben}} \cdot \rho \cdot g} \quad \text{where } p_{\text{ben}} \text{ is now the gage pressure}$$

$$h = 5.81 \text{ m}$$

## Problem 6.53

[Difficulty: 2]

**6.53** A can of Coke (you're not sure if it's diet or regular) has a small pinhole leak in it. The Coke sprays vertically into the air to a height of 0.5 m. What is the pressure inside the can of Coke? (Estimate for both kinds of Coke.)

**Given:** Ruptured Coke can

**Find:** Pressure in can

**Solution:**

Basic equation 
$$\frac{p}{\rho_{\text{Coke}}} + \frac{V^2}{2} + g \cdot z = \text{const}$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data 
$$\rho_w = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad h = 0.5 \cdot \text{m} \quad \text{From a web search} \quad SG_{\text{DietCoke}} = 1 \quad SG_{\text{RegularCoke}} = 1.11$$

Hence, applying Bernoulli between the coke can and the rise height of the coke

$$\frac{p_{\text{can}}}{\rho_{\text{Coke}}} = \frac{p_{\text{atm}}}{\rho_{\text{Coke}}} + g \cdot h \quad \text{where we assume } V_{\text{Coke}} \ll, \text{ and } h \text{ is the rise height}$$

Hence 
$$p_{\text{Coke}} = \rho_{\text{Coke}} \cdot g \cdot h = SG_{\text{Coke}} \cdot \rho_w \cdot g \cdot h \quad \text{where } p_{\text{Coke}} \text{ is now the gage pressure}$$


Hence 
$$p_{\text{Diet}} = SG_{\text{DietCoke}} \cdot \rho_w \cdot g \cdot h \quad p_{\text{Diet}} = 4.90 \cdot \text{kPa} \quad (\text{gage})$$

and 
$$p_{\text{Regular}} = SG_{\text{RegularCoke}} \cdot \rho_w \cdot g \cdot h \quad p_{\text{Regular}} = 5.44 \cdot \text{kPa} \quad (\text{gage})$$

## Problem 6.54

[Difficulty: 3]

**6.54** The water flow rate through the siphon is 5 L/s, its temperature is 20°C, and the pipe diameter is 25 mm. Compute the maximum allowable height,  $h$ , so that the pressure at point  $A$  is above the vapor pressure of the water. (Assume the flow is frictionless.)



**Given:** Flow rate through siphon

**Find:** Maximum height  $h$  to avoid cavitation

**Solution:**

Basic equation  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$   $Q = V \cdot A$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data  $Q = 5 \cdot \frac{\text{L}}{\text{s}}$   $Q = 5 \times 10^{-3} \frac{\text{m}^3}{\text{s}}$   $D = 25\text{-mm}$   $\rho = 999 \frac{\text{kg}}{\text{m}^3}$   $p_{\text{atm}} = 101\text{-kPa}$

From continuity  $V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V = \frac{4}{\pi} \times 0.005 \frac{\text{m}^3}{\text{s}} \times \left(\frac{1}{.025\text{m}}\right)^2$   $V = 10.2 \frac{\text{m}}{\text{s}}$

Hence, applying Bernoulli between the free surface and point A

$$\frac{p_{\text{atm}}}{\rho} = \frac{p_A}{\rho} + g \cdot h + \frac{V^2}{2}$$

where we assume  $V_{\text{Surface}} \ll V$

Hence  $p_A = p_{\text{atm}} - \rho \cdot g \cdot h - \rho \cdot \frac{V^2}{2}$

From the steam tables, at 20°C the vapor pressure is  $p_v = 2.358 \cdot \text{kPa}$

This is the lowest permissible value of  $p_A$


Hence  $p_A = p_v = p_{\text{atm}} - \rho \cdot g \cdot h - \rho \cdot \frac{V^2}{2}$  or  $h = \frac{p_{\text{atm}} - p_v}{\rho \cdot g} - \frac{V^2}{2 \cdot g}$

Hence  $h = (101 - 2.358) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{999} \cdot \frac{\text{m}^3}{\text{kg}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - \frac{1}{2} \times \left(10.2 \frac{\text{m}}{\text{s}}\right)^2 \times \frac{\text{s}^2}{9.81 \cdot \text{m}}$   $h = 4.76 \text{ m}$

### Problem 6.55

[Difficulty: 2]

6.55 A stream of liquid moving at low speed leaves a nozzle pointed directly downward. The velocity may be considered uniform across the nozzle exit and the effects of friction may be ignored. At the nozzle exit, located at elevation  $z_0$ , the jet velocity and area are  $V_0$  and  $A_0$ , respectively. Determine the variation of jet area with elevation.



Solution:

Basic equations: 
$$\frac{P}{\rho} + \frac{V_0^2}{2} + g z_0 = \frac{P}{\rho} + \frac{V^2}{2} + g z$$

$$0 = \frac{\partial}{\partial t} \int_{cs} \rho dV + \int_{cs} \rho \vec{V} \cdot d\vec{A}$$

- Assumptions:
- (1) steady flow
  - (2) incompressible flow
  - (3) frictionless flow
  - (4) flow along a streamline
  - (5)  $P = P_0 = P_{atm}$
  - (6) uniform flow at a section

From the Bernoulli equation

$$V^2 = V_0^2 + 2g(z_0 - z)$$

From the continuity equation

$$0 = \int_{cs} \rho \vec{V} \cdot d\vec{A} = -\{\rho V_0 A_0\} + \{\rho V A\}$$

and

$$V_0 A_0 = V A \quad \text{or} \quad V = V_0 \frac{A_0}{A}$$

Thus

$$V_0^2 \left(\frac{A_0}{A}\right)^2 = V_0^2 + 2g(z_0 - z)$$

Solving for  $A$ ,

$$A = A_0 \sqrt{\frac{1}{1 + \frac{2g(z_0 - z)}{V_0^2}}}$$


$A(z)$

{ Note: jet area decreases as  $z$  decreases, owing to the higher velocity }

## Problem 6.56

[Difficulty: 2]

**6.56** Water flows from a very large tank through a 5-cm-diameter tube. The dark liquid in the manometer is mercury. Estimate the velocity in the pipe and the rate of discharge from the tank. (Assume the flow is frictionless.)



**Given:** Flow through tank-pipe system

**Find:** Velocity in pipe; Rate of discharge

**Solution:**

Basic equations  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$   $\Delta p = \rho \cdot g \cdot \Delta h$   $Q = V \cdot A$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Hence, applying Bernoulli between the free surface and the manometer location

$$\frac{p_{\text{atm}}}{\rho} = \frac{p}{\rho} - g \cdot H + \frac{V^2}{2} \quad \text{where we assume } V_{\text{Surface}} \ll, \text{ and } H = 4 \text{ m}$$

Hence  $p = p_{\text{atm}} + \rho \cdot g \cdot H - \rho \cdot \frac{V^2}{2}$

For the manometer  $p - p_{\text{atm}} = SG_{\text{Hg}} \cdot \rho \cdot g \cdot h_2 - \rho \cdot g \cdot h_1$

Note that we have water on one side and mercury on the other of the manometer

Combining equations  $\rho \cdot g \cdot H - \rho \cdot \frac{V^2}{2} = SG_{\text{Hg}} \cdot \rho \cdot g \cdot h_2 - \rho \cdot g \cdot h_1$  or  $V = \sqrt{2 \cdot g \cdot (H - SG_{\text{Hg}} \cdot h_2 + h_1)}$


Hence  $V = \sqrt{2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (4 - 13.6 \times 0.15 + 0.75) \cdot \text{m}}$   $V = 7.29 \frac{\text{m}}{\text{s}}$

The flow rate is  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $Q = \frac{\pi}{4} \times 7.29 \cdot \frac{\text{m}}{\text{s}} \times (0.05 \cdot \text{m})^2$   $Q = 0.0143 \frac{\text{m}^3}{\text{s}}$

### Problem 6.57

[Difficulty: 2]

6.57 In a laboratory experiment, water flows radially outward at moderate speed through the space between circular plane parallel disks. The perimeter of the disks is open to the atmosphere. The disks have diameter  $D = 150$  mm and the spacing between the disks is  $h = 0.8$  mm. The measured mass flow rate of water is  $\dot{m} = 305$  g/s. Assuming frictionless flow in the space between the disks, estimate the theoretical static pressure between the disks at radius  $r = 50$  mm. In the laboratory situation, where *some* friction is present, would the pressure measured at the same location be above or below the theoretical value? Why?



#### Solution:

Basic equations:

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho \, dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2$$

- Assumptions:
- (1) steady flow
  - (2) incompressible flow
  - (3) flow along a streamline
  - (4) neglect friction
  - (5) uniform flow at each section

Apply continuity to the CV shown

$$0 = \{-\dot{m}\} + \{pV + 2\pi r h\} \quad \text{so } V = \frac{\dot{m}}{2\pi r h}$$

$$V_1 = V_{r=50\text{mm}} = \frac{1}{2\pi} \times \frac{0.305 \text{ kg}}{\text{s}} \times \frac{\text{m}^3}{\text{kg}} \times \frac{1}{0.0008 \text{ m}} \times \frac{1}{0.05 \text{ m}} = 1.21 \text{ m/s}$$

$$V_2 = V_{r=R} = \frac{1}{2\pi} \times \frac{0.305 \text{ kg}}{\text{s}} \times \frac{\text{m}^3}{\text{kg}} \times \frac{1}{0.0008 \text{ m}} \times \frac{1}{0.075 \text{ m}} = 0.810 \text{ m/s}$$

From the Bernoulli equation

$$p_1 - p_2 = p_{r=50\text{mm}} - p_{\text{atm}} = \frac{1}{2} \rho V_2^2 - \frac{1}{2} \rho V_1^2 = \frac{\rho}{2} (V_2^2 - V_1^2)$$

$$p_{r=50\text{mm}} = \frac{1}{2} \times 999 \frac{\text{kg}}{\text{m}^3} \left[ (0.810)^2 - (1.21)^2 \right] \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$p_{r=50\text{mm}} = -404 \text{ N/m}^2 \text{ (gage)} \quad p_{r=50\text{mm}}$$

Friction would cause a pressure drop in the flow direction. Since the discharge pressure is fixed at  $p_{\text{atm}}$ , the measured pressure would be greater than the theoretical value.

## Problem 6.58

[Difficulty: 3]

**6.58** Consider frictionless, incompressible flow of air over the wing of an airplane flying at 200 km/hr. The air approaching the wing is at 65 kPa and  $-10^{\circ}\text{C}$ . At a certain point in the flow, the pressure is 60 kPa. Calculate the speed of the air relative to the wing at this point and the absolute air speed.

**Given:** Air flow over a wing

**Find:** Air speed relative to wing at a point; absolute air speed

**Solution:**

Basic equation  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$   $p = \rho \cdot R \cdot T$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data  $T = -10^{\circ}\text{C}$   $p_1 = 65 \cdot \text{kPa}$   $V_1 = 200 \cdot \frac{\text{km}}{\text{hr}}$   $p_2 = 60 \cdot \text{kPa}$   $R = 286.9 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}}$

For air  $\rho = \frac{p_1}{R \cdot T}$   $\rho = (65) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{286.9 \cdot \text{N} \cdot \text{m}} \times \frac{1}{(-10 + 273) \cdot \text{K}}$   $\rho = 0.861 \frac{\text{kg}}{\text{m}^3}$

Hence, applying Bernoulli between the upstream point (1) and the point on the wing (2)

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2} \quad \text{where we ignore gravity effects}$$

Hence 
$$V_2 = \sqrt{V_1^2 + 2 \cdot \frac{(p_1 - p_2)}{\rho}}$$

Then 
$$V_2 = \sqrt{\left(200 \cdot \frac{\text{km}}{\text{hr}}\right)^2 \times \left(\frac{1000 \cdot \text{m}}{1 \cdot \text{km}}\right)^2 \times \left(\frac{1 \cdot \text{hr}}{3600 \cdot \text{s}}\right)^2 + 2 \times \frac{\text{m}^3}{0.861 \cdot \text{kg}} \times (65 - 60) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}} V_2 = 121 \frac{\text{m}}{\text{s}}$$

NOTE: At this speed, significant density changes will occur, so this result is not very realistic

The absolute velocity is

$$V_{2\text{abs}} = V_2 - V_1 \quad V_{2\text{abs}} = 65.7 \frac{\text{m}}{\text{s}}$$

## Problem 6.59

[Difficulty: 3]

**6.59** A speedboat on hydrofoils is moving at 20 m/s in a freshwater lake. Each hydrofoil is 3 m below the surface. Assuming, as an approximation, frictionless, incompressible flow, find the stagnation pressure (gage) at the front of each hydrofoil. At one point on a hydrofoil, the pressure is  $-75$  kPa (gage). Calculate the speed of the water relative to the hydrofoil at this point and the absolute water speed.

**Given:** Water flow over a hydrofoil

**Find:** Stagnation pressure; water speed relative to airfoil at a point; absolute value

**Solution:**

Basic equations 
$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const} \quad \Delta p = \rho \cdot g \cdot h$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Available data 
$$V_1 = 20 \cdot \frac{\text{m}}{\text{s}} \quad \rho = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad h = 3 \cdot \text{m} \quad p_2 = -75 \cdot \text{kPa} \quad (\text{gage})$$

Using coordinates fixed to the hydrofoil, the pressure at depth  $h$  is 
$$p_1 = \rho \cdot g \cdot h \quad p_1 = 29.4 \cdot \text{kPa}$$

Applying Bernoulli between the upstream (1) and the stagnation point (at the front of the hydrofoil)

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_0}{\rho} \quad \text{or} \quad p_0 = p_1 + \frac{1}{2} \cdot \rho \cdot V_1^2 \quad p_0 = 229 \cdot \text{kPa}$$

Applying Bernoulli between the upstream point (1) and the point on the hydrofoil (2)

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2}$$

Hence 
$$V_2 = \sqrt{V_1^2 + 2 \cdot \frac{(p_1 - p_2)}{\rho}} \quad V_2 = 24.7 \frac{\text{m}}{\text{s}}$$


This is the speed of the water relative to the hydrofoil; in absolute coordinates 
$$V_{2\text{abs}} = V_2 + V_1 \quad V_{2\text{abs}} = 44.7 \frac{\text{m}}{\text{s}}$$

6.60 A mercury barometer is carried in a car on a day when there is no wind. The temperature is 20°C and the corrected barometer height is 761 mm of mercury. One window is open slightly as the car travels at 105 km/hr. The barometer reading in the moving car is 5 mm lower than when the car is stationary. Explain what is happening. Calculate the local speed of the air flowing past the window, *relative to the automobile*.

Solution: (a) Air speed relative to car is higher than in the free stream, thus lowering the pressure at window.

(b) Apply the Bernoulli equation in frame seen by an observer on the car:

Basic equation: 
$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g z_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g z_2$$



Assumptions: (1) Steady flow (seen by observer on car)

(2) Incompressible flow

(3) Neglect friction

(4) Flow along a streamline

(5) Neglect  $\Delta z$

Then 
$$V_2^2 = \left[ V_1^2 + 2 \left( \frac{p_1 - p_2}{\rho} \right) \right] \quad \text{or} \quad V_2 = \left[ V_1^2 + 2 \left( \frac{p_1 - p_2}{\rho} \right) \right]^{1/2} \quad (1)$$

From fluid statics

$$p_1 - p_2 = \rho g (h_1 - h_2) = SG (H_{20} g \Delta h)$$

$$= 13.6 \times 1000 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.005 \text{ m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$p_1 - p_2 = 667 \text{ N/m}^2$$

and from ideal gas

$$\rho = \frac{p}{RT} = 13.6 \times 1000 \frac{\text{kg}}{\text{m}^3} \times \frac{9.81 \text{ m}}{\text{s}^2} \times 0.761 \text{ m} \times \frac{\text{kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m}} \times \frac{1}{(273 + 20) \text{ K}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\rho = 1.21 \text{ kg/m}^3$$

Substituting into Eq. 1

$$V_2 = \left[ \left( 105 \frac{\text{km}}{\text{hr}} \times \frac{1000 \text{ m}}{\text{km}} \times \frac{\text{hr}}{3600 \text{ s}} \right)^2 + 2 \times 667 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^2}{1.21 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]^{1/2}$$

$$V_2 = 44.2 \text{ m/s} \quad (159 \text{ km/hr}) \text{ relative to car}$$

$V_2$

## Problem 6.61

[Difficulty: 2]

**6.61** A fire nozzle is coupled to the end of a hose with inside diameter  $D = 3$  in. The nozzle is contoured smoothly and has outlet diameter  $d = 1$  in. The design inlet pressure for the nozzle is  $p_1 = 100$  psi (gage). Evaluate the maximum flow rate the nozzle could deliver.

**Given:** Flow through fire nozzle

**Find:** Maximum flow rate

**Solution:**

Basic equation  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const} \quad Q = V \cdot A$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Hence, applying Bernoulli between the inlet (1) and exit (2)

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2} \quad \text{where we ignore gravity effects}$$

But we have  $Q = V_1 \cdot A_1 = V_1 \cdot \frac{\pi \cdot D^2}{4} = V_2 \cdot A_2 = \frac{\pi \cdot d^2}{4} \quad \text{so} \quad V_1 = V_2 \cdot \left(\frac{d}{D}\right)^2$

$$V_2^2 - V_2^2 \cdot \left(\frac{d}{D}\right)^4 = \frac{2 \cdot (p_2 - p_1)}{\rho}$$

Hence 
$$V_2 = \sqrt{\frac{2 \cdot (p_1 - p_2)}{\rho \cdot \left[1 - \left(\frac{d}{D}\right)^4\right]}}$$

Then 
$$V_2 = \sqrt{2 \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times (100 - 0) \cdot \frac{\text{lbf}}{\text{in}^2} \times \left(\frac{12 \cdot \text{in}}{1 \cdot \text{ft}}\right)^2 \times \frac{1}{1 - \left(\frac{1}{3}\right)^3} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2}} \quad V_2 = 124 \cdot \frac{\text{ft}}{\text{s}}$$

$$Q = V_2 \cdot \frac{\pi \cdot d^2}{4} \quad Q = \frac{\pi}{4} \times 124 \cdot \frac{\text{ft}}{\text{s}} \times \left(\frac{1}{12} \cdot \text{ft}\right)^2 \quad Q = 0.676 \cdot \frac{\text{ft}^3}{\text{s}} \quad Q = 304 \cdot \frac{\text{gal}}{\text{min}}$$

## Problem 6.62

[Difficulty: 2]

**6.62** A racing car travels at 235 mph along a straightaway. The team engineer wishes to locate an air inlet on the body of the car to obtain cooling air for the driver's suit. The plan is to place the inlet at a location where the air speed is 60 mph along the surface of the car. Calculate the static pressure at the proposed inlet location. Express the pressure rise above ambient as a fraction of the freestream dynamic pressure.

**Given:** Race car on straightaway

**Find:** Air inlet where speed is 60 mph; static pressure; pressure rise

**Solution:**

Basic equation 
$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline 5) Standard atmosphere

Available data 
$$p_{\text{atm}} = 101 \cdot \text{kPa} \quad \rho = 0.002377 \frac{\text{slug}}{\text{ft}^3} \quad V_1 = 235 \cdot \text{mph} \quad V_2 = 60 \cdot \text{mph}$$

Between location 1 (the upstream flow at 235 mph with respect to the car), and point 2 (on the car where  $V = 60$  mph), Bernoulli becomes

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_{\text{atm}}}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2}$$

Hence 
$$p_2 = p_{\text{atm}} + \frac{1}{2} \cdot \rho \cdot V_1^2 \cdot \left[ 1 - \left( \frac{V_2}{V_1} \right)^2 \right] \quad p_2 = 15.6 \text{ psi}$$

Note that the pressure rise is 
$$\Delta p = \frac{1}{2} \cdot \rho \cdot V_1^2 \cdot \left[ 1 - \left( \frac{V_2}{V_1} \right)^2 \right] \quad \Delta p = 0.917 \cdot \text{psi}$$

The freestream dynamic pressure is 
$$q = \frac{1}{2} \cdot \rho \cdot V_1^2 \quad q = 0.980 \cdot \text{psi}$$

Then 
$$\frac{\Delta p}{q} = 93.5\%$$


Note that at this speed the flow is borderline compressible!

### Problem 6.63

[Difficulty: 2]

6.63 Steady, frictionless, and incompressible flow from left to right over a stationary circular cylinder, of radius  $a$ , is represented by the velocity field

$$\vec{V} = U \left[ 1 - \left( \frac{a}{r} \right)^2 \right] \cos \theta \hat{e}_r - U \left[ 1 + \left( \frac{a}{r} \right)^2 \right] \sin \theta \hat{e}_\theta$$



Obtain an expression for the pressure distribution along the streamline forming the cylinder surface,  $r = a$ . Determine the locations where the static pressure on the cylinder is equal to the freestream static pressure.

Solution:

Basic equation:  $\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{constant}$

- Assumptions:
- (1) steady flow (given)
  - (2) incompressible flow (given)
  - (3) frictionless flow (given)
  - (4) flow along a streamline.

Along the cylinder surface  $r = a$  and  $\vec{V} = -2U \sin \theta \hat{e}_\theta$

Applying the Bernoulli equation along the streamline  $r = a$ ,

$$\frac{p}{\rho} + \frac{V^2}{2} = \frac{p_\infty}{\rho} + \frac{U^2}{2}$$

$$p = p_\infty + \frac{\rho}{2} (U^2 - V^2) = p_\infty + \frac{\rho}{2} (U^2 - 4U^2 \sin^2 \theta)$$

$$p = p_\infty + \frac{\rho}{2} U^2 (1 - 4 \sin^2 \theta) \quad \underline{p}$$

For  $p = p_\infty$ ,  $1 - 4 \sin^2 \theta = 0$  and  $\sin \theta = \pm 0.5$


$$\therefore \theta = 30^\circ, 150^\circ, 210^\circ, 330^\circ \quad \underline{\theta}$$

500 SHEETS, FILLER 3 SQUARE  
 250 SHEETS, FILLER 3 SQUARE  
 100 SHEETS, FILLER 3 SQUARE  
 200 SHEETS, FILLER 3 SQUARE  
 100 RECYCLED WHITE 3 SQUARE  
 200 RECYCLED WHITE 3 SQUARE  
 13-782  
 42-381  
 42-382  
 42-383  
 42-384  
 42-385  
 42-386  
 42-387  
 42-388  
 42-389  
 42-390  
 42-391  
 42-392  
 42-393  
 42-394  
 42-395  
 42-396  
 42-397  
 42-398  
 42-399  
 42-400  
 42-401  
 42-402  
 42-403  
 42-404  
 42-405  
 42-406  
 42-407  
 42-408  
 42-409  
 42-410  
 42-411  
 42-412  
 42-413  
 42-414  
 42-415  
 42-416  
 42-417  
 42-418  
 42-419  
 42-420  
 42-421  
 42-422  
 42-423  
 42-424  
 42-425  
 42-426  
 42-427  
 42-428  
 42-429  
 42-430  
 42-431  
 42-432  
 42-433  
 42-434  
 42-435  
 42-436  
 42-437  
 42-438  
 42-439  
 42-440  
 42-441  
 42-442  
 42-443  
 42-444  
 42-445  
 42-446  
 42-447  
 42-448  
 42-449  
 42-450  
 42-451  
 42-452  
 42-453  
 42-454  
 42-455  
 42-456  
 42-457  
 42-458  
 42-459  
 42-460  
 42-461  
 42-462  
 42-463  
 42-464  
 42-465  
 42-466  
 42-467  
 42-468  
 42-469  
 42-470  
 42-471  
 42-472  
 42-473  
 42-474  
 42-475  
 42-476  
 42-477  
 42-478  
 42-479  
 42-480  
 42-481  
 42-482  
 42-483  
 42-484  
 42-485  
 42-486  
 42-487  
 42-488  
 42-489  
 42-490  
 42-491  
 42-492  
 42-493  
 42-494  
 42-495  
 42-496  
 42-497  
 42-498  
 42-499  
 42-500  
 42-501  
 42-502  
 42-503  
 42-504  
 42-505  
 42-506  
 42-507  
 42-508  
 42-509  
 42-510  
 42-511  
 42-512  
 42-513  
 42-514  
 42-515  
 42-516  
 42-517  
 42-518  
 42-519  
 42-520  
 42-521  
 42-522  
 42-523  
 42-524  
 42-525  
 42-526  
 42-527  
 42-528  
 42-529  
 42-530  
 42-531  
 42-532  
 42-533  
 42-534  
 42-535  
 42-536  
 42-537  
 42-538  
 42-539  
 42-540  
 42-541  
 42-542  
 42-543  
 42-544  
 42-545  
 42-546  
 42-547  
 42-548  
 42-549  
 42-550  
 42-551  
 42-552  
 42-553  
 42-554  
 42-555  
 42-556  
 42-557  
 42-558  
 42-559  
 42-560  
 42-561  
 42-562  
 42-563  
 42-564  
 42-565  
 42-566  
 42-567  
 42-568  
 42-569  
 42-570  
 42-571  
 42-572  
 42-573  
 42-574  
 42-575  
 42-576  
 42-577  
 42-578  
 42-579  
 42-580  
 42-581  
 42-582  
 42-583  
 42-584  
 42-585  
 42-586  
 42-587  
 42-588  
 42-589  
 42-590  
 42-591  
 42-592  
 42-593  
 42-594  
 42-595  
 42-596  
 42-597  
 42-598  
 42-599  
 42-600  
 42-601  
 42-602  
 42-603  
 42-604  
 42-605  
 42-606  
 42-607  
 42-608  
 42-609  
 42-610  
 42-611  
 42-612  
 42-613  
 42-614  
 42-615  
 42-616  
 42-617  
 42-618  
 42-619  
 42-620  
 42-621  
 42-622  
 42-623  
 42-624  
 42-625  
 42-626  
 42-627  
 42-628  
 42-629  
 42-630  
 42-631  
 42-632  
 42-633  
 42-634  
 42-635  
 42-636  
 42-637  
 42-638  
 42-639  
 42-640  
 42-641  
 42-642  
 42-643  
 42-644  
 42-645  
 42-646  
 42-647  
 42-648  
 42-649  
 42-650  
 42-651  
 42-652  
 42-653  
 42-654  
 42-655  
 42-656  
 42-657  
 42-658  
 42-659  
 42-660  
 42-661  
 42-662  
 42-663  
 42-664  
 42-665  
 42-666  
 42-667  
 42-668  
 42-669  
 42-670  
 42-671  
 42-672  
 42-673  
 42-674  
 42-675  
 42-676  
 42-677  
 42-678  
 42-679  
 42-680  
 42-681  
 42-682  
 42-683  
 42-684  
 42-685  
 42-686  
 42-687  
 42-688  
 42-689  
 42-690  
 42-691  
 42-692  
 42-693  
 42-694  
 42-695  
 42-696  
 42-697  
 42-698  
 42-699  
 42-700  
 42-701  
 42-702  
 42-703  
 42-704  
 42-705  
 42-706  
 42-707  
 42-708  
 42-709  
 42-710  
 42-711  
 42-712  
 42-713  
 42-714  
 42-715  
 42-716  
 42-717  
 42-718  
 42-719  
 42-720  
 42-721  
 42-722  
 42-723  
 42-724  
 42-725  
 42-726  
 42-727  
 42-728  
 42-729  
 42-730  
 42-731  
 42-732  
 42-733  
 42-734  
 42-735  
 42-736  
 42-737  
 42-738  
 42-739  
 42-740  
 42-741  
 42-742  
 42-743  
 42-744  
 42-745  
 42-746  
 42-747  
 42-748  
 42-749  
 42-750  
 42-751  
 42-752  
 42-753  
 42-754  
 42-755  
 42-756  
 42-757  
 42-758  
 42-759  
 42-760  
 42-761  
 42-762  
 42-763  
 42-764  
 42-765  
 42-766  
 42-767  
 42-768  
 42-769  
 42-770  
 42-771  
 42-772  
 42-773  
 42-774  
 42-775  
 42-776  
 42-777  
 42-778  
 42-779  
 42-780  
 42-781  
 42-782  
 42-783  
 42-784  
 42-785  
 42-786  
 42-787  
 42-788  
 42-789  
 42-790  
 42-791  
 42-792  
 42-793  
 42-794  
 42-795  
 42-796  
 42-797  
 42-798  
 42-799  
 42-800  
 42-801  
 42-802  
 42-803  
 42-804  
 42-805  
 42-806  
 42-807  
 42-808  
 42-809  
 42-810  
 42-811  
 42-812  
 42-813  
 42-814  
 42-815  
 42-816  
 42-817  
 42-818  
 42-819  
 42-820  
 42-821  
 42-822  
 42-823  
 42-824  
 42-825  
 42-826  
 42-827  
 42-828  
 42-829  
 42-830  
 42-831  
 42-832  
 42-833  
 42-834  
 42-835  
 42-836  
 42-837  
 42-838  
 42-839  
 42-840  
 42-841  
 42-842  
 42-843  
 42-844  
 42-845  
 42-846  
 42-847  
 42-848  
 42-849  
 42-850  
 42-851  
 42-852  
 42-853  
 42-854  
 42-855  
 42-856  
 42-857  
 42-858  
 42-859  
 42-860  
 42-861  
 42-862  
 42-863  
 42-864  
 42-865  
 42-866  
 42-867  
 42-868  
 42-869  
 42-870  
 42-871  
 42-872  
 42-873  
 42-874  
 42-875  
 42-876  
 42-877  
 42-878  
 42-879  
 42-880  
 42-881  
 42-882  
 42-883  
 42-884  
 42-885  
 42-886  
 42-887  
 42-888  
 42-889  
 42-890  
 42-891  
 42-892  
 42-893  
 42-894  
 42-895  
 42-896  
 42-897  
 42-898  
 42-899  
 42-900  
 42-901  
 42-902  
 42-903  
 42-904  
 42-905  
 42-906  
 42-907  
 42-908  
 42-909  
 42-910  
 42-911  
 42-912  
 42-913  
 42-914  
 42-915  
 42-916  
 42-917  
 42-918  
 42-919  
 42-920  
 42-921  
 42-922  
 42-923  
 42-924  
 42-925  
 42-926  
 42-927  
 42-928  
 42-929  
 42-930  
 42-931  
 42-932  
 42-933  
 42-934  
 42-935  
 42-936  
 42-937  
 42-938  
 42-939  
 42-940  
 42-941  
 42-942  
 42-943  
 42-944  
 42-945  
 42-946  
 42-947  
 42-948  
 42-949  
 42-950  
 42-951  
 42-952  
 42-953  
 42-954  
 42-955  
 42-956  
 42-957  
 42-958  
 42-959  
 42-960  
 42-961  
 42-962  
 42-963  
 42-964  
 42-965  
 42-966  
 42-967  
 42-968  
 42-969  
 42-970  
 42-971  
 42-972  
 42-973  
 42-974  
 42-975  
 42-976  
 42-977  
 42-978  
 42-979  
 42-980  
 42-981  
 42-982  
 42-983  
 42-984  
 42-985  
 42-986  
 42-987  
 42-988  
 42-989  
 42-990  
 42-991  
 42-992  
 42-993  
 42-994  
 42-995  
 42-996  
 42-997  
 42-998  
 42-999  
 43-000  
 43-001  
 43-002  
 43-003  
 43-004  
 43-005  
 43-006  
 43-007  
 43-008  
 43-009  
 43-010  
 43-011  
 43-012  
 43-013  
 43-014  
 43-015  
 43-016  
 43-017  
 43-018  
 43-019  
 43-020  
 43-021  
 43-022  
 43-023  
 43-024  
 43-025  
 43-026  
 43-027  
 43-028  
 43-029  
 43-030  
 43-031  
 43-032  
 43-033  
 43-034  
 43-035  
 43-036  
 43-037  
 43-038  
 43-039  
 43-040  
 43-041  
 43-042  
 43-043  
 43-044  
 43-045  
 43-046  
 43-047  
 43-048  
 43-049  
 43-050  
 43-051  
 43-052  
 43-053  
 43-054  
 43-055  
 43-056  
 43-057  
 43-058  
 43-059  
 43-060  
 43-061  
 43-062  
 43-063  
 43-064  
 43-065  
 43-066  
 43-067  
 43-068  
 43-069  
 43-070  
 43-071  
 43-072  
 43-073  
 43-074  
 43-075  
 43-076  
 43-077  
 43-078  
 43-079  
 43-080  
 43-081  
 43-082  
 43-083  
 43-084  
 43-085  
 43-086  
 43-087  
 43-088  
 43-089  
 43-090  
 43-091  
 43-092  
 43-093  
 43-094  
 43-095  
 43-096  
 43-097  
 43-098  
 43-099  
 43-100  
 43-101  
 43-102  
 43-103  
 43-104  
 43-105  
 43-106  
 43-107  
 43-108  
 43-109  
 43-110  
 43-111  
 43-112  
 43-113  
 43-114  
 43-115  
 43-116  
 43-117  
 43-118  
 43-119  
 43-120  
 43-121  
 43-122  
 43-123  
 43-124  
 43-125  
 43-126  
 43-127  
 43-128  
 43-129  
 43-130  
 43-131  
 43-132  
 43-133  
 43-134  
 43-135  
 43-136  
 43-137  
 43-138  
 43-139  
 43-140  
 43-141  
 43-142  
 43-143  
 43-144  
 43-145  
 43-146  
 43-147  
 43-148  
 43-149  
 43-150  
 43-151  
 43-152  
 43-153  
 43-154  
 43-155  
 43-156  
 43-157  
 43-158  
 43-159  
 43-160  
 43-161  
 43-162  
 43-163  
 43-164  
 43-165  
 43-166  
 43-167  
 43-168  
 43-169  
 43-170  
 43-171  
 43-172  
 43-173  
 43-174  
 43-175  
 43-176  
 43-177  
 43-178  
 43-179  
 43-180  
 43-181  
 43-182  
 43-183  
 43-184  
 43-185  
 43-186  
 43-187  
 43-188  
 43-189  
 43-190  
 43-191  
 43-192  
 43-193  
 43-194  
 43-195  
 43-196  
 43-197  
 43-198  
 43-199  
 43-200  
 43-201  
 43-202  
 43-203  
 43-204  
 43-205  
 43-206  
 43-207  
 43-208  
 43-209  
 43-210  
 43-211  
 43-212  
 43-213  
 43-214  
 43-215  
 43-216  
 43-217  
 43-218  
 43-219  
 43-220  
 43-221  
 43-222  
 43-223  
 43-224  
 43-225  
 43-226  
 43-227  
 43-228  
 43-229  
 43-230  
 43-231  
 43-232  
 43-233  
 43-234  
 43-235  
 43-236  
 43-237  
 43-238  
 43-239  
 43-240  
 43-241  
 43-242  
 43-243  
 43-244  
 43-245  
 43-246  
 43-247  
 43-248  
 43-249  
 43-250  
 43-251  
 43-252  
 43-253  
 43-254  
 43-255  
 43-256  
 43-257  
 43-258  
 43-259  
 43-260  
 43-261  
 43-262  
 43-263  
 43-264  
 43-265  
 43-266  
 43-267  
 43-268  
 43-269  
 43-270  
 43-271  
 43-272  
 43-273  
 43-274  
 43-275  
 43-276  
 43-277  
 43-278  
 43-279  
 43-280  
 43-281  
 43-282  
 43-283  
 43-284  
 43-285  
 43-286  
 43-287  
 43-288  
 43-289  
 43-290  
 43-291  
 43-292  
 43-293  
 43-294  
 43-295  
 43-296  
 43-297  
 43-298  
 43-299  
 43-300  
 43-301  
 43-302  
 43-303  
 43-304  
 43-305  
 43-306  
 43-307  
 43-308  
 43-309  
 43-310  
 43-311  
 43-312  
 43-313  
 43-314  
 43-315  
 43-316  
 43-317  
 43-318  
 43-319  
 43-320  
 43-321  
 43-322  
 43-323  
 43-324  
 43-325  
 43-326  
 43-327  
 43-328  
 43-329  
 43-330  
 43-331  
 43-332  
 43-333  
 43-334  
 43-335  
 43-336  
 43-337  
 43-338  
 43-339  
 43-340  
 43-341  
 43-342  
 43-343  
 43-344  
 43-345  
 43-346  
 43-347  
 43-348  
 43-349  
 43-350  
 43-351  
 43-352  
 43-353  
 43-354  
 43-355  
 43-356  
 43-357  
 43-358  
 43-359  
 43-360  
 43-361  
 43-362  
 43-363  
 43-364  
 43-365  
 43-366  
 43-367  
 43-368  
 43-369  
 43-370  
 43-371  
 43-372  
 43-373  
 43-374  
 43-375  
 43-376  
 43-377  
 43-378  
 43-379  
 43-380  
 43-381  
 43-3

## Problem 6.64

[Difficulty: 3]

**6.64** The velocity field for a plane source at a distance  $h$  above an infinite wall aligned along the  $x$  axis was given in Problem 6.8. Using the data from that problem, plot the pressure distribution along the wall from  $x = -10h$  to  $x = +10h$  (assume the pressure at infinity is atmospheric). Find the net force on the wall if the pressure on the lower surface is atmospheric. Does the force tend to pull the wall towards the source, or push it away?



**Given:** Velocity field

**Find:** Pressure distribution along wall; plot distribution; net force on wall

**Solution:**

The given data is

$$q = 2 \cdot \frac{\text{m}^3}{\text{s} \cdot \text{m}} \quad h = 1 \cdot \text{m} \quad \rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$$

$$u = \frac{q \cdot x}{2 \cdot \pi \cdot [x^2 + (y - h)^2]} + \frac{q \cdot x}{2 \cdot \pi \cdot [x^2 + (y + h)^2]} \quad v = \frac{q \cdot (y - h)}{2 \cdot \pi \cdot [x^2 + (y - h)^2]} + \frac{q \cdot (y + h)}{2 \cdot \pi \cdot [x^2 + (y + h)^2]}$$

The governing equation is the Bernoulli equation

$$\frac{p}{\rho} + \frac{1}{2} \cdot V^2 + g \cdot z = \text{const} \quad \text{where} \quad V = \sqrt{u^2 + v^2}$$

Apply this to point arbitrary point  $(x,0)$  on the wall and at infinity (neglecting gravity)

At  $|x| \rightarrow 0$        $u \rightarrow 0$        $v \rightarrow 0$        $V \rightarrow 0$

At point  $(x,0)$

$$u = \frac{q \cdot x}{\pi \cdot (x^2 + h^2)} \quad v = 0 \quad V = \frac{q \cdot x}{\pi \cdot (x^2 + h^2)}$$

Hence the Bernoulli equation becomes

$$\frac{p_{\text{atm}}}{\rho} = \frac{p}{\rho} + \frac{1}{2} \cdot \left[ \frac{q \cdot x}{\pi \cdot (x^2 + h^2)} \right]^2$$

or (with pressure expressed as gage pressure)

$$p(x) = -\frac{\rho}{2} \cdot \left[ \frac{q \cdot x}{\pi \cdot (x^2 + h^2)} \right]^2$$

(Alternatively, the pressure distribution could have been obtained from Problem 6.8, where the momentum equation was used to find

the pressure gradient  $\frac{\partial}{\partial x} p = \frac{\rho \cdot q^2 \cdot x \cdot (x^2 - h^2)}{\pi^2 \cdot (x^2 + h^2)^3}$  along the wall. Integration of this with respect to  $x$  leads to the same result for  $p(x)$ )

The plot of pressure can be done in *Excel* (see below). From the plot it is clear that the wall experiences a negative gage pressure on the upper surface (and zero gage pressure on the lower), so the net force on the wall is upwards, towards the source

The force per width on the wall is given by  $F = \int_{-10 \cdot h}^{10 \cdot h} (p_{\text{upper}} - p_{\text{lower}}) dx$   $F = -\frac{\rho \cdot q^2}{2 \cdot \pi^2} \int_{-10 \cdot h}^{10 \cdot h} \frac{x^2}{(x^2 + h^2)^2} dx$

The integral is  $\int \frac{x^2}{(x^2 + h^2)^2} dx = \frac{\text{atan}\left(\frac{x}{h}\right)}{2 \cdot h} - \frac{x}{2 \cdot h^2 + 2 \cdot x^2}$

so  $F = -\frac{\rho \cdot q^2}{2 \cdot \pi^2 \cdot h} \cdot \left(-\frac{10}{101} + \text{atan}(10)\right)$

$$F = -\frac{1}{2 \cdot \pi^2} \times 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left(2 \cdot \frac{\text{m}^2}{\text{s}}\right)^2 \times \frac{1}{1 \cdot \text{m}} \times \left(-\frac{10}{101} + \text{atan}(10)\right) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F = -278 \cdot \frac{\text{N}}{\text{m}}$$


In Excel:

$$q = 2 \text{ m}^3/\text{s}/\text{m}$$

$$h = 1 \text{ m}$$

$$\rho = 1000 \text{ kg}/\text{m}^3$$

x (m)	p (Pa)
0.0	0.00
1.0	-50.66
2.0	-32.42
3.0	-18.24
4.0	-11.22
5.0	-7.49
6.0	-5.33
7.0	-3.97
8.0	-3.07
9.0	-2.44
10.0	-1.99



## Problem 6.65

[Difficulty: 3]

**6.65** The velocity field for a plane doublet is given in Table 6.2. If  $\Lambda = 3 \text{ m}^3 \cdot \text{s}^{-1}$ , the fluid density is  $\rho = 1.5 \text{ kg/m}^3$ , and the pressure at infinity is 100 kPa, plot the pressure along the  $x$  axis from  $x = -2.0 \text{ m}$  to  $-0.5 \text{ m}$  and  $x = 0.5 \text{ m}$  to  $2.0 \text{ m}$ .

**Given:** Velocity field for plane doublet

**Find:** Pressure distribution along  $x$  axis; plot distribution

**Solution:**

The governing equation is the Bernoulli equation  $\frac{p}{\rho} + \frac{1}{2} \cdot V^2 + g \cdot z = \text{const}$  where  $V = \sqrt{u^2 + v^2}$

The given data is  $\Lambda = 3 \cdot \frac{\text{m}^3}{\text{s}}$   $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$   $p_0 = 100 \cdot \text{kPa}$

From Table 6.1  $V_r = -\frac{\Lambda}{r^2} \cdot \cos(\theta)$   $V_\theta = -\frac{\Lambda}{r^2} \cdot \sin(\theta)$

where  $V_r$  and  $V_\theta$  are the velocity components in cylindrical coordinates  $(r, \theta)$ . For points along the  $x$  axis,  $r = x$ ,  $\theta = 0$ ,  $V_r = u$  and  $V_\theta = v = 0$

$$u = -\frac{\Lambda}{x^2} \quad v = 0$$

so (neglecting gravity)  $\frac{p}{\rho} + \frac{1}{2} \cdot u^2 = \text{const}$


Apply this to point arbitrary point  $(x,0)$  on the  $x$  axis and at infinity

$$\text{At } |x| \rightarrow 0 \quad u \rightarrow 0 \quad p \rightarrow p_0 \quad \text{At point } (x,0) \quad u = -\frac{\Lambda}{x^2}$$


Hence the Bernoulli equation becomes  $\frac{p_0}{\rho} = \frac{p}{\rho} + \frac{\Lambda^2}{2 \cdot x^4}$  or  $p(x) = p_0 - \frac{\rho \cdot \Lambda^2}{2 \cdot x^4}$

The plot of pressure can be done in *Excel*:

$x$ (m)	$p$ (Pa)
0.5	99.892
0.6	99.948
0.7	99.972
0.8	99.984
0.9	99.990
1.0	99.993
1.1	99.995
1.2	99.997
1.3	99.998
1.4	99.998
1.5	99.999
1.6	99.999
1.7	99.999
1.8	99.999
1.9	99.999
2.0	100.000



6.66 A smoothly contoured nozzle, with outlet diameter  $d = 20$  mm, is coupled to a straight pipe by means of flanges. Water flows in the pipe, of diameter  $D = 50$  mm, and the nozzle discharges to the atmosphere. For steady flow and neglecting the effects of viscosity, find the volume flow rate in the pipe corresponding to a calculated axial force of 45.5 N needed to keep the nozzle attached to the pipe.



Solution: Apply continuity,  $x$  momentum, and Bernoulli.

Basic equation:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g \int_1^2 dz = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g \int_1^2 dz$$

$$F_{Rx} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

- Assumptions: (1) Steady flow (2) Uniform flow at each section (3) Flow along a streamline (4) Incompressible flow (5) No friction (6) Horizontal,  $F_{Bx} = 0, z_1 = z_2$  (7) Use gage pressures

Then  $0 = \{-V_1 A_1\} + \{+V_2 A_2\}$ ;  $V_2 = V_1 \frac{A_1}{A_2} = V_1 \left(\frac{D}{d}\right)^2$ ;  $Q = V_1 A_1 = V_2 A_2$

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{V_2^2}{2}$$

$$p_1 = \rho \left( \frac{V_2^2}{2} - \frac{V_1^2}{2} \right) = \frac{\rho V_1^2}{2} \left[ \left( \frac{V_2}{V_1} \right)^2 - 1 \right] = \frac{\rho V_1^2}{2} \left[ \left( \frac{D}{d} \right)^4 - 1 \right]$$

$$R_x + p_1 A_1 - p_2 A_2 = u_1 \{-\rho V_1 A_1\} + u_2 \{+\rho V_2 A_2\} = \rho V_1 A_1 (V_2 - V_1)$$

$$u_1 = V_1 \quad u_2 = V_2$$

$$R_x + A_1 \frac{\rho V_1^2}{2} \left[ \left( \frac{D}{d} \right)^4 - 1 \right] = \rho V_1^2 A_1 \left( \frac{V_2}{V_1} - 1 \right) = \rho V_1^2 A_1 \left[ \left( \frac{D}{d} \right)^2 - 1 \right]$$

Thus  $V_1^2 = \frac{-2R_x}{\rho A_1} \frac{1}{\left( \frac{D}{d} \right)^4 - 2 \left( \frac{D}{d} \right)^2 + 1}$  so  $V_1 = \sqrt{\frac{-2R_x}{\rho A_1} \frac{1}{\left( \frac{D}{d} \right)^2 - 1}}$

$$V_1 = \left[ \frac{-2 \times 45.5 \text{ N}}{999 \text{ kg/m}^3 \times \pi (0.050 \text{ m})^2} \times \frac{4}{\left( \frac{50}{20} \right)^2 - 1} \right]^{\frac{1}{2}} = 1.30 \text{ m/s}$$

Finally,


$$Q = V_1 A_1 = 1.30 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} (0.050 \text{ m})^2 = 2.55 \times 10^{-3} \text{ m}^3/\text{s}$$

{ Note: It is necessary to recognize that  $R_x < 0$  for a nozzle, see Example Problem 4.7. }

## Problem 6.67

[Difficulty: 3]

**6.67** A fire nozzle is coupled to the end of a hose with inside diameter  $D = 75$  mm. The nozzle is smoothly contoured and its outlet diameter is  $d = 25$  mm. The nozzle is designed to operate at an inlet water pressure of 700 kPa (gage). Determine the design flow rate of the nozzle. (Express your answer in L/s.) Evaluate the axial force required to hold the nozzle in place. Indicate whether the hose coupling is in tension or compression.



**Given:** Flow through fire nozzle

**Find:** Maximum flow rate

**Solution:**

Basic equation  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$   $Q = V \cdot A$   $F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Hence, applying Bernoulli between the inlet (1) and exit (2)

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2} \quad \text{where we ignore gravity effects}$$

But we have  $Q = V_1 \cdot A_1 = V_1 \cdot \frac{\pi \cdot D^2}{4} = V_2 \cdot \frac{\pi \cdot d^2}{4}$  so  $V_1 = V_2 \cdot \left(\frac{d}{D}\right)^2$

Hence in Bernoulli  $V_2^2 - V_2^2 \cdot \left(\frac{d}{D}\right)^4 = \frac{2 \cdot (p_2 - p_1)}{\rho}$  or  $V_2 = \sqrt{\frac{2 \cdot (p_1 - p_2)}{\rho \cdot \left[1 - \left(\frac{d}{D}\right)^4\right]}}$

$$V_2 = \sqrt{2 \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times (700 - 0) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{1 - \left(\frac{25}{75}\right)^4} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}} \quad V_2 = 37.6 \frac{\text{m}}{\text{s}}$$

Then  $Q = V_2 \cdot \frac{\pi \cdot d^2}{4}$   $Q = \frac{\pi}{4} \times 37.6 \cdot \frac{\text{m}}{\text{s}} \times (0.025 \cdot \text{m})^2$   $Q = 0.0185 \cdot \frac{\text{m}^3}{\text{s}}$   $Q = 18.5 \cdot \frac{\text{L}}{\text{s}}$

From x momentum  $R_x + p_1 \cdot A_1 = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2)$  using gage pressures

Hence  $R_x = -p_1 \cdot \frac{\pi \cdot D^2}{4} + \rho \cdot Q \cdot (V_2 - V_1) = -p_1 \cdot \frac{\pi \cdot D^2}{4} + \rho \cdot Q \cdot V_2 \cdot \left[1 - \left(\frac{d}{D}\right)^2\right]$


$$R_x = -700 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\pi}{4} \cdot (0.075 \cdot \text{m})^2 + 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 0.0185 \cdot \frac{\text{m}^3}{\text{s}} \times 37.6 \cdot \frac{\text{m}}{\text{s}} \times \left[1 - \left(\frac{25}{75}\right)^2\right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad R_x = -2423 \text{ N}$$

This is the force of the nozzle on the fluid; hence the force of the fluid on the nozzle is 2400 N to the right; the nozzle is in tension

6.68 Water flows steadily through a 3.25-in.-diameter pipe and discharges through a 1.25-in.-diameter nozzle to atmospheric pressure. The flow rate is 24.5 gpm. Calculate the minimum static pressure required in the pipe to produce this flow rate. Evaluate the axial force of the nozzle assembly on the pipe flange.

Solution:

Apply the Bernoulli equation along the central streamline between sections ① and ②



$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g z_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g z_2$$

- Assumptions: (1) steady flow (2) incompressible flow  
 (3) frictionless flow (4) flow along a streamline.  
 (5)  $g z = 0$  (6) uniform flow at each section

then  $p_1 = p_2 + \frac{\rho}{2} (V_2^2 - V_1^2) = p_2 + \frac{\rho V_2^2}{2} \left[ 1 - \left( \frac{V_1}{V_2} \right)^2 \right]$

$p_2 = p_{atm}$  and from continuity,  $A_2 V_2 = A_1 V_1$ .

$\therefore p_{1g} = \frac{\rho}{2} V_2^2 \left[ 1 - \left( \frac{A_2}{A_1} \right)^2 \right] = \frac{\rho V_2^2}{2} \left[ 1 - \left( \frac{D_2}{D_1} \right)^4 \right]$

$V_2 = \frac{Q}{A} = \frac{24.5 \text{ gal}}{\pi (3.25)^2} = \frac{24.5 \text{ gal}}{\pi} \times \frac{1.488 \text{ ft}^3}{\text{gal}} \times \frac{1}{\pi (3.25)^2} = \frac{1.14 \text{ ft}^3}{\text{ft}^2 \cdot \text{s}}$

$V_2 = 6.41 \text{ ft/s}$  and

$p_{1g} = \frac{1}{2} \times 1.94 \frac{\text{slug}}{\text{ft}^3} \times (6.41)^2 \frac{\text{ft}^2}{\text{s}^2} \times \frac{\text{lb} \cdot \text{s}^2}{\text{ft} \cdot \text{slug}} \left[ 1 - \left( \frac{1.25}{3.25} \right)^4 \right] = 39.0 \text{ psf} \leftarrow p_1$

b) Apply the x momentum equation to the CV

$F_{R_x} + F_{p_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{v} \cdot d\vec{A}$

$R_x + p_1 A_1 = u_1 \{ -\dot{m} \} + u_2 \{ \dot{m} \} = -V_1 \dot{m} + V_2 \dot{m}$

$R_x = -p_1 A_1 + \dot{m} (V_2 - V_1) = -p_1 A_1 + \rho Q V_2 \left( 1 - \frac{V_1}{V_2} \right)$

$= -39 \frac{\text{lb}}{\text{ft}^2} \times \pi (3.25)^2 \text{ ft}^2 + 1.94 \frac{\text{sl}}{\text{ft}^3} \times 24.5 \frac{\text{gal}}{\text{s}} \times \frac{\text{ft}^3}{\text{gal}} \times \frac{1}{\pi (3.25)^2} \times 6.41 \text{ ft} \left[ 1 - \left( \frac{1.25}{3.25} \right)^2 \right] \frac{\text{lb} \cdot \text{s}^2}{\text{ft} \cdot \text{sl}}$


$R_x = -2.25 + 0.58 = -1.67 \text{ lbf}$

Force of nozzle on flange  $K_x = -R_x = 1.67 \text{ lbf} \leftarrow K_x$

## Problem 6.69

[Difficulty: 3]

**6.69** Water flows steadily through the reducing elbow shown. The elbow is smooth and short, and the flow accelerates; so the effect of friction is small. The volume flow rate is  $Q = 2.5 \text{ L/s}$ . The elbow is in a horizontal plane. Estimate the gage pressure at section ①. Calculate the  $x$  component of the force exerted by the reducing elbow on the supply pipe.



**Given:** Flow through reducing elbow

**Find:** Gage pressure at location 1;  $x$  component of force

**Solution:**

Basic equations:  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$        $F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$        $Q = V \cdot A$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline 5) Ignore elevation change 6)  $p_2 = p_{\text{atm}}$

Available data:  $Q = 2.5 \frac{\text{L}}{\text{s}}$        $Q = 2.5 \times 10^{-3} \frac{\text{m}^3}{\text{s}}$        $D = 45\text{-mm}$        $d = 25\text{-mm}$        $\rho = 999 \frac{\text{kg}}{\text{m}^3}$

From continuity  $V_1 = \frac{Q}{\left(\frac{\pi \cdot D^2}{4}\right)}$        $V_1 = 1.57 \frac{\text{m}}{\text{s}}$        $V_2 = \frac{Q}{\left(\frac{\pi \cdot d^2}{4}\right)}$        $V_2 = 5.09 \frac{\text{m}}{\text{s}}$

Hence, applying Bernoulli between the inlet (1) and exit (2)  $\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2}$

or, in gage pressures  $p_{1g} = \frac{\rho}{2} \cdot (V_2^2 - V_1^2)$        $p_{1g} = 11.7 \cdot \text{kPa}$

From  $x$ -momentum  $R_x + p_{1g} \cdot A_1 = u_1 \cdot (-m_{\text{rate}}) + u_2 \cdot (m_{\text{rate}}) = -m_{\text{rate}} \cdot V_1 = -\rho \cdot Q \cdot V_1$       because  $u_1 = V_1$        $u_2 = 0$


$R_x = -p_{1g} \cdot \frac{\pi \cdot D^2}{4} - \rho \cdot Q \cdot V_1$        $R_x = -22.6 \text{ N}$

The force on the supply pipe is then  $K_x = -R_x$        $K_x = 22.6 \text{ N}$       on the pipe to the right

## Problem 6.70

[Difficulty: 3]

**6.70** A flow nozzle is a device for measuring the flow rate in a pipe. This particular nozzle is to be used to measure low-speed air flow for which compressibility may be neglected. During operation, the pressures  $p_1$  and  $p_2$  are recorded, as well as upstream temperature,  $T_1$ . Find the mass flow rate in terms of  $\Delta p = p_2 - p_1$  and  $T_1$ , the gas constant for air, and device diameters  $D_1$  and  $D_2$ . Assume the flow is frictionless. Will the actual flow be more or less than this predicted flow? Why?



**Given:** Flow nozzle

**Find:** Mass flow rate in terms of  $\Delta p$ ,  $T_1$  and  $D_1$  and  $D_2$

**Solution:**

Basic equation 
$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const} \quad Q = V \cdot A$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Hence, applying Bernoulli between the inlet (1) and exit (2)

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2} \quad \text{where we ignore gravity effects}$$

But we have 
$$Q = V_1 \cdot A_1 = V_1 \cdot \frac{\pi \cdot D_1^2}{4} = V_2 \cdot \frac{\pi \cdot D_2^2}{4} \quad \text{so} \quad V_1 = V_2 \cdot \left(\frac{D_2}{D_1}\right)^2$$

Note that we assume the flow at  $D_2$  is at the same pressure as the entire section 2; this will be true if there is turbulent mixing

Hence 
$$V_2^2 - V_2^2 \cdot \left(\frac{D_2}{D_1}\right)^4 = \frac{2 \cdot (p_2 - p_1)}{\rho} \quad \text{or} \quad V_2 = \sqrt{\frac{2 \cdot (p_1 - p_2)}{\rho \cdot \left[1 - \left(\frac{D_2}{D_1}\right)^4\right]}}$$

Then the mass flow rate is 
$$m_{\text{flow}} = \rho \cdot V_2 \cdot A_2 = \rho \cdot \frac{\pi \cdot D_2^2}{4} \cdot \sqrt{\frac{2 \cdot (p_1 - p_2)}{\rho \cdot \left[1 - \left(\frac{D_2}{D_1}\right)^4\right]}} = \frac{\pi \cdot D_2^2}{2 \cdot \sqrt{2}} \cdot \sqrt{\frac{\Delta p \cdot \rho}{\left[1 - \left(\frac{D_2}{D_1}\right)^4\right]}}$$

Using  $p = \rho \cdot R \cdot T$  
$$m_{\text{flow}} = \frac{\pi \cdot D_2^2}{2 \cdot \sqrt{2}} \cdot \sqrt{\frac{\Delta p \cdot p_1}{R \cdot T_1 \cdot \left[1 - \left(\frac{D_2}{D_1}\right)^4\right]}}$$


For a flow nozzle  $m_{\text{flow}} = k \cdot \sqrt{\Delta p}$  where 
$$k = \frac{\pi \cdot D_2^2}{2 \cdot \sqrt{2}} \cdot \sqrt{\frac{p_1}{R \cdot T_1 \cdot \left[1 - \left(\frac{D_2}{D_1}\right)^4\right]}}$$

We can expect the actual flow will be less because there is actually significant loss in the device. Also the flow will experience a vena contracta so that the minimum diameter is actually smaller than  $D_2$ . We will discuss this device in Chapter 8.

## Problem 6.71

[Difficulty: 4]

**6.71** The branching of a blood vessel is shown. Blood at a pressure of 140 mm Hg flows in the main vessel at 4.5 L/min. Estimate the blood pressure in each branch, assuming that blood vessels behave as rigid tubes, that we have frictionless flow, and that the vessel lies in the horizontal plane. What is the force generated at the branch by the blood? You may approximate blood to have a density of 1060 kg/m<sup>3</sup>.



**Given:** Flow through branching blood vessel

**Find:** Blood pressure in each branch; force at branch

**Solution:**

Basic equations

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const} \qquad \sum_{CV} Q = 0 \qquad Q = V \cdot A \qquad \Delta p = \rho \cdot g \cdot \Delta h$$

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

$$F_y = F_{S_y} + F_{B_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Given data

$$Q_1 = 4.5 \cdot \frac{\text{L}}{\text{min}} \qquad Q_2 = 2 \cdot \frac{\text{L}}{\text{min}} \qquad D_1 = 10 \cdot \text{mm} \qquad D_2 = 5 \cdot \text{mm} \qquad D_3 = 3 \cdot \text{mm}$$

$$SG_{\text{Hg}} = 13.6 \qquad \rho = 999 \cdot \frac{\text{kg}}{\text{m}^3} \qquad \rho_b = 1060 \cdot \frac{\text{kg}}{\text{m}^3} \qquad h_1 = 140 \cdot \text{mm} \quad (\text{pressure in in. Hg})$$

For Q<sub>3</sub> we have

$$\sum_{CV} Q = -Q_1 + Q_2 + Q_3 = 0 \qquad \text{so} \qquad Q_3 = Q_1 - Q_2 \qquad Q_3 = 2.50 \cdot \frac{\text{L}}{\text{min}}$$

We will need each velocity

$$V_1 = \frac{Q_1}{A_1} \qquad V_1 = \frac{4 \cdot Q_1}{\pi \cdot D_1^2} \qquad V_1 = 0.955 \frac{\text{m}}{\text{s}}$$

Similarly

$$V_2 = \frac{4 \cdot Q_2}{\pi \cdot D_2^2} \qquad V_2 = 1.70 \frac{\text{m}}{\text{s}} \qquad V_3 = \frac{4 \cdot Q_3}{\pi \cdot D_3^2} \qquad V_3 = 5.89 \frac{\text{m}}{\text{s}}$$

Hence, applying Bernoulli between the inlet (1) and exit (2)

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2} \qquad \text{where we ignore gravity effects}$$

$$p_2 = p_1 + \frac{\rho}{2} \cdot (V_1^2 - V_2^2) \quad \text{and} \quad p_1 = SG_{\text{Hg}} \cdot \rho \cdot g \cdot h_1 \quad p_1 = 18.7 \cdot \text{kPa}$$

Hence 
$$p_2 = p_1 + \frac{\rho_b}{2} \cdot (V_1^2 - V_2^2) \quad p_2 = 17.6 \cdot \text{kPa}$$

In mm Hg 
$$h_2 = \frac{p_2}{SG_{\text{Hg}} \cdot \rho \cdot g} \quad h_2 = 132 \cdot \text{mm}$$

Similarly for exit (3) 
$$p_3 = p_1 + \frac{\rho}{2} \cdot (V_1^2 - V_3^2) \quad p_3 = 1.75 \cdot \text{kPa}$$

In mm Hg 
$$h_3 = \frac{p_3}{SG_{\text{Hg}} \cdot \rho \cdot g} \quad h_3 = 13.2 \cdot \text{mm}$$

Note that all pressures are gage.

For x momentum 
$$R_x + p_3 \cdot A_3 \cdot \cos(60 \cdot \text{deg}) - p_2 \cdot A_2 \cdot \cos(45 \cdot \text{deg}) = u_3 \cdot (\rho \cdot Q_3) + u_2 \cdot (\rho \cdot Q_2)$$

$$R_x = p_2 \cdot A_2 \cdot \cos(45 \cdot \text{deg}) - p_3 \cdot A_3 \cdot \cos(60 \cdot \text{deg}) + \rho \cdot (Q_2 \cdot V_2 \cdot \cos(45 \cdot \text{deg}) - Q_3 \cdot V_3 \cdot \cos(60 \cdot \text{deg}))$$

$$R_x = p_2 \cdot \frac{\pi \cdot D_2^2}{4} \cdot \cos(45 \cdot \text{deg}) - p_3 \cdot \frac{\pi \cdot D_3^2}{4} \cdot \cos(60 \cdot \text{deg}) + \rho \cdot (Q_2 \cdot V_2 \cdot \cos(45 \cdot \text{deg}) - Q_3 \cdot V_3 \cdot \cos(60 \cdot \text{deg})) \quad R_x = 0.156 \text{ N}$$

For y momentum 
$$R_y - p_3 \cdot A_3 \cdot \sin(60 \cdot \text{deg}) - p_2 \cdot A_2 \cdot \sin(45 \cdot \text{deg}) + p_1 \cdot A_1 = v_3 \cdot (\rho \cdot Q_3) + v_2 \cdot (\rho \cdot Q_2)$$

$$R_y = p_2 \cdot A_2 \cdot \sin(45 \cdot \text{deg}) + p_3 \cdot A_3 \cdot \sin(60 \cdot \text{deg}) - p_1 \cdot A_1 + \rho \cdot (Q_2 \cdot V_2 \cdot \sin(45 \cdot \text{deg}) + Q_3 \cdot V_3 \cdot \sin(60 \cdot \text{deg}))$$

$$R_y = p_2 \cdot \frac{\pi \cdot D_2^2}{4} \cdot \sin(45 \cdot \text{deg}) + p_3 \cdot \frac{\pi \cdot D_3^2}{4} \cdot \sin(60 \cdot \text{deg}) - p_1 \cdot \frac{\pi \cdot D_1^2}{4} + \rho \cdot (Q_2 \cdot V_2 \cdot \sin(45 \cdot \text{deg}) + Q_3 \cdot V_3 \cdot \sin(60 \cdot \text{deg}))$$

$$R_y = -0.957 \text{ N}$$

### Problem 6.72

[Difficulty: 3] Part 1/2


**6.72** An object, with a flat horizontal lower surface, moves downward into the jet of the spray system of Problem 4.81 with speed  $U = 5$  ft/s. Determine the minimum supply pressure needed to produce the jet leaving the spray system at  $V = 15$  ft/s. Calculate the maximum pressure exerted by the liquid jet on the flat object at the instant when the object is  $h = 1.5$  ft above the jet exit. Estimate the force of the water jet on the flat object.

Solution:

(a) The minimum pressure occurs when friction is neglected, and so we apply the Bernoulli equation

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2$$

- Assume:
- (1) steady flow
  - (2) incompressible flow
  - (3) no friction
  - (4) flow along a streamline
  - (5) neglect  $\frac{\partial \rho}{\partial t}$
  - (6)  $p_2 = p_{atm}$
  - (7) uniform flow at ①-②



Then

$$p_1 - p_2 = \rho \frac{V_2^2 - V_1^2}{2} = \frac{\rho V_2^2}{2} \left[ 1 - \left( \frac{V_1}{V_2} \right)^2 \right]$$

From continuity,  $A_1 V_1 = A_2 V_2$ , and  $\frac{V_1}{V_2} = \frac{A_2}{A_1} = \frac{1}{9}$ . Then

$$p_1 - p_2 = \frac{\rho V_2^2}{2} \left[ 1 - \left( \frac{1}{9} \right)^2 \right] = \frac{1}{2} \cdot 1.94 \frac{\text{slug}}{\text{ft}^3} \cdot (15)^2 \frac{\text{ft}^2}{\text{s}^2} \left[ 1 - \left( \frac{1}{81} \right) \right] = \frac{16.5 \text{ ft}^2}{\text{ft} \cdot \text{slug}} \cdot \frac{\text{ft}^2}{144 \text{ in}^2} = 1.35 \text{ psig} \leftarrow p_1 - p_2$$

Frictional effects would cause this value to be higher.

(b) The maximum pressure of the jet on the object is the stagnation pressure

$$p_0 = p + \frac{1}{2} \rho V^2$$

where  $V$  is the velocity of the impinging jet relative to the object

At  $z = 1.5$  ft, the jet velocity,  $V_4$ , in the absence of the object can be calculated from

$$\frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2 = \frac{p_4}{\rho} + \frac{V_4^2}{2} + gz_4$$

$$V_4 = \left[ V_2^2 - 2g(z_4 - z_2) \right]^{1/2} = \left[ (15)^2 \frac{\text{ft}^2}{\text{s}^2} - 2 \cdot 32.2 \frac{\text{ft}}{\text{s}^2} \cdot (1.5) \text{ ft} \right]^{1/2} = 11.3 \text{ ft/s}$$


Then

$$V_{rel} = V_4 - (-U) = (11.3 + 5) \text{ ft/s} = 16.3 \text{ ft/s}$$

and

$$p_0 - p_{atm} = p_{og} = \frac{1}{2} \rho V_{rel}^2 = \frac{1}{2} \cdot 1.94 \frac{\text{slug}}{\text{ft}^3} \cdot (16.3)^2 \frac{\text{ft}^2}{\text{s}^2} = \frac{16.5 \text{ ft}^2}{\text{ft} \cdot \text{slug}} \cdot \frac{\text{ft}^2}{144 \text{ in}^2} = 1.79 \text{ psig} \leftarrow p_{og}$$

(c) To determine the force of the water on the object we apply the z component of the momentum equation to the CV shown.



$$F_{sz} + \Delta \dot{p}_z = \frac{\partial}{\partial t} \int_{CV} w_{zsz} \rho dV + \int_{CS} w_{zsz} (\rho \vec{V}_{zsz} \cdot d\vec{A})$$

- Assumptions:
- (8) neglected  $\frac{\partial}{\partial t} \int_{CV}$
  - (9) neglected body forces
  - (10) uniform radial flow at (B)
  - (11) uniform vertical flow at (A) with  $z_h = 1.5 \text{ ft}$

Then  $-F_1 = -w_{zsz} / \rho V_{zsz} A_1$

where  $F_1$  is applied force necessary to maintain motion of plate at constant speed  $U$ .

$$V_{zsz} = v_u - (-U) = v_u + U$$

$$w_{zsz} = V_{zsz} = v_u + U$$

$$\therefore F_1 = \rho (v_u + U)^2 A_1$$

From continuity  $A_2 v_2 = A_1 v_1$

$$\text{and } A_1 = \frac{v_2}{v_1} A_2 = \frac{15}{11.3} \cdot 1 \text{ in}^2 = 1.33 \text{ in}^2$$

Then

$$F_1 = \rho (v_u + U)^2 A_1 = 1.94 \frac{\text{slug}}{\text{ft}^3} (11.3 + 5)^2 \frac{\text{ft}^2}{\text{s}^2} \cdot 1.33 \frac{\text{in}^2 \cdot \text{ft}^2}{144 \text{ in}^2} = \frac{\text{lb} \cdot \text{s}^2}{\text{ft} \cdot \text{slug}}$$

$$F_1 = 4.76 \text{ lbf (in the direction shown)}$$

Since the plate is moving at constant speed, then



$$\sum \vec{F}_{\text{plate}} = m \vec{a} = 0 \quad \text{and}$$

neglecting the weight of the plate then

$$F_{120} = F_1 = 4.76 \text{ lbf}$$


$$\vec{F}_{120} = 4.76 \hat{k} \text{ lbf}$$

6.73 A water jet is directed upward from a well-designed nozzle of area  $A_1 = 600 \text{ mm}^2$ ; the exit jet speed is  $V_1 = 6.3 \text{ m/s}$ . The flow is steady and the liquid stream does not break up. Point ② is located  $H = 1.55 \text{ m}$  above the nozzle exit plane. Determine the velocity in the undisturbed jet at point ②. Calculate the pressure that would be sensed by a stagnation tube located there. Evaluate the force that would be exerted on a flat plate placed normal to the stream at point ②. Sketch the pressure distribution on the plate.

Solution: Apply Bernoulli and then y-momentum equation

Basis eq.:  $\frac{p}{\rho} + \frac{V^2}{2} + gz = \frac{p}{\rho} + \frac{V^2}{2} + gz$

- Assumptions: (1) steady flow  
 (2) incompressible flow  
 (3) frictionless flow  
 (4) flow along a streamline  
 (5)  $p_1 = p_2 = p_{atm}$



Then

$$V_2 = [V_1^2 + 2g(z_1 - z_2)]^{1/2}$$

$$V_2 = [(6.3)^2 + 2 \times 9.81 \frac{\text{m}}{\text{s}^2} (-1.55\text{m})]^{1/2}$$

$$V_2 = 3.05 \text{ m/s}$$


By definition,  $p_{02} = p_2 + \frac{1}{2} \rho V_2^2 = p_{atm} + \frac{1}{2} \rho V_2^2$ , so

$$p_{02 \text{ gage}} = \frac{1}{2} \times 999 \frac{\text{kg}}{\text{m}^3} \times (3.05)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 4.65 \text{ kPa (g)} \rightarrow p_{02}$$

Apply y-momentum equation to CV surrounding plate

Basis eq.:  $F_{sy} + F_{py} = \frac{d}{dt} \int_{CV} \rho v_y dV + \int_{CS} \rho v_y v_n dA$

- Assumptions: (6) neglect mass in CV  
 (7)  $V_2$  enters CV uniformly  
 (8)  $V_3 = V_4 = 0$




Then  $R_y = V_2 \{ -\rho V_1 A_1 \} + V_3 \{ \rho V_3 A_3 \} + V_4 \{ \rho V_4 A_4 \} = -\rho V_1 A_1 V_2$  and

$$K_y = -R_y = \rho V_1 A_1 V_2 = 999 \frac{\text{kg}}{\text{m}^3} \times 6.3 \frac{\text{m}}{\text{s}} \times 600 \text{ mm}^2 \times 3.05 \frac{\text{m}}{\text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$K_y = 11.5 \text{ N (force up)}$$


The pressure distribution on the plate is as shown.



## Problem 6.74

[Difficulty: 3]

**6.74** Water flows out of a kitchen faucet of 1.25 cm diameter at the rate of 0.1 L/s. The bottom of the sink is 45 cm below the faucet outlet. Will the cross-sectional area of the fluid stream increase, decrease, or remain constant between the faucet outlet and the bottom of the sink? Explain briefly. Obtain an expression for the stream cross section as a function of distance  $y$  above the sink bottom. If a plate is held directly under the faucet, how will the force required to hold the plate in a horizontal position vary with height above the sink? Explain briefly.



**Given:** Flow through kitchen faucet

**Find:** Area variation with height; force to hold plate as function of height

**Solution:**

Basic equation  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$        $Q = V \cdot A$        $F_y = F_{S_y} + F_{B_y} = \frac{\partial}{\partial t} \int_{CV} v \rho dV + \int_{CS} v \rho \vec{V} \cdot d\vec{A}$


Assumptions: 1) Incompressible flow 2) Inviscid 3) Steady 4) Along a streamline

Hence, applying Bernoulli between the faucet (1) and any height  $y$

$$\frac{V_1^2}{2} + g \cdot H = \frac{V^2}{2} + g \cdot y \quad \text{where we assume the water is at } p_{\text{atm}}$$

Hence 
$$V(y) = \sqrt{V_1^2 + 2 \cdot g \cdot (H - y)}$$

The problem doesn't require a plot, but it looks like  $V_1 = 0.815 \frac{\text{m}}{\text{s}}$        $V(0 \cdot \text{m}) = 3.08 \frac{\text{m}}{\text{s}}$



The speed increases as  $y$  decreases because the fluid particles "trade" potential energy for kinetic, just as a falling solid particle does!


But we have 
$$Q = V_1 \cdot A_1 = V_1 \cdot \frac{\pi \cdot D^2}{4} = V \cdot A$$

Hence 
$$A = \frac{V_1 \cdot A_1}{V} \quad A(y) = \frac{\pi \cdot D_1^2 \cdot V_1}{4 \cdot \sqrt{V_1^2 + 2 \cdot g \cdot (H - y)}}$$

The problem doesn't require a plot, but it looks like

$$A(H) = 1.23 \cdot \text{cm}^2$$

$$A(0) = 0.325 \cdot \text{cm}^2$$



The area decreases as the speed increases. If the stream falls far enough the flow will change to turbulent.

For the CV above  $R_y - W = u_{in} \cdot (-\rho \cdot V_{in} \cdot A_{in}) = -V \cdot (-\rho \cdot Q)$

$$R_y = W + \rho \cdot V^2 \cdot A = W + \rho \cdot Q \cdot \sqrt{V_1^2 + 2 \cdot g \cdot (H - y)}$$

Hence  $R_y$  increases in the same way as  $V$  as the height  $y$  varies; the maximum force is when  $y = H$

$$R_{y\max} = W + \rho \cdot Q \cdot \sqrt{V_1^2 + 2 \cdot g \cdot H}$$

## Problem 6.75

[Difficulty: 4]

---

**6.75** An old magic trick uses an empty thread spool and a playing card. The playing card is placed against the bottom of the spool. Contrary to intuition, when one blows downward through the central hole in the spool, the card is not blown away. Instead it is “sucked” up against the spool. Explain.

---

**Open-Ended Problem Statement:** An old magic trick uses an empty thread spool and a playing card. The playing card is placed against the bottom of the spool. Contrary to intuition, when one blows downward through the central hole in the spool, the card is not blown away. Instead it is “sucked” up against the spool. Explain.

**Discussion:** The secret to this “parlor trick” lies in the velocity distribution, and hence the pressure distribution, that exists between the spool and the playing cards.

Neglect viscous effects for the purposes of discussion. Consider the space between the end of the spool and the playing card as a pair of parallel disks. Air from the hole in the spool enters the annular space surrounding the hole, and then flows radially outward between the parallel disks. For a given flow rate of air the edge of the hole is the cross-section of minimum flow area and therefore the location of maximum air speed.

After entering the space between the parallel disks, air flows radially outward. The flow area becomes larger as the radius increases. Thus the air slows and its pressure increases. The largest flow area, slowest air speed, and highest pressure between the disks occur at the outer periphery of the spool where the air is discharged from an annular area.


The air leaving the annular space between the disk and card must be at atmospheric pressure. This is the location of the highest pressure in the space between the parallel disks. Therefore pressure at smaller radii between the disks must be lower, and hence the pressure between the disks is sub-atmospheric. Pressure above the card is less than atmospheric pressure; pressure beneath the card is atmospheric. Each portion of the card experiences a pressure difference acting upward. This causes a net pressure force to act upward on the whole card. The upward pressure force acting on the card tends to keep it from blowing off the spool when air is introduced through the central hole in the spool.

Viscous effects are present in the narrow space between the disk and card. However, they only reduce the pressure rise as the air flows outward, they do not dominate the flow behavior.

## Problem 6.76

[Difficulty: 4]

**6.76** A horizontal axisymmetric jet of air with 0.4 in. diameter strikes a stationary vertical disk of 7.5 in. diameter. The jet speed is 225 ft/s at the nozzle exit. A manometer is connected to the center of the disk. Calculate (a) the deflection, if the manometer liquid has  $SG = 1.75$ , (b) the force exerted by the jet on the disk, and (c) the force exerted on the disk if it is assumed that the stagnation pressure acts on the entire forward surface of the disk. Sketch the streamline pattern and plot the distribution of pressure on the face of the disk.



**Given:** Air jet striking disk

**Find:** Manometer deflection; Force to hold disk; Force assuming  $p_0$  on entire disk; plot pressure distribution

**Solution:**

Basic equations: Hydrostatic pressure, Bernoulli, and momentum flux in x direction

$$\Delta p = SG \cdot \rho \cdot g \cdot \Delta h \quad \frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible 3) No friction 4) Flow along streamline 5) Uniform flow 6) Horizontal flow ( $g_x = 0$ )

Applying Bernoulli between jet exit and stagnation point

$$\frac{p_{atm}}{\rho_{air}} + \frac{V^2}{2} = \frac{p_0}{\rho_{air}} + 0 \quad p_0 - p_{atm} = \frac{1}{2} \cdot \rho_{air} \cdot V^2$$

But from hydrostatics

$$p_0 - p_{atm} = SG \cdot \rho \cdot g \cdot \Delta h \quad \text{so} \quad \Delta h = \frac{\frac{1}{2} \cdot \rho_{air} \cdot V^2}{SG \cdot \rho \cdot g} = \frac{\rho_{air} \cdot V^2}{2 \cdot SG \cdot \rho \cdot g}$$

$$\Delta h = 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(225 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{1}{2 \cdot 1.75} \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \quad \Delta h = 0.55 \cdot \text{ft} \quad \Delta h = 6.60 \cdot \text{in}$$

For x momentum

$$R_x = V \cdot (-\rho_{air} \cdot A \cdot V) = -\rho_{air} \cdot V^2 \cdot \frac{\pi \cdot d^2}{4}$$

$$R_x = -0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(225 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{\pi \cdot \left(\frac{0.4}{12} \cdot \text{ft}\right)^2}{4} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = -0.105 \cdot \text{lb} \cdot \text{f}$$

The force of the jet on the plate is then  $F = -R_x$

$$F = 0.105 \cdot \text{lb} \cdot \text{f}$$

The stagnation pressure is  $p_0 = p_{atm} + \frac{1}{2} \cdot \rho_{air} \cdot V^2$

The force on the plate, assuming stagnation pressure on the front face, is

$$F = (p_0 - p) \cdot A = \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2 \cdot \frac{\pi \cdot D^2}{4}$$

$$F = \frac{\pi}{8} \times 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(225 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \left(\frac{7.5}{12} \cdot \text{ft}\right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F = 18.5 \cdot \text{lbf}$$

Obviously this is a huge overestimate!

For the pressure distribution on the disk, we use Bernoulli between the disk outside edge any radius  $r$  for radial flow

$$\frac{p_{\text{atm}}}{\rho_{\text{air}}} + \frac{1}{2} \cdot v_{\text{edge}}^2 = \frac{p}{\rho_{\text{air}}} + \frac{1}{2} \cdot v^2$$

We need to obtain the speed  $v$  as a function of radius. If we assume the flow remains constant thickness  $h$ , then

$$Q = v \cdot 2 \cdot \pi \cdot r \cdot h = V \cdot \frac{\pi \cdot d^2}{4} \quad v(r) = V \cdot \frac{d^2}{8 \cdot h \cdot r}$$

We need an estimate for  $h$ . As an approximation, we assume that  $h = d$  (this assumption will change the scale of  $p(r)$  but not the basic shape)

Hence


$$v(r) = V \cdot \frac{d}{8 \cdot r}$$

Using this in Bernoulli

$$p(r) = p_{\text{atm}} + \frac{1}{2} \cdot \rho_{\text{air}} \cdot \left(v_{\text{edge}}^2 - v(r)^2\right) = p_{\text{atm}} + \frac{\rho_{\text{air}} \cdot V^2 \cdot d^2}{128} \cdot \left(\frac{4}{D^2} - \frac{1}{r^2}\right)$$

Expressed as a gage pressure

$$p(r) = \frac{\rho_{\text{air}} \cdot V^2 \cdot d^2}{128} \cdot \left(\frac{4}{D^2} - \frac{1}{r^2}\right)$$





Non-dimensionalize (divide by  $h_0$ ) to obtain

$$\frac{h}{h_0} = \left\{ 1 - \sqrt{\frac{g}{2h_0} \left( \frac{D}{d} \right)^2 t} \right\}^2$$



Draining of a cylindrical liquid tank:

Plot of  $h/h_0$  vs.  $t$  for  $0.1 < h_0 < 1$  m

Input Data:			
$D =$	50	mm	
$d =$	5	mm	
$h_0$ (m) =	0.1	0.3	1
Time, $t$ (s)	$h/h_0$ (---)	$h/h_0$ (---)	$h/h_0$ (---)
0	1.00	1.00	1.00
2	0.739	0.845	0.913
4	0.518	0.703	0.831
6	0.336	0.574	0.752
8	0.193	0.458	0.677
10	0.090	0.355	0.606
12	0.025	0.265	0.539
14	0.000	0.188	0.476
16		0.125	0.417
18		0.074	0.362
20		0.037	0.310
22		0.012	0.263
24		0.001	0.219
26			0.180
28			0.144
30			0.113
32			0.085
34			0.061
36			0.041
38			0.025
40			0.013
45			0.000

Plot of  $h/h_0$  vs.  $t$  for  $10 < D/d < 2$

Input Data:			
$h_0 =$	1	m	
$D/d$ (---) =	2	5	10
Time, $t$ (s)	$h/h_0$ (---)	$h/h_0$ (---)	$h/h_0$ (---)
0	1.00	1.00	1.00
0.5	0.523	0.913	0.978
1	0.199	0.831	0.956
1.5	0.029	0.752	0.935
1.6	0.013	0.737	0.930
3		0.539	0.872
4		0.417	0.831
5		0.310	0.791
6		0.219	0.752
7		0.144	0.714
8		0.085	0.677
9		0.041	0.641
10		0.013	0.606
12			0.539
14			0.476
16			0.417
18			0.362
20			0.310




14-787  
 14-788  
 14-789  
 14-790  
 14-791  
 14-792  
 14-793  
 14-794  
 14-795  
 14-796  
 14-797  
 14-798  
 14-799  
 14-800  
 14-801  
 14-802  
 14-803  
 14-804  
 14-805  
 14-806  
 14-807  
 14-808  
 14-809  
 14-810  
 14-811  
 14-812  
 14-813  
 14-814  
 14-815  
 14-816  
 14-817  
 14-818  
 14-819  
 14-820  
 14-821  
 14-822  
 14-823  
 14-824  
 14-825  
 14-826  
 14-827  
 14-828  
 14-829  
 14-830  
 14-831  
 14-832  
 14-833  
 14-834  
 14-835  
 14-836  
 14-837  
 14-838  
 14-839  
 14-840  
 14-841  
 14-842  
 14-843  
 14-844  
 14-845  
 14-846  
 14-847  
 14-848  
 14-849  
 14-850  
 14-851  
 14-852  
 14-853  
 14-854  
 14-855  
 14-856  
 14-857  
 14-858  
 14-859  
 14-860  
 14-861  
 14-862  
 14-863  
 14-864  
 14-865  
 14-866  
 14-867  
 14-868  
 14-869  
 14-870  
 14-871  
 14-872  
 14-873  
 14-874  
 14-875  
 14-876  
 14-877  
 14-878  
 14-879  
 14-880  
 14-881  
 14-882  
 14-883  
 14-884  
 14-885  
 14-886  
 14-887  
 14-888  
 14-889  
 14-890  
 14-891  
 14-892  
 14-893  
 14-894  
 14-895  
 14-896  
 14-897  
 14-898  
 14-899  
 14-900  
 14-901  
 14-902  
 14-903  
 14-904  
 14-905  
 14-906  
 14-907  
 14-908  
 14-909  
 14-910  
 14-911  
 14-912  
 14-913  
 14-914  
 14-915  
 14-916  
 14-917  
 14-918  
 14-919  
 14-920  
 14-921  
 14-922  
 14-923  
 14-924  
 14-925  
 14-926  
 14-927  
 14-928  
 14-929  
 14-930  
 14-931  
 14-932  
 14-933  
 14-934  
 14-935  
 14-936  
 14-937  
 14-938  
 14-939  
 14-940  
 14-941  
 14-942  
 14-943  
 14-944  
 14-945  
 14-946  
 14-947  
 14-948  
 14-949  
 14-950  
 14-951  
 14-952  
 14-953  
 14-954  
 14-955  
 14-956  
 14-957  
 14-958  
 14-959  
 14-960  
 14-961  
 14-962  
 14-963  
 14-964  
 14-965  
 14-966  
 14-967  
 14-968  
 14-969  
 14-970  
 14-971  
 14-972  
 14-973  
 14-974  
 14-975  
 14-976  
 14-977  
 14-978  
 14-979  
 14-980  
 14-981  
 14-982  
 14-983  
 14-984  
 14-985  
 14-986  
 14-987  
 14-988  
 14-989  
 14-990  
 14-991  
 14-992  
 14-993  
 14-994  
 14-995  
 14-996  
 14-997  
 14-998  
 14-999  
 15-000



### Problem 6.78

[Difficulty: 4] Part 1/2

6.78 The water level in a large tank is maintained at height  $H$  above the surrounding level terrain. A rounded nozzle placed in the side of the tank discharges a horizontal jet. Neglecting friction, determine the height  $h$  at which the orifice should be placed so the water strikes the ground at the maximum horizontal distance  $X$  from the tank. Plot jet speed  $V$  and distance  $X$  as functions of  $h$  ( $0 < h < H$ ).



Apply Bernoulli equation between tank surface and jet.

Basic equation:  $\frac{p}{\rho} + \frac{V^2}{2} + gy_0 = \frac{p}{\rho} + \frac{V^2}{2} + gy_1$

Assumptions: (1) steady flow (2) incompressible flow (3) flow along streamline (4) no friction

Then  $gh = \frac{V^2}{2} + gh$  or  $V = \sqrt{2g(H-h)}$  (1)

Assume no air resistance in the stream. Then  $u = \text{constant}$ , and  $X = ut = \sqrt{2g(H-h)} \cdot t$  (2)

The only force acting on the stream is gravity  $\sum F_y = -mg = ma_y = m \frac{dv}{dt}$ ; thus  $\frac{dv}{dt} = -g$

Integrating we obtain  $v = v_0 - gt$  and  $y = y_0 + v_0 t - \frac{1}{2}gt^2$

Solving for  $t$ ,  $t = \left[ \frac{2(y_0 - y)}{g} \right]^{1/2}$

The time of flight is then  $t = \sqrt{\frac{2y_0}{g}} = \sqrt{\frac{2H}{g}}$

Substituting into Eq. 2

$X = \sqrt{2g(H-h)} \sqrt{\frac{2H}{g}} = 2\sqrt{h(H-h)}$  (3)

$X$  will be maximized when  $h(H-h)$  is maximized, or when

$\frac{d}{dh} [h(H-h)] = 0 = (H-h) + h(-1) = H - 2h$  or  $h = \frac{H}{2}$

The corresponding range is

$\bar{X} = 2\sqrt{\frac{H}{2} \cdot \frac{H}{2}} = H$

See the next page for plots

42,389  
42,392  
42,393  
42,394  
42,395  
42,396  
42,397  
42,398  
42,399  
42,400  
42,401  
42,402  
42,403  
42,404  
42,405  
42,406  
42,407  
42,408  
42,409  
42,410  
42,411  
42,412  
42,413  
42,414  
42,415  
42,416  
42,417  
42,418  
42,419  
42,420  
42,421  
42,422  
42,423  
42,424  
42,425  
42,426  
42,427  
42,428  
42,429  
42,430  
42,431  
42,432  
42,433  
42,434  
42,435  
42,436  
42,437  
42,438  
42,439  
42,440  
42,441  
42,442  
42,443  
42,444  
42,445  
42,446  
42,447  
42,448  
42,449  
42,450  
42,451  
42,452  
42,453  
42,454  
42,455  
42,456  
42,457  
42,458  
42,459  
42,460  
42,461  
42,462  
42,463  
42,464  
42,465  
42,466  
42,467  
42,468  
42,469  
42,470  
42,471  
42,472  
42,473  
42,474  
42,475  
42,476  
42,477  
42,478  
42,479  
42,480  
42,481  
42,482  
42,483  
42,484  
42,485  
42,486  
42,487  
42,488  
42,489  
42,490  
42,491  
42,492  
42,493  
42,494  
42,495  
42,496  
42,497  
42,498  
42,499  
42,500

National Brand

# Problem 6.78

[Difficulty: 4] Part 2/2

From Eq. 1,



$$\frac{V}{\sqrt{2gH}} = \sqrt{1 - \frac{h}{H}}$$

From Eq. 2,

$$\frac{X}{H} = 2 \sqrt{\frac{h}{H} \left(1 - \frac{h}{H}\right)}$$

Exit velocity and throw distance from orifice in side of tank, versus height  $h/H$

$h/H$	$V/(2gH)^{1/2}$	$X/H$
0.00	1.00	0.000
0.01	0.995	0.199
0.02	0.990	0.280
0.03	0.985	0.341
0.04	0.980	0.392
0.05	0.975	0.436
0.10	0.949	0.600
0.15	0.922	0.714
0.20	0.894	0.800
0.25	0.866	0.866
0.30	0.837	0.917
0.35	0.806	0.954
0.40	0.775	0.980
0.45	0.742	0.995
0.50	0.707	1.000
0.55	0.671	0.995
0.60	0.632	0.980
0.65	0.592	0.954
0.70	0.548	0.917
0.75	0.500	0.866
0.80	0.447	0.800
0.85	0.387	0.714
0.90	0.316	0.600
0.95	0.224	0.436
0.96	0.200	0.392
0.97	0.173	0.341
0.98	0.141	0.280
0.99	0.100	0.199
1.00	0.00	0.00




13-782 500 SHEETS FULL 5 SQUARE  
 42-381 500 SHEETS FULL 5 SQUARE  
 42-382 100 SHEETS FULL 5 SQUARE  
 42-383 200 SHEETS FULL 5 SQUARE  
 42-384 100 SHEETS FULL 5 SQUARE  
 42-385 200 SHEETS FULL 5 SQUARE  
 42-386 100 SHEETS FULL 5 SQUARE  
 42-387 200 SHEETS FULL 5 SQUARE  
 42-388 100 SHEETS FULL 5 SQUARE  
 42-389 200 SHEETS FULL 5 SQUARE  
 Made in U.S.A.



### Problem 6.79

[Difficulty: 4]

**6.79** The flow over a Quonset hut may be approximated by the velocity distribution of Problem 6.63 with  $0 \leq \theta \leq \pi$ . During a storm the wind speed reaches 100 km/hr; the outside temperature is  $5^\circ\text{C}$ . A barometer inside the hut reads 720 mm of mercury; pressure  $p_\infty$  is also 720 mm Hg. The hut has a diameter of 6 m and a length of 18 m. Determine the net force tending to lift the hut off its foundation.



Solution:

Basic equations:  $\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{const}$   $F = \int p dA$

- Assumptions:
- (1) steady flow
  - (2) incompressible flow
  - (3) frictionless flow
  - (4) flow along a streamline

Along the top half of the cylinder,  $r = a$  and  $\vec{V} = -2U \sin\theta \hat{e}_\theta$ ,  $0 \leq \theta \leq \pi$   
 Applying the Bernoulli equation along the streamline ( $r = a$ )

$$\frac{p}{\rho} + \frac{V^2}{2} = \frac{p_\infty}{\rho} + \frac{U^2}{2}$$

$$p - p_\infty = \frac{\rho}{2} (U^2 - V^2) = \frac{\rho}{2} (U^2 - 4U^2 \sin^2\theta) = \frac{\rho U^2}{2} (1 - 4 \sin^2\theta)$$

$$F_{\text{lift}} = \int_0^\pi (p_\infty - p) dA \sin\theta = \int_0^\pi (p_\infty - p) \sin\theta L a d\theta$$

$$= \int_0^\pi \frac{\rho U^2}{2} (4 \sin^2\theta - 1) \sin\theta L a d\theta = \frac{\rho U^2}{2} a L \left\{ 4 \left[ \frac{\cos^3\theta}{3} - \cos\theta \right]_0^\pi + \cos\theta \right\}$$

$$= \frac{\rho U^2}{2} a L \left\{ 4 \left[ \left( -\frac{1}{3} + 1 \right) - \left( \frac{1}{3} - 1 \right) \right] + (-1 - 1) \right\}$$

$$F_{\text{lift}} = \frac{\rho U^2}{2} a L \left( \frac{10}{3} \right) = \frac{5}{3} \rho U^2 a L$$

From the ideal gas equation of state

$$\rho = \frac{p}{RT} = \frac{720 \text{ mm Hg}}{160 \text{ mm}} \times \frac{1.01 \times 10^5 \text{ N}}{\text{m}^2 \cdot \text{atm}} \times \frac{1 \text{ atm}}{287 \text{ N} \cdot \text{m}} \times \frac{1}{278 \text{ K}} = 1.20 \frac{\text{kg}}{\text{m}^3}$$

$$F_{\text{lift}} = \frac{5}{3} \rho U^2 a L = \frac{5}{3} \times 1.20 \frac{\text{kg}}{\text{m}^3} \times (100 \frac{\text{m}}{\text{hr}})^2 \times \frac{\text{hr}^2}{(2400)^2 \text{ s}^2} \times 3 \text{ m} \times 18 \text{ m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$F_{\text{lift}} = 83.3 \text{ kN}$$

Comment: The actual pressure distribution over the rear portion of the hut is not modelled well by ideal flow. The force calculated here is lower than the actual force.

## Problem 6.80

[Difficulty: 3]

**6.80** Many recreation facilities use inflatable “bubble” structures. A tennis bubble to enclose four courts is shaped roughly as a circular semicylinder with a diameter of 50 ft and a length of 50 ft. The blowers used to inflate the structure can maintain the air pressure inside the bubble at 0.75 in. of water above ambient pressure. The bubble is subjected to a wind that blows at 35 mph in a direction perpendicular to the

axis of the semicylindrical shape. Using polar coordinates, with angle  $\theta$  measured from the ground on the upwind side of the structure, the resulting pressure distribution may be expressed as

$$\frac{p - p_\infty}{\frac{1}{2}\rho V_\infty^2} = 1 - 4 \sin^2 \theta$$

where  $p$  is the pressure at the surface,  $p_\infty$  the atmospheric pressure, and  $V_\infty$  the wind speed. Determine the net vertical force exerted on the structure.

**Given:** Air flow over "bubble" structure

**Find:** Net vertical force

**Solution:** The net force is given by  $\vec{F} = \int p \, d\vec{A}$  also  $\Delta p = \rho \cdot g \cdot \Delta h$

Available data  $L = 50 \cdot \text{ft}$   $R = 25 \text{ft}$   $V = 35 \cdot \text{mph}$   $\Delta h = 0.75 \cdot \text{in}$   $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$   $\rho_{\text{air}} = 0.00238 \cdot \frac{\text{slug}}{\text{ft}^3}$

The internal pressure is  $\Delta p = \rho \cdot g \cdot \Delta h$   $\Delta p = 187 \text{ Pa}$

Through symmetry only the vertical component of force is non-zero  $F_V = \int_0^\pi (p_i - p) \cdot \sin(\theta) \cdot R \cdot L \, d\theta$

where  $p_i$  is the internal pressure and  $p$  the external  $p_i = p_{\text{atm}} + \Delta p$   $p = p_{\text{atm}} - \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2 \cdot (1 - 4 \cdot \sin(\theta)^2)$

Hence  $F_V = \int_0^\pi \left[ \Delta p - \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2 \cdot (1 - 4 \cdot \sin(\theta)^2) \right] \cdot \sin(\theta) \cdot R \cdot L \, d\theta$

$$F_V = R \cdot L \cdot \Delta p \cdot \int_0^\pi \sin(\theta) \, d\theta - R \cdot L \cdot \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2 \cdot \int_0^\pi (1 - 4 \cdot \sin(\theta)^2) \cdot \sin(\theta) \, d\theta$$

But  $\int (\sin(\theta) - 4 \cdot \sin(\theta)^3) \, d\theta = -\cos(\theta) + 4 \cdot \left( \cos(\theta) - \frac{1}{3} \cdot \cos(\theta)^3 \right)$  so  $\int_0^\pi (\sin(\theta) - 4 \cdot \sin(\theta)^3) \, d\theta = -\frac{10}{3}$

$\int \sin(\theta) \, d\theta = -\cos(\theta)$  so  $\int_0^\pi \sin(\theta) \, d\theta = 2$

Combining results  $F_V = R \cdot L \cdot \left( 2 \cdot \Delta p + \frac{5}{3} \cdot \rho_{\text{air}} \cdot V^2 \right)$   $F_V = 2.28 \times 10^4 \cdot \text{lbf}$   $F_V = 22.8 \cdot \text{kip}$

### Problem 6.81

[Difficulty: 4] Part 1/2

**6.81** High-pressure air forces a stream of water from a tiny, rounded orifice, of area  $A$ , in a tank. The pressure is high enough that gravity may be neglected. The air expands slowly, so that the expansion may be considered isothermal. The initial volume of air in the tank is  $V_0$ . At later instants the volume of air is  $V(t)$ ; the total volume of the tank is  $V_t$ . Obtain an algebraic expression for the mass flow rate of water leaving the tank. Find an algebraic expression for the rate of change in mass of the water inside the tank. Develop an ordinary differential equation and solve for the water mass in the tank at any instant. If  $V_0 = 5 \text{ m}^3$ ,  $V_t = 10 \text{ m}^3$ ,  $A = 25 \text{ mm}^2$ , and  $p_0 = 1 \text{ MPa}$ , plot the water mass in the tank versus time for the first forty minutes.


Solution:

Basic equations:  $\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{const}$

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

Assumptions: (1) quasi-steady flow  
 $V_s \ll V$

- (2) frictionless
- (3) incompressible
- (4) flow along a streamline
- (5) uniform flow at outlet.
- (6) neglect gravity
- (7)  $p \rightarrow p_{\text{atm}} \therefore p_{\text{abs}} = p_{\text{gage}}$



Apply Bernoulli equation between liquid surface and orifice:

$$V_s = \left[ \frac{2(p - p_{\text{atm}})}{\rho} \right]^{1/2} \approx \sqrt{\frac{2p}{\rho}}$$

$$\dot{m} = \rho A V_s = \rho A \sqrt{\frac{2p}{\rho}} = \sqrt{2p\rho} A \quad \leftarrow \dot{m}$$

Rate of change of mass in tank is  $\frac{dM}{dt} = \frac{\partial}{\partial t} (\rho dV)$

$$\frac{dM}{dt} = \rho_w \frac{dV_w}{dt} = -\rho_w \frac{dV_{\text{air}}}{dt} \quad (V_t = V_{\text{air}} + V_w) \quad \leftarrow \frac{dM}{dt}$$

For isothermal flow,  $\frac{p}{\rho} = RT = \text{constant} = \frac{p_0}{\rho_0}$

where  $\rho$  is the air density, and  $\rho = M_{\text{air}} / V_{\text{air}}$

thus 
$$pV = p_0 V_0 \quad \text{or} \quad p = p_0 \frac{V_0}{V}$$

From continuity

$$0 = \rho_w \frac{dV_w}{dt} + \dot{m}$$

and

$$0 = -\rho_w \frac{dV_{\text{air}}}{dt} + \sqrt{2p\rho_w} A$$

$$\frac{dV}{dt} = \sqrt{\frac{2p}{\rho_w}} = \sqrt{\frac{2p_0 V_0}{\rho_w V}}$$

# Problem 6.81

Separating variables,  $A^{1/2} dA = \sqrt{\frac{2\rho_0 H_0}{\rho}} A dt$

Integrating  $\int_{A_0}^{A} A^{1/2} dA = \sqrt{\frac{2\rho_0 H_0}{\rho}} \int_0^t A dt$

$$\frac{2}{3} (A^{3/2} - A_0^{3/2}) = \sqrt{\frac{2\rho_0 H_0}{\rho}} A t$$


Then  $(\frac{A}{A_0})^{3/2} = \left[ 1 + \frac{3}{2} \sqrt{\frac{2\rho_0 H_0}{\rho}} \frac{A t}{A_0} \right]$

$$\frac{A}{A_0} = \left[ 1 + 1.5 \sqrt{\frac{2\rho_0 H_0}{\rho}} \frac{A t}{A_0} \right]^{2/3}$$

But  $M_w = \rho (A_t - A) = \rho A_0 \left\{ \frac{A_t}{A_0} - \frac{A}{A_0} \right\}$

$$\therefore M_w = \rho A_0 \left\{ \frac{A_t}{A_0} - \left[ 1 + 1.5 \sqrt{\frac{2\rho_0 H_0}{\rho}} \frac{A t}{A_0} \right]^{2/3} \right\}$$

t (s)	M <sub>w</sub> (kg)
0	4995
2	4862
4	4730
6	4600
8	4472
10	4345
12	4220
14	4096
16	3973
18	3851
20	3731
22	3612
24	3494
26	3377
28	3260
30	3145
32	3031
34	2918
36	2806
38	2695
40	2584




42 SHEETS 5 SQUARE  
 42 SHEETS 3 SQUARE  
 42 SHEETS 2 SQUARE  
 42 SHEETS 1 SQUARE  
 NATIONAL

## Problem 6.82

[Difficulty: 4]

**6.82** Water flows at low speed through a circular tube with inside diameter of 2 in. A smoothly contoured body of 1.5 in. diameter is held in the end of the tube where the water discharges to atmosphere. Neglect frictional effects and assume uniform velocity profiles at each section. Determine the pressure measured by the gage and the force required to hold the body.



**Given:** Water flow out of tube

**Find:** Pressure indicated by gage; force to hold body in place

**Solution:**

Basic equations: Bernoulli, and momentum flux in x direction

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad Q = V \cdot A \quad F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Steady flow 2) Incompressible 3) No friction 4) Flow along streamline 5) Uniform flow 6) Horizontal flow ( $g_x = 0$ )

Applying Bernoulli between jet exit and stagnation point

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_2^2}{2} = \frac{V_2^2}{2} \quad \text{where we work in gage pressure}$$

$$p_1 = \frac{\rho}{2} \cdot (V_2^2 - V_1^2)$$

But from continuity  $Q = V_1 \cdot A_1 = V_2 \cdot A_2$   $V_2 = V_1 \cdot \frac{A_1}{A_2} = V_1 \cdot \frac{D^2}{D^2 - d^2}$  where  $D = 2$  in and  $d = 1.5$  in

$$V_2 = 20 \cdot \frac{\text{ft}}{\text{s}} \cdot \left( \frac{2^2}{2^2 - 1.5^2} \right) \quad V_2 = 45.7 \cdot \frac{\text{ft}}{\text{s}}$$

Hence  $p_1 = \frac{1}{2} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times (45.7^2 - 20^2) \cdot \left( \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$   $p_1 = 1638 \cdot \frac{\text{lb} \cdot \text{s}^2}{\text{ft}^2}$   $p_1 = 11.4 \cdot \text{psi}$  (gage)

The x momentum is  $-F + p_1 \cdot A_1 - p_2 \cdot A_2 = u_1 \cdot (-\rho \cdot V_1 \cdot A_1) + u_2 \cdot (\rho \cdot V_2 \cdot A_2)$

$$F = p_1 \cdot A_1 + \rho \cdot (V_1^2 \cdot A_1 - V_2^2 \cdot A_2) \quad \text{using gage pressures}$$

$$F = 11.4 \cdot \frac{\text{lb} \cdot \text{s}^2}{\text{in}^2} \times \frac{\pi \cdot (2 \cdot \text{in})^2}{4} + 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left[ \left( 20 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\pi \cdot (2 \cdot \text{in})^2}{4} - \left( 45.7 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\pi \cdot [(2 \cdot \text{in})^2 - (1.5 \cdot \text{in})^2]}{4} \right] \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$F = 14.1 \cdot \text{lb} \cdot \text{ft} \quad \text{in the direction shown}$$





## Problem 6.84

[Difficulty: 5]

---

**6.84** Describe the pressure distribution on the exterior of a multistory building in a steady wind. Identify the locations of the maximum and minimum pressures on the outside of the building. Discuss the effect of these pressures on infiltration of outside air into the building.

---

**Open-Ended Problem Statement:** Describe the pressure distribution on the exterior of a multistory building in a steady wind. Identify the locations of the maximum and minimum pressures on the outside of the building. Discuss the effect of these pressures on infiltration of outside air into the building.

**Discussion:** A multi-story building acts as a bluff-body obstruction in a thick atmospheric boundary layer. The boundary-layer velocity profile causes the air speed near the top of the building to be highest and that toward the ground to be lower.

Obstruction of air flow by the building causes regions of stagnation pressure on upwind surfaces. The stagnation pressure is highest where the air speed is highest. Therefore the maximum surface pressure occurs near the roof on the upwind side of the building. Minimum pressure on the upwind surface of the building occurs near the ground where the air speed is lowest.

The minimum pressure on the entire building will likely be in the low-speed, low-pressure wake region on the downwind side of the building.

Static pressure inside the building will tend to be an average of all the surface pressures that act on the outside of the building. It is never possible to seal all openings completely. Therefore air will tend to infiltrate into the building in regions where the outside surface pressure is above the interior pressure, and will tend to pass out of the building in regions where the outside surface pressure is below the interior pressure. Thus generally air will tend to move through the building from the upper floors toward the lower floors, and from the upwind side to the downwind side.

## Problem 6.85

[Difficulty: 5]

---

**6.85** Imagine a garden hose with a stream of water flowing out through a nozzle. Explain why the end of the hose may be unstable when held a half meter or so from the nozzle end.

---

**Open-Ended Problem Statement:** Imagine a garden hose with a stream of water flowing out through a nozzle. Explain why the end of the hose may be unstable when held a half meter or so from the nozzle end.

**Discussion:** Water flowing out of the nozzle tends to exert a thrust force on the end of the hose. The thrust force is aligned with the flow from the nozzle and is directed toward the hose.

Any misalignment of the hose will lead to a tendency for the thrust force to bend the hose further. This will quickly become unstable, with the result that the free end of the hose will “flail” about, spraying water from the nozzle in all directions.

This instability phenomenon can be demonstrated easily in the backyard. However, it will tend to do least damage when the person demonstrating it is wearing a bathing suit!

## Problem 6.86

[Difficulty: 5]

---

**6.86** An aspirator provides suction by using a stream of water flowing through a venturi. Analyze the shape and dimensions of such a device. Comment on any limitations on its use.

---

**Open-Ended Problem Statement:** An aspirator provides suction by using a stream of water flowing through a venturi. Analyze the shape and dimensions of such a device. Comment on any limitations on its use.

**Discussion:** The basic shape of the aspirator channel should be a converging nozzle section to reduce pressure followed by a diverging diffuser section to promote pressure recovery. The basic shape is that of a venturi flow meter.

If the diffuser exhausts to atmosphere, the exit pressure will be atmospheric. The pressure rise in the diffuser will cause the pressure at the diffuser inlet (venturi throat) to be below atmospheric.

A small tube can be brought in from the side of the throat to aspirate another liquid or gas into the throat as a result of the reduced pressure there.

The following comments can be made about limitations on the aspirator:


1. It is desirable to minimize the area of the aspirator tube compared to the flow area of the venturi throat. This minimizes the disturbance of the main flow through the venturi and promotes the best possible pressure recovery in the diffuser.
2. It is desirable to avoid cavitation in the throat of the venturi. Cavitation alters the effective shape of the flow channel and destroys the pressure recovery in the diffuser. To avoid cavitation, the reduced pressure must always be above the vapor pressure of the driver liquid.
3. It is desirable to limit the flow rate of gas into the venturi throat. A large amount of gas can alter the flow pattern and adversely affect pressure recovery in the diffuser.

The best combination of specific dimensions could be determined experimentally by a systematic study of aspirator performance. A good starting point probably would be to use dimensions similar to those of a commercially available venturi flow meter.

### Problem 6.87

[Difficulty: 5]

6.87 A tank with a reentrant orifice called a Borda mouthpiece is shown. The fluid is inviscid and incompressible. The reentrant orifice essentially eliminates flow along the tank walls, so the pressure there is nearly hydrostatic. Calculate the contraction coefficient,  $C_c = A/A_0$ . Hint: Equate the unbalanced hydrostatic pressure force and momentum flux from the jet.



Solution:

Apply the x-component of the momentum equation to the CV shown

$$F_{sx} + F_{px} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{v} \cdot d\vec{A}$$

- Assumptions:
- (1) steady flow
  - (2) uniform flow at jet exit.
  - (3) hydrostatic pressure variation across CS,  $\rho \Delta z$
  - (4) x-momentum flux across horizontal portion of CS is negligible.
  - (5)  $p = \text{constant}$

Then

$$\int_{A_0} p dA_1 = \dot{m} V_j = \rho V_j A_j V_j = \rho A_j V_j^2$$

$$p_1 A_0 = \rho g h A_0 = \rho A_j V_j^2$$

$$\therefore \frac{A_0}{A_j} = \frac{g h}{V_j^2}$$

Apply the Bernoulli equation along the central streamline from (1) to the jet exit.

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g z_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g z_2$$

Assumptions: (6) frictionless flow

$$p_1 = \rho g h = \rho \frac{V_2^2}{2}$$

$$\therefore \frac{V_2^2}{2} = g h$$

and

$$\frac{A_0}{A_j} = \frac{V_2^2}{g h} = 2$$


$$\therefore C_c = \frac{A_j}{A_0} = \frac{1}{2}$$

$C_c$

### Problem 6.88

[Difficulty: 3]

**6.88** Apply the unsteady Bernoulli equation to the U-tube manometer of constant diameter shown. Assume that the manometer is initially deflected and then released. Obtain a differential equation for  $l$  as a function of time.



Solution

Basic equation: 
$$\frac{P_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{P_2}{\rho} + \frac{V_2^2}{2} + gz_2 + \int_1^2 \frac{\partial V_s}{\partial t} ds$$

Assumptions: (1) incompressible flow  
(2) frictionless flow  
(3) flow along a streamline

Since  $P_1 = P_2 = P_{atm}$  and  $V_1^2 = V_2^2$ , then

$$g(z_1 - z_2) = \int_1^2 \frac{\partial V_s}{\partial t} ds$$

Let  $L$  = total length of column  
 $l$  = deflection

Then  $ds = dl$   
 $V_s = V = \frac{dl}{dt}$

$$\therefore 2gl = \int_1^2 \frac{\partial V}{\partial t} dl = \frac{\partial V}{\partial t} \int_1^2 dl = L \frac{\partial V}{\partial t}$$

Since  $V = -\frac{dl}{dt}$


$$2gl = L \frac{\partial V}{\partial t} = -L \frac{d^2 l}{dt^2}$$

Finally 
$$\frac{d^2 l}{dt^2} + \frac{2g}{L} l = 0$$

## Problem 6.89

[Difficulty: 3]

**6.89** Compressed air is used to accelerate water from a tube. Neglect the velocity in the reservoir and assume the flow in the tube is uniform at any section. At a particular instant, it is known that  $V = 6 \text{ ft/s}$  and  $dV/dt = 7.5 \text{ ft/s}^2$ . The cross-sectional area of the tube is  $A = 32 \text{ in}^2$ . Determine the pressure in the tank at this instant.



**Given:** Unsteady water flow out of tube

**Find:** Pressure in the tank

**Solution:**

Basic equation: Unsteady Bernoulli

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2 + \int_1^2 \frac{\partial V}{\partial t} ds$$

Assumptions: 1) Unsteady flow 2) Incompressible 3) No friction 4) Flow along streamline 5) Uniform flow 6) Horizontal flow ( $g_x = 0$ )

Applying unsteady Bernoulli between reservoir and tube exit

$$\frac{p}{\rho} + g \cdot h = \frac{V^2}{2} + \int_1^2 \frac{\partial V}{\partial t} ds = \frac{V^2}{2} + \frac{dV}{dt} \cdot \int_1^2 1 ds \quad \text{where we work in gage pressure}$$


Hence 
$$p = \rho \cdot \left( \frac{V^2}{2} - g \cdot h + \frac{dV}{dt} \cdot L \right)$$

Hence 
$$p = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( \frac{6^2}{2} - 32.2 \times 4.5 + 7.5 \times 35 \right) \cdot \left( \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad p = 263 \cdot \frac{\text{lbf}}{\text{ft}^2} \quad p = 1.83 \cdot \text{psi} \quad (\text{gage})$$

## Problem 6.90

[Difficulty: 3]

**6.90** If the water in the pipe in Problem 6.89 is initially at rest and the air pressure is 3 psig, what will be the initial acceleration of the water in the pipe?



**Given:** Unsteady water flow out of tube

**Find:** Initial acceleration

**Solution:**

Basic equation: Unsteady Bernoulli

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2 + \int_1^2 \frac{\partial V}{\partial t} ds$$

Assumptions: 1) Unsteady flow 2) Incompressible 3) No friction 4) Flow along streamline 5) Uniform flow 6) Horizontal flow ( $g_x = 0$ )

Applying unsteady Bernoulli between reservoir and tube exit

$$\frac{p}{\rho} + g \cdot h = \int_1^2 \frac{\partial V}{\partial t} ds = \frac{dV}{dt} \cdot \int_1^2 1 ds = a_x \cdot L \quad \text{where we work in gage pressure}$$

Hence

$$a_x = \frac{1}{L} \left( \frac{p}{\rho} + g \cdot h \right)$$

Hence


$$a_x = \frac{1}{35 \cdot \text{ft}} \times \left[ 3 \cdot \frac{\text{lbf}}{\text{in}^2} \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}} + 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 4.5 \cdot \text{ft} \right] \quad a_x = 10.5 \cdot \frac{\text{ft}}{\text{s}^2}$$

Note that we obtain the same result if we treat the water in the pipe as a single body at rest with gage pressure  $p + \rho gh$  at the left end!

### Problem 6.91

[Difficulty: 4]

6.91 Consider the reservoir and disk flow system with the reservoir level maintained constant. Flow between the disks is started from rest at  $t = 0$ . Evaluate the rate of change of volume flow rate at  $t = 0$ , if  $r_1 = 50$  mm.



Solution:

Apply the unsteady Bernoulli equation from the surface to the exit.

$$\cancel{\frac{p}{\rho}} + \cancel{\frac{V^2}{2}} + g z_0 = \cancel{\frac{p_e}{\rho}} + \cancel{\frac{V_e^2}{2}} + g z_e + \int_1^2 \frac{\partial V_s}{\partial t} ds$$

$$gH = \frac{V_e^2}{2} + \int_1^2 \frac{\partial V_s}{\partial t} ds$$

Assumptions: (1) frictionless flow  
(2) incompressible flow  
(3) flow along a streamline.

For uniform flow at any section between the plates, for  $r \geq r_1$ , the volume flow rate is given by

$$Q = \int \vec{v} \cdot d\vec{A} = v_r 2\pi r h \quad \text{and} \quad v_r = \frac{Q}{2\pi r h}$$

At the exit  $v_e = \frac{Q}{2\pi R h}$

Assume that the rate of change of fluid velocity in the reservoir (out to  $r = r_1$ ) is negligible. Then

$$\int_1^2 \frac{\partial V_s}{\partial t} ds = \frac{\partial}{\partial t} \int_{r_1}^R v_r dr = \frac{\partial}{\partial t} \int_{r_1}^R \frac{Q}{2\pi h r} dr = \frac{\ln R/r_1}{2\pi h} \frac{dQ}{dt}$$

Then substituting into the unsteady Bernoulli equation, we obtain

$$gH = \frac{Q^2}{8\pi^2 R^2 h^2} + \frac{\ln R/r_1}{2\pi h} \frac{dQ}{dt}$$

At  $t = 0$ ,  $Q = 0$  and

$$\frac{dQ}{dt} = \frac{2\pi h g H}{\ln R/r_1}$$

$$= 2\pi \times 0.0015 \text{ m} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 1 \text{ m} \times \frac{1}{\ln \frac{300}{50}}$$


$$\frac{dQ}{dt} = 0.0516 \text{ m}^3/\text{s}/\text{s}$$

$\left. \frac{dQ}{dt} \right|_{t=0}$

## Problem 6.92

[Difficulty: 4]

**6.92** If the water in the pipe of Problem 6.89 is initially at rest, and the air pressure is maintained at 1.5 psig, derive a differential equation for the velocity  $V$  in the pipe as a function of time, integrate, and plot  $V$  versus  $t$  for  $t = 0$  to 5 s.



**Given:** Unsteady water flow out of tube

**Find:** Differential equation for velocity; Integrate; Plot  $v$  versus time

**Solution:**

Basic equation: Unsteady Bernoulli 
$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2 + \int_1^2 \frac{\partial V}{\partial t} ds$$

Assumptions: 1) Unsteady flow 2) Incompressible 3) No friction 4) Flow along streamline 5) Uniform flow 6) Horizontal flow ( $g_x = 0$ )

Applying unsteady Bernoulli between reservoir and tube exit


$$\frac{p}{\rho} + g \cdot h = \frac{V^2}{2} + \int_1^2 \frac{\partial}{\partial t} V ds = \frac{V^2}{2} + \frac{dV}{dt} \cdot \int_1^2 ds = \frac{V^2}{2} + \frac{dV}{dt} \cdot L \quad \text{where we work in gage pressure}$$

Hence 
$$\frac{dV}{dt} + \frac{V^2}{2 \cdot L} = \frac{1}{L} \cdot \left( \frac{p}{\rho} + g \cdot h \right)$$
 is the differential equation for the flow

Separating variable: 
$$\frac{L \cdot dV}{\frac{p}{\rho} + g \cdot h - \frac{V^2}{2}} = dt$$

Integrating and using limits  $V(0) = 0$  and  $V(t) = V$

$$V(t) = \sqrt{2 \cdot \left( \frac{p}{\rho} + g \cdot h \right)} \cdot \tanh \left( \sqrt{\frac{\left( \frac{p}{\rho} + g \cdot h \right)}{2 \cdot L^2}} \cdot t \right)$$



This graph is suitable for plotting in *Excel*

For large times 
$$V = \sqrt{2 \cdot \left( \frac{p}{\rho} + g \cdot h \right)} \quad V = 22.6 \cdot \frac{\text{ft}}{\text{s}}$$

6.93 Consider the tank of Problem 4.46. Using the Bernoulli equation for unsteady flow along a streamline, evaluate the minimum diameter ratio,  $D/d$ , required to justify the assumption that flow from the tank is quasi-steady.

Solution:

For incompressible, frictionless flow along a streamline, the unsteady Bernoulli equation is

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g y_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g y_2 + \int_1^2 \frac{\partial V}{\partial t} dy$$

$$p_1 = p_2 = p_{atm}, \quad y_2 = 0$$

From continuity  $V_1 A_1 = V_2 A_2 = V A$

$$\therefore \frac{1}{2} V_1^2 \left( \frac{A_1}{A} \right) + g y_1 = \frac{1}{2} V_1^2 + \int_1^2 \frac{\partial V}{\partial t} dy$$

$$\text{or,} \quad g y_1 = \frac{1}{2} V_1^2 \left[ 1 - \left( \frac{A_1}{A} \right)^2 \right] + \int_1^2 \frac{\partial V}{\partial t} dy$$

If we assume quasi-steady flow, we say that

$$\int_1^2 \frac{\partial V}{\partial t} dy \text{ is negligible and hence } \frac{g y_1}{\frac{1}{2} V_1^2 [1 - AR^2]} = 1 \quad \text{where } AR = \frac{A_1}{A}$$

$$\text{Now, } \int_1^2 \frac{\partial V}{\partial t} dy = L \frac{\partial V}{\partial t} = L \frac{\partial V}{\partial t} = L \frac{\partial}{\partial t} \left( V \frac{A_1}{A} \right) = L \frac{A_1}{A} \frac{\partial V}{\partial t}$$

Thus for the assumption to be reasonable we must have

$$L \frac{A_1}{A} \frac{\partial V}{\partial t} \ll g y_1 \quad \text{or} \quad \left| \frac{A_1}{A} \frac{\partial V}{\partial t} \right| \ll g$$

Under the assumption of quasi-steady flow

$$V = \left[ \frac{2 g y_1}{(1 - AR^2)} \right]^{1/2} \quad \text{where } AR = \frac{A_1}{A}$$

then,

$$\frac{\partial V}{\partial t} = \sqrt{\frac{2 g y_1}{(1 - AR^2)}} \frac{1}{2 y_1} \frac{\partial y_1}{\partial t} = \frac{\partial y_1}{\partial t} \sqrt{\frac{g}{2 y_1 (1 - AR^2)}}$$


Since

$$\frac{\partial V}{\partial t} = -V_1 = -V \frac{A_1}{A}, \quad \text{then}$$

$$\frac{\partial V}{\partial t} = -V \frac{A_1}{A} \sqrt{\frac{g}{2 y_1 (1 - AR^2)}} = -\frac{A_1}{A} \sqrt{\frac{V^2 (1 - AR^2)}{2 g y_1}} \frac{g}{(1 - AR^2)}$$

and

$$\frac{\partial V}{\partial t} = -\frac{A_1}{A} \frac{g}{(1 - AR^2)}$$



### Problem 6.93

[Difficulty: 5] Part 2/2

For  $\left| \frac{A_j}{A_1} \frac{dV_j}{dt} \right| \ll g$ , then  $\left( \frac{A_j}{A_1} \right)^2 \frac{1}{(1-Ar^2)} \ll 1$

If we take  $\left( \frac{A_j}{A_1} \right)^2 \frac{1}{(1-Ar^2)} \approx 0.01$

then,  $\left( \frac{A_j}{A_1} \right)^2 = 0.01(1-Ar^2) = 0.01 \left[ 1 - \left( \frac{A_j}{A_1} \right)^2 \right]$

and  $1.01 \left( \frac{A_j}{A_1} \right)^2 = 0.01$

$$\frac{A_j}{A_1} = 0.0995$$

or


$$\frac{D_j}{D_1} = \left( \frac{A_j}{A_1} \right)^{1/2} = 0.32 \quad \leftarrow$$

In problem 4.48,  $D_j/D_1 = d/y = .04$  and hence the assumption of quasi-steady flow is valid.

### Problem 6.94

[Difficulty: 5]

6.94 Two circular disks, of radius  $R$ , are separated by distance  $b$ . The upper disk moves toward the lower one at constant speed  $V$ . The space between the disks is filled with a frictionless, incompressible fluid, which is squeezed out as the disks come together. Assume that, at any radial section, the velocity is uniform across the gap width  $b$ . However, note that  $b$  is a function of time. The pressure surrounding the disks is atmospheric. Determine the gage pressure at  $r = 0$ .



Solution.

Basic equation: 
$$\frac{P_1}{\rho} + \frac{V_1^2}{2} + g z_1 = \frac{P_2}{\rho} + \frac{V_2^2}{2} + g z_2 + \int_1^2 \frac{\partial V_s}{\partial t} ds$$

$$0 = \frac{\partial}{\partial t} \int_{CV} p dV + \int_{CS} p \vec{V} \cdot d\vec{A}$$

- Assumptions:
- (1) incompressible flow
  - (2) frictionless flow
  - (3) flow along a streamline
  - (4) uniform radial flow at any  $r$
  - (5) neglect elevation changes.

Res.

$$0 = \frac{\partial}{\partial t} \int_{CV} p dV + \int_{CS} p \vec{V} \cdot d\vec{A} = \frac{\partial}{\partial t} (p \pi r^2 b) + p v_r 2\pi r b$$

$$= p \pi r^2 \frac{\partial b}{\partial t} + p v_r 2\pi r b \quad \text{But } \frac{\partial b}{\partial t} = -V$$

$$\therefore 0 = -p \pi r^2 V + p v_r 2\pi r b \quad \text{and } v_r = v_r \frac{r}{2b}$$

Applying the Bernoulli equation between point (1) ( $r=r$ ) and point (2) ( $r=R$ )

$$P_1 - P_2 = \frac{\rho}{2} [V_2^2 - V_1^2] + \int_r^R \rho \frac{\partial v_r}{\partial t} dr \quad \text{Now, } \frac{\partial v_r}{\partial t} = \frac{\partial}{\partial t} \left( v_r \frac{r}{2b} \right) = \frac{r v_r}{2} \left( -\frac{1}{b^2} \frac{\partial b}{\partial t} \right) = \frac{V v_r r}{2b^2}$$

$$= \frac{\rho}{2} \left[ \left( \frac{V R}{2b} \right)^2 - \left( \frac{V r}{2b} \right)^2 \right] + \int_r^R \rho \frac{V v_r r}{2b^2} dr$$

$$= \frac{\rho V^2}{8b^2} [R^2 - r^2] + \frac{\rho V^2}{4b^2} \left[ r^2 \right]_r^R = \frac{\rho V^2}{8b^2} [R^2 - r^2] + \frac{\rho V^2}{4b^2} [R^2 - r^2]$$

$$P_1 - P_{atm} = \frac{3}{8} \frac{\rho V^2}{b^2} [R^2 - r^2] = \frac{3}{8} \frac{\rho V^2 R^2}{b^2} \left[ 1 - \left( \frac{r}{R} \right)^2 \right]$$

When  $r = 0$   $P_1 = P_g$


$$\therefore P_g - P_{atm} = \frac{3}{8} \frac{\rho V^2 R^2}{b^2}$$

## Problem 6.95


[Difficulty: 2]

**6.95** Carefully sketch the energy grade lines (EGL) and hydraulic grade lines (HGL) for the system shown in Fig. 6.6 if the pipe is horizontal (i.e., the outlet is at the base of the reservoir), and a water turbine (extracting energy) is located at point ②, or at point ③. In Chapter 8 we will investigate the effects of friction on internal flows. Can you anticipate and sketch the effect of friction on the EGL and HGL for the two cases?

- (a) Note that the effect of friction would be that the EGL would tend to drop: suddenly at the contraction, gradually in the large pipe, more steeply in the small pipe. The HGL would then “hang” below the HGL in a manner similar to that shown.



- (b) Note that the effect of friction would be that the EGL would tend to drop: suddenly at the contraction, gradually in the large pipe, more steeply in the small pipe. The HGL would then “hang” below the HGL in a manner similar to that shown.




## Problem 6.96


[Difficulty: 2]

**6.96** Carefully sketch the energy grade lines (EGL) and hydraulic grade lines (HGL) for the system shown in Fig. 6.6 if a pump (adding energy to the fluid) is located at point ②, or at point ③, such that flow is *into* the reservoir. In Chapter 8 we will investigate the effects of friction on internal flows. Can you anticipate and sketch the effect of friction on the EGL and HGL for the two cases?

- (a) Note that the effect of friction would be that the EGL would tend to drop from right to left: steeply in the small pipe, gradually in the large pipe, and suddenly at the expansion. The HGL would then “hang” below the HGL in a manner similar to that shown.



- (b) Note that the effect of friction would be that the EGL would tend to drop from right to left: steeply in the small pipe, gradually in the large pipe, and suddenly at the expansion. The HGL would then “hang” below the EGL in a manner similar to that shown.



### Problem 6.97

[Difficulty: 2]

6.97 Determine whether the Bernoulli equation can be applied between different radii for the vortex flow fields

(a)  $\vec{V} = \omega r \hat{e}_\theta$  and (b)  $\vec{V} = \hat{e}_\theta K/2\pi r$ .

Solution: Since  $v_r = 0$ , the streamlines are concentric circles. In order for it to be possible to apply the Bernoulli equation between different radii, it is necessary that the flow be irrotational.

$$\text{Basic equation: } \vec{\omega} = \frac{1}{2} \nabla \times \vec{V}$$

Flow (1)

$$\begin{aligned} \nabla \times \vec{V}_1 &= \left( \hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{e}_z \frac{\partial}{\partial z} \right) \times \omega r \hat{e}_\theta \\ &= \hat{e}_r \times \hat{e}_\theta \frac{\partial}{\partial r} (\omega r) + \hat{e}_r \times \omega r \frac{\partial \hat{e}_\theta}{\partial r} + \hat{e}_\theta \times \hat{e}_\theta \frac{1}{r} \frac{\partial (\omega r)}{\partial \theta} + \hat{e}_\theta \times \omega r \frac{\partial \hat{e}_\theta}{\partial \theta} \\ &= \hat{e}_z \omega + \hat{e}_\theta \times \omega (-\hat{e}_r) \end{aligned}$$

$$\nabla \times \vec{V}_1 = 2\omega \hat{e}_z$$

$\therefore$  Flow (1) is rotational and Bernoulli equation cannot be applied between different radii.

Flow (2)

$$\begin{aligned} \nabla \times \vec{V}_2 &= \left( \hat{e}_r \frac{\partial}{\partial r} + \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} + \hat{e}_z \frac{\partial}{\partial z} \right) \times \frac{K}{2\pi r} \hat{e}_\theta \\ &= \hat{e}_r \times \hat{e}_\theta \frac{\partial}{\partial r} \left( \frac{K}{2\pi r} \right) + \hat{e}_r \times \left( \frac{K}{2\pi r} \right) \frac{\partial \hat{e}_\theta}{\partial r} + \hat{e}_\theta \times \hat{e}_\theta \frac{1}{r} \frac{\partial}{\partial \theta} \left( \frac{K}{2\pi r} \right) + \hat{e}_\theta \times \frac{1}{r} \left( \frac{K}{2\pi r} \right) \frac{\partial \hat{e}_\theta}{\partial \theta} \\ &= -\hat{e}_z \frac{K}{2\pi r^2} + \hat{e}_\theta \times \frac{K}{2\pi r^2} (-\hat{e}_r) \\ &= -\hat{e}_z \frac{K}{2\pi r^2} + \hat{e}_z \frac{K}{2\pi r^2} \end{aligned}$$

$$\nabla \times \vec{V}_2 = 0$$

Since the flow field is irrotational, Bernoulli equation can be applied between different radii if the flow is also incompressible and frictionless.

## Problem 6.98

[Difficulty: 3]

**6.98** Consider a two-dimensional fluid flow:  $u = ax + by$  and  $v = cx + dy$ , where  $a$ ,  $b$ ,  $c$  and  $d$  are constant. If the flow is incompressible and irrotational, find the relationships among  $a$ ,  $b$ ,  $c$ , and  $d$ . Find the stream function and velocity potential function of this flow.

**Given:** 2D incompressible, inviscid flow field

**Find:** Relationships among constants; stream function; velocity potential

**Solution:**

Basic equations      Incompressible       $u = \frac{\partial \psi}{\partial y}$        $v = \frac{\partial \psi}{\partial x}$       Irrotational       $u = \frac{\partial \phi}{\partial x}$        $v = \frac{\partial \phi}{\partial y}$

$$u(x, y) = a \cdot x + b \cdot y \quad v(x, y) = c \cdot x + d \cdot y$$

Check incompressibility       $\frac{\partial}{\partial x} u(x, y) + \frac{\partial}{\partial y} v(x, y) = a + d$       Hence must have       $d = -a$

Check irrotational       $\frac{\partial}{\partial x} v(x, y) - \frac{\partial}{\partial y} u(x, y) = c - b$       Hence must have       $c = b$

Hence for the streamfunction       $\psi(x, y) = \int u(x, y) dy = a \cdot x \cdot y + \frac{1}{2} \cdot b \cdot y^2 + f(x)$

$$\psi(x, y) = - \int v(x, y) dx = -\frac{1}{2} \cdot c \cdot x^2 - d \cdot x \cdot y + g(y)$$

Comparing       $\psi(x, y) = \frac{1}{2} \cdot b \cdot y^2 - \frac{1}{2} \cdot c \cdot x^2 + a \cdot x \cdot y$        $\psi(x, y) = a \cdot x \cdot y + \frac{1}{2} \cdot b \cdot (y^2 - x^2)$

Check       $u(x, y) = \frac{\partial}{\partial y} \psi(x, y) = a \cdot x + b \cdot y$        $v(x, y) = \frac{\partial}{\partial x} \psi(x, y) = b \cdot x - a \cdot y$

Hence for the velocity potential       $\phi(x, y) = - \int u(x, y) dx = -\frac{1}{2} \cdot a \cdot x^2 - b \cdot x \cdot y + f(y)$

$$\phi(x, y) = - \int v(x, y) dy = -c \cdot x \cdot y - \frac{1}{2} \cdot d \cdot y^2 + g(x)$$

Comparing       $\phi(x, y) = -\frac{1}{2} \cdot a \cdot x^2 - \frac{1}{2} \cdot d \cdot y^2 - b \cdot x \cdot y$        $\phi(x, y) = -b \cdot x \cdot y - \frac{1}{2} \cdot a \cdot (x^2 - y^2)$

Check       $u(x, y) = \frac{\partial}{\partial x} \phi(x, y) = a \cdot x + b \cdot y$        $v(x, y) = \frac{\partial}{\partial y} \phi(x, y) = b \cdot x - a \cdot y$

## Problem 6.99

[Difficulty: 3]

**6.99** Consider the flow represented by the stream function  $\psi = Ax^2y$ , where  $A$  is a dimensional constant equal to  $2.5 \text{ m}^{-1} \cdot \text{s}^{-1}$ . The density is  $1200 \text{ kg/m}^3$ . Is the flow rotational? Can the pressure difference between points  $(x, y) = (1, 4)$  and  $(2, 1)$  be evaluated? If so, calculate it, and if not, explain why.

**Given:** Stream function

**Find:** If the flow is irrotational; Pressure difference between points (1,4) and (2,1)

**Solution:**

Basic equations: Incompressibility because  $\psi$  exists  $u = \frac{\partial}{\partial y}\psi$   $v = \frac{\partial}{\partial x}\psi$  Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

$$\psi(x, y) = A \cdot x^2 \cdot y$$

$$u(x, y) = \frac{\partial}{\partial y}\psi(x, y) = \frac{\partial}{\partial y}(A \cdot x^2 \cdot y) \quad u(x, y) = A \cdot x^2$$

$$v(x, y) = \frac{\partial}{\partial x}\psi(x, y) = \frac{\partial}{\partial x}(A \cdot x^2 \cdot y) \quad v(x, y) = -2 \cdot A \cdot x \cdot y$$

Hence  $\frac{\partial}{\partial x}v(x, y) - \frac{\partial}{\partial y}u(x, y) = -2 \cdot A \cdot y$   $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u \neq 0$  so flow is NOT IRROTATIONAL

Since flow is rotational, we must be on same streamline to be able to use Bernoulli

At point (1,4)  $\psi(1, 4) = 4A$  and at point (2,1)  $\psi(2, 1) = 4A$

Hence these points are on same streamline so Bernoulli can be used. The velocity at a point is  $V(x, y) = \sqrt{u(x, y)^2 + v(x, y)^2}$

Hence at (1,4)  $V_1 = \sqrt{\left[\frac{2.5}{\text{m}\cdot\text{s}} \times (1\cdot\text{m})\right]^2 + \left(-2 \times \frac{2.5}{\text{m}\cdot\text{s}} \times 1\cdot\text{m} \times 4\cdot\text{m}\right)^2}$   $V_1 = 20.2 \frac{\text{m}}{\text{s}}$

Hence at (2,1)  $V_2 = \sqrt{\left[\frac{2.5}{\text{m}\cdot\text{s}} \times (2\cdot\text{m})\right]^2 + \left(-2 \times \frac{2.5}{\text{m}\cdot\text{s}} \times 2\cdot\text{m} \times 1\cdot\text{m}\right)^2}$   $V_2 = 14.1 \frac{\text{m}}{\text{s}}$

Using Bernoulli  $\frac{p_1}{\rho} + \frac{1}{2} \cdot V_1^2 = \frac{p_2}{\rho} + \frac{1}{2} \cdot V_2^2$   $\Delta p = \frac{\rho}{2} \cdot (V_2^2 - V_1^2)$

$$\Delta p = \frac{1}{2} \times 1200 \cdot \frac{\text{kg}}{\text{m}^3} \times (14.1^2 - 20.2^2) \cdot \left(\frac{\text{m}}{\text{s}}\right)^2 \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}}$$

$$\Delta p = -126 \cdot \text{kPa}$$

**6.100** The velocity field for a two-dimensional flow is  $\vec{V} = (Ax - By)t\hat{i} - (Bx + Ay)t\hat{j}$ , where  $A = 1 \text{ s}^{-2}$ ,  $B = 2 \text{ s}^{-2}$ ,  $t$  is in seconds, and the coordinates are measured in meters. Is this a possible incompressible flow? Is the flow steady or unsteady? Show that the flow is irrotational and derive an expression for the velocity potential.

Solution: For incompressible flow,  $\nabla \cdot \vec{V} = 0$

For given flow  $\nabla \cdot \vec{V} = \frac{\partial}{\partial x}(Ax - By)t - \frac{\partial}{\partial y}(Bx + Ay)t = At - At = 0$

$\therefore$  velocity field represents a possible incompressible flow

The flow is unsteady since  $\vec{V} = \vec{V}(x, y, t)$

The rotation is given by  $\vec{\omega} = \frac{1}{2} \nabla \times \vec{V} = \frac{1}{2} \left( \frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right) \hat{k}$

$\vec{\omega} = \frac{1}{2} \left[ \frac{\partial}{\partial x} - (Bx + Ay)t - \frac{\partial}{\partial y} (Ax - By)t \right] = -Bt + Bt = 0$

$\vec{\omega} = 0$ , so flow is irrotational

From the definition of the velocity potential,  $\vec{V} = -\nabla \phi$

$u = -\frac{\partial \phi}{\partial x}$  and  $\phi = \int u dx + f(y, t) = \int -(Ax - By)t dx + f(y, t)$   
 $\phi = \left( -A \frac{x^2}{2} + Bxy \right) t + f(y, t)$

$v = -\frac{\partial \phi}{\partial y}$  and  $\phi = \int -v dy + g(x, t) = \int (Bx + Ay)t dy + g(x, t)$   
 $\phi = \left( Bxy + A \frac{y^2}{2} \right) t + g(x, t)$

Comparing the two expressions for  $\phi$  we conclude

$f(y, t) = \frac{A}{2} y^2 t$  and  $g(x, t) = -\frac{A}{2} x^2 t$

Hence,

$\phi = \left\{ \frac{A}{2} (y^2 - x^2) + Bxy \right\} t$

$\phi$

## Problem 6.101

[Difficulty: 3]

**6.101** Using Table 6.2, find the stream function and velocity potential for a plane source, of strength  $q$ , near a  $90^\circ$  corner. The source is equidistant  $h$  from each of the two infinite planes that make up the corner. Find the velocity distribution along one of the planes, assuming  $p = p_0$  at infinity. By choosing suitable values for  $q$  and  $h$ , plot the streamlines and lines of constant velocity potential. (*Hint: Use the Excel workbook of Example 6.10.*)

**Given:** Data from Table 6.2

**Find:** Stream function and velocity potential for a source in a corner; plot; velocity along one plane

**Solution:**

From Table 6.2, for a source at the origin  $\psi(r, \theta) = \frac{q}{2 \cdot \pi} \cdot \theta$   $\phi(r, \theta) = -\frac{q}{2 \cdot \pi} \cdot \ln(r)$

Expressed in Cartesian coordinates  $\psi(x, y) = \frac{q}{2 \cdot \pi} \cdot \text{atan}\left(\frac{y}{x}\right)$   $\phi(x, y) = -\frac{q}{4 \cdot \pi} \cdot \ln(x^2 + y^2)$

To build flow in a corner, we need image sources at three locations so that there is symmetry about both axes. We need sources at  $(h, h)$ ,  $(h, -h)$ ,  $(-h, h)$ , and  $(-h, -h)$

Hence the composite stream function and velocity potential are

$$\psi(x, y) = \frac{q}{2 \cdot \pi} \cdot \left( \text{atan}\left(\frac{y-h}{x-h}\right) + \text{atan}\left(\frac{y+h}{x-h}\right) + \text{atan}\left(\frac{y+h}{x+h}\right) + \text{atan}\left(\frac{y-h}{x+h}\right) \right)$$

$$\phi(x, y) = -\frac{q}{4 \cdot \pi} \cdot \ln\left[\left[(x-h)^2 + (y-h)^2\right] \cdot \left[(x-h)^2 + (y+h)^2\right]\right] - \frac{q}{4 \cdot \pi} \cdot \left[\left[(x+h)^2 + (y+h)^2\right] \cdot \left[(x+h)^2 + (y-h)^2\right]\right]$$

By a similar reasoning the horizontal velocity is given by

$$u = \frac{q \cdot (x-h)}{2 \cdot \pi \left[ (x-h)^2 + (y-h)^2 \right]} + \frac{q \cdot (x-h)}{2 \cdot \pi \left[ (x-h)^2 + (y+h)^2 \right]} + \frac{q \cdot (x+h)}{2 \cdot \pi \left[ (x+h)^2 + (y+h)^2 \right]} + \frac{q \cdot (x+h)}{2 \cdot \pi \left[ (x+h)^2 + (y-h)^2 \right]}$$


Along the horizontal wall ( $y = 0$ )

$$u = \frac{q \cdot (x-h)}{2 \cdot \pi \left[ (x-h)^2 + h^2 \right]} + \frac{q \cdot (x-h)}{2 \cdot \pi \left[ (x-h)^2 + h^2 \right]} + \frac{q \cdot (x+h)}{2 \cdot \pi \left[ (x+h)^2 + h^2 \right]} + \frac{q \cdot (x+h)}{2 \cdot \pi \left[ (x+h)^2 + h^2 \right]}$$


or 
$$u(x) = \frac{q}{\pi} \cdot \left[ \frac{x-h}{(x-h)^2 + h^2} + \frac{x+h}{(x+h)^2 + h^2} \right]$$

The results in *Excel* are:

### Velocity Potential



### Stream Function



## Problem 6.102

[Difficulty: 3]

**6.102** The flow field for a plane source at a distance  $h$  above an infinite wall aligned along the  $x$  axis is given by

$$\vec{V} = \frac{q}{2\pi[x^2 + (y-h)^2]}[x\hat{i} + (y-h)\hat{j}] + \frac{q}{2\pi[x^2 + (y+h)^2]}[x\hat{i} + (y+h)\hat{j}]$$

where  $q$  is the strength of the source. The flow is irrotational and incompressible. Derive the stream function and velocity potential. By choosing suitable values for  $q$  and  $h$ , plot the streamlines and lines of constant velocity potential. (*Hint: Use the Excel workbook of Example 6.10.*)

**Given:** Velocity field of irrotational and incompressible flow

**Find:** Stream function and velocity potential; plot

**Solution:**

The velocity field is

$$u = \frac{q \cdot x}{2 \cdot \pi [x^2 + (y - h)^2]} + \frac{q \cdot x}{2 \cdot \pi [x^2 + (y + h)^2]} \quad v = \frac{q \cdot (y - h)}{2 \cdot \pi [x^2 + (y - h)^2]} + \frac{q \cdot (y + h)}{2 \cdot \pi [x^2 + (y + h)^2]}$$

The basic equations are

$$u = \frac{\partial}{\partial y} \psi \quad v = \frac{\partial}{\partial x} \psi \quad u = \frac{\partial}{\partial x} \phi \quad v = \frac{\partial}{\partial y} \phi$$

Hence for the stream function

$$\psi = \int u(x, y) dy = \frac{q}{2 \cdot \pi} \cdot \left( \text{atan} \left( \frac{y - h}{x} \right) + \text{atan} \left( \frac{y + h}{x} \right) \right) + f(x)$$

$$\psi = - \int v(x, y) dx = \frac{q}{2 \cdot \pi} \cdot \left( \text{atan} \left( \frac{y - h}{x} \right) + \text{atan} \left( \frac{y + h}{x} \right) \right) + g(y)$$

The simplest expression for  $\psi$  is

$$\psi(x, y) = \frac{q}{2 \cdot \pi} \cdot \left( \text{atan} \left( \frac{y - h}{x} \right) + \text{atan} \left( \frac{y + h}{x} \right) \right)$$

For the stream function

$$\phi = - \int u(x, y) dx = - \frac{q}{4 \cdot \pi} \cdot \ln \left[ [x^2 + (y - h)^2] \cdot [x^2 + (y + h)^2] \right] + f(y)$$


$$\phi = - \int v(x, y) dy = - \frac{q}{4 \cdot \pi} \cdot \ln \left[ [x^2 + (y - h)^2] \cdot [x^2 + (y + h)^2] \right] + g(x)$$

The simplest expression for  $\phi$  is


$$\phi(x, y) = - \frac{q}{4 \cdot \pi} \cdot \ln \left[ [x^2 + (y - h)^2] \cdot [x^2 + (y + h)^2] \right]$$

In Excel:

## Stream Function



## Velocity Potential



## Problem 6.103

[Difficulty: 3]

**6.103** Using Table 6.2, find the stream function and velocity potential for a plane vortex, of strength  $K$ , near a  $90^\circ$  corner. The vortex is equidistant  $h$  from each of the two infinite planes that make up the corner. Find the velocity distribution along one of the planes, assuming  $p = p_0$  at infinity. By choosing suitable values for  $K$  and  $h$ , plot the streamlines and lines of constant velocity potential. (*Hint: Use the Excel workbook of Example Problem 6.10.*)

**Given:** Data from Table 6.2

**Find:** Stream function and velocity potential for a vortex in a corner; plot; velocity along one plane

**Solution:**

From Table 6.2, for a vortex at the origin

$$\phi(r, \theta) = \frac{K}{2 \cdot \pi} \cdot \theta \qquad \psi(r, \theta) = -\frac{K}{2 \cdot \pi} \cdot \ln(r)$$

Expressed in Cartesian coordinates

$$\phi(x, y) = \frac{K}{2 \cdot \pi} \cdot \operatorname{atan}\left(\frac{y}{x}\right) \qquad \psi(x, y) = -\frac{K}{4 \cdot \pi} \cdot \ln(x^2 + y^2)$$

To build flow in a corner, we need image vortices at three locations so that there is symmetry about both axes. We need vortices at  $(h, h)$ ,  $(h, -h)$ ,  $(-h, h)$ , and  $(-h, -h)$ . Note that some of them must have strengths of  $-K$ !

Hence the composite velocity potential and stream function are

$$\phi(x, y) = \frac{K}{2 \cdot \pi} \cdot \left( \operatorname{atan}\left(\frac{y-h}{x-h}\right) - \operatorname{atan}\left(\frac{y+h}{x-h}\right) + \operatorname{atan}\left(\frac{y+h}{x+h}\right) - \operatorname{atan}\left(\frac{y-h}{x+h}\right) \right)$$

$$\psi(x, y) = -\frac{K}{4 \cdot \pi} \cdot \ln \left[ \frac{(x-h)^2 + (y-h)^2}{(x-h)^2 + (y+h)^2} \cdot \frac{(x+h)^2 + (y+h)^2}{(x+h)^2 + (y-h)^2} \right]$$

By a similar reasoning the horizontal velocity is given by

$$u = -\frac{K \cdot (y-h)}{2 \cdot \pi \left[ (x-h)^2 + (y-h)^2 \right]} + \frac{K \cdot (y+h)}{2 \cdot \pi \left[ (x-h)^2 + (y+h)^2 \right]} - \frac{K \cdot (y+h)}{2 \cdot \pi \left[ (x+h)^2 + (y+h)^2 \right]} + \frac{K \cdot (y-h)}{2 \cdot \pi \left[ (x+h)^2 + (y-h)^2 \right]}$$



Along the horizontal wall ( $y = 0$ )

$$u = \frac{K \cdot h}{2 \cdot \pi \left[ (x-h)^2 + h^2 \right]} + \frac{K \cdot h}{2 \cdot \pi \left[ (x-h)^2 + h^2 \right]} - \frac{K \cdot h}{2 \cdot \pi \left[ (x+h)^2 + h^2 \right]} - \frac{K \cdot h}{2 \cdot \pi \left[ (x+h)^2 + h^2 \right]}$$

or

$$u(x) = \frac{K \cdot h}{\pi} \cdot \left[ \frac{1}{(x-h)^2 + h^2} - \frac{1}{(x+h)^2 + h^2} \right]$$

In Excel:



## Problem 6.104

[Difficulty: 2]

**6.104** The stream function of a flow field is  $\psi = Ax^2y - By^3$ , where  $A = 1 \text{ m}^{-1} \cdot \text{s}^{-1}$ ,  $B = \frac{1}{3} \text{ m}^{-1} \cdot \text{s}^{-1}$ , and the coordinates are measured in meters. Find an expression for the velocity potential.

**Given:** Stream function

**Find:** Velocity potential

**Solution:**

Basic equations: Incompressibility because  $\psi$  exists  $u = \frac{\partial}{\partial y} \psi$   $v = \frac{\partial}{\partial x} \psi$   $u = \frac{\partial}{\partial x} \varphi$   $v = \frac{\partial}{\partial y} \varphi$

Irrotationality  $\frac{\partial}{\partial x} v - \frac{\partial}{\partial y} u = 0$

We have  $\psi(x, y) = A \cdot x^2 \cdot y - B \cdot y^3$

Then  $u(x, y) = \frac{\partial}{\partial y} \psi(x, y)$   $u(x, y) = A \cdot x^2 - 3 \cdot B \cdot y^2$

$v(x, y) = \frac{\partial}{\partial x} \psi(x, y)$   $v(x, y) = -2 \cdot A \cdot x \cdot y$

Then  $\frac{\partial}{\partial x} v(x, y) - \frac{\partial}{\partial y} u(x, y) = 6 \cdot B \cdot y - 2 \cdot A \cdot y$  but  $6 \cdot B - 2 \cdot A = 0 \frac{1}{\text{m} \cdot \text{s}}$  hence flow is IRROTATIONAL

Hence  $u = \frac{\partial}{\partial x} \varphi$  so  $\varphi(x, y) = - \int u(x, y) dx + f(y) \rightarrow \varphi(x, y) = f(y) - \frac{A \cdot x^3}{3} + 3 \cdot B \cdot x \cdot y^2$

$v = \frac{\partial}{\partial y} \varphi$  so  $\varphi(x, y) = - \int v(x, y) dy + g(x) \rightarrow \varphi(x, y) = A \cdot x \cdot y^2 + g(x)$

Comparing, the simplest velocity potential is then  $\varphi(x, y) = A \cdot x \cdot y^2 - \frac{A \cdot x^3}{3}$

## Problem 6.105

[Difficulty: 2]

**6.105** A flow field is represented by the stream function  $\psi = x^5 - 10x^3y^2 + 5xy^4$ . Find the corresponding velocity field. Show that this flow field is irrotational and obtain the potential function.

**Given:** Stream function

**Find:** Velocity field; Show flow is irrotational; Velocity potential

**Solution:**

Basic equations: Incompressibility because  $\psi$  exists  $u = \frac{\partial}{\partial y}\psi$   $v = \frac{\partial}{\partial x}\psi$   $u = \frac{\partial}{\partial x}\varphi$   $v = \frac{\partial}{\partial y}\varphi$

Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

$$\psi(x, y) = x^5 - 10x^3y^2 + 5xy^4$$

$$u(x, y) = \frac{\partial}{\partial y}\psi(x, y) \quad u(x, y) = 20x^3y - 20x^3$$

$$v(x, y) = \frac{\partial}{\partial x}\psi(x, y) \quad v(x, y) = 30x^2y^2 - 5x^4 - 5y^4$$

$$\frac{\partial}{\partial x}v(x, y) - \frac{\partial}{\partial y}u(x, y) = 0$$

Hence flow is IRROTATIONAL

Hence  $u = \frac{\partial}{\partial x}\varphi$  so

$$\varphi(x, y) = -\int u(x, y) dx + f(y) = 5x^4y - 10x^2y^3 + f(y)$$

$v = \frac{\partial}{\partial y}\varphi$  so

$$\varphi(x, y) = -\int v(x, y) dy + g(x) = 5x^4y - 10x^2y^3 + y^5 + g(x)$$

Comparing, the simplest velocity potential is then

$$\varphi(x, y) = 5x^4y - 10x^2y^3 + y^5$$

## Problem 6.106

[Difficulty: 2]

**6.106** The stream function of a flow field is  $\psi = Ax^3 - Bxy^2$ , where  $A = 1 \text{ m}^{-1} \cdot \text{s}^{-1}$  and  $B = 3 \text{ m}^{-1} \cdot \text{s}^{-1}$ , and coordinates are measured in meters. Find an expression for the velocity potential.

**Given:** Stream function

**Find:** Velocity potential

**Solution:**

Basic equations: Incompressibility because  $\psi$  exists  $u = \frac{\partial}{\partial y} \psi$   $v = \frac{\partial}{\partial x} \psi$   $u = \frac{\partial}{\partial x} \varphi$   $v = \frac{\partial}{\partial y} \varphi$

Irrotationality  $\frac{\partial}{\partial x} v - \frac{\partial}{\partial y} u = 0$

We have  $\psi(x, y) = A \cdot x^3 - B \cdot x \cdot y^2$

Then  $u(x, y) = \frac{\partial}{\partial y} \psi(x, y)$   $u(x, y) = -2 \cdot B \cdot x \cdot y$

$v(x, y) = \frac{\partial}{\partial x} \psi(x, y)$   $v(x, y) = B \cdot y^2 - 3 \cdot A \cdot x^2$

Then  $\frac{\partial}{\partial x} v(x, y) - \frac{\partial}{\partial y} u(x, y) = 2 \cdot B \cdot x - 6 \cdot A \cdot x$  but  $2 \cdot B - 6 \cdot A = 0 \frac{1}{\text{m} \cdot \text{s}}$  hence flow is IRROTATIONAL

Hence  $u = \frac{\partial}{\partial x} \varphi$  so  $\varphi(x, y) = - \int u(x, y) dx + f(y) \rightarrow \varphi(x, y) = B \cdot y \cdot x^2 + f(y)$

$v = \frac{\partial}{\partial y} \varphi$  so  $\varphi(x, y) = - \int v(x, y) dy + g(x) \rightarrow \varphi(x, y) = g(x) - \frac{B \cdot y^3}{3} + 3 \cdot A \cdot x^2 \cdot y$

Comparing, the simplest velocity potential is then  $\varphi(x, y) = 3 \cdot A \cdot x^2 \cdot y - \frac{B \cdot y^3}{3}$

## Problem 6.107

[Difficulty: 2]

**6.107** The stream function of a flow field is  $\psi = Ax^3 + B(xy^2 + x^2 - y^2)$ , where  $\psi$ ,  $x$ ,  $y$ ,  $A$ , and  $B$  are all dimensionless. Find the relation between  $A$  and  $B$  for this to be an irrotational flow. Find the velocity potential.

**Given:** Stream function

**Find:** Find  $A$  vs  $B$  if flow is irrotational; Velocity potential

**Solution:**

Basic equations: Incompressibility because  $\psi$  exists  $u = \frac{\partial}{\partial y}\psi$   $v = \frac{\partial}{\partial x}\psi$   $u = \frac{\partial}{\partial x}\varphi$   $v = \frac{\partial}{\partial y}\varphi$

Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

We have  $\psi(x, y) = Ax^3 + B(x \cdot y^2 + x^2 - y^2)$

$$u(x, y) = \frac{\partial}{\partial y}\psi(x, y)$$

$$u(x, y) = -B \cdot (2 \cdot y - 2 \cdot x \cdot y)$$

$$v(x, y) = \frac{\partial}{\partial x}\psi(x, y)$$

$$v(x, y) = -3 \cdot A \cdot x^2 - B \cdot (y^2 + 2 \cdot x)$$

$$\frac{\partial}{\partial x}v(x, y) - \frac{\partial}{\partial y}u(x, y) = -2 \cdot x \cdot (3 \cdot A + B)$$

Hence flow is IRROTATIONAL if  $B = -3 \cdot A$

Hence

$$u = \frac{\partial}{\partial x}\varphi$$

so

$$\varphi(x, y) = - \int u(x, y) dx + f(y) = 2 \cdot B \cdot y \cdot x - B \cdot y \cdot x^2 + f(y)$$

$$v = \frac{\partial}{\partial y}\varphi$$

so

$$\varphi(x, y) = - \int v(x, y) dy + g(x) = 3 \cdot A \cdot x^2 \cdot y + 2 \cdot B \cdot x \cdot y + \frac{B \cdot y^3}{3} + g(x)$$

Comparing, the simplest velocity potential is then

$$\varphi(x, y) = 2 \cdot B \cdot y \cdot x - B \cdot y \cdot x^2 + B \cdot \frac{y^3}{3}$$

## Problem 6.108

[Difficulty: 2]

**6.108** A flow field is represented by the stream function  $\psi = x^5 - 15x^4y^2 + 15x^2y^4 - y^6$ . Find the corresponding velocity field. Show that this flow field is irrotational and obtain the potential function.

**Given:** Stream function

**Find:** Velocity field; Show flow is irrotational; Velocity potential

**Solution:**

Basic equations: Incompressibility because  $\psi$  exists  $u = \frac{\partial}{\partial y}\psi$   $v = \frac{\partial}{\partial x}\psi$   $u = \frac{\partial}{\partial x}\varphi$   $v = \frac{\partial}{\partial y}\varphi$

Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

We have  $\psi(x, y) = x^5 - 15x^4y^2 + 15x^2y^4 - y^6$

$$u(x, y) = \frac{\partial}{\partial y}\psi(x, y) \quad u(x, y) = 60x^2y^3 - 30x^4y - 6y^5$$

$$v(x, y) = \frac{\partial}{\partial x}\psi(x, y) \quad v(x, y) = 60x^3y^2 - 6x^5 - 30xy^4$$

$$\frac{\partial}{\partial x}v(x, y) - \frac{\partial}{\partial y}u(x, y) = 0 \quad \text{Hence flow is IRROTATIONAL}$$

$$\text{Hence } u = \frac{\partial}{\partial x}\varphi \quad \text{so} \quad \varphi(x, y) = - \int u(x, y) dx + f(y) = 6x^5y - 20x^3y^3 + 6xy^5 + f(y)$$

$$v = \frac{\partial}{\partial y}\varphi \quad \text{so} \quad \varphi(x, y) = - \int v(x, y) dy + g(x) = 6x^5y - 20x^3y^3 + 6xy^5 + g(x)$$

$$\text{Comparing, the simplest velocity potential is then } \varphi(x, y) = 6x^5y - 20x^3y^3 + 6xy^5$$

## Problem 6.109

[Difficulty: 2]

**6.109** Consider the flow field represented by the potential function  $\phi = Ax^2 + Bxy - Ay^2$ . Verify that this is an incompressible flow and determine the corresponding stream function.

**Given:** Velocity potential

**Find:** Show flow is incompressible; Stream function

**Solution:**

Basic equations: Irrotationality because  $\phi$  exists  $u = \frac{\partial}{\partial y}\psi$   $v = \frac{\partial}{\partial x}\psi$   $u = \frac{\partial}{\partial x}\phi$   $v = \frac{\partial}{\partial y}\phi$

Incompressibility  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$

We have  $\phi(x, y) = A \cdot x^2 + B \cdot x \cdot y - A \cdot y^2$

$$u(x, y) = \frac{\partial}{\partial x}\phi(x, y) \quad u(x, y) = -2 \cdot A \cdot x - B \cdot y$$

$$v(x, y) = \frac{\partial}{\partial y}\phi(x, y) \quad v(x, y) = 2 \cdot A \cdot y - B \cdot x$$

Hence  $\frac{\partial}{\partial x}u(x, y) + \frac{\partial}{\partial y}v(x, y) = 0$  Hence flow is INCOMPRESSIBLE

Hence  $u = \frac{\partial}{\partial y}\psi$  so  $\psi(x, y) = \int u(x, y) dy + f(x) = -2 \cdot A \cdot x \cdot y - \frac{1}{2} \cdot B \cdot y^2 + f(x)$

$v = \frac{\partial}{\partial x}\psi$  so  $\psi(x, y) = - \int v(x, y) dx + g(y) = -2 \cdot A \cdot x \cdot y + \frac{1}{2} \cdot B \cdot x^2 + g(y)$

Comparing, the simplest stream function is then  $\psi(x, y) = -2 \cdot A \cdot x \cdot y + \frac{1}{2} \cdot B \cdot x^2 - \frac{1}{2} \cdot B \cdot y^2$

## Problem 6.110

[Difficulty: 2]

**6.110** Consider the flow field presented by the potential function  $\phi = x^5 - 10x^3y^2 + 5xy^4 - x^2 + y^2$ . Verify that this is an incompressible flow, and obtain the corresponding stream function.

**Given:** Velocity potential

**Find:** Show flow is incompressible; Stream function

**Solution:**

Basic equations: Irrotationality because  $\phi$  exists  $u = \frac{\partial}{\partial y}\psi$   $v = \frac{\partial}{\partial x}\psi$   $u = \frac{\partial}{\partial x}\phi$   $v = \frac{\partial}{\partial y}\phi$

Incompressibility  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$

We have  $\phi(x, y) = x^5 - 10x^3y^2 + 5xy^4 - x^2 + y^2$

$$u(x, y) = \frac{\partial}{\partial x}\phi(x, y) \quad u(x, y) = 5x^4 - 30x^2y^2 + 5y^4 - 2x$$

$$v(x, y) = \frac{\partial}{\partial y}\phi(x, y) \quad v(x, y) = -20x^3y + 20xy^3 + 2y$$

Hence  $\frac{\partial}{\partial x}u(x, y) + \frac{\partial}{\partial y}v(x, y) = 0$

Hence flow is INCOMPRESSIBLE

Hence  $u = \frac{\partial}{\partial y}\psi$  so  $\psi(x, y) = \int u(x, y) dy + f(x) = 10x^2y^3 - 5x^4y + 2xy - y^5 + f(x)$

$v = \frac{\partial}{\partial x}\psi$  so  $\psi(x, y) = -\int v(x, y) dx + g(y) = 10x^2y^3 - 5x^4y + 2xy + g(y)$

Comparing, the simplest stream function is then

$$\psi(x, y) = 10x^2y^3 - 5x^4y + 2xy - y^5$$

## Problem 6.111

[Difficulty: 2]

**6.111** Consider the flow field presented by the potential function  $\phi = x^6 - 15x^4y^2 + 15x^2y^4 - y^6$ . Verify that this is an incompressible flow and obtain the corresponding stream function.

**Given:** Velocity potential

**Find:** Show flow is incompressible; Stream function

**Solution:**

Basic equations: Irrotationality because  $\phi$  exists  $u = \frac{\partial}{\partial y} \psi$   $v = \frac{\partial}{\partial x} \psi$   $u = \frac{\partial}{\partial x} \phi$   $v = \frac{\partial}{\partial y} \phi$

Incompressibility  $\frac{\partial}{\partial x} u + \frac{\partial}{\partial y} v = 0$

$$\phi(x, y) = x^6 - 15x^4y^2 + 15x^2y^4 - y^6$$

$$u(x, y) = \frac{\partial}{\partial x} \phi(x, y) \quad u(x, y) = 60x^3y^2 - 6x^5 - 30xy^4$$

$$v(x, y) = \frac{\partial}{\partial y} \phi(x, y) \quad v(x, y) = 30x^4y - 60x^2y^3 + 6y^5$$

Hence  $\frac{\partial}{\partial x} u(x, y) + \frac{\partial}{\partial y} v(x, y) = 0$

Hence flow is INCOMPRESSIBLE

Hence  $u = \frac{\partial}{\partial y} \psi$  so  $\psi(x, y) = \int u(x, y) dy + f(x) = 20x^3y^3 - 6x^5y - 6xy^5 + f(x)$

$v = \frac{\partial}{\partial x} \psi$  so  $\psi(x, y) = - \int v(x, y) dx + g(y) = 20x^3y^3 - 6x^5y - 6xy^5 + g(y)$

Comparing, the simplest stream function is then

$$\psi(x, y) = 20x^3y^3 - 6x^5y - 6xy^5$$

## Problem 6.112

[Difficulty: 4]

**6.112** Show by expanding and collecting real and imaginary terms that  $f = z^6$  (where  $z$  is the complex number  $z = x + iy$ ) leads to a valid velocity potential (the real part of  $f$ ) and a corresponding stream function (the negative of the imaginary part of  $f$ ) of an irrotational and incompressible flow. Then show that the real and imaginary parts of  $df/dz$  yield  $-u$  and  $v$ , respectively.

**Given:** Complex function

**Find:** Show it leads to velocity potential and stream function of irrotational incompressible flow; Show that  $df/dz$  leads to  $u$  and  $v$

**Solution:**

Basic equations: Irrotationality because  $\phi$  exists  $u = \frac{\partial}{\partial y}\psi$   $v = \frac{\partial}{\partial x}\psi$   $u = \frac{\partial}{\partial x}\phi$   $v = \frac{\partial}{\partial y}\phi$

Incompressibility  $\frac{\partial}{\partial x}u + \frac{\partial}{\partial y}v = 0$  Irrotationality  $\frac{\partial}{\partial x}v - \frac{\partial}{\partial y}u = 0$

$f(z) = z^6 = (x + iy)^6$  Expanding  $f(z) = x^6 - 15x^4 \cdot y^2 + 15x^2 \cdot y^4 - y^6 + i(6x \cdot y^5 + 6x^5 \cdot y - 20x^3 \cdot y^3)$

We are thus to check the following

$\phi(x, y) = x^6 - 15x^4 \cdot y^2 + 15x^2 \cdot y^4 - y^6$   $\psi(x, y) = -(6x \cdot y^5 + 6x^5 \cdot y - 20x^3 \cdot y^3)$

$u(x, y) = \frac{\partial}{\partial x}\phi(x, y)$  so  $u(x, y) = 60x^3 \cdot y^2 - 6x^5 - 30x \cdot y^4$

$v(x, y) = \frac{\partial}{\partial y}\phi(x, y)$  so  $v(x, y) = 30x^4 \cdot y - 60x^2 \cdot y^3 + 6y^5$

An alternative derivation of  $u$  and  $v$  is

$u(x, y) = \frac{\partial}{\partial x}\psi(x, y)$   $u(x, y) = 60x^3 \cdot y^2 - 6x^5 - 30x \cdot y^4$

$v(x, y) = \frac{\partial}{\partial x}\psi(x, y)$   $v(x, y) = 30x^4 \cdot y - 60x^2 \cdot y^3 + 6y^5$

Hence  $\frac{\partial}{\partial x}v(x, y) - \frac{\partial}{\partial y}u(x, y) = 0$  Hence flow is IRROTATIONAL

Hence  $\frac{\partial}{\partial x}u(x, y) + \frac{\partial}{\partial y}v(x, y) = 0$  Hence flow is INCOMPRESSIBLE

Next we find  $\frac{df}{dz} = \frac{d(z^6)}{dz} = 6z^5 = 6(x + iy)^5 = (6x^5 - 60x^3 \cdot y^2 + 30x \cdot y^4) + i(30x^4 \cdot y + 6y^5 - 60x^2 \cdot y^3)$

Hence we see  $\frac{df}{dz} = -u + i \cdot v$  Hence the results are verified;  $u = -\text{Re}\left(\frac{df}{dz}\right)$  and  $v = \text{Im}\left(\frac{df}{dz}\right)$

These interesting results are explained in Problem 6.113!

## Problem 6.113

[Difficulty: 4]

**6.113** Show that *any* differentiable function  $f(z)$  of the complex number  $z = x + iy$  leads to a valid potential (the real part of  $f$ ) and a corresponding stream function (the negative of the imaginary part of  $f$ ) of an incompressible, irrotational flow. To do so, prove using the chain rule that  $f(z)$  automatically satisfies the Laplace equation. Then show that  $df/dz = -u + iv$ .

**Given:** Complex function

**Find:** Show it leads to velocity potential and stream function of irrotational incompressible flow; Show that  $df/dz$  leads to  $u$  and  $v$

**Solution:**

Basic equations:  $u = \frac{\partial}{\partial y}\psi$        $v = \frac{\partial}{\partial x}\psi$        $u = \frac{\partial}{\partial x}\varphi$        $v = \frac{\partial}{\partial y}\varphi$

First consider  $\frac{\partial}{\partial x}f = \frac{\partial}{\partial z} \cdot \frac{d}{dz}f = 1 \cdot \frac{d}{dz}f = \frac{d}{dz}f$       (1)      and also  $\frac{\partial}{\partial y}f = \frac{\partial}{\partial z} \cdot \frac{d}{dz}f = i \cdot \frac{d}{dz}f = i \cdot \frac{d}{dz}f$       (2)

Hence  $\frac{\partial^2}{\partial x^2}f = \frac{\partial}{\partial x}\left(\frac{\partial}{\partial x}f\right) = \frac{d}{dz}\left(\frac{d}{dz}f\right) = \frac{d^2}{dz^2}f$       and       $\frac{\partial^2}{\partial y^2}f = \frac{\partial}{\partial y}\left(\frac{\partial}{\partial y}f\right) = i \cdot \frac{d}{dz}\left(i \cdot \frac{d}{dz}f\right) = -\frac{d^2}{dz^2}f$

Combining  $\frac{\partial^2}{\partial x^2}f + \frac{\partial^2}{\partial y^2}f = \frac{d^2}{dz^2}f - \frac{d^2}{dz^2}f = 0$       Any differentiable function  $f(z)$  automatically satisfies the Laplace Equation; so do its real and imaginary parts!

We demonstrate derivation of velocities  $u$  and  $v$

From Eq 1  $\frac{d}{dz}f = \frac{\partial}{\partial x}f = \frac{\partial}{\partial x}(\varphi - i\psi) = \frac{\partial}{\partial x}\varphi - i \cdot \frac{\partial}{\partial x}\psi = -u + i \cdot v$

From Eq 2  $\frac{d}{dz}f = \frac{1}{i} \cdot \frac{\partial}{\partial y}f = \frac{1}{i} \cdot \frac{\partial}{\partial y}(\varphi - i\psi) = -i \cdot \frac{\partial}{\partial y}\varphi - \frac{\partial}{\partial y}\psi = i \cdot v - u$

Hence we have demonstrated that  $\frac{df}{dz} = -u + i \cdot v$

6.114 Consider the flow field represented by the velocity potential  $\phi = Ax + Bx^2 - By^2$ , where  $A = 1 \text{ m} \cdot \text{s}^{-1}$ ,  $B = 1 \text{ m}^{-1} \cdot \text{s}^{-1}$ , and the coordinates are measured in meters. Obtain expressions for the velocity field and the stream function. Calculate the pressure difference between the origin and point  $(x, y) = (1, 2)$ .

Solution

The velocity field is determined from the velocity potential

$$\left. \begin{aligned} u &= -\frac{\partial \phi}{\partial x} = -A - 2Bx \\ v &= -\frac{\partial \phi}{\partial y} = 2By \end{aligned} \right\} \vec{V} = -(A + 2Bx)\hat{i} + 2By\hat{j}$$

From the definition of the stream function,  $u = \frac{\partial \psi}{\partial y}$  &  $v = -\frac{\partial \psi}{\partial x}$

Then

$$\begin{aligned} \psi &= \int u \, dy + f(x) = \int -(A + 2Bx) \, dy + f(x) \\ \psi &= -Ay - 2Bxy + f(x) \end{aligned}$$

Also,

$$\begin{aligned} \psi &= \int -v \, dx + g(y) = \int -2By \, dx + g(y) \\ \psi &= -2Bxy + g(y) \end{aligned}$$

Comparing the two expressions for  $\psi$  we conclude

$$f(x) = 0, \quad g(y) = -Ay$$

$$\therefore \psi = -(Ay + 2Bxy)$$

Since  $\nabla^2 \phi = 2B - 2B = 0$ , the flow is irrotational and the Bernoulli equation can be applied between any two points in the flow field

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2 \quad \left\{ \begin{array}{l} \text{Assume: } p = \text{constant} \\ z_1 = z_2 \end{array} \right.$$

$$\vec{V}(0,0) = -A\hat{i} = -\hat{i} \text{ m/s} \quad V_{0,0} = 1 \text{ m/s}$$

$$\vec{V}(1,2) = -(A+2B)\hat{i} + 4B\hat{j} = -3\hat{i} + 4\hat{j} \text{ m/s} \quad \therefore V_{1,2} = 5 \text{ m/s}$$

$$\therefore p_1 - p_2 = \rho \left( \frac{V_2^2}{2} - \frac{V_1^2}{2} \right) = \frac{\rho}{2} (V_2^2 - V_1^2)$$

Assume fluid is water

$$p_1 - p_2 = \frac{1}{2} \times 999 \frac{\text{kg}}{\text{m}^3} (25 - 1) \frac{\text{m}^2}{\text{s}^2} = 12 \text{ kN/m}^2$$

42 SHEETS 3 SQUARE  
43 SHEETS 3 SQUARE  
200 SHEETS 3 SQUARE





## Problem 6.115

[Difficulty: 2] Part 2/2



Using *Excel*, the stream function and velocity potential can be plotted.  
The data below was obtained using the workbook for Example Problem 6.10.  
Note the orthogonality of  $\psi$  and  $\phi$ !

#NAME? Stream Function



#NAME? Velocity Potential

Note that the plot is  
from  $x = -5$  to  $5$  and  $y = -5$  to  $5$



## Problem 6.116

[Difficulty: 3]

**6.116** An incompressible flow field is characterized by the stream function  $\psi = 3Ax^2y - Ay^3$ , where  $A = 1 \text{ m}^{-1} \cdot \text{s}^{-1}$ . Show that this flow field is irrotational. Derive the velocity potential for the flow. Plot the streamlines and potential lines, and visually verify that they are orthogonal. (*Hint: Use the Excel workbook of Example 6.10.*)

Solution:

For a 2-D incompressible, irrotational flow  $\nabla^2 \psi = 0$  (6.30)

For the flow field:

$$\nabla^2 \psi = \frac{\partial^2}{\partial x^2} (3Ax^2y - Ay^3) + \frac{\partial^2}{\partial y^2} (3Ax^2y - Ay^3) = 6Ay - 6Ay = 0 \quad \leftarrow \text{irrotational}$$

The velocity field is given by  $\mathbf{V} = u\mathbf{i} + v\mathbf{j}$

$$u = \frac{\partial \psi}{\partial y} = 3Ax^2 - 3Ay^2 = 3A(x^2 - y^2) \quad \left. \begin{aligned} & \\ & \end{aligned} \right\} \mathbf{V} = 3A(x^2 - y^2)\mathbf{i} - 6Axy\mathbf{j}$$

$$v = -\frac{\partial \psi}{\partial x} = -6Axy$$


The velocity potential is defined such that  $u = \frac{\partial \phi}{\partial x}$  and  $v = \frac{\partial \phi}{\partial y}$

$$\text{Then, } \phi = -\int u dx + f(y) = -\int 3A(x^2 - y^2) dx + f(y) = -Ax^3 + 3Axy^2 + f(y) \quad (1)$$

$$\text{Also, } \phi = -\int v dy + g(x) = \int 6Axy dy + g(x) = 3Axy^2 + g(x) \quad (2)$$

Equating expressions for  $\phi$  (Eqs 1 and 2) we see that

$$g(x) = -Ax^3 \text{ and } f(y) = 0 \quad \therefore \phi = 3Axy^2 - Ax^3 \quad \leftarrow \phi$$



## Problem 6.117

[Difficulty: 3]

**6.117** A certain irrotational flow field in the  $xy$  plane has the stream function  $\psi = Bxy$ , where  $B = 0.25 \text{ s}^{-1}$ , and the coordinates are measured in meters. Determine the rate of flow between points  $(x, y) = (2, 2)$  and  $(3, 3)$ . Find the velocity potential for this flow. Plot the streamlines and potential lines, and visually verify that they are orthogonal. (Hint: Use the Excel workbook of Example 6.10.)

Solution:

The volume flow rate (per unit depth) between points ① and ② is given by

$$Q_{12} = \psi_2 - \psi_1 = B[x_2 y_2 - x_1 y_1] = 0.25 \text{ s}^{-1} [3 \times 3 - 2 \times 2]$$

$$Q_{12} = 1.25 \text{ m}^3/\text{s/m} \quad \leftarrow \quad Q_{12}$$

The velocity field is determined from the stream function

$$u = \partial \psi / \partial y = Bx \quad v = -\partial \psi / \partial x = -By \quad \therefore \vec{v} = Bx\hat{i} - By\hat{j}$$


For irrotational flow  $\vec{v} = -\nabla \phi$  and  $u = -\partial \phi / \partial x$ ,  $v = -\partial \phi / \partial y$

and  $\phi = -\int u dx + f(y) = -\int Bx dx + f(y) = -\frac{B}{2}x^2 + f(y) \dots (1)$

Also  $\phi = -\int v dy + g(x) = -\int -By dy + g(x) = \frac{By^2}{2} + g(x) \dots (2)$

Equating expressions for  $\phi$  (Eqs 1 and 2) we conclude that

$$f(y) = \frac{By^2}{2}, \quad g(x) = -\frac{B}{2}x^2 \quad \text{and} \quad \phi = \frac{B}{2}(y^2 - x^2)$$



**6.118** The velocity distribution in a two-dimensional, steady, inviscid flow field in the  $xy$  plane is  $\vec{V} = (Ax + B)\hat{i} + (C - Ay)\hat{j}$ , where  $A = 3 \text{ s}^{-1}$ ,  $B = 6 \text{ m/s}$ ,  $C = 4 \text{ m/s}$ , and the coordinates are measured in meters. The body force distribution is  $\vec{B} = -g\hat{k}$  and the density is  $825 \text{ kg/m}^3$ . Does this represent a possible incompressible flow field? Plot a few streamlines in the upper half plane. Find the stagnation point(s) of the flow field. Is the flow irrotational? If so, obtain the potential function. Evaluate the pressure difference between the origin and point  $(x, y, z) = (2, 2, 2)$ .

Solution:

For incompressible flow  $\nabla \cdot \vec{V} = 0$ . For this flow

$$\nabla \cdot \vec{V} = \frac{\partial}{\partial x} (Ax + B) + \frac{\partial}{\partial y} (C - Ay) = A - A = 0$$

$\therefore$  velocity field represents possible incompressible flow.

At the stagnation point  $u = v = 0$ . ( $\vec{V} = 0$ )

$$u = 0 = (Ax + B) \quad \therefore x = -\frac{B}{A} = -\frac{6 \text{ m/s}}{3 \text{ s}^{-1}} = -2 \text{ m}$$

$$v = 0 = (C - Ay) \quad \therefore y = \frac{C}{A} = \frac{4 \text{ m/s}}{3 \text{ s}^{-1}} = \frac{4}{3} \text{ m}$$

Stagnation point is at  $(x, y) = (-2, \frac{4}{3}) \text{ m}$ .

The fluid rotation (for a 2-D flow) is given by  $\omega_z = \frac{1}{2} \left( \frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right)$

For this flow 
$$\omega_z = \frac{1}{2} \left[ \frac{\partial}{\partial x} (C - Ay) - \frac{\partial}{\partial y} (Ax + B) \right] = 0$$

$\therefore$  flow is irrotational.

Then,  $\vec{V} = -\nabla \phi$  and  $u = -\frac{\partial \phi}{\partial x}$  and  $v = -\frac{\partial \phi}{\partial y}$ .

and 
$$\phi = -\int u dx + f(y) = -\int (Ax + B) dx + f(y) = -A\frac{x^2}{2} - Bx + f(y) \quad (1)$$

Also 
$$\phi = -\int v dy + g(x) = -\int (C - Ay) dy + g(x) = A\frac{y^2}{2} - Cy + g(x) \quad (2)$$

Equating the two expressions for  $\phi$  (Eqs 1 and 2) we note that

$$g(x) = -\left( A\frac{x^2}{2} + Bx \right) \quad \text{and} \quad f(y) = A\frac{y^2}{2} - Cy$$

$$\therefore \phi = \frac{A}{2} (y^2 - x^2) - Bx - Cy \quad \leftarrow \phi$$

Since the flow is irrotational we can apply the Bernoulli equation between any two points in the flow field.

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g z_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g z_2$$

At point 1,  $(0, 0, 0)$ ,  $\vec{V} = B\hat{i} + C\hat{j} = 6\hat{i} + 4\hat{j} \text{ m/s}$ ,  $V_1^2 = 52 \text{ m}^2/\text{s}^2$


42-383 42-384 42-385 42-386 42-387 42-388 42-389 42-390 42-391 42-392 42-393 42-394 42-395 42-396 42-397 42-398 42-399 42-400 42-401 42-402 42-403 42-404 42-405 42-406 42-407 42-408 42-409 42-410 42-411 42-412 42-413 42-414 42-415 42-416 42-417 42-418 42-419 42-420 42-421 42-422 42-423 42-424 42-425 42-426 42-427 42-428 42-429 42-430 42-431 42-432 42-433 42-434 42-435 42-436 42-437 42-438 42-439 42-440 42-441 42-442 42-443 42-444 42-445 42-446 42-447 42-448 42-449 42-450 42-451 42-452 42-453 42-454 42-455 42-456 42-457 42-458 42-459 42-460 42-461 42-462 42-463 42-464 42-465 42-466 42-467 42-468 42-469 42-470 42-471 42-472 42-473 42-474 42-475 42-476 42-477 42-478 42-479 42-480 42-481 42-482 42-483 42-484 42-485 42-486 42-487 42-488 42-489 42-490 42-491 42-492 42-493 42-494 42-495 42-496 42-497 42-498 42-499 42-500 42-501 42-502 42-503 42-504 42-505 42-506 42-507 42-508 42-509 42-510 42-511 42-512 42-513 42-514 42-515 42-516 42-517 42-518 42-519 42-520 42-521 42-522 42-523 42-524 42-525 42-526 42-527 42-528 42-529 42-530 42-531 42-532 42-533 42-534 42-535 42-536 42-537 42-538 42-539 42-540 42-541 42-542 42-543 42-544 42-545 42-546 42-547 42-548 42-549 42-550 42-551 42-552 42-553 42-554 42-555 42-556 42-557 42-558 42-559 42-560 42-561 42-562 42-563 42-564 42-565 42-566 42-567 42-568 42-569 42-570 42-571 42-572 42-573 42-574 42-575 42-576 42-577 42-578 42-579 42-580 42-581 42-582 42-583 42-584 42-585 42-586 42-587 42-588 42-589 42-590 42-591 42-592 42-593 42-594 42-595 42-596 42-597 42-598 42-599 42-600 42-601 42-602 42-603 42-604 42-605 42-606 42-607 42-608 42-609 42-610 42-611 42-612 42-613 42-614 42-615 42-616 42-617 42-618 42-619 42-620 42-621 42-622 42-623 42-624 42-625 42-626 42-627 42-628 42-629 42-630 42-631 42-632 42-633 42-634 42-635 42-636 42-637 42-638 42-639 42-640 42-641 42-642 42-643 42-644 42-645 42-646 42-647 42-648 42-649 42-650 42-651 42-652 42-653 42-654 42-655 42-656 42-657 42-658 42-659 42-660 42-661 42-662 42-663 42-664 42-665 42-666 42-667 42-668 42-669 42-670 42-671 42-672 42-673 42-674 42-675 42-676 42-677 42-678 42-679 42-680 42-681 42-682 42-683 42-684 42-685 42-686 42-687 42-688 42-689 42-690 42-691 42-692 42-693 42-694 42-695 42-696 42-697 42-698 42-699 42-700 42-701 42-702 42-703 42-704 42-705 42-706 42-707 42-708 42-709 42-710 42-711 42-712 42-713 42-714 42-715 42-716 42-717 42-718 42-719 42-720 42-721 42-722 42-723 42-724 42-725 42-726 42-727 42-728 42-729 42-730 42-731 42-732 42-733 42-734 42-735 42-736 42-737 42-738 42-739 42-740 42-741 42-742 42-743 42-744 42-745 42-746 42-747 42-748 42-749 42-750 42-751 42-752 42-753 42-754 42-755 42-756 42-757 42-758 42-759 42-760 42-761 42-762 42-763 42-764 42-765 42-766 42-767 42-768 42-769 42-770 42-771 42-772 42-773 42-774 42-775 42-776 42-777 42-778 42-779 42-780 42-781 42-782 42-783 42-784 42-785 42-786 42-787 42-788 42-789 42-790 42-791 42-792 42-793 42-794 42-795 42-796 42-797 42-798 42-799 42-800 42-801 42-802 42-803 42-804 42-805 42-806 42-807 42-808 42-809 42-810 42-811 42-812 42-813 42-814 42-815 42-816 42-817 42-818 42-819 42-820 42-821 42-822 42-823 42-824 42-825 42-826 42-827 42-828 42-829 42-830 42-831 42-832 42-833 42-834 42-835 42-836 42-837 42-838 42-839 42-840 42-841 42-842 42-843 42-844 42-845 42-846 42-847 42-848 42-849 42-850 42-851 42-852 42-853 42-854 42-855 42-856 42-857 42-858 42-859 42-860 42-861 42-862 42-863 42-864 42-865 42-866 42-867 42-868 42-869 42-870 42-871 42-872 42-873 42-874 42-875 42-876 42-877 42-878 42-879 42-880 42-881 42-882 42-883 42-884 42-885 42-886 42-887 42-888 42-889 42-890 42-891 42-892 42-893 42-894 42-895 42-896 42-897 42-898 42-899 42-900 42-901 42-902 42-903 42-904 42-905 42-906 42-907 42-908 42-909 42-910 42-911 42-912 42-913 42-914 42-915 42-916 42-917 42-918 42-919 42-920 42-921 42-922 42-923 42-924 42-925 42-926 42-927 42-928 42-929 42-930 42-931 42-932 42-933 42-934 42-935 42-936 42-937 42-938 42-939 42-940 42-941 42-942 42-943 42-944 42-945 42-946 42-947 42-948 42-949 42-950 42-951 42-952 42-953 42-954 42-955 42-956 42-957 42-958 42-959 42-960 42-961 42-962 42-963 42-964 42-965 42-966 42-967 42-968 42-969 42-970 42-971 42-972 42-973 42-974 42-975 42-976 42-977 42-978 42-979 42-980 42-981 42-982 42-983 42-984 42-985 42-986 42-987 42-988 42-989 42-990 42-991 42-992 42-993 42-994 42-995 42-996 42-997 42-998 42-999 43-000



At point  $a (2,2,2)$   $\vec{V}_1 = [3s^1 + 2m + 6n]i + [4n]j - 3s^1 + 2m]k$   
 $\vec{V}_2 = 12i - 2j \text{ m/s}$        $V_2^2 = 148 \text{ m}^2/\text{s}^2$   
 $\phi_1 - \phi_2 = \frac{\rho}{2} (V_2^2 - V_1^2) + \rho g (z_2 - z_1) = \rho \left[ \frac{(V_2^2 - V_1^2)}{2} + g(z_2 - z_1) \right]$   
 $= 825 \frac{\text{kg}}{\text{m}^3} \times \left[ \frac{1}{2} \times (148 - 52) \frac{\text{m}^2}{\text{s}^2} + 9.81 \frac{\text{m}}{\text{s}^2} \times (2\text{m}) \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$   
 $\phi_1 - \phi_2 = 55.8 \text{ kPa}$  AP

The stream function is defined such that  $u = \frac{\partial \psi}{\partial y}$ ,  $v = -\frac{\partial \psi}{\partial x}$   
 For,  $\psi = \int u dy + f(x) = \int (Ax + B) dy + f(x) = Axy + By + f(x) \dots (1)$   
 Also,  $\psi = -\int v dx + g(y) = \int (-C + Ay) dx + g(y) = -Cx + Axy + g(y) \dots (2)$   
 Equating the two expressions for  $\psi$  (Eqs 1 and 2) we note that  
 $f(x) = -Cx$ ,  $g(y) = By$  and  $\therefore \psi = Axy + By - Cx$   $\psi$

The stagnation streamline goes through the stagnation point  $(-2, \frac{4}{3})$   
 $\psi_{\text{stag}} = 3s^1 \times (-2m) \times \frac{4}{3} + 6n \cdot s^1 \times \frac{4}{3} - 4n \cdot s^1 \times (-2m) = 8 \text{ m}^2/\text{s}$   $\psi_{\text{stag}}$



## Problem 6.119

[Difficulty: 3]

---

**6.119** Consider flow around a circular cylinder with freestream velocity from right to left and a counterclockwise free vortex. Show that the lift force on the cylinder can be expressed as  $F_L = -\rho U\Gamma$ , as illustrated in Example 6.12.

---

**Open-Ended Problem Statement:** Consider flow around a circular cylinder with freestream velocity from right to left and a counterclockwise free vortex. Show that the lift force on the cylinder can be expressed as  $F_L = -\rho U\Gamma$ , as illustrated in Example 6.12.

**Discussion:** The only change in this flow from the flow of Example 6.12 is that the directions of the freestream velocity and the vortex are changed. This changes the sign of the freestream velocity from  $U$  to  $-U$  and the sign of the vortex strength from  $K$  to  $-K$ . Consequently the signs of both terms in the equation for lift are changed. Therefore the direction of the lift force remains unchanged.

The analysis of Example 6.12 shows that only the term involving the vortex strength contributes to the lift force. Therefore the expression for lift obtained with the changed freestream velocity and vortex strength is identical to that derived in Example 6.12. Thus the general solution of Example 6.12 holds for any orientation of the freestream and vortex velocities. For the present case,  $F_L = -\rho U\Gamma$ , as shown for the general case in Example 6.12.

6.120 Consider the flow past a circular cylinder, of radius  $a$ , used in Example 6.11. Show that  $V_r = 0$  along the lines  $(r, \theta) = (r, \pm\pi/2)$ . Plot  $V_\theta/U$  versus radius for  $r \geq a$ , along the line  $(r, \theta) = (r, \pi/2)$ . Find the distance beyond which the influence of the cylinder is less than 1 percent of  $U$ .

Solution

From Example Problem 6.11


$$\vec{V} = \left( -\frac{U \cos\theta}{r^2} + U \cos\theta \right) \hat{e}_r + \left( -\frac{U \sin\theta}{r^2} - U \sin\theta \right) \hat{e}_\theta \quad \dots (1)$$

For  $V_r = \left( -\frac{U}{r^2} + U \right) \cos\theta$  For  $\theta = \pm \frac{\pi}{2}$ ,  $\cos\theta = 0$  and  $V_r = 0$

$V_\theta = -\left( \frac{U}{r^2} + U \right) \sin\theta$ , but  $\frac{U}{r^2} = a^2$

$\therefore V_\theta = -\left( \frac{U}{r^2} + U \right) \sin\theta$  For  $\theta = \frac{\pi}{2}$ .

$$\frac{V_\theta}{U} = -\left( 1 + \frac{a^2}{r^2} \right)$$



$$\vec{V} = U \cos\theta \left( 1 - \frac{a^2}{r^2} \right) \hat{e}_r - U \sin\theta \left( 1 + \frac{a^2}{r^2} \right) \hat{e}_\theta$$

For  $\theta = \pi/2$

$$\frac{V_\theta}{U} = 1 + \frac{a^2}{r^2}$$

If  $\frac{V_\theta}{U} = 1.01$  then  $\frac{a^2}{r^2} = 0.01$  or  $\frac{a}{r} = 0.1$

$\therefore \frac{V_\theta}{U} < 1.01$  for  $r > 10a$

### Problem 6.121

[Difficulty: 3]

**6.121** A crude model of a tornado is formed by combining a sink, of strength  $q = 2800 \text{ m}^2/\text{s}$ , and a free vortex, of strength  $K = 5600 \text{ m}^2/\text{s}$ . Obtain the stream function and velocity potential for this flow field. Estimate the radius beyond which the flow may be treated as incompressible. Find the gage pressure at that radius.

Solution:

$$\psi = \psi_{\text{sink}} + \psi_{\text{vortex}} = -\frac{q\theta}{2\pi} - \frac{K}{2\pi} \ln r$$

$$\phi = \phi_{\text{sink}} + \phi_{\text{vortex}} = \frac{q}{2\pi} \ln r - \frac{K}{2\pi} \theta$$

$$\vec{V} = V_r \hat{e}_r + V_\theta \hat{e}_\theta$$

$$V_r = -\frac{q}{2\pi r}, \quad V_\theta = 0; \quad V_{r0} = 0, \quad V_{\theta0} = \frac{K}{2\pi r}$$

$$\therefore \vec{V} = -\frac{q}{2\pi r} \hat{e}_r + \frac{K}{2\pi r} \hat{e}_\theta$$

$$V = (V_r^2 + V_\theta^2)^{1/2} = \left[ \left(\frac{q}{2\pi r}\right)^2 + \left(\frac{K}{2\pi r}\right)^2 \right]^{1/2} \frac{1}{r}$$

For incompressible flow  $M \leq 0.3$ . For standard air this corresponds to  $V \leq 102 \text{ m/sec}$

Then, for incompressible flow

$$V = 102 \text{ m/sec} < \left[ \frac{q^2 + K^2}{2\pi^2} \right]^{1/2} \frac{1}{r}$$

$$r > \left[ \frac{q^2 + K^2}{2\pi^2} \right]^{1/2} \frac{1}{102 \text{ m}} = \left[ \frac{(2800)^2 + (5600)^2}{2\pi^2} \right]^{1/2} \frac{1}{102 \text{ m}}$$

$$r > 9.77 \text{ m}$$

To determine the gage pressure at this radius, apply the Bernoulli equation for irrotational flow

$$\frac{p}{\rho} + \frac{V^2}{2} + gz = \frac{p}{\rho} + \frac{V^2}{2} + gz \quad \text{assume } gz = 0$$

Then


$$p_{\text{gage}} = p - p_0 = -\frac{1}{2} \rho V^2 = -\frac{1}{2} \cdot 1.225 \frac{\text{kg}}{\text{m}^3} \cdot (102)^2 \frac{\text{m}^2}{\text{s}^2} = -6.37 \frac{\text{N}}{\text{m}^2}$$

$$p_{\text{gage}} = -6.37 \text{ kPa (for standard air)}$$

$p_{\text{gage}}$

**6.122** A source and a sink with strengths of equal magnitude,  $q = 3\pi \text{ m}^2/\text{s}$ , are placed on the  $x$  axis at  $x = -a$  and  $x = a$ , respectively. A uniform flow, with speed  $U = 20 \text{ m/s}$ , in the positive  $x$  direction, is added to obtain the flow past a Rankine body. Obtain the stream function, velocity potential, and velocity field for the combined flow. Find the value of  $\psi = \text{constant}$  on the stagnation streamline. Locate the stagnation points if  $a = 0.3 \text{ m}$ .

Solution:



$$\psi = \psi_{\text{source}} + \psi_{\text{sink}} + \psi_{\text{unif}} = \frac{q\theta}{2\pi} - \frac{q\theta}{2\pi} + Uy$$

$$v = \frac{q}{2\pi} (\theta_1 - \theta_2) + U r \sin\theta$$

$$\phi = \phi_{\text{source}} + \phi_{\text{sink}} + \phi_{\text{unif}} = -\frac{q}{2\pi} \ln r_1 + \frac{q}{2\pi} \ln r_2 - Ux$$

$$\phi = \frac{q}{2\pi} \ln \frac{r_2}{r_1} - U r \cos\theta$$

$$u = u_{\text{source}} + u_{\text{sink}} + u_{\text{unif}} = \frac{q}{2\pi r_1} \cos\theta_1 - \frac{q}{2\pi r_2} \cos\theta_2 + U$$

$$v = v_{\text{source}} + v_{\text{sink}} + v_{\text{unif}} = \frac{q}{2\pi r_1} \sin\theta_1 - \frac{q}{2\pi r_2} \sin\theta_2$$

$$\vec{V} = u\hat{i} + v\hat{j} = \left\{ \frac{q}{2\pi} \left( \frac{\cos\theta_1}{r_1} - \frac{\cos\theta_2}{r_2} \right) + U \right\} \hat{i} + \frac{q}{2\pi} \left( \frac{\sin\theta_1}{r_1} - \frac{\sin\theta_2}{r_2} \right) \hat{j}$$

At stagnation point  $\vec{V} = 0$

$$y = 0 \quad \theta_1 = \theta_2 = 0$$

$$r_2 = r_s - a, \quad r_1 = r_s + a$$

$$\therefore u = 0 = \frac{q}{2\pi} \left( \frac{1}{r_s + a} - \frac{1}{r_s - a} \right) + U = \frac{q}{2\pi} \left[ \frac{(r_s - a) - (r_s + a)}{(r_s^2 - a^2)} \right] + U$$

$$0 = -\frac{qa}{\pi(r_s^2 - a^2)} + U \quad \text{or} \quad (r_s^2 - a^2) = \frac{qa}{\pi U}$$

$$r_s = \left( a^2 + \frac{qa}{\pi U} \right)^{1/2} = a \left( 1 + \frac{q}{\pi U a} \right)^{1/2}$$

For  $a = 0.3 \text{ m}$

$$r = 0.3 \text{ m} \left[ 1 + \frac{3\pi}{1} \frac{12^2}{5} \cdot \frac{1}{20 \text{ m}} + \frac{1}{0.3 \text{ m}} \right]^{1/2} = 0.367 \text{ m}$$

Stagnation points located at  $\theta = 0, \pi \quad r = 0.367 \text{ m}$

Since  $\psi = \frac{q}{2\pi} (\theta_1 - \theta_2) + Uy$  and  $\theta_1 = \theta_2 = y = 0$  at stagnation

$$\psi_{\text{stag}} = 0$$

### Problem 6.123


[Difficulty: 3]

6.123 Consider again the flow past a Rankine body of Problem 6.122. The half-width,  $h$ , of the body in the  $y$  direction is given by the transcendental equation

$$\frac{h}{a} = \cot\left(\frac{\pi U h}{q}\right)$$

Evaluate the half-width,  $h$ . Find the local velocity and the pressure at points  $(x, y) = (0, \pm h)$ . Assume the fluid density is that of standard air.

Solution:



$$\psi = \psi_{\text{circ}} + \psi_s + \psi_w = \frac{q}{2\pi} (\theta_1 - \theta_2) + U r \sin \theta$$

At stagnation point  $\theta_1 = \theta_2$  and  $\theta = 0, \pi$ .

$\therefore U_{\text{stag}} = 0$  and equation of stag. streamline is

$$\theta = \frac{q}{2\pi} (\theta_1 - \theta_2) + U r \sin \theta$$

$$\text{or } r = \frac{q}{2\pi U} \frac{(\theta_1 - \theta_2)}{\sin \theta}$$

At half width,  $\theta = \frac{\pi}{2}$ ,  $\theta_2 = \pi - \theta_1$ , and  $r = h = \frac{q}{2\pi U} \frac{[(\pi - \theta_1) - \theta_1]}{1}$

$$\therefore hU = \frac{q}{2\pi} [\pi - 2\theta_1] = \frac{q\pi}{2\pi} - \frac{q\theta_1}{\pi} \quad \text{or } \theta_1 = \frac{\pi}{2} - \frac{U h \pi}{q}$$

Since  $h = a \tan \theta$ ,

$$\frac{h}{a} = \tan\left(\frac{\pi}{2} - \frac{U h \pi}{q}\right) = \cot\left(\frac{U h \pi}{q}\right)$$

Substituting values,  $\frac{h}{0.3} = \cot\left(\frac{20}{30} h\right)$ . Trial and error solution gives  $h = 0.1615 \text{ m}$

The velocity field is given by  $\vec{v} = u\hat{i} + v\hat{j}$

$$\vec{v} = \left\{ \frac{q}{2\pi} \left( \frac{\cos \theta_1}{r_1} - \frac{\cos \theta_2}{r_2} \right) + U \right\} \hat{i} + \frac{q}{2\pi} \left( \frac{\sin \theta_1}{r_1} - \frac{\sin \theta_2}{r_2} \right) \hat{j}$$

At  $(0, h)$ ,  $r_1 = r_2$ ,  $\theta_2 = \pi - \theta_1$ ,  $\therefore \sin \theta_2 = \sin \theta_1$ ,  $\cos \theta_2 = -\cos \theta_1$ ,

$$\text{so } \vec{v} = \left( \frac{q \cos \theta_1}{r_1} + U \right) \hat{i}$$

$$\theta_1 = \tan^{-1} \frac{h}{a} = \tan^{-1} \frac{0.1615}{0.3} = 28.3^\circ \quad r_1 = [a^2 + h^2]^{1/2} = [0.3^2 + 0.1615^2]^{1/2} = 0.341 \text{ m}$$

$$\vec{v} = \left( \frac{q \cos \theta_1}{r_1} + U \right) \hat{i} = \left( 3\pi \frac{\text{m}^2}{\text{s}^2} \times \frac{\cos 28.3^\circ}{0.341 \text{ m}} + 20 \frac{\text{m}}{\text{s}} \right) \hat{i} = 44.3 \hat{i} \text{ m/s}$$

To find the gage pressure apply the Bernoulli equation between the point at conditions at  $\infty$

$$\frac{p}{\rho} + \frac{U^2}{2} = \frac{p}{\rho} + \frac{v^2}{2}$$

$$p_{\text{gage}} = p - p_\infty = \frac{1}{2} \rho (U^2 - v^2) = \frac{1}{2} \times 1.225 \frac{\text{kg}}{\text{m}^3} \left[ (20)^2 - (44.3)^2 \right] \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$p_{\text{gage}} = -957 \text{ N/m}^2$$



## Problem 6.124

[Difficulty: 3] Part 2/2



Using *Excel*, the stream function and velocity potential can be plotted.  
The data below was obtained using the workbook for Example Problem 6.10.  
Note the orthogonality of  $\psi$  and  $\phi$ !

Stream Function




Velocity Potential

Note that the plot is  
from  $x = -5$  to  $5$  and  $y = -5$  to  $5$



**6.125** Consider the flow field formed by combining a uniform flow in the positive  $x$  direction with a sink located at the origin. Let  $U = 50$  m/s and  $q = 90$  m<sup>2</sup>/s. Use a suitably chosen control volume to evaluate the net force per unit depth needed to hold in place (in standard air) the surface shape formed by the stagnation streamline.

Solution:



$$\psi = \psi_{\text{unif}} + \psi_{\text{sink}} = Uy - \frac{q\theta}{2\pi} = U r \sin\theta - \frac{q\theta}{2\pi} \quad \dots (1)$$

$$u = u_{\text{unif}} + u_{\text{sink}} ; u_{\text{unif}} = U, u_{\text{sink}} = -U_r \cos\theta = -\frac{q}{2\pi r} \frac{x}{r} \therefore u = U - \frac{q}{2\pi r} \frac{x}{r}$$

$$v = v_{\text{unif}} + v_{\text{sink}} ; v_{\text{unif}} = 0, v_{\text{sink}} = -U_r \sin\theta = -\frac{q}{2\pi r} \frac{y}{r} \therefore v = -\frac{q}{2\pi r} \frac{y}{r}$$

$$\therefore \vec{V} = u\vec{i} + v\vec{j} = \left( U - \frac{q}{2\pi} \frac{x}{r^2} \right) \vec{i} - \frac{q}{2\pi} \frac{y}{r^2} \vec{j}$$

At the stagnation point,  $\vec{V} = 0$

$$\therefore -\frac{q}{2\pi} \frac{y}{r^2} = 0, \text{ i.e. } y=0. \text{ Also } U - \frac{q}{2\pi} \frac{x}{r^2} = 0 \therefore U = \frac{q}{2\pi} \left( \frac{x}{y^2} \right)$$

$$\text{and } x_{\text{stag}} = \frac{q}{2\pi U} = \frac{90 \text{ m}^2/\text{s}}{50 \text{ m/s}} = \frac{90}{50} = 1.8 \text{ m}$$


At stagnation point,  $y=0$  and  $\theta=0$ . From eq. (1), then  $\psi_{\text{stag}} = 0$ . The equation of the stagnation streamline is then,

$$\psi = 0 = U r \sin\theta - \frac{q\theta}{2\pi} \text{ or } r_{\text{stag}} = \frac{q\theta}{2\pi U \sin\theta}$$

Since  $y = r \sin\theta$ , then along the stagnation streamline  $y = \frac{q\theta}{2\pi U}$ .

Far upstream,  $\theta \rightarrow \pi$  and  $y = y_1 \rightarrow \frac{q\pi}{2\pi U}$ .

The surface shape formed by the stagnation streamline is then as follows:



There is no flow across this streamline. The flow in through the left face must be equal to the flow ( $q$ ) which leaves through the sink at the origin.

Applying the  $x$  momentum equation to the CV shown.  $R_x$  is force required to hold shape in place.

$$-R_x = \int u \rho \vec{v} \cdot d\vec{A} = -U \rho b = -U \rho g b$$

$$\therefore \frac{R_x}{b} = \rho g U$$

For standard air  $\rho = 1.225 \text{ kg/m}^3$  and

$$\frac{R_x}{b} = 1.225 \frac{\text{kg}}{\text{m}^3} \times \frac{90 \text{ m}^2/\text{s}}{50 \text{ m/s}} = 2.205 \frac{\text{N}}{\text{m}}$$

$$R_x/b = -5.512 \text{ kN/m} \quad \leftarrow R_x/b$$

100 SHEETS 3 SQUARE  
22.381  
42.389  
200 SHEETS 3 SQUARE  
NATIONAL



## Problem 6.126

[Difficulty: 3] Part 2/2



Using *Excel*, the stream function and velocity potential can be plotted.  
The data below was obtained using the workbook for Example Problem 6.10.  
Note the orthogonality of  $\psi$  and  $\phi$ !

#NAME? Stream Function



#NAME? Velocity Potential

Note that the plot is  
from  $x = -5$  to  $5$  and  $y = -5$  to  $5$



### Problem 6.127


[Difficulty: 4] Part 1/2

**6.127** Consider the flow field formed by combining a uniform flow in the positive  $x$  direction and a source located at the origin. Let  $U = 30$  m/s and  $q = 150$  m<sup>2</sup>/s. Plot the ratio of the local velocity to the freestream velocity as a function of  $\theta$  along the stagnation streamline. Locate the points on the stagnation streamline where the velocity reaches its maximum value. Find the gage pressure there if the fluid density is 1.2 kg/m<sup>3</sup>.

Solution:

Superposition of a uniform flow and source gives flow around a half body.

$$u = u_{ur} + u_{s0} = U \cos \theta + \frac{q}{2\pi r} \cos \theta = U \cos \theta + \frac{q}{2\pi r} \cos \theta \quad \text{--- (1)}$$



$$u = u_{ur} + u_{s0} ; u_{ur} = U \cos \theta ; u_{s0} = \frac{q}{2\pi r} \cos \theta \quad \therefore u = U \cos \theta + \frac{q}{2\pi r} \cos \theta$$

$$v = v_{ur} + v_{s0} ; v_{ur} = -U \sin \theta ; v_{s0} = \frac{q}{2\pi r} \sin \theta \quad \therefore v = -U \sin \theta + \frac{q}{2\pi r} \sin \theta$$

$$\therefore \vec{V} = u^2 + v^2 = \left( U \cos \theta + \frac{q}{2\pi r} \cos \theta \right)^2 + \left( -U \sin \theta + \frac{q}{2\pi r} \sin \theta \right)^2 \quad \text{--- (2)}$$

$$V^2 = u^2 + v^2 = \left( U + \frac{q}{2\pi r} \cos \theta \right)^2 + \left( \frac{q}{2\pi r} \sin \theta \right)^2$$

$$= U^2 + \left( \frac{q}{2\pi r} \right)^2 \cos^2 \theta + \frac{Uq}{\pi r} \cos \theta + \left( \frac{q}{2\pi r} \right)^2 \sin^2 \theta$$

$$V^2 = U^2 + \left( \frac{q}{2\pi r} \right)^2 + \frac{Uq}{\pi r} \cos \theta \quad \text{--- (3)}$$

To determine the equation of the stagnation streamline, we locate the stagnation point ( $V=0$ ). From Eq. 2  $y=0$  and

$$U + \frac{q}{2\pi r} \cos \theta = 0 = U + \frac{q}{2\pi r} \cos \theta = U + \frac{q}{2\pi x} \quad \text{and } x_{stag} = -\frac{q}{2\pi U}$$

$$x_{stag} = -\frac{q}{2\pi U} = -\frac{1}{2\pi} \times \frac{150}{30} = -\frac{1}{2\pi} \times 5 = -0.796 \text{ m}$$

At the stagnation point  $y=0$  and  $\theta = \pi$ . From Eq. 1  $u_{stag} = \frac{q}{2\pi r}$  the equation of the stagnation streamline is then:

$$u_{stag} = \frac{q}{2\pi r} = U \cos \theta + \frac{q}{2\pi r} \cos \theta \quad \text{Solving for } r, \text{ we obtain}$$

$$r = \frac{1}{U \cos \theta} \left( \frac{q}{2} - \frac{q \cos \theta}{2\pi} \right) = \frac{q(\pi - \theta)}{2\pi U \sin \theta} \quad \text{--- (4)}$$

Substituting this value of  $r$  into the expression for  $V^2$  [Eq. 3] we obtain


$$V^2 = U^2 + \left[ \frac{q}{2\pi} \frac{2\pi U \sin \theta}{q(\pi - \theta)} \right]^2 + \frac{Uq \cos \theta}{\pi} \times \frac{2\pi U \sin \theta}{q(\pi - \theta)}$$

$$V^2 = U^2 + \frac{U^2 \sin^2 \theta}{(\pi - \theta)^2} + \frac{2U^2 \sin \theta \cos \theta}{(\pi - \theta)} = U^2 \left[ 1 + \frac{\sin^2 \theta}{(\pi - \theta)^2} + \frac{2 \sin \theta \cos \theta}{(\pi - \theta)} \right]$$

Along the stagnation streamline

$$\frac{V}{U} = \left[ 1 + \frac{\sin^2 \theta}{(\pi - \theta)^2} + \frac{2 \sin \theta \cos \theta}{(\pi - \theta)} \right]^{1/2} \quad \text{--- (5)}$$

$V/U$  is plotted as a function of  $\theta$



From the plot we see that  $V/U$  is a maximum at  $\theta = 63^\circ$  (also at  $\theta = 297^\circ$  from symmetry with respect to the  $x$  axis).

At  $\theta = 63^\circ$ , Eq. 5 gives  $V/U_{max} = 1.26$

Eq. 4 gives  $r = \frac{150 \frac{m^2}{s} \times (\pi - 0.35\pi)}{2\pi \sin 63^\circ \times 30 \frac{m}}{s} = 1.82 \text{ m}$

Thus  $V = V_{max}$  at  $r = 1.82 \text{ m}$  and  $\theta = 63^\circ, 297^\circ$  ( $r, \theta$ )<sub>max</sub>

To determine the gage pressure at this point, write the Bernoulli equation between a point upstream and the part of maximum velocity:


$$\frac{p}{\rho} + \frac{U^2}{2} = \frac{p}{\rho} + \frac{V_{max}^2}{2}$$

$$\therefore p - p_\infty = \frac{\rho}{2} [U^2 - V_{max}^2] = \frac{1}{2} \rho U^2 \left[ 1 - \left( \frac{V_{max}}{U} \right)^2 \right]$$

$$= \frac{1}{2} \times 1.2 \frac{\text{kg}}{\text{m}^3} \times (30 \frac{\text{m}}{\text{s}})^2 \left[ 1 - (1.26)^2 \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$p - p_\infty = 317 \text{ N/m}^2$$

Note: From the plot we see that  $V/U = 1.0$ , and hence  $p = p_\infty$ , at  $\theta = 113^\circ$ . The corresponding  $r$  is  $1.01 \text{ m}$ .



## Problem 7.1

[Difficulty: 2]

**7.1** The propagation speed of small-amplitude surface waves in a region of uniform depth is given by

$$c^2 = \left( \frac{\sigma}{\rho} \frac{2\pi}{\lambda} + \frac{g\lambda}{2\pi} \right) \tanh \frac{2\pi h}{\lambda}$$

where  $h$  is depth of the undisturbed liquid and  $\lambda$  is wavelength. Using  $L$  as a characteristic length and  $V_0$  as a characteristic velocity, obtain the dimensionless groups that characterize the equation.

**Given:** Equation describing the propagation speed of surface waves in a region of uniform depth

**Find:** Nondimensionalization for the equation using length scale  $L$  and velocity scale  $V_0$ . Obtain the dimensionless groups that characterize the flow.

**Solution:** To nondimensionalize the equation all lengths are divided by the reference length and all velocities are divided by the reference velocity. Denoting the nondimensional quantities by an asterisk:

$$\lambda^* = \frac{\lambda}{L} \quad h^* = \frac{h}{L} \quad c^* = \frac{c}{V_0}$$

Substituting into the governing equation:  $(c^* V_0)^2 = \left( \frac{\sigma}{\rho} \frac{2\pi}{\lambda^* L} + \frac{g \lambda^* L}{2\pi} \right) \tanh \frac{2\pi h^* L}{\lambda^* L}$  Simplifying this expression:

$$c^{*2} = \left( \frac{\sigma}{\rho L V_0^2} \frac{2\pi}{\lambda^*} + \frac{g L}{V_0^2} \frac{\lambda^*}{2\pi} \right) \tanh \frac{2\pi h^*}{\lambda^*}$$

The dimensionless group is  $\frac{g \cdot L}{V_0^2}$  which is the reciprocal of the square of the Froude number, and  $\frac{\sigma}{\rho \cdot L \cdot V_0^2}$

which is the inverse of the Weber number.

## Problem 7.2

[Difficulty: 2]

**7.2** The equation describing small-amplitude vibration of a beam is

$$\rho A \frac{\partial^2 y}{\partial t^2} + EI \frac{\partial^4 y}{\partial x^4} = 0$$

where  $y$  is the beam deflection at location  $x$  and time  $t$ ,  $\rho$  and  $E$  are the density and modulus of elasticity of the beam material, respectively, and  $A$  and  $I$  are the beam cross-section area and second moment of area, respectively. Use the beam length  $L$ , and frequency of vibration  $\omega$ , to non-dimensionalize this equation. Obtain the dimensionless groups that characterize the equation.

**Given:** Equation for beam

**Find:** Dimensionless groups

**Solution:**

Denoting nondimensional quantities by an asterisk

$$A^* = \frac{A}{L^2} \quad y^* = \frac{y}{L} \quad t^* = t\omega \quad I^* = \frac{I}{L^4} \quad x^* = \frac{x}{L}$$

Hence

$$A = L^2 A^* \quad y = L y^* \quad t = \frac{t^*}{\omega} \quad I = L^4 I^* \quad x = L x^*$$

Substituting into the governing equation

$$\rho L^2 L \omega^2 A^* \frac{\partial^2 y^*}{\partial t^{*2}} + EL^4 \frac{1}{L^4} LI^* \frac{\partial^4 y^*}{\partial x^{*4}} = 0$$

The final dimensionless equation is

$$A^* \frac{\partial^2 y^*}{\partial t^{*2}} + \left( \frac{E}{\rho L^2 \omega^2} \right) I^* \frac{\partial^4 y^*}{\partial x^{*4}} = 0$$

The dimensionless group is

$$\left( \frac{E}{\rho L^2 \omega^2} \right)$$

## Problem 7.3

[Difficulty: 2]

**7.3** The slope of the free surface of a steady wave in one-dimensional flow in a shallow liquid layer is described by the equation

$$\frac{\partial h}{\partial x} = -\frac{u}{g} \frac{\partial u}{\partial x}$$

Use a length scale,  $L$ , and a velocity scale,  $V_0$ , to nondimensionalize this equation. Obtain the dimensionless groups that characterize this flow.

**Given:** Equation describing the slope of a steady wave in a shallow liquid layer

**Find:** Nondimensionalization for the equation using length scale  $L$  and velocity scale  $V_0$ . Obtain the dimensionless groups that characterize the flow.

**Solution:** To nondimensionalize the equation all lengths are divided by the reference length and all velocities are divided by the reference velocity. Denoting the nondimensional quantities by an asterisk:

$$h^* = \frac{h}{L} \quad x^* = \frac{x}{L} \quad u^* = \frac{u}{V_0}$$

Substituting into the governing equation:  $\frac{\partial(h^*L)}{\partial(x^*L)} = -\frac{u^*V_0}{g} \frac{\partial(u^*V_0)}{\partial(x^*L)}$   $\frac{\partial h^*}{\partial x^*} = -\frac{V_0^2}{gL} u^* \frac{\partial u^*}{\partial x^*}$

The dimensionless group is  $\frac{V_0^2}{g \cdot L}$  which is the square of the Froude number.

## Problem 7.4

[Difficulty: 2]

**7.4** One-dimensional unsteady flow in a thin liquid layer is described by the equation

$$\frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} = -g \frac{\partial h}{\partial x}$$

Use a length scale,  $L$ , and a velocity scale,  $V_0$ , to nondimensionalize this equation. Obtain the dimensionless groups that characterize this flow.

**Given:** Equation describing one-dimensional unsteady flow in a thin liquid layer

**Find:** Nondimensionalization for the equation using length scale  $L$  and velocity scale  $V_0$ . Obtain the dimensionless groups that characterize the flow.

**Solution:** To nondimensionalize the equation all lengths are divided by the reference length and all velocities are divided by the reference velocity. Denoting the nondimensional quantities by an asterisk:

$$x^* = \frac{x}{L} \quad h^* = \frac{h}{L} \quad u^* = \frac{u}{V_0} \quad t^* = \frac{t}{L/V_0}$$

Substituting into the governing equation:  $\frac{\partial(u^* V_0)}{\partial(t^* L/V_0)} + u^* V_0 \frac{\partial(u^* V_0)}{\partial(x^* L)} = -g \frac{\partial(h^* L)}{\partial(x^* L)}$  Simplifying this expression:

$$\frac{V_0^2}{L} \frac{\partial u^*}{\partial t^*} + \frac{V_0^2}{L} u^* \frac{\partial u^*}{\partial x^*} = -g \frac{\partial h^*}{\partial x^*} \quad \text{Thus:} \quad \frac{\partial u^*}{\partial t^*} + u^* \frac{\partial u^*}{\partial x^*} = -\frac{gL}{V_0^2} \frac{\partial h^*}{\partial x^*}$$

The dimensionless group is  $\frac{g \cdot L}{V_0^2}$  which is the reciprocal of the square of the Froude number.

## Problem 7.5

[Difficulty: 2]

**7.5** A two-dimensional steady flow in a viscous liquid is described by the equation:

$$u \frac{\partial u}{\partial x} = -g \frac{\partial h}{\partial x} + \frac{\mu}{\rho} \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} \right)$$

Use a length scale,  $L$ , and a velocity scale,  $V_0$ , to nondimensionalize this equation. Obtain the dimensionless groups that characterize this flow.

**Given:** Equation describing two-dimensional steady flow in a liquid

**Find:** Nondimensionalization for the equation using length scale  $L$  and velocity scale  $V_0$ . Obtain the dimensionless groups that characterize the flow.

**Solution:** To nondimensionalize the equation all lengths are divided by the reference length and all velocities are divided by the reference velocity. Denoting the nondimensional quantities by an asterisk:

$$x^* = \frac{x}{L} \quad h^* = \frac{h}{L} \quad u^* = \frac{u}{V_0} \quad y^* = \frac{y}{L}$$

Substituting into the governing equation:

$$u^* V_0 \frac{\partial(u^* V_0)}{\partial(x^* L)} = -g \frac{\partial(h^* L)}{\partial(x^* L)} + \frac{\mu}{\rho} \left( \frac{\partial^2(u^* V_0)}{\partial(x^* L)\partial(x^* L)} + \frac{\partial^2(u^* V_0)}{\partial(y^* L)\partial(y^* L)} \right)$$

Simplifying this expression:

$$\frac{V_0^2}{L} u^* \frac{\partial u^*}{\partial x^*} = -g \frac{\partial h^*}{\partial x^*} + \frac{\mu V_0}{\rho L^2} \left( \frac{\partial^2 u^*}{\partial x^{*2}} + \frac{\partial^2 u^*}{\partial y^{*2}} \right)$$

$$\text{Thus: } u^* \frac{\partial u^*}{\partial x^*} = -\frac{gL}{V_0^2} \frac{\partial h^*}{\partial x^*} + \frac{\mu}{V_0 \rho L} \left( \frac{\partial^2 u^*}{\partial x^{*2}} + \frac{\partial^2 u^*}{\partial y^{*2}} \right)$$

The dimensionless groups are  $\frac{g \cdot L}{V_0^2}$  which is the reciprocal of the square of the Froude number, and  $\frac{\mu}{V_0 \cdot \rho \cdot L}$  which is the

reciprocal of the Reynolds number.

## Problem 7.6

[Difficulty: 2]

**7.6** In atmospheric studies the motion of the earth's atmosphere can sometimes be modeled with the equation

$$\frac{D\vec{V}}{Dt} + 2\vec{\Omega} \times \vec{V} = -\frac{1}{\rho} \nabla p$$

where  $\vec{V}$  is the large-scale velocity of the atmosphere across the Earth's surface,  $\nabla p$  is the climatic pressure gradient, and  $\vec{\Omega}$  is the Earth's angular velocity. What is the meaning of the term  $\vec{\Omega} \times \vec{V}$ ? Use the pressure difference,  $\Delta p$ , and typical length scale,  $L$  (which could, for example, be the magnitude of, and distance between, an atmospheric high and low, respectively), to nondimensionalize this equation. Obtain the dimensionless groups that characterize this flow.

**Given:** Equations for modeling atmospheric motion

**Find:** Non-dimensionalized equation; Dimensionless groups

**Solution:**

Recall that the total acceleration is

$$\frac{D\vec{V}}{Dt} = \frac{\partial \vec{V}}{\partial t} + \vec{V} \cdot \nabla \vec{V}$$

Nondimensionalizing the velocity vector, pressure, angular velocity, spatial measure, and time, (using a typical velocity magnitude  $V$  and angular velocity magnitude  $\Omega$ ):

$$\vec{V}^* = \frac{\vec{V}}{V} \quad p^* = \frac{p}{\Delta p} \quad \vec{\Omega}^* = \frac{\vec{\Omega}}{\Omega} \quad x^* = \frac{x}{L} \quad t^* = t \frac{V}{L}$$

Hence

$$\vec{V} = V \vec{V}^* \quad p = \Delta p p^* \quad \vec{\Omega} = \Omega \vec{\Omega}^* \quad x = L x^* \quad t = \frac{L}{V} t^*$$

Substituting into the governing equation

$$V \frac{V}{L} \frac{\partial \vec{V}^*}{\partial t^*} + V \frac{V}{L} \vec{V}^* \cdot \nabla^* \vec{V}^* + 2\Omega V \vec{\Omega}^* \times \vec{V}^* = -\frac{1}{\rho} \frac{\Delta p}{L} \nabla p^*$$

The final dimensionless equation is

$$\frac{\partial \vec{V}^*}{\partial t^*} + \vec{V}^* \cdot \nabla^* \vec{V}^* + 2 \left( \frac{\Omega L}{V} \right) \vec{\Omega}^* \times \vec{V}^* = -\frac{\Delta p}{\rho V^2} \nabla p^*$$

The dimensionless groups are

$$\frac{\Delta p}{\rho V^2} \quad \frac{\Omega L}{V}$$

The second term on the left of the governing equation is the Coriolis force due to a rotating coordinate system. This is a very significant term in atmospheric studies, leading to such phenomena as geostrophic flow.

## Problem 7.7

[Difficulty: 4]

**7.7** By using order of magnitude analysis, the continuity and Navier–Stokes equations can be simplified to the Prandtl boundary-layer equations. For steady, incompressible, and two-dimensional flow, neglecting gravity, the result is

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$$

$$u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} = -\frac{1}{\rho} \frac{\partial p}{\partial x} + \nu \frac{\partial^2 u}{\partial y^2}$$

Use  $L$  and  $V_0$  as characteristic length and velocity, respectively. Nondimensionalize these equations and identify the similarity parameters that result.

**Given:** The Prandtl boundary-layer equations for steady, incompressible, two-dimensional flow neglecting gravity

**Find:** Nondimensionalization for the equation using length scale  $L$  and velocity scale  $V_0$ . Obtain the dimensionless groups that characterize the flow.

**Solution:** To nondimensionalize the equation all lengths are divided by the reference length and all velocities are divided by the reference velocity. Denoting the nondimensional quantities by an asterisk:

$$x^* = \frac{x}{L} \quad y^* = \frac{y}{L} \quad u^* = \frac{u}{V_0} \quad v^* = \frac{v}{V_0}$$

Substituting into the continuity equation:  $\frac{\partial(u^*V_0)}{\partial(x^*L)} + \frac{\partial(v^*V_0)}{\partial(y^*L)} = 0$  Simplifying this expression:  $\frac{V_0}{L} \frac{\partial u^*}{\partial x^*} + \frac{V_0}{L} \frac{\partial v^*}{\partial y^*} = 0$

$$\frac{\partial u^*}{\partial x^*} + \frac{\partial v^*}{\partial y^*} = 0$$

We expand out the second derivative in the momentum equation by writing it as the derivative of the derivative. Upon substitution:

$$u^*V_0 \frac{\partial(u^*V_0)}{\partial(x^*L)} + v^*V_0 \frac{\partial(u^*V_0)}{\partial(y^*L)} = -\frac{1}{\rho} \frac{\partial p}{\partial(x^*L)} + \nu \frac{\partial}{\partial(y^*L)} \frac{\partial(u^*V_0)}{\partial(y^*L)}$$

Simplifying this expression yields:

$$u^* \frac{\partial u^*}{\partial x^*} + v^* \frac{\partial u^*}{\partial y^*} = -\frac{1}{\rho V_0^2} \frac{\partial p}{\partial x^*} + \frac{\nu}{V_0 L} \frac{\partial^2 u^*}{\partial y^{*2}}$$

Now every term in this equation has been non-dimensionalized except the pressure gradient. We define a dimensionless pressure as:

$$p^* = \frac{p}{\rho V_0^2} \quad \text{Substituting this into the momentum equation:} \quad u^* \frac{\partial u^*}{\partial x^*} + v^* \frac{\partial u^*}{\partial y^*} = -\frac{1}{\rho V_0^2} \frac{\partial(p^* \rho V_0^2)}{\partial x^*} + \frac{\nu}{V_0 L} \frac{\partial^2 u^*}{\partial y^{*2}}$$

Simplifying this expression yields:

$$u^* \frac{\partial u^*}{\partial x^*} + v^* \frac{\partial u^*}{\partial y^*} = -\frac{\partial p^*}{\partial x^*} + \frac{\nu}{V_0 L} \frac{\partial^2 u^*}{\partial y^{*2}}$$

The dimensionless group is  $\frac{\nu}{V_0 \cdot L}$  which is the reciprocal of the Reynolds number.

## Problem 7.8

[Difficulty: 2]

**7.8** An unsteady, two-dimensional, compressible, inviscid flow can be described by the equation

$$\frac{\partial^2 \psi}{\partial t^2} + \frac{\partial}{\partial t} (u^2 + v^2) + (u^2 - c^2) \frac{\partial^2 \psi}{\partial x^2} + (v^2 - c^2) \frac{\partial^2 \psi}{\partial y^2} + 2uv \frac{\partial^2 \psi}{\partial x \partial y} = 0$$

where  $\psi$  is the stream function,  $u$  and  $v$  are the  $x$  and  $y$  components of velocity, respectively,  $c$  is the local speed of sound, and  $t$  is the time. Using  $L$  as a characteristic length and  $c_0$  (the speed of sound at the stagnation point) to non-dimensionalize this equation, obtain the dimensionless groups that characterize the equation.

**Given:** Equation for unsteady, 2D compressible, inviscid flow

**Find:** Dimensionless groups

**Solution:**

Denoting nondimensional quantities by an asterisk

$$x^* = \frac{x}{L} \quad y^* = \frac{y}{L} \quad u^* = \frac{u}{c_0} \quad v^* = \frac{v}{c_0} \quad c^* = \frac{c}{c_0} \quad t^* = \frac{t c_0}{L} \quad \psi^* = \frac{\psi}{L c_0}$$

Note that the stream function indicates volume flow rate/unit depth!

Hence

$$x = L x^* \quad y = L y^* \quad u = c_0 u^* \quad v = c_0 v^* \quad c = c_0 c^* \quad t = \frac{L t^*}{c_0} \quad \psi = L c_0 \psi^*$$

Substituting into the governing equation

$$\left(\frac{c_0^3}{L}\right) \frac{\partial^2 \psi^*}{\partial t^{*2}} + \left(\frac{c_0^3}{L}\right) \frac{\partial (u^{*2} + v^{*2})}{\partial t} + \left(\frac{c_0^3}{L}\right) (u^{*2} - c^{*2}) \frac{\partial^2 \psi^*}{\partial x^{*2}} + \left(\frac{c_0^3}{L}\right) (v^{*2} - c^{*2}) \frac{\partial^2 \psi^*}{\partial y^{*2}} + \left(\frac{c_0^3}{L}\right) 2u^* v^* \frac{\partial^2 \psi^*}{\partial x^* \partial y^*} = 0$$

The final dimensionless equation is

$$\frac{\partial^2 \psi^*}{\partial t^{*2}} + \frac{\partial (u^{*2} + v^{*2})}{\partial t} + (u^{*2} - c^{*2}) \frac{\partial^2 \psi^*}{\partial x^{*2}} + (v^{*2} - c^{*2}) \frac{\partial^2 \psi^*}{\partial y^{*2}} + 2u^* v^* \frac{\partial^2 \psi^*}{\partial x^* \partial y^*} = 0$$

No dimensionless group is needed for this equation!

## Problem 7.9

[Difficulty: 2]

**7.9** The equation describing motion of fluid in a pipe due to an applied pressure gradient, when the flow starts from rest, is

$$\frac{\partial u}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial x} + \nu \left( \frac{\partial^2 u}{\partial r^2} + \frac{1}{r} \frac{\partial u}{\partial r} \right)$$

Use the average velocity  $\bar{V}$ , pressure drop  $\Delta p$ , pipe length  $L$ , and diameter  $D$  to nondimensionalize this equation. Obtain the dimensionless groups that characterize this flow.

**Given:** Equations Describing pipe flow

**Find:** Non-dimensionalized equation; Dimensionless groups

**Solution:**

Nondimensionalizing the velocity, pressure, spatial measures, and time:

$$u^* = \frac{u}{\bar{V}} \quad p^* = \frac{p}{\Delta p} \quad x^* = \frac{x}{L} \quad r^* = \frac{r}{L} \quad t^* = t \frac{\bar{V}}{L}$$

Hence

$$u = \bar{V} u^* \quad p = \Delta p p^* \quad x = L x^* \quad r = D r^* \quad t = \frac{L}{\bar{V}} t^*$$

Substituting into the governing equation

$$\frac{\partial u}{\partial t} = \bar{V} \frac{\bar{V}}{L} \frac{\partial u^*}{\partial t^*} = -\frac{1}{\rho} \Delta p \frac{1}{L} \frac{\partial p^*}{\partial x^*} + \nu \bar{V} \frac{1}{D^2} \left( \frac{\partial^2 u^*}{\partial r^{*2}} + \frac{1}{r^*} \frac{\partial u^*}{\partial r^*} \right)$$

The final dimensionless equation is

$$\frac{\partial u^*}{\partial t^*} = -\frac{\Delta p}{\rho \bar{V}^2} \frac{\partial p^*}{\partial x^*} + \left( \frac{\nu}{D \bar{V}} \right) \left( \frac{L}{D} \right) \left( \frac{\partial^2 u^*}{\partial r^{*2}} + \frac{1}{r^*} \frac{\partial u^*}{\partial r^*} \right)$$

The dimensionless groups are

$$\frac{\Delta p}{\rho \bar{V}^2} \quad \frac{\nu}{D \bar{V}} \quad \frac{L}{D}$$

## Problem 7.10

[Difficulty: 2]

**7.10** Experiments show that the pressure drop for flow through an orifice plate of diameter  $d$  mounted in a length of pipe of diameter  $D$  may be expressed as  $\Delta p = p_1 - p_2 = f(\rho, \mu, \bar{V}, d, D)$ . You are asked to organize some experimental data. Obtain the resulting dimensionless parameters.

**Given:** Functional relationship between pressure drop through orifice plate and physical parameters

**Find:** Appropriate dimensionless parameters

**Solution:** We will use the Buckingham pi-theorem.

1  $\Delta p \quad \rho \quad \mu \quad V \quad D \quad d$  n = 6 parameters

2 Select primary dimensions M, L, t:

3  $\Delta p \quad \rho \quad \mu \quad V \quad D \quad d$

$$\frac{M}{L \cdot t^2} \quad \frac{M}{L^3} \quad \frac{M}{L \cdot t} \quad \frac{L}{t} \quad L \quad L$$

r = 3 dimensions

4  $\rho \quad V \quad D$  m = r = 3 repeating parameters

5 We have n - m = 3 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = \Delta p \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \left(\frac{M}{L \cdot t^2}\right) \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = -1 \quad b = -2 \quad c = 0$

$$\Pi_1 = \frac{\Delta p}{\rho \cdot V^2}$$

Check using F, L, t primary dimensions:  $\frac{F}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} = 1$  Checks out.

$$\Pi_2 = \mu \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \left(\frac{M}{L \cdot t}\right) \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-1 - b = 0$

The solution to this system is:

$a = -1 \quad b = -1 \quad c = -1$

$$\Pi_2 = \frac{\mu}{\rho \cdot V \cdot D}$$

(This is the Reynolds number, so it checks out)

$$\Pi_3 = d \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } a = 0$$

$$\text{L: } 1 + c = 0$$

$$\text{t: } b = 0$$

The solution to this system is:

$$a = 0 \quad b = 0 \quad c = -1$$

$$\Pi_3 = \frac{d}{D}$$

(This checks out)

## Problem 7.11

[Difficulty: 2]

**7.11** At relatively high speeds the drag on an object is independent of fluid viscosity. Thus the aerodynamic drag force,  $F$ , on an automobile, is a function only of speed,  $V$ , air density  $\rho$ , and vehicle size, characterized by its frontal area  $A$ . Use dimensional analysis to determine how the drag force  $F$  depends on the speed  $V$ .

**Given:** That drag depends on speed, air density and frontal area

**Find:** How drag force depend on speed

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $F \quad V \quad \rho \quad A \quad n = 4$  parameters

② Select primary dimensions  $M, L, t$

③  $F \quad V \quad \rho \quad A \quad r = 3$  primary dimensions

$$\frac{ML}{t^2} \quad \frac{L}{t} \quad \frac{M}{L^3} \quad L^2$$

④  $V \quad \rho \quad A \quad m = r = 3$  repeat parameters

⑤ Then  $n - m = 1$  dimensionless groups will result. Setting up a dimensional equation,

$$\begin{aligned} \Pi_1 &= V^a \rho^b A^c F \\ &= \left(\frac{L}{t}\right)^a \left(\frac{M}{L^3}\right)^b (L^2)^c \frac{ML}{t^2} = M^0 L^0 t^0 \end{aligned}$$

Summing exponents,

$$\begin{array}{l} M: \quad b + 1 = 0 \\ L: \quad a - 3b + 2c + 1 = 0 \\ t: \quad -a - 2 = 0 \end{array} \quad \left| \begin{array}{l} b = -1 \\ c = -1 \\ a = -2 \end{array} \right.$$

Hence

$$\Pi_1 = \frac{F}{\rho V^2 A}$$

⑥ Check using  $F, L, t$  as primary dimensions

$$\Pi_1 = \frac{F}{\frac{Ft^2}{L^4} \frac{L^2}{t^2}} = [1]$$

The relation between drag force  $F$  and speed  $V$  must then be

$$F \propto \rho V^2 A \propto V^2$$

The drag is proportional to the *square* of the speed.

## Problem 7.12

[Difficulty: 2]

**7.12** At very low speeds, the drag on an object is independent of fluid density. Thus the drag force,  $F$ , on a small sphere is a function only of speed,  $V$ , fluid viscosity,  $\mu$ , and sphere diameter,  $D$ . Use dimensional analysis to determine how the drag force  $F$  depends on the speed  $V$ .

**Given:** At low speeds, drag  $F$  on a sphere is only dependent upon speed  $V$ , viscosity  $\mu$ , and diameter  $D$

**Find:** Appropriate dimensionless parameters

**Solution:** We will use the Buckingham pi-theorem.

1  $F \quad V \quad \mu \quad D \quad n = 4 \text{ parameters}$

2 Select primary dimensions M, L, t:

3  $F \quad V \quad \mu \quad D \quad n = 4 \text{ parameters}$

$$\frac{ML}{t^2} \quad \frac{L}{t} \quad \frac{M}{Lt} \quad L \quad r = 3 \text{ dimensions}$$

4  $V \quad \mu \quad D \quad m = r = 3 \text{ repeating parameters}$

5 We have  $n - m = 1$  dimensionless group. Setting up a dimensional equation:

$$\Pi_1 = F \cdot V^a \cdot \mu^b \cdot D^c \quad \text{Thus:} \quad \left(\frac{M \cdot L}{t^2}\right) \cdot \left(\frac{L}{t}\right)^a \cdot \left(\frac{M}{L \cdot t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + b = 0$

L:  $1 + a - b + c = 0$

t:  $-2 - a - b = 0$

The solution to this system is:

$a = -1 \quad b = -1 \quad c = -1$

$$\Pi_1 = \frac{F}{\mu \cdot V \cdot D}$$

Check using F, L, t primary dimensions:  $F \cdot \frac{t}{L} \cdot \frac{L^2}{F \cdot t} \cdot \frac{1}{L} = 1$  Checks out.

Since the procedure produces only one dimensionless group, it must be a constant. Therefore:

$$\frac{F}{\mu \cdot V \cdot D} = \text{constant}$$

## Problem 7.13

[Difficulty: 2]

**7.13** The drag force on the International Space Station depends on the mean free path of the molecules  $\lambda$  (a length), the density  $\rho$ , a characteristic length  $L$ , and the mean speed of the air molecules  $c$ . Find a nondimensional form of this functional relationship.

**Given:** Functional relationship between the drag on a satellite and other physical parameters

**Find:** Expression for  $F_D$  in terms of the other variables

**Solution:** We will use the Buckingham pi-theorem.

1  $F_D \quad \lambda \quad \rho \quad L \quad c$  n = 5 parameters

2 Select primary dimensions M, L, t:

3  $F_D \quad \lambda \quad \rho \quad L \quad c$  r = 3 dimensions

$$\frac{M \cdot L}{t^2} \quad L \quad \frac{M}{L^3} \quad L \quad \frac{L}{t}$$

4  $\rho \quad L \quad c$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = D \cdot \rho^a \cdot L^b \cdot c^d \quad \text{Thus:} \quad \frac{M \cdot L}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t}\right)^d = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $1 - 3 \cdot a + b + d = 0$

t:  $-2 - d = 0$

The solution to this system is:

$a = -1 \quad b = -2 \quad d = -2$

$$\Pi_1 = \frac{F_D}{\rho \cdot L^2 \cdot c^2}$$

Check using F, L, t dimensions:

$$F \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^2} \cdot \frac{t^2}{L^2} = 1$$

$$\Pi_2 = \lambda \cdot \rho^a \cdot L^b \cdot c^d \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t}\right)^d = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + d = 0$

t:  $d = 0$

The solution to this system is:

$a = 0 \quad b = -1 \quad d = 0$

$$\Pi_2 = \frac{\lambda}{L} \quad (\Pi_2 \text{ is sometimes referred to as the Knudsen number.})$$

Check using F, L, t dimensions:

$$L \cdot \frac{1}{L} = 1$$

The functional relationship is:  $\Pi_1 = f(\Pi_2)$   $\frac{F_D}{\rho \cdot L^2 \cdot c^2} = f\left(\frac{\lambda}{L}\right)$   $F_D = \rho \cdot L^2 \cdot c^2 \cdot f\left(\frac{\lambda}{L}\right)$

## Problem 7.14

[Difficulty: 2]

**7.14** We saw in Chapter 3 that the buoyant force,  $F_B$ , on a body submerged in a fluid is directly proportional to the specific weight of the fluid,  $\gamma$ . Demonstrate this using dimensional analysis, by starting with the buoyant force as a function of the volume of the body and the specific weight of the fluid.

**Given:** Functional relationship between buoyant force of a fluid and physical parameters

**Find:** Buoyant force is proportional to the specific weight as demonstrated in Chapter 3.

**Solution:** We will use the Buckingham pi-theorem.

1  $F_B \quad V \quad \gamma$  n = 3 parameters

2 Select primary dimensions F, L, t:

3  $F_B \quad V \quad \gamma$

$$F \quad L^3 \quad \frac{F}{L^3}$$

r = 2 dimensions

4  $V \quad \gamma$  m = r = 2 repeating parameters

5 We have n - m = 1 dimensionless group. Setting up dimensional equations:

$$\Pi_1 = F_B \cdot V^a \cdot \gamma^b \quad \text{Thus:} \quad F \cdot (L^3)^a \cdot \left(\frac{F}{L^3}\right)^b = F^0 \cdot L^0$$

Summing exponents:

$$F: \quad 1 + b = 0$$

$$L: \quad 3 \cdot a - 3 \cdot b = 0$$

The solution to this system is:

$$a = -1 \quad b = -1$$

$$\Pi_1 = \frac{F_B}{V \cdot \gamma}$$

Check using M, L, t dimensions:  $\frac{M \cdot L}{t^2} \cdot \frac{1}{L^3} \cdot \frac{t^2 \cdot L^2}{M} = 1$

The functional relationship is:  $\Pi_1 = C \quad \frac{F_B}{V \cdot \gamma} = C$  Solving for the buoyant force:  $F_B = C \cdot V \cdot \gamma$  Buoyant force is proportional to  $\gamma$  (Q.E.D.)

## Problem 7.15

[Difficulty: 2]

**7.15** When an object travels at supersonic speeds, the aerodynamic drag force  $F$  acting on the object is a function of the velocity  $V$ , air density  $\rho$ , object size (characterized by some reference area  $A$ ), and the speed of sound  $c$  (note that all of the variables except  $c$  were considered when traveling at subsonic speeds as in Problem 7.11). Develop a functional relationship between a set of dimensionless variables to describe this problem.

**Given:** Functional relationship between drag on an object in a supersonic flow and physical parameters

**Find:** Functional relationship for this problem using dimensionless parameters

**Solution:** We will use the Buckingham pi-theorem.

1  $F_D \quad V \quad \rho \quad A \quad c$  n = 5 parameters

2 Select primary dimensions M, L, t:

3  $F_D \quad V \quad \rho \quad A \quad c$

$$\frac{M \cdot L}{t^2} \quad \frac{L}{t} \quad \frac{M}{L^3} \quad L^2 \quad \frac{L}{t}$$

r = 3 dimensions

4  $V \quad \rho \quad A$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = F_D \cdot V^a \cdot \rho^b \cdot A^c \quad \text{Thus:} \quad \frac{M \cdot L}{t^2} \cdot \left(\frac{L}{t}\right)^a \cdot \left(\frac{M}{L^3}\right)^b \cdot (L^2)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + b = 0$

L:  $1 + a - 3 \cdot b + 2 \cdot c = 0$

t:  $-2 - a = 0$

The solution to this system is:

$a = -2 \quad b = -1 \quad c = -1$

$$\Pi_1 = \frac{F_D}{V^2 \cdot \rho \cdot A}$$

Check using F, L, t dimensions:  $F \cdot \frac{t^2}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^2} = 1$

$$\Pi_2 = c \cdot V^a \cdot \rho^b \cdot A^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left(\frac{L}{t}\right)^a \cdot \left(\frac{M}{L^3}\right)^b \cdot (L^2)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $b = 0$

L:  $1 + a - 3 \cdot b + 2 \cdot c = 0$

t:  $-1 - a = 0$

The solution to this system is:

$a = -1 \quad b = 0 \quad c = 0$

$$\Pi_2 = \frac{c}{V} \quad \text{(The reciprocal of } \Pi_2 \text{ is also referred to as the Mach number.)}$$

Check using F, L, t dimensions:  $\frac{L}{t} \cdot \frac{t}{L} = 1$

The functional relationship is:  $\Pi_1 = g(\Pi_2)$

$$\frac{F_D}{V^2 \cdot \rho \cdot A} = f\left(\frac{c}{V}\right)$$

## Problem 7.16

[Difficulty: 2]

**7.16** The speed,  $V$ , of a free-surface wave in shallow liquid is a function of depth,  $D$ , density,  $\rho$ , gravity,  $g$ , and surface tension,  $\sigma$ . Use dimensional analysis to find the functional dependence of  $V$  on the other variables. Express  $V$  in the simplest form possible.

**Given:** That speed of shallow waves depends on depth, density, gravity and surface tension

**Find:** Dimensionless groups; Simplest form of  $V$

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $V \quad D \quad \rho \quad g \quad \sigma \quad n = 5$  parameters

② Select primary dimensions M, L, t

③ 
$$\left\{ \begin{array}{ccccc} V & D & \rho & g & \sigma \\ \frac{L}{t} & L & \frac{M}{L^3} & \frac{L}{t^2} & \frac{M}{t^2} \end{array} \right\} \quad r = 3 \text{ primary dimensions}$$

④  $g \quad \rho \quad D \quad m = r = 3$  repeat parameters

⑤ Then  $n - m = 2$  dimensionless groups will result. Setting up a dimensional equation,

$$\Pi_1 = g^a \rho^b D^c V = \left(\frac{L}{t^2}\right)^a \left(\frac{M}{L^3}\right)^b (L)^c \frac{L}{t} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad b = 0 \\ L: \quad a - 3b + c + 1 = 0 \\ t: \quad -2a - 1 = 0 \end{array} \quad \left| \quad \begin{array}{l} b = 0 \\ c = -\frac{1}{2} \\ a = -\frac{1}{2} \end{array} \right. \quad \text{Hence} \quad \Pi_1 = \frac{V}{\sqrt{gD}}$$

$$\Pi_2 = g^a \rho^b D^c \sigma = \left(\frac{L}{t^2}\right)^a \left(\frac{M}{L^3}\right)^b (L)^c \frac{M}{t^2} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad b + 1 = 0 \\ L: \quad a - 3b + c = 0 \\ t: \quad -2a - 2 = 0 \end{array} \quad \left| \quad \begin{array}{l} b = -1 \\ c = -2 \\ a = -1 \end{array} \right. \quad \text{Hence} \quad \Pi_2 = \frac{\sigma}{g\rho D^2}$$

⑥ Check using  $F, L, t$  as primary dimensions 
$$\Pi_1 = \frac{L}{\left(\frac{L}{t^2} L\right)^{\frac{1}{2}}} = [1] \quad \Pi_2 = \frac{F}{\frac{L}{t^2} \frac{F t^2}{L^4} L^2} = [1]$$

The relation between drag force speed  $V$  is 
$$\Pi_1 = f(\Pi_2) \quad \frac{V}{\sqrt{gD}} = f\left(\frac{\sigma}{g\rho D^2}\right) \quad V = \sqrt{gD} f\left(\frac{\sigma}{g\rho D^2}\right)$$

## Problem 7.17

[Difficulty: 2]

**7.17** The wall shear stress,  $\tau_w$ , in a boundary layer depends on distance from the leading edge of the body,  $x$ , the density,  $\rho$ , and viscosity,  $\mu$ , of the fluid, and the freestream speed of the flow,  $U$ . Obtain the dimensionless groups and express the functional relationship among them.

**Given:** Functional relationship between wall shear stress in a boundary layer and physical parameters

**Find:** Appropriate dimensionless parameters

**Solution:** We will use the Buckingham pi-theorem.

1  $\tau_w \quad x \quad \rho \quad \mu \quad U$  n = 5 parameters

2 Select primary dimensions M, L, t:

3  $\tau_w \quad x \quad \rho \quad \mu \quad U$

$$\frac{M}{Lt^2} \quad L \quad \frac{M}{L^3} \quad \frac{M}{Lt} \quad \frac{L}{t}$$

r = 3 dimensions

4  $\rho \quad x \quad U$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = \tau_w \cdot \rho^a \cdot x^b \cdot U^c \quad \text{Thus:} \quad \left(\frac{M}{L \cdot t^2}\right) \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-2 - c = 0$

The solution to this system is:

$a = -1 \quad b = 0 \quad c = -2$

$$\Pi_1 = \frac{\tau_w}{\rho \cdot U^2}$$

Check using F, L, t dimensions:  $\left(\frac{F}{L^2}\right) \cdot \left(\frac{L^4}{F \cdot t^2}\right) \cdot \left(\frac{t^2}{L}\right) = 1$

$$\Pi_2 = \mu \cdot \rho^a \cdot x^b \cdot U^c \quad \text{Thus:} \quad \left(\frac{M}{L \cdot t}\right) \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-1 - c = 0$

The solution to this system is:

$a = -1 \quad b = -1 \quad c = -1$

$$\Pi_2 = \frac{\mu}{\rho \cdot x \cdot U}$$

Check using F, L, t dimensions:  $\left(\frac{F \cdot t}{L^2}\right) \cdot \left(\frac{L^4}{F \cdot t^2}\right) \cdot \left(\frac{1}{L}\right) \cdot \left(\frac{t^2}{L}\right) = 1$

The functional relationship is:

$$\Pi_1 = f(\Pi_2)$$

## Problem 7.18

[Difficulty: 2]

**7.18** The boundary-layer thickness,  $\delta$ , on a smooth flat plate in an incompressible flow without pressure gradients depends on the freestream speed,  $U$ , the fluid density,  $\rho$ , the fluid viscosity,  $\mu$ , and the distance from the leading edge of the plate,  $x$ . Express these variables in dimensionless form.

**Given:** Functional relationship between boundary layer thickness and physical parameters

**Find:** Appropriate dimensionless parameters

**Solution:** We will use the Buckingham pi-theorem.

1     $\delta$      $x$      $\rho$      $\mu$      $U$     n = 5 parameters

2    Select primary dimensions M, L, t:

3     $\delta$      $x$      $\rho$      $\mu$      $U$

$L$      $L$      $\frac{M}{L^3}$      $\frac{M}{Lt}$      $\frac{L}{t}$     r = 3 dimensions

4     $\rho$      $x$      $U$     m = r = 3 repeating parameters

5    We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = \delta \cdot \rho^a \cdot x^b \cdot U^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M: 0 + a = 0	The solution to this system is:	$\Pi_1 = \frac{\delta}{x}$
L: 1 - 3·a + b + c = 0	a = 0    b = -1    c = 0	
t: 0 - c = 0		

Check using F, L, t dimensions:  $(L) \cdot \left(\frac{1}{L}\right) = 1$

$$\Pi_2 = \mu \cdot \rho^a \cdot x^b \cdot U^c \quad \text{Thus:} \quad \left(\frac{M}{L \cdot t}\right) \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M: 1 + a = 0	The solution to this system is:	$\Pi_2 = \frac{\mu}{\rho \cdot x \cdot U}$
L: -1 - 3·a + b + c = 0	a = -1    b = -1    c = -1	
t: -1 - c = 0		

Check using F, L, t dimensions:  $\left(\frac{F \cdot t}{L^2}\right) \cdot \left(\frac{L^4}{F \cdot t^2}\right) \cdot \left(\frac{1}{L}\right) \cdot \left(\frac{t^2}{L}\right) = 1$

The functional relationship is:

$$\Pi_1 = f(\Pi_2)$$

## Problem 7.19

[Difficulty: 2]

**7.19** If an object is light enough it can be supported on the surface of a fluid by surface tension. Tests are to be done to investigate this phenomenon. The weight,  $W$ , supportable in this way depends on the object's perimeter,  $p$ , and the fluid's density,  $\rho$ , surface tension  $\sigma$ , and gravity,  $g$ . Determine the dimensionless parameters that characterize this problem.

**Given:** That light objects can be supported by surface tension

**Find:** Dimensionless groups

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $W \quad p \quad \rho \quad g \quad \sigma \quad n = 5$  parameters

② Select primary dimensions M, L, t

③ 
$$\left\{ \begin{array}{ccccc} W & p & \rho & g & \sigma \\ \frac{ML}{t^2} & L & \frac{M}{L^3} & \frac{L}{t^2} & \frac{M}{t^2} \end{array} \right\} \quad r = 3 \text{ primary dimensions}$$

④  $g \quad \rho \quad p \quad m = r = 3$  repeat parameters

⑤ Then  $n - m = 2$  dimensionless groups will result. Setting up a dimensional equation,

$$\Pi_1 = g^a \rho^b p^c W = \left(\frac{L}{t^2}\right)^a \left(\frac{M}{L^3}\right)^b (L)^c \frac{ML}{t^2} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad b + 1 = 0 \\ L: \quad a - 3b + c + 1 = 0 \\ t: \quad -2a - 2 = 0 \end{array} \quad \left| \quad \begin{array}{l} b = -1 \\ c = -3 \\ a = -1 \end{array} \right. \quad \text{Hence} \quad \Pi_1 = \frac{W}{g\rho p^3}$$

$$\Pi_2 = g^a \rho^b p^c \sigma = \left(\frac{L}{t^2}\right)^a \left(\frac{M}{L^3}\right)^b (L)^c \frac{M}{t^2} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad b + 1 = 0 \\ L: \quad a - 3b + c = 0 \\ t: \quad -2a - 2 = 0 \end{array} \quad \left| \quad \begin{array}{l} b = -1 \\ c = -2 \\ a = -1 \end{array} \right. \quad \text{Hence} \quad \Pi_2 = \frac{\sigma}{g\rho p^2}$$

⑥ Check using  $F, L, t$  as primary dimensions 
$$\Pi_1 = \frac{F}{\frac{L}{t^2} \frac{F t^2}{L^4} L^3} = [1] \quad \Pi_2 = \frac{F}{\frac{L}{t^2} \frac{F t^2}{L^4} L^2} = [1]$$

Note: Any combination of  $\Pi_1$  and  $\Pi_2$  is a  $\Pi$  group, e.g.,  $\frac{\Pi_1}{\Pi_2} = \frac{Wp}{\sigma}$ , so  $\Pi_1$  and  $\Pi_2$  are not unique!

## Problem 7.20

[Difficulty: 2]

**7.20** The speed,  $V$ , of a free-surface gravity wave in deep water is a function of wavelength,  $\lambda$ , depth,  $D$ , density,  $\rho$ , and acceleration of gravity,  $g$ . Use dimensional analysis to find the functional dependence of  $V$  on the other variables. Express  $V$  in the simplest form possible.

**Given:** Functional relationship between the speed of a free-surface gravity wave in deep water and physical parameters

**Find:** The dependence of the speed on the other variables

**Solution:** We will use the Buckingham pi-theorem.

1  $V \quad \lambda \quad D \quad \rho \quad g$  n = 5 parameters

2 Select primary dimensions M, L, t:

3  $V \quad \lambda \quad D \quad \rho \quad g$  r = 3 dimensions

$$\frac{L}{t} \quad L \quad L \quad \frac{M}{L^3} \quad \frac{L}{t^2}$$

4  $D \quad \rho \quad g$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = V \cdot D^a \cdot \rho^b \cdot g^c \quad \text{Thus:} \quad \frac{L}{t} \cdot L^a \cdot \left(\frac{M}{L^3}\right)^b \cdot \left(\frac{L}{t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M: $b = 0$	The solution to this system is:	$\Pi_1 = \frac{V}{\sqrt{g \cdot D}}$
L: $1 + a - 3b + c = 0$	$a = -\frac{1}{2} \quad b = 0 \quad c = -\frac{1}{2}$	
t: $-1 - 2c = 0$		

Check using F, L, t dimensions:  $\left(\frac{L}{t}\right) \cdot \left(\frac{t}{L}\right) = 1$

$$\Pi_2 = \lambda \cdot D^a \cdot \rho^b \cdot g^c \quad \text{Thus:} \quad L \cdot L^a \cdot \left(\frac{M}{L^3}\right)^b \cdot \left(\frac{L}{t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M: $b = 0$	The solution to this system is:	$\Pi_2 = \frac{\lambda}{D}$
L: $1 + a - 3b + c = 0$	$a = -1 \quad b = 0 \quad c = 0$	
t: $-2 \cdot c = 0$		

Check using F, L, t dimensions:  $L \cdot \frac{1}{L} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2) \quad \frac{V}{\sqrt{g \cdot D}} = f\left(\frac{\lambda}{D}\right)$  Therefore the velocity is:  $V = \sqrt{g \cdot D} \cdot f\left(\frac{\lambda}{D}\right)$

## Problem 7.21

[Difficulty: 2]

**7.21** The mean velocity,  $\bar{u}$ , for turbulent flow in a pipe or a boundary layer may be correlated using the wall shear stress,  $\tau_w$ , distance from the wall,  $y$ , and the fluid properties,  $\rho$  and  $\mu$ . Use dimensional analysis to find one dimensionless parameter containing  $\bar{u}$  and one containing  $y$  that are suitable for organizing experimental data. Show that the result may be written

$$\frac{\bar{u}}{u_*} = f\left(\frac{yu_*}{\nu}\right)$$

where  $u_* = (\tau_w/\rho)^{1/2}$  is the friction velocity.

**Given:** Functional relationship between mean velocity for turbulent flow in a pipe or boundary layer and physical parameters

**Find:** (a) Appropriate dimensionless parameters containing mean velocity and one containing the distance from the wall that are suitable for organizing experimental data.  
(b) Show that the result may be written as:

$$\frac{\bar{u}}{u_*} = f\left(\frac{yu_*}{\nu}\right) \quad \text{where } u_* = \sqrt{\frac{\tau_w}{\rho}} \text{ is the friction velocity}$$

**Solution:** We will use the Buckingham pi-theorem.

1      $\bar{u}$       $\tau_w$       $y$       $\rho$       $\mu$      n = 5 parameters

2     Select primary dimensions M, L, t:

3      $\bar{u}$       $\tau_w$       $y$       $\rho$       $\mu$

$\frac{L}{t}$	$\frac{M}{Lt^2}$	$L$	$\frac{M}{L^3}$	$\frac{M}{Lt}$	r = 3 dimensions
---------------	------------------	-----	-----------------	----------------	------------------

4      $\rho$       $y$       $\tau_w$      m = r = 3 repeating parameters

5     We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = \bar{u} \rho^a y^b \tau_w^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{M}{L \cdot t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a + c = 0$

L:  $1 - 3 \cdot a + b - c = 0$

t:  $-1 - 2 \cdot c = 0$

The solution to this system is:

$$a = \frac{1}{2} \quad b = 0 \quad c = -\frac{1}{2}$$

$$\Pi_1 = \bar{u} \sqrt{\frac{\rho}{\tau_w}} = \frac{\bar{u}}{u_*}$$

Check using F, L, t dimensions:  $\left(\frac{L}{t}\right) \cdot \left(\frac{t}{L}\right) = 1$

$$\Pi_2 = \mu \rho^a y^b \tau_w^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{M}{L \cdot t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } 1 + a + c = 0$$

$$\text{L: } -1 - 3 \cdot a + b - c = 0$$

$$\text{t: } -1 - 2 \cdot c = 0$$

The solution to this system is:

$$a = -\frac{1}{2} \quad b = -1 \quad c = -\frac{1}{2}$$

$$\Pi_2 = \frac{\mu}{y\sqrt{\rho\tau_w}} = \frac{\mu}{\rho y} \sqrt{\frac{\rho}{\tau_w}} = \frac{\mu}{\rho y u_*} = \frac{\nu}{y u_*}$$

$\Pi_2$  is the reciprocal of the Reynolds number, so we know that it checks out.

The functional relationship  
is:

$$\Pi_1 = g(\Pi_2)$$

$$\frac{\bar{u}}{u_*} = g\left(\frac{\nu}{y u_*}\right)$$

which may be rewritten as:

$$\frac{\bar{u}}{u_*} = f\left(\frac{y u_*}{\nu}\right)$$

## Problem 7.22

[Difficulty: 2]

**7.22** The energy released during an explosion,  $E$ , is a function of the time after detonation  $t$ , the blast radius  $R$  at time  $t$ , and the ambient air pressure  $p$ , and density  $\rho$ . Determine, by dimensional analysis, the general form of the expression for  $E$  in terms of the other variables.

(The solution to this problem was first devised by G.I. Taylor in the paper "The formation of a blast wave by a very intense explosion. I. Theoretical discussion," Proceedings of the Royal Society of London. Series A, Mathematical and Physical Sciences, Vol. 201, No. 1065, pages 159 - 174 (22 March 1950).)

**Given:** Functional relationship between the energy released by an explosion and other physical parameters

**Find:** Expression for  $E$  in terms of the other variables

**Solution:** We will use the Buckingham pi-theorem.

1  $E \quad t \quad R \quad p \quad \rho$  n = 5 parameters

2 Select primary dimensions M, L, t:

3  $E \quad t \quad R \quad p \quad \rho$

$$\frac{M \cdot L^2}{t^2} \quad t \quad L \quad \frac{M}{L \cdot t^2} \quad \frac{M}{L^3}$$

r = 3 dimensions

4  $\rho \quad t \quad R$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = E \cdot \rho^a \cdot t^b \cdot R^c \quad \text{Thus:} \quad \frac{M \cdot L^2}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot t^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $2 - 3 \cdot a + c = 0$

t:  $-2 + b = 0$

The solution to this system is:

$a = -1 \quad b = 2 \quad c = -5$

$$\Pi_1 = \frac{E \cdot t^2}{\rho \cdot R^5}$$

Check using F, L, t dimensions:

$$F \cdot L \cdot \frac{L^4}{F \cdot t^2} \cdot t^2 \cdot \frac{1}{L^5} = 1$$

$$\Pi_2 = p \cdot \rho^a \cdot t^b \cdot R^c$$

Thus:  $\frac{M}{L \cdot t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot t^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + c = 0$

t:  $-2 + b = 0$

The solution to this system is:

$a = -1 \quad b = 2 \quad c = -2$

$$\Pi_2 = \frac{p \cdot t^2}{\rho \cdot R^2}$$

Check using F, L, t dimensions:

$$\frac{F}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot t^2 \cdot \frac{1}{L^2} = 1$$

The functional relationship is:  $\Pi_1 = f(\Pi_2)$

$$\frac{E \cdot t^2}{\rho \cdot R^5} = f\left(\frac{p \cdot t^2}{\rho \cdot R^2}\right)$$

$$E = \frac{\rho \cdot R^5}{t^2} \cdot f\left(\frac{p \cdot t^2}{\rho \cdot R^2}\right)$$

## Problem 7.23

[Difficulty: 2]

**7.23** Capillary waves are formed on a liquid free surface as a result of surface tension. They have short wavelengths. The speed of a capillary wave depends on surface tension,  $\sigma$ , wavelength,  $\lambda$ , and liquid density,  $\rho$ . Use dimensional analysis to express wave speed as a function of these variables.

**Given:** Functional relationship between the speed of a capillary wave and other physical parameters

**Find:** An expression for  $V$  based on the other variables

**Solution:** We will use the Buckingham pi-theorem.

1     $V$      $\sigma$      $\lambda$      $\rho$     n = 4 parameters

2    Select primary dimensions M, L, t:

3     $V$      $\sigma$      $\lambda$      $\rho$     r = 3 dimensions

$$\frac{L}{t} \quad \frac{M}{t^2} \quad L \quad \frac{M}{L^3}$$

4     $\sigma$     $\lambda$     $\rho$     m = r = 3 repeating parameters

5    We have  $n - m = 1$  dimensionless group. Setting up dimensional equations:

$$\Pi_1 = V \cdot \sigma^a \cdot \lambda^b \cdot \rho^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left(\frac{M}{t^2}\right)^a \cdot L^b \cdot \left(\frac{M}{L^3}\right)^c = L^0 \cdot t^0$$

Summing exponents:

M:  $a + c = 0$

L:  $1 + b - 3 \cdot c = 0$

t:  $-1 - 2 \cdot a = 0$

The solution to this system is:

$$a = -\frac{1}{2} \quad b = \frac{1}{2} \quad c = \frac{1}{2}$$

$$\Pi_1 = V \cdot \sqrt{\frac{\lambda \cdot \rho}{\sigma}}$$

Check using F, L, t dimensions:  $\left(\frac{L}{t}\right) \cdot \sqrt{L \cdot \frac{F \cdot t^2}{L^4} \cdot \frac{L}{F}} = 1$

The functional relationship is:  $\Pi_1 = C \quad V \cdot \sqrt{\frac{\lambda \cdot \rho}{\sigma}} = C$

Therefore the velocity is:  $V = C \cdot \sqrt{\frac{\sigma}{\lambda \cdot \rho}}$



## Problem 7.25

[Difficulty: 2]

**7.25** The torque,  $T$ , of a handheld automobile buffer is a function of rotational speed,  $\omega$ , applied normal force,  $F$ , automobile surface roughness,  $e$ , buffing paste viscosity,  $\mu$ , and surface tension,  $\sigma$ . Determine the dimensionless parameters that characterize this problem.

**Given:** That automobile buffer depends on several parameters

**Find:** Dimensionless groups

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $T \quad \omega \quad F \quad e \quad \mu \quad \sigma \quad n = 6$  parameters

② Select primary dimensions M, L, t

$$\textcircled{3} \quad \left\{ \begin{array}{cccccc} T & \omega & F & e & \mu & \sigma \\ \frac{ML^2}{t^2} & \frac{1}{t} & \frac{ML}{t^2} & L & \frac{M}{Lt} & \frac{M}{t^2} \end{array} \right\} \quad r = 3 \text{ primary dimensions}$$

④  $F \quad e \quad \omega \quad m = r = 3$  repeat parameters

⑤ Then  $n - m = 3$  dimensionless groups will result. Setting up a dimensional equation,

$$\Pi_1 = F^a e^b \omega^c T = \left(\frac{ML}{t^2}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{ML^2}{t^2} = M^0 L^0 t^0$$

Summing exponents,

$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad a + b + 2 = 0 \\ t: \quad -2a - c - 2 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = -1 \\ c = 0 \end{array} \right. \quad \text{Hence} \quad \Pi_1 = \frac{T}{Fe}$$

$$\Pi_2 = F^a e^b \omega^c \mu = \left(\frac{ML}{t^2}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{M}{Lt} = M^0 L^0 t^0$$

Summing exponents,

$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad a + b - 1 = 0 \\ t: \quad -2a - c - 1 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = 2 \\ c = 1 \end{array} \right. \quad \text{Hence} \quad \Pi_2 = \frac{\mu e^2 \omega}{F}$$

$$\Pi_3 = F^a e^b \omega^c \sigma = \left(\frac{ML}{t^2}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{M}{t^2} = M^0 L^0 t^0$$

Summing exponents,

$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad a + b = 0 \\ t: \quad -2a - c - 2 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = 1 \\ c = 0 \end{array} \right. \quad \text{Hence} \quad \Pi_3 = \frac{\sigma e}{F}$$

⑥ Check using  $F, L, t$  as primary dimensions

$$\Pi_1 = \frac{FL}{FL} = [1] \qquad \Pi_2 = \frac{\frac{Ft}{L^2} L^2 \frac{1}{t}}{F} = [1] \qquad \Pi_3 = \frac{\frac{F}{L} L}{F} = [1]$$

Note: Any combination of  $\Pi_1$ ,  $\Pi_2$  and  $\Pi_3$  is a  $\Pi$  group, e.g.,  $\frac{\Pi_1}{\Pi_2} = \frac{T}{\mu\omega e^3}$ , so  $\Pi_1$ ,  $\Pi_2$  and  $\Pi_3$  are not unique!

## Problem 7.26

[Difficulty: 2]

**7.26** The power,  $\mathcal{P}$ , used by a vacuum cleaner is to be correlated with the amount of suction provided (indicated by the pressure drop,  $\Delta p$ , below the ambient room pressure). It also depends on impeller diameter,  $D$ , and width,  $d$ , motor speed,  $\omega$ , air density,  $\rho$ , and cleaner inlet and exit widths,  $d_i$  and  $d_o$ , respectively. Determine the dimensionless parameters that characterize this problem.

**Given:** That the power of a vacuum depends on various parameters

**Find:** Dimensionless groups

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $\mathcal{P} \quad \Delta p \quad D \quad d \quad \omega \quad \rho \quad d_i \quad d_o \quad n = 8$  parameters

② Select primary dimensions M, L, t

③ 
$$\left\{ \begin{array}{cccccccc} \mathcal{P} & \Delta p & D & d & \omega & \rho & d_i & d_o \\ \frac{ML^2}{t^3} & \frac{M}{Lt^2} & L & L & \frac{1}{t} & \frac{M}{L^3} & L & L \end{array} \right\} \quad r = 3 \text{ primary dimensions}$$

④  $\rho \quad D \quad \omega \quad m = r = 3$  repeat parameters

⑤ Then  $n - m = 5$  dimensionless groups will result. Setting up a dimensional equation,

$$\Pi_1 = \rho^a D^b \omega^c \mathcal{P} = \left(\frac{M}{L^3}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{ML^2}{t^3} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad -3a + b + 2 = 0 \\ t: \quad -c - 3 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = -5 \\ c = -3 \end{array} \right. \quad \text{Hence} \quad \Pi_1 = \frac{\mathcal{P}}{\rho D^5 \omega^3}$$

$$\Pi_2 = \rho^a D^b \omega^c \Delta p = \left(\frac{M}{L^3}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{M}{Lt^2} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad -3a + b - 1 = 0 \\ t: \quad -c - 2 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = -2 \\ c = -2 \end{array} \right. \quad \text{Hence} \quad \Pi_2 = \frac{\Delta p}{\rho D^2 \omega^2}$$

The other  $\Pi$  groups can be found by inspection:  $\Pi_3 = \frac{d}{D} \quad \Pi_4 = \frac{d_i}{D} \quad \Pi_5 = \frac{d_o}{D}$

⑥ Check using  $F, L, t$  as primary dimensions

$$\Pi_1 = \frac{\frac{FL}{t}}{\frac{Ft^2}{L^4} L^5 \frac{1}{t^3}} = [1] \quad \Pi_2 = \frac{\frac{F}{L^2}}{\frac{Ft^2}{L^4} L^2 \frac{1}{t^2}} = [1] \quad \Pi_3 = \Pi_4 = \Pi_5 = \frac{L}{L} = [1]$$

Note: Any combination of  $\Pi_1, \Pi_2$  and  $\Pi_3$  is a  $\Pi$  group, e.g.,  $\frac{\Pi_1}{\Pi_2} = \frac{\mathcal{P}}{\Delta p D^3 \omega}$ , so the  $\Pi$ 's are not unique!

## Problem 7.27

[Difficulty: 2]

**7.27** The load-carrying capacity,  $W$ , of a journal bearing is known to depend on its diameter,  $D$ , length,  $l$ , and clearance,  $c$ , in addition to its angular speed,  $\omega$ , and lubricant viscosity,  $\mu$ . Determine the dimensionless parameters that characterize this problem.

**Given:** Functional relationship between the load bearing capacity of a journal bearing and other physical parameters

**Find:** Dimensionless parameters that characterize the problem.

**Solution:** We will use the Buckingham pi-theorem.

1     $W$      $D$      $l$      $c$      $\omega$      $\mu$     n = 6 parameters

2    Select primary dimensions F, L, t:

3     $W$      $D$      $l$      $c$      $\omega$      $\mu$     r = 3 dimensions

$F$      $L$      $L$      $L$      $\frac{1}{t}$      $\frac{F \cdot t}{L^2}$

4     $D$      $\omega$      $\mu$     m = r = 3 repeating parameters

5    We have  $n - m = 3$  dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = W \cdot D^a \cdot \omega^b \cdot \mu^c \quad \text{Thus:} \quad F \cdot L^a \cdot \left(\frac{1}{t}\right)^b \cdot \left(\frac{F \cdot t}{L^2}\right)^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

F:  $1 + c = 0$

L:  $a - 2 \cdot c = 0$

t:  $-b + c = 0$

The solution to this system is:

$a = -2$      $b = -1$      $c = -1$

$$\Pi_1 = \frac{W}{D^2 \cdot \omega \cdot \mu}$$

Check using M, L, t dimensions:  $\frac{M \cdot L}{t^2} \cdot \frac{1}{L^2} \cdot t \cdot \frac{L \cdot t}{M} = 1$     By inspection, we can see that:     $\Pi_2 = \frac{l}{D}$      $\Pi_3 = \frac{c}{D}$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3)$

$$\frac{W}{D^2 \cdot \omega \cdot \mu} = f\left(\frac{l}{D}, \frac{c}{D}\right)$$

## Problem 7.28 (In Excel)

[Difficulty: 2]

**7.28** The time,  $t$ , for oil to drain out of a viscosity calibration container depends on the fluid viscosity,  $\mu$ , and density,  $\rho$ , the orifice diameter,  $d$ , and gravity,  $g$ . Use dimensional analysis to find the functional dependence of  $t$  on the other variables. Express  $t$  in the simplest possible form.

**Given:** That drain time depends on fluid viscosity and density, orifice diameter, and gravity

**Find:** Functional dependence of  $t$  on other variables

**Solution:**

We will use the workbook of Example 7.1, modified for the current problem

The number of parameters is:  $n = 5$   
 The number of primary dimensions is:  $r = 3$   
 The number of repeat parameters is:  $m = r = 3$   
 The number of  $\Pi$  groups is:  $n - m = 2$

Enter the dimensions (**M, L, t**) of the repeating parameters, and of up to four other parameters (for up to four  $\Pi$  groups). The spreadsheet will compute the exponents  $a, b, c$  for each.

**REPEATING PARAMETERS:** Choose  $\rho, g, d$

	<b>M</b>	<b>L</b>	<b>t</b>
$\rho$	1	-3	
$g$		1	-2
$d$		1	

**$\Pi$  GROUPS:**

$t$	<b>M</b>	<b>L</b>	<b>t</b>	$\mu$	<b>M</b>	<b>L</b>	<b>t</b>
	0	0	1		1	-1	-1
$\Pi_1:$	$a =$	0		$\Pi_2:$	$a =$	-1	
	$b =$	0.5			$b =$	-0.5	
	$c =$	-0.5			$c =$	-1.5	

The following  $\Pi$  groups from Example 7.1 are not used:

$\Pi_3:$	<b>M</b>	<b>L</b>	<b>t</b>	$\Pi_4:$	<b>M</b>	<b>L</b>	<b>t</b>
	0	0	0		0	0	0
	$a =$	0			$a =$	0	
	$b =$	0			$b =$	0	
	$c =$	0			$c =$	0	

Hence  $\Pi_1 = t \sqrt{\frac{g}{d}}$  and  $\Pi_2 = \frac{\mu}{\rho g^{\frac{1}{2}} d^{\frac{3}{2}}} \rightarrow \frac{\mu^2}{\rho^2 g d^3}$  with  $\Pi_1 = f(\Pi_2)$

The final result is  $t = \sqrt{\frac{d}{g}} f\left(\frac{\mu^2}{\rho^2 g d^3}\right)$

## Problem 7.29

[Difficulty: 2]

**7.29** The power per unit cross-sectional area,  $E$ , transmitted by a sound wave is a function of wave speed,  $V$ , medium density,  $\rho$ , wave amplitude,  $r$ , and wave frequency,  $n$ . Determine, by dimensional analysis, the general form of the expression for  $E$  in terms of the other variables.

**Given:** Functional relationship between the power transmitted by a sound wave and other physical parameters

**Find:** Expression for  $E$  in terms of the other variables

**Solution:** We will use the Buckingham pi-theorem.

1  $E \quad V \quad \rho \quad r \quad n$  n = 5 parameters

2 Select primary dimensions M, L, t:

3  $E \quad V \quad \rho \quad r \quad n$

$$\frac{M}{t^3} \quad \frac{L}{t} \quad \frac{M}{L^3} \quad L \quad \frac{1}{t} \quad \text{r = 3 dimensions}$$

4  $\rho \quad V \quad r$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = E \cdot \rho^a \cdot V^b \cdot r^c \quad \text{Thus:} \quad \frac{M}{t^3} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\begin{aligned} \text{M: } & 1 + a = 0 \\ \text{L: } & -3 \cdot a + b + c = 0 \\ \text{t: } & -3 - b = 0 \end{aligned}$$

The solution to this system is:

$$a = -1 \quad b = -3 \quad c = 0$$

$$\Pi_1 = \frac{E}{\rho \cdot V^3}$$

Check using F, L, t dimensions:

$$\frac{F}{L \cdot t} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^3}{L^3} = 1$$

$$\Pi_2 = n \cdot \rho^a \cdot V^b \cdot r^c \quad \text{Thus:} \quad \frac{1}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\begin{aligned} \text{M: } & a = 0 \\ \text{L: } & -3 \cdot a + b + c = 0 \\ \text{t: } & -1 - b = 0 \end{aligned}$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = 1$$

$$\Pi_2 = \frac{n \cdot r}{V}$$

Check using F, L, t dimensions:

$$\frac{1}{t} \cdot L \cdot \frac{t}{L} = 1$$

The functional relationship is:  $\Pi_1 = f(\Pi_2)$

$$\frac{E}{\rho \cdot V^3} = f\left(\frac{n \cdot r}{V}\right)$$

$$E = \rho \cdot V^3 \cdot f\left(\frac{n \cdot r}{V}\right)$$

## Problem 7.30

[Difficulty: 2]

**7.30** You are asked to find a set of dimensionless parameters to organize data from a laboratory experiment, in which a tank is drained through an orifice from initial liquid level  $h_0$ . The time,  $\tau$ , to drain the tank depends on tank diameter,  $D$ , orifice diameter,  $d$ , acceleration of gravity,  $g$ , liquid density,  $\rho$ , and liquid viscosity,  $\mu$ . How many dimensionless parameters will result? How many repeating variables must be selected to determine the dimensionless parameters? Obtain the  $\Pi$  parameter that contains the viscosity.

**Given:** Functional relationship between the time needed to drain a tank through an orifice plate and other physical parameters

**Find:** (a) the number of dimensionless parameters  
 (b) the number of repeating variables  
 (c) the  $\Pi$  term which contains the viscosity

**Solution:** We will use the Buckingham pi-theorem.

1     $\tau$      $h_0$      $D$      $d$      $g$      $\rho$      $\mu$     n = 7 parameters

2    Select primary dimensions M, L, t:

3     $\tau$      $h_0$      $D$      $d$      $g$      $\rho$      $\mu$

	T	L	L	L	L	$\frac{L}{t^2}$	$\frac{M}{L^3}$	$\frac{M}{L \cdot t}$	r = 3 dimensions
--	---	---	---	---	---	-----------------	-----------------	-----------------------	------------------

4     $\rho$      $d$      $g$     m = r = 3 repeating parameters    We have n - m = 4 dimensionless groups.

5    Setting up dimensional equation including the viscosity:

$$\Pi_1 = \mu \cdot \rho^a \cdot d^b \cdot g^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-1 - 2 \cdot c = 0$

The solution to this system is:

$$a = -1 \quad b = -\frac{3}{2} \quad c = -\frac{1}{2}$$

$$\Pi_1 = \frac{\mu}{\rho \cdot d^{\frac{3}{2}} \cdot g^{\frac{1}{2}}}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^2} \cdot \frac{t}{L^2} = 1$$

## Problem 7.31

[Difficulty: 3]

**7.31** A continuous belt moving vertically through a bath of viscous liquid drags a layer of liquid, of thickness  $h$ , along with it. The volume flow rate of liquid,  $Q$ , is assumed to depend on  $\mu$ ,  $\rho$ ,  $g$ ,  $h$ , and  $V$ , where  $V$  is the belt speed. Apply dimensional analysis to predict the form of dependence of  $Q$  on the other variables.

**Given:** Functional relationship between the flow rate of viscous liquid dragged out of a bath and other physical parameters

**Find:** Expression for  $Q$  in terms of the other variables

**Solution:** We will use the Buckingham pi-theorem.

1  $Q \quad \mu \quad \rho \quad g \quad h \quad V$   $n = 6$  parameters

2 Select primary dimensions M, L, t:

3  $Q \quad \mu \quad \rho \quad g \quad h \quad V$

$\frac{L^3}{t}$	$\frac{M}{L \cdot t}$	$\frac{M}{L^3}$	$\frac{L}{t^2}$	$L$	$\frac{L}{t}$	$r = 3$ dimensions
-----------------	-----------------------	-----------------	-----------------	-----	---------------	--------------------

4  $\rho \quad V \quad h$   $m = r = 3$  repeating parameters

5 We have  $n - m = 3$  dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = Q \cdot \rho^a \cdot V^b \cdot h^c \quad \text{Thus:} \quad \frac{L^3}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: \quad a = 0$$

$$L: \quad 3 - 3 \cdot a + b + c = 0$$

$$t: \quad -1 - b = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = -2$$

$$\Pi_1 = \frac{Q}{V \cdot h^2}$$

Check using F, L, t dimensions:

$$\frac{L^3}{t} \cdot \frac{t}{L} \cdot \frac{1}{L^2} = 1$$

$$\Pi_2 = \mu \cdot \rho^a \cdot V^b \cdot h^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: \quad 1 + a = 0$$

$$L: \quad -1 - 3 \cdot a + b + c = 0$$

$$t: \quad -1 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = -1$$

$$\Pi_2 = \frac{\mu}{\rho \cdot V \cdot h}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$$

$$\Pi_3 = g \cdot \rho^a \cdot V^b \cdot h^c \quad \text{Thus:} \quad \frac{L}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

The solution to this system is:

$$\Pi_3 = \frac{g \cdot h}{V^2}$$

M:  $a = 0$

$a = 0 \quad b = -2 \quad c = 1$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-2 - b = 0$

Check using F, L, t dimensions:  $\frac{L}{t^2} \cdot L \cdot \frac{t^2}{L^2} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3)$        $\frac{Q}{V \cdot h^2} = f\left(\frac{\rho \cdot V \cdot h}{\mu}, \frac{V^2}{g \cdot h}\right)$        $Q = V \cdot h^2 \cdot f\left(\frac{\rho \cdot V \cdot h}{\mu}, \frac{V^2}{g \cdot h}\right)$

## Problem 7.32

[Difficulty: 2]

**7.32** The power,  $\mathcal{P}$ , required to drive a fan is believed to depend on fluid density,  $\rho$ , volume flow rate,  $Q$ , impeller diameter,  $D$ , and angular velocity,  $\omega$ . Use dimensional analysis to determine the dependence of  $\mathcal{P}$  on the other variables.

**Given:** Functional relationship between the power required to drive a fan and other physical parameters

**Find:** Expression for  $P$  in terms of the other variables

**Solution:** We will use the Buckingham pi-theorem.

1  $P \quad \rho \quad Q \quad D \quad \omega$  n = 5 parameters

2 Select primary dimensions M, L, t:

3  $P \quad \rho \quad Q \quad D \quad \omega$  r = 3 dimensions

$$\frac{M \cdot L^2}{t^3} \quad \frac{M}{L^3} \quad \frac{L^3}{t} \quad L \quad \frac{1}{t}$$

4  $\rho \quad D \quad \omega$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = P \cdot \rho^a \cdot D^b \cdot \omega^c \quad \text{Thus:} \quad \frac{M \cdot L^2}{t^3} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{1}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: 2 - 3 \cdot a + b = 0$$

$$t: -3 - c = 0$$

The solution to this system is:

$$a = -1 \quad b = -5 \quad c = -3$$

$$\Pi_1 = \frac{P}{\rho \cdot D^5 \cdot \omega^3}$$

Check using F, L, t dimensions:

$$\frac{F \cdot L}{t} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^5} \cdot t^3 = 1$$

$$\Pi_2 = Q \cdot \rho^a \cdot D^b \cdot \omega^c \quad \text{Thus:} \quad \frac{L^3}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{1}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: a = 0$$

$$L: 3 - 3 \cdot a + b = 0$$

$$t: -1 - c = 0$$

The solution to this system is:

$$a = 0 \quad b = -3 \quad c = -1$$

$$\Pi_2 = \frac{Q}{D^3 \cdot \omega}$$

Check using F, L, t dimensions:

$$\frac{1}{t} \cdot L \cdot \frac{t}{L} = 1$$

The functional relationship is:  $\Pi_1 = f(\Pi_2)$

$$\frac{P}{\rho \cdot D^5 \cdot \omega^3} = f\left(\frac{Q}{D^3 \cdot \omega}\right)$$

$$P = \rho \cdot D^5 \cdot \omega^3 \cdot f\left(\frac{Q}{D^3 \cdot \omega}\right)$$

## Problem 7.33

[Difficulty: 2]

**7.33** In a fluid mechanics laboratory experiment a tank of water, with diameter  $D$ , is drained from initial level  $h_0$ . The smoothly rounded drain hole has diameter  $d$ . Assume the mass flow rate from the tank is a function of  $h$ ,  $D$ ,  $d$ ,  $g$ ,  $\rho$ , and  $\mu$ , where  $g$  is the acceleration of gravity and  $\rho$  and  $\mu$  are fluid properties. Measured data are to be correlated in dimensionless form. Determine the number of dimensionless parameters that will result. Specify the number of repeating parameters that must be selected to determine the dimensionless parameters. Obtain the  $\Pi$  parameter that contains the viscosity.

**Given:** Functional relationship between the mass flow rate exiting a tank through a rounded drain hole and other physical parameters

**Find:** (a) Number of dimensionless parameters that will result  
 (b) Number of repeating parameters  
 (c) The  $\Pi$  term that contains the viscosity

**Solution:** We will use the Buckingham pi-theorem.

1     $m$      $h_0$      $D$      $d$      $g$      $\rho$      $\mu$  n = 7 parameters

2    Select primary dimensions M, L, t:

3     $m$      $h_0$      $D$      $d$      $g$      $\rho$      $\mu$  r = 3 dimensions

	$\frac{M}{t}$	L	L	L	$\frac{L}{t^2}$	$\frac{M}{L^3}$	$\frac{M}{L \cdot t}$	
--	---------------	---	---	---	-----------------	-----------------	-----------------------	--

We have  $n - r = 4$  dimensionless groups.

4     $\rho$      $d$      $g$  m = r = 3 repeating parameters

5    Setting up dimensional equation involving the viscosity:

$$\Pi_1 = \mu \cdot \rho^a \cdot d^b \cdot g^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{L}{t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-1 - 2 \cdot c = 0$

The solution to this system is:

$$a = -1 \quad b = -\frac{3}{2} \quad c = -\frac{1}{2}$$

$$\Pi_1 = \frac{\mu}{\rho \cdot \sqrt{d^3 \cdot g}}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^2} \cdot \frac{t}{L^2} = 1$$

## Problem 7.34

[Difficulty: 3]

**7.34** Cylindrical water tanks are frequently found on the tops of tall buildings. When a tank is filled with water, the bottom of the tank typically deflects under the weight of the water inside. The deflection  $\delta$  is a function of the tank diameter  $D$ , the height of water  $h$ , the thickness of the tank bottom  $d$ , the specific weight of the water  $\gamma$ , and the modulus of elasticity of the tank material  $E$ . Determine the functional relationship among these parameters using dimensionless groups.

**Given:** Functional relationship between the deflection of the bottom of a cylindrical tank and other physical parameters

**Find:** Functional relationship between these parameters using dimensionless groups.

**Solution:** We will use the Buckingham pi-theorem.

1  $\delta$   $D$   $h$   $d$   $\gamma$   $E$  n = 6 parameters

2 Select primary dimensions F, L, t:

3  $\delta$   $D$   $h$   $d$   $\gamma$   $E$  r = 2 dimensions

$L$   $L$   $L$   $L$   $\frac{F}{L^3}$   $\frac{F}{L^2}$

4  $D$   $\gamma$  m = r = 2 repeating parameters We have n - m = 4 dimensionless groups.

5 Setting up dimensional equations:

$$\Pi_1 = \delta \cdot D^a \cdot \gamma^b \quad \text{Thus:} \quad L \cdot L^a \cdot \left(\frac{F}{L^3}\right)^b = F^0 \cdot L^0$$

Summing exponents:

F:  $b = 0$

L:  $1 + a - 3 \cdot b = 0$

The solution to this system is:

$a = -1$   $b = 0$

$$\Pi_1 = \frac{\delta}{D}$$

Check using M, L, t dimensions:  $L \cdot \frac{1}{L} = 1$

Now since  $h$  and  $d$  have the same dimensions as  $\delta$ , it would follow that the the next two pi terms would be:  $\Pi_2 = \frac{h}{D}$   $\Pi_3 = \frac{d}{D}$

$$\Pi_4 = E \cdot D^a \cdot \gamma^b \quad \text{Thus:} \quad \frac{F}{L^2} \cdot L^a \cdot \left(\frac{F}{L^3}\right)^b = F^0 \cdot L^0$$

Summing exponents:

F:  $1 + b = 0$

L:  $-2 + a - 3 \cdot b = 0$

The solution to this system is:

$a = -1$   $b = -1$

$$\Pi_4 = \frac{E}{D \cdot \gamma}$$

Check using M, L, t dimensions:  $\frac{M}{L \cdot t^2} \cdot \frac{1}{L} \cdot \frac{L^2 \cdot t^2}{M} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3, \Pi_4)$   $\frac{\delta}{D} = f\left(\frac{h}{D}, \frac{d}{D}, \frac{E}{D \cdot \gamma}\right)$

(For further reading, one should consult an appropriate text, such as *Advanced Strength of Materials* by Cook and Young)

## Problem 7.35

[Difficulty: 3]

**7.35** Small droplets of liquid are formed when a liquid jet breaks up in spray and fuel injection processes. The resulting droplet diameter,  $d$ , is thought to depend on liquid density, viscosity, and surface tension, as well as jet speed,  $V$ , and diameter,  $D$ . How many dimensionless ratios are required to characterize this process? Determine these ratios.

**Given:** Functional relationship between the diameter of droplets formed during jet breakup and other physical parameters

**Find:** (a) The number of dimensionless parameters needed to characterize the process  
(b) The ratios ( $\Pi$ -terms)

**Solution:** We will use the Buckingham pi-theorem.

1  $d \quad \rho \quad \mu \quad \sigma \quad V \quad D$  n = 6 parameters

2 Select primary dimensions M, L, t:

3  $d \quad \rho \quad \mu \quad \sigma \quad V \quad D$  r = 3 dimensions

$L \quad \frac{M}{L^3} \quad \frac{M}{L \cdot t} \quad \frac{M}{t^2} \quad \frac{L}{t} \quad L$

4  $\rho \quad V \quad D$  m = r = 3 repeating parameters We have n - m = 3 dimensionless groups.

5 Setting up dimensional equations:

$$\Pi_1 = d \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-b = 0$

The solution to this system is:

$a = 0 \quad b = 0 \quad c = -1$

$$\Pi_1 = \frac{d}{D}$$

Check using F, L, t dimensions:

$$L \cdot \frac{1}{L} = 1$$

$$\Pi_2 = \mu \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-1 - b = 0$

The solution to this system is:

$a = -1 \quad b = -1 \quad c = -1$

$$\Pi_2 = \frac{\mu}{\rho \cdot V \cdot D}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$$

$$\Pi_3 = \sigma \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-3 \cdot a + b + c = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = -1 \quad b = -2 \quad c = -1$

$$\Pi_3 = \frac{\sigma}{\rho \cdot V^2 \cdot D}$$


Check using F, L, t dimensions:

$$\frac{F}{L} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} \cdot \frac{1}{L} = 1$$

## Problem 7.36

[Difficulty: 3]

**7.36** The sketch shows an air jet discharging vertically. Experiments show that a ball placed in the jet is suspended in a stable position. The equilibrium height of the ball in the jet is found to depend on  $D$ ,  $d$ ,  $V$ ,  $\rho$ ,  $\mu$ , and  $W$ , where  $W$  is the weight of the ball. Dimensional analysis is suggested to correlate experimental data. Find the  $\Pi$  parameters that characterize this phenomenon.



**Given:** Functional relationship between the height of a ball supported by a vertical air jet and other physical parameters

**Find:** The  $\Pi$  terms that characterize this phenomenon

**Solution:** We will use the Buckingham pi-theorem.

1     $h$      $D$      $d$      $V$      $\rho$      $\mu$      $W$     n = 7 parameters

2    Select primary dimensions M, L, t:

3     $h$      $D$      $d$      $V$      $\rho$      $\mu$      $W$     r = 3 dimensions

L    L    L     $\frac{L}{t}$      $\frac{M}{L^3}$      $\frac{M}{L \cdot t}$      $\frac{M \cdot L}{t^2}$

4     $\rho$      $V$      $d$     m = r = 3 repeating parameters

5    We have n - m = 4 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = h \cdot \rho^a \cdot V^b \cdot d^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-b = 0$

The solution to this system is:

$a = 0$      $b = 0$      $c = -1$

$$\Pi_1 = \frac{h}{d}$$

Check using F, L, t dimensions:

$$L \cdot \frac{1}{L} = 1$$

$$\Pi_2 = D \cdot \rho^a \cdot V^b \cdot d^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-b = 0$

The solution to this system is:

$a = 0$      $b = 0$      $c = -1$

$$\Pi_2 = \frac{D}{d}$$

Check using F, L, t dimensions:

$$L \cdot \frac{1}{L} = 1$$

$$\Pi_3 = \mu \cdot \rho^a \cdot V^b \cdot d^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } 1 + a = 0$$

$$\text{L: } -1 - 3 \cdot a + b + c = 0$$

$$\text{t: } -1 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = -1$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$$

$$\Pi_3 = \frac{\mu}{\rho \cdot V \cdot d}$$

$$\Pi_4 = W \cdot \rho^a \cdot V^b \cdot d^c \quad \text{Thus:} \quad \frac{M \cdot L}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } 1 + a = 0$$

$$\text{L: } 1 - 3 \cdot a + b + c = 0$$

$$\text{t: } -2 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -2 \quad c = -2$$

Check using F, L, t dimensions:

$$F \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} \cdot \frac{1}{L^2} = 1$$

$$\Pi_4 = \frac{W}{\rho \cdot V^2 \cdot d^2}$$

## Problem 7.37 (In Excel)

[Difficulty: 3]

**7.37** The diameter,  $d$ , of the dots made by an ink jet printer depends on the ink viscosity,  $\mu$ , density,  $\rho$ , and surface tension,  $\sigma$ , the nozzle diameter,  $D$ , the distance,  $L$ , of the nozzle from the paper surface, and the ink jet velocity,  $V$ . Use dimensional analysis to find the  $\Pi$  parameters that characterize the ink jet's behavior.

**Given:** That dot size depends on ink viscosity, density, and surface tension, and geometry

**Find:**  $\Pi$  groups

**Solution:**

We will use the workbook of Example 7.1, modified for the current problem

The number of parameters is:  $n = 7$   
 The number of primary dimensions is:  $r = 3$   
 The number of repeat parameters is:  $m = r = 3$   
 The number of  $\Pi$  groups is:  $n - m = 4$

Enter the dimensions (**M, L, t**) of the repeating parameters, and of up to four other parameters (for up to four  $\Pi$  groups). The spreadsheet will compute the exponents  $a, b,$  and  $c$  for each.

**REPEATING PARAMETERS:** Choose  $\rho, V, D$

	<b>M</b>	<b>L</b>	<b>t</b>
$\rho$	1	-3	
$V$		1	-1
$D$		1	

**$\Pi$  GROUPS:**

	<b>M</b>	<b>L</b>	<b>t</b>
$d$	0	1	0
$\Pi_1:$	$a =$	0	
	$b =$	0	
	$c =$	-1	

	<b>M</b>	<b>L</b>	<b>t</b>
$\mu$	1	-1	-1
$\Pi_2:$	$a =$	-1	
	$b =$	-1	
	$c =$	-1	

	<b>M</b>	<b>L</b>	<b>t</b>
$\sigma$	1	0	-2
$\Pi_3:$	$a =$	-1	
	$b =$	-2	
	$c =$	-1	

	<b>M</b>	<b>L</b>	<b>t</b>
$L$	0	1	0
$\Pi_4:$	$a =$	0	
	$b =$	0	
	$c =$	-1	

Hence  $\Pi_1 = \frac{d}{D}$      $\Pi_2 = \frac{\mu}{\rho V D} \rightarrow \frac{\rho V D}{\mu}$      $\Pi_3 = \frac{\sigma}{\rho V^2 D}$      $\Pi_4 = \frac{L}{D}$

Note that groups  $\Pi_1$  and  $\Pi_4$  can be obtained by inspection

## Problem 7.38 (In Excel)

[Difficulty: 3]

**7.38** The diameter,  $d$ , of bubbles produced by a bubble-making toy depends on the soapy water viscosity,  $\mu$ , density,  $\rho$ , and surface tension,  $\sigma$ , the ring diameter,  $D$ , and the pressure differential,  $\Delta p$ , generating the bubbles. Use dimensional analysis to find the  $\Pi$  parameters that characterize this phenomenon.

**Given:** Bubble size depends on viscosity, density, surface tension, geometry and pressure

**Find:**  $\Pi$  groups

**Solution:**

We will use the workbook of Example 7.1, modified for the current problem

The number of parameters is:  $n = 6$   
 The number of primary dimensions is:  $r = 3$   
 The number of repeat parameters is:  $m = r = 3$   
 The number of  $\Pi$  groups is:  $n - m = 3$

Enter the dimensions (**M, L, t**) of the repeating parameters, and of up to four other parameters (for up to four  $\Pi$  groups). The spreadsheet will compute the exponents  $a, b$ , and  $c$  for each.

**REPEATING PARAMETERS:** Choose  $\rho, \Delta p, D$

	<b>M</b>	<b>L</b>	<b>t</b>
$\rho$	1	-3	
$\Delta p$	1	-1	-2
$D$		1	

**$\Pi$  GROUPS:**

	<b>M</b>	<b>L</b>	<b>t</b>
$d$	0	1	0
$\Pi_1:$	$a =$	<b>0</b>	
	$b =$	<b>0</b>	
	$c =$	<b>-1</b>	

	<b>M</b>	<b>L</b>	<b>t</b>
$\mu$	1	-1	-1
$\Pi_2:$	$a =$	<b>-0.5</b>	
	$b =$	<b>-0.5</b>	
	$c =$	<b>-1</b>	

	<b>M</b>	<b>L</b>	<b>t</b>
$\sigma$	1	0	-2
$\Pi_3:$	$a =$	<b>0</b>	
	$b =$	<b>-1</b>	
	$c =$	<b>-1</b>	

	<b>M</b>	<b>L</b>	<b>t</b>
$\sigma$	0	0	0
$\Pi_4:$	$a =$	<b>0</b>	
	$b =$	<b>0</b>	
	$c =$	<b>0</b>	

Hence  $\Pi_1 = \frac{d}{D}$      $\Pi_2 = \frac{\mu}{\rho^{\frac{1}{2}} \Delta p^{\frac{1}{2}} D} \rightarrow \frac{\mu^2}{\rho \Delta p D^2}$      $\Pi_3 = \frac{\sigma}{D \Delta p}$

Note that the  $\Pi_1$  group can be obtained by inspection

## Problem 7.39 (In Excel)

[Difficulty: 3]

**7.39** The terminal speed  $V$  of shipping boxes sliding down an incline on a layer of air (injected through numerous pinholes in the incline surface) depends on the box mass,  $m$ , and base area,  $A$ , gravity,  $g$ , the incline angle,  $\theta$ , the air viscosity,  $\mu$ , and the air layer thickness,  $\delta$ . Use dimensional analysis to find the  $\Pi$  parameters that characterize this phenomenon.

**Given:** Speed depends on mass, area, gravity, slope, and air viscosity and thickness

**Find:**  $\Pi$  groups

**Solution:**

We will use the workbook of Example 7.1, modified for the current problem

The number of parameters is:  $n = 7$   
 The number of primary dimensions is:  $r = 3$   
 The number of repeat parameters is:  $m = r = 3$   
 The number of  $\Pi$  groups is:  $n - m = 4$

Enter the dimensions (**M, L, t**) of the repeating parameters, and of up to four other parameters (for up to four  $\Pi$  groups). The spreadsheet will compute the exponents  $a, b,$  and  $c$  for each.

**REPEATING PARAMETERS:** Choose  $g, \delta, m$

	<b>M</b>	<b>L</b>	<b>t</b>
$g$		1	-2
$\delta$		1	
$m$	1		

**$\Pi$  GROUPS:**

		<b>M</b>	<b>L</b>	<b>t</b>			<b>M</b>	<b>L</b>	<b>t</b>
	$V$	0	1	-1		$\mu$	1	-1	-1
$\Pi_1:$	$a =$	-0.5			$\Pi_2:$	$a =$	-0.5		
	$b =$	-0.5				$b =$	1.5		
	$c =$	0				$c =$	-1		
	$\theta$	0	0	0		$A$	0	2	0
$\Pi_3:$	$a =$	0			$\Pi_4:$	$a =$	0		
	$b =$	0				$b =$	-2		
	$c =$	0				$c =$	0		

$$\text{Hence } \Pi_1 = \frac{V}{g^{\frac{1}{2}} \delta^{\frac{1}{2}}} \rightarrow \frac{V^2}{g\delta} \quad \Pi_2 = \frac{\mu \delta^{\frac{3}{2}}}{g^{\frac{1}{2}} m} \rightarrow \frac{\mu^2 \delta^3}{m^2 g} \quad \Pi_3 = \theta \quad \Pi_4 = \frac{A}{\delta^2}$$

Note that the  $\Pi_1, \Pi_3$  and  $\Pi_4$  groups can be obtained by inspection

## Problem 7.40

[Difficulty: 2]

**7.40** The length of the wake  $w$  behind an airfoil is a function of the flow speed  $V$ , chord length  $L$ , thickness  $t$ , and fluid density  $\rho$  and viscosity  $\mu$ . Find the dimensionless parameters that characterize this phenomenon.

**Given:** Functional relationship between the length of a wake behind an airfoil and other physical parameters

**Find:** The  $\Pi$  terms that characterize this phenomenon

**Solution:** We will use the Buckingham pi-theorem.

1  $w \quad V \quad L \quad t \quad \rho \quad \mu$  n = 6 parameters

2 Select primary dimensions M, L, t:

3  $w \quad V \quad L \quad t \quad \rho \quad \mu$   
 $L \quad \frac{L}{t} \quad L \quad L \quad \frac{M}{L^3} \quad \frac{M}{L \cdot t}$  r = 3 dimensions

4  $\rho \quad V \quad L$  m = r = 3 repeating parameters

5 We have n - m = 3 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = w \cdot \rho^a \cdot V^b \cdot L^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-b = 0$

The solution to this system is:

$a = 0 \quad b = 0 \quad c = -1$

$$\Pi_1 = \frac{w}{L}$$

Check using F, L, t dimensions:

$$L \cdot \frac{1}{L} = 1$$

$$\Pi_2 = t \cdot \rho^a \cdot V^b \cdot L^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-b = 0$

The solution to this system is:

$a = 0 \quad b = 0 \quad c = -1$

$$\Pi_2 = \frac{t}{L}$$

Check using F, L, t dimensions:

$$L \cdot \frac{1}{L} = 1$$

$$\Pi_3 = \mu \cdot \rho^a \cdot V^b \cdot L^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-1 - b = 0$

The solution to this system is:

$a = -1 \quad b = -1 \quad c = -1$

$$\Pi_3 = \frac{\mu}{\rho \cdot V \cdot L}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$$

## Problem 7.41

[Difficulty: 2]

**7.41** A washing machine agitator is to be designed. The power,  $\mathcal{P}$ , required for the agitator is to be correlated with the amount of water used (indicated by the depth,  $H$ , of the water). It also depends on the agitator diameter,  $D$ , height,  $h$ , maximum angular velocity,  $\omega_{\max}$ , and frequency of oscillations,  $f$ , and water density,  $\rho$ , and viscosity,  $\mu$ . Determine the dimensionless parameters that characterize this problem.

**Given:** That the power of a washing machine agitator depends on various parameters

**Find:** Dimensionless groups

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $\mathcal{P} \quad H \quad D \quad h \quad \omega_{\max} \quad f \quad \rho \quad \mu \quad n = 8$  parameters

② Select primary dimensions M, L, t

③ 
$$\left\{ \begin{array}{cccccccc} \mathcal{P} & H & D & h & \omega_{\max} & f & \rho & \mu \\ \frac{ML^2}{t^3} & L & L & L & \frac{1}{t} & \frac{1}{t} & \frac{M}{L^3} & \frac{M}{Lt} \end{array} \right\} \quad r = 3 \text{ primary dimensions}$$

④  $\rho \quad D \quad \omega_{\max} \quad m = r = 3$  repeat parameters

⑤ Then  $n - m = 5$  dimensionless groups will result. Setting up a dimensional equation,

$$\Pi_1 = \rho^a D^b \omega_{\max}^c \mathcal{P} = \left(\frac{M}{L^3}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{ML^2}{t^3} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad -3a + b + 2 = 0 \\ t: \quad -c - 3 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = -5 \\ c = -3 \end{array} \right. \quad \text{Hence} \quad \Pi_1 = \frac{\mathcal{P}}{\rho D^5 \omega_{\max}^3}$$

$$\Pi_2 = \rho^a D^b \omega_{\max}^c \mu = \left(\frac{M}{L^3}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{M}{Lt} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad -3a + b - 1 = 0 \\ t: \quad -c - 1 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = -2 \\ c = -1 \end{array} \right. \quad \text{Hence} \quad \Pi_2 = \frac{\mu}{\rho D^2 \omega_{\max}}$$

The other  $\Pi$  groups can be found by inspection:  $\Pi_3 = \frac{H}{D} \quad \Pi_4 = \frac{h}{D} \quad \Pi_5 = \frac{f}{\omega_{\max}}$

⑥ Check using  $F, L, t$  as primary dimensions

$$\Pi_1 = \frac{\frac{FL}{t}}{\frac{Ft^2}{L^4} L^5 \frac{1}{t^3}} = [1] \quad \Pi_2 = \frac{\frac{Ft}{L^2}}{\frac{Ft^2}{L^4} L^2 \frac{1}{t}} = [1] \quad \Pi_3 = \Pi_4 = \Pi_5 = [1]$$

Note: Any combination of  $\Pi$ 's is a  $\Pi$  group, e.g.,  $\frac{\Pi_1}{\Pi_2} = \frac{\mathcal{P}}{D^3 \omega_{\max}^2 \mu}$ , so the  $\Pi$ 's are not unique!

## Problem 7.42

[Difficulty: 3]

**7.42** Choked-flow nozzles are often used to meter the flow of gases through piping systems. The mass flow rate of gas is thought to depend on nozzle area  $A$ , pressure  $p$ , and temperature  $T$  upstream of the meter, and the gas constant  $R$ . Determine how many independent  $\Pi$  parameters can be formed for this problem. State the functional relationship for the mass flow rate in terms of the dimensionless parameters.

**Given:** Functional relationship between the mass flow rate of gas through a choked-flow nozzle and other physical parameters

**Find:** (a) How many independent  $\Pi$  terms that characterize this phenomenon  
 (b) Find the  $\Pi$  terms  
 (c) State the functional relationship for the mass flow rate in terms of the  $\Pi$  terms

**Solution:** We will use the Buckingham pi-theorem.

1     $m$      $A$      $p$      $T$      $R$     (Mathcad can't render dots!)     $n = 5$  parameters

2    Select primary dimensions  $M, L, t$ :

3     $m$      $A$      $p$      $T$      $R$   
 $\frac{M}{t}$      $L^2$      $\frac{M}{L \cdot t^2}$      $T$      $\frac{L^2}{t^2 \cdot T}$      $r = 4$  dimensions

4     $p$      $A$      $T$      $R$      $m = r = 4$  repeating parameters    We have  $n - m = 1$  dimensionless group.

5    Setting up dimensional equations:

$$\Pi_1 = m \cdot p^a \cdot A^b \cdot T^c \cdot R^d \quad \text{Thus:} \quad \frac{M}{t} \cdot \left( \frac{M}{L \cdot t^2} \right)^a \cdot (L^2)^b \cdot T^c \cdot \left( \frac{L^2}{t^2 \cdot T} \right)^d = M^0 \cdot L^0 \cdot t^0 \cdot T^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-a + 2 \cdot b + 2 \cdot d = 0$

t:  $-1 - 2 \cdot a - 2 \cdot d = 0$

T:  $c - d = 0$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = \frac{1}{2} \quad d = \frac{1}{2}$$

$$\Pi_1 = \frac{m}{p \cdot A} \cdot \sqrt{R \cdot T}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L} \cdot \frac{L^2}{F} \cdot \frac{1}{L^2} \cdot \frac{L}{1} \cdot T^{\frac{1}{2}} = 1$$

The functional relationship is:  $\Pi_1 = C \quad \frac{m}{p \cdot A} \cdot \sqrt{R \cdot T} = C$     So the mass flow rate is:  $m = C \cdot \frac{p \cdot A}{\sqrt{R \cdot T}}$

## Problem 7.43 (In Excel)

[Difficulty: 3]

**7.43** The time,  $t$ , for a flywheel, with moment of inertia,  $I$ , to reach angular velocity,  $\omega$ , from rest, depends on the applied torque,  $T$ , and the following flywheel bearing properties: the oil viscosity,  $\mu$ , gap,  $\delta$ , diameter,  $D$ , and length,  $L$ . Use dimensional analysis to find the  $\Pi$  parameters that characterize this phenomenon.

**Given:** Time to speed up depends on inertia, speed, torque, oil viscosity and geometry

**Find:**  $\Pi$  groups

**Solution:**

We will use the workbook of Example 7.1, modified for the current problem

The number of parameters is:  $n = 8$   
 The number of primary dimensions is:  $r = 3$   
 The number of repeat parameters is:  $m = r = 3$   
 The number of  $\Pi$  groups is:  $n - m = 5$

Enter the dimensions (**M, L, t**) of the repeating parameters, and of up to four other parameters (for up to four  $\Pi$  groups). The spreadsheet will compute the exponents  $a, b$ , and  $c$  for each.

**REPEATING PARAMETERS:** Choose  $\omega, D, T$

	<b>M</b>	<b>L</b>	<b>t</b>
$\omega$	-1		
$D$	1		
$T$	1    2    -2		

**$\Pi$  GROUPS:**

Two  $\Pi$  groups can be obtained by inspection:  $\delta/D$  and  $L/D$ . The others are obtained below

<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="padding: 5px;"></th> <th style="padding: 5px; text-align: center;"><b>M</b></th> <th style="padding: 5px; text-align: center;"><b>L</b></th> <th style="padding: 5px; text-align: center;"><b>t</b></th> </tr> </thead> <tbody> <tr> <td style="padding: 5px;"><math>t</math></td> <td colspan="3" style="text-align: center;">0    0    1</td> </tr> <tr> <td style="padding: 5px;"><math>\Pi_1:</math></td> <td style="padding: 5px;"><math>a =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">1</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>b =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">0</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>c =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">0</td> </tr> </tbody> </table>		<b>M</b>	<b>L</b>	<b>t</b>	$t$	0    0    1			$\Pi_1:$	$a =$	1			$b =$	0			$c =$	0		<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="padding: 5px;"></th> <th style="padding: 5px; text-align: center;"><b>M</b></th> <th style="padding: 5px; text-align: center;"><b>L</b></th> <th style="padding: 5px; text-align: center;"><b>t</b></th> </tr> </thead> <tbody> <tr> <td style="padding: 5px;"><math>\mu</math></td> <td colspan="3" style="text-align: center;">1    -1    -1</td> </tr> <tr> <td style="padding: 5px;"><math>\Pi_2:</math></td> <td style="padding: 5px;"><math>a =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">1</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>b =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">3</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>c =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">-1</td> </tr> </tbody> </table>		<b>M</b>	<b>L</b>	<b>t</b>	$\mu$	1    -1    -1			$\Pi_2:$	$a =$	1			$b =$	3			$c =$	-1	
	<b>M</b>	<b>L</b>	<b>t</b>																																						
$t$	0    0    1																																								
$\Pi_1:$	$a =$	1																																							
	$b =$	0																																							
	$c =$	0																																							
	<b>M</b>	<b>L</b>	<b>t</b>																																						
$\mu$	1    -1    -1																																								
$\Pi_2:$	$a =$	1																																							
	$b =$	3																																							
	$c =$	-1																																							
<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="padding: 5px;"></th> <th style="padding: 5px; text-align: center;"><b>M</b></th> <th style="padding: 5px; text-align: center;"><b>L</b></th> <th style="padding: 5px; text-align: center;"><b>t</b></th> </tr> </thead> <tbody> <tr> <td style="padding: 5px;"><math>I</math></td> <td colspan="3" style="text-align: center;">1    2    0</td> </tr> <tr> <td style="padding: 5px;"><math>\Pi_3:</math></td> <td style="padding: 5px;"><math>a =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">2</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>b =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">0</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>c =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">-1</td> </tr> </tbody> </table>		<b>M</b>	<b>L</b>	<b>t</b>	$I$	1    2    0			$\Pi_3:$	$a =$	2			$b =$	0			$c =$	-1		<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="padding: 5px;"></th> <th style="padding: 5px; text-align: center;"><b>M</b></th> <th style="padding: 5px; text-align: center;"><b>L</b></th> <th style="padding: 5px; text-align: center;"><b>t</b></th> </tr> </thead> <tbody> <tr> <td style="padding: 5px;"><math>\mu</math></td> <td colspan="3" style="text-align: center;">0    0    0</td> </tr> <tr> <td style="padding: 5px;"><math>\Pi_4:</math></td> <td style="padding: 5px;"><math>a =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">0</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>b =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">0</td> </tr> <tr> <td></td> <td style="padding: 5px;"><math>c =</math></td> <td colspan="2" style="border: 1px solid black; text-align: center;">0</td> </tr> </tbody> </table>		<b>M</b>	<b>L</b>	<b>t</b>	$\mu$	0    0    0			$\Pi_4:$	$a =$	0			$b =$	0			$c =$	0	
	<b>M</b>	<b>L</b>	<b>t</b>																																						
$I$	1    2    0																																								
$\Pi_3:$	$a =$	2																																							
	$b =$	0																																							
	$c =$	-1																																							
	<b>M</b>	<b>L</b>	<b>t</b>																																						
$\mu$	0    0    0																																								
$\Pi_4:$	$a =$	0																																							
	$b =$	0																																							
	$c =$	0																																							

Hence the  $\Pi$  groups are

$$t\omega \quad \frac{\delta}{D} \quad \frac{L}{D} \quad \frac{\mu\omega D^3}{T} \quad \frac{I\omega^2}{T}$$

Note that the  $\Pi_1$  group can also be easily obtained by inspection

## Problem 7.44

[Difficulty: 3]

**7.44** A large tank of liquid under pressure is drained through a smoothly contoured nozzle of area  $A$ . The mass flow rate is thought to depend on nozzle area,  $A$ , liquid density,  $\rho$ , difference in height between the liquid surface and nozzle,  $h$ , tank gage pressure,  $\Delta p$ , and gravitational acceleration,  $g$ . Determine how many independent  $\Pi$  parameters can be formed for this problem. Find the dimensionless parameters. State the functional relationship for the mass flow rate in terms of the dimensionless parameters.

**Given:** Functional relationship between the mass flow rate of liquid from a pressurized tank through a contoured nozzle and other physical parameters

**Find:** (a) How many independent  $\Pi$  terms that characterize this phenomenon  
 (b) Find the  $\Pi$  terms  
 (c) State the functional relationship for the mass flow rate in terms of the  $\Pi$  terms

**Solution:** We will use the Buckingham pi-theorem.

1     $m$      $A$      $\rho$      $h$      $\Delta p$      $g$     n = 6 parameters

2    Select primary dimensions M, L, t:

3     $m$      $A$      $\rho$      $h$      $\Delta p$      $g$     r = 3 dimensions

$\frac{M}{t}$      $L^2$      $\frac{M}{L^3}$      $L$      $\frac{M}{L \cdot t^2}$      $\frac{L}{t^2}$

4     $\rho$      $A$      $g$     m = r = 3 repeating parameters    We have n - m = 3 dimensionless groups.

5    Setting up dimensional equations:

$$\Pi_1 = m \cdot \rho^a \cdot A^b \cdot g^c \quad \text{Thus:} \quad \frac{M}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot (L^2)^b \cdot \left(\frac{L}{t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-3 \cdot a + 2 \cdot b + c = 0$

t:  $-1 - 2 \cdot c = 0$

The solution to this system is:

$$a = -1 \quad b = -\frac{5}{4} \quad c = -\frac{1}{2}$$

$$\Pi_1 = \frac{m}{\rho \cdot A^{\frac{5}{4}} \cdot g^{\frac{1}{2}}}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^2} \cdot \frac{t}{L^{\frac{1}{2}}} = 1$$

$$\Pi_2 = h \cdot \rho^a \cdot A^b \cdot g^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot (L^2)^b \cdot \left(\frac{L}{t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + 2 \cdot b + c = 0$

t:  $-2 \cdot c = 0$

The solution to this system is:

$$a = 0 \quad b = -\frac{1}{2} \quad c = 0$$

$$\Pi_2 = \frac{h}{\sqrt{A}}$$

Check using F, L, t dimensions:

$$L \cdot \frac{1}{L} = 1$$

$$\Pi_3 = \Delta p \cdot \rho^a \cdot A^b \cdot g^c \quad \text{Thus:} \quad \frac{M}{L \cdot t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot (L^2)^b \cdot \left(\frac{L}{t^2}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } 1 + a = 0$$

$$\text{L: } -1 - 3 \cdot a + 2 \cdot b + c = 0$$

$$\text{t: } -2 - 2 \cdot c = 0$$

The solution to this system is:

$$a = -1 \quad b = -\frac{1}{2} \quad c = -1$$

$$\Pi_3 = \frac{\Delta p}{\rho \cdot g \cdot \sqrt{A}}$$

Check using F, L, t dimensions:  $\frac{F}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L} \cdot \frac{1}{L} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3)$

$$\frac{m}{\rho \cdot A^{\frac{5}{4}} \cdot g^{\frac{1}{2}}} = f\left(\frac{h}{\sqrt{A}}, \frac{\Delta p}{\rho \cdot g \cdot \sqrt{A}}\right)$$

So the mass flow rate is:

$$m = \rho \cdot A^{\frac{5}{4}} \cdot g^{\frac{1}{2}} \cdot f\left(\frac{h}{\sqrt{A}}, \frac{\Delta p}{\rho \cdot g \cdot \sqrt{A}}\right)$$

## Problem 7.45

[Difficulty: 3]

**7.45** Spin plays an important role in the flight trajectory of golf, Ping-Pong, and tennis balls. Therefore, it is important to know the rate at which spin decreases for a ball in flight. The aerodynamic torque,  $T$ , acting on a ball in flight, is thought to depend on flight speed,  $V$ , air density,  $\rho$ , air viscosity,  $\mu$ , ball diameter,  $D$ , spin rate (angular speed),  $\omega$ , and diameter of the dimples on the ball,  $d$ . Determine the dimensionless parameters that result.

**Given:** Functional relationship between the aerodynamic torque on a spinning ball and other physical parameters

**Find:** The  $\Pi$  terms that characterize this phenomenon

**Solution:** We will use the Buckingham pi-theorem.

1  $T \quad V \quad \rho \quad \mu \quad D \quad \omega \quad d$  n = 7 parameters

2 Select primary dimensions M, L, t:

3  $T \quad V \quad \rho \quad \mu \quad D \quad \omega \quad d$   
 $\frac{M \cdot L^2}{t^2} \quad \frac{L}{t} \quad \frac{M}{L^3} \quad \frac{M}{L \cdot t} \quad L \quad \frac{1}{t} \quad L$  r = 3 dimensions

4  $\rho \quad V \quad D$  m = r = 3 repeating parameters

5 We have n - m = 4 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = T \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M \cdot L^2}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: \quad 1 + a = 0$$

$$L: \quad 2 - 3 \cdot a + b + c = 0$$

$$t: \quad -2 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -2 \quad c = -3$$

$$\Pi_1 = \frac{T}{\rho \cdot V^2 \cdot D^3}$$

Check using F, L, t dimensions:

$$F \cdot L \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} \cdot \frac{1}{L^3} = 1$$

$$\Pi_2 = \mu \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: \quad 1 + a = 0$$

$$L: \quad -1 - 3 \cdot a + b + c = 0$$

$$t: \quad -1 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = -1$$

$$\Pi_2 = \frac{\mu}{\rho \cdot V \cdot D}$$

Check using F, L, t dimensions:

$$\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$$

$$\Pi_3 = \omega \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{1}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } a = 0$$

$$\text{L: } -3 \cdot a + b + c = 0$$

$$\text{t: } -1 - b = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = 1$$

$$\Pi_3 = \frac{\omega \cdot D}{V}$$

Check using F, L, t dimensions:  $\frac{1}{t} \cdot L \cdot \frac{t}{L} = 1$

$$\Pi_4 = d \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } a = 0$$

$$\text{L: } 1 - 3 \cdot a + b + c = 0$$

$$\text{t: } -b = 0$$

The solution to this system is:

$$a = 0 \quad b = 0 \quad c = -1$$

$$\Pi_4 = \frac{d}{D}$$

Check using F, L, t dimensions:  $\frac{1}{L} \cdot L = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3, \Pi_4)$

$$\frac{T}{\rho \cdot V^2 \cdot D^3} = f\left(\frac{\mu}{\rho \cdot V \cdot D}, \frac{\omega \cdot D}{V}, \frac{d}{D}\right)$$

## Problem 7.46

[Difficulty: 2]

**7.46** The ventilation in the clubhouse on a cruise ship is insufficient to clear cigarette smoke (the ship is not yet completely smoke-free). Tests are to be done to see if a larger extractor fan will work. The concentration of smoke,  $c$  (particles per cubic meter) depends on the number of smokers,  $N$ , the pressure drop produced by the fan,  $\Delta p$ , the fan diameter,  $D$ , motor speed,  $\omega$ , the particle and air densities,  $\rho_p$  and  $\rho$ , respectively, gravity,  $g$ , and air viscosity,  $\mu$ . Determine the dimensionless parameters that characterize this problem.

**Given:** Ventilation system of cruise ship clubhouse

**Find:** Dimensionless groups

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $c \quad N \quad \Delta p \quad D \quad \omega \quad \rho_p \quad \rho \quad g \quad \mu \quad n = 9$  parameters

② Select primary dimensions M, L, t

③ 
$$\left\{ \begin{array}{cccccccc} c & N & \Delta p & D & \omega & \rho_p & \rho & g & \mu \\ \frac{1}{L^3} & 1 & \frac{M}{Lt^2} & L & \frac{1}{t} & \frac{M}{L^3} & \frac{M}{L^3} & \frac{L}{t^2} & \frac{M}{Lt} \end{array} \right\} \quad r = 3 \text{ primary dimensions}$$

④  $\rho \quad D \quad \omega \quad m = r = 3$  repeat parameters

⑤ Then  $n - m = 6$  dimensionless groups will result. Setting up a dimensional equation,

$$\Pi_1 = \rho^a D^b \omega^c \Delta p = \left(\frac{M}{L^3}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{M}{L^2} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad -3a + b - 1 = 0 \\ t: \quad -c - 2 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = -2 \\ c = -2 \end{array} \right. \quad \text{Hence} \quad \Pi_1 = \frac{\Delta p}{\rho D^2 \omega^2}$$

$$\Pi_2 = \rho^a D^b \omega^c \mu = \left(\frac{M}{L^3}\right)^a (L)^b \left(\frac{1}{t}\right)^c \frac{M}{Lt} = M^0 L^0 t^0$$

Summing exponents, 
$$\begin{array}{l} M: \quad a + 1 = 0 \\ L: \quad -3a + b - 1 = 0 \\ t: \quad -c - 1 = 0 \end{array} \quad \left| \quad \begin{array}{l} a = -1 \\ b = -2 \\ c = -1 \end{array} \right. \quad \text{Hence} \quad \Pi_2 = \frac{\mu}{\rho D^2 \omega}$$

The other  $\Pi$  groups can be found by inspection:  $\Pi_3 = cD^3 \quad \Pi_4 = N \quad \Pi_5 = \frac{\rho_p}{\rho} \quad \Pi_6 = \frac{g}{D\omega^2}$

⑥ Check using  $F, L, t$  as primary dimensions

$$\Pi_1 = \frac{\frac{F}{L^2}}{\frac{Ft^2}{L^4} L^2 \frac{1}{t^2}} = [1] \quad \Pi_2 = \frac{\frac{Ft}{L^2}}{\frac{Ft^2}{L^4} L^2 \frac{1}{t}} = [1] \quad \Pi_3 = \Pi_4 = \Pi_5 = \Pi_6 = [1]$$

Note: Any combination of  $\Pi$ 's is a  $\Pi$  group, e.g.,  $\frac{\Pi_1}{\Pi_2} = \frac{\Delta p}{\omega \mu}$ , so the  $\Pi$ 's are not unique!

## Problem 7.47

[Difficulty: 3]

**7.47** The mass burning rate of flammable gas  $\dot{m}$  is a function of the thickness of the flame  $\delta$ , the gas density  $\rho$ , the thermal diffusivity  $\alpha$ , and the mass diffusivity  $D$ . Using dimensional analysis, determine the functional form of this dependence in terms of dimensionless parameters. Note that  $\alpha$  and  $D$  have the dimensions  $L^2/t$ .

**Given:** Functional relationship between the mass burning rate of a combustible mixture and other physical parameters

**Find:** The dependence of mass burning rate

**Solution:** We will use the Buckingham pi-theorem.

1  $\dot{m}$   $\delta$   $\rho$   $\alpha$   $D$  (Mathcad can't render dots!)

2 Select primary dimensions M, L, t:

n = 5 parameters

3  $\dot{m}$   $\delta$   $\rho$   $\alpha$   $D$

$$\frac{M}{t} \quad L \quad \frac{M}{L^3} \quad \frac{L^2}{t} \quad \frac{L^2}{t}$$

r = 3 dimensions

4  $\delta$   $\rho$   $\alpha$  m = r = 3 repeating parameters

5 We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = \dot{m} \cdot \delta^a \cdot \rho^b \cdot \alpha^c \quad \text{Thus:} \quad \frac{M}{t} \cdot L^a \cdot \left(\frac{M}{L^3}\right)^b \cdot \left(\frac{L^2}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

The solution to this system is:

$$\Pi_1 = \frac{\dot{m}}{\delta \cdot \rho \cdot \alpha}$$

$$M: 1 + b = 0$$

$$a = -1 \quad b = -1 \quad c = -1$$

$$L: a - 3 \cdot b + 2 \cdot c = 0$$

$$t: -1 - c = 0$$

$$\Pi_2 = D \cdot \delta^a \cdot \rho^b \cdot \alpha^c \quad \text{Thus:} \quad \frac{L^2}{t} \cdot L^a \cdot \left(\frac{M}{L^3}\right)^b \cdot \left(\frac{L^2}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

The solution to this system is:

$$\Pi_2 = \frac{D}{\alpha}$$

$$M: b = 0$$

$$a = 0 \quad b = 0 \quad c = -1$$

$$L: 2 + a - 3 \cdot b + 2 \cdot c = 0$$

$$t: -1 - c = 0$$

6 Check using F, L, t dimensions:  $\frac{F \cdot t}{L} \cdot \frac{1}{L} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L^2} = 1$      $\frac{L^2}{t} \cdot \frac{t}{L^2} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2)$

$$\frac{\dot{m}}{\delta \cdot \rho \cdot \alpha} = f\left(\frac{D}{\alpha}\right)$$

## Problem 7.48

[Difficulty: 3]

**7.48** The power loss,  $\mathcal{P}$ , in a journal bearing depends on length,  $l$ , diameter,  $D$ , and clearance,  $c$ , of the bearing, in addition to its angular speed,  $\omega$ . The lubricant viscosity and mean pressure are also important. Obtain the dimensionless parameters that characterize this problem. Determine the functional form of the dependence of  $\mathcal{P}$  on these parameters.

**Given:** Functional relationship between the power loss in a journal bearing and other physical parameters

**Find:** The  $\Pi$  terms that characterize this phenomenon and the function form of the dependence of  $P$  on these parameters

**Solution:** We will use the Buckingham pi-theorem.

1     $P$      $l$      $D$      $c$      $\omega$      $\mu$      $p$     n = 7 parameters

2    Select primary dimensions F, L, t:

3     $P$      $l$      $D$      $c$      $\omega$      $\mu$      $p$

$\frac{F \cdot L}{t}$	L	L	L	$\frac{1}{t}$	$\frac{F \cdot t}{L^2}$	$\frac{F}{L^2}$		r = 3 dimensions
-----------------------	---	---	---	---------------	-------------------------	-----------------	--	------------------

4     $D$      $\omega$      $p$     m = r = 3 repeating parameters

5    We have n - m = 4 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = P \cdot D^a \cdot \omega^b \cdot p^c \quad \text{Thus:} \quad \frac{F \cdot L}{t} \cdot L^a \cdot \left(\frac{1}{t}\right)^b \cdot \left(\frac{F}{L^2}\right)^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

F:  $1 + c = 0$

L:  $1 + a - 2 \cdot c = 0$

t:  $-1 - b = 0$

The solution to this system is:

$a = -3$      $b = -1$      $c = -1$

$$\Pi_1 = \frac{P}{D^3 \cdot \omega \cdot p}$$

$$\Pi_2 = l \cdot D^a \cdot \omega^b \cdot p^c \quad \text{Thus:} \quad L \cdot L^a \cdot \left(\frac{1}{t}\right)^b \cdot \left(\frac{F}{L^2}\right)^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

F:  $c = 0$

L:  $1 + a - 2 \cdot c = 0$

t:  $-b = 0$

The solution to this system is:

$a = -1$      $b = 0$      $c = 0$

$$\Pi_2 = \frac{l}{D}$$

$$\Pi_3 = c \cdot D^a \cdot \omega^b \cdot p^c \quad \text{Thus:} \quad L \cdot L^a \cdot \left(\frac{1}{t}\right)^b \cdot \left(\frac{F}{L^2}\right)^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

F:  $c = 0$

L:  $1 + a - 2 \cdot c = 0$

t:  $-b = 0$

The solution to this system is:

$a = -1$      $b = 0$      $c = 0$

$$\Pi_3 = \frac{c}{D}$$

$$\Pi_4 = \mu \cdot D^a \cdot \omega^b \cdot p^c \quad \text{Thus:} \quad \frac{F \cdot t}{L^2} \cdot L^a \cdot \left(\frac{1}{t}\right)^b \cdot \left(\frac{F}{L^2}\right)^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$F: \quad 1 + c = 0$$

$$L: \quad -2 + a - 2 \cdot c = 0$$

$$t: \quad 1 - b = 0$$

The solution to this system is:

$$a = 0 \quad b = 1 \quad c = -1$$

$$\Pi_4 = \frac{\mu \cdot \omega}{p}$$

6 Check using M, L, t dimensions:  $\frac{M \cdot L^2}{t^3} \cdot \frac{1}{L^3} \cdot t \cdot \frac{L \cdot t^2}{M} = 1 \quad L \cdot \frac{1}{L} = 1 \quad L \cdot \frac{1}{L} = 1 \quad \frac{M}{L \cdot t} \cdot \frac{1}{t} \cdot \frac{L \cdot t^2}{M} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3, \Pi_4) \quad \frac{P}{\omega \cdot p \cdot D^3} = f\left(\frac{1}{D}, \frac{c}{D}, \frac{\mu \cdot \omega}{p}\right) \quad P = \omega \cdot p \cdot D^3 \cdot f\left(\frac{1}{D}, \frac{c}{D}, \frac{\mu \cdot \omega}{p}\right)$

## Problem 7.49

[Difficulty: 4]

**7.49** In a fan-assisted convection oven, the heat transfer rate to a roast,  $\dot{Q}$  (energy per unit time), is thought to depend on the specific heat of air,  $c_p$ , temperature difference,  $\Theta$ , a length scale,  $L$ , air density,  $\rho$ , air viscosity,  $\mu$ , and air speed,  $V$ . How many basic dimensions are included in these variables? Determine the number of  $\Pi$  parameters needed to characterize the oven. Evaluate the  $\Pi$  parameters.

**Given:** Functional relationship between the heat transfer rate in a convection oven and other physical parameters

**Find:** The number of  $\Pi$  terms that characterize this phenomenon and the  $\Pi$  terms

**Solution:** We will use the Buckingham pi-theorem.

1  $Q \quad c_p \quad \Theta \quad L \quad \rho \quad \mu \quad V$  n = 7 parameters

2 Select primary dimensions F, L, t, T (temperature):

3  $Q \quad c_p \quad \Theta \quad L \quad \rho \quad \mu \quad V$   
 $\frac{F \cdot L}{t} \quad \frac{L^2}{t^2 \cdot T} \quad T \quad L \quad \frac{F \cdot t^2}{L^4} \quad \frac{F \cdot t}{L^2} \quad \frac{L}{t}$  r = 4 dimensions

4  $\rho \quad V \quad L \quad \Theta$  m = r = 4 repeating parameters We have n - m = 3 dimensionless groups.

5 Setting up dimensional equations:

$$\Pi_1 = Q \cdot \rho^a \cdot V^b \cdot L^c \cdot \Theta^d \quad \text{Thus:} \quad \frac{F \cdot L}{t} \cdot \left( \frac{F \cdot t^2}{L^4} \right)^a \cdot \left( \frac{L}{t} \right)^b \cdot L^c \cdot T^d = F^0 \cdot L^0 \cdot t^0 \cdot T^0$$

Summing exponents:

F:  $1 + a = 0$

L:  $1 - 4 \cdot a + b + c = 0$

t:  $-1 + 2 \cdot a - b = 0$

T:  $d = 0$

The solution to this system is:

$a = -1 \quad b = -3 \quad c = -2 \quad d = 0$

$$\Pi_1 = \frac{Q}{\rho \cdot V^3 \cdot L^2}$$

$$\Pi_2 = c_p \cdot \rho^a \cdot V^b \cdot L^c \cdot \Theta^d \quad \text{Thus:} \quad \frac{L^2}{t^2 \cdot T} \cdot \left( \frac{F \cdot t^2}{L^4} \right)^a \cdot \left( \frac{L}{t} \right)^b \cdot L^c \cdot T^d = F^0 \cdot L^0 \cdot t^0 \cdot T^0$$

Summing exponents:

F:  $a = 0$

L:  $2 - 4 \cdot a + b + c = 0$

t:  $-2 + 2 \cdot a - b = 0$

T:  $-1 + d = 0$

The solution to this system is:

$a = 0 \quad b = -2 \quad c = 0 \quad d = 1$

$$\Pi_2 = \frac{c_p \cdot \Theta}{V^2}$$

$$\Pi_3 = \mu \cdot \rho^a \cdot V^b \cdot L^c \cdot \Theta^d \quad \text{Thus:} \quad \frac{F \cdot t}{L^2} \cdot \left( \frac{F \cdot t^2}{L^4} \right)^a \cdot \left( \frac{L}{t} \right)^b \cdot L^c \cdot T^d = F^0 \cdot L^0 \cdot t^0 \cdot T^0$$

Summing exponents:

F:  $1 + a = 0$

L:  $-2 - 4 \cdot a + b + c = 0$

t:  $1 + 2 \cdot a - b = 0$

T:  $d = 0$

The solution to this system is:

$a = -1 \quad b = -1 \quad c = -1 \quad d = 0$

$$\Pi_3 = \frac{\mu}{\rho \cdot V \cdot L}$$

6 Check using M, L, t, T dimensions:  $\frac{M \cdot L^2}{t^3} \cdot \frac{L^3}{M} \cdot \frac{t^2}{L^2} \cdot \frac{1}{L^3} = 1$   $\frac{L^2}{t^2 \cdot T} \cdot \frac{t^2}{L^2} \cdot T = 1$   $\frac{M}{L \cdot t} \cdot \frac{L^3}{M} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3)$   $\frac{Q}{\rho \cdot V^3 \cdot L^2} = f\left(\frac{c_p \cdot \Theta}{V^2}, \frac{\mu}{\rho \cdot V \cdot L}\right)$   $Q = \rho \cdot V^3 \cdot L^2 \cdot f\left(\frac{c_p \cdot \Theta}{V^2}, \frac{\mu}{\rho \cdot V \cdot L}\right)$

## Problem 7.50

[Difficulty: 3]

**7.50** The thrust of a marine propeller is to be measured during “open-water” tests at a variety of angular speeds and forward speeds (“speeds of advance”). The thrust,  $F_T$ , is thought to depend on water density,  $\rho$ , propeller diameter,  $D$ , speed of advance,  $V$ , acceleration of gravity,  $g$ , angular speed,  $\omega$ , pressure in the liquid,  $p$ , and liquid viscosity,  $\mu$ . Develop a set of dimensionless parameters to characterize the performance of the propeller. (One of the resulting parameters,  $gD/V^2$ , is known as the *Froude speed of advance*.)

**Given:** Functional relationship between the thrust of a marine propeller and other physical parameters

**Find:** The  $\Pi$  terms that characterize this phenomenon

**Solution:** We will use the Buckingham pi-theorem.

1  $F_T \quad \rho \quad D \quad V \quad g \quad \omega \quad p \quad \mu$  n = 8 parameters

2 Select primary dimensions F, L, t:

3  $F_T \quad \rho \quad D \quad V \quad g \quad \omega \quad p \quad \mu$

$$\frac{M \cdot L}{t^2} \quad \frac{M}{L^3} \quad L \quad \frac{L}{t} \quad \frac{L}{t^2} \quad \frac{1}{t} \quad \frac{M}{L \cdot t^2} \quad \frac{M}{L \cdot t}$$

r = 3 dimensions

4  $\rho \quad V \quad D$  m = r = 3 repeating parameters

5 We have n - m = 5 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = F_T \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M \cdot L}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = -1 \quad b = -2 \quad c = -2$

$$\Pi_1 = \frac{F_T}{\rho \cdot V^2 \cdot D^2}$$

$$\Pi_2 = g \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{L}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = 0 \quad b = -2 \quad c = 1$

$$\Pi_2 = \frac{g \cdot D}{V^2}$$

$$\Pi_3 = \omega \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{1}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $-3 \cdot a + b + c = 0$

t:  $-1 - b = 0$

The solution to this system is:

$a = 0 \quad b = -1 \quad c = 1$

$$\Pi_3 = \frac{\omega \cdot D}{V}$$

$$\Pi_4 = p \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: -1 - 3 \cdot a + b + c = 0$$

$$t: -2 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -2 \quad c = 0$$

$$\Pi_4 = \frac{p}{\rho \cdot V^2}$$

$$\Pi_5 = \mu \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: -1 - 3 \cdot a + b + c = 0$$

$$t: -1 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = -1$$

$$\Pi_5 = \frac{\mu}{\rho \cdot V \cdot D}$$

6 Check using F, L, t dimensions:  $F \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} \cdot \frac{1}{L^2} = 1$     $\frac{L}{t^2} \cdot L \cdot \frac{t^2}{L^2} = 1$     $\frac{1}{t} \cdot L \cdot \frac{t}{L} = 1$     $\frac{F}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} = 1$     $\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$

## Problem 7.51

[Difficulty: 3]

**7.51** The rate  $dT/dt$  at which the temperature  $T$  at the center of a rice kernel falls during a food technology process is critical—too high a value leads to cracking of the kernel, and too low a value makes the process slow and costly. The rate depends on the rice specific heat,  $c$ , thermal conductivity,  $k$ , and size,  $L$ , as well as the cooling air specific heat,  $c_p$ , density,  $\rho$ , viscosity,  $\mu$ , and speed,  $V$ . How many basic dimensions are included in these variables? Determine the  $\Pi$  parameters for this problem.

**Given:** That the cooling rate depends on rice properties and air properties

**Find:** The  $\Pi$  groups

**Solution:**

Apply the Buckingham  $\Pi$  procedure

①  $dT/dt \quad c \quad k \quad L \quad c_p \quad \rho \quad \mu \quad V \quad n = 8 \text{ parameters}$

② Select primary dimensions  $M, L, t$  and  $T$  (temperature)

③  $dT/dt \quad c \quad k \quad L \quad c_p \quad \rho \quad \mu \quad V \quad r = 4 \text{ primary dimensions}$

$$\frac{T}{t} \quad \frac{L^2}{t^2 T} \quad \frac{ML}{t^2 T} \quad L \quad \frac{L^2}{t^2 T} \quad \frac{M}{L^3} \quad \frac{M}{Lt} \quad \frac{L}{t}$$

④  $V \quad \rho \quad L \quad c_p \quad m = r = 4 \text{ repeat parameters}$

Then  $n - m = 4$  dimensionless groups will result. By inspection, one  $\Pi$  group is  $c/c_p$ . Setting up a dimensional equation,

$$\Pi_1 = V^a \rho^b L^c c_p^d \frac{dT}{dt} = \left(\frac{L}{t}\right)^a \left(\frac{M}{L^3}\right)^b (L)^c \left(\frac{L^2}{t^2 T}\right)^d \frac{T}{t} = T^0 M^0 L^0 t^0$$

Summing exponents,

$$\begin{array}{l|l} T: & -d + 1 = 0 & d = 1 \\ M: & b = 0 & b = 0 \\ L: & a - 3b + c + 2d = 0 & a + c = -2 \rightarrow c = 1 \\ t: & -a - 2d - 1 = 0 & a = -3 \end{array}$$

Hence  $\Pi_1 = \frac{dT}{dt} \frac{Lc_p}{V^3}$

By a similar process, we find  $\Pi_2 = \frac{k}{\rho L^2 c_p}$  and  $\Pi_3 = \frac{\mu}{\rho L V}$

Hence

$$\frac{dT}{dt} \frac{Lc_p}{V^3} = f\left(\frac{c}{c_p}, \frac{k}{\rho L^2 c_p}, \frac{\mu}{\rho L V}\right)$$

## Problem 7.52

[Difficulty: 3]

**7.52** The power,  $\mathcal{P}$ , required to drive a propeller is known to depend on the following variables: freestream speed,  $V$ , propeller diameter,  $D$ , angular speed,  $\omega$ , fluid viscosity,  $\mu$ , fluid density,  $\rho$ , and speed of sound in the fluid,  $c$ . How many dimensionless groups are required to characterize this situation? Obtain these dimensionless groups.

**Given:** Functional relationship between the power to drive a marine propeller and other physical parameters

**Find:** (a) The number of  $\Pi$  terms that characterize this phenomenon  
(b) The  $\Pi$  terms

**Solution:** We will use the Buckingham pi-theorem.

1     $P$      $\rho$      $D$      $V$      $c$      $\omega$      $\mu$     n = 7 parameters

2    Select primary dimensions F, L, t:

3     $P$      $\rho$      $D$      $V$      $c$      $\omega$      $\mu$

$$\frac{M \cdot L^2}{t^3} \quad \frac{M}{L^3} \quad L \quad \frac{L}{t} \quad \frac{L}{t} \quad \frac{1}{t} \quad \frac{M}{L \cdot t}$$

r = 3 dimensions

4     $\rho$      $V$      $D$     m = r = 3 repeating parameters

5    We have n - m = 4 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = P \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M \cdot L^2}{t^3} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: \quad 1 + a = 0$$

$$L: \quad 2 - 3 \cdot a + b + c = 0$$

$$t: \quad -3 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -3 \quad c = -2$$

$$\Pi_1 = \frac{P}{\rho \cdot V^3 \cdot D^2}$$

$$\Pi_2 = c \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: \quad a = 0$$

$$L: \quad 1 - 3 \cdot a + b + c = 0$$

$$t: \quad -1 - b = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = 0$$

$$\Pi_2 = \frac{c}{V}$$

$$\Pi_3 = \omega \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{1}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: \quad a = 0$$

$$L: \quad -3 \cdot a + b + c = 0$$

$$t: \quad -1 - b = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = 1$$

$$\Pi_3 = \frac{\omega \cdot D}{V}$$

$$\Pi_4 = \mu \cdot \rho^a \cdot V^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: -1 - 3 \cdot a + b + c = 0$$

$$t: -1 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = -1$$


$$\Pi_4 = \frac{\mu}{\rho \cdot V \cdot D}$$

6 Check using F, L, t dimensions:  $\frac{F \cdot L}{t} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^3}{L^3} \cdot \frac{1}{L^2} = 1 \quad \frac{L}{t} \cdot \frac{t}{L} = 1 \quad \frac{1}{t} \cdot L \cdot \frac{t}{L} = 1 \quad \frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$

## Problem 7.53

[Difficulty: 2]

**7.53** The fluid velocity  $u$  at any point in a boundary layer depends on the distance  $y$  of the point above the surface, the free-stream velocity  $U$  and free-stream velocity gradient  $dU/dx$ , the fluid kinematic viscosity  $\nu$ , and the boundary layer thickness  $\delta$ . How many dimensionless groups are required to describe this problem? Find: (a) two  $\Pi$  groups by inspection, (b) one  $\Pi$  that is a standard fluid mechanics group, and (c) any remaining  $\Pi$  groups using the Buckingham Pi theorem.



**Given:** Boundary layer profile

**Find:** Two  $\Pi$  groups by inspection; One  $\Pi$  that is a standard fluid mechanics group; Dimensionless groups

**Solution:**

Two obvious  $\Pi$  groups are  $u/U$  and  $y/\delta$ . A dimensionless group common in fluid mechanics is  $U\delta/\nu$  (Reynolds number)

Apply the Buckingham  $\Pi$  procedure

①  $u \quad y \quad U \quad dU/dx \quad \nu \quad \delta \quad n = 6$  parameters

② Select primary dimensions M, L, t

③ 
$$\left\{ \begin{array}{cccccc} u & y & U & dU/dx & \nu & \delta \\ \frac{L}{t} & L & \frac{L}{t} & \frac{1}{t} & \frac{L^2}{t} & L \end{array} \right\} \quad m = r = 3 \text{ primary dimensions}$$

④  $U \quad \delta \quad m = r = 2$  repeat parameters

⑤ Then  $n - m = 4$  dimensionless groups will result. We can easily do these by inspection

$$\Pi_1 = \frac{u}{U} \quad \Pi_2 = \frac{y}{\delta} \quad \Pi_3 = \frac{(dU/dy)\delta}{U} \quad \Pi_4 = \frac{\nu}{\delta U}$$

⑥ Check using  $F, L, t$  as primary dimensions, is not really needed here

Note: Any combination of  $\Pi$ 's can be used; they are not unique!

## Problem 7.54

[Difficulty: 4]

**7.54** When a valve is closed suddenly in a pipe with flowing water, a water hammer pressure wave is set up. The very high pressures generated by such waves can damage the pipe. The maximum pressure,  $p_{\max}$ , generated by water hammer is a function of liquid density,  $\rho$ , initial flow speed,  $U_0$ , and liquid bulk modulus,  $E_v$ . How many dimensionless groups are needed to characterize water hammer? Determine the functional relationship among the variables in terms of the necessary  $\Pi$  groups.

**Given:** Functional relationship between the maximum pressure experienced in a water hammer wave and other physical parameters

**Find:** (a) The number of  $\Pi$  terms that characterize this phenomenon  
(b) The functional relationship between the  $\Pi$  terms

**Solution:** We will use the Buckingham pi-theorem.

1  $p_{\max}$   $\rho$   $U_0$   $E_v$  n = 4 parameters

2 Select primary dimensions M, L, t:

3  $p_{\max}$   $\rho$   $U_0$   $E_v$

$$\frac{M}{L \cdot t^2} \quad \frac{M}{L^3} \quad \frac{L}{t} \quad \frac{M}{L \cdot t^2}$$

r = 3 dimensions

4  $\rho$   $U_0$  m = 2 repeating parameters because  $p_{\max}$  and  $E_v$  have the same dimensions.  
We have n - m = 2 dimensionless groups.

5 Setting up dimensional equations:

$$\Pi_1 = p_{\max} \cdot \rho^a \cdot U_0^b \quad \text{Thus:} \quad \frac{M}{L \cdot t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = -1 \quad b = -2$

$$\Pi_1 = \frac{p_{\max}}{\rho \cdot U_0^2}$$

$$\Pi_2 = E_v \cdot \rho^a \cdot U_0^b \quad \text{Thus:} \quad \frac{M}{L \cdot t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = -1 \quad b = -2$

$$\Pi_2 = \frac{E_v}{\rho \cdot U_0^2}$$

6 Check using F, L, t dimensions:  $\frac{F}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} = 1 \quad \frac{F}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2)$  Thus:

$$\frac{p_{\max}}{\rho \cdot U_0^2} = f\left(\frac{E_v}{\rho \cdot U_0^2}\right)$$

## Problem 7.55

[Difficulty: 3]

**7.55** The designers of a large tethered pollution-sampling balloon wish to know what the drag will be on the balloon for the maximum anticipated wind speed of 5 m/s (the air is assumed to be at 20°C). A  $\frac{1}{20}$ -scale model is built for testing in water at 20°C. What water speed is required to model the prototype? At this speed the model drag is measured to be 2 kN. What will be the corresponding drag on the prototype?

**Given:** Model scale for on balloon

**Find:** Required water model water speed; drag on prototype based on model drag

**Solution:**

$$\text{From Appendix A (inc. Fig. A.2)} \quad \rho_{\text{air}} = 1.24 \frac{\text{kg}}{\text{m}^3} \quad \mu_{\text{air}} = 1.8 \times 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \quad \rho_{\text{w}} = 999 \frac{\text{kg}}{\text{m}^3} \quad \mu_{\text{w}} = 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$$

$$\text{The given data is} \quad V_{\text{air}} = 5 \frac{\text{m}}{\text{s}} \quad L_{\text{ratio}} = 20 \quad F_{\text{w}} = 2 \cdot \text{kN}$$

$$\text{For dynamic similarity we assume} \quad \frac{\rho_{\text{w}} \cdot V_{\text{w}} \cdot L_{\text{w}}}{\mu_{\text{w}}} = \frac{\rho_{\text{air}} \cdot V_{\text{air}} \cdot L_{\text{air}}}{\mu_{\text{air}}}$$

$$\text{Then} \quad V_{\text{w}} = V_{\text{air}} \cdot \frac{\mu_{\text{w}}}{\mu_{\text{air}}} \cdot \frac{\rho_{\text{air}}}{\rho_{\text{w}}} \cdot \frac{L_{\text{air}}}{L_{\text{w}}} = V_{\text{air}} \cdot \frac{\mu_{\text{w}}}{\mu_{\text{air}}} \cdot \frac{\rho_{\text{air}}}{\rho_{\text{w}}} \cdot L_{\text{ratio}} = 5 \frac{\text{m}}{\text{s}} \times \left( \frac{10^{-3}}{1.8 \times 10^{-5}} \right) \times \left( \frac{1.24}{999} \right) \times 20 \quad V_{\text{w}} = 6.90 \frac{\text{m}}{\text{s}}$$

$$\text{For the same Reynolds numbers, the drag coefficients will be the same so we have} \quad \frac{F_{\text{air}}}{\frac{1}{2} \cdot \rho_{\text{air}} \cdot A_{\text{air}} \cdot V_{\text{air}}^2} = \frac{F_{\text{w}}}{\frac{1}{2} \cdot \rho_{\text{w}} \cdot A_{\text{w}} \cdot V_{\text{w}}^2}$$

$$\text{where} \quad \frac{A_{\text{air}}}{A_{\text{w}}} = \left( \frac{L_{\text{air}}}{L_{\text{w}}} \right)^2 = L_{\text{ratio}}^2$$

$$\text{Hence the prototype drag is} \quad F_{\text{air}} = F_{\text{w}} \cdot \frac{\rho_{\text{air}}}{\rho_{\text{w}}} \cdot L_{\text{ratio}}^2 \cdot \left( \frac{V_{\text{air}}}{V_{\text{w}}} \right)^2 = 2000 \cdot \text{N} \times \left( \frac{1.24}{999} \right) \times 20^2 \times \left( \frac{5}{6.9} \right)^2 \quad F_{\text{air}} = 522 \text{ N}$$

## Problem 7.56

[Difficulty: 3]

**7.56** An airship is to operate at 20 m/s in air at standard conditions. A model is constructed to  $\frac{1}{20}$  scale and tested in a wind tunnel at the same air temperature to determine drag. What criterion should be considered to obtain dynamic similarity? If the model is tested at 75 m/s, what pressure should be used in the wind tunnel? If the model drag force is 250 N, what will be the drag of the prototype?

**Given:** Airship is to operate at 20 m/s in air at standard conditions. A 1/20 scale model is to be tested in a wind tunnel at the same temperature to determine drag.

**Find:** (a) Criterion needed to obtain dynamic similarity  
 (b) Air pressure required if air speed in wind tunnel is 75 m/s  
 (c) Prototype drag if the drag on the model is 250 N

**Solution:** Dimensional analysis predicts:  $\frac{F}{\rho \cdot V^2 \cdot L^2} = f\left(\frac{\rho \cdot V \cdot L}{\mu}\right)$  Therefore, for dynamic similarity, it would follow that:

$$\frac{\rho_m \cdot V_m \cdot L_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot L_p}{\mu_p}$$

Since the tests are performed at the same temperature, the viscosities are the same. Solving for the ratio of densities:

$$\frac{\rho_m}{\rho_p} = \frac{V_p}{V_m} \cdot \frac{L_p}{L_m} \cdot \frac{\mu_m}{\mu_p} = \frac{20}{75} \times 20 \times 1 = 5.333 \quad \text{Now from the ideal gas equation of state: } \rho = \frac{p}{R \cdot T} \quad \text{Thus:}$$

$$p_m = p_p \cdot \frac{\rho_m}{\rho_p} \cdot \frac{T_p}{T_m} \quad p_m = 101 \cdot \text{kPa} \times 5.333 \times 1 \quad p_m = 5.39 \times 10^5 \text{ Pa}$$

From the force ratios:  $\frac{F_p}{\rho_p \cdot V_p^2 \cdot L_p^2} = \frac{F_m}{\rho_m \cdot V_m^2 \cdot L_m^2}$  Thus:  $F_p = F_m \cdot \frac{\rho_p}{\rho_m} \cdot \left(\frac{V_p}{V_m}\right)^2 \cdot \left(\frac{L_p}{L_m}\right)^2$

Substituting known values:  $F_p = 250 \cdot \text{N} \times \frac{1}{5.333} \times \left(\frac{20}{75}\right)^2 \times (20)^2 \quad F_p = 1.333 \cdot \text{kN}$

## Problem 7.57

[Difficulty: 2]

**7.57** To match the Reynolds number in an air flow and a water flow using the same size model, which flow will require the higher flow speed? How much higher must it be?

**Given:** A model is to be subjected to the same Reynolds number in air flow and water flow

**Find:** (a) Which flow will require the higher flow speed  
(b) How much higher the flow speed needs to be

**Solution:** For dynamic similarity:  $\frac{\rho_w \cdot V_w \cdot L_w}{\mu_w} = \frac{\rho_a \cdot V_a \cdot L_a}{\mu_a}$  We know that  $L_w = L_a$  Thus:  $\frac{V_a}{V_w} = \frac{\rho_w}{\rho_a} \cdot \frac{\mu_a}{\mu_w} = \frac{\nu_a}{\nu_w}$

From Tables A.8 and A.10 at 20 deg C:  $\nu_w = 1.00 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$  and  $\nu_a = 1.51 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$  Therefore:

$$\frac{V_a}{V_w} = \frac{1.51 \times 10^{-5}}{1.00 \times 10^{-6}} = 15.1$$

Air speed must be higher than water speed.

To match Reynolds number:  $V_a = 15.1 \cdot V_w$

## Problem 7.58

[Difficulty: 5]

**7.58** An ocean-going vessel is to be powered by a rotating circular cylinder. Model tests are planned to estimate the power required to rotate the prototype cylinder. A dimensional analysis is needed to scale the power requirements from model test results to the prototype. List the parameters that should be included in the dimensional analysis. Perform a dimensional analysis to identify the important dimensionless groups.

**Given:** Vessel to be powered by a rotating circular cylinder. Model tests are planned to determine the required power for the prototype.

**Find:** (a) List of parameters that should be included in the analysis  
(b) Perform dimensional analysis to identify the important dimensionless groups

**Solution:** From an inspection of the physical problem:  $P = f(\rho, \mu, V, \omega, D, H)$

We will now use the Buckingham pi-theorem to find the dimensionless groups.

1     $P$      $\rho$      $\mu$      $V$      $\omega$      $D$      $H$      $n = 7$  parameters

2    Select primary dimensions  $M, L, t$ :

3     $P$      $\rho$      $\mu$      $V$      $\omega$      $D$      $H$   
 $\frac{M \cdot L^2}{t^3}$      $\frac{M}{L^3}$      $\frac{M}{L \cdot t}$      $\frac{L}{t}$      $\frac{1}{t}$      $L$      $L$      $r = 3$  dimensions

4     $\rho$      $\omega$      $D$      $m = r = 3$  repeating parameters

5    We have  $n - m = 4$  dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = P \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad \frac{M \cdot L^2}{t^3} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: 2 - 3 \cdot a + c = 0$$

$$t: -3 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -3 \quad c = -5$$

$$\Pi_1 = \frac{P}{\rho \cdot \omega^3 \cdot D^5}$$

$$\Pi_2 = \mu \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: -1 - 3 \cdot a + c = 0$$

$$t: -1 - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = -2$$

$$\Pi_2 = \frac{\mu}{\rho \cdot \omega \cdot D^2}$$

$$\Pi_3 = V \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: a = 0$$


$$L: 1 - 3 \cdot a + c = 0$$

$$t: -1 - b = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = -1$$

$$\Pi_3 = \frac{V}{\omega \cdot D}$$



$$\Pi_4 = H \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\text{M: } a = 0$$

$$\text{L: } 1 - 3 \cdot a + c = 0$$

$$\text{t: } -b = 0$$

The solution to this system is:

$$a = 0 \quad b = 0 \quad c = -1$$

$$\Pi_4 = \frac{H}{D}$$

6 Check using F, L, t dimensions:  $\frac{F \cdot L}{t} \cdot \frac{L^4}{F \cdot t^2} \cdot t^3 \cdot \frac{1}{L^5} = 1 \quad \frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot t \cdot \frac{1}{L^2} = 1 \quad \frac{L}{t} \cdot t \cdot \frac{1}{L} = 1 \quad L \cdot \frac{1}{L} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2, \Pi_3, \Pi_4)$

$$\frac{P}{\rho \cdot \omega^3 \cdot D^5} = f\left(\frac{\mu}{\rho \cdot \omega \cdot D^2}, \frac{V}{\omega \cdot D}, \frac{H}{D}\right)$$

## Problem 7.59

[Difficulty: 3]

**7.59** Measurements of drag force are made on a model automobile in a towing tank filled with fresh water. The model length scale is  $\frac{1}{5}$  that of the prototype. State the conditions required to ensure dynamic similarity between the model and prototype. Determine the fraction of the prototype speed in air at which the model test should be made in water to ensure dynamically similar conditions. Measurements made at various speeds show that the dimensionless force ratio becomes constant at model test speeds above  $V_m = 4$  m/s. The drag force measured during a test at this speed is  $F_{D_m} = 182$  N. Calculate the drag force expected on the prototype vehicle operating at 90 km/hr in air.

**Given:** Measurements of drag are made on a model car in a fresh water tank. The model is 1/5-scale.

**Find:** (a) Conditions required to ensure dynamic similarity between the model and the prototype.  
 (b) Required fraction of speed in air at which the model needs to be tested in water to ensure dynamically similar conditions.  
 (c) Drag force on the prototype model traveling at 90 kph in air if the model drag is 182 N traveling at 4 m/s in water.

**Solution:** The flows must be geometrically and kinematically similar, and have equal Reynolds numbers to be dynamically similar:

Geometric similarity requires a true model in all respects.  
 Kinematic similarity requires the same flow pattern, i.e., no free-surface or cavitation effects.  
 The problem may be stated as  $F = f(\rho, V, L, \mu)$

Dimensional analysis gives this relation:  $\frac{F}{\rho \cdot V^2 \cdot L^2} = g(\text{Re})$  where  $\text{Re} = \frac{\rho \cdot V \cdot L}{\mu} = \frac{V \cdot L}{\nu}$

Matching Reynolds numbers between the model and prototype flows:  $\frac{V_m \cdot L_m}{\nu_m} = \frac{V_p \cdot L_p}{\nu_p}$  Thus:  $\frac{V_m}{V_p} = \frac{\nu_m}{\nu_p} \cdot \frac{L_p}{L_m}$

From Tables A.8 and A.10 at 20 deg C:  $\nu_w = 1.00 \times 10^{-6} \frac{\text{m}^2}{\text{s}}$  and  $\nu_a = 1.51 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$  Therefore:

$$\frac{V_m}{V_p} = \frac{1.00 \times 10^{-6}}{1.51 \times 10^{-5}} \times \frac{5}{1} = 0.331 \qquad \frac{V_m}{V_p} = 0.331$$

If the conditions are dynamically similar:  $\frac{F_m}{\rho_m \cdot V_m^2 \cdot L_m^2} = \frac{F_p}{\rho_p \cdot V_p^2 \cdot L_p^2}$  Thus:  $F_p = F_m \cdot \frac{\rho_p}{\rho_m} \cdot \left(\frac{V_p}{V_m}\right)^2 \cdot \left(\frac{L_p}{L_m}\right)^2$

Substituting in known values:  $F_p = 182 \cdot \text{N} \times \frac{1.20}{999} \times \left(90 \cdot \frac{\text{km}}{\text{hr}} \times \frac{1000 \cdot \text{m}}{\text{km}} \times \frac{\text{hr}}{3600 \cdot \text{s}} \times \frac{\text{s}}{4 \cdot \text{m}}\right)^2 \times \left(\frac{5}{1}\right)^2$   $F_p = 213 \text{ N}$

## Problem 7.60

[Difficulty: 2]

**7.60** On a cruise ship, passengers complain about the noise emanating from the ship's propellers (probably due to turbulent flow effects between the propeller and the ship). You have been hired to find out the source of this noise. You will study the flow pattern around the propellers and have decided to use a 1:9-scale water tank. If the ship's propellers rotate at 100 rpm, estimate the model propeller rotation speed if (a) the Froude number or (b) the Reynolds number is the governing dimensionless group. Which is most likely to lead to the best modeling?

**Given:** Flow around ship's propeller

**Find:** Model propeller speed using Froude number and Reynolds number

**Solution:**

**Basic equations:**

$$Fr = \frac{V}{\sqrt{g \cdot L}} \qquad Re = \frac{V \cdot L}{\nu}$$

**Assumptions:** (a) The model and the actual propeller are geometrically similar  
 (b) The flows about the propellers are kinematically and dynamically similar

Using the Froude number

$$Fr_m = \frac{V_m}{\sqrt{g \cdot L_m}} = Fr_p = \frac{V_p}{\sqrt{g \cdot L_p}} \qquad \text{or} \qquad \frac{V_m}{V_p} = \sqrt{\frac{L_m}{L_p}} \qquad (1)$$

But the angular velocity is given by  $V = L \cdot \omega$

$$\text{so} \qquad \frac{V_m}{V_p} = \frac{L_m}{L_p} \cdot \frac{\omega_m}{\omega_p} \qquad (2)$$

Comparing Eqs. 1 and 2

$$\frac{L_m}{L_p} \cdot \frac{\omega_m}{\omega_p} = \sqrt{\frac{L_m}{L_p}} \qquad \frac{\omega_m}{\omega_p} = \sqrt{\frac{L_p}{L_m}}$$

The model rotation speed is then

$$\omega_m = \omega_p \cdot \sqrt{\frac{L_p}{L_m}} \qquad \omega_m = 100 \cdot \text{rpm} \times \sqrt{\frac{9}{1}} \qquad \omega_m = 300 \cdot \text{rpm}$$

Using the Reynolds number

$$Re_m = \frac{V_m \cdot L_m}{\nu_m} = Re_p = \frac{V_p \cdot L_p}{\nu_p} \qquad \text{or} \qquad \frac{V_m}{V_p} = \frac{L_p}{L_m} \cdot \frac{\nu_m}{\nu_p} = \frac{L_p}{L_m} \qquad (3)$$

(We have assumed the viscosities of the sea water and model water are comparable)

Comparing Eqs. 2 and 3

$$\frac{L_m}{L_p} \cdot \frac{\omega_m}{\omega_p} = \frac{L_p}{L_m} \qquad \frac{\omega_m}{\omega_p} = \left(\frac{L_p}{L_m}\right)^2$$

The model rotation speed is then

$$\omega_m = \omega_p \cdot \left(\frac{L_p}{L_m}\right)^2 \qquad \omega_m = 100 \cdot \text{rpm} \times \left(\frac{9}{1}\right)^2 \qquad \omega_m = 8100 \cdot \text{rpm}$$

Of the two models, the Froude number appears most realistic; at 8100 rpm serious cavitation will occur, which would invalidate the similarity assumptions. Both flows will likely have high Reynolds numbers so that the flow becomes independent of Reynolds number; the Froude number is likely to be a good indicator of static pressure to dynamic pressure for this (although cavitation number would be better).

## Problem 7.61

[Difficulty: 3]

**7.61** A  $\frac{1}{5}$ -scale model of a torpedo is tested in a wind tunnel to determine the drag force. The prototype operates in water, has 533 mm diameter, and is 6.7 m long. The desired operating speed of the prototype is 28 m/s. To avoid compressibility effects in the wind tunnel, the maximum speed is limited to 110 m/s. However, the pressure in the wind tunnel can be varied while holding the temperature constant at 20°C. At what minimum pressure should the wind tunnel be operated to achieve a dynamically similar test? At dynamically similar test conditions, the drag force on the model is measured as 618 N. Evaluate the drag force expected on the full-scale torpedo.

**Given:** A torpedo with  $D = 533$  mm and  $L = 6.7$  m is to travel at 28 m/s in water. A  $1/5$  scale model of the torpedo is to be tested in a wind tunnel. The maximum speed in the tunnel is fixed at 110 m/s, but the pressure can be varied at a constant temperature of 20 deg C.

**Find:** (a) Minimum pressure required in the wind tunnel for dynamically similar testing.  
(b) The expected drag on the prototype if the model drag is 618 N.

**Solution:** The problem may be stated as:  $F = f(\rho, V, D, \mu)$  From the Buckingham pi theorem, we expect 2  $\Pi$  terms:

$$\frac{F}{\rho \cdot V^2 \cdot D^2} = g(\text{Re}) \quad \text{where} \quad \text{Re} = \frac{\rho \cdot V \cdot D}{\mu}$$

Matching Reynolds numbers between the model and prototype flows:  $\frac{\rho_m \cdot V_m \cdot D_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot D_p}{\mu_p}$  Thus:  $\rho_m = \rho_p \cdot \frac{V_p}{V_m} \cdot \frac{D_p}{D_m} \cdot \frac{\mu_m}{\mu_p}$

At 20 deg C:  $\mu_p = 1.00 \times 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$  and  $\mu_m = 1.81 \times 10^{-5} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$  So substituting in values yields:

$$\rho_m = 998 \cdot \frac{\text{kg}}{\text{m}^3} \times \frac{28}{110} \times \frac{5}{1} \times \frac{1.81 \times 10^{-5}}{1.00 \times 10^{-3}} \quad \rho_m = 23.0 \cdot \frac{\text{kg}}{\text{m}^3} \quad \text{From the ideal gas equation of state:} \quad p_m = \rho_m \cdot R \cdot T_m$$

$$\text{Substituting in values:} \quad p_m = 23.0 \cdot \frac{\text{kg}}{\text{m}^3} \times 287 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 293 \cdot \text{K} \times \frac{\text{Pa} \cdot \text{m}^2}{\text{N}} \quad p_m = 1.934 \cdot \text{MPa}$$

$$\text{If the conditions are dynamically similar:} \quad \frac{F_m}{\rho_m \cdot V_m^2 \cdot D_m^2} = \frac{F_p}{\rho_p \cdot V_p^2 \cdot D_p^2} \quad \text{Thus:} \quad F_p = F_m \cdot \frac{\rho_p}{\rho_m} \cdot \left(\frac{V_p}{V_m}\right)^2 \cdot \left(\frac{D_p}{D_m}\right)^2$$

$$\text{Substituting in known values:} \quad F_p = 618 \cdot \text{N} \times \frac{998}{23.0} \times \left(\frac{28}{110}\right)^2 \times \left(\frac{5}{1}\right)^2 \quad F_p = 43.4 \cdot \text{kN}$$

## Problem 7.62

[Difficulty: 3]

**7.62** The drag of an airfoil at zero angle of attack is a function of density, viscosity, and velocity, in addition to a length parameter. A 1:5-scale model of an airfoil was tested in a wind tunnel at a speed of 130 ft/s, temperature of 59°F, and 5 atmospheres absolute pressure. The prototype airfoil has a chord length of 6 ft and is to be flown in air at standard conditions. Determine the Reynolds number at which the wind tunnel model was tested and the corresponding prototype speed at the same Reynolds number.

**Given:** A 1/10 scale airfoil was tested in a wind tunnel at known test conditions. Prototype airfoil has a chord length of 6 ft and is to be flown at standard conditions.

**Find:** (a) Reynolds number at which the model was tested  
(b) Corresponding prototype speed

**Solution:**

**Assumptions:** (a) The viscosity of air does not vary appreciably between 1 and 5 atmospheres  
(b) Geometric, kinematic, and dynamic similarity applies

The problem may be stated as:  $F = f(\rho, V, L, \mu)$  From the Buckingham pi theorem, we expect 2  $\Pi$  terms:

$$\frac{F}{\rho \cdot V^2 \cdot L^2} = g(\text{Re}) \quad \text{where} \quad \text{Re} = \frac{\rho \cdot V \cdot L}{\mu} \quad \text{The model chord length is} \quad L_m = \frac{6 \cdot \text{ft}}{5} = 1.20 \cdot \text{ft}$$

We can calculate the model flow density from the ideal gas equation of state:  $\rho_m = \frac{p_m}{R \cdot T_m}$  Substituting known values:

$$\rho_m = \left( 5 \cdot \text{atm} \times \frac{2116 \cdot \text{lbf}}{\text{atm} \cdot \text{ft}^2} \right) \times \frac{\text{lbf} \cdot \text{R}}{53.33 \cdot \text{ft} \cdot \text{lbf}} \times \frac{1}{519 \cdot \text{R}} \times \frac{\text{slug}}{32.2 \cdot \text{lbf}} \quad \rho_m = 0.0119 \cdot \frac{\text{slug}}{\text{ft}^3}$$

$$\text{At } 59 \text{ deg F: } \mu_m = 3.74 \times 10^{-7} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \quad \text{Therefore:} \quad \text{Re}_m = 0.0119 \cdot \frac{\text{slug}}{\text{ft}^3} \times 130 \cdot \frac{\text{ft}}{\text{s}} \times 1.2 \cdot \text{ft} \times \frac{\text{ft}^2}{3.74 \times 10^{-7} \cdot \text{lbf} \cdot \text{s}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$\text{Re}_m = 5.0 \times 10^6$$

Matching Reynolds numbers between the model and prototype flows:  $\frac{\rho_m \cdot V_m \cdot L_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot L_p}{\mu_p}$  Thus:  $V_p = V_m \cdot \frac{\rho_m}{\rho_p} \cdot \frac{L_m}{L_p} \cdot \frac{\mu_p}{\mu_m}$

From the ideal gas equation of state:  $\frac{\rho_m}{\rho_p} = \frac{p_m}{p_p} \cdot \frac{T_p}{T_m}$  Therefore:  $V_p = V_m \cdot \frac{p_m}{p_p} \cdot \frac{T_p}{T_m} \cdot \frac{L_m}{L_p} \cdot \frac{\mu_p}{\mu_m}$  So substituting in values yields:

$$V_p = 130 \cdot \frac{\text{ft}}{\text{s}} \times \frac{5}{1} \times \frac{519}{519} \times \frac{1}{5} \times \frac{3.74 \times 10^{-7}}{3.74 \times 10^{-7}} \quad V_p = 130.0 \cdot \frac{\text{ft}}{\text{s}}$$

## Problem 7.63

[Difficulty: 2]

**7.63** Consider a smooth sphere, of diameter  $D$ , immersed in a fluid moving with speed  $V$ . The drag force on a 10-ft-diameter weather balloon in air moving at 5 ft/s is to be calculated from test data. The test is to be performed in water using a 2-in.-diameter model. Under dynamically similar conditions, the model drag force is measured as 0.85 lbf. Evaluate the model test speed and the drag force expected on the full-scale balloon.

**Given:** Model of weather balloon

**Find:** Model test speed; drag force expected on full-scale balloon

**Solution:**

From Buckingham II 
$$\frac{F}{\rho \cdot V^2 \cdot D^2} = f\left(\frac{\nu}{V \cdot D}, \frac{V}{c}\right) = F(\text{Re}, M)$$

For similarity  $\text{Re}_p = \text{Re}_m$  and  $M_p = M_m$  (Mach number criterion satisfied because  $M \ll 1$ )

Hence 
$$\text{Re}_p = \frac{V_p \cdot D_p}{\nu_p} = \text{Re}_m = \frac{V_m \cdot D_m}{\nu_m}$$

$$V_m = V_p \cdot \frac{\nu_m}{\nu_p} \cdot \frac{D_p}{D_m}$$

From Table A.7 at 68°F  $\nu_m = 1.08 \times 10^{-5} \frac{\text{ft}^2}{\text{s}}$  From Table A.9 at 68°F  $\nu_p = 1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}$

$$V_m = 5 \cdot \frac{\text{ft}}{\text{s}} \times \left( \frac{1.08 \times 10^{-5} \frac{\text{ft}^2}{\text{s}}}{1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}} \right) \times \left( \frac{10 \cdot \text{ft}}{\frac{1}{6} \cdot \text{ft}} \right)$$

$$V_m = 20.0 \cdot \frac{\text{ft}}{\text{s}}$$

Then 
$$\frac{F_m}{\rho_m \cdot V_m^2 \cdot D_m^2} = \frac{F_p}{\rho_p \cdot V_p^2 \cdot D_p^2}$$
 
$$F_p = F_m \cdot \frac{\rho_p}{\rho_m} \cdot \frac{V_p^2}{V_m^2} \cdot \frac{D_p^2}{D_m^2}$$

$$F_p = 0.85 \cdot \text{lbf} \times \left( \frac{0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}}{1.94 \cdot \frac{\text{slug}}{\text{ft}^3}} \right) \times \left( \frac{5 \frac{\text{ft}}{\text{s}}}{20 \cdot \frac{\text{ft}}{\text{s}}} \right)^2 \times \left( \frac{10 \cdot \text{ft}}{\frac{1}{6} \cdot \text{ft}} \right)^2$$

$$F_p = 0.231 \cdot \text{lbf}$$

## Problem 7.64

[Difficulty: 2]

**7.64** An airplane wing, with chord length of 1.5 m and span of 9 m, is designed to move through standard air at a speed of 7.5 m/s. A  $\frac{1}{10}$ -scale model of this wing is to be tested in a water tunnel. What speed is necessary in the water tunnel to achieve dynamic similarity? What will be the ratio of forces measured in the model flow to those on the prototype wing?

**Given:** Model of wing

**Find:** Model test speed for dynamic similarity; ratio of model to prototype forces

**Solution:**

We would expect  $F = F(l, s, V, \rho, \mu)$  where  $F$  is the force (lift or drag),  $l$  is the chord and  $s$  the span

From Buckingham  $\Pi$  
$$\frac{F}{\rho \cdot V^2 \cdot l \cdot s} = f\left(\frac{\rho \cdot V \cdot l}{\mu}, \frac{l}{s}\right)$$

For dynamic similarity 
$$\frac{\rho_m \cdot V_m \cdot l_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot l_p}{\mu_p}$$

Hence 
$$V_m = V_p \cdot \frac{\rho_p}{\rho_m} \cdot \frac{l_p}{l_m} \cdot \frac{\mu_m}{\mu_p}$$

From Table A.8 at 20°C  $\mu_m = 1.01 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$       From Table A.10 at 20°C  $\mu_p = 1.81 \times 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

$$V_m = 7.5 \frac{\text{m}}{\text{s}} \times \left(\frac{1.21 \cdot \frac{\text{kg}}{\text{m}^3}}{998 \cdot \frac{\text{kg}}{\text{m}^3}}\right) \times \left(\frac{10}{1}\right) \times \left(\frac{1.01 \times 10^{-3} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}}{1.81 \times 10^{-5} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}}\right) \quad V_m = 5.07 \frac{\text{m}}{\text{s}}$$

Then 
$$\frac{F_m}{\rho_m \cdot V_m^2 \cdot l_m \cdot s_m} = \frac{F_p}{\rho_p \cdot V_p^2 \cdot l_p \cdot s_p} \quad \frac{F_m}{F_p} = \frac{\rho_m}{\rho_p} \cdot \frac{V_m^2}{V_p^2} \cdot \frac{l_m \cdot s_m}{l_p \cdot s_p} = \frac{998}{1.21} \times \left(\frac{5.07}{7.5}\right)^2 \times \frac{1}{10} \times \frac{1}{10} = 3.77$$

## Problem 7.65

[Difficulty: 3]

**7.65** The fluid dynamic characteristics of a golf ball are to be tested using a model in a wind tunnel. Dependent parameters are the drag force,  $F_D$ , and lift force,  $F_L$ , on the ball. The independent parameters should include angular speed,  $\omega$ , and dimple depth,  $d$ . Determine suitable dimensionless parameters and express the functional dependence among them. A golf pro can hit a ball at  $V = 75$  m/s and  $\omega = 8100$  rpm. To model these conditions in a wind tunnel with a maximum speed of 25 m/s, what diameter model should be used? How fast must the model rotate? (The diameter of a U.S. golf ball is 4.27 cm.)

**Given:** The fluid dynamic characteristics of a gold ball are to be tested using a model in a wind tunnel. The dependent variables are the drag and lift forces. Independent variables include the angular speed and dimple depth. A pro golfer can hit a ball at a speed of 75 m/s and 8100 rpm. Wind tunnel maximum speed is 25 m/s.

**Find:** (a) Suitable dimensionless parameters and express the functional dependence between them.  
(b) Required diameter of model  
(c) Required rotational speed of model

**Solution:**

**Assumption:** Wind tunnel is at standard conditions

The problem may be stated as:  $F_D = F_D(D, V, \omega, d, \rho, \mu)$   $F_L = F_L(D, V, \omega, d, \rho, \mu)$   $n = 7$  and  $m = r = 3$ , so

from the Buckingham pi theorem, we expect two sets of four  $\Pi$  terms. The application of the Buckingham pi theorem will not be shown here, but the functional dependences would be:

$$\frac{F_D}{\rho \cdot V^2 \cdot D^2} = f\left(\frac{\rho \cdot V \cdot D}{\mu}, \frac{\omega \cdot D}{V}, \frac{d}{D}\right) \quad \frac{F_L}{\rho \cdot V^2 \cdot D^2} = g\left(\frac{\rho \cdot V \cdot D}{\mu}, \frac{\omega \cdot D}{V}, \frac{d}{D}\right)$$

To determine the required model diameter, we match Reynolds numbers between the model and prototype flows:

$$\frac{\rho_m \cdot V_m \cdot D_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot D_p}{\mu_p} \quad \text{Thus: } D_m = D_p \cdot \frac{\rho_p}{\rho_m} \cdot \frac{V_p}{V_m} \cdot \frac{\mu_m}{\mu_p} \quad \text{Substituting known values: } D_m = 4.27 \cdot \text{cm} \times 1 \times \frac{75}{25} \times 1$$

$$D_m = 12.81 \cdot \text{cm}$$

To determine the required angular speed of the model, we match the dimensionless rotational speed between the flows:

$$\frac{\omega_m \cdot D_m}{V_m} = \frac{\omega_p \cdot D_p}{V_p} \quad \text{Thus: } \omega_m = \omega_p \cdot \frac{D_p}{D_m} \cdot \frac{V_m}{V_p} \quad \text{Substituting known values: } \omega_m = 8100 \cdot \text{rpm} \times \frac{4.27}{12.81} \times \frac{25}{75} \quad \omega_m = 900 \cdot \text{rpm}$$

## Problem 7.66

[Difficulty: 3]

**7.66** A water pump with impeller diameter 24 in. is to be designed to move 15 ft<sup>3</sup>/s when running at 750 rpm. Testing is performed on a 1:4 scale model running at 2400 rpm using air (68°F) as the fluid. For similar conditions (neglecting Reynolds number effects), what will be the model flow rate? If the model draws 0.1 hp, what will be the power requirement of the prototype?

**Given:** Model of water pump

**Find:** Model flow rate for dynamic similarity (ignoring Re); Power of prototype

**Solution:**

From Buckingham II  $\frac{Q}{\omega \cdot D^3}$  and  $\frac{P}{\rho \cdot \omega^3 \cdot D^5}$  where Q is flow rate,  $\omega$  is angular speed, d is diameter, and  $\rho$  is density (these II groups will be discussed in Chapter 10)

For dynamic similarity 
$$\frac{Q_m}{\omega_m \cdot D_m^3} = \frac{Q_p}{\omega_p \cdot D_p^3}$$

Hence 
$$Q_m = Q_p \cdot \frac{\omega_m}{\omega_p} \cdot \left(\frac{D_m}{D_p}\right)^3$$

$$Q_m = 15 \cdot \frac{\text{ft}^3}{\text{s}} \times \left(\frac{2400}{750}\right) \times \left(\frac{1}{4}\right)^3 \qquad Q_m = 0.750 \cdot \frac{\text{ft}^3}{\text{s}}$$

From Table A.8 at 68°F  $\rho_p = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$  From Table A.9 at 68°F  $\rho_m = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$

Then 
$$\frac{P_m}{\rho_m \cdot \omega_m^3 \cdot D_m^5} = \frac{P_p}{\rho_p \cdot \omega_p^3 \cdot D_p^5}$$

$$P_p = P_m \cdot \frac{\rho_p}{\rho_m} \cdot \left(\frac{\omega_p}{\omega_m}\right)^3 \cdot \left(\frac{D_p}{D_m}\right)^5$$

$$P_p = 0.1 \cdot \text{hp} \times \frac{1.94}{0.00234} \times \left(\frac{750}{2400}\right)^3 \times \left(\frac{4}{1}\right)^5 \qquad P_p = 2.59 \times 10^3 \cdot \text{hp}$$

Note that if we had used water instead of air as the working fluid for the model pump, it would have drawn 83 hp. Water would have been an acceptable working fluid for the model, and there would have been less discrepancy in the Reynolds number.

## Problem 7.67

[Difficulty: 2]

**7.67** A model test is performed to determine the flight characteristics of a Frisbee. Dependent parameters are drag force,  $F_D$ , and lift force,  $F_L$ . The independent parameters should include angular speed,  $\omega$ , and roughness height,  $h$ . Determine suitable dimensionless parameters, and express the functional dependence among them. The test (using air) on a 1:7-scale model Frisbee is to be geometrically, kinematically, and dynamically similar to the prototype. The wind tunnel test conditions are  $V_m = 140$  ft/s and  $\omega_m = 5000$  rpm. What are the corresponding values of  $V_p$  and  $\omega_p$ ?

**Given:** Model of Frisbee

**Find:** Dimensionless parameters; Prototype speed and angular speed

**Solution:**

**Assumption:** Geometric, kinematic, and dynamic similarity between model and prototype.

The functional dependence is  $F = F(D, V, \omega, h, \rho, \mu)$  where F represents lift or drag

From Buckingham  $\Pi$  
$$\frac{F}{\rho \cdot V^2 \cdot D^2} = f\left(\frac{\rho \cdot V \cdot D}{\mu}, \frac{\omega \cdot D}{V}, \frac{h}{D}\right)$$

For dynamic similarity 
$$\frac{\rho_m \cdot V_m \cdot D_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot D_p}{\mu_p} \quad V_p = V_m \cdot \frac{\rho_m}{\rho_p} \cdot \frac{D_m}{D_p} \cdot \frac{\mu_p}{\mu_m} \quad V_p = 140 \cdot \frac{\text{ft}}{\text{s}} \times (1) \times \left(\frac{1}{7}\right) \times (1)$$

$$V_p = 20 \cdot \frac{\text{ft}}{\text{s}}$$

Also 
$$\frac{\omega_m \cdot D_m}{V_m} = \frac{\omega_p \cdot D_p}{V_p} \quad \omega_p = \omega_m \cdot \frac{D_m}{D_p} \cdot \frac{V_p}{V_m} \quad \omega_p = 5000 \cdot \text{rpm} \times \left(\frac{1}{7}\right) \times \left(\frac{20}{140}\right)$$

$$\omega_p = 102 \cdot \text{rpm}$$

## Problem 7.68

[Difficulty: 3]

**7.68** A model hydrofoil is to be tested at 1:20 scale. The test speed is chosen to duplicate the Froude number corresponding to the 60-knot prototype speed. To model cavitation correctly, the cavitation number also must be duplicated. At what ambient pressure must the test be run? Water in the model test basin can be heated to 130°F, compared to 45°F for the prototype.

**Given:** A 1:20 model of a hydrofoil is to be tested in water at 130 deg F. The prototype operates at a speed of 60 knots in water at 45 deg F. To model the cavitation, the cavitation number must be duplicated.

**Find:** Ambient pressure at which the test must be run

**Solution:** To duplicate the Froude number between the model and the prototype requires:  $\frac{V_m}{\sqrt{g \cdot L_m}} = \frac{V_p}{\sqrt{g \cdot L_p}}$  Thus:

$$V_m = V_p \cdot \sqrt{\frac{L_m}{L_p}} \quad V_m = 60 \cdot \text{knot} \cdot \sqrt{\frac{1}{20}} \quad V_m = 13.42 \cdot \text{knot}$$

To match the cavitation number between the model and the prototype:  $\frac{p_m - p_{vm}}{\frac{1}{2} \cdot \rho_m \cdot V_m^2} = \frac{p_p - p_{vp}}{\frac{1}{2} \cdot \rho_p \cdot V_p^2}$  Therefore:

$$p_m = p_{vm} + (p_p - p_{vp}) \cdot \frac{\rho_m}{\rho_p} \cdot \left(\frac{V_m}{V_p}\right)^2 \quad \text{Assuming that the densities are equal: } p_m = p_{vm} + (p_p - p_{vp}) \cdot \left(\frac{V_m}{V_p}\right)^2$$

From table A.7: at 130 deg F  $p_{vm} = 2.23 \cdot \text{psi}$  at 45 deg F  $p_{vp} = 0.15 \cdot \text{psi}$  Thus the model pressure is:

$$p_m = 2.23 \cdot \text{psi} + (14.7 \cdot \text{psi} - 0.15 \cdot \text{psi}) \cdot \left(\frac{13.42}{60}\right)^2 \quad p_m = 2.96 \cdot \text{psi}$$

## Problem 7.69

[Difficulty: 2]

**7.69** SAE 10W oil at 77°F flowing in a 1-in.-diameter horizontal pipe, at an average speed of 3 ft/s, produces a pressure drop of 7 psi (gage) over a 500-ft length. Water at 60°F flows through the same pipe under dynamically similar conditions. Using the results of Example 7.2, calculate the average speed of the water flow and the corresponding pressure drop.

**Given:** Oil flow in pipe and dynamically similar water flow

**Find:** Average water speed and pressure drop

**Solution:**

From Example 7.2 
$$\frac{\Delta p}{\rho \cdot V^2} = f\left(\frac{\mu}{\rho \cdot V \cdot D}, \frac{l}{D}, \frac{e}{D}\right)$$

For dynamic similarity 
$$\frac{\mu_{H_2O}}{\rho_{H_2O} \cdot V_{H_2O} \cdot D_{H_2O}} = \frac{\mu_{Oil}}{\rho_{Oil} \cdot V_{Oil} \cdot D_{Oil}} \quad \text{so} \quad V_{H_2O} = \frac{\mu_{H_2O}}{\rho_{H_2O}} \cdot \frac{\rho_{Oil}}{\mu_{Oil}} \cdot V_{oil} = \frac{\nu_{H_2O}}{\nu_{Oil}} \cdot V_{Oil}$$

From Fig. A.3 at 77°F 
$$\nu_{Oil} = 10.8 \times 8 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}} = 8.64 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$$

From Table A.8 at 60°F 
$$\nu_{H_2O} = 1.21 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$$

Hence 
$$V_{H_2O} = \frac{1.21 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}}{8.64 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}} \times 3 \cdot \frac{\text{ft}}{\text{s}} \quad V_{H_2O} = 0.0420 \cdot \frac{\text{ft}}{\text{s}}$$

Then 
$$\frac{\Delta p_{Oil}}{\rho_{Oil} \cdot V_{Oil}^2} = \frac{\Delta p_{H_2O}}{\rho_{H_2O} \cdot V_{H_2O}^2} \quad \Delta p_{H_2O} = \frac{\rho_{H_2O} \cdot V_{H_2O}^2}{\rho_{Oil} \cdot V_{Oil}^2} \cdot \Delta p_{Oil}$$


From Table A.2 
$$SG_{Oil} = 0.92$$

$$\Delta p_{H_2O} = \frac{1}{0.92} \times \left(\frac{0.0420}{3}\right)^2 \times 7 \cdot \text{psi} \quad \Delta p_{H_2O} = 1.49 \times 10^{-3} \cdot \text{psi}$$

## Problem 7.70

[Difficulty: 3]

**7.70** In some speed ranges, vortices are shed from the rear of bluff cylinders placed across a flow. The vortices alternately leave the top and bottom of the cylinder, as shown, causing an alternating force normal to the freestream velocity. The vortex shedding frequency,  $f$ , is thought to depend on  $\rho$ ,  $d$ ,  $V$ , and  $\mu$ . Use dimensional analysis to develop a functional relationship for  $f$ . Vortex shedding occurs in standard air on two cylinders with a diameter ratio of 2. Determine the velocity ratio for dynamic similarity, and the ratio of vortex shedding frequencies.



**Given:** The frequency of vortex shedding from the rear of a bluff cylinder is a function of  $\rho$ ,  $d$ ,  $V$ , and  $\mu$ . Vortex shedding occurs in standard air on two cylinders with a diameter ratio of 2.

**Find:** (a) Functional relationship for  $f$  using dimensional analysis  
 (b) Velocity ratio for vortex shedding  
 (c) Frequency ratio for vortex shedding

**Solution:** We will use the Buckingham pi-theorem.

1  $f$   $\rho$   $d$   $V$   $\mu$  n = 5 parameters

2 Select primary dimensions F, L, t:

3  $f$   $\rho$   $d$   $V$   $\mu$

$\frac{1}{t}$	$\frac{M}{L^3}$	$L$	$\frac{L}{t}$	$\frac{M}{L \cdot t}$	r = 3 dimensions
---------------	-----------------	-----	---------------	-----------------------	------------------

4  $\rho$   $V$   $d$  m = r = 3 repeating parameters

5 We have  $n - m = 2$  dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = f \cdot \rho^a \cdot V^b \cdot d^c \quad \text{Thus:} \quad \frac{1}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\begin{aligned} \text{M: } a &= 0 \\ \text{L: } -3 \cdot a + b + c &= 0 \\ \text{t: } -1 - b &= 0 \end{aligned}$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = 1$$

$$\Pi_1 = \frac{f \cdot d}{V}$$

$$\Pi_2 = \mu \cdot \rho^a \cdot V^b \cdot d^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$\begin{aligned} \text{M: } 1 + a &= 0 \\ \text{L: } -1 - 3 \cdot a + b + c &= 0 \\ \text{t: } -1 - b &= 0 \end{aligned}$$

The solution to this system is:

$$a = -1 \quad b = -1 \quad c = -1$$

$$\Pi_2 = \frac{\mu}{\rho \cdot V \cdot d}$$

6 Check using F, L, t dimensions:  $\frac{1}{t} \cdot \frac{t}{L} \cdot L = 1$   $\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$

The functional relationship is:  $\Pi_1 = f(\Pi_2)$

$$\frac{f \cdot d}{V} = f\left(\frac{\rho \cdot V \cdot d}{\mu}\right)$$

To achieve dynamic similarity between geometrically similar flows, we must duplicate all but one of the dimensionless groups:

$$\frac{\rho_1 \cdot V_1 \cdot d_1}{\mu_1} = \frac{\rho_2 \cdot V_2 \cdot d_2}{\mu_2} \quad \frac{V_1}{V_2} = \frac{\rho_2}{\rho_1} \cdot \frac{d_2}{d_1} \cdot \frac{\mu_1}{\mu_2} = 1 \times \frac{1}{2} \times 1 \quad \frac{V_1}{V_2} = \frac{1}{2}$$

Now if  $\frac{\rho_1 \cdot V_1 \cdot d_1}{\mu_1} = \frac{\rho_2 \cdot V_2 \cdot d_2}{\mu_2}$  it follows that:  $\frac{f_1 \cdot d_1}{V_1} = \frac{f_2 \cdot d_2}{V_2}$  and  $\frac{f_1}{f_2} = \frac{d_2}{d_1} \cdot \frac{V_1}{V_2} = \frac{1}{2} \times \frac{1}{2} \quad \frac{f_1}{f_2} = \frac{1}{4}$

## Problem 7.71

[Difficulty: 3]

**7.71** A  $\frac{1}{8}$ -scale model of a tractor-trailer rig is tested in a pressurized wind tunnel. The rig width, height, and length are  $W = 0.305$  m,  $H = 0.476$  m, and  $L = 2.48$  m, respectively. At wind speed  $V = 75.0$  m/s, the model drag force is  $F_D = 128$  N. (Air density in the tunnel is  $\rho = 3.23$  kg/m<sup>3</sup>.) Calculate the aerodynamic drag coefficient for the model. Compare the Reynolds numbers for the model test and for the prototype vehicle at 55 mph. Calculate the aerodynamic drag force on the prototype vehicle at a road speed of 55 mph into a headwind of 10 mph.

**Given:** 1/8-scale model of a tractor-trailer rig was tested in a pressurized wind tunnel.

**Find:** (a) Aerodynamic drag coefficient for the model  
 (b) Compare the Reynolds numbers for the model and the prototype vehicle at 55 mph  
 (c) Calculate aerodynamic drag on the prototype at a speed of 55 mph into a headwind of 10 mph

**Solution:** We will use definitions of the drag coefficient and Reynolds number.

**Governing Equations:**

$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} \quad (\text{Drag Coefficient})$$

$$Re = \frac{\rho \cdot V \cdot L}{\mu} \quad (\text{Reynolds Number})$$

Assume that the frontal area for the model is:  $A_m = W_m \cdot H_m$      $A_m = 0.305 \cdot \text{m} \times 0.476 \cdot \text{m}$      $A_m = 0.1452 \cdot \text{m}^2$

The drag coefficient would then be:  $C_{Dm} = 2 \times 128 \cdot \text{N} \times \frac{\text{m}^3}{3.23 \cdot \text{kg}} \times \left( \frac{\text{s}}{75.0 \cdot \text{m}} \right)^2 \times \frac{1}{0.1452 \cdot \text{m}^2} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}$      $C_{Dm} = 0.0970$

From the definition of Re:  $\frac{Re_m}{Re_p} = \frac{\rho_m}{\rho_p} \cdot \frac{V_m}{V_p} \cdot \frac{L_m}{L_p} \cdot \frac{\mu_p}{\mu_m}$     Assuming standard conditions and equal viscosities:

$$\frac{Re_m}{Re_p} = \frac{3.23}{1.23} \times \left( 75 \cdot \frac{\text{m}}{\text{s}} \times \frac{\text{hr}}{55 \cdot \text{mi}} \times \frac{\text{mi}}{5280 \cdot \text{ft}} \times \frac{\text{ft}}{0.3048 \cdot \text{m}} \times \frac{3600 \cdot \text{s}}{\text{hr}} \right) \times \frac{1}{8} \times 1 = 1 \quad Re_m = Re_p$$

Since the Reynolds numbers match, assuming geometric and kinetic similarity we can say that the drag coefficients are equal:

$F_{Dp} = \frac{1}{2} \cdot C_D \cdot \rho_p \cdot V_p^2 \cdot A_p$     Substituting known values yields:

$$F_{Dp} = \frac{1}{2} \times 0.0970 \times 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ (55 + 10) \frac{\text{mi}}{\text{hr}} \times \frac{5280 \cdot \text{ft}}{\text{mi}} \times \frac{0.3048 \cdot \text{m}}{\text{ft}} \times \frac{\text{hr}}{3600 \cdot \text{s}} \right]^2 \times 0.1452 \cdot \text{m}^2 \times 8^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_{Dp} = 468 \text{ N}$$

## Problem 7.72

[Difficulty: 2]

**7.72** On a cruise ship, passengers complain about the amount of smoke that becomes entrained behind the cylindrical smoke stack. You have been hired to study the flow pattern around the stack, and have decided to use a 1:15 scale model of the 15-ft smoke stack. What range of wind tunnel speeds could you use if the ship speed for which the problem occurs is 12 to 24 knots?

**Given:** Flow around cruise ship smoke stack

**Find:** Range of wind tunnel speeds

**Solution:**

For dynamic similarity  $\frac{V_m \cdot D_m}{\nu_m} = \frac{V_p \cdot D_p}{\nu_p}$  or  $V_m = \frac{D_p}{D_m} \cdot V_p = \frac{15}{1} \cdot V_p = 15 \cdot V_p$

Since  $1 \cdot \text{knot} = 1 \cdot \frac{\text{nmi}}{\text{hr}}$  and  $1 \cdot \text{nmi} = 6076.1 \cdot \text{ft}$

Hence for  $V_p = 12 \cdot \frac{\text{nmi}}{\text{hr}} \times \frac{6076.1 \cdot \text{ft}}{\text{nmi}} \times \frac{\text{hr}}{3600 \cdot \text{s}}$   $V_p = 20.254 \cdot \frac{\text{ft}}{\text{s}}$   $V_m = 15 \times 20.254 \cdot \frac{\text{ft}}{\text{s}}$   $V_m = 304 \cdot \frac{\text{ft}}{\text{s}}$

$V_p = 24 \cdot \frac{\text{nmi}}{\text{hr}} \times \frac{6076.1 \cdot \text{ft}}{\text{nmi}} \times \frac{\text{hr}}{3600 \cdot \text{s}}$   $V_p = 40.507 \cdot \frac{\text{ft}}{\text{s}}$   $V_m = 15 \times 40.507 \cdot \frac{\text{ft}}{\text{s}}$   $V_m = 608 \cdot \frac{\text{ft}}{\text{s}}$

Note that these speeds are very high - compressibility effects may become important, since the Mach number is no longer much less than 1!

## Problem 7.73

[Difficulty: 2]

**7.73** The aerodynamic behavior of a flying insect is to be investigated in a wind tunnel using a 1:8-scale model. If the insect flaps its wings 60 times per second when flying at 1.5 m/s, determine the wind tunnel air speed and wing oscillation required for dynamic similarity. Do you expect that this would be a successful or practical model for generating an easily measurable wing lift? If not, can you suggest a different fluid (e.g., water, or air at a different pressure or temperature) that would produce a better modeling?

**Given:** Model of flying insect

**Find:** Wind tunnel speed and wing frequency; select a better model fluid

**Solution:** For dynamic similarity the following dimensionless groups must be the same in the insect and model (these are Reynolds number and Strouhal number, and can be obtained from a Buckingham II analysis)

$$\frac{V_{\text{insect}} \cdot L_{\text{insect}}}{\nu_{\text{air}}} = \frac{V_m \cdot L_m}{\nu_m} \quad \frac{\omega_{\text{insect}} \cdot L_{\text{insect}}}{V_{\text{insect}}} = \frac{\omega_m \cdot L_m}{V_m}$$

From Table A.9 (68°F)  $\rho_{\text{air}} = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu_{\text{air}} = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$

The given data is  $\omega_{\text{insect}} = 60 \cdot \text{Hz}$   $V_{\text{insect}} = 1.5 \cdot \frac{\text{m}}{\text{s}}$   $\frac{L_{\text{insect}}}{L_m} = \frac{1}{8}$

Hence in the wind tunnel  $V_m = V_{\text{insect}} \cdot \frac{L_{\text{insect}}}{L_m} \cdot \frac{\nu_m}{\nu_{\text{air}}} = V_{\text{insect}} \cdot \frac{L_{\text{insect}}}{L_m}$   $V_m = 1.5 \cdot \frac{\text{m}}{\text{s}} \times \frac{1}{8}$   $V_m = 0.1875 \frac{\text{m}}{\text{s}}$

Also  $\omega_m = \omega_{\text{insect}} \cdot \frac{V_m}{V_{\text{insect}}} \cdot \frac{L_{\text{insect}}}{L_m}$   $\omega_m = 60 \cdot \text{Hz} \times \frac{0.1875}{1.5} \times \frac{1}{8}$   $\omega_m = 0.9375 \cdot \text{Hz}$

It is unlikely measurable wing lift can be measured at such a low wing frequency (unless the measured lift was averaged, using an integrator circuit, or perhaps a load cell and data acquisition system). Maybe try hot air (100°C) for the model

For hot air try  $\nu_{\text{hot}} = 2.29 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$  instead of  $\nu_{\text{air}} = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$

Hence  $\frac{V_{\text{insect}} \cdot L_{\text{insect}}}{\nu_{\text{air}}} = \frac{V_m \cdot L_m}{\nu_{\text{hot}}}$   $V_m = V_{\text{insect}} \cdot \frac{L_{\text{insect}}}{L_m} \cdot \frac{\nu_{\text{hot}}}{\nu_{\text{air}}}$   $V_m = 1.5 \cdot \frac{\text{m}}{\text{s}} \times \frac{1}{8} \times \frac{2.29 \times 10^{-5}}{1.50 \times 10^{-5}}$   $V_m = 0.286 \frac{\text{m}}{\text{s}}$

Also  $\omega_m = \omega_{\text{insect}} \cdot \frac{V_m}{V_{\text{insect}}} \cdot \frac{L_{\text{insect}}}{L_m}$   $\omega_m = 60 \cdot \text{Hz} \times \frac{0.286}{1.5} \times \frac{1}{8}$   $\omega_m = 1.43 \cdot \text{Hz}$

Hot air does not improve things much. Try modeling in water  $\nu_w = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$

Hence  $\frac{V_{\text{insect}} \cdot L_{\text{insect}}}{\nu_{\text{air}}} = \frac{V_m \cdot L_m}{\nu_w}$   $V_m = V_{\text{insect}} \cdot \frac{L_{\text{insect}}}{L_m} \cdot \frac{\nu_w}{\nu_{\text{air}}}$   $V_m = 1.5 \cdot \frac{\text{m}}{\text{s}} \times \frac{1}{8} \times \frac{1.01 \times 10^{-6}}{1.50 \times 10^{-5}}$   $V_m = 0.01262 \frac{\text{m}}{\text{s}}$

Also  $\omega_m = \omega_{\text{insect}} \cdot \frac{V_m}{V_{\text{insect}}} \cdot \frac{L_{\text{insect}}}{L_m} = \omega_{\text{insect}} \cdot \frac{V_m}{V_{\text{insect}}} \cdot L_{\text{ratio}}$   $\omega_m = 60 \cdot \text{Hz} \times \frac{0.01262}{1.5} \times \frac{1}{8}$   $\omega_m = 0.0631 \cdot \text{Hz}$

This is even worse! It seems the best bet is hot (very hot) air for the wind tunnel. Alternatively, choose a much smaller wind tunnel model, e.g., a 2.5 X model would lead to  $V_m = 0.6 \text{ m/s}$  and  $\omega_m = 9.6 \text{ Hz}$

## Problem 7.74

[Difficulty: 3]

**7.74** A model test of a tractor-trailer rig is performed in a wind tunnel. The drag force,  $F_D$ , is found to depend on frontal area  $A$ , wind speed  $V$ , air density  $\rho$ , and air viscosity  $\mu$ . The model scale is 1:4; frontal area of the model is  $7 \text{ ft}^2$ . Obtain a set of dimensionless parameters suitable to characterize the model test results. State the conditions required to obtain dynamic similarity between model and prototype flows. When tested at wind speed  $V = 300 \text{ ft/s}$  in standard air, the measured drag force on the model was  $F_D = 550 \text{ lbf}$ . Assuming dynamic similarity, estimate the aerodynamic drag force on the full-scale vehicle at  $V = 75 \text{ ft/s}$ . Calculate the power needed to overcome this drag force if there is no wind.

**Given:** A model test of a 1:4 scale tractor-trailer rig is performed in standard air. The drag force is a function of  $A$ ,  $V$ ,  $\rho$ , and  $\mu$ .

**Find:** (a) Dimensionless parameters to characterize the model test results  
 (b) Conditions for dynamic similarity  
 (c) Drag force on the prototype vehicle based on test results  
 (d) Power needed to overcome the drag force

**Solution:** We will use the Buckingham pi-theorem.

1  $F_D$   $A$   $V$   $\rho$   $\mu$  n = 5 parameters

2 Select primary dimensions F, L, t:

3  $F_D$   $A$   $V$   $\rho$   $\mu$  r = 3 dimensions

$$\frac{M \cdot L}{t^2} \quad L^2 \quad \frac{L}{t} \quad \frac{M}{L^3} \quad \frac{M}{L \cdot t}$$

4  $\rho$   $V$   $A$  m = r = 3 repeating parameters

5 We have  $n - m = 2$  dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = F \cdot \rho^a \cdot V^b \cdot A^c \quad \text{Thus:} \quad \frac{M \cdot L}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot (L^2)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $1 - 3 \cdot a + b + 2c = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = -1 \quad b = -2 \quad c = -1$

$$\Pi_1 = \frac{F_D}{\rho \cdot V^2 \cdot A}$$

$$\Pi_2 = \mu \cdot \rho^a \cdot V^b \cdot A^c$$

$$\text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t}\right)^b \cdot (L^2)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + 2 \cdot c = 0$

t:  $-1 - b = 0$

The solution to this system is:

$a = -1 \quad b = -1 \quad c = -\frac{1}{2}$

$$\Pi_2 = \frac{\mu}{\rho \cdot V \cdot \sqrt{A}}$$

6 Check using F, L, t dimensions:  $F \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t^2}{L^2} \cdot \frac{1}{L^2} = 1$       $\frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L} \cdot \frac{1}{L} = 1$

For dynamic similarity:

We must have geometric and kinematic similarity, and The Reynolds numbers must match.

Once dynamic similarity is insured, the drag coefficients must be equal:

$$\frac{F_{Dm}}{\frac{1}{2} \cdot \rho_m \cdot V_m^2 \cdot A_m} = \frac{F_{Dp}}{\frac{1}{2} \cdot \rho_p \cdot V_p^2 \cdot A_p}$$

So for the prototype:  $F_{Dp} = F_{Dm} \cdot \frac{\rho_p}{\rho_m} \cdot \left(\frac{V_p}{V_m}\right)^2 \cdot \frac{A_p}{A_m}$   $F_{Dp} = 550 \cdot \text{lbf} \times \frac{0.00237}{0.00237} \times \left(\frac{75}{300}\right)^2 \times 4^2$   $F_{Dp} = 550 \cdot \text{lbf}$

The power requirement would be:  $P = F_{Dp} \cdot V_p$   $P = 550 \cdot \text{lbf} \times 75 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\text{hp} \cdot \text{s}}{550 \cdot \text{ft} \cdot \text{lbf}}$   $P = 75.0 \cdot \text{hp}$   
 $P = 55.9 \cdot \text{kW}$

## Problem 7.75

[Difficulty: 2]

**7.75** Tests are performed on a 1:10-scale boat model. What must be the kinematic viscosity of the model fluid if friction and wave drag phenomena are to be correctly modeled? The full-size boat will be used in a freshwater lake where the average water temperature is 50°F.

**Given:** Model of boat

**Find:** Model kinematic viscosity for dynamic similarity

**Solution:**

For dynamic similarity  $\frac{V_m \cdot L_m}{\nu_m} = \frac{V_p \cdot L_p}{\nu_p}$  (1)  $\frac{V_m}{\sqrt{g \cdot L_m}} = \frac{V_p}{\sqrt{g \cdot L_p}}$  (2) (from Buckingham  $\Pi$ ; the first is the Reynolds number, the second the Froude number)

Hence from Eq 2  $\frac{V_m}{V_p} = \sqrt{\frac{g \cdot L_m}{g \cdot L_p}} = \sqrt{\frac{L_m}{L_p}}$

Using this in Eq 1  $\nu_m = \nu_p \cdot \frac{V_m}{V_p} \cdot \frac{L_m}{L_p} = \nu_p \cdot \sqrt{\frac{L_m}{L_p}} \cdot \frac{L_m}{L_p} = \nu_p \cdot \left(\frac{L_m}{L_p}\right)^{\frac{3}{2}}$


From Table A.8 at 50°F  $\nu_p = 1.41 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$   $\nu_m = 1.41 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}} \times \left(\frac{1}{10}\right)^{\frac{3}{2}}$   $\nu_m = 4.46 \times 10^{-7} \cdot \frac{\text{ft}^2}{\text{s}}$

Note that there aren't any fluids in Figure A.3 with viscosities that low!

## Problem 7.76

[Difficulty: 4]

**7.76** Your favorite professor likes mountain climbing, so there is always a possibility that the professor may fall into a crevasse in some glacier. If that happened today, and the professor was trapped in a slowly moving glacier, you are curious to know whether the professor would reappear at the downstream drop-off of the glacier during this academic year. Assuming ice is a Newtonian fluid with the density of glycerine but a million times as viscous, you decide to build a glycerin model and use dimensional analysis and similarity to estimate when the professor would reappear. Assume the real glacier is 15 m deep and is on a slope that falls 1.5 m in a horizontal distance of 1850 m. Develop the dimensionless parameters and conditions expected to govern dynamic similarity in this problem. If the model professor reappears in the laboratory after 9.6 hours, when should you return to the end of the real glacier to provide help to your favorite professor?



**Given:** Model the motion of a glacier using glycerine. Assume ice as Newtonian fluid with density of glycerine but one million times as viscous. In laboratory test the professor reappears in 9.6 hours.

**Find:** (a) Dimensionless parameters to characterize the model test results  
(b) Time needed for professor to reappear

**Solution:** We will use the Buckingham pi-theorem.

1     $V$      $\rho$      $g$      $\mu$      $D$      $H$      $L$     n = 7 parameters

2    Select primary dimensions F, L, t:

3     $V$      $\rho$      $g$      $\mu$      $D$      $H$      $L$

$\frac{L}{t}$      $\frac{M}{L^3}$      $\frac{L}{t^2}$      $\frac{M}{L \cdot t}$     L    L    L

r = 3 dimensions

4     $\rho$      $g$      $D$     m = r = 3 repeating parameters

5    We have n - m = 4 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = V \cdot \rho^a \cdot g^b \cdot D^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t^2}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $1 - 3 \cdot a + b + c = 0$

t:  $-1 - 2 \cdot b = 0$

The solution to this system is:

$$a = 0 \quad b = -\frac{1}{2} \quad c = -\frac{1}{2}$$

$$\Pi_1 = \frac{V}{\sqrt{g \cdot D}}$$

$$\Pi_2 = \mu \cdot \rho^a \cdot g^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t^2}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + b + c = 0$

t:  $-1 - 2 \cdot b = 0$

The solution to this system is:

$$a = -1 \quad b = -\frac{1}{2} \quad c = -\frac{3}{2}$$

$$\Pi_2 = \frac{\mu}{\rho \sqrt{g \cdot D^3}} \quad \text{(This is a gravity-driven version of Reynolds #)}$$

$$\Pi_3 = H \cdot \rho^a \cdot g^b \cdot D^c \quad \text{Thus:} \quad L \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{L}{t^2}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: a = 0$$

$$L: -1 - 3 \cdot a + b + c = 0$$

$$t: -2 \cdot b = 0$$

The solution to this system is:

$$a = 0 \quad b = 0 \quad c = -1$$

$$\Pi_3 = \frac{H}{D}$$

By inspection we can see that  $\Pi_4 = \frac{L}{D}$

$$6 \quad \text{Check using F, L, t dimensions:} \quad \frac{L}{t} \cdot \frac{t}{L^2} \cdot \frac{1}{L^2} = 1 \quad \frac{F \cdot t}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{t}{L^2} \cdot \frac{1}{L^2} = 1 \quad L \cdot \frac{1}{L} = 1$$

The functional relationship would be:  $\Pi_1 = f(\Pi_2, \Pi_3, \Pi_4)$  Matching the last two terms insures geometric similarity.

For dynamic similarity:  $\frac{\mu_m}{\rho_m \cdot \sqrt{g_m \cdot D_m^3}} = \frac{\mu_p}{\rho_p \cdot \sqrt{g_p \cdot D_p^3}}$  From Tables A.1 and A.2:  $SG_{ice} = 0.92 \quad SG_{glycerine} = 1.26$

Therefore:  $\frac{D_m}{D_p} = \left(\frac{\mu_m \cdot \rho_p}{\mu_p \cdot \rho_m}\right)^{\frac{2}{3}} = \left(\frac{1}{10^6} \times \frac{0.92}{1.26}\right)^{\frac{2}{3}} = 8.11 \times 10^{-5}$  Since we have geometric similarity, the last two terms must match for model and prototype:

So  $\frac{L_m}{L_p} = 8.11 \times 10^{-5} \quad L_m = 1850 \cdot m \times 8.11 \times 10^{-5}$  Matching the first  $\Pi$  term:  $\frac{V_m}{V_p} = \sqrt{\frac{D_m}{D_p}} = 0.00900$   
 $L_m = 0.1500 \text{ m}$

The time needed to reappear would be:  $\tau = \frac{L}{V}$  Thus:  $\tau_m = \frac{L_m}{V_m} \quad V_m = \frac{L_m}{\tau_m}$  Solving for the actual time:

$$\tau_p = \frac{L_p}{V_p} = \frac{L_m}{V_m} \cdot \frac{L_p}{L_m} \cdot \frac{V_m}{V_p} = \tau_m \cdot \frac{L_p}{L_m} \cdot \frac{V_m}{V_p} \quad \tau_p = 9.6 \cdot \text{hr} \times \frac{1}{8.11 \cdot 10^{-5}} \times 0.00900 \times \frac{\text{day}}{24 \cdot \text{hr}} \quad \tau_p = 44.4 \cdot \text{day}$$

Your professor will be back before the end of the semester!

## Problem 7.77

[Difficulty: 3]

**7.77** An automobile is to travel through standard air at 60 mph. To determine the pressure distribution, a  $\frac{1}{5}$ -scale model is to be tested in water. What factors must be considered to ensure kinematic similarity in the tests? Determine the water speed that should be used. What is the corresponding ratio of drag force between prototype and model flows? The lowest pressure coefficient is  $C_p = -1.4$  at the location of the minimum static pressure on the surface. Estimate the minimum tunnel pressure required to avoid cavitation, if the onset of cavitation occurs at a cavitation number of 0.5.

**Given:** Model of automobile

**Find:** Factors for kinematic similarity; Model speed; ratio of prototype and model drags; minimum pressure for no cavitation

**Solution:**

For dynamic similarity 
$$\frac{\rho_m \cdot V_m \cdot L_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot L_p}{\mu_p} \qquad V_m = V_p \cdot \frac{\rho_p}{\rho_m} \cdot \frac{L_p}{L_m} \cdot \frac{\mu_m}{\mu_p}$$

For air (Table A.9) and water (Table A.7) at 68°F

$$\begin{aligned} \rho_p &= 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3} & \mu_p &= 3.79 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \\ \rho_m &= 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} & \mu_m &= 2.10 \times 10^{-5} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \end{aligned}$$

$$V_m = 60 \cdot \text{mph} \times \frac{88 \cdot \frac{\text{ft}}{\text{s}}}{60 \cdot \text{mph}} \times \left( \frac{0.00234}{1.94} \right) \times \left( \frac{5}{1} \right) \times \left( \frac{2.10 \times 10^{-5}}{3.79 \times 10^{-7}} \right) \qquad V_m = 29.4 \cdot \frac{\text{ft}}{\text{s}}$$

Then 
$$\frac{F_m}{\rho_m \cdot V_m^2 \cdot L_m^2} = \frac{F_p}{\rho_p \cdot V_p^2 \cdot L_p^2}$$

Hence 
$$\frac{F_p}{F_m} = \frac{\rho_p \cdot V_p^2 \cdot L_p^2}{\rho_m \cdot V_m^2 \cdot L_m^2} = \left( \frac{0.00234}{1.94} \right) \times \left( \frac{88}{29.4} \right)^2 \times \left( \frac{5}{1} \right)^2 \qquad \frac{F_p}{F_m} = 0.270$$

For  $Ca = 0.5$  
$$\frac{p_{\min} - p_v}{\frac{1}{2} \cdot \rho \cdot V^2} = 0.5 \qquad \text{so we get} \qquad p_{\min} = p_v + \frac{1}{4} \cdot \rho \cdot V^2 \qquad \text{for the water tank}$$

From steam tables, for water at 68°F  $p_v = 0.339 \cdot \text{psi}$  so

$$p_{\min} = 0.339 \cdot \text{psi} + \frac{1}{4} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 29.4 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \qquad p_{\min} = 3.25 \cdot \text{psi}$$

This is the minimum allowable pressure in the water tank; we can use it to find the required tank pressure

$$C_p = -1.4 = \frac{p_{\min} - p_{\text{tank}}}{\frac{1}{2} \cdot \rho \cdot V^2} \qquad p_{\text{tank}} = p_{\min} + \frac{1.4}{2} \cdot \rho \cdot V^2 = p_{\min} + 0.7 \cdot \rho \cdot V^2$$

$$p_{\text{tank}} = 3.25 \cdot \text{psi} + 0.7 \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 29.4 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \qquad p_{\text{tank}} = 11.4 \cdot \text{psi}$$

## Problem 7.78

[Difficulty: 3]

**7.78** A 1:50-scale model of a submarine is to be tested in a towing tank under two conditions: motion at the free surface and motion far below the surface. The tests are performed in freshwater. On the surface, the submarine cruises at 24 knots. At what speed should the model be towed to ensure dynamic similarity? Far below the surface, the sub cruises at 0.35 knot. At what speed should the model be towed to ensure dynamic similarity? What must the drag of the model be multiplied by under each condition to give the drag of the full-scale submarine?

**Given:** A scale model of a submarine is to be tested in fresh water under two conditions:  
 1 - on the surface  
 2 - far below the surface

**Find:** (a) Speed for the model test on the surface  
 (b) Speed for the model test submerged  
 (c) Ratio of full-scale drag to model drag

**Solution:** On the surface, we need to match Froude numbers:  $\frac{V_m}{\sqrt{g \cdot L_m}} = \frac{V_p}{\sqrt{g \cdot L_p}}$  or:  $V_m = V_p \cdot \sqrt{\frac{L_m}{L_p}}$

Thus for 1:50 scale:  $V_m = 24 \cdot \text{knot} \times \sqrt{\frac{1}{50}}$   $V_m = 3.39 \cdot \text{knot}$  or  $V_m = 1.75 \cdot \frac{\text{m}}{\text{s}}$

When submerged, we need to match Reynolds numbers:  $\frac{\rho_m \cdot V_m \cdot L_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot L_p}{\mu_p}$  or:  $V_m = V_p \cdot \frac{\rho_p}{\rho_m} \cdot \frac{L_p}{L_m} \cdot \frac{\mu_m}{\mu_p}$

From Table A.2,  $SG_{\text{seawater}} = 1.025$  and  $\mu_{\text{seawater}} = 1.08 \times 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$  at 20°C. Thus for 1:50 scale:

$V_m = 0.35 \cdot \text{knot} \times \frac{1.025}{0.998} \times \frac{50}{1} \times \frac{1.08 \times 10^{-3}}{1.00 \times 10^{-3}}$   $V_m = 19.41 \cdot \text{knot}$  or  $V_m = 9.99 \cdot \frac{\text{m}}{\text{s}}$

Under dynamically similar conditions, the drag coefficients will match:  $\frac{F_{Dm}}{\frac{1}{2} \cdot \rho_m \cdot V_m^2 \cdot A_m} = \frac{F_{Dp}}{\frac{1}{2} \cdot \rho_p \cdot V_p^2 \cdot A_p}$

Solving for the ratio of forces:  $\frac{F_{Dp}}{F_{Dm}} = \frac{\rho_p}{\rho_m} \cdot \left(\frac{V_p}{V_m}\right)^2 \cdot \frac{A_p}{A_m} = \frac{\rho_p}{\rho_m} \cdot \left(\frac{V_p}{V_m} \cdot \frac{L_p}{L_m}\right)^2$  Substituting in known values:

For surface travel:  $\frac{F_{Dp}}{F_{Dm}} = \frac{1.025}{0.998} \times \left(\frac{24}{3.39} \times \frac{50}{1}\right)^2 = 1.29 \times 10^5$   $\frac{F_{Dp}}{F_{Dm}} = 1.29 \times 10^5$  (on surface)

For submerged travel:  $\frac{F_{Dp}}{F_{Dm}} = \frac{1.025}{0.998} \times \left(\frac{0.35}{19.41} \times \frac{50}{1}\right)^2 = 0.835$   $\frac{F_{Dp}}{F_{Dm}} = 0.835$  (submerged)

## Problem 7.79

[Difficulty: 2]

**7.79** A wind tunnel is being used to study the aerodynamics of a full-scale model rocket that is 12 in. long. Scaling for drag calculations are based on the Reynolds number. The rocket has an expected maximum velocity of 120 mph. What is the Reynolds number at this speed? Assume ambient air is at 68°F. The wind tunnel is capable of speeds up to 100 mph; so an attempt is made to improve this top speed by varying the air temperature. Calculate the equivalent speed for the wind tunnel using air at 40°F and 150°F. Would replacing air with carbon dioxide provide higher equivalent speeds?

**Given:** Model size, model speed, and air temperatures.

**Find:** Equivalent speed of the full scale vehicle corresponding to the different air temperatures.

**Solution:**

$$Re_L = \frac{VL}{\nu} \quad (\text{Reynolds Number})$$

**Governing Equation:**

where V is the air velocity, L is the length of the rocket or model, and  $\nu$  is the kinematic viscosity of air. Subscript m corresponds to the model and r is the rocket.

**Assumption:** Modeling follows the Reynolds equivalency.

The given or available data is:  $L_m = L_R = 12\text{in}$   $V_T = 100\text{mph}$   $V_R = 120\text{mph}$

$$\nu_{40^\circ\text{F}} = 1.47 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \quad (\text{Table A.9})$$

$$\nu_{68^\circ\text{F}} = 1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \quad (\text{Table A.9})$$

$$\nu_{150^\circ\text{F}} = 2.09 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \quad (\text{Table A.9})$$

$$\nu_{\text{CO}_2} = 8.3 \times 10^{-6} \frac{\text{m}^2}{\text{s}} \quad (\text{Figure A.3 or other source})$$

Determine the Reynolds Number for expected maximum speed at ambient temperature:

$$Re_L = \frac{V_R L_R}{\nu_R} = \frac{120 \frac{\text{mile}}{\text{hr}} \times \frac{5280\text{ft}}{\text{mile}} \times \frac{\text{hr}}{3600\text{s}} \times 12\text{in} \times \frac{\text{ft}}{12\text{in}}}{1.62 \times 10^{-4} \times \frac{\text{ft}^2}{\text{s}}} \quad Re_L = 1.09 \times 10^6$$

Re-arrange the Reynolds Number Equation for speed equivalents:  $Re_L = \frac{VL}{\nu} \Rightarrow V_R = V_T \times \frac{L_M}{L_R} \times \frac{\nu_{68^\circ\text{F}}}{\nu_T}$

In this problem, the only term that changes is  $\nu_T$

$$\text{Solve for speed at the low temperature: } V_R = V_T \times \frac{L_M}{L_R} \times \frac{\nu_{68^\circ\text{F}}}{\nu_{40^\circ\text{F}}} = 100\text{mph} \times \frac{12\text{in}}{12\text{in}} \times \frac{1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}}{1.47 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}} = 110\text{mph}$$

$$\text{Solve for speed at the high temperature: } V_R = V_T \times \frac{L_M}{L_R} \times \frac{v_{68^\circ\text{F}}}{v_{150^\circ\text{F}}} = 100\text{mph} \times \frac{12\text{in}}{12\text{in}} \times \frac{1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}}{2.09 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}} = 77.5\text{mph}$$

$$\text{Solve for CO}_2\text{: } V_R = V_T \times \frac{L_M}{L_R} \times \frac{v_{68^\circ\text{F}}}{v_{\text{CO}_2}} = 100\text{mph} \times \frac{12\text{in}}{12\text{in}} \times \frac{1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}}{8.3 \times 10^{-6} \frac{\text{m}^2}{\text{s}} \times \left(\frac{\text{ft}}{0.305\text{m}}\right)^2} = 181\text{mph}$$

$$V_{R@40^\circ\text{F}} = 110\text{mph}$$

$$V_{R@150^\circ\text{F}} = 77.5\text{mph}$$

$$V_{R@CO_2} = 181\text{mph}$$

Chilling the air to 40°F increases the model speed, but not enough to achieve the target. Heating the air works against the desired outcome.

This shows that the equivalent speed can be increased by decreasing the kinematic viscosity. An inspection of figure A.3 shows that cooling air decreases the kinematic viscosity. It also shows that CO<sub>2</sub> has a lower kinematic viscosity than air resulting in much higher model speeds.

## Problem 7.80

[Difficulty: 3]

**7.80** Consider water flow around a circular cylinder, of diameter  $D$  and length  $l$ . In addition to geometry, the drag force is known to depend on liquid speed,  $V$ , density,  $\rho$ , and viscosity,  $\mu$ . Express drag force,  $F_D$ , in dimensionless form as a function of all relevant variables. The static pressure distribution on a circular cylinder, measured in the laboratory, can be expressed in terms of the dimensionless pressure coefficient; the lowest pressure coefficient is  $C_p = -2.4$  at the location of the minimum static pressure on the cylinder surface. Estimate the maximum speed at which a cylinder could be towed in water at atmospheric pressure, without causing cavitation, if the onset of cavitation occurs at a cavitation number of 0.5.

**Given:** The drag force on a circular cylinder immersed in a water flow can be expressed as a function of  $D$ ,  $l$ ,  $V$ ,  $\rho$ , and  $\mu$ . Static pressure distribution can be expressed in terms of the pressure coefficient. At the minimum static pressure, the pressure coefficient is equal to  $-2.4$ . Cavitation onset occurs at a cavitation number of 0.5.

**Find:** (a) Drag force in dimensionless form as a function of all relevant variables  
(b) Maximum speed at which a cylinder could be towed in water at atmospheric pressure without cavitation

**Solution:** The functional relationship for drag force is:  $F_D = F_D(D, l, V, \rho, \mu)$  From the Buckingham  $\Pi$ -theorem, we have 6 variables and 3 repeating parameters. Therefore, we will have 3 dimensionless groups. The functional form of these groups is:

$$\frac{F_D}{\rho \cdot V^2 \cdot D^2} = f\left(\frac{l}{D}, \frac{\rho \cdot V \cdot D}{\mu}\right)$$

The pressure coefficient is:  $C_p = \frac{p - p_{\text{inf}}}{\frac{1}{2} \cdot \rho \cdot V^2}$  and the cavitation number is:  $Ca = \frac{p - p_v}{\frac{1}{2} \cdot \rho \cdot V^2}$

At the minimum pressure point  $p_{\text{min}} = p_{\text{inf}} + \frac{1}{2} \cdot \rho \cdot V_{\text{max}}^2 \cdot C_{p\text{min}}$  where  $C_{p\text{min}} = -2.4$

At the onset of cavitation  $p_{\text{min}} = p_v + \frac{1}{2} \cdot \rho \cdot V_{\text{max}}^2 \cdot Ca$  where  $Ca = 0.5$

Equating these two expressions:  $p_{\text{inf}} + \frac{1}{2} \cdot \rho \cdot V_{\text{max}}^2 \cdot C_{p\text{min}} = p_v + \frac{1}{2} \cdot \rho \cdot V_{\text{max}}^2 \cdot Ca$  and if we solve for  $V_{\text{max}}$ :

$$V_{\text{max}} = \sqrt{\frac{2(p_{\text{inf}} - p_v)}{\rho(Ca - C_{p\text{min}})}} \quad \text{At room temperature (68 deg F): } p_v = 0.339 \cdot \text{psi} \quad \rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$$

Substituting values we get:

$$V_{\text{max}} = \sqrt{2 \times (14.7 - 0.339) \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \frac{1}{[0.5 - (-2.4)]} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} \times \frac{144 \cdot \text{in}^2}{\text{ft}^2}} \quad V_{\text{max}} = 27.1 \cdot \frac{\text{ft}}{\text{s}}$$

## Problem 7.81

[Difficulty: 4]

**7.81** A circular container, partially filled with water, is rotated about its axis at constant angular speed,  $\omega$ . At any time,  $\tau$ , from the start of rotation, the speed,  $V_\theta$ , at distance  $r$  from the axis of rotation, was found to be a function of  $\tau$ ,  $\omega$ , and the properties of the liquid. Write the dimensionless parameters that characterize this problem. If, in another experiment, honey is rotated in the same cylinder at the same angular speed, determine from your dimensionless parameters whether honey will attain steady motion as quickly as water. Explain why the Reynolds number would not be an important dimensionless parameter in scaling the steady-state motion of liquid in the container.

**Given:** A circular container partially filled with water is rotated about its axis at constant angular velocity  $\omega$ . Velocity in the  $\theta$  direction is a function of  $r$ ,  $\tau$ ,  $\omega$ ,  $\rho$ , and  $\mu$ .

**Find:** (a) Dimensionless parameters that characterize this problem  
 (b) If honey would attain steady motion as quickly as water if rotated at the same angular speed  
 (c) Why Reynolds number is not an important parameter in scaling the steady-state motion of liquid in the container.

**Solution:** The functional relationship for drag force is:  $V_\theta = V_\theta(\omega, r, \tau, \rho, \mu)$  From the Buckingham  $\Pi$ -theorem, we have 6 variables and 3 repeating parameters. Therefore, we will have 3 dimensionless groups. The functional form of these groups is:

$$\frac{V_\theta}{\omega \cdot r} = g\left(\frac{\mu}{\rho \cdot \omega \cdot r^2}, \omega \cdot \tau\right)$$

From the above result  $\Pi_2 = \frac{\mu}{\rho \cdot \omega \cdot r^2}$  containing the properties  $\mu$  and  $\rho$ , and  $\Pi_3 = \omega \cdot \tau$  containing the time  $\tau$

$$\Pi_2 \cdot \Pi_3 = \frac{\mu}{\rho \cdot \omega \cdot r^2} \cdot \omega \cdot \tau = \frac{\mu \cdot \tau}{\rho \cdot r^2} = \frac{\nu \cdot \tau}{r^2} \quad \text{Now for steady flow: } \frac{\nu_h \cdot \tau_h}{r^2} = \frac{\nu_w \cdot \tau_w}{r^2} \quad \text{and at the same radius:}$$

$$\nu_h \cdot \tau_h = \nu_w \cdot \tau_w \quad \tau_h = \tau_w \cdot \frac{\nu_w}{\nu_h} \quad \text{Now since honey is more viscous than water, it follows that: } \tau_h < \tau_w$$

At steady state, solid body rotation exists. There are no viscous forces, and therefore, the Reynolds number would not be important.

## Problem 7.82

[Difficulty: 3]

**7.82** A  $\frac{1}{10}$ -scale model of a tractor-trailer rig is tested in a wind tunnel. The model frontal area is  $A_m = 0.1 \text{ m}^2$ . When tested at  $V_m = 75 \text{ m/s}$  in standard air, the measured drag force is  $F_D = 350 \text{ N}$ . Evaluate the drag coefficient for the model conditions given. Assuming that the drag coefficient is the same for model and prototype, calculate the drag force on a prototype rig at a highway speed of  $90 \text{ km/hr}$ . Determine the air speed at which a model should be tested to ensure dynamically similar results if the prototype speed is  $90 \text{ km/hr}$ . Is this air speed practical? Why or why not?

**Given:** Model of tractor-trailer truck

**Find:** Drag coefficient; Drag on prototype; Model speed for dynamic similarity

### Solution

For kinematic similarity we need to ensure the geometries of model and prototype are similar, as is the incoming flow field

The drag coefficient is

$$C_D = \frac{F_m}{\frac{1}{2} \cdot \rho_m \cdot V_m^2 \cdot A_m}$$

For air (Table A.10) at  $20^\circ\text{C}$

$$\rho_m = 1.21 \cdot \frac{\text{kg}}{\text{m}^3} \quad \mu_p = 1.81 \times 10^{-5} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$$

$$C_D = 2 \times 350 \cdot \text{N} \times \frac{\text{m}^3}{1.21 \cdot \text{kg}} \times \left( \frac{\text{s}}{75 \cdot \text{m}} \right)^2 \times \frac{1}{0.1 \cdot \text{m}^2} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} \quad C_D = 1.028$$

This is the drag coefficient for model and prototype

For the rig

$$F_p = \frac{1}{2} \cdot \rho_p \cdot V_p^2 \cdot A_p \cdot C_D \quad \text{with} \quad \frac{A_p}{A_m} = \left( \frac{L_p}{L_m} \right)^2 = 100 \quad A_p = 10 \cdot \text{m}^2$$

$$F_p = \frac{1}{2} \times 1.21 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 90 \cdot \frac{\text{km}}{\text{hr}} \times \frac{1000 \cdot \text{m}}{1 \cdot \text{km}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} \right)^2 \times 10 \cdot \text{m}^2 \times 1.028 \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} \quad F_p = 3.89 \cdot \text{kN}$$

For dynamic similarity

$$\frac{\rho_m \cdot V_m \cdot L_m}{\mu_m} = \frac{\rho_p \cdot V_p \cdot L_p}{\mu_p} \quad V_m = V_p \cdot \frac{\rho_p}{\rho_m} \cdot \frac{L_p}{L_m} \cdot \frac{\mu_m}{\mu_p} = V_p \cdot \frac{L_p}{L_m}$$

$$V_m = 90 \cdot \frac{\text{km}}{\text{hr}} \times \frac{1000 \cdot \text{m}}{1 \cdot \text{km}} \times \frac{1 \cdot \text{hr}}{3600 \cdot \text{s}} \times \frac{10}{1} \quad V_m = 250 \frac{\text{m}}{\text{s}}$$

For air at standard conditions, the speed of sound is  $c = \sqrt{k \cdot R \cdot T}$

$$c = \sqrt{1.40 \times 286.9 \cdot \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times (20 + 273) \cdot \text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{s}^2 \cdot \text{N}}} \quad c = 343 \frac{\text{m}}{\text{s}}$$

Hence we have  $M = \frac{V_m}{c} = \frac{250}{343} = 0.729$  which indicates compressibility is significant - this model speed is impractical (and unnecessary)

## Problem 7.83

[Difficulty: 3]


**7.83** It is recommended in [8] that the frontal area of a model be less than 5 percent of the wind tunnel test section area and  $Re = Vw/\nu > 2 \times 10^6$ , where  $w$  is the model width. Further, the model height must be less than 30 percent of the test section height, and the maximum projected width of the model at maximum yaw ( $20^\circ$ ) must be less than 30 percent of the test section width. The maximum air speed should be less than 300 ft/s to avoid compressibility effects. A model of a tractor-trailer rig is to be tested in a wind tunnel that has a test section 1.5 ft high and 2 ft wide. The height, width, and length of the full-scale rig are 13 ft 6 in., 8 ft, and 65 ft, respectively. Evaluate the scale ratio of the largest model that meets the recommended criteria. Assess whether an adequate Reynolds number can be achieved in this test facility.

**Given:** Recommended procedures for wind tunnel tests of trucks and buses suggest:  
 -Model frontal area less than 5% of test section area  
 -Reynolds number based on model width greater than 2,000,000  
 -Model height less than 30% of test section height  
 -Model projected width at maximum yaw ( $20^\circ$ ) less than 30% of test section width  
 -Air speed less than 300 ft/s to avoid compressibility effects  
 Model of a tractor-trailer to be tested in a tunnel 1.5 ft high x 2 ft wide. Full scale rig is 13'6" high, 8' wide, and 65' long.

**Find:** (a) Max scale for tractor-trailer model in this tunnel  
 (b) If adequate Reynolds number can be achieved in this facility.

**Solution:** Let  $s$  be the scale ratio. Then:  $h_m = s \cdot h_p$   $w_m = s \cdot w_p$   $l_m = s \cdot l_p$   
 Area criterion:  $A_m = 0.05 \times 1.5 \cdot \text{ft} \times 2.0 \cdot \text{ft}$   $A_m = 0.15 \cdot \text{ft}^2$  Therefore:  $s = \sqrt{\frac{0.15}{13.5 \times 8}}$   $s = 0.0373$   
 Height criterion:  $h_m = 0.30 \times 1.5 \cdot \text{ft}$   $h_m = 0.45 \cdot \text{ft}$  Therefore:  $s = \frac{0.45}{13.5}$   $s = 0.0333$

Width criterion: we need to account for the yaw in the model. We make a relationship for the maximum width as a function of the model dimensions and the yaw angle and relate that to the full-scale dimensions.



$$w_{m20\text{deg}} = w_m \cdot \cos(20 \cdot \text{deg}) + l_m \cdot \sin(20 \cdot \text{deg}) = s \cdot (w_p \cdot \cos(20 \cdot \text{deg}) + l_p \cdot \sin(20 \cdot \text{deg}))$$

$$w_{m20\text{deg}} = 0.30 \times 2.0 \cdot \text{ft} \quad w_{m20\text{deg}} = 0.60 \cdot \text{ft}$$

$$\text{Therefore: } s = \frac{0.60}{8 \times \cos(20 \cdot \text{deg}) + 65 \times \sin(20 \cdot \text{deg})} \quad s = 0.0202$$

To determine the acceptable scale for the model, we take the smallest of these scale factors:  $s = 0.0202$

$\frac{1}{s} = 49.58$  We choose a round number to make the model scale easier to calculate:  $\text{Model} = \frac{1}{50} \text{Prototype}$

For the current model conditions:  $Re = \frac{V_m \cdot w_m}{\nu_m}$  For standard air:  $\nu_m = 1.57 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$  Substituting known values:

$$Re = 300 \cdot \frac{\text{ft}}{\text{s}} \times \left( \frac{1}{50} \times 8 \cdot \text{ft} \right) \times \frac{s}{1.57 \times 10^{-4} \cdot \text{ft}^2} \quad Re = 3.06 \times 10^5$$

This is less than the minimum stipulated in the problem, thus:  
An adequate Reynolds number can not be achieved.

## Problem 7.84

[Difficulty: 4]

**7.84** The power,  $\mathcal{P}$ , required to drive a fan is assumed to depend on fluid density  $\rho$ , volume flow rate  $Q$ , impeller diameter  $D$ , and angular speed  $\omega$ . If a fan with  $D_1 = 8$  in. delivers  $Q_1 = 15$  ft<sup>3</sup>/s of air at  $\omega_1 = 2500$  rpm, what size diameter fan could be expected to deliver  $Q_2 = 88$  ft<sup>3</sup>/s of air at  $\omega_2 = 1800$  rpm, provided they were geometrically and dynamically similar?

**Given:** Power to drive a fan is a function of  $\rho$ ,  $Q$ ,  $D$ , and  $\omega$ .

$$\text{Condition 1: } D_1 = 8 \cdot \text{in} \quad \omega_1 = 2500 \cdot \text{rpm} \quad Q_1 = 15 \cdot \frac{\text{ft}^3}{\text{s}} \quad \text{Condition 2: } Q_2 = 88 \cdot \frac{\text{ft}^3}{\text{s}} \quad \omega_2 = 1800 \cdot \text{rpm}$$

**Find:** Fan diameter for condition 2 to insure dynamic similarity

**Solution:** We will use the Buckingham pi-theorem.

1     $P$      $\rho$      $Q$      $D$      $\omega$     n = 5 parameters

2    Select primary dimensions M, L, t:

3     $P$      $\rho$      $Q$      $D$      $\omega$

$$\frac{M \cdot L^2}{t^3} \quad \frac{M}{L^3} \quad \frac{L^3}{t} \quad L \quad \frac{1}{t}$$

r = 3 dimensions

4     $\rho$      $D$      $\omega$     m = r = 3 repeating parameters

5    We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = P \cdot \rho^a \cdot D^b \cdot \omega^c \quad \text{Thus: } \frac{M \cdot L^2}{t^3} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{1}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $2 - 3 \cdot a + b = 0$

t:  $-3 - c = 0$

The solution to this system is:

$a = -1 \quad b = -5 \quad c = -3$

$$\Pi_1 = \frac{P}{\rho \cdot \omega^3 \cdot D^5}$$

$$\Pi_2 = Q \cdot \rho^a \cdot D^b \cdot \omega^c \quad \text{Thus: } \frac{L^3}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{1}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $3 - 3 \cdot a + b = 0$

t:  $-1 - c = 0$

The solution to this system is:

$a = 0 \quad b = -3 \quad c = -1$

$$\Pi_2 = \frac{Q}{\omega \cdot D^3}$$

6    Check using F, L, t dimensions:  $\frac{F \cdot L}{t} \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^5} \cdot t^3 = 1 \quad \frac{L^3}{t} \cdot t \cdot \frac{1}{L^3} = 1$     Thus the relationship is:  $\frac{P}{\rho \cdot \omega^3 \cdot D^5} = f\left(\frac{Q}{\omega \cdot D^3}\right)$

For dynamic similarity we must have geometric and kinematic similarity, and:

$$D_2 = D_1 \cdot \left(\frac{Q_2 \cdot \omega_1}{Q_1 \cdot \omega_2}\right)^{\frac{1}{3}} \quad D_2 = 8 \cdot \text{in} \times \left(\frac{88}{15} \times \frac{2500}{1800}\right)^{\frac{1}{3}} \quad \frac{Q_1}{\omega_1 \cdot D_1^3} = \frac{Q_2}{\omega_2 \cdot D_2^3} \quad \text{Solving for } D_2$$

$$D_2 = 16.10 \cdot \text{in}$$

## Problem 7.85 (In Excel)

[Difficulty: 3]

**7.85** Over a certain range of air speeds,  $V$ , the lift,  $F_L$ , produced by a model of a complete aircraft in a wind tunnel depends on the air speed, air density,  $\rho$ , and a characteristic length (the wing base chord length,  $c = 150$  mm). The following experimental data is obtained for air at standard atmospheric conditions:

$V$ (m/s)	10	15	20	25	30	35	40	45	50
$F_L$ (N)	2.2	4.8	8.7	13.3	19.6	26.5	34.5	43.8	54

Plot the lift versus speed curve. By using *Excel* to perform a trendline analysis on this curve, generate and plot data for the lift produced by the prototype, which has a wing base chord length of 5 m, over a speed range of 75 m/s to 250 m/s.

**Given:** Data on model of aircraft

**Find:** Plot of lift vs speed of model; also of prototype

**Solution:**

$V_m$ (m/s)	10	15	20	25	30	35	40	45	50
$F_m$ (N)	2.2	4.8	8.7	13.3	19.6	26.5	34.5	43.8	54.0

This data can be fit to

$$F_m = \frac{1}{2} \cdot \rho \cdot A_m \cdot C_D \cdot V_m^2 \quad \text{or} \quad F_m = k_m \cdot V_m^2$$

From the trendline, we see that

$$k_m = 0.0219 \quad \text{N}/(\text{m/s})^2$$

(And note that the power is 1.9954 or 2.00 to three significant figures, confirming the relation is quadratic)


Also,  $k_p = 1110 k_m$

Hence,


$$k_p = 24.3 \text{ N}/(\text{m/s})^2 \quad F_p = k_p V_m^2$$

$V_p$ (m/s)	75	100	125	150	175	200	225	250
$F_p$ (kN) (Trendline)	137	243	380	547	744	972	1231	1519


### Lift vs Speed for an Airplane Model




### Lift vs Speed for an Airplane Prototype



Lift vs Speed for an Airplane Model  
(Log-Log Plot)



Lift vs Speed for an Airplane Prototype (Log-Log Plot)



## Problem 7.86

[Difficulty: 2]

**7.86** The pressure rise,  $\Delta p$ , of a liquid flowing steadily through a centrifugal pump depends on pump diameter  $D$ , angular speed of the rotor  $\omega$ , volume flow rate  $Q$ , and density  $\rho$ . The table gives data for the prototype and for a geometrically similar model pump. For conditions corresponding to dynamic similarity between the model and prototype pumps, calculate the missing values in the table.

Variable	Prototype	Model
$\Delta p$	525 kPa	
$Q$		0.0928 m <sup>3</sup> /min
$\rho$	800 kg/m <sup>3</sup>	999 kg/m <sup>3</sup>
$\omega$	183 rad/s	367 rad/s
$D$	150 mm	50 mm

**Given:** Information relating to geometrically similar model test for a centrifugal pump.

**Find:** The missing values in the table

**Solution:** We will use the Buckingham pi-theorem.

1     $\Delta p$      $Q$      $\rho$      $\omega$      $D$  n = 5 parameters

2    Select primary dimensions M, L, t:

3     $\Delta p$      $Q$      $\rho$      $\omega$      $D$

$$\frac{M}{L \cdot t^2} \quad \frac{L^3}{t} \quad \frac{M}{L^3} \quad \frac{1}{t} \quad L$$

r = 3 dimensions

4     $\rho$      $\omega$      $D$  m = r = 3 repeating parameters

5    We have n - m = 2 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = \Delta p \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad \frac{M}{L \cdot t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $1 + a = 0$

L:  $-1 - 3 \cdot a + c = 0$

t:  $-2 - b = 0$

The solution to this system is:

$a = -1 \quad b = -2 \quad c = -2$

$$\Pi_1 = \frac{\Delta p}{\rho \cdot \omega^2 \cdot D^2}$$

$$\Pi_2 = Q \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad \frac{L^3}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

M:  $a = 0$

L:  $3 - 3 \cdot a + c = 0$

t:  $-1 - b = 0$

The solution to this system is:

$a = 0 \quad b = -1 \quad c = -3$

$$\Pi_2 = \frac{Q}{\omega \cdot D^3}$$

6    Check using F, L, t dimensions:  $\frac{F}{L^2} \cdot \frac{L^4}{F \cdot t^2} \cdot t^2 \cdot \frac{1}{L^2} = 1 \quad \frac{L^3}{t} \cdot t \cdot \frac{1}{L^3} = 1$     Thus the relationship is:  $\frac{\Delta p}{\rho \cdot \omega^2 \cdot D^2} = f\left(\frac{Q}{\omega \cdot D^3}\right)$

The flows are geometrically similar, and we assume kinematic similarity. Thus, for dynamic similarity:

$$\text{If } \frac{Q_m}{\omega_m \cdot D_m^3} = \frac{Q_p}{\omega_p \cdot D_p^3} \text{ then } \frac{\Delta p_m}{\rho_m \cdot \omega_m^2 \cdot D_m^2} = \frac{\Delta p_p}{\rho_p \cdot \omega_p^2 \cdot D_p^2}$$

$$\text{From the first relation: } Q_p = Q_m \cdot \frac{\omega_p}{\omega_m} \cdot \left(\frac{D_p}{D_m}\right)^3 \quad Q_p = 0.0928 \cdot \frac{\text{m}^3}{\text{min}} \times \frac{183}{367} \times \left(\frac{150}{50}\right)^3 \quad Q_p = 1.249 \cdot \frac{\text{m}^3}{\text{min}}$$

$$\text{From the second relation: } \Delta p_m = \Delta p_p \cdot \frac{\rho_m}{\rho_p} \cdot \left(\frac{\omega_m}{\omega_p} \cdot \frac{D_m}{D_p}\right)^2 \quad \Delta p_m = 52.5 \cdot \text{kPa} \times \frac{999}{800} \times \left(\frac{367}{183} \times \frac{50}{150}\right)^2 \quad \Delta p_m = 29.3 \cdot \text{kPa}$$

## Problem 7.87

[Difficulty: 3]

**7.87** Tests are performed on a 3-ft-long ship model in a water tank. Results obtained (after doing some data analysis) are as follows:

$V$ (ft/s)	10	20	30	40	50	60	70
$D_{Wave}$ (lbf)	0	0.028	0.112	0.337	0.674	0.899	1.237
$D_{Friction}$ (lbf)	0.022	0.079	0.169	0.281	0.45	0.618	0.731

The assumption is that wave drag is done using the Froude number and friction drag by the Reynolds number. The full-size ship will be 150 ft long when built. Estimate the total drag when it is cruising at 15 knots and at 20 knots in a freshwater lake.

For drag we can use  $C_D = \frac{D}{\frac{1}{2} \rho V^2 A}$

As a suitable scaling area for  $A$  we use  $L^2$

$$C_D = \frac{D}{\frac{1}{2} \rho V^2 L^2}$$

**Model:**  $L = 3$  ft

For water  $\rho = 1.94$  slug/ft<sup>3</sup>  
 $\mu = 2.10 \times 10^{-5}$  lbf s/ft<sup>2</sup>

The data is:

$V$ (ft/s)	10	20	30	40	50	60	70
$D_{Wave}$ (lbf)	0	0.028	0.112	0.337	0.674	0.899	1.237
$D_{Friction}$ (lbf)	0.022	0.079	0.169	0.281	0.45	0.618	0.731

$Fr$	1.017	2.035	3.052	4.070	5.087	6.105	7.122
$Re$	2.77E+06	5.54E+06	8.31E+06	1.11E+07	1.39E+07	1.66E+07	1.94E+07
$C_{D(Wave)}$	0.00E+00	8.02E-06	1.43E-05	2.41E-05	3.09E-05	2.86E-05	2.89E-05
$C_{D(Friction)}$	2.52E-05	2.26E-05	2.15E-05	2.01E-05	2.06E-05	1.97E-05	1.71E-05

The friction drag coefficient becomes a constant, as expected, at high  $Re$ .  
 The wave drag coefficient appears to be linear with  $Fr$ , over most values

**Ship:**  $L = 150$  ft

$V$ (knot)	15	20
$V$ (ft/s)	25.32	33.76
$Fr$	0.364	0.486
$Re$	3.51E+08	4.68E+08

$$D = \frac{1}{2} \rho V^2 L^2 C_D$$

Hence for the ship we have very high  $Re$ , and low  $Fr$ .



From the graph we see the friction  $C_D$  levels out at about  $1.9 \times 10^{-5}$

From the graph we see the wave  $C_D$  is negligibly small

$C_{D(Wave)}$	0	0
$C_{D(Friction)}$	1.90E-05	1.90E-05

$D_{Wave}$ (lbf)	0	0
$D_{Friction}$ (lbf)	266	473

$D_{Total}$ (lbf)	266	473
-------------------	-----	-----



## Problem 7.88 (In Excel)

[Difficulty: 4]

**7.88** A centrifugal water pump running at speed  $\omega = 800$  rpm has the following data for flow rate,  $Q$ , and pressure head,  $\Delta p$ .

$Q$ (ft <sup>3</sup> /min)	0	50	75	100	120	140	150	165
$\Delta p$ (psf)	7.54	7.29	6.85	6.12	4.80	3.03	2.38	1.23

The pressure head is a function of the flow rate, speed, impeller diameter  $D$ , and water density  $\rho$ . Plot the pressure head versus flow rate curve. Find the two  $\Pi$  parameters for this problem, and, from the above data, plot one against the other. By using *Excel* to perform a trendline analysis on this latter curve, generate and plot data for pressure head versus flow rate for impeller speeds of 600 rpm and 1200 rpm.

**Given:** Data on centrifugal water pump

**Find:**  $\Pi$  groups; plot pressure head vs flow rate for range of speeds

**Solution:**

We will use the workbook of Example 7.1, modified for the current problem

The number of parameters is:	$n = 5$
The number of primary dimensions is:	$r = 3$
The number of repeat parameters is:	$m = r = 3$
The number of $\Pi$ groups is:	$n - m = 2$

Enter the dimensions (**M, L, t**) of the repeating parameters, and of up to four other parameters (for up to four  $\Pi$  groups). The spreadsheet will compute the exponents  $a$ ,  $b$ , and  $c$  for each.

**REPEATING PARAMETERS:** Choose  $\rho$ ,  $g$ ,  $d$

	<b>M</b>	<b>L</b>	<b>t</b>
$\rho$	1	-3	
$\omega$			-1
$D$		1	

**$\Pi$  GROUPS:**

	<b>M</b>	<b>L</b>	<b>t</b>			<b>M</b>	<b>L</b>	<b>t</b>
$\Delta p$	1	-1	-2		$Q$	0	3	-1
$\Pi_1$ :	$a =$	-1			$\Pi_2$ :	$a =$	0	
	$b =$	-2				$b =$	-1	
	$c =$	-2				$c =$	-3	

The following  $\Pi$  groups from Example 7.1 are not used:

	<b>M</b>	<b>L</b>	<b>t</b>			<b>M</b>	<b>L</b>	<b>t</b>
$\Pi_3$ :	0	0	0		$\Pi_4$ :	0	0	0
	$a =$	0				$a =$	0	
	$b =$	0				$b =$	0	
	$c =$	0				$c =$	0	

Hence  $\Pi_1 = \frac{\Delta p}{\rho \omega^2 D^2}$  and  $\Pi_2 = \frac{Q}{\omega D^3}$  with  $\Pi_1 = f(\Pi_2)$ .

Based on the plotted data, it looks like the relation between  $\Pi_1$  and  $\Pi_2$  may be parabolic


Hence  $\frac{\Delta p}{\rho \omega^2 D^2} = a + b \left( \frac{Q}{\omega D^3} \right) + c \left( \frac{Q}{\omega D^3} \right)^2$

The data is

$Q$ (ft <sup>3</sup> /min)	0	50	75	100	120	140	150	165
$\Delta p$ (psf)	7.54	7.29	6.85	6.12	4.80	3.03	2.38	1.23

$\rho = 1.94$  slug/ft<sup>3</sup>  
 $\omega = 800$  rpm  
 $D = 1$  ft ( $D$  is not given; use  $D = 1$  ft as a scale)

$Q/(\omega D^3)$	0.00000	0.00995	0.01492	0.01989	0.02387	0.02785	0.02984	0.03283
$\Delta p/(\rho \omega^2 D^2)$	0.000554	0.000535	0.000503	0.000449	0.000353	0.000223	0.000175	0.000090



The curve fit result is:  $\Delta p/(\rho \omega^2 D^2) = -0.6302 (Q/(\omega D^3))^2 + 0.006476 (Q/(\omega D^3)) + 0.0005490$

From the *Trendline* analysis

$a = 0.000549$   
 $b = 0.006476$   
 $c = -0.6302$

and 
$$\Delta p = \rho \omega^2 D^2 \left[ a + b \left( \frac{Q}{\omega D^3} \right) + c \left( \frac{Q}{\omega D^3} \right)^2 \right]$$


Finally, data at 500 and 1000 rpm can be calculated and plotted

$\omega = 600$  rpm

$Q$ (ft <sup>3</sup> /min)	0	20	40	60	80	100	120	132
$\Delta p$ (kPa)	4.20	4.33	4.19	3.77	3.08	2.12	0.89	0.00

$\omega = 1200$  rpm

$Q$ (ft <sup>3</sup> /min)	0	50	75	100	120	140	150	165
$\Delta p$ (kPa)	16.82	17.29	16.88	16.05	15.09	13.85	13.12	11.91



## Problem 7.89

[Difficulty: 3]

**7.89** An axial-flow pump is required to deliver  $0.75 \text{ m}^3/\text{s}$  of water at a head of  $15 \text{ J/kg}$ . The diameter of the rotor is  $0.25 \text{ m}$ , and it is to be driven at  $500 \text{ rpm}$ . The prototype is to be modeled on a small test apparatus having a  $2.25 \text{ kW}$ ,  $1000 \text{ rpm}$  power supply. For similar performance between the prototype and the model, calculate the head, volume flow rate, and diameter of the model.

**Given:** Model of water pump

**Find:** Model head, flow rate and diameter

**Solution:**

From Buckingham II 
$$\frac{h}{\omega^2 \cdot D^2} = f\left(\frac{Q}{\omega \cdot D^3}, \frac{\rho \cdot \omega \cdot D^2}{\mu}\right) \quad \text{and} \quad \frac{P}{\omega^3 \cdot D^5} = f\left(\frac{Q}{\omega \cdot D^3}, \frac{\rho \cdot \omega \cdot D^2}{\mu}\right)$$

Neglecting viscous effects 
$$\frac{Q_m}{\omega_m \cdot D_m^3} = \frac{Q_p}{\omega_p \cdot D_p^3} \quad \text{then} \quad \frac{h_m}{\omega_m^2 \cdot D_m^2} = \frac{h_p}{\omega_p^2 \cdot D_p^2} \quad \text{and} \quad \frac{P_m}{\omega_m^3 \cdot D_m^5} = \frac{P_p}{\omega_p^3 \cdot D_p^5}$$

Hence if 
$$\frac{Q_m}{Q_p} = \frac{\omega_m}{\omega_p} \cdot \left(\frac{D_m}{D_p}\right)^3 = \frac{1000}{500} \cdot \left(\frac{D_m}{D_p}\right)^3 = 2 \cdot \left(\frac{D_m}{D_p}\right)^3 \quad (1)$$

then 
$$\frac{h_m}{h_p} = \frac{\omega_m^2}{\omega_p^2} \cdot \frac{D_m^2}{D_p^2} = \left(\frac{1000}{500}\right)^2 \cdot \frac{D_m^2}{D_p^2} = 4 \cdot \frac{D_m^2}{D_p^2} \quad (2)$$

and 
$$\frac{P_m}{P_p} = \frac{\omega_m^3}{\omega_p^3} \cdot \frac{D_m^5}{D_p^5} = \left(\frac{1000}{500}\right)^3 \cdot \frac{D_m^5}{D_p^5} = 8 \cdot \frac{D_m^5}{D_p^5} \quad (3)$$

We can find  $P_p$  from 
$$P_p = \rho \cdot Q \cdot h = 1000 \frac{\text{kg}}{\text{m}^3} \times 0.75 \frac{\text{m}^3}{\text{s}} \times 15 \frac{\text{J}}{\text{kg}} = 11.25 \text{ kW}$$

From Eq 3 
$$\frac{P_m}{P_p} = 8 \cdot \frac{D_m^5}{D_p^5} \quad \text{so} \quad D_m = D_p \cdot \left(\frac{1}{8} \cdot \frac{P_m}{P_p}\right)^{\frac{1}{5}} \quad D_m = 0.25 \text{ m} \times \left(\frac{1}{8} \times \frac{2.25}{11.25}\right)^{\frac{1}{5}} \quad D_m = 0.120 \text{ m}$$

From Eq 1 
$$\frac{Q_m}{Q_p} = 2 \cdot \left(\frac{D_m}{D_p}\right)^3 \quad \text{so} \quad Q_m = Q_p \cdot 2 \cdot \left(\frac{D_m}{D_p}\right)^3 \quad Q_m = 0.75 \frac{\text{m}^3}{\text{s}} \times 2 \times \left(\frac{0.12}{0.25}\right)^3 \quad Q_m = 0.166 \frac{\text{m}^3}{\text{s}}$$

From Eq 2 
$$\frac{h_m}{h_p} = 4 \cdot \left(\frac{D_m}{D_p}\right)^2 \quad \text{so} \quad h_m = h_p \cdot 4 \cdot \left(\frac{D_m}{D_p}\right)^2 \quad h_m = 15 \frac{\text{J}}{\text{kg}} \times 4 \times \left(\frac{0.12}{0.25}\right)^2 \quad h_m = 13.8 \frac{\text{J}}{\text{kg}}$$

## Problem 7.90

[Difficulty: 3]

**7.90** A model propeller 1 m in diameter is tested in a wind tunnel. Air approaches the propeller at 50 m/s when it rotates at 1800 rpm. The thrust and torque measured under these conditions are 100 N and 10 N·m, respectively. A prototype 8 times as large as the model is to be built. At a dynamically similar operating point, the approach air speed is to be 130 m/s. Calculate the speed, thrust, and torque of the prototype propeller under these conditions, neglecting the effect of viscosity but including density.

**Given:** Data on model propeller

**Find:** Speed, thrust and torque on prototype

**Solution:** We will use the Buckingham Pi-theorem to find the functional relationships between these variables. Neglecting the effects of viscosity:

1     $F$      $T$      $\rho$      $V$      $D$      $\omega$     n = 6 parameters

2    Select primary dimensions M, L, t:

3     $F$      $T$      $\rho$      $V$      $D$      $\omega$     r = 3 dimensions

$$\frac{M \cdot L}{t^2} \quad \frac{M \cdot L^2}{t^2} \quad \frac{M}{L^3} \quad \frac{L}{t} \quad L \quad \frac{1}{t}$$

4     $\rho$      $D$      $\omega$     m = r = 3 repeating parameters

5    We have n - m = 3 dimensionless groups. Setting up dimensional equations:

$$\Pi_1 = F \cdot \rho^a \cdot D^b \cdot \omega^c \quad \text{Thus:} \quad \frac{M \cdot L}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{1}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: 1 - 3 \cdot a + b = 0$$

$$t: -2 - c = 0$$

The solution to this system is:

$$a = -1 \quad b = -4 \quad c = -2$$

$$\Pi_1 = \frac{F}{\rho \cdot D^4 \cdot \omega^2}$$

$$\Pi_2 = T \cdot \rho^a \cdot D^b \cdot \omega^c \quad \text{Thus:} \quad \frac{M \cdot L^2}{t^2} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{1}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 1 + a = 0$$

$$L: 2 - 3 \cdot a + b = 0$$

$$t: -2 - c = 0$$

The solution to this system is:

$$a = -1 \quad b = -5 \quad c = -2$$

$$\Pi_2 = \frac{T}{\rho \cdot D^5 \cdot \omega^2}$$

$$\Pi_3 = V \cdot \rho^a \cdot D^b \cdot \omega^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left(\frac{M}{L^3}\right)^a \cdot L^b \cdot \left(\frac{1}{t}\right)^c = M^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$M: 0 + a = 0$$

$$L: 1 - 3 \cdot a + b = 0$$

$$t: -1 - c = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = -1$$

$$\Pi_3 = \frac{V}{D \cdot \omega}$$

6 Check using F, L, t dimensions:  $F \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^4} \cdot t^2 = 1$     $F \cdot L \cdot \frac{L^4}{F \cdot t^2} \cdot \frac{1}{L^5} \cdot t^2 = 1$     $\frac{L}{t} \cdot \frac{1}{L} \cdot t = 1$

For dynamically similar conditions:

$$\frac{V_m}{D_m \cdot \omega_m} = \frac{V_p}{D_p \cdot \omega_p} \quad \text{Thus:} \quad \omega_p = \omega_m \cdot \frac{V_p}{V_m} \cdot \frac{D_m}{D_p} \quad \omega_p = 1800 \cdot \text{rpm} \times \frac{130}{50} \times \frac{1}{8} \quad \omega_p = 585 \cdot \text{rpm}$$

$$\frac{F_m}{\rho_m \cdot D_m^4 \cdot \omega_m^2} = \frac{F_p}{\rho_p \cdot D_p^4 \cdot \omega_p^2} \quad \text{Thus:} \quad F_p = F_m \cdot \frac{\rho_p}{\rho_m} \cdot \left(\frac{D_p}{D_m}\right)^4 \cdot \left(\frac{\omega_p}{\omega_m}\right)^2 \quad F_p = 100 \cdot \text{N} \times \frac{1}{1} \times \left(\frac{8}{1}\right)^4 \times \left(\frac{585}{1800}\right)^2$$

$$F_p = 43.3 \cdot \text{kN}$$

$$\frac{T_m}{\rho_m \cdot D_m^5 \cdot \omega_m^2} = \frac{T_p}{\rho_p \cdot D_p^5 \cdot \omega_p^2} \quad \text{Thus:} \quad T_p = T_m \cdot \frac{\rho_p}{\rho_m} \cdot \left(\frac{D_p}{D_m}\right)^5 \cdot \left(\frac{\omega_p}{\omega_m}\right)^2 \quad T_p = 10 \cdot \text{N} \cdot \text{m} \times \frac{1}{1} \times \left(\frac{8}{1}\right)^5 \times \left(\frac{585}{1800}\right)^2$$

$$T_p = 34.6 \cdot \text{kN} \cdot \text{m}$$

## Problem 7.91

[Difficulty: 3]

**7.91** Consider again Problem 7.51. Experience shows that for ship-size propellers, viscous effects on scaling are small. Also, when cavitation is not present, the nondimensional parameter containing pressure can be ignored. Assume that torque,  $T$ , and power,  $\mathcal{P}$ , depend on the same parameters as thrust. For conditions under which effects of  $\mu$  and  $p$  can be neglected, derive scaling “laws” for propellers, similar to the pump “laws” of Section 7.6, that relate thrust, torque, and power to the angular speed and diameter of the propeller.

**Given:** For a marine propeller (Problem 7.40) the thrust force is:  $F_T = F_T(\rho, D, V, g, \omega, \rho, \mu)$   
 For ship size propellers viscous and pressure effects can be neglected. Assume that power and torque depend on the same parameters as thrust.

**Find:** Scaling laws for propellers that relate thrust, power and torque to other variables

**Solution:** We will use the Buckingham pi-theorem. Based on the simplifications given above:

1  $F_T \quad P \quad T \quad \rho \quad D \quad V \quad g \quad \omega$  n = 8 parameters

2 Select primary dimensions F, L, t:

3  $F_T \quad P \quad T \quad \rho \quad D \quad V \quad g \quad \omega$   
 $F \quad \frac{F \cdot L}{t} \quad F \cdot L \quad \frac{F \cdot t^2}{L^4} \quad L \quad \frac{L}{t} \quad \frac{L}{t^2} \quad \frac{1}{t}$  r = 3 dimensions

4  $\rho \quad \omega \quad D$  m = r = 3 repeating parameters

5 We have n - m = 5 dimensionless groups (3 dependent, 2 independent). Setting up dimensional equations:

$$\Pi_1 = F_T \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad F \cdot \left(\frac{F \cdot t^2}{L^4}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

F:  $1 + a = 0$

L:  $-4 \cdot a + c = 0$

t:  $2 \cdot a - b = 0$

The solution to this system is:

$a = -1 \quad b = -2 \quad c = -2$

$$\Pi_1 = \frac{F_T}{\rho \cdot \omega^2 \cdot D^4}$$

$$\Pi_2 = P \cdot \rho^a \cdot \omega^b \cdot D^c$$

$$\text{Thus:} \quad \frac{F \cdot L}{t} \cdot \left(\frac{F \cdot t^2}{L^4}\right)^a \cdot \left(\frac{1}{t}\right)^b \cdot L^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

F:  $1 + a = 0$

L:  $1 - 4 \cdot a + c = 0$

t:  $-1 + 2 \cdot a - b = 0$

The solution to this system is:

$a = -1 \quad b = -3 \quad c = -5$

$$\Pi_2 = \frac{P}{\rho \cdot \omega^3 \cdot D^5}$$

$$\Pi_3 = T \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad F \cdot L \cdot \left( \frac{F \cdot t^2}{L^4} \right)^a \cdot \left( \frac{1}{t} \right)^b \cdot L^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$F: \quad 1 + a = 0$$

$$L: \quad 1 - 4 \cdot a + c = 0$$

$$t: \quad 2 \cdot a - b = 0$$

The solution to this system is:

$$a = -1 \quad b = -2 \quad c = -5$$

$$\Pi_3 = \frac{T}{\rho \cdot \omega^2 \cdot D^5}$$

$$\Pi_4 = V \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left( \frac{F \cdot t^2}{L^4} \right)^a \cdot \left( \frac{1}{t} \right)^b \cdot L^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$F: \quad a = 0$$

$$L: \quad 1 - 4 \cdot a + c = 0$$

$$t: \quad -1 + 2 \cdot a - b = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = -1$$

$$\Pi_4 = \frac{V}{\omega \cdot D}$$

$$\Pi_5 = g \cdot \rho^a \cdot \omega^b \cdot D^c \quad \text{Thus:} \quad \frac{L}{t} \cdot \left( \frac{F \cdot t^2}{L^4} \right)^a \cdot \left( \frac{1}{t} \right)^b \cdot L^c = F^0 \cdot L^0 \cdot t^0$$

Summing exponents:

$$F: \quad a = 0$$

$$L: \quad 1 - 4 \cdot a + c = 0$$

$$t: \quad -1 + 2 \cdot a - b = 0$$

The solution to this system is:

$$a = 0 \quad b = -1 \quad c = -1$$

$$\Pi_5 = \frac{g}{\omega^2 \cdot D}$$

6 Check using M, L, t dimensions:  $\frac{M \cdot L}{t^2} \cdot \frac{L^3}{M} \cdot t^2 \cdot \frac{1}{L^4} = 1 \quad \frac{M \cdot L^2}{t^3} \cdot \frac{L^3}{M} \cdot t^3 \cdot \frac{1}{L^5} = 1 \quad \frac{M \cdot L^2}{t^2} \cdot \frac{L^3}{M} \cdot t^2 \cdot \frac{1}{L^5} = 1$

$$\frac{L}{t} \cdot t \cdot \frac{1}{L} = 1 \quad \frac{L}{t^2} \cdot t^2 \cdot \frac{1}{L^2} = 1$$

Based on the dependent and independent variables, the "scaling laws" are:

$$\frac{F_T}{\rho \cdot \omega^2 \cdot D^4} = f_1 \left( \frac{V}{\omega \cdot D}, \frac{g}{\omega^2 \cdot D} \right)$$

$$\frac{P}{\rho \cdot \omega^3 \cdot D^5} = f_2 \left( \frac{V}{\omega \cdot D}, \frac{g}{\omega^2 \cdot D} \right)$$

$$\frac{T}{\rho \cdot \omega^2 \cdot D^5} = f_3 \left( \frac{V}{\omega \cdot D}, \frac{g}{\omega^2 \cdot D} \right)$$

## Problem 7.92

[Difficulty: 2]

**7.92** Water drops are produced by a mechanism that it is believed follows the pattern  $d_p = D(\text{We})^{-3/5}$ . In this formula,  $d_p$  is the drop size,  $D$  is proportional to a length scale, and  $\text{We}$  is the Weber number. In scaling up, if the large-scale characteristic length scale was increased by a factor of 20 and the large-scale velocity decreased by a factor of 5, how would the small- and large-scale drops differ from each other for the same material, for example, water?

**Given:** Water drop mechanism

**Find:** Difference between small and large scale drops

**Solution:**

Given relation 
$$d = D \cdot (\text{We})^{-\frac{3}{5}} = D \cdot \left( \frac{\rho \cdot V^2 \cdot D}{\sigma} \right)^{-\frac{3}{5}}$$

For dynamic similarity 
$$\frac{d_m}{d_p} = \frac{D_m \cdot \left( \frac{\rho \cdot V_m^2 \cdot D_m}{\sigma} \right)^{-\frac{3}{5}}}{D_p \cdot \left( \frac{\rho \cdot V_p^2 \cdot D_p}{\sigma} \right)^{-\frac{3}{5}}} = \left( \frac{D_m}{D_p} \right)^{\frac{2}{5}} \cdot \left( \frac{V_m}{V_p} \right)^{-\frac{6}{5}}$$
 where  $d_p$  stands for  $d_{\text{prototype}}$  not the original  $d_p$ !

Hence 
$$\frac{d_m}{d_p} = \left( \frac{1}{20} \right)^{\frac{2}{5}} \times \left( \frac{5}{1} \right)^{-\frac{6}{5}} \qquad \frac{d_m}{d_p} = 0.044$$

The small scale droplets are 4.4% of the size of the large scale

## Problem 7.93

[Difficulty: 2]

**7.93** Closed-circuit wind tunnels can produce higher speeds than open-circuit tunnels with the same power input because energy is recovered in the diffuser downstream from the test section. The *kinetic energy ratio* is a figure of merit defined as the ratio of the kinetic energy flux in the test section to the drive power. Estimate the kinetic energy ratio for the 40 ft × 80 ft wind tunnel at NASA-Ames described on page 318.

**Given:** Kinetic energy ratio for a wind tunnel is the ratio of the kinetic energy flux in the test section to the drive power

**Find:** Kinetic energy ratio for the 40 ft x 80 ft tunnel at NASA-Ames

**Solution:** From the text:  $P = 125000 \cdot \text{hp}$   $V_{\max} = 300 \cdot \frac{\text{nmi}}{\text{hr}} \times \frac{6080 \cdot \text{ft}}{\text{nmi}} \times \frac{\text{hr}}{3600 \cdot \text{s}}$   $V_{\max} = 507 \cdot \frac{\text{ft}}{\text{s}}$

Therefore, the kinetic energy ratio is: 
$$\text{KE}_{\text{ratio}} = \frac{\frac{\rho \cdot V \cdot A \cdot V^2}{2}}{P} = \frac{(\rho \cdot V \cdot A) \cdot V^2}{2 \cdot P} = \frac{\rho \cdot A \cdot V^3}{2 \cdot P}$$
 Assuming standard conditions and substituting values:

$$\text{KE}_{\text{ratio}} = \frac{1}{2} \times 0.00238 \cdot \frac{\text{slug}}{\text{ft}^3} \times (40 \cdot \text{ft} \times 80 \cdot \text{ft}) \times \left(507 \cdot \frac{\text{ft}}{\text{s}}\right)^3 \times \frac{1}{125000 \cdot \text{hp}} \times \frac{\text{hp} \cdot \text{s}}{550 \cdot \text{ft} \cdot \text{lbf}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$\text{KE}_{\text{ratio}} = 7.22$$

## Problem 7.94

[Difficulty: 3]

**7.94** A 1:16 model of a 60-ft-long truck is tested in a wind tunnel at a speed of 250 ft/s, where the axial static pressure gradient is  $-0.07 \text{ lbf/ft}^2$  per foot. The frontal area of the prototype is  $110 \text{ ft}^2$ . Estimate the horizontal buoyancy correction for this situation. Express the correction as a fraction of the measured  $C_D$ , of  $C_D = 0.85$ .

**Given:** A scale model of a truck is tested in a wind tunnel. The axial pressure gradient and frontal area of the prototype are known. Drag coefficient is 0.85.

**Find:** (a) Horizontal buoyancy correction  
(b) Express this correction as a fraction of the measured drag force.

**Solution:** The horizontal buoyancy force is the difference in the pressure force between the front and back of the model due to the pressure gradient in the tunnel:

$$F_B = (p_f - p_b) \cdot A = \frac{\Delta p}{\Delta L} \cdot L_m \cdot A_m \quad \text{where:} \quad L_m = \frac{L_p}{16} \quad A_m = \frac{A_p}{16^2}$$

$$\text{Thus: } F_B = -0.07 \cdot \frac{\text{lbf}}{\text{ft}^2 \cdot \text{ft}} \times \frac{60 \cdot \text{ft}}{16} \times \frac{110 \cdot \text{ft}^2}{16^2} \quad F_B = -0.113 \cdot \text{lbf}$$

The horizontal buoyancy correction should be added to the measured drag force on the model. The measured drag force on the model is given by:

$$F_{Dm} = \frac{1}{2} \cdot \rho \cdot V^2 \cdot A_m \cdot C_D = \frac{1}{2} \cdot \rho \cdot V^2 \cdot \frac{A_p}{16^2} \cdot C_D \quad \text{When we substitute in known values we get:}$$

$$F_{Dm} = \frac{1}{2} \times 0.00238 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left(250 \cdot \frac{\text{ft}}{\text{s}}\right)^2 \times \frac{110 \cdot \text{ft}^2}{16^2} \times 0.85 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad F_{Dm} = 27.16 \cdot \text{lbf}$$

$$\text{Therefore the ratio of the forces is: } \text{DragRatio} = \frac{-0.113}{27.16} \quad \text{DragRatio} = -0.42\%$$

## Problem 7.95

[Difficulty: 4]

---

**7.95** Frequently one observes a flag on a pole flapping in the wind. Explain why this occurs.

---

**Given:** Flapping flag on a flagpole

**Find:** Explanation of the flapping

**Solution:**

**Discussion:** The natural wind contains significant fluctuations in air speed and direction. These fluctuations tend to disturb the flag from an initially plane position.

When the flag is bent or curved from the plane position, the flow nearby must follow its contour. Flow over a convex surface tends to be faster, and have lower pressure, than flow over a concave curved surface. The resulting pressure forces tend to exaggerate the curvature of the flag. The result is a seemingly random "flapping" motion of the flag.

The rope or chain used to raise the flag may also flap in the wind. It is much more likely to exhibit a periodic motion than the flag itself. The rope is quite close to the flag pole, where it is influenced by any vortices shed from the pole. If the Reynolds number is such that periodic vortices are shed from the pole, they will tend to make the rope move with the same frequency. This accounts for the periodic thump of a rope or clank of a chain against the pole.

The vortex shedding phenomenon is characterized by the Strouhal number,  $St = fD/V_\infty$ , where  $f$  is the vortex shedding frequency,  $D$  is the pole diameter, and  $V_\infty$  is the wind speed. The Strouhal number is constant at approximately 0.2 over a broad range of Reynolds numbers.

## Problem 7.96

[Difficulty: 3]

**7.96** A 1:16 model of a bus is tested in a wind tunnel in standard air. The model is 152 mm wide, 200 mm high, and 762 mm long. The measured drag force at 26.5 m/s wind speed is 6.09 N. The longitudinal pressure gradient in the wind tunnel test section is  $-11.8 \text{ N/m}^2/\text{m}$ . Estimate the correction that should be made to the measured drag force to correct for horizontal buoyancy caused by the pressure gradient in the test section. Calculate the drag coefficient for the model. Evaluate the aerodynamic drag force on the prototype at 100 km/hr on a calm day.

**Given:** A 1:16 scale model of a bus (152 mm x 200 mm x 762 mm) is tested in a wind tunnel at 26.5 m/s. Drag force is 6.09 N. The axial pressure gradient is  $-11.8 \text{ N/m}^2/\text{m}$ .

**Find:** (a) Horizontal buoyancy correction  
(b) Drag coefficient for the model  
(c) Aerodynamic drag on the prototype at 100 kph on a calm day.

**Solution:** The horizontal buoyancy force is the difference in the pressure force between the front and back of the model due to the pressure gradient in the tunnel:

$$F_B = (p_f - p_b) \cdot A = \frac{dp}{dx} \cdot L_m \cdot A_m \quad \text{where: } A_m = 152 \cdot \text{mm} \times 200 \cdot \text{mm} \quad A_m = 30400 \cdot \text{mm}^2$$

$$\text{Thus: } F_B = -11.8 \cdot \frac{\text{N}}{\text{m}^2 \cdot \text{m}} \times 762 \cdot \text{mm} \times 30400 \cdot \text{mm}^2 \times \left( \frac{\text{m}}{1000 \cdot \text{mm}} \right)^3 \quad F_B = -0.273 \text{ N}$$

$$\text{So the corrected drag force is: } F_{Dc} = 6.09 \cdot \text{N} - 0.273 \cdot \text{N} \quad F_{Dc} = 5.817 \text{ N}$$

$$\text{The corrected model drag coefficient would then be: } C_{Dm} = \frac{F_{Dc}}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A_m} \quad \text{Substituting in values:}$$

$$C_{Dm} = 2 \times 5.82 \cdot \text{N} \times \frac{\text{m}^3}{1.23 \cdot \text{kg}} \times \left( \frac{\text{s}}{26.5 \cdot \text{m}} \right)^2 \times \frac{1}{30400 \cdot \text{mm}^2} \times \left( \frac{1000 \cdot \text{mm}}{\text{m}} \right)^2 \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \quad C_{Dm} = 0.443$$

If we assume that the test was conducted at high enough Reynolds number, then the drag coefficient should be the same at both scales, i.e.:  $C_{Dp} = C_{Dm}$

$$F_{Dp} = \frac{1}{2} \cdot \rho \cdot V^2 \cdot A_p \cdot C_{Dp} \quad \text{where } A_p = 30400 \cdot \text{mm}^2 \cdot 16^2 \cdot \left( \frac{\text{m}}{1000 \cdot \text{mm}} \right)^2 \quad A_p = 7.782 \cdot \text{m}^2$$

$$F_{Dp} = \frac{1}{2} \times 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 100 \cdot \frac{\text{km}}{\text{hr}} \times \frac{1000 \cdot \text{m}}{\text{km}} \cdot \frac{\text{hr}}{3600 \times \text{s}} \right)^2 \times 7.782 \cdot \text{m}^2 \times 0.443 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad F_{Dp} = 1.636 \cdot \text{kN}$$

(The rolling resistance must also be included to obtain the total tractive effort needed to propel the vehicle.)

## Problem 7.97

[Difficulty: 5]

**7.97** Explore the variation in wave propagation speed given by the equation of Problem 7.1 for a free-surface flow of water. Find the operating depth to minimize the speed of capillary waves (waves with small wavelength, also called ripples). First assume wavelength is much smaller than water depth. Then explore the effect of depth. What depth do you recommend for a water table used to visualize compressible-flow wave phenomena? What is the effect of reducing surface tension by adding a surfactant?

**Discussion:** The equation given in Problem 7.2 contains three terms. The first term contains surface tension and gives a speed inversely proportional to wavelength. These terms will be important when small wavelengths are considered.


The second term contains gravity and gives a speed proportional to wavelength. This term will be important when long wavelengths are considered.

The argument of the hyperbolic tangent is proportional to water depth and inversely proportional to wavelength. For small wavelengths this term should approach unity since the hyperbolic tangent of a large number approaches one.

The governing equation is: 
$$c^2 = \left( \frac{\sigma}{\rho} \cdot \frac{2 \cdot \pi}{\lambda} + \frac{g \cdot \lambda}{2 \cdot \pi} \right) \cdot \tanh\left( \frac{2 \cdot \pi \cdot h}{\lambda} \right)$$

The relevant physical parameters are:  $g = 9.81 \cdot \frac{\text{m}}{\text{s}^2}$   $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$   $\sigma = 0.0728 \cdot \frac{\text{N}}{\text{m}}$

A plot of the wave speed versus wavelength at different depths is shown here:



## Problem 8.1

[Difficulty: 1]

**8.1** Air at 100°C enters a 125-mm-diameter duct. Find the volume flow rate at which the flow becomes turbulent. At this flow rate, estimate the entrance length required to establish fully developed flow.

**Given:** Air entering duct

**Find:** Flow rate for turbulence; Entrance length

**Solution:**

The basic equations are  $Re = \frac{V \cdot D}{\nu}$   $Re_{crit} = 2300$   $Q = \frac{\pi}{4} \cdot D^2 \cdot V$

The given data is  $D = 125\text{-mm}$  From Table A.10  $\nu = 2.29 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$

$L_{laminar} = 0.06 Re_{crit} \cdot D$  or, for turbulent,  $L_{turb} = 25D$  to  $40D$

Hence  $Re_{crit} = \frac{\frac{Q}{\frac{\pi}{4} \cdot D^2} \cdot D}{\nu}$  or  $Q = \frac{Re_{crit} \cdot \pi \cdot \nu \cdot D}{4}$   $Q = 5.171 \times 10^{-3} \frac{\text{m}^3}{\text{s}}$

For laminar flow  $L_{laminar} = 0.06 \cdot Re_{crit} \cdot D$   $L_{laminar} = 17.3\text{ m}$

For turbulent flow  $L_{min} = 25 \cdot D$   $L_{min} = 3.13\text{ m}$   $L_{max} = 40 \cdot D$   $L_{max} = 5.00\text{ m}$

## Problem 8.2

[Difficulty: 2]

**8.2** Consider incompressible flow in a circular channel. Derive general expressions for Reynolds number in terms of (a) volume flow rate and tube diameter and (b) mass flow rate and tube diameter. The Reynolds number is 1800 in a section where the tube diameter is 10 mm. Find the Reynolds number for the same flow rate in a section where the tube diameter is 6 mm.

Solution:

Assume steady, incompressible flow

Definitions:  $Re = \frac{\rho \bar{v} D}{\mu}$ ,  $Q = A \bar{v}$ ,  $\dot{m} = \rho A \bar{v}$  and  $A = \frac{\pi D^2}{4}$

Then,

$$Re = \frac{\rho \bar{v} D}{\mu} = \frac{\rho \bar{v}}{\mu} \frac{Q}{A} = \frac{\rho \bar{v}}{\mu} \frac{Q}{\frac{\pi D^2}{4}} = \frac{4 \rho \bar{v} Q}{\pi \mu D} = \frac{4 Q}{\pi D} \left[ \frac{\rho}{\mu} \right] \quad Re$$

Also

$$Re = \frac{\rho \bar{v} D}{\mu} = \frac{\dot{m}}{\mu} \frac{\rho \bar{v} D}{\rho A} = \frac{\dot{m}}{\mu} \frac{D}{\frac{\pi D^2}{4}} = \frac{4 \dot{m}}{\pi \mu D} \left[ \frac{\rho}{\rho} \right] \quad Re$$

From Eq (i) a

$$Q = \frac{\pi D Re}{4} \left[ \frac{\mu}{\rho} \right]$$

Then for same flow rate in sections with different channel diameter,


$$D_1 Re_1 = D_2 Re_2$$

$$Re_2 = \frac{D_1}{D_2} Re_1 = \frac{10 \text{ mm}}{6 \text{ mm}} \times 1800 = 3000 \quad Re_2$$

### Problem 8.3

[Difficulty: 3]

**8.3** Air at 40°C flows in a pipe system in which diameter is decreased in two stages from 25 mm to 15 mm to 10 mm. Each section is 2 m long. As the flow rate is increased, which section will become turbulent first? Determine the flow rates at which one, two, and then all three sections first become turbulent. At each of these flow rates, determine which sections, if any, attain fully developed flow.



**Given:** Air entering pipe system

**Find:** Flow rate for turbulence in each section; Which become fully developed

**Solution:**

From Table A.10  $\nu = 1.69 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$

The given data is  $L = 2 \cdot \text{m}$      $D_1 = 25 \cdot \text{mm}$      $D_2 = 15 \cdot \text{mm}$      $D_3 = 10 \cdot \text{mm}$

The critical Reynolds number is  $Re_{\text{crit}} = 2300$

Writing the Reynolds number as a function of flow rate

$$Re = \frac{V \cdot D}{\nu} = \frac{Q}{\frac{\pi}{4} \cdot D^2} \cdot \frac{D}{\nu} \quad \text{or} \quad Q = \frac{Re \cdot \pi \cdot \nu \cdot D}{4}$$

Then the flow rates for turbulence to begin in each section of pipe are

$$Q_1 = \frac{Re_{\text{crit}} \cdot \pi \cdot \nu \cdot D_1}{4} \quad Q_1 = 7.63 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$$

$$Q_2 = \frac{Re_{\text{crit}} \cdot \pi \cdot \nu \cdot D_2}{4} \quad Q_2 = 4.58 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$$

$$Q_3 = \frac{Re_{\text{crit}} \cdot \pi \cdot \nu \cdot D_3}{4} \quad Q_3 = 3.05 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$$

Hence, **smallest** pipe becomes turbulent first, then second, then the largest.

**For the smallest pipe transitioning to turbulence ( $Q_3$ )**

For pipe 3     $Re_3 = 2300$      $L_{\text{laminar}} = 0.06 \cdot Re_3 \cdot D_3$      $L_{\text{laminar}} = 1.38 \text{ m}$      $L_{\text{laminar}} < L$ : Fully developed

or, for turbulent,     $L_{\text{min}} = 25 \cdot D_3$      $L_{\text{min}} = 0.25 \text{ m}$      $L_{\text{max}} = 40 \cdot D_3$      $L_{\text{max}} = 0.4 \text{ m}$      $L_{\text{max/min}} < L$ : Fully developed

For pipes 1 and 2     $L_{\text{laminar}} = 0.06 \cdot \left( \frac{4 \cdot Q_3}{\pi \cdot \nu \cdot D_1} \right) \cdot D_1$      $L_{\text{laminar}} = 1.38 \text{ m}$      $L_{\text{laminar}} < L$ : Fully developed

$$L_{\text{laminar}} = 0.06 \cdot \left( \frac{4 \cdot Q_3}{\pi \cdot \nu \cdot D_2} \right) \cdot D_2$$

$$L_{\text{laminar}} = 1.38 \text{ m}$$

$L_{\text{laminar}} < L$ : Fully developed

### For the middle pipe transitioning to turbulence ( $Q_2$ )

For pipe 2  $Re_2 = 2300$   $L_{\text{laminar}} = 0.06 \cdot Re_2 \cdot D_2$   $L_{\text{laminar}} = 2.07 \text{ m}$   $L_{\text{laminar}} > L$ : Not fully developed

or, for turbulent,  $L_{\text{min}} = 25 \cdot D_2$   $L_{\text{min}} = 1.23 \cdot \text{ft}$   $L_{\text{max}} = 40 \cdot D_2$   $L_{\text{max}} = 0.6 \text{ m}$

$L_{\text{max/min}} < L$ : Fully developed

For pipes 1 and 3  $L_1 = 0.06 \cdot \left( \frac{4 \cdot Q_2}{\pi \cdot \nu \cdot D_1} \right) \cdot D_1$

$$L_1 = 2.07 \cdot \text{m}$$

$L_{\text{laminar}} > L$ : Not fully developed

$$L_{3\text{min}} = 25 \cdot D_3 \quad L_{3\text{min}} = 0.25 \cdot \text{m}$$

$$L_{3\text{max}} = 40 \cdot D_3$$

$$L_{3\text{max}} = 0.4 \text{ m}$$

$L_{\text{max/min}} < L$ : Fully developed

### For the large pipe transitioning to turbulence ( $Q_1$ )

For pipe 1  $Re_1 = 2300$   $L_{\text{laminar}} = 0.06 \cdot Re_1 \cdot D_1$   $L_{\text{laminar}} = 3.45 \text{ m}$   $L_{\text{laminar}} > L$ : Not fully developed

or, for turbulent,  $L_{\text{min}} = 25 \cdot D_1$   $L_{\text{min}} = 2.05 \cdot \text{ft}$   $L_{\text{max}} = 40 \cdot D_1$   $L_{\text{max}} = 1.00 \text{ m}$

$L_{\text{max/min}} < L$ : Fully developed

For pipes 2 and 3  $L_{2\text{min}} = 25 \cdot D_2$   $L_{2\text{min}} = 1.23 \cdot \text{ft}$   $L_{2\text{max}} = 40 \cdot D_2$   $L_{2\text{max}} = 0.6 \text{ m}$

$L_{\text{max/min}} < L$ : Fully developed

$$L_{3\text{min}} = 25 \cdot D_3 \quad L_{3\text{min}} = 0.82 \cdot \text{ft}$$

$$L_{3\text{max}} = 40 \cdot D_3$$

$$L_{3\text{max}} = 0.4 \text{ m}$$

$L_{\text{max/min}} < L$ : Fully developed

## Problem 8.4

[Difficulty: 2]

**8.4** For flow in circular tubes, transition to turbulence usually occurs around  $Re \approx 2300$ . Investigate the circumstances under which the flows of (a) standard air and (b) water at  $15^\circ\text{C}$  become turbulent. On log-log graphs, plot: the average velocity, the volume flow rate, and the mass flow rate, at which turbulence first occurs, as functions of tube diameter.

**Given:** That transition to turbulence occurs at about  $Re = 2300$

**Find:** Plots of average velocity and volume and mass flow rates for turbulence for air and water

**Solution:**

The basic equations are  $Re = \frac{V \cdot D}{\nu}$   $Re_{\text{crit}} = 2300$

From Tables A.8 and A.10  $\rho_{\text{air}} = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu_{\text{air}} = 1.45 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$   $\rho_{\text{w}} = 999 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu_{\text{w}} = 1.14 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$

For the average velocity  $V = \frac{Re_{\text{crit}} \cdot \nu}{D}$

Hence for air  $V_{\text{air}} = \frac{2300 \times 1.45 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}}{D}$   $V_{\text{air}} = \frac{0.0334 \cdot \frac{\text{m}^2}{\text{s}}}{D}$

For water  $V_{\text{w}} = \frac{2300 \times 1.14 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}}{D}$   $V_{\text{w}} = \frac{0.00262 \cdot \frac{\text{m}^2}{\text{s}}}{D}$

For the volume flow rates  $Q = A \cdot V = \frac{\pi}{4} \cdot D^2 \cdot V = \frac{\pi}{4} \cdot D^2 \cdot \frac{Re_{\text{crit}} \cdot \nu}{D} = \frac{\pi \cdot Re_{\text{crit}} \cdot \nu}{4} \cdot D$

Hence for air  $Q_{\text{air}} = \frac{\pi}{4} \times 2300 \times 1.45 \cdot 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \cdot D$   $Q_{\text{air}} = 0.0262 \cdot \frac{\text{m}^2}{\text{s}} \times D$

For water  $Q_{\text{w}} = \frac{\pi}{4} \times 2300 \times 1.14 \cdot 10^{-6} \cdot \frac{\text{m}^2}{\text{s}} \cdot D$   $Q_{\text{w}} = 0.00206 \cdot \frac{\text{m}^2}{\text{s}} \times D$

Finally, the mass flow rates are obtained from volume flow rates

$m_{\text{air}} = \rho_{\text{air}} \cdot Q_{\text{air}}$   $m_{\text{air}} = 0.0322 \cdot \frac{\text{kg}}{\text{m} \cdot \text{s}} \times D$


$m_{\text{w}} = \rho_{\text{w}} \cdot Q_{\text{w}}$   $m_{\text{w}} = 2.06 \cdot \frac{\text{kg}}{\text{m} \cdot \text{s}} \times D$

These results can be plotted in *Excel* as shown below in the next two pages


From Tables A.8 and A.10 the data required is

$$\begin{aligned} \rho_{\text{air}} &= 1.23 \text{ kg/m}^3 & \nu_{\text{air}} &= 1.45\text{E-}05 \text{ m}^2/\text{s} \\ \rho_{\text{w}} &= 999 \text{ kg/m}^3 & \nu_{\text{w}} &= 1.14\text{E-}06 \text{ m}^2/\text{s} \end{aligned}$$


$D$ (m)	0.0001	0.001	0.01	0.05	1.0	2.5	5.0	7.5	10.0
$V_{\text{air}}$ (m/s)	333.500	33.350	3.335	0.667	3.34E-02	1.33E-02	6.67E-03	4.45E-03	3.34E-03
$V_{\text{w}}$ (m/s)	26.2	2.62	0.262	5.24E-02	2.62E-03	1.05E-03	5.24E-04	3.50E-04	2.62E-04
$Q_{\text{air}}$ (m <sup>3</sup> /s)	2.62E-06	2.62E-05	2.62E-04	1.31E-03	2.62E-02	6.55E-02	1.31E-01	1.96E-01	2.62E-01
$Q_{\text{w}}$ (m <sup>3</sup> /s)	2.06E-07	2.06E-06	2.06E-05	1.03E-04	2.06E-03	5.15E-03	1.03E-02	1.54E-02	2.06E-02
$m_{\text{air}}$ (kg/s)	3.22E-06	3.22E-05	3.22E-04	1.61E-03	3.22E-02	8.05E-02	1.61E-01	2.42E-01	3.22E-01
$m_{\text{w}}$ (kg/s)	2.06E-04	2.06E-03	2.06E-02	1.03E-01	2.06E+00	5.14E+00	1.03E+01	1.54E+01	2.06E+01



### Flow Rate for Turbulence in a Pipe



### Mass Flow Rate for Turbulence in a Pipe





# Problem 8.5





Fig. 8.1 Flow in the entrance region of a pipe.




42-281 50 SHEETS BY-LASER (3.50) (A1)  
 42-282 100 SHEETS BY-LASER (3.50) (A1)  
 42-283 200 SHEETS BY-LASER (3.50) (A1)  
 42-284 400 SHEETS BY-LASER (3.50) (A1)  
 42-285 800 SHEETS BY-LASER (3.50) (A1)  
 42-286 1600 SHEETS BY-LASER (3.50) (A1)  
 42-287 3200 SHEETS BY-LASER (3.50) (A1)  
 42-288 6400 SHEETS BY-LASER (3.50) (A1)  
 42-289 12800 SHEETS BY-LASER (3.50) (A1)  
 42-290 25600 SHEETS BY-LASER (3.50) (A1)  
 42-291 51200 SHEETS BY-LASER (3.50) (A1)  
 42-292 102400 SHEETS BY-LASER (3.50) (A1)  
 42-293 204800 SHEETS BY-LASER (3.50) (A1)  
 42-294 409600 SHEETS BY-LASER (3.50) (A1)  
 42-295 819200 SHEETS BY-LASER (3.50) (A1)  
 42-296 1638400 SHEETS BY-LASER (3.50) (A1)  
 42-297 3276800 SHEETS BY-LASER (3.50) (A1)  
 42-298 6553600 SHEETS BY-LASER (3.50) (A1)  
 42-299 13107200 SHEETS BY-LASER (3.50) (A1)  
 42-300 26214400 SHEETS BY-LASER (3.50) (A1)  
 42-301 52428800 SHEETS BY-LASER (3.50) (A1)  
 42-302 104857600 SHEETS BY-LASER (3.50) (A1)  
 42-303 209715200 SHEETS BY-LASER (3.50) (A1)  
 42-304 419430400 SHEETS BY-LASER (3.50) (A1)  
 42-305 838860800 SHEETS BY-LASER (3.50) (A1)  
 42-306 1677721600 SHEETS BY-LASER (3.50) (A1)  
 42-307 3355443200 SHEETS BY-LASER (3.50) (A1)  
 42-308 6710886400 SHEETS BY-LASER (3.50) (A1)  
 42-309 13421772800 SHEETS BY-LASER (3.50) (A1)  
 42-310 26843545600 SHEETS BY-LASER (3.50) (A1)  
 42-311 53687091200 SHEETS BY-LASER (3.50) (A1)  
 42-312 107374182400 SHEETS BY-LASER (3.50) (A1)  
 42-313 214748364800 SHEETS BY-LASER (3.50) (A1)  
 42-314 429496729600 SHEETS BY-LASER (3.50) (A1)  
 42-315 858993459200 SHEETS BY-LASER (3.50) (A1)  
 42-316 1717986918400 SHEETS BY-LASER (3.50) (A1)  
 42-317 3435973836800 SHEETS BY-LASER (3.50) (A1)  
 42-318 6871947673600 SHEETS BY-LASER (3.50) (A1)  
 42-319 13743895347200 SHEETS BY-LASER (3.50) (A1)  
 42-320 27487790694400 SHEETS BY-LASER (3.50) (A1)  
 42-321 54975581388800 SHEETS BY-LASER (3.50) (A1)  
 42-322 109951162777600 SHEETS BY-LASER (3.50) (A1)  
 42-323 219902325555200 SHEETS BY-LASER (3.50) (A1)  
 42-324 439804651110400 SHEETS BY-LASER (3.50) (A1)  
 42-325 879609302220800 SHEETS BY-LASER (3.50) (A1)  
 42-326 1759218604441600 SHEETS BY-LASER (3.50) (A1)  
 42-327 3518437208883200 SHEETS BY-LASER (3.50) (A1)  
 42-328 7036874417766400 SHEETS BY-LASER (3.50) (A1)  
 42-329 14073748835532800 SHEETS BY-LASER (3.50) (A1)  
 42-330 28147497671065600 SHEETS BY-LASER (3.50) (A1)  
 42-331 56294995342131200 SHEETS BY-LASER (3.50) (A1)  
 42-332 112589990684262400 SHEETS BY-LASER (3.50) (A1)  
 42-333 225179981368524800 SHEETS BY-LASER (3.50) (A1)  
 42-334 450359962737049600 SHEETS BY-LASER (3.50) (A1)  
 42-335 900719925474099200 SHEETS BY-LASER (3.50) (A1)  
 42-336 1801439850948198400 SHEETS BY-LASER (3.50) (A1)  
 42-337 3602879701896396800 SHEETS BY-LASER (3.50) (A1)  
 42-338 7205759403792793600 SHEETS BY-LASER (3.50) (A1)  
 42-339 14411518807585587200 SHEETS BY-LASER (3.50) (A1)  
 42-340 28823037615171174400 SHEETS BY-LASER (3.50) (A1)  
 42-341 57646075230342348800 SHEETS BY-LASER (3.50) (A1)  
 42-342 115292150460684697600 SHEETS BY-LASER (3.50) (A1)  
 42-343 230584300921369395200 SHEETS BY-LASER (3.50) (A1)  
 42-344 461168601842738790400 SHEETS BY-LASER (3.50) (A1)  
 42-345 922337203685477580800 SHEETS BY-LASER (3.50) (A1)  
 42-346 1844674407370955161600 SHEETS BY-LASER (3.50) (A1)  
 42-347 3689348814741910323200 SHEETS BY-LASER (3.50) (A1)  
 42-348 7378697629483820646400 SHEETS BY-LASER (3.50) (A1)  
 42-349 14757395258967641292800 SHEETS BY-LASER (3.50) (A1)  
 42-350 29514790517935282585600 SHEETS BY-LASER (3.50) (A1)  
 42-351 59029581035870565171200 SHEETS BY-LASER (3.50) (A1)  
 42-352 118059162071741130342400 SHEETS BY-LASER (3.50) (A1)  
 42-353 236118324143482260684800 SHEETS BY-LASER (3.50) (A1)  
 42-354 472236648286964521369600 SHEETS BY-LASER (3.50) (A1)  
 42-355 944473296573929042739200 SHEETS BY-LASER (3.50) (A1)  
 42-356 1888946593147858085478400 SHEETS BY-LASER (3.50) (A1)  
 42-357 3777893186295716170956800 SHEETS BY-LASER (3.50) (A1)  
 42-358 7555786372591432341913600 SHEETS BY-LASER (3.50) (A1)  
 42-359 15111572745182864683827200 SHEETS BY-LASER (3.50) (A1)  
 42-360 30223145490365729367654400 SHEETS BY-LASER (3.50) (A1)  
 42-361 60446290980731458735308800 SHEETS BY-LASER (3.50) (A1)  
 42-362 120892581961462917470617600 SHEETS BY-LASER (3.50) (A1)  
 42-363 241785163922925834941235200 SHEETS BY-LASER (3.50) (A1)  
 42-364 483570327845851669882470400 SHEETS BY-LASER (3.50) (A1)  
 42-365 967140655691703339764940800 SHEETS BY-LASER (3.50) (A1)  
 42-366 1934281311383406679529881600 SHEETS BY-LASER (3.50) (A1)  
 42-367 3868562622766813359059763200 SHEETS BY-LASER (3.50) (A1)  
 42-368 7737125245533626718119526400 SHEETS BY-LASER (3.50) (A1)  
 42-369 15474250491067253436239052800 SHEETS BY-LASER (3.50) (A1)  
 42-370 30948500982134506872478105600 SHEETS BY-LASER (3.50) (A1)  
 42-371 61897001964269013744956211200 SHEETS BY-LASER (3.50) (A1)  
 42-372 123794003928538027489912422400 SHEETS BY-LASER (3.50) (A1)  
 42-373 247588007857076054979824844800 SHEETS BY-LASER (3.50) (A1)  
 42-374 495176015714152109959649689600 SHEETS BY-LASER (3.50) (A1)  
 42-375 990352031428304219919299379200 SHEETS BY-LASER (3.50) (A1)  
 42-376 1980704062856608439838598758400 SHEETS BY-LASER (3.50) (A1)  
 42-377 3961408125713216879677197516800 SHEETS BY-LASER (3.50) (A1)  
 42-378 7922816251426433759354395033600 SHEETS BY-LASER (3.50) (A1)  
 42-379 15845632502852867518708790067200 SHEETS BY-LASER (3.50) (A1)  
 42-380 31691265005705735037417580134400 SHEETS BY-LASER (3.50) (A1)  
 42-381 63382530011411470074835160268800 SHEETS BY-LASER (3.50) (A1)  
 42-382 126765060022822940149670320537600 SHEETS BY-LASER (3.50) (A1)  
 42-383 253530120045645880299340641075200 SHEETS BY-LASER (3.50) (A1)  
 42-384 507060240091291760598681282150400 SHEETS BY-LASER (3.50) (A1)  
 42-385 1014120480182583521197362564300800 SHEETS BY-LASER (3.50) (A1)  
 42-386 2028240960365167042394725128601600 SHEETS BY-LASER (3.50) (A1)  
 42-387 4056481920730334084789450257203200 SHEETS BY-LASER (3.50) (A1)  
 42-388 8112963841460668169578900514406400 SHEETS BY-LASER (3.50) (A1)  
 42-389 16225927682921336339157801028812800 SHEETS BY-LASER (3.50) (A1)  
 42-390 32451855365842672678315602057625600 SHEETS BY-LASER (3.50) (A1)  
 42-391 64903710731685345356631204115251200 SHEETS BY-LASER (3.50) (A1)  
 42-392 129807421463370700713262408230502400 SHEETS BY-LASER (3.50) (A1)  
 42-393 259614842926741401426524816461004800 SHEETS BY-LASER (3.50) (A1)  
 42-394 519229685853482802853049632922009600 SHEETS BY-LASER (3.50) (A1)  
 42-395 1038459371706965605706099265844019200 SHEETS BY-LASER (3.50) (A1)  
 42-396 2076918743413931211412198531688038400 SHEETS BY-LASER (3.50) (A1)  
 42-397 4153837486827862422824397063376076800 SHEETS BY-LASER (3.50) (A1)  
 42-398 8307674973655724845648794126752153600 SHEETS BY-LASER (3.50) (A1)  
 42-399 16615349947311449691297588253504307200 SHEETS BY-LASER (3.50) (A1)  
 42-400 33230699894622899382595175107008614400 SHEETS BY-LASER (3.50) (A1)  
 42-401 66461399789245798765190350214017228800 SHEETS BY-LASER (3.50) (A1)  
 42-402 132922799578491597530380700428034457600 SHEETS BY-LASER (3.50) (A1)  
 42-403 265845599156983195060761400856068915200 SHEETS BY-LASER (3.50) (A1)  
 42-404 53169119831396639012152280171213782400 SHEETS BY-LASER (3.50) (A1)  
 42-405 106338239662793278024304560342427564800 SHEETS BY-LASER (3.50) (A1)  
 42-406 212676479325586556048609120684855129600 SHEETS BY-LASER (3.50) (A1)  
 42-407 425352958651173112097218241369710259200 SHEETS BY-LASER (3.50) (A1)  
 42-408 850705917302346224194436482739420518400 SHEETS BY-LASER (3.50) (A1)  
 42-409 1701411834604692448388872965478841036800 SHEETS BY-LASER (3.50) (A1)  
 42-410 3402823669209384896777745930957682073600 SHEETS BY-LASER (3.50) (A1)  
 42-411 6805647338418769793555491861915364147200 SHEETS BY-LASER (3.50) (A1)  
 42-412 13611294676837539587110983723830728294400 SHEETS BY-LASER (3.50) (A1)  
 42-413 27222589353675079174221967447661456588800 SHEETS BY-LASER (3.50) (A1)  
 42-414 54445178707350158348443934895322913177600 SHEETS BY-LASER (3.50) (A1)  
 42-415 108890357414700316696887869790645826355200 SHEETS BY-LASER (3.50) (A1)  
 42-416 217780714829400633393775739581291652710400 SHEETS BY-LASER (3.50) (A1)  
 42-417 435561429658801266787551479162583305420800 SHEETS BY-LASER (3.50) (A1)  
 42-418 871122859317602533575102958325166610841600 SHEETS BY-LASER (3.50) (A1)  
 42-419 174224571863520506715020591665033322163200 SHEETS BY-LASER (3.50) (A1)  
 42-420 348449143727041013430041183330066644326400 SHEETS BY-LASER (3.50) (A1)  
 42-421 696898287454082026860082366660133288652800 SHEETS BY-LASER (3.50) (A1)  
 42-422 1393796574908164053720164733320266577305600 SHEETS BY-LASER (3.50) (A1)  
 42-423 2787593149816328107440329466640533154611200 SHEETS BY-LASER (3.50) (A1)  
 42-424 5575186299632656214880658933281066309222400 SHEETS BY-LASER (3.50) (A1)  
 42-425 11150372599265312429761317866562132618444800 SHEETS BY-LASER (3.50) (A1)  
 42-426 22300745198530624859522635733124265236889600 SHEETS BY-LASER (3.50) (A1)  
 42-427 4460149039706124971904527146624853073779200 SHEETS BY-LASER (3.50) (A1)  
 42-428 8920298079412249943809054293249706147558400 SHEETS BY-LASER (3.50) (A1)  
 42-429 17840596158824499887618108586499412315116800 SHEETS BY-LASER (3.50) (A1)  
 42-430 35681192317648999775236217172998824630233600 SHEETS BY-LASER (3.50) (A1)  
 42-431 71362384635297999550472434345997649260467200 SHEETS BY-LASER (3.50) (A1)  
 42-432 142724769270595999100944868691995298520934400 SHEETS BY-LASER (3.50) (A1)  
 42-433 285449538541191998201889737383990597041868800 SHEETS BY-LASER (3.50) (A1)  
 42-434 570899077082383996403779474767981194083737600 SHEETS BY-LASER (3.50) (A1)  
 42-435 1141798154164767992807558949535962388167475200 SHEETS BY-LASER (3.50) (A1)  
 42-436 228359630832953598561511789907192477633494400 SHEETS BY-LASER (3.50) (A1)  
 42-437 456719261665907197123023579814384955266988800 SHEETS BY-LASER (3.50) (A1)  
 42-438 913438523331814394246047159628769910533977600 SHEETS BY-LASER (3.50) (A1)  
 42-439 1826877046663628788492094319257539821067955200 SHEETS BY-LASER (3.50) (A1)  
 42-440 3653754093327257576984188638515079642135910400 SHEETS BY-LASER (3.50) (A1)  
 42-441 7307508186654515153968377277030159284271820800 SHEETS BY-LASER (3.50) (A1)  
 42-442 14615016373309030307936754554060318568543641600 SHEETS BY-LASER (3.50) (A1)  
 42-443 29230032746618060615873509108120637137087283200 SHEETS BY-LASER (3.50) (A1)  
 42-444 58460065493236121231747018216241274274174566400 SHEETS BY-LASER (3.50) (A1)  
 42-445 116920130986472242463494036432482548548349132800 SHEETS BY-LASER (3.50) (A1)  
 42-446 233840261972944484926988072864965097096698265600 SHEETS BY-LASER (3.50) (A1)  
 42-447 467680523945888969853976145729930194193396531200 SHEETS BY-LASER (3.50) (A1)  
 42-448 935361047891777939707952291459860388386793062400 SHEETS BY-LASER (3.50) (A1)  
 42-449 1870722095783555879415904582919720776773586124800 SHEETS BY-LASER (3.50) (A1)  
 42-450 3741444191567111758831809165839441553547172249600 SHEETS BY-LASER (3.50) (A1)  
 42-451 7482888383134223517663618331678883107094344499200 SHEETS BY-LASER (3.50) (A1)  
 42-452 14965776766268447035327236663357766214188689998400 SHEETS BY-LASER (3.50) (A1)  
 42-453 29931553532536894070654473326715532428377379996800 SHEETS BY-LASER (3.50) (A1)  
 42-454 59863107065073788141308946653431064856754759993600 SHEETS BY-LASER (3.50) (A1)  
 42-455 119726214130147576282617893306862137113509519987200 SHEETS BY-LASER (3.50) (A1)  
 42-456 239452428260295152565235786613724274227019039974400 SHEETS BY-LASER (3.50) (A1)  
 42-457 478904856520590305130471573227448548454038079948800 SHEETS BY-LASER (3.50) (A1)  
 42-458 957809713041180610260943146454897096908076159897600 SHEETS BY-LASER (3.50) (A1)  
 42-459 1915619426082361220521886292909794193816152319795200 SHEETS BY-LASER (3.50) (A1)  
 42-460 3831238852164722441043772585819588387632304639590400 SHEETS BY-LASER (3.50) (A1)  
 42-461 7662477704329444882087545171639176775264609279180800 SHEETS BY-LASER (3.50) (A1)  
 42-462 15324955408658889764175090343278353550529218558361600 SHEETS BY-LASER (3.50) (A1)  
 42-463 30649910817317779528350180686556707101058437116723200 SHEETS BY-LASER (3.50) (A1)  
 42-464 61299821634635559056700361373113414202116874233446400 SHEETS BY-LASER (3.50) (A1)  
 42-465 122599643269271118113400722746226828404233748466892800 SHEETS BY-LASER (3.50) (A1)  
 42-466 245199286538542236226801445492453656808467496933785600 SHEETS BY-LASER (3.50) (A1)  
 42-467 490398573077084472453602890984907313616934993867571200 SHEETS BY-LASER (3.50) (A1)  
 42-468 980797146154168944907205781969814627233869987735142400 SHEETS BY-LASER (3.50) (A1)  
 42-469 1961594292308337889814411633939629254467739975470284800 SHEETS BY-LASER (3.50) (A1)  
 42-470 3923188584616675779628823267879258508935479950940569600 SHEETS BY-LASER (3.50) (A1)  
 42-471 7846377169233351559257646535758517077870959901881139200 SHEETS BY-LASER (3.50) (A1)  
 42-472 15692754338466703118515293071517034155741919803762278400 SHEETS BY-LASER (3.50) (A1)  
 42-473 31385508676933406237030586143034068311483839607524556800 SHEETS BY-LASER (3.50) (A1)  
 42-474 62771017353866812474061172286068136222967679215049113600 SHEETS BY-LASER (3.50) (A1)  
 42-475 125542034707733624948122344572136272445935358430098227200 SHEETS BY-LASER (3.50) (A1)  
 42-476 251084069415467249896244689144272544891870716860196454400 SHEETS BY-LASER (3.50) (A1)  
 42-477 502168138830934499792489378288545089783741437320392908800 SHEETS BY-LASER (3.50) (A1)  
 42-478 100433627766186899958497875657709017956748287464078585600 SHEETS BY-LASER (3.50) (A1)  
 42-479 200867255532373799916995751315418035913496574928157171200 SHEETS BY-LASER (3.50) (A1)  
 42-480 401734511064747599833991502630836071826993149856314342400 SHEETS BY-LASER (3.50) (A1)  
 42-481 8034690221294951996679

### Problem 8.6

[Difficulty: 2]

8.6 An incompressible fluid flows between two infinite stationary parallel plates. The velocity profile is given by  $u = u_{\max} (Ay^2 + By + C)$ , where  $A$ ,  $B$ , and  $C$  are constants and  $y$  is measured upward from the lower plate. The total gap width is  $h$  units. Use appropriate boundary conditions to express the magnitude and units of the constants in terms of  $h$ . Develop an expression for volume flow rate per unit depth and evaluate the ratio  $\bar{V}/u_{\max}$ .



#### Solution:

- (a) Available boundary conditions :
- (1)  $y=0, u=0$
  - (2)  $y=h, u=0$
  - (3)  $y=h/2, u=u_{\max}$

From B.c (1)  $u(0) = 0 = u_{\max} C \quad \therefore C = 0$  C

From B.c (2)  $u(h) = 0 = u_{\max} (Ah^2 + Bh) \quad \dots (i)$

From B.c (3)  $u(h/2) = u_{\max} = u_{\max} (A \frac{h^2}{4} + B \frac{h}{2}) \quad \dots (ii)$

From Eq (i),  $B = -Ah$ . Substituting into Eq (ii) gives

$$u_{\max} = u_{\max} (A \frac{h^2}{4} - A \frac{h^2}{2}) \quad \therefore A = -\frac{4}{h^2} \quad \text{A}$$

$$\text{and } B = -Ah = \frac{4}{h} \quad \text{B}$$

Then

$$u = u_{\max} (Ay^2 + By + C) = u_{\max} \left( -\frac{4y^2}{h^2} + \frac{4y}{h} \right) = 4u_{\max} \left[ \frac{y}{h} - \frac{(y/h)^2}{h} \right]$$

(b)  $Q = \int_0^h u b dy = \int_0^h 4u_{\max} \left[ \frac{y}{h} - \frac{y^2}{h^2} \right] b dy = 4u_{\max} b \left[ \frac{y^2}{2h} - \frac{y^3}{3h^2} \right]_0^h$

$$Q = 4b u_{\max} \left[ \frac{h}{2} - \frac{h}{3} \right] = \frac{2}{3} u_{\max} b h$$

$$Q/b = \frac{2}{3} u_{\max} h \quad \text{Q/b}$$

(c) Since  $Q = \bar{V} A = \bar{V} b h$

$$\bar{V} = \bar{V} h = \frac{2}{3} u_{\max} h$$

and

$$\frac{\bar{V}}{u_{\max}} = \frac{2}{3}$$

$$\frac{\bar{V}}{u_{\max}}$$




### Problem 8.8

[Difficulty: 3]

**8.8** A fluid flows steadily between two parallel plates. The flow is fully developed and laminar. The distance between the plates is  $h$ .

(a) Derive an equation for the shear stress as a function of  $y$ . Sketch this function.

(b) For  $\mu = 2.4 \times 10^{-5} \text{ lbf} \cdot \text{s}/\text{ft}^2$ ,  $\partial p/\partial x = -4.0 \text{ lbf}/\text{ft}^2/\text{ft}$ , and  $h = 0.05 \text{ in.}$ , calculate the maximum shear stress, in  $\text{lbf}/\text{ft}^2$ .



Solution: From Eq. 8.7, with  $a = h$ ,  $u = -\frac{h^2}{8\mu} \frac{\partial p}{\partial x} \left[ 1 - \left( \frac{2y}{h} \right)^2 \right]$ .

By symmetry, the origin for  $y$  must be located at the channel centerline. Apply Newton's law of viscosity.

$$\tau_{yx} = \mu \frac{du}{dy}$$

Assumption: Newtonian fluid

Then 
$$\tau_{yx} = \mu \frac{d}{dy} \left\{ -\frac{h^2}{8\mu} \frac{\partial p}{\partial x} \left[ 1 - \left( \frac{2y}{h} \right)^2 \right] \right\} = y \frac{\partial p}{\partial x}$$

For  $u > 0$ ,  $\partial p/\partial x < 0$ . Thus  $\tau_{yx} < 0$  for  $y > 0$  and  $\tau_{yx} > 0$  for  $y < 0$ .

On the upper plate (a minus  $y$  surface),  $\tau_{yx} < 0$ , so shear stress acts to the right.


On the lower plate (a plus  $y$  surface),  $\tau_{yx} > 0$ , so shear stress acts to the right.

The maximum stress occurs when  $y = \pm h/2$ . Thus

$$\tau_{\max} = \tau_{yx} \left( \frac{h}{2} \right) = \frac{h}{2} \frac{\partial p}{\partial x} = \frac{1}{2} \times 0.05 \text{ in.} \times \frac{\text{ft.}}{12 \text{ in.}} \times (-4.0 \frac{\text{lbf}}{\text{ft}^2}) = -0.00835 \frac{\text{lbf}}{\text{ft}^2}$$

or 
$$\tau_{\max} = \tau_{yx} \left( -\frac{h}{2} \right) = 0.00835 \frac{\text{lbf}}{\text{ft}^2}$$


Plot:



## Problem 8.9

[Difficulty: 3]

**8.9** Oil is confined in a 4-in.-diameter cylinder by a piston having a radial clearance of 0.001 in. and a length of 2 in. A steady force of 4500 lbf is applied to the piston. Assume the properties of SAE 30 oil at 120°F. Estimate the rate at which oil leaks past the piston.



**Given:** Piston cylinder assembly

**Find:** Rate of oil leak

**Solution:**

Basic equation  $\frac{Q}{l} = \frac{a^3 \cdot \Delta p}{12 \cdot \mu \cdot L}$        $Q = \frac{\pi \cdot D \cdot a^3 \cdot \Delta p}{12 \cdot \mu \cdot L}$       (from Eq. 8.6c; we assume laminar flow and verify this is correct after solving)

For the system  $\Delta p = p_1 - p_{atm} = \frac{F}{A} = \frac{4 \cdot F}{\pi \cdot D^2}$

$$\Delta p = \frac{4}{\pi} \times 4500 \cdot \text{lbf} \times \left( \frac{1}{4 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \qquad \Delta p = 358 \cdot \text{psi}$$

At 120°F (about 50°C), from Fig. A.2  $\mu = 0.06 \times 0.0209 \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$        $\mu = 1.25 \times 10^{-3} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$

$$Q = \frac{\pi}{12} \times 4 \cdot \text{in} \times \left( 0.001 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^3 \times 358 \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{144 \cdot \text{in}^2}{1 \cdot \text{ft}^2} \times \frac{\text{ft}^2}{1.25 \times 10^{-3} \text{ lbf} \cdot \text{s}} \times \frac{1}{2} \qquad Q = 1.25 \times 10^{-5} \cdot \frac{\text{ft}^3}{\text{s}} \qquad Q = 0.0216 \cdot \frac{\text{in}^3}{\text{s}}$$

Check Re:  $V = \frac{Q}{A} = \frac{Q}{a \cdot \pi \cdot D}$        $V = \frac{1}{\pi} \times 1.25 \times 10^{-5} \frac{\text{ft}^3}{\text{s}} \times \frac{1}{.001 \cdot \text{in}} \times \frac{1}{4 \cdot \text{in}} \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2$        $V = 0.143 \cdot \frac{\text{ft}}{\text{s}}$

$$Re = \frac{V \cdot a}{\nu} \qquad \nu = 6 \times 10^{-5} \times 10.8 \frac{\text{ft}^2}{\text{s}} \qquad \nu = 6.48 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \quad (\text{at } 120^\circ\text{F, from Fig. A.3})$$

$$Re = 0.143 \cdot \frac{\text{ft}}{\text{s}} \times 0.001 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \times \frac{\text{s}}{6.48 \times 10^{-4} \text{ ft}^2} \qquad Re = 0.0184 \qquad \text{so flow is very much laminar}$$

The speed of the piston is approximately


$$V_p = \frac{Q}{\left( \frac{\pi \cdot D^2}{4} \right)} \qquad V_p = \frac{4}{\pi} \times 1.25 \times 10^{-5} \frac{\text{ft}^3}{\text{s}} \times \left( \frac{1}{4 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \qquad V_p = 1.432 \times 10^{-4} \cdot \frac{\text{ft}}{\text{s}}$$

The piston motion is negligible so our assumption of flow between parallel plates is reasonable

### Problem 8.10

[Difficulty: 2]

**8.10** A viscous oil flows steadily between stationary parallel plates. The flow is laminar and fully developed. The total gap width between the plates is  $h = 5$  mm. The oil viscosity is  $0.5 \text{ N}\cdot\text{s}/\text{m}^2$  and the pressure gradient is  $-1000 \text{ N}/\text{m}^2/\text{m}$ . Find the magnitude and direction of the shear stress on the upper plate and the volume flow rate through the channel, per meter of width.



Solution: From Eq. 8.7 with  $a = h$ ,

$$u = -\frac{h^2}{8\mu} \frac{\partial p}{\partial x} \left[ 1 - \left( \frac{2y}{h} \right)^2 \right]$$

Then

$$\tau_{yx} = \mu \frac{du}{dy} = -\frac{h^2}{8} \frac{\partial p}{\partial x} \left( -\frac{4y}{h^2} \right) = y \frac{\partial p}{\partial x}$$

At upper surface,  $y = h/2$ , and

$$\tau_{yx} = \frac{0.005 \text{ m}}{2} \times \frac{-1000 \text{ N}}{\text{m}^3} = -2.5 \text{ N}/\text{m}^2$$

The upper plate is a negative  $y$  surface. Thus since  $\tau_{yx} < 0$ , stress acts to right, in  $+x$  direction.

The volume flow rate is

$$Q = \int_A u dA = \int_{-h/2}^{h/2} u b dy = 2 \int_0^{h/2} u b dy = 2 \left( \frac{h}{2} \right) b \int_0^1 u d\left( \frac{2y}{h} \right)$$

or

$$\frac{Q}{b} = h \int_0^1 u d\eta \quad \text{where } \eta = \frac{2y}{h} \text{ and } u = -\frac{h^2}{8\mu} \frac{\partial p}{\partial x} (1 - \eta^2)$$

$$\text{Thus } \frac{Q}{b} = h \int_0^1 -\frac{h^2}{8\mu} \frac{\partial p}{\partial x} (1 - \eta^2) d\eta = -\frac{h^3}{8\mu} \frac{\partial p}{\partial x} \left( \eta - \frac{1}{3}\eta^3 \right) \Big|_0^1 = -\frac{h^3}{12\mu} \frac{\partial p}{\partial x}$$

$$\frac{Q}{b} = -\frac{1}{12} \times (0.005)^3 \text{ m}^3 \times \frac{\text{m}^2}{0.5 \text{ N}\cdot\text{s}} \times \frac{-1000 \text{ N}}{\text{m}^3} = 20.8 \times 10^{-6} \text{ m}^2/\text{s}$$

Note  $u > 0$ , so flow is from left to right.


$\tau_{yx}$

$Q/b$

## Problem 8.11

[Difficulty: 2]

**8.11** Viscous oil flows steadily between parallel plates. The flow is fully developed and laminar. The pressure gradient is  $1.25 \text{ kPa/m}$  and the channel half-width is  $h = 1.5 \text{ mm}$ . Calculate the magnitude and direction of the wall shear stress at the upper plate surface. Find the volume flow rate through the channel ( $\mu = 0.50 \text{ N} \cdot \text{s/m}^2$ ).



**Given:** Laminar flow between flat plates

**Find:** Shear stress on upper plate; Volume flow rate per width

**Solution:**

Basic equation  $\tau_{yx} = \mu \cdot \frac{du}{dy}$   $u(y) = -\frac{h^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ 1 - \left( \frac{y}{h} \right)^2 \right]$  (from Eq. 8.7)

Then  $\tau_{yx} = \frac{-h^2}{2} \cdot \frac{dp}{dx} \cdot \left( -\frac{2 \cdot y}{h^2} \right) = -y \cdot \frac{dp}{dx}$

At the upper surface  $y = h$   $\tau_{yx} = -1.5 \text{ mm} \times \frac{1 \cdot \text{m}}{1000 \text{ mm}} \times 1.25 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2 \cdot \text{m}}$   $\tau_{yx} = -1.88 \text{ Pa}$

The volume flow rate is  $Q = \int u \, dA = \int_{-h}^h u \cdot b \, dy = -\frac{h^2 \cdot b}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \int_{-h}^h \left[ 1 - \left( \frac{y}{h} \right)^2 \right] dy$   $Q = -\frac{2 \cdot h^3 \cdot b}{3 \cdot \mu} \cdot \frac{dp}{dx}$

$\frac{Q}{b} = -\frac{2}{3} \times \left( 1.5 \text{ mm} \times \frac{1 \cdot \text{m}}{1000 \text{ mm}} \right)^3 \times 1.25 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2 \cdot \text{m}} \times \frac{\text{m}^2}{0.5 \cdot \text{N} \cdot \text{s}}$   $\frac{Q}{b} = -5.63 \times 10^{-6} \frac{\text{m}^2}{\text{s}}$

## Problem 8.12

[Difficulty: 3]

**8.12** A large mass is supported by a piston of diameter  $D = 4$  in. and length  $L = 4$  in. The piston sits in a cylinder closed at the bottom, and the gap  $a = 0.001$  in. between the cylinder wall and piston is filled with SAE 10 oil at  $68^\circ\text{F}$ . The piston slowly sinks due to the mass, and oil is forced out at a rate of 0.1 gpm. What is the mass (slugs)?

**Given:** Piston-cylinder assembly

**Find:** Mass supported by piston

**Solution:**

Basic equation  $\frac{Q}{l} = \frac{a^3 \cdot \Delta p}{12 \cdot \mu \cdot L}$  This is the equation for pressure-driven flow between parallel plates; for a small gap  $a$ , the flow between the piston and cylinder can be modeled this way, with  $l = \pi D$

Available data  $L = 4 \cdot \text{in}$   $D = 4 \cdot \text{in}$   $a = 0.001 \cdot \text{in}$   $Q = 0.1 \cdot \text{gpm}$   $68^\circ\text{F} = 20^\circ\text{C}$

From Fig. A.2, SAE10 oil at  $20^\circ\text{F}$  is  $\mu = 0.1 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$  or  $\mu = 2.089 \times 10^{-3} \cdot \frac{\text{lb}\cdot\text{s}}{\text{ft}^2}$

Hence, solving for  $\Delta p$   $\Delta p = \frac{12 \cdot \mu \cdot L \cdot Q}{\pi \cdot D \cdot a^3}$   $\Delta p = 2.133 \times 10^4 \cdot \text{psi}$

A force balance for the piston involves the net pressure force  $F = \Delta p \cdot A = \Delta p \cdot \frac{\pi}{4} \cdot D^2$  and the weight  $W = M \cdot g$

Hence  $M = \frac{\pi \cdot D^2}{4} \cdot \frac{\Delta p}{g}$   $M = 8331 \cdot \text{slug}$   $M = 2.68 \times 10^5 \cdot \text{lb}$

Note the following  $V_{\text{ave}} = \frac{Q}{a \cdot \pi \cdot D}$   $V_{\text{ave}} = 2.55 \cdot \frac{\text{ft}}{\text{s}}$   $\nu = 10^{-4} \cdot \frac{\text{m}^2}{\text{s}}$   $\nu = 1.076 \times 10^{-3} \cdot \frac{\text{ft}^2}{\text{s}}$

Hence an estimate of the Reynolds number in the gap is  $\text{Re} = \frac{a \cdot V_{\text{ave}}}{\nu}$   $\text{Re} = 0.198$

This is a highly viscous flow; it can be shown that the force on the piston due to this motion is much less than that due to  $\Delta p$ !

Note also that the piston speed is  $V_{\text{piston}} = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V_{\text{piston}} = 0.00255 \cdot \frac{\text{ft}}{\text{s}}$

$\frac{V_{\text{piston}}}{V_{\text{ave}}} = 0.1\%$  so the approximation of stationary walls is valid

### Problem 8.13

[Difficulty: 3]

**8.13** A high pressure in a system is created by a small piston-cylinder assembly. The piston diameter is 6 mm and it extends 50 mm into the cylinder. The radial clearance between the piston and cylinder is 0.002 mm. Neglect elastic deformations of the piston and cylinder caused by pressure. Assume the fluid properties are those of SAE 10W oil at 35°C. When the pressure in the cylinder is 600 MPa, estimate the leakage rate.

Solution:      Computing equation:  $\frac{Q}{l} = \frac{a^3 \Delta P}{12\mu l}$       (8.10c)

Assumptions: (1) Laminar flow  
(2) Fully developed flow ( $l \gg a$ )

For SAE 10W oil at 35°C,  $\mu = 3.8 \times 10^{-2} \text{ N}\cdot\text{s}/\text{m}^2$  (Fig. A.2)

For this configuration,  $l = \pi l$ , since  $a \ll l$ . Then

$$Q = \frac{a^3 \Delta P l}{12\mu l} = \frac{\pi a^3 \Delta P l}{12\mu l}$$

$$Q = \frac{\pi}{12} \times (2 \times 10^{-6} \text{ m})^3 \times 6 \times 10^8 \frac{\text{N}}{\text{m}^2} \times 0.006 \text{ m} \times 3.8 \times 10^{-2} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times \frac{1}{0.05 \text{ m}}$$

$$Q = 3.97 \times 10^{-9} \text{ m}^3/\text{s} = 3.97 \times 10^{-6} \text{ L/s} \quad Q$$

Check Re to assure laminar flow

$$\bar{V} = \frac{Q}{A} = \frac{Q}{\pi a^2} = \frac{1}{\pi} \times 3.97 \times 10^{-9} \frac{\text{m}^3}{\text{s}} \times \frac{1}{0.006 \text{ m}} \times \frac{1}{2 \times 10^{-6} \text{ m}} = 0.105 \text{ m/s}$$

$$SG = 0.88 \text{ (Table A.2)}; \rho = SG \rho_{H_2O}$$

$$Re = \frac{\rho \bar{V} a}{\mu} = \frac{SG \rho_{H_2O} \bar{V} a}{\mu}$$

$$= 0.88 \times 999 \frac{\text{kg}}{\text{m}^3} \times 0.105 \frac{\text{m}}{\text{s}} \times 2 \times 10^{-6} \text{ m} \times 3.8 \times 10^{-2} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$$

$$Re = 0.005 \ll 2300 \text{ so flow is definitely laminar!}$$

## Problem 8.14


[Difficulty: 3]

**8.14** A hydraulic jack supports a load of 9000 kg. The following data are given:

Diameter of piston	100 mm
Radial clearance between piston and cylinder	0.05 mm
Length of piston	120 mm

Estimate the rate of leakage of hydraulic fluid past the piston, assuming the fluid is SAE 30 oil at 30°C.

Solution:



Model the flow as steady, fully developed laminar flow between stationary parallel plates, i.e., neglect motion of the piston.

Then, the leakage flow rate can be evaluated from Eq. 8.6c (in the text)

$$\frac{Q}{l} = \frac{a^3 \Delta p}{12 \mu} \quad \text{where } l = \pi d$$

From Fig. A.2 at  $T = 30^\circ\text{C}$ ,  $\mu = 3.0 \times 10^{-4} \text{ N}\cdot\text{s}/\text{m}^2$

$$\Delta p = p_1 - p_{\text{atm}} \quad \text{and} \quad p_1 = \frac{W}{A} = \frac{mg}{A} = \frac{4mg}{\pi d^2}$$

$$p_1 = \frac{4}{\pi} \times 9000 \text{ kg} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \frac{1}{(\text{0.1 m})^2} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}} = 11.2 \text{ MPa}$$

$$Q = \frac{\pi d a^3 \Delta p}{12 \mu L} = \frac{\pi}{12} \times (\text{0.1 m}) \times (5 \times 10^{-5} \text{ m})^3 \times 11.2 \times 10^6 \frac{\text{N}}{\text{m}^2} \times \frac{1}{3 \times 10^{-4} \frac{\text{N}\cdot\text{s}}{\text{m}^2}} \times \frac{1}{\text{0.12 m}}$$

$$Q = 1.01 \times 10^{-6} \text{ m}^3/\text{s} = 1.0 \times 10^{-3} \text{ L/s} \quad \underline{Q}$$

$$\text{Check } Re = \frac{\rho V d}{\mu} = \frac{\rho V}{4 \mu} \quad \text{where } V = 2.8 \times 10^{-4} \text{ m}^2/\text{s} \quad (\text{Fig. A.3})$$

$$\bar{v} = \frac{V}{A} = \frac{Q}{aL} = \frac{Q}{\pi d L} = \frac{1}{\pi} \times 1.0 \times 10^{-6} \frac{\text{m}^3}{\text{s}} \times \frac{1}{5 \times 10^{-5} \text{ m}} \times \frac{1}{\text{0.1 m}} = 0.0643 \text{ m/s}$$

$$Re = \frac{\rho \bar{v} d}{\mu} = 5 \times 10^{-5} \text{ m} \times 0.0643 \frac{\text{m}}{\text{s}} \times \frac{1}{2.8 \times 10^{-4} \frac{\text{N}\cdot\text{s}}{\text{m}^2}} = 0.011$$

$\therefore$  flow is definitely laminar

Piston moving down at speed  $v$  displaces liquid at rate  $Q$  where

$$Q = \frac{\pi d^2}{4} v$$


$$\text{Then } v = \frac{4Q}{\pi d^2} = \frac{4}{\pi} \times 1.0 \times 10^{-6} \frac{\text{m}^3}{\text{s}} \times \frac{1}{(\text{0.1 m})^2} = 1.29 \times 10^{-4} \text{ m/s}$$

Since  $\frac{v}{\bar{v}} = \frac{1.29 \times 10^{-4} \text{ m/s}}{0.0643 \text{ m/s}} = 2.0 \times 10^{-3}$ , motion of piston can be neglected.

## Problem 8.15

[Difficulty: 3]

**8.15** A hydrostatic bearing is to support a load of 1000 lbf/ft of length perpendicular to the diagram. The bearing is supplied with SAE 10W-30 oil at 212°F and 35 psig through the central slit. Since the oil is viscous and the gap is small, the flow may be considered fully developed. Calculate (a) the required width of the bearing pad, (b) the resulting pressure gradient,  $dp/dx$ , and (c) the gap height, if the flow rate is  $Q = 2.5$  gal/hr/ft.



**Given:** Hydrostatic bearing

**Find:** Required pad width; Pressure gradient; Gap height

**Solution:**

Basic equation 
$$\frac{Q}{l} = -\frac{h^3}{12 \cdot \mu} \cdot \left( \frac{dp}{dx} \right)$$

Available data  $F = 1000 \cdot \text{lbf}$       $l = 1 \cdot \text{ft}$      ( $F$  is the load on width  $l$ )      $p_i = 35 \cdot \text{psi}$       $Q = 2.5 \cdot \frac{\text{gal}}{\text{hr}}$  per ft  
 $212^\circ\text{F} = 100^\circ\text{C}$      At  $100^\circ\text{C}$  from Fig. A.2, for SAE 10-30      $\mu = 0.01 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$       $\mu = 2.089 \times 10^{-4} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$

For a laminar flow (we will verify this assumption later), the pressure gradient is constant

$$p(x) = p_i \cdot \left( 1 - \frac{2 \cdot x}{W} \right) \quad \text{where } p_i = 35 \text{ psi is the inlet pressure (gage), and } x = 0 \text{ to } W/2$$

Hence the total force in the  $y$  direction due to pressure is  $F = l \cdot \int p \, dx$      where  $b$  is the pad width into the paper

$$F = 2 \cdot l \cdot \int_0^{W/2} p_i \cdot \left( 1 - \frac{2 \cdot x}{W} \right) dx \quad F = \frac{1}{2} \cdot p_i \cdot l \cdot W$$

This must be equal to the applied load  $F$ . Hence 
$$W = \frac{2 \cdot F}{p_i \cdot l} \quad W = 0.397 \cdot \text{ft}$$

The pressure gradient is then 
$$\frac{dp}{dx} = -\frac{\Delta p}{W} = -\frac{2 \cdot \Delta p}{W} = -2 \times \frac{35 \cdot \text{lbf}}{\text{in}^2} \times \frac{1}{0.397 \cdot \text{ft}} = -176 \cdot \frac{\text{psia}}{\text{ft}}$$

From the basic equation 
$$\frac{Q}{l} = -\frac{h^3}{12 \cdot \mu} \cdot \left( \frac{dp}{dx} \right) \quad \text{we can solve for } h = \left( -\frac{12 \cdot \mu \cdot Q}{l \cdot \frac{dp}{dx}} \right)^{\frac{1}{3}} \quad h = 2.51 \times 10^{-3} \cdot \text{in}$$

Check Re: 
$$\text{Re} = \frac{V \cdot D}{\nu} = \frac{D \cdot Q}{\nu \cdot A} = \frac{h \cdot Q}{\nu \cdot l \cdot h}$$


From Fig. A.3 
$$\nu = 1.2 \cdot 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad \nu = 1.29 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \quad \text{Re} = \frac{Q}{\nu \cdot l} \quad \text{Re} = 0.72$$

so flow is very laminar

### Problem 8.16

[Difficulty: 3]

**8.16** The basic component of a pressure gage tester consists of a piston-cylinder apparatus as shown. The piston, 6 mm in diameter, is loaded to develop a pressure of known magnitude. (The piston length is 25 mm.) Calculate the mass,  $M$ , required to produce 1.5 MPa (gage) in the cylinder. Determine the leakage flow rate as a function of radial clearance,  $a$ , for this load if the liquid is SAE 30 oil at 20°C. Specify the maximum allowable radial clearance so the vertical movement of the piston due to leakage will be less than 1 mm/min.



Solution: The mass may be found from a force balance on the piston.

$$\sum F_y = \frac{\pi D^2}{4} (p - p_{atm}) - Mg = 0 \quad \text{so } M = \frac{\pi D^2}{4g} p_{gage}$$

$$M = \frac{\pi}{4} \times (0.006)^2 \text{ m}^2 \times 1.5 \times 10^6 \frac{\text{N}}{\text{m}^2} \times \frac{\text{s}^2}{9.81 \text{ m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} = 4.32 \text{ kg}$$

The leakage flow rate may be evaluated for flow between flat plates. From Eq. 8.6c, neglecting motion of the piston,

$$\frac{Q}{L} = \frac{a^3 \Delta p}{12 \mu L} \quad \text{or, since } l = \pi D, \quad Q = \frac{\pi a^3 \Delta p D}{12 \mu L} \sim a^3$$

The piston, moving downward at speed,  $v$ , displaces liquid at rate

$$Q = \frac{\pi D^2}{4} v = \frac{\pi}{4} (0.006)^2 \text{ m}^2 \times 0.001 \frac{\text{m}}{\text{min}} \times \frac{\text{min}}{60 \text{ s}} = 4.71 \times 10^{-10} \text{ m}^3/\text{s}$$

Then, with  $\mu = 0.42 \text{ N} \cdot \text{sec}/\text{m}^2$  (at 20°C, Fig. A.2),

$$a = \left[ \frac{12 \mu Q L}{\pi D \Delta p} \right]^{1/3} = \left[ \frac{12 \times 0.42 \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times 4.71 \times 10^{-10} \frac{\text{m}^3}{\text{s}} \times 0.025 \text{ m} \times \frac{1}{0.006 \text{ m}} \times \frac{\text{m}^2}{1.5 \times 10^6 \text{ N}} \right]^{1/3}$$

$$a = 1.28 \times 10^{-5} \text{ m} \quad (12.8 \mu\text{m})$$

Check assumptions:  $\nabla = \frac{Q}{A} = \frac{Q}{\pi D a} = \frac{1}{\pi} \times 4.71 \times 10^{-10} \frac{\text{m}^3}{\text{s}} \times \frac{1}{0.006 \text{ m}} \times \frac{1}{1.28 \times 10^{-5} \text{ m}} = 1.95 \frac{\text{mm}}{\text{s}}$

Thus  $\frac{v}{\nabla} = \frac{1 \text{ mm}}{\text{min}} \times \frac{\text{sec}}{1.95 \text{ mm}} \times \frac{\text{min}}{60 \text{ s}} = 0.00855 < 0.01$

Therefore piston motion is negligible.

Also:  $Re = \frac{\nabla a}{\nu}$ ;  $\nu = \frac{\mu}{\rho} = \frac{\mu}{Sg \rho_{oil}}$ . From Table A.2 (Appendix A),  $Sg = 0.92$

$$\nu = 0.42 \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times \frac{\text{m}^3}{(0.92) 1000 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} = 4.57 \times 10^{-4} \text{ m}^2/\text{s}$$

$$Re = 1.95 \times 10^{-3} \frac{\text{m}}{\text{s}} \times 1.28 \times 10^{-5} \text{ m} \times \frac{\text{s}}{4.57 \times 10^{-4} \text{ m}^2} = 5.46 \times 10^{-5} \ll 1$$

Therefore flow is surely laminar!

## Problem 8.17

[Difficulty: 2]

**8.17** In Section 8.2 we derived the velocity profile between parallel plates (Eq. 8.5) by using a differential control volume. Instead, following the procedure we used in Example 5.9, derive Eq. 8.5 by starting with the Navier–Stokes equations (Eqs. 5.27). Be sure to state all assumptions.

**Given:** Navier-Stokes Equations

**Find:** Derivation of Eq. 8.5

**Solution:**

The Navier-Stokes equations are

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad (5.1c)$$

$$\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial p}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right) \quad (5.27a)$$

$$\rho \left( \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) = \rho g_y - \frac{\partial p}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} + \frac{\partial^2 v}{\partial z^2} \right) \quad (5.27b)$$

$$\rho \left( \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) = \rho g_z - \frac{\partial p}{\partial z} + \mu \left( \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} \right) \quad (5.27c)$$

The following assumptions have been applied:

- (1) Steady flow (given).
- (2) Incompressible flow;  $\rho = \text{constant}$ .
- (3) No flow or variation of properties in the  $z$  direction;  $w = 0$  and  $\partial/\partial z = 0$ .
- (4) Fully developed flow, so no properties except pressure  $p$  vary in the  $x$  direction;  $\partial/\partial x = 0$ .
- (5) See analysis below.
- (6) No body force in the  $x$  direction;  $g_x = 0$

Assumption (1) eliminates time variations in any fluid property. Assumption (2) eliminates space variations in density. Assumption (3) states that there is no  $z$  component of velocity and no property variations in the  $z$  direction. All terms in the  $z$  component of the Navier–Stokes equation cancel. After assumption (4) is applied, the continuity equation reduces to  $\partial v/\partial y = 0$ . Assumptions (3) and (4) also indicate that  $\partial v/\partial z = 0$  and  $\partial v/\partial x = 0$ . Therefore  $v$  must be constant. Since  $v$  is zero at the solid surface, then  $v$  must be zero everywhere. The fact that  $v = 0$  reduces the Navier–Stokes equations further, as indicated by (5). Hence for the  $y$  direction

$$\frac{\partial p}{\partial y} = \rho g$$

which indicates a hydrostatic variation of pressure. In the  $x$  direction, after assumption (6) we obtain

$$\mu \frac{\partial^2 u}{\partial y^2} - \frac{\partial p}{\partial x} = 0$$

Integrating twice

$$u = \frac{1}{2\mu} \frac{\partial p}{\partial x} y^2 + \frac{c_1}{\mu} y + c_2$$

To evaluate the constants,  $c_1$  and  $c_2$ , we must apply the boundary conditions. At  $y = 0$ ,  $u = 0$ . Consequently,  $c_2 = 0$ . At  $y = a$ ,  $u = 0$ . Hence

$$0 = \frac{1}{2\mu} \frac{\partial p}{\partial x} a^2 + \frac{c_1}{\mu} a$$

which gives

$$c_1 = -\frac{1}{2\mu} \frac{\partial p}{\partial x} a$$

and finally

$$u = \frac{a^2}{2\mu} \frac{\partial p}{\partial x} \left[ \left( \frac{y}{a} \right)^2 - \left( \frac{y}{a} \right) \right]$$

## Problem 8.18

[Difficulty: 4]

**8.18** Consider the simple power-law model for a non-Newtonian fluid given by Eq. 2.16. Extend the analysis of Section 8.2 to show that the velocity profile for fully developed laminar flow of a power-law fluid between stationary parallel plates separated by distance  $2h$  may be written

$$u = \left(\frac{h}{k} \frac{\Delta p}{L}\right)^{1/n} \frac{nh}{n+1} \left[1 - \left(\frac{y}{h}\right)^{(n+1)/n}\right]$$


where  $y$  is the coordinate measured from the channel centerline. Plot the profiles  $u/U_{\max}$  versus  $y/h$  for  $n = 0.7, 1.0$ , and  $1.3$ .

Solution: Apply momentum equation to differential CV

Basic equation:

$$F_{sx} + F_{bx} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

$\uparrow = 0(1)$       $\uparrow = 0(2)$       $\uparrow = 0(3)$



- Assumptions: (1) Horizontal flow  
 (2) Steady flow  
 (3) Fully developed flow

Then

$$p_w dy + (\tau + \frac{\partial \tau}{\partial y} dy) w dx - (p + \frac{\partial p}{\partial x} dx) w dy - \tau_w dx = 0 \quad \text{or} \quad \frac{\partial \tau}{\partial y} = \frac{\partial p}{\partial x}$$

Since  $\tau = \tau(y)$  and  $p = p(x)$ , then  $\frac{d\tau}{dy} = \frac{\partial p}{\partial x} = \text{constant}$  and  $\tau = y \frac{\partial p}{\partial x}$  or

$$\tau_w = k \left(\frac{du}{dy}\right)^n = y \frac{\partial p}{\partial x} = -y \frac{\Delta p}{L}$$

Thus  $\frac{du}{dy} = -\left(\frac{1}{k} \frac{\Delta p}{L}\right)^{1/n} y^{1/n}$

Integrating

$$u = -\left(\frac{1}{k} \frac{\Delta p}{L}\right)^{1/n} \frac{1}{1/n+1} y^{1/n+1} + c = -\left(\frac{1}{k} \frac{\Delta p}{L}\right)^{1/n} \frac{n}{n+1} y^{n/n} + c$$

But  $u = 0$  at  $y = h$ , so

$$c = \left(\frac{1}{k} \frac{\Delta p}{L}\right)^{1/n} \frac{n}{n+1} h^{n/n}$$


and

$$u = \left(\frac{1}{k} \frac{\Delta p}{L}\right)^{1/n} \frac{n}{n+1} h^{n/n} \left[1 - \left(\frac{y}{h}\right)^{n/n}\right]$$

or

$$u = \left(\frac{h}{k} \frac{\Delta p}{L}\right)^{1/n} \frac{nh}{n+1} \left[1 - \left(\frac{y}{h}\right)^{n/n}\right]$$

$y/h$	$n = 0.7$	$n = 1.0$	$n = 1.3$
0	1	1	1
0.03	1.000	0.999	0.998
0.06	0.999	0.996	0.993
0.1	0.996	0.990	0.983
0.2	0.980	0.960	0.942
0.3	0.946	0.910	0.881
0.4	0.892	0.840	0.802
0.5	0.814	0.750	0.707
0.6	0.711	0.640	0.595
0.7	0.580	0.510	0.468
0.8	0.418	0.360	0.326
0.9	0.226	0.190	0.170
1	0	0	0




### Problem 8.19

[Difficulty: 5]

**8.19** Viscous liquid, at volume flow rate  $Q$ , is pumped through the central opening into the narrow gap between the parallel disks shown. The flow rate is low, so the flow is laminar, and the pressure gradient due to convective acceleration in the gap is negligible compared with the gradient caused by viscous forces (this is termed *creeping flow*). Obtain a general expression for the variation of average velocity in the gap between the disks. For creeping flow, the velocity profile at any cross section in the gap is the same

as for fully developed flow between stationary parallel plates. Evaluate the pressure gradient,  $dp/dr$ , as a function of radius. Obtain an expression for  $p(r)$ . Show that the net force required to hold the upper plate in the position shown is

$$F = \frac{3\mu QR^2}{h^3} \left[ 1 - \left( \frac{R_0}{R} \right)^2 \right]$$



Solution: From the definition of mean velocity,  $Q = \bar{v} 2\pi r h$  so  $\bar{v} = \frac{Q}{2\pi r h}$   $\bar{v}(r)$

The pressure change with radius can be evaluated by analogy to Eq. 8.6b

$$\frac{Q}{L} = -\frac{1}{12\mu} \left( \frac{\partial p}{\partial x} \right) h^3 \quad \text{with } L = 2\pi r \quad \text{so} \quad \frac{Q}{2\pi r} = -\frac{1}{12\mu} \left( \frac{\partial p}{\partial r} \right) h^3$$

Thus

$$\frac{dp}{dr} = -\frac{6\mu Q}{\pi h^3 r}$$

Integrating to find  $p(r)$ ,

$$\int_p^{p_{atm}} dp = p_{atm} - p = \int_r^R -\frac{6\mu Q}{\pi h^3 r} dr = -\frac{6\mu Q}{\pi h^3} \ln r \Big|_r^R = \frac{6\mu Q}{\pi h^3} \ln(r/R)$$

Thus  $p(r) = p_{atm} - \frac{6\mu Q}{\pi h^3} \ln(r/R)$  ( $R_0 < r < R$ );  $p = p_0$  ( $r < R_0$ )  $p(r)$

The force on the upper plate is  $dF_z = (p(r) - p_{atm}) 2\pi r dr$

Integrating and using gage pressures (note  $p_{og} = -\frac{6\mu Q}{\pi h^3} \ln(\frac{R_0}{R})$ )


$$\begin{aligned} F_z &= p_0 \pi R_0^2 + \int_{R_0}^R p(r) 2\pi r dr = p_0 \pi R_0^2 + 2\pi R^2 \int_{R_0/R}^1 p(r) \left( \frac{r}{R} \right) d\left( \frac{r}{R} \right) \\ &= p_0 \pi R_0^2 + 2\pi R^2 \int_{R_0/R}^1 -\frac{6\mu Q}{\pi h^3} \ln\left( \frac{r}{R} \right) \left( \frac{r}{R} \right) d\left( \frac{r}{R} \right) = p_0 \pi R_0^2 - \frac{12\mu Q R^2}{h^3} \left( \frac{r}{R} \right) \left[ \frac{1}{2} \ln\left( \frac{r}{R} \right) - \frac{1}{4} \right] \Big|_{R_0/R}^1 \\ &= p_0 \pi R_0^2 - \frac{12\mu Q R^2}{h^3} \left\{ (1) \left[ \frac{1}{2} (0) - \frac{1}{4} \right] - \left( \frac{R_0}{R} \right) \left[ \frac{1}{2} \ln\left( \frac{R_0}{R} \right) - \frac{1}{4} \right] \right\} \\ &= -\frac{6\mu Q R^2}{h^3} \left( \frac{R_0}{R} \right)^2 \ln\left( \frac{R_0}{R} \right) - \frac{6\mu Q R^2}{h^3} \left[ -\frac{1}{2} - \left( \frac{R_0}{R} \right)^2 \ln\left( \frac{R_0}{R} \right) + \frac{1}{2} \left( \frac{R_0}{R} \right)^2 \right] \end{aligned}$$

$$F_z = \frac{3\mu Q R^2}{h^3} \left[ 1 - \left( \frac{R_0}{R} \right)^2 \right]$$

## Problem 8.20

[Difficulty: 2]


**8.20** A sealed journal bearing is formed from concentric cylinders. The inner and outer radii are 25 and 26 mm, the journal length is 100 mm, and it turns at 2800 rpm. The gap is filled with oil in laminar motion. The velocity profile is linear across the gap. The torque needed to turn the journal is 0.2 N·m. Calculate the viscosity of the oil. Will the torque increase or decrease with time? Why?



Solution: "Unfold" bearing since gap is small, and consider as flow between parallel plates. Apply Newton's law of viscosity.

Basic equation:  $\tau_{yx} = \mu \frac{du}{dy}$

Assumption: Linear velocity profile



Then  $\tau_{yx} = \mu \frac{U}{\Delta r} = \frac{\mu \omega r_i}{\Delta r}$

and

$$T = r_i (2\pi r_i L \tau_{yx}) = 2\pi r_i^2 L \tau_{yx} = \frac{2\pi \mu \omega r_i^3 L}{\Delta r}$$

Solving,  $\mu = \frac{\Delta r T}{2\pi \omega r_i^3 L}$

$$\mu = \frac{1}{2\pi} \times 0.001 \text{ m} \times 0.2 \text{ N}\cdot\text{m} \times \frac{\text{min}}{2800 \text{ rev}} \times \frac{1}{(0.025)^3 \text{ m}^3} \times \frac{1}{0.1 \text{ m}} \times \frac{\text{rev}}{2\pi \text{ rad}} \times \frac{60 \text{ s}}{\text{min}}$$

$$\mu = 0.0695 \text{ N}\cdot\text{s} / \text{m}^2$$

Bearing is sealed, so oil temperature will increase as energy is dissipated by friction. For liquids,  $\mu$  decreases as  $T$  increases. Thus torque will decrease, since it is proportional to  $\mu$ .

## Problem 8.21

[Difficulty: 3]

**8.21** Using the profile of Problem 8.18, show that the flow rate for fully developed laminar flow of a power-law fluid between stationary parallel plates may be written as

$$Q = \left( \frac{h}{k} \frac{\Delta p}{L} \right)^{1/n} \frac{2nwh^2}{2n+1}$$

Here  $w$  is the plate width. In such an experimental setup the following data on applied pressure difference  $\Delta p$  and flow rate  $Q$  were obtained:

$\Delta p$ (kPa)	10	20	30	40	50	60	70	80	90	100
$Q$ (L/min)	0.451	0.759	1.01	1.15	1.41	1.57	1.66	1.85	2.05	2.25

Determine if the fluid is pseudoplastic or dilatant, and obtain an experimental value for  $n$ .

**Given:** Laminar velocity profile of power-law fluid flow between parallel plates

**Find:** Expression for flow rate; from data determine the type of fluid

**Solution:**

The velocity profile is

$$u = \left( \frac{h}{k} \frac{\Delta p}{L} \right)^{\frac{1}{n}} \cdot \frac{n \cdot h}{n+1} \cdot \left[ 1 - \left( \frac{y}{h} \right)^{\frac{n+1}{n}} \right]$$

The flow rate is then

$$Q = w \cdot \int_{-h}^h u \, dy \quad \text{or, because the flow is symmetric} \quad Q = 2 \cdot w \cdot \int_0^h u \, dy$$

The integral is computed as

$$\int \left[ 1 - \left( \frac{y}{h} \right)^{\frac{n+1}{n}} \right] dy = y \cdot \left[ 1 - \frac{n}{2 \cdot n + 1} \cdot \left( \frac{y}{h} \right)^{\frac{2 \cdot n + 1}{n}} \right]$$

Using this with the limits

$$Q = 2 \cdot w \cdot \left( \frac{h}{k} \frac{\Delta p}{L} \right)^{\frac{1}{n}} \cdot \frac{n \cdot h}{n+1} \cdot h \cdot \left[ 1 - \frac{n}{2 \cdot n + 1} \cdot (1)^{\frac{2 \cdot n + 1}{n}} \right] \quad Q = \left( \frac{h}{k} \frac{\Delta p}{L} \right)^{\frac{1}{n}} \cdot \frac{2 \cdot n \cdot w \cdot h^2}{2 \cdot n + 1}$$

An *Excel* spreadsheet can be used for computation of  $n$ .


The data is

$dp$ (kPa)	10	20	30	40	50	60	70	80	90	100
$Q$ (L/min)	0.451	0.759	1.01	1.15	1.41	1.57	1.66	1.85	2.05	2.25

This must be fitted to

$$Q = \left( \frac{h}{k} \frac{\Delta p}{L} \right)^{\frac{1}{n}} \cdot \frac{2 \cdot n \cdot w \cdot h^2}{2 \cdot n + 1} \quad \text{or} \quad Q = k \cdot \Delta p^{\frac{1}{n}}$$

We can fit a power curve to the data



Hence  $1/n = 0.677$   $n = 1.48$

It's a dilatant fluid

## Problem 8.22


[Difficulty: 2]

**8.22** Consider fully developed laminar flow between infinite parallel plates separated by gap width  $d = 0.2$  in. The upper plate moves to the right with speed  $U_2 = 5$  ft/s; the lower plate moves to the left with speed  $U_1 = 2$  ft/s. The pressure gradient in the direction of flow is zero. Develop an expression for the velocity distribution in the gap. Find the volume flow rate per unit depth (gpm/ft) passing a given cross section.

**Given:** Laminar flow between moving plates

**Find:** Expression for velocity; Volume flow rate per depth

**Solution:**



Given data  $d = 0.2 \text{ in}$   $U_1 = 5 \cdot \frac{\text{ft}}{\text{s}}$   $U_2 = 2 \cdot \frac{\text{ft}}{\text{s}}$

Using the analysis of Section 8.2, the sum of forces in the x direction is

$$\left[ \tau + \frac{\partial \tau}{\partial y} \tau \cdot \frac{dy}{2} - \left( \tau - \frac{\partial \tau}{\partial y} \tau \cdot \frac{dy}{2} \right) \right] \cdot b \cdot dx + \left( p - \frac{\partial p}{\partial x} p \cdot \frac{dx}{2} - p + \frac{\partial p}{\partial x} p \cdot \frac{dx}{2} \right) \cdot b \cdot dy = 0$$

Simplifying  $\frac{d\tau}{dy} = \frac{dp}{dx} = 0$  or  $\mu \cdot \frac{d^2 u}{dy^2} = 0$

Integrating twice  $u = c_1 \cdot y + c_2$

Boundary conditions:  $u(0) = -U_1$   $c_2 = -U_1$   $c_2 = -5 \frac{\text{ft}}{\text{s}}$   $u(y = d) = U_2$   $c_1 = \frac{U_1 + U_2}{d}$   $c_1 = 420 \text{ s}^{-1}$

Hence  $u(y) = (U_1 + U_2) \cdot \frac{y}{d} - U_1$   $u(y) = 420 \cdot y - 5$   $u$  in ft/s,  $y$  in ft

The volume flow rate is  $Q = \int u \, dA = b \cdot \int u \, dy$   $Q = b \cdot \int_0^d \left[ (U_1 + U_2) \cdot \frac{y}{d} - U_1 \right] dx = b \cdot \left( \frac{U_1 + U_2}{d} \cdot \frac{d^2}{2} - U_1 \cdot d \right)$

Hence  $Q = b \cdot d \cdot \frac{(U_2 - U_1)}{2}$   $\frac{Q}{b} = d \cdot \frac{(U_2 - U_1)}{2}$


$$\frac{Q}{b} = 0.2 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \times \frac{1}{2} \times (2 - 5) \times \frac{\text{ft}}{\text{s}} \quad \frac{Q}{b} = -.025 \cdot \frac{\text{ft}^3}{\text{ft} \cdot \text{s}}$$

$$\frac{Q}{b} = -.025 \cdot \frac{\text{ft}^3}{\text{ft} \cdot \text{s}} \times \frac{7.48 \cdot \text{gal}}{1 \cdot \text{ft}^3} \times \frac{60 \cdot \text{s}}{1 \cdot \text{min}} \quad \frac{Q}{b} = -11.2 \cdot \frac{\text{gpm}}{\text{ft}}$$

### Problem 8.23

[Difficulty: 2]

8.23 Water at 60°C flows between two large flat plates. The lower plate moves to the left at a speed of 0.3 m/s; the upper plate is stationary. The plate spacing is 3 mm, and the flow is laminar. Determine the pressure gradient required to produce zero net flow at a cross section.



Solution: Apply momentum equation using CV and coordinates shown.

Basic equations:  $F_{Sx} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} \rho u \, dV + \int_{CS} \rho u \vec{V} \cdot d\vec{A}$ ,  $\tau = \tau_{yx} = \mu \frac{du}{dy}$

- Assumptions: (1)  $F_{Bx} = 0$   
 (2) Steady flow  
 (3) Fully-developed flow  
 (4) Newtonian fluid

Then  $F_{Sx} = 0$ . Substituting the force terms (see page 315 for details) gives

$$\frac{\partial p}{\partial x} = \frac{d\tau_{yx}}{dy} = \frac{d}{dy} \left( \mu \frac{du}{dy} \right) = \mu \frac{d^2 u}{dy^2} \quad \text{or} \quad \frac{d^2 u}{dy^2} = \frac{1}{\mu} \frac{\partial p}{\partial x}$$

Integrating twice,

$$u = \frac{1}{2\mu} \frac{\partial p}{\partial x} y^2 + C_1 y + C_2$$

To evaluate the constants  $C_1$  and  $C_2$ , we must use the boundary conditions. At  $y=0$ ,  $u = -U$ , so  $C_2 = -U$ . At  $y=b$ ,  $u=0$ , so

$$0 = \frac{1}{2\mu} \frac{\partial p}{\partial x} b^2 + C_1 b - U \quad \text{or} \quad C_1 = \frac{U}{b} - \frac{1}{2\mu} \frac{\partial p}{\partial x} b$$

Thus

$$u = \frac{1}{2\mu} \frac{\partial p}{\partial x} (y^2 - by) + U \left( \frac{y}{b} - 1 \right)$$

To find the flowrate, we integrate

$$\frac{Q}{W} = \int_0^b u \, dy = \int_0^b \left[ \frac{1}{2\mu} \frac{\partial p}{\partial x} (y^2 - by) + U \left( \frac{y}{b} - 1 \right) \right] dy = -\frac{1}{12\mu} \frac{\partial p}{\partial x} b^3 - \frac{U b}{2}$$

For  $Q = 0$ , with  $\mu = 4.63 \times 10^{-4} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$  from Table A.8,

$$\frac{\partial p}{\partial x} = -\frac{6U\mu}{b^2} = -6 \times 0.3 \frac{\text{m}}{\text{s}} \times 4.63 \times 10^{-4} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times \frac{1}{(0.003)^2 \text{m}^2} = -92.6 \text{ N/m}^2 \cdot \text{m}$$

Thus pressure must decrease in  $x$  direction for zero net flowrate. ←

$\frac{\partial p}{\partial x}$

## Problem 8.24

[Difficulty: 3]

**8.24** Two immiscible fluids are contained between infinite parallel plates. The plates are separated by distance  $2h$ , and the two fluid layers are of equal thickness  $h = 5$  mm. The dynamic viscosity of the upper fluid is four times that of the lower fluid, which is  $\mu_{\text{lower}} = 0.1 \text{ N}\cdot\text{s}/\text{m}^2$ . If the plates are stationary and the applied pressure gradient is  $-50 \text{ kPa}/\text{m}$ , find the velocity at the interface. What is the maximum velocity of the flow? Plot the velocity distribution.

**Given:** Properties of two fluids flowing between parallel plates; applied pressure gradient

**Find:** Velocity at the interface; maximum velocity; plot velocity distribution


**Solution:**

Given data  $\frac{dp}{dx} = k \quad k = -50 \cdot \frac{\text{kPa}}{\text{m}} \quad h = 5 \cdot \text{mm} \quad \mu_1 = 0.1 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2} \quad \mu_2 = 4 \cdot \mu_1 \quad \mu_2 = 0.4 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

(Lower fluid is fluid 1; upper is fluid 2)

Following the analysis of Section 8.2, analyse the forces on a differential CV of either fluid

The net force is zero for steady flow, so

$$\left[ \tau + \frac{d\tau}{dy} \cdot \frac{dy}{2} - \left( \tau - \frac{d\tau}{dy} \cdot \frac{dy}{2} \right) \right] \cdot dx \cdot dz + \left[ p - \frac{dp}{dx} \cdot \frac{dx}{2} - \left( p + \frac{dp}{dx} \cdot \frac{dx}{2} \right) \right] \cdot dy \cdot dz = 0$$


Simplifying  $\frac{d\tau}{dy} = \frac{dp}{dx} = k$  so for each fluid  $\mu \cdot \frac{d^2}{dy^2} u = k$

Applying this to fluid 1 (lower fluid) and fluid 2 (upper fluid), integrating twice yields

$$u_1 = \frac{k}{2 \cdot \mu_1} \cdot y^2 + c_1 \cdot y + c_2 \quad u_2 = \frac{k}{2 \cdot \mu_2} \cdot y^2 + c_3 \cdot y + c_4$$

For convenience the origin of coordinates is placed at the centerline

We need four BCs. Three are obvious  $y = -h \quad u_1 = 0 \quad (1) \quad y = 0 \quad u_1 = u_2 \quad (2) \quad y = h \quad u_2 = 0 \quad (3)$

The fourth BC comes from the fact that the stress at the interface generated by each fluid is the same

$$y = 0 \quad \mu_1 \cdot \frac{du_1}{dy} = \mu_2 \cdot \frac{du_2}{dy} \quad (4)$$

Using these four BCs  $0 = \frac{k}{2 \cdot \mu_1} \cdot h^2 - c_1 \cdot h + c_2 \quad c_2 = c_4 \quad 0 = \frac{k}{2 \cdot \mu_2} \cdot h^2 + c_3 \cdot h + c_4 \quad \mu_1 \cdot c_1 = \mu_2 \cdot c_3$

Hence, after some algebra

$$c_1 = \frac{k \cdot h}{2 \cdot \mu_1} \cdot \frac{(\mu_2 - \mu_1)}{(\mu_2 + \mu_1)} \quad c_4 = -\frac{k \cdot h^2}{\mu_2 + \mu_1} \quad c_2 = c_4 \quad c_3 = \frac{k \cdot h}{2 \cdot \mu_2} \cdot \frac{(\mu_2 - \mu_1)}{(\mu_2 + \mu_1)}$$

$$c_1 = -750 \frac{1}{s}$$

$$c_2 = 2.5 \frac{m}{s}$$

$$c_3 = -187.5 \frac{1}{s}$$

$$c_4 = 2.5 \frac{m}{s}$$

The velocity distributions are then


$$u_1(y) = \frac{k}{2 \cdot \mu_1} \cdot \left[ y^2 + y \cdot h \cdot \frac{(\mu_2 - \mu_1)}{(\mu_2 + \mu_1)} \right] - \frac{k \cdot h^2}{\mu_2 + \mu_1}$$

$$u_2(y) = \frac{k}{2 \cdot \mu_2} \cdot \left[ y^2 + y \cdot h \cdot \frac{(\mu_2 - \mu_1)}{(\mu_2 + \mu_1)} \right] - \frac{k \cdot h^2}{\mu_2 + \mu_1}$$

Evaluating either velocity at  $y = 0$ , gives the velocity at the interface

$$u_{\text{interface}} = -\frac{k \cdot h^2}{\mu_2 + \mu_1} \quad u_{\text{interface}} = 2.5 \frac{m}{s}$$

The plots of these velocity distributions can be done in *Excel*. Typical curves are shown below



Clearly,  $u_1$  has the maximum velocity, when  $\frac{du_1}{dy} = 0$  or  $2 \cdot y_{\text{max}} + h \cdot \frac{(\mu_2 - \mu_1)}{(\mu_2 + \mu_1)} = 0$

$$y_{\text{max}} = -\frac{h}{2} \cdot \frac{(\mu_2 - \mu_1)}{(\mu_2 + \mu_1)} \quad y_{\text{max}} = -1.5 \text{ mm} \quad u_{\text{max}} = u_1(y_{\text{max}}) \quad u_{\text{max}} = 3.06 \frac{m}{s}$$

(We could also have used *Excel*'s Solver for this.)

## Problem 8.25


[Difficulty: 3]

**8.25** Two immiscible fluids are contained between infinite parallel plates. The plates are separated by distance  $2h$ , and the two fluid layers are of equal thickness  $h$ ; the dynamic viscosity of the upper fluid is three times that of the lower fluid. If the lower plate is stationary and the upper plate moves at constant speed  $U = 20$  ft/s, what is the velocity at the interface? Assume laminar flows, and that the pressure gradient in the direction of flow is zero.

**Given:** Laminar flow of two fluids between plates

**Find:** Velocity at the interface

**Solution:**



Using the analysis of Section 8.2, the sum of forces in the x direction is

$$\left[ \tau + \frac{\partial \tau}{\partial y} \cdot \frac{dy}{2} - \left( \tau - \frac{\partial \tau}{\partial y} \cdot \frac{dy}{2} \right) \right] \cdot b \cdot dx + \left( p - \frac{\partial p}{\partial x} \cdot \frac{dx}{2} - p + \frac{\partial p}{\partial x} \cdot \frac{dx}{2} \right) \cdot b \cdot dy = 0$$

Simplifying  $\frac{d\tau}{dy} = \frac{dp}{dx} = 0$  or  $\mu \cdot \frac{d^2 u}{dy^2} = 0$

Applying this to fluid 1 (lower fluid) and fluid 2 (upper fluid), integrating twice yields  $u_1 = c_1 \cdot y + c_2$   $u_2 = c_3 \cdot y + c_4$

We need four BCs. Three are obvious  $y = 0 \quad u_1 = 0 \quad y = h \quad u_1 = u_2 \quad y = 2 \cdot h \quad u_2 = U$

The fourth BC comes from the fact that the stress at the interface generated by each fluid is the same

$$y = h \quad \mu_1 \cdot \frac{du_1}{dy} = \mu_2 \cdot \frac{du_2}{dy}$$

Using these four BCs  $0 = c_2 \quad c_1 \cdot h + c_2 = c_3 \cdot h + c_4 \quad U = c_3 \cdot 2 \cdot h + c_4 \quad \mu_1 \cdot c_1 = \mu_2 \cdot c_3$

Hence  $c_2 = 0$

From the 2nd and 3rd equations  $c_1 \cdot h - U = -c_3 \cdot h$  and  $\mu_1 \cdot c_1 = \mu_2 \cdot c_3$

Hence  $c_1 \cdot h - U = -c_3 \cdot h = -\frac{\mu_1}{\mu_2} \cdot h \cdot c_1$   $c_1 = \frac{U}{h \cdot \left( 1 + \frac{\mu_1}{\mu_2} \right)}$

Hence for fluid 1 (we do not need to complete the analysis for fluid 2)  $u_1 = \frac{U}{h \cdot \left( 1 + \frac{\mu_1}{\mu_2} \right)} \cdot y$

Evaluating this at  $y = h$ , where  $u_1 = u_{\text{interface}}$   $u_{\text{interface}} = \frac{20 \cdot \frac{\text{ft}}{\text{s}}}{\left( 1 + \frac{1}{3} \right)}$   $u_{\text{interface}} = 15 \cdot \frac{\text{ft}}{\text{s}}$

## Problem 8.26

[Difficulty: 2]

**8.26** The record-read head for a computer disk-drive memory storage system rides above the spinning disk on a very thin film of air (the film thickness is  $0.25 \mu\text{m}$ ). The head location is 25 mm from the disk centerline; the disk spins at 8500 rpm. The record-read head is 5 mm square. For standard air in the gap between the head and disk, determine (a) the Reynolds number of the flow, (b) the viscous shear stress, and (c) the power required to overcome viscous shear.

**Given:** Computer disk drive

**Find:** Flow Reynolds number; Shear stress; Power required

**Solution:**

For a distance  $R$  from the center of a disk spinning at speed  $\omega$

$$V = R \cdot \omega \quad V = 25\text{-mm} \times \frac{1\text{-m}}{1000\text{mm}} \times 8500\text{rpm} \times \frac{2 \cdot \pi \cdot \text{rad}}{\text{rev}} \times \frac{1\text{-min}}{60\text{-s}} \quad V = 22.3 \frac{\text{m}}{\text{s}}$$

The gap Reynolds number is  $Re = \frac{\rho \cdot V \cdot a}{\mu} = \frac{V \cdot a}{\nu}$   $\nu = 1.45 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$  from Table A.10 at 15°C

$$Re = 22.3 \frac{\text{m}}{\text{s}} \times 0.25 \times 10^{-6} \cdot \text{m} \times \frac{\text{s}}{1.45 \times 10^{-5} \cdot \text{m}^2} \quad Re = 0.384$$

The flow is definitely laminar

The shear stress is then  $\tau = \mu \cdot \frac{du}{dy} = \mu \cdot \frac{V}{a}$   $\mu = 1.79 \times 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$  from Table A.10 at 15°C

$$\tau = 1.79 \times 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times 22.3 \frac{\text{m}}{\text{s}} \times \frac{1}{0.25 \times 10^{-6} \cdot \text{m}} \quad \tau = 1.60 \cdot \text{kPa}$$

The power required is  $P = T \cdot \omega$  where torque  $T$  is given by

$$T = \tau \cdot A \cdot R \quad \text{with} \quad A = (5\text{-mm})^2 \quad A = 2.5 \times 10^{-5} \text{m}^2$$

$$P = \tau \cdot A \cdot R \cdot \omega \quad P = 1600 \cdot \frac{\text{N}}{\text{m}^2} \times 2.5 \times 10^{-5} \cdot \text{m}^2 \times 25\text{-mm} \times \frac{1\text{-m}}{1000\text{-mm}} \times 8500\text{-rpm} \times \frac{2 \cdot \pi \cdot \text{rad}}{\text{rev}} \times \frac{1\text{-min}}{60\text{-s}} \quad P = 0.890 \text{ W}$$

## Problem 8.27


[Difficulty: 2]

**8.27** The dimensionless velocity profile for fully developed laminar flow between infinite parallel plates with the upper plate moving at constant speed  $U$  is shown in Fig. 8.6. Find the pressure gradient  $\partial p/\partial x$  at which (a) the upper plate and (b) the lower plate experience zero shear stress, in terms of  $U$ ,  $a$ , and  $\mu$ . Plot the dimensionless velocity profiles for these cases.

**Given:** Velocity profile between parallel plates

**Find:** Pressure gradients for zero stress at upper/lower plates; plot

**Solution:**



**Fig. 8.6** Dimensionless velocity profile for fully developed laminar flow between infinite parallel plates: upper plate moving with constant speed,  $U$ .

From Eq. 8.8, the velocity distribution is

$$u = \frac{U \cdot y}{a} + \frac{a^2}{2 \cdot \mu} \cdot \left( \frac{\partial p}{\partial x} \right) \cdot \left[ \left( \frac{y}{a} \right)^2 - \frac{y}{a} \right]$$

The shear stress is

$$\tau_{yx} = \mu \cdot \frac{du}{dy} = \mu \cdot \frac{U}{a} + \frac{a^2}{2} \cdot \left( \frac{\partial p}{\partial x} \right) \cdot \left( 2 \cdot \frac{y}{a^2} - \frac{1}{a} \right)$$

(a) For  $\tau_{yx} = 0$  at  $y = a$

$$0 = \mu \cdot \frac{U}{a} + \frac{a}{2} \cdot \frac{\partial p}{\partial x} \qquad \frac{\partial p}{\partial x} = -\frac{2 \cdot U \cdot \mu}{a^2}$$

The velocity distribution is then

$$u = \frac{U \cdot y}{a} - \frac{a^2}{2 \cdot \mu} \cdot \frac{2 \cdot U \cdot \mu}{a^2} \cdot \left[ \left( \frac{y}{a} \right)^2 - \frac{y}{a} \right] \qquad \frac{u}{U} = 2 \cdot \frac{y}{a} - \left( \frac{y}{a} \right)^2$$

(b) For  $\tau_{yx} = 0$  at  $y = 0$


$$0 = \mu \cdot \frac{U}{a} - \frac{a}{2} \cdot \frac{\partial p}{\partial x} \qquad \frac{\partial p}{\partial x} = \frac{2 \cdot U \cdot \mu}{a^2}$$

The velocity distribution is then

$$u = \frac{U \cdot y}{a} + \frac{a^2}{2 \cdot \mu} \cdot \frac{2 \cdot U \cdot \mu}{a^2} \cdot \left[ \left( \frac{y}{a} \right)^2 - \frac{y}{a} \right] \qquad \frac{u}{U} = \left( \frac{y}{a} \right)^2$$

The velocity distributions can be plotted in *Excel*.

$y/a$	(a) $u/U$	(b) $u/U$
0.0	0.000	0.000
0.1	0.190	0.010
0.2	0.360	0.040
0.3	0.510	0.090
0.4	0.640	0.160
0.5	0.750	0.250
0.6	0.840	0.360
0.7	0.910	0.490
0.8	0.960	0.640
0.9	0.990	0.810
1.0	1.00	1.000




### Problem 8.28

[Difficulty: 2]

**8.28** Consider steady, fully developed laminar flow of a viscous liquid down an inclined surface. The liquid layer is of constant thickness,  $h$ . Use a suitably chosen differential control volume to obtain the velocity profile. Develop an expression for the volume flow rate.

Solution: Flow is fully developed, so  $u = u(y)$  and  $r = r(y)$ . Expand  $r$  in a Taylor series about the center of the differential CV.



$$r_c = r + \frac{dr}{dy} \frac{dy}{2}$$

$$r_b = r + \frac{dr}{dy} \left(-\frac{dy}{2}\right)$$

The boundary conditions on the velocity profile are:

@  $y=0$ ,  $u=0$  (no slip).

@  $y=h$ ,  $\frac{du}{dy}=0$  (no shear stress).

Apply the  $x$  component of the momentum equation to the differential CV shown

$$F_{s_x} + F_{a_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{v} \cdot d\vec{A}$$

Assumptions: (1) steady flow

(2) fully developed flow, so  $u$  and  $r$  are functions of  $y$  only

(3) no variation of pressure in the  $x$  direction

Then

$$F_{s_x} + F_{a_x} = 0 = \left(r + \frac{dr}{dy} \frac{dy}{2}\right) dx dz - \left(r - \frac{dr}{dy} \frac{dy}{2}\right) dx dz + \rho g \sin \theta dx dy dz$$

or

$$\frac{dr}{dy} = -\rho g \sin \theta$$

Integrating,

$$r = -\rho g \sin \theta y + c_1$$

But  $r=0$  @  $y=h$ ,  $\therefore c_1 = \rho g \sin \theta h$ , and

$$\frac{du}{dy} = \frac{\rho g \sin \theta}{\mu} (h-y)$$

Integrating again,

$$u = \frac{\rho g \sin \theta}{2\mu} \left(hy - \frac{y^2}{2}\right) + c_2$$

At  $y=0$ ,  $u=0$ , so  $c_2 = 0$  and hence

$$u = \frac{\rho g \sin \theta}{2\mu} \left(hy - \frac{y^2}{2}\right)$$

$$Q/w = \int_0^h u dy = \frac{\rho g \sin \theta}{2\mu} \int_0^h \left(hy - \frac{y^2}{2}\right) dy = \frac{\rho g \sin \theta}{2\mu} \left[ \frac{h^2 y}{2} - \frac{y^3}{6} \right]_0^h$$

$$Q/w = \rho g \sin \theta h^3 / 3\mu$$

## Problem 8.29

[Difficulty: 2]

**8.29** Consider steady, incompressible, and fully developed laminar flow of a viscous liquid down an incline with no pressure gradient. The velocity profile was derived in Example 5.9. Plot the velocity profile. Calculate the kinematic viscosity of the liquid if the film thickness on a 30° slope is 0.8 mm and the maximum velocity is 15.7 mm/s.

Solution:

$$u = \frac{\rho g \sin \theta}{\mu} \left( hy - \frac{y^2}{2} \right) = \frac{\rho g \sin \theta}{\mu} \left( hy - \frac{y^2}{2} \right)$$

$$u = u_{\max} \text{ at } y = h$$

$$\therefore u_{\max} = \frac{\rho g \sin \theta}{\mu} \left( h^2 - \frac{h^2}{2} \right) = \frac{\rho g \sin \theta h^2}{2\mu}$$


and:

$$\nu = \frac{\rho g \sin \theta h^2}{2 u_{\max}} = \frac{\sin 30^\circ}{2} \times \frac{9.81 \frac{\text{m}}{\text{s}^2}}{0.1} \times \frac{(0.8 \times 10^{-3})^2}{15.7 \times 10^{-3} \frac{\text{m}}{\text{s}}}$$

$$\nu = 1.00 \times 10^{-4} \text{ m}^2/\text{s}$$

$$\text{Plot } \frac{u}{u_{\max}} = \frac{\rho g \sin \theta}{\mu} \left( hy - \frac{y^2}{2} \right) \times \frac{2\mu}{\rho g \sin \theta h^2} = 2 \frac{y}{h} - \left( \frac{y}{h} \right)^2$$

$u/u_{\max}$	$y/h$
0	0
0.0396	0.02
0.098	0.05
0.190	0.1
0.360	0.2
0.510	0.3
0.640	0.4
0.750	0.5
0.840	0.6
0.910	0.7
0.960	0.8
0.990	0.9
1.00	1.0



## Problem 8.30

[Difficulty: 3]

**8.30** Two immiscible fluids of equal density are flowing down a surface inclined at a  $60^\circ$  angle. The two fluid layers are of equal thickness  $h = 10$  mm; the kinematic viscosity of the upper fluid is 1/5th that of the lower fluid, which is  $\nu_{\text{lower}} = 0.01$  m<sup>2</sup>/s. Find the velocity at the interface and the velocity at the free surface. Plot the velocity distribution.

**Given:** Data on flow of liquids down an incline

**Find:** Velocity at interface; velocity at free surface; plot

**Solution:**

Given data       $h = 10\text{-mm}$        $\theta = 60\text{-deg}$        $\nu_1 = 0.01 \cdot \frac{\text{m}^2}{\text{s}}$        $\nu_2 = \frac{\nu_1}{5}$        $\nu_2 = 2 \times 10^{-3} \frac{\text{m}^2}{\text{s}}$

(The lower fluid is designated fluid 1, the upper fluid 2)

From Example 5.9 (or Exanple 8.3 with  $g$  replaced with  $g\sin\theta$ ), a free body analysis leads to (for either fluid)

$$\frac{d^2}{dy^2}u = -\frac{\rho \cdot g \cdot \sin(\theta)}{\mu}$$

Applying this to fluid 1 (lower fluid) and fluid 2 (upper fluid), integrating twice yields

$$u_1 = -\frac{\rho \cdot g \cdot \sin(\theta)}{2 \cdot \mu_1} \cdot y^2 + c_1 \cdot y + c_2 \quad u_2 = -\frac{\rho \cdot g \cdot \sin(\theta)}{2 \cdot \mu_2} \cdot y^2 + c_3 \cdot y + c_4$$

We need four BCs. Two are obvious

$$y = 0 \quad u_1 = 0 \quad (1)$$

$$y = h \quad u_1 = u_2 \quad (2)$$

The third BC comes from the fact that there is no shear stress at the free surface

$$y = 2 \cdot h \quad \mu_2 \cdot \frac{du_2}{dy} = 0 \quad (3)$$

The fourth BC comes from the fact that the stress at the interface generated by each fluid is the same

$$y = h \quad \mu_1 \cdot \frac{du_1}{dy} = \mu_2 \cdot \frac{du_2}{dy} \quad (4)$$

Using these four BCs

$$c_2 = 0$$

$$-\frac{\rho \cdot g \cdot \sin(\theta)}{2 \cdot \mu_1} \cdot h^2 + c_1 \cdot h + c_2 = -\frac{\rho \cdot g \cdot \sin(\theta)}{2 \cdot \mu_2} \cdot h^2 + c_3 \cdot h + c_4$$

$$-\rho \cdot g \cdot \sin(\theta) \cdot 2 \cdot h + \mu_2 \cdot c_3 = 0 \quad -\rho \cdot g \cdot \sin(\theta) \cdot h + \mu_1 \cdot c_1 = -\rho \cdot g \cdot \sin(\theta) \cdot h + \mu_2 \cdot c_3$$

Hence, after some algebra       $c_1 = \frac{2 \cdot \rho \cdot g \cdot \sin(\theta) \cdot h}{\mu_1}$        $c_2 = 0$        $c_3 = \frac{2 \cdot \rho \cdot g \cdot \sin(\theta) \cdot h}{\mu_2}$        $c_4 = 3 \cdot \rho \cdot g \cdot \sin(\theta) \cdot h^2 \cdot \frac{(\mu_2 - \mu_1)}{2 \cdot \mu_1 \cdot \mu_2}$

The velocity distributions are then

$$u_1 = \frac{\rho \cdot g \cdot \sin(\theta)}{2 \cdot \mu_1} \cdot (4 \cdot y \cdot h - y^2) \quad u_2 = \frac{\rho \cdot g \cdot \sin(\theta)}{2 \cdot \mu_2} \cdot \left[ 3 \cdot h^2 \cdot \frac{(\mu_2 - \mu_1)}{\mu_1} + 4 \cdot y \cdot h - y^2 \right]$$

Rewriting in terms of  $\nu_1$  and  $\nu_2$  ( $\rho$  is constant and equal for both fluids)

$$u_1 = \frac{g \cdot \sin(\theta)}{2 \cdot \nu_1} \cdot (4 \cdot y \cdot h - y^2) \quad u_2 = \frac{g \cdot \sin(\theta)}{2 \cdot \nu_2} \cdot \left[ 3 \cdot h^2 \cdot \frac{(\nu_2 - \nu_1)}{\nu_1} + 4 \cdot y \cdot h - y^2 \right]$$

(Note that these result in the same expression if  $\nu_1 = \nu_2$ , i.e., if we have one fluid)

Evaluating either velocity at  $y = h$ , gives the velocity at the interface

$$u_{\text{interface}} = \frac{3 \cdot g \cdot h^2 \cdot \sin(\theta)}{2 \cdot \nu_1} \quad u_{\text{interface}} = 0.127 \frac{\text{m}}{\text{s}}$$


Evaluating  $u_2$  at  $y = 2h$  gives the velocity at the free surface

$$u_{\text{freesurface}} = g \cdot h^2 \cdot \sin(\theta) \cdot \frac{(3 \cdot \nu_2 + \nu_1)}{2 \cdot \nu_1 \cdot \nu_2} \quad u_{\text{freesurface}} = 0.340 \frac{\text{m}}{\text{s}}$$

Note that a Reynolds number based on the free surface velocity is  $\frac{u_{\text{freesurface}} \cdot h}{\nu_2} = 1.70$  indicating laminar flow

The velocity distributions can be plotted in *Excel*.


y (mm)	$u_1$ (m/s)	$u_2$ (m/s)
0.000	0.000	
1.000	0.0166	
2.000	0.0323	
3.000	0.0472	
4.000	0.061	
5.000	0.074	
6.000	0.087	
7.000	0.098	
8.000	0.109	
9.000	0.119	
10.000	0.127	0.127
11.000		0.168
12.000		0.204
13.000		0.236
14.000		0.263
15.000		0.287
16.000		0.306
17.000		0.321
18.000		0.331
19.000		0.338
20.000		0.340



## Problem 8.31

[Difficulty: 2]

**8.31** The velocity distribution for flow of a thin viscous film down an inclined plane surface was developed in Example 5.9. Consider a film 7 mm thick, of liquid with SG = 1.2 and dynamic viscosity of 1.60 N·s/m<sup>2</sup>. Derive an expression for the shear stress distribution within the film and indicate its direction. Evaluate the volume flow rate in the film, in mm<sup>3</sup>/s per millimeter of surface width. Calculate the film Reynolds number based on average velocity.



**Given:** Velocity distribution on incline

**Find:** Expression for shear stress; Maximum shear; volume flow rate/mm width; Reynolds number

**Solution:**

From Example 5.9

$$u(y) = \frac{\rho \cdot g \cdot \sin(\theta)}{\mu} \cdot \left( h \cdot y - \frac{y^2}{2} \right)$$

For the shear stress

$$\tau = \mu \cdot \frac{du}{dy} = \rho \cdot g \cdot \sin(\theta) \cdot (h - y)$$

$\tau$  is a maximum at  $y = 0$

$$\tau_{\max} = \rho \cdot g \cdot \sin(\theta) \cdot h = SG \cdot \rho_{H_2O} \cdot g \cdot \sin(\theta) \cdot h$$

$$\tau_{\max} = 1.2 \times 1000 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \sin(15 \cdot \text{deg}) \times 0.007 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \tau_{\max} = 21.3 \text{ Pa}$$

This stress is in the x direction on the wall

The flow rate is

$$Q = \int u \, dA = w \cdot \int_0^h u(y) \, dy = w \cdot \int_0^h \frac{\rho \cdot g \cdot \sin(\theta)}{\mu} \cdot \left( h \cdot y - \frac{y^2}{2} \right) dy \quad Q = \frac{\rho \cdot g \cdot \sin(\theta) \cdot w \cdot h^3}{3 \cdot \mu}$$

$$\frac{Q}{w} = \frac{1}{3} \times 1.2 \times 1000 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \sin(15 \cdot \text{deg}) \times (0.007 \cdot \text{m})^3 \times \frac{\text{m}^2}{1.60 \cdot \text{N} \cdot \text{s}} \cdot \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 2.18 \times 10^{-4} \frac{\text{m}^3}{\text{m}} \quad \frac{Q}{w} = 217 \frac{\text{mm}^3}{\text{mm}}$$

The average velocity is

$$V = \frac{Q}{A} = \frac{Q}{w \cdot h} \quad V = 217 \cdot \frac{\frac{\text{mm}^3}{\text{mm}}}{\text{mm}} \times \frac{1}{7 \cdot \text{mm}} \quad V = 31.0 \cdot \frac{\text{mm}}{\text{s}}$$

The gap Reynolds number is

$$Re = \frac{\rho \cdot V \cdot h}{\mu}$$

$$Re = 1.2 \times 1000 \frac{\text{kg}}{\text{m}^3} \times 31 \cdot \frac{\text{mm}}{\text{s}} \times 7 \cdot \text{mm} \times \frac{\text{m}^2}{1.60 \cdot \text{N} \cdot \text{s}} \times \left( \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \right)^2 \quad Re = 0.163$$

The flow is definitely laminar

## Problem 8.32

[Difficulty: 3]

**8.32** Consider fully developed flow between parallel plates with the upper plate moving at  $U = 5$  ft/s; the spacing between the plates is  $a = 0.1$  in. Determine the flow rate per unit depth for the case of zero pressure gradient. If the fluid is air, evaluate the shear stress on the lower plate and plot the shear stress distribution across the channel for the zero

pressure gradient case. Will the flow rate increase or decrease if the pressure gradient is adverse? Determine the pressure gradient that will give zero shear stress at  $y = 0.25a$ . Plot the shear stress distribution across the channel for the latter case.

**Given:** Flow between parallel plates

**Find:** Shear stress on lower plate; Plot shear stress; Flow rate for pressure gradient; Pressure gradient for zero shear; Plot

**Solution:**

From Section 8-2 
$$u(y) = \frac{U \cdot y}{a} + \frac{a^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{a} \right)^2 - \frac{y}{a} \right]$$

For  $dp/dx = 0$  
$$u = U \cdot \frac{y}{a} \quad \frac{Q}{1} = \int_0^a u(y) dy = w \cdot \int_0^a U \cdot \frac{y}{a} dy = \frac{U \cdot a}{2} \quad Q = \frac{1}{2} \times 5 \cdot \frac{\text{ft}}{\text{s}} \times \frac{0.1}{12} \cdot \text{ft} \quad Q = 0.0208 \cdot \frac{\text{ft}^3}{\text{s}}$$

For the shear stress 
$$\tau = \mu \cdot \frac{du}{dy} = \frac{\mu \cdot U}{a} \quad \text{when } dp/dx = 0 \quad \mu = 3.79 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \quad (\text{Table A.9})$$

The shear stress is constant - no need to plot!


$$\tau = 3.79 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \times 5 \cdot \frac{\text{ft}}{\text{s}} \times \frac{12}{0.1 \cdot \text{ft}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \quad \tau = 1.58 \times 10^{-6} \cdot \text{psi}$$

Q will decrease if  $dp/dx > 0$ ; it will increase if  $dp/dx < 0$ .

For non- zero  $dp/dx$ : 
$$\tau = \mu \cdot \frac{du}{dy} = \frac{\mu \cdot U}{a} + a \cdot \frac{dp}{dx} \cdot \left( \frac{y}{a} - \frac{1}{2} \right)$$

At  $y = 0.25a$ , we get 
$$\tau(y = 0.25 \cdot a) = \mu \cdot \frac{U}{a} + a \cdot \frac{dp}{dx} \cdot \left( \frac{1}{4} - \frac{1}{2} \right) = \mu \cdot \frac{U}{a} - \frac{a}{4} \cdot \frac{dp}{dx}$$

Hence this stress is zero when 
$$\frac{dp}{dx} = \frac{4 \cdot \mu \cdot U}{a^2} = 4 \times 3.79 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} \times 5 \cdot \frac{\text{ft}}{\text{s}} \times \left( \frac{12}{0.1 \cdot \text{ft}} \right)^2 = 0.109 \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2} = 7.58 \times 10^{-4} \frac{\text{psi}}{\text{ft}}$$



## Problem 8.33

[Difficulty: 3]

**8.33** Glycerin at 59°F flows between parallel plates with gap width  $b = 0.1$  in. The upper plate moves with speed  $U = 2$  ft/s in the positive  $x$  direction. The pressure gradient is  $\partial p/\partial x = -50$  psi/ft. Locate the point of maximum velocity and determine its magnitude (let  $y=0$  at the bottom plate). Determine the volume of flow (gal/ft) that passes a given cross section ( $x = \text{constant}$ ) in 10 s. Plot the velocity and shear stress distributions.

**Given:** Flow between parallel plates

**Find:** Location and magnitude of maximum velocity; Volume flow in 10 s; Plot velocity and shear stress

**Solution:**

From Section 8.2 
$$u(y) = \frac{U \cdot y}{b} + \frac{b^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{b} \right)^2 - \frac{y}{b} \right]$$

For  $u_{\max}$  set  $du/dx = 0$  
$$\frac{du}{dy} = 0 = \frac{U}{b} + \frac{b^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left( \frac{2 \cdot y}{b^2} - \frac{1}{a} \right) = \frac{U}{b} + \frac{1}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot (2 \cdot y - b)$$

Hence 
$$u = u_{\max} \quad \text{at} \quad y = \frac{b}{2} - \frac{\mu \cdot U}{b \cdot \frac{dp}{dx}}$$

From Fig. A.2 at  $59^\circ\text{F} = 15^\circ\text{C}$  
$$\mu = 4 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \quad \mu = 0.0835 \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$$

$$y = \frac{0.1 \cdot \text{in}}{2} + 0.0835 \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \times 2 \cdot \frac{\text{ft}}{\text{s}} \times \frac{1}{0.1 \cdot \text{in}} \times \frac{\text{in}^2 \cdot \text{ft}}{50 \cdot \text{lbf}} \quad y = 0.0834 \cdot \text{in}$$

Hence 
$$u_{\max} = \frac{U \cdot y}{b} + \frac{b^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{b} \right)^2 - \frac{y}{b} \right] \quad \text{with} \quad y = 0.0834 \cdot \text{in}$$

$$u_{\max} = 2 \cdot \frac{\text{ft}}{\text{s}} \times \left( \frac{.0834}{0.1} \right) + \frac{1}{2} \times \left( \frac{0.1}{12} \cdot \text{ft} \right)^2 \times \frac{\text{ft}^2}{.0835 \cdot \text{lbf} \cdot \text{s}} \times \left( -\frac{50 \cdot \text{psi}}{\text{ft}} \right) \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \times \left[ \left( \frac{.0834}{0.1} \right)^2 - \left( \frac{.0834}{0.1} \right) \right]$$

$$u_{\max} = 2.083 \cdot \frac{\text{ft}}{\text{s}}$$

$$\frac{Q}{w} = \int_0^b u(y) dy = w \cdot \int_0^b \left[ \frac{U \cdot y}{b} + \frac{b^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{b} \right)^2 - \frac{y}{b} \right] \right] dy = \frac{U \cdot b}{2} - \frac{b^3}{12 \cdot \mu} \cdot \frac{dp}{dx}$$

$$\frac{Q}{w} = \frac{1}{2} \times 2 \cdot \frac{\text{ft}}{\text{s}} \times \frac{0.1}{12} \cdot \text{ft} - \frac{1}{12} \times \left( \frac{0.1}{12} \cdot \text{ft} \right)^3 \times \frac{\text{ft}^2}{.0835 \cdot \text{lbf} \cdot \text{s}} \times \left( -\frac{50 \cdot \text{psi}}{\text{ft}} \right) \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2$$

$$\frac{Q}{w} = 0.0125 \cdot \frac{\text{ft}^3}{\text{s}} \quad \frac{Q}{w} = 5.61 \cdot \frac{\text{gpm}}{\text{ft}}$$



$$\text{Flow} = \frac{Q}{w} \cdot \Delta t = 5.61 \cdot \frac{\text{gpm}}{\text{ft}} \times \frac{1 \cdot \text{min}}{60 \cdot \text{s}} \times 10 \cdot \text{s}$$

$$\text{Flow} = 0.935 \cdot \frac{\text{gal}}{\text{ft}}$$

The velocity profile is 
$$\frac{u}{U} = \frac{y}{b} + \frac{b^2}{2 \cdot \mu \cdot U} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{b} \right)^2 - \frac{y}{b} \right]$$

For the shear stress 
$$\tau = \mu \cdot \frac{du}{dy} = \mu \cdot \frac{U}{b} + \frac{b}{2} \cdot \frac{dp}{dx} \cdot \left[ 2 \cdot \left( \frac{y}{b} \right) - 1 \right]$$

The graphs below can be plotted in *Excel*



## Problem 8.34

[Difficulty: 3]

**8.34** The velocity profile for fully developed flow of castor oil at 20°C between parallel plates with the upper plate moving is given by Eq. 8.8. Assume  $U = 1.5$  m/s and  $a = 5$  mm. Find the pressure gradient for which there is no net flow in the  $x$  direction. Plot the expected velocity distribution and the expected shear stress distribution across the channel for this flow. For the case where  $u = \frac{1}{2}U$  at  $y/a = 0.5$ , plot the expected velocity distribution and shear stress distribution across the channel. Comment on features of the plots.

**Given:** Flow between parallel plates

**Find:** Pressure gradient for no flow; plot velocity and stress distributions; also plot for  $u = U$  at  $y = a/2$



**Solution:**

Basic equations 
$$u(y) = \frac{U \cdot y}{a} + \frac{a^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{a} \right)^2 - \frac{y}{a} \right] \quad (1) \quad \frac{Q}{l} = \frac{U \cdot a}{2} - \frac{a^3}{12 \cdot \mu} \cdot \frac{dp}{dx} \quad (2) \quad \tau = \mu \cdot \frac{U}{a} + a \cdot \frac{dp}{dx} \cdot \left( \frac{y}{a} - \frac{1}{2} \right) \quad (3)$$

Available data 
$$U = 1.5 \cdot \frac{\text{m}}{\text{s}} \quad a = 5 \cdot \text{mm} \quad \text{From Fig. A.2 for castor oil at } 20^\circ\text{C} \quad \mu = 1 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$$

From Eq 2 for  $Q = 0$  
$$\frac{dp}{dx} = \frac{6 \cdot \mu \cdot U}{a^2} = 6 \times 1 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times 1.5 \cdot \frac{\text{m}}{\text{s}} \times \frac{1}{(0.005 \cdot \text{m})^2} \quad \frac{dp}{dx} = 360 \cdot \frac{\text{kPa}}{\text{m}}$$

The graphs below, using Eqs. 1 and 3, can be plotted in *Excel*





The pressure gradient is adverse, to counteract the flow generated by the upper plate motion

For  $u = U$  at  $y = a/2$  we need to adjust the pressure gradient. From Eq. 1  $u(y) = \frac{U \cdot y}{a} + \frac{a^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{a} \right)^2 - \frac{y}{a} \right]$

Hence 
$$U = \frac{U \cdot \frac{a}{2}}{a} + \frac{a^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{\frac{a}{2}}{a} \right)^2 - \frac{\frac{a}{2}}{a} \right] \quad \text{or} \quad \frac{dp}{dx} = -\frac{4 \cdot U \cdot \mu}{a^2} = -4 \times 1 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times 1.5 \cdot \frac{\text{m}}{\text{s}} \times \frac{1}{(0.005 \cdot \text{m})^2}$$

$$\frac{dp}{dx} = -240 \cdot \frac{\text{kPa}}{\text{m}}$$



The pressure gradient is positive to provide the "bulge" needed to satisfy the velocity requirement

## Problem 8.35

[Difficulty: 3]

**8.35** The velocity profile for fully developed flow of carbon tetrachloride at 68°F between parallel plates (gap  $a = 0.05$  in.), with the upper plate moving, is given by Eq. 8.8. Assuming a volume flow rate per unit depth is 1.5 gpm/ft for zero pressure gradient, find  $U$ . Evaluate the shear stress on the lower plate. Would the volume flow rate increase or decrease with a mild adverse pressure gradient? Calculate the pressure gradient that will give zero shear stress at  $y/a = 0.25$ . Plot the velocity distribution and the shear stress distribution for this case.

**Given:** Flow between parallel plates

**Find:** Shear stress on lower plate; pressure gradient for zero shear stress at  $y/a = 0.25$ ; plot velocity and shear stress

**Solution:**

Basic equations 
$$u(y) = \frac{U \cdot y}{a} + \frac{a^2}{2 \cdot \mu} \cdot \frac{dp}{dx} \cdot \left[ \left( \frac{y}{a} \right)^2 - \frac{y}{a} \right] \quad (1) \quad \frac{Q}{l} = \frac{U \cdot a}{2} - \frac{a^3}{12 \cdot \mu} \cdot \frac{dp}{dx} \quad (2) \quad \tau = \mu \cdot \frac{U}{a} + a \cdot \frac{dp}{dx} \cdot \left( \frac{y}{a} - \frac{1}{2} \right) \quad (3)$$

Available data 
$$q = 1.5 \cdot \frac{\text{gpm}}{\text{ft}} \quad a = 0.05 \cdot \text{in} \quad 68^\circ\text{F} = 20^\circ\text{C}$$



From Fig. A.2, Carbon tetrachloride at 20°C 
$$\mu = 0.001 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \quad \mu = 2.089 \times 10^{-5} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2}$$

From Eq. 2, for zero pressure gradient 
$$U = \frac{2 \cdot Q}{a \cdot l} \quad \text{or} \quad U = \frac{2 \cdot q}{a} \quad U = 1.60 \cdot \frac{\text{ft}}{\text{s}}$$

From Eq. 3, when  $y = 0$ , with  $U = 1.60 \cdot \frac{\text{ft}}{\text{s}}$  
$$\tau_{yx} = \frac{\mu \cdot U}{a} \quad \tau_{yx} = 5.58 \times 10^{-5} \cdot \text{psi}$$

A mild adverse pressure gradient would reduce the flow rate.

For zero shear stress at  $y/a = 0.25$ , from Eq. 3 
$$0 = \mu \cdot \frac{U}{a} + a \cdot \frac{dp}{dx} \cdot \left( \frac{1}{4} - \frac{1}{2} \right) \quad \text{or} \quad \frac{dp}{dx} = \frac{4 \cdot \mu \cdot U}{a^2} \quad \frac{dp}{dx} = 0.0536 \cdot \frac{\text{psi}}{\text{ft}}$$



Note that the location of zero shear is also where  $u$  is maximum!

## Problem 8.36

[Difficulty: 3]

**8.36** Free-surface waves begin to form on a laminar liquid film flowing down an inclined surface whenever the Reynolds number, based on mass flow per unit width of film, is larger than about 33. Estimate the maximum thickness of a laminar film of water that remains free from waves while flowing down a vertical surface.

**Solution:** The mass flow rate is  $\dot{m} = \rho \bar{v} A = \rho \bar{v} w \delta$ , so  $\dot{m}/w = \rho \bar{v} \delta$ .

Thus

$$Re = \frac{\rho \bar{v} \delta}{\mu} = \frac{\bar{v} \delta}{\nu} = 33 \text{ (maximum)}$$

Using the result for average velocity from Example 8.3

$$\bar{v} = \frac{\rho g \delta^2}{3\mu}$$

Thus

$$\frac{\rho \bar{v} \delta}{\mu} = \frac{\rho^2 g \delta^3}{3\mu^2} = 33$$

Solving for  $\delta$ ,

$$\delta = \left[ \frac{99\mu^2}{\rho^2 g} \right]^{1/3}$$

At  $T = 20^\circ\text{C}$ ,  $\mu = 1.00 \times 10^{-3} \text{ kg/m}\cdot\text{s}$  and  $\rho = 998 \text{ kg/m}^3$  (Table A.8). Substituting,

$$\delta = \left[ 99 \times (1.00 \times 10^{-3})^2 \frac{\text{kg}^2}{\text{m}^2 \cdot \text{s}^2} \times \frac{\text{m}^6}{(998)^2 \text{ kg}^2} \times \frac{\text{s}^2}{9.81 \text{ m}} \right]^{1/3}$$

$$\delta = 2.16 \times 10^{-4} \text{ m} \text{ or } 0.216 \text{ mm}$$

$\delta_{\text{max}}$



# Problem 8.37

[Difficulty: 3]


**8.37** Microchips are supported on a thin air film on a smooth horizontal surface during one stage of the manufacturing process. The chips are 11.7 mm long and 9.35 mm wide and have a mass of 0.325 g. The air film is 0.125 mm thick. The initial speed of a chip is  $V_0 = 1.75$  mm/s; the chip slows as the result of viscous shear in the air film. Analyze the chip

motion during deceleration to develop a differential equation for chip speed  $V$  versus time  $t$ . Calculate the time required for a chip to lose 5 percent of its initial speed. Plot the variation of chip speed versus time during deceleration. Explain why it looks as you have plotted it.

Solution: Apply Newton's law of viscosity

Basic equations:  $\tau_{yx} = \mu \frac{du}{dy}$

$F_V = \tau A$        $\Sigma F = ma_x$



Assume: (1) Newtonian fluid (2) Linear velocity profile in narrow gap (3) Air at STP

Then

$\tau_{yx} = \mu \frac{du}{dy} = \mu \frac{V}{h}$ ;  $F_V = \tau A = \mu \frac{V}{h} wL = \frac{\mu V w L}{h}$

The free-body diagram for the chip is



$\Sigma F_x = -F_V = -\frac{\mu V w L}{h} = m \frac{dV}{dt}$  ;  $\frac{dV}{V} = -\frac{\mu w L}{mh} dt$

Integrating,  $\int_{V_0}^V \frac{dV}{V} = \frac{\mu w L}{mh} \int_0^t dt = -\frac{\mu w L}{mh} t$


Thus

$t = -\frac{mh}{\mu w L} \ln \frac{V}{V_0}$

$t = -0.325 \text{ g} \times 0.125 \text{ mm} \times \frac{\text{m} \cdot \text{s}}{1.79 \times 10^{-5} \text{ kg}} \times \frac{1}{9.35 \text{ mm}} \times \frac{1}{11.7 \text{ mm}} \times \ln 0.95 \times \frac{\text{kg}}{1000 \text{ g}} \times \frac{1000 \text{ mm}}{\text{m}}$

$t = 1.06 \text{ s}$


From Excel, the plot of speed vs. time is:



### Problem 8.38

[Difficulty: 5]


**8.38** A viscous-shear pump is made from a stationary housing with a close-fitting rotating drum inside. The clearance is small compared with the diameter of the drum, so flow in the annular space may be treated as flow between parallel plates. Fluid is dragged around the annulus by viscous forces. Evaluate the performance characteristics of the shear pump (pressure differential, input power, and efficiency) as functions of volume flow rate. Assume that the depth normal to the diagram is  $b$ .



Solution: Since  $a \ll R$ , unwrap to form flow between parallel plates.  
Apply Eqs. 8.9 to fully developed flow:

$$\text{Volume flow rate is } \frac{Q}{b} = \frac{Ua}{2} - \frac{1}{12\mu} \left( \frac{\partial p}{\partial x} \right) a^3$$

Substituting  $U = R\omega$  and  $\frac{\partial p}{\partial x} = \frac{\Delta p}{L}$ , then



$$\Delta p = \frac{12\mu L}{a^3} \left( \frac{WRa}{2} - \frac{Q}{b} \right) = \frac{6\mu L R \omega}{a^2} \left( 1 - \frac{2Q}{abR\omega} \right)$$

Torque is  $T = \tau R(bL) = RLb\tau$ . Power is  $P = T\omega$ . From Eq. 8.9a, at  $y=a$ ,

$$P = RLb\omega \left[ \frac{\mu R\omega}{a} + \frac{\Delta p}{L} \frac{a}{2} \right] = RLb\omega \left[ \frac{\mu R\omega}{a} + \frac{6\mu L R \omega}{a^2} \left( 1 - \frac{2Q}{abR\omega} \right) \frac{a}{2L} \right]$$

$$P = RLb\omega \left[ \frac{\mu R\omega}{a} \left( 4 - \frac{6Q}{abR\omega} \right) \right] = \frac{\mu L b (R\omega)^2}{a} \left( 4 - \frac{6Q}{abR\omega} \right)$$

Output power is  $Q\Delta p$ , so efficiency is


$$\eta = \frac{Q\Delta p}{P} = \frac{6\mu Q L R \omega}{a^3} \left( 1 - \frac{2Q}{abR\omega} \right) \frac{a}{\mu L b (R\omega)^2} \frac{1}{\left( 4 - \frac{6Q}{abR\omega} \right)}$$

$$\eta = \frac{6Q}{abR\omega} \frac{\left( 1 - \frac{2Q}{abR\omega} \right)}{\left( 4 - \frac{6Q}{abR\omega} \right)}$$

### Problem 8.39

[Difficulty: 5]


**8.39** The clamping force to hold a part in a metal-turning operation is provided by high-pressure oil supplied by a pump. Oil leaks axially through an annular gap with diameter  $D$ , length  $L$ , and radial clearance  $a$ . The inner member of the annulus rotates at angular speed  $\omega$ . Power is required both to pump the oil and to overcome viscous dissipation in the annular gap. Develop expressions in terms of the specified geometry for the pump power,  $\mathcal{P}_p$ , and the viscous dissipation power,  $\mathcal{P}_v$ . Show that the total power requirement is minimized when the radial clearance,  $a$ , is chosen such that  $\mathcal{P}_v = 3\mathcal{P}_p$ .



Solution: Apply Eqs. 8.6 and 8.9 for flow between parallel plates.

Assumptions: (1)  $a \ll D$ , so unfold to flat plates

(2) No pressure gradient circumferentially



The viscous power is the product of viscous torque times  $\omega$ :

$$P_v = T\omega = \tau(2\pi RL)R\omega = \mu \frac{V}{a} (2\pi \frac{D}{2} L) \frac{D}{2} \omega = \mu \frac{\omega D}{2a} \pi D L \frac{D}{2} \omega = \frac{\pi \mu \omega^2 D^3 L}{4a} \quad P_v$$

The pump power is the product of flow rate times pressure drop.

$$P_p = Q \Delta p$$

From Eq. 8.6c,  $Q = \frac{la^3 \Delta p}{12\mu L} = \frac{\pi D a^3 \Delta p}{12\mu L}$ , so  $P_p = \frac{\pi D a^3 \Delta p^2}{12\mu L} \quad P_p$

The total power required is  $P_T = P_v + P_p = \frac{\pi \mu \omega^2 D^3 L}{4a} + \frac{\pi D a^3 \Delta p^2}{12\mu L}$

It may be minimized by setting  $\frac{dP_T}{da} = 0$ . Thus

$$\frac{dP_T}{da} = -\frac{\pi \mu \omega^2 D^3 L}{4a^2} + \frac{\pi D a^2 \Delta p^2}{4\mu L} = 0 \quad (1)$$

This can be written

$$\frac{dP_T}{da} = -\frac{1}{a} P_v + \frac{3}{a} P_p = 0$$

which is satisfied when  $3P_p - P_v = 0$  or  $P_v = 3P_p$  Optimum

Equation 1 also can be solved for  $a$  at optimum conditions:

$$a^4 = \frac{\mu^2 \omega^2 D^2 L^2}{\Delta p^2} \quad \text{or} \quad a^2 = \frac{\mu \omega D L}{\Delta p} \quad \text{or} \quad \frac{a}{D} = \sqrt{\frac{\mu \omega L}{D \Delta p}} \quad (\text{optimum})$$


## Problem 8.40

[Difficulty: 2]

**8.40** The efficiency of the viscous-shear pump of Fig. P8.39 is given by

$$\eta = 6q \frac{(1 - 2q)}{(4 - 6q)}$$

where  $q = Q/abR\omega$  is a dimensionless flow rate ( $Q$  is the flow rate at pressure differential  $\Delta p$ , and  $b$  is the depth normal to the diagram). Plot the efficiency versus dimensionless flow rate, and find the flow rate for maximum efficiency. Explain why the efficiency peaks, and why it is zero at certain values of  $q$ .




**Given:** Expression for efficiency

**Find:** Plot; find flow rate for maximum efficiency; explain curve

**Solution:**

$q$	$\eta$
0.00	0.0%
0.05	7.30%
0.10	14.1%
0.15	20.3%
0.20	25.7%
0.25	30.0%
0.30	32.7%
0.35	33.2%
0.40	30.0%
0.45	20.8%
0.50	0.0%



For the maximum efficiency point we can use *Solver* (or alternatively differentiate)

$q$	$\eta$
0.333	33.3%

The efficiency is zero at zero flow rate because there is no output at all  
 The efficiency is zero at maximum flow rate  $\Delta p = 0$  so there is no output  
 The efficiency must therefore peak somewhere between these extremes

# Problem 8.41

[Difficulty: 5]

8.41 Automotive design is tending toward all-wheel drive to improve vehicle performance and safety when traction is poor. An all-wheel drive vehicle must have an interaxle differential to allow operation on dry roads. Numerous vehicles are being built using multiplate viscous drives for interaxle differentials. Perform the analysis and design needed to define the torque transmitted by the differential

for a given speed difference, in terms of the design parameters. Identify suitable dimensions for a viscous differential to transmit a torque of 150 N·m at a speed loss of 125 rpm, using lubricant with the properties of SAE 30 oil. Discuss how to find the minimum material cost for the viscous differential, if the plate cost per square meter is constant.

**Solution:** From Problem 2.66;  $dT = r dF = r \tau dA$

But  $\tau = \mu \frac{du}{dy} = \mu \frac{u}{h} = \mu r \frac{\Delta \omega}{h}$ ;  $dA = 2\pi r dr$

Thus  $dT = r \mu \frac{r \Delta \omega}{h} 2\pi r dr = \frac{2\pi \mu \Delta \omega}{h} r^3 dr$ ;  $T = \frac{\pi \mu \Delta \omega}{2h} [R_o^4 - R_i^4]$

or  $T = \frac{\pi \mu \Delta \omega}{2h} R^4 (1 - \alpha^4)$  where  $\alpha = R_i/R$

This value is per gap. Each rotor has 2 gaps to a housing. For  $n$  gaps

$$T_n = \frac{n \pi \mu \Delta \omega}{2h} R^4 (1 - \alpha^4) \tag{1}$$

From Eq. 1, assuming  $\mu = 0.18 \text{ kg/m}\cdot\text{s}$  (Fig. A.2) and  $\alpha = \frac{1}{2}$ , so  $1 - \alpha^4 = 1 - \frac{1}{16} \approx 1$ , then

$$\frac{n R^4}{h} = \frac{2 T_n}{\pi \mu \Delta \omega} = \frac{2 \times 150 \text{ N}\cdot\text{m}}{\pi \times 0.18 \text{ N}\cdot\text{s}} \times \frac{\text{m}^2}{125 \text{ rev}} \times \frac{\text{min}}{2\pi \text{ rad}} \times \frac{60 \text{ s}}{\text{min}} = 40.5 \text{ m}^3 = C$$


or

$$R^4 = C \frac{h}{n}$$

For  $n = 100$  and  $h = 0.2 \text{ mm}$ ,  $R^4 = 40.5 \text{ m}^3 \times 0.0002 \text{ m} \times \frac{1}{100} = 8.11 \times 10^{-5} \text{ m}^4$

$$R = [8.11 \times 10^{-5}]^{1/4} \text{ m} = 0.0949 \text{ m} \text{ (or } D = 190 \text{ mm)}$$

The stack length might be



$\approx 2.5 \text{ mm}$  for  $n = 2$ , or  $125 \text{ mm}$  for  $n = 100$

### Problem 8.42

[Difficulty: 5] Part 1/2

**8.42** An inventor proposes to make a "viscous timer" by placing a weighted cylinder inside a slightly larger cylinder containing viscous liquid, creating a narrow annular gap close to the wall. Analyze the flow field created when the apparatus is inverted and the mass begins to fall under gravity. Would this system make a satisfactory timer? If so, for what range of time intervals? What would be the effect of a temperature change on measured time?

Solution: Apply conservation of mass to a CV enclosing the cylinder and the moving mass:

$$\text{Then: } Q = U \frac{\pi D^2}{4} = \bar{v} \pi D a = \bar{v} l a \quad (1)$$

- Assume: (1) Gap is narrow,  $a \ll D$   
 (2) Unroll gap so flat,  $l = \pi D$   
 (3) Steady flow  
 (4) Fully developed laminar flow

Under these assumptions, the flow field in the gap is that for flow between parallel plates with one plate moving.

Place coordinates on the moving mass:

Then the volume flow rate (Eq. 8.9b) is

$$\frac{Q}{l} = \frac{Q}{\pi D} = \frac{U a}{2} - \frac{1}{12\mu} \left( \frac{\partial p}{\partial x} \right) a^3$$

But  $\frac{\partial p}{\partial x} = -\frac{\Delta p_v}{L}$ , where  $\Delta p_v$  is the pressure drop driving viscous flow, so

$$\frac{Q}{l} = \frac{U a}{2} - \frac{1}{12\mu} \left( -\frac{\Delta p_v}{L} \right) a^3 = \frac{U a}{2} + \frac{\Delta p_v a^3}{12\mu L} \quad (2)$$

The pressure change across the moving mass is

$$\Delta p = \rho_l g L + \Delta p_v \quad (3)$$

Summing forces on the moving mass gives


$$\sum F_x = \Delta p \frac{\pi D^2}{4} - mg + F_v = m \frac{dU}{dt} \stackrel{=0(3)}{\quad}$$

But  $mg = \rho_m \frac{\pi D^2}{4} L$  and  $F_v = \tau_s \pi D L$



From Eq. 8.9a,  $\tau_s = \mu \frac{U}{a} - \frac{a}{2} \left( \frac{\partial p}{\partial x} \right) = \mu \frac{U}{a} + \frac{a}{2} \frac{\Delta p_v}{L}$

Substituting,  $\Delta p \frac{\pi D^2}{4} - \rho_m \frac{\pi D^2}{4} L g + \left[ \mu \frac{U}{a} + \frac{a}{2} \frac{\Delta p_v}{L} \right] \pi D L = 0$

$$\text{or } \Delta p = \rho_m g L - \left[ \mu \frac{U}{a} + \frac{a}{2} \frac{\Delta p_v}{L} \right] \frac{4L}{D} \quad (4)$$



Flow Field



## Problem 8.42

[Difficulty: 5] Part 2/2

Combining Eqs. 1 and 2 gives  $\frac{UD}{4} = \frac{U_0 a}{2} + \frac{\Delta p_v a^3}{12\mu L}$

Thus

$$\Delta p_v = \frac{12\mu L}{a^3} \left[ \frac{UD}{4} - \frac{U_0 a}{2} \right] = \frac{3\mu U L D}{a^3} \quad (5)$$

Combining Eqs. 3 and 4 gives  $\Delta p = \rho_l g L + \Delta p_v = \rho_m g L - \left[ \mu \frac{U}{a} + \frac{a}{2} \frac{\Delta p_v}{L} \right] \frac{4L}{D}$

Using Eq. 5,

$$\rho_l g L + \frac{3\mu U L D}{a^3} = \rho_m g L - \mu \frac{U}{a} \frac{4L}{D} - \frac{a}{2} \frac{3\mu U L D}{L a^3} \frac{4L}{D}$$

Simplifying and re-arranging,

$$(\rho_m - \rho_l) g L = \frac{3\mu U L D}{a^3} + \frac{4\mu U L}{a D} + \frac{6\mu U L}{a^2} \approx \frac{3\mu U L D}{a^3}$$

Finally, using  $\rho = SG \rho_{H_2O}$ ,

$$U = \frac{(SG_m - SG_l) \rho_{H_2O} g a^3}{3\mu D}$$

The time interval for the mass to move distance  $H$  is

$$\Delta t = \frac{H}{U} = \frac{3\mu D}{(SG_m - SG_l) \rho_{H_2O} g a^3} \quad (6)$$

Equation 6 shows that the time interval for the mass to fall any distance  $H$  is proportional to liquid viscosity  $\mu$  and inversely proportional to gap width  $a$  cubed. A temperature change would affect the diameter of the measuring tube and the diameter of the falling mass. A temperature change also would affect the viscosity of the liquid in the tube.

Speed of the falling mass is proportional to the cube of gap width. If the coefficient of thermal expansion of the falling mass were greater than that of the glass measuring tube (which seems likely), then the width of the annular gap would decrease with increasing temperature. This would tend to slow the falling mass. The total amount of thermal expansion would depend on the diameter of the mass and tube. The effect on gap width would be greater, the larger the tube diameter compared to the initial gap width.

It might be possible to "tailor" the thermal expansion coefficient of the cylinder, by using a suitable material, to closely match that of the falling mass. Then there would be no differential thermal expansion between the mass and tube, and changes in temperature would not affect the gap width.

Speed of the falling mass is inversely proportional to liquid viscosity. Liquid viscosity decreases sharply as temperature increases (the viscosity of SAE 30 oil drops more than 10 percent as its temperature increases from 20°C to 25°C, see Fig. A.2). This would tend to increase the speed of the falling mass.

The entire device could be maintained at constant temperature.

## Problem 8.43

[Difficulty: 3]

**8.43** A journal bearing consists of a shaft of diameter  $D = 35$  mm and length  $L = 50$  mm (moment of inertia  $I = 0.125 \text{ kg} \cdot \text{m}^2$ ) installed symmetrically in a stationary housing such that the annular gap is  $\delta = 1$  mm. The fluid in the gap has viscosity  $\mu = 0.1 \text{ N} \cdot \text{s}/\text{m}^2$ . If the shaft is given an initial angular velocity of  $\omega = 500$  rpm, determine the time for the shaft to slow to 100 rpm. On another day, an unknown fluid is tested in the same way, but takes 10 minutes to slow from 500 to 100 rpm. What is its viscosity?

**Given:** Data on a journal bearing

**Find:** Time for the bearing to slow to 100 rpm; viscosity of new fluid

**Solution:**

The given data is

$D = 35 \cdot \text{mm}$	$L = 50 \cdot \text{mm}$	$\delta = 1 \cdot \text{mm}$	$I = 0.125 \cdot \text{kg} \cdot \text{m}^2$
$\omega_i = 500 \cdot \text{rpm}$	$\omega_f = 100 \cdot \text{rpm}$	$\mu = 0.1 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$	

The equation of motion for the slowing bearing is  $I \cdot \alpha = \text{Torque} = -\tau \cdot A \cdot \frac{D}{2}$

where  $\alpha$  is the angular acceleration and  $\tau$  is the viscous stress, and  $A = \pi \cdot D \cdot L$  is the surface area of the bearing

As in Example 8.2 the stress is given by  $\tau = \mu \cdot \frac{U}{\delta} = \frac{\mu \cdot D \cdot \omega}{2 \cdot \delta}$

where  $U$  and  $\omega$  are the instantaneous linear and angular velocities.

Hence  $I \cdot \alpha = I \cdot \frac{d\omega}{dt} = -\frac{\mu \cdot D \cdot \omega}{2 \cdot \delta} \cdot \pi \cdot D \cdot L \cdot \frac{D}{2} = -\frac{\mu \cdot \pi \cdot D^3 \cdot L}{4 \cdot \delta} \cdot \omega$

Separating variables  $\frac{d\omega}{\omega} = -\frac{\mu \cdot \pi \cdot D^3 \cdot L}{4 \cdot \delta \cdot I} \cdot dt$

Integrating and using IC  $\omega = \omega_0$   $\omega(t) = \omega_i \cdot e^{-\frac{\mu \cdot \pi \cdot D^3 \cdot L}{4 \cdot \delta \cdot I} \cdot t}$

The time to slow down to  $\omega_f = 10$  rpm is obtained from solving  $\omega_f = \omega_i \cdot e^{-\frac{\mu \cdot \pi \cdot D^3 \cdot L}{4 \cdot \delta \cdot I} \cdot t}$

so  $t = -\frac{4 \cdot \delta \cdot I}{\mu \cdot \pi \cdot D^3 \cdot L} \cdot \ln\left(\frac{\omega_f}{\omega_i}\right)$  Hence  $t = 1.19 \times 10^3 \text{ s}$   $t = 19.9 \cdot \text{min}$

For the new fluid, the time to slow down is  $t = 10 \cdot \text{min}$

Rearranging the equation  $\mu = -\frac{4 \cdot \delta \cdot I}{\pi \cdot D^3 \cdot L \cdot t} \cdot \ln\left(\frac{\omega_f}{\omega_i}\right)$   $\mu = 0.199 \frac{\text{kg}}{\text{m} \cdot \text{s}}$  It is more viscous as it slows down the rotation in a shorter time

## Problem 8.44

[Difficulty: 2]

**8.44** In Example 8.3 we derived the velocity profile for laminar flow on a vertical wall by using a differential control volume. Instead, following the procedure we used in Example 5.9, derive the velocity profile by starting with the Navier–Stokes equations (Eqs. 5.27). Be sure to state all assumptions.

**Given:** Navier-Stokes Equations

**Find:** Derivation of Example 8.3 result

**Solution:**

The Navier-Stokes equations are (using the coordinates of Example 8.3, so that  $x$  is vertical,  $y$  is horizontal)

$$\frac{\partial v}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad (5.1c)$$

$$\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial p}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right) \quad (5.27a)$$

$$\rho \left( \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) = \rho g_y - \frac{\partial p}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} + \frac{\partial^2 v}{\partial z^2} \right) \quad (5.27b)$$

$$\rho \left( \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) = \rho g_z - \frac{\partial p}{\partial z} + \mu \left( \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} \right) \quad (5.27c)$$

The following assumptions have been applied:

- (1) Steady flow (given).
- (2) Incompressible flow;  $\rho = \text{constant}$ .
- (3) No flow or variation of properties in the  $z$  direction;  $w = 0$  and  $\partial/\partial z = 0$ .
- (4) Fully developed flow, so no properties except possibly pressure  $p$  vary in the  $x$  direction;  $\partial/\partial x = 0$ .
- (5) See analysis below.
- (6) No body force in the  $y$  direction;  $g_y = 0$

Assumption (1) eliminates time variations in any fluid property. Assumption (2) eliminates space variations in density. Assumption (3) states that there is no  $z$  component of velocity and no property variations in the  $z$  direction. All terms in the  $z$  component of the Navier–Stokes equation cancel. After assumption (4) is applied, the continuity equation reduces to  $\partial v/\partial y = 0$ . Assumptions (3) and (4) also indicate that  $\partial v/\partial z = 0$  and  $\partial v/\partial x = 0$ . Therefore  $v$  must be constant. Since  $v$  is zero at the solid surface, then  $v$  must be zero everywhere. The fact that  $v = 0$  reduces the Navier–Stokes equations further, as indicated by (5). Hence for the  $y$  direction

$$\frac{\partial p}{\partial y} = 0$$

which indicates the pressure is a constant across the layer. However, at the free surface  $p = p_{\text{atm}} = \text{constant}$ . Hence we conclude that  $p = \text{constant}$  throughout the fluid, and so

$$\frac{\partial p}{\partial x} = 0$$

In the  $x$  direction, we obtain

$$\mu \frac{\partial^2 u}{\partial y^2} + \rho g = 0$$

Integrating twice

$$u = -\frac{1}{2\mu} \rho g y^2 + \frac{c_1}{\mu} y + c_2$$

To evaluate the constants,  $c_1$  and  $c_2$ , we must apply the boundary conditions. At  $y = 0$ ,  $u = 0$ . Consequently,  $c_2 = 0$ . At  $y = a$ ,  $du/dy = 0$  (we assume air friction is negligible). Hence

$$\tau(y = \delta) = \mu \left. \frac{du}{dy} \right|_{y=\delta} = -\frac{1}{\mu} \rho g \delta + \frac{c_1}{\mu} = 0$$

which gives

$$c_1 = \rho g \delta$$


and finally

$$u = -\frac{1}{2\mu} \rho g y^2 + \frac{\rho g}{\mu} y = \frac{\rho g}{\mu} \delta^2 \left[ \left( \frac{y}{\delta} \right) - \frac{1}{2} \left( \frac{y}{\delta} \right)^2 \right]$$

### Problem 8.45

[Difficulty: 3]

8.45 A continuous belt, passing upward through a chemical bath at speed  $U_0$ , picks up a liquid film of thickness  $h$ , density  $\rho$ , and viscosity  $\mu$ . Gravity tends to make the liquid drain down, but the movement of the belt keeps the liquid from running off completely. Assume that the flow is fully developed and laminar with zero pressure gradient, and that the atmosphere produces no shear stress at the outer surface of the film. State clearly the boundary conditions to be satisfied by the velocity at  $y=0$  and  $y=h$ . Obtain an expression for the velocity profile.



Solution: Choose CV  $dx dy dz$  as shown.

Bath:  $f, u$

Apply  $x$  component of momentum equation.

Basic equations:

$$F_{sx} + F_{bx} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} ; \tau_{yx} = \mu \frac{du}{dy} = \tau$$

- Assumptions: (1)  $F_{sx}$  due to shear forces only  
 (2) Steady flow  
 (3) Fully-developed flow

Then

$$F_{sx} + F_{bx} = F_{\text{top}} - F_{\text{bottom}} + F_{\text{right}} = \left( \tau + \frac{d\tau}{dy} \frac{dy}{2} \right) dx dz - \left( \tau - \frac{d\tau}{dy} \frac{dy}{2} \right) dx dz - \rho g dx dy dz = 0$$

or  $\frac{d\tau}{dy} = \rho g$ . Integrating

$$\tau = \rho g y + c_1 = \mu \frac{du}{dy} \quad \text{or} \quad \frac{du}{dy} = \frac{\rho g y}{\mu} + \frac{c_1}{\mu} \quad \text{Integrating again,}$$

$$u = \frac{\rho g y^2}{2\mu} + \frac{c_1}{\mu} y + c_2$$

To evaluate the constants  $c_1$  and  $c_2$ , apply the boundary conditions:

At  $y=0$ ,  $u = U_0$ , so  $c_2 = U_0$

At  $y=h$ ,  $\tau = 0$ , so  $\frac{du}{dy} = 0$ , and  $c_1 = -\rho g h$  ← BC

Substituting,

$$u = \frac{\rho g y^2}{2\mu} - \frac{\rho g h y}{\mu} + U_0 = \frac{\rho g}{\mu} \left( \frac{y^2}{2} - h y \right) + U_0 \quad \leftarrow u$$

{ Note that at  $y=h$ ,

$$u = \frac{\rho g}{\mu} \left( -\frac{h^2}{2} \right) + U_0 \neq 0$$

} Thus the solution is determined only when  $U_0$  and  $h$  are known.

## Problem 8.46

[Difficulty: 3]

**8.46** A wet paint film of uniform thickness,  $\delta$ , is painted on a vertical wall. The wet paint can be approximated as a Bingham fluid with a yield stress,  $\tau_y$ , and density,  $\rho$ . Derive an expression for the maximum value of  $\delta$  that can be sustained without having the paint flow down the wall. Calculate the maximum thickness for lithographic ink whose yield stress  $\tau_y = 40$  Pa and density is approximately  $1000 \text{ kg/m}^3$ .

**Given:** Paint flow (Bingham fluid)

**Find:** Maximum thickness of paint film before flow occur

**Solution:**

Basic equations: Bingham fluid:  $\tau_{yx} = \tau_y + \mu_p \cdot \frac{du}{dy}$

Use the analysis of Example 8.3, where we obtain a force balance between gravity and shear stresses:  $\frac{d\tau_{yx}}{dy} = -\rho \cdot g$

The given data is  $\tau_y = 40 \cdot \text{Pa}$   $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$

From the force balance equation, integrating  $\tau_{yx} = -\rho \cdot g \cdot y + c$  and we have boundary condition  $\tau_{yx}(y = \delta) = 0$

Hence  $\tau_{yx} = -\rho \cdot g \cdot (\delta - y)$  and this is a maximum at the wall  $|\tau_{\max}| = \rho \cdot g \cdot \delta$

Motion occurs when  $|\tau_{\max}| \geq |\tau_y|$  or  $\rho \cdot g \cdot \delta \geq \tau_y$

Hence the maximum thickness is  $\delta = \frac{\tau_y}{\rho \cdot g}$   $\delta = 4.08 \times 10^{-3} \text{ m}$   $\delta = 4.08 \text{ mm}$

## Problem 8.47

[Difficulty: 4]


**8.47** When dealing with the lubrication of bearings, the governing equation describing pressure is the Reynolds equation, generally written in 1D as

$$\frac{d}{dx} \left( \frac{h^3}{\mu} \frac{dp}{dx} \right) + 6U \frac{dh}{dx} = 0$$

where  $h$  is the step height and  $U$  is the velocity of the lower surface. Step bearings have a relatively simple design and are used with low-viscosity fluids such as water, gasoline, and solvents. The minimum film thickness in these applications is quite small. The step height must be small enough for good load capacity, yet large enough for the bearing to accommodate some wear without losing its load capacity by becoming smooth and flat. Beginning with the 1D equation

for fluid motion in the  $x$  direction, show that the pressure distribution in the step bearing is as shown, where

$$p_x = \frac{6\mu(h_2 - h_1)}{\frac{h_1^3}{L_1} + \frac{h_2^3}{L_2}}$$



**Given:** Equation for fluid motion in the  $x$ -direction.

**Find:** Expression for peak pressure

**Solution:** Begin with the steady-state Navier-Stokes equation –  $x$ -direction

**Governing equation:**

The Navier-Stokes equations are

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad (5.1c)$$

$$\rho \left( \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} \right) = \rho g_x - \frac{\partial p}{\partial x} + \mu \left( \frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right) \quad (5.27a)$$

$$\rho \left( \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} \right) = \rho g_y - \frac{\partial p}{\partial y} + \mu \left( \frac{\partial^2 v}{\partial x^2} + \frac{\partial^2 v}{\partial y^2} + \frac{\partial^2 v}{\partial z^2} \right) \quad (5.27b)$$

$$\rho \left( \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} \right) = \rho g_z - \frac{\partial p}{\partial z} + \mu \left( \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} \right) \quad (5.27c)$$

The following assumptions have been applied:

- (1) Steady flow (given).
- (2) Incompressible flow;  $\rho = \text{constant}$ .
- (3) No flow or variation of properties in the  $z$  direction;  $w = 0$  and  $\partial/\partial z = 0$ .
- (4) Fully developed flow, so no properties except possibly pressure  $p$  vary in the  $x$  direction;  $\partial/\partial x = 0$ .
- (5) See analysis below.
- (6) No body force in the  $y$  direction;  $g_y = 0$

Assumption (1) eliminates time variations in any fluid property. Assumption (2) eliminates space variations in density. Assumption (3) states that there is no  $z$  component of velocity and no property variations in the  $z$  direction. All terms in the  $z$  component of the Navier–Stokes equation cancel. After assumption (4) is applied, the continuity equation reduces to  $\partial v/\partial y = 0$ . Assumptions (3) and (4) also indicate that  $\partial v/\partial z = 0$  and  $\partial v/\partial x = 0$ . Therefore  $v$  must be constant (except of course in a more realistic model  $v \neq 0$  near the

transition. Since  $v$  is zero at the solid surface, then  $v$  must be zero everywhere. The fact that  $v = 0$  reduces the Navier–Stokes equations further, as indicated by (5). Hence for the  $y$  direction

$$\frac{\partial p}{\partial y} = 0$$

which indicates the pressure is a constant across the flow. Hence we conclude that  $p$  is a function at most of  $x$ .

In the  $x$  direction, we obtain

$$0 = -\frac{\partial p}{\partial x} + \mu \frac{\partial^2 u}{\partial y^2} \quad (1)$$

Integrating this twice for the first region

$$u_1 = \frac{1}{2\mu} \frac{dp}{dx} \Big|_1 y^2 + \frac{c_1}{\mu} y + c_2$$

where  $\frac{dp}{dx} \Big|_1$  denotes the pressure gradient in region 1. Note that we change to regular derivative as  $p$  is a function of  $x$  only. Note that

Eq 1 implies that we have a function of  $x$  only  $\left(\frac{\partial p}{\partial x}\right)$  and a function of  $y$  only  $\left(\frac{\partial^2 u}{\partial y^2}\right)$  that must add up to be a constant (0); hence

EACH is a constant! This means that

$$\frac{dp}{dx} \Big|_1 = \text{const} = \frac{p_s}{L_1}$$

using the notation of the figure.

To evaluate the constants,  $c_1$  and  $c_2$ , we must apply the boundary conditions. We do this separately for each region.

In the first region, at  $y = 0$ ,  $u = U$ . Consequently,  $c_2 = U$ . At  $y = h_1$ ,  $u = 0$ . Hence

$$0 = \frac{1}{2\mu} \frac{dp}{dx} \Big|_1 h_1^2 + \frac{c_1}{\mu} h_1 + U$$

so

$$c_1 = -\frac{1}{2} \frac{dp}{dx} \Big|_1 h_1 - \frac{\mu U}{h_1}$$

Hence, combining results

$$u_1 = \frac{1}{2\mu} \frac{dp}{dx} \Big|_1 (y^2 - h_1 y) + U \left( \frac{y}{h_1} - 1 \right)$$

Exactly the same reasoning applies to the second region, so

$$u_2 = \frac{1}{2\mu} \frac{dp}{dx} \Big|_2 (y^2 - h_2 y) + U \left( \frac{y}{h_2} - 1 \right)$$

where

$$\left. \frac{dp}{dx} \right|_2 = \text{const} = -\frac{p_s}{L_2}$$

What connects these flow is the flow rate  $Q$ .

$$q = \int_0^{h_1} u_1 dy = \int_0^{h_2} u_2 dy = -\frac{1}{12\mu} \left. \frac{dp}{dx} \right|_1 h_1^3 - \frac{Uh_1}{2} = -\frac{1}{12\mu} \left. \frac{dp}{dx} \right|_2 h_2^3 - \frac{Uh_2}{2}$$

Hence

$$\frac{1}{12\mu} \frac{p_s}{L_1} h_1^3 + \frac{Uh_1}{2} = -\frac{1}{12\mu} \frac{p_s}{L_2} h_2^3 + \frac{Uh_2}{2}$$

Solving for  $p_s$ ,

$$\frac{p_s}{12\mu} \left( \frac{h_1^3}{L_1} + \frac{h_2^3}{L_2} \right) = \frac{Uh_2}{2} - \frac{Uh_1}{2}$$

or

$$p_s = \frac{6\mu U(h_2 - h_1)}{\left( \frac{h_1^3}{L_1} + \frac{h_2^3}{L_2} \right)}$$

### Problem 8.48

[Difficulty: 2]

**8.48** Consider first water and then SAE 10W lubricating oil flowing at 40°C in a 6-mm-diameter tube. Determine the maximum flow rate (and the corresponding pressure gradient,  $\partial p/\partial x$ ) for each fluid at which laminar flow would be expected.

Solution: Laminar flow is expected for  $Re \leq 2300$ . Expressing this in terms of flowrate,

$$Re = \frac{\rho \bar{v} D}{\mu} = \frac{\bar{v} D}{\nu} = \frac{Q D}{A \nu} = \frac{4}{\pi D^2} \frac{Q D}{\nu} = \frac{4Q}{\pi \nu D} \quad \text{or} \quad Q = \frac{\pi \nu D Re}{4}$$

Thus

$$Q_{max} = \frac{\pi \nu D Re_{max}}{4} = \frac{\pi}{4} \times 2300 \times 0.006 \text{ m} \times \nu \frac{\text{m}^2}{\text{s}} = 10.8 \nu \left( \frac{\text{m}^3}{\text{s}} \right)$$

Also,  $Q = -\frac{\pi R^4}{8\mu} \frac{\partial p}{\partial x}$  for laminar flow, according to Eq. 8.136. Then

$$\frac{\partial p}{\partial x} = -\frac{8\mu Q}{\pi R^4} = -\frac{128\mu Q}{\pi D^4}$$

so

$$\frac{\partial p}{\partial x} = -\frac{128}{\pi} \times \mu \frac{\text{N}\cdot\text{s}}{\text{m}^2} \times \frac{Q \text{ m}^3}{\text{s}} \times \frac{1}{(0.006)^4 \text{ m}^4} = -3.14 \times 10^{10} \mu Q \left( \frac{\text{N}}{\text{m}^2} \right)$$

Using data from Appendix A, at 40°C,

Fluid	$\nu \left( \frac{\text{m}^2}{\text{s}} \right)$	$Q \left( \frac{\text{m}^3}{\text{s}} \right)$	$\mu \left( \frac{\text{N}\cdot\text{s}}{\text{m}^2} \right)$	$\mu Q \left( \text{N}\cdot\text{m} \right)$	$\frac{\partial p}{\partial x} \left( \frac{\text{N}}{\text{m}^2} \right)$
Water	$6.57 \times 10^{-7}$	$7.10 \times 10^{-6}$	$6.51 \times 10^{-4}$	$4.62 \times 10^{-9}$	-145
SAE 10W oil	$3.8 \times 10^{-5}$	$4.10 \times 10^{-4}$	$3.4 \times 10^{-2}$	$1.39 \times 10^{-5}$	$-4.36 \times 10^5$

$\frac{\partial p}{\partial x}$

$Q_{ma}$

{ Note  $Q \sim \nu = \frac{\mu}{\rho}$  and  $\frac{\partial p}{\partial x} \sim \mu Q \sim \frac{\mu^2}{\rho}$ . }

Problem 8.49

[Difficulty: 2]

8.49 For fully developed laminar flow in a pipe, determine the radial distance from the pipe axis at which the velocity equals the average velocity.

Solution: First determine  $\bar{V}$ .

$$\bar{V} = \frac{Q}{A} = \frac{1}{\pi R^2} \int_A u \, dA = \frac{1}{\pi R^2} \int_0^R \left\{ -\frac{R^2}{4\mu} \frac{\partial p}{\partial x} \left[ 1 - \left(\frac{r}{R}\right)^2 \right] \right\} 2\pi r \, dr$$

$$= -\frac{R^2}{2\mu} \frac{\partial p}{\partial x} \int_0^R \left[ 1 - \left(\frac{r}{R}\right)^2 \right] \left(\frac{r}{R}\right) d\left(\frac{r}{R}\right) = -\frac{R^2}{2\mu} \frac{\partial p}{\partial x} \left[ \frac{1}{2} \left(\frac{r}{R}\right)^2 - \frac{1}{4} \left(\frac{r}{R}\right)^4 \right]_0^R$$

$$\bar{V} = -\frac{R^2}{8\mu} \frac{\partial p}{\partial x}$$

Then  $u = \bar{V}$  when

$$u = -\frac{R^2}{4\mu} \frac{\partial p}{\partial x} \left[ 1 - \left(\frac{r}{R}\right)^2 \right] = \bar{V} = -\frac{R^2}{8\mu} \frac{\partial p}{\partial x}$$

or

$$1 - \left(\frac{r}{R}\right)^2 = \frac{1}{2}$$

or

$$\left(\frac{r}{R}\right)^2 = \frac{1}{2}$$

$$r = \frac{R}{\sqrt{2}} = 0.707R \quad \leftarrow$$

## Problem 8.50

[Difficulty: 3]

**8.50** Using Eq. A.3 in Appendix A for the viscosity of water, find the viscosity at  $-20^\circ\text{C}$  and  $120^\circ\text{C}$ . Plot the viscosity over this range. Find the maximum laminar flow rate (L/hr) in a 7.5-mm-diameter tube at these temperatures. Plot the maximum laminar flow rate over this temperature range.

**Given:** Data on water temperature and tube


**Find:** Maximum laminar flow; plot

**Solution:** From Appendix A  $A = 2.414 \cdot 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$   $B = 247.8 \cdot \text{K}$   $C = 140 \cdot \text{K}$  in  $\mu(T) = A \cdot 10^{\frac{B}{T-C}}$

$D = 7.5 \cdot \text{mm}$   $\rho = 1000 \frac{\text{kg}}{\text{m}^3}$   $\text{Re}_{\text{crit}} = 2300$


$T_1 = -20^\circ\text{C}$   $T_1 = 253 \text{ K}$   $\mu(T_1) = 3.74 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$   $T_2 = 120^\circ\text{C}$   $T_2 = 393 \text{ K}$   $\mu(T_2) = 2.3 \times 10^{-4} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

The plot of viscosity is



For the flow rate  $\text{Re}_{\text{crit}} = \frac{\rho \cdot V_{\text{crit}} \cdot D}{\mu} = \frac{\rho \cdot Q_{\text{max}} \cdot D}{\mu \cdot \frac{\pi}{4} \cdot D^2} = \frac{4 \cdot \rho \cdot Q_{\text{max}}}{\mu \cdot \pi \cdot D}$   $Q_{\text{max}}(T) = \frac{\pi \cdot \mu(T) \cdot D \cdot \text{Re}_{\text{crit}}}{4 \cdot \rho}$


$Q_{\text{max}}(T_1) = 5.07 \times 10^{-5} \frac{\text{m}^3}{\text{s}}$   $Q_{\text{max}}(T_1) = 182 \frac{\text{L}}{\text{hr}}$   $Q_{\text{max}}(T_2) = 3.12 \times 10^{-6} \frac{\text{m}^3}{\text{s}}$   $Q_{\text{max}}(T_2) = 11.2 \frac{\text{L}}{\text{hr}}$



## Problem 8.51

[Difficulty: 2]

**8.51** A hypodermic needle, with inside diameter  $d = 0.005$  in. and length  $L = 1$  in., is used to inject saline solution with viscosity five times that of water. The plunger diameter is  $D = 0.375$  in.; the maximum force that can be exerted by a thumb on the plunger is  $F = 7.5$  lbf. Estimate the volume flow rate of saline that can be produced.



**Given:** Hypodermic needle

**Find:** Volume flow rate of saline

**Solution:**

Basic equation  $Q = \frac{\pi \cdot \Delta p \cdot d^4}{128 \mu \cdot L}$  (Eq. 8.13c; we assume laminar flow and verify this is correct after solving)

For the system  $\Delta p = p_1 - p_{\text{atm}} = \frac{F}{A} = \frac{4 \cdot F}{\pi \cdot D^2}$

$$\Delta p = \frac{4}{\pi} \times 7.5 \text{ lbf} \times \left( \frac{1}{0.375 \text{ in}} \times \frac{12 \text{ in}}{1 \text{ ft}} \right)^2 \quad \Delta p = 67.9 \text{ psi}$$

At 68°F, from Table A.7  $\mu_{\text{H}_2\text{O}} = 2.1 \times 10^{-5} \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$   $\mu = 5 \cdot \mu_{\text{H}_2\text{O}}$   $\mu = 1.05 \times 10^{-4} \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$

$$Q = \frac{\pi}{128} \times 67.9 \frac{\text{lbf}}{\text{in}^2} \times \frac{144 \cdot \text{in}^2}{1 \cdot \text{ft}^2} \times \left( 0.005 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^4 \times \frac{\text{ft}^2}{1.05 \times 10^{-4} \text{ lbf} \cdot \text{s}} \times \frac{1}{1 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}}$$

$$Q = 8.27 \times 10^{-7} \frac{\text{ft}^3}{\text{s}} \quad Q = 1.43 \times 10^{-3} \frac{\text{in}^3}{\text{s}} \quad Q = 0.0857 \frac{\text{in}^3}{\text{min}}$$

Check Re:  $V = \frac{Q}{A} = \frac{Q}{\frac{\pi \cdot d^2}{4}}$   $V = \frac{4}{\pi} \times 8.27 \times 10^{-7} \frac{\text{ft}^3}{\text{s}} \times \left( \frac{1}{0.005 \cdot \text{in}} \right)^2 \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2$   $V = 6.07 \frac{\text{ft}}{\text{s}}$

$$\text{Re} = \frac{\rho \cdot V \cdot d}{\mu} \quad \rho = 1.94 \frac{\text{slug}}{\text{ft}^3} \quad (\text{assuming saline is close to water})$$

$$\text{Re} = 1.94 \frac{\text{slug}}{\text{ft}^3} \times 6.07 \frac{\text{ft}}{\text{s}} \times 0.005 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \times \frac{\text{ft}^2}{1.05 \times 10^{-4} \cdot \text{lbf} \cdot \text{s}} \times \frac{\text{slug} \cdot \text{ft}}{\text{s}^2 \cdot \text{lbf}} \quad \text{Re} = 46.7$$

Flow is laminar

## Problem 8.52

[Difficulty: 3]

**8.52** In engineering science, there are often analogies to be made between disparate phenomena. For example, the applied pressure difference,  $\Delta p$ , and corresponding volume flow rate,  $Q$ , in a tube can be compared to the applied DC voltage,  $V$ , across and current,  $I$ , through an electrical resistor, respectively. By analogy, find a formula for the "resistance" of laminar flow of fluid of viscosity,  $\mu$ , in a tube length of  $L$  and diameter  $D$ , corresponding to electrical resistance,  $R$ . For a tube 250 mm long with inside diameter 7.5 mm, find the maximum flow rate and pressure difference for which this analogy will hold for (a) kerosene and (b) castor oil (both at 40°C). When the flow exceeds this maximum, why does the analogy fail?

**Given:** Data on a tube

**Find:** "Resistance" of tube; maximum flow rate and pressure difference for which electrical analogy holds for (a) kerosene and (b) castor oil

**Solution:**

The given data is  $L = 250 \cdot \text{mm}$   $D = 7.5 \cdot \text{mm}$

From Fig. A.2 and Table A.2

Kerosene:	$\mu = 1.1 \times 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$	$\rho = 0.82 \times 990 \cdot \frac{\text{kg}}{\text{m}^3} = 812 \cdot \frac{\text{kg}}{\text{m}^3}$
Castor oil:	$\mu = 0.25 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$	$\rho = 2.11 \times 990 \cdot \frac{\text{kg}}{\text{m}^3} = 2090 \cdot \frac{\text{kg}}{\text{m}^3}$

For an electrical resistor  $V = R \cdot I$  (1)

The governing equation for the flow rate for laminar flow in a tube is Eq. 8.13c

$$Q = \frac{\pi \cdot \Delta p \cdot D^4}{128 \cdot \mu \cdot L}$$

or

$$\Delta p = \frac{128 \cdot \mu \cdot L}{\pi \cdot D^4} \cdot Q \quad (2)$$

By analogy, current  $I$  is represented by flow rate  $Q$ , and voltage  $V$  by pressure drop  $\Delta p$ . Comparing Eqs. (1) and (2), the "resistance" of the tube is

$$R = \frac{128 \cdot \mu \cdot L}{\pi \cdot D^4}$$

The "resistance" of a tube is directly proportional to fluid viscosity and pipe length, and strongly dependent on the inverse of diameter

The analogy is only valid for  $Re < 2300$  or  $\frac{\rho \cdot V \cdot D}{\mu} < 2300$

Writing this constraint in terms of flow rate  $\frac{\rho \cdot \frac{Q}{\frac{\pi \cdot D^2}{4}} \cdot D}{\mu} < 2300$  or  $Q_{\max} = \frac{2300 \cdot \mu \cdot \pi \cdot D}{4 \cdot \rho}$

The corresponding maximum pressure gradient is then obtained from Eq. (2)

$$\Delta p_{\max} = \frac{128 \cdot \mu \cdot L}{\pi \cdot D^4} \cdot Q_{\max} = \frac{32 \cdot 2300 \cdot \mu^2 \cdot L}{\rho \cdot D^3}$$

Substituting values

(a) For kerosine  $Q_{\max} = 1.84 \times 10^{-5} \frac{\text{m}^3}{\text{s}}$   $Q_{\max} = 1.10 \cdot \frac{1}{\text{min}}$   $\Delta p_{\max} = 65.0 \cdot \text{Pa}$

(b) For castor oil  $Q_{\max} = 1.62 \times 10^{-3} \frac{\text{m}^3}{\text{s}}$   $Q_{\max} = 97.3 \cdot \frac{1}{\text{min}}$   $\Delta p_{\max} = 1.30 \cdot \text{MPa}$


The analogy fails when  $Re > 2300$  because the flow becomes turbulent, and "resistance" to flow is then no longer linear with flow rate

### Problem 8.53

[Difficulty: 3]

**8.53** Consider fully developed laminar flow in the annulus between two concentric pipes. The outer pipe is stationary, and the inner pipe moves in the  $x$  direction with speed  $V$ . Assume the axial pressure gradient is zero ( $\partial p / \partial x = 0$ ).

Obtain a general expression for the shear stress,  $\tau$ , as a function of the radius,  $r$ , in terms of a constant,  $C_1$ . Obtain a general expression for the velocity profile,  $u(r)$ , in terms of two constants,  $C_1$  and  $C_2$ . Obtain expressions for  $C_1$  and  $C_2$ .



Solution: Apply  $x$  component of momentum equation, using annular CV shown.

Basic Equations:  $F_{sx} + F_{bx} = \frac{\partial}{\partial t} \int_{CV} \rho u dV + \int_{CS} \rho u \vec{V} \cdot d\vec{A}$ ;  $\tau_x = \mu \frac{du}{dr} = \tau$

- Assumptions: (1)  $F_{bx} = 0$   
 (2) steady flow  
 (3) Fully-developed flow

Then

$$F_{sx} = F_{\text{top}} - F_{\text{bottom}} = \left( \tau + \frac{d\tau}{dr} \frac{dr}{2} \right) 2\pi \left( r + \frac{dr}{2} \right) dx - \left( \tau - \frac{d\tau}{dr} \frac{dr}{2} \right) 2\pi \left( r - \frac{dr}{2} \right) dx = 0$$

Neglecting products of differentials, this reduces to

$$\tau + r \frac{d\tau}{dr} = 0 \quad \text{or} \quad \frac{d}{dr} (r\tau) = 0$$

Thus  $r\tau = C_1$  or  $\tau = \frac{C_1}{r}$   $\tau(r)$

But  $\tau = \mu \frac{du}{dr}$ , so  $\frac{du}{dr} = \frac{C_1}{\mu r}$

and  $u = \frac{C_1}{\mu} \ln r + C_2$   $u(r)$

To evaluate constants  $C_1$  and  $C_2$ , use boundary conditions.

At  $r = r_i$ ,  $u = V_0$ , so  $V_0 = \frac{C_1}{\mu} \ln r_i + C_2$

At  $r = r_o$ ,  $u = 0$ , so  $0 = \frac{C_1}{\mu} \ln r_o + C_2$  and  $C_2 = -\frac{C_1}{\mu} \ln r_o$

Thus, subtracting,  $V_0 = \frac{C_1}{\mu} \ln \left( \frac{r_i}{r_o} \right)$  or  $C_1 = \frac{\mu V_0}{\ln(r_i/r_o)}$  so  $C_2 = -\frac{V_0 \ln r_o}{\ln(r_i/r_o)}$


Finally

$$u = \frac{V_0}{\ln(r_i/r_o)} (\ln r - \ln r_i) = V_0 \frac{\ln(r/r_i)}{\ln(r_i/r_o)}$$
  $u(r)$

### Problem 8.54

[Difficulty: 3]

**8.54** Consider fully developed laminar flow in a circular pipe. Use a cylindrical control volume as shown. Indicate the forces acting on the control volume. Using the momentum equation, develop an expression for the velocity distribution.



Solution: The forces on a CV of radius  $r$  are shown above.

Apply the  $x$  component of momentum, to CV shown.

Basic equations: 
$$F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} \rho u \, dV + \int_{CS} \rho u \vec{V} \cdot d\vec{A}, \quad \tau_{rx} = \mu \frac{du}{dr}$$

Assumptions: (1)  $F_{B_x} = 0$   
 (2) Steady flow  
 (3) Fully-developed flow

Then

$$F_{S_x} = \left(p - \frac{\partial p}{\partial x} \frac{dx}{2}\right) \pi r^2 + \tau_{rx} 2\pi r dx - \left(p + \frac{\partial p}{\partial x} \frac{dx}{2}\right) \pi r^2 = 0$$

canceling and combining terms,

$$-r \frac{\partial p}{\partial x} + 2\tau_{rx} = 0 \quad \text{or} \quad \tau_{rx} = \mu \frac{du}{dr} = \frac{r}{2} \frac{\partial p}{\partial x}$$

Thus 
$$\frac{du}{dr} = \frac{r}{2\mu} \frac{\partial p}{\partial x}$$

and

$$u = \frac{r^2}{4\mu} \frac{\partial p}{\partial x} + c_1$$

To evaluate  $c_1$ , apply the boundary condition  $u = 0$  at  $r = R$ . Thus

$$c_1 = -\frac{R^2}{4\mu} \frac{\partial p}{\partial x}$$

and

$$u = \frac{1}{4\mu} \frac{\partial p}{\partial x} (r^2 - R^2) = -\frac{R^2}{4\mu} \frac{\partial p}{\partial x} \left[1 - \left(\frac{r}{R}\right)^2\right]$$


which is identical to Eq. 8.12.

### Problem 8.56

[Difficulty: 4] Part 1/2

**8.56** For the flow of Problem 8.55 show that the volume flow rate is given by

$$Q = -\frac{\pi R^4}{8\mu} \frac{\partial p}{\partial x} \left[ (1-k^4) - \frac{(1-k^2)^2}{\ln(1/k)} \right]$$



Find an expression for the average velocity. Compare the limiting case,  $k \rightarrow 0$ , with the corresponding expression for flow in a circular pipe.

Solution: The volume flow rate is given by

$$\begin{aligned} Q &= \int u dA = \int_{kR}^R u 2\pi r dr = 2\pi \int_{kR}^R u r dr \\ &= 2\pi \left( \frac{-R^2}{4\mu} \frac{\partial p}{\partial x} \right) \int_{kR}^R \left[ r - \frac{r^3}{R^2} + \frac{(1-k^2)}{\ln(1/k)} r \ln \frac{r}{R} \right] dr \\ &= \frac{-\pi R^4}{2\mu} \frac{\partial p}{\partial x} \int_k^1 \left[ r^2 - \left(\frac{r}{R}\right)^3 + \frac{(1-k^2)}{\ln(1/k)} \frac{r}{R} \ln \frac{r}{R} \right] d\left(\frac{r}{R}\right) \\ &= \frac{-\pi R^4}{2\mu} \frac{\partial p}{\partial x} \left[ \frac{1}{3} \left(\frac{r}{R}\right)^3 - \frac{1}{4} \left(\frac{r}{R}\right)^4 + \frac{(1-k^2)}{\ln(1/k)} \left\{ \left(\frac{r}{R}\right)^2 \left[ \frac{1}{2} \ln \left(\frac{r}{R}\right) - \frac{1}{4} \right] \right\} \right]_k^1 \\ &= \frac{-\pi R^4}{2\mu} \frac{\partial p}{\partial x} \left[ \frac{1}{3} - \frac{1}{4} + \frac{1}{3} - \frac{1}{4} + \frac{(1-k^2)}{\ln(1/k)} \left\{ -\frac{1}{4} - k^2 \left[ \frac{1}{2} \ln k - \frac{1}{4} \right] \right\} \right] \\ &= \frac{-\pi R^4}{2\mu} \frac{\partial p}{\partial x} \left[ \frac{1}{4} - \frac{k^2}{4} + \frac{(1-k^2)}{\ln(1/k)} \left\{ -\frac{1}{4} + \frac{k^2}{4} - k^2 \frac{1}{2} \ln k \right\} \right] \\ &= \frac{-\pi R^4}{2\mu} \frac{\partial p}{\partial x} \left[ \frac{1-2k^2+k^4}{4} + \frac{(1-k^2)}{\ln(1/k)} \left\{ \frac{k^2-1}{4} - \frac{(1-k^2)}{2} k^2 \frac{1}{2} \ln k \right\} \right] \\ &= \frac{-\pi R^4}{2\mu} \frac{\partial p}{\partial x} \left[ \frac{1-2k^2+k^4}{4} - \frac{(1-k^2)^2}{4 \ln(1/k)} + \frac{k^2-k^4}{2} \right] \\ &= \frac{-\pi R^4}{2\mu} \frac{\partial p}{\partial x} \left[ \frac{1-2k^2+k^4}{4} + \frac{2k^2-2k^4}{4} - \frac{(1-k^2)^2}{4 \ln(1/k)} \right] \\ Q &= \frac{-\pi R^4}{8\mu} \frac{\partial p}{\partial x} \left[ (1-k^4) - \frac{(1-k^2)^2}{\ln(1/k)} \right] \end{aligned}$$

The average velocity,  $\bar{v} = \frac{Q}{A} = \frac{Q}{\pi R^2}$

The area is given by

$$A = \int dA = \int 2\pi r dr = 2\pi R^2 \int_{\frac{r}{R}} d\left(\frac{r}{R}\right)$$

$$A = 2\pi R^2 \left[ \frac{1}{2} \left(\frac{r}{R}\right)^2 \right]_0^1 = 2\pi R^2 \cdot \frac{1}{2} (1 - 0^2) = \pi R^2 (1 - 0^2)$$

Thus

$$\bar{v} = \frac{Q}{A} = -\frac{\pi R^4}{8\mu} \frac{\partial p}{\partial x} \cdot \frac{1}{\pi R^2} \left[ \frac{(1-r^4)}{(1-r^2)} - \frac{(1-r^2)}{\ln(1/r)} \right]$$

$$\bar{v} = -\frac{R^2}{8\mu} \frac{\partial p}{\partial x} \left[ \frac{(1-r^4)}{(1-r^2)} - \frac{(1-r^2)}{\ln(1/r)} \right] \quad \leftarrow \bar{v}$$

For  $r \rightarrow 0$


$$Q = -\frac{\pi R^4}{8\mu} \frac{\partial p}{\partial x} \quad \text{and} \quad \bar{v} = -\frac{R^2}{8\mu} \frac{\partial p}{\partial x}$$

These agree with the results for flow in a circular pipe.

### Problem 8.57

[Difficulty: 4]

**8.57** It has been suggested in the design of an agricultural sprinkler that a structural member be held in place by a wire placed along the centerline of a pipe; it is surmised that a relatively small wire would have little effect on the pressure drop for a given flow rate. Using the result of Problem 8.56, derive an expression giving the percentage change in pressure drop as a function of the ratio of wire diameter to pipe diameter for laminar flow. Plot the percentage change in pressure drop as a function of radius ratio  $k$  for  $0.001 \leq k \leq 0.10$ .



Solution: The results of problem 8.56 give

$$Q = -\frac{\pi R^4}{8\mu} \frac{\Delta p}{\Delta x} \left[ (1-k^4) - \frac{(1-k^2)^2}{\ln(1/k)} \right]$$

Thus

$$\frac{\Delta p}{L} = -\frac{\Delta p}{\Delta x} = \frac{8\mu Q}{\pi R^4} \times \frac{1}{\left[ (1-k^4) - \frac{(1-k^2)^2}{\ln(1/k)} \right]}$$

or  $k=0$ ,

$$\frac{\Delta p}{L} = \frac{8\mu Q}{\pi R^4}$$

$$\text{Percent change} = \frac{\Delta p/L - \Delta p/L|_{k=0}}{\Delta p/L|_{k=0}} = \frac{1}{\left[ (1-k^4) - \frac{(1-k^2)^2}{\ln(1/k)} \right]} - 1$$


$$\% \text{ change} = \frac{1 - \left[ (1-k^4) - \frac{(1-k^2)^2}{\ln(1/k)} \right]}{\left[ (1-k^4) - \frac{(1-k^2)^2}{\ln(1/k)} \right]}$$

For small  $k$ ,

$$\% \text{ change} = \frac{1 - \left[ 1 - \frac{1}{\ln(1/k)} \right]}{\left[ 1 - \frac{1}{\ln(1/k)} \right]} = \frac{1 - \left[ 1 + \frac{1}{\ln k} \right]}{\left[ 1 + \frac{1}{\ln k} \right]} = \frac{-\frac{1}{\ln k}}{\left[ 1 + \frac{1}{\ln k} \right]}$$

$$\% \text{ change} = -\frac{1}{\ln k \left( 1 + \frac{1}{\ln k} \right)} \times 100$$

$k = r_1/R$	% change in $\Delta p$
0.0001	12.2
0.0002	13.3
0.0005	15.1
0.001	16.9
0.002	19.2
0.005	23.3
0.01	27.7
0.02	34.3
0.05	50.1
0.1	76.8



The plot shows that even the smallest of wires causes a significant increase in pressure drop for a given flow rate.

## Problem 8.58

[Difficulty: 2]

**8.58** Consider fully developed pressure-driven flow in a cylindrical tube of radius,  $R$ , and length,  $L = 10$  mm, with flow generated by an applied pressure gradient,  $\Delta p$ . Tests are performed with room temperature water for various values of  $R$ , with a fixed flow rate of  $Q = 10 \mu\text{L}/\text{min}$ . The hydraulic resistance is defined as  $R_{\text{hyd}} = \Delta p/Q$  (by analogy with the electrical resistance  $R_{\text{elec}} = \Delta V/I$ , where  $\Delta V$  is the electrical potential drop and  $I$  is the electric current). Calculate the required pressure gradient and hydraulic resistance for the range of tube radii listed in the table. Based on the results, is it appropriate to use a pressure gradient to pump fluids in microchannels, or should some other driving mechanism be used?

$R$ (mm)	$\Delta p$ (Pa)	$R_{\text{hyd}}$ ( $\text{Pa} \cdot \text{s}/\text{m}^3$ )
1		
$10^{-1}$		
$10^{-2}$		
$10^{-3}$		
$10^{-4}$		

**Given:** Tube dimensions and volumetric flow rate

**Find:** Pressure difference and hydraulic resistance

**Solution:**

The flow rate of a fully developed pressure-driven flow in a pipe is  $Q = \frac{\pi \Delta p R^4}{8 \mu L}$ . Rearranging it, one obtains  $\Delta p = \frac{8 \mu L Q}{\pi R^4}$ . For a flow rate  $Q = 10 \mu\text{L}/\text{min}$ ,  $L = 1$  cm,  $\mu = 1.0 \times 10^{-3} \text{ Pa}\cdot\text{s}$ , and  $R = 1$  mm,

$$\Delta p = \frac{8}{\pi} \times \frac{10 \times 10^{-9}}{60} \times \frac{\text{m}^3}{\text{s}} \times \frac{0.01}{1 \times 10^{-12}} \times \frac{\text{m}}{\text{m}^4} \times 1.0 \times 10^{-3} \text{ Pa}\cdot\text{s} = 0.00424 \text{ Pa}$$

Similarly, the required pressure drop for other values of  $R$  can be obtained.

The hydraulic resistance  $R_{\text{hyd}} = \frac{\Delta p}{Q} = \frac{8 \mu L}{\pi R^4}$ . Substituting the values of the viscosity, length and radius of the tube, one obtains the value of the hydraulic resistance.

$R$ (mm)	$\Delta p$	$R_{\text{hyd}}$ ( $\text{Pa}\cdot\text{s}/\text{m}^3$ )
1	0.00424 Pa	$2.55 \times 10^7$
$10^{-1}$	42.4 Pa	$2.55 \times 10^{11}$
$10^{-2}$	424 kPa	$2.55 \times 10^{15}$
$10^{-3}$	4.24 GPa	$2.55 \times 10^{19}$
$10^{-4}$	$4.24 \times 10^4$ GPa	$2.55 \times 10^{23}$

(3) To achieve a reasonable flow rate in microscale or nanoscale channel, a very high pressure difference is required since  $\Delta p$  is proportional to  $R^{-4}$ . Therefore, the widely used pressure-driven flow in large scale systems is not appropriate in microscale or nanoscale channel applications. Other means to manipulate fluids in microscale or nanoscale channel applications are required.

## Problem 8.59

[Difficulty: 2]

**8.59** The figure schematically depicts a conical diffuser, which is designed to increase pressure and reduce kinetic energy. We assume the angle  $\alpha$  is small ( $\alpha < 10^\circ$ ) so that  $\tan \alpha \approx \alpha$  and  $r_e = r_i + \alpha l$ , where  $r_i$  is the radius at the diffuser inlet,  $r_e$  is the radius at the exit, and  $l$  is the length of the diffuser. The flow in a diffuser is complex, but here we assume that each layer of fluid in the diffuser flow is laminar, as in a cylindrical tube with constant cross-sectional area. Based on reasoning similar to that in Section 8.3, the pressure difference  $\Delta p$  between the ends of a cylindrical pipe is

$$\Delta p = \frac{8\mu}{\pi} Q \int_0^x \frac{1}{r^3} dx$$

where  $x$  is the location in the diffuser,  $\mu$  is the fluid dynamic viscosity, and  $Q$  is the flow rate. The equation above is applicable to flows in a diffuser assuming that the inertial force and exit effects are negligible. Derive the hydraulic resistance,  $R_{hyd} = \Delta p/Q$ , of the diffuser.

**Given:** Definition of hydraulic resistance


**Find:** Hydraulic resistance in a diffuser

**Solution:**

Basic equation:  $R_{hyd} = \frac{\Delta p}{Q}$

$$\begin{aligned} R_{hyd} &= \frac{\Delta p}{Q} = \frac{8\mu}{\pi} \int_{z_1}^{z_2} \frac{1}{r^4} dz = \frac{8\mu}{\pi} \int_{z_1}^{z_2} \frac{1}{(r_i + \alpha z)^4} dz \\ &= \frac{8\mu}{\pi} \int_0^l \frac{1}{(r_i + \alpha z)^4} d(r_i + \alpha z) \\ &= -\frac{8\mu}{\pi \alpha} \frac{1}{3} (r_i + \alpha z)^{-3} \Big|_0^l = -\frac{8\mu}{3\pi \alpha} [(r_i + \alpha z)^{-3} - r_i^{-3}] \end{aligned}$$

$$R_{hyd} = -\frac{8\mu}{3\pi \alpha} \left[ \frac{1}{(r_i + \alpha z)^3} - \frac{1}{r_i^3} \right]$$



## Problem 8.60

[Difficulty: 4]

**8.60** Consider blood flow in an artery. Blood is non-Newtonian; the shear stress versus shear rate is described by the Casson relationship:

$$\begin{cases} \sqrt{\tau} = \sqrt{\tau_c} + \sqrt{\mu \frac{du}{dr}}, & \text{for } \tau \geq \tau_c \\ \tau = 0 & \text{for } \tau < \tau_c \end{cases}$$

where  $\tau_c$  is the critical shear stress, and  $\mu$  is a constant having the same dimensions as dynamic viscosity. The Casson relationship shows a linear relationship between  $\sqrt{\tau}$  and  $\sqrt{du/dr}$ , with intercept  $\sqrt{\tau_c}$  and slope  $\sqrt{\mu}$ . The Casson relationship approaches Newtonian behavior at high values of deformation rate. Derive the velocity profile of steady fully developed blood flow in an artery of radius  $R$ . Determine the flow rate in the blood vessel. Calculate the flow rate due to a pressure gradient  $dp/dx = -100$  Pa/m, in an artery of radius  $R = 1$  mm, using the following blood data:  $\mu = 3.5$  cP,  $\tau_c = 0.05$  dynes/cm<sup>2</sup>.

**Given:** Relationship between shear stress and deformation rate; fully developed flow in a cylindrical blood vessel

**Find:** Velocity profile; flow rate

**Solution:**

Similar to the Example Problem described in Section 8.3, based on the force balance, one obtains

$$\tau_{rx} = \frac{r}{2} \frac{dp}{dx} \quad (1)$$

This result is valid for all types of fluids, since it is based on a simple force balance without any assumptions about fluid rheology. Since the axial pressure gradient in a steady fully developed flow is a constant, Equation (1) shows that  $\tau = 0 < \tau_c$  at  $r = 0$ . Therefore, there must be a small region near the center line of the blood vessel for which  $\tau < \tau_c$ . If we call  $R_c$  the radial location at which  $\tau = \tau_c$ , the flow can then be divided into two regions:

$r > R_c$ : The shear stress vs. shear rate is governed by

$$\sqrt{\tau} = \sqrt{\tau_c} + \sqrt{\mu \frac{du}{dr}} \quad (2)$$

$r < R_c$ :  $\tau = 0 < \tau_c$ .

We first determine the velocity profile in the region  $r > R_c$ . Substituting (1) into (2), one obtains:

$$\sqrt{\frac{r}{2} \frac{dp}{dx}} = \sqrt{\tau_c} + \sqrt{\mu \frac{du}{dr}} \quad (3)$$

Using equation (3) and the fact that  $du/dr$  at  $r = R_c$  is zero, the critical shear stress can be written as

$$\sqrt{\frac{R_c}{2} \frac{dp}{dx}} = \sqrt{\tau_c} \quad (4)$$

Rearranging eq. (4),  $R_c$  is

$$R_c = 2\tau_c / \frac{dp}{dx} \quad (5)$$

Inserting (4) into (3), rearranging, and squaring both sides, one obtains

$$\mu \frac{du}{dr} = \frac{1}{2} \frac{dp}{dx} [r - 2\sqrt{rR_c} + R_c] \quad (6)$$

Integrating the above first-order differential equation using the non-slip boundary condition,  $u = 0$  at  $r = R$ :

$$u = -\frac{1}{4\mu} \frac{dp}{dx} \left[ (R^2 - r^2) - \frac{8}{3} \sqrt{R_c} (R_c^{3/2} - r^{3/2}) + 2R_c(R - r) \right] \text{ for } R_c \leq r \leq R \quad (7)$$

In the region  $r < R_c$ , since the shear stress is zero, fluid travels as a plug with a plug velocity. Since the plug velocity must match the velocity at  $r = R_c$ , we set  $r = R_c$  in equation (7) to obtain the plug velocity:

$$u = -\frac{1}{4\mu} \frac{dp}{dx} \left[ (R^2 - R_c^2) + 2R_c(R - R_c) \right] \text{ for } r \leq R_c \quad (8)$$

The flow rate is obtained by integrating  $u(r)$  across the vessel cross section:

$$\begin{aligned} Q &= \int_0^R u(r) 2\pi r dr = \int_0^{R_c} u(r) 2\pi r dr + \int_{R_c}^R u(r) 2\pi r dr \\ &= -\frac{\pi R^4}{8\mu} \frac{dp}{dx} \left[ 1 - \frac{16}{7} \sqrt{\frac{R_c}{R}} + \frac{4}{3} \frac{R_c}{R} - \frac{1}{21} \left( \frac{R_c}{R} \right)^4 \right] \end{aligned} \quad (9)$$

Given  $R = 1\text{mm} = 10^{-3}\text{m}$ ,  $\mu = 3.5\text{ cP} = 3.5 \times 10^{-3}\text{ Pa}\cdot\text{s}$ , and  $\tau_c = 0.05\text{ dynes/cm}^2 = 0.05 \times 10^{-1}\text{ Pa}$ , and  $\frac{dp}{dx} = -100\text{ Pa/m}$ .

From eq. (5),  $R_c = 2\tau_c / \frac{dp}{dx}$

$$R_c = \frac{2 \times 0.05 \times 10 \times 10^{-6} \text{ N/m}^2}{100 \text{ Pa/m}} = 0.1\text{mm}$$

Substituting the values of  $R$ ,  $\mu$ ,  $R_c$ , and  $\frac{dp}{dx}$  into eq. (9),

$$Q = -\frac{\pi}{8} \frac{1 \times 10^{-12} \text{ m}^4}{3.5 \times 10^{-3} \text{ Pa}\cdot\text{s}} \times (-100) \text{ Pa/m} \times \left[ 1 - \frac{16}{7} \sqrt{\frac{0.1 \text{ mm}}{1 \text{ mm}}} + \frac{4}{3} \frac{0.1 \text{ mm}}{1 \text{ mm}} - \frac{1}{21} \left( \frac{0.1 \text{ mm}}{1 \text{ mm}} \right)^4 \right] = 3.226 \times 10^{-9} \text{ m}^3/\text{s}$$

## Problem 8.61

[Difficulty: 4]

**8.61** Using Eq. 2.16, derive the velocity profile, flow rate, and average velocity of a non-Newtonian fluid in a circular tube. For a flow rate of  $Q = 1 \mu\text{L}/\text{min}$  and  $R = 1 \text{ mm}$ , with  $k$  having a value of unity in standard SI units, compare the required pressure gradients for  $n = 0.5, 1.0,$  and  $1.5$ . Which fluid requires the smallest pump for the same pipe length?

**Given:** Fully developed flow, Navier-Stokes equations; Non-Newtonian fluid

**Find:** Velocity profile, flow rate and average velocity

**Solution:**

According to equation (8.10), we can write the governing equation for Non-Newtonian fluid velocity in a circular tube

$$\tau_{rx} = k \left( \frac{du}{dr} \right)^n = \frac{r}{2} \frac{\partial p}{\partial x} + \frac{c_1}{r} \quad (1)$$

However, as for the Newtonian fluid case, we must set  $c_1 = 0$  as otherwise we'd have infinite stress at  $r = 0$ . Hence, equation (1) becomes

$$k \left( \frac{du}{dr} \right)^n = \frac{r}{2} \frac{\partial p}{\partial x} \quad (2)$$

The general solution for equation (2), obtained by integrating, is given by

$$u = \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} \frac{1}{\left( 1 + \frac{1}{n} \right)} r^{1 + \frac{1}{n}} + c_2 \quad (3)$$

Apply the no slip boundary condition at  $r = R$  into equation (3), we get

$$c_2 = - \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} \frac{1}{\left( 1 + \frac{1}{n} \right)} R^{1 + \frac{1}{n}} \quad (4)$$

The fluid velocity then is given as

$$u(r) = \frac{n}{(n+1)} \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} \left( r^{\frac{n+1}{n}} - R^{\frac{n+1}{n}} \right) \quad (5)$$

The volume flow rate is

$$Q = \int_A u dA = \int_0^R 2\pi r \frac{n}{(n+1)} \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} \left( r^{\frac{n+1}{n}} - R^{\frac{n+1}{n}} \right) dr \quad (6)$$

Hence

$$Q = \frac{2n\pi}{(n+1)} \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} \left[ \frac{n}{3n+1} r^{\frac{3n+1}{n}} - \frac{r^2}{2} R^{\frac{n+1}{n}} \right]_0^R = \frac{2n\pi}{(n+1)} \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} R^{\frac{3n+1}{n}} \left( \frac{n}{3n+1} - \frac{1}{2} \right) \quad (7)$$

Simplifying

$$Q = -\frac{n\pi}{(3n+1)} \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} R^{\frac{3n+1}{n}} \quad (8)$$

When  $n = 1$ , then  $k = \mu$ , and  $Q = -\frac{\pi a^4}{8\mu} \frac{\partial p}{\partial x}$ , just like equation (8.13b) in the textbook.

The average velocity is given by

$$\bar{V} = \frac{Q}{A} = \frac{Q}{\pi R^2} = -\frac{n}{(3n+1)} \left( \frac{1}{2k} \frac{\partial p}{\partial x} \right)^{\frac{1}{n}} R^{\frac{n+1}{n}} \quad (9)$$

Based on Eq. (7), the pressure gradient is

$$\frac{\partial p}{\partial x} = -2k \left[ \frac{Q(3n+1)}{n\pi R^{\frac{3n+1}{n}}} \right]^n \quad (10)$$

Substituting  $Q = 1 \mu\text{L}/\text{min} = 1 \times 10^{-9}/60 \text{ m}^3/\text{s}$ ,  $R = 1\text{mm} = 10^{-3} \text{ m}$ , and  $n = 0.5$  into eq.(10):

$$\frac{\partial p}{\partial x} = -2k \left[ \frac{10^{-9}}{60} \frac{(3(0.5)+1)}{0.5\pi^{\frac{3(0.5)+1}{0.5}}} \right]^{0.5} = -325k \text{ Pa/m} \quad \text{for } n = 0.5 \quad (11)$$

Similarly, the required pressure gradients for  $n = 1$  and  $n = 1.5$  can be obtained:

$$\frac{\partial p}{\partial x} = -42.4k \text{ Pa/m, for } n = 1 \quad (12)$$

$$\frac{\partial p}{\partial x} \approx -5.42k \text{ Pa/m, for } n = 1.5 \quad (12)$$

Obviously, the magnitude of the required pressure gradient increases as  $n$  decreases. Among the three types of fluids (pseudoplastic for  $n = 0.5$ , Newtonian for  $n = 1$ , and dilatant for  $n = 1.5$ ), the dilatant fluid requires the lowest pressure pump for the same pipe length.

## Problem 8.62

[Difficulty: 2]

**8.62** The classic Poiseuille flow (Eq. 8.12), is for no-slip conditions at the walls. If the fluid is a gas, and when the mean free path,  $l$  (the average distance a molecule travels before collision with another molecule), is comparable to the length-scale  $L$  of the flow, slip will occur at the walls, and the flow rate and velocity will be increased for a given pressure gradient. In Eq. 8.11,  $c_1$  will still be zero, but  $c_2$  must satisfy the slip condition  $u = l \partial u / \partial r$  at  $r = R$ . Derive the velocity profile and flow rate of gas flow in a micro- or nanotube which has such a slip velocity on the wall. Calculate the flow rate when  $R = 10 \mu\text{m}$ ,  $\mu = 1.84 \times 10^{-5} \text{ N} \cdot \text{s}/\text{m}^2$ , the mean free path  $l = 68 \text{ nm}$ , and  $-\partial p / \partial x = 1.0 \times 10^6 \text{ Pa}/\text{m}$ .

**Given:** Fully developed flow in a pipe; slip boundary condition on the wall

**Find:** Velocity profile and flow rate

**Solution:**

Similar to the example described in Section 8.3, one obtained

$$u = \frac{r^2}{4\mu} \frac{\partial p}{\partial x} + c_2 \quad (1)$$

The constant  $c_2$  will be determined by the slip velocity boundary condition at  $r = R$ :

$$u = l \frac{\partial u}{\partial r} \quad (2)$$

and one obtains

$$c_2 = \frac{R^2}{4\mu} \frac{\partial p}{\partial x} \left( 2 \frac{l}{R} - 1 \right) \quad (3)$$

Substituting  $c_2$  into Eq.(1), one obtains

$$u = -\frac{1}{4\mu} \frac{\partial p}{\partial x} (R^2 - r^2 + 2lR) \quad (4)$$

The volume flow rate is

$$Q = \int_0^R u 2\pi r dr = -\frac{\pi R^4}{8\mu} \frac{\partial p}{\partial x} \left[ 1 + 4 \frac{l}{R} \right] \quad (5)$$

Substituting  $R = 10 \mu\text{m}$ ,  $\mu = 1.84 \times 10^{-5} \text{ N} \cdot \text{s}/\text{m}^2$ , mean free path  $l = 68 \text{ nm}$ , and  $-\frac{\partial p}{\partial x} = 1.0 \times 10^6 \text{ Pa}/\text{m}$  into eq. (5),

$$Q = -\frac{\pi (10 \times 10^{-6})^4}{8 \cdot 1.84 \times 10^{-5}} \frac{\text{m}^4}{\text{Pa} \cdot \text{s}} \times (-1.0 \times 10^6) \text{ Pa}/\text{m} \times \left[ 1 + 4 \frac{68 \times 10^{-9}}{10 \times 10^{-6}} \frac{\text{m}}{\text{m}} \right] = 2.19 \times 10^{-10} \text{ m}^3/\text{s}.$$

## Problem 8.63

[Difficulty: 3]

**8.63** The following solution:

$$u = u_0 \left( 1 - \frac{y^2}{a^2} - \frac{z^2}{b^2} \right)$$

can be used as a model for the velocity profile of fully developed pressure-driven flow in a channel with an elliptic cross section. The center of the ellipse is  $(y, z) = (0, 0)$ , and the major axis of length  $a$  and the minor axis of length  $b$  are parallel to the  $y$  axis and  $z$  axes, respectively. The axial pressure gradient,  $\partial p / \partial x$ , is constant. Based on the Navier–Stokes equations, determine the maximum velocity  $u_0$  in terms of  $a$ ,  $b$ , viscosity  $\mu$ , and  $\partial p / \partial x$ . Letting  $(\rho, \phi)$  be the radial and azimuthal polar coordinates, respectively, of a unit disk ( $0 \leq \rho \leq 1$  and  $0 \leq \phi \leq 2\pi$ ), the coordinates  $(y, z)$  and the velocity  $u(y, z)$  can be expressed as functions of  $(\rho, \phi)$ :

$$y(\rho, \phi) = a\rho \cos \phi \quad z(\rho, \phi) = b\rho \sin \phi \quad u(\rho, \phi) = u_0(1 - \rho^2)$$

The flow rate is  $Q = \int u(y, z) dy dz = ab \int_0^{2\pi} \int_0^1 \rho u(\rho, \phi) d\rho d\phi$ . Derive the flow rate of fully developed pressure-driven flow in an elliptic pipe. Compare the flow rates in a channel with an elliptic cross section with  $a = 1.5R$  and  $b = R$  and in a pipe of radius  $R$  with the same pressure gradient.

**Given:** Fully developed flow, velocity profile, and expression to calculate the flow rate

**Find:** Velocity and flow rate

**Solution:**

For the fully developed flow, the N-S equations can be simplified to

$$\mu \left( \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} \right) = \frac{\partial p}{\partial x} = \text{constant} \quad (1)$$

Substituting the trial solution in equation (1), one obtains

$$-2\mu u_0 \left( \frac{1}{a^2} + \frac{1}{b^2} \right) = \frac{\partial p}{\partial x} \quad (2)$$

Rearrange it and one obtains

$$u_0 = -\frac{a^2 b^2}{2\mu(a^2 + b^2)} \frac{\partial p}{\partial x} \quad (3)$$

The flow rate is

$$Q = \int u(y, z) dy dz = ab \int_0^{2\pi} \int_0^1 \rho u(\rho, \phi) d\rho d\phi \quad (4)$$

Substituting  $u(\rho, \phi) = u_0(1 - \rho^2)$  into Eq. (4) and integrating twice:  $Q = ab \int_0^{2\pi} \int_0^1 \rho u_0(1 - \rho^2) d\rho d\phi = \frac{1}{2} \pi ab u_0$  (5)

Substituting  $u_0$  into (5), one obtains

$$Q = \frac{1}{2} \pi ab u_0 = -\frac{\pi a^3 b^3}{4\mu(a^2 + b^2)} \frac{\partial p}{\partial x} \quad (6)$$

For a pipe radius  $R$ ,  $a = b = R$ , from equation (6),

$$Q_{pipe} = \frac{1}{8} \left( -\frac{\pi R^4}{\mu} \frac{\partial p}{\partial x} \right)$$

which is the same as equation (8.13b) in the book.




For a channel with an elliptic cross-section with  $a = R$  and  $b = 1.5R$ , from equation (6), one has

$$Q_{pipe} = \frac{29}{104} \left( -\frac{\pi R^4}{\mu} \frac{\partial p}{\partial x} \right).$$

## Problem 8.64

[Difficulty: 2]

**8.64** For pressure-driven, steady, fully developed laminar flow of an incompressible fluid through a straight channel of length  $L$ , we can define the hydraulic resistance as  $R_{\text{hyd}} = \Delta p/Q$ , where  $\Delta p$  is the pressure drop and  $Q$  is the flow rate (analogous to the electrical resistance  $R_{\text{elec}} = \Delta V/I$ , where  $\Delta V$  is the electrical potential drop and  $I$  is the electric current). The following table summarizes the hydraulic resistance of channels with different cross sectional shapes [30]:

Shape	Formula for $R_{\text{hyd}}$	Computed $R_{\text{hyd}}$
Circle 	$\frac{8\mu L}{\pi a^4}$	
Ellipse 	$\frac{4\mu L[1 + (b/a)^2]}{\pi ab^3}$	
Triangle 	$\frac{320\mu L}{\sqrt{3}a^4}$	
Two plates 	$\frac{12\mu L}{h^3 w}$	
Rectangle 	$\frac{12\mu L}{h^3 w[1 - 0.63(h/w)]}$	
Square 	$\frac{12\mu L}{0.37h^4}$	

Calculate the hydraulic resistance of a straight channel with the listed cross-sectional shapes using the following parameters:  $\mu = 1 \text{ mPa} \cdot \text{s}$  (water),  $L = 10 \text{ mm}$ ,  $a = 100 \text{ } \mu\text{m}$ ,  $b = 33 \text{ } \mu\text{m}$ ,  $h = 100 \text{ } \mu\text{m}$ , and  $w = 300 \text{ } \mu\text{m}$ . Based on the calculated hydraulic resistance, which shape is the most energy efficient to pump water?

**Given:** The expression of hydraulic resistance of straight channels with different cross sectional shapes

**Find:** Hydraulic resistance

**Solution:**

Based on the expressions of hydraulic resistance listed in the table, one obtains

Using the circle as the example,

$$R_{\text{hyd}} = \frac{8}{\pi} \mu L \frac{1}{a^4} = \frac{8}{\pi} \frac{1 \times 10^{-3} \text{ Pa} \cdot \text{s} \times 10 \times 10^{-3} \text{ m}}{(1 \times 10^{-4})^4 \text{ m}^4} = 0.254 \times 10^{12} \text{ Pa} \cdot \text{s}/\text{m}^3$$

The results are

Shape	$R_{\text{hyd}} (10^{12} \text{ Pa s}/\text{m}^3)$
Circle	0.25
Ellipse	3.93
Triangle	18.48
Two plates	0.40
Rectangle	0.51
Square	3.24

Comparing the values of the hydraulic resistances, a straight channel with a circular cross section is the most energy efficient to pump fluid with a fixed volumetric flow rate; the triangle is the worst.

## Problem 8.65

[Difficulty: 3]

**8.65** In a food industry plant, two immiscible fluids are pumped through a tube such that fluid 1 ( $\mu_1 = 0.5 \text{ N}\cdot\text{s}/\text{m}^2$ ) forms an inner core and fluid 2 ( $\mu_2 = 5 \text{ N}\cdot\text{s}/\text{m}^2$ ) forms an outer annulus. The tube has  $D = 5 \text{ mm}$  diameter and length  $L = 5 \text{ m}$ . Derive and plot the velocity distribution if the applied pressure difference,  $\Delta p$ , is 5 MPa.

**Given:** Two-fluid flow in tube

**Find:** Velocity distribution; Plot

**Solution:**

Given data  $D = 5\text{-mm}$        $L = 5\text{-m}$        $\Delta p = -5\text{-MPa}$        $\mu_1 = 0.5 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$        $\mu_2 = 5 \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

From Section 8-3 for flow in a pipe, Eq. 8.11 can be applied to either fluid

$$u = \frac{r^2}{4\cdot\mu} \cdot \left( \frac{\partial}{\partial x} p \right) + \frac{c_1}{\mu} \cdot \ln(r) + c_2$$

Applying this to fluid 1 (inner fluid) and fluid 2 (outer fluid)

$$u_1 = \frac{r^2}{4\cdot\mu_1} \cdot \frac{\Delta p}{L} + \frac{c_1}{\mu_1} \cdot \ln(r) + c_2 \qquad u_2 = \frac{r^2}{4\cdot\mu_2} \cdot \frac{\Delta p}{L} + \frac{c_3}{\mu_2} \cdot \ln(r) + c_4$$

We need four BCs. Two are obvious  $r = \frac{D}{2}$        $u_2 = 0$  (1)       $r = \frac{D}{4}$        $u_1 = u_2$  (2)

The third BC comes from the fact that the axis is a line of symmetry

$$r = 0 \qquad \frac{du_1}{dr} = 0 \qquad (3)$$

The fourth BC comes from the fact that the stress at the interface generated by each fluid is the same

$$r = \frac{D}{4} \qquad \mu_1 \cdot \frac{du_1}{dr} = \mu_2 \cdot \frac{du_2}{dr} \qquad (4)$$

Using these four BCs  $\frac{\left(\frac{D}{2}\right)^2}{4\cdot\mu_2} \cdot \frac{\Delta p}{L} + \frac{c_3}{\mu_2} \cdot \ln\left(\frac{D}{2}\right) + c_4 = 0$        $\frac{\left(\frac{D}{4}\right)^2}{4\cdot\mu_1} \cdot \frac{\Delta p}{L} + \frac{c_1}{\mu_1} \cdot \ln\left(\frac{D}{4}\right) + c_2 = \frac{\left(\frac{D}{4}\right)^2}{4\cdot\mu_2} \cdot \frac{\Delta p}{L} + \frac{c_3}{\mu_2} \cdot \ln\left(\frac{D}{4}\right) + c_4$

$$\lim_{r \rightarrow 0} \frac{c_1}{\mu_1 \cdot r} = 0 \qquad \frac{D}{8} \cdot \frac{\Delta p}{L} + \frac{4\cdot c_1}{D} = \frac{D}{8} \cdot \frac{\Delta p}{L} + \frac{4\cdot c_3}{D}$$

Hence, after some algebra

$$c_1 = 0 \quad (\text{To avoid singularity}) \qquad c_2 = -\frac{D^2 \cdot \Delta p}{64 \cdot L} \cdot \frac{(\mu_2 + 3 \cdot \mu_1)}{\mu_1 \cdot \mu_2} \qquad c_3 = 0 \qquad c_4 = -\frac{D^2 \cdot \Delta p}{16 \cdot L \cdot \mu_2}$$

The velocity distributions are then

$$u_1(r) = \frac{\Delta p}{4 \cdot \mu_1 \cdot L} \cdot \left[ r^2 - \left( \frac{D}{2} \right)^2 \cdot \frac{(\mu_2 + 3 \cdot \mu_1)}{4 \cdot \mu_2} \right] \quad u_2(r) = \frac{\Delta p}{4 \cdot \mu_2 \cdot L} \cdot \left[ r^2 - \left( \frac{D}{2} \right)^2 \right]$$


(Note that these result in the same expression if  $\mu_1 = \mu_2$ , i.e., if we have one fluid)

Evaluating either velocity at  $r = D/4$  gives the velocity at the interface

$$u_{\text{interface}} = -\frac{3 \cdot D^2 \cdot \Delta p}{64 \cdot \mu_2 \cdot L} \quad u_{\text{interface}} = -\frac{3}{64} \times (0.005 \cdot \text{m})^2 \times \left( -5 \times 10^6 \cdot \frac{\text{N}}{\text{m}^2} \right) \times \frac{\text{m}^2}{5 \cdot \text{N} \cdot \text{s}} \times \frac{1}{5 \cdot \text{m}} \quad u_{\text{interface}} = 0.234 \frac{\text{m}}{\text{s}}$$

Evaluating  $u_1$  at  $r = 0$  gives the maximum velocity

$$u_{\text{max}} = -\frac{D^2 \cdot \Delta p \cdot (\mu_2 + 3 \cdot \mu_1)}{64 \cdot \mu_1 \cdot \mu_2 \cdot L} \quad u_{\text{max}} = -\frac{1}{64} \times (0.005 \cdot \text{m})^2 \times \left( -5 \times 10^6 \cdot \frac{\text{N}}{\text{m}^2} \right) \times \frac{5 + 3 \times 0.5}{5 \times .5} \cdot \frac{\text{m}^2}{\text{N} \cdot \text{s}} \times \frac{1}{5 \cdot \text{m}} \quad u_{\text{max}} = 1.02 \frac{\text{m}}{\text{s}}$$



The velocity distributions can be plotted in *Excel*

## Problem 8.66

[Difficulty: 2]

**8.66** A horizontal pipe carries fluid in fully developed turbulent flow. The static pressure difference measured between two sections is 750 psi. The distance between the sections is 15 ft, and the pipe diameter is 3 in. Calculate the shear stress,  $\tau_w$ , that acts on the walls.

**Given:** Turbulent pipe flow

**Find:** Wall shear stress

**Solution:**

Basic equation 
$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad (\text{Eq. 4.18a})$$

Assumptions 1) Horizontal pipe 2) Steady flow 3) Fully developed flow

With these assumptions the x momentum equation becomes

$$p_1 \cdot \frac{\pi \cdot D^2}{4} + \tau_w \cdot \pi \cdot D \cdot L - p_2 \cdot \frac{\pi \cdot D^2}{4} = 0 \quad \text{or} \quad \tau_w = \frac{(p_2 - p_1) \cdot D}{4 \cdot L} = -\frac{\Delta p \cdot D}{4 \cdot L}$$
$$\tau_w = -\frac{1}{4} \times 750 \cdot \text{psi} \times \frac{3}{15} \quad \tau_w = -3.13 \cdot \text{psi}$$

Since  $\tau_w$  is negative it acts to the left on the fluid, to the right on the pipe wall

## Problem 8.67

[Difficulty: 2]

**8.67** One end of a horizontal pipe is attached using glue to a pressurized tank containing liquid, and the other has a cap attached. The inside diameter of the pipe is 3 in., and the tank pressure is 30 psig. Find the force the glue must withstand with the cap on, and the force it must withstand when the cap is off and the liquid is discharging to atmosphere.

**Given:** Pipe glued to tank

**Find:** Force glue must hold when cap is on and off

**Solution:**

Basic equation 
$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad (\text{Eq. 4.18a})$$

First solve when the cap is on. In this static case

$$F_{\text{glue}} = \frac{\pi \cdot D^2}{4} \cdot p_1 \quad \text{where } p_1 \text{ is the tank pressure}$$

Second, solve for when flow is occurring:

Assumptions 1) Horizontal pipe 2) Steady flow 3) Fully developed flow

With these assumptions the x momentum equation becomes

$$p_1 \cdot \frac{\pi \cdot D^2}{4} + \tau_w \cdot \pi \cdot D \cdot L - p_2 \cdot \frac{\pi \cdot D^2}{4} = 0$$

Here  $p_1$  is again the tank pressure and  $p_2$  is the pressure at the pipe exit; the pipe exit pressure is  $p_{\text{atm}} = 0$  kPa gage. Hence

$$F_{\text{pipe}} = F_{\text{glue}} = -\tau_w \cdot \pi \cdot D \cdot L = \frac{\pi \cdot D^2}{4} \cdot p_1$$

We conclude that in each case the force on the glue is the same! When the cap is on the glue has to withstand the tank pressure; when the cap is off, the glue has to hold the pipe in place against the friction of the fluid on the pipe, which is equal in magnitude to the pressure drop.

$$F_{\text{glue}} = \frac{\pi}{4} \times (3 \cdot \text{in})^2 \times 30 \cdot \frac{\text{lbf}}{\text{in}^2} \quad F_{\text{glue}} = 212 \cdot \text{lbf}$$

## Problem 8.68

[Difficulty: 2]

**8.68** Kerosene is pumped through a smooth tube with inside diameter  $D = 30$  mm at close to the critical Reynolds number. The flow is unstable and fluctuates between laminar and turbulent states, causing the pressure gradient to intermittently change from approximately  $-4.5$  kPa/m to  $-11$  kPa/m. Which pressure gradient corresponds to laminar, and which to turbulent, flow? For each flow, compute the shear stress at the tube wall, and sketch the shear stress distributions.

**Given:** Data on pressure drops in flow in a tube

**Find:** Which pressure drop is laminar flow, which turbulent

**Solution:**

Given data  $\frac{\partial}{\partial x} p_1 = -4.5 \cdot \frac{\text{kPa}}{\text{m}}$   $\frac{\partial}{\partial x} p_2 = -11 \cdot \frac{\text{kPa}}{\text{m}}$   $D = 30 \cdot \text{mm}$

From Section 8-4, a force balance on a section of fluid leads to

$$\tau_w = -\frac{R}{2} \cdot \frac{\partial}{\partial x} p = -\frac{D}{4} \cdot \frac{\partial}{\partial x} p$$

Hence for the two cases

$$\tau_{w1} = -\frac{D}{4} \cdot \frac{\partial}{\partial x} p_1 \quad \tau_{w1} = 33.8 \text{ Pa}$$

$$\tau_{w2} = -\frac{D}{4} \cdot \frac{\partial}{\partial x} p_2 \quad \tau_{w2} = 82.5 \text{ Pa}$$

Because both flows are at the same nominal flow rate, the higher pressure drop must correspond to the turbulent flow, because, as indicated in Section 8-4, turbulent flows experience additional stresses. Also indicated in Section 8-4 is that for both flows the shear stress varies from zero at the centerline to the maximums computed above at the walls.

The stress distributions are linear in both cases: Maximum at the walls and zero at the centerline.

## Problem 8.69

[Difficulty: 2]

**8.69** The pressure drop between two taps separated in the streamwise direction by 30 ft in a horizontal, fully developed channel flow of water is 1 psi. The cross section of the channel is a 1 in.  $\times$  9 $\frac{1}{2}$  in. rectangle. Calculate the average wall shear stress.

**Given:** Flow through channel

**Find:** Average wall stress

**Solution:**

Basic equation 
$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad (\text{Eq. 4.18a})$$

Assumptions 1) Horizontal pipe 2) Steady flow 3) Fully developed flow

With these assumptions the x momentum equation becomes

$$p_1 \cdot W \cdot H + \tau_w \cdot 2 \cdot L \cdot (W + H) - p_2 \cdot W \cdot H = 0 \quad \text{or} \quad \tau_w = (p_2 - p_1) \cdot \frac{W \cdot H}{2 \cdot (W + H) \cdot L} \quad \tau_w = -\Delta p \cdot \frac{\frac{H}{L}}{2 \cdot \left(1 + \frac{H}{W}\right)}$$

$$\tau_w = -\frac{1}{2} \times 1 \cdot \frac{\text{lbf}}{\text{in}^2} \times \frac{144 \cdot \text{in}^2}{\text{ft}^2} \times \frac{1 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}}}{30 \cdot \text{ft}} \times \left( \frac{1}{9.5 \cdot \text{in} \times \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} + 1 + \frac{1 \cdot \text{ft}}{30 \cdot \text{ft}}} \right) \quad \tau_w = -0.195 \cdot \frac{\text{lbf}}{\text{ft}^2} \quad \tau_w = -1.35 \times 10^{-3} \cdot \text{psi}$$

Since  $\tau_w < 0$ , it acts to the left on the fluid, to the right on the channel wall

### Problem 8.70

[Difficulty: 3]

**8.70** A liquid drug, with the viscosity and density of water, is to be administered through a hypodermic needle. The inside diameter of the needle is 0.25 mm and its length is 50 mm. Determine (a) the maximum volume flow rate for which the flow will be laminar, (b) the pressure drop required to deliver the maximum flow rate, and (c) the corresponding wall shear stress.

Solution: Flow will be laminar for  $Re < 2300$ .

$$Re = \frac{\rho \bar{v} D}{\mu} = \frac{\bar{v} D}{\nu} = \frac{Q}{A} \frac{D}{\nu} = \frac{4Q}{\pi D^2 \nu} = \frac{4Q}{\pi \nu D} < 2300$$

Thus (at  $T = 20^\circ\text{C}$ )

$$Q < \frac{2300 \pi \nu D}{4} = \frac{2300 \pi}{4} \times 1.0 \times 10^{-6} \text{ m}^2/\text{s} \times 0.00025 \text{ m} = 4.52 \times 10^{-7} \text{ m}^3/\text{s}$$

(This flow rate corresponds to 27.1 mL/min.)

A force balance on a fluid element shows:

$$\sum F_x = \Delta p \frac{\pi D^2}{4} - \tau_w \pi D L = 0$$

or

$$\Delta p = \tau_w \frac{4L}{D}$$

For laminar pipe flow,  $u = u_{\max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right]$ , from Eq. 8.14. Thus

$$\tau_w = \mu \left. \frac{\partial u}{\partial y} \right|_{y=0} = -\mu \left. \frac{\partial u}{\partial r} \right|_{r=R} = -\mu u_{\max} \left( -\frac{2r}{R^2} \right)_{r=R} = \frac{2\mu u_{\max}}{R}$$

$$\text{But } u_{\max} = 2\bar{v}, \text{ so } \tau_w = \frac{2\mu 2\bar{v}}{D/2} = \frac{8\mu \bar{v}}{D} = 8\rho \nu \bar{v} / D$$

Also


$$\bar{v} = \frac{Q}{A} = \frac{4Q}{\pi D^2} = \frac{4}{\pi} \times 4.52 \times 10^{-7} \frac{\text{m}^3}{\text{s}} \times \frac{1}{(0.00025)^2 \text{ m}^2} = 9.21 \text{ m/s}$$

Thus

$$\tau_w = 8 \times 999 \frac{\text{kg}}{\text{m}^3} \times 1.0 \times 10^{-6} \frac{\text{m}^2}{\text{s}} \times 9.21 \frac{\text{m}}{\text{s}} \times \frac{1}{0.00025 \text{ m}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 294 \text{ N/m}^2 \text{ (294 Pa)}$$

and

$$\Delta p = 4 \times 0.05 \text{ m} \times \frac{1}{0.00025 \text{ m}} \times 294 \frac{\text{N}}{\text{m}^2} = 235 \text{ kPa}$$



## Problem 8.71

[Difficulty: 1]

**8.71** The “pitch-drop” experiment has been running continuously at the University of Queensland since 1927 ([http://www.physics.uq.edu.au/physics\\_museum/pitchdrop.shtml](http://www.physics.uq.edu.au/physics_museum/pitchdrop.shtml)). In this experiment, a funnel pitch is being used to measure the viscosity of pitch. Flow averages at about one drop—*per decade!* Viscosity is calculated using the volume flow rate equation

$$Q = \frac{V}{t} = \frac{\pi D^4 \rho g}{128 \mu} \left(1 + \frac{h}{L}\right)$$

where  $D$  is the diameter of the flow from the funnel,  $h$  is the depth to the pitch in the main body of the funnel,  $L$  is the length of the funnel stem, and  $t$  is the elapsed time. Compare this equation with Eq. 8.13c using hydrostatic force instead of a pressure gradient. After the 6th drop in 1979, they measured that it took 17,708 days for  $4.7 \times 10^{-5} \text{ m}^3$  of pitch to fall. Given the measurements  $D = 9.4 \text{ mm}$ ,  $h = 75 \text{ mm}$ ,  $L = 29 \text{ mm}$ , and  $\rho_{\text{pitch}} = 1.1 \times 10^3 \text{ kg/m}^3$ , what is the viscosity of the pitch?

**Given:** Data from a funnel viscometer filled with pitch.

**Find:** Viscosity of pitch.

**Solution:**

**Basic equation:**  $Q = \frac{V}{t} = \frac{\pi D^4 \rho g}{128 \mu} \left(1 + \frac{h}{L}\right)$  (Volume flow rate)

where  $Q$  is the volumetric flow rate,  $V$  flow volume,  $t$  is the time of flow,  $D$  is the diameter of the funnel stem,  $\rho$  is the density of the pitch,  $\mu$  is the viscosity of the pitch,  $h$  is the depth of the pitch in the funnel body, and  $L$  is the length of the funnel stem.

**Assumption:** Viscous effects above the stem are negligible and the stem has a uniform diameter.

The given or available data is:

$V = 4.7 \times 10^{-5} \text{ m}^3$	$t = 17,708 \text{ days}$	$D = 9.4 \text{ mm}$	
$h = 75 \text{ mm}$	$L = 29 \text{ mm}$		$\rho = 1.1 \times 10^3 \frac{\text{kg}}{\text{m}^3}$

Calculate the flow rate:

$$Q = \frac{V}{t} = \frac{4.7 \times 10^{-5} \text{ m}^3}{17708 \text{ day} \times \frac{24 \text{ hour}}{\text{day}} \times \frac{3600 \text{ s}}{\text{hour}}} = 3.702 \times 10^{-14} \frac{\text{m}^3}{\text{s}}$$

Solve the governing equation for viscosity:

$$\mu = \frac{\pi D^4 \rho g}{128 Q} \left(1 + \frac{h}{L}\right)$$

$$\mu = \frac{\pi \times (9.4 \text{ mm})^4 \times \left(\frac{\text{m}}{1000 \text{ mm}}\right)^4 \times 1.1 \times 10^3 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \left(1 + \frac{75 \text{ mm}}{29 \text{ mm}}\right) \times \frac{\text{N} \times \text{s}^2}{\text{kg} \times \text{m}}}{128 \times 3.702 \times 10^{-14} \frac{\text{m}^3}{\text{s}}}$$

$$\mu = 2.41 \times 10^8 \frac{\text{N} \cdot \text{s}}{\text{m}^2}$$

Compare this to the viscosity of water, which is  $10^{-3} \text{ N} \cdot \text{s/m}^2$ !

Relate this equation to 8.13c for flow driven by a pressure gradient:

$$Q = \frac{\pi \Delta p D^4}{128 \mu L} = \frac{\pi D^4}{128 \mu} \times \frac{\Delta p}{L}.$$

For this problem, the pressure ( $\Delta p$ ) is replaced by the hydrostatic force of the pitch. Consider the pressure variation in a static fluid.

$$\frac{dp}{dz} = -\rho g = -\rho g = \frac{\Delta p}{\Delta z} = \frac{\Delta p}{L+h}.$$

Replacing the term in 8.13c

$$Q = \frac{\pi D^4}{128 \mu} \times \frac{\Delta p}{L} = \frac{\pi D^4}{128 \mu} \times \frac{\rho g \times (L+h)}{L} = \frac{\pi D^4}{128 \mu} \times \rho g \times \left(1 + \frac{h}{L}\right)$$

Hence

$$Q = \frac{V}{t} = \frac{\pi D^4 \rho g}{128 \mu} \left(1 + \frac{h}{L}\right)$$

which is the same as the given equation.



## Problem 8.73

[Difficulty: 3]

**8.73** Laufer [5] measured the following data for mean velocity in fully developed turbulent pipe flow at  $Re_U = 50,000$ :

$\bar{u}/U$	0.996	0.981	0.963	0.937	0.907	0.866	0.831
$y/r$	0.898	0.794	0.691	0.588	0.486	0.383	0.280
$\bar{u}/U$	0.792	0.742	0.700	0.650	0.619	0.551	
$y/R$	0.216	0.154	0.093	0.062	0.041	0.024	

In addition, Laufer measured the following data for mean velocity in fully developed turbulent pipe flow at  $Re_U = 500,000$ :

$\bar{u}/U$	0.997	0.988	0.975	0.959	0.934	0.908	
$y/R$	0.898	0.794	0.691	0.588	0.486	0.383	
$\bar{u}/U$	0.874	0.847	0.818	0.771	0.736	0.690	
$y/R$	0.280	0.216	0.154	0.093	0.062	0.037	

Using *Excel's* trendline analysis, fit each set of data to the "power-law" profile for turbulent flow, Eq. 8.22, and obtain a value of  $n$  for each set. Do the data tend to confirm the validity of Eq. 8.22? Plot the data and their corresponding trendlines on the same graph.

**Given:** Data on mean velocity in fully developed turbulent flow

**Find:** Trendlines for each set; values of  $n$  for each set; plot


**Solution:**

$y/R$	$u/U$
0.898	0.996
0.794	0.981
0.691	0.963
0.588	0.937
0.486	0.907
0.383	0.866
0.280	0.831
0.216	0.792
0.154	0.742
0.093	0.700
0.062	0.650
0.041	0.619
0.024	0.551

$y/R$	$u/U$
0.898	0.997
0.794	0.998
0.691	0.975
0.588	0.959
0.486	0.934
0.383	0.908
0.280	0.874
0.216	0.847
0.154	0.818
0.093	0.771
0.062	0.736
0.037	0.690

Equation 8.22 is

$$\frac{\bar{u}}{U} = \left(\frac{y}{R}\right)^{1/n} = \left(1 - \frac{y}{R}\right)^{1/n}$$



Applying the *Trendline* analysis to each set of data:

At  $Re = 50,000$

$$u/U = 1.017(y/R)^{0.161}$$

with  $R^2 = 0.998$  (high confidence)

Hence  $1/n = 0.161$   
 $n = 6.21$

At  $Re = 500,000$

$$u/U = 1.017(y/R)^{0.117}$$

with  $R^2 = 0.999$  (high confidence)

Hence  $1/n = 0.117$   
 $n = 8.55$

Both sets of data tend to confirm the validity of Eq. 8.22

## Problem 8.74

[Difficulty: 3]

**8.74** Equation 8.23 gives the power-law velocity profile exponent,  $n$ , as a function of centerline Reynolds number,  $Re_U$ , for fully developed turbulent flow in smooth pipes. Equation 8.24 relates mean velocity,  $\bar{V}$ , to centerline velocity,  $U$ , for various values of  $n$ . Prepare a plot of  $\bar{V}/U$  as a function of Reynolds number,  $Re_{\bar{V}}$ .

Solution:

Prepare a Table of values


$Re_U$

$n$  from Eq. 8.23

$\bar{V}/U$  from Eq. 8.24

$$Re_{\bar{V}} = \frac{\bar{V}L}{\nu} = \frac{\bar{V}}{U} Re_U$$

$Re_U$	$n$	$Re_{\bar{V}}$	$V_{avg}/U$
1.90E+04	6.00	1.50E+04	0.791
3.60E+04	6.50	2.90E+04	0.805
6.85E+04	7.00	5.59E+04	0.817
1.29E+05	7.50	1.07E+05	0.827
2.45E+05	8.00	2.05E+05	0.837
4.65E+05	8.50	3.93E+05	0.845
8.80E+05	9.00	7.50E+05	0.853
1.67E+06	9.50	1.44E+06	0.860
3.16E+06	10.0	2.74E+06	0.866



100% RECYCLED PAPER  
 50% RECYCLED FIBER  
 100% RECYCLED INK  
 100% RECYCLED GLUE  
 100% RECYCLED WHITE  
 5 SQUARE  
 42-389 200 RECYCLED WHITE 5 SQUARE  
 MADE IN U.S.A.  
 National Brand



# Problem 8.75

[Difficulty: 3] Part 2/2


To plot  $\beta$  vs  $n$

- $$\bar{U} = \frac{2n^2}{(n+1)(2n+1)} \dots (8.24)$$

- $$\beta = \left[ \frac{\bar{U}}{\sqrt{2}} \right]^2 \frac{n^2}{(n+2)(n+1)}$$

- $$\beta = \frac{(n+1)(2n+1)^2}{4n^2(n+2)}$$

$n$	$\beta$
6.0	1.027
6.5	1.023
7.0	1.020
7.5	1.018
8.0	1.016
8.5	1.014
9.0	1.013
9.5	1.012
10.0	1.011



42-385  
42-386  
42-387  
42-388  
42-389  
42-390  
42-391  
42-392  
42-393  
42-394  
42-395  
42-396  
42-397  
42-398  
42-399  
42-400  
42-401  
42-402  
42-403  
42-404  
42-405  
42-406  
42-407  
42-408  
42-409  
42-410  
42-411  
42-412  
42-413  
42-414  
42-415  
42-416  
42-417  
42-418  
42-419  
42-420  
42-421  
42-422  
42-423  
42-424  
42-425  
42-426  
42-427  
42-428  
42-429  
42-430  
42-431  
42-432  
42-433  
42-434  
42-435  
42-436  
42-437  
42-438  
42-439  
42-440  
42-441  
42-442  
42-443  
42-444  
42-445  
42-446  
42-447  
42-448  
42-449  
42-450  
42-451  
42-452  
42-453  
42-454  
42-455  
42-456  
42-457  
42-458  
42-459  
42-460  
42-461  
42-462  
42-463  
42-464  
42-465  
42-466  
42-467  
42-468  
42-469  
42-470  
42-471  
42-472  
42-473  
42-474  
42-475  
42-476  
42-477  
42-478  
42-479  
42-480  
42-481  
42-482  
42-483  
42-484  
42-485  
42-486  
42-487  
42-488  
42-489  
42-490  
42-491  
42-492  
42-493  
42-494  
42-495  
42-496  
42-497  
42-498  
42-499  
42-500  
42-501  
42-502  
42-503  
42-504  
42-505  
42-506  
42-507  
42-508  
42-509  
42-510  
42-511  
42-512  
42-513  
42-514  
42-515  
42-516  
42-517  
42-518  
42-519  
42-520  
42-521  
42-522  
42-523  
42-524  
42-525  
42-526  
42-527  
42-528  
42-529  
42-530  
42-531  
42-532  
42-533  
42-534  
42-535  
42-536  
42-537  
42-538  
42-539  
42-540  
42-541  
42-542  
42-543  
42-544  
42-545  
42-546  
42-547  
42-548  
42-549  
42-550  
42-551  
42-552  
42-553  
42-554  
42-555  
42-556  
42-557  
42-558  
42-559  
42-560  
42-561  
42-562  
42-563  
42-564  
42-565  
42-566  
42-567  
42-568  
42-569  
42-570  
42-571  
42-572  
42-573  
42-574  
42-575  
42-576  
42-577  
42-578  
42-579  
42-580  
42-581  
42-582  
42-583  
42-584  
42-585  
42-586  
42-587  
42-588  
42-589  
42-590  
42-591  
42-592  
42-593  
42-594  
42-595  
42-596  
42-597  
42-598  
42-599  
42-600  
42-601  
42-602  
42-603  
42-604  
42-605  
42-606  
42-607  
42-608  
42-609  
42-610  
42-611  
42-612  
42-613  
42-614  
42-615  
42-616  
42-617  
42-618  
42-619  
42-620  
42-621  
42-622  
42-623  
42-624  
42-625  
42-626  
42-627  
42-628  
42-629  
42-630  
42-631  
42-632  
42-633  
42-634  
42-635  
42-636  
42-637  
42-638  
42-639  
42-640  
42-641  
42-642  
42-643  
42-644  
42-645  
42-646  
42-647  
42-648  
42-649  
42-650  
42-651  
42-652  
42-653  
42-654  
42-655  
42-656  
42-657  
42-658  
42-659  
42-660  
42-661  
42-662  
42-663  
42-664  
42-665  
42-666  
42-667  
42-668  
42-669  
42-670  
42-671  
42-672  
42-673  
42-674  
42-675  
42-676  
42-677  
42-678  
42-679  
42-680  
42-681  
42-682  
42-683  
42-684  
42-685  
42-686  
42-687  
42-688  
42-689  
42-690  
42-691  
42-692  
42-693  
42-694  
42-695  
42-696  
42-697  
42-698  
42-699  
42-700  
42-701  
42-702  
42-703  
42-704  
42-705  
42-706  
42-707  
42-708  
42-709  
42-710  
42-711  
42-712  
42-713  
42-714  
42-715  
42-716  
42-717  
42-718  
42-719  
42-720  
42-721  
42-722  
42-723  
42-724  
42-725  
42-726  
42-727  
42-728  
42-729  
42-730  
42-731  
42-732  
42-733  
42-734  
42-735  
42-736  
42-737  
42-738  
42-739  
42-740  
42-741  
42-742  
42-743  
42-744  
42-745  
42-746  
42-747  
42-748  
42-749  
42-750  
42-751  
42-752  
42-753  
42-754  
42-755  
42-756  
42-757  
42-758  
42-759  
42-760  
42-761  
42-762  
42-763  
42-764  
42-765  
42-766  
42-767  
42-768  
42-769  
42-770  
42-771  
42-772  
42-773  
42-774  
42-775  
42-776  
42-777  
42-778  
42-779  
42-780  
42-781  
42-782  
42-783  
42-784  
42-785  
42-786  
42-787  
42-788  
42-789  
42-790  
42-791  
42-792  
42-793  
42-794  
42-795  
42-796  
42-797  
42-798  
42-799  
42-800  
42-801  
42-802  
42-803  
42-804  
42-805  
42-806  
42-807  
42-808  
42-809  
42-810  
42-811  
42-812  
42-813  
42-814  
42-815  
42-816  
42-817  
42-818  
42-819  
42-820  
42-821  
42-822  
42-823  
42-824  
42-825  
42-826  
42-827  
42-828  
42-829  
42-830  
42-831  
42-832  
42-833  
42-834  
42-835  
42-836  
42-837  
42-838  
42-839  
42-840  
42-841  
42-842  
42-843  
42-844  
42-845  
42-846  
42-847  
42-848  
42-849  
42-850  
42-851  
42-852  
42-853  
42-854  
42-855  
42-856  
42-857  
42-858  
42-859  
42-860  
42-861  
42-862  
42-863  
42-864  
42-865  
42-866  
42-867  
42-868  
42-869  
42-870  
42-871  
42-872  
42-873  
42-874  
42-875  
42-876  
42-877  
42-878  
42-879  
42-880  
42-881  
42-882  
42-883  
42-884  
42-885  
42-886  
42-887  
42-888  
42-889  
42-890  
42-891  
42-892  
42-893  
42-894  
42-895  
42-896  
42-897  
42-898  
42-899  
42-900  
42-901  
42-902  
42-903  
42-904  
42-905  
42-906  
42-907  
42-908  
42-909  
42-910  
42-911  
42-912  
42-913  
42-914  
42-915  
42-916  
42-917  
42-918  
42-919  
42-920  
42-921  
42-922  
42-923  
42-924  
42-925  
42-926  
42-927  
42-928  
42-929  
42-930  
42-931  
42-932  
42-933  
42-934  
42-935  
42-936  
42-937  
42-938  
42-939  
42-940  
42-941  
42-942  
42-943  
42-944  
42-945  
42-946  
42-947  
42-948  
42-949  
42-950  
42-951  
42-952  
42-953  
42-954  
42-955  
42-956  
42-957  
42-958  
42-959  
42-960  
42-961  
42-962  
42-963  
42-964  
42-965  
42-966  
42-967  
42-968  
42-969  
42-970  
42-971  
42-972  
42-973  
42-974  
42-975  
42-976  
42-977  
42-978  
42-979  
42-980  
42-981  
42-982  
42-983  
42-984  
42-985  
42-986  
42-987  
42-988  
42-989  
42-990  
42-991  
42-992  
42-993  
42-994  
42-995  
42-996  
42-997  
42-998  
42-999  
43-000



MADE IN U.S.A.

## Problem 8.76

[Difficulty: 3]

**8.76** Consider fully developed laminar flow of water between stationary parallel plates. The maximum flow speed, plate spacing, and width are 20 ft/s, 0.075 in. and 1.25 in., respectively. Find the kinetic energy coefficient,  $\alpha$ .

**Given:** Laminar flow between parallel plates

**Find:** Kinetic energy coefficient,  $\alpha$

**Solution:**

Basic Equation: The kinetic energy coefficient,  $\alpha$  is given by

$$\alpha = \frac{\int_A \rho V^3 dA}{\dot{m} \bar{V}^2} \quad (8.26b)$$

From Section 8-2, for flow between parallel plates

$$u = u_{\max} \left[ 1 - \left( \frac{y}{a/2} \right)^2 \right] = \frac{3}{2} \bar{V} \left[ 1 - \left( \frac{y}{a/2} \right)^2 \right]$$

since  $u_{\max} = \frac{3}{2} \bar{V}$ .

Substituting

$$\alpha = \frac{\int_A \rho V^3 dA}{\dot{m} \bar{V}^2} = \frac{\int_A \rho u^3 dA}{\rho \bar{V} A \bar{V}^2} = \frac{1}{A} \int_A \left( \frac{u}{\bar{V}} \right)^3 dA = \frac{1}{wa} \int_{-\frac{a}{2}}^{\frac{a}{2}} \left( \frac{u}{\bar{V}} \right)^3 w dy = \frac{2}{a} \int_0^{\frac{a}{2}} \left( \frac{u}{\bar{V}} \right)^3 dy$$

Then

$$\alpha = \frac{2}{a} \frac{a}{2} \int_0^1 \left( \frac{u}{u_{\max}} \right)^3 \left( \frac{u_{\max}}{\bar{V}} \right)^3 d \left( \frac{y}{a/2} \right) = \left( \frac{3}{2} \right)^3 \int_0^1 (1 - \eta^2)^3 d\eta$$

where  $\eta = \frac{y}{a/2}$

Evaluating,

$$(1 - \eta^2)^3 = 1 - 3\eta^2 + 3\eta^4 - \eta^6$$


The integral is then

$$\alpha = \left( \frac{3}{2} \right)^3 \int_0^1 (1 - 3\eta^2 + 3\eta^4 - \eta^6) d\eta = \left( \frac{3}{2} \right)^3 \left[ \eta - \eta^3 + \frac{3}{5} \eta^5 - \frac{1}{7} \eta^7 \right]_0^1 = \frac{27}{8} \frac{16}{35} = 1.54$$

### Problem 8.77

[Difficulty: 3]

**8.77** Consider fully developed laminar flow in a circular tube. Evaluate the kinetic energy coefficient for this flow.



Solution: Apply definition of kinetic energy coefficient,

$$\alpha = \frac{\int_A \rho V^3 dA}{\dot{m} \bar{V}^2}, \quad \dot{m} = \rho \bar{V} A \quad (8.26b)$$

From the analysis of section 8-3, for flow in a circular tube,

$$u = u_{max} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] = 2\bar{V} \left[ 1 - \left( \frac{r}{R} \right)^2 \right] \quad \text{since } u_{max} = 2\bar{V}$$

Substituting into Eq. 8.25b,

$$\alpha = \frac{\int_A \rho V^3 dA}{\dot{m} \bar{V}^2} = \frac{\int_A \rho u^3 dA}{\rho \bar{V} A \bar{V}^2} = \frac{1}{A} \int_A \left( \frac{u}{\bar{V}} \right)^3 dA = \frac{1}{\pi R^2} \int_0^R \left( \frac{u}{\bar{V}} \right)^3 2\pi r dr = 2 \int_0^1 \left( \frac{u}{\bar{V}} \right)^3 \left( \frac{r}{R} \right) d\left( \frac{r}{R} \right)$$

Then

$$\alpha = 2 \int_0^1 \left( \frac{u}{u_{max}} \right)^3 \left( \frac{u_{max}}{\bar{V}} \right)^3 \left( \frac{r}{R} \right) d\left( \frac{r}{R} \right) = 2(2)^3 \int_0^1 (1-\eta^2)^3 \eta d\eta \quad \text{where } \eta = \frac{r}{R}$$

Evaluating,

$$(1-\eta^2)^3 \eta = \eta - 3\eta^3 + 3\eta^5 - \eta^7$$

The integral is

$$\int_0^1 (1-\eta^2)^3 \eta d\eta = \left[ \frac{\eta^2}{2} - \frac{3}{4} \eta^4 + \frac{3}{6} \eta^6 - \frac{1}{8} \eta^8 \right]_0^1 = \frac{1}{2} - \frac{3}{4} + \frac{1}{2} - \frac{1}{8} = \frac{1}{8}$$

Substituting,

$$\alpha = 16 \int_0^1 (1-\eta^2)^3 \eta d\eta = 16 \times \frac{1}{8} = 2$$

$\alpha$

## Problem 8.78

[Difficulty: 3]

**8.78** Show that the kinetic energy coefficient,  $\alpha$ , for the “power law” turbulent velocity profile of Eq. 8.22 is given by Eq. 8.27. Plot  $\alpha$  as a function of  $Re_{\bar{v}}$ , for  $Re_{\bar{v}} = 1 \times 10^4$  to  $1 \times 10^7$ . When analyzing pipe flow problems it is common practice to assume  $\alpha \approx 1$ . Plot the error associated with this assumption as a function of  $Re_{\bar{v}}$ , for  $Re_{\bar{v}} = 1 \times 10^4$  to  $1 \times 10^7$ .

**Given:** Definition of kinetic energy correction coefficient  $\alpha$

**Find:**  $\alpha$  for the power-law velocity profile; plot

**Solution:**

Equation 8.26b is

$$\alpha = \frac{\int \rho \cdot V^3 dA}{m_{\text{rate}} \cdot V_{\text{av}}^2}$$

where  $V$  is the velocity,  $m_{\text{rate}}$  is the mass flow rate and  $V_{\text{av}}$  is the average velocity

For the power-law profile (Eq. 8.22)

$$V = U \cdot \left(1 - \frac{r}{R}\right)^{\frac{1}{n}}$$

For the mass flow rate

$$m_{\text{rate}} = \rho \cdot \pi \cdot R^2 \cdot V_{\text{av}}$$

Hence the denominator of Eq. 8.26b is

$$m_{\text{rate}} \cdot V_{\text{av}}^2 = \rho \cdot \pi \cdot R^2 \cdot V_{\text{av}}^3$$

We next must evaluate the numerator of Eq. 8.26b

$$\int \rho \cdot V^3 dA = \int \rho \cdot 2 \cdot \pi \cdot r \cdot U^3 \cdot \left(1 - \frac{r}{R}\right)^{\frac{3}{n}} dr$$

$$\int_0^R \rho \cdot 2 \cdot \pi \cdot r \cdot U^3 \cdot \left(1 - \frac{r}{R}\right)^{\frac{3}{n}} dr = \frac{2 \cdot \pi \cdot \rho \cdot R^2 \cdot n^2 \cdot U^3}{(3 + n) \cdot (3 + 2 \cdot n)}$$

To integrate substitute

$$m = 1 - \frac{r}{R} \quad dm = -\frac{dr}{R}$$

Then

$$r = R \cdot (1 - m) \quad dr = -R \cdot dm$$

$$\int_0^R \rho \cdot 2 \cdot \pi \cdot r \cdot U^3 \cdot \left(1 - \frac{r}{R}\right)^{\frac{3}{n}} dr = - \int_1^0 \rho \cdot 2 \cdot \pi \cdot R \cdot (1 - m) \cdot m^{\frac{3}{n}} \cdot R \cdot dm$$

Hence

$$\int \rho \cdot V^3 dA = \int_0^1 \rho \cdot 2 \cdot \pi \cdot R \cdot \left( m^n - m^{\frac{3}{n}+1} \right) \cdot R dm$$

$$\int \rho \cdot V^3 dA = \frac{2 \cdot R^2 \cdot n^2 \cdot \rho \cdot \pi \cdot U^3}{(3+n) \cdot (3+2 \cdot n)}$$

Putting all these results together

$$\alpha = \frac{\int \rho \cdot V^3 dA}{m_{rate} \cdot V_{av}^2} = \frac{\frac{2 \cdot R^2 \cdot n^2 \cdot \rho \cdot \pi \cdot U^3}{(3+n) \cdot (3+2 \cdot n)}}{\rho \cdot \pi \cdot R^2 \cdot V_{av}^3}$$

$$\alpha = \left( \frac{U}{V_{av}} \right)^3 \cdot \frac{2 \cdot n^2}{(3+n) \cdot (3+2 \cdot n)}$$

To plot  $\alpha$  versus  $Re_{V_{av}}$  we use the following parametric relations

$$n = -1.7 + 1.8 \cdot \log(Re_U) \quad (\text{Eq. 8.23})$$

$$\frac{V_{av}}{U} = \frac{2 \cdot n^2}{(n+1) \cdot (2 \cdot n+1)} \quad (\text{Eq. 8.24})$$



$$Re_{V_{av}} = \frac{V_{av}}{U} \cdot Re_U$$

$$\alpha = \left( \frac{U}{V_{av}} \right)^3 \cdot \frac{2 \cdot n^2}{(3+n) \cdot (3+2 \cdot n)} \quad (\text{Eq. 8.27})$$

A value of  $Re_U$  leads to a value for  $n$ ; this leads to a value for  $V_{av}/U$ ; these lead to a value for  $Re_{V_{av}}$  and  $\alpha$

The plots of  $\alpha$ , and the error in assuming  $\alpha = 1$ , versus  $Re_{V_{av}}$  can be done in *Excel*.


$Re_U$	$n$	$V_{av}/U$	$Re_{V_{av}}$	$Alpha$	Error
1.00E+04	5.50	0.776	7.76E+03	1.09	8.2%
2.50E+04	6.22	0.797	1.99E+04	1.07	6.7%
5.00E+04	6.76	0.811	4.06E+04	1.06	5.9%
7.50E+04	7.08	0.818	6.14E+04	1.06	5.4%
1.00E+05	7.30	0.823	8.23E+04	1.05	5.1%
2.50E+05	8.02	0.837	2.09E+05	1.05	4.4%
5.00E+05	8.56	0.846	4.23E+05	1.04	3.9%
7.50E+05	8.88	0.851	6.38E+05	1.04	3.7%
1.00E+06	9.10	0.854	8.54E+05	1.04	3.5%
2.50E+06	9.82	0.864	2.16E+06	1.03	3.1%
5.00E+06	10.4	0.870	4.35E+06	1.03	2.8%
7.50E+06	10.7	0.873	6.55E+06	1.03	2.6%
1.00E+07	10.9	0.876	8.76E+06	1.03	2.5%



## Problem 8.79

[Difficulty: 2]

**8.79** Measurements are made for the flow configuration shown in Fig. 8.12. At the inlet, section ①, the pressure is 70 kPa (gage), the average velocity is 1.75 m/s, and the elevation is 2.25 m. At the outlet, section ②, the pressure, average velocity, and elevation are 45 kPa (gage), 3.5 m/s, and 3 m, respectively. Calculate the head loss in meters. Convert to units of energy per unit mass.



**Given:** Data on flow through elbow

**Find:** Head loss

**Solution:**

Basic equation 
$$\left( \frac{p_1}{\rho \cdot g} + \alpha \cdot \frac{V_1^2}{2 \cdot g} + z_1 \right) - \left( \frac{p_2}{\rho \cdot g} + \alpha \cdot \frac{V_2^2}{2 \cdot g} + z_2 \right) = \frac{h_{IT}}{g} = H_{IT}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1

Then 
$$H_{IT} = \frac{p_1 - p_2}{\rho \cdot g} + \frac{V_1^2 - V_2^2}{2 \cdot g} + z_1 - z_2$$

$$H_{IT} = (70 - 45) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} + \frac{1}{2} \times (1.75^2 - 3.5^2) \cdot \left( \frac{\text{m}}{\text{s}} \right)^2 \times \frac{\text{s}^2}{9.81 \cdot \text{m}} + (2.25 - 3) \cdot H_{IT} = 1.33 \text{ m}$$

In terms of energy/mass 
$$h_{IT} = g \cdot H_{IT} \qquad h_{IT} = 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1.33 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \qquad h_{IT} = 13.0 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg}}$$

## Problem 8.80

[Difficulty: 2]

**8.80** Water flows in a horizontal constant-area pipe; the pipe diameter is 75 mm and the average flow speed is 5 m/s. At the pipe inlet, the gage pressure is 275 kPa, and the outlet is at atmospheric pressure. Determine the head loss in the pipe. If the pipe is now aligned so that the outlet is 15 m above the inlet, what will the inlet pressure need to be to maintain the same flow rate? If the pipe is now aligned so that the outlet is 15 m below the inlet, what will the inlet pressure need to be to maintain the same flow rate? Finally, how much lower than the inlet must the outlet be so that the same flow rate is maintained if both ends of the pipe are at atmospheric pressure (i.e., gravity feed)?

**Given:** Data on flow in a pipe

**Find:** Head loss for horizontal pipe; inlet pressure for different alignments; slope for gravity feed

**Solution:**

The basic equation between inlet (1) and exit (2) is

$$\left( \frac{p_1}{\rho} + \alpha_1 \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad (8.29)$$

Given or available data       $D = 75 \cdot \text{mm}$        $V = 5 \cdot \frac{\text{m}}{\text{s}}$        $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$        $\mu = 0.001 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$

Horizontal pipe data       $p_1 = 275 \cdot \text{kPa}$        $p_2 = 0 \cdot \text{kPa}$       (Gage pressures)       $z_1 = z_2$        $V_1 = V_2$

Equation 8.29 becomes       $h_{IT} = \frac{p_1 - p_2}{\rho}$        $h_{IT} = 275 \cdot \frac{\text{J}}{\text{kg}}$

For an inclined pipe with the same flow rate, the head loss will be the same as above; in addition we have the following new data

$z_1 = 0 \cdot \text{m}$        $z_2 = 15 \cdot \text{m}$

Equation 8.29 becomes       $p_1 = p_2 + \rho \cdot g \cdot (z_2 - z_1) + \rho \cdot h_{IT}$        $p_1 = 422 \cdot \text{kPa}$

For a declining pipe with the same flow rate, the head loss will be the same as above; in addition we have the following new data

$z_1 = 0 \cdot \text{m}$        $z_2 = -15 \cdot \text{m}$

Equation 8.29 becomes       $p_1 = p_2 + \rho \cdot g \cdot (z_2 - z_1) + \rho \cdot h_{IT}$        $p_1 = 128 \cdot \text{kPa}$

For a gravity feed with the same flow rate, the head loss will be the same as above; in addition we have the following new data


$p_1 = 0 \cdot \text{kPa}$       (Gage)

Equation 8.29 becomes       $z_2 = z_1 - \frac{h_{IT}}{g}$        $z_2 = -28.1 \text{ m}$

## Problem 8.81

[Difficulty: 2]

**8.81** For the flow configuration of Fig. 8.12, it is known that the head loss is 1 m. The pressure drop from inlet to outlet is 50 kPa, the velocity doubles from inlet to outlet, and the elevation increase is 2 m. Compute the inlet water velocity.



**Given:** Data on flow through elbow

**Find:** Inlet velocity

**Solution:**

$$\text{Basic equation} \quad \left( \frac{p_1}{\rho \cdot g} + \alpha \cdot \frac{V_1^2}{2 \cdot g} + z_1 \right) - \left( \frac{p_2}{\rho \cdot g} + \alpha \cdot \frac{V_2^2}{2 \cdot g} + z_2 \right) = \frac{h_{IT}}{g} = H_{IT}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1

$$\text{Then} \quad V_2^2 - V_1^2 = (2 \cdot V_1)^2 - V_1^2 = 3 \cdot V_1^2 = \frac{2 \cdot (p_1 - p_2)}{\rho} + 2 \cdot g \cdot (z_1 - z_2) - 2 \cdot g \cdot H_{IT}$$

$$V_1 = \sqrt{\frac{2}{3} \cdot \left[ \frac{(p_1 - p_2)}{\rho} + g \cdot (z_1 - z_2) - g \cdot H_{IT} \right]}$$

$$V_1 = \sqrt{\frac{2}{3} \times \left[ 50 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} + \frac{9.81 \cdot \text{m}}{\text{s}^2} \times (-2) \cdot \text{m} - 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1 \cdot \text{m} \right]} \quad V_1 = 3.70 \frac{\text{m}}{\text{s}}$$

## Problem 8.82

[Difficulty: 2]

**8.82** For a given volume flow rate and piping system, will the pressure loss be greater for hot water or cold water? Explain.

**Given:** A given piping system and volume flow rate with two liquid choices.

**Find:** Which liquid has greater pressure loss

**Solution:**

**Governing equation:**

$$\left( \frac{P_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + gz_1 \right) - \left( \frac{P_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + gz_2 \right) = h_{l_r}$$
$$h_{l_r} = h_l + h_{l_m} = f \frac{L}{D} \frac{\bar{V}^2}{2} + K \frac{\bar{V}^2}{2}$$

**Assumption:** 1) Steady flow 2) Incompressible 3) Neglect elevation effects 4) Neglect velocity effects

$$\Delta P = \rho f \frac{L}{D} \frac{\bar{V}^2}{2} + \rho K \frac{\bar{V}^2}{2}$$

From Table A.8 it is seen that hot water has a lower density and lower kinematic viscosity than cold water.

The lower density means that for a constant minor loss coefficient ( $K$ ) and velocity the pressure loss due to minor losses will be less for hot water.

The lower kinematic viscosity means that for a constant diameter and velocity the Reynolds number will increase. From Figure 8.13 it is seen that increasing the Reynolds number will either result in a decreased friction factor ( $f$ ) or no change in the friction factor. This potential decrease in friction factor combined with a lower density for hot water means that the pressure loss due to major losses will be less for hot water as well.

Cold water has a greater pressure drop

## Problem 8.83

[Difficulty: 2]

**8.83** Consider the pipe flow from the water tower of Example 8.7. After another 5 years the pipe roughness has increased such that the flow is fully turbulent and  $f=0.035$ . Find by how much the flow rate is decreased.

**Given:** Increased friction factor for water tower flow

**Find:** How much flow is decreased

**Solution:**

Basic equation from Example 8.7

$$V_2 = \sqrt{\frac{2 \cdot g \cdot (z_1 - z_2)}{f \cdot \left(\frac{L}{D} + 8\right) + 1}}$$

where

$$L = 680 \cdot \text{ft} \qquad D = 4 \cdot \text{in} \qquad z_1 - z_2 = 80 \cdot \text{ft}$$

With  $f = 0.0308$ , we obtain

$$V_2 = 8.97 \cdot \frac{\text{ft}}{\text{s}} \qquad \text{and } Q = 351 \text{ gpm}$$

We need to recompute with  $f = 0.035$

$$V_2 = \sqrt{2 \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 80 \cdot \text{ft} \times \frac{1}{0.035 \cdot \left(\frac{680}{\frac{4}{12}} + 8\right) + 1}} \qquad V_2 = 8.42 \cdot \frac{\text{ft}}{\text{s}}$$

Hence

$$Q = V_2 \cdot A = V_2 \cdot \frac{\pi \cdot D^2}{4}$$

$$Q = 8.42 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} \times \left(\frac{4}{12} \cdot \text{ft}\right)^2 \times \frac{7.48 \cdot \text{gal}}{1 \cdot \text{ft}^3} \times \frac{60 \cdot \text{s}}{1 \cdot \text{min}} \qquad Q = 330 \cdot \text{gpm}$$

(From Table G.2  $1 \text{ ft}^3 = 7.48 \text{ gal}$ )

Hence the flow is decreased by

$$(330 - 309) \cdot \text{gpm} = 21 \cdot \text{gpm}$$

## Problem 8.84

[Difficulty: 2]

**8.84** Consider the pipe flow from the water tower of Problem 8.83. To increase delivery, the pipe length is reduced from 600 ft to 450 ft (the flow is still fully turbulent and  $f = 0.035$ ). What is the flow rate?

**Given:** Increased friction factor for water tower flow, and reduced length

**Find:** How much flow is decreased

**Solution:**

Basic equation from Example 8.7

$$V_2 = \sqrt{\frac{2 \cdot g \cdot (z_1 - z_2)}{f \cdot \left(\frac{L}{D} + 8\right) + 1}}$$

where now we have

$$L = 530 \cdot \text{ft}$$

$$D = 4 \cdot \text{in}$$

$$z_1 - z_2 = 80 \cdot \text{ft}$$

We need to recompute with  $f = 0.04$

$$V_2 = \sqrt{2 \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 80 \cdot \text{ft} \times \frac{1}{0.035 \cdot \left(\frac{530}{\frac{4}{12}} + 8\right) + 1}} \quad V_2 = 9.51 \cdot \frac{\text{ft}}{\text{s}}$$

Hence

$$Q = V_2 \cdot A = V_2 \cdot \frac{\pi \cdot D^2}{4}$$

$$Q = 9.51 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} \times \left(\frac{4}{12} \cdot \text{ft}\right)^2 \times \frac{7.48 \cdot \text{gal}}{1 \cdot \text{ft}^3} \times \frac{60 \cdot \text{s}}{1 \cdot \text{min}}$$


$$Q = 372 \cdot \text{gpm}$$

(From Table G.2  $1 \text{ ft}^3 = 7.48 \text{ gal}$ )

### Problem 8.85

[Difficulty: 2]

**8.85** Water flows from a horizontal tube into a large tank. The tube is located 2.5 m below the free surface of water in the tank. The head loss is 2 J/kg. Compute the average flow speed in the tube.



Solution:

Apply definition of head loss, Eq 8.29,

$$\left( \frac{P_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1 \right) - \left( \frac{P_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2 \right) = h_{eT}$$

At free surface,  $V_2 = 0$ ,  $P_2 = P_{atm}$

At tube discharge  $P_1 = P_{atm}$ ,  $z_1 = 0$ . Assume  $\alpha_1 = 1$

Then

$$g d + \frac{V_1^2}{2} - g d = h_{eT}$$

$$V_1^2 = 2 h_{eT} = 2 \times 2 \frac{N \cdot m}{kg} \times \frac{kg \cdot m}{N \cdot s^2} = 4 \frac{m^2}{s^2}$$

$$V_1 = 2 \text{ m/s}$$

$V_1$



## Problem 8.86

[Difficulty: 2]

**8.86** The average flow speed in a constant-diameter section of the Alaskan pipeline is 2.5 m/s. At the inlet, the pressure is 8.25 MPa (gage) and the elevation is 45 m; at the outlet, the pressure is 350 kPa (gage) and the elevation is 115 m. Calculate the head loss in this section of pipeline.

**Given:** Data on flow through Alaskan pipeline

**Find:** Head loss

**Solution:**

Basic equation 
$$\left( \frac{p_1}{\rho_{\text{oil}} \cdot g} + \alpha \cdot \frac{V_1^2}{2 \cdot g} + z_1 \right) - \left( \frac{p_2}{\rho_{\text{oil}} \cdot g} + \alpha \cdot \frac{V_2^2}{2 \cdot g} + z_2 \right) = \frac{h_{\text{IT}}}{g} = H_{\text{IT}}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) SG = 0.9 (Table A.2)

Then 
$$H_{\text{IT}} = \frac{p_1 - p_2}{\text{SG}_{\text{oil}} \cdot \rho_{\text{H}_2\text{O}} \cdot g} + z_1 - z_2$$


$$H_{\text{IT}} = (8250 - 350) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{1}{0.9} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} + (45 - 115) \cdot \text{m} \quad H_{\text{IT}} = 825 \text{ m}$$

In terms of energy/mass  $h_{\text{IT}} = g \cdot H_{\text{IT}}$  
$$h_{\text{IT}} = 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 825 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad h_{\text{IT}} = 8.09 \cdot \frac{\text{kN} \cdot \text{m}}{\text{kg}}$$

### Problem 8.87

[Difficulty: 2]

**8.87** At the inlet to a constant-diameter section of the Alaskan pipeline, the pressure is 8.5 MPa and the elevation is 45 m; at the outlet the elevation is 115 m. The head loss in this section of pipeline is 6.9 kJ/kg. Calculate the outlet pressure.



Solution:

Computing equation: 
$$\left( \frac{P_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1 \right) - \left( \frac{P_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2 \right) = h_{L,T} \quad (8.29)$$

- Assumptions: (1) incompressible flow, so  $\bar{V}_1 = \bar{V}_2$   
 (2) fully developed so  $\alpha_1 = \alpha_2$   
 (3) SG crude oil = 0.90 (Table A.2)

Then

$$\begin{aligned}
 P_2 &= P_1 + \rho g (z_1 - z_2) - \rho h_{L,T} \\
 &= 8.5 \times 10^6 \text{ N/m}^2 + 0.9 \times 999 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times (-70 \text{ m}) \times \frac{1.5^2}{0.6^5 \text{ m}} \\
 &\quad - 0.9 \times 999 \frac{\text{kg}}{\text{m}^3} \times 6.9 \times 10^3 \frac{\text{N}\cdot\text{m}}{\text{kg}}
 \end{aligned}$$

$P_2 = 1.68 \text{ MPa}$

$P_2$

40 PROBLEM SHEETS IN ALASKA'S 2004  
 42 2004 2005 SHEETS RELEASED  
 42 2004 400 RECYCLED PAPER  
 42 2004 2005 RECYCLED PAPER SOLUTIONS  
 MADE IN U.S.A.



## Problem 8.88

[Difficulty: 2]

**8.88** Water flows at 10 L/min through a horizontal 15-mm-diameter tube. The pressure drop along a 20-m length of tube is 85 kPa. Calculate the head loss.

**Given:** Data on flow through a tube

**Find:** Head loss

**Solution:**

Basic equation

$$\left( \frac{p_1}{\rho \cdot g} + \alpha \cdot \frac{V_1^2}{2 \cdot g} + z_1 \right) - \left( \frac{p_2}{\rho \cdot g} + \alpha \cdot \frac{V_2^2}{2 \cdot g} + z_2 \right) = \frac{h_{IT}}{g} = H_{IT}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1

Given or available data

$$Q = 10 \cdot \frac{\text{L}}{\text{min}} \quad D = 15 \cdot \text{mm} \quad \Delta p = 85 \cdot \text{kPa} \quad \rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$$

The basic equation reduces to

$$h_{IT} = \frac{\Delta p}{\rho} \quad h_{IT} = 85.1 \frac{\text{m}^2}{\text{s}^2} \quad H_{IT} = \frac{h_{IT}}{g} \quad H_{IT} = 8.68 \text{ m}$$

## Problem 8.89

[Difficulty: 2]

**8.89** Laufer [5] measured the following data for mean velocity near the wall in fully developed turbulent pipe flow at  $Re_U = 50,000$  ( $U = 9.8$  ft/s and  $R = 4.86$  in.) in air:

$\bar{u}/U$	0.343	0.318	0.300	0.264	0.228	0.221	0.179	0.152	0.140
$y/R$	0.0082	0.0075	0.0071	0.0061	0.0055	0.0051	0.0041	0.0034	0.0030

Plot the data and obtain the best-fit slope,  $d\bar{u}/dy$ . Use this to estimate the wall shear stress from  $\tau_w = \mu d\bar{u}/dy$ . Compare this value to that obtained using the friction factor  $f$  computed using (a) the Colebrook formula (Eq. 8.37), and (b) the Blasius correlation (Eq. 8.38).

Solution: "Best-fit" slope is  $\left\{ \begin{array}{l} \text{from analysis} \\ \text{in Excel file} \end{array} \right\} \frac{\bar{u}}{U}$

$$\frac{d(\bar{u}/U)}{d(y/R)} \approx \frac{\Delta(\bar{u}/U)}{\Delta(y/R)} = 39.8$$

$$\frac{d\bar{u}}{dy} = \frac{U d(\bar{u}/U)}{R d(y/R)} = 39.8 \times 9.8 \frac{\text{ft}}{\text{s}} \times \frac{1}{4.86 \text{ in.}} \times \frac{12 \text{ in.}}{\text{ft}} = 963 \text{ s}^{-1}$$

For standard air,  $\mu = 3.72 \times 10^{-7} \text{ lbf} \cdot \text{s} / \text{ft}^2$ , so

$$\tau_w = \mu \frac{d\bar{u}}{dy} = 3.72 \times 10^{-7} \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \times \frac{963}{\text{s}} = 3.58 \times 10^{-4} \text{ lbf} / \text{ft}^2$$

Friction factor is  $f = f(Re, \epsilon/D)$ . For  $Re_U = 50,000$ ,  $n = 6.8$  from Eq. 8.23. Then from Eq. 8.24,

$$\frac{\bar{V}}{U} = \frac{2n^2}{(n+1)(2n+1)} = 0.812 \quad \text{and} \quad Re_{\bar{V}} = 0.812 Re_U = 0.812 \times 50,000 = 40,600$$

Assuming smooth pipe,  $f = 0.0219$  from Eq. 8.37

Balancing forces on a fluid element:  $(p+\Delta p) \frac{\pi D^2}{4} \rightarrow \left[ \text{fluid element} \right] \leftarrow p \frac{\pi D^2}{4}$   
 $\tau_w \pi D L$


$$\text{Then } (p+\Delta p) \frac{\pi D^2}{4} - \tau_w \pi D L - p \frac{\pi D^2}{4} = 0$$

$$\tau_w = \frac{R}{2} \frac{\Delta p}{L} = \frac{D}{4L} f \frac{\rho \bar{V}^2}{2} = \frac{f}{8} \rho \bar{V}^2; \quad \bar{V} = 0.812 U = 0.812 \times 9.8 \frac{\text{ft}}{\text{s}} = 7.96 \text{ ft/sec}$$

Substituting,

$$\tau_w = \frac{0.0219}{8} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times \frac{(7.96)^2 \text{ ft}^2}{\text{s}^2} \times \frac{16 \text{ lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} = 4.13 \times 10^{-4} \text{ lbf} / \text{ft}^2$$


The result calculated from the friction factor is 15% higher than that evaluated graphically!



## Problem 8.90

[Difficulty: 3]

**8.90** Water is pumped at the rate of  $0.075 \text{ m}^3/\text{s}$  from a reservoir  $20 \text{ m}$  above a pump to a free discharge  $35 \text{ m}$  above the pump. The pressure on the intake side of the pump is  $150 \text{ kPa}$  and the pressure on the discharge side is  $450 \text{ kPa}$ . All pipes are commercial steel of  $15 \text{ cm}$  diameter. Determine (a) the head supplied by the pump and (b) the total head loss between the pump and point of free discharge.



**Given:** Data on flow from reservoir

**Find:** Head from pump; head loss

**Solution:**

Basic equations 
$$\left( \frac{p_3}{\rho \cdot g} + \alpha \cdot \frac{V_3^2}{2 \cdot g} + z_3 \right) - \left( \frac{p_4}{\rho \cdot g} + \alpha \cdot \frac{V_4^2}{2 \cdot g} + z_4 \right) = \frac{h_{IT}}{g} = H_{IT} \quad \text{for flow from 3 to 4}$$

$$\left( \frac{p_3}{\rho \cdot g} + \alpha \cdot \frac{V_3^2}{2 \cdot g} + z_3 \right) - \left( \frac{p_2}{\rho \cdot g} + \alpha \cdot \frac{V_2^2}{2 \cdot g} + z_2 \right) = \frac{\Delta h_{\text{pump}}}{g} = H_{\text{pump}} \quad \text{for flow from 2 to 3}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $V_2 = V_3 = V_4$  (constant area pipe)

Then for the pump 
$$H_{\text{pump}} = \frac{p_3 - p_2}{\rho \cdot g}$$

$$H_{\text{pump}} = (450 - 150) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} \quad H_{\text{pump}} = 30.6 \text{ m}$$

In terms of energy/mass 
$$h_{\text{pump}} = g \cdot H_{\text{pump}} \quad h_{\text{pump}} = 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 30.6 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad h_{\text{pump}} = 300 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg}}$$

For the head loss from 3 to 4 
$$H_{IT} = \frac{p_3 - p_4}{\rho \cdot g} + z_3 - z_4$$

$$H_{IT} = (450 - 0) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} \times \frac{\text{s}^2}{9.81 \cdot \text{m}} + (0 - 35) \cdot \text{m} \quad H_{IT} = 10.9 \text{ m}$$

In terms of energy/mass 
$$h_{IT} = g \cdot H_{IT} \quad h_{IT} = 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 10.9 \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad h_{IT} = 107 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg}}$$

## Problem 8.91

[Difficulty: 2]

**8.91** A smooth, 75-mm-diameter pipe carries water (65°C) horizontally. When the mass flow rate is 0.075 kg/s, the pressure drop is measured to be 7.5 Pa per 100 m of pipe. Based on these measurements, what is the friction factor? What is the Reynolds number? Does this Reynolds number generally indicate laminar or turbulent flow? Is the flow actually laminar or turbulent?

**Given:** Data on flow in a pipe

**Find:** Friction factor; Reynolds number; if flow is laminar or turbulent

**Solution:**

Given data  $D = 75 \text{ mm}$   $\frac{\Delta p}{L} = 0.075 \cdot \frac{\text{Pa}}{\text{m}}$   $m_{\text{rate}} = 0.075 \cdot \frac{\text{kg}}{\text{s}}$

From Appendix A  $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$   $\mu = 4 \cdot 10^{-4} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

The governing equations between inlet (1) and exit (2) are

$$\left( \frac{p_1}{\rho} + \alpha_1 \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad (8.29)$$

$$h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34)$$

For a constant area pipe  $V_1 = V_2 = V$

Hence Eqs. 8.29 and 8.34 become  $f = \frac{2 \cdot D}{L \cdot V^2} \cdot \frac{(p_1 - p_2)}{\rho} = \frac{2 \cdot D}{\rho \cdot V^2} \cdot \frac{\Delta p}{L}$

For the velocity  $V = \frac{m_{\text{rate}}}{\rho \cdot \frac{\pi}{4} \cdot D^2}$   $V = 0.017 \frac{\text{m}}{\text{s}}$

Hence  $f = \frac{2 \cdot D}{\rho \cdot V^2} \cdot \frac{\Delta p}{L}$   $f = 0.0390$

The Reynolds number is  $Re = \frac{\rho \cdot V \cdot D}{\mu}$   $Re = 3183$

This Reynolds number indicates the flow is turbulent.

(From Eq. 8.37, at this Reynolds number the friction factor for a smooth pipe is  $f = 0.043$ ; the friction factor computed above thus indicates that, within experimental error, the flow corresponds to turbulent flow in a smooth pipe)



## Problem 8.93

[Difficulty: 3]

**8.93** The Colebrook equation (Eq. 8.37) for computing the turbulent friction factor is implicit in  $f$ . An explicit expression [31] that gives reasonable accuracy is

$$f_0 = 0.25 \left[ \log \left( \frac{e/D}{3.7} + \frac{5.74}{Re^{0.9}} \right) \right]^{-2}$$

Compare the accuracy of this expression for  $f$  with Eq. 8.37 by computing the percentage discrepancy as a function of  $Re$  and  $e/D$ , for  $Re = 10^4$  to  $10^8$ , and  $e/D = 0, 0.0001, 0.001, 0.01$ , and  $0.05$ . What is the maximum discrepancy for these  $Re$  and  $e/D$  values? Plot  $f$  against  $Re$  with  $e/D$  as a parameter.

Using the above formula for  $f_0$ , and Eq. 8.37 for  $f_1$

$e/D =$	0	0.0001	0.0002	0.0005	0.001	0.002	0.005	0.01	0.02	0.05
---------	---	--------	--------	--------	-------	-------	-------	------	------	------

$Re$	$f_0$									
1.00E+04	0.0310	0.0311	0.0313	0.0318	0.0327	0.0342	0.0383	0.0440	0.0534	0.0750
2.50E+04	0.0244	0.0247	0.0250	0.0258	0.0270	0.0291	0.0342	0.0407	0.0508	0.0731
5.00E+04	0.0208	0.0212	0.0216	0.0226	0.0242	0.0268	0.0325	0.0395	0.0498	0.0724
7.50E+04	0.0190	0.0195	0.0200	0.0212	0.0230	0.0258	0.0319	0.0390	0.0494	0.0721
1.00E+05	0.0179	0.0185	0.0190	0.0204	0.0223	0.0253	0.0316	0.0388	0.0493	0.0720
2.50E+05	0.0149	0.0158	0.0167	0.0186	0.0209	0.0243	0.0309	0.0383	0.0489	0.0717
5.00E+05	0.0131	0.0145	0.0155	0.0178	0.0204	0.0239	0.0307	0.0381	0.0488	0.0717
7.50E+05	0.0122	0.0139	0.0150	0.0175	0.0201	0.0238	0.0306	0.0380	0.0487	0.0716
1.00E+06	0.0116	0.0135	0.0148	0.0173	0.0200	0.0237	0.0305	0.0380	0.0487	0.0716
5.00E+06	0.0090	0.0124	0.0140	0.0168	0.0197	0.0235	0.0304	0.0379	0.0487	0.0716
1.00E+07	0.0081	0.0122	0.0139	0.0168	0.0197	0.0235	0.0304	0.0379	0.0486	0.0716
5.00E+07	0.0066	0.0120	0.0138	0.0167	0.0196	0.0234	0.0304	0.0379	0.0486	0.0716
1.00E+08	0.0060	0.0120	0.0137	0.0167	0.0196	0.0234	0.0304	0.0379	0.0486	0.0716

Using the add-in function *Friction factor* from the Web

$e/D =$	0	0.0001	0.0002	0.0005	0.001	0.002	0.005	0.01	0.02	0.05
---------	---	--------	--------	--------	-------	-------	-------	------	------	------


$Re$	$f$									
1.00E+04	0.0309	0.0310	0.0312	0.0316	0.0324	0.0338	0.0376	0.0431	0.0523	0.0738
2.50E+04	0.0245	0.0248	0.0250	0.0257	0.0268	0.0288	0.0337	0.0402	0.0502	0.0725
5.00E+04	0.0209	0.0212	0.0216	0.0226	0.0240	0.0265	0.0322	0.0391	0.0494	0.0720
7.50E+04	0.0191	0.0196	0.0200	0.0212	0.0228	0.0256	0.0316	0.0387	0.0492	0.0719
1.00E+05	0.0180	0.0185	0.0190	0.0203	0.0222	0.0251	0.0313	0.0385	0.0490	0.0718
2.50E+05	0.0150	0.0158	0.0166	0.0185	0.0208	0.0241	0.0308	0.0381	0.0488	0.0716
5.00E+05	0.0132	0.0144	0.0154	0.0177	0.0202	0.0238	0.0306	0.0380	0.0487	0.0716
7.50E+05	0.0122	0.0138	0.0150	0.0174	0.0200	0.0237	0.0305	0.0380	0.0487	0.0716
1.00E+06	0.0116	0.0134	0.0147	0.0172	0.0199	0.0236	0.0305	0.0380	0.0487	0.0716
5.00E+06	0.0090	0.0123	0.0139	0.0168	0.0197	0.0235	0.0304	0.0379	0.0486	0.0716
1.00E+07	0.0081	0.0122	0.0138	0.0168	0.0197	0.0234	0.0304	0.0379	0.0486	0.0716
5.00E+07	0.0065	0.0120	0.0138	0.0167	0.0196	0.0234	0.0304	0.0379	0.0486	0.0716
1.00E+08	0.0059	0.0120	0.0137	0.0167	0.0196	0.0234	0.0304	0.0379	0.0486	0.0716

The error can now be computed

$e/D =$	0	0.0001	0.0002	0.0005	0.001	0.002	0.005	0.01	0.02	0.05
---------	---	--------	--------	--------	-------	-------	-------	------	------	------

$Re$	Error (%)									
1.00E+04	0.29%	0.36%	0.43%	0.61%	0.88%	1.27%	1.86%	<b>2.12%</b>	2.08%	1.68%
2.50E+04	0.39%	0.24%	0.11%	0.21%	0.60%	1.04%	1.42%	1.41%	1.21%	0.87%
5.00E+04	0.63%	0.39%	0.19%	0.25%	0.67%	1.00%	1.11%	0.98%	0.77%	0.52%
7.50E+04	0.69%	0.38%	0.13%	0.35%	0.73%	0.95%	0.93%	0.77%	0.58%	0.38%
1.00E+05	0.71%	0.33%	0.06%	0.43%	0.76%	0.90%	0.81%	0.64%	0.47%	0.30%
2.50E+05	0.65%	0.04%	0.28%	0.64%	0.72%	0.66%	0.48%	0.35%	0.24%	0.14%
5.00E+05	0.52%	0.26%	0.51%	0.64%	0.59%	0.47%	0.31%	0.21%	0.14%	0.08%
7.50E+05	0.41%	0.41%	0.58%	0.59%	0.50%	0.37%	0.23%	0.15%	0.10%	0.06%
1.00E+06	0.33%	0.49%	0.60%	0.54%	0.43%	0.31%	0.19%	0.12%	0.08%	0.05%
5.00E+06	0.22%	0.51%	0.39%	0.24%	0.16%	0.10%	0.06%	0.03%	0.02%	0.01%
1.00E+07	0.49%	0.39%	0.27%	0.15%	0.10%	0.06%	0.03%	0.02%	0.01%	0.01%
5.00E+07	1.15%	0.15%	0.09%	0.05%	0.03%	0.02%	0.01%	0.01%	0.00%	0.00%
1.00E+08	1.44%	0.09%	0.06%	0.03%	0.02%	0.01%	0.00%	0.00%	0.00%	0.00%

The maximum discrepancy is 2.12% at  $Re = 10,000$  and  $e/D = 0.01$



## Problem 8.94

[Difficulty: 3]


**8.94** Using Eqs. 8.36 and 8.37, generate the Moody chart of Fig. 8.13.

### Solution:

Using the add-in function *Friction factor* from the web site

$e/D =$	0	0.0001	0.0002	0.0005	0.001	0.002	0.005	0.01	0.02	0.04
---------	---	--------	--------	--------	-------	-------	-------	------	------	------

$Re$	$f$									
500	0.1280	0.1280	0.1280	0.1280	0.1280	0.1280	0.1280	0.1280	0.1280	0.1280
1.00E+03	0.0640	0.0640	0.0640	0.0640	0.0640	0.0640	0.0640	0.0640	0.0640	0.0640
1.50E+03	0.0427	0.0427	0.0427	0.0427	0.0427	0.0427	0.0427	0.0427	0.0427	0.0427
2.30E+03	0.0473	0.0474	0.0474	0.0477	0.0481	0.0489	0.0512	0.0549	0.0619	0.0747
1.00E+04	0.0309	0.0310	0.0312	0.0316	0.0324	0.0338	0.0376	0.0431	0.0523	0.0672
1.50E+04	0.0278	0.0280	0.0282	0.0287	0.0296	0.0313	0.0356	0.0415	0.0511	0.0664
1.00E+05	0.0180	0.0185	0.0190	0.0203	0.0222	0.0251	0.0313	0.0385	0.0490	0.0649
1.50E+05	0.0166	0.0172	0.0178	0.0194	0.0214	0.0246	0.0310	0.0383	0.0489	0.0648
1.00E+06	0.0116	0.0134	0.0147	0.0172	0.0199	0.0236	0.0305	0.0380	0.0487	0.0647
1.50E+06	0.0109	0.0130	0.0144	0.0170	0.0198	0.0235	0.0304	0.0379	0.0487	0.0647
1.00E+07	0.0081	0.0122	0.0138	0.0168	0.0197	0.0234	0.0304	0.0379	0.0486	0.0647
1.50E+07	0.0076	0.0121	0.0138	0.0167	0.0197	0.0234	0.0304	0.0379	0.0486	0.0647
1.00E+08	0.0059	0.0120	0.0137	0.0167	0.0196	0.0234	0.0304	0.0379	0.0486	0.0647



### Problem 8.95

[Difficulty: 2]


8.95 The Moody diagram gives the Darcy friction factor,  $f$ , in terms of Reynolds number and relative roughness. The Fanning friction factor for pipe flow is defined as

$$f_F = \frac{\tau_w}{\frac{1}{2}\rho\bar{V}^2}$$

where  $\tau_w$  is the wall shear stress in the pipe. Show that the relation between the Darcy and Fanning friction factors for fully developed pipe flow is given by  $f = 4f_F$ .

Solution: Consider cylindrical CV containing fluid in pipe; apply force balance, definition of  $f$ .

Basic equations:  $\sum F_x = 0$



$$\Delta p = f \frac{L}{D} \frac{\rho\bar{V}^2}{2}$$

From the force balance,

$$(p + \Delta p) \frac{\pi D^2}{4} - \tau_w \pi D L - p \frac{\pi D^2}{4} = 0 \quad \text{or} \quad \tau_w = \frac{D}{4} \frac{\Delta p}{L}$$

Substituting,

$$\tau_w = \frac{D}{4L} f \frac{L}{D} \frac{\rho\bar{V}^2}{2} = f \frac{\rho\bar{V}^2}{8}$$

But

$$f_F \equiv \frac{\tau_w}{\frac{1}{2}\rho\bar{V}^2} = \frac{f \frac{\rho\bar{V}^2}{8}}{\frac{1}{2}\rho\bar{V}^2} = \frac{f}{4}$$

$f_F$

## Problem 8.96

[Difficulty: 3]

**8.96** We saw in Section 8.7 that instead of the implicit Colebrook equation (Eq. 8.37) for computing the turbulent friction factor  $f$ , an explicit expression that gives reasonable accuracy is

$$\frac{1}{\sqrt{f}} = -1.8 \log \left[ \left( \frac{e/D}{3.7} \right)^{1.11} + \frac{6.9}{Re} \right]$$

Compare the accuracy of this expression for  $f$  with Eq. 8.37 by computing the percentage discrepancy as a function of  $Re$  and  $e/D$ , for  $Re = 10^4$  to  $10^8$ , and  $e/D = 0, 0.0001, 0.001, 0.01$ , and  $0.05$ . What is the maximum discrepancy for these  $Re$  and  $e/D$  values? Plot  $f$  against  $Re$  with  $e/D$  as a parameter.

Using the above formula for  $f_0$ , and Eq. 8.37 for  $f_1$

e/D =	0	0.0001	0.0002	0.0005	0.001	0.002	0.005	0.01	0.02	0.05
Re	$f_0$									
1.00E+04	0.0309	0.0310	0.0311	0.0315	0.0322	0.0335	0.0374	0.0430	0.0524	0.0741
2.50E+04	0.0244	0.0245	0.0248	0.0254	0.0265	0.0285	0.0336	0.0401	0.0502	0.0727
5.00E+04	0.0207	0.0210	0.0213	0.0223	0.0237	0.0263	0.0321	0.0391	0.0495	0.0722
7.50E+04	0.0189	0.0193	0.0197	0.0209	0.0226	0.0254	0.0316	0.0387	0.0492	0.0720
1.00E+05	0.0178	0.0183	0.0187	0.0201	0.0220	0.0250	0.0313	0.0385	0.0491	0.0719
2.50E+05	0.0148	0.0156	0.0164	0.0183	0.0207	0.0241	0.0308	0.0382	0.0489	0.0718
5.00E+05	0.0131	0.0143	0.0153	0.0176	0.0202	0.0238	0.0306	0.0381	0.0488	0.0717
7.50E+05	0.0122	0.0137	0.0148	0.0173	0.0200	0.0237	0.0305	0.0381	0.0488	0.0717
1.00E+06	0.0116	0.0133	0.0146	0.0172	0.0199	0.0236	0.0305	0.0380	0.0488	0.0717
5.00E+06	0.0090	0.0123	0.0139	0.0168	0.0197	0.0235	0.0304	0.0380	0.0487	0.0717
1.00E+07	0.0081	0.0122	0.0139	0.0168	0.0197	0.0235	0.0304	0.0380	0.0487	0.0717
5.00E+07	0.0066	0.0120	0.0138	0.0167	0.0197	0.0235	0.0304	0.0380	0.0487	0.0717
1.00E+08	0.0060	0.0120	0.0138	0.0167	0.0197	0.0235	0.0304	0.0380	0.0487	0.0717

Using the add-in function *Friction factor* from the Web


e/D =	0	0.0001	0.0002	0.0005	0.001	0.002	0.005	0.01	0.02	0.05
Re	$f$									
1.00E+04	0.0309	0.0310	0.0312	0.0316	0.0324	0.0338	0.0376	0.0431	0.0523	0.0738
2.50E+04	0.0245	0.0248	0.0250	0.0257	0.0268	0.0288	0.0337	0.0402	0.0502	0.0725
5.00E+04	0.0209	0.0212	0.0216	0.0226	0.0240	0.0265	0.0322	0.0391	0.0494	0.0720
7.50E+04	0.0191	0.0196	0.0200	0.0212	0.0228	0.0256	0.0316	0.0387	0.0492	0.0719
1.00E+05	0.0180	0.0185	0.0190	0.0203	0.0222	0.0251	0.0313	0.0385	0.0490	0.0718
2.50E+05	0.0150	0.0158	0.0166	0.0185	0.0208	0.0241	0.0308	0.0381	0.0488	0.0716
5.00E+05	0.0132	0.0144	0.0154	0.0177	0.0202	0.0238	0.0306	0.0380	0.0487	0.0716
7.50E+05	0.0122	0.0138	0.0150	0.0174	0.0200	0.0237	0.0305	0.0380	0.0487	0.0716
1.00E+06	0.0116	0.0134	0.0147	0.0172	0.0199	0.0236	0.0305	0.0380	0.0487	0.0716
5.00E+06	0.0090	0.0123	0.0139	0.0168	0.0197	0.0235	0.0304	0.0379	0.0486	0.0716
1.00E+07	0.0081	0.0122	0.0138	0.0168	0.0197	0.0234	0.0304	0.0379	0.0486	0.0716
5.00E+07	0.0065	0.0120	0.0138	0.0167	0.0196	0.0234	0.0304	0.0379	0.0486	0.0716
1.00E+08	0.0059	0.0120	0.0137	0.0167	0.0196	0.0234	0.0304	0.0379	0.0486	0.0716

The error can now be computed

$e/D =$	0	0.0001	0.0002	0.0005	0.001	0.002	0.005	0.01	0.02	0.05
---------	---	--------	--------	--------	-------	-------	-------	------	------	------

$Re$	Error (%)									
1.00E+04	0.01%	0.15%	0.26%	0.46%	0.64%	0.73%	0.55%	0.19%	0.17%	0.43%
2.50E+04	0.63%	0.88%	1.02%	1.20%	1.22%	1.03%	0.51%	0.11%	0.14%	0.29%
5.00E+04	0.85%	1.19%	1.32%	1.38%	1.21%	0.84%	0.28%	0.00%	0.16%	0.24%
7.50E+04	0.90%	1.30%	1.40%	1.35%	1.07%	0.65%	0.16%	0.06%	0.17%	0.23%
1.00E+05	0.92%	1.34%	<b>1.42%</b>	1.28%	0.94%	0.52%	0.09%	0.09%	0.18%	0.22%
2.50E+05	0.84%	1.33%	1.25%	0.85%	0.47%	0.16%	0.07%	0.15%	0.19%	0.21%
5.00E+05	0.70%	1.16%	0.93%	0.48%	0.19%	0.00%	0.13%	0.18%	0.20%	0.20%
7.50E+05	0.59%	0.99%	0.72%	0.30%	0.07%	0.07%	0.16%	0.18%	0.20%	0.20%
1.00E+06	0.50%	0.86%	0.57%	0.20%	0.01%	0.10%	0.17%	0.19%	0.20%	0.20%
5.00E+06	0.07%	0.17%	0.01%	0.11%	0.15%	0.18%	0.19%	0.20%	0.20%	0.20%
1.00E+07	0.35%	0.00%	0.09%	0.15%	0.18%	0.19%	0.20%	0.20%	0.20%	0.20%
5.00E+07	1.02%	0.16%	0.18%	0.19%	0.20%	0.20%	0.20%	0.20%	0.20%	0.20%
1.00E+08	1.31%	0.18%	0.19%	0.20%	0.20%	0.20%	0.20%	0.20%	0.20%	0.20%

The maximum discrepancy is 1.42% at  $Re = 100,000$  and  $e/D = 0.0002$



## Problem 8.97

[Difficulty: 3]

**8.97** Water flows at 25 L/s through a gradual contraction, in which the pipe diameter is reduced from 75 mm to 37.5 mm, with a 150° included angle. If the pressure before the contraction is 500 kPa, estimate the pressure after the contraction. Recompute the answer if the included angle is changed to 180° (a sudden contraction).

**Given:** Flow through gradual contraction

**Find:** Pressure after contraction; compare to sudden contraction

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{lm} \quad h_{lm} = K \cdot \frac{V_2^2}{2} \quad Q = V \cdot A$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) Horizontal

Available data  $Q = 25 \cdot \frac{\text{L}}{\text{s}} \quad Q = 0.025 \frac{\text{m}^3}{\text{s}} \quad D_1 = 75 \text{ mm} \quad D_2 = 37.5 \text{ mm} \quad p_1 = 500 \text{ kPa} \quad \rho = 999 \frac{\text{kg}}{\text{m}^3}$

For an included angle of 150° and an area ratio  $\frac{A_2}{A_1} = \left( \frac{D_2}{D_1} \right)^2 = \left( \frac{37.5}{75} \right)^2 = 0.25$  we find from Table 8.3  $K = 0.35$

Hence the energy equation becomes 
$$\left( \frac{p_1}{\rho} + \frac{V_1^2}{2} \right) - \left( \frac{p_2}{\rho} + \frac{V_2^2}{2} \right) = K \cdot \frac{V_2^2}{2} \quad \text{with} \quad V_1 = \frac{4 \cdot Q}{\pi \cdot D_1^2} \quad V_2 = \frac{4 \cdot Q}{\pi \cdot D_2^2}$$

$$p_2 = p_1 - \frac{\rho}{2} \cdot \left[ (1 + K) \cdot V_2^2 - V_1^2 \right] = p_2 - \frac{8 \cdot \rho \cdot Q^2}{\pi^2} \cdot \left[ \frac{(1 + K)}{D_2^4} - \frac{1}{D_1^4} \right]$$

$$p_2 = 500 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} - \frac{8}{\pi^2} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 0.025 \cdot \frac{\text{m}^3}{\text{s}} \right)^2 \times \left[ (1 + 0.35) \times \frac{1}{(0.0375 \cdot \text{m})^4} - \frac{1}{(0.075 \cdot \text{m})^4} \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad p_2 = 170 \cdot \text{kPa}$$


Repeating the above analysis for an included angle of 180° (sudden contraction)  $K = 0.41$

$$p_2 = 500 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} - \frac{8}{\pi^2} \times 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \left( 0.025 \cdot \frac{\text{m}^3}{\text{s}} \right)^2 \times \left[ (1 + 0.41) \times \frac{1}{(0.0375 \cdot \text{m})^4} - \frac{1}{(0.075 \cdot \text{m})^4} \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad p_2 = 155 \cdot \text{kPa}$$

### Problem 8.98

[Difficulty: 3]

**8.98** Water flows through a 25-mm-diameter tube that suddenly enlarges to a diameter of 50 mm. The flow rate through the enlargement is 1.25 Liter/s. Calculate the pressure rise across the enlargement. Compare with the value for frictionless flow.



Solution: Apply energy equation for pipe flow.

Computing equation:  $\frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g z_1 = \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g z_2 + h_{LT}$

- Assumptions: (1) Steady flow  
 (2) Incompressible flow  
 (3) Uniform flow at each section:  $\alpha_1 = \alpha_2 = 1$   
 (4) Horizontal section

$$h_{LT} = K \frac{\bar{V}_1^2}{2}$$

Then

$$p_2 - p_1 = \frac{\rho}{2} (\bar{V}_1^2 - \bar{V}_2^2) - \rho h_{LT,12}$$

From continuity,  $\bar{V}_1 A_1 = \bar{V}_2 A_2$ , so  $\bar{V}_2 = \bar{V}_1 \frac{A_1}{A_2} = \bar{V}_1 \left(\frac{D_1}{D_2}\right)^2$ ;  $\bar{V}_2^2 = \bar{V}_1^2 \left(\frac{D_1}{D_2}\right)^4$

From Fig. 8.14, at  $AR = \left(\frac{D_1}{D_2}\right)^4 = \frac{1}{4}$ ,  $K = 0.56$ .

$$\bar{V}_1 = \frac{Q}{A_1} = \frac{4Q}{\pi D_1^2} = \frac{4}{\pi} \times \frac{1.25 \text{ L}}{\text{s}} \times 10^{-3} \frac{\text{m}^3}{\text{s}} \times \frac{1}{(25 \times 10^{-3} \text{ m})^2} = 2.55 \text{ m/s}$$

Substituting,

$$\begin{aligned} p_2 - p_1 &= \frac{\rho \bar{V}_1^2}{2} \left[ 1 - \left(\frac{D_1}{D_2}\right)^4 \right] - K \rho \frac{\bar{V}_1^2}{2} = \frac{1}{2} \rho \bar{V}_1^2 \left[ 1 - \left(\frac{D_1}{D_2}\right)^4 - K \right] \\ &= \frac{1}{2} \times 999 \frac{\text{kg}}{\text{m}^3} \times (2.55)^2 \frac{\text{m}^2}{\text{s}^2} \left[ 1 - \left(\frac{1}{2}\right)^4 - 0.56 \right] \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \end{aligned}$$

$$p_2 - p_1 = 1.22 \text{ kPa}$$

$\Delta p_a$

For frictionless flow,  $K = 0$ , and

$$p_2 - p_1 = \frac{1}{2} \rho \bar{V}_1^2 \left[ 1 - \left(\frac{D_1}{D_2}\right)^4 \right] = 3.04 \text{ kPa}$$

$\Delta p_f$


Thus  $\frac{\Delta p_{\text{actual}}}{\Delta p_{\text{frictionless}}} = \frac{1.22}{3.04} = 0.403$  or 40.3%

Ratio

## Problem 8.99

[Difficulty: 3]

**8.99** Water flows through a 2-in.-diameter tube that suddenly contracts to 1 in. diameter. The pressure drop across the contraction is 0.5 psi. Determine the volume flow rate.



**Given:** Flow through sudden contraction

**Find:** Volume flow rate

**Solution:**

$$\text{Basic equations} \quad \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{lm} \quad h_{lm} = K \cdot \frac{V_2^2}{2} \quad Q = V \cdot A$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) Horizontal

Hence the energy equation becomes

$$\left( \frac{p_1}{\rho} + \frac{V_1^2}{2} \right) - \left( \frac{p_2}{\rho} + \frac{V_2^2}{2} \right) = K \cdot \frac{V_2^2}{2}$$

$$\text{From continuity} \quad V_1 = V_2 \cdot \frac{A_2}{A_1} = V_2 \cdot AR$$

$$\text{Hence} \quad \left( \frac{p_1}{\rho} + \frac{V_2^2 \cdot AR^2}{2} \right) - \left( \frac{p_2}{\rho} + \frac{V_2^2}{2} \right) = K \cdot \frac{V_2^2}{2}$$

$$\text{Solving for } V_2 \quad V_2 = \sqrt{\frac{2 \cdot (p_1 - p_2)}{\rho \cdot (1 - AR^2 + K)}} \quad AR = \left( \frac{D_2}{D_1} \right)^2 = \left( \frac{1}{2} \right)^2 = 0.25 \quad \text{so from Fig. 8.14} \quad K = 0.4$$

$$\text{Hence} \quad V_2 = \sqrt{2 \times 0.5 \cdot \frac{\text{lbf}}{\text{in}^2} \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \frac{1}{(1 - 0.25^2 + 0.4)} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2}} \quad V_2 = 7.45 \cdot \frac{\text{ft}}{\text{s}}$$


$$Q = V_2 \cdot A_2 = \frac{\pi \cdot D_2^2}{4} \cdot V_2$$

$$Q = \frac{\pi}{4} \times \left( \frac{1}{12} \cdot \text{ft} \right)^2 \times 7.45 \cdot \frac{\text{ft}}{\text{s}} = 0.0406 \cdot \frac{\text{ft}^3}{\text{s}} \quad Q = 2.44 \cdot \frac{\text{ft}^3}{\text{min}} \quad Q = 18.2 \cdot \text{gpm}$$

## Problem 8.100

[Difficulty: 3]

**8.100** Air at standard conditions flows through a sudden expansion in a circular duct. The upstream and downstream duct diameters are 75 mm and 225 mm, respectively. The pressure downstream is 5 mm of water higher than that upstream. Determine the average speed of the air approaching the expansion and the volume flow rate.



**Given:** Flow through sudden expansion

**Find:** Inlet speed; Volume flow rate

**Solution:**

$$\text{Basic equations} \quad \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{lm} \quad h_{lm} = K \cdot \frac{V_1^2}{2} \quad Q = V \cdot A \quad \Delta p = \rho_{H_2O} \cdot g \cdot \Delta h$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) Horizontal

Hence the energy equation becomes

$$\left( \frac{p_1}{\rho} + \frac{V_1^2}{2} \right) - \left( \frac{p_2}{\rho} + \frac{V_2^2}{2} \right) = K \cdot \frac{V_1^2}{2}$$

$$\text{From continuity} \quad V_2 = V_1 \cdot \frac{A_1}{A_2} = V_1 \cdot AR$$

$$\text{Hence} \quad \left( \frac{p_1}{\rho} + \frac{V_1^2}{2} \right) - \left( \frac{p_2}{\rho} + \frac{V_1^2 \cdot AR^2}{2} \right) = K \cdot \frac{V_1^2}{2}$$

$$\text{Solving for } V_1 \quad V_1 = \sqrt{\frac{2 \cdot (p_2 - p_1)}{\rho \cdot (1 - AR^2 - K)}} \quad AR = \left( \frac{D_1}{D_2} \right)^2 = \left( \frac{75}{225} \right)^2 = 0.111 \quad \text{so from Fig. 8.14} \quad K = 0.8$$

$$\text{Also} \quad p_2 - p_1 = \rho_{H_2O} \cdot g \cdot \Delta h = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times \frac{5}{1000} \cdot \text{m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 49.1 \cdot \text{Pa}$$

$$\text{Hence} \quad V_1 = \sqrt{2 \times 49.1 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{1.23 \cdot \text{kg}} \times \frac{1}{(1 - 0.111^2 - 0.8)} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}} \quad V_1 = 20.6 \frac{\text{m}}{\text{s}}$$

$$Q = V_1 \cdot A_1 = \frac{\pi \cdot D_1^2}{4} \cdot V_1 \quad Q = \frac{\pi}{4} \times \left( \frac{75}{1000} \cdot \text{m} \right)^2 \times 20.6 \cdot \frac{\text{m}}{\text{s}} \quad Q = 0.0910 \cdot \frac{\text{m}^3}{\text{s}} \quad Q = 5.46 \cdot \frac{\text{m}^3}{\text{min}}$$

## Problem 8.101

[Difficulty: 4]

**8.101** In an undergraduate laboratory, you have been assigned the task of developing a crude flow meter for measuring the flow in a 45-mm-diameter water pipe system. You are to install a 22.5-mm-diameter section of pipe and a water manometer to measure the pressure drop at the sudden contraction. Derive an expression for the theoretical calibration constant  $k$  in  $Q = k\sqrt{\Delta h}$ , where  $Q$  is the volume flow rate in L/min, and  $\Delta h$  is the manometer deflection in mm. Plot the theoretical calibration curve for a flow rate range of 10 to 50 L/min. Would you expect this to be a practical device for measuring flow rate?

**Given:** Data on a pipe sudden contraction

**Find:** Theoretical calibration constant; plot

**Solution:**

Given data  $D_1 = 45\text{-mm}$   $D_2 = 22.5\text{-mm}$

The governing equations between inlet (1) and exit (2) are

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad (8.29)$$

where 
$$h_l = K \cdot \frac{V_2^2}{2} \quad (8.40a)$$

Hence the pressure drop is (assuming  $\alpha = 1$ )

$$\Delta p = p_1 - p_2 = \rho \cdot \left( \frac{V_2^2}{2} - \frac{V_1^2}{2} + K \cdot \frac{V_2^2}{2} \right)$$

For the sudden contraction 
$$V_1 \cdot \frac{\pi}{4} \cdot D_1^2 = V_2 \cdot \frac{\pi}{4} \cdot D_2^2 = Q \quad \text{or} \quad V_2 = V_1 \cdot \left( \frac{D_1}{D_2} \right)^2$$

so 
$$\Delta p = \frac{\rho \cdot V_1^2}{2} \cdot \left[ \left( \frac{D_1}{D_2} \right)^4 (1 + K) - 1 \right]$$

For the pressure drop we can use the manometer equation

$$\Delta p = \rho \cdot g \cdot \Delta h$$

Hence 
$$\rho \cdot g \cdot \Delta h = \frac{\rho \cdot V_1^2}{2} \cdot \left[ \left( \frac{D_1}{D_2} \right)^4 (1 + K) - 1 \right]$$

In terms of flow rate  $Q$  
$$\rho \cdot g \cdot \Delta h = \frac{\rho}{2} \cdot \frac{Q^2}{\left( \frac{\pi}{4} \cdot D_1^2 \right)^2} \cdot \left[ \left( \frac{D_1}{D_2} \right)^4 (1 + K) - 1 \right]$$

or

$$g \cdot \Delta h = \frac{8 \cdot Q^2}{\pi^2 \cdot D_1^4} \left[ \left( \frac{D_1}{D_2} \right)^4 (1 + K) - 1 \right]$$

Hence for flow rate  $Q$  we find  $Q = k \cdot \sqrt{\Delta h}$

where

$$k = \sqrt{\frac{g \cdot \pi^2 \cdot D_1^4}{8 \cdot \left[ \left( \frac{D_1}{D_2} \right)^4 (1 + K) - 1 \right]}}$$

For  $K$ , we need the aspect ratio  $AR$   $AR = \left( \frac{D_2}{D_1} \right)^2$   $AR = 0.25$

From Fig. 8.15  $K = 0.4$


Using this in the expression for  $k$ , with the other given values

$$k = \sqrt{\frac{g \cdot \pi^2 \cdot D_1^4}{8 \cdot \left[ \left( \frac{D_1}{D_2} \right)^4 (1 + K) - 1 \right]}} \quad k = 1.52 \times 10^{-3} \cdot \frac{\text{m}^{\frac{5}{2}}}{\text{s}}$$

For  $\Delta h$  in mm and  $Q$  in L/min

$$k = 2.89 \cdot \frac{\frac{\text{L}}{\text{min}}}{\frac{\text{mm}^{\frac{1}{2}}}{\text{s}}}$$

The plot of theoretical  $Q$  versus flow rate  $\Delta h$  can be done in *Excel*.




It is a practical device, but is a) Nonlinear and b) has a large energy loss

## Problem 8.102

[Difficulty: 3]

**8.102** Water flows from a larger pipe, diameter  $D_1 = 100$  mm, into a smaller one, diameter  $D_2 = 50$  mm, by way of a reentrant device. Find the head loss between points ① and ②.



**Given:** Flow through a reentrant device

**Find:** Head loss

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K \cdot \frac{V_2^2}{2} \quad Q = V \cdot A$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $L \ll$  so ignore  $h_l$  5) Reentrant

Available data  $D_1 = 100 \text{ mm} \quad D_2 = 50 \text{ mm} \quad Q = 0.01 \cdot \frac{\text{m}^3}{\text{s}} \quad \text{and from Table 8.2} \quad K = 0.78$

$$A_1 = \frac{\pi}{4} \cdot D_1^2 \quad A_1 = 7.85 \times 10^3 \text{ mm}^2 \quad A_2 = \frac{\pi}{4} \cdot D_2^2 \quad A_2 = 1.96 \times 10^3 \text{ mm}^2$$

Hence between the free surface (Point 1) and the exit (2) the energy equation becomes

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} - \frac{V_2^2}{2} - \frac{p_2}{\rho} = K \cdot \frac{V_2^2}{2}$$

From continuity  $Q = V_1 \cdot A_1 = V_2 \cdot A_2$  and also  $\frac{p_1 - p_2}{\rho} = \frac{\rho \cdot g \cdot h}{\rho} = g \cdot h$  where  $h$  is the head loss

Hence 
$$g \cdot h + \frac{1}{2} \cdot \left( \frac{Q}{A_1} \right)^2 - \frac{1}{2} \cdot \left( \frac{Q}{A_2} \right)^2 = K \cdot \frac{1}{2} \cdot \left( \frac{Q}{A_2} \right)^2$$

Solving for  $h$  
$$h = \frac{\left( \frac{Q}{A_2} \right)^2}{2 \cdot g} \cdot \left[ 1 + K - \left( \frac{A_2}{A_1} \right)^2 \right] \quad h = 2.27 \text{ m}$$


## Problem 8.103

[Difficulty: 4]

**8.103** Flow through a sudden contraction is shown. The minimum flow area at the vena contracta is given in terms of the area ratio by the contraction coefficient [32],

$$C_c = \frac{A_c}{A_2} = 0.62 + 0.38 \left( \frac{A_2}{A_1} \right)^3$$

The loss in a sudden contraction is mostly a result of the vena contracta: The fluid accelerates into the contraction, there is flow separation (as shown by the dashed lines), and the vena contracta acts as a miniature sudden expansion with significant secondary flow losses. Use these assumptions to obtain and plot estimates of the minor loss coefficient for a sudden contraction, and compare with the data presented in Fig. 8.15.



**Given:** Contraction coefficient for sudden contraction

**Find:** Expression for minor head loss; compare with Fig. 8.15; plot

**Solution:**

We analyse the loss at the "sudden expansion" at the vena contracta

The governing CV equations (mass, momentum, and energy) are

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12)$$

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad (4.18a)$$

$$\dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} \left( u + pv + \frac{V^2}{2} + gz \right) \rho \vec{V} \cdot d\vec{A} \quad (4.56)$$

Assume: 1) Steady flow 2) Incompressible flow 3) Uniform flow at each section 4) Horizontal: no body force 5) No shaft work 6) Neglect viscous friction 7) Neglect gravity

The mass equation becomes 
$$V_c \cdot A_c = V_2 \cdot A_2 \quad (1)$$

The momentum equation becomes 
$$p_c \cdot A_2 - p_2 \cdot A_2 = V_c \cdot (-\rho \cdot V_c \cdot A_c) + V_2 \cdot (\rho \cdot V_2 \cdot A_2)$$

or (using Eq. 1) 
$$p_c - p_2 = \rho \cdot V_c \cdot \frac{A_c}{A_2} \cdot (V_2 - V_c) \quad (2)$$

The energy equation becomes 
$$Q_{\text{rate}} = \left( u_c + \frac{p_c}{\rho} + V_c^2 \right) \cdot (-\rho \cdot V_c \cdot A_c) + \left( u_2 + \frac{p_2}{\rho} + V_2^2 \right) \cdot (\rho \cdot V_2 \cdot A_2)$$

or (using Eq. 1) 
$$h_{lm} = u_2 - u_c - \frac{Q_{\text{rate}}}{m_{\text{rate}}} = \frac{V_c^2 - V_2^2}{2} + \frac{p_c - p_2}{\rho} \quad (3)$$

Combining Eqs. 2 and 3

$$h_{lm} = \frac{V_c^2 - V_2^2}{2} + V_c \cdot \frac{A_c}{A_2} \cdot (V_2 - V_c)$$

$$h_{lm} = \frac{V_c^2}{2} \cdot \left[ 1 - \left( \frac{V_2}{V_c} \right)^2 \right] + V_c^2 \cdot \frac{A_c}{A_2} \cdot \left[ \left( \frac{V_2}{V_c} \right) - 1 \right]$$

From Eq. 1

$$C_c = \frac{A_c}{A_2} = \frac{V_2}{V_c}$$

Hence

$$h_{lm} = \frac{V_c^2}{2} \cdot (1 - C_c^2) + V_c^2 \cdot C_c \cdot (C_c - 1)$$

$$h_{lm} = \frac{V_c^2}{2} \cdot (1 - C_c^2 + 2 \cdot C_c^2 - 2 \cdot C_c)$$

$$h_{lm} = \frac{V_c^2}{2} \cdot (1 - C_c)^2 \quad (4)$$

But we have

$$h_{lm} = K \cdot \frac{V_2^2}{2} = K \cdot \frac{V_c^2}{2} \cdot \left( \frac{V_2}{V_c} \right)^2 = K \cdot \frac{V_c^2}{2} \cdot C_c^2 \quad (5)$$

Hence, comparing Eqs. 4 and 5

$$K = \frac{(1 - C_c)^2}{C_c^2}$$


So, finally

$$K = \left( \frac{1}{C_c} - 1 \right)^2$$

where

$$C_c = 0.62 + 0.38 \cdot \left( \frac{A_2}{A_1} \right)^3$$


This result can be plotted in *Excel*. The agreement with Fig. 8.15 is reasonable.



## Problem 8.104

[Difficulty: 3]

**8.104** Water flows from the tank shown through a very short pipe. Assume the flow is quasi-steady. Estimate the flow rate at the instant shown. How could you improve the flow system if a larger flow rate were desired?



**Given:** Flow through short pipe

**Find:** Volume flow rate; How to improve flow rate

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_I + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K \cdot \frac{V_2^2} {2} \quad Q = V \cdot A$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $L \ll$  so ignore  $h_I$  5) Reentrant

Hence between the free surface (Point 1) and the exit (2) the energy equation becomes

$$\frac{V_1^2}{2} + g \cdot z_1 - \frac{V_2^2}{2} = K \cdot \frac{V_2^2}{2}$$

From continuity 
$$V_1 = V_2 \cdot \frac{A_2}{A_1}$$

Hence 
$$\frac{V_2^2}{2} \cdot \left( \frac{A_2}{A_1} \right)^2 + g \cdot h - \frac{V_2^2}{2} = K \cdot \frac{V_2^2}{2}$$

Solving for  $V_2$  
$$V_2 = \sqrt{\frac{2 \cdot g \cdot h}{\left[ 1 + K - \left( \frac{A_2}{A_1} \right)^2 \right]}} \quad \text{and from Table 8.2} \quad K = 0.78$$


Hence 
$$V_2 = \sqrt{2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 1 \cdot \text{m} \times \frac{1}{\left[ 1 + 0.78 - \left( \frac{350}{3500} \right)^2 \right]}} \quad V_2 = 3.33 \frac{\text{m}}{\text{s}}$$

$$Q = V_2 \cdot A_2 \quad Q = 3.33 \cdot \frac{\text{m}}{\text{s}} \times 350 \cdot \text{mm}^2 \times \left( \frac{1 \cdot \text{m}}{1000 \cdot \text{mm}} \right)^2 \quad Q = 1.17 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 0.070 \cdot \frac{\text{m}^3}{\text{min}}$$

The flow rate could be increased by (1) rounding the entrance and/or (2) adding a diffuser (both somewhat expensive)



**8.106** Air flows out of a clean room test chamber through a 150-mm-diameter duct of length  $L$ . The original duct had a square edged entrance, but this has been replaced with a well-rounded one. The pressure in the chamber is 2.5 mm of water above ambient. Losses from friction are negligible compared with the entrance and exit losses. Estimate the increase in volume flow rate that results from the change in entrance contour.



Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equations:

$$\frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g\beta_1 \approx 0(1) = \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g\beta_2 + h_{\text{ext}}$$

$$h_{\text{ext}} = h_{\text{e}} + h_{\text{e,m}}; h_{\text{e,m}} = K_{\text{ent}} \frac{\bar{V}_2^2}{2}; \Delta p = \rho h_{\text{ext}} g \Delta h \approx 0(4)$$

Assumptions: (1)  $\bar{V}_1 \approx 0$  (3) Uniform flow at exit  
 (2) Neglect elevation changes (4) Neglect frictional losses

Then

$$\frac{\Delta p}{\rho} = \frac{p_1 - p_2}{\rho} = \frac{\bar{V}_2^2}{2} + K_{\text{ent}} \frac{\bar{V}_2^2}{2} = \frac{\bar{V}_2^2}{2} (1 + K_{\text{ent}}) = \frac{\rho h_{\text{ext}} g \Delta h}{\rho}$$

or

$$\bar{V}_2 = \sqrt{\frac{2(p_1 - p_2)}{\rho(1 + K_{\text{ent}})}} = \sqrt{\frac{2\rho h_{\text{ext}} g \Delta h}{\rho(1 + K_{\text{ent}})}}$$

From Table 8.2,  $K_{\text{ent}} = 0.5$  for square-edged,  $K_{\text{ent}} = 0.04$  for rounded entrance.

$$\bar{V}_2 = \sqrt{\frac{2}{1.50} \times \frac{999 \text{ kg}}{\text{m}^3} \times \frac{9.81 \text{ m}}{\text{s}^2} \times 0.0025 \text{ m} \times \frac{\text{m}^3}{1.23 \text{ kg}}} = 5.15 \text{ m/s}$$

$$\bar{V}_2 (\text{modified}) = \sqrt{\frac{2}{1.04} \times \frac{999 \text{ kg}}{\text{m}^3} \times \frac{9.81 \text{ m}}{\text{s}^2} \times 0.0025 \text{ m} \times \frac{\text{m}^3}{1.23 \text{ kg}}} = 6.19 \text{ m/s}$$

Since  $Q = \bar{V}A$ , then

$$\Delta Q = (\bar{V}_{2m} - \bar{V}_2)A = (6.19 - 5.15) \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} (0.150)^2 \text{ m}^2 = 0.0184 \text{ m}^3/\text{s}$$

The percentage improvement is

$$\% = \frac{\Delta Q}{Q} \times 100 = \frac{\bar{V}_{2m} - \bar{V}_2}{\bar{V}_2} \times 100 = \frac{6.19 - 5.15}{5.15} \times 100 = 20.2 \text{ percent}$$

## Problem 8.107

[Difficulty: 3]

**8.107** A water tank (open to the atmosphere) contains water to a depth of 5 m. A 25-mm-diameter hole is punched in the bottom. Modeling the hole as square-edged, estimate the flow rate (L/s) exiting the tank. If you were to stick a short section of pipe into the hole, by how much would the flow rate change? If instead you were to machine the inside of the hole to give it a rounded edge ( $r = 5$  mm), by how much would the flow rate change?

**Given:** Flow out of water tank

**Find:** Volume flow rate using hole; Using short pipe section; Using rounded edge

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} h_{IT} = h_1 + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K \cdot \frac{V_2^2} {2} \quad Q = V \cdot A$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $V_1 \ll V_2$  5)  $L \ll h$  so  $h_1 = 0$

Available data  $D = 25\text{-mm}$   $r = 5\text{-mm}$   $h = 5\text{-m}$

Hence for all three cases, between the free surface (Point 1) and the exit (2) the energy equation becomes

$$g \cdot z_1 - \frac{V_2^2}{2} = K \cdot \frac{V_2^2}{2} \quad \text{and solving for } V_2 \quad V_2 = \sqrt{\frac{2 \cdot g \cdot h}{1 + K}}$$

From Table 8.2  $K_{\text{hole}} = 0.5$  for a hole (assumed to be square-edged)  $K_{\text{pipe}} = 0.78$  for a short pipe (reentrant)

Also, for a rounded edge  $\frac{r}{D} = \frac{5\text{-mm}}{25\text{-mm}} = 0.2 > 0.15$  so from Table 8.2  $K_{\text{round}} = 0.04$

Hence for the hole 
$$V_2 = \sqrt{2 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 5\text{-m} \times \frac{1}{(1 + 0.5)}} \quad V_2 = 8.09 \frac{\text{m}}{\text{s}}$$

$$Q = V_2 \cdot A_2 \quad Q = 8.09 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.025\text{m})^2 \quad Q = 3.97 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 3.97 \frac{\text{L}}{\text{s}}$$

Hence for the pipe 
$$V_2 = \sqrt{2 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 5\text{-m} \times \frac{1}{(1 + 0.78)}} \quad V_2 = 7.42 \frac{\text{m}}{\text{s}}$$

$$Q = V_2 \cdot A_2 \quad Q = 7.42 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.025\text{m})^2 \quad Q = 3.64 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 3.64 \frac{\text{L}}{\text{s}}$$

Hence the change in flow rate is  $3.64 - 3.97 = -0.33 \frac{\text{L}}{\text{s}}$  The pipe leads to a LOWER flow rate

Hence for the rounded 
$$V_2 = \sqrt{2 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 5\text{-m} \times \frac{1}{(1 + 0.04)}} \quad V_2 = 9.71 \frac{\text{m}}{\text{s}} \quad Q = V_2 \cdot A_2 \quad Q = 4.77 \frac{\text{L}}{\text{s}}$$

Hence the change in flow rate is  $4.77 - 3.97 = 0.8 \frac{\text{L}}{\text{s}}$  The rounded edge leads to a HIGHER flow rate

## Problem 8.108

[Difficulty: 2]

**8.108** A conical diffuser is used to expand a pipe flow from a diameter of 100 mm to a diameter of 150 mm. Find the minimum length of the diffuser if we want a loss coefficient (a)  $K_{\text{diffuser}} \leq 0.2$ , (b)  $K_{\text{diffuser}} \leq 0.35$ .

**Given:** Data on inlet and exit diameters of diffuser

**Find:** Minimum lengths to satisfy requirements

**Solution:**

Given data  $D_1 = 100 \cdot \text{mm}$   $D_2 = 150 \cdot \text{mm}$

The governing equations for the diffuser are

$$h_{\text{lm}} = K \cdot \frac{V_1^2}{2} = (C_{\text{pi}} - C_{\text{p}}) \cdot \frac{V_1^2}{2} \quad (8.44)$$

and 
$$C_{\text{pi}} = 1 - \frac{1}{AR^2} \quad (8.42)$$

Combining these we obtain an expression for the loss coefficient  $K$

$$K = 1 - \frac{1}{AR^2} - C_{\text{p}} \quad (1)$$

The area ratio  $AR$  is 
$$AR = \left( \frac{D_2}{D_1} \right)^2 \quad AR = 2.25$$

The pressure recovery coefficient  $C_{\text{p}}$  is obtained from Eq. 1 above once we select  $K$ ; then, with  $C_{\text{p}}$  and  $AR$  specified, the minimum value of  $N/R_1$  (where  $N$  is the length and  $R_1$  is the inlet radius) can be read from Fig. 8.15

(a)  $K = 0.2$  
$$C_{\text{p}} = 1 - \frac{1}{AR^2} - K \quad C_{\text{p}} = 0.602$$

From Fig. 8.15 
$$\frac{N}{R_1} = 5.5 \quad R_1 = \frac{D_1}{2} \quad R_1 = 50 \cdot \text{mm}$$

$$N = 5.5 \cdot R_1 \quad N = 275 \cdot \text{mm}$$

(b)  $K = 0.35$  
$$C_{\text{p}} = 1 - \frac{1}{AR^2} - K \quad C_{\text{p}} = 0.452$$

From Fig. 8.15 
$$\frac{N}{R_1} = 3$$

$$N = 3 \cdot R_1 \quad N = 150 \cdot \text{mm}$$

## Problem 8.109

[Difficulty: 3]

**8.109** A conical diffuser of length 6 in. is used to expand a pipe flow from a diameter of 2 in. to a diameter of 3.5 in. For a water flow rate of 750 gal/min, estimate the static pressure rise. What is the approximate value of the loss coefficient?

**Given:** Data on geometry of conical diffuser; flow rate

**Find:** Static pressure rise; loss coefficient

**Solution:**

Basic equations 
$$C_p = \frac{p_2 - p_1}{\frac{1}{2} \cdot \rho \cdot V_1^2} \quad (8.41) \quad h_{lm} = K \cdot \frac{V_1^2}{2} = (C_{pi} - C_p) \cdot \frac{V_1^2}{2} \quad (8.44) \quad C_{pi} = 1 - \frac{1}{AR^2} \quad (8.42)$$

Given data 
$$D_1 = 2 \cdot \text{in} \quad D_2 = 3.5 \cdot \text{in} \quad N = 6 \cdot \text{in} \quad (N = \text{length}) \quad Q = 750 \cdot \text{gpm}$$

From Eq. 8.41 
$$\Delta p = p_2 - p_1 = \frac{1}{2} \cdot \rho \cdot V_1^2 \cdot C_p \quad (1)$$

Combining Eqs. 8.44 and 8.42 we obtain an expression for the loss coefficient 
$$K = 1 - \frac{1}{AR^2} - C_p \quad (2)$$

The pressure recovery coefficient  $C_p$  for use in Eqs. 1 and 2 above is obtained from Fig. 8.15 once compute  $AR$  and the dimensionless length  $N/R_1$  (where  $R_1$  is the inlet radius)

The aspect ratio  $AR$  is 
$$AR = \left( \frac{D_2}{D_1} \right)^2 \quad AR = \left( \frac{3.5}{2} \right)^2 \quad AR = 3.06$$

$$R_1 = \frac{D_1}{2} \quad R_1 = 1 \cdot \text{in} \quad \text{Hence} \quad \frac{N}{R_1} = 6$$

From Fig. 8.15, with  $AR = 3.06$  and the dimensionless length  $N/R_1 = 6$ , we find  $C_p = 0.6$

To complete the calculations we need  $V_1$  
$$V_1 = \frac{Q}{\frac{\pi}{4} \cdot D_1^2} \quad V_1 = \frac{4}{\pi} \times 750 \cdot \frac{\text{gal}}{\text{min}} \times \frac{1 \cdot \text{ft}^3}{7.48 \cdot \text{gal}} \times \frac{1 \cdot \text{min}}{60 \cdot \text{s}} \times \left( \frac{1}{\frac{2}{12} \cdot \text{ft}} \right)^2 \quad V_1 = 76.6 \cdot \frac{\text{ft}}{\text{s}}$$

We can now compute the pressure rise and loss coefficient from Eqs. 1 and 2 
$$\Delta p = \frac{1}{2} \cdot \rho \cdot V_1^2 \cdot C_p$$

$$\Delta p = \frac{1}{2} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 76.6 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times 0.6 \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \quad \Delta p = 23.7 \cdot \text{psi}$$


$$K = 1 - \frac{1}{AR^2} - C_p \quad K = 1 - \frac{1}{3.06^2} - 0.6 \quad K = 0.293$$

### Problem 8.110

[Difficulty: 4]

**8.110** Space has been found for a conical diffuser 0.45 m long in the clean room ventilation system described in Problem 8.106. The best diffuser of this size is to be used. Assume that data from Fig. 8.16 may be used. Determine the appropriate diffuser angle and area ratio for this installation and estimate the volume flow rate that will be delivered after it is installed.

Modified:



Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equations:

$$\frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g z_1 \approx 0(1) = \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g z_2 + h_{ET} \quad (\text{or to section 3})$$

$$h_{ET} = h_c + h_{em}; \quad h_{em} = K_{ent} + h_{c,diffuser}; \quad \Delta p = \rho_{H_2O} g \Delta h$$

$$\text{From Eq. 8.42, } h_{c,diffuser} = \frac{\bar{V}_2^2}{2} \left[ 1 - \frac{1}{AR^2} - C_p \right]$$

Assumptions: (1)  $\bar{V}_1 \approx 0$

(2) Neglect  $\Delta z$

(3) Uniform flow at each section

(4) Neglect frictional losses

$$\text{For the original system, } \frac{p_1 - p_2}{\rho} = \frac{\bar{V}_2^2}{2} + K_{ent} \frac{\bar{V}_2^2}{2} = 1.5 \frac{\bar{V}_2^2}{2} = \frac{\rho_{H_2O} g \Delta h}{\rho} \quad (K_{ent} = 0.5)$$

$$\text{Thus } \bar{V}_2 = \sqrt{\frac{2}{1.5} \frac{\rho_{H_2O} g \Delta h}{\rho}} = \sqrt{\frac{2}{1.5} \times \frac{999 \text{ kg}}{\text{m}^3} \times \frac{9.81 \text{ m}}{\text{s}^2} \times \frac{0.0025 \text{ m}}{1.23 \text{ kg}}} = 5.15 \text{ m/s}$$

$$\text{For the modified system, } \frac{p_1 - p_3}{\rho} = \frac{\bar{V}_2^2}{2} + K_{ent} \frac{\bar{V}_2^2}{2} + \frac{\bar{V}_2^2}{2} \left[ 1 - \frac{1}{AR^2} - C_p \right] = \frac{\bar{V}_2^2}{2} [1 + K_{ent} - C_p]$$

Since  $\bar{V}_3^2 = \bar{V}_2^2 \frac{1}{AR^2}$ . Thus the best diffuser has the highest  $C_p$ .

From Fig. 8.16,  $C_p = f(N/AR, AR)$ .  $N/AR = 2N/D_1 = \frac{2 \times 0.45 \text{ m}}{0.15 \text{ m}} = 6$ . From the figure, the best diffuser is

$$C_p \approx 0.62 \text{ at } AR \approx 2.7 \text{ and } 2\phi \approx 12 \text{ deg}$$

For the modified system,

$$\bar{V}_2 = \sqrt{\frac{2}{1 + K_{ent} - C_p} \frac{\rho_{H_2O} g \Delta h}{\rho}} = \sqrt{\frac{2}{1 + 0.04 - 0.62} \times \frac{999 \text{ kg}}{\text{m}^3} \times \frac{9.81 \text{ m}}{\text{s}^2} \times \frac{0.0025 \text{ m}}{1.23 \text{ kg}}} = 9.74 \text{ m/s}$$

and

$$Q = \bar{V}_2 A_2 = 9.74 \frac{\text{m}^3}{\text{s}} \times \frac{\pi}{4} (0.15)^2 \text{ m}^2 = 0.172 \text{ m}^3/\text{s}$$

{ The improvement is  $\frac{Q_m - Q}{Q} \times 100 = \frac{\bar{V}_m - \bar{V}}{\bar{V}} \times 100 = \frac{9.74 - 5.15}{5.15} \times 100 = 89.1 \text{ percent more}$  }

## Problem 8.111

[Difficulty: 4]

**8.111** By applying the basic equations to a control volume starting at the expansion and ending downstream, analyze flow through a sudden expansion (assume the inlet pressure  $p_1$  acts on the area  $A_2$  at the expansion). Develop an expression for and plot the minor head loss across the expansion as a function of area ratio, and compare with the data of Fig. 8.15.

**Given:** Sudden expansion

**Find:** Expression for minor head loss; compare with Fig. 8.15; plot

**Solution:**

The governing CV equations (mass, momentum, and energy) are

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12)$$

$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} \quad (4.18a)$$

$$\dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} \left( u + pv + \frac{V^2}{2} + gz \right) \rho \vec{V} \cdot d\vec{A} \quad (4.56)$$

Assume: 1) Steady flow 2) Incompressible flow 3) Uniform flow at each section 4) Horizontal: no body force 5) No shaft work 6) Neglect viscous friction 7) Neglect gravity

The mass equation becomes 
$$V_1 \cdot A_1 = V_2 \cdot A_2 \quad (1)$$

The momentum equation becomes 
$$p_1 \cdot A_2 - p_2 \cdot A_2 = V_1 \cdot (-\rho \cdot V_1 \cdot A_1) + V_2 \cdot (\rho \cdot V_2 \cdot A_2)$$

or (using Eq. 1) 
$$p_1 - p_2 = \rho \cdot V_1 \cdot \frac{A_1}{A_2} \cdot (V_2 - V_1) \quad (2)$$

The energy equation becomes 
$$Q_{\text{rate}} = \left( u_1 + \frac{p_1}{\rho} + V_1^2 \right) \cdot (-\rho \cdot V_1 \cdot A_1) + \left( u_2 + \frac{p_2}{\rho} + V_2^2 \right) \cdot (\rho \cdot V_2 \cdot A_2)$$

or (using Eq. 1) 
$$h_{\text{lm}} = u_2 - u_1 - \frac{Q_{\text{rate}}}{m_{\text{rate}}} = \frac{V_1^2 - V_2^2}{2} + \frac{p_1 - p_2}{\rho} \quad (3)$$

Combining Eqs. 2 and 3 
$$h_{\text{lm}} = \frac{V_1^2 - V_2^2}{2} + V_1 \cdot \frac{A_1}{A_2} \cdot (V_2 - V_1)$$

$$h_{\text{lm}} = \frac{V_1^2}{2} \cdot \left[ 1 - \left( \frac{V_2}{V_1} \right)^2 \right] + V_1^2 \cdot \frac{A_1}{A_2} \cdot \left[ \left( \frac{V_2}{V_1} \right) - 1 \right]$$

From Eq. 1

$$AR = \frac{A_1}{A_2} = \frac{V_2}{V_1}$$

Hence

$$h_{lm} = \frac{V_1^2}{2} \cdot (1 - AR^2) + V_1^2 \cdot AR \cdot (AR - 1)$$

$$h_{lm} = \frac{V_1^2}{2} \cdot (1 - AR^2 + 2 \cdot AR^2 - 2 \cdot AR)$$

$$h_{lm} = K \cdot \frac{V_1^2}{2} = (1 - AR)^2 \cdot \frac{V_1^2}{2}$$


Finally

$$K = (1 - AR)^2$$

This result, and the curve of Fig. 8.15, are shown below as computed in *Excel*. The agreement is excellent.

$AR$	$K_{CV}$	$K_{Fig. 8.15}$
0.0	1.00	1.00
0.1	0.81	
0.2	0.64	0.60
0.3	0.49	
0.4	0.36	0.38
0.5	0.25	0.25
0.6	0.16	
0.7	0.09	0.10
0.8	0.04	
0.9	0.01	0.01
1.0	0.00	0.00

(Data from Fig. 8.15  
is "eyeballed")





## Problem 8.113

[Difficulty: 2]

**8.113** Analyze flow through a sudden expansion to obtain an expression for the upstream average velocity  $\bar{V}_1$  in terms of the pressure change  $\Delta p = p_2 - p_1$ , area ratio  $AR$ , fluid density  $\rho$ , and loss coefficient  $K$ . If the flow were frictionless, would the flow rate indicated by a measured pressure change be higher or lower than a real flow, and why? Conversely, if the flow were frictionless, would a given flow generate a larger or smaller pressure change, and why?

**Given:** Sudden expansion

**Find:** Expression for upstream average velocity

**Solution:**

The basic equation is

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad (8.29)$$

$$h_{IT} = h_1 + K \cdot \frac{V_1^2}{2}$$

Assume: 1) Steady flow 2) Incompressible flow 3)  $h_1 = 0$  4)  $\alpha_1 = \alpha_2 = 1$  5) Neglect gravity

The mass equation is

$$V_1 \cdot A_1 = V_2 \cdot A_2 \quad \text{so} \quad V_2 = V_1 \frac{A_1}{A_2}$$

$$V_2 = AR \cdot V_1 \quad (1)$$

Equation 8.29 becomes

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} = \frac{p_2}{\rho} + \frac{V_1^2}{2} + K \cdot \frac{V_1^2}{2}$$

or (using Eq. 1)

$$\frac{\Delta p}{\rho} = \frac{p_2 - p_1}{\rho} = \frac{V_1^2}{2} \cdot (1 - AR^2 - K)$$

Solving for  $V_1$

$$V_1 = \sqrt{\frac{2 \cdot \Delta p}{\rho \cdot (1 - AR^2 - K)}}$$

If the flow were frictionless,  $K = 0$ , so

$$V_{\text{inviscid}} = \sqrt{\frac{2 \cdot \Delta p}{\rho \cdot (1 - AR^2)}} < V_1$$

Hence the flow rate indicated by a given  $\Delta p$  would be lower

If the flow were frictionless,  $K = 0$ , so

$$\Delta p_{\text{inviscid}} = \frac{V_1^2}{2} \cdot (1 - AR^2)$$

compared to


$$\Delta p = \frac{V_1^2}{2} \cdot (1 - AR^2 - K)$$

Hence a given flow rate would generate a larger  $\Delta p$  for inviscid flow

## Problem 8.114

[Difficulty: 4]

**8.114** Water discharges to atmosphere from a large reservoir through a moderately rounded horizontal nozzle of 25 mm diameter. The free surface is 2.5 m above the nozzle exit plane. Calculate the change in flow rate when a short section of 50-mm-diameter pipe is attached to the end of the nozzle to form a sudden expansion. Determine the location and estimate the magnitude of the minimum pressure with the sudden expansion in place. If the flow were frictionless (with the sudden expansion in place), would the minimum pressure be higher, lower, or the same? Would the flow rate be higher, lower, or the same?



**Given:** Flow out of water tank through a nozzle

**Find:** Change in flow rate when short pipe section is added; Minimum pressure; Effect of frictionless flow

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K \cdot \frac{V_2^2}{2} \quad Q = V \cdot A$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $V_1 \ll V_2$  5)  $L \ll r$  so  $h_l = 0$

Available data  $D_2 = 25\text{-mm} \quad r = 0.02 \cdot D_2 \quad D_3 = 50\text{-mm} \quad r = 0.5\text{-mm} \quad z_1 = 2.5\text{-m} \quad \rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$

For a rounded edge, we choose the first value from Table 8.2  $K_{\text{nozzle}} = 0.28$

Hence for the nozzle case, between the free surface (Point 1) and the exit (2) the energy equation becomes

$$g \cdot z_1 - \frac{V_2^2}{2} = K_{\text{nozzle}} \cdot \frac{V_2^2}{2}$$

Solving for  $V_2$  
$$V_2 = \sqrt{\frac{2 \cdot g \cdot z_1}{1 + K_{\text{nozzle}}}}$$

Hence 
$$V_2 = \sqrt{2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2.5 \cdot \text{m} \times \frac{1}{(1 + 0.28)}} \quad V_2 = 6.19 \frac{\text{m}}{\text{s}}$$

$$Q = V_2 \cdot A_2 \quad Q = 6.19 \cdot \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.025 \cdot \text{m})^2 \quad Q = 3.04 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 3.04 \frac{\text{L}}{\text{s}}$$

When a small piece of pipe is added the energy equation between the free surface (Point 1) and the exit (3) becomes

$$g \cdot z_1 - \frac{V_3^2}{2} = K_{\text{nozzle}} \cdot \frac{V_2^2}{2} + K_e \cdot \frac{V_2^2}{2}$$

From continuity 
$$V_3 = V_2 \cdot \frac{A_2}{A_3} = V_2 \cdot AR$$

Solving for  $V_2$

$$V_2 = \sqrt{\frac{2 \cdot g \cdot z_1}{(AR^2 + K_{\text{nozzle}} + K_e)}}$$

We need the AR for the sudden expansion  $AR = \frac{A_2}{A_3} = \left(\frac{D_2}{D_3}\right)^2 = \left(\frac{25}{50}\right)^2 = 0.25$   $AR = 0.25$

From Fig. 8.15 for  $AR = 0.25$   $K_e = 0.6$

$$V_2 = \sqrt{\frac{2 \cdot g \cdot z_1}{(AR^2 + K_{\text{nozzle}} + K_e)}}$$

Hence  $V_2 = \sqrt{2 \times 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2.5 \cdot \text{m} \times \frac{1}{(0.25^2 + 0.28 + 0.6)}} = 7.21 \frac{\text{m}}{\text{s}}$

$$Q = V_2 \cdot A_2 \quad Q = 7.21 \cdot \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.025 \cdot \text{m})^2 \quad Q = 3.54 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 3.54 \frac{\text{L}}{\text{s}}$$

Comparing results we see the flow increases from 3.04 L/s to 3.54 L/s  $\frac{\Delta Q}{Q} = \frac{3.54 - 3.04}{3.04} = 16.4\%$

The flow increases because the effect of the pipe is to allow an exit pressure at the nozzle LESS than atmospheric!

The minimum pressure point will now be at Point 2 (it was atmospheric before adding the small pipe). The energy equation between 1 and 2 is

$$g \cdot z_1 - \left(\frac{p_2}{\rho} + \frac{V_2^2}{2}\right) = K_{\text{nozzle}} \cdot \frac{V_2^2}{2}$$

Solving for  $p_2$   $p_2 = \rho \cdot \left[ g \cdot z_1 - \frac{V_2^2}{2} \cdot (K_{\text{nozzle}} + 1) \right]$

Hence  $p_2 = 999 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 2.5 \cdot \text{m} - \frac{1}{2} \times \left( 7.21 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times (0.28 + 1) \right] \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} = -8.736 \cdot \text{kPa}$

If the flow were frictionless the the two loss coefficients would be zero. Instead of

Instead of  $V_2 = \sqrt{\frac{2 \cdot g \cdot z_1}{(AR^2 + K_{\text{nozzle}} + K_e)}}$  we'd have  $V_2 = \sqrt{\frac{2 \cdot g \cdot z_1}{AR^2}}$  which is larger

If  $V_2$  is larger, then  $p_2$ , through Bernoulli, would be lower (more negative)

### Problem 8.115

[Difficulty: 2]

**8.115** Water flows steadily from a large tank through a length of smooth plastic tubing, then discharges to atmosphere. The tubing inside diameter is 3.18 mm, and its length is 15.3 m. Calculate the maximum volume flow rate for which flow in the tubing will remain laminar. Estimate the water level in the tank below which flow will be laminar (for laminar flow,  $\alpha = 2$  and  $K_{ent} = 1.4$ ).

Solution: Assume water at 20°C. From Table A.8,  $\rho = 998 \text{ kg/m}^3$ ,  $\nu = 1.00 \times 10^{-6} \text{ m}^2/\text{s}$ .

$$Re = \frac{\rho \bar{V} D}{\mu} = \frac{\bar{V} D}{\nu} \leq 2300; \quad \bar{V}_{max} = \frac{2300 \nu}{D} = 2300 \times \frac{1.00 \times 10^{-6} \text{ m}^2/\text{s}}{0.00318 \text{ m}} = 0.723 \text{ m/s}$$

$$Q = \bar{V} A; \quad A = \frac{\pi D^2}{4} = \frac{\pi (0.00318)^2 \text{ m}^2}{4} = 7.94 \times 10^{-6} \text{ m}^2$$


$$Q = 0.723 \frac{\text{m}}{\text{s}} \times 7.94 \times 10^{-6} \text{ m}^2 = 5.74 \times 10^{-6} \frac{\text{m}^3}{\text{s}} \times 10^3 \frac{\text{L}}{\text{m}^3} \times 60 \frac{\text{s}}{\text{min}} = 0.345 \text{ L/min}$$

Apply energy equation for steady,  $\rho = \text{constant}$  pipe flow:

Computing

$$\text{Equation: } \left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g z_2 \right) = h_{eT}$$

$$h_{eT} = h_{em} + h_e$$



Assumptions: (1)  $p_1 = p_2 = p_{atm}$

(2)  $\bar{V}_1 \approx 0$

(3)  $K_{ent} = 1.4$  (given)

$$\text{Then } g d = \alpha_2 \frac{\bar{V}_2^2}{2} + K_{ent} \frac{\bar{V}_2^2}{2} + f \frac{L}{D} \frac{\bar{V}_2^2} {2} \quad \text{or } d = \frac{\bar{V}_2^2}{2g} \left( \alpha_2 + K_{ent} + f \frac{L}{D} \right)$$

For laminar flow,  $f = \frac{64}{Re} = \frac{64}{2300} = 0.0278$ . Substituting

$$d = \frac{1}{2} \times (0.723)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{s}^2}{9.81 \text{ m}} \left( 2.0 + 1.4 + 0.0278 \frac{15.3 \text{ m}}{0.00318 \text{ m}} \right)$$

$$d = 3.65 \text{ m}$$

**8.116** You are asked to compare the behavior of fully developed laminar flow and fully developed turbulent flow in a horizontal pipe under different conditions. For the same flow rate, which will have the larger centerline velocity? Why? If the pipe discharges to atmosphere, what would you expect the trajectory of the discharge stream to look like (for the same flow rate)? Sketch your expectations for each case.


For the same flow rate, which flow would give the larger wall shear stress? Why? Sketch the shear stress distribution  $\tau/\tau_w$  as a function of radius for each flow. For the same Reynolds number, which flow would have the larger pressure drop per unit length? Why? For a given imposed pressure differential, which flow would have the larger flow rate? Why?

12-732  
42-281  
42-282  
42-283  
42-284  
42-285  
42-286  
42-287  
42-288  
42-289  
42-290  
42-291  
42-292  
42-293  
42-294  
42-295  
42-296  
42-297  
42-298  
42-299  
42-300  
42-301  
42-302  
42-303  
42-304  
42-305  
42-306  
42-307  
42-308  
42-309  
42-310  
42-311  
42-312  
42-313  
42-314  
42-315  
42-316  
42-317  
42-318  
42-319  
42-320  
42-321  
42-322  
42-323  
42-324  
42-325  
42-326  
42-327  
42-328  
42-329  
42-330  
42-331  
42-332  
42-333  
42-334  
42-335  
42-336  
42-337  
42-338  
42-339  
42-340  
42-341  
42-342  
42-343  
42-344  
42-345  
42-346  
42-347  
42-348  
42-349  
42-350  
42-351  
42-352  
42-353  
42-354  
42-355  
42-356  
42-357  
42-358  
42-359  
42-360  
42-361  
42-362  
42-363  
42-364  
42-365  
42-366  
42-367  
42-368  
42-369  
42-370  
42-371  
42-372  
42-373  
42-374  
42-375  
42-376  
42-377  
42-378  
42-379  
42-380  
42-381  
42-382  
42-383  
42-384  
42-385  
42-386  
42-387  
42-388  
42-389  
42-390  
42-391  
42-392  
42-393  
42-394  
42-395  
42-396  
42-397  
42-398  
42-399  
42-400  
42-401  
42-402  
42-403  
42-404  
42-405  
42-406  
42-407  
42-408  
42-409  
42-410  
42-411  
42-412  
42-413  
42-414  
42-415  
42-416  
42-417  
42-418  
42-419  
42-420  
42-421  
42-422  
42-423  
42-424  
42-425  
42-426  
42-427  
42-428  
42-429  
42-430  
42-431  
42-432  
42-433  
42-434  
42-435  
42-436  
42-437  
42-438  
42-439  
42-440  
42-441  
42-442  
42-443  
42-444  
42-445  
42-446  
42-447  
42-448  
42-449  
42-450  
42-451  
42-452  
42-453  
42-454  
42-455  
42-456  
42-457  
42-458  
42-459  
42-460  
42-461  
42-462  
42-463  
42-464  
42-465  
42-466  
42-467  
42-468  
42-469  
42-470  
42-471  
42-472  
42-473  
42-474  
42-475  
42-476  
42-477  
42-478  
42-479  
42-480  
42-481  
42-482  
42-483  
42-484  
42-485  
42-486  
42-487  
42-488  
42-489  
42-490  
42-491  
42-492  
42-493  
42-494  
42-495  
42-496  
42-497  
42-498  
42-499  
42-500  
42-501  
42-502  
42-503  
42-504  
42-505  
42-506  
42-507  
42-508  
42-509  
42-510  
42-511  
42-512  
42-513  
42-514  
42-515  
42-516  
42-517  
42-518  
42-519  
42-520  
42-521  
42-522  
42-523  
42-524  
42-525  
42-526  
42-527  
42-528  
42-529  
42-530  
42-531  
42-532  
42-533  
42-534  
42-535  
42-536  
42-537  
42-538  
42-539  
42-540  
42-541  
42-542  
42-543  
42-544  
42-545  
42-546  
42-547  
42-548  
42-549  
42-550  
42-551  
42-552  
42-553  
42-554  
42-555  
42-556  
42-557  
42-558  
42-559  
42-560  
42-561  
42-562  
42-563  
42-564  
42-565  
42-566  
42-567  
42-568  
42-569  
42-570  
42-571  
42-572  
42-573  
42-574  
42-575  
42-576  
42-577  
42-578  
42-579  
42-580  
42-581  
42-582  
42-583  
42-584  
42-585  
42-586  
42-587  
42-588  
42-589  
42-590  
42-591  
42-592  
42-593  
42-594  
42-595  
42-596  
42-597  
42-598  
42-599  
42-600  
42-601  
42-602  
42-603  
42-604  
42-605  
42-606  
42-607  
42-608  
42-609  
42-610  
42-611  
42-612  
42-613  
42-614  
42-615  
42-616  
42-617  
42-618  
42-619  
42-620  
42-621  
42-622  
42-623  
42-624  
42-625  
42-626  
42-627  
42-628  
42-629  
42-630  
42-631  
42-632  
42-633  
42-634  
42-635  
42-636  
42-637  
42-638  
42-639  
42-640  
42-641  
42-642  
42-643  
42-644  
42-645  
42-646  
42-647  
42-648  
42-649  
42-650  
42-651  
42-652  
42-653  
42-654  
42-655  
42-656  
42-657  
42-658  
42-659  
42-660  
42-661  
42-662  
42-663  
42-664  
42-665  
42-666  
42-667  
42-668  
42-669  
42-670  
42-671  
42-672  
42-673  
42-674  
42-675  
42-676  
42-677  
42-678  
42-679  
42-680  
42-681  
42-682  
42-683  
42-684  
42-685  
42-686  
42-687  
42-688  
42-689  
42-690  
42-691  
42-692  
42-693  
42-694  
42-695  
42-696  
42-697  
42-698  
42-699  
42-700  
42-701  
42-702  
42-703  
42-704  
42-705  
42-706  
42-707  
42-708  
42-709  
42-710  
42-711  
42-712  
42-713  
42-714  
42-715  
42-716  
42-717  
42-718  
42-719  
42-720  
42-721  
42-722  
42-723  
42-724  
42-725  
42-726  
42-727  
42-728  
42-729  
42-730  
42-731  
42-732  
42-733  
42-734  
42-735  
42-736  
42-737  
42-738  
42-739  
42-740  
42-741  
42-742  
42-743  
42-744  
42-745  
42-746  
42-747  
42-748  
42-749  
42-750  
42-751  
42-752  
42-753  
42-754  
42-755  
42-756  
42-757  
42-758  
42-759  
42-760  
42-761  
42-762  
42-763  
42-764  
42-765  
42-766  
42-767  
42-768  
42-769  
42-770  
42-771  
42-772  
42-773  
42-774  
42-775  
42-776  
42-777  
42-778  
42-779  
42-780  
42-781  
42-782  
42-783  
42-784  
42-785  
42-786  
42-787  
42-788  
42-789  
42-790  
42-791  
42-792  
42-793  
42-794  
42-795  
42-796  
42-797  
42-798  
42-799  
42-800  
42-801  
42-802  
42-803  
42-804  
42-805  
42-806  
42-807  
42-808  
42-809  
42-810  
42-811  
42-812  
42-813  
42-814  
42-815  
42-816  
42-817  
42-818  
42-819  
42-820  
42-821  
42-822  
42-823  
42-824  
42-825  
42-826  
42-827  
42-828  
42-829  
42-830  
42-831  
42-832  
42-833  
42-834  
42-835  
42-836  
42-837  
42-838  
42-839  
42-840  
42-841  
42-842  
42-843  
42-844  
42-845  
42-846  
42-847  
42-848  
42-849  
42-850  
42-851  
42-852  
42-853  
42-854  
42-855  
42-856  
42-857  
42-858  
42-859  
42-860  
42-861  
42-862  
42-863  
42-864  
42-865  
42-866  
42-867  
42-868  
42-869  
42-870  
42-871  
42-872  
42-873  
42-874  
42-875  
42-876  
42-877  
42-878  
42-879  
42-880  
42-881  
42-882  
42-883  
42-884  
42-885  
42-886  
42-887  
42-888  
42-889  
42-890  
42-891  
42-892  
42-893  
42-894  
42-895  
42-896  
42-897  
42-898  
42-899  
42-900  
42-901  
42-902  
42-903  
42-904  
42-905  
42-906  
42-907  
42-908  
42-909  
42-910  
42-911  
42-912  
42-913  
42-914  
42-915  
42-916  
42-917  
42-918  
42-919  
42-920  
42-921  
42-922  
42-923  
42-924  
42-925  
42-926  
42-927  
42-928  
42-929  
42-930  
42-931  
42-932  
42-933  
42-934  
42-935  
42-936  
42-937  
42-938  
42-939  
42-940  
42-941  
42-942  
42-943  
42-944  
42-945  
42-946  
42-947  
42-948  
42-949  
42-950  
42-951  
42-952  
42-953  
42-954  
42-955  
42-956  
42-957  
42-958  
42-959  
42-960  
42-961  
42-962  
42-963  
42-964  
42-965  
42-966  
42-967  
42-968  
42-969  
42-970  
42-971  
42-972  
42-973  
42-974  
42-975  
42-976  
42-977  
42-978  
42-979  
42-980  
42-981  
42-982  
42-983  
42-984  
42-985  
42-986  
42-987  
42-988  
42-989  
42-990  
42-991  
42-992  
42-993  
42-994  
42-995  
42-996  
42-997  
42-998  
42-999  
43-000




**Discussion:** In the following fully developed laminar flow and fully developed turbulent flow in a pipe are compared:

- (a) For the same flow rate, laminar flow has the higher maximum velocity, because the turbulent velocity profile is more blunt.
- (b) The trajectory of the discharge stream spreads out for laminar flow because of the large variation in velocity across the pipe exit. For turbulent flow the exit profile is more nearly uniform (except for the region adjacent to the wall) and hence the trajectory is more uniform. Since centerline velocity is larger for laminar flow, liquid travels the greatest horizontal distance. Trajectories for the two flow cases are shown below:



(i) Laminar flow



(ii) Turbulent flow

- (c) For the same flow rate (same mean velocity), turbulent flow has larger wall shear stress because of the larger velocity gradient at the pipe wall. For fully developed flow the pressure force driving the flow is balanced by the shear force at the wall.
- (d) Shear stress varies linearly with radius for both flow cases, from its maximum value at the wall to zero at the pipe centerline.
- (e) For the same Reynolds number, turbulent flow has a larger pressure drop per unit length because the friction factor is larger.
- (f) For a given pressure drop (per unit length), laminar flow has the larger flow rate (larger mean velocity), because it has the smaller friction factor.

The two flow cases are compared in the NCFMF video *Turbulence*, in which R. W. Stewart uses a clever experimental setup to contrast the two flow regimes at constant volume flow rate by varying the liquid viscosity. The trajectories of the liquid streams leaving the end of the pipe are particularly well shown.

## Problem 8.117

[Difficulty: 3]

**8.117** Estimate the minimum level in the water tank of Problem 8.115 such that the flow will be turbulent.

**Given:** Data on water flow from a tank/tubing system

**Find:** Minimum tank level for turbulent flow

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$f = \frac{64}{Re} \quad (8.36) \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

The energy equation (Eq. 8.29) becomes 
$$g \cdot d - \alpha \cdot \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$$

This can be solved explicitly for height  $d$ , or solved using *Solver*

Given data:		Tabulated or graphical data:	
$L = 15.3$	m	$\nu = 1.00E-06$	$m^2/s$
$D = 3.18$	mm	$\rho = 998$	$kg/m^3$
$K_{ent} = 1.4$		(Appendix A)	
$\alpha = 2$			
<b>Computed results:</b>			
$Re = 2300$	(Transition $Re$ )		
$V = 0.723$	m/s		
$\alpha = 1$	(Turbulent)		
$f = 0.0473$	(Turbulent)		
$d = 6.13$	m	(Vary $d$ to minimize error in energy equation)	
<b>Energy equation:</b>	<b>Left (<math>m^2/s</math>)</b>	<b>Right (<math>m^2/s</math>)</b>	<b>Error</b>
(Using <i>Solver</i> )	59.9	59.9	0.00%
Note that we used $\alpha = 1$ (turbulent); using $\alpha = 2$ (laminar) gives $d = 6.16$ m			

**8.118** A laboratory experiment is set up to measure pressure drop for flow of water through a smooth tube. The tube diameter is 15.9 mm, and its length is 3.56 m. Flow enters the tube from a reservoir through a square-edged entrance. Calculate the volume flow rate needed to obtain turbulent flow in the tube. Evaluate the reservoir height differential required to obtain turbulent flow in the tube.

Solution:

Flow will be turbulent for  $Re_D > 2300$

$$Re_D = \frac{\rho \bar{V} D}{\mu} = \frac{\bar{V} D}{\nu} = \frac{Q D}{A \nu} = \frac{Q D}{\frac{\pi D^2}{4} \nu} = \frac{4Q}{\pi D \nu} \quad \text{so } Q = \frac{\pi D \nu}{4} Re$$

Assume  $T = 20^\circ\text{C}$ ,  $\nu = 1.00 \times 10^{-6} \text{ m}^2/\text{s}$  (Table A.8)

For  $Re = 2300$ ,

$$Q = \frac{\pi}{4} \times 1.0 \times 10^{-6} \times 15.9 \times 10^{-3} \times 2300 = 2.87 \times 10^{-5} \text{ m}^3/\text{s} \quad Q$$

Basic equations:  $\left(\frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g z_1\right) - \left(\frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g z_2\right) = h_{\text{LT}} \quad (8.29)$

$$h_{\text{LT}} = h_e + h_{\text{en}} \quad h_e = f \frac{L}{D} \frac{\bar{V}^2}{2}, \quad h_{\text{en}} = K_{\text{en}} \frac{\bar{V}^2}{2}$$

Assumptions: (1)  $p_1 = p_2 = p_{\text{atm}}$  (2)  $\bar{V}_1 = \bar{V}_2 = 0$   
 (3)  $K_{\text{ent}} = 0.5$  (Table 8.2),  $K_{\text{exit}} = 1.0$

Then,  $z_1 - z_2 = \frac{\bar{V}^2}{2g} \left[ f \frac{L}{D} + K_{\text{ent}} + K_{\text{exit}} \right] \quad (1)$

$$\bar{V} = \frac{Q}{A} = \frac{4Q}{\pi D^2} = \frac{4}{\pi} \times 2.87 \times 10^{-5} \frac{\text{m}^3}{\text{s}} \times \frac{1}{(15.9 \times 10^{-3} \text{ m})^2} = 0.145 \text{ m/s}$$

For turbulent flow in a smooth pipe at  $Re = 2300$ ,  
 $f \approx 0.05$  (Fig 8.13)

From Eq. 1

$$d = z_1 - z_2 = \frac{(0.145)^2}{2} \frac{\text{m}^2}{\text{s}^2} + \frac{9.81 \text{ m}}{\text{s}^2} \left[ 0.05 \times \frac{3.56 \times 10^3}{15.9} + 0.5 + 1.0 \right]$$

$$d = 0.0126 \text{ m} \text{ or } 12.6 \text{ mm} \quad d$$

13-782  
42-381  
42-382  
42-383  
42-384  
42-385  
42-386  
Made in U.S.A.



## Problem 8.119

[Difficulty: 3]

**8.119** A benchtop experiment consists of a reservoir with a 500-mm-long horizontal tube of diameter 7.5 mm attached to its base. The tube exits to a sink. A flow of water at 10°C is to be generated such that the Reynolds number is 10,000. What is the flow rate? If the entrance to the tube is square-edged, how deep should the reservoir be? If the entrance to the tube is well-rounded, how deep should the reservoir be?

**Given:** Data on water flow from a tank/tubing system

**Find:** Minimum tank level for turbulent flow

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) Velocity at free surface is  $\ll$

The available data is  $D = 7.5 \text{ mm}$      $L = 500 \text{ mm}$     From Table A.8 at 10°C     $\rho = 1000 \frac{\text{kg}}{\text{m}^3}$      $\mu = 1.3 \cdot 10^{-3} \frac{\text{N} \cdot \text{s}}{\text{m}^2}$

$Re = 10000$      $K_{\text{ent}} = 0.5$     (Table 8.2)     $K_{\text{exit}} = 1$

From  $Re = \frac{\rho \cdot V \cdot D}{\mu}$      $Re = \frac{\rho \cdot Q \cdot D}{\frac{\pi}{4} \cdot D^2 \cdot \mu}$     or     $Q = \frac{\pi \cdot \mu \cdot D \cdot Re}{4 \cdot \rho}$      $Q = 7.66 \times 10^{-5} \frac{\text{m}^3}{\text{s}}$      $Q = 0.0766 \cdot \frac{\text{l}}{\text{s}}$

Hence  $V = \frac{Q}{\left( \frac{\pi \cdot D^2}{4} \right)}$      $V = 1.73 \frac{\text{m}}{\text{s}}$

Assuming a smooth tube  $\frac{1}{\sqrt{f}} = -2 \cdot \log \left( \frac{2.51}{Re \cdot \sqrt{f}} \right)$     so     $f = 0.0309$

The energy equation (Eq. 8.29) becomes  $g \cdot d = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{\text{ent}} \cdot \frac{V^2}{2} + K_{\text{exit}} \cdot \frac{V^2}{2}$

Solving for  $d$   $d = \frac{V^2}{2 \cdot g} \cdot \left( f \cdot \frac{L}{D} + K_{\text{ent}} + K_{\text{exit}} \right)$      $d = 545 \text{ mm}$

FOR  $r > 0.15D$ )     $K_{\text{ent}} = 0.04$  (Table 8.2)     $d = 475 \text{ mm}$

## Problem 8.120

[Difficulty: 4]

**8.120** As discussed in Problem 8.52, the applied pressure difference,  $\Delta p$ , and corresponding volume flow rate,  $Q$ , for laminar flow in a tube can be compared to the applied DC voltage  $V$  across, and current  $I$  through, an electrical resistor, respectively. Investigate whether or not this analogy is valid for turbulent flow by plotting the "resistance"  $\Delta p/Q$  as a function of  $Q$  for turbulent flow of kerosene (at 40°C) in a tube 250 mm long with inside diameter 7.5 mm.

**Given:** Data on a tube

**Find:** "Resistance" of tube for flow of kerosene; plot

**Solution:**

The basic equations for turbulent flow are

$$\left( \frac{p_1}{\rho} + \alpha_1 \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad (8.29)$$

$$h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad (8.37)$$

The given data is

$$L = 250 \cdot \text{mm} \quad D = 7.5 \cdot \text{mm}$$

From Fig. A.2 and Table A.2

$$\mu = 1.1 \times 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \quad \rho = 0.82 \times 990 \cdot \frac{\text{kg}}{\text{m}^3} = 812 \cdot \frac{\text{kg}}{\text{m}^3} \quad (\text{Kerosene})$$

For an electrical resistor

$$V = R \cdot I \quad (1)$$

Simplifying Eqs. 8.29 and 8.34 for a horizontal, constant-area pipe

$$\frac{p_1 - p_2}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \left( \frac{\frac{Q}{\frac{\pi \cdot D^2}{4}}}{2} \right)^2 \quad \text{or} \quad \Delta p = \frac{8 \cdot \rho \cdot f \cdot L}{\pi^2 \cdot D^5} \cdot Q^2 \quad (2)$$

By analogy, current  $I$  is represented by flow rate  $Q$ , and voltage  $V$  by pressure drop  $\Delta p$ . Comparing Eqs. (1) and (2), the "resistance" of the tube is

$$R = \frac{\Delta p}{Q} = \frac{8 \cdot \rho \cdot f \cdot L \cdot Q}{\pi^2 \cdot D^5}$$

The "resistance" of a tube is not constant, but is proportional to the "current"  $Q$ ! Actually, the dependence is not quite linear, because  $f$  decreases slightly (and nonlinearly) with  $Q$ . The analogy fails!

The analogy is hence invalid for

$$\text{Re} > 2300$$

or


$$\frac{\rho \cdot V \cdot D}{\mu} > 2300$$

Writing this constraint in terms of flow rate  $\frac{\rho \cdot \frac{Q}{\frac{\pi}{4} \cdot D^2} \cdot D}{\mu} > 2300$  or  $Q > \frac{2300 \cdot \mu \cdot \pi \cdot D}{4 \cdot \rho}$

Flow rate above which analogy fails  $Q = 1.84 \times 10^{-5} \frac{m^3}{s}$

The plot of "resistance" versus flow rate can be done in *Excel*.

Given data:			Tabulated or graphical data:		
$L =$	250	mm	$\mu =$	1.01E-03	N.s/m <sup>2</sup>
$D =$	7.5	mm	$SG_{ker} =$	0.82	
			$\rho_w =$	990	kg/m <sup>3</sup>
			$\rho =$	812	kg/m <sup>3</sup>
			(Appendix A)		
Computed results:					
$Q$ (m <sup>3</sup> /s)	$V$ (m/s)	$Re$	$f$	"R" (10 <sup>9</sup> Pa/m <sup>3</sup> /s)	
2.0E-05	0.5	2729	0.0448	0.0062	
4.0E-05	0.9	5458	0.0365	0.0101	
8.0E-05	1.8	10916	0.0302	0.0167	
1.2E-04	2.7	16374	0.0272	0.0226	
1.6E-04	3.6	21832	0.0253	0.0281	
2.0E-04	4.5	27290	0.0240	0.0333	
4.0E-04	9.1	54580	0.0205	0.0568	
8.0E-04	18.1	109161	0.0177	0.0980	
1.2E-03	27.2	163741	0.0163	0.1353	
1.6E-03	36.2	218322	0.0154	0.1705	
The "resistance" is not constant; the analogy is invalid for turbulent flow					



## Problem 8.121

[Difficulty: 3]

**8.121** Plot the required reservoir depth of water to create flow in a smooth tube of diameter 10 mm and length 100 m, for a flow rate range of 1 L/min through 10 L/min.

**Given:** Data on tube geometry

**Find:** Plot of reservoir depth as a function of flow rate

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$f = \frac{64}{Re} \quad (8.36) \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

The energy equation (Eq. 8.29) becomes 
$$g \cdot d - \alpha \cdot \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$$


This can be solved explicitly for height  $d$ , or solved using *Solver*

$$d = \frac{V^2}{2 \cdot g} \cdot \left( \alpha + f \cdot \frac{L}{D} + K \right)$$

In *Excel*:

Given data:			Tabulated or graphical data:		
$L =$	100	m	$\mu =$	1.01E-03	N.s/m <sup>2</sup>
$D =$	10	mm	$\rho =$	998	kg/m <sup>3</sup>
$\alpha =$	1	(All flows turbulent)	(Table A.8)		
			$K_{ent} =$	0.5	(Square-edged)
			(Table 8.2)		
Computed results:					
$Q$ (L/min)	$V$ (m/s)	$Re$	$f$	$d$ (m)	
1	0.2	2.1E+03	0.0305	0.704	
2	0.4	4.2E+03	0.0394	3.63	
3	0.6	6.3E+03	0.0350	7.27	
4	0.8	8.4E+03	0.0324	11.9	
5	1.1	1.0E+04	0.0305	17.6	
6	1.3	1.3E+04	0.0291	24.2	
7	1.5	1.5E+04	0.0280	31.6	
8	1.7	1.7E+04	0.0270	39.9	
9	1.9	1.9E+04	0.0263	49.1	
10	2.1	2.1E+04	0.0256	59.1	

### Required Reservoir Head versus Flow Rate



## Problem 8.122

[Difficulty: 3]

**8.122** Oil with kinematic viscosity  $\nu = 7.5 \times 10^{-4} \text{ ft}^2/\text{s}$  flows at 45 gpm in a 100-ft-long horizontal drawn-tubing pipe of 1 in. diameter. By what percentage ratio will the energy loss increase if the same flow rate is maintained while the pipe diameter is reduced to 0.75 in.?

**Given:** Flow of oil in a pipe

**Find:** Percentage change in loss if diameter is reduced

**Solution:**

Basic equations 
$$h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad f = \frac{64}{\text{Re}} \quad \text{Laminar} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad \text{Turbulent}$$

Available data 
$$\nu = 7.5 \cdot 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \quad L = 100 \cdot \text{ft} \quad D = 1 \cdot \text{in} \quad Q = 45 \cdot \text{gpm} \quad Q = 0.100 \frac{\text{ft}^3}{\text{s}}$$

Here 
$$V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = \frac{4}{\pi} \times 0.1 \cdot \frac{\text{ft}^3}{\text{s}} \times \left( \frac{12}{1} \cdot \frac{1}{\text{ft}} \right)^2 \quad V = 18.3 \cdot \frac{\text{ft}}{\text{s}}$$

Then 
$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 18.3 \cdot \frac{\text{ft}}{\text{s}} \times \frac{1}{12} \cdot \text{ft} \times \frac{\text{s}}{7.5 \times 10^{-4} \cdot \text{ft}^2} \quad \text{Re} = 2033$$

The flow is LAMINAR 
$$h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad h_l = \frac{64}{\text{Re}} \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad h_l = \frac{64}{2033} \times \frac{100}{\frac{1}{12}} \times \frac{\left( 18.3 \frac{\text{ft}}{\text{s}} \right)^2}{2} \quad h_l = 6326 \cdot \frac{\text{ft}^2}{\text{s}^2}$$

When the diameter is reduced to

$$D = 0.75 \cdot \text{in}$$

$$V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = \frac{4}{\pi} \times 0.1 \cdot \frac{\text{ft}^3}{\text{s}} \times \left( \frac{12}{0.75} \cdot \frac{1}{\text{ft}} \right)^2 \quad V = 32.6 \cdot \frac{\text{ft}}{\text{s}}$$

$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 32.6 \cdot \frac{\text{ft}}{\text{s}} \times \frac{0.75}{12} \cdot \text{ft} \times \frac{\text{s}}{7.5 \times 10^{-4} \cdot \text{ft}^2} \quad \text{Re} = 2717$$

The flow is TURBULENT For drawn tubing, from Table 8.1

$$e = 0.000005 \cdot \text{ft}$$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0449$$

$$h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad h_l = .0449 \times \frac{100}{\frac{0.75}{12}} \times \frac{\left( 32.6 \frac{\text{ft}}{\text{s}} \right)^2}{2} \quad h_l = 3.82 \times 10^4 \cdot \frac{\text{ft}^2}{\text{s}^2}$$

The increase in loss is 
$$\frac{3.82 \times 10^4 - 6326}{6326} = 504. \%$$

This is a HUGH increase! The main increase is because the diameter reduction causes the velocity to increase; the loss goes as  $V^2$ , and  $1/D$ , so it increases very rapidly

## Problem 8.123

[Difficulty: 4]

**8.123** A water system is used in a laboratory to study flow in a smooth pipe. The water is at 10°C. To obtain a reasonable range, the maximum Reynolds number in the pipe must be 100,000. The system is supplied from an overhead constant-head tank. The pipe system consists of a square-edged entrance, two 45° standard elbows, two 90° standard elbows, and a fully open gate valve. The pipe diameter is 7.5 mm, and the total length of pipe is 1 m. Calculate the minimum height of the supply tank above the pipe system discharge to reach the desired Reynolds number. If a pressurized chamber is used instead of the reservoir, what will be the required pressure?

**Given:** Data on water system

**Find:** Minimum tank height; equivalent pressure

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

Available data  $D = 7.5\text{-mm}$   $L = 1\text{-m}$   $Re = 100000$  and so  $f = 0.0180$  at this  $Re$

From Section 8.7  $K_{ent} = 0.5$   $L_{elbow45} = 16 \cdot D$   $L_{elbow90} = 30 \cdot D$   $L_{GV} = 8 \cdot D$

$L_{elbow45} = 0.12\text{ m}$   $L_{elbow90} = 0.225\text{ m}$   $L_{GV} = 0.06\text{ m}$

From Table A.8 at 10°C  $\rho = 1000 \frac{\text{kg}}{\text{m}^3}$   $\mu = 1.3 \cdot 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$

Then  $Q = \frac{\pi \cdot \mu \cdot D \cdot Re}{4 \cdot \rho}$   $Q = 7.66 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$   $Q = 0.766 \frac{\text{l}}{\text{s}}$   $V = \frac{Q}{\left( \frac{\pi \cdot D^2}{4} \right)}$   $V = 17.3 \frac{\text{m}}{\text{s}}$

The energy equation becomes 
$$d - \frac{V^2}{2 \cdot g} = \frac{V^2}{2 \cdot g} \cdot \left( f \cdot \frac{L}{D} + 2 \cdot f \cdot \frac{L_{elbow90}}{D} + 2 \cdot f \cdot \frac{L_{elbow45}}{D} + f \cdot \frac{L_{GV}}{D} \right)$$

Hence 
$$d = \frac{V^2}{2 \cdot g} \cdot \left( 1 + f \cdot \frac{L}{D} + 2 \cdot f \cdot \frac{L_{elbow90}}{D} + 2 \cdot f \cdot \frac{L_{elbow45}}{D} + f \cdot \frac{L_{GV}}{D} \right) \quad d = 79.6\text{-m}$$


Unrealistic!

IF INSTEAD the reservoir was pressurized  $\Delta p = \rho \cdot g \cdot d$   $\Delta p = 781 \cdot \text{kPa}$  which is feasible

## Problem 8.124

[Difficulty: 2]

**8.124** Water from a pump flows through a 9-in.-diameter commercial steel pipe for a distance of 4 miles from the pump discharge to a reservoir open to the atmosphere. The level of the water in the reservoir is 50 ft above the pump discharge, and the average speed of the water in the pipe is 10 ft/s. Calculate the pressure at the pump discharge.



**Given:** Flow from pump to reservoir

**Find:** Pressure at pump discharge

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V_1^2}{2} + K_{exit} \cdot \frac{V_1^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $V_2 \ll V_1$

Hence the energy equation between Point 1 and the free surface (Point 2) becomes

$$\left( \frac{p_1}{\rho} + \frac{V_1^2}{2} \right) - (g \cdot z_2) = f \cdot \frac{L}{D} \cdot \frac{V_1^2}{2} + K_{exit} \cdot \frac{V_1^2}{2}$$

Solving for  $p_1$  
$$p_1 = \rho \cdot \left( g \cdot z_2 - \frac{V_1^2}{2} + f \cdot \frac{L}{D} \cdot \frac{V_1^2}{2} + K_{exit} \cdot \frac{V_1^2}{2} \right)$$

From Table A.7 (68°F)  $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \nu = 1.08 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$

$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 10 \cdot \frac{\text{ft}}{\text{s}} \times \frac{9}{12} \cdot \text{ft} \times \frac{\text{s}}{1.08 \times 10^{-5} \cdot \text{ft}^2} \quad \text{Re} = 6.94 \times 10^5 \quad \text{Turbulent}$$

For commercial steel pipe  $e = 0.00015 \cdot \text{ft}$  (Table 8.1) so  $\frac{e}{D} = 0.000200$

Flow is turbulent: Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0150$$

For the exit  $K_{exit} = 1.0$  so we find 
$$p_1 = \rho \cdot \left( g \cdot z_2 + f \cdot \frac{L}{D} \cdot \frac{V_1^2}{2} \right)$$

$$p_1 = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left[ 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 50 \cdot \text{ft} + .0150 \times \frac{4 \cdot \text{mile}}{0.75 \cdot \text{ft}} \times \frac{5280 \cdot \text{ft}}{1 \cdot \text{mile}} \times \frac{1}{2} \times \left( 10 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \right] \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad p_1 = 4.41 \times 10^4 \cdot \frac{\text{lbf}}{\text{ft}^2} \quad p_1 = 306 \cdot \text{psi}$$

## Problem 8.125

[Difficulty: 3]

**8.125** Water is to flow by gravity from one reservoir to a lower one through a straight, inclined galvanized iron pipe. The pipe diameter is 50 mm, and the total length is 250 m. Each reservoir is open to the atmosphere. Plot the required elevation difference  $\Delta z$  as a function of flow rate  $Q$ , for  $Q$  ranging from 0 to  $0.01 \text{ m}^3/\text{s}$ . Estimate the fraction of  $\Delta z$  due to minor losses.



**Given:** Data on reservoir/pipe system

**Find:** Plot elevation as a function of flow rate; fraction due to minor losses

**Solution:**

$$\begin{aligned} L &= 250 \text{ m} \\ D &= 50 \text{ mm} \\ e/D &= 0.003 \\ K_{\text{ent}} &= 0.5 \\ K_{\text{exit}} &= 1.0 \\ \nu &= 1.01\text{E-}06 \text{ m}^2/\text{s} \end{aligned}$$


$Q \text{ (m}^3/\text{s)}$	$V \text{ (m/s)}$	$Re$	$f$	$\Delta z \text{ (m)}$	$h_{lm}/h_{IT}$
0.0000	0.000	0.00E+00		0.000	
0.0005	0.255	1.26E+04	0.0337	0.562	0.882%
0.0010	0.509	2.52E+04	0.0306	2.04	0.972%
0.0015	0.764	3.78E+04	0.0293	4.40	1.01%
0.0020	1.02	5.04E+04	0.0286	7.64	1.04%
0.0025	1.27	6.30E+04	0.0282	11.8	1.05%
0.0030	1.53	7.56E+04	0.0279	16.7	1.07%
0.0035	1.78	8.82E+04	0.0276	22.6	1.07%
0.0040	2.04	1.01E+05	0.0275	29.4	1.08%
0.0045	2.29	1.13E+05	0.0273	37.0	1.09%
0.0050	2.55	1.26E+05	0.0272	45.5	1.09%
0.0055	2.80	1.39E+05	0.0271	54.8	1.09%
0.0060	3.06	1.51E+05	0.0270	65.1	1.10%
0.0065	3.31	1.64E+05	0.0270	76.2	1.10%
0.0070	3.57	1.76E+05	0.0269	88.2	1.10%
0.0075	3.82	1.89E+05	0.0269	101	1.10%
0.0080	4.07	2.02E+05	0.0268	115	1.11%
0.0085	4.33	2.14E+05	0.0268	129	1.11%
0.0090	4.58	2.27E+05	0.0268	145	1.11%
0.0095	4.84	2.40E+05	0.0267	161	1.11%
0.0100	5.09	2.52E+05	0.0267	179	1.11%



## Problem 8.126

[Difficulty: 3]

**8.126** A 5-cm-diameter potable water line is to be run through a maintenance room in a commercial building. Three possible layouts for the water line are proposed, as shown. Which is the best option, based on minimizing losses? Assume galvanized iron, and a flow rate of 350 L/min.



**Given:** Flow through three different layouts

**Find:** Which has minimum loss

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \sum_{\text{Minor}} \left( f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \right)$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) Ignore additional length of elbows

For a flow rate of  $Q = 350 \cdot \frac{\text{L}}{\text{min}} \quad V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = \frac{4}{\pi} \times 350 \cdot \frac{\text{L}}{\text{min}} \times \frac{0.001 \cdot \text{m}^3}{1 \cdot \text{L}} \times \frac{1 \cdot \text{min}}{60 \cdot \text{s}} \times \left( \frac{1}{0.05 \cdot \text{m}} \right)^2 \quad V = 2.97 \frac{\text{m}}{\text{s}}$

For water at 20°C  $\nu = 1.01 \times 10^{-6} \frac{\text{m}^2}{\text{s}} \quad \text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 2.97 \cdot \frac{\text{m}}{\text{s}} \times 0.05 \cdot \text{m} \times \frac{\text{s}}{1.01 \times 10^{-6} \cdot \text{m}^2} \quad \text{Re} = 1.47 \times 10^5$

Flow is turbulent. From Table 8.1  $e = 0.15 \cdot \text{mm} \quad \frac{e}{D} = 6.56 \times 10^{-4}$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7 \cdot D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0201$

For Case (a)  $L = \sqrt{5.25^2 + 2.5^2} \cdot \text{m} \quad L = 5.81 \text{ m} \quad \text{Two } 45^\circ \text{ miter bends (Fig. 8.16), for each } \frac{L_e}{D} = 13$

Hence the energy equation is  $\frac{p_1}{\rho} - \frac{p_2}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + 2 \cdot f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2}$

Solving for  $\Delta p$   $\Delta p = p_1 - p_2 = \rho \cdot f \cdot \frac{V^2}{2} \cdot \left( \frac{L}{D} + 2 \cdot \frac{L_e}{D} \right)$

$\Delta p = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times 0.0201 \times \left( 2.97 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \left( \frac{5.81}{0.05} + 2 \cdot 13 \right) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \Delta p = 25.2 \cdot \text{kPa}$

For Case (b)  $L = (5.25 + 2.5) \cdot \text{m} \quad L = 7.75 \text{ m} \quad \text{One standard } 90^\circ \text{ elbow (Table 8.4)} \quad \frac{L_e}{D} = 30$

Hence the energy equation is  $\frac{p_1}{\rho} - \frac{p_2}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2}$

Solving for  $\Delta p$

$$\Delta p = p_1 - p_2 = \rho \cdot f \cdot \frac{V^2}{2} \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right)$$

$$\Delta p = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times .0201 \times \left( 2.97 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \left( \frac{7.75}{0.05} + 30 \right) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \Delta p = 32.8 \cdot \text{kPa}$$

For Case (c)  $L = (5.25 + 2.5) \cdot \text{m} \quad L = 7.75 \text{ m} \quad \text{Three standard } 90^\circ \text{ elbows, for each} \quad \frac{L_e}{D} = 30$

Hence the energy equation is  $\frac{p_1}{\rho} - \frac{p_2}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + 3 \cdot f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2}$

Solving for  $\Delta p$

$$\Delta p = p_1 - p_2 = \rho \cdot f \cdot \frac{V^2}{2} \cdot \left( \frac{L}{D} + 3 \cdot \frac{L_e}{D} \right)$$

$$\Delta p = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times .0201 \times \left( 2.97 \cdot \frac{\text{m}}{\text{s}} \right)^2 \times \left( \frac{7.75}{0.05} + 3 \times 30 \right) \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \Delta p = 43.4 \cdot \text{kPa}$$

Hence we conclude Case (a) is the best and Case (c) is the worst

## Problem 8.127

[Difficulty: 2]

**8.127** In an air-conditioning installation, a flow rate of 1750 cfm of air at 50°F is required. A smooth sheet metal duct of rectangular section (0.75 ft by 2.5 ft) is to be used. Determine the pressure drop (inches of water) for a 1000-ft horizontal duct section.

**Given:** Flow through rectangular duct

**Find:** Pressure drop

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \sum_{\text{Minor}} \left( f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \right)$$

$$D_h = \frac{4 \cdot a \cdot b}{2 \cdot (a + b)}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Available data  $Q = 1750 \cdot \text{cfm}$   $L = 1000 \cdot \text{ft}$   $b = 2.5 \cdot \text{ft}$   $a = 0.75 \cdot \text{ft}$

At 50°F, from Table A.9  $\rho = 0.00242 \cdot \frac{\text{slug}}{\text{ft}^3}$   $\mu = 3.69 \cdot 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2}$   $\rho_w = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$

Hence  $V = \frac{Q}{a \cdot b}$   $V = 15.6 \cdot \frac{\text{ft}}{\text{s}}$  and  $D_h = \frac{4 \cdot a \cdot b}{2 \cdot (a + b)}$   $D_h = 1.15 \cdot \text{ft}$

$$Re = \frac{\rho \cdot V \cdot D_h}{\mu} \quad Re = 1.18 \times 10^5$$

For a smooth duct  $\frac{1}{\sqrt{f}} = -2 \cdot \log \left( \frac{2.51}{Re \cdot \sqrt{f}} \right)$  so  $f = 0.017$


Hence  $\Delta p = f \cdot \frac{L}{D_h} \cdot \rho \cdot \frac{V^2}{2}$   $\Delta p = 0.031 \cdot \text{psi}$

or, in in water  $h = \frac{\Delta p}{\rho_w \cdot g}$   $h = 0.848 \cdot \text{in}$

## Problem 8.128

[Difficulty: 3]

**8.128** A system for testing variable-output pumps consists of the pump, four standard elbows, and an open gate valve forming a closed circuit as shown. The circuit is to absorb the energy added by the pump. The tubing is 75-mm-diameter cast iron, and the total length of the circuit is 20-m. Plot the pressure difference required from the pump for water flow rates  $Q$  ranging from 0.01 m<sup>3</sup>/s to 0.06 m<sup>3</sup>/s.



**Given:** Data on circuit

**Find:** Plot pressure difference for a range of flow rates

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$f = \frac{64}{Re} \quad (8.36) \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$


The energy equation (Eq. 8.29) becomes for the circuit ( 1 = pump inlet, 2 = pump outlet)

$$\frac{p_1 - p_2}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + 4 \cdot f \cdot L_{\text{elbow}} \cdot \frac{V^2}{2} + f \cdot L_{\text{valve}} \cdot \frac{V^2}{2} \quad \text{or} \quad \Delta p = \rho \cdot f \cdot \frac{V^2}{2} \cdot \left( \frac{L}{D} + 4 \cdot \frac{L_{\text{elbow}}}{D} + \frac{L_{\text{valve}}}{D} \right)$$

In Excel:

Given data:			Tabulated or graphical data:		
$L =$	20	m	$\epsilon =$	0.26	mm
$D =$	75	mm	(Table 8.1)		
			$\mu =$	1.00E-03	N.s/m <sup>2</sup>
			$\rho =$	999	kg/m <sup>3</sup>
			(Appendix A)		
			Gate valve $L_e/D =$	8	
			Elbow $L_e/D =$	30	
			(Table 8.4)		
Computed results:					
$Q$ (m <sup>3</sup> /s)	$V$ (m/s)	$Re$	$f$	$\Delta p$ (kPa)	
0.010	2.26	1.70E+05	0.0280	28.3	
0.015	3.40	2.54E+05	0.0277	63.1	
0.020	4.53	3.39E+05	0.0276	112	
0.025	5.66	4.24E+05	0.0276	174	
0.030	6.79	5.09E+05	0.0275	250	
0.035	7.92	5.94E+05	0.0275	340	
0.040	9.05	6.78E+05	0.0274	444	
0.045	10.2	7.63E+05	0.0274	561	
0.050	11.3	8.48E+05	0.0274	692	
0.055	12.4	9.33E+05	0.0274	837	
0.060	13.6	1.02E+06	0.0274	996	


### Required Pressure Head for a Circuit



## Problem 8.129

[Difficulty: 3]

**8.129** A pipe friction experiment is to be designed, using water, to reach a Reynolds number of 100,000. The system will use 5-cm smooth PVC pipe from a constant-head tank to the flow bench and 20 m of smooth 2.5-cm PVC line mounted horizontally for the test section. The water level in the constant-head tank is 0.5 m above the entrance to the 5-cm PVC line. Determine the required average speed of water in the 2.5-cm pipe. Estimate the feasibility of using a constant-head tank. Calculate the pressure difference expected between taps 5 m apart in the horizontal test section.



**Given:** Pipe friction experiment

**Find:** Required average speed; Estimate feasibility of constant head tank; Pressure drop over 5 m

**Solution:**

$$\text{Basic equations} \quad \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_A + h_B = f_A \cdot \frac{L_A}{D_A} \cdot \frac{V_A^2}{2} + f_B \cdot \frac{L_B}{D_B} \cdot \frac{V_B^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) Ignore minor losses

We wish to have  $Re_B = 10^5$

$$\text{Hence, from} \quad Re_B = \frac{V_B \cdot D_B}{\nu} \quad V_B = \frac{Re_B \cdot \nu}{D_B} \quad \text{and for water at } 20^\circ\text{C} \quad \nu = 1.01 \times 10^{-6} \frac{\text{m}^2}{\text{s}}$$

$$V_B = 10^5 \times 1.01 \times 10^{-6} \frac{\text{m}^2}{\text{s}} \times \frac{1}{0.025 \cdot \text{m}} \quad V_B = 4.04 \frac{\text{m}}{\text{s}}$$

$$\text{We will also need} \quad V_A = V_B \cdot \left( \frac{D_B}{D_A} \right)^2 \quad V_A = 4.04 \cdot \frac{\text{m}}{\text{s}} \times \left( \frac{2.5}{5} \right)^2 \quad V_A = 1.01 \frac{\text{m}}{\text{s}}$$

$$Re_A = \frac{V_A \cdot D_A}{\nu} \quad Re_A = 1.01 \cdot \frac{\text{m}}{\text{s}} \times 0.05 \cdot \text{m} \times \frac{\text{s}}{1.01 \times 10^{-6} \cdot \text{m}^2} \quad Re_A = 5 \times 10^4$$

Both tubes have turbulent flow

For PVC pipe (from Googling!)  $e = 0.0015 \cdot \text{mm}$

$$\text{For tube A} \quad \text{Given} \quad \frac{1}{\sqrt{f_A}} = -2.0 \cdot \log \left( \frac{e}{3.7 D_A} + \frac{2.51}{Re_A \cdot \sqrt{f_A}} \right) \quad f_A = 0.0210$$

$$\text{For tube B} \quad \text{Given} \quad \frac{1}{\sqrt{f_B}} = -2.0 \cdot \log \left( \frac{e}{3.7 D_B} + \frac{2.51}{Re_B \cdot \sqrt{f_B}} \right) \quad f_B = 0.0183$$

Applying the energy equation between Points 1 and 3

$$g \cdot (L_A + h) - \frac{V_B^2}{2} = f_A \cdot \frac{L_A}{D_A} \cdot \frac{V_A^2}{2} + f_B \cdot \frac{L_B}{D_B} \cdot \frac{V_B^2}{2}$$

Solving for  $L_A$

$$L_A = \frac{\frac{V_B^2}{2} \cdot \left(1 + f_B \cdot \frac{L_B}{D_B}\right) - g \cdot h}{\left(g - \frac{f_A}{D_A} \cdot \frac{V_A^2}{2}\right)}$$

$$L_A = \frac{\frac{1}{2} \times \left(4.04 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times \left(1 + 0.0183 \times \frac{20}{0.025}\right) - 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 0.5 \cdot \text{m}}{9.81 \cdot \frac{\text{m}}{\text{s}^2} - \frac{0.0210}{2} \times \frac{1}{0.05 \cdot \text{m}} \times \left(1.01 \cdot \frac{\text{m}}{\text{s}}\right)^2}$$

$$L_A = 12.8 \text{ m}$$

Most ceilings are about 3.5 m or 4 m, so this height is IMPRACTICAL

Applying the energy equation between Points 2 and 3

$$\left(\frac{p_2}{\rho} + \frac{V_B^2}{2}\right) - \left(\frac{p_3}{\rho} + \frac{V_B^2}{2}\right) = f_B \cdot \frac{L}{D_B} \cdot \frac{V_B^2}{2} \quad \text{or} \quad \Delta p = \rho \cdot f_B \cdot \frac{L}{D_B} \cdot \frac{V_B^2}{2}$$


$$\Delta p = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \frac{0.0183}{2} \times \frac{5 \cdot \text{m}}{0.025 \cdot \text{m}} \times \left(4.04 \cdot \frac{\text{m}}{\text{s}}\right)^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\Delta p = 29.9 \cdot \text{kPa}$$

### Problem 8.130

[Difficulty: 3] Part 1/2

**8.130** Two reservoirs are connected by three clean cast-iron pipes in series,  $L_1 = 600$  m,  $D_1 = 0.3$  m,  $L_2 = 900$  m,  $D_2 = 0.4$  m,  $L_3 = 1500$  m, and  $D_3 = 0.45$  m. When the discharge is  $0.11$  m<sup>3</sup>/s of water at  $15^\circ\text{C}$ , determine the difference in elevation between the reservoirs.



Solution: Apply the energy equation for steady, incompressible flow that is uniform at each section.

$$\text{Basic equations: } \frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2 + h_{ET}$$

$$h_{ET} = \sum f \frac{L}{D} \frac{V^2}{2} + h_{em}; \quad h_{em} = K_{ent} \frac{V^2}{2} + \sum h_{exp} + K_{exit} \frac{V^2}{2}$$

Assumptions: (1)  $p_1 = p_2 = p_{atm}$

(2)  $V_1 = V_2 = 0$

(3) Neglect  $h_{exp}$  at pipe joints (note all minor losses are probably small due to long lengths of straight pipe sections, but we will check)

For non-smooth pipe,  $f = f(Re, e/D)$ ,  $\mu = 1.1 \times 10^{-3} \text{ N}\cdot\text{s}/\text{m}^2$  from Table A.8.

Section ②:  $e/D_2 = 0.24 \text{ mm}/300 \text{ mm} = 0.00087$  (for cast iron,  $e = 0.24 \text{ mm}$ , Table 8.1)

$$V_2 = \frac{Q}{A_2} = \frac{0.11 \text{ m}^3/\text{s}}{\pi (0.3)^2 \text{ m}^2} = 1.56 \text{ m/s}$$

$$Re_2 = \frac{\rho V_2 D_2}{\mu} = \frac{999 \text{ kg}/\text{m}^3 \times 1.56 \text{ m}/\text{s} \times 0.3 \text{ m}}{1.14 \times 10^{-3} \text{ N}\cdot\text{s}/\text{m}^2} = 4.10 \times 10^5$$

From Fig. 8.13,  $f_2 = 0.020$

Section ③:  $e/D_3 = 0.00065$

$$V_3 = \frac{Q}{A_3} = \frac{0.11 \text{ m}^3/\text{s}}{\pi (0.4)^2 \text{ m}^2} = 0.875 \text{ m/s}$$

$$Re_3 = \frac{\rho V_3 D_3}{\mu} = \frac{999 \text{ kg}/\text{m}^3 \times 0.875 \text{ m}/\text{s} \times 0.4 \text{ m}}{1.14 \times 10^{-3} \text{ N}\cdot\text{s}/\text{m}^2} = 3.07 \times 10^5$$

From Fig. 8.13,  $f_3 = 0.019$

Section ④:  $e/D_4 = 0.00058$

$$\bar{V}_4 = \frac{Q}{A_4} = \frac{0.11 \frac{\text{m}^3}{\text{s}}}{\frac{4}{\pi} (0.45)^2 \text{m}^2} = 0.692 \text{ m/s}$$

$$Re_4 = \frac{\rho \bar{V}_4 D_4}{\mu} = \frac{999 \frac{\text{kg}}{\text{m}^3} \times 0.692 \frac{\text{m}}{\text{s}} \times 0.45 \text{ m}}{1.14 \times 10^{-3} \frac{\text{N}\cdot\text{s}}{\text{kg}\cdot\text{m}}} = 2.73 \times 10^5$$

From Fig. 8.13,  $f_4 = 0.0185$

$$\begin{aligned} \text{Then } \sum f \frac{L}{D} \frac{\bar{V}^2}{2} &= 0.020 \times \frac{600 \text{ m}}{0.3 \text{ m}} \times \frac{1}{2} \frac{(1.56)^2 \text{ m}^2}{\text{s}^2} + 0.019 \times \frac{900 \text{ m}}{0.4 \text{ m}} \times \frac{1}{2} \frac{(0.875)^2 \text{ m}^2}{\text{s}^2} \\ &+ 0.0185 \times \frac{1500 \text{ m}}{0.45 \text{ m}} \times \frac{1}{2} \frac{(0.692)^2 \text{ m}^2}{\text{s}^2} = 79.8 \text{ m}^2/\text{s}^2 \end{aligned}$$

The minor loss coefficients are  $K_{ent} = 0.5$  (Table 8.2) and  $K_{exit} = 1.0$ . Thus,

$$h_{em} = K_{ent} \frac{\bar{V}_2^2}{2} + K_{exit} \frac{\bar{V}_4^2}{2}$$

$$h_{em} = 0.5 \times \frac{1}{2} \times \frac{(1.56)^2 \text{ m}^2}{\text{s}^2} + 1.0 \times \frac{1}{2} \times \frac{(0.692)^2 \text{ m}^2}{\text{s}^2} = 0.848 \text{ m}^2/\text{s}^2$$

Therefore minor losses are roughly 1 percent of the frictional losses, so they may be neglected. Thus from the energy equation

$$z_1 - z_5 = \sum f \frac{L}{D} \frac{\bar{V}^2}{2g} = \frac{79.8 \text{ m}^2/\text{s}^2}{9.81 \text{ m/s}^2} = 8.13 \text{ m.}$$

$z_1 - z_5$  ←

## Problem 8.131

[Difficulty: 3]

**8.131** Consider flow of standard air at 1250 ft<sup>3</sup>/min. Compare the pressure drop per unit length of a round duct with that for rectangular ducts of aspect ratio 1, 2, and 3. Assume that all ducts are smooth, with cross-sectional areas of 1 ft<sup>2</sup>.

**Given:** Same flow rate in various ducts

**Find:** Pressure drops of each compared to round duct

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad D_h = \frac{4 \cdot A}{P_w} \quad e = 0 \quad (\text{Smooth})$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) Ignore minor losses

The energy equation simplifies to

$$\Delta p = p_1 - p_2 = \rho \cdot f \cdot \frac{L}{D_h} \cdot \frac{V^2}{2} \quad \text{or} \quad \frac{\Delta p}{L} = \rho \cdot \frac{f}{D_h} \cdot \frac{V^2}{2}$$

But we have 
$$V = \frac{Q}{A} \quad V = 1250 \cdot \frac{\text{ft}^3}{\text{min}} \times \frac{1 \cdot \text{min}}{60 \cdot \text{s}} \times \frac{1}{1 \cdot \text{ft}^2} \quad V = 20.8 \cdot \frac{\text{ft}}{\text{s}}$$

From Table A.9 
$$\nu = 1.62 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \quad \rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \text{at } 68^\circ\text{F}$$

Hence 
$$\text{Re} = \frac{V \cdot D_h}{\nu} \quad \text{Re} = 20.8 \cdot \frac{\text{ft}}{\text{s}} \times \frac{\text{s}}{1.62 \times 10^{-4} \cdot \text{ft}^2} \times D_h = 1.284 \times 10^5 \cdot D_h \quad (D_h \text{ in ft})$$

For a round duct 
$$D_h = D = \sqrt{\frac{4 \cdot A}{\pi}} \quad D_h = \sqrt{\frac{4}{\pi} \times 1 \cdot \text{ft}^2} \quad D_h = 1.13 \cdot \text{ft}$$

For a rectangular duct 
$$D_h = \frac{4 \cdot A}{P_w} = \frac{4 \cdot b \cdot h}{2 \cdot (b + h)} = \frac{2 \cdot h \cdot \text{ar}}{1 + \text{ar}} \quad \text{where} \quad \text{ar} = \frac{b}{h}$$

But 
$$h = \frac{b}{\text{ar}} \quad \text{so} \quad h^2 = \frac{b \cdot h}{\text{ar}} = \frac{A}{\text{ar}} \quad \text{or} \quad h = \sqrt{\frac{A}{\text{ar}}} \quad \text{and} \quad D_h = \frac{2 \cdot \sqrt{\text{ar}}}{1 + \text{ar}} \cdot \sqrt{A}$$

The results are:

Round 
$$D_h = 1.13 \cdot \text{ft} \quad \text{Re} = 1.284 \times 10^5 \cdot \frac{1}{\text{ft}} \cdot D_h \quad \text{Re} = 1.45 \times 10^5$$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7 D_h} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0167 \quad \frac{\Delta p}{L} = \rho \cdot \frac{f}{D_h} \cdot \frac{V^2}{2} \quad \frac{\Delta p}{L} = 7.51 \times 10^{-3} \cdot \frac{\text{lbf}}{\text{ft}^3}$$

ar = 1 
$$D_h = \frac{2 \cdot \sqrt{\text{ar}}}{1 + \text{ar}} \cdot \sqrt{A} \quad D_h = 1 \cdot \text{ft} \quad \text{Re} = 1.284 \times 10^5 \cdot \frac{1}{\text{ft}} \cdot D_h \quad \text{Re} = 1.28 \times 10^5$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{D_h} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0171 \quad \frac{\Delta p}{L} = \rho \cdot \frac{f}{D_h} \cdot \frac{V^2}{2} \quad \frac{\Delta p}{L} = 8.68 \times 10^{-3} \frac{\text{lbf}}{\text{ft}^3}$$

Hence the square duct experiences a percentage increase in pressure drop of  $\frac{8.68 \times 10^{-3} - 7.51 \times 10^{-3}}{7.51 \times 10^{-3}} = 15.6\%$

$$\text{ar} = 2 \quad D_h = \frac{2 \cdot \sqrt{\text{ar}}}{1 + \text{ar}} \cdot \sqrt{A} \quad D_h = 0.943 \cdot \text{ft} \quad \text{Re} = 1.284 \times 10^5 \cdot \frac{1}{\text{ft}} \cdot D_h \quad \text{Re} = 1.21 \times 10^5$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{D_h} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0173 \quad \frac{\Delta p}{L} = \rho \cdot \frac{f}{D_h} \cdot \frac{V^2}{2} \quad \frac{\Delta p}{L} = 9.32 \times 10^{-3} \frac{\text{lbf}}{\text{ft}^3}$$

Hence the 2 x 1 duct experiences a percentage increase in pressure drop of  $\frac{9.32 \times 10^{-3} - 7.51 \times 10^{-3}}{7.51 \times 10^{-3}} = 24.1\%$

$$\text{ar} = 3 \quad D_h = \frac{2 \cdot \sqrt{\text{ar}}}{1 + \text{ar}} \cdot \sqrt{A} \quad D_h = 0.866 \cdot \text{ft} \quad \text{Re} = 1.284 \times 10^5 \cdot \frac{1}{\text{ft}} \cdot D_h \quad \text{Re} = 1.11 \times 10^5$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{D_h} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0176 \quad \frac{\Delta p}{L} = \rho \cdot \frac{f}{D_h} \cdot \frac{V^2}{2} \quad \frac{\Delta p}{L} = 0.01 \frac{\text{lbf}}{\text{ft}^3}$$

Hence the 3 x 1 duct experiences a percentage increase in pressure drop of  $\frac{0.01 - 7.51 \times 10^{-3}}{7.51 \times 10^{-3}} = 33.2\%$

Note that  $f$  varies only about 7%; the large change in  $\Delta p/L$  is primarily due to the  $1/D_h$  factor

## Problem 8.132

[Difficulty: 4]

**8.132** Data were obtained from measurements on a vertical section of old, corroded, galvanized iron pipe of 50 mm inside diameter. At one section the pressure was  $p_1 = 750$  kPa (gage); at a second section, 40 m lower, the pressure was  $p_2 = 250$  kPa (gage). The volume flow rate of water was  $0.015$  m<sup>3</sup>/s. Estimate the relative roughness of the pipe. What percentage savings in pumping power would result if the pipe were restored to its new, clean relative roughness?

**Given:** Flow down corroded iron pipe

**Find:** Pipe roughness; Power savings with new pipe

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_1 \quad h_1 = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) No minor losses

Available data  $D = 50\text{-mm}$   $\Delta z = 40\text{-m}$   $L = \Delta z$   $p_1 = 750\text{-kPa}$   $p_2 = 250\text{-kPa}$   $Q = 0.015 \frac{\text{m}^3}{\text{s}}$   $\rho = 999 \frac{\text{kg}}{\text{m}^3}$

Hence the energy equation becomes

$$\left( \frac{p_1}{\rho} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + g \cdot z_2 \right) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Here  $V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V = \frac{4}{\pi} \times 0.015 \frac{\text{m}^3}{\text{s}} \times \frac{1}{(0.05\text{-m})^2}$   $V = 7.64 \frac{\text{m}}{\text{s}}$

In this problem we can compute directly  $f$  and  $Re$ , and hence obtain  $e/D$

Solving for  $f$  
$$f = \frac{2 \cdot D}{L \cdot V^2} \cdot \left( \frac{p_1 - p_2}{\rho} + g(z_1 - z_2) \right)$$

$$f = 2 \times \frac{0.05}{40} \times \left( \frac{\text{s}}{7.64 \cdot \text{m}} \right)^2 \times \left[ (750 - 250) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} + 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times 40 \cdot \text{m} \right] f = 0.0382$$

From Table A.8 (20°F)  $\nu = 1.01 \times 10^{-6} \frac{\text{m}^2}{\text{s}}$   $Re = \frac{V \cdot D}{\nu}$   $Re = 7.64 \cdot \frac{\text{m}}{\text{s}} \times 0.05 \cdot \text{m} \times \frac{\text{s}}{1.01 \times 10^{-6} \cdot \text{m}^2}$   $Re = 3.78 \times 10^5$

Flow is turbulent: 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{D} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$$

Solving for e

$$e = 3.7 \cdot D \cdot \left( 10^{-\frac{1}{2 \cdot \sqrt{f}}} - \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad e = 0.507 \text{ mm} \quad \frac{e}{D} = 0.0101$$

New pipe (Table 8.1)  $e = 0.15 \cdot \text{mm} \quad \frac{e}{D} = 0.003$

Given

$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$$

$$f = 0.0326$$

In this problem

$$\Delta p = p_1 - p_2 = \rho \cdot \left[ g \cdot (z_2 - z_1) + f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \right]$$

Hence

$$\Delta p_{\text{new}} = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (-40 \cdot \text{m}) + \frac{0.0326}{2} \times \frac{40}{0.05} \times \left( 7.64 \cdot \frac{\text{m}}{\text{s}} \right)^2 \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \Delta p_{\text{new}} = 369 \cdot \text{kPa}$$

$$\Delta p_{\text{old}} = p_1 - p_2 \quad \Delta p_{\text{old}} = 500 \text{ kPa}$$

Compared to  $\Delta p_{\text{old}} = 500 \cdot \text{kPa}$  we find

$$\frac{\Delta p_{\text{old}} - \Delta p_{\text{new}}}{\Delta p_{\text{old}}} = 26.3\%$$

As power is  $\Delta p Q$  and  $Q$  is constant, the power reduction is the same as the above percentage!

## Problem 8.133

[Difficulty: 3]

**8.133** Water, at volume flow rate  $Q = 0.75 \text{ ft}^3/\text{s}$ , is delivered by a fire hose and nozzle assembly. The hose ( $L = 250 \text{ ft}$ ,  $D = 3 \text{ in.}$ , and  $e/D = 0.004$ ) is made up of four 60-ft sections joined by couplings. The entrance is square-edged; the minor loss coefficient for each coupling is  $K_c = 0.5$ , based on mean velocity through the hose. The nozzle loss coefficient is  $K_n = 0.02$ , based on velocity in the exit jet, of  $D_2 = 1 \text{ in.}$  diameter. Estimate the supply pressure required at this flow rate.

**Given:** Flow through fire hose and nozzle

**Find:** Supply pressure

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \sum_{\text{Minor}} \left( K \cdot \frac{V^2}{2} \right)$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4)  $p_2 = p_{\text{atm}}$  so  $p_2 = 0$  gage

Hence the energy equation between Point 1 at the supply and the nozzle exit (Point n); let the velocity in the hose be  $V$

$$\frac{p_1}{\rho} - \frac{V_n^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + (K_e + 4 \cdot K_c) \cdot \frac{V^2}{2} + K_n \cdot \frac{V_n^2}{2}$$

From continuity 
$$V_n = \left( \frac{D}{D_2} \right)^2 \cdot V \quad \text{and} \quad V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = \frac{4}{\pi} \times 0.75 \frac{\text{ft}^3}{\text{s}} \times \frac{1}{\left( \frac{1}{4} \cdot \text{ft} \right)^2} \quad V = 15.3 \frac{\text{ft}}{\text{s}}$$

Solving for  $p_1$  
$$p_1 = \frac{\rho \cdot V^2}{2} \cdot \left[ f \cdot \frac{L}{D} + K_e + 4 \cdot K_c + \left( \frac{D}{D_2} \right)^4 \cdot (1 + K_n) \right]$$

From Table A.7 (68°F) 
$$\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \nu = 1.08 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$$

$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 15.3 \cdot \frac{\text{ft}}{\text{s}} \times \frac{3}{12} \cdot \text{ft} \times \frac{\text{s}}{1.08 \times 10^{-5} \cdot \text{ft}^2} \quad \text{Re} = 3.54 \times 10^5 \quad \text{Turbulent}$$

For the hose 
$$\frac{e}{D} = 0.004$$

Flow is turbulent: Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e/D}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0287$$

$$p_1 = \frac{1}{2} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 15.3 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \left[ 0.0287 \times \frac{250}{\frac{1}{4}} + 0.5 + 4 \times 0.5 + \left( \frac{3}{1} \right)^4 \times (1 + 0.02) \right] \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$p_1 = 2.58 \times 10^4 \cdot \frac{\text{lbf}}{\text{ft}^2} \quad p_1 = 179 \cdot \text{psi}$$

## Problem 8.134

[Difficulty: 4]

**8.134** Flow in a tube may alternate between laminar and turbulent states for Reynolds numbers in the transition zone. Design a bench-top experiment consisting of a constant-head cylindrical transparent plastic tank with depth graduations, and a length of plastic tubing (assumed smooth) attached at the base of the tank through which the water flows to a measuring container. Select tank and tubing dimensions so that the system is compact, but will operate in the transition zone range. Design the experiment so that you can easily increase the tank head from a low range (laminar flow) through transition to turbulent flow, and vice versa. (Write instructions for students on recognizing when the flow is laminar or turbulent.) Generate plots (on the same graph) of tank depth against Reynolds number, assuming laminar or turbulent flow.

**Given:** Proposal for bench top experiment

**Find:** Design it; Plot tank depth versus Re

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$f = \frac{64}{Re} \quad (8.36) \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

The energy equation (Eq. 8.29) becomes

$$g \cdot H - \alpha \cdot \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$$

This can be solved explicitly for reservoir height  $H$

$$H = \frac{V^2}{2 \cdot g} \cdot \left( \alpha + f \cdot \frac{L}{D} + K \right)$$


In Excel:

Choose data:			Tabulated or graphical data:		
$L =$	1.0	m	$\mu =$	1.00E-03	N.s/m <sup>2</sup>
$D =$	3.0	mm	$\rho =$	999	kg/m <sup>3</sup>
$e =$	0.0	mm	(Appendix A)		
$\alpha =$	2	(Laminar)	$K_{ent} =$	0.5	(Square-edged)
$=$	1	(Turbulent)	(Table 8.2)		

Computed results:

$Q$ (L/min)	$V$ (m/s)	$Re$	Regime	$f$	$H$ (m)
0.200	0.472	1413	Laminar	0.0453	0.199
0.225	0.531	1590	Laminar	0.0403	0.228
0.250	0.589	1767	Laminar	0.0362	0.258
0.275	0.648	1943	Laminar	0.0329	0.289
0.300	0.707	2120	Laminar	0.0302	0.320
0.325	0.766	2297	Laminar	0.0279	0.353
0.350	0.825	2473	Turbulent	0.0462	0.587
0.375	0.884	2650	Turbulent	0.0452	0.660
0.400	0.943	2827	Turbulent	0.0443	0.738
0.425	1.002	3003	Turbulent	0.0435	0.819
0.450	1.061	3180	Turbulent	0.0428	0.904


The flow rates are realistic, and could easily be measured using a tank/timer system  
 The head required is also realistic for a small-scale laboratory experiment  
 Around  $Re = 2300$  the flow may oscillate between laminar and turbulent:  
 Once turbulence is triggered (when  $H > 0.353$  m), the resistance to flow increases  
 requiring  $H > 0.587$  m to maintain; hence the flow reverts to laminar, only to trip over  
 again to turbulent! This behavior will be visible: the exit flow will switch back and  
 forth between smooth (laminar) and chaotic (turbulent)



Problem 8.135

[Difficulty: 3]

8.135 A small swimming pool is drained using a garden hose. The hose has 20 mm inside diameter, a roughness height of 0.2 mm, and is 30 m long. The free end of the hose is located 3 m below the elevation of the bottom of the pool. The average velocity at the hose discharge is 1.2 m/s. Estimate the depth of the water in the swimming pool. If the flow were inviscid, what would be the velocity?



Solution:

Apply the energy equation for steady incompressible flow between sections ① and ②.

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + gz_2 \right) = h_{\text{net}} \quad (8.2a)$$

$$h_{\text{net}} = h_e + h_{\text{em}}; \quad h_e = f \frac{L}{D} \frac{V^2}{2}; \quad h_{\text{em}} = K_{\text{ent}} \frac{V^2}{2}$$

- Assumptions:
- (1)  $p_1 = p_2 = p_{\text{atm}}$
  - (2)  $V_1 = 0, \alpha_2 = 1.0$
  - (3) square edged entrance

Then

$$z_1 - z_2 = d + 3\text{m} = f \frac{L}{D} \frac{V^2}{2g} + K_{\text{ent}} \frac{V^2}{2g} + \frac{V^2}{2g} = \frac{V^2}{2g} \left[ f \frac{L}{D} + K_{\text{ent}} + 1 \right]$$

$$\therefore d = \frac{V^2}{2g} \left[ f \frac{L}{D} + K_{\text{ent}} + 1 \right] - 3\text{m} \quad (1)$$

For square edged entrance (Table 8.2)  $K_{\text{ent}} = 0.5$

$$Re = \frac{VD}{\nu} = \frac{0.020\text{m} \times 1.2\text{m/s}}{1.00 \times 10^{-6} \frac{\text{m}^2}{\text{s}}} = 2.4 \times 10^4 \quad \left\{ \begin{array}{l} \text{assume } T = 20^\circ\text{C} \\ \text{Table A.8} \end{array} \right.$$

$\epsilon_D = 0.2/20 = 0.01$ . From Fig. 8.13,  $f = 0.04$

Then from Eq. 1

$$d = \frac{(1.2)^2}{2 \times 9.81} \times 2.81\text{m} \left[ 0.04 \times \frac{30}{0.02} + 0.5 + 1 \right] - 3\text{m} = 1.51\text{m} \leftarrow d$$

For frictionless flow,  $h_{\text{net}} = f \frac{L}{D} \frac{V^2}{2} + K_{\text{ent}} \frac{V^2}{2} = 0$  and

Eq. 1 gives  $d = \frac{V^2}{2g} - 3\text{m}$

and  $V = [2g(d+3\text{m})]^{1/2} = \left[ 2 \times 9.81 \frac{\text{m}}{\text{s}^2} (1.51+3)\text{m} \right]^{1/2}$

$V = 9.41\text{ m/s} \leftarrow V_{\text{inviscid}}$

100% RECYCLED PAPER  
 50% RECYCLED FIBER  
 100% RECYCLED INK  
 100% RECYCLED GLUE  
 100% RECYCLED COVER  
 100% RECYCLED BINDING  
 100% RECYCLED CONTENTS  
 100% RECYCLED PAPER  
 50% RECYCLED FIBER  
 100% RECYCLED INK  
 100% RECYCLED GLUE  
 100% RECYCLED COVER  
 100% RECYCLED BINDING  
 100% RECYCLED CONTENTS  
 National Brand

## Problem 8.136

[Difficulty: 3]

**8.136** When you drink your beverage with a straw, you need to overcome both gravity and friction in the straw. Estimate the fraction of the total effort you put into quenching your thirst of each factor, making suitable assumptions about the liquid and straw properties, and your drinking rate (for example, how long it would take you to drink a 12-oz drink if you drank it all in one go (quite a feat with a straw). Is the flow laminar or turbulent? (Ignore minor losses.)

**Given:** Drinking of a beverage

**Find:** Fraction of effort of drinking of friction and gravity

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) No minor losses

Hence the energy equation becomes, between the bottom of the straw (Point 1) and top (Point 2)

$$g \cdot z_1 - \left( \frac{p_2}{\rho} + g \cdot z_2 \right) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad \text{where } p_2 \text{ is the gage pressure in the mouth}$$

The negative gage pressure the mouth must create is therefore due to two parts

$$p_{\text{grav}} = -\rho \cdot g \cdot (z_2 - z_1) \quad p_{\text{fric}} = -\rho \cdot f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Assuming a person can drink 12 fluid ounces in 5 s

$$Q = \frac{12 \cdot \text{gal}}{5 \cdot \text{s}} \times \frac{1 \cdot \text{ft}^3}{7.48 \cdot \text{gal}} \quad Q = 2.51 \times 10^{-3} \cdot \frac{\text{ft}^3}{\text{s}}$$

Assuming a straw is 6 in long diameter 0.2 in, with roughness  $e = 5 \times 10^{-5}$  in (from Googling!)

$$V = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = \frac{4}{\pi} \times 2.51 \times 10^{-3} \frac{\text{ft}^3}{\text{s}} \times \left( \frac{1}{0.2 \cdot \text{in}} \times \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \quad V = 11.5 \cdot \frac{\text{ft}}{\text{s}}$$

From Table A.7 (68°F)  $\nu = 1.08 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$  (for water, but close enough)

$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 11.5 \cdot \frac{\text{ft}}{\text{s}} \times \frac{0.2}{12} \cdot \text{ft} \times \frac{\text{s}}{1.08 \times 10^{-5} \cdot \text{ft}^2} \quad \text{Re} = 1.775 \times 10^4$$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0272$$

Then 
$$p_{\text{grav}} = -1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{1}{2} \cdot \text{ft} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad p_{\text{grav}} = -31.2 \cdot \frac{\text{lbf}}{\text{ft}^2} \quad p_{\text{grav}} = -0.217 \cdot \text{psi}$$

and 
$$p_{\text{fric}} = -1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 0.0272 \times \frac{6}{0.2} \times \frac{1}{2} \times \left( 11.5 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad p_{\text{fric}} = -105 \cdot \frac{\text{lbf}}{\text{ft}^2} \quad p_{\text{fric}} = -0.727 \cdot \text{psi}$$

Hence the fraction due to friction is 
$$\frac{p_{\text{fric}}}{p_{\text{fric}} + p_{\text{grav}}} = 77.7\% \quad \text{and gravity is} \quad \frac{p_{\text{grav}}}{p_{\text{fric}} + p_{\text{grav}}} = 23.3\%$$

These results will vary depending on assumptions, but it seems friction is significant!

## Problem 8.137

[Difficulty: 4]

**8.137** The hose in Problem 8.135 is replaced with a larger-diameter hose, diameter 25 mm (same length and roughness). Assuming a pool depth of 1.5 m, what will be the new average velocity and flow rate?

**Given:** Draining of swimming pool with larger hose

**Find:** Flow rate and average velocity

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad h_{lm} = K_{ent} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) No minor losses

Available data  $D = 25\text{-mm} \quad L = 30\text{-m} \quad e = 0.2\text{-mm} \quad h = 3\text{-m} \quad \Delta z = 1.5\text{-m} \quad K_{ent} = 0.5 \quad \nu = 1 \cdot 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$

Hence the energy equation becomes 
$$g \cdot (\Delta z + h) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{ent} \cdot \frac{V^2}{2} + \frac{V^2}{2}$$

Solving for V 
$$V = \sqrt{\frac{2 \cdot g \cdot (\Delta z + h)}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad (1)$$

We also have 
$$Re = \frac{V \cdot D}{\nu} \quad (2) \quad \text{In addition} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (3)$$

Equations 1, 2 and 3 form a set of simultaneous equations for V, Re and f, which we can solve iteratively

Make a guess for f  $f = 0.1$  then 
$$V = \sqrt{\frac{2 \cdot g \cdot (\Delta z + h)}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad V = 0.852 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.13 \times 10^4$$

using Eq 3, at this Re  $f = 0.0382$

Then, repeating 
$$V = \sqrt{\frac{2 \cdot g \cdot (\Delta z + h)}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad V = 1.37 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 3.41 \times 10^4$$

using Eq 3, at this Re  $f = 0.0371$

Then, repeating 
$$V = \sqrt{\frac{2 \cdot g \cdot (\Delta z + h)}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad V = 1.38 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 3.46 \times 10^4$$

Using Eq 3, at this Re  $f = 0.0371$  which is the same as before, so we have convergence

The flow rate is then 
$$Q = V \cdot \frac{\pi \cdot D^2}{4} \quad Q = 6.79 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \quad Q = 0.679 \frac{\text{l}}{\text{s}}$$

Note that we could use *Excel's Solver* for this problem

## Problem 8.138

[Difficulty: 4]

**8.138** What flow rate (gpm) will be produced in a 75-mm-diameter water pipe for which there is a pressure drop of 425 kPa over a 200-m length? The pipe roughness is 2.5 mm. The water is at 0°C.

**Given:** Flow in horizontal pipe

**Find:** Flow rate

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) No minor losses

Available data  $L = 200 \cdot \text{m}$      $D = 75 \cdot \text{mm}$      $e = 2.5 \cdot \text{mm}$      $\Delta p = 425 \cdot \text{kPa}$      $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$      $\mu = 1.76 \cdot 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$

Hence the energy equation becomes

$$\frac{p_1}{\rho} - \frac{p_2}{\rho} = \frac{\Delta p}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Solving for V  $V = \sqrt{\frac{2 \cdot D \cdot \Delta p}{L \cdot \rho \cdot f}}$      $V = \frac{k}{\sqrt{f}}$  (1)     $k = \sqrt{\frac{2 \cdot D \cdot \Delta p}{L \cdot \rho}}$      $k = 0.565 \frac{\text{m}}{\text{s}}$

We also have  $Re = \frac{\rho \cdot V \cdot D}{\mu}$  or  $Re = c \cdot V$  (2)    where  $c = \frac{\rho \cdot D}{\mu}$      $c = 4.26 \times 10^4 \frac{\text{s}}{\text{m}}$

In addition  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$  (3)

Equations 1, 2 and 3 form a set of simultaneous equations for V, Re and f

Make a guess for f     $f = 0.1$     then  $V = \frac{k}{\sqrt{f}}$      $V = 5.86 \cdot \frac{\text{ft}}{\text{s}}$      $Re = c \cdot V$      $Re = 7.61 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$      $f = 0.0573$      $V = \frac{k}{\sqrt{f}}$      $V = 7.74 \cdot \frac{\text{ft}}{\text{s}}$      $Re = c \cdot V$      $Re = 1.01 \times 10^5$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$      $f = 0.0573$      $V = \frac{k}{\sqrt{f}}$      $V = 7.74 \cdot \frac{\text{ft}}{\text{s}}$      $Re = c \cdot V$      $Re = 1.01 \times 10^5$


The flow rate is then  $Q = V \cdot \frac{\pi \cdot D^2}{4}$      $Q = 0.0104 \frac{\text{m}^3}{\text{s}}$      $Q = 10.42 \frac{\text{l}}{\text{s}}$      $Q = 165 \cdot \text{gpm}$

Note that we could use *Excel's Solver* for this problem

Problem 8.139

[Difficulty: 2]

8.139 A compressed air drill requires 0.25 kg/s of air at 650 kPa (gage) at the drill. The hose from the air compressor to the drill is 40 mm inside diameter. The maximum compressor discharge gage pressure is 670 kPa; air leaves the compressor at 40°C. Neglect changes in density and any effects of hose curvature. Calculate the longest hose that may be used.



Solution:

Computing equation:  $\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + gz_2 \right) = h_{ef} = h_f + h_{em}$  (8.29)

where  $h_f = f \frac{L}{D} \frac{\bar{V}^2}{2}$        $h_{em} = K \frac{\bar{V}^2}{2}$

For  $p=c$ , then  $\bar{V}_1 = \bar{V}_2$ , since  $A_1 = A_2$ . Since  $p_1$  and  $p_2$  are given, neglect minor losses. Assume  $\alpha_1 = \alpha_2$  and neglect elevation changes. Then Eq. 8.29 can be written as

$$\frac{p_1 - p_2}{\rho} = f \frac{L}{D} \frac{\bar{V}^2}{2} \quad \text{or} \quad L = \frac{(p_1 - p_2) D}{\rho f \bar{V}^2}$$

The density is

$$\rho = \rho_1 = \frac{p_1}{RT_1} = \frac{7.91 \times 10^5 \text{ N/m}^2}{312 \text{ K}} \times \frac{\text{kg} \cdot \text{K}}{28714 \text{ N} \cdot \text{m}} \times \frac{1}{313 \text{ K}} = 8.81 \text{ kg/m}^3$$

From continuity

$$\bar{V} = \frac{\dot{m}}{\rho A} = \frac{0.4 \text{ m}^3/\text{s}}{\pi (0.04 \text{ m})^2} = \frac{4}{\pi} \times \frac{0.25 \text{ kg/s} \times \frac{\text{m}^3}{8.81 \text{ kg}}}{(0.04 \text{ m})^2} = 22.6 \text{ m/sec}$$

For air at 40°C,  $\mu = 1.91 \times 10^{-5} \text{ kg/m} \cdot \text{s}$  (Table A.10), so

$$Re = \frac{\rho \bar{V} D}{\mu} = \frac{8.81 \text{ kg/m}^3 \times 22.6 \text{ m/sec} \times 0.04 \text{ m}}{1.91 \times 10^{-5} \text{ kg/m} \cdot \text{s}} = 4.17 \times 10^5$$

Assume smooth pipe; then from Fig. 8.13,  $f = 0.0134$

Substituting gives

$$L = \frac{(p_1 - p_2) D}{\rho f \bar{V}^2} = \frac{20 \times 10^3 \text{ N/m}^2 \times 0.04 \text{ m}}{8.81 \text{ kg/m}^3 \times 0.0134 \times (22.6 \text{ m/sec})^2} = 26.5 \text{ m}$$

$L = 26.5 \text{ m}$

## Problem 8.140

[Difficulty: 4]


**8.140** You recently bought a house and want to improve the flow rate of water on your top floor. The poor flow rate is due to three reasons: The city water pressure at the water meter is poor ( $p = 200$  kPa gage); the piping has a small diameter ( $D = 1.27$  cm) and has been crudded up, increasing its roughness ( $e/D = 0.05$ ); and the top floor of the house is 15 m

higher than the water meter. You are considering two options to improve the flow rate: Option 1 is replacing all the piping after the water meter with new smooth piping with a diameter of 1.9 cm; and option 2 is installing a booster pump while keeping the original pipes. The booster pump has an outlet pressure of 300 kPa. Which option would be more effective? Neglect minor losses.

**Given:** Two potential solutions to improve flowrate.

**Find:** Which solution provides higher flowrate

**Solution:**



**Basic equations:**

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + gz_2 \right) = h_{l_r}$$

$$h_{l_r} = h_l + h_{l_m} = f \frac{L}{D} \frac{\bar{V}^2}{2} + K \frac{\bar{V}^2}{2} \quad \frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{e/D}{3.7} + \frac{2.51}{\text{Re} \sqrt{f}} \right) \quad Q = VA$$

**Assumptions:** 1) Steady flow 2) Incompressible 3) Neglect minor losses 4)  $\alpha_1 \frac{\bar{V}_1^2}{2} = \alpha_2 \frac{\bar{V}_2^2}{2}$

**Option 1:** let  $z_1 = 0$      $p_2 = p_{atm} = 0$  kPa gage

Given data     $p_1 = 200$  kPa gage     $D = 0.019$  m     $z_2 = 15$  m     $\frac{e}{D} = 0$      $L = 23$  m

The energy equation becomes:

$$\frac{p_1}{\rho} - gz_2 = f \frac{L}{D} \frac{\bar{V}^2}{2}$$

Solving for  $\bar{V}$ :

$$\bar{V} = \sqrt{\frac{2 \cdot D \cdot \left( \frac{p_1}{\rho} - g \cdot z_2 \right)}{f \cdot L}} \quad \bar{V} = \frac{k}{\sqrt{f}} \quad (1)$$

$$k = \sqrt{\frac{2 \cdot D \cdot \left( \frac{p_1}{\rho} - g \cdot z_2 \right)}{L}} = \sqrt{2 \times 0.019 \text{ m} \times \left( 200,000 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - 9.81 \frac{\text{m}}{\text{s}^2} \times 15 \text{ m} \right) \times \frac{1}{23 \text{ m}}}$$

$$k = 0.296 \frac{\text{m}}{\text{s}}$$

We also have  $\text{Re} = \frac{\rho \cdot \bar{V} \cdot D}{\mu}$  or  $\text{Re} = c \cdot \bar{V}$  (2) where  $c = \frac{\rho \cdot D}{\mu}$

Assuming water at 20°C ( $\rho = 999 \text{ kg/m}^3$ ,  $\mu = 1 \times 10^{-3} \text{ kg/(m s)}$ ):  $c = 999 \frac{\text{kg}}{\text{m}^3} \times 0.019 \text{ m} \times \frac{\text{m} \cdot \text{s}}{1 \times 10^{-3} \text{ kg}} = 18981 \frac{\text{s}}{\text{m}}$

In addition:  $\frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{2.51}{\text{Re} \sqrt{f}} \right)$  (3)

Equations 1, 2 and 3 form a set of simultaneous equations for  $\bar{V}$ , Re and  $f$

Make a guess for  $f$   $f = 0.015$  then  $\bar{V} = \frac{k}{\sqrt{f}} = 2.42 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot \bar{V} = 4.59 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{2.51}{\text{Re} \sqrt{f}} \right)$   $f = 0.0213$   $\bar{V} = \frac{k}{\sqrt{f}} = 2.03 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot \bar{V} = 3.85 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{2.51}{\text{Re} \sqrt{f}} \right)$   $f = 0.0222$   $\bar{V} = \frac{k}{\sqrt{f}} = 1.99 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot \bar{V} = 3.77 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{2.51}{\text{Re} \sqrt{f}} \right)$   $f = 0.0223$   $\bar{V} = \frac{k}{\sqrt{f}} = 1.98 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot \bar{V} = 3.76 \times 10^4$

The flowrate is then:  $Q_1 = \frac{\pi}{4} \times (0.019)^2 \text{ m}^2 \times 1.98 \frac{\text{m}}{\text{s}} = 5.61 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$

**Option 2:** let  $z_1 = 0$   $p_2 = p_{atm} = 0 \text{ kPa gage}$

Given data  $p_1 = 300 \text{ kPa gage}$   $D = 0.0127 \text{ m}$   $z_2 = 15 \text{ m}$   $\frac{e}{D} = 0.05$   $L = 16 \text{ m}$

The analysis for Option 2 is identical to Option 1:

The energy equation becomes:  $\frac{p_1}{\rho} - g z_2 = f \frac{L}{D} \frac{\bar{V}^2}{2}$

Solving for  $V$ :

$$\bar{V} = \sqrt{\frac{2 \cdot D \cdot \left( \frac{p_1}{\rho} - g \cdot z_2 \right)}{f \cdot L}} \quad \bar{V} = \frac{k}{\sqrt{f}} \quad (4)$$

$$k = \sqrt{\frac{2 \cdot D \cdot \left( \frac{p_1}{\rho} - g \cdot z_2 \right)}{L}} = \sqrt{2 \times 0.0127 \text{ m} \times \left( 300,000 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - 9.81 \frac{\text{m}}{\text{s}^2} \times 15 \text{ m} \right) \times \frac{1}{16 \text{ m}}}$$

$$k = 0.493 \frac{\text{m}}{\text{s}}$$

We also have  $\text{Re} = \frac{\rho \cdot \bar{V} \cdot D}{\mu}$  or  $\text{Re} = c \cdot \bar{V}$  (5) where  $c = \frac{\rho \cdot D}{\mu}$

$$c = 999 \frac{\text{kg}}{\text{m}^3} \times 0.0127 \text{ m} \times \frac{\text{m} \cdot \text{s}}{1 \times 10^{-3} \text{ kg}} = 12687.3 \frac{\text{s}}{\text{m}}$$

In addition:  $\frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{e/D}{3.7} + \frac{2.51}{\text{Re} \sqrt{f}} \right) = -2.0 \log \left( \frac{0.05}{3.7} + \frac{2.51}{\text{Re} \sqrt{f}} \right)$  (6)

Equations 4, 5 and 6 form a set of simultaneous equations for  $\bar{V}$ , Re and  $f$

Make a guess for  $f$   $f = 0.07$  then  $\bar{V} = \frac{k}{\sqrt{f}} = 1.86 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot \bar{V} = 2.36 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{0.05}{3.7} + \frac{2.51}{\text{Re} \sqrt{f}} \right)$   $f = 0.0725$   $\bar{V} = \frac{k}{\sqrt{f}} = 1.83 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot \bar{V} = 2.32 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{0.05}{3.7} + \frac{2.51}{\text{Re} \sqrt{f}} \right)$   $f = 0.0725$   $\bar{V} = \frac{k}{\sqrt{f}} = 1.83 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot \bar{V} = 2.32 \times 10^4$

The flowrate is then:  $Q_2 = \frac{\pi}{4} \times (0.0127)^2 \text{ m}^2 \times 1.83 \frac{\text{m}}{\text{s}} = 2.32 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$  Option 1 is 2.42 times more effective!

This problem can also be solved explicitly:

The energy equation becomes:  $\frac{p_1}{\rho} - g z_2 = f \frac{L}{D} \frac{\bar{V}^2}{2}$

or:  $\sqrt{f} = \frac{1}{\bar{V}} \sqrt{\frac{2D \left( \frac{p_1}{\rho} - g z_2 \right)}{L}}$

Plugging this into the Colebrook equation:

$$\frac{1}{\sqrt{f}} = \bar{V} \sqrt{\frac{L}{2D \left( \frac{p_1}{\rho} - gz_2 \right)}} = -2.0 \log \left( \frac{e/D}{3.7} + \frac{2.51\mu}{\rho \bar{V} D} \left( \bar{V} \sqrt{\frac{L}{2D \left( \frac{p_1}{\rho} - gz_2 \right)}} \right) \right)$$

Noting that the  $\bar{V}$  s on the right hand side cancel provides:

$$\bar{V} = -2.0 \log \left( \frac{e/D}{3.7} + \frac{2.51\mu}{\rho D} \sqrt{\frac{L}{2D \left( \frac{p_1}{\rho} - gz_2 \right)}} \right) \left( \sqrt{\frac{2D \left( \frac{p_1}{\rho} - gz_2 \right)}{L}} \right)$$

Assuming water at 20°C ( $\rho = 999 \text{ kg/m}^3$ ,  $\mu = 1 \times 10^{-3} \text{ kg/(m s)}$ ) gives the remaining information needed to perform the calculation.

For Option 1:

$$\bar{V} = -2.0 \log \left( \frac{2.51 \times 1 \times 10^{-3} \frac{\text{kg}}{\text{m} \cdot \text{s}} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{1}{0.019 \text{ m}}}{\sqrt{\frac{23 \text{ m}}{2 \times 0.019 \text{ m}} \times \frac{1}{\left( 200,000 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - 9.81 \frac{\text{m}}{\text{s}^2} \times 15 \text{ m} \right)}}} \right)$$

$$\times \left( \sqrt{\frac{2 \times 0.019 \text{ m}}{23 \text{ m}} \times \left( 200,000 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - 9.81 \frac{\text{m}}{\text{s}^2} \times 15 \text{ m} \right)} \right)$$

$$\bar{V} = 1.98 \frac{\text{m}}{\text{s}}$$

and:

$$Q_1 = \frac{\pi}{4} \times (0.019)^2 \text{ m}^2 \times 1.98 \frac{\text{m}}{\text{s}} = 5.61 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$$

**Option 2:** let  $z_1 = 0$       $p_2 = p_{atm} = 0 \text{ kPa gage}$

Given data      $p_1 = 300 \text{ kPa gage}$       $D = 0.0127 \text{ m}$       $z_2 = 15 \text{ m}$       $\frac{e}{D} = 0.05$       $L = 16 \text{ m}$

The analysis for Option 2 results in the same equations as used in Option 1 once again giving:

$$\bar{V} = -2.0 \log \left( \frac{e/D}{3.7} + \frac{2.51\mu}{\rho D} \sqrt{\frac{L}{2D \left( \frac{p_1}{\rho} - gz_2 \right)}} \right) \left( \sqrt{\frac{2D \left( \frac{p_1}{\rho} - gz_2 \right)}{L}} \right)$$

$$\bar{V} = -2.0 \log \left( \frac{0.05}{3.7} + 2.51 \times 10^{-3} \frac{\text{kg}}{\text{m} \cdot \text{s}} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{1}{0.0127 \text{ m}} \right) \\ \times \sqrt{\frac{16 \text{ m}}{2 \times 0.0127 \text{ m}} \times \frac{1}{\left( 300,000 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - 9.81 \frac{\text{m}}{\text{s}^2} \times 15 \text{ m} \right)}} \\ \times \left( \sqrt{\frac{2 \times 0.0127 \text{ m}}{16 \text{ m}} \times \left( 300,000 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - 9.81 \frac{\text{m}}{\text{s}^2} \times 15 \text{ m} \right)} \right)$$

$$\bar{V} = 1.83 \frac{\text{m}}{\text{s}}$$

The flowrate is then:  $Q_2 = \frac{\pi}{4} \times (0.0127)^2 \text{ m}^2 \times 1.83 \frac{\text{m}}{\text{s}} = 2.32 \times 10^{-4} \frac{\text{m}^3}{\text{s}}$

## Problem 8.141

[Difficulty: 3]

**8.141** The students of Phi Gamma Delta are putting a kiddy pool on a porch attached to the second story of their house and plan to fill it with water from a garden hose. The kiddy pool has a diameter of 5 ft, and is 2.5 ft deep. The porch is 18 ft above the faucet. The garden hose is very smooth on the inside, has a length of 50 ft, and a diameter of 5/8 in. If the water pressure at the faucet is 60 psi, how long will it take to fill the pool? Neglect minor losses.

**Given:** Kiddy pool on a porch.

**Find:** Time to fill pool with a hose.

**Solution:**

**Basic equations:**

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + gz_2 \right) = h_{l_r}$$

$$h_{l_r} = h_l + h_{l_m} = f \frac{L}{D} \frac{\bar{V}^2}{2} + K \frac{\bar{V}^2}{2} \quad \frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{e/D}{3.7} + \frac{2.51}{\text{Re} \sqrt{f}} \right) \quad Q = VA$$

**Assumptions:** 1) Steady flow 2) Incompressible 3) Neglect minor losses 4)  $\alpha_1 \frac{\bar{V}_1^2}{2} = \alpha_2 \frac{\bar{V}_2^2}{2}$

Given data

$p_1 = 60 \frac{\text{lbf}}{\text{in}^2} \text{ gage}$	$z_1 = 0 \text{ ft}$	$D = 0.625 \text{ in}$	$p_2 = 0 \frac{\text{lbf}}{\text{in}^2} \text{ gage}$
$z_2 = 20.5 \text{ ft}$	$\frac{e}{D} = 0$	$L = 50 \text{ ft}$	

The energy equation becomes:

$$\frac{p_1}{\rho} - gz_2 = f \frac{L}{D} \frac{\bar{V}^2}{2}$$

Solving for V:

$$\bar{V} = \sqrt{\frac{2 \cdot D \cdot \left( \frac{p_1}{\rho} - g \cdot z_2 \right)}{f \cdot L}} \quad \bar{V} = \frac{k}{\sqrt{f}} \quad (1)$$

$$k = \sqrt{\frac{2 \cdot D \cdot \left( \frac{p_1}{\rho} - g \cdot z_2 \right)}{L}} = \sqrt{2 \times 0.625 \text{ in} \times \frac{\text{ft}}{12 \text{ in}} \times \left( 60 \frac{\text{lbf}}{\text{in}^2} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} - 32.2 \frac{\text{ft}}{\text{s}^2} \times 20.5 \text{ ft} \right) \times \frac{1}{50 \text{ ft}}}$$

$$k = 2.81 \frac{\text{ft}}{\text{s}}$$

We also have  $Re = \frac{\rho \cdot \bar{V} \cdot D}{\mu}$  or  $Re = c \cdot \bar{V}$  (2) where  $c = \frac{\rho \cdot D}{\mu}$

Assuming water at 68°F ( $\rho = 1.94 \text{ slug/ft}^3$ ,  $\mu = 2.1 \times 10^{-5} \text{ lbf}\cdot\text{s/ft}^2$ ):

$$c = 1.94 \frac{\text{slug}}{\text{ft}^3} \times 0.625 \text{ in} \times \frac{\text{ft}}{12 \text{ in}} \times \frac{\text{ft}^2}{2.1 \times 10^{-5} \text{ lbf}\cdot\text{s}} \times \frac{\text{lbf}\cdot\text{s}^2}{\text{slug}\cdot\text{ft}} = 4811.5 \frac{\text{s}}{\text{ft}}$$

In addition:  $\frac{1}{\sqrt{f}} = -2.0 \log\left(\frac{2.51}{Re \sqrt{f}}\right)$  (3)

Equations 1, 2 and 3 form a set of simultaneous equations for  $\bar{V}$ ,  $Re$  and  $f$

Make a guess for  $f$   $f = 0.015$  then  $\bar{V} = \frac{k}{\sqrt{f}} = 22.94 \frac{\text{ft}}{\text{s}}$   $Re = c \cdot \bar{V} = 1.1 \times 10^5$

Given  $\frac{1}{\sqrt{f}} = -2.0 \log\left(\frac{2.51}{Re \sqrt{f}}\right)$   $f = 0.0177$   $\bar{V} = \frac{k}{\sqrt{f}} = 21.12 \frac{\text{ft}}{\text{s}}$   $Re = c \cdot \bar{V} = 1.02 \times 10^5$

Given  $\frac{1}{\sqrt{f}} = -2.0 \log\left(\frac{2.51}{Re \sqrt{f}}\right)$   $f = 0.0179$   $\bar{V} = \frac{k}{\sqrt{f}} = 21.0 \frac{\text{ft}}{\text{s}}$   $Re = c \cdot \bar{V} = 1.01 \times 10^5$

The flowrate is then:

$$Q = \frac{\pi}{4} \times (0.625)^2 \text{ in}^2 \times \frac{\text{ft}^2}{144 \text{ in}^2} \times 21.0 \frac{\text{ft}}{\text{s}} = 0.0447 \frac{\text{ft}^3}{\text{s}}$$

$$Volume_{pool} = 2.5 \text{ ft} \times \frac{\pi}{4} \times (5)^2 \text{ ft}^2 = 49.1 \text{ ft}^3$$

$$time = \frac{Volume_{pool}}{Q} = \frac{49.1 \text{ ft}^3}{0.0447 \frac{\text{ft}^3}{\text{s}}} = 1097 \text{ s} = 18.3 \text{ min.}$$

This problem can also be solved explicitly in the following manner:

The energy equation becomes:  $\frac{p_1}{\rho} - gz_2 = f \frac{L}{D} \frac{\bar{V}^2}{2}$

or:  $\sqrt{f} = \frac{1}{\bar{V}} \sqrt{\frac{2D \left( \frac{p_1}{\rho} - gz_2 \right)}{L}}$

Plugging this into the Colebrook equation:

$$\frac{1}{\sqrt{f}} = \bar{V} \sqrt{\frac{L}{2D \left( \frac{p_1}{\rho} - gz_2 \right)}} = -2.0 \log \left( \frac{2.51 \mu}{\rho \bar{V} D} \left( \bar{V} \sqrt{\frac{L}{2D \left( \frac{p_1}{\rho} - gz_2 \right)}} \right) \right)$$

Noting that the  $\bar{V}$  s on the right hand side cancel provides:

$$\bar{V} = -2.0 \log \left( \frac{2.51\mu}{\rho D} \sqrt{\frac{L}{2D \left( \frac{p_1}{\rho} - gz_2 \right)}} \right) \left( \sqrt{\frac{2D \left( \frac{p_1}{\rho} - gz_2 \right)}{L}} \right)$$

Assuming water at 68°F ( $\rho = 1.94 \text{ slug/ft}^3$ ,  $\mu = 2 \times 10^{-5} \text{ lbf s/ft}^2$ ) and  $g = 32.2 \text{ ft/s}^2$  gives the remaining information needed to perform the calculation finding:

$$\bar{V} = -2.0 \log \left( \frac{2.51 \times 2.1 \times 10^{-5} \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} \times \frac{1}{0.625 \text{ in}} \times \frac{12 \text{ in}}{\text{ft}}}{\sqrt{\frac{50 \text{ ft}}{2 \times 0.625 \text{ in}} \times \frac{12 \text{ in}}{\text{ft}} \times \frac{1}{\left( 60 \frac{\text{lbf}}{\text{in}^2} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} - 32.2 \frac{\text{ft}}{\text{s}^2} \times 20.5 \text{ ft} \right)}}}} \right)$$

$$\times \left( \sqrt{\frac{2 \times 0.625 \text{ in}}{50 \text{ ft}} \times \frac{\text{ft}}{12 \text{ in}} \times \left( 60 \frac{\text{lbf}}{\text{in}^2} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} - 32.2 \frac{\text{ft}}{\text{s}^2} \times 20.5 \text{ ft} \right)} \right)$$

$$\bar{V} = 21.0 \frac{\text{ft}}{\text{s}}$$

and:

$$Q = \frac{\pi}{4} \times (0.052)^2 \text{ ft}^2 \times 21.0 \frac{\text{ft}}{\text{s}} = 0.0447 \frac{\text{ft}^3}{\text{s}}$$

$$Volume_{pool} = 2.5 \text{ ft} \times \frac{\pi}{4} \times (5)^2 \text{ ft}^2 = 49.1 \text{ ft}^3$$

$$time = \frac{Volume_{pool}}{Q} = \frac{49.1 \text{ ft}^3}{0.0447 \frac{\text{ft}^3}{\text{s}}} = 1097 \text{ s} = 18.3 \text{ min.}$$

### Problem 8.142

[Difficulty: 3]

**8.142** Gasoline flows in a long, underground pipeline at a constant temperature of 15°C. Two pumping stations at the same elevation are located 13 km apart. The pressure drop between the stations is 1.4 MPa. The pipeline is made from 0.6-m-diameter pipe. Although the pipe is made from commercial steel, age and corrosion have raised the pipe roughness to approximately that for galvanized iron. Compute the volume flow rate.

Solution: Apply the energy equation for steady, incompressible flow that is uniform at each section.

$$\text{Basic equation: } \frac{p_1}{\rho} + \frac{\bar{V}_1^2}{2} + g z_1^{\uparrow=0(1)} = \frac{p_2}{\rho} + \frac{\bar{V}_2^2}{2} + g z_2^{\uparrow=0(2)} + h_{LT}; \quad h_{LT} = f \frac{L}{D} \frac{\bar{V}^2}{2} + h_{cm}^{\uparrow=0(1)}$$

Assumptions: (1) Constant area pipe, so  $\bar{V}_1 = \bar{V}_2$ ,  $h_{cm} = 0$   
 (2) Level, so  $z_1 = z_2$

Thus

$$\frac{p_1 - p_2}{\rho} = f \frac{L}{D} \frac{\bar{V}^2}{2} \quad \text{or} \quad \bar{V} = \left[ \frac{2D(p_1 - p_2)}{\rho f L} \right]^{\frac{1}{2}}$$

But  $f = f(Re, e/D)$ , and the Reynolds number is not known. Therefore iteration is required. Choose  $f$  in the fully-rough zone. From Table 8.1,  $e = 0.15 \text{ mm}$ ;  $e/D = 0.00025$ . Then from Fig. 8.13,  $f \approx 0.014$ . { From Eq. 8.37, using Excel's solver,  $f = 0.014$ . } Then,

$$\bar{V} = \left[ 2 \times 0.6 \text{ m} \times \frac{1.4 \times 10^6 \text{ N}}{\text{m}^2} \times \frac{1}{(0.72) 1000 \text{ kg}} \times \frac{1}{0.014} \times \frac{1}{13 \times 10^3 \text{ m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]^{\frac{1}{2}}$$

{  $SG = 0.72$ , Table A.2 }

$$\bar{V} = 3.58 \text{ m/s}$$

Now compute  $Re$  and check on guess for  $f$ . Choose  $\mu \approx 5 \times 10^{-4} \text{ N} \cdot \text{s} / \text{m}^2$  (Fig. A.2).\*

$$Re = \frac{\rho \bar{V} D}{\mu} = \frac{(0.72) 1000 \text{ kg}}{\text{m}^3} \times \frac{3.58 \text{ m}}{\text{s}} \times \frac{0.6 \text{ m}}{5 \times 10^{-4} \text{ N} \cdot \text{s}} \times \frac{\text{m}^2}{\text{kg} \cdot \text{m}} = 3.09 \times 10^6$$

Checking on Fig. 8.13, flow is essentially in the fully-rough zone, and initial guess for  $f$  was okay. Thus

$$Q = \bar{V} A = 3.58 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} (0.6)^2 \text{ m}^2 = 1.01 \text{ m}^3/\text{s}$$

\* Note gasoline is between heptane and octane.

### Problem 8.143

[Difficulty: 3]

**8.143** Water flows steadily in a horizontal 125-mm-diameter cast-iron pipe. The pipe is 150 m long and the pressure drop between sections ① and ② is 150 kPa. Find the volume flow rate through the pipe.

Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equation:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g z_2 \right) + h_{LT}$$

$$h_{LT} = h_L + h_{em} = f \frac{L}{D} \frac{\bar{V}^2}{2} + K \frac{\bar{V}^2}{2}$$

Assumptions: (1) Fully developed flow:  $\alpha_1 \bar{V}_1^2 = \alpha_2 \bar{V}_2^2$

(2) Horizontal:  $z_1 = z_2$

(3) Constant area, so  $K = 0$

Then

$$\frac{\Delta p}{\rho} = h_{LT} = f \frac{L}{D} \frac{\bar{V}^2}{2} \quad \text{so} \quad \bar{V} = \sqrt{\frac{2 \Delta p D}{\rho f L}}$$

Since flow rate (hence  $Re$  and  $f$ ) are unknown, must iterate. Guess a trial value of  $f$  in the fully rough zone. From Table 8.1,  $e = 0.26 \text{ mm}$

Then  $e/D = \frac{0.26}{125} = 0.0021$ . Then from Eq. 8.37\*,  $f = 0.0237$  for  $Re \geq 6 \times 10^5$

$$\bar{V} = \left[ 2 \times 150 \times 10^3 \frac{\text{N}}{\text{m}^2} \times 0.125 \text{ m} \times 0.0098 \frac{\text{m}^3}{\text{kg}} \times \frac{1}{0.0237} \times \frac{1}{150 \text{ m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]^{1/2} = 3.25 \text{ m/s}$$

and, checking  $Re$ , with  $\nu = 1.14 \times 10^{-6} \text{ m}^2/\text{s}$  at  $T = 15^\circ\text{C}$  (Table A.8),

$$Re = \frac{\bar{V} D}{\nu} = \frac{3.25 \text{ m}}{\text{s}} \times \frac{0.125 \text{ m}}{1.14 \times 10^{-6} \text{ m}^2/\text{s}} = 3.56 \times 10^5$$

The friction factor at this  $Re$  is still  $f = 0.0242$  (2% error), so convergence is ok.

$$Q = \bar{V} A = 3.25 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} \times (0.125 \text{ m})^2 = 0.0399 \text{ m}^3/\text{s}$$

Using  $f = 0.0242$ ,  $\bar{V} = 3.22 \text{ m/s}$  and  $Q = 0.0393 \text{ m}^3/\text{s}$

\* Value of  $f = 0.0237$  obtained using Excel's Solver (or Goal Seek)

**8.144** Water flows steadily in a 125-mm-diameter cast-iron pipe 150 m long. The pressure drop between sections ① and ② is 150 kPa, and section ② is located 15 m above section ①. Find the volume flow rate.

Solution: Apply the energy equation for steady, incompressible pipe flow

Computing equation:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + gz_2 \right) = h_{eT} \quad (1)$$


$$h_{eT} = h_f + h_{em} = f \frac{L}{D} \frac{\bar{V}^2}{2} + K \frac{\bar{V}^2}{2} \quad (2)$$

Assumptions: (1)  $\bar{V}_1 = \bar{V}_2$  from continuity

(2)  $\alpha_1 = \alpha_2$

(3)  $z_2 - z_1 = 15 \text{ m}$

(4) neglect minor losses



For cast iron pipe with  $D = 125 \text{ mm}$ ,  $\frac{e}{D} = 0.0021$  ( $e = 0.26 \text{ mm}$ , Table 8.1)

Since  $f = f(Re)$  and  $\bar{V}$  is unknown, iteration will be required

From Eqs (1) and (2)

$$\left( \frac{p_1}{\rho} + gz_1 \right) - \left( \frac{p_2}{\rho} + gz_2 \right) = f \frac{L}{D} \frac{\bar{V}^2}{2}$$

Then

$$f \bar{V}^2 = \frac{2D}{L} \left[ (p_1 - p_2) + \rho g (z_1 - z_2) \right]$$

$$f \bar{V}^2 = 2 \times \frac{0.125 \text{ m}}{150 \text{ m}} \left[ 150 \times 10^3 \frac{\text{N}}{\text{m}^2} + 999 \frac{\text{kg}}{\text{m}^3} \times \frac{0.125 \text{ m}}{1.52} \right] + 9.81 \frac{\text{m}}{\text{s}^2} \times (-15 \text{ m})$$

$$f \bar{V}^2 = 0.005 \text{ m}^2/\text{s}^2$$

Assume flow in fully rough region,  $f = 0.0237$ , then  $\bar{V} = 0.46 \text{ m/s}$

Check  $Re$ . Assume  $T = -15^\circ \text{C}$ ,  $\nu = 1.14 \times 10^{-6} \text{ m}^2/\text{s}$  (Table A.8)

$$\text{Then } Re = \frac{D \bar{V}}{\nu} = 0.125 \text{ m} \times \frac{0.46 \text{ m/s}}{1.14 \times 10^{-6} \frac{\text{m}^2}{\text{s}}} = 50,400$$

From Eq. 8.37 with  $Re = 50,400$ ,  $e/D = 0.0021$ , then using Excel's solver (or Goal Seek)

$$f = 0.0267 \text{ and } \bar{V} = 0.433 \text{ m/s}$$

With this value of  $\bar{V}$ ,  $Re = 47,500$ ,  $f = 0.0268$ ,  $\bar{V} = 0.432 \text{ m/s}$


Then

$$Q = A \bar{V} = \frac{\pi D^2}{4} \bar{V} = \frac{\pi}{4} (0.125 \text{ m})^2 \times 0.432 \frac{\text{m}}{\text{s}} = 0.0053 \text{ m}^3/\text{s} \quad \underline{Q}$$

### Problem 8.145

[Difficulty: 3]

**8.145** Two open standpipes of equal diameter are connected by a straight tube, as shown. Water flows by gravity from one standpipe to the other. For the instant shown, estimate the rate of change of water level in the left standpipe.



Solution: Apply the energy equation for quasi-steady, incompressible pipe flow.

Computing equation:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2 \right) = h_{LT}; \quad h_{LT} = h_L + h_{em} = \left[ f \frac{(L-D)}{d} + K_{ent} + K_{exit} \right] \frac{\bar{V}^2}{2}$$

From continuity,  $A_1 V_1 = A_2 \bar{V}$

- Assumptions:
- (1) Neglect unsteady effects
  - (2) Incompressible flow
  - (3)  $p_1 = p_2 = p_{atm}$
  - (4)  $V_1 = V_2$  since diameters are equal

$$\text{Then } g \Delta h = h_{LT} = \left[ f \frac{(L-D)}{d} + K_{ent} + K_{exit} \right] \frac{\bar{V}^2}{2}$$

Flow rate (hence speed) is unknown, so assume flow is in fully rough zone.

$$\frac{e}{D} = \frac{0.3}{75} = 0.004, \text{ so } f \approx 0.0285 \text{ from Eq. 8.37 (using Excel's Solver or Goal Seek)}$$

From Table 8.2,  $K_{ent} = 0.5$ ; from Fig. 8.15,  $K_{exit} = 1$ . Then

$$\bar{V} = \left[ \frac{2g \Delta h}{f \frac{(L-D)}{d} + K_{ent} + K_{exit}} \right]^{\frac{1}{2}} = \left[ \frac{2 \times 9.81 \frac{m}{s^2} \times 2.5 m}{0.028 \frac{(4 - 0.75)}{0.075} + 0.5 + 1.0} \right]^{\frac{1}{2}} = 4.23 \text{ m/s}$$

Check  $Re$  and  $f$ . For water at  $20^\circ C$ ,  $\nu = 1.00 \times 10^{-6} \text{ m}^2/\text{s}$  (Table A.5)

$$Re = \frac{\bar{V} d}{\nu} = 4.23 \frac{m}{s} \times 0.075 m \times \frac{s}{1.00 \times 10^{-6} m^2} = 3.18 \times 10^5$$

From Equation 8.37,  $f \approx 0.0288$ , so this is satisfactory agreement. ( $\sim 1\%$ )


$$V_1 = \frac{A_p}{A_1} V_p = \left( \frac{d}{D} \right)^2 V_p = \left( \frac{0.075}{0.75} \right)^2 \times 4.23 \frac{m}{s} = 0.0423 \text{ m/s (down)}$$

The water level in the left tank falls at about 42.3 mm/s

## Problem 8.146

[Difficulty: 4]

**8.146** Two galvanized iron pipes of diameter  $D$  are connected to a large water reservoir, as shown. Pipe  $A$  has length  $L$  and pipe  $B$  has length  $2L$ . Both pipes discharge to atmosphere. Which pipe will pass the larger flow rate? Justify (without calculating the flow rate in each pipe). Compute the flow rates if  $H = 10$  m,  $D = 50$  mm, and  $L = 10$  m.



**Given:** Flow from large reservoir

**Find:** Flow rates in two pipes

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad h_{lm} = K_{ent} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Available data  $D = 50\text{-mm}$        $H = 10\text{-m}$        $L = 10\text{-m}$   
 $e = 0.15\text{-mm}$       (Table 8.1)       $\nu = 1 \cdot 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$       (Table A.8)       $K_{ent} = 0.5$

The energy equation becomes

$$g \cdot (z_1 - z_2) - \frac{1}{2} \cdot V_2^2 = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K_{ent} \cdot \frac{V_2^2}{2} \quad \text{and} \quad V_2 = V \quad z_1 - z_2 = H$$

Solving for  $V$

$$V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad (1)$$

We also have 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad (2) \quad \text{Re} = \frac{V \cdot D}{\nu} \quad (3)$$

We must solve Eqs. 1, 2 and 3 iteratively.

Make a guess for  $V$        $V = 1 \cdot \frac{\text{m}}{\text{s}}$       Then       $\text{Re} = \frac{V \cdot D}{\nu}$        $\text{Re} = 5.00 \times 10^4$

and 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0286$$

Then 
$$V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad V = 5.21 \frac{\text{m}}{\text{s}}$$

Repeating  $Re = \frac{V \cdot D}{\nu}$   $Re = 2.61 \times 10^5$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$   $f = 0.0267$

Then  $V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{ent} + 1}}$   $V = 5.36 \frac{m}{s}$

Repeating  $Re = \frac{V \cdot D}{\nu}$   $Re = 2.68 \times 10^5$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$   $f = 0.0267$

Then  $V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{ent} + 1}}$   $V = 5.36 \frac{m}{s}$

Hence  $Q = \frac{\pi}{4} \cdot D^2 \cdot V$   $Q = 0.0105 \frac{m^3}{s}$   $Q = 10.5 \cdot \frac{l}{s}$

We repeat the analysis for the second pipe, using 2L instead of L:

Make a guess for V  $V = 1 \cdot \frac{m}{s}$  Then  $Re = \frac{V \cdot D}{\nu}$   $Re = 5.00 \times 10^4$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$   $f = 0.0286$

Then  $V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{2 \cdot L}{D} + K_{ent} + 1}}$   $V = 3.89 \frac{m}{s}$

Repeating  $Re = \frac{V \cdot D}{\nu}$   $Re = 1.95 \times 10^5$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$   $f = 0.0269$

Then  $V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{2 \cdot L}{D} + K_{ent} + 1}}$   $V = 4.00 \frac{m}{s}$

Repeating  $Re = \frac{V \cdot D}{\nu}$   $Re = 2.00 \times 10^5$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$   $f = 0.0268$

Then  $V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{2 \cdot L}{D} + K_{ent} + 1}}$   $V = 4.00 \frac{m}{s}$

Hence  $Q = \frac{\pi}{4} \cdot D^2 \cdot V$   $Q = 7.861 \times 10^{-3} \frac{m^3}{s}$   $Q = 7.86 \cdot \frac{l}{s}$

As expected, the flow is considerably less in the longer pipe.

## Problem 8.147

[Difficulty: 3]

**8.147** Galvanized iron drainpipes of diameter 50 mm are located at the four corners of a building, but three of them become clogged with debris. Find the rate of downpour (cm/min) at which the single functioning drainpipe can no longer drain the roof. The building roof area is 500 m<sup>2</sup>, and the height is 5 m. Assume the drainpipes are the same height as the building, and that both ends are open to atmosphere. Ignore minor losses.

**Given:** Galvanized drainpipe

**Find:** Maximum downpour it can handle

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) No minor losses

Available data  $D = 50\text{-mm}$   $e = 0.15\text{-mm}$  (Table 8.1)  $h = L$  From Table A.7 (20°C)  $\nu = 1.01 \times 10^{-6} \frac{\text{m}^2}{\text{s}}$

The energy equation becomes 
$$g \cdot z_1 - g \cdot z_2 = g \cdot (z_1 - z_2) = g \cdot h = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Solving for V 
$$V = \sqrt{\frac{2 \cdot D \cdot g \cdot h}{L \cdot f}} = \sqrt{\frac{2 \cdot D \cdot g}{f}} \quad V = \frac{k}{\sqrt{f}} \quad (1)$$

$$k = \sqrt{2 \cdot D \cdot g} \quad k = \sqrt{2 \times 0.05 \cdot \text{m} \times 9.81 \cdot \frac{\text{m}}{\text{s}^2}} \quad k = 0.99 \frac{\text{m}}{\text{s}}$$

We also have 
$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{or} \quad \text{Re} = c \cdot V \quad (2) \quad \text{where} \quad c = \frac{D}{\nu}$$

$$c = 0.05 \cdot \text{m} \times \frac{\text{s}}{1.01 \times 10^{-6} \cdot \text{m}^2} \quad c = 4.95 \times 10^4 \cdot \frac{\text{s}}{\text{m}}$$

In addition 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad (3)$$

Equations 1, 2 and 3 form a set of simultaneous equations for V, Re and f

Make a guess for f  $f = 0.01$  then  $V = \frac{k}{\sqrt{f}} \quad V = 9.90 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 4.9 \times 10^5$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$$

$$f = 0.0264 \quad V = \frac{k}{\sqrt{f}} \quad V = 6.09 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 3.01 \times 10^5$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$$

$$f = 0.0266 \quad V = \frac{k}{\sqrt{f}} \quad V = 6.07 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 3.00 \times 10^5$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$$

$$f = 0.0266 \quad V = \frac{k}{\sqrt{f}} \quad V = 6.07 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 3.00 \times 10^5$$

$$\text{The flow rate is then } Q = V \cdot \frac{\pi \cdot D^2}{4} \quad Q = 0.0119 \cdot \frac{\text{m}^3}{\text{s}}$$


$$\text{The downpour rate is then } \frac{Q}{A_{\text{roof}}} = \frac{0.0119 \cdot \frac{\text{m}^3}{\text{s}}}{500 \cdot \text{m}^2} \times \frac{100 \cdot \text{cm}}{1 \cdot \text{m}} \times \frac{60 \cdot \text{s}}{1 \cdot \text{min}} = 0.143 \cdot \frac{\text{cm}}{\text{min}} \quad \text{The drain can handle 0.143 cm/min}$$

Note that we could use *Excel's Solver* for this problem

### Problem 8.148

[Difficulty: 3] Part 1/2

**8.148** A mining engineer plans to do hydraulic mining with a high-speed jet of water. A lake is located  $H = 300$  m above the mine site. Water will be delivered through  $L = 900$  m of fire hose; the hose has inside diameter  $D = 75$  mm and relative roughness  $e/D = 0.01$ . Couplings, with equivalent length  $L_c = 20D$ , are located every 10 m along the hose. The nozzle outlet diameter is  $d = 25$  mm. Its minor loss coefficient is  $K = 0.02$  based on outlet velocity. Estimate the maximum outlet velocity that this system could deliver. Determine the maximum force exerted on a rock face by this water jet.



Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equation: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2 \right) = h_{ET}$$

Assume: (1)  $p_1 = 0$ ; (2)  $V_1 = 0$ ; (3)  $p_2 = 0$ ; (4)  $\alpha_2 = 1$ ; (5)  $z_2 = 0$ ; (6) Fully-rough zone

Then 
$$gH = h_{ET} + \frac{V_2^2}{2} = f \frac{L}{D} \frac{V_p^2}{2} + f_c 90 \frac{L_c}{D} \frac{V_p^2}{2} + K \frac{V_0^2}{2} + \frac{V_2^2}{2}$$

From continuity  $V_p A_p = V_0 A_0$ ;  $V_2 = V_0 \frac{A_0}{A_2}$ ;  $V_2^2 = V_0^2 \left( \frac{A_0}{A_2} \right)^2 = V_0^2 \left( \frac{d}{D} \right)^4$

Substituting, 
$$gH = \left[ f \left( \frac{L}{D} + 90 \frac{L_c}{D} \left( \frac{d}{D} \right)^4 + 1 + K \right) \right] \frac{V_0^2}{2}$$

$$V_0 = \left[ \frac{2gH}{f \left( \frac{L}{D} + 90 \frac{L_c}{D} \left( \frac{d}{D} \right)^4 + 1 + K \right)} \right]^{1/2}$$
; in fully-rough zone ( $\frac{e}{D} = 0.01$ ),  $f = 0.038^*$  (Eq. 8.37)

$$V_0 = \left[ 2 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 300 \text{ m} \times \frac{1}{0.038 \left( \frac{900 \text{ m}}{0.075 \text{ m}} + 90 (20) \left( \frac{0.025 \text{ m}}{0.075 \text{ m}} \right)^4 + 1 + 0.02 \right)} \right]^{1/2} = 28.0 \text{ m/s (est.)}$$

Check for fully-rough flow zone:

$$Re = \frac{V_p D}{\nu}$$
;  $V_p = V_0 \left( \frac{d}{D} \right)^4 = 28.0 \frac{\text{m}}{\text{s}} \left( \frac{1}{3} \right)^4 = 0.346 \text{ m/s}$  {Assume  $T = 20^\circ\text{C}$ }

$$Re = 0.346 \frac{\text{m}}{\text{sec}} \times 0.075 \text{ m} \times \frac{1}{1 \times 10^{-6} \text{ m}^2} = 2.60 \times 10^4$$
; at  $\frac{e}{D} = 0.01$ ,  $f = 0.040$  (Eq. 8.37)

The new estimate is

$$V_0 = \sqrt{\frac{0.038}{0.040}} V_0 \text{ (est.)} = \sqrt{\frac{0.038}{0.040}} 28.0 \frac{\text{m}}{\text{s}} = 27.3 \text{ m/s}$$


Apply momentum to find force: CV is shown.

$$F_{Sx} + F_{Bx} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: (1) No pressure forces

(2)  $F_{Bx} = 0$

(3) Steady flow



## Problem 8.148

[Difficulty: 3] Part 2/2

(4) Uniform flow at each cross-section

Then

$$R_x = u_2 \{-\rho \bar{V}_0 A_0\} + u_3 \{+\rho \bar{V}_0 A_0\}$$

$$u_2 = \bar{V}_0 \quad u_3 = 0$$

$$R_x = -\rho \bar{V}_0^2 A_0$$

The force on the rock face is

$$K_x = -R_x = \rho \bar{V}_0^2 A_0$$

$$= 999 \frac{\text{kg}}{\text{m}^3} \times (27.3)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\pi}{4} (0.025)^2 \text{m}^2 \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$


$$K_x = 365 \text{ N (to right)}$$

$K_x$

\* Values of F obtained from Eq. 8.37 using Excel's Solver (or Goal Seek)


42, 781, 50 SHEETS, 1 COLUMN  
 42, 782, 100 SHEETS, 5 COLUMNS  
 42, 784, 200 SHEETS, 5 SQUARES  
 NATIONAL





It is not possible to roughen the tube sufficiently to slow the flow down to a laminar flow for this  $\Delta p$ . Even a relative roughness of 0.5 (a physical impossibility!) would not work.





The "critical" length of tube is between 15 and 20 km. For this range, the fluid is making a transition between laminar and turbulent flow, and is quite unstable. In this range the flow oscillates between laminar and turbulent; no consistent solution is found (i.e., an  $Re$  corresponding to turbulent flow needs an  $f$  assuming laminar to produce the  $\Delta p$  required, and vice versa!) More realistic numbers (e.g., tube length) are obtained for a fluid such as SAE 10W oil (The graph will remain the same except for scale)

## Problem 8.151

[Difficulty: 5]

**8.151** For the pipe flow into a reservoir of Example 8.5 consider the effect of pipe roughness on flow rate, assuming the pressure of the pump is maintained at 153 kPa. Plot the flow rate against pipe roughness ranging from smooth ( $e = 0$ ) to very rough ( $e = 3.75$  mm). Also consider the effect of pipe length (again assuming the pump always produces 153 kPa) for smooth pipe. Plot the flow rate against pipe length for  $L = 100$  m through  $L = 1000$  m.

**Given:** Flow from a reservoir

**Find:** Effect of pipe roughness and pipe length on flow rate; Plot

**Solution:**

Governing equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$f = \frac{64}{Re} \quad (8.36) \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

The energy equation (Eq. 8.29) becomes for this flow (see Example 8.5)

$$p_{\text{pump}} = \Delta p = \rho \cdot \left( g \cdot d + f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \right)$$


We need to solve this for velocity  $V$ , (and hence flow rate  $Q$ ) as a function of roughness  $e$ , then length  $L$ . This cannot be solved explicitly for velocity  $V$ , (and hence flow rate  $Q$ ) because  $f$  depends on  $V$ ; solution for a given relative roughness  $e/D$  or length  $L$  requires iteration (or use of *Solver*)

Given data:			Tabulated or graphical data:				
$\Delta p =$	153	kPa	$\mu =$	1.00E-03	N.s/m <sup>2</sup>		
$D =$	75	mm	$\rho =$	999	kg/m <sup>3</sup>		
$L =$	100	m	(Water - Appendix A)				
Computed results:							
$e/D$	$V$ (m/s)	$Q$ (m <sup>3</sup> /s)	$Re$	Regime	$f$	$\Delta p$ (kPa)	Error
0.000	3.98	0.0176	2.98E+05	Turbulent	0.0145	153	0.0%
0.005	2.73	0.0121	2.05E+05	Turbulent	0.0308	153	0.0%
0.010	2.45	0.0108	1.84E+05	Turbulent	0.0382	153	0.0%
0.015	2.29	0.0101	1.71E+05	Turbulent	0.0440	153	0.0%
0.020	2.168	0.00958	1.62E+05	Turbulent	0.0489	153	0.0%
0.025	2.076	0.00917	1.56E+05	Turbulent	0.0533	153	0.0%
0.030	2.001	0.00884	1.50E+05	Turbulent	0.0574	153	0.0%
0.035	1.937	0.00856	1.45E+05	Turbulent	0.0612	153	0.0%
0.040	1.882	0.00832	1.41E+05	Turbulent	0.0649	153	0.0%
0.045	1.833	0.00810	1.37E+05	Turbulent	0.0683	153	0.0%
0.050	1.790	0.00791	1.34E+05	Turbulent	0.0717	153	0.0%


Computed results:							
$L$ (m)	$V$ (m/s)	$Q$ (m <sup>3</sup> /s)	$Re$	Regime	$f$	$\Delta p$ (kPa)	Error
100	1.37	0.00606	1.03E+05	Turbulent	0.1219	153	0.0%
200	1.175	0.00519	8.80E+04	Turbulent	0.0833	153	0.0%
300	1.056	0.00467	7.92E+04	Turbulent	0.0686	153	0.0%
400	0.975	0.00431	7.30E+04	Turbulent	0.0604	153	0.0%
500	0.913	0.004036	6.84E+04	Turbulent	0.0551	153	0.0%
600	0.865	0.003821	6.48E+04	Turbulent	0.0512	153	0.0%
700	0.825	0.003645	6.18E+04	Turbulent	0.0482	153	0.0%
800	0.791	0.003496	5.93E+04	Turbulent	0.0459	153	0.0%
900	0.762	0.003368	5.71E+04	Turbulent	0.0439	153	0.0%
1000	0.737	0.003257	5.52E+04	Turbulent	0.0423	153	0.0%

It is not possible to roughen the tube sufficiently to slow the flow down to a laminar flow for this  $\Delta p$ .

**Flow Rate versus Tube Relative Roughness for fixed  $D_p$**



**Flow Rate versus Tube Length for fixed  $D_p$**



## Problem 8.152

[Difficulty: 4]

**8.152** Water for a fire protection system is supplied from a water tower through a 150-mm cast-iron pipe. A pressure gage at a fire hydrant indicates 600 kPa when no water is flowing. The total pipe length between the elevated tank and the hydrant is 200 m. Determine the height of the water tower above the hydrant. Calculate the maximum volume flow rate that can be achieved when the system is flushed by opening the hydrant wide (assume minor losses are 10 percent of major losses at this condition). When a fire hose is attached to the hydrant, the volume flow rate is 0.75 m<sup>3</sup>/min. Determine the reading of the pressure gage at this flow condition.

**Given:** System for fire protection

**Find:** Height of water tower; Maximum flow rate; Pressure gage reading

**Solution:**

Governing equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = 0.1 \cdot h_l \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$f = \frac{64}{Re} \quad (8.36) \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

For no flow the energy equation (Eq. 8.29) applied between the water tower free surface (state 1; height  $H$ ) and pressure gage is

$$g \cdot H = \frac{p_2}{\rho} \quad \text{or} \quad H = \frac{p_2}{\rho \cdot g} \quad (1)$$

The energy equation (Eq. 8.29) becomes, for maximum flow (and  $\alpha = 1$ )

$$g \cdot H - \frac{V^2}{2} = h_{IT} = (1 + 0.1) \cdot h_l \quad \text{or} \quad g \cdot H = \frac{V^2}{2} \cdot \left( 1 + 1.1 \cdot f \cdot \frac{L}{D} \right) \quad (2)$$

This can be solved for  $V$  (and hence  $Q$ ) by iterating, or by using *Solver*

The energy equation (Eq. 8.29) becomes, for restricted flow

$$g \cdot H - \frac{p_2}{\rho} + \frac{V^2}{2} = h_{IT} = (1 + 0.1) \cdot h_l \quad p_2 = \rho \cdot g \cdot H - \rho \cdot \frac{V^2}{2} \cdot \left( 1 + 1.1 \cdot f \cdot \frac{L}{D} \right) \quad (3)$$


The results in Excel are shown below:

Given data:			Tabulated or graphical data:						
$p_2 =$	600	kPa		$e =$	0.26	mm			
	(Closed)				(Table 8.1)				
$D =$	150	mm		$\mu =$	1.00E-03	N.s/m <sup>2</sup>			
$L =$	200	m		$\rho =$	999	kg/m <sup>3</sup>			
$Q =$	0.75	m <sup>3</sup> /min			(Water - Appendix A)				
	(Open)								
Computed results:									
Closed:			Fully open:			Partially open:			
$H =$	61.2	m	$V =$	5.91	m/s	$Q =$	0.75	m <sup>3</sup> /min	
	(Eq. 1)		$Re =$	8.85E+05		$V =$	0.71	m/s	
			$f =$	0.0228		$Re =$	1.06E+05		
						$f =$	0.0243		
			Eq. 2, solved by varying $V$ using <i>Solver</i> :			$p_2 =$	591	kPa	
			<b>Left (m<sup>3</sup>/s)</b>	<b>Right (m<sup>3</sup>/s)</b>	<b>Error</b>		(Eq. 3)		
			601	601	0%				
			$Q =$	0.104	m <sup>3</sup> /s				

## Problem 8.153

[Difficulty: 4]

**8.153** The siphon shown is fabricated from 50-mm-i.d. drawn aluminum tubing. The liquid is water at 15°C. Compute the volume flow rate through the siphon. Estimate the minimum pressure inside the tube.



**Given:** Syphon system

**Find:** Flow rate; Minimum pressure

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + h_{lm}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Hence the energy equation applied between the tank free surface (Point 1) and the tube exit (Point 2,  $z = 0$ ) becomes

$$g \cdot z_1 - \frac{V_2^2}{2} = g \cdot z_1 - \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{ent} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2}$$

From Table 8.2 for reentrant entrance  $K_{ent} = 0.78$

For the bend  $\frac{R}{D} = 9$  so from Fig. 8.16  $\frac{L_e}{D} = 28$  for a 90° bend so for a 180° bend  $\frac{L_e}{D} = 56$

Solving for V 
$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left[ 1 + K_{ent} + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) \right]}} \quad (1) \quad \text{and} \quad h = 2.5 \cdot \text{m}$$

The two lengths are  $L_e = 56 \cdot D$   $L_e = 2.8 \text{ m}$   $L = (0.6 + \pi \cdot 0.45 + 2.5) \cdot \text{m}$   $L = 4.51 \text{ m}$

We also have  $Re = \frac{V \cdot D}{\nu}$  or  $Re = c \cdot V$  (2) where  $c = \frac{D}{\nu}$

From Table A.7 (15°C)  $\nu = 1.14 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$   $c = 0.05 \cdot \text{m} \times \frac{\text{s}}{1.14 \times 10^{-6} \cdot \text{m}^2}$   $c = 4.39 \times 10^4 \cdot \frac{\text{s}}{\text{m}}$

In addition 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (3) \quad e = 0.0015 \cdot \text{mm} \quad (\text{Table 8.1})$$

Equations 1, 2 and 3 form a set of simultaneous equations for V, Re and f

Make a guess for f  $f = 0.01$  then

$$V = \sqrt{\frac{2 \cdot g \cdot h}{1 + K_{\text{ent}} + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right)}} \quad V = 3.89 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.71 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0164$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{1 + K_{\text{ent}} + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right)}} \quad V = 3.43 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.50 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0168$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{1 + K_{\text{ent}} + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right)}} \quad V = 3.40 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.49 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0168$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{1 + K_{\text{ent}} + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right)}} \quad V = 3.40 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.49 \times 10^5$$

Note that we could use *Excel's Solver* for this problem.

The flow rate is then  $Q = \frac{\pi \cdot D^2}{4} \cdot V \quad Q = 6.68 \times 10^{-3} \frac{\text{m}^3}{\text{s}}$

The minimum pressure occurs at the top of the curve (Point 3). Applying the energy equation between Points 1 and 3

$$g \cdot z_1 - \left( \frac{p_3}{\rho} + \frac{V_3^2}{2} + g \cdot z_3 \right) = g \cdot z_1 - \left( \frac{p_3}{\rho} + \frac{V^2}{2} + g \cdot z_3 \right) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{\text{ent}} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2}$$

where we have  $\frac{L_e}{D} = 28$  for the first 90° of the bend, and  $L = \left( 0.6 + \frac{\pi \times 0.45}{2} \right) \cdot \text{m} \quad L = 1.31 \text{ m}$

$$p_3 = \rho \cdot \left[ g \cdot (z_1 - z_3) - \frac{V^2}{2} \cdot \left[ 1 + K_{\text{ent}} + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) \right] \right]$$

$$p_3 = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ 9.81 \cdot \frac{\text{m}}{\text{s}^2} \times (-0.45 \cdot \text{m}) - \frac{\left( 3.4 \cdot \frac{\text{m}}{\text{s}} \right)^2}{2} \cdot \left[ 1 + 0.78 + 0.0168 \cdot \left( \frac{1.31}{0.05} + 28 \right) \right] \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad p_3 = -20.0 \cdot \text{kPa}$$

## Problem 8.154

[Difficulty: 4]

**8.154** A large open water tank has a horizontal cast iron drainpipe of diameter  $D = 1$  in. and length  $L = 2$  ft attached at its base. If the depth of water is  $h = 3$  ft, find the flow rate (gpm) if the pipe entrance is (a) reentrant, (b) square-edged, and (c) rounded ( $r = 0.2$  in.).

**Given:** Tank with drainpipe

**Find:** Flow rate for reentrant, square-edged, and rounded entrances

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{ent} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Available data  $D = 1$  in  $L = 2$  ft  $e = 0.00085$  ft (Table 8.1)  $h = 3$  ft  $r = 0.2$  in

Hence the energy equation applied between the tank free surface (Point 1) and the pipe exit (Point 2,  $z = 0$ ) becomes

$$g \cdot z_1 - \frac{V_2^2}{2} = g \cdot z_1 - \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{ent} \cdot \frac{V^2}{2}$$

Solving for V 
$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{ent} + f \cdot \frac{L}{D}\right)}} \quad (1)$$

We also have 
$$Re = \frac{V \cdot D}{\nu} \quad \text{or} \quad Re = c \cdot V \quad (2) \quad \text{where} \quad c = \frac{D}{\nu}$$

From Table A.7 (20°C) 
$$\nu = 1.01 \times 10^{-6} \frac{\text{m}^2}{\text{s}} \quad \nu = 1.09 \times 10^{-5} \frac{\text{ft}^2}{\text{s}} \quad c = \frac{D}{\nu} \quad c = 7665 \frac{\text{s}}{\text{ft}}$$

In addition 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (3)$$

Equations 1, 2 and 3 form a set of simultaneous equations for V, Re and f

For a reentrant entrance, from Table 8.2  $K_{ent} = 0.78$

Make a guess for f  $f = 0.01$  then 
$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{ent} + f \cdot \frac{L}{D}\right)}} \quad V = 2.98 \frac{\text{m}}{\text{s}}$$

$$Re = c \cdot V \quad Re = 7.49 \times 10^4$$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0389$$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 2.57 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 6.46 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0391$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 2.57 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 6.46 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0391$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 2.57 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 6.46 \times 10^4$$

Note that we could use *Excel's Solver* for this problem

The flow rate is then  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $Q = 0.0460 \frac{\text{ft}^3}{\text{s}}$   $Q = 20.6 \cdot \text{gpm}$

For a square-edged entrance, from Table 8.2  $K_{\text{ent}} = 0.5$

Make a guess for  $f$   $f = 0.01$  then  $V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 3.21 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 8.07 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0389$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 2.71 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 6.83 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0390$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 2.71 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 6.82 \times 10^4$$

The flow rate is then  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $Q = 0.0485 \frac{\text{ft}^3}{\text{s}}$   $Q = 21.8 \cdot \text{gpm}$

For a rounded entrance, from Table 8.2  $\frac{r}{D} = 0.2$   $K_{\text{ent}} = 0.04$

Make a guess for  $f$   $f = 0.01$

then

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}}$$

$$V = 3.74 \frac{\text{m}}{\text{s}}$$

$$\text{Re} = c \cdot V$$

$$\text{Re} = 9.41 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0388$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}}$$

$$V = 3.02 \frac{\text{m}}{\text{s}}$$

$$\text{Re} = c \cdot V$$

$$\text{Re} = 7.59 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0389$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}}$$

$$V = 3.01 \frac{\text{m}}{\text{s}}$$

$$\text{Re} = c \cdot V$$

$$\text{Re} = 7.58 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0389$

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}}$$

$$V = 3.01 \frac{\text{m}}{\text{s}}$$

$$\text{Re} = c \cdot V$$

$$\text{Re} = 7.58 \times 10^4$$

Note that we could use *Excel's Solver* for this problem

The flow rate is then  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $Q = 0.0539 \frac{\text{ft}^3}{\text{s}}$   $Q = 24.2 \cdot \text{gpm}$

In summary: Renentrant:  $Q = 20.6 \cdot \text{gpm}$  Square-edged:  $Q = 21.8 \cdot \text{gpm}$  Rounded:  $Q = 24.2 \cdot \text{gpm}$

## Problem 8.155

[Difficulty: 4]

**8.155** Repeat Problem 8.154, except now the pipe is vertical, as shown.

**Given:** Tank with drainpipe

**Find:** Flow rate for reentrant, square-edged, and rounded entrances

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{ent} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Available data  $D = 1 \cdot \text{in}$   $L = 2 \cdot \text{ft}$   $e = 0.00085 \cdot \text{ft}$  (Table 8.1)  $h = 3 \cdot \text{ft}$   $r = 0.2 \cdot \text{in}$

Hence the energy equation applied between the tank free surface (Point 1) and the pipe exit (Point 2,  $z = 0$ ) becomes

$$g \cdot z_1 - \frac{V_2^2}{2} = g \cdot z_1 - \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K_{ent} \cdot \frac{V^2}{2}$$

Solving for V 
$$V = \sqrt{\frac{2 \cdot g \cdot H}{\left( 1 + K_{ent} + f \cdot \frac{L}{D} \right)}} \quad (1)$$

where now we have  $H = h + L$   $H = 5 \text{ ft}$

We also have  $Re = \frac{V \cdot D}{\nu}$  or  $Re = c \cdot V$  (2) where  $c = \frac{D}{\nu}$

From Table A.7 (20°C)  $\nu = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$   $\nu = 1.09 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$   $c = \frac{D}{\nu}$   $c = 7665 \cdot \frac{\text{s}}{\text{ft}}$

In addition 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (3)$$

Equations 1, 2 and 3 form a set of simultaneous equations for V, Re and f

For a reentrant entrance, from Table 8.2  $K_{ent} = 0.78$

Make a guess for f  $f = 0.01$  then 
$$V = \sqrt{\frac{2 \cdot g \cdot H}{\left( 1 + K_{ent} + f \cdot \frac{L}{D} \right)}} \quad V = 3.85 \frac{\text{m}}{\text{s}}$$

$Re = c \cdot V$   $Re = 9.67 \times 10^4$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0388$$

$$V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 3.32 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 8.35 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{c}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0389$

$$V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 3.32 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 8.35 \times 10^4$$

Note that we could use *Excel's Solver* for this problem

The flow rate is then  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $Q = 0.0594 \frac{\text{ft}^3}{\text{s}}$   $Q = 26.7 \cdot \text{gpm}$

For a square-edged entrance, from Table 8.2  $K_{\text{ent}} = 0.5$

Make a guess for  $f$   $f = 0.01$  then  $V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 4.14 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.04 \times 10^5$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{c}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0387$

$$V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 3.51 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 8.82 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{c}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0388$

$$V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 3.51 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 8.82 \times 10^4$$

The flow rate is then  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $Q = 0.0627 \frac{\text{ft}^3}{\text{s}}$   $Q = 28.2 \cdot \text{gpm}$

For a rounded entrance, from Table 8.2  $\frac{r}{D} = 0.2$   $K_{\text{ent}} = 0.04$

Make a guess for  $f$   $f = 0.01$  then  $V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}} \quad V = 4.83 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.22 \times 10^5$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0386$

$V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}}$   $V = 3.90 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot V$   $\text{Re} = 9.80 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0388$

$V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}}$   $V = 3.89 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot V$   $\text{Re} = 9.80 \times 10^4$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log\left(\frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}}\right)$   $f = 0.0388$

$V = \sqrt{\frac{2 \cdot g \cdot H}{\left(1 + K_{\text{ent}} + f \cdot \frac{L}{D}\right)}}$   $V = 3.89 \frac{\text{m}}{\text{s}}$   $\text{Re} = c \cdot V$   $\text{Re} = 9.80 \times 10^4$

Note that we could use *Excel's Solver* for this problem

The flow rate is then  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $Q = 0.0697 \frac{\text{ft}^3}{\text{s}}$   $Q = 31.3 \cdot \text{gpm}$

In summary: Renentrant:  $Q = 26.7 \cdot \text{gpm}$  Square-edged:  $Q = 28.2 \cdot \text{gpm}$  Rounded:  $Q = 31.3 \cdot \text{gpm}$

## Problem 8.156

[Difficulty: 5]

**8.156** A tank containing  $30 \text{ m}^3$  of kerosene is to be emptied by a gravity feed using a drain hose of diameter 15 mm, roughness 0.2 mm, and length 1 m. The top of the tank is open to the atmosphere and the hose exits to an open chamber. If the kerosene level is initially 10 m above the drain exit, estimate (by assuming steady flow) the initial drainage rate. Estimate the flow rate when the kerosene level is down to 5 m, and then down to 1 m. Based on these three estimates, make a rough estimate of the time it took to drain to the 1-m level.

**Given:** Tank with drain hose

**Find:** Flow rate at different instants; Estimate of drain time

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1 4) Ignore minor loss at entrance ( $L \gg r$ ; verify later)

Available data  $L = 1 \cdot \text{m}$      $D = 15 \cdot \text{mm}$      $e = 0.2 \cdot \text{mm}$      $\text{Vol} = 30 \cdot \text{m}^3$

Hence the energy equation applied between the tank free surface (Point 1) and the hose exit (Point 2,  $z = 0$ ) becomes

$$g \cdot z_1 - \frac{V_2^2}{2} = g \cdot z_1 - \frac{V^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Solving for V 
$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad (1) \quad \text{and} \quad h = 10 \cdot \text{m} \quad \text{initially}$$

We also have 
$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{or} \quad \text{Re} = c \cdot V \quad (2) \quad \text{where} \quad c = \frac{D}{\nu}$$

From Fig. A.2 (20°C) 
$$\nu = 1.8 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}} \quad c = \frac{D}{\nu} \quad c = 8333 \frac{\text{s}}{\text{m}}$$

In addition 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7 \cdot D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad (3)$$

Equations 1, 2 and 3 form a set of simultaneous equations for V, Re and f

Make a guess for f  $f = 0.01$  then

$$V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad V = 10.8 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 9.04 \times 10^4$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0427 \quad V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad V = 7.14 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 5.95 \times 10^4$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0427 \quad V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad V = 7.14 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 5.95 \times 10^4$$

Note that we could use *Excel's Solver* for this problem

$$\text{Note: } f \cdot \frac{L}{D} = 2.8 \quad K_e = 0.5 \quad h_{lm} < h_1$$

$$\text{The flow rate is then } Q = V \cdot \frac{\pi \cdot D^2}{4} \quad Q = 1.26 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 1.26 \cdot \frac{1}{\text{s}}$$

Next we recompute everything for  $h = 5 \cdot \text{m}$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0430 \quad V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad V = 5.04 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 4.20 \times 10^4$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0430 \quad V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad V = 5.04 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 4.20 \times 10^4$$

$$\text{The flow rate is then } Q = V \cdot \frac{\pi \cdot D^2}{4} \quad Q = 8.9 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \quad Q = 0.890 \cdot \frac{1}{\text{s}}$$

Next we recompute everything for  $h = 1 \cdot \text{m}$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0444 \quad V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad V = 2.23 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.85 \times 10^4$$

$$\text{Given } \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0444 \quad V = \sqrt{\frac{2 \cdot g \cdot h}{\left(1 + f \cdot \frac{L}{D}\right)}} \quad V = 2.23 \frac{\text{m}}{\text{s}} \quad \text{Re} = c \cdot V \quad \text{Re} = 1.85 \times 10^4$$

$$\text{The flow rate is then } Q = V \cdot \frac{\pi \cdot D^2}{4} \quad Q = 3.93 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \quad Q = 0.393 \cdot \frac{1}{\text{s}}$$

Initially we have  $dQ/dt = -1.26 \text{ L/s}$ , then  $-0.890 \text{ L/s}$ , then  $-0.393 \text{ L/s}$ . These occur at  $h = 10 \text{ m}$ ,  $5 \text{ m}$  and  $1 \text{ m}$ . The corresponding volumes in the tank are then  $Q = 30,000 \text{ L}$ ,  $15,000 \text{ L}$ , and  $3,000 \text{ L}^3$ . Using *Excel* we can fit a power trendline to the  $dQ/dt$  versus  $Q$  data to find, approximately

$$\frac{dQ}{dt} = -0.00683 \cdot Q^{\frac{1}{2}} \quad \text{where } dQ/dt \text{ is in L/s and } t \text{ is s. Solving this with initial condition } Q = -1.26 \text{ L/s when } t = 0 \text{ gives}$$

$$t = 293 \cdot (\sqrt{30} - \sqrt{Q}) \quad \text{Hence, when } Q = 3000 \text{ L (} h = 1 \text{ m)} \quad t = 293 \cdot (\sqrt{30000} - \sqrt{3000}) \cdot \text{s} \quad t = 3.47 \times 10^4 \text{ s} \quad t = 9.64 \text{ hr}$$



**Problem 8.158**

[Difficulty: 4] Part 1/2

**8.158** You are watering your lawn with an *old* hose. Because lime deposits have built up over the years, the 0.75-in.-i.d. hose now has an average roughness height of 0.022 in. One 50-ft length of the hose, attached to your spigot, delivers 15 gpm of water (60°F). Compute the pressure at the spigot, in psi. Estimate the delivery if two 50-ft lengths of the hose are connected. Assume that the pressure at the spigot varies with flow rate and the water main pressure remains constant at 50 psig.

Solution:



Apply the energy equation for steady, incompressible flow between the spigot (2) and the hose discharge (3)

Basic equations: 
$$\left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2 \right) - \left( \frac{p_3}{\rho} + \alpha_3 \frac{V_3^2}{2} + g z_3 \right) = h_{eT} \quad (8.20)$$

$$h_{eT} = h_e + h_{en}, \quad h_e = f \frac{L}{D} \frac{V^2}{2}$$

- Assumptions: (1)  $p_3 = p_{atm}$  (4) Turbulent flow so  $\Delta P_{1-2} \propto Q^2$   
 (2)  $V_2 = V_3, \alpha_2 = \alpha_3 = 1.0$   
 (3)  $z_2 = z_3$

Then 
$$p_2 = \rho f \frac{L}{D} \frac{V^2}{2} \quad (1)$$

$$V = \frac{Q}{A} = \frac{15 \text{ gal}}{\pi (0.75 \text{ in})^2} = \frac{15 \text{ gal}}{\pi \text{ ft}^2} \times \frac{1.488 \text{ gal}}{\text{ft}^3} \times \frac{1 \text{ min}}{60 \text{ s}} = 10.9 \text{ ft/s}$$

$$Re = \frac{VD}{\nu} = \frac{0.75 \text{ ft} \times 10.9 \text{ ft/s}}{1.21 \times 10^{-5} \text{ ft}^2/\text{s}} = 5.63 \times 10^4 \quad \{ \nu \text{ from Table A.7} \}$$

$$e/D = 0.022 / 0.75 = 0.0293$$

From Eq. 8.37  $f = 0.056^*$ . From Eq. 1,

$$p_2 = 1.94 \frac{\text{slug}}{\text{ft}^3} \times 0.056 \times \frac{50 \text{ ft}}{0.75 \text{ in}} \times \frac{12 \text{ in}}{\text{ft}} \times \frac{1}{2} \times (10.9 \text{ ft/s})^2 \times \frac{16 \text{ ft}^2}{52} \times \frac{\text{ft}^2}{144 \text{ in}^2}$$

$$p_2 = 35.9 \text{ psi gage} \quad p_2$$

The pressure drop from the main (1) to the spigot (2) is proportional to the square of the flow rate. Obtain the loss coefficient using the energy equation between (1) and (2).

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2 \right) = K \frac{V_2^2}{2}$$

Assumptions: (4)  $V_1 = V_2 = V$  (5)  $z_1 = z_2$

$$p_1 - p_2 = \rho \left[ K \frac{V^2}{2} + \frac{V^2}{2} \right] = \rho \frac{V^2}{2} [K + 1]$$

$$K = \frac{\Delta P}{\rho V^2 / 2} - 1 = \frac{2(50 - 35.9) 144 \frac{\text{ft}^2}{\text{s}^2}}{1.94 \text{ slug} \times (10.9 \text{ ft/s})^2} \times \frac{\text{slug} \cdot \text{ft}}{16 \text{ ft}^2} - 1$$

$$K = 16.6$$

\* Value of  $f$  obtained using Excel's Solver (or Goal Seek).

42-291  
 42-292  
 42-293  
 42-294  
 42-295  
 42-296  
 42-297  
 42-298  
 42-299  
 42-300  
 42-301  
 42-302  
 42-303  
 42-304  
 42-305  
 42-306  
 42-307  
 42-308  
 42-309  
 42-310  
 42-311  
 42-312  
 42-313  
 42-314  
 42-315  
 42-316  
 42-317  
 42-318  
 42-319  
 42-320  
 42-321  
 42-322  
 42-323  
 42-324  
 42-325  
 42-326  
 42-327  
 42-328  
 42-329  
 42-330  
 42-331  
 42-332  
 42-333  
 42-334  
 42-335  
 42-336  
 42-337  
 42-338  
 42-339  
 42-340  
 42-341  
 42-342  
 42-343  
 42-344  
 42-345  
 42-346  
 42-347  
 42-348  
 42-349  
 42-350  
 42-351  
 42-352  
 42-353  
 42-354  
 42-355  
 42-356  
 42-357  
 42-358  
 42-359  
 42-360  
 42-361  
 42-362  
 42-363  
 42-364  
 42-365  
 42-366  
 42-367  
 42-368  
 42-369  
 42-370  
 42-371  
 42-372  
 42-373  
 42-374  
 42-375  
 42-376  
 42-377  
 42-378  
 42-379  
 42-380  
 42-381  
 42-382  
 42-383  
 42-384  
 42-385  
 42-386  
 42-387  
 42-388  
 42-389  
 42-390  
 42-391  
 42-392  
 42-393  
 42-394  
 42-395  
 42-396  
 42-397  
 42-398  
 42-399  
 42-400  
 42-401  
 42-402  
 42-403  
 42-404  
 42-405  
 42-406  
 42-407  
 42-408  
 42-409  
 42-410  
 42-411  
 42-412  
 42-413  
 42-414  
 42-415  
 42-416  
 42-417  
 42-418  
 42-419  
 42-420  
 42-421  
 42-422  
 42-423  
 42-424  
 42-425  
 42-426  
 42-427  
 42-428  
 42-429  
 42-430  
 42-431  
 42-432  
 42-433  
 42-434  
 42-435  
 42-436  
 42-437  
 42-438  
 42-439  
 42-440  
 42-441  
 42-442  
 42-443  
 42-444  
 42-445  
 42-446  
 42-447  
 42-448  
 42-449  
 42-450  
 42-451  
 42-452  
 42-453  
 42-454  
 42-455  
 42-456  
 42-457  
 42-458  
 42-459  
 42-460  
 42-461  
 42-462  
 42-463  
 42-464  
 42-465  
 42-466  
 42-467  
 42-468  
 42-469  
 42-470  
 42-471  
 42-472  
 42-473  
 42-474  
 42-475  
 42-476  
 42-477  
 42-478  
 42-479  
 42-480  
 42-481  
 42-482  
 42-483  
 42-484  
 42-485  
 42-486  
 42-487  
 42-488  
 42-489  
 42-490  
 42-491  
 42-492  
 42-493  
 42-494  
 42-495  
 42-496  
 42-497  
 42-498  
 42-499  
 42-500  
 42-501  
 42-502  
 42-503  
 42-504  
 42-505  
 42-506  
 42-507  
 42-508  
 42-509  
 42-510  
 42-511  
 42-512  
 42-513  
 42-514  
 42-515  
 42-516  
 42-517  
 42-518  
 42-519  
 42-520  
 42-521  
 42-522  
 42-523  
 42-524  
 42-525  
 42-526  
 42-527  
 42-528  
 42-529  
 42-530  
 42-531  
 42-532  
 42-533  
 42-534  
 42-535  
 42-536  
 42-537  
 42-538  
 42-539  
 42-540  
 42-541  
 42-542  
 42-543  
 42-544  
 42-545  
 42-546  
 42-547  
 42-548  
 42-549  
 42-550  
 42-551  
 42-552  
 42-553  
 42-554  
 42-555  
 42-556  
 42-557  
 42-558  
 42-559  
 42-560  
 42-561  
 42-562  
 42-563  
 42-564  
 42-565  
 42-566  
 42-567  
 42-568  
 42-569  
 42-570  
 42-571  
 42-572  
 42-573  
 42-574  
 42-575  
 42-576  
 42-577  
 42-578  
 42-579  
 42-580  
 42-581  
 42-582  
 42-583  
 42-584  
 42-585  
 42-586  
 42-587  
 42-588  
 42-589  
 42-590  
 42-591  
 42-592  
 42-593  
 42-594  
 42-595  
 42-596  
 42-597  
 42-598  
 42-599  
 42-600  
 42-601  
 42-602  
 42-603  
 42-604  
 42-605  
 42-606  
 42-607  
 42-608  
 42-609  
 42-610  
 42-611  
 42-612  
 42-613  
 42-614  
 42-615  
 42-616  
 42-617  
 42-618  
 42-619  
 42-620  
 42-621  
 42-622  
 42-623  
 42-624  
 42-625  
 42-626  
 42-627  
 42-628  
 42-629  
 42-630  
 42-631  
 42-632  
 42-633  
 42-634  
 42-635  
 42-636  
 42-637  
 42-638  
 42-639  
 42-640  
 42-641  
 42-642  
 42-643  
 42-644  
 42-645  
 42-646  
 42-647  
 42-648  
 42-649  
 42-650  
 42-651  
 42-652  
 42-653  
 42-654  
 42-655  
 42-656  
 42-657  
 42-658  
 42-659  
 42-660  
 42-661  
 42-662  
 42-663  
 42-664  
 42-665  
 42-666  
 42-667  
 42-668  
 42-669  
 42-670  
 42-671  
 42-672  
 42-673  
 42-674  
 42-675  
 42-676  
 42-677  
 42-678  
 42-679  
 42-680  
 42-681  
 42-682  
 42-683  
 42-684  
 42-685  
 42-686  
 42-687  
 42-688  
 42-689  
 42-690  
 42-691  
 42-692  
 42-693  
 42-694  
 42-695  
 42-696  
 42-697  
 42-698  
 42-699  
 42-700  
 42-701  
 42-702  
 42-703  
 42-704  
 42-705  
 42-706  
 42-707  
 42-708  
 42-709  
 42-710  
 42-711  
 42-712  
 42-713  
 42-714  
 42-715  
 42-716  
 42-717  
 42-718  
 42-719  
 42-720  
 42-721  
 42-722  
 42-723  
 42-724  
 42-725  
 42-726  
 42-727  
 42-728  
 42-729  
 42-730  
 42-731  
 42-732  
 42-733  
 42-734  
 42-735  
 42-736  
 42-737  
 42-738  
 42-739  
 42-740  
 42-741  
 42-742  
 42-743  
 42-744  
 42-745  
 42-746  
 42-747  
 42-748  
 42-749  
 42-750  
 42-751  
 42-752  
 42-753  
 42-754  
 42-755  
 42-756  
 42-757  
 42-758  
 42-759  
 42-760  
 42-761  
 42-762  
 42-763  
 42-764  
 42-765  
 42-766  
 42-767  
 42-768  
 42-769  
 42-770  
 42-771  
 42-772  
 42-773  
 42-774  
 42-775  
 42-776  
 42-777  
 42-778  
 42-779  
 42-780  
 42-781  
 42-782  
 42-783  
 42-784  
 42-785  
 42-786  
 42-787  
 42-788  
 42-789  
 42-790  
 42-791  
 42-792  
 42-793  
 42-794  
 42-795  
 42-796  
 42-797  
 42-798  
 42-799  
 42-800  
 42-801  
 42-802  
 42-803  
 42-804  
 42-805  
 42-806  
 42-807  
 42-808  
 42-809  
 42-810  
 42-811  
 42-812  
 42-813  
 42-814  
 42-815  
 42-816  
 42-817  
 42-818  
 42-819  
 42-820  
 42-821  
 42-822  
 42-823  
 42-824  
 42-825  
 42-826  
 42-827  
 42-828  
 42-829  
 42-830  
 42-831  
 42-832  
 42-833  
 42-834  
 42-835  
 42-836  
 42-837  
 42-838  
 42-839  
 42-840  
 42-841  
 42-842  
 42-843  
 42-844  
 42-845  
 42-846  
 42-847  
 42-848  
 42-849  
 42-850  
 42-851  
 42-852  
 42-853  
 42-854  
 42-855  
 42-856  
 42-857  
 42-858  
 42-859  
 42-860  
 42-861  
 42-862  
 42-863  
 42-864  
 42-865  
 42-866  
 42-867  
 42-868  
 42-869  
 42-870  
 42-871  
 42-872  
 42-873  
 42-874  
 42-875  
 42-876  
 42-877  
 42-878  
 42-879  
 42-880  
 42-881  
 42-882  
 42-883  
 42-884  
 42-885  
 42-886  
 42-887  
 42-888  
 42-889  
 42-890  
 42-891  
 42-892  
 42-893  
 42-894  
 42-895  
 42-896  
 42-897  
 42-898  
 42-899  
 42-900  
 42-901  
 42-902  
 42-903  
 42-904  
 42-905  
 42-906  
 42-907  
 42-908  
 42-909  
 42-910  
 42-911  
 42-912  
 42-913  
 42-914  
 42-915  
 42-916  
 42-917  
 42-918  
 42-919  
 42-920  
 42-921  
 42-922  
 42-923  
 42-924  
 42-925  
 42-926  
 42-927  
 42-928  
 42-929  
 42-930  
 42-931  
 42-932  
 42-933  
 42-934  
 42-935  
 42-936  
 42-937  
 42-938  
 42-939  
 42-940  
 42-941  
 42-942  
 42-943  
 42-944  
 42-945  
 42-946  
 42-947  
 42-948  
 42-949  
 42-950  
 42-951  
 42-952  
 42-953  
 42-954  
 42-955  
 42-956  
 42-957  
 42-958  
 42-959  
 42-960  
 42-961  
 42-962  
 42-963  
 42-964  
 42-965  
 42-966  
 42-967  
 42-968  
 42-969  
 42-970  
 42-971  
 42-972  
 42-973  
 42-974  
 42-975  
 42-976  
 42-977  
 42-978  
 42-979  
 42-980  
 42-981  
 42-982  
 42-983  
 42-984  
 42-985  
 42-986  
 42-987  
 42-988  
 42-989  
 42-990  
 42-991  
 42-992  
 42-993  
 42-994  
 42-995  
 42-996  
 42-997  
 42-998  
 42-999  
 42-1000



To find the delivery with two hoses, again apply the energy equation from the man (1) to the end (4) of the second hose

$$\left( \frac{P_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1 \right) - \left( \frac{P_4}{\rho} + \alpha_4 \frac{V_4^2}{2} + g z_4 \right) = f \frac{L_{24}}{D} \frac{V_4^2}{2} + K \frac{V_4^2}{2}$$

$$P_1 = P_4 = P_{atm}, \quad z_1 = z_4, \quad V_1 = 0, \quad \alpha_1 = 1$$

$$\frac{P_1 - P_{atm}}{\rho} = \frac{P_1 - P_2}{\rho} = \frac{V_4^2}{2} \left( f \frac{L_{24}}{D} + K + 1 \right) \quad \text{and}$$

$$V_4 = \left[ \frac{2(P_1 - P_2)}{\rho \left( 2f \frac{L}{D} + K + 1 \right)} \right]^{1/2}$$

Delivery will be reduced somewhat with two lengths of hose, but  $f$  will not change much. Assume  $f \approx 0.056$  and check

$$V_4 = \left[ \frac{2 \times 50 \frac{\text{ft}}{\text{s}^2} \times 144 \frac{\text{in}^2}{\text{ft}^2} \times 1.94 \frac{\text{slug}}{\text{ft}^3}}{\rho \left( 2 \times 0.056 \times \frac{100 \text{ ft}}{0.75 \text{ in}} \times \frac{1 \text{ in}}{12 \text{ ft}} + 16.6 + 1 \right)} \right]^{1/2}$$

$$V_4 = 8.32 \text{ ft/s}$$

Checking,

$$Re = \frac{V D}{\nu} = \frac{0.75 \text{ ft} \times 8.32 \frac{\text{ft}}{\text{s}}}{1.21 \times 10^{-5} \frac{\text{ft}^2}{\text{s}}} = 4.30 \times 10^4, \quad \text{so } f \approx 0.056$$

Flow with two hoses,

$$Q = V A = 8.32 \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} \times \left( \frac{0.75}{12} \right)^2 \text{ ft}^2 \times \frac{7.48 \text{ gal}}{\text{ft}^3} \times \frac{60 \text{ s}}{\text{min}} = 11.5 \text{ gpm} \quad Q$$

{ Similar calculations could be performed using any desired number of hose lengths. }

National Brand  
 100% RECYCLED PAPER  
 50% RECYCLED FIBER  
 100% RECYCLED INK  
 100% RECYCLED WASTE  
 5 SQUARE  
 MANUFACTURED IN U.S.A.





## Problem 8.160

[Difficulty: 5]

**8.160** Your boss, from the “old school,” claims that for pipe flow the flow rate,  $Q \propto \sqrt{\Delta p}$ , where  $\Delta p$  is the pressure difference driving the flow. You dispute this, so perform some calculations. You take a 1-in.-diameter commercial steel pipe and assume an initial flow rate of 1.25 gal/min of water. You then increase the applied pressure in equal increments and compute the new flow rates so you can plot  $Q$  versus  $\Delta p$ , as computed by you and your boss. Plot the two curves on the same graph. Was your boss right?

Applying the energy equation between inlet and exit:


$$\frac{\Delta p}{\rho} = f \frac{L}{D} \frac{V^2}{2} \quad \text{or} \quad \frac{\Delta p}{L} = \frac{\rho f}{D} \frac{V^2}{2}$$

“Old school”:

$$\frac{\Delta p}{L} = \left( \frac{\Delta p}{L} \right)_0 \left( \frac{Q_0}{Q} \right)^2$$

$$\begin{aligned} D &= 1 \text{ in} \\ e &= 0.00015 \text{ ft} \\ \nu &= 1.08\text{E-}05 \text{ ft}^2/\text{s} \\ \rho &= 1.94 \text{ slug/ft}^3 \end{aligned}$$

$Q$ (gpm)	$Q$ (ft <sup>3</sup> /s)	$V$ (ft/s)	$Re$	$f$	$\Delta p$ (old school) (psi)	$\Delta p$ (psi/ft)
1.25	0.00279	0.511	3940	0.0401	0.00085	0.00085
1.50	0.00334	0.613	4728	0.0380	0.00122	0.00115
1.75	0.00390	0.715	5516	0.0364	0.00166	0.00150
2.00	0.00446	0.817	6304	0.0350	0.00216	0.00189



8.75	0.01950	3.575	27582	0.0240	0.04142	0.02477
9.00	0.02005	3.677	28370	0.0238	0.04382	0.02604

**Your boss was wrong!**

## Problem 8.161

[Difficulty: 5]

**8.161** For Problem 8.146, what would the diameter of the pipe of length  $2L$  need to be to generate the same flow as the pipe of length  $L$ ?

**Given:** Flow from large reservoir

**Find:** Diameter for flow rates in two pipes to be same

**Solution:**

$$\text{Basic equations} \quad \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad h_{lm} = K_{ent} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

$$\begin{array}{llll} \text{Available data} & D = 50\text{-mm} & H = 10\text{-m} & L = 10\text{-m} \\ & e = 0.15\text{-mm} & (\text{Table 8.1}) & \nu = 1 \cdot 10^{-6} \frac{\text{m}^2}{\text{s}} \quad (\text{Table A.8}) \quad K_{ent} = 0.5 \end{array}$$

For the pipe of length  $L$  the energy equation becomes

$$g \cdot (z_1 - z_2) - \frac{1}{2} \cdot V_2^2 = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K_{ent} \cdot \frac{V_2^2}{2} \quad \text{and} \quad V_2 = V \quad z_1 - z_2 = H$$

Solving for  $V$

$$V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad (1)$$

We also have

$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad (2) \quad \text{Re} = \frac{V \cdot D}{\nu} \quad (3)$$

We must solve Eqs. 1, 2 and 3 iteratively.

$$\text{Make a guess for } V \quad V = 1 \cdot \frac{\text{m}}{\text{s}} \quad \text{Then} \quad \text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 5.00 \times 10^4$$

$$\text{and} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0286$$

$$\text{Then} \quad V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{ent} + 1}} \quad V = 5.21 \frac{\text{m}}{\text{s}}$$

$$\text{Repeating} \quad \text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 2.61 \times 10^5$$

and 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0267$$

Then 
$$V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{\text{ent}} + 1}} \quad V = 5.36 \frac{\text{m}}{\text{s}}$$

Repeating 
$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 2.68 \times 10^5$$

and 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0267$$

Then 
$$V = \sqrt{\frac{2 \cdot g \cdot H}{f \cdot \frac{L}{D} + K_{\text{ent}} + 1}} \quad V = 5.36 \frac{\text{m}}{\text{s}}$$

Hence 
$$Q = \frac{\pi}{4} \cdot D^2 \cdot V \quad Q = 0.0105 \frac{\text{m}^3}{\text{s}} \quad Q = 10.5 \cdot \frac{\text{l}}{\text{s}}$$

This is the flow rate we require in the second pipe (of length 2L)

For the pipe of length 2L the energy equation becomes

$$g \cdot (z_1 - z_2) - \frac{1}{2} \cdot V_2^2 = f \cdot \frac{2 \cdot L}{D} \cdot \frac{V_2^2}{2} + K_{\text{ent}} \cdot \frac{V_2^2}{2} \quad \text{and} \quad V_2 = V \quad z_1 - z_2 = H \quad Q = 0.0105 \frac{\text{m}^3}{\text{s}}$$

Hence 
$$H = \frac{V^2}{2 \cdot g} \cdot \left( f \cdot \frac{2 \cdot L}{D} + K_{\text{ent}} + 1 \right) \quad (4)$$

We must make a guess for D (larger than the other pipe)  $D = 0.06 \cdot \text{m}$  Then we have  $V = \frac{Q}{\frac{\pi}{4} \cdot D^2} \quad V = 3.72 \frac{\text{m}}{\text{s}}$

Then 
$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 2.23 \times 10^5$$

and 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0256$$

Using Eq 4 to find H 
$$H_{\text{iterate}} = \frac{V^2}{2 \cdot g} \cdot \left( f \cdot \frac{2 \cdot L}{D} + K_{\text{ent}} + 1 \right) \quad H_{\text{iterate}} = 7.07 \text{ m} \quad \text{But} \quad H = 10 \text{ m}$$

Hence the diameter is too large: Only a head of  $H_{\text{iterate}} = 7.07 \text{ m}$  would be needed to generate the flow. We make D smaller

Try  $D = 0.055 \cdot \text{m}$  Then we have  $V = \frac{Q}{\frac{\pi}{4} \cdot D^2}$   $V = 4.43 \frac{\text{m}}{\text{s}}$

Then  $\text{Re} = \frac{V \cdot D}{\nu}$   $\text{Re} = 2.43 \times 10^5$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$   $f = 0.0261$

Using Eq 4 to find H  $H_{\text{iterate}} = \frac{V^2}{2 \cdot g} \cdot \left( f \cdot \frac{2 \cdot L}{D} + K_{\text{ent}} + 1 \right)$   $H_{\text{iterate}} = 10.97 \text{ m}$  But  $H = 10 \text{ m}$

Hence the diameter is too small: A head of  $H_{\text{iterate}} = 10.97 \text{ m}$  would be needed. We make D slightly larger

Try  $D = 0.056 \cdot \text{m}$  Then we have  $V = \frac{Q}{\frac{\pi}{4} \cdot D^2}$   $V = 4.27 \frac{\text{m}}{\text{s}}$

Then  $\text{Re} = \frac{V \cdot D}{\nu}$   $\text{Re} = 2.39 \times 10^5$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$   $f = 0.0260$

Using Eq 4 to find H  $H_{\text{iterate}} = \frac{V^2}{2 \cdot g} \cdot \left( f \cdot \frac{2 \cdot L}{D} + K_{\text{ent}} + 1 \right)$   $H_{\text{iterate}} = 10.02 \text{ m}$  But  $H = 10 \text{ m}$

Hence the diameter is too large A head of  $H_{\text{iterate}} = 10.02 \text{ m}$  would be needed. We can make D smaller

Try  $D = 0.05602 \cdot \text{m}$  Then we have  $V = \frac{Q}{\frac{\pi}{4} \cdot D^2}$   $V = 4.27 \frac{\text{m}}{\text{s}}$

Then  $\text{Re} = \frac{V \cdot D}{\nu}$   $\text{Re} = 2.39 \times 10^5$

and  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$   $f = 0.0260$

Using Eq 4 to find H  $H_{\text{iterate}} = \frac{V^2}{2 \cdot g} \cdot \left( f \cdot \frac{2 \cdot L}{D} + K_{\text{ent}} + 1 \right)$   $H_{\text{iterate}} = 10 \text{ m}$  But  $H = 10 \text{ m}$

Hence we have  $D = 0.05602 \text{ m}$   $D = 56.02 \cdot \text{mm}$   $V = 4.27 \frac{\text{m}}{\text{s}}$

Check  $Q = 0.0105 \frac{\text{m}^3}{\text{s}}$   $\frac{\pi}{4} \cdot D^2 \cdot V = 0.0105 \frac{\text{m}^3}{\text{s}}$

## Problem 8.162

[Difficulty: 3]

**8.162** A hydraulic press is powered by a remote high-pressure pump. The gage pressure at the pump outlet is 3000 psi, whereas the pressure required for the press is 2750 psi (gage), at a flow rate of 0.02 ft<sup>3</sup>/s. The press and pump are connected by 165 ft of smooth, drawn steel tubing. The fluid is SAE 10W oil at 100°F. Determine the minimum tubing diameter that may be used.

**Given:** Hydraulic press system

**Find:** Minimum required diameter of tubing

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) Ignore minor losses

The flow rate is low and it's oil, so try assuming laminar flow. Then, from Eq. 8.13c

$$\Delta p = \frac{128 \mu \cdot Q \cdot L}{\pi \cdot D^4} \quad \text{or} \quad D = \left( \frac{128 \mu \cdot Q \cdot L}{\pi \cdot \Delta p} \right)^{\frac{1}{4}}$$

For SAE 10W oil at 100°F (Fig. A.2, 38°C) 
$$\mu = 3.5 \times 10^{-2} \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times \frac{0.0209 \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}}{1 \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}} \quad \mu = 7.32 \times 10^{-4} \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$$

Hence 
$$D = \left[ \frac{128}{\pi} \times 7.32 \times 10^{-4} \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2} \times 0.02 \frac{\text{ft}^3}{\text{s}} \times 165 \cdot \text{ft} \times \frac{\text{in}^2}{(3000 - 2750) \cdot \text{lbf}} \times \left( \frac{1 \cdot \text{ft}}{12 \cdot \text{in}} \right)^2 \right]^{\frac{1}{4}} \quad D = 0.0407 \cdot \text{ft} \quad D = 0.488 \text{ in}$$

Check Re to assure flow is laminar 
$$V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = \frac{4}{\pi} \times 0.02 \frac{\text{ft}^3}{\text{s}} \times \left( \frac{12}{0.488 \text{ ft}} \cdot \frac{1}{12} \right)^2 \quad V = 15.4 \frac{\text{ft}}{\text{s}}$$

From Table A.2  $SG_{\text{oil}} = 0.92$  so 
$$Re = \frac{SG_{\text{oil}} \rho_{\text{H}_2\text{O}} \cdot V \cdot D}{\mu}$$


$$Re = 0.92 \times 1.94 \frac{\text{slug}}{\text{ft}^3} \times 15.4 \frac{\text{ft}}{\text{s}} \times \frac{0.488}{12} \cdot \text{ft} \times \frac{\text{ft}^2}{7.32 \times 10^{-4} \text{lbf} \cdot \text{s}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad Re = 1527$$

Hence the flow is laminar,  $Re < 2300$ . The minimum diameter is 0.488 in, so 0.5 in ID tube should be chosen

## Problem 8.163

[Difficulty: 4]

**8.163** A pump is located 4.5 m to one side of, and 3.5 m above a reservoir. The pump is designed for a flow rate of 6 L/s. For satisfactory operation, the static pressure at the pump inlet must not be lower than  $-6$  m of water gage. Determine the smallest standard commercial steel pipe that will give the required performance.



**Given:** Flow out of reservoir by pump

**Find:** Smallest pipe needed

**Solution:**

$$\text{Basic equations} \quad \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} \quad h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K_{ent} \cdot \frac{V_2^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V_2^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $V_1 \ll V_2$

Hence for flow between the free surface (Point 1) and the pump inlet (2) the energy equation becomes

$$-\frac{p_2}{\rho} - g \cdot z_2 - \frac{V_2^2}{2} = -\frac{p_2}{\rho} - g \cdot z_2 - \frac{V_2^2}{2} = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} + K_{ent} \cdot \frac{V_2^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V_2^2}{2} \quad \text{and} \quad p = \rho \cdot g \cdot h$$

$$\text{Solving for } h_2 = p_2/\rho g \quad h_2 = -z_2 - \frac{V_2^2}{2 \cdot g} \cdot \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K_{ent} \right] \quad (1)$$

From Table 8.2  $K_{ent} = 0.78$  for reentrant, and from Table 8.4 two standard elbows lead to  $\frac{L_e}{D} = 2 \times 30 = 60$

We also have  $e = 0.046$ -mm (Table 8.1)  $\nu = 1.51 \times 10^{-6} \frac{\text{m}^2}{\text{s}}$  (Table A.8)

and we are given  $Q = 6 \cdot \frac{\text{L}}{\text{s}} \quad Q = 6 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad z_2 = 3.5 \cdot \text{m} \quad L = (3.5 + 4.5) \cdot \text{m} \quad L = 8 \text{ m} \quad h_2 = -6 \cdot \text{m}$

Equation 1 is tricky because  $D$  is unknown, so  $V$  is unknown (even though  $Q$  is known),  $L/D$  and  $L_e/D$  are unknown, and  $Re$  and hence  $f$  are unknown! We COULD set up *Excel* to solve Eq 1, the Reynolds number, and  $f$ , simultaneously by varying  $D$ , but here we try guesses:

$$D = 2.5\text{-cm} \quad V = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = 12.2 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.02 \times 10^5$$

$$\text{Given} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7 \cdot D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0238$$

$$h_2 = -z_2 - \frac{V_2^2}{2 \cdot g} \cdot \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K_{ent} \right] \quad h_2 = -78.45 \text{ m} \quad \text{but we need } -6 \text{ m!}$$

$$D = 5 \cdot \text{cm} \quad V = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = 3.06 \frac{\text{m}}{\text{s}} \quad \text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 1.01 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0219$

$$h_2 = -z_2 - \frac{V^2}{2 \cdot g} \cdot \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K_{\text{ent}} \right] \quad h_2 = -6.16 \text{ m} \quad \text{but we need -6 m!}$$

$$D = 5.1 \cdot \text{cm} \quad V = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = 2.94 \frac{\text{m}}{\text{s}} \quad \text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 9.92 \times 10^4$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0219$

$$h_2 = -z_2 - \frac{V^2}{2 \cdot g} \cdot \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K_{\text{ent}} \right] \quad h_2 = -5.93 \text{ m}$$

To within 1%, we can use 5-5.1 cm tubing; this corresponds to standard 2 in pipe.

## Problem 8.164

[Difficulty: 4]

**8.164** Determine the minimum size smooth rectangular duct with an aspect ratio of 3 that will pass  $1 \text{ m}^3/\text{s}$  of  $10^\circ\text{C}$  air with a head loss of 25 mm of water per 100 m of duct.

**Given:** Flow of air in rectangular duct

**Find:** Minimum required size

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_l = f \cdot \frac{L}{D_h} \cdot \frac{V^2}{2} \quad D_h = \frac{4 \cdot A}{P_w}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) Ignore minor losses

Available data 
$$Q = 1 \cdot \frac{\text{m}^3}{\text{s}} \quad L = 100 \cdot \text{m} \quad \Delta h = 25 \cdot \text{mm} \quad \text{ar} = 3 \quad e = 0 \cdot \text{m}$$

$$\rho_{\text{H}_2\text{O}} = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad \rho = 1.25 \cdot \frac{\text{kg}}{\text{m}^3} \quad \nu = 1.41 \cdot 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad (\text{Table A.10})$$

Hence for flow between the inlet (Point 1) and the exit (2) the energy equation becomes

$$\frac{p_1}{\rho} - \frac{p_2}{\rho} = \frac{\Delta p}{\rho} = f \cdot \frac{L}{D_h} \cdot \frac{V^2}{2}$$

and 
$$\Delta p = \rho_{\text{H}_2\text{O}} \cdot g \cdot \Delta h \quad \Delta p = 245 \text{ Pa}$$

For a rectangular duct 
$$D_h = \frac{4 \cdot b \cdot h}{2 \cdot (b + h)} = \frac{2 \cdot h^2 \cdot \text{ar}}{h \cdot (1 + \text{ar})} = \frac{2 \cdot h \cdot \text{ar}}{1 + \text{ar}} \quad \text{and also} \quad A = b \cdot h = h^2 \cdot \frac{b}{h} = h^2 \cdot \text{ar}$$

Hence 
$$\Delta p = \rho \cdot f \cdot L \cdot \frac{V^2}{2} \cdot \frac{(1 + \text{ar})}{2 \cdot h \cdot \text{ar}} = \rho \cdot f \cdot L \cdot \frac{Q^2}{2 \cdot A^2} \cdot \frac{(1 + \text{ar})}{2 \cdot h \cdot \text{ar}} = \frac{\rho \cdot f \cdot L \cdot Q^2}{4} \cdot \frac{(1 + \text{ar})}{\text{ar}^3} \cdot \frac{1}{h^5}$$

Solving for h 
$$h = \left[ \frac{\rho \cdot f \cdot L \cdot Q^2}{4 \cdot \Delta p} \cdot \frac{(1 + \text{ar})}{\text{ar}^3} \right]^{\frac{1}{5}} \quad (1)$$

Equation 1 is tricky because h is unknown, so  $D_h$  is unknown, hence V is unknown (even though Q is known), and Re and hence f are unknown! We COULD set up *Excel* to solve Eq 1, the Reynolds number, and f, simultaneously by varying h, but here we try guesses:

$$f = 0.01 \quad h = \left[ \frac{\rho \cdot f \cdot L \cdot Q^2}{4 \cdot \Delta p} \cdot \frac{(1 + \text{ar})}{\text{ar}^3} \right]^{\frac{1}{5}} \quad h = 0.180 \text{ m} \quad V = \frac{Q}{h^2 \cdot \text{ar}} \quad V = 10.3 \frac{\text{m}}{\text{s}}$$

$$D_h = \frac{2 \cdot h \cdot ar}{1 + ar} \quad D_h = 0.270 \text{ m}$$

$$Re = \frac{V \cdot D_h}{\nu} \quad Re = 1.97 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D_h}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$

$$f = 0.0157$$

$$h = \left[ \frac{\rho \cdot f \cdot L \cdot Q^2}{4 \cdot \Delta p} \cdot \frac{(1 + ar)}{ar^3} \right]^{\frac{1}{5}}$$

$$h = 0.197 \text{ m}$$

$$V = \frac{Q}{h^2 \cdot ar}$$

$$V = 8.59 \frac{\text{m}}{\text{s}}$$

$$D_h = \frac{2 \cdot h \cdot ar}{1 + ar} \quad D_h = 0.295 \text{ m}$$

$$Re = \frac{V \cdot D_h}{\nu} \quad Re = 1.8 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D_h}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$

$$f = 0.0160$$

$$h = \left[ \frac{\rho \cdot f \cdot L \cdot Q^2}{4 \cdot \Delta p} \cdot \frac{(1 + ar)}{ar^3} \right]^{\frac{1}{5}}$$

$$h = 0.198 \text{ m}$$

$$V = \frac{Q}{h^2 \cdot ar}$$

$$V = 8.53 \frac{\text{m}}{\text{s}}$$

$$D_h = \frac{2 \cdot h \cdot ar}{1 + ar} \quad D_h = 0.297 \text{ m}$$

$$Re = \frac{V \cdot D_h}{\nu} \quad Re = 1.79 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D_h}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$

$$f = 0.0160$$

Hence

$$h = 0.198 \text{ m}$$

$$h = 198 \text{ mm}$$

$$b = 2 \cdot h$$

$$b = 395 \cdot \text{mm}$$

$$V = \frac{Q}{h^2 \cdot ar}$$

$$V = 8.53 \frac{\text{m}}{\text{s}}$$

$$D_h = \frac{2 \cdot h \cdot ar}{1 + ar}$$

$$D_h = 0.297 \text{ m}$$

$$Re = \frac{V \cdot D_h}{\nu}$$

$$Re = 1.79 \times 10^5$$

In this process h and f have converged to a solution. The minimum dimensions are 198 mm by 395 mm

## Problem 8.165

[Difficulty: 4]

**8.165** A new industrial plant requires a water flow rate of  $5.7 \text{ m}^3/\text{min}$ . The gage pressure in the water main, located in the street 50 m from the plant, is 800 kPa. The supply line will require installation of 4 elbows in a total length of 65 m. The gage pressure required in the plant is 500 kPa. What size galvanized iron line should be installed?

Solution: Apply the energy equation for steady, incompressible flow that is uniform at each section ( $\alpha \approx 1$ ).

$$\text{Basic equation: } \frac{p_1}{\rho} + \frac{\overset{(2)}{V_1^2}}{2} + g z_1^{\overset{(3)}} = \frac{p_2}{\rho} + \frac{\overset{(2)}{V_2^2}}{2} + g z_2^{\overset{(3)}} + f \frac{L}{D} \frac{\bar{V}^2}{2} + h_{em}$$

Assumptions: (1)  $p_1 - p_2 \approx 300 \text{ kPa} = \Delta p$

(2) Fully developed flow in constant-area pipe,  $\bar{V}_1 = \bar{V}_2 = \bar{V}$

(3)  $z_1 = z_2$

(4)  $h_{em} = 4 \left(\frac{L_e}{D}\right)_{\text{elbow}} \frac{\bar{V}^2}{2} = 120 \frac{\bar{V}^2}{2}$  ( $L_e/D = 30$ , from Table 8.5)

Then

$$\frac{\Delta p}{\rho} = f \left(\frac{L}{D} + 120\right) \frac{\bar{V}^2}{2} \quad \text{or} \quad \Delta p = f f \left(\frac{L}{D} + 120\right) \frac{\bar{V}^2}{2}$$

Since  $D$  is unknown, iteration is required. The calculating equations are:

$$\bar{V} = \frac{Q}{A} = \frac{4Q}{\pi D^2} = \frac{4}{\pi} \times \frac{5.7 \text{ m}^3}{\text{min}} \times \frac{1}{\text{D}^2 \text{ m}^2} \times \frac{\text{min}}{60 \text{ s}} = \frac{0.121}{\text{D}^2} \text{ (m/s)}$$

$$Re = \frac{\bar{V} D}{\nu} = \frac{4Q}{\pi \nu D} = \frac{4}{\pi} \times \frac{5.7 \text{ m}^3}{\text{min}} \times \frac{\text{s}}{1.14 \times 10^{-6} \text{ m}^2} \times \frac{1}{\text{D m}} \times \frac{\text{min}}{60 \text{ s}} = \frac{1.06 \times 10^5}{D} \quad (T = 15^\circ\text{C})$$

$e = 0.15 \text{ mm}$  (Table 8.1),  $f$  from Eq. 8.37\*,  $L = 65 \text{ m}$ .  $D$  from Table 8.5.

$D$ (nom.)	$D$ (m)	$\bar{V}$ (m/s)	$Re$ (-)	$e/D$ (-)	$f$ (-)	$L/D$ (-)	$\Delta p$ (kPa)
3	0.0779	19.9	$1.36 \times 10^6$	0.0019	0.024	834	4530
5	0.128	7.39	$8.29 \times 10^5$	0.0012	0.021	508	360
6	0.154	5.10	$6.89 \times 10^5$	0.001	0.020	422	141

Pipe friction calculations are accurate only within about  $\pm 10$  percent. Line resistance (and consequently  $\Delta p$ ) will increase with age.

Recommend installation of 6 in. (nominal) line. D

\* Values of  $f$  obtained using Excel's Solver (or Goal Seek)

## Problem 8.166

[Difficulty: 4]

**8.166** Air at 40°F flows in a horizontal square cross-section duct made from commercial steel. The duct is 1000 ft long. What size (length of a side) duct is required to convey 1500 cfm of air with a pressure drop of 0.75 in. H<sub>2</sub>O?

**Given:** Flow of air in square duct

**Find:** Minimum required size

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_1 h_1 = f \cdot \frac{L}{D_h} \cdot \frac{V^2}{2} \quad D_h = \frac{4 \cdot A}{P_w}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) Ignore minor losses

Available data  $Q = 1500 \cdot \text{cfm}$        $L = 1000 \cdot \text{ft}$        $e = 0.00015 \cdot \text{ft}$       (Table 8.1)       $\Delta h = 0.75 \cdot \text{in}$

$$\rho_{\text{H}_2\text{O}} = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \nu = 1.47 \cdot 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \quad \rho = 0.00247 \cdot \frac{\text{slug}}{\text{ft}^3} \quad (\text{Table A.9})$$

Hence for flow between the inlet (Point 1) and the exit (2) the energy equation becomes

$$\frac{p_1}{\rho} - \frac{p_2}{\rho} = \frac{\Delta p}{\rho} = f \cdot \frac{L}{D_h} \cdot \frac{V^2}{2} \quad \text{and} \quad \Delta p = \rho_{\text{H}_2\text{O}} \cdot g \cdot \Delta h \quad \Delta p = 3.90 \frac{\text{lb}_f}{\text{ft}^2} \quad \Delta p = 0.0271 \cdot \text{psi}$$

For a square duct  $D_h = \frac{4 \cdot h \cdot h}{2 \cdot (h + h)} = h$       and also  $A = h \cdot h = h^2$

Hence 
$$\Delta p = \rho \cdot f \cdot L \cdot \frac{V^2}{2 \cdot h} = \rho \cdot f \cdot L \cdot \frac{Q^2}{2 \cdot h \cdot A^2} = \frac{\rho \cdot f \cdot L \cdot Q^2}{2 \cdot h^5}$$

Solving for h 
$$h = \left( \frac{\rho \cdot f \cdot L \cdot Q^2}{2 \cdot \Delta p} \right)^{\frac{1}{5}} \quad (1)$$

Equation 1 is tricky because h is unknown, so  $D_h$  is unknown, hence V is unknown (even though Q is known), and Re and hence f are unknown! We COULD set up *Excel* to solve Eq 1, the Reynolds number, and f, simultaneously by varying h, but here we try guesses:

$$f = 0.01 \quad h = \left( \frac{\rho \cdot f \cdot L \cdot Q^2}{2 \cdot \Delta p} \right)^{\frac{1}{5}} \quad h = 1.15 \cdot \text{ft} \quad V = \frac{Q}{h^2} \quad V = 19.0 \cdot \frac{\text{ft}}{\text{s}}$$

$$D_h = h \quad D_h = 1.15 \cdot \text{ft} \quad \text{Re} = \frac{V \cdot D_h}{\nu} \quad \text{Re} = 1.48 \times 10^5$$

$$\text{Given} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D_h}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0174$$

$$h = \left( \frac{\rho \cdot f \cdot L \cdot Q^2}{2 \cdot \Delta p} \right)^{\frac{1}{5}} \quad h = 1.28 \cdot \text{ft} \quad V = \frac{Q}{h^2} \quad V = 15.2 \cdot \frac{\text{ft}}{\text{s}}$$

$$D_h = h \quad D_h = 1.28 \cdot \text{ft} \quad \text{Re} = \frac{V \cdot D_h}{\nu} \quad \text{Re} = 1.33 \times 10^5$$

$$\text{Given} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D_h}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0177$$

$$h = \left( \frac{\rho \cdot f \cdot L \cdot Q^2}{2 \cdot \Delta p} \right)^{\frac{1}{5}} \quad h = 1.28 \cdot \text{ft} \quad V = \frac{Q}{h^2} \quad V = 15.1 \cdot \frac{\text{ft}}{\text{s}}$$

$$D_h = h \quad D_h = 1.28 \cdot \text{ft} \quad \text{Re} = \frac{V \cdot D_h}{\nu} \quad \text{Re} = 1.32 \times 10^5$$


$$\text{Given} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D_h}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0177$$

$$\text{Hence} \quad h = 1.28 \cdot \text{ft} \quad D_h = h \quad D_h = 1.28 \cdot \text{ft} \quad V = \frac{Q}{h^2} \quad V = 15.1 \cdot \frac{\text{ft}}{\text{s}}$$

$$\text{Re} = \frac{V \cdot D_h}{\nu} \quad \text{Re} = 1.32 \times 10^5$$

In this process h and f have converged to a solution. The minimum dimensions are 1.28 ft square (15.4 in square)






### Problem 8.169

[Difficulty: 3] Part 1/2

**8.169** A large reservoir supplies water for a community. A portion of the water supply system is shown. Water is pumped from the reservoir to a large storage tank before being sent on to the water treatment facility. The system is designed to provide 1310 L/s of water at 20°C. From B to C the system consists of a square-edged entrance, 760 m of pipe, three gate valves, four 45° elbows, and two 90° elbows. Gage pressure at C is 197 kPa. The system between F and G contains 760 m of pipe, two gate valves, and four 90° elbows. All pipe is 508 mm diameter, cast iron. Calculate the average velocity of water in the pipe, the gage pressure at section F, the power input to the pump (its efficiency is 80 percent), and the wall shear stress in section FG.



Solution:

$$\text{Since } Q = AV, \bar{V} = \frac{Q}{A} = \frac{1310}{\frac{\pi}{4}(0.508)^2} = 6.46 \text{ m/s}$$

To determine the pressure at point F, apply the energy equation for steady, incompressible flow between A and G.

$$\text{Basic equation: } \left( \frac{p_A}{\rho} + \alpha \frac{\bar{V}_A^2}{2} + gz_A \right) - \left( \frac{p_F}{\rho} + \alpha \frac{\bar{V}_F^2}{2} + gz_F \right) = h_{\text{net}} \quad (8.22)$$

$$h_{\text{net}} = h_e + h_{\text{en}}, \quad h_e = f \frac{L}{D} \frac{\bar{V}^2}{2}, \quad h_{\text{en}} = \sum K \frac{\bar{V}^2}{2}$$

Assume: (1)  $\bar{V}_H = 0$  (large storage tank) (2)  $p_H = p_{\text{atm}}$   
(3)  $\alpha_F = 1.0$

$$\text{Then } \frac{p_F}{\rho} = h_{\text{net}} + g(z_H - z_F) - \frac{\bar{V}_F^2}{2}$$

$$\frac{p_F}{\rho} = h_{\text{net}} + g(z_H - z_F) - \frac{\bar{V}_F^2}{2}$$

$$\frac{p_F}{\rho} = f \frac{L}{D} \frac{\bar{V}^2}{2} + 2K_{\text{GV}} \frac{\bar{V}^2}{2} + 4K_{\text{E}45} \frac{\bar{V}^2}{2} + K_{\text{E}90} \frac{\bar{V}^2}{2} + g(z_H - z_F) - \frac{\bar{V}_F^2}{2} \quad (1)$$

From Table 8.4  $(K_{\text{GV}})_{\text{sq}} = 8$ ,  $(K_{\text{E}90})_{\text{cast}} = 30$ ; also  $K_{\text{E}45} = 1$

$$Re = \frac{\bar{V} D}{\nu} = \frac{6.46 \text{ m/s} \times 0.508 \text{ m}}{1.00 \times 10^{-6} \text{ m}^2/\text{s}} = 3.28 \times 10^6 \quad (\nu \text{ from Table A.8})$$

From Table 8.1,  $e = 0.26 \text{ mm}$   $\therefore e/D = 0.00051$

From Eq. 8.37,  $f = 0.017$  (using Excel's Solver [or Goal Seek])

From Eq. (1)

$$\frac{p_F}{\rho} = f \frac{L}{D} \left[ \frac{\bar{V}^2}{2} + 2 \left( \frac{\bar{V}^2}{2} \right) + 4 \left( \frac{\bar{V}^2}{2} \right) \right] + g(z_H - z_F)$$

Problem 8.169

[Difficulty: 3] Part 2/2

$$\frac{p}{\rho} = f \frac{V^2}{2} \left[ \frac{L}{D} + 2(8) + 4(30) \right] + g(z_H - z_F) = f \frac{V^2}{2} (1630) + g(z_H - z_F)$$

$$p_F = \rho \left[ 1630 f \frac{V^2}{2} + g(z_H - z_F) \right]$$

$$= 999 \frac{\text{kg}}{\text{m}^3} \left[ \frac{1630}{2} \times 0.017 \times \frac{(6.46)^2}{\text{s}^2} + 9.81 \frac{\text{m}}{\text{s}^2} (104 - 91) \text{m} \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$p_F = 705 \text{ kPa (gage)} \quad \leftarrow p_F$$

For fully developed flow in a pipe  $r = \frac{R}{2} \frac{\partial p}{\partial x}$  (8.15)

At the pipe centerline,  $r = 0$   $\leftarrow r_c$

To determine the power input to the fluid apply the energy equation across the pump. Assuming 100% efficiency

$$\dot{w}_{\text{pump}} = \left( \frac{p}{\rho} + \frac{V^2}{2} + gz \right)_{\text{discharge}} - \left( \frac{p}{\rho} + \frac{V^2}{2} + gz \right)_{\text{suction}} \quad (8.47)$$

$$\dot{w}_{\text{pump}} = \left( \frac{p_F}{\rho} - \frac{p_c}{\rho} \right) \rho A V = (p_F - p_c) Q$$

$$\dot{w}_{\text{pump}} = (705 - 197) \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{1310 \text{ L}}{\text{s}} \times 10^{-3} \text{ m}^3 = 6.65 \times 10^5 \frac{\text{N} \cdot \text{m}}{\text{s}}$$

The actual pump input,  $\dot{w}_{\text{pump,act}} = \dot{w}_{\text{pump,ideal}} / \eta$

$$\dot{w}_{\text{pump,act}} = 8.32 \times 10^5 \text{ N} \cdot \text{m/s} = 832 \text{ kW} \quad \leftarrow \dot{w}_{\text{act,ual}}$$

From Eq. 8.15  $\tau_w = \frac{R}{2} \frac{\partial p}{\partial x}$

Along the pipe from F to G

$$\frac{\partial p}{\partial x} = f \frac{V^2}{2R}$$

$$\therefore \frac{\partial p}{\partial x} = \frac{\Delta p}{L} = \rho f \frac{V^2}{2R} = 999 \frac{\text{kg}}{\text{m}^3} \times \frac{0.017}{0.508 \text{ m}} \times \frac{1}{2} \times \frac{(6.46)^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$\frac{\partial p}{\partial x} = 698 \text{ N/m}^2/\text{m}$$

$$\therefore \tau_w = \frac{R}{2} \frac{\partial p}{\partial x} = \frac{0.254 \text{ m}}{2} \times 698 \frac{\text{N}}{\text{m}^2} = 88.6 \text{ N/m}^2 \quad \leftarrow \tau_w$$

8.170 An air-pipe friction experiment consists of a smooth brass tube with 63.5 mm inside diameter; the distance between pressure taps is 1.52 m. The pressure drop is indicated by a manometer filled with Meriam red oil. The centerline velocity  $U$  is measured with a pitot cylinder. At one flow condition,  $U = 23.1$  m/s and the pressure drop is

12.3 mm of oil. For this condition, evaluate the Reynolds number based on average flow velocity. Calculate the friction factor and compare with the value obtained from Eq. 8.37 (use  $n = 7$  in the power-law velocity profile).

Solution:

Apply the energy equation for steady, incompressible flow along the pipe

$$\text{Basic equation: } \left( \frac{P_1}{\rho} + \alpha_1 \frac{U_1^2}{2} + g z_1 \right) - \left( \frac{P_2}{\rho} + \alpha_2 \frac{U_2^2}{2} + g z_2 \right) = h_{L,T} \quad (8.29)$$

$$h_L = f \frac{L}{D} \frac{U^2}{2} = \frac{2n^2}{(n+1)(2n+1)} \quad (8.24)$$

Assumptions: (1) power law profile,  $n=7$

(2)  $\alpha_1 = \alpha_2$ ,  $z_1 = z_2$

(3) air at  $T = 15^\circ\text{C}$   $\nu = 1.46 \times 10^{-5} \text{ m}^2/\text{s}$  (Table A.10)

From Eq. 8.24 with  $n=7$

$$\frac{U_{avg}}{U} = \frac{2(7)^2}{(8)(15)} = 0.817$$

$$Re_D = \frac{U_{avg} D}{\nu} = 0.0635 \text{ m} \times 0.817 \times 23.1 \frac{\text{m}}{\text{s}} \times \frac{1}{1.45 \times 10^{-5} \frac{\text{m}^2}{\text{s}}} = 8.26 \times 10^4 \quad Re_D$$

From Eq. 8.29  $\Delta P / \rho = f \frac{L}{D} \frac{U^2}{2}$

and

$$f = \frac{\Delta P}{\rho \frac{L}{D} \frac{U^2}{2}} = \frac{\rho_{oil} g \Delta h}{\rho_{air} \frac{L}{D} \frac{U^2}{2}} = \frac{2 \rho_{oil} SG_{oil} g \Delta h}{\rho_{air} \frac{L}{D} U^2} \quad \left\{ \begin{array}{l} SG = 0.827 \\ \text{Table A.1} \end{array} \right.$$

$$f = 2 \times \frac{10^3}{1.23} \times 0.827 \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.0123 \text{ m} \times \frac{0.0635 \text{ m}}{1.52 \text{ m}} \times (0.817 \times 23.1 \frac{\text{m}}{\text{s}})^2 \frac{\text{s}^2}{\text{m}^2}$$

$$f = 0.0190 \quad f$$

From Eq. 8.37 at  $Re = 8.26 \times 10^4$  for smooth tube,  $f = 0.0187$

The value of  $f$  is obtained using Enal's Solver (or Goal Seek)

13 282  
14 283  
15 284  
16 285  
17 286  
18 287  
19 288  
20 289  
21 290  
22 291  
23 292  
24 293  
25 294  
26 295  
27 296  
28 297  
29 298  
30 299  
31 300  
32 301  
33 302  
34 303  
35 304  
36 305  
37 306  
38 307  
39 308  
40 309  
41 310  
42 311  
43 312  
44 313  
45 314  
46 315  
47 316  
48 317  
49 318  
50 319  
51 320  
52 321  
53 322  
54 323  
55 324  
56 325  
57 326  
58 327  
59 328  
60 329  
61 330  
62 331  
63 332  
64 333  
65 334  
66 335  
67 336  
68 337  
69 338  
70 339  
71 340  
72 341  
73 342  
74 343  
75 344  
76 345  
77 346  
78 347  
79 348  
80 349  
81 350  
82 351  
83 352  
84 353  
85 354  
86 355  
87 356  
88 357  
89 358  
90 359  
91 360  
92 361  
93 362  
94 363  
95 364  
96 365  
97 366  
98 367  
99 368  
100 369  
101 370  
102 371  
103 372  
104 373  
105 374  
106 375  
107 376  
108 377  
109 378  
110 379  
111 380  
112 381  
113 382  
114 383  
115 384  
116 385  
117 386  
118 387  
119 388  
120 389  
121 390  
122 391  
123 392  
124 393  
125 394  
126 395  
127 396  
128 397  
129 398  
130 399  
131 400  
132 401  
133 402  
134 403  
135 404  
136 405  
137 406  
138 407  
139 408  
140 409  
141 410  
142 411  
143 412  
144 413  
145 414  
146 415  
147 416  
148 417  
149 418  
150 419  
151 420  
152 421  
153 422  
154 423  
155 424  
156 425  
157 426  
158 427  
159 428  
160 429  
161 430  
162 431  
163 432  
164 433  
165 434  
166 435  
167 436  
168 437  
169 438  
170 439  
171 440  
172 441  
173 442  
174 443  
175 444  
176 445  
177 446  
178 447  
179 448  
180 449  
181 450  
182 451  
183 452  
184 453  
185 454  
186 455  
187 456  
188 457  
189 458  
190 459  
191 460  
192 461  
193 462  
194 463  
195 464  
196 465  
197 466  
198 467  
199 468  
200 469  
201 470  
202 471  
203 472  
204 473  
205 474  
206 475  
207 476  
208 477  
209 478  
210 479  
211 480  
212 481  
213 482  
214 483  
215 484  
216 485  
217 486  
218 487  
219 488  
220 489  
221 490  
222 491  
223 492  
224 493  
225 494  
226 495  
227 496  
228 497  
229 498  
230 499  
231 500  
232 501  
233 502  
234 503  
235 504  
236 505  
237 506  
238 507  
239 508  
240 509  
241 510  
242 511  
243 512  
244 513  
245 514  
246 515  
247 516  
248 517  
249 518  
250 519  
251 520  
252 521  
253 522  
254 523  
255 524  
256 525  
257 526  
258 527  
259 528  
260 529  
261 530  
262 531  
263 532  
264 533  
265 534  
266 535  
267 536  
268 537  
269 538  
270 539  
271 540  
272 541  
273 542  
274 543  
275 544  
276 545  
277 546  
278 547  
279 548  
280 549  
281 550  
282 551  
283 552  
284 553  
285 554  
286 555  
287 556  
288 557  
289 558  
290 559  
291 560  
292 561  
293 562  
294 563  
295 564  
296 565  
297 566  
298 567  
299 568  
300 569  
301 570  
302 571  
303 572  
304 573  
305 574  
306 575  
307 576  
308 577  
309 578  
310 579  
311 580  
312 581  
313 582  
314 583  
315 584  
316 585  
317 586  
318 587  
319 588  
320 589  
321 590  
322 591  
323 592  
324 593  
325 594  
326 595  
327 596  
328 597  
329 598  
330 599  
331 600  
332 601  
333 602  
334 603  
335 604  
336 605  
337 606  
338 607  
339 608  
340 609  
341 610  
342 611  
343 612  
344 613  
345 614  
346 615  
347 616  
348 617  
349 618  
350 619  
351 620  
352 621  
353 622  
354 623  
355 624  
356 625  
357 626  
358 627  
359 628  
360 629  
361 630  
362 631  
363 632  
364 633  
365 634  
366 635  
367 636  
368 637  
369 638  
370 639  
371 640  
372 641  
373 642  
374 643  
375 644  
376 645  
377 646  
378 647  
379 648  
380 649  
381 650  
382 651  
383 652  
384 653  
385 654  
386 655  
387 656  
388 657  
389 658  
390 659  
391 660  
392 661  
393 662  
394 663  
395 664  
396 665  
397 666  
398 667  
399 668  
400 669  
401 670  
402 671  
403 672  
404 673  
405 674  
406 675  
407 676  
408 677  
409 678  
410 679  
411 680  
412 681  
413 682  
414 683  
415 684  
416 685  
417 686  
418 687  
419 688  
420 689  
421 690  
422 691  
423 692  
424 693  
425 694  
426 695  
427 696  
428 697  
429 698  
430 699  
431 700  
432 701  
433 702  
434 703  
435 704  
436 705  
437 706  
438 707  
439 708  
440 709  
441 710  
442 711  
443 712  
444 713  
445 714  
446 715  
447 716  
448 717  
449 718  
450 719  
451 720  
452 721  
453 722  
454 723  
455 724  
456 725  
457 726  
458 727  
459 728  
460 729  
461 730  
462 731  
463 732  
464 733  
465 734  
466 735  
467 736  
468 737  
469 738  
470 739  
471 740  
472 741  
473 742  
474 743  
475 744  
476 745  
477 746  
478 747  
479 748  
480 749  
481 750  
482 751  
483 752  
484 753  
485 754  
486 755  
487 756  
488 757  
489 758  
490 759  
491 760  
492 761  
493 762  
494 763  
495 764  
496 765  
497 766  
498 767  
499 768  
500 769  
501 770  
502 771  
503 772  
504 773  
505 774  
506 775  
507 776  
508 777  
509 778  
510 779  
511 780  
512 781  
513 782  
514 783  
515 784  
516 785  
517 786  
518 787  
519 788  
520 789  
521 790  
522 791  
523 792  
524 793  
525 794  
526 795  
527 796  
528 797  
529 798  
530 799  
531 800  
532 801  
533 802  
534 803  
535 804  
536 805  
537 806  
538 807  
539 808  
540 809  
541 810  
542 811  
543 812  
544 813  
545 814  
546 815  
547 816  
548 817  
549 818  
550 819  
551 820  
552 821  
553 822  
554 823  
555 824  
556 825  
557 826  
558 827  
559 828  
560 829  
561 830  
562 831  
563 832  
564 833  
565 834  
566 835  
567 836  
568 837  
569 838  
570 839  
571 840  
572 841  
573 842  
574 843  
575 844  
576 845  
577 846  
578 847  
579 848  
580 849  
581 850  
582 851  
583 852  
584 853  
585 854  
586 855  
587 856  
588 857  
589 858  
590 859  
591 860  
592 861  
593 862  
594 863  
595 864  
596 865  
597 866  
598 867  
599 868  
600 869  
601 870  
602 871  
603 872  
604 873  
605 874  
606 875  
607 876  
608 877  
609 878  
610 879  
611 880  
612 881  
613 882  
614 883  
615 884  
616 885  
617 886  
618 887  
619 888  
620 889  
621 890  
622 891  
623 892  
624 893  
625 894  
626 895  
627 896  
628 897  
629 898  
630 899  
631 900  
632 901  
633 902  
634 903  
635 904  
636 905  
637 906  
638 907  
639 908  
640 909  
641 910  
642 911  
643 912  
644 913  
645 914  
646 915  
647 916  
648 917  
649 918  
650 919  
651 920  
652 921  
653 922  
654 923  
655 924  
656 925  
657 926  
658 927  
659 928  
660 929  
661 930  
662 931  
663 932  
664 933  
665 934  
666 935  
667 936  
668 937  
669 938  
670 939  
671 940  
672 941  
673 942  
674 943  
675 944  
676 945  
677 946  
678 947  
679 948  
680 949  
681 950  
682 951  
683 952  
684 953  
685 954  
686 955  
687 956  
688 957  
689 958  
690 959  
691 960  
692 961  
693 962  
694 963  
695 964  
696 965  
697 966  
698 967  
699 968  
700 969  
701 970  
702 971  
703 972  
704 973  
705 974  
706 975  
707 976  
708 977  
709 978  
710 979  
711 980  
712 981  
713 982  
714 983  
715 984  
716 985  
717 986  
718 987  
719 988  
720 989  
721 990  
722 991  
723 992  
724 993  
725 994  
726 995  
727 996  
728 997  
729 998  
730 999  
731 1000




### Problem 8.171

[Difficulty: 4]

**8.171** Oil has been flowing from a large tank on a hill to a tanker at the wharf. The compartment in the tanker is nearly full and an operator is in the process of stopping the flow. A valve on the wharf is closed at a rate such that 1 MPa is maintained in the line immediately upstream of the valve.

Assume:

Length of line from tank to valve	3 km
Inside diameter of line	200 mm
Elevation of oil surface in tank	60 m
Elevation of valve on wharf	6 m
Instantaneous flow rate	2.5 m <sup>3</sup> /min
Head loss in line (exclusive of valve being closed) at this rate of flow	23 m of oil
Specific gravity of oil	0.88



Calculate the initial instantaneous rate of change of volume flow rate.

Solution: For unsteady flow with friction, we modify the unsteady Bernoulli equation (Eq. 6.21) to include a head loss term.

Computing equation: 
$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + gz_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + gz_2 + \int_1^2 \frac{\partial V}{\partial t} ds + h_L$$

Assume: (1)  $V_1 = 0$   
(2)  $p_1 = p_{atm}$   
(3)  $p = \text{constant}$

Then 
$$\int_1^2 \frac{\partial V}{\partial t} ds = \frac{p_1 - p_2}{\rho} + g(z_1 - z_2) - h_L - \frac{V_2^2}{2}$$

If we neglect velocity in the tank except for small region near the inlet to the pipe, then

$$\int_1^2 \frac{\partial V}{\partial t} ds = \int_0^L \frac{\partial V}{\partial t} ds$$
 Since  $V_s = V_2$  everywhere, then  
$$\int_0^L \frac{\partial V}{\partial t} ds = L \frac{dV_2}{dt} \text{ and}$$

$$\frac{dV_2}{dt} = \frac{1}{L} \left[ \frac{p_1 - p_2}{\rho} + g(z_1 - z_2) - h_L - \frac{V_2^2}{2} \right], \quad V_2 = 0 = \frac{4Q}{\pi D^2}$$

Note  $h_L = h_L(V)$  and hence this result can only be used to obtain the initial instantaneous rate of change of flow velocity.

$$\left. \frac{dV_2}{dt} \right|_{\text{initial}} = \frac{1}{3 \times 10^3 \text{ m}} \left[ \frac{10^6 \text{ N}}{\text{m}^2} - 999 \frac{\text{N}}{\text{m}^3} \times 0.88 \left( \frac{9.81 \text{ m}}{\text{s}^2} \times 54 \text{ m} \right) - \frac{1}{2} \left( \frac{4}{\pi} \times \frac{2.5 \text{ m}^3}{\text{min}} \times \frac{1}{(0.2 \text{ m})^2} \times \frac{1 \text{ min}}{60 \text{ s}} \right)^2 \right]$$

$$\left. \frac{dV_2}{dt} \right|_{\text{initial}} = -0.278 \text{ m/s/s}$$

The instantaneous rate of change of volume flow rate is

$$dQ/dt = \frac{d}{dt}(AV) = A \frac{dV}{dt} = \frac{\pi D^2}{4} \frac{dV}{dt}$$

$$dQ/dt = \frac{\pi}{4} (0.2 \text{ m})^2 \times (-0.278 \text{ m/s/s}) \times \frac{60 \text{ s}}{\text{min}} = -0.524 \text{ m}^3/\text{min} \leftarrow \frac{dQ}{dt}$$





## Problem 8.173

[Difficulty: 2]

**8.173** A pump draws water at a steady flow rate of 25 lbm/s through a piping system. The pressure on the suction side of the pump is -2.5 psig. The pump outlet pressure is 50 psig. The inlet pipe diameter is 3 in.; the outlet pipe diameter is 2 in. The pump efficiency is 70 percent. Calculate the power required to drive the pump.

**Given:** Flow through water pump

**Find:** Power required

**Solution:**

Basic equations 
$$h_{\text{pump}} = \left( \frac{p_d}{\rho} + \frac{V_d^2}{2} + g \cdot z_d \right) - \left( \frac{p_s}{\rho} + \frac{V_s^2}{2} + g \cdot z_s \right) \quad V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

Hence for the inlet 
$$V_s = \frac{4}{\pi} \times 25 \cdot \frac{\text{lbm}}{\text{s}} \times \frac{1 \cdot \text{slug}}{32.2 \cdot \text{lbm}} \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \left( \frac{12}{3} \cdot \frac{1}{\text{ft}} \right)^2 \quad V_s = 8.15 \cdot \frac{\text{ft}}{\text{s}} \quad p_s = -2.5 \cdot \text{psi}$$

For the outlet 
$$V_d = \frac{4}{\pi} \times 25 \cdot \frac{\text{lbm}}{\text{s}} \times \frac{1 \cdot \text{slug}}{32.2 \cdot \text{lbm}} \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \left( \frac{12}{2} \cdot \frac{1}{\text{ft}} \right)^2 \quad V_d = 18.3 \cdot \frac{\text{ft}}{\text{s}} \quad p_d = 50 \cdot \text{psi}$$

Then 
$$h_{\text{pump}} = \frac{p_d - p_s}{\rho} + \frac{V_d^2 - V_s^2}{2} \quad \text{and} \quad W_{\text{pump}} = m_{\text{pump}} \cdot h_{\text{pump}}$$

$$W_{\text{pump}} = m_{\text{pump}} \cdot \left( \frac{p_d - p_s}{\rho} + \frac{V_d^2 - V_s^2}{2} \right)$$

Note that the software cannot render a dot, so the power is  $W_{\text{pump}}$  and mass flow rate is  $m_{\text{pump}}$ !

$$W_{\text{pump}} = 25 \cdot \frac{\text{lbm}}{\text{s}} \times \frac{1 \cdot \text{slug}}{32.2 \cdot \text{lbm}} \times \left[ (50 - -2.5) \cdot \frac{\text{lbf}}{\text{in}^2} \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} + \frac{1}{2} \times (18.3^2 - 8.15^2) \cdot \left( \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \right] \times \frac{1 \cdot \text{hp}}{550 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}}$$

$$W_{\text{pump}} = 5.69 \cdot \text{hp} \quad \text{For an efficiency of} \quad \eta = 70\% \quad W_{\text{required}} = \frac{W_{\text{pump}}}{\eta} \quad W_{\text{required}} = 8.13 \cdot \text{hp}$$

## Problem 8.174

[Difficulty: 1]

**8.174** The pressure rise across a water pump is 35 psi when the volume flow rate is 500 gpm. If the pump efficiency is 80 percent, determine the power input to the pump.

**Given:** Flow through water pump

**Find:** Power required

**Solution:**

Basic equations 
$$h_{\text{pump}} = \left( \frac{p_d}{\rho} + \frac{V_d^2}{2} + g \cdot z_d \right) - \left( \frac{p_s}{\rho} + \frac{V_s^2}{2} + g \cdot z_s \right)$$

Assumptions: 1) Steady flow 2) Incompressible flow 3) Uniform flow

In this case we assume  $D_s = D_d$  so  $V_s = V_d$

The available data is  $\Delta p = 35 \cdot \text{psi}$   $Q = 500 \cdot \text{gpm}$   $\eta = 80 \cdot \%$

Then 
$$h_{\text{pump}} = \frac{p_d - p_s}{\rho} = \frac{\Delta p}{\rho} \quad \text{and} \quad W_{\text{pump}} = m_{\text{pump}} \cdot h_{\text{pump}}$$

$$W_{\text{pump}} = m_{\text{pump}} \cdot \frac{\Delta p}{\rho} = \rho \cdot Q \cdot \frac{\Delta p}{\rho}$$

$$W_{\text{pump}} = Q \cdot \Delta p \quad W_{\text{pump}} = 5615 \frac{\text{ft} \cdot \text{lb}_f}{\text{s}} \quad W_{\text{pump}} = 10.2 \cdot \text{hp}$$

Note that the software cannot render a dot, so the power is  $W_{\text{pump}}$  and mass flow rate is  $m_{\text{pump}}$ !

For an efficiency of  $\eta = 80 \cdot \%$  
$$W_{\text{required}} = \frac{W_{\text{pump}}}{\eta} \quad W_{\text{required}} = 12.8 \cdot \text{hp}$$

## Problem 8.175

[Difficulty: 3]

**8.175** A 125-mm-diameter pipeline conveying water at 10°C contains 50 m of straight galvanized pipe, 5 fully open gate valves, 1 fully open angle valve, 7 standard 90° elbows, 1 square-edged entrance from a reservoir, and 1 free discharge. The entrance conditions are  $p_1 = 150$  kPa and  $z_1 = 15$  m, and exit conditions are  $p_2 = 0$  kPa and  $z_2 = 30$  m. A centrifugal pump is installed in the line to move the water. What pressure rise must the pump deliver so that the volume flow rate will be  $Q = 50$  L/s?

**Given:** Flow in pipeline with pump

**Find:** Pump pressure  $\Delta p$

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) + \frac{\Delta p_{\text{pump}}}{\rho} = h_{\text{IT}}$$

$$h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad h_{\text{lm}} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad h_{\text{lm}} = K \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Available data  $L = 50 \cdot \text{m}$        $D = 125 \cdot \text{mm}$        $Q = 50 \cdot \frac{1}{\text{s}}$        $e = 0.15 \cdot \text{mm}$

$p_1 = 150 \cdot \text{kPa}$        $p_2 = 0 \cdot \text{kPa}$        $z_1 = 15 \cdot \text{m}$        $z_2 = 30 \cdot \text{m}$

From Section 8.8  $K_{\text{ent}} = 0.5$        $L_{\text{elbow90}} = 30 \cdot D$        $L_{\text{elbow90}} = 3.75 \text{ m}$        $L_{\text{GV}} = 8 \cdot D$        $L_{\text{GV}} = 1 \text{ m}$

$L_{\text{AV}} = 150 \cdot D$        $L_{\text{AV}} = 18.75 \text{ m}$        $\rho = 1000 \frac{\text{kg}}{\text{m}^3}$        $\mu = 1.3 \cdot 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$       (Table A.8)

Hence  $V = \frac{Q}{\left( \frac{\pi \cdot D^2}{4} \right)}$        $V = 4.07 \frac{\text{m}}{\text{s}}$        $\text{Re} = \frac{\rho \cdot V \cdot D}{\mu}$        $\text{Re} = 3.918 \times 10^5$

and Given  $\frac{1}{\sqrt{f}} = -2 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right)$        $f = 0.0212$

The loss is then

$$h_{\text{IT}} = \frac{V^2}{2} \cdot \left( f \cdot \frac{L}{D} + 7 \cdot f \cdot \frac{L_{\text{elbow90}}}{D} + 5 \cdot f \cdot \frac{L_{\text{GV}}}{D} + f \cdot \frac{L_{\text{AV}}}{D} + K_{\text{ent}} \right) \quad h_{\text{IT}} = 145 \frac{\text{m}^2}{\text{s}^2}$$


The energy equation becomes  $\frac{p_1 - p_2}{\rho} + g \cdot (z_1 - z_2) - \frac{V^2}{2} + \frac{\Delta p_{\text{pump}}}{\rho} = h_{\text{IT}}$

$$\Delta p_{\text{pump}} = \rho \cdot h_{\text{IT}} + \rho \cdot g \cdot (z_2 - z_1) + \rho \cdot \frac{V^2}{2} + (p_2 - p_1) \quad \Delta p_{\text{pump}} = 150 \cdot \text{kPa}$$

### Problem 8.176

[Difficulty: 3]

**8.176** Cooling water is pumped from a reservoir to rock drills on a construction job using the pipe system shown. The flow rate must be 600 gpm and water must leave the spray nozzle at 120 ft/s. Calculate the minimum pressure needed at the pump outlet. Estimate the required power input if the pump efficiency is 70 percent.



Solution:

Computing equations:  $\left(\frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1\right) - \left(\frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2\right) + \Delta h_{\text{pump}} = h_L$  (8.48)

$h_{\text{tot}} = h_e + h_{\text{en}} , h_e = f \frac{L}{D} \frac{V^2}{2} , h_{\text{en}} = \frac{V^2}{2} (\sum K + \sum f \frac{L}{D})$

Assumptions: (1)  $V_1 = 0$  (2)  $\alpha_1 = \alpha_2 = 1$  (3)  $p_1 = p_2 = p_{\text{atm}}$

$\Delta h_{\text{pump}} = g z_2 + \frac{V^2}{2} + f \frac{L}{D} \frac{V^2}{2} + \frac{V^2}{2} \left[ K_{\text{ent}} + f \left(\frac{L}{D}\right)_{\text{eq}} + 2f \left(\frac{L}{D}\right)_{\text{std}} + 15 K_j \right] - h_L$

$V = \frac{Q}{A} = \frac{600 \text{ gal}}{2.44 \text{ gal}} = \frac{1}{60 \text{ sec}} \times \frac{1}{60 \text{ sec}} \times (0.333 \text{ ft})^2 = 15.3 \text{ ft/s}$

$Re = \frac{V D}{\nu} = \frac{1 \text{ ft} \times 15.3 \text{ ft/s}}{1.24 \times 10^{-5} \text{ ft}^2/\text{s}} = 4.11 \times 10^5$  {at  $T = 60^\circ\text{F}$ , Table A.1}

Table 8.1,  $e = 5 \times 10^{-6} \text{ ft}$  (drawn tubing)  $\therefore e/D = 1.5 \times 10^{-5}$

From Fig. 8.13,  $f = 0.0135$

From Table 8.1,  $K_{\text{ent}} = 0.78$

From Table 8.4,  $L_e/D|_{90^\circ} = 8$ ,  $L_e/D|_{45^\circ} = 30$ ,  $L_e/D|_{45^\circ} = 16$

Per from Eq. (1)

$\Delta h_{\text{pump}} = 32.2 \frac{\text{ft}}{\text{s}^2} \times 400 \text{ ft} + \frac{1}{2} (120 \frac{\text{ft}}{\text{s}})^2 + 0.0135 \times \frac{700}{0.333} \frac{1}{2} (15.3)^2 \frac{\text{ft}^2}{\text{s}^2}$   
 $+ \frac{1}{2} (15.3)^2 \frac{\text{ft}^2}{\text{s}^2} [0.78 + 0.0135(30) + 2 \times 0.0135(6) + 15(1)]$

$\Delta h_{\text{pump}} = 2.53 \times 10^4 \text{ ft}^2/\text{s}^2$

The theoretical power input to the pump is given by  $\dot{W}_{\text{pump}} = \dot{m} \Delta h_{\text{pump}}$

From the definition of efficiency,  $\eta = \frac{\dot{W}_{\text{theor}}}{\dot{W}_{\text{act}}}$ , then

$\dot{W}_{\text{act}} = \frac{\dot{m} \Delta h_{\text{pump}}}{\eta} = \frac{\rho \dot{V} \Delta h_{\text{pump}}}{\eta}$

$\dot{W}_{\text{act}} = \frac{1.94 \text{ slug}}{0.7 \text{ ft}^3} \times \frac{600 \text{ gal}}{2.44 \text{ gal}} \times \frac{1}{60 \text{ sec}} \times 2.53 \times 10^4 \frac{\text{ft}^2}{\text{s}^2} \times \frac{1 \text{ hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}} = 170 \text{ hp}$

The discharge pressure from the pump is obtained by applying Eq. 8.48 between sections ① and ③ neglecting losses in the inlet section, elevation change, and kinetic energy at ③

$p_3 - p_1 = \rho \Delta h_{\text{pump}} = 1.94 \frac{\text{slug}}{\text{ft}^3} \times 2.53 \times 10^4 \frac{\text{ft}^2}{\text{s}^2} \times \frac{1 \text{ lb} \cdot \text{s}^2}{\text{ft} \cdot \text{slug}} \times \frac{1 \text{ ft}^2}{144 \text{ in}^2} = 341 \text{ psi}$



## Problem 8.178

[Difficulty: 3]

**8.178** Air conditioning on a university campus is provided by chilled water (10°C) pumped through a main supply pipe. The pipe makes a loop 5 km in length. The pipe diameter is 0.75 m and the material is steel. The maximum design volume flow rate is 0.65 m<sup>3</sup>/s. The circulating pump is driven by an electric motor. The efficiencies of pump and motor are  $\eta_p = 85$  percent and  $\eta_m = 85$  percent, respectively. Electricity cost is 14¢/(kW·hr). Determine (a) the pressure drop, (b) the rate of energy addition to the water, and (c) the daily cost of electrical energy for pumping.

**Given:** Flow in air conditioning system

**Find:** Pressure drop; cost

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \qquad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Available data  $L = 5 \cdot \text{km}$      $D = 0.75 \cdot \text{m}$      $e = 0.046 \cdot \text{mm}$      $Q = 0.65 \cdot \frac{\text{m}^3}{\text{s}}$      $\eta_p = 85\%$      $\eta_m = 85\%$

$\rho = 1000 \frac{\text{kg}}{\text{m}^3}$      $\mu = 1.3 \cdot 10^{-3} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$     (Table A.8)     $\text{cost} = \frac{0.14}{\text{kW} \cdot \text{hr}}$  (dollars)

Then  $V = \frac{Q}{\left( \frac{\pi \cdot D^2}{4} \right)}$      $V = 1.47 \frac{\text{m}}{\text{s}}$      $Re = \frac{\rho \cdot V \cdot D}{\mu}$      $Re = 8.49 \times 10^5$

so    Given  $\frac{1}{\sqrt{f}} = -2 \cdot \log \left( \frac{e}{D} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$      $f = 0.0131$

The energy equation becomes  $\Delta p = f \cdot \frac{L}{D} \cdot \rho \cdot \frac{V^2}{2}$      $\Delta p = 94.4 \cdot \text{kPa}$

and  $W_{\text{pump}} = Q \cdot \Delta p$      $W_{\text{pump}} = 61.3 \cdot \text{kW}$


The required power is  $\text{Power} = \frac{W_{\text{pump}}}{\eta_p \cdot \eta_m}$      $\text{Power} = 84.9 \cdot \text{kW}$

The daily cost is then  $C = \text{cost} \cdot \text{Power} \cdot \text{day}$      $C = 285 \text{ dollars}$

## Problem 8.179

[Difficulty: 4]

**8.179** A fire nozzle is supplied through 100 m of 3.5-cm-diameter, smooth, rubber-lined hose. Water from a hydrant is supplied to a booster pump on board the pumper truck at 350 kPa (gage). At design conditions, the pressure at the nozzle inlet is 700 kPa (gage), and the pressure drop along the hose is 750 kPa per 100 m of length. Determine (a) the design flow rate, (b) the nozzle exit velocity, assuming no losses in the nozzle, and (c) the power required to drive the booster pump, if its efficiency is 70 percent.



**Given:** Fire nozzle/pump system

**Find:** Design flow rate; nozzle exit velocity; pump power needed

**Solution:**

Basic equations 
$$\left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) - \left( \frac{p_3}{\rho} + \alpha \cdot \frac{V_3^2}{2} + g \cdot z_3 \right) = h_f \quad h_f = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} \quad \text{for the hose}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 2 and 3 is approximately 1 4) No minor loss

$$\frac{p_3}{\rho} + \frac{V_3^2}{2} + g \cdot z_3 = \frac{p_4}{\rho} + \frac{V_4^2}{2} + g \cdot z_4 \quad \text{for the nozzle (assuming Bernoulli applies)}$$

$$\left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) - \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) = h_{\text{pump}} \quad \text{for the pump}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) No minor loss

Hence for the hose 
$$\frac{\Delta p}{\rho} = \frac{p_2 - p_3}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad \text{or} \quad V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}}$$

We need to iterate to solve this for  $V$  because  $f$  is unknown until  $Re$  is known. This can be done using *Excel's Solver*, but here:

$$\Delta p = 750 \cdot \text{kPa} \quad L = 100 \cdot \text{m} \quad e = 0 \quad D = 3.5 \cdot \text{cm} \quad \rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad \nu = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$$

Make a guess for  $f$  
$$f = 0.01 \quad V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 7.25 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.51 \times 10^5$$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0150$$

$$V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 5.92 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.05 \times 10^5$$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0156$$

$$V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 5.81 \frac{\text{m}}{\text{s}} \quad \text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 2.01 \times 10^5$$

Given  $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad f = 0.0156$

$$V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 5.80 \frac{\text{m}}{\text{s}} \quad \text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 2.01 \times 10^5$$

$$Q = V \cdot A = \frac{\pi \cdot D^2}{4} \cdot V \quad Q = \frac{\pi}{4} \times (0.035 \cdot \text{m})^2 \times 5.80 \cdot \frac{\text{m}}{\text{s}} \quad Q = 5.58 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 0.335 \cdot \frac{\text{m}^3}{\text{min}}$$

For the nozzle  $\frac{p_3}{\rho} + \frac{V_3^2}{2} + g \cdot z_3 = \frac{p_4}{\rho} + \frac{V_4^2}{2} + g \cdot z_4$  so  $V_4 = \sqrt{\frac{2 \cdot (p_3 - p_4)}{\rho} + V_3^2}$

$$V_4 = \sqrt{2 \times 700 \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{1000 \cdot \text{kg}} \times \frac{\text{kg} \cdot \text{m}}{\text{s}^2 \cdot \text{N}} + \left( 5.80 \cdot \frac{\text{m}}{\text{s}} \right)^2} \quad V_4 = 37.9 \frac{\text{m}}{\text{s}}$$

For the pump  $\left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) - \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) = h_{\text{pump}}$  so  $h_{\text{pump}} = \frac{p_2 - p_1}{\rho}$

$$p_1 = 350 \cdot \text{kPa} \quad p_2 = 700 \cdot \text{kPa} + 750 \cdot \text{kPa} \quad p_2 = 1450 \cdot \text{kPa}$$

The pump power is  $P_{\text{pump}} = m_{\text{pump}} \cdot h_{\text{pump}}$   $P_{\text{pump}}$  and  $m_{\text{pump}}$  are pump power and mass flow rate (software can't do a dot!)

$$P_{\text{pump}} = \rho \cdot Q \cdot \frac{(p_2 - p_1)}{\rho} = Q \cdot (p_2 - p_1) \quad P_{\text{pump}} = 5.58 \times 10^{-3} \cdot \frac{\text{m}^3}{\text{s}} \times (1450 - 350) \times 10^3 \cdot \frac{\text{N}}{\text{m}^2} \quad P_{\text{pump}} = 6.14 \cdot \text{kW}$$

$$P_{\text{required}} = \frac{P_{\text{pump}}}{\eta} \quad P_{\text{required}} = \frac{6.14 \cdot \text{kW}}{70. \%} \quad P_{\text{required}} = 8.77 \cdot \text{kW}$$

### Problem 8.180

[Difficulty: 4] Part 1/2

**8.180** Heavy crude oil (SG = 0.925 and  $\nu = 1.0 \times 10^{-4} \text{ m}^2/\text{s}$ ) is pumped through a pipeline laid on flat ground. The line is made from steel pipe with 600 mm i.d. and has a wall thickness of 12 mm. The allowable tensile stress in the pipe wall is limited to 275 MPa by corrosion considerations. It is important to keep the oil under pressure to ensure that gases remain in solution. The minimum recommended pressure is 500 kPa. The pipeline carries a flow of 400,000 barrels (in the petroleum industry, a "barrel" is 42 gal) per day. Determine the maximum spacing between pumping stations. Compute the power added to the oil at each pumping station.

Solution: First find the maximum pressure allowable in pipe.  
Consider a free body diagram of a segment of length,  $L$ :

Basic equation:  $\Sigma F_x = 0$


Assumption: Neglect hydrostatic pressure variation, and atmospheric pressure

Then

$$\Sigma F_x = p_{\max} DL - 2\sigma_{\max} tL = 0$$

$$p_{\max} = 2\sigma_{\max} \frac{t}{D} = 2 \times 275 \text{ MPa} \times \frac{12 \text{ mm}}{600 \text{ mm}} = 11 \text{ MPa (gage)}$$

Thus the pumping problem is as shown below:



To find  $L$ , apply the energy equation for steady, incompressible flow that is uniform at each section.

$$\text{Basic equation: } \frac{p_1}{\rho} + \frac{\bar{V}_1^2}{2} + g\bar{z}_1 = \frac{p_2}{\rho} + \frac{\bar{V}_2^2}{2} + g\bar{z}_2 + h_{\text{et}}; \quad h_{\text{et}} = f \frac{L}{D} \frac{\bar{V}^2}{2} + h_{\text{em}} \quad = \alpha(z)$$

Assumptions: (1)  $\bar{V}_1 = \bar{V}_2$

(2)  $\bar{z}_1 = \bar{z}_2$  (level)

(3)  $h_{\text{em}} = 0$ , since straight, constant area pipe

Then

$$f \frac{L}{D} \frac{\bar{V}^2}{2} = \frac{p_1 - p_2}{\rho} \quad \text{or} \quad L = \frac{D}{f} \left( \frac{p_1 - p_2}{\rho} \right) \frac{2}{\bar{V}^2} \quad \text{--- (1)}$$

$$\bar{V} = \frac{Q}{A} = 4 \times 10^5 \frac{\text{bbl}}{\text{day}} \times \frac{\text{day}}{24 \text{ hr}} \times \frac{\text{hr}}{3600 \text{ s}} \times \frac{42 \text{ gal}}{\text{bbl}} \times \frac{4 \text{ qt}}{\text{gal}} \times \frac{9.46 \times 10^{-4} \text{ m}^3}{\text{qt}} \times \frac{4}{\pi (0.6 \text{ m})^2} = 2.6 \text{ m/s}$$

$f = f(\text{Re}, e/D)$ . From Table 8.1,  $e = 0.046 \text{ mm}$ , so  $e/D = 7.7 \times 10^{-5}$  Reynolds number is

$$\text{Re} = \frac{\rho \bar{V} D}{\mu} = \frac{\bar{V} D}{\nu} = 2.6 \frac{\text{m}}{\text{s}} \times 0.6 \text{ m} \times \frac{\text{s}}{1.0 \times 10^{-4} \text{ m}^2} = 1.56 \times 10^4$$

From Eq 8.37,  $f = 0.0277$  (Using Excel's Solver or Goal Seek)



## Problem 8.181

[Difficulty: 2]

**8.181** The volume flow rate through a water fountain on a college campus is  $0.075 \text{ m}^3/\text{s}$ . Each water stream can rise to a height of 10 m. Estimate the daily cost to operate the fountain. Assume that the pump motor efficiency is 85 percent, the pump efficiency is 85 percent, and the cost of electricity is  $14\text{¢}/(\text{kW}\cdot\text{hr})$ .

**Given:** Flow in water fountain

**Find:** Daily cost

**Solution:**

Basic equations  $W_{\text{pump}} = Q \cdot \Delta p$   $\Delta p = \rho \cdot g \cdot H$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  is approximately 1

Available data  $Q = 0.075 \cdot \frac{\text{m}^3}{\text{s}}$   $H = 10 \cdot \text{m}$   $\eta_p = 85\%$   $\eta_m = 85\%$

$$\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad \text{Cost} = \frac{0.14}{\text{kW}\cdot\text{hr}} \quad (\text{dollars})$$

Hence  $\Delta p = \rho \cdot g \cdot H$   $\Delta p = 98 \cdot \text{kPa}$

$$W_{\text{pump}} = Q \cdot \Delta p \quad W_{\text{pump}} = 7.35 \cdot \text{kW}$$

$$\text{Power} = \frac{W_{\text{pump}}}{\eta_p \cdot \eta_m} \quad \text{Power} = 10.2 \cdot \text{kW}$$


$$C = \text{Cost} \cdot \text{Power} \cdot \text{day} \quad C = 34.17 \quad (\text{dollars})$$



## Problem 8.183

[Difficulty: 4]

**8.183** The pump testing system of Problem 8.128 is run with a pump that generates a pressure difference given by  $\Delta p = 750 - 15 \times 10^4 Q^2$  where  $\Delta p$  is in kPa, and the generated flow rate is  $Q$  m<sup>3</sup>/s. Find the water flow rate, pressure difference, and power supplied to the pump if it is 70 percent efficient.



**Given:** Flow in a pump testing system

**Find:** Flow rate; Pressure difference; Power

**Solution:**

Governing equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = \sum_{\text{major}} h_l + \sum_{\text{minor}} h_{lm} \quad (8.29)$$

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} \quad (8.40b)$$

$$f = \frac{64}{Re} \quad (8.36) \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (8.37) \quad (\text{Turbulent})$$

The energy equation (Eq. 8.29) becomes for the circuit (1 = pump outlet, 2 = pump inlet)

$$\frac{p_1 - p_2}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + 4 \cdot f \cdot L_{\text{elbow}} \cdot \frac{V^2}{2} + f \cdot L_{\text{valve}} \cdot \frac{V^2}{2}$$

or 
$$\Delta p = \rho \cdot f \cdot \frac{V^2}{2} \cdot \left( \frac{L}{D} + 4 \cdot \frac{L_{\text{elbow}}}{D} + \frac{L_{\text{valve}}}{D} \right) \quad (1)$$

This must be matched to the pump characteristic equation; at steady state, the pressure generated by the pump just equals that lost to friction in the circuit

$$\Delta p = 750 - 15 \times 10^4 \cdot Q^2 \quad (2)$$


Finally, the power supplied to the pump, efficiency  $\eta$ , is

$$\text{Power} = \frac{Q \cdot \Delta p}{\eta} \quad (3)$$

In Excel:

Given data:			Tabulated or graphical data:		
$L =$	20	m	$e =$	0.26	mm
$D =$	75	mm		(Table 8.1)	
$\eta_{\text{pump}} =$	70%		$\mu =$	1.00E-03	N.s/m <sup>2</sup>
			$\rho =$	999	kg/m <sup>3</sup>
				(Appendix A)	
			Gate valve $L_e/D =$	8	
			Elbow $L_e/D =$	30	
				(Table 8.4)	

Computed results:						
$Q$ (m <sup>3</sup> /s)	$V$ (m/s)	$Re$	$f$	$\Delta p$ (kPa) (Eq 1)	$\Delta p$ (kPa) (Eq 2)	
0.010	2.26	1.70E+05	0.0280	28.3	735	
0.015	3.40	2.54E+05	0.0277	63.1	716	
0.020	4.53	3.39E+05	0.0276	112	690	
0.025	5.66	4.24E+05	0.0276	174	656	
0.030	6.79	5.09E+05	0.0275	250	615	
0.035	7.92	5.94E+05	0.0275	340	566	
0.040	9.05	6.78E+05	0.0274	444	510	
0.045	10.2	7.63E+05	0.0274	561	446	
0.050	11.3	8.48E+05	0.0274	692	375	
0.055	12.4	9.33E+05	0.0274	837	296	
0.060	13.6	1.02E+06	0.0274	996	210	
						<b>Error</b>
0.0419	9.48	7.11E+05	0.0274	487	487	0 Using Solver!
Power =	29.1	kW	(Eq. 3)			



## Problem 8.184 Equations

[Difficulty: 4]

**8.184** A water pump can generate a pressure difference  $\Delta p$  (psi) given by  $\Delta p = 145 - 0.1 Q^2$ , where the flow rate is  $Q$  ft<sup>3</sup>/s. It supplies a pipe of diameter 20 in., roughness 0.5 in., and length 2500 ft. Find the flow rate, pressure difference, and the power supplied to the pump if it is 70 percent efficient. If the pipe were replaced with one of roughness 0.25 in., how much would the flow increase, and what would the required power be?

**Given:** Pump/pipe system

**Find:** Flow rate, pressure drop, and power supplied; Effect of roughness

**Solution:**

$$Re = \frac{\rho \cdot V \cdot D}{\mu} \quad \left( \frac{p_1}{\rho} + \alpha_1 \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - \Delta h_{\text{pump}} \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

$$f = \frac{64}{Re} \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (\text{Turbulent})$$

The energy equation becomes for the system (1 = pipe inlet, 2 = pipe outlet)

$$\Delta h_{\text{pump}} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad \text{or} \quad \Delta p_{\text{pump}} = \rho \cdot f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (1)$$

This must be matched to the pump characteristic equation; at steady state, the pressure generated by the pump just equals that lost to friction in the circuit

$$\Delta p_{\text{pump}} = 145 - 0.1 \cdot Q^2 \quad (2)$$

Finally, the power supplied to the pump, efficiency  $\eta$ , is


$$\text{Power} = \frac{Q \cdot \Delta p}{\eta} \quad (3)$$

In *Excel*:

Tabulated or graphical data:			Given data:		
	$\mu =$	2.10E-05	lbf·s/ft <sup>2</sup>	$L =$	2500 ft
	$\rho =$	1.94	slug/ft <sup>3</sup>	$D =$	20 in
	(Appendix A)			$\eta_{\text{pump}} =$	70%


Computed results:		$e =$	0.5	in				
$Q$ (ft <sup>3</sup> /s)	$V$ (ft/s)	$Re$	$f$	$\Delta p$ (psi) (Eq 1)	$\Delta p$ (psi) (Eq 2)			
10	4.58	7.06E+05	0.0531	11.3	135.0			
12	5.50	8.47E+05	0.0531	16.2	130.6			
14	6.42	9.88E+05	0.0531	22.1	125.4			
16	7.33	1.13E+06	0.0531	28.9	119.4			
18	8.25	1.27E+06	0.0531	36.5	112.6			
20	9.17	1.41E+06	0.0531	45.1	105.0			
22	10.08	1.55E+06	0.0531	54.6	96.6			
24	11.00	1.69E+06	0.0531	64.9	87.4			
26	11.92	1.83E+06	0.0531	76.2	77.4			
28	12.83	1.98E+06	0.0531	88.4	66.6			
30	13.75	2.12E+06	0.0531	101.4	55.0			
						<b>Error</b>		
26.1	12.0	1.84E+06	0.0531	76.8	76.8	0.00	Using Solver!	
Power =	750	hp	(Eq. 3)					

Repeating, with smoother pipe								
Computed results:		$e =$	0.25	in				
$Q$ (ft <sup>3</sup> /s)	$V$ (ft/s)	$Re$	$f$	$\Delta p$ (psi) (Eq 1)	$\Delta p$ (psi) (Eq 2)			
10	4.58	7.06E+05	0.0410	8.71	135.0			
12	5.50	8.47E+05	0.0410	12.5	130.6			
14	6.42	9.88E+05	0.0410	17.1	125.4			
16	7.33	1.13E+06	0.0410	22.3	119.4			
18	8.25	1.27E+06	0.0410	28.2	112.6			
20	9.17	1.41E+06	0.0410	34.8	105.0			
22	10.08	1.55E+06	0.0410	42.1	96.6			
24	11.00	1.69E+06	0.0410	50.1	87.4			
26	11.92	1.83E+06	0.0410	58.8	77.4			
28	12.83	1.98E+06	0.0410	68.2	66.6			
30	13.75	2.12E+06	0.0410	78.3	55.0			
						<b>Error</b>		
27.8	12.8	1.97E+06	0.0410	67.4	67.4	0.00	Using Solver!	
Power =	702	hp	(Eq. 3)					





### Fan and Duct Pressure Heads




**8.186** The head versus capacity curve for a certain fan may be approximated by the equation  $H = 30 - 10^{-7}Q^2$ , where  $H$  is the output static head in inches of water and  $Q$  is the air flow rate in  $\text{ft}^3/\text{min}$ . The fan outlet dimensions are  $8 \times 16$  in. Determine the air flow rate delivered by the fan into a 200 ft straight length of  $8 \times 16$  in. rectangular duct.

Solution:

Basic equation:  $\left( \frac{P_1}{\rho g} + \alpha \frac{V_1^2}{2g} + z_1 \right) - \left( \frac{P_2}{\rho g} + \alpha \frac{V_2^2}{2g} + z_2 \right) = H_{\text{net}} \quad (8.30)$

$$H_{\text{net}} = f \frac{L}{D} \frac{V^2}{2g} + h_{\text{ext}} \quad ; \quad h_{\text{ext}} = \frac{4A}{P_w}$$

Assumptions: (1)  $V_1 = V_2$ ,  $\alpha_1 = \alpha_2 = 1$   
 (2)  $z_1 = z_2$   
 (3)  $h_{\text{ext}} = 0$



$$A = ab = \frac{8}{12} \text{ ft} \times \frac{16}{12} \text{ ft} = 0.889 \text{ ft}^2$$

$$h_{\text{ext}} = \frac{4A}{P_w} = \frac{4A}{2(a+b)} = \frac{2 \times 0.889 \text{ ft}^2}{(2/3 + 4/3) \text{ ft}} = 0.889 \text{ ft}$$

From Eq. 8.30  $\Delta P = f \frac{L}{D} \frac{\rho_{\text{air}} V^2}{2} = f \frac{L}{D} \frac{\rho}{2} \frac{Q^2}{A^2} = \gamma_{\text{H}_2\text{O}} H_{\text{duct}}$   
 where  $H_{\text{duct}}$  is the pressure drop in head of water.

$$H_{\text{duct}} = \frac{f L \rho_{\text{air}} Q^2}{2 \gamma_{\text{H}_2\text{O}} A^2} = \frac{f \cdot 200 \text{ ft} \cdot 0.00238 \frac{\text{slugs}}{\text{ft}^3} \cdot \frac{\text{ft}^3}{\text{min}}}{2 \cdot 0.889 \text{ ft}^2 \cdot 62.4 \frac{\text{lb}}{\text{ft}^3} \cdot (0.889 \text{ ft})^2} \times \left[ \frac{\text{ft}^3}{\text{min}} \times \frac{\text{min}}{60 \text{ s}} \right] \times \frac{12 \text{ in}}{\text{ft}}$$

$$H_{\text{duct}} = 1.81 \times 10^{-5} f Q^2 \quad (\text{where } H \text{ is in in. H}_2\text{O}) \quad \dots (1)$$

For a smooth duct,  $f = f(Re)$

$$Re = \frac{V D_h}{\nu} = \frac{D_h Q}{\nu A} \quad \text{For } T = 68^\circ \text{F, from Table A.9, } \nu = 1.62 \times 10^{-4} \text{ ft}^2/\text{s}$$

$$Re = \frac{0.889 \text{ ft}}{0.889 \text{ ft}^2} \times 1.62 \times 10^{-4} \text{ ft}^2 \times \frac{Q \frac{\text{ft}^3}{\text{min}} \times \frac{\text{min}}{60 \text{ s}}}{1} = 103 Q$$

To determine the air flow rate delivered we need to determine the operating point of the fan.

- The operating point is at the intersection of the
- fan head capacity curve, and the
  - system curve (the head loss in the duct)

This is shown on the plot below.

Note that the friction factor  $f$  is determined from the Colebrook equation (8.37a) using Eq. 8.37b for the initial estimate of  $f$ .

42-384 42-385 42-386 42-387 42-388 42-389 42-390  
 100% RECYCLED PAPER  
 50% RECYCLED FIBER  
 100% RECYCLED INK  
 100% RECYCLED GLUE  
 100% RECYCLED LABEL  
 100% RECYCLED WRITING  
 100% RECYCLED WHITE  
 100% RECYCLED YELLOW






## Problem 8.187

[Difficulty: 5]

**8.187** The water pipe system shown is constructed from galvanized iron pipe. Minor losses may be neglected. The inlet is at 400 kPa (gage), and all exits are at atmospheric pressure. Find the flow rates  $Q_0$ ,  $Q_1$ ,  $Q_2$ ,  $Q_3$ , and  $Q_4$ .



**Given:** Pipe system

**Find:** Flow in each branch

**Solution:**

Governing equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad (8.29) \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34)$$

$$f = \frac{64}{Re} \quad (\text{Laminar}) \quad (8.36) \quad \frac{1}{f^{0.5}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot f^{0.5}} \right) \quad (\text{Turbulent}) \quad (8.37)$$

The energy equation (Eq. 8.29) can be simplified to 
$$\Delta p = \rho \cdot f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

This can be written for each pipe section

In addition we have the following constraints

$$Q_0 = Q_1 + Q_4 \quad (1) \quad Q_4 = Q_2 + Q_3 \quad (2)$$

$$\Delta p = \Delta p_0 + \Delta p_1 \quad (3) \quad \Delta p = \Delta p_0 + \Delta p_4 + \Delta p_2 \quad (4)$$

$$\Delta p_2 = \Delta p_3 \quad (5)$$

We have 5 unknown flow rates (or, equivalently, velocities) and five equations

In Excel:


Pipe Data:				
	Pipe	L (m)	D (mm)	e (mm)
	0	400	75	0.15
	1	300	50	0.15
	2	150	50	0.15
	3	150	35	0.15
	4	100	75	0.15
Fluid Properties:				
	$\rho =$	999	kg/m <sup>3</sup>	
	$\mu =$	0.001	N.s/m <sup>2</sup>	
Available Head:				
	$\Delta p =$	400	kPa	

<b>Flows:</b>		$Q_0$ (m <sup>3</sup> /s)	$Q_1$ (m <sup>3</sup> /s)	$Q_2$ (m <sup>3</sup> /s)	$Q_3$ (m <sup>3</sup> /s)	$Q_4$ (m <sup>3</sup> /s)
		0.00812	0.00286	0.00379	0.00147	0.00526
		$V_0$ (m/s)	$V_1$ (m/s)	$V_2$ (m/s)	$V_3$ (m/s)	$V_4$ (m/s)
		1.84	1.458	1.932	1.526	1.19
		$Re_0$	$Re_1$	$Re_2$	$Re_3$	$Re_4$
		1.38E+05	7.28E+04	9.65E+04	5.34E+04	8.92E+04
		$f_0$	$f_1$	$f_2$	$f_3$	$f_4$
		0.0247	0.0279	0.0275	0.0309	0.0253
<b>Heads:</b>		$\Delta p_0$ (kPa)	$\Delta p_1$ (kPa)	$\Delta p_2$ (kPa)	$\Delta p_3$ (kPa)	$\Delta p_4$ (kPa)
		222.3	177.7	153.9	153.9	23.9
<b>Constraints:</b>		(1) $Q_0 = Q_1 + Q_4$		(2) $Q_4 = Q_2 + Q_3$		
		0.00%		0.00%		
		(3) $\Delta p = \Delta p_0 + \Delta p_1$		(4) $\Delta p = \Delta p_0 + \Delta p_4 + \Delta p_2$		
		0.01%		0.01%		
		(5) $\Delta p_2 = \Delta p_3$				
		0.00%				
		<b>Error:</b>	0.03%	Vary $Q_0, Q_1, Q_2, Q_3$ and $Q_4$		
				using <i>Solver</i> to minimize total error		

## Problem 8.188

[Difficulty: 5]

**8.188** Find flow rates  $Q_0$ ,  $Q_1$ ,  $Q_2$ , and  $Q_4$  if pipe 3 becomes blocked.



**Given:** Pipe system

**Find:** Flow in each branch if pipe 3 is blocked

**Solution:**

Governing equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_f \quad (8.29) \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34)$$

$$f = \frac{64}{Re} \quad (\text{Laminar}) \quad (8.36) \quad \frac{1}{f^{0.5}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot f^{0.5}} \right) \quad (\text{Turbulent}) \quad (8.37)$$

The energy equation (Eq. 8.29) can be simplified to 
$$\Delta p = \rho \cdot f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

This can be written for each pipe section

In addition we have the following constraints

$$Q_0 = Q_1 + Q_4 \quad (1) \quad Q_4 = Q_2 \quad (2)$$

$$\Delta p = \Delta p_0 + \Delta p_1 \quad (3) \quad \Delta p = \Delta p_0 + \Delta p_4 + \Delta p_2 \quad (4)$$

We have 4 unknown flow rates (or, equivalently, velocities) and four equations

In Excel:

Pipe Data:					
		Pipe	L (m)	D (mm)	e (mm)
		0	400	75	0.15
		1	300	50	0.15
		2	150	50	0.15
		3	150	35	0.15
		4	100	75	0.15
Fluid Properties:					
		$\rho =$	999	kg/m <sup>3</sup>	
		$\mu =$	0.001	N.s/m <sup>2</sup>	
Available Head:					
		$\Delta p =$	400	kPa	

<b>Flows:</b>		$Q_0$ (m <sup>3</sup> /s)	$Q_1$ (m <sup>3</sup> /s)	$Q_2$ (m <sup>3</sup> /s)	$Q_3$ (m <sup>3</sup> /s)	$Q_4$ (m <sup>3</sup> /s)
		0.00744	0.00314	0.00430	NA	0.00430
		$V_0$ (m/s)	$V_1$ (m/s)	$V_2$ (m/s)	$V_3$ (m/s)	$V_4$ (m/s)
		1.68	1.599	2.190	NA	0.97
		$Re_0$	$Re_1$	$Re_2$	$Re_3$	$Re_4$
		1.26E+05	7.99E+04	1.09E+05	NA	7.29E+04
		$f_0$	$f_1$	$f_2$	$f_3$	$f_4$
		0.0248	0.0278	0.0274	NA	0.0257
<b>Heads:</b>		$\Delta p_0$ (kPa)	$\Delta p_1$ (kPa)	$\Delta p_2$ (kPa)	$\Delta p_3$ (kPa)	$\Delta p_4$ (kPa)
		187.2	212.8	196.6	NA	16.2
<b>Constraints:</b>		(1) $Q_0 = Q_1 + Q_4$			(2) $Q_4 = Q_2$	
		0.00%			0.00%	
		(3) $\Delta p = \Delta p_0 + \Delta p_1$			(4) $\Delta p = \Delta p_0 + \Delta p_4 + \Delta p_2$	
		0.00%			0.00%	
		<b>Error:</b>	0.00%	Vary $Q_0$ , $Q_1$ , $Q_2$ , and $Q_4$ using <i>Solver</i> to minimize total error		

## Problem 8.189

[Difficulty: 5]

**8.189** A cast-iron pipe system consists of a 500-ft section of water pipe, after which the flow branches into two 300-ft sections. The two branches then meet in a final 250-ft section. Minor losses may be neglected. All sections are 1.5-in. diameter, except one of the two branches, which is 1-in. diameter. If the applied pressure across the system is 100 psi, find the overall flow rate and the flow rates in each of the two branches.

**Given:** Water pipe system

**Find:** Flow rates

**Solution:**

Basic equations

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_{lT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

$$f = \frac{64}{\text{Re}} \quad (\text{Laminar}) \quad \frac{1}{\sqrt{f}} = -2.0 \log \left( \frac{e}{3.7D} + \frac{2.51}{\text{Re} \cdot \sqrt{f}} \right) \quad (\text{Turbulent})$$

The energy equation can be simplified to

$$\Delta p = \rho \cdot f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

This can be written for each pipe section

Pipe A (first section)

$$\Delta p_A = \rho \cdot f_A \cdot \frac{L_A}{D_A} \cdot \frac{V_A^2}{2} \quad (1)$$

Pipe B (1.5 in branch)

$$\Delta p_B = \rho \cdot f_B \cdot \frac{L_B}{D_B} \cdot \frac{V_B^2}{2} \quad (2)$$

Pipe C (1 in branch)

$$\Delta p_C = \rho \cdot f_C \cdot \frac{L_C}{D_C} \cdot \frac{V_C^2}{2} \quad (3)$$

Pipe D (last section)

$$\Delta p_D = \rho \cdot f_D \cdot \frac{L_D}{D_D} \cdot \frac{V_D^2}{2} \quad (4)$$

In addition we have the following constraints

$$Q_A = Q_D \quad (5)$$

$$Q_A = Q_B + Q_C \quad (6)$$

$$\Delta p = \Delta p_A + \Delta p_B + \Delta p_D \quad (7)$$

$$\Delta p_B = \Delta p_C \quad (8)$$

We have 4 unknown flow rates (or velocities) and four equations (5 - 8); Eqs 1 - 4 relate pressure drops to flow rates (velocities)

In Excel:

The workbook for Example Problem 8.11 is modified for use in this problem				
<b>Pipe Data:</b>				
	<b>Pipe</b>	<b>L (ft)</b>	<b>D (in)</b>	<b>e (ft)</b>
	A	500	1.5	0.00085
	B	300	1.5	0.00085
	C	300	1	0.00085
	D	250	1.5	0.00085
<b>Fluid Properties:</b>				
	$\rho =$	1.94	slug/ft <sup>3</sup>	
	$\mu =$	2.10E-05	lbf·s/ft <sup>2</sup>	
<b>Available Head:</b>				
	$\Delta p =$	100	psi	
<b>Flows:</b>				
	<b><math>Q_A</math> (ft<sup>3</sup>/s)</b>	<b><math>Q_B</math> (ft<sup>3</sup>/s)</b>	<b><math>Q_C</math> (ft<sup>3</sup>/s)</b>	<b><math>Q_D</math> (ft<sup>3</sup>/s)</b>
	0.0942	0.0704	0.0238	0.0942
	<b><math>V_A</math> (ft/s)</b>	<b><math>V_B</math> (ft/s)</b>	<b><math>V_C</math> (ft/s)</b>	<b><math>V_D</math> (ft/s)</b>
	7.68	5.74	4.36	7.68
	<b><math>Re_A</math></b>	<b><math>Re_B</math></b>	<b><math>Re_C</math></b>	<b><math>Re_D</math></b>
	8.87E+04	6.63E+04	3.36E+04	8.87E+04
	<b><math>f_A</math></b>	<b><math>f_B</math></b>	<b><math>f_C</math></b>	<b><math>f_D</math></b>
	0.0343	0.0345	0.0399	0.0343
<b>Heads:</b>				
	<b><math>\Delta p_A</math> (psi)</b>	<b><math>\Delta p_B</math> (psi)</b>	<b><math>\Delta p_C</math> (psi)</b>	<b><math>\Delta p_D</math> (psi)</b>
	54.5	18.4	18.4	27.2
<b>Constraints:</b>				
	(5) $Q_A = Q_D$		(6) $Q_A = Q_B + Q_C$	
	0.00%		0.00%	
	(7) $\Delta p = \Delta p_A + \Delta p_B + \Delta p_D$		(8) $\Delta p_B = \Delta p_C$	
	0.00%		0.00%	
	<b>Error:</b>	0.00%	Vary $Q_A$ , $Q_B$ , $Q_C$ , and $Q_D$	
			using <i>Solver</i> to minimize total error	



## Problem 8.191

[Difficulty: 5] Part 1/2

**8.191** Why does the shower temperature change when a toilet is flushed? Sketch pressure curves for the hot and cold water supply systems to explain what happens.

**Discussion:** Assume the pressure in the water main servicing the dwelling remains constant. The hot and cold water flow rates reaching the shower are controlled by valve(s) in the shower. Assuming a water heater temperature of  $140^{\circ}\text{F}$ , a cold water temperature of  $60^{\circ}\text{F}$ , and a shower water temperature of  $100^{\circ}\text{F}$ , the hot and cold flow rates must be equal. The two water streams mix before reaching the shower head, then spray out into the shower itself at  $100^{\circ}\text{F}$ .

Supply curves and system curves for the hot and cold water streams are shown below. Diagram *a* is the cold water system and diagram *b* is the hot water system. The numerical values are representative of an actual system.

In general the supply curves for the hot and cold streams are not the same. The difference is caused by the two systems having different pipe lengths and different fittings.


Each stream operates at the flow rate where the curves intersect. An equal flow split is accomplished by adjusting the shower valves to vary their resistances.

Flushing the toilet temporarily increases the flow rate of cold water to the bathroom. This reduces the cold water supply pressure reaching the shower. The system curves do not change because the valve settings stay the same. Therefore the flow rate of cold water must decrease to again match the supply and system curves (diagram *c*).

When the flow rate of cold water decreases the shower temperature increases, as experience testifies!

13-782  
42-381  
42-382  
42-383  
42-384  
42-385  
42-386  
42-387  
42-388  
42-389  
42-390  
42-391  
42-392  
42-393  
42-394  
42-395  
42-396  
42-397  
42-398  
42-399  
42-400  
42-401  
42-402  
42-403  
42-404  
42-405  
42-406  
42-407  
42-408  
42-409  
42-410  
42-411  
42-412  
42-413  
42-414  
42-415  
42-416  
42-417  
42-418  
42-419  
42-420  
42-421  
42-422  
42-423  
42-424  
42-425  
42-426  
42-427  
42-428  
42-429  
42-430  
42-431  
42-432  
42-433  
42-434  
42-435  
42-436  
42-437  
42-438  
42-439  
42-440  
42-441  
42-442  
42-443  
42-444  
42-445  
42-446  
42-447  
42-448  
42-449  
42-450  
42-451  
42-452  
42-453  
42-454  
42-455  
42-456  
42-457  
42-458  
42-459  
42-460  
42-461  
42-462  
42-463  
42-464  
42-465  
42-466  
42-467  
42-468  
42-469  
42-470  
42-471  
42-472  
42-473  
42-474  
42-475  
42-476  
42-477  
42-478  
42-479  
42-480  
42-481  
42-482  
42-483  
42-484  
42-485  
42-486  
42-487  
42-488  
42-489  
42-490  
42-491  
42-492  
42-493  
42-494  
42-495  
42-496  
42-497  
42-498  
42-499  
42-500  
42-501  
42-502  
42-503  
42-504  
42-505  
42-506  
42-507  
42-508  
42-509  
42-510  
42-511  
42-512  
42-513  
42-514  
42-515  
42-516  
42-517  
42-518  
42-519  
42-520  
42-521  
42-522  
42-523  
42-524  
42-525  
42-526  
42-527  
42-528  
42-529  
42-530  
42-531  
42-532  
42-533  
42-534  
42-535  
42-536  
42-537  
42-538  
42-539  
42-540  
42-541  
42-542  
42-543  
42-544  
42-545  
42-546  
42-547  
42-548  
42-549  
42-550  
42-551  
42-552  
42-553  
42-554  
42-555  
42-556  
42-557  
42-558  
42-559  
42-560  
42-561  
42-562  
42-563  
42-564  
42-565  
42-566  
42-567  
42-568  
42-569  
42-570  
42-571  
42-572  
42-573  
42-574  
42-575  
42-576  
42-577  
42-578  
42-579  
42-580  
42-581  
42-582  
42-583  
42-584  
42-585  
42-586  
42-587  
42-588  
42-589  
42-590  
42-591  
42-592  
42-593  
42-594  
42-595  
42-596  
42-597  
42-598  
42-599  
42-600  
42-601  
42-602  
42-603  
42-604  
42-605  
42-606  
42-607  
42-608  
42-609  
42-610  
42-611  
42-612  
42-613  
42-614  
42-615  
42-616  
42-617  
42-618  
42-619  
42-620  
42-621  
42-622  
42-623  
42-624  
42-625  
42-626  
42-627  
42-628  
42-629  
42-630  
42-631  
42-632  
42-633  
42-634  
42-635  
42-636  
42-637  
42-638  
42-639  
42-640  
42-641  
42-642  
42-643  
42-644  
42-645  
42-646  
42-647  
42-648  
42-649  
42-650  
42-651  
42-652  
42-653  
42-654  
42-655  
42-656  
42-657  
42-658  
42-659  
42-660  
42-661  
42-662  
42-663  
42-664  
42-665  
42-666  
42-667  
42-668  
42-669  
42-670  
42-671  
42-672  
42-673  
42-674  
42-675  
42-676  
42-677  
42-678  
42-679  
42-680  
42-681  
42-682  
42-683  
42-684  
42-685  
42-686  
42-687  
42-688  
42-689  
42-690  
42-691  
42-692  
42-693  
42-694  
42-695  
42-696  
42-697  
42-698  
42-699  
42-700  
42-701  
42-702  
42-703  
42-704  
42-705  
42-706  
42-707  
42-708  
42-709  
42-710  
42-711  
42-712  
42-713  
42-714  
42-715  
42-716  
42-717  
42-718  
42-719  
42-720  
42-721  
42-722  
42-723  
42-724  
42-725  
42-726  
42-727  
42-728  
42-729  
42-730  
42-731  
42-732  
42-733  
42-734  
42-735  
42-736  
42-737  
42-738  
42-739  
42-740  
42-741  
42-742  
42-743  
42-744  
42-745  
42-746  
42-747  
42-748  
42-749  
42-750  
42-751  
42-752  
42-753  
42-754  
42-755  
42-756  
42-757  
42-758  
42-759  
42-760  
42-761  
42-762  
42-763  
42-764  
42-765  
42-766  
42-767  
42-768  
42-769  
42-770  
42-771  
42-772  
42-773  
42-774  
42-775  
42-776  
42-777  
42-778  
42-779  
42-780  
42-781  
42-782  
42-783  
42-784  
42-785  
42-786  
42-787  
42-788  
42-789  
42-790  
42-791  
42-792  
42-793  
42-794  
42-795  
42-796  
42-797  
42-798  
42-799  
42-800  
42-801  
42-802  
42-803  
42-804  
42-805  
42-806  
42-807  
42-808  
42-809  
42-810  
42-811  
42-812  
42-813  
42-814  
42-815  
42-816  
42-817  
42-818  
42-819  
42-820  
42-821  
42-822  
42-823  
42-824  
42-825  
42-826  
42-827  
42-828  
42-829  
42-830  
42-831  
42-832  
42-833  
42-834  
42-835  
42-836  
42-837  
42-838  
42-839  
42-840  
42-841  
42-842  
42-843  
42-844  
42-845  
42-846  
42-847  
42-848  
42-849  
42-850  
42-851  
42-852  
42-853  
42-854  
42-855  
42-856  
42-857  
42-858  
42-859  
42-860  
42-861  
42-862  
42-863  
42-864  
42-865  
42-866  
42-867  
42-868  
42-869  
42-870  
42-871  
42-872  
42-873  
42-874  
42-875  
42-876  
42-877  
42-878  
42-879  
42-880  
42-881  
42-882  
42-883  
42-884  
42-885  
42-886  
42-887  
42-888  
42-889  
42-890  
42-891  
42-892  
42-893  
42-894  
42-895  
42-896  
42-897  
42-898  
42-899  
42-900  
42-901  
42-902  
42-903  
42-904  
42-905  
42-906  
42-907  
42-908  
42-909  
42-910  
42-911  
42-912  
42-913  
42-914  
42-915  
42-916  
42-917  
42-918  
42-919  
42-920  
42-921  
42-922  
42-923  
42-924  
42-925  
42-926  
42-927  
42-928  
42-929  
42-930  
42-931  
42-932  
42-933  
42-934  
42-935  
42-936  
42-937  
42-938  
42-939  
42-940  
42-941  
42-942  
42-943  
42-944  
42-945  
42-946  
42-947  
42-948  
42-949  
42-950  
42-951  
42-952  
42-953  
42-954  
42-955  
42-956  
42-957  
42-958  
42-959  
42-960  
42-961  
42-962  
42-963  
42-964  
42-965  
42-966  
42-967  
42-968  
42-969  
42-970  
42-971  
42-972  
42-973  
42-974  
42-975  
42-976  
42-977  
42-978  
42-979  
42-980  
42-981  
42-982  
42-983  
42-984  
42-985  
42-986  
42-987  
42-988  
42-989  
42-990  
42-991  
42-992  
42-993  
42-994  
42-995  
42-996  
42-997  
42-998  
42-999  
43-000

Made in U.S.A.




# Problem 8.191

[Difficulty: 5] Part 2/2


**(a) Cold water system:**

Q (gpm)	System Curve p (psig)	Supply Curve p (psig)
0	0.00	50.0
0.2	0.53	49.6
0.4	2.13	48.6
0.6	4.80	46.8
0.8	8.53	44.3
1.0	13.3	41.1
1.2	19.2	37.2
1.4	26.1	32.6
1.6	34.1	27.2
1.7	38.5	24.3
1.8		21.2




**(b) Hot water system:**

Q (gpm)	System Curve p (psig)	Supply Curve p (psig)
0	0.00	50.0
0.2	0.71	49.8
0.4	2.84	49.3
0.6	6.40	48.4
0.8	11.38	47.2
1.0	17.78	45.6
1.2	25.60	43.6
1.4	34.84	41.3
1.6	45.51	38.6
1.7		37.2
1.8		



**(c) Cold water system: toilet flush**

Q (gpm)	System Curve		Supply Curve	
	p (psig)	p (psig)	Old Supply Curve p (psig)	New Supply Curve p (psig)
0	0.00	50.0	50.0	50.0
0.2	0.53	49.6	49.6	49.6
0.4	2.13	48.6	48.6	48.2
0.6	4.80	46.8	46.8	46.0
0.8	8.53	44.3	44.3	42.9
1.0	13.3	41.1	41.1	38.9
1.2	19.2	37.2	37.2	34.0
1.4	26.1	32.6	32.6	28.2
1.430	27.27	31.8	27.28	27.28
1.6	34.1	27.2	21.6	
1.7	38.5	24.3		
1.8				



13-782  
 13-781  
 13-780  
 13-779  
 13-778  
 13-777  
 13-776  
 13-775  
 13-774  
 13-773  
 13-772  
 13-771  
 13-770  
 13-769  
 13-768  
 13-767  
 13-766  
 13-765  
 13-764  
 13-763  
 13-762  
 13-761  
 13-760  
 13-759  
 13-758  
 13-757  
 13-756  
 13-755  
 13-754  
 13-753  
 13-752  
 13-751  
 13-750  
 13-749  
 13-748  
 13-747  
 13-746  
 13-745  
 13-744  
 13-743  
 13-742  
 13-741  
 13-740  
 13-739  
 13-738  
 13-737  
 13-736  
 13-735  
 13-734  
 13-733  
 13-732  
 13-731  
 13-730  
 13-729  
 13-728  
 13-727  
 13-726  
 13-725  
 13-724  
 13-723  
 13-722  
 13-721  
 13-720  
 13-719  
 13-718  
 13-717  
 13-716  
 13-715  
 13-714  
 13-713  
 13-712  
 13-711  
 13-710  
 13-709  
 13-708  
 13-707  
 13-706  
 13-705  
 13-704  
 13-703  
 13-702  
 13-701  
 13-700  
 13-699  
 13-698  
 13-697  
 13-696  
 13-695  
 13-694  
 13-693  
 13-692  
 13-691  
 13-690  
 13-689  
 13-688  
 13-687  
 13-686  
 13-685  
 13-684  
 13-683  
 13-682  
 13-681  
 13-680  
 13-679  
 13-678  
 13-677  
 13-676  
 13-675  
 13-674  
 13-673  
 13-672  
 13-671  
 13-670  
 13-669  
 13-668  
 13-667  
 13-666  
 13-665  
 13-664  
 13-663  
 13-662  
 13-661  
 13-660  
 13-659  
 13-658  
 13-657  
 13-656  
 13-655  
 13-654  
 13-653  
 13-652  
 13-651  
 13-650  
 13-649  
 13-648  
 13-647  
 13-646  
 13-645  
 13-644  
 13-643  
 13-642  
 13-641  
 13-640  
 13-639  
 13-638  
 13-637  
 13-636  
 13-635  
 13-634  
 13-633  
 13-632  
 13-631  
 13-630  
 13-629  
 13-628  
 13-627  
 13-626  
 13-625  
 13-624  
 13-623  
 13-622  
 13-621  
 13-620  
 13-619  
 13-618  
 13-617  
 13-616  
 13-615  
 13-614  
 13-613  
 13-612  
 13-611  
 13-610  
 13-609  
 13-608  
 13-607  
 13-606  
 13-605  
 13-604  
 13-603  
 13-602  
 13-601  
 13-600  
 13-599  
 13-598  
 13-597  
 13-596  
 13-595  
 13-594  
 13-593  
 13-592  
 13-591  
 13-590  
 13-589  
 13-588  
 13-587  
 13-586  
 13-585  
 13-584  
 13-583  
 13-582  
 13-581  
 13-580  
 13-579  
 13-578  
 13-577  
 13-576  
 13-575  
 13-574  
 13-573  
 13-572  
 13-571  
 13-570  
 13-569  
 13-568  
 13-567  
 13-566  
 13-565  
 13-564  
 13-563  
 13-562  
 13-561  
 13-560  
 13-559  
 13-558  
 13-557  
 13-556  
 13-555  
 13-554  
 13-553  
 13-552  
 13-551  
 13-550  
 13-549  
 13-548  
 13-547  
 13-546  
 13-545  
 13-544  
 13-543  
 13-542  
 13-541  
 13-540  
 13-539  
 13-538  
 13-537  
 13-536  
 13-535  
 13-534  
 13-533  
 13-532  
 13-531  
 13-530  
 13-529  
 13-528  
 13-527  
 13-526  
 13-525  
 13-524  
 13-523  
 13-522  
 13-521  
 13-520  
 13-519  
 13-518  
 13-517  
 13-516  
 13-515  
 13-514  
 13-513  
 13-512  
 13-511  
 13-510  
 13-509  
 13-508  
 13-507  
 13-506  
 13-505  
 13-504  
 13-503  
 13-502  
 13-501  
 13-500  
 13-499  
 13-498  
 13-497  
 13-496  
 13-495  
 13-494  
 13-493  
 13-492  
 13-491  
 13-490  
 13-489  
 13-488  
 13-487  
 13-486  
 13-485  
 13-484  
 13-483  
 13-482  
 13-481  
 13-480  
 13-479  
 13-478  
 13-477  
 13-476  
 13-475  
 13-474  
 13-473  
 13-472  
 13-471  
 13-470  
 13-469  
 13-468  
 13-467  
 13-466  
 13-465  
 13-464  
 13-463  
 13-462  
 13-461  
 13-460  
 13-459  
 13-458  
 13-457  
 13-456  
 13-455  
 13-454  
 13-453  
 13-452  
 13-451  
 13-450  
 13-449  
 13-448  
 13-447  
 13-446  
 13-445  
 13-444  
 13-443  
 13-442  
 13-441  
 13-440  
 13-439  
 13-438  
 13-437  
 13-436  
 13-435  
 13-434  
 13-433  
 13-432  
 13-431  
 13-430  
 13-429  
 13-428  
 13-427  
 13-426  
 13-425  
 13-424  
 13-423  
 13-422  
 13-421  
 13-420  
 13-419  
 13-418  
 13-417  
 13-416  
 13-415  
 13-414  
 13-413  
 13-412  
 13-411  
 13-410  
 13-409  
 13-408  
 13-407  
 13-406  
 13-405  
 13-404  
 13-403  
 13-402  
 13-401  
 13-400  
 13-399  
 13-398  
 13-397  
 13-396  
 13-395  
 13-394  
 13-393  
 13-392  
 13-391  
 13-390  
 13-389  
 13-388  
 13-387  
 13-386  
 13-385  
 13-384  
 13-383  
 13-382  
 13-381  
 13-380  
 13-379  
 13-378  
 13-377  
 13-376  
 13-375  
 13-374  
 13-373  
 13-372  
 13-371  
 13-370  
 13-369  
 13-368  
 13-367  
 13-366  
 13-365  
 13-364  
 13-363  
 13-362  
 13-361  
 13-360  
 13-359  
 13-358  
 13-357  
 13-356  
 13-355  
 13-354  
 13-353  
 13-352  
 13-351  
 13-350  
 13-349  
 13-348  
 13-347  
 13-346  
 13-345  
 13-344  
 13-343  
 13-342  
 13-341  
 13-340  
 13-339  
 13-338  
 13-337  
 13-336  
 13-335  
 13-334  
 13-333  
 13-332  
 13-331  
 13-330  
 13-329  
 13-328  
 13-327  
 13-326  
 13-325  
 13-324  
 13-323  
 13-322  
 13-321  
 13-320  
 13-319  
 13-318  
 13-317  
 13-316  
 13-315  
 13-314  
 13-313  
 13-312  
 13-311  
 13-310  
 13-309  
 13-308  
 13-307  
 13-306  
 13-305  
 13-304  
 13-303  
 13-302  
 13-301  
 13-300  
 13-299  
 13-298  
 13-297  
 13-296  
 13-295  
 13-294  
 13-293  
 13-292  
 13-291  
 13-290  
 13-289  
 13-288  
 13-287  
 13-286  
 13-285  
 13-284  
 13-283  
 13-282  
 13-281  
 13-280  
 13-279  
 13-278  
 13-277  
 13-276  
 13-275  
 13-274  
 13-273  
 13-272  
 13-271  
 13-270  
 13-269  
 13-268  
 13-267  
 13-266  
 13-265  
 13-264  
 13-263  
 13-262  
 13-261  
 13-260  
 13-259  
 13-258  
 13-257  
 13-256  
 13-255  
 13-254  
 13-253  
 13-252  
 13-251  
 13-250  
 13-249  
 13-248  
 13-247  
 13-246  
 13-245  
 13-244  
 13-243  
 13-242  
 13-241  
 13-240  
 13-239  
 13-238  
 13-237  
 13-236  
 13-235  
 13-234  
 13-233  
 13-232  
 13-231  
 13-230  
 13-229  
 13-228  
 13-227  
 13-226  
 13-225  
 13-224  
 13-223  
 13-222  
 13-221  
 13-220  
 13-219  
 13-218  
 13-217  
 13-216  
 13-215  
 13-214  
 13-213  
 13-212  
 13-211  
 13-210  
 13-209  
 13-208  
 13-207  
 13-206  
 13-205  
 13-204  
 13-203  
 13-202  
 13-201  
 13-200  
 13-199  
 13-198  
 13-197  
 13-196  
 13-195  
 13-194  
 13-193  
 13-192  
 13-191  
 13-190  
 13-189  
 13-188  
 13-187  
 13-186  
 13-185  
 13-184  
 13-183  
 13-182  
 13-181  
 13-180  
 13-179  
 13-178  
 13-177  
 13-176  
 13-175  
 13-174  
 13-173  
 13-172  
 13-171  
 13-170  
 13-169  
 13-168  
 13-167  
 13-166  
 13-165  
 13-164  
 13-163  
 13-162  
 13-161  
 13-160  
 13-159  
 13-158  
 13-157  
 13-156  
 13-155  
 13-154  
 13-153  
 13-152  
 13-151  
 13-150  
 13-149  
 13-148  
 13-147  
 13-146  
 13-145  
 13-144  
 13-143  
 13-142  
 13-141  
 13-140  
 13-139  
 13-138  
 13-137  
 13-136  
 13-135  
 13-134  
 13-133  
 13-132  
 13-131  
 13-130  
 13-129  
 13-128  
 13-127  
 13-126  
 13-125  
 13-124  
 13-123  
 13-122  
 13-121  
 13-120  
 13-119  
 13-118  
 13-117  
 13-116  
 13-115  
 13-114  
 13-113  
 13-112  
 13-111  
 13-110  
 13-109  
 13-108  
 13-107  
 13-106  
 13-105  
 13-104  
 13-103  
 13-102  
 13-101  
 13-100  
 13-99  
 13-98  
 13-97  
 13-96  
 13-95  
 13-94  
 13-93  
 13-92  
 13-91  
 13-90  
 13-89  
 13-88  
 13-87  
 13-86  
 13-85  
 13-84  
 13-83  
 13-82  
 13-81  
 13-80  
 13-79  
 13-78  
 13-77  
 13-76  
 13-75  
 13-74  
 13-73  
 13-72  
 13-71  
 13-70  
 13-69  
 13-68  
 13-67  
 13-66  
 13-65  
 13-64  
 13-63  
 13-62  
 13-61  
 13-60  
 13-59  
 13-58  
 13-57  
 13-56  
 13-55  
 13-54  
 13-53  
 13-52  
 13-51  
 13-50  
 13-49  
 13-48  
 13-47  
 13-46  
 13-45  
 13-44  
 13-43  
 13-42  
 13-41  
 13-40  
 13-39  
 13-38  
 13-37  
 13-36  
 13-35  
 13-34  
 13-33  
 13-32  
 13-31  
 13-30  
 13-29  
 13-28  
 13-27  
 13-26  
 13-25  
 13-24  
 13-23  
 13-22  
 13-21  
 13-20  
 13-19  
 13-18  
 13-17  
 13-16  
 13-15  
 13-14  
 13-13  
 13-12  
 13-11  
 13-10  
 13-9  
 13-8  
 13-7  
 13-6  
 13-5  
 13-4  
 13-3  
 13-2  
 13-1  
 13-0  
 12-99  
 12-98  
 12-97  
 12-96  
 12-95  
 12-94  
 12-93  
 12-92  
 12-91  
 12-90  
 12-89  
 12-88  
 12-87  
 12-86  
 12-85  
 12-84  
 12-83  
 12-82  
 12-81  
 12-80  
 12-79  
 12-78  
 12-77  
 12-76  
 12-75  
 12-74  
 12-73  
 12-72  
 12-71  
 12-70  
 12-69  
 12-68  
 12-67  
 12-66  
 12-65  
 12-64  
 12-63  
 12-62  
 12-61  
 12-60  
 12-59  
 12-58  
 12-57  
 12-56  
 12-55  
 12-54  
 12-53  
 12-52  
 12-51  
 12-50  
 12-49  
 12-48  
 12-47  
 12-46  
 12-45  
 12-44  
 12-43  
 12-42  
 12-41  
 12-40  
 12-39  
 12-38  
 12-37  
 12-36  
 12-35  
 12-34  
 12-33  
 12-32  
 12-31  
 12-30  
 12-29  
 12-28  
 12-27  
 12-26  
 12-25  
 12-24  
 12-23  
 12-22  
 12-21  
 12-20  
 12-19  
 12-18  
 12-17  
 12-16  
 12-15  
 12-14  
 12-13  
 12-12  
 12-11  
 12-10  
 12-9  
 12-8  
 12-7  
 12-6  
 12-5  
 12-4  
 12-3  
 12-2  
 12-1  
 12-0  
 11-99  
 11-98  
 11-97  
 11-96  
 11-95  
 11-94  
 11-93  
 11-92  
 11-91  
 11-90  
 11-89  
 11-88  
 11-87  
 11-86  
 11-85  
 11-84  
 11-83  
 11-82  
 11-81  
 11-80  
 11-79  
 11-78  
 11-77  
 11-76  
 11-75  
 11-74  
 11-73  
 11-72  
 11-71  
 11-70  
 11-69  
 11-68  
 11-67  
 11-66  
 11-65  
 11-64  
 11-63  
 11-62  
 11-61  
 11-60  
 11-59  
 11-58  
 11-57  
 11-56  
 11-55  
 11-54  
 11-53  
 11-52  
 11-51  
 11-50  
 11-49  
 11-

## Problem 8.192

[Difficulty: 2]

**8.192** A square-edged orifice with corner taps and a water manometer are used to meter compressed air. The following data are given:

Inside diameter of air line	150 mm
Orifice plate diameter	100 mm
Upstream pressure	600 kPa
Temperature of air	25°C
Manometer deflection	750 mm
	H <sub>2</sub> O

Calculate the volume flow rate in the line, expressed in cubic meters per hour.

Solution: Apply analysis of section 8-10; data from Fig. 8.23 apply

Computing equation:  $\dot{m}_{\text{actual}} = K A_t \sqrt{2\rho(P_1 - P_2)}$  (8.5b)

Since  $\dot{m} = \rho Q$ , then

$$Q = \frac{\dot{m}}{\rho} = K A_t \sqrt{\frac{2(P_1 - P_2)}{\rho}}$$

$$P_1 - P_2 = 750 \text{ mm H}_2\text{O} = \rho g \Delta h_{\text{H}_2\text{O}} = 999 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.75 \text{ m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 7.35 \text{ kPa}$$

For this small  $\Delta p$ , the assumption of incompressible flow is certainly valid

$$\rho = \frac{P_1}{RT} = \frac{701 \times 10^3 \text{ N/m}^2 \times \frac{\text{kg}}{\text{m}^3 \cdot \text{K}}}{287 \text{ J/K}} = \frac{1}{298 \text{ K}} \times \frac{\text{J}}{\text{N} \cdot \text{m}} = 8.20 \text{ kg/m}^3$$

The flow coefficient  $K = K(\text{Re}_D, \frac{D_t}{D})$

Assume  $\text{Re} > 2 \times 10^5$ . For  $\beta = \frac{D_t}{D} = \frac{2}{3}$ , from Fig. 8.20,  $K = 0.675$

$$Q = K A_t \sqrt{\frac{2(P_1 - P_2)}{\rho}} = 0.675 \frac{\pi}{4} (0.1 \text{ m})^2 \left[ 2 \times 7350 \frac{\text{N}}{\text{m}^2} \times 8.20 \frac{\text{kg}}{\text{m}^3} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]^{1/2}$$

$$Q = 0.224 \text{ m}^3/\text{s}$$

Check  $\text{Re}$ . At  $T = 25^\circ\text{C}$   $\mu = 1.84 \times 10^{-5} \text{ N} \cdot \text{s}/\text{m}^2$  (Table A.10)

$$\text{Re} = \frac{\rho D V}{\mu} = \frac{\rho D Q}{\mu A} = \frac{\rho D Q \cdot 4}{\mu \pi D^2} = \frac{4 \rho Q}{\pi \mu D}$$

$$\text{Re} = \frac{4}{\pi} \times 8.20 \frac{\text{kg}}{\text{m}^3} \times 0.224 \frac{\text{m}^3}{\text{s}} \times \frac{1}{1.84 \times 10^{-5} \frac{\text{N} \cdot \text{s}}{\text{m}^2}} \times \frac{1}{0.15 \text{ m} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}}$$

$$\text{Re} = 8.47 \times 10^5 \quad \checkmark \quad \text{assumption is valid}$$

## Problem 8.193

[Difficulty: 2]

**8.193** Water at 65°C flows through a 75-mm-diameter orifice installed in a 150-mm-i.d. pipe. The flow rate is 20 L/s. Determine the pressure difference between the corner taps.

**Given:** Flow through an orifice

**Find:** Pressure drop

**Solution:**

Basic equation  $m_{\text{actual}} = K \cdot A_t \cdot \sqrt{2 \cdot \rho \cdot (p_1 - p_2)} = K \cdot A_t \cdot \sqrt{2 \cdot \rho \cdot \Delta p}$

Note that  $m_{\text{actual}}$  is mass flow rate (the software cannot render a dot!)

For the flow coefficient  $K = K \left( \text{Re}_{D1}, \frac{D_t}{D_1} \right)$

At 65°C, (Table A.8)  $\rho = 980 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu = 4.40 \times 10^{-7} \cdot \frac{\text{m}^2}{\text{s}}$

$V = \frac{Q}{A}$   $V = \frac{4}{\pi} \times \frac{1}{(0.15 \cdot \text{m})^2} \times 20 \cdot \frac{\text{L}}{\text{s}} \times \frac{0.001 \cdot \text{m}^3}{1 \cdot \text{L}}$   $V = 1.13 \frac{\text{m}}{\text{s}}$

$\text{Re}_{D1} = \frac{V \cdot D}{\nu}$   $\text{Re}_{D1} = 1.13 \cdot \frac{\text{m}}{\text{s}} \times 0.15 \cdot \text{m} \times \frac{\text{s}}{4.40 \times 10^{-7} \cdot \text{m}^2}$   $\text{Re}_{D1} = 3.85 \times 10^5$

$\beta = \frac{D_t}{D_1}$   $\beta = \frac{75}{150}$   $\beta = 0.5$

From Fig. 8.20  $K = 0.624$

Then  $\Delta p = \left( \frac{m_{\text{actual}}}{K \cdot A_t} \right)^2 \cdot \frac{1}{2 \cdot \rho} = \left( \frac{\rho \cdot Q}{K \cdot A_t} \right)^2 \cdot \frac{1}{2 \cdot \rho} = \frac{\rho}{2} \cdot \left( \frac{Q}{K \cdot A_t} \right)^2$

$\Delta p = \frac{1}{2} \times 980 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ 20 \cdot \frac{\text{L}}{\text{s}} \times \frac{0.001 \cdot \text{m}^3}{1 \cdot \text{L}} \times \frac{1}{0.624} \times \frac{4}{\pi} \times \frac{1}{(0.075 \cdot \text{m})^2} \right]^2$   $\Delta p = 25.8 \cdot \text{kPa}$

## Problem 8.194

[Difficulty: 3]

**8.194** A smooth 200-m pipe, 100 mm diameter connects two reservoirs (the entrance and exit of the pipe are sharp-edged). At the midpoint of the pipe is an orifice plate with diameter 40 mm. If the water levels in the reservoirs differ by 30 m, estimate the pressure differential indicated by the orifice plate and the flow rate.

**Given:** Reservoir-pipe system

**Find:** Orifice plate pressure difference; Flow rate

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} = h_l + \Sigma h_{lm} \quad (8.29)$$

$$h_l = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad (8.34) \quad h_{lm} = K \cdot \frac{V^2}{2} \quad (8.40a)$$

$$f = \frac{64}{Re} \quad (\text{Laminar}) \quad (8.36) \quad \frac{1}{f^{0.5}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot f^{0.5}} \right) \quad (\text{Turbulent}) \quad (8.37)$$

There are three minor losses: at the entrance; at the orifice plate; at the exit. For each 
$$h_{lm} = K \cdot \frac{V^2}{2}$$

The energy equation (Eq. 8.29) becomes ( $\alpha = 1$ ) 
$$g \cdot \Delta H = \frac{V^2}{2} \cdot \left( f \cdot \frac{L}{D} + K_{ent} + K_{orifice} + K_{exit} \right) \quad (1)$$

( $\Delta H$  is the difference in reservoir heights)

This cannot be solved for  $V$  (and hence  $Q$ ) because  $f$  depends on  $V$ ; we can solve by manually iterating, or by using *Solver*

The tricky part to this problem is that the orifice loss coefficient  $K_{orifice}$  is given in Fig. 8.23 as a percentage of pressure differential  $\Delta p$  across the orifice, which is unknown until  $V$  is known!

The mass flow rate is given by 
$$m_{rate} = K \cdot A_t \cdot \sqrt{2 \cdot \rho \cdot \Delta p} \quad (2)$$

where  $K$  is the orifice flow coefficient,  $A_t$  is the orifice area, and  $\Delta p$  is the pressure drop across the orifice

Equations 1 and 2 form a set for solving for TWO unknowns: the pressure drop  $\Delta p$  across the orifice (leading to a value for  $K_{orifice}$ ) and the velocity  $V$ . The easiest way to do this is by using *Solver*

In Excel:

Given data:			Tabulated or graphical data:		
$\Delta H =$	30	m	$K_{ent} =$	0.50	(Fig. 8.14)
$L =$	200	m	$K_{exit} =$	1.00	(Fig. 8.14)
$D =$	100	mm	Loss at orifice =	80%	(Fig. 8.23)
$D_t =$	40	mm	$\mu =$	0.001	N.s/m <sup>2</sup>
$\beta =$	0.40		$\rho =$	999	kg/m <sup>3</sup>
					(Water - Appendix A)
Computed results:					
Orifice loss coefficient:		Flow system:		Orifice pressure drop	
$K =$	0.61	$V =$	2.25	m/s	$\Delta p =$ 265 kPa
	(Fig. 8.20)	$Q =$	0.0176	m <sup>3</sup> /s	
	Assuming high $Re$ )	$Re =$	2.24E+05		
		$f =$	0.0153		
Eq. 1, solved by varying $V$ AND $\Delta p$ , using <i>Solver</i> :					
	<b>Left (m<sup>2</sup>/s)</b>	<b>Right (m<sup>2</sup>/s)</b>	<b>Error</b>	Procedure using <i>Solver</i> :	
	294	293	0.5%	a) Guess at $V$ and $\Delta p$	
				b) Compute error in Eq. 1	
				c) Compute error in mass flow rate	
	<b>(From <math>Q</math>)</b>	<b>(From Eq. 2)</b>	<b>Error</b>	d) Minimize total error	
$m_{rate}$ (kg/s) =	17.6	17.6	0.0%	e) Minimize total error by varying $V$ and $\Delta p$	
		<b>Total Error</b>	0.5%		

## Problem 8.195

[Difficulty: 2]

**8.195** A venturi meter with a 3-in.-diameter throat is placed in a 6-in.-diameter line carrying water at 75°F. The pressure drop between the upstream tap and the venturi throat is 12 in. of mercury. Compute the rate of flow.

**Given:** Flow through a venturi meter (NOTE: Throat is obviously 3 in not 30 in!)

**Find:** Flow rate

**Solution:**

Basic equation 
$$m_{\text{actual}} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot (p_1 - p_2)} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot \Delta p}$$
 Note that  $m_{\text{actual}}$  is mass flow rate (the software cannot render a dot!)

For  $Re_{D1} > 2 \times 10^5$ ,  $0.980 < C < 0.995$ . Assume  $C = 0.99$ , then check  $Re$

$$\beta = \frac{D_t}{D_1} \qquad \beta = \frac{3}{6} \qquad \beta = 0.5$$

Also 
$$\Delta p = \rho_{\text{Hg}} \cdot g \cdot \Delta h = SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h$$

Then 
$$Q = \frac{m_{\text{actual}}}{\rho} = \frac{C \cdot A_t}{\rho \cdot \sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot \Delta p} = \frac{\pi \cdot C \cdot D_t^2}{4 \cdot \rho \cdot \sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot SG_{\text{Hg}} \cdot \rho \cdot g \cdot \Delta h} = \frac{\pi \cdot C \cdot D_t^2}{4 \cdot \sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot SG_{\text{Hg}} \cdot g \cdot \Delta h}$$

$$Q = \frac{\pi}{4 \times \sqrt{1 - 0.5^4}} \times 0.99 \times \left(\frac{1}{4} \cdot \text{ft}\right)^2 \times \sqrt{2 \times 13.6 \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times 1 \cdot \text{ft}} \qquad Q = 1.49 \cdot \frac{\text{ft}^3}{\text{s}}$$

Hence 
$$V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D_1^2} \qquad V = \frac{4}{\pi} \times \frac{1}{\left(\frac{1}{2} \cdot \text{ft}\right)^2} \times 1.49 \cdot \frac{\text{ft}^3}{\text{s}} \qquad V = 7.59 \cdot \frac{\text{ft}}{\text{s}}$$

At 75°F, (Table A.7)  $\nu = 9.96 \times 10^{-6} \cdot \frac{\text{ft}^2}{\text{s}}$

$$Re_{D1} = \frac{V \cdot D_1}{\nu} \qquad Re_{D1} = 7.59 \cdot \frac{\text{ft}}{\text{s}} \times \frac{1}{2} \cdot \text{ft} \times \frac{\text{s}}{9.96 \times 10^{-6} \cdot \text{ft}^2} \qquad Re_{D1} = 3.81 \times 10^5$$

Thus  $Re_{D1} > 2 \times 10^5$ . The volume flow rate is 
$$Q = 1.49 \cdot \frac{\text{ft}^3}{\text{s}}$$

## Problem 8.196

[Difficulty: 2]

**8.196** Consider a horizontal 2 in. × 1 in. venturi with water flow. For a differential pressure of 25 psi, calculate the volume flow rate (gpm).

**Given:** Flow through an venturi meter

**Find:** Flow rate

**Solution:**

Basic equation 
$$m_{\text{actual}} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot (p_1 - p_2)} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot \Delta p}$$
 Note that  $m_{\text{actual}}$  is mass flow rate (the software cannot render a dot!)

For  $Re_{D1} > 2 \times 10^5$ ,  $0.980 < C < 0.995$ . Assume  $C = 0.99$ , then check Re

Available data  $D_1 = 2\text{-in}$        $D_t = 1\text{-in}$        $\Delta p = 25\text{-psi}$        $\rho = 1.94 \frac{\text{slug}}{\text{ft}^3}$

$\beta = \frac{D_t}{D_1}$        $\beta = 0.5$       and assume       $C = 0.99$

Then 
$$Q = \frac{m_{\text{actual}}}{\rho} = \frac{C \cdot A_t}{\rho \cdot \sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot \Delta p}$$

$$Q = \frac{\pi \cdot C \cdot D_t^2}{4 \cdot \sqrt{1 - \beta^4}} \cdot \sqrt{\frac{2 \cdot \Delta p}{\rho}}$$
       $Q = 0.340 \frac{\text{ft}^3}{\text{s}}$        $Q = 152 \cdot \text{gpm}$

Hence  $V = \frac{Q}{A}$        $V = \frac{4 \cdot Q}{\pi \cdot D_1^2}$        $V = 15.6 \frac{\text{ft}}{\text{s}}$

At 68°F (Table A.7)  $\nu = 1.08 \cdot 10^{-5} \frac{\text{ft}^2}{\text{s}}$        $Re_{D1} = \frac{V \cdot D_1}{\nu}$        $Re_{D1} = 2.403 \times 10^5$

Thus  $Re_{D1} > 2 \times 10^5$ . The volume flow rate is  $Q = 152 \cdot \text{gpm}$

8.197 Gasoline flows through a  $2 \times 1$  in. venturi meter. The differential pressure is 380 mm of mercury. Find the volume flow rate.

Solution: Apply the analysis of Section 8-10.3.

Computing equations:

$$m_{actual} = \frac{CA_t}{\sqrt{1-\beta^4}} \sqrt{2\rho(p_1 - p_2)} \quad (8.52)$$

$$C = 0.99 \text{ for } Re_{D_1} > 2 \times 10^5$$

For the manometer,  $\Delta p = \rho_{Hg} g \Delta h = SG_{Hg} \rho_{H_2O} g \Delta h$

Then

$$Q = \frac{m}{\rho} = \frac{CA_t}{\sqrt{1-\beta^4}} \sqrt{\frac{2\Delta p}{\rho}} = \frac{CA_t}{\sqrt{1-\beta^4}} \sqrt{\frac{2SG_{Hg} \rho_{H_2O} g \Delta h}{SG_{gas} \rho_{H_2O}}} = \frac{CA_t}{\sqrt{1-\beta^4}} \sqrt{\frac{2SG_{Hg} g \Delta h}{SG_{gas}}}$$

$$Q = \frac{0.99}{\sqrt{1-(0.5)^4}} \frac{\pi (0.0254)^2 m^2}{4} \sqrt{2 \times \frac{13.6}{0.73} \times \frac{9.81 m}{s^2} \times 0.38 m} = 0.00611 m^3/s$$

Now check Reynolds number:

$$\bar{V}_1 = \frac{Q}{A_1} = \frac{0.00611 m^3/s}{\pi (0.0508)^2 m^2} = 3.01 m/s$$

Assume viscosity midway between octane and heptane at  $20^\circ C$ . From Fig. A.1,

$$\mu \approx 5.0 \times 10^{-4} N \cdot s / m^2$$

$$Re_{D_1} = \frac{\rho \bar{V}_1 D_1}{\mu} = \frac{(0.73) 1000 \frac{kg}{m^3} \times 3.01 \frac{m}{s} \times 0.0508 m}{5.0 \times 10^{-4} N \cdot s / m^2} = 2.23 \times 10^5$$

Thus assumption that  $C = 0.99$  is okay

$$Q = 0.00611 m^3/s$$

Q

## Problem 8.198

[Difficulty: 3]

**8.198** Air flows through the venturi meter described in Problem 8.195. Assume that the upstream pressure is 60 psi, and that the temperature is everywhere constant at 68°F. Determine the maximum possible mass flow rate of air for which the assumption of incompressible flow is a valid engineering approximation. Compute the corresponding differential pressure reading on a mercury manometer.

**Given:** Flow through a venturi meter

**Find:** Maximum flow rate for incompressible flow; Pressure reading

**Solution:**

Basic equation 
$$m_{\text{actual}} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot (p_1 - p_2)} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot \Delta p}$$
 Note that  $m_{\text{actual}}$  is mass flow rate (the software cannot render a dot!)

Assumptions: 1) Neglect density change 2) Use ideal gas equation for density

Then 
$$\rho = \frac{p}{R_{\text{air}} \cdot T} \quad \rho = 60 \cdot \frac{\text{lbf}}{\text{in}^2} \times \left( \frac{12 \cdot \text{in}}{1 \cdot \text{ft}} \right)^2 \times \frac{\text{lbf} \cdot \text{R}}{53.33 \cdot \text{ft} \cdot \text{lbf}} \times \frac{1 \cdot \text{slug}}{32.2 \cdot \text{lbfm}} \cdot \frac{1}{(68 + 460) \cdot \text{F}} \quad \rho = 9.53 \times 10^{-3} \cdot \frac{\text{slug}}{\text{ft}^3}$$

For incompressible flow  $V$  must be less than about 100 m/s or 330 ft/s at the throat. Hence

$$m_{\text{actual}} = \rho \cdot V_2 \cdot A_2 \quad m_{\text{actual}} = 9.53 \times 10^{-3} \frac{\text{slug}}{\text{ft}^3} \times 330 \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} \times \left( \frac{1}{4} \cdot \text{ft} \right)^2 \quad m_{\text{actual}} = 0.154 \cdot \frac{\text{slug}}{\text{s}}$$

$$\beta = \frac{D_t}{D_1} \quad \beta = \frac{3}{6} \quad \beta = 0.5$$

Also 
$$\Delta p = \rho_{\text{Hg}} \cdot g \cdot \Delta h \quad \Delta h = \frac{\Delta p}{\rho_{\text{Hg}} \cdot g}$$

and in addition 
$$\Delta p = \frac{1}{2 \cdot \rho} \cdot \left( \frac{m_{\text{actual}}}{C \cdot A_t} \right)^2 \cdot (1 - \beta^4) \quad \text{so} \quad \Delta h = \frac{(1 - \beta^4)}{2 \cdot \rho \cdot \rho_{\text{Hg}} \cdot g} \cdot \left( \frac{m_{\text{actual}}}{C \cdot A_t} \right)^2$$

For  $Re_{D1} > 2 \times 10^5$ ,  $0.980 < C < 0.995$ . Assume  $C = 0.99$ , then check  $Re$

$$\Delta h = \frac{(1 - 0.5^4)}{2} \times \frac{\text{ft}^3}{9.53 \times 10^{-3} \text{ slug}} \times \frac{\text{ft}^3}{13.6 \cdot 1.94 \cdot \text{slug}} \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \times \left[ 0.154 \frac{\text{slug}}{\text{s}} \times \frac{1}{0.99} \times \frac{4}{\pi} \times \left( \frac{4}{1 \cdot \text{ft}} \right)^2 \right]^2 \quad \Delta h = 6.98 \cdot \text{in}$$

Hence 
$$V = \frac{Q}{A} = \frac{4 \cdot m_{\text{actual}}}{\pi \cdot \rho \cdot D_1^2} \quad V = \frac{4}{\pi} \times \frac{\text{ft}^3}{9.53 \times 10^{-3} \text{ slug}} \times \frac{1}{\left( \frac{1}{2} \cdot \text{ft} \right)^2} \times 0.154 \frac{\text{slug}}{\text{s}} \quad V = 82.3 \cdot \frac{\text{ft}}{\text{s}}$$

At 68°F, (Table A.7) 
$$\nu = 1.08 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$$

$$Re_{D1} = \frac{V \cdot D_1}{\nu} \quad Re_{D1} = 82.3 \cdot \frac{\text{ft}}{\text{s}} \times \frac{1}{2} \cdot \text{ft} \times \frac{\text{s}}{1.08 \times 10^{-5} \cdot \text{ft}^2} \quad Re_{D1} = 3.81 \times 10^6$$

Thus  $Re_{D1} > 2 \times 10^5$ . The mass flow rate is  $m_{\text{actual}} = 0.154 \cdot \frac{\text{slug}}{\text{s}}$  and pressure  $\Delta h = 6.98 \cdot \text{in Hg}$

## Problem 8.199

[Difficulty: 3]

**8.199** Air flow rate in a test of an internal combustion engine is to be measured using a flow nozzle installed in a plenum. The engine displacement is 1.6 liters, and its maximum operating speed is 6000 rpm. To avoid loading the engine, the maximum pressure drop across the nozzle should not exceed 0.25 m of water. The manometer can be read to  $\pm 0.5$  mm of water. Determine the flow nozzle diameter that should be specified. Find the minimum rate of air flow that can be metered to  $\pm 2$  percent using this setup.

Solution: Apply computing equation for flow nozzle.

Computing equation:  $\dot{m} = K A_t \sqrt{2\rho(p_1 - p_2)}$  (8.54)

Assumptions: (1)  $K = 0.97$  (Section 8-10.26.)

(2)  $\beta = 0$  (nozzle inlet is from atmosphere)

(3) Four-stroke cycle engine with 100 percent volumetric efficiency ( $\forall \text{ rev} = \text{displacement} / 2$ )

(4) standard air

Then

$$\dot{m} = \rho Q = 1.23 \frac{\text{kg}}{\text{m}^3} \times \frac{1.6 \text{ L}}{2 \text{ rev}} \times \frac{6000 \text{ rev}}{\text{min}} \times \frac{\text{m}^3}{1000 \text{ L}} \times \frac{\text{min}}{60 \text{ s}} = 0.0984 \text{ kg/s}$$

Solving for  $A_t$ ,

$$A_t = \frac{\dot{m}}{K \sqrt{2\rho \Delta p}} = \frac{\dot{m}}{K \sqrt{2\rho \rho_{H_2O} g \Delta h}}$$

$$A_t = 0.0984 \frac{\text{kg}}{\text{s}} \times \frac{1}{0.97} \left[ \frac{1}{2} \times \frac{\text{m}^3}{1.23 \text{ kg}} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{s}^2}{9.81 \text{ m}} \times \frac{1}{0.25 \text{ m}} \right]^{\frac{1}{2}} = 1.31 \times 10^{-3} \text{ m}^2$$

$$A_t = \frac{\pi D_t^2}{4}; \quad D_t = \sqrt{\frac{4 A_t}{\pi}} = 40.8 \text{ mm}$$

The allowable error is  $\pm 2$  percent, or  $\pm 0.02$ . As discussed in Appendix E, the square-root relationship halves the experimental uncertainty. Thus

$$e = \pm 0.02 \text{ when } e_{\Delta h} = \pm 0.04; \quad \Delta h_{\min} = \frac{\pm 0.5 \text{ mm}}{\pm 0.04} = 12.5 \text{ mm}$$

$$\dot{m}_{\min} \approx \dot{m} \sqrt{\frac{\Delta h_{\min}}{\Delta h}} = 0.0984 \frac{\text{kg}}{\text{s}} \sqrt{\frac{12.5 \text{ mm}}{250 \text{ mm}}} = 0.0220 \text{ kg/s}$$

The air flow rate could be measured with  $\pm 2$  percent accuracy down to about

$$\omega = 6000 \text{ rpm} \frac{0.0220}{0.0984} = 1340 \text{ rpm}$$

with this setup.

## Problem 8.200

[Difficulty: 3]

**8.200** Water at 10°C flows steadily through a venturi. The pressure upstream from the throat is 200 kPa (gage). The throat diameter is 50 mm; the upstream diameter is 100 mm. Estimate the maximum flow rate this device can handle without cavitation.

**Given:** Flow through venturi

**Find:** Maximum flow rate before cavitation

**Solution:**

Basic equation 
$$m_{\text{actual}} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot (p_1 - p_2)} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot \Delta p}$$
 Note that  $m_{\text{actual}}$  is mass flow rate (the software cannot render a dot!)

For  $Re_{D1} > 2 \times 10^5$ ,  $0.980 < C < 0.995$ . Assume  $C = 0.99$ , then check Re

Available data  $D_1 = 100 \cdot \text{mm}$        $D_t = 50 \cdot \text{mm}$        $p_{1g} = 200 \cdot \text{kPa}$        $C = 0.99$       (Assumption - verify later)

$p_{\text{atm}} = 101 \cdot \text{kPa}$        $p_v = 1.23 \cdot \text{kPa}$       Steam tables - saturation pressure at 10°C

$\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$        $\nu = 1.3 \cdot 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$  (Table A.8)

Then  $A_t = \frac{\pi \cdot D_t^2}{4}$        $A_t = 1963 \cdot \text{mm}^2$        $A_1 = \frac{\pi \cdot D_1^2}{4}$        $A_1 = 7854 \cdot \text{mm}^2$

$\beta = \frac{D_t}{D_1}$        $\beta = 0.5$

$p_1 = p_{\text{atm}} + p_{1g}$        $p_1 = 301 \cdot \text{kPa}$

The smallest allowable throat pressure is the saturation pressure  $p_t = p_v$        $p_t = 1.23 \text{ kPa}$

Hence the largest  $\Delta p$  is  $\Delta p = p_1 - p_t$        $\Delta p = 300 \cdot \text{kPa}$

Then  $m_{\text{rate}} = \frac{C \cdot A_t}{\sqrt{1 - \beta^4}} \cdot \sqrt{2 \cdot \rho \cdot \Delta p}$        $m_{\text{rate}} = 49.2 \frac{\text{kg}}{\text{s}}$

$Q = \frac{m_{\text{rate}}}{\rho}$        $Q = 0.0492 \frac{\text{m}^3}{\text{s}}$

$V_1 = \frac{Q}{A_1}$        $V_1 = 6.26 \frac{\text{m}}{\text{s}}$


Check the Re  $Re_1 = \frac{V_1 \cdot D_1}{\nu}$        $Re_1 = 4.81 \times 10^5$

Thus  $Re_{D1} > 2 \times 10^5$ . The volume flow rate is  $Q = 0.0492 \frac{\text{m}^3}{\text{s}}$        $Q = 49.2 \frac{\text{L}}{\text{s}}$

## Problem 8.201

[Difficulty: 1]

**8.201** Derive Eq. 8.42, the pressure loss coefficient for a diffuser assuming ideal (frictionless) flow.



**Given:** Flow through a diffuser

**Find:** Derivation of Eq. 8.42

**Solution:**

Basic equations

$$C_p = \frac{p_2 - p_1}{\frac{1}{2} \cdot \rho \cdot V_1^2} \quad \frac{p_1}{\rho} + \frac{V_1^2}{2} + g \cdot z_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g \cdot z_2 \quad Q = V \cdot A$$

Assumptions: 1) All the assumptions of the Bernoulli equation 2) Horizontal flow 3) No flow separation

From Bernoulli

$$\frac{p_2 - p_1}{\rho} = \frac{V_1^2}{2} - \frac{V_2^2}{2} = \frac{V_1^2}{2} - \frac{V_1^2}{2} \cdot \left( \frac{A_1}{A_2} \right)^2 \quad \text{using continuity}$$

Hence

$$C_p = \frac{p_2 - p_1}{\frac{1}{2} \cdot \rho \cdot V_1^2} = \frac{1}{\frac{1}{2} \cdot \rho \cdot V_1^2} \cdot \left[ \frac{V_1^2}{2} - \frac{V_1^2}{2} \cdot \left( \frac{A_1}{A_2} \right)^2 \right] = 1 - \left( \frac{A_1}{A_2} \right)^2$$

Finally

$$C_p = 1 - \frac{1}{AR^2} \quad \text{which is Eq. 8.42.}$$

This result is not realistic as a real diffuser is very likely to have flow separation


### Problem 8.202

[Difficulty: 4] Part 1/2

**8.202** Consider a flow nozzle installation in a pipe. Apply the basic equations to the control volume indicated, to show that the permanent head loss across the meter can be expressed, in dimensionless form, as the head loss coefficient,

$$C_l = \frac{p_1 - p_3}{p_1 - p_2} = \frac{1 - A_2/A_1}{1 + A_2/A_1}$$

Plot  $C_l$  as a function of diameter ratio,  $D_2/D_1$ .



Solution: Apply the Bernoulli, continuity, momentum and energy equations, using the CV shown.

Basic equations:

$$\frac{p_1}{\rho} + \frac{\bar{V}_1^2}{2} + g z_1^{\uparrow} = \frac{p_2}{\rho} + \frac{\bar{V}_2^2}{2} + g z_2^{\uparrow} \quad (4)$$

$$0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \bar{V} \cdot d\bar{A}$$

$$F_{Sx} + F_{Bx}^{\uparrow} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \bar{V} \cdot d\bar{A}$$

$$\dot{Q} + \dot{W}_S^{\uparrow} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} \left( u + \frac{\bar{V}^2}{2} + g z^{\uparrow} + \frac{p}{\rho} \right) \rho \bar{V} \cdot d\bar{A} \quad (4)$$

- Assumptions:
- (1) Steady flow
  - (2) Incompressible flow
  - (3) No friction between ① and ②
  - (4) Neglect elevation terms
  - (5)  $F_{Bx} = 0$
  - (6)  $\dot{W}_S = 0$
  - (7) Uniform flow at each section

From continuity,

$$Q = \bar{V}_1 A_1 = \bar{V}_2 A_2 = \bar{V}_3 A_3$$

Apply Bernoulli along a streamline from ① to ②, noting  $A_1 = A_3$ ,

$$\frac{p_1 - p_2}{\rho} = \frac{\bar{V}_2^2 - \bar{V}_1^2}{2} = \frac{\bar{V}_2^2}{2} \left[ 1 - \left( \frac{A_2}{A_1} \right)^2 \right] = \frac{\bar{V}_2^2}{2} \left[ 1 - \left( \frac{A_2}{A_3} \right)^2 \right]$$

From momentum, and using continuity,

$$F_{Sx} = p_2 A_1 - p_3 A_3 = \bar{V}_2 \{ -\rho \bar{V}_2 A_2 \} + \bar{V}_3 \{ +\rho \bar{V}_3 A_3 \} = (\bar{V}_3 - \bar{V}_2) \rho \bar{V}_3 A_3$$

$$\text{or } \frac{p_3 - p_2}{\rho} = \bar{V}_3 (\bar{V}_2 - \bar{V}_3) = \bar{V}_2 \frac{A_2}{A_3} \left[ \bar{V}_2 - \bar{V}_2 \frac{A_2}{A_3} \right] = \bar{V}_2^2 \frac{A_2}{A_3} \left( 1 - \frac{A_2}{A_3} \right)$$

From energy,

$$\dot{Q} = \left( u_2 + \frac{\bar{V}_2^2}{2} + \frac{p_2}{\rho} \right) \{ -\rho \bar{V}_2 A_2 \} + \left( u_3 + \frac{\bar{V}_3^2}{2} + \frac{p_3}{\rho} \right) \{ \rho \bar{V}_3 A_3 \}$$

### Problem 8.202

[Difficulty: 4] Part 2/2

$$\text{or } h_{e23} = u_3 - u_2 - \frac{\dot{Q}}{m} = \frac{\bar{V}_2^2 - \bar{V}_3^2}{2} - \frac{p_3 - p_2}{\rho} = \frac{\bar{V}_2^2}{2} \left[ 1 - \left( \frac{A_2}{A_3} \right)^2 \right] - \frac{p_3 - p_2}{\rho}$$

But  $h_{e12} \approx 0$  by assumption (3), so  $h_{e13} \approx h_{e23}$  and using momentum

$$h_{e13} \approx \frac{\bar{V}_2^2}{2} \left[ 1 - \left( \frac{A_2}{A_3} \right)^2 \right] - \bar{V}_2^2 \frac{A_2}{A_3} \left( 1 - \frac{A_2}{A_3} \right)$$

After a little algebra, this may be written

$$h_{e13} \approx \frac{\bar{V}_2^2}{2} \left( 1 - \frac{A_2}{A_3} \right)^2$$

Dividing by  $(p_1 - p_2)/\rho$ , a loss coefficient is derived as


$$C_L = \frac{h_{e13}}{(p_1 - p_2)/\rho} = \frac{\frac{\bar{V}_2^2}{2} \left( 1 - \frac{A_2}{A_3} \right)^2}{\frac{\bar{V}_2^2}{2} \left[ 1 - \left( \frac{A_2}{A_3} \right)^2 \right]} = \frac{\left( 1 - A_2/A_3 \right)^2}{\left[ 1 - \left( A_2/A_3 \right)^2 \right]}$$

But  $1 - \left( \frac{A_2}{A_3} \right)^2 = \left( 1 + \frac{A_2}{A_3} \right) \left( 1 - \frac{A_2}{A_3} \right)$ , so

$$C_L = \frac{h_{e13}}{(p_1 - p_2)/\rho} = \frac{1 - A_2/A_3}{1 + A_2/A_3}$$

$C_L$


Plotting:



## Problem 8.203

[Difficulty: 3]

**8.203** Drinking straws are to be used to improve the air flow in a pipe-flow experiment. Packing a section of the air pipe with drinking straws to form a "laminar flow element" might allow the air flow rate to be measured directly, and simultaneously would act as a flow straightener. To evaluate this idea, determine (a) the Reynolds number for flow in each drinking straw, (b) the friction factor for flow in each straw, and (c) the gage pressure at the exit from the drinking straws. (For laminar flow in a tube, the entrance loss coefficient is  $K_{ent} = 1.4$  and  $\alpha = 2.0$ .) Comment on the utility of this idea.



Solution: Apply energy equation for steady, incompressible pipe flow.

Computing equation:

$$\frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g z_1 \stackrel{\approx 0(1)}{=} \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g z_2 + h_{LT}$$

$$h_{LT} = h_L + h_{em} = f \frac{L}{D} \frac{\bar{V}^2}{2} + K_{ent} \frac{\bar{V}^2}{2} = \left( f \frac{L}{D} + K_{ent} \right) \frac{\bar{V}^2}{2}$$

Assumptions: (1) Flow from atmosphere;  $p_1 = p_{atm}$ ,  $\bar{V}_1 \approx 0$   
 (2) Horizontal.  
 (3) Neglect thickness of straws

Then 
$$\bar{V}_2 = \frac{Q}{A} = \frac{100 \text{ m}^3/\text{hr}}{\pi (0.0635)^2 \text{ m}^2} \times \frac{\text{hr}}{3600 \text{ s}} = 8.77 \text{ m/s}$$

$$Re_d = \frac{\bar{V}_2 d}{\nu} = \frac{8.77 \text{ m}}{\text{sec}} \times 0.003 \text{ m} \times \frac{\text{sec}}{1.46 \times 10^{-5} \text{ m}^2} = 1800$$

For laminar flow,

$$f = \frac{64}{Re} = \frac{64}{1800} = 0.0356$$

The gage pressure at (2) is

$$p_{2g} = -\rho \frac{\bar{V}_2^2}{2} \left( \alpha_2 + K_{ent} + f \frac{L}{D} \right)$$

$$= -\frac{1}{2} \times 1.23 \frac{\text{kg}}{\text{m}^3} \times (8.77)^2 \frac{\text{m}^2}{\text{s}^2} \left( 2.0 + 1.4 + 0.0356 \times \frac{230 \text{ mm}}{3 \text{ mm}} \right) \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}}$$

$$p_{2g} = -290 \text{ N/m}^2 \text{ (gage)}$$

This pressure drop is equivalent to


$$\Delta h = \frac{\Delta p}{\rho_{H_2O} g} = \frac{290 \text{ N}}{\text{m}^2} \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{\text{s}^2}{9.81 \text{ m}} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} = 29.6 \text{ mm H}_2\text{O}$$

Comments: (1) This pressure drop is large enough to measure readily. The straws could be used as a flowmeter.  
 (2) Straws would eliminate any swirl from the flow.

**8.204** In some western states, water for mining and irrigation was sold by the "miner's inch," the rate at which water flows through an opening in a vertical plank of 1 in.<sup>2</sup> area, up to 4 in. tall, under a head of 6 to 9 in. Develop an equation to predict the flow rate through such an orifice. Specify clearly the aspect ratio of the opening, thickness of the plank, and

datum level for measurement of head (top, bottom, or middle of the opening). Show that the unit of measure varies from 38.4 (in Colorado) to 50 (in Arizona, Idaho, Nevada, and Utah) miner's inches equal to 1 ft<sup>3</sup>/s.

**Analysis:** The geometry of the opening in a vertical plank is shown. The analysis includes the effect on flow speed of the variation in water depth vertically across the opening.



Aspect ratio,  $ar \equiv \frac{H_0}{w}$ ; area,  $A = wH_0 = 1 \text{ in.}^2$   
 $\alpha = 0, 1/2, 1$

$$Q_{geom} = \int v dA = \int_a^b \sqrt{2gy} w dy = w \sqrt{2g} \left[ \frac{2}{3} y^{3/2} \right]_a^b = \frac{2}{3} w a \sqrt{2g} \left[ \left( \frac{b}{a} \right)^{3/2} - 1 \right]$$

For  $ar = 1$ ,  $\alpha = 0$ ,  $a = H = 9 \text{ in.}$ ,  $b = 10.0 \text{ in.}$ ,  $w = 1.0 \text{ in.}$

$$Q_{geom} = \frac{2}{3} \times 1.0 \text{ in.} \times 9 \text{ in.} \left[ 2 \times 32.2 \frac{\text{ft}}{\text{s}^2} \times 9 \text{ in.} \times \frac{\text{ft}}{12 \text{ in.}} \right]^{1/2} \left[ \left( \frac{10}{9} \right)^{3/2} - 1 \right] \frac{\text{ft}^3}{144 \text{ in.}^2} = 0.0496 \frac{\text{ft}^3}{\text{s}}$$

$$Q_{actual} = 0.6 Q_{geom} = 0.0297 \text{ ft}^3/\text{s}; \text{ thus } 1/0.0297 = 33.6 \text{ MI} = 1 \text{ cfs}$$

MI

Numerical results are presented in the spread sheet on the next page.

**Discussion:** All results assume a *vena contracta* in the liquid jet leaving the opening, reducing the effective flow area to 60 percent of the geometric area of the opening.

The calculated unit of measure varies from 31.3 to 52.4 miner's inch per cubic foot of water flow per second. This range encompasses the 38.4 and 50 values given in the problem statement.

Trends may be summarized as follows. The largest flow rate occurs when datum  $H$  is measured to the top of the opening in the vertical plank. This gives the deepest submergence and thus the highest flow speeds through the opening.

When  $ar = 1$ , the opening is square; when  $ar = 16$ , the opening is 4 inches tall and 1/4 inch wide. Increasing  $ar$  from 1 to 16 increases the flow rate through the opening when  $H$  is measured to the top of the opening, because it increases the submergence of the lower portion of the opening, thus increasing the flow speeds. When  $H$  is measured to the center of the opening  $ar$  has almost no effect on flow rate. When  $H$  is measured to the bottom of the opening, increasing  $ar$  reduces the flow rate. For this case, the depth of the opening decreases as  $ar$  becomes larger.

Plank thickness does not affect calculated flow rates since a *vena contracta* is assumed. In this flow model, water separates from the interior edges of the opening in the vertical plank. Only if the plank were several inches thick might the stream reattach and affect the flow rate.

The actual relationship between  $Q_{flow}$  and  $Q_{geom}$  might be a weak function of aspect ratio. The flow separates from all four edges of the opening in the vertical plank. At large  $ar$ , contraction on the narrow ends of the stream has a relatively small effect on flow area. As  $ar$  approaches 1 the effect becomes more pronounced, but would need to be measured experimentally. Assuming a constant 60 percent area fraction certainly gives reasonable trends.





# Problem 8.205

[Difficulty: 5] Part 2/2

$$V_{\text{bar}}/U = 0.817$$

$$n = 7$$


$k =$  Number of measurement points

**Case 1:** Measure at centerline plus  
at  $(k - 1)$  other locations

**Case 2:** Measure at  $k$  locations  
not including the centerline

$k$	$i$	$r_i/R$	$u/U$	$u/V_{\text{bar}}$	(%) Error	$k$	$i$	$r_i/R$	$u/U$	$u/V_{\text{bar}}$	(%) Error
1	1	0.000	1.000	1.22	22.4	1	1	0.707	0.839	1.03	2.7
2	1	0.000	1.000	1.22	7.2	2	1	0.500	0.906	1.11	1.4
	2	0.866	0.750	0.92			0.866	0.750	0.92		
3	1	0.000	1.000	1.22	3.9	3	1	0.408	0.928	1.14	0.9
	2	0.707	0.839	1.03			0.707	0.839	1.03		
	3	0.913	0.706	0.864			0.913	0.706	0.86		
4	1	0.000	1.000	1.22	2.5	4	1	0.354	0.940	1.15	0.7
	2	0.612	0.873	1.07			0.612	0.873	1.07		
	3	0.791	0.800	0.98			0.791	0.800	0.98		
	4	0.935	0.676	0.828			0.935	0.676	0.83		
5	1	0.000	1.000	1.22	1.8	5	1	0.316	0.947	1.16	0.5
	2	0.548	0.893	1.09			0.548	0.893	1.09		
	3	0.707	0.839	1.03			0.707	0.839	1.03		
	4	0.837	0.772	0.945			0.837	0.772	0.95		
	5	0.949	0.654	0.801			0.949	0.654	0.80		

$k$	Case 1 e (%)	Case 2 e (%)
1	22.4	2.7
2	7.2	1.4
3	3.9	0.9
4	2.5	0.7
5	1.8	0.5



13-788  
 13-789  
 13-790  
 13-791  
 13-792  
 13-793  
 13-794  
 13-795  
 13-796  
 13-797  
 13-798  
 13-799  
 13-800  
 13-801  
 13-802  
 13-803  
 13-804  
 13-805  
 13-806  
 13-807  
 13-808  
 13-809  
 13-810  
 13-811  
 13-812  
 13-813  
 13-814  
 13-815  
 13-816  
 13-817  
 13-818  
 13-819  
 13-820  
 13-821  
 13-822  
 13-823  
 13-824  
 13-825  
 13-826  
 13-827  
 13-828  
 13-829  
 13-830  
 13-831  
 13-832  
 13-833  
 13-834  
 13-835  
 13-836  
 13-837  
 13-838  
 13-839  
 13-840  
 13-841  
 13-842  
 13-843  
 13-844  
 13-845  
 13-846  
 13-847  
 13-848  
 13-849  
 13-850  
 13-851  
 13-852  
 13-853  
 13-854  
 13-855  
 13-856  
 13-857  
 13-858  
 13-859  
 13-860  
 13-861  
 13-862  
 13-863  
 13-864  
 13-865  
 13-866  
 13-867  
 13-868  
 13-869  
 13-870  
 13-871  
 13-872  
 13-873  
 13-874  
 13-875  
 13-876  
 13-877  
 13-878  
 13-879  
 13-880  
 13-881  
 13-882  
 13-883  
 13-884  
 13-885  
 13-886  
 13-887  
 13-888  
 13-889  
 13-890  
 13-891  
 13-892  
 13-893  
 13-894  
 13-895  
 13-896  
 13-897  
 13-898  
 13-899  
 13-900  
 13-901  
 13-902  
 13-903  
 13-904  
 13-905  
 13-906  
 13-907  
 13-908  
 13-909  
 13-910  
 13-911  
 13-912  
 13-913  
 13-914  
 13-915  
 13-916  
 13-917  
 13-918  
 13-919  
 13-920  
 13-921  
 13-922  
 13-923  
 13-924  
 13-925  
 13-926  
 13-927  
 13-928  
 13-929  
 13-930  
 13-931  
 13-932  
 13-933  
 13-934  
 13-935  
 13-936  
 13-937  
 13-938  
 13-939  
 13-940  
 13-941  
 13-942  
 13-943  
 13-944  
 13-945  
 13-946  
 13-947  
 13-948  
 13-949  
 13-950  
 13-951  
 13-952  
 13-953  
 13-954  
 13-955  
 13-956  
 13-957  
 13-958  
 13-959  
 13-960  
 13-961  
 13-962  
 13-963  
 13-964  
 13-965  
 13-966  
 13-967  
 13-968  
 13-969  
 13-970  
 13-971  
 13-972  
 13-973  
 13-974  
 13-975  
 13-976  
 13-977  
 13-978  
 13-979  
 13-980  
 13-981  
 13-982  
 13-983  
 13-984  
 13-985  
 13-986  
 13-987  
 13-988  
 13-989  
 13-990  
 13-991  
 13-992  
 13-993  
 13-994  
 13-995  
 13-996  
 13-997  
 13-998  
 13-999  
 14-000



## Problem 9.1

[Difficulty: 2]

**9.1** The roof of a minivan is approximated as a horizontal flat plate. Plot the length of the laminar boundary layer as a function of minivan speed,  $V$ , as the minivan accelerates from 10 mph to 90 mph.

**Given:** Minivan traveling at various speeds

**Find:** Plot of boundary layer length as function of speed

**Solution:**

Governing equations:

The critical Reynolds number for transition to turbulence is

$$Re_{crit} = \rho V L_{crit} / \mu = 500000$$

The critical length is then


$$L_{crit} = 500000 \mu / V \rho$$

Tabulated or graphical data:

$$\begin{aligned} \mu &= 3.79\text{E-}07 && \text{lb}\cdot\text{s}/\text{ft}^2 \\ \rho &= 0.00234 && \text{slug}/\text{ft}^3 \\ &&& (\text{Table A.9, } 68^\circ\text{F}) \end{aligned}$$

Computed results:

$V$ (mph)	$L_{crit}$ (ft)
10	5.52
13	4.42
15	3.68
18	3.16
20	2.76
30	1.84
40	1.38
50	1.10
60	0.920
70	0.789
80	0.690
90	0.614



## Problem 9.2

[Difficulty: 2]

**9.2** A model of a river towboat is to be tested at 1:18 scale. The boat is designed to travel at 3.5 m/s in fresh water at 10°C. Estimate the distance from the bow where transition occurs. Where should transition be stimulated on the model towboat?

**Given:** Model of riverboat

**Find:** Distance at which transition occurs

**Solution:**

Basic equation  $Re_x = \frac{\rho \cdot U \cdot x}{\mu} = \frac{U \cdot x}{\nu}$  and transition occurs at about  $Re_x = 5 \times 10^5$

For water at 10°C  $\nu = 1.30 \times 10^{-6} \frac{m^2}{s}$  (Table A.8) and we are given  $U = 3.5 \frac{m}{s}$

Hence  $x_p = \frac{\nu \cdot Re_x}{U}$   $x_p = 0.186 \text{ m}$   $x_p = 18.6 \text{ cm}$

For the model  $x_m = \frac{x_p}{18}$   $x_m = 0.0103 \text{ m}$   $x_m = 10.3 \text{ mm}$

## Problem 9.3

[Difficulty: 3]

**9.3** The takeoff speed of a Boeing 757 is 160 mph. At approximately what distance will the boundary layer on the wings become turbulent? If it cruises at 530 mph at 33,000 ft, at approximately what distance will the boundary layer on the wings become turbulent?

**Given:** Boeing 757

**Find:** Point at which BL transition occurs during takeoff and at cruise

**Solution:**

Basic equation  $Re_x = \frac{\rho \cdot U \cdot x}{\mu} = \frac{U \cdot x}{\nu}$  and transition occurs at about  $Re_x = 5 \times 10^5$

For air at 68°F  $\nu = 1.62 \times 10^{-4} \cdot \frac{ft^2}{s}$  (Table A.9) and we are given  $U = 160 \cdot \frac{mi}{hr} = 234.7 \cdot \frac{ft}{s}$

Hence  $x_p = \frac{\nu \cdot Re_x}{U}$   $x_p = 0.345 \cdot ft$   $x_p = 4.14 \cdot in$

At 33,000 ft  $T = 401.9 \cdot R$  (Intepolating from Table A.3)  $T = -57.8 \cdot ^\circ F$

We need to estimate  $\nu$  or  $\mu$  at this temperature. From Appendix A-3

$$\mu = \frac{b \cdot \sqrt{T}}{1 + \frac{S}{T}} \quad b = 1.458 \times 10^{-6} \cdot \frac{kg}{m \cdot s \cdot K^2} \quad S = 110.4 \cdot K$$

Hence  $\mu = \frac{b \cdot \sqrt{T}}{1 + \frac{S}{T}}$   $\mu = 1.458 \times 10^{-5} \cdot \frac{N \cdot s}{m^2}$   $\mu = 3.045 \times 10^{-7} \cdot \frac{lbf \cdot s}{ft^2}$

For air at 10,000 m (Table A.3)

$$\frac{\rho}{\rho_{SL}} = 0.3376 \quad \rho_{SL} = 0.002377 \cdot \frac{slug}{ft^3} \quad \rho = 0.3376 \cdot \rho_{SL} \quad \rho = 8.025 \times 10^{-4} \cdot \frac{slug}{ft^3}$$

$\nu = \frac{\mu}{\rho}$   $\nu = 3.79 \times 10^{-4} \cdot \frac{ft^2}{s}$  and we are given  $U = 530 \cdot \frac{mi}{hr}$

Hence  $x_p = \frac{\nu \cdot Re_x}{U}$   $x_p = 0.244 \cdot ft$   $x_p = 2.93 \cdot in$

## Problem 9.4

[Difficulty: 2]

**9.4** A student is to design an experiment involving dragging a sphere through a tank of fluid to illustrate (a) “creeping flow” ( $Re_D < 1$ ) and (b) flow for which the boundary layer becomes turbulent ( $Re_D \approx 2.5 \times 10^5$ ). She proposes to use a smooth sphere of diameter 1 cm in SAE 10 oil at room temperature. Is this realistic for both cases? If either case is unrealistic, select an alternative reasonable sphere diameter and common fluid for that case.

**Given:** Experiment with 1 cm diameter sphere in SAE 10 oil

**Find:** Reasonableness of two flow extremes

**Solution:**

Basic equation  $Re_D = \frac{\rho \cdot U \cdot D}{\mu} = \frac{U \cdot D}{\nu}$  and transition occurs at about  $Re_D = 2.5 \times 10^5$

For SAE 10  $\nu = 1.1 \times 10^{-4} \frac{m^2}{s}$  (Fig. A.3 at 20°C) and  $D = 1 \text{ cm}$

For  $Re_D = 1$  we find  $U = \frac{\nu \cdot Re_D}{D} = 0.011 \frac{m}{s}$   $U = 1.10 \frac{cm}{s}$  which is reasonable

For  $Re_D = 2.5 \times 10^5$   $U = \frac{\nu \cdot Re_D}{D} = 2750 \frac{m}{s}$  which is much too high!

Note that for  $Re_D = 2.5 \times 10^5$  we need to increase the sphere diameter  $D$  by a factor of about 1000, or reduce the viscosity  $\nu$  by the same factor, or some combination of these. One possible solution is

For water  $\nu = 1.01 \times 10^{-6} \frac{m^2}{s}$  (Table A.8 at 20°C) and  $D = 10 \text{ cm}$

For  $Re_D = 2.5 \times 10^5$  we find  $U = \frac{\nu \cdot Re_D}{D} = 2.52 \frac{m}{s}$  which is reasonable

Hence one solution is to use a 10 cm diameter sphere in a water tank.

## Problem 9.5

[Difficulty: 2]

**9.5** For flow around a sphere the boundary layer becomes turbulent around  $Re_D \approx 2.5 \times 10^5$ . Find the speeds at which (a) an American golf ball ( $D = 1.68$  in.), (b) a British golf ball ( $D = 41.1$  mm), and (c) a soccer ball ( $D = 8.75$  in.) develop turbulent boundary layers. Assume standard atmospheric conditions.

**Given:** Flow around American and British golf balls, and soccer ball

**Find:** Speed at which boundary layer becomes turbulent

**Solution:**

Basic equation  $Re_D = \frac{\rho \cdot U \cdot D}{\mu} = \frac{U \cdot D}{\nu}$  and transition occurs at about  $Re_D = 2.5 \times 10^5$

For air  $\nu = 1.62 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$  (Table A.9)

For the American golf ball  $D = 1.68 \cdot \text{in}$  Hence  $U = \frac{\nu \cdot Re_D}{D}$   $U = 289 \cdot \frac{\text{ft}}{\text{s}}$   $U = 197 \cdot \text{mph}$   $U = 88.2 \cdot \frac{\text{m}}{\text{s}}$

For the British golf ball  $D = 41.1 \cdot \text{mm}$  Hence  $U = \frac{\nu \cdot Re_D}{D}$   $U = 300 \cdot \frac{\text{ft}}{\text{s}}$   $U = 205 \cdot \text{mph}$   $U = 91.5 \cdot \frac{\text{m}}{\text{s}}$

For soccer ball  $D = 8.75 \cdot \text{in}$  Hence  $U = \frac{\nu \cdot Re_D}{D}$   $U = 55.5 \cdot \frac{\text{ft}}{\text{s}}$   $U = 37.9 \cdot \text{mph}$   $U = 16.9 \cdot \frac{\text{m}}{\text{s}}$

## Problem 9.6

[Difficulty: 2]

**9.6** 1 m × 2 m sheet of plywood is attached to the roof of your vehicle after being purchased at the hardware store. At what speed (in kilometers per hour, in 20°C air) will the boundary layer first start becoming turbulent? At what speed is about 90 percent of the boundary layer turbulent?

**Given:** Sheet of plywood attached to the roof of a car

**Find:** Speed at which boundary layer becomes turbulent; Speed at which 90% is turbulent

**Solution:**

Basic equation  $Re_x = \frac{\rho \cdot U \cdot x}{\mu} = \frac{U \cdot x}{\nu}$  and transition occurs at about  $Re_x = 5 \times 10^5$

For air  $\nu = 1.50 \times 10^{-5} \frac{m^2}{s}$  (Table A.10)

Now if we assume that we orient the plywood such that the longer dimension is parallel to the motion of the car, we can say:  $x = 2 \cdot m$

Hence  $U = \frac{\nu \cdot Re_x}{x}$   $U = 3.8 \cdot \frac{m}{s}$   $U = 13.50 \cdot \frac{km}{hr}$

When 90% of the boundary layer is turbulent  $x = 0.1 \times 2 \cdot m$  Hence  $U = \frac{\nu \cdot Re_x}{x}$   $U = 37.5 \cdot \frac{m}{s}$   $U = 135.0 \cdot \frac{km}{hr}$

## Problem 9.7

[Difficulty: 2]

**9.7** Plot on one graph the length of the laminar boundary layer on a flat plate, as a function of freestream velocity, for (a) water and standard air at (b) sea level and (c) 10 km altitude. Use log-log axes, and compute data for the boundary-layer length ranging from 0.01 m to 10 m.

**Given:** Laminar boundary layer (air & water)

**Find:** Plot of boundary layer length as function of speed (at various altitudes for air)

**Solution:**

Governing equations:

The critical Reynolds number for transition to turbulence is

$$Re_{crit} = UL_{crit}/\mu = 500000$$

The critical length is then

$$L_{crit} = 500000\mu/U\rho$$

For air at sea level and 10 km, we can use tabulated data for density  $\rho$  from Table A.3.

For the viscosity  $\mu$ , use the Sutherland correlation (Eq. A.1)

$$\mu = bT^{1/2}/(1+S/T)$$

$$b = 1.46\text{E-}06 \text{ kg/m}\cdot\text{s}\cdot\text{K}^{1/2}$$

$$S = 110.4 \text{ K}$$

Air (sea level,  $T = 288.2 \text{ K}$ ):

$$\rho = 1.225 \text{ kg/m}^3$$

(Table A.3)

$$\mu = 1.79\text{E-}05 \text{ N}\cdot\text{s/m}^2$$

(Sutherland)

Air (10 km,  $T = 223.3 \text{ K}$ ):

$$\rho = 0.414 \text{ kg/m}^3$$

(Table A.3)

$$\mu = 1.46\text{E-}05 \text{ N}\cdot\text{s/m}^2$$

(Sutherland)

Water (20°C):


$$\rho = 998 \text{ slug/ft}^3$$

$$\mu = 1.01\text{E-}03 \text{ N}\cdot\text{s/m}^2$$

(Table A.8)

Computed results:

$U$ (m/s)	Water $L_{crit}$ (m)	Air (Sea level) $L_{crit}$ (m)	Air (10 km) $L_{crit}$ (m)
0.05	10.12	146.09	352.53
0.10	5.06	73.05	176.26
0.5	1.01	14.61	35.25
1.0	0.506	7.30	17.63
5.0	0.101	1.46	3.53
15	0.0337	0.487	1.18
20	0.0253	0.365	0.881
25	0.0202	0.292	0.705
30	0.0169	0.243	0.588
50	0.0101	0.146	0.353
100	0.00506	0.0730	0.176
200	0.00253	0.0365	0.0881
1000	0.00051	0.0073	0.0176



## Problem 9.8

[Difficulty: 2]

---

**9.8** The extent of the laminar boundary layer on the surface of an aircraft or missile varies with altitude. For a given speed, will the laminar boundary-layer length increase or decrease with altitude? Why? Plot the ratio of laminar boundary-layer length at altitude  $z$ , to boundary-layer length at sea level, as a function of  $z$ , up to altitude  $z = 30$  km, for a standard atmosphere.

---

**Given:** Aircraft or missile at various altitudes

**Find:** Plot of boundary layer length as function of altitude

**Solution:**

Governing equations:

The critical Reynolds number for transition to turbulence is

$$Re_{\text{crit}} = \rho U L_{\text{crit}} / \mu = 500000$$

The critical length is then

$$L_{\text{crit}} = 500000 \mu / U \rho$$

Let  $L_0$  be the length at sea level (density  $\rho_0$  and viscosity  $\mu_0$ ). Then

$$L_{\text{crit}} / L_0 = (\mu / \mu_0) / (\rho / \rho_0)$$

The viscosity of air increases with temperature so generally decreases with elevation; the density also decreases with elevation, but much more rapidly.

Hence we expect that the length ratio increases with elevation

For the density  $\rho$ , we use data from Table A.3.

For the viscosity  $\mu$ , we use the Sutherland correlation (Eq. A.1)


$$\mu = b T^{1/2} / (1 + S/T)$$

$$b = 1.46 \text{E-}06 \text{ kg/m.s.K}^{1/2}$$

$$S = 110.4 \text{ K}$$

Computed results:

$z$ (km)	$T$ (K)	$\rho/\rho_0$	$\mu/\mu_0$	$L_{crit}/L_0$
0.0	288.2	1.0000	1.000	1.000
0.5	284.9	0.9529	0.991	1.04
1.0	281.7	0.9075	0.982	1.08
1.5	278.4	0.8638	0.973	1.13
2.0	275.2	0.8217	0.965	1.17
2.5	271.9	0.7812	0.955	1.22
3.0	268.7	0.7423	0.947	1.28
3.5	265.4	0.7048	0.937	1.33
4.0	262.2	0.6689	0.928	1.39
4.5	258.9	0.6343	0.919	1.45
5.0	255.7	0.6012	0.910	1.51
6.0	249.2	0.5389	0.891	1.65
7.0	242.7	0.4817	0.872	1.81
8.0	236.2	0.4292	0.853	1.99
9.0	229.7	0.3813	0.834	2.19
10.0	223.3	0.3376	0.815	2.41
11.0	216.8	0.2978	0.795	2.67
12.0	216.7	0.2546	0.795	3.12
13.0	216.7	0.2176	0.795	3.65
14.0	216.7	0.1860	0.795	4.27
15.0	216.7	0.1590	0.795	5.00
16.0	216.7	0.1359	0.795	5.85
17.0	216.7	0.1162	0.795	6.84
18.0	216.7	0.0993	0.795	8.00
19.0	216.7	0.0849	0.795	9.36
20.0	216.7	0.0726	0.795	10.9
22.0	218.6	0.0527	0.800	15.2
24.0	220.6	0.0383	0.806	21.0
26.0	222.5	0.0280	0.812	29.0
28.0	224.5	0.0205	0.818	40.0
30.0	226.5	0.0150	0.824	54.8



## Problem 9.9

[Difficulty: 2]

**9.9** The most general sinusoidal velocity profile for laminar boundary-layer flow on a flat plate is  $u = A \sin(By) + C$ . State three boundary conditions applicable to the laminar boundary-layer velocity profile. Evaluate constants  $A$ ,  $B$ , and  $C$ .

**Given:** Sinusoidal velocity profile for laminar boundary layer:

$$u = A \sin(By) + C$$

**Find:** (a) Three boundary conditions applicable to this profile  
(b) Constants  $A$ ,  $B$ , and  $C$ .

**Solution:** For the boundary layer, the following conditions apply:

$$u = 0 \quad \text{at} \quad y = 0 \quad (\text{no slip condition})$$

$$u = U \quad \text{at} \quad y = \delta \quad (\text{continuity with freestream})$$

$$\frac{\partial u}{\partial y} = 0 \quad \text{at} \quad y = \delta \quad (\text{no shear stress at freestream})$$

Applying these boundary conditions:


$$(1) \quad u(0) = A \sin(0) + C = 0 \quad C = 0$$

$$(2) \quad u(\delta) = A \sin(B \cdot \delta) = U$$

$$(3) \quad \frac{\partial u}{\partial y} = A \cdot B \cdot \cos(B \cdot y) \quad \text{Thus:} \quad \frac{\partial}{\partial y} u(\delta) = A \cdot B \cdot \cos(B \cdot \delta) = 0 \quad \text{Therefore:} \quad B \cdot \delta = \frac{\pi}{2} \quad \text{or} \quad B = \frac{\pi}{2 \cdot \delta}$$

$$\text{Back into (2):} \quad A \cdot \sin\left(\frac{\pi}{2} \cdot \delta\right) = U \quad \text{Therefore:} \quad A = U$$

$$\text{So the expression for the velocity profile is:} \quad u = U \cdot \sin\left(\frac{\pi}{2} \cdot \frac{y}{\delta}\right)$$



## Problem 9.10

[Difficulty: 2]

**9.10** Velocity profiles in laminar boundary layers often are approximated by the equations

$$\text{Linear : } \frac{u}{U} = \frac{y}{\delta}$$

$$\text{Sinusoidal : } \frac{u}{U} = \sin\left(\frac{\pi y}{2\delta}\right)$$


$$\text{Parabolic : } \frac{u}{U} = 2\left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$$

Compare the shapes of these velocity profiles by plotting  $y/\delta$  (on the ordinate) versus  $u/U$  (on the abscissa).

**Given:** Linear, sinusoidal, and parabolic velocity profiles

**Find:** Plots of  $y/\delta$  vs  $u/U$  for all three profiles

**Solution:** Here are the profiles:



## Problem 9.11

[Difficulty: 2]

**9.11** An approximation for the velocity profile in a laminar boundary layer is

$$\frac{u}{U} = \frac{3}{2} \frac{y}{\delta} - \frac{1}{2} \left( \frac{y}{\delta} \right)^3$$

Does this expression satisfy boundary conditions applicable to the laminar boundary-layer velocity profile? Evaluate  $\delta^*/\delta$  and  $\theta/\delta$ .

**Given:** Laminar boundary layer profile

**Find:** If it satisfies BC's; Evaluate  $\delta^*/\delta$  and  $\theta/\delta$

**Solution:**

The boundary layer equation is  $\frac{u}{U} = \frac{3}{2} \frac{y}{\delta} - \frac{1}{2} \left( \frac{y}{\delta} \right)^3$  for which  $u = U$  at  $y = \delta$

The BC's are  $u(0) = 0 \quad \left. \frac{du}{dy} \right|_{y=\delta} = 0$

At  $y = 0$   $\frac{u}{U} = \frac{3}{2}(0) - \frac{1}{2}(0)^3 = 0$

At  $y = \delta$   $\left. \frac{du}{dy} \right|_{y=\delta} = U \left( \frac{3}{2} \frac{1}{\delta} - \frac{3}{2} \frac{y^2}{\delta^3} \right) \Big|_{y=\delta} = U \left( \frac{3}{2} \frac{1}{\delta} - \frac{3}{2} \frac{\delta^2}{\delta^3} \right) = 0$

For  $\delta^*$ :  $\delta^* = \int_0^{\infty} \left( 1 - \frac{u}{U} \right) dy = \int_0^{\delta} \left( 1 - \frac{u}{U} \right) dy$

Then  $\frac{\delta^*}{\delta} = \frac{1}{\delta} \int_0^{\delta} \left( 1 - \frac{u}{U} \right) dy = \int_0^1 \left( 1 - \frac{u}{U} \right) d\left( \frac{y}{\delta} \right) = \int_0^1 \left( 1 - \frac{u}{U} \right) d\eta$

with  $\frac{u}{U} = \frac{3}{2}\eta - \frac{1}{2}\eta^3$

Hence  $\frac{\delta^*}{\delta} = \int_0^1 \left( 1 - \frac{u}{U} \right) d\eta = \int_0^1 \left( 1 - \frac{3}{2}\eta + \frac{1}{2}\eta^3 \right) d\eta = \left[ \eta - \frac{3}{4}\eta^2 + \frac{1}{8}\eta^4 \right]_0^1 = \frac{3}{8} = 0.375$

For  $\theta$ :  $\theta = \int_0^{\infty} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy = \int_0^{\delta} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy$

Then  $\frac{\theta}{\delta} = \frac{1}{\delta} \int_0^{\delta} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\left( \frac{y}{\delta} \right) = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\eta$

Hence  $\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\eta = \int_0^1 \left( \frac{3}{2}\eta - \frac{1}{2}\eta^3 \right) \left( 1 - \frac{3}{2}\eta + \frac{1}{2}\eta^3 \right) d\eta = \int_0^1 \left( \frac{3}{2}\eta - \frac{9}{4}\eta^2 - \frac{1}{2}\eta^3 + \frac{3}{2}\eta^4 - \frac{1}{4}\eta^6 \right) d\eta$

$\frac{\theta}{\delta} = \left[ \frac{3}{4}\eta^2 - \frac{3}{4}\eta^3 - \frac{1}{8}\eta^4 + \frac{3}{10}\eta^5 - \frac{1}{28}\eta^7 \right]_0^1 = \frac{39}{280} = 0.139$

## Problem 9.12

[Difficulty: 2]

**9.12** An approximation for the velocity profile in a laminar boundary layer is

$$\frac{u}{U} = 2\frac{y}{\delta} - 2\left(\frac{y}{\delta}\right)^3 + \left(\frac{y}{\delta}\right)^4$$

Does this expression satisfy boundary conditions applicable to the laminar boundary-layer velocity profile? Evaluate  $\delta^*/\delta$  and  $\theta/\delta$ .

**Given:** Laminar boundary layer profile

**Find:** If it satisfies BC's; Evaluate  $\delta^*/\delta$  and  $\theta/\delta$

**Solution:**

The boundary layer equation is  $\frac{u}{U} = 2\frac{y}{\delta} - 2\left(\frac{y}{\delta}\right)^3 + \left(\frac{y}{\delta}\right)^4$  for which  $u = U$  at  $y = \delta$

The BC's are  $u(0) = 0 \quad \left. \frac{du}{dy} \right|_{y=0} = 0$

At  $y = 0$   $\frac{u}{U} = 2(0) - 2(0)^3 + (0)^4 = 0$

At  $y = \delta$   $\left. \frac{du}{dy} = U \left( 2\frac{1}{\delta} - 6\frac{y^2}{\delta^3} + 4\frac{y^3}{\delta^4} \right) \right|_{y=\delta} = U \left( 2\frac{1}{\delta} - 6\frac{\delta^2}{\delta^3} + 4\frac{\delta^3}{\delta^4} \right) = 0$

For  $\delta^*$ :  $\delta^* = \int_0^{\infty} \left( 1 - \frac{u}{U} \right) dy = \int_0^{\delta} \left( 1 - \frac{u}{U} \right) dy$

Then  $\frac{\delta^*}{\delta} = \frac{1}{\delta} \int_0^{\delta} \left( 1 - \frac{u}{U} \right) dy = \int_0^1 \left( 1 - \frac{u}{U} \right) d\left(\frac{y}{\delta}\right) = \int_0^1 \left( 1 - \frac{u}{U} \right) d\eta$

with  $\frac{u}{U} = 2\eta - 2\eta^3 + \eta^4$

Hence  $\frac{\delta^*}{\delta} = \int_0^1 \left( 1 - \frac{u}{U} \right) d\eta = \int_0^1 (1 - 2\eta + 2\eta^3 - \eta^4) d\eta = \left[ \eta - \eta^2 + \frac{1}{2}\eta^4 - \frac{1}{5}\eta^5 \right]_0^1 = \frac{3}{10} = 0.3$

For  $\theta$ :  $\theta = \int_0^{\infty} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy = \int_0^{\delta} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy$

Then  $\frac{\theta}{\delta} = \frac{1}{\delta} \int_0^{\delta} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\left(\frac{y}{\delta}\right) = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\eta$

Hence

$\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\eta = \int_0^1 (2\eta - \eta^3 + \eta^4)(1 - 2\eta + \eta^3 - \eta^4) d\eta = \int_0^1 (2\eta - 4\eta^2 - 2\eta^3 + 9\eta^4 - 4\eta^5 - 4\eta^6 + 4\eta^7 - \eta^8) d\eta$

$$\frac{\theta}{\delta} = \left[ \eta^2 - \frac{4}{3}\eta^3 - \frac{1}{2}\eta^4 + \frac{9}{5}\eta^5 - \frac{4}{7}\eta^7 + \frac{1}{2}\eta^8 - \frac{1}{9}\eta^9 \right]_0^1 = \frac{37}{315} = 0.117$$

## Problem 9.13

[Difficulty: 3]

**9.13** A simplistic laminar boundary-layer model is

$$\frac{u}{U} = \sqrt{2} \frac{y}{\delta} \quad 0 < y \leq \frac{\delta}{2}$$

$$\frac{u}{U} = (2 - \sqrt{2}) \frac{y}{\delta} + (\sqrt{2} - 1) \quad \frac{\delta}{2} < y \leq \delta$$

Does this expression satisfy boundary conditions applicable to the laminar boundary-layer velocity profile? Evaluate  $\delta^*/\delta$  and  $\theta/\delta$ .

**Given:** Laminar boundary layer profile

**Find:** If it satisfies BC's; Evaluate  $\delta^*/\delta$  and  $\theta/\delta$

**Solution:**

The boundary layer equation is

$$\frac{u}{U} = \sqrt{2} \frac{y}{\delta} \quad 0 < y < \frac{\delta}{2}$$

$$\frac{u}{U} = (2 - \sqrt{2}) \frac{y}{\delta} + (\sqrt{2} - 1) \quad \frac{\delta}{2} < y < \delta \quad \text{for which } u = U \text{ at } y = \delta$$

The BC's are

$$u(0) = 0 \quad \left. \frac{du}{dy} \right|_{y=\delta} = 0$$

At  $y = 0$

$$\frac{u}{U} = \sqrt{2}(0) = 0$$

At  $y = \delta$

$$\left. \frac{du}{dy} \right|_{y=\delta} = U \left[ (2 - \sqrt{2}) \frac{1}{\delta} \right] \neq 0 \quad \text{so it fails the outer BC.}$$

This simplistic distribution is a piecewise linear profile: The first half of the layer has velocity gradient  $\sqrt{2} \frac{U}{\delta} = 1.414 \frac{U}{\delta}$ , and the second half has velocity gradient  $(2 - \sqrt{2}) \frac{U}{\delta} = 0.586 \frac{U}{\delta}$ . At  $y = \delta$ , we make another transition to zero velocity gradient.

For  $\delta^*$ :

$$\delta^* = \int_0^{\infty} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy$$

Then

$$\frac{\delta^*}{\delta} = \frac{1}{\delta} \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy = \int_0^1 \left(1 - \frac{u}{U}\right) d\left(\frac{y}{\delta}\right) = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$$

with

$$\frac{u}{U} = \sqrt{2}\eta \quad 0 < \eta < \frac{1}{2}$$

$$\frac{u}{U} = (2 - \sqrt{2})\eta + (\sqrt{2} - 1) \quad \frac{1}{2} < \eta < 1$$

Hence

$$\frac{\delta^*}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta = \int_0^{1/2} (1 - \sqrt{2}\eta) d\eta + \int_{1/2}^1 [1 - (2 - \sqrt{2})\eta - (\sqrt{2} - 1)] d\eta = \left[ \frac{1}{2\sqrt{2}} (\sqrt{2}\eta - 1)^2 \right]_0^{1/2} + \left[ \frac{1}{2} (\eta - 1)^2 (\sqrt{2} - 2) \right]_{1/2}^1$$

$$\frac{\delta^*}{\delta} = \left[ \frac{1}{2} - \frac{\sqrt{2}}{8} \right] + \left[ \frac{1}{4} - \frac{\sqrt{2}}{8} \right] = \frac{3}{4} - \frac{\sqrt{2}}{4} = 0.396$$

For  $\theta$ :

$$\theta = \int_0^{\infty} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy = \int_0^{\delta} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy$$

Then

$$\frac{\theta}{\delta} = \frac{1}{\delta} \int_0^{\delta} \frac{u}{U} \left( 1 - \frac{u}{U} \right) dy = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\left(\frac{y}{\delta}\right) = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\eta$$

Hence, after a LOT of work

$$\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \left( 1 - \frac{u}{U} \right) d\eta = \int_0^{1/2} \sqrt{2}\eta(1 - \sqrt{2}\eta) d\eta + \int_{1/2}^1 \left[ \left( (2 - \sqrt{2})\eta + (\sqrt{2} - 1) \right) \left( 1 - (2 - \sqrt{2})\eta - (\sqrt{2} - 1) \right) \right] d\eta$$

$$\frac{\theta}{\delta} = \left[ \sqrt{2}\eta^2 \left( \frac{\sqrt{2}\eta}{3} - \frac{1}{2} \right) \right]_0^{1/2} + \left[ \left( \frac{1}{3}(\sqrt{2} - 2)(\eta - 1) - \frac{1}{2} \right) (\sqrt{2} - 2)(\eta - 1)^2 \right]_{1/2}^1 = \frac{\sqrt{2}}{8} - \frac{1}{12} + \frac{\sqrt{2}}{24} = \frac{\sqrt{2}}{6} - \frac{1}{12} = 0.152$$

## Problem 9.14

[Difficulty: 2]

**9.14** The velocity profile in a turbulent boundary layer often is approximated by the  $\frac{1}{7}$ -power-law equation


$$\frac{u}{U} = \left(\frac{y}{\delta}\right)^{1/7}$$

Compare the shape of this profile with the parabolic laminar boundary-layer velocity profile (Problem 9.10) by plotting  $y/\delta$  (on the ordinate) versus  $u/U$  (on the abscissa) for both profiles.

**Given:** Power law velocity profiles

**Find:** Plots of  $y/\delta$  vs  $u/U$  for this profile and the parabolic profile of Problem 9.10

**Solution:** Here are the profiles:



Note that the power law profile gives an infinite value of  $du/dy$  as  $y$  approaches zero:

$$\frac{du}{dy} = \frac{U}{\delta} \frac{d(u/U)}{d(y/\delta)} = \frac{U}{7\delta} \left(\frac{y}{\delta}\right)^{-6/7} \rightarrow \infty \quad \text{as } y \rightarrow 0$$

## Problem 9.15

[Difficulty: 2]

**9.15** Evaluate  $\theta/\delta$  for each of the laminar boundary-layer velocity profiles given in Problem 9.10.

Linear :  $\frac{u}{U} = \frac{y}{\delta}$

Sinusoidal :  $\frac{u}{U} = \sin\left(\frac{\pi y}{2\delta}\right)$

Parabolic :  $\frac{u}{U} = 2\left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$

**Given:** Linear, sinusoidal, and parabolic velocity profiles

**Find:** The momentum thickness expressed as  $\theta/\delta$  for each profile

**Solution:** We will apply the definition of the momentum thickness to each profile.

**Governing Equation:**

$$\theta = \int_0^{\delta} \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) dy \quad \text{(Definition of momentum thickness)}$$

If we divide both sides of the equation by  $\delta$ , we get:  $\frac{\theta}{\delta} = \frac{1}{\delta} \int_0^{\delta} \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) dy$  However, we can change

the variable of integration to  $\eta = y/\delta$ , resulting in:  $d\eta = \frac{1}{\delta} \cdot dy$  Therefore:  $\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta$

For the linear profile:  $\frac{u}{U} = \eta$  Into the momentum thickness:

$$\frac{\theta}{\delta} = \int_0^1 \eta \cdot (1 - \eta) d\eta = \int_0^1 (\eta - \eta^2) d\eta \quad \text{Evaluating this integral: } \frac{\theta}{\delta} = \frac{1}{2} - \frac{1}{3} = \frac{1}{6} \quad \frac{\theta}{\delta} = 0.1667$$

For the sinusoidal profile:  $\frac{u}{U} = \sin\left(\frac{\pi}{2} \cdot \eta\right)$  Into the momentum thickness:

$$\frac{\theta}{\delta} = \int_0^1 \sin\left(\frac{\pi}{2} \cdot \eta\right) \cdot \left(1 - \sin\left(\frac{\pi}{2} \cdot \eta\right)\right) d\eta = \int_0^1 \left[ \sin\left(\frac{\pi}{2} \cdot \eta\right) - \left(\sin\left(\frac{\pi}{2} \cdot \eta\right)\right)^2 \right] d\eta$$

$$\text{Evaluating this integral: } \frac{\theta}{\delta} = \frac{2}{\pi} - \frac{2}{\pi} \cdot \frac{\pi}{4} \quad \frac{\theta}{\delta} = 0.1366$$

For the parabolic profile:  $\frac{u}{U} = 2 \cdot \eta - \eta^2$  Into the momentum thickness:

$$\frac{\theta}{\delta} = \int_0^1 (2 \cdot \eta - \eta^2) \cdot [1 - (2 \cdot \eta - \eta^2)] d\eta = \int_0^1 (2 \cdot \eta - 5 \cdot \eta^2 + 4 \cdot \eta^3 - \eta^4) d\eta$$

$$\text{Evaluating this integral: } \frac{\theta}{\delta} = 1 - \frac{5}{3} + 1 - \frac{1}{5} = \frac{2}{15} \quad \frac{\theta}{\delta} = 0.1333$$

## Problem 9.16

[Difficulty: 2]

**9.16** Evaluate  $\delta^*/\delta$  for each of the laminar boundary-layer velocity profiles given in Problem 9.10.

$$\text{Linear : } \frac{u}{U} = \frac{y}{\delta}$$

$$\text{Sinusoidal : } \frac{u}{U} = \sin\left(\frac{\pi y}{2\delta}\right)$$

$$\text{Parabolic : } \frac{u}{U} = 2\left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$$

**Given:** Linear, sinusoidal, and parabolic velocity profiles

**Find:** The displacement thickness expressed as  $\delta^*/\delta$  for each profile

**Solution:** We will apply the definition of the displacement thickness to each profile.

**Governing Equation:**

$$\delta_{\text{disp}} = \int_0^{\text{infinity}} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy \quad (\text{Definition of displacement thickness})$$

If we divide both sides of the equation by  $\delta$ , we get:  $\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{\delta} \cdot \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy$  However, we can change

the variable of integration to  $\eta = y/\delta$ , resulting in:  $d\eta = \frac{1}{\delta} \cdot dy$  Therefore:  $\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$

For the linear profile:  $\frac{u}{U} = \eta$  Into the displacement thickness:

$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 (1 - \eta) d\eta \quad \text{Evaluating this integral: } \frac{\delta_{\text{disp}}}{\delta} = 1 - \frac{1}{2} = \frac{1}{2} \quad \frac{\delta_{\text{disp}}}{\delta} = 0.5000$$

For the sinusoidal profile:  $\frac{u}{U} = \sin\left(\frac{\pi}{2} \cdot \eta\right)$  Into the displacement thickness:

$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \sin\left(\frac{\pi}{2} \cdot \eta\right)\right) d\eta \quad \text{Evaluating this integral: } \frac{\delta_{\text{disp}}}{\delta} = 1 - \frac{2}{\pi} \quad \frac{\delta_{\text{disp}}}{\delta} = 0.3634$$

For the parabolic profile:  $\frac{u}{U} = 2 \cdot \eta - \eta^2$  Into the displacement thickness:

$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 [1 - (2 \cdot \eta - \eta^2)] d\eta = \int_0^1 (1 - 2 \cdot \eta + \eta^2) d\eta$$

Evaluating this integral:  $\frac{\delta_{\text{disp}}}{\delta} = 1 - 1 + \frac{1}{3} = \frac{1}{3} \quad \frac{\delta_{\text{disp}}}{\delta} = 0.3333$

## Problem 9.17

[Difficulty: 2]

**9.17** Evaluate  $\delta^*/\delta$  and  $\theta/\delta$  for the turbulent  $\frac{1}{7}$  power-law velocity profile given in Problem 9.14. Compare with ratios for the parabolic laminar boundary-layer velocity profile given in Problem 9.10.

$$\frac{u}{U} = \left(\frac{y}{\delta}\right)^{1/7} \quad \text{Parabolic:} \quad \frac{u}{U} = 2\left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$$

**Given:** Power law and parabolic velocity profiles

**Find:** The displacement and momentum thicknesses expressed as  $\delta^*/\delta$  and  $\theta/\delta$  for each profile

**Solution:** We will apply the definition of the displacement and momentum thickness to each profile.

**Governing Equations:**

$$\delta_{\text{disp}} = \int_0^{\text{infinity}} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy \quad (\text{Definition of displacement thickness})$$

$$\theta = \int_0^{\delta} \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) dy \quad (\text{Definition of momentum thickness})$$

If we divide both sides of the equations by  $\delta$ , we get: 
$$\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{\delta} \cdot \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy \quad \frac{\theta}{\delta} = \frac{1}{\delta} \cdot \int_0^{\delta} \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) dy$$

However, we can change the variable of integration to  $\eta = y/\delta$ , resulting in:  $d\eta = \frac{1}{\delta} \cdot dy$  Therefore:

$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta \quad \frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta$$

For the power law profile:  $\frac{u}{U} = \eta^{1/7}$  Into the displacement thickness: 
$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \eta^{1/7}\right) d\eta$$

Evaluating this integral: 
$$\frac{\delta_{\text{disp}}}{\delta} = 1 - \frac{7}{8} = \frac{1}{8} \quad \frac{\delta_{\text{disp}}}{\delta} = 0.1250$$

Into the momentum thickness: 
$$\frac{\theta}{\delta} = \int_0^1 \eta^{1/7} \cdot \left(1 - \eta^{1/7}\right) d\eta = \int_0^1 \left(\eta^{1/7} - \eta^{2/7}\right) d\eta$$
 Evaluating this integral: 
$$\frac{\theta}{\delta} = \frac{7}{8} - \frac{7}{9} = \frac{7}{72}$$
  

$$\frac{\theta}{\delta} = 0.0972$$

For the parabolic profile:  $\frac{u}{U} = 2 \cdot \eta - \eta^2$

Into the displacement thickness: 
$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 [1 - (2 \cdot \eta - \eta^2)] d\eta = \int_0^1 (1 - 2 \cdot \eta + \eta^2) d\eta$$

Evaluating this integral:  $\frac{\delta_{\text{disp}}}{\delta} = 1 - 1 + \frac{1}{3} = \frac{1}{3}$

$\frac{\delta_{\text{disp}}}{\delta} = 0.3333$

Into the momentum thickness:  $\frac{\theta}{\delta} = \int_0^1 (2 \cdot \eta - \eta^2) \cdot [1 - (2 \cdot \eta - \eta^2)] d\eta = \int_0^1 (2 \cdot \eta - 5 \cdot \eta^2 + 4 \cdot \eta^3 - \eta^4) d\eta$

Evaluating this integral:  $\frac{\theta}{\delta} = 1 - \frac{5}{3} + 1 - \frac{1}{5} = \frac{2}{15}$


$\frac{\theta}{\delta} = 0.1333$

Profile	$\delta_{\text{disp}}$	$\theta$
Power Law	$0.1250 \cdot \delta$	$0.0972 \cdot \delta$
Parabolic	$0.3333 \cdot \delta$	$0.1333 \cdot \delta$

## Problem 9.18

[Difficulty: 3]

**9.18** A fluid, with density  $\rho = 1.5 \text{ slug/ft}^3$ , flows at  $U = 10 \text{ ft/s}$  over a flat plate 10 ft long and 3 ft wide. At the trailing edge, the boundary-layer thickness is  $\delta = 1 \text{ in.}$  Assume the velocity profile is linear, as shown, and that the flow is two-dimensional (flow conditions are independent of  $z$ ). Using control volume  $abcd$ , shown by the dashed lines, compute the mass flow rate across surface  $ab$ . Determine the drag force on the upper surface of the plate. Explain how this (viscous) drag can be computed from the given data even though we do not know the fluid viscosity (see Problem 9.41).




**Given:** Data on fluid and boundary layer geometry

**Find:** Mass flow rate across  $ab$ ; Drag

**Solution:**

The given data is  $\rho = 1.5 \frac{\text{slug}}{\text{ft}^3}$   $U = 10 \frac{\text{ft}}{\text{s}}$   $L = 10 \text{ ft}$   $\delta = 1 \text{ in}$   $b = 3 \text{ ft}$



**Governing equations:**

$$\text{Mass} \quad \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12)$$

$$\text{Momentum} \quad \vec{F} = \vec{F}_S + \vec{F}_B = \frac{\partial}{\partial t} \int_{CV} \vec{V} \rho dV + \int_{CS} \vec{V} \rho \vec{V} \cdot d\vec{A} \quad (4.17a)$$

Assumptions: (1) Steady flow (2) No pressure force (3) No body force in  $x$  direction (4) Uniform flow at  $a$

Applying these to the CV  $abcd$

$$\text{Mass} \quad (-\rho \cdot U \cdot b \cdot \delta) + \int_0^\delta \rho \cdot u \cdot b \cdot dy + m_{ab} = 0$$

$$\text{For the boundary layer} \quad \frac{u}{U} = \frac{y}{\delta} = \eta \quad \frac{dy}{\delta} = d\eta$$

$$\text{Hence} \quad m_{ab} = \rho \cdot U \cdot b \cdot \delta - \int_0^1 \rho \cdot U \cdot \eta \cdot \delta \cdot dy = \rho \cdot U \cdot b \cdot \delta - \frac{1}{2} \cdot \rho \cdot U \cdot b \cdot \delta$$

$$m_{ab} = \frac{1}{2} \cdot \rho \cdot U \cdot b \cdot \delta \quad m_{ab} = 1.875 \frac{\text{slug}}{\text{s}}$$

$$\text{Momentum} \quad R_x = U \cdot (-\rho \cdot U \cdot \delta) + m_{ab} \cdot u_{ab} + \int_0^\delta u \cdot \rho \cdot u \cdot b \cdot dy$$

$$\text{Note that} \quad u_{ab} = U \quad \text{and} \quad \int_0^\delta u \cdot \rho \cdot u \cdot b \cdot dy = \int_0^1 \rho \cdot U^2 \cdot b \cdot \delta \cdot \eta^2 \cdot d\eta$$

$$R_x = -\rho \cdot U^2 \cdot b \cdot \delta + \frac{1}{2} \cdot \rho \cdot U \cdot b \cdot \delta \cdot U + \int_0^1 \rho \cdot U^2 \cdot b \cdot \delta \cdot \eta^2 \cdot dy$$

$$R_x = -\rho \cdot U^2 \cdot b \cdot \delta + \frac{1}{2} \cdot \rho \cdot U^2 \cdot \delta + \frac{1}{3} \cdot \rho \cdot U^2 \cdot \delta \quad R_x = -\frac{1}{6} \cdot \rho \cdot U^2 \cdot b \cdot \delta \quad R_x = -6.25 \cdot \text{lbf}$$

We are able to compute the boundary layer drag even though we do not know the viscosity because it is the viscosity that creates the boundary layer in the first place

## Problem 9.19

[Difficulty: 3]

**9.19** The flat plate of Problem 9.18 is turned so that the 3-ft side is parallel to the flow (the width becomes 10 ft). Should we expect that the drag increases or decreases? Why? The trailing edge boundary-layer thickness is now  $\delta = 0.6$  in. Assume again that the velocity profile is linear and that the flow is two-dimensional (flow conditions are independent of  $z$ ). Repeat the analysis of Problem 9.18.

**Given:** Data on fluid and boundary layer geometry

**Find:** Mass flow rate across  $ab$ ; Drag; Compare to Problem 9.18

**Solution:**

The given data is  $\rho = 1.5 \cdot \frac{\text{slug}}{\text{ft}^3}$        $U = 10 \cdot \frac{\text{ft}}{\text{s}}$        $L = 3\text{-ft}$        $\delta = 0.6\text{-in}$        $b = 10\text{-ft}$

**Governing equations:**

Mass 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12)$$

Momentum 
$$\vec{F} = \vec{F}_S + \vec{F}_B = \frac{\partial}{\partial t} \int_{CV} \vec{V} \rho dV + \int_{CS} \vec{V} \rho \vec{V} \cdot d\vec{A} \quad (4.17a)$$

**Assumptions:** (1) Steady flow (2) No pressure force (3) No body force in  $x$  direction (4) Uniform flow at  $a$

Applying these to the CV  $abcd$

Mass 
$$(-\rho \cdot U \cdot b \cdot \delta) + \int_0^\delta \rho \cdot u \cdot b \, dy + m_{ab} = 0$$

For the boundary layer 
$$\frac{u}{U} = \frac{y}{\delta} = \eta \quad \frac{dy}{\delta} = d\eta$$

Hence 
$$m_{ab} = \rho \cdot U \cdot b \cdot \delta - \int_0^1 \rho \cdot U \cdot \eta \cdot \delta \, dy = \rho \cdot U \cdot b \cdot \delta - \frac{1}{2} \cdot \rho \cdot U \cdot b \cdot \delta$$

$$m_{ab} = \frac{1}{2} \cdot \rho \cdot U \cdot b \cdot \delta \quad m_{ab} = 3.75 \cdot \frac{\text{slug}}{\text{s}}$$

Momentum 
$$R_x = U \cdot (-\rho \cdot U \cdot \delta) + m_{ab} \cdot u_{ab} + \int_0^\delta u \cdot \rho \cdot u \cdot b \, dy$$

Note that  $u_{ab} = U$  and 
$$\int_0^\delta u \cdot \rho \cdot u \cdot b \, dy = \int_0^1 \rho \cdot U^2 \cdot b \cdot \delta \cdot \eta^2 \, d\eta$$

$$R_x = -\rho \cdot U^2 \cdot b \cdot \delta + \frac{1}{2} \cdot \rho \cdot U \cdot b \cdot \delta \cdot U + \int_0^1 \rho \cdot U^2 \cdot b \cdot \delta \cdot \eta^2 \, d\eta$$

$$R_x = -\rho \cdot U^2 \cdot b \cdot \delta + \frac{1}{2} \cdot \rho \cdot U^2 \cdot \delta + \frac{1}{3} \cdot \rho \cdot U^2 \cdot \delta$$


$$R_x = -\frac{1}{6} \cdot \rho \cdot U^2 \cdot b \cdot \delta \quad R_x = -12.50 \cdot \text{lbf}$$

We should expect the drag to be larger than for Problem 9.18 because the viscous friction is mostly concentrated near the leading edge (which is only 3 ft wide in Problem 9.18 but 10 ft here). The reason viscous stress is highest at the front region is that the boundary layer is very small ( $\delta \ll L$ ) so  $\tau = \mu du/dy \sim \mu U/\delta \gg \dots$

## Problem 9.20

[Difficulty: 3]

**9.20** Solve Problem 9.18 again with the velocity profile at section *bc* given by the parabolic expression from Problem 9.10.



**Given:** Flow over a flat plate with parabolic laminar boundary layer profile

**Find:** (a) Mass flow rate across *ab*  
(b) *x* component (and direction) of force needed to hold the plate in place

**Solution:** We will apply the continuity and *x*-momentum equations to this system.


**Governing Equations:**

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (\text{Continuity})$$

$$\frac{\partial}{\partial t} \int_{CV} \rho u dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} = F_{sx} + F_{bx} \quad (\text{x-Momentum})$$

**Assumptions:**

- (1) Steady flow
- (2) No net pressure forces
- (3) No body forces in the *x*-direction
- (4) Uniform flow at *da*



From the assumptions, the continuity equation becomes:  $-\rho \cdot U \cdot b \cdot \delta + \int_0^\delta \rho \cdot u \cdot b \, dy + m_{ab} = 0$  The integral can be written as:

$$\int_0^\delta \rho \cdot u \cdot b \, dy = \rho \cdot b \cdot \int_0^\delta u \, dy = \rho \cdot U \cdot b \cdot \delta \cdot \int_0^1 (2 \cdot \eta - \eta^2) \, d\eta \quad \text{where } \eta = \frac{y}{\delta} \quad \text{This integral is equal to: } \rho \cdot U \cdot b \cdot \delta \cdot \left(1 - \frac{1}{3}\right) = \frac{2}{3} \cdot \rho \cdot U \cdot b \cdot \delta$$

Solving continuity for the mass flux through *ab* we get:  $m_{ab} = \rho \cdot U \cdot b \cdot \delta - \frac{2}{3} \cdot \rho \cdot U \cdot b \cdot \delta = \frac{1}{3} \cdot \rho \cdot U \cdot b \cdot \delta$  Substituting known values:

$$m_{ab} = \frac{1}{3} \times 1.5 \frac{\text{slug}}{\text{ft}^3} \times 10 \frac{\text{ft}}{\text{s}} \times 3.0 \text{ ft} \times 1 \cdot \text{in} \times \frac{\text{ft}}{12 \cdot \text{in}} \quad m_{ab} = 1.250 \frac{\text{slug}}{\text{s}}$$

From the assumptions, the momentum equation becomes:  $R_x = u_{da} \cdot (-\rho \cdot U \cdot b \cdot \delta) + u_{ab} \cdot m_{ab} + \int_0^\delta u \cdot \rho \cdot u \cdot b \, dy$  where  $u_{da} = u_{ab} = U$

Thus:  $R_x = -\rho \cdot U^2 \cdot b \cdot \delta + \frac{1}{3} \cdot \rho \cdot U^2 \cdot b \cdot \delta + \int_0^\delta u \cdot \rho \cdot u \cdot b \, dy = -\frac{2}{3} \cdot \rho \cdot U^2 \cdot b \cdot \delta + \int_0^\delta u \cdot \rho \cdot u \cdot b \, dy$  The integral can be written as:

$$\int_0^\delta u \cdot \rho \cdot u \cdot b \, dy = \rho \cdot b \cdot \int_0^\delta u^2 \, dy = \rho \cdot U^2 \cdot b \cdot \delta \cdot \int_0^1 (2 \cdot \eta - \eta^2)^2 \, d\eta = \rho \cdot U^2 \cdot b \cdot \delta \cdot \int_0^1 (4 \cdot \eta^2 - 4 \cdot \eta^3 + \eta^4) \, d\eta \quad \text{This integral is equal to:}$$

$$\rho \cdot U^2 \cdot b \cdot \delta \cdot \left(\frac{4}{3} - 1 + \frac{1}{5}\right) = \frac{8}{15} \cdot \rho \cdot U \cdot b \cdot \delta \quad \text{Therefore the force on the plate is: } R_x = \left(\frac{8}{15} - \frac{2}{3}\right) \cdot \rho \cdot U^2 \cdot b \cdot \delta = -\frac{2}{15} \cdot \rho \cdot U^2 \cdot b \cdot \delta$$

Substituting known values:  $R_x = -\frac{2}{15} \times 1.5 \frac{\text{slug}}{\text{ft}^3} \times \left(10 \frac{\text{ft}}{\text{s}}\right)^2 \times 3.0 \text{ ft} \times 1 \cdot \text{in} \times \frac{\text{ft}}{12 \cdot \text{in}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \quad R_x = -5.00 \cdot \text{lbf}$   
(to the left)

This force must be applied to the control volume by the plate.

## Problem 9.21

[Difficulty: 2]

**9.21** The test section of a low-speed wind tunnel is 5 ft long, preceded by a nozzle with a diffuser at the outlet. The tunnel cross section is 1 ft × 1 ft. The wind tunnel is to operate with 100°F air and have a design velocity of 160 ft/s in the test section. A potential problem with such a wind tunnel is boundary-layer blockage. The boundary-layer displacement thickness reduces the effective cross-sectional area (the test area, in which we have uniform flow); in addition, the uniform flow will be accelerated. If these effects are pronounced, we end up with a smaller useful test cross section with a velocity somewhat higher than anticipated. If the boundary layer thickness is 0.4 in. at the entrance and 1 in. at the exit, and the boundary layer velocity profile is given by  $u/U = (y/\delta)^{1/7}$ , estimate the displacement thickness at the end of the test section and the percentage change in the uniform velocity between the inlet and outlet.

**Given:** Data on wind tunnel and boundary layers

**Find:** Displacement thickness at exit; Percent change in uniform velocity through test section

### Solution

The solution involves using mass conservation in the inviscid core, allowing for the fact that as the boundary layer grows it reduces the size of the core. One approach would be to integrate the 1/7 law velocity profile to compute the mass flow in the boundary layer; an easier approach is to simply use the displacement thickness!

Basic equations 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12)$$
 
$$\delta_{\text{disp}} = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy$$

Assumptions: 1) Steady flow 2) Incompressible 3) No friction outside boundary layer 4) Flow along streamline 5) Horizontal

For this flow 
$$\rho \cdot U \cdot A = \text{const} \quad \text{and} \quad \frac{u}{U} = \left(\frac{y}{\delta}\right)^{\frac{1}{7}}$$

The design data is 
$$U_{\text{design}} = 160 \cdot \frac{\text{ft}}{\text{s}} \quad w = 1 \cdot \text{ft} \quad h = 1 \cdot \text{ft} \quad A_{\text{design}} = w \cdot h \quad A_{\text{design}} = 1 \cdot \text{ft}^2$$

The volume flow rate is 
$$Q = U_{\text{design}} \cdot A_{\text{design}} \quad Q = 160 \cdot \frac{\text{ft}^3}{\text{s}}$$

We also have 
$$\delta_{\text{in}} = 0.4 \cdot \text{in} \quad \delta_{\text{exit}} = 1 \cdot \text{in}$$

Hence 
$$\delta_{\text{disp}} = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left[1 - \left(\frac{y}{\delta}\right)^{\frac{1}{7}}\right] dy = \delta \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta \quad \text{where} \quad \eta = \frac{y}{\delta} \quad \delta_{\text{disp}} = \frac{\delta}{8}$$

Hence at the inlet and exit

$$\delta_{\text{dispin}} = \frac{\delta_{\text{in}}}{8} \quad \delta_{\text{dispin}} = 0.05 \cdot \text{in} \quad \delta_{\text{dispexit}} = \frac{\delta_{\text{exit}}}{8} \quad \delta_{\text{dispexit}} = 0.125 \cdot \text{in}$$

Hence the areas are

$$A_{\text{in}} = (w - 2 \cdot \delta_{\text{dispin}}) \cdot (h - 2 \cdot \delta_{\text{dispin}})$$

$$A_{\text{exit}} = (w - 2 \cdot \delta_{\text{dispexit}}) \cdot (h - 2 \cdot \delta_{\text{dispexit}})$$

$$A_{\text{in}} = 0.9834 \cdot \text{ft}^2$$

$$A_{\text{exit}} = 0.9588 \cdot \text{ft}^2$$

Applying mass conservation between "design" conditions and the inlet

$$(-\rho \cdot U_{\text{design}} \cdot A_{\text{design}}) + (\rho \cdot U_{\text{in}} \cdot A_{\text{in}}) = 0$$

or

$$U_{\text{in}} = U_{\text{design}} \cdot \frac{A_{\text{design}}}{A_{\text{in}}} \quad U_{\text{in}} = 162.7 \cdot \frac{\text{ft}}{\text{s}}$$

Also

$$U_{\text{exit}} = U_{\text{design}} \cdot \frac{A_{\text{design}}}{A_{\text{exit}}} \quad U_{\text{exit}} = 166.9 \cdot \frac{\text{ft}}{\text{s}}$$

The percent change in uniform velocity is then  $\frac{U_{\text{exit}} - U_{\text{in}}}{U_{\text{in}}} = 2.57\%$  The exit displacement thickness is  $\delta_{\text{dispexit}} = 0.125 \cdot \text{in}$

## Problem 9.22

[Difficulty: 2]

**9.22** Air flows in a horizontal cylindrical duct of diameter  $D = 100$  mm. At a section a few meters from the entrance, the turbulent boundary layer is of thickness  $\delta_1 = 5.25$  mm, and the velocity in the inviscid central core is  $U_1 = 12.5$  m/s. Farther downstream the boundary layer is of thickness  $\delta_2 = 24$  mm. The velocity profile in the boundary layer is approximated well by the  $\frac{1}{7}$ -power expression. Find the velocity,  $U_2$ , in the inviscid central core at the second section, and the pressure drop between the two sections.

**Given:** Data on boundary layer in a cylindrical duct

**Find:** Velocity  $U_2$  in the inviscid core at location 2; Pressure drop

**Solution:**

The solution involves using mass conservation in the inviscid core, allowing for the fact that as the boundary layer grows it reduces the size of the core. One approach would be to integrate the  $1/7$  law velocity profile to compute the mass flow in the boundary layer; an easier approach is to simply use the displacement thickness!

The given or available data (from Appendix A) is

$$\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \quad U_1 = 12.5 \cdot \frac{\text{m}}{\text{s}} \quad D = 100 \cdot \text{mm} \quad \delta_1 = 5.25 \cdot \text{mm} \quad \delta_2 = 24 \cdot \text{mm}$$

**Governing equations:**

Mass  $\frac{\partial}{\partial t} \int_{\text{CV}} \rho \, dV + \int_{\text{CS}} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12)$

Bernoulli  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad (4.24)$

The displacement thicknesses can be computed from boundary layer thicknesses using Eq. 9.1

$$\delta_{\text{disp}} = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy = \delta \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta = \frac{\delta}{8}$$

Hence at locations 1 and 2  $\delta_{\text{disp1}} = \frac{\delta_1}{8} \quad \delta_{\text{disp1}} = 0.656 \cdot \text{mm} \quad \delta_{\text{disp2}} = \frac{\delta_2}{8} \quad \delta_{\text{disp2}} = 3 \cdot \text{mm}$

Applying mass conservation at locations 1 and 2  $(-\rho \cdot U_1 \cdot A_1) + (\rho \cdot U_2 \cdot A_2) = 0 \quad \text{or} \quad U_2 = U_1 \cdot \frac{A_1}{A_2}$

The two areas are given by the duct cross section area minus the displacement boundary layer

$$A_1 = \frac{\pi}{4} \cdot (D - 2 \cdot \delta_{\text{disp1}})^2 \quad A_1 = 7.65 \times 10^{-3} \text{ m}^2 \quad A_2 = \frac{\pi}{4} \cdot (D - 2 \cdot \delta_{\text{disp2}})^2 \quad A_2 = 6.94 \times 10^{-3} \text{ m}^2$$

Hence  $U_2 = U_1 \cdot \frac{A_1}{A_2} \quad U_2 = 13.8 \frac{\text{m}}{\text{s}}$

For the pressure drop we can apply Bernoulli to locations 1 and 2 to find  $p_1 - p_2 = \Delta p = \frac{\rho}{2} \cdot (U_2^2 - U_1^2) \quad \Delta p = 20.6 \text{ Pa}$

## Problem 9.23

[Difficulty: 2]

**9.23** Laboratory wind tunnels have test sections 25 cm square and 50 cm long. With nominal air speed  $U_1 = 25$  m/s at the test section inlet, turbulent boundary layers form on the top, bottom, and side walls of the tunnel. The boundary-layer thickness is  $\delta_1 = 20$  mm at the inlet and  $\delta_2 = 30$  mm at the outlet from the test section. The boundary-layer velocity profiles are of power-law form, with  $u/U = (y/\delta)^{1/7}$ . Evaluate the freestream velocity,  $U_2$ , at the exit from the wind-tunnel test section. Determine the change in static pressure along the test section.

**Given:** Data on wind tunnel and boundary layers

**Find:** Uniform velocity at exit; Change in static pressure through the test section

**Solution:**

**Basic equations**  $\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$  (4.12)  $\delta_{\text{disp}} = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy$   $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$

Assumptions: 1) Steady flow 2) Incompressible 3) No friction outside boundary layer 4) Flow along streamline 5) Horizontal

For this flow  $\rho \cdot U \cdot A = \text{const}$  and  $\frac{u}{U} = \left(\frac{y}{\delta}\right)^{\frac{1}{7}}$

The given data is  $U_1 = 25 \cdot \frac{\text{m}}{\text{s}}$   $h = 25 \cdot \text{cm}$   $A = h^2$   $A = 625 \cdot \text{cm}^2$

We also have  $\delta_1 = 20 \cdot \text{mm}$   $\delta_2 = 30 \cdot \text{mm}$

Hence  $\delta_{\text{disp}} = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left[1 - \left(\frac{y}{\delta}\right)^{\frac{1}{7}}\right] dy = \delta \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta$  where  $\eta = \frac{y}{\delta}$   $\delta_{\text{disp}} = \frac{\delta}{8}$

Hence at the inlet and exit

$\delta_{\text{disp1}} = \frac{\delta_1}{8}$   $\delta_{\text{disp1}} = 2.5 \cdot \text{mm}$   $\delta_{\text{disp2}} = \frac{\delta_2}{8}$   $\delta_{\text{disp2}} = 3.75 \cdot \text{mm}$

Hence the areas are  $A_1 = (h - 2 \cdot \delta_{\text{disp1}})^2$   $A_1 = 600 \cdot \text{cm}^2$

$A_2 = (h - 2 \cdot \delta_{\text{disp2}})^2$   $A_2 = 588 \cdot \text{cm}^2$

Applying mass conservation between Points 1 and 2

$(-\rho \cdot U_1 \cdot A_1) + (\rho \cdot U_2 \cdot A_2) = 0$  or  $U_2 = U_1 \cdot \frac{A_1}{A_2}$   $U_2 = 25.52 \frac{\text{m}}{\text{s}}$

The pressure change is found from Bernoulli  $\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$  with  $\rho = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$

Hence  $\Delta p = \frac{\rho}{2} \cdot (U_1^2 - U_2^2)$   $\Delta p = -15.8 \text{ Pa}$  The pressure drops slightly through the test section

## Problem 9.24

[Difficulty: 2]

**9.24** The square test section of a small laboratory wind tunnel has sides of width  $W = 40$  cm. At one measurement location, the turbulent boundary layers on the tunnel walls are  $\delta_1 = 1$  cm thick. The velocity profile is approximated well by the  $\frac{1}{7}$ -power expression. At this location, the freestream air speed is  $U_1 = 20$  m/s, and the static pressure is  $p_1 = -250$  Pa (gage). At a second measurement location downstream, the boundary layer thickness is  $\delta_2 = 1.3$  cm. Evaluate the air speed in the freestream in the second section. Calculate the difference in static pressure from section ① to section ②.

**Given:** Data on wind tunnel and boundary layers

**Find:** Uniform velocity at Point 2; Change in static pressure through the test section

**Solution:**

**Basic equations** 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12) \quad \delta_{\text{disp}} = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy \quad \frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$$

Assumptions: 1) Steady flow 2) Incompressible 3) No friction outside boundary layer 4) Flow along streamline 5) Horizontal

For this flow  $\rho \cdot U \cdot A = \text{const}$  and  $\frac{u}{U} = \left(\frac{y}{\delta}\right)^{\frac{1}{7}}$

The given data is  $U_1 = 20 \cdot \frac{\text{m}}{\text{s}}$   $W = 40 \cdot \text{cm}$   $A = W^2$   $A = 0.1600 \cdot \text{m}^2$

We also have  $\delta_1 = 1 \cdot \text{cm}$   $\delta_2 = 1.3 \cdot \text{cm}$

Hence 
$$\delta_{\text{disp}} = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left[1 - \left(\frac{y}{\delta}\right)^{\frac{1}{7}}\right] dy = \delta \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta \quad \text{where} \quad \eta = \frac{y}{\delta} \quad \delta_{\text{disp}} = \frac{\delta}{8}$$

Hence at the inlet and exit

$$\delta_{\text{disp}1} = \frac{\delta_1}{8} \quad \delta_{\text{disp}1} = 0.125 \cdot \text{cm} \quad \delta_{\text{disp}2} = \frac{\delta_2}{8} \quad \delta_{\text{disp}2} = 0.1625 \cdot \text{cm}$$

Hence the areas are  $A_1 = (W - 2 \cdot \delta_{\text{disp}1})^2$   $A_1 = 0.1580 \cdot \text{m}^2$

$$A_2 = (W - 2 \cdot \delta_{\text{disp}2})^2 \quad A_2 = 0.1574 \cdot \text{m}^2$$

Applying mass conservation between Points 1 and 2

$$(-\rho \cdot U_1 \cdot A_1) + (\rho \cdot U_2 \cdot A_2) = 0 \quad \text{or} \quad U_2 = U_1 \cdot \frac{A_1}{A_2} \quad U_2 = 20.1 \cdot \frac{\text{m}}{\text{s}}$$


The pressure change is found from Bernoulli  $\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$  with  $\rho = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$

Hence 
$$\Delta p = \frac{\rho}{2} \cdot (U_1^2 - U_2^2) \quad \Delta p = -2.66 \times 10^{-4} \cdot \text{psi} \quad \Delta p = -1.835 \cdot \text{Pa}$$

## Problem 9.25

[Difficulty: 2]

**9.25** Air flows in the entrance region of a square duct, as shown. The velocity is uniform,  $U_0 = 100$  ft/s, and the duct is 3 in. square. At a section 1 ft downstream from the entrance, the displacement thickness,  $\delta^*$ , on each wall measures 0.035 in. Determine the pressure change between sections ① and ②.



**Given:** Data on wind tunnel and boundary layers

**Find:** Pressure change between points 1 and 2

**Solution:**

**Basic equations**  $\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$  (4.12)  $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$

Assumptions: 1) Steady flow 2) Incompressible 3) No friction outside boundary layer 4) Flow along streamline 5) Horizontal

For this flow  $\rho \cdot U \cdot A = \text{const}$

The given data is  $U_0 = 100 \cdot \frac{\text{ft}}{\text{s}}$   $U_1 = U_0$   $h = 3 \cdot \text{in}$   $A_1 = h^2$   $A_1 = 9 \cdot \text{in}^2$

We also have  $\delta_{\text{disp}2} = 0.035 \cdot \text{in}$

Hence at the Point 2  $A_2 = (h - 2 \cdot \delta_{\text{disp}2})^2$   $A_2 = 8.58 \cdot \text{in}^2$

Applying mass conservation between Points 1 and 2

$$(-\rho \cdot U_1 \cdot A_1) + (\rho \cdot U_2 \cdot A_2) = 0 \quad \text{o}$$

$$U_2 = U_1 \cdot \frac{A_1}{A_2} \quad \text{r} \quad U_2 = 105 \cdot \frac{\text{ft}}{\text{s}}$$

The pressure change is found from Bernoulli  $\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$   $\text{wit}$   $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$

Hence  $\Delta p = \frac{\rho}{2} \cdot (U_1^2 - U_2^2)$   $\Delta p = -8.05 \times 10^{-3} \cdot \text{psi}$   $\Delta p = -1.16 \cdot \frac{\text{lbf}}{\text{ft}^2}$

The pressure drops by a small amount as the air accelerates

## Problem 9.26

[Difficulty: 3]

**9.26** Flow of 68°F air develops in a flat horizontal duct following a well-rounded entrance section. The duct height is  $H = 1$  ft. Turbulent boundary layers grow on the duct walls, but the flow is not yet fully developed. Assume that the velocity profile in each boundary layer is  $u/U = (y/\delta)^{1/7}$ . The inlet flow is uniform at  $V = 40$  ft/s at section ①. At section ②, the boundary-layer thickness on each wall of the channel is  $\delta_2 = 4$  in. Show that, for this flow,  $\delta^* = \delta/8$ . Evaluate the static gage pressure at section ①. Find the average wall shear stress between the entrance and section ②, located at  $L = 20$  ft.

**Given:** Developing flow of air in flat horizontal duct. Assume 1/7-power law velocity profile in boundary layer.

**Find:** (a) Displacement thickness is 1/8 times boundary layer thickness  
 (b) Static gage pressure at section 1.  
 (c) Average wall shear stress between entrance and section 2.

**Solution:** We will apply the continuity and x-momentum equations to this problem.

**Governing Equations:**


$$\delta_{\text{disp}} = \int_0^{\infty} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy \quad (\text{Definition of displacement thickness})$$

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (\text{Continuity})$$

$$\frac{\partial}{\partial t} \int_{CV} \rho u dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} = F_{sx} + F_{bx} \quad (\text{x-Momentum})$$

**Assumptions:**

- (1) Steady, incompressible flow
- (2) No body forces in the x-direction
- (3) No viscous forces outside boundary layer
- (4) Boundary layers only grow on horizontal walls



If we divide both sides of the displacement thickness definition by  $\delta$ , we get:

$$\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{\delta} \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy$$

However, we can change the variable of integration to  $\eta = y/\delta$ , resulting in:

$$d\eta = \frac{1}{\delta} dy \quad \text{Therefore:} \quad \frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$$

For the power law profile:  $\frac{u}{U} = \eta^{1/7}$  Into the displacement thickness:

$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \eta^{1/7}\right) d\eta$$

$$\text{Evaluating this integral:} \quad \frac{\delta_{\text{disp}}}{\delta} = 1 - \frac{7}{8} = \frac{1}{8} \qquad \frac{\delta_{\text{disp}}}{\delta} = \frac{1}{8}$$

After applying the assumptions from above, continuity reduces to:  $V_1 \cdot A_1 = V_2 \cdot A_2$  or  $V_1 \cdot w \cdot H = V_2 \cdot w \cdot (H - 2 \cdot \delta_{\text{disp}2})$

Solving for the velocity at 2:  $V_2 = V_1 \cdot \frac{H}{H - 2 \cdot \delta_{\text{disp}2}} = V_1 \cdot \frac{H}{H - \frac{\delta_2}{4}}$  Substituting known values:

$$V_2 = 40 \cdot \frac{\text{ft}}{\text{s}} \times 1 \cdot \text{ft} \times \left( \frac{1}{1 - \frac{1}{4} \times \frac{4}{12}} \right) \cdot \frac{1}{\text{ft}} \quad V_2 = 43.6 \cdot \frac{\text{ft}}{\text{s}}$$

From Bernoulli equation, since  $z = \text{constant}$ :  $\frac{p_0}{\rho} = \frac{p}{\rho} + \frac{V^2}{2}$  along a streamline. Therefore:

$$p_{1g} = p_1 - p_0 = -\frac{1}{2} \cdot \rho \cdot V_1^2 \quad p_{1g} = -\frac{1}{2} \times 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 40 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_{1g} = -0.01300 \cdot \text{psi}$$

$$p_{2g} = p_2 - p_0 = -\frac{1}{2} \cdot \rho \cdot V_2^2 \quad p_{2g} = -\frac{1}{2} \times 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 43.6 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad p_{2g} = -0.01545 \cdot \text{psi}$$

Now if we apply the momentum equation to the control volume (considering the assumptions shown):  $F_{sx} = \int_{CS} u \rho \vec{V} \cdot d\vec{A}$

$$(p_1 - p_2) \cdot w \cdot \frac{H}{2} - \tau \cdot w \cdot L = V_1 \left( -\rho \cdot V_1 \cdot \frac{H}{2} \cdot w \right) + \int_0^{\delta_2} u \cdot \rho \cdot u \cdot w \cdot dy + V_2 \cdot \left[ \rho \cdot V_2 \cdot \left( \frac{H}{2} - \delta_2 \right) \cdot w \right]$$

The integral is equal to:  $\rho \cdot w \cdot \int_0^{\delta_2} u^2 \cdot dy = \rho \cdot V_2^2 \cdot \delta_2 \cdot w \cdot \int_0^1 \eta^{\frac{2}{7}} \cdot d\eta = \rho \cdot V_2^2 \cdot \frac{7}{9} \delta_2 \cdot w$  Therefore the momentum equation becomes:

$$(p_1 - p_2) \cdot w \cdot \frac{H}{2} - \tau \cdot w \cdot L = -\rho \cdot V_1^2 \cdot \frac{H}{2} \cdot w + \rho \cdot V_2^2 \cdot \left( \frac{H}{2} - \frac{2}{9} \delta_2 \right) \cdot w \quad \text{Simplifying and solving for the shear stress we get:}$$

$$\tau = \frac{1}{L} \cdot \left[ (p_1 - p_2) \cdot \frac{H}{2} + \rho \cdot \left[ V_1^2 \cdot \frac{H}{2} - V_2^2 \cdot \left( \frac{H}{2} - \frac{2}{9} \delta_2 \right) \right] \right] \quad \text{Substituting in known values we get:}$$

$$\tau = \frac{1}{20 \cdot \text{ft}} \cdot \left[ [(-0.01328) - (-0.01578)] \cdot \frac{\text{lbf}}{\text{in}^2} \cdot \frac{1 \cdot \text{ft}}{2} + 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3} \cdot \left[ \left( 40 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \cdot \frac{1 \cdot \text{ft}}{2} - \left( 43.6 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \cdot \left( \frac{1}{2} - \frac{2}{9} \cdot \frac{4}{12} \right) \cdot \text{ft} \right] \cdot \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \cdot \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \right]$$

$$\tau = 5.46 \times 10^{-5} \cdot \text{psi}$$

## Problem 9.27

[Difficulty: 3]

**9.27** A laboratory wind tunnel has a square test section with sides of width  $W = 1$  ft and length  $L = 2$  ft. When the freestream air speed at the test section entrance is  $U_1 = 80$  ft/s, the head loss from the atmosphere is 0.3 in.  $H_2O$ . Turbulent boundary layers form on the top, bottom, and side walls of the test section. Measurements show the boundary-layer thicknesses are  $\delta_1 = 0.8$  in at the entrance and  $\delta_2 = 1$  in at the outlet of the test section. The velocity profiles are of  $\frac{1}{7}$ -power form. Evaluate the free-stream air speed at the outlet from the test section. Determine the static pressures at the test section inlet and outlet.

**Given:** Air flow in laboratory wind tunnel test section.

**Find:** (a) Freestream speed at exit  
(b) Pressure at exit

**Solution:** We will apply the continuity and Bernoulli equations to this problem.

**Governing Equations:**

$$\delta_{\text{disp}} = \int_0^{\text{infinity}} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy \quad (\text{Definition of displacement thickness})$$

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (\text{Continuity})$$

$$\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{const} \quad (\text{Bernoulli})$$

**Assumptions:**

- |  |   |
|--|---|
| (1) Steady, incompressible flow                | (5) Uniform flow outside boundary layer     |
| (2) No body forces in the x-direction          | (6) Boundary layer is the same on all walls |
| (3) No viscous forces outside boundary layer   | (7) Neglect corner effects                  |
| (4) Streamline exists between stations 1 and 2 | (8) Constant elevation between 1 and 2      |

If we divide both sides of the displacement thickness definition by  $\delta$ , we get:

$$\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{\delta} \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy$$

However, we can change the variable of integration to  $\eta = y/\delta$ , resulting in:

$$d\eta = \frac{1}{\delta} \cdot dy$$

Therefore:  $\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$  For the power law profile:  $\frac{u}{U} = \eta^{\frac{1}{7}}$  Into the displacement thickness:


$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta$  Evaluating this integral:  $\frac{\delta_{\text{disp}}}{\delta} = 1 - \frac{7}{8} = \frac{1}{8}$  So the displacement thicknesses are:

$$\delta_{\text{disp}1} = \frac{1}{8} \times 0.8 \cdot \text{in}$$

$$\delta_{\text{disp}1} = 0.100 \cdot \text{in}$$

$$\delta_{\text{disp}2} = \frac{1}{8} \times 1 \cdot \text{in}$$

$$\delta_{\text{disp}2} = 0.125 \cdot \text{in}$$



After applying the assumptions from above, continuity reduces to:  $U_1 \cdot A_1 = U_2 \cdot A_2$  or  $U_1 \cdot (W - 2 \cdot \delta_{\text{disp1}})^2 = U_2 \cdot (W - 2 \cdot \delta_{\text{disp2}})^2$

Solving for the speed at 2:  $U_2 = U_1 \cdot \left( \frac{W - 2 \cdot \delta_{\text{disp1}}}{W - 2 \cdot \delta_{\text{disp2}}} \right)^2$  Substituting known values:  $U_2 = 80 \cdot \frac{\text{ft}}{\text{s}} \times \left( \frac{1 - 2 \times 0.100}{1 - 2 \times 0.125} \right)^2$

$$U_2 = 91.0 \cdot \frac{\text{ft}}{\text{s}}$$

From Bernoulli equation, since  $z = \text{constant}$ :  $\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$  along a streamline. Therefore:

$$\Delta p_{12} = \frac{\rho}{2} \cdot (U_1^2 - U_2^2) \quad \Delta p_{12} = \frac{1}{2} \times 0.00239 \cdot \frac{\text{slug}}{\text{ft}^3} \times (80^2 - 91^2) \frac{\text{ft}^2}{\text{s}^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad \Delta p_{12} = -0.01561 \cdot \text{psi}$$

From ambient to station 1 we see a loss at the tunnel entrance:



$$\left( \frac{p_0}{\rho} + \frac{U_0^2}{2} \right) - \left( \frac{p_1}{\rho} + \frac{U_1^2}{2} \right) = h_{IT} \quad \text{Since } U_0 = 0 \text{ and } p_0 = p_{\text{atm}} = 0 \text{ we can solve for the pressure at 1:}$$

$$p_1 = -\rho \cdot h_{IT} + \frac{1}{2} \cdot \rho \cdot U_1^2 \quad \text{where} \quad \rho h_{IT} = -\frac{0.3}{12} \cdot \text{ft} \times 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \times 32.2 \cdot \frac{\text{ft}}{\text{s}^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 \quad \rho h_{IT} = -0.01085 \cdot \text{psi}$$

Therefore:  $p_1 = -0.01085 \cdot \frac{\text{lbf}}{\text{in}^2} - \frac{1}{2} \times 0.00239 \cdot \frac{\text{slug}}{\text{ft}^3} \times \left( 80 \cdot \frac{\text{ft}}{\text{s}} \right)^2 \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \left( \frac{\text{ft}}{12 \cdot \text{in}} \right)^2 = -0.0640 \cdot \text{psi}$  So the pressure at 2 is:

$$p_2 = p_1 + \Delta p_{12} \quad p_2 = -0.0640 \cdot \text{psi} - 0.01561 \cdot \text{psi} = -0.0796 \cdot \text{psi} \quad \text{Since the pressure drop can be expressed as } p_2 = \rho \cdot g \cdot h_2$$

it follows that:  $h_2 = \frac{p_2}{\rho \cdot g}$  So in terms of water height:  $h_2 = 0.0796 \cdot \frac{\text{lbf}}{\text{in}^2} \times \left( \frac{12 \cdot \text{in}}{\text{ft}} \right)^2 \times \frac{\text{ft}^3}{1.94 \cdot \text{slug}} \times \frac{\text{s}^2}{32.2 \cdot \text{ft}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} \times \frac{12 \cdot \text{in}}{\text{ft}}$

$$p_2 = -0.0796 \cdot \text{psi}$$

$$h_2 = 2.20 \cdot \text{in}$$

## Problem 9.28

[Difficulty: 3]

**9.28** Flow of air develops in a horizontal cylindrical duct, of diameter  $D = 15$  in., following a well-rounded entrance. A turbulent boundary grows on the duct wall, but the flow is not yet fully developed. Assume that the velocity profile in the boundary layer is  $u/U = (y/\delta)^{1/7}$ . The inlet flow is  $U = 50$  ft/s at section ①. At section ②, the boundary-layer thickness is  $\delta_2 = 4$  in. Evaluate the static gage pressure at section ②, located at  $L = 20$  ft. Find the average wall shear stress.

**Given:** Data on fluid and boundary layer geometry

**Find:** Gage pressure at location 2; average wall stress

**Solution:**

The solution involves using mass conservation in the inviscid core, allowing for the fact that as the boundary layer grows it reduces the size of the core. One approach would be to integrate the 1/7 law velocity profile to compute the mass flow in the boundary layer; an easier approach is to simply use the displacement thickness!

The average wall stress can be estimated using the momentum equation for a CV

The given and available (from Appendix A) data is

$$\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3} \quad U_1 = 50 \cdot \frac{\text{ft}}{\text{s}} \quad L = 20 \cdot \text{ft} \quad D = 15 \cdot \text{in} \quad \delta_2 = 4 \cdot \text{in}$$

Governing equations:

Mass (4.12)

$$\frac{\partial}{\partial t} \int_{\text{CV}} \rho \, dV + \int_{\text{CS}} \rho \vec{V} \cdot d\vec{A} = 0$$

Momentum (4.17a)

$$\vec{F} = \vec{F}_S + \vec{F}_B = \frac{\partial}{\partial t} \int_{\text{CV}} \vec{V} \rho \, dV + \int_{\text{CS}} \vec{V} \rho \vec{V} \cdot d\vec{A}$$

Bernoulli (4.24)

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant}$$

Assumptions: (1) Steady flow (2) No pressure force (3) No body force in x direction

The displacement thickness at location 2 can be computed from boundary layer thickness using Eq. 9.1

$$\delta_{\text{disp}2} = \int_0^{\delta_2} \left(1 - \frac{u}{U}\right) dy = \delta_2 \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta = \frac{\delta_2}{8}$$

Hence  $\delta_{\text{disp}2} = \frac{\delta_2}{8}$   $\delta_{\text{disp}2} = 0.500 \cdot \text{in}$

Applying mass conservation at locations 1 and 2  $(-\rho \cdot U_1 \cdot A_1) + (\rho \cdot U_2 \cdot A_2) = 0$  or  $U_2 = U_1 \cdot \frac{A_1}{A_2}$

$$A_1 = \frac{\pi}{4} \cdot D^2 \quad A_1 = 1.227 \cdot \text{ft}^2$$

The area at location 2 is given by the duct cross section area minus the displacement boundary layer

$$A_2 = \frac{\pi}{4} \cdot (D - 2 \cdot \delta_{\text{disp}2})^2 \quad A_2 = 1.069 \cdot \text{ft}^2$$

Hence 
$$U_2 = U_1 \cdot \frac{A_1}{A_2} \qquad U_2 = 57.4 \cdot \frac{\text{ft}}{\text{s}}$$

For the pressure change we can apply Bernoulli to locations 1 and 2 to find

$$p_1 - p_2 = \Delta p = \frac{\rho}{2} \cdot (U_2^2 - U_1^2) \qquad \Delta p = 6.46 \times 10^{-3} \cdot \text{psi} \qquad p_2 = -\Delta p$$

Hence 
$$p_2(\text{gage}) = p_1(\text{gage}) - \Delta p \qquad p_2 = -6.46 \times 10^{-3} \cdot \text{psi}$$

For the average wall shear stress we use the momentum equation, simplified for this problem

$$\Delta p \cdot A_1 - \tau \cdot \pi \cdot D \cdot L = -\rho \cdot U_1^2 \cdot A_1 + \rho \cdot U_2^2 \cdot \frac{\pi}{4} \cdot (D - 2 \cdot \delta_2)^2 + \rho \cdot \int_{\frac{D}{2} - \delta_2}^{\frac{D}{2}} 2 \cdot \pi \cdot r \cdot u^2 \, dr$$

where 
$$u(r) = U_2 \cdot \left( \frac{y}{\delta_2} \right)^{\frac{1}{7}} \qquad \text{and} \qquad r = \frac{D}{2} - y \qquad dr = -dy$$

The integral is 
$$\rho \cdot \int_{\frac{D}{2} - \delta_2}^{\frac{D}{2}} 2 \cdot \pi \cdot r \cdot u^2 \, dr = -2 \cdot \pi \cdot \rho \cdot U_2^2 \cdot \int_{\delta_2}^0 \left( \frac{D}{2} - y \right) \cdot \left( \frac{y}{\delta_2} \right)^{\frac{2}{7}} \, dy$$

$$\rho \cdot \int_{\frac{D}{2} - \delta_2}^{\frac{D}{2}} 2 \cdot \pi \cdot r \cdot u^2 \, dr = 7 \cdot \pi \cdot \rho \cdot U_2^2 \cdot \delta_2 \cdot \left( \frac{D}{9} - \frac{\delta_2}{8} \right)$$

Hence 
$$\tau = \frac{\Delta p \cdot A_1 + \rho \cdot U_1^2 \cdot A_1 - \rho \cdot U_2^2 \cdot \frac{\pi}{4} \cdot (D - 2 \cdot \delta_2)^2 - 7 \cdot \pi \cdot \rho \cdot U_2^2 \cdot \delta_2 \cdot \left( \frac{D}{9} - \frac{\delta_2}{8} \right)}{\pi \cdot D \cdot L}$$


$$\tau = 6.767 \times 10^{-5} \cdot \text{psi}$$

## Problem 9.29

[Difficulty: 5]

**9.29** Air flows into the inlet contraction section of a wind tunnel in an undergraduate laboratory. From the inlet the air enters the test section, which is square in cross-section with side dimensions of 305 mm. The test section is 609 mm long. At one operating condition air leaves the contraction at 50.2 m/s with negligible boundary-layer thickness. Measurements show that boundary layers at the downstream end of the test section are 20.3 mm thick. Evaluate the displacement thickness of the boundary layers at the downstream end of the wind tunnel test section. Calculate the change in static pressure along the wind tunnel test section. Estimate the approximate total drag force caused by skin friction on each wall of the wind tunnel.

**Given:** Air flow in laboratory wind tunnel test section.



**Find:** (a) Displacement thickness at station 2  
 (b) Pressure drop between 1 and 2  
 (c) Total drag force caused by friction on each wall

**Solution:** We will apply the continuity, x-momentum, and Bernoulli equations to this problem.

**Governing Equations:**

$$\delta_{\text{disp}} = \int_0^{\infty} \left(1 - \frac{u}{U}\right) dy = \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy \quad (\text{Definition of displacement thickness})$$

$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0 \quad (\text{Continuity})$$

$$\frac{p}{\rho} + \frac{V^2}{2} + gz = \text{const} \quad (\text{Bernoulli})$$

$$\frac{\partial}{\partial t} \int_{CV} \rho u dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A} = F_{sx} + F_{bx} \quad (\text{x-Momentum})$$

**Assumptions:**

- (1) Steady, incompressible flow
- (2) No body forces in the x-direction
- (3) No viscous forces outside boundary layer
- (4) Streamline exists between stations 1 and 2
- (5) Uniform flow outside boundary layer
- (6) Boundary layer is the same on all walls
- (7) Neglect corner effects
- (8) Constant elevation between 1 and 2

If we divide both sides of the displacement thickness definition by \$\delta\$, we get:  $\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{\delta} \int_0^{\delta} \left(1 - \frac{u}{U}\right) dy$

However, we can change the variable of integration to \$\eta = y/\delta\$, resulting in:  $d\eta = \frac{1}{\delta} \cdot dy$  Therefore:  $\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$

If we assume the power law profile (turbulent BL):  $\frac{u}{U} = \eta^{\frac{1}{7}}$  Into the displacement thickness:  $\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta$

Evaluating this integral:  $\frac{\delta_{\text{disp}}}{\delta} = 1 - \frac{7}{8} = \frac{1}{8}$  So the displacement thickness is:  $\delta_{\text{disp}2} = \frac{1}{8} \times 20.3 \cdot \text{mm}$   $\delta_{\text{disp}2} = 2.54 \cdot \text{mm}$

After applying the assumptions from above, continuity reduces to:  $U_1 \cdot A_1 = U_2 \cdot A_2$  or  $U_1 \cdot H^2 = U_2 \cdot (H - 2 \cdot \delta_{\text{disp}2})^2$

Solving for the speed at 2:  $U_2 = U_1 \cdot \left(\frac{H}{H - 2 \cdot \delta_{\text{disp}2}}\right)^2$  Substituting known values:  $U_2 = 50.2 \cdot \frac{\text{m}}{\text{s}} \times \left(\frac{305}{305 - 2 \times 2.54}\right)^2$

$$U_2 = 51.9 \frac{\text{m}}{\text{s}}$$

From Bernoulli equation, since  $z = \text{constant}$ :  $\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$  along a streamline. Therefore:

$$\Delta p_{12} = \frac{\rho}{2} \cdot (U_1^2 - U_2^2) \quad \Delta p_{12} = \frac{1}{2} \times 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \times (50.2^2 - 51.9^2) \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \quad \Delta p_{12} = -106.7 \text{ Pa}$$

To determine the drag on the walls, we choose the control volume shown above and apply the x-momentum equation.

From the assumptions, the equation reduces to:  $\int_{CS} u \rho \vec{V} \cdot d\vec{A} = F_{sx}$  Applying this to the control volume:

$p_1 \cdot H \cdot \delta_2 - F_D - p_2 \cdot H \cdot \delta_2 = U_1 \cdot (-\rho \cdot U_1 \cdot H \cdot \delta_2) + U_{\text{avg}} \cdot m_{\text{top}} + \int_0^{\delta_2} u \cdot \rho \cdot u \cdot H \, dy$  The mass flow rate through the top of the CV

can be determined using the continuity equation across the control volume:  $m_{\text{top}} = m_1 - m_2 = \rho \cdot U_1 \cdot H \cdot \delta_2 - \int_0^{\delta_2} \rho \cdot u \cdot H \, dy$

This integral can be evaluated using the power law profile:  $\int_0^{\delta_2} \rho \cdot u \cdot H \, dy = \rho \cdot U_2 \cdot H \cdot \delta_2 \cdot \int_0^1 \eta^{\frac{1}{7}} \, d\eta = \frac{7}{8} \cdot \rho \cdot U_2 \cdot H \cdot \delta_2$  Therefore:

$m_{\text{top}} = \rho \cdot H \cdot \delta_2 \cdot \left(U_1 - \frac{7}{8} \cdot U_2\right)$  The average speed can be approximated as the mean of the speeds at 1 and 2:  $U_{\text{avg}} = \frac{U_1 + U_2}{2}$

Finally the integral in the momentum equation may also be evaluated using the power law profile:

$\int_0^{\delta_2} u \cdot \rho \cdot u \cdot H \, dy = \rho \cdot U_2^2 \cdot H \cdot \delta_2 \cdot \int_0^1 \eta^{\frac{2}{7}} \, d\eta = \frac{7}{9} \cdot \rho \cdot U_2^2 \cdot H \cdot \delta_2$  Thus, the momentum equation may be rewritten as:

$p_1 \cdot H \cdot \delta_2 - F_D - p_2 \cdot H \cdot \delta_2 = U_1 \cdot (-\rho \cdot U_1 \cdot H \cdot \delta_2) + \frac{U_1 + U_2}{2} \cdot \rho \cdot H \cdot \delta_2 \cdot \left(U_1 - \frac{7}{8} \cdot U_2\right) + \frac{7}{9} \cdot \rho \cdot U_2^2 \cdot H \cdot \delta_2$  Solving for the drag force:


$$F_D = \left[ (p_1 - p_2) + \rho \left[ U_1^2 - \left( \frac{U_1 + U_2}{2} \right) \cdot \left( U_1 - \frac{7}{8} \cdot U_2 \right) - \frac{7}{9} \cdot U_2^2 \right] \right] \cdot H \cdot \delta_2$$

Substituting in all known values yields:

$$F_D = \left[ 106.7 \cdot \frac{\text{N}}{\text{m}^2} + 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \times \left[ \left( 50.2 \cdot \frac{\text{m}}{\text{s}} \right)^2 - \frac{(50.2 + 51.9)}{2} \times \left( 50.2 - \frac{7}{8} \cdot 51.9 \right) \cdot \frac{\text{m}^2}{\text{s}^2} - \frac{7}{9} \cdot \left( 51.9 \cdot \frac{\text{m}}{\text{s}} \right)^2 \right] \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \right] \times 0.305 \cdot \text{m} \times 0.020$$

$$F_D = 2.04 \text{ N}$$

The viscous drag force acts on the CV in the direction shown. The viscous drag force on the wall of the test section is equal and opposite:



## Problem 9.30


[Difficulty: 2]

**\*9.30** Using numerical results for the Blasius exact solution for laminar boundary-layer flow on a flat plate, plot the dimensionless velocity profile,  $u/U$  (on the abscissa), versus dimensionless distance from the surface,  $y/\delta$  (on the ordinate). Compare with the approximate parabolic velocity profile of Problem 9.10.

**Given:** Blasius exact solution for laminar boundary layer flow

**Find:** Plot and compare to parabolic velocity profile:  $\frac{u}{U} = 2\left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$

**Solution:** The Blasius solution is given in Table 9.1; it is plotted below.



## Problem 9.31

[Difficulty: 3]

**\*9.31** Using numerical results obtained by Blasius (Table 9.1), evaluate the distribution of shear stress in a laminar boundary layer on a flat plate. Plot  $\tau/\tau_w$  versus  $y/\delta$ . Compare with results derived from the approximate sinusoidal velocity profile given in Problem 9.10.

**Given:** Blasius exact solution for laminar boundary layer flow

**Find:**

(a) Evaluate shear stress distribution

(b) Plot  $\tau/\tau_w$  versus  $y/\delta$

(c) Compare with results from sinusoidal velocity profile:  $\frac{u}{U} = \sin\left(\frac{\pi \cdot y}{2 \delta}\right)$

**Solution:** We will apply the shear stress definition to both velocity profiles.

**Governing Equation:**

$$\tau = \mu \cdot \frac{\partial u}{\partial y} \quad (\text{Shear stress in Newtonian fluid})$$


For Blasius:  $u = U \cdot f'(\eta)$  and  $\eta = y \cdot \sqrt{\frac{U}{\nu \cdot x}}$  The shear stress is:  $\tau = \mu \cdot \frac{\partial}{\partial y} (U \cdot f'(\eta)) = U \cdot \mu \cdot (f''(\eta)) \cdot \left(\frac{\partial}{\partial y} \eta\right) = U \cdot \mu \cdot f''(\eta) \cdot \sqrt{\frac{U}{\nu \cdot x}}$

Therefore:  $\frac{\tau}{\rho \cdot U^2} = \frac{\mu}{\rho \cdot U} \cdot f''(\eta) \cdot \sqrt{\frac{U}{\nu \cdot x}} = \frac{f''(\eta)}{\sqrt{Re_x}}$   $\tau$  is proportional to  $f''(\eta)$

From the above equation:  $\frac{\tau}{\tau_w} = \frac{f''(\eta)}{f''(0)} = \frac{f''(\eta)}{0.33206}$  Since  $y = \delta$  at  $\eta = 5$  it follows that  $\frac{y}{\delta} = \frac{\eta}{5}$

For the sinusoidal profile:  $\tau = \frac{\mu \cdot U}{\delta} \cdot \left[ \frac{d}{d\left(\frac{y}{\delta}\right)} \left(\frac{u}{U}\right) \right] = \frac{\mu \cdot U}{\delta} \cdot \frac{\pi}{2} \cdot \cos\left(\frac{\pi \cdot y}{2 \delta}\right)$   $\tau_w = \frac{\mu \cdot U}{\delta} \cdot \frac{\pi}{2}$  Thus:  $\frac{\tau}{\tau_w} = \cos\left(\frac{\pi \cdot y}{2 \delta}\right)$

Both profiles are plotted here:



## Problem 9.32

[Difficulty: 3]

**\*9.32** Using numerical results obtained by Blasius (Table 9.1), evaluate the distribution of shear stress in a laminar boundary layer on a flat plate. Plot  $\tau/\tau_w$  versus  $y/\delta$ . Compare with results derived from the approximate parabolic velocity profile given in Problem 9.10.

**Given:** Blasius exact solution for laminar boundary layer flow

**Find:**

(a) Evaluate shear stress distribution

(b) Plot  $\tau/\tau_w$  versus  $y/\delta$

(c) Compare with results from sinusoidal velocity profile:  $\frac{u}{U} = 2 \cdot \frac{y}{\delta} - \left(\frac{y}{\delta}\right)^2$

**Solution:** We will apply the shear stress definition to both velocity profiles.

**Governing Equation:**

$$\tau = \mu \cdot \frac{\partial}{\partial y} u \quad (\text{Shear stress in Newtonian fluid})$$


For Blasius:  $u = U \cdot f'(\eta)$  and  $\eta = y \cdot \sqrt{\frac{U}{\nu \cdot x}}$  The shear stress is:  $\tau = \mu \cdot \frac{\partial}{\partial y} (U \cdot f'(\eta)) = U \cdot \mu \cdot (f''(\eta)) \cdot \left(\frac{\partial}{\partial y} \eta\right) = U \cdot \mu \cdot f''(\eta) \cdot \sqrt{\frac{U}{\nu \cdot x}}$

Therefore:  $\frac{\tau}{\rho \cdot U^2} = \frac{\mu}{\rho \cdot U} \cdot f''(\eta) \cdot \sqrt{\frac{U}{\nu \cdot x}} = \frac{f''(\eta)}{\sqrt{Re_x}}$   $\tau$  is proportional to  $f''(\eta)$

From the above equation:  $\frac{\tau}{\tau_w} = \frac{f''(\eta)}{f''(0)} = \frac{f''(\eta)}{0.33206}$  Since  $y = \delta$  at  $\eta = 5$  it follows that  $\frac{y}{\delta} = \frac{\eta}{5}$

For the parabolic profile:  $\tau = \frac{\mu \cdot U}{\delta} \cdot \left[ \frac{d}{d\left(\frac{y}{\delta}\right)} \left(\frac{u}{U}\right) \right] = \frac{\mu \cdot U}{\delta} \cdot \left(2 - 2 \cdot \frac{y}{\delta}\right)$   $\tau_w = \frac{\mu \cdot U}{\delta} \cdot 2$  Thus:  $\frac{\tau}{\tau_w} = 1 - \frac{y}{\delta}$

Both profiles are plotted here:



## Problem 9.33

[Difficulty: 3]

**\*9.33** Using numerical results obtained by Blasius (Table 9.1), evaluate the vertical component of velocity in a laminar boundary layer on a flat plate. Plot  $v/U$  versus  $y/\delta$  for  $Re_x = 10^5$ .

**Given:** Blasius exact solution for laminar boundary layer flow

**Find:** Plot  $v/U$  versus  $y/\delta$  for  $Re_x = 10^5$

**Solution:** We will apply the stream function definition to the Blasius solution.


For Blasius:  $u = U \cdot f(\eta)$  and  $\eta = y \cdot \sqrt{\frac{U}{\nu \cdot x}}$  The stream function is:  $\psi = \sqrt{U \cdot \nu \cdot x} \cdot f(\eta)$

From the stream function:  $v = \frac{\partial}{\partial x} \psi = \left[ \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot f(\eta) + \sqrt{\nu \cdot U \cdot x} \cdot \left( \frac{d}{d\eta} f \right) \cdot \left( \frac{\partial}{\partial x} \eta \right) \right]$  But  $\frac{\partial}{\partial x} \eta = -\frac{1}{2} \cdot \frac{y}{x} \cdot \sqrt{\frac{U}{\nu \cdot x}} = -\frac{1}{2} \cdot \frac{\eta}{x}$

Thus  $v = \left[ \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot f(\eta) + \sqrt{\nu \cdot U \cdot x} \cdot \left( \frac{d}{d\eta} f \right) \cdot \left( -\frac{1}{2} \cdot \frac{\eta}{x} \right) \right] = \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot (\eta \cdot f(\eta) - f(\eta))$  and  $\frac{v}{U} = \frac{1}{2} \cdot \sqrt{\frac{\nu}{U \cdot x}} \cdot (\eta \cdot f(\eta) - f(\eta))$

$$\frac{v}{U} = \frac{\eta \cdot f(\eta) - f(\eta)}{2 \sqrt{Re_x}}$$

Since  $y = \delta$  at  $\eta = 5$  it follows that  $\frac{y}{\delta} = \frac{\eta}{5}$  Plotting  $v/U$  as a function of  $y/\delta$ :



## Problem 9.34

[Difficulty: 3]

**\*9.34** Verify that the  $y$  component of velocity for the Blasius solution to the Prandtl boundary-layer equations is given by Eq. 9.10. Obtain an algebraic expression for the  $x$  component of the acceleration of a fluid particle in the laminar boundary layer. Plot  $a_x$  versus  $\eta$  to determine the maximum  $x$  component of acceleration at a given  $x$ .

**Given:** Blasius exact solution for laminar boundary layer flow

**Find:** (a) Prove that the  $y$  component of velocity in the solution is given by Eq. 9.10.  
 (b) Algebraic expression for the  $x$  component of a fluid particle in the BL  
 (c) Plot  $a_x$  vs  $\eta$  to determine the maximum  $x$  component of acceleration at a given  $x$

**Solution:** We will apply the stream function definition to the Blasius solution.

For Blasius:  $u = U \cdot f(\eta)$  and  $\eta = y \cdot \sqrt{\frac{U}{\nu \cdot x}}$  The stream function is:  $\psi = \sqrt{U \cdot \nu \cdot x} \cdot f(\eta)$

From the stream function:  $v = \frac{\partial}{\partial x} \psi = \left[ \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot f(\eta) + \sqrt{\nu \cdot U \cdot x} \cdot \left( \frac{d}{d\eta} f \right) \cdot \left( \frac{\partial}{\partial x} \eta \right) \right]$  But  $\frac{\partial}{\partial x} \eta = -\frac{1}{2} \cdot \frac{y}{x} \cdot \sqrt{\frac{U}{\nu \cdot x}} = -\frac{1}{2} \cdot \frac{\eta}{x}$

Thus  $v = \left[ \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot f(\eta) + \sqrt{\nu \cdot U \cdot x} \cdot \left( \frac{d}{d\eta} f \right) \cdot \left( -\frac{1}{2} \cdot \frac{\eta}{x} \right) \right] = \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot (\eta \cdot f'(\eta) - f(\eta))$  which is Eq. 9.10.

$$v = \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot (\eta \cdot f'(\eta) - f(\eta))$$


The acceleration in the  $x$ -direction is given by:  $a_x = u \cdot \frac{\partial}{\partial x} u + v \cdot \frac{\partial}{\partial y} u$  where  $u = U \cdot f(\eta)$  Evaluating the partial derivatives:

$$\frac{\partial}{\partial x} u = U \cdot \frac{d}{d\eta} f(\eta) \cdot \left( \frac{d}{dx} \eta \right) = U \cdot f'(\eta) \cdot \left( -\frac{\eta}{2 \cdot x} \right) = -\frac{1}{2} \cdot \frac{\eta \cdot U \cdot f'(\eta)}{x} \quad \frac{\partial}{\partial y} u = U \cdot \frac{d}{d\eta} f(\eta) \cdot \left( \frac{d}{dy} \eta \right) = U \cdot f'(\eta) \cdot \sqrt{\frac{U}{\nu \cdot x}} \quad \text{Therefore:}$$

$$a_x = U \cdot f(\eta) \cdot \left( -\frac{1}{2} \cdot \frac{\eta \cdot U \cdot f'(\eta)}{x} \right) + \left[ \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot (\eta \cdot f' - f) \right] \cdot \left( U \cdot f' \cdot \sqrt{\frac{U}{\nu \cdot x}} \right) = -\frac{1}{2} \cdot \frac{U^2}{x} \cdot \eta \cdot f' \cdot f' + \frac{1}{2} \cdot \frac{U^2}{x} \cdot (\eta \cdot f' \cdot f' - f \cdot f'') \quad \text{Simplifying yields:}$$

$$a_x = -\frac{U^2}{2x} \cdot f(\eta) \cdot f''(\eta)$$

If we plot  $f(\eta)f''(\eta)$  as a function of  $\eta$ :



The maximum value of this function is 0.23 at  $\eta$  of approximately 3.

$$a_{x\max} = -0.115 \cdot \frac{U^2}{x}$$

## Problem 9.35

[Difficulty: 4]

**\*9.35** Numerical results of the Blasius solution to the Prandtl boundary-layer equations are presented in Table 9.1. Consider steady, incompressible flow of standard air over a flat plate at freestream speed  $U = 5$  m/s. At  $x = 20$  cm, estimate the distance from the surface at which  $u = 0.95 U$ . Evaluate the slope of the streamline through this point. Obtain an algebraic expression for the local skin friction,  $\tau_w(x)$ . Obtain an algebraic expression for the total skin friction drag force on the plate. Evaluate the momentum thickness at  $L = 1$  m.

**Given:** Blasius solution for laminar boundary layer

**Find:** Point at which  $u = 0.95U$ ; Slope of streamline; expression for skin friction coefficient and total drag; Momentum thickness

**Solution:**

Basic equation: Use results of Blasius solution (Table 9.1 on the web), and  $\eta = y \cdot \sqrt{\frac{\nu \cdot x}{U}}$

$$f = \frac{u}{U} = 0.9130 \quad \text{at} \quad \eta = 3.5$$

$$f = \frac{u}{U} = 0.9555 \quad \text{at} \quad \eta = 4.0$$

Hence by linear interpolation, when  $f = 0.95$   $\eta = 3.5 + \frac{(4 - 3.5)}{(0.9555 - 0.9130)} \cdot (0.95 - 0.9130) \eta = 3.94$

From Table A.10 at 20°C  $\nu = 1.50 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$  and  $U = 5 \frac{\text{m}}{\text{s}} \quad x = 20 \text{ cm}$

Hence  $y = \eta \cdot \sqrt{\frac{\nu \cdot x}{U}} \quad y = 0.305 \text{ cm}$

The streamline slope is given by  $\frac{dy}{dx} = \frac{v}{u}$  where  $u = U \cdot f$  and  $v = \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot (\eta \cdot f' - f)$

$$\frac{dy}{dx} = \frac{1}{2} \cdot \sqrt{\frac{\nu \cdot U}{x}} \cdot (\eta \cdot f' - f) \cdot \frac{1}{U \cdot f} = \frac{1}{2} \cdot \sqrt{\frac{\nu}{U \cdot x}} \cdot \frac{(\eta \cdot f' - f)}{f} = \frac{1}{2 \cdot \sqrt{\text{Re}_x}} \cdot \frac{(\eta \cdot f' - f)}{f}$$

We have  $\text{Re}_x = \frac{U \cdot x}{\nu} \quad \text{Re}_x = 6.67 \times 10^4$

From the Blasius solution (Table 9.1 on the web)

$$f = 1.8377 \quad \text{at} \quad \eta = 3.5$$

$$f = 2.3057 \quad \text{at} \quad \eta = 4.0$$

Hence by linear interpolation  $f = 1.8377 + \frac{(2.3057 - 1.8377)}{(4.0 - 3.5)} \cdot (3.94 - 3.5) \quad f = 2.25$

$$\frac{dy}{dx} = \frac{1}{2 \cdot \sqrt{\text{Re}_x}} \cdot \frac{(\eta \cdot f' - f)}{f} = 0.00326$$

The shear stress is  $\tau_w = \mu \cdot \left( \frac{\partial u}{\partial y} + \frac{\partial v}{\partial x} \right) = \mu \cdot \frac{\partial u}{\partial y}$  at  $y = 0$  ( $v = 0$  at the wall for all  $x$ , so the derivative is zero there)

$$\tau_w = \mu \cdot U \cdot \sqrt{\frac{U}{\nu \cdot x}} \cdot \frac{d^2 f}{d\eta^2} \quad \text{and at } \eta = 0 \quad \frac{d^2 f}{d\eta^2} = 0.3321 \quad (\text{from Table 9.1})$$

$$\tau_w = 0.3321 \cdot U \cdot \sqrt{\frac{\rho \cdot U \cdot \mu}{x}}$$

$$\tau_w = 0.3321 \cdot \rho \cdot U^2 \cdot \sqrt{\frac{\mu}{\rho \cdot U \cdot x}} = 0.3321 \cdot \frac{\rho \cdot U^2}{\sqrt{\text{Re}_x}}$$

The friction drag is

$$F_D = \int \tau_w dA = \int_0^L \tau_w \cdot b \, dx$$

where b is the plate width

$$F_D = \int_0^L 0.3321 \cdot \frac{\rho \cdot U^2}{\sqrt{\text{Re}_x}} \cdot b \, dx = 0.3321 \cdot \rho \cdot U^2 \cdot \sqrt{\frac{\nu}{U}} \cdot \int_0^L \frac{1}{x^{\frac{1}{2}}} \, dx$$

$$F_D = 0.3321 \cdot \rho \cdot U^2 \cdot \sqrt{\frac{\nu}{U}} \cdot b \cdot 2 \cdot L^{\frac{1}{2}}$$

$$F_D = \rho \cdot U^2 \cdot b \cdot L \cdot \frac{0.6642}{\sqrt{\text{Re}_L}}$$

For the momentum integral

$$\frac{\tau_w}{\rho \cdot U^2} = \frac{d\theta}{dx} \quad \text{or}$$

$$d\theta = \frac{\tau_w}{\rho \cdot U^2} \cdot dx$$

$$\theta_L = \frac{1}{\rho \cdot U^2} \cdot \int_0^L \tau_w \, dx = \frac{1}{\rho \cdot U^2} \cdot \frac{F_D}{b} = \frac{0.6642 \cdot L}{\sqrt{\text{Re}_L}}$$

We have

$$L = 1 \cdot \text{m} \quad \text{Re}_L = \frac{U \cdot L}{\nu}$$

$$\text{Re}_L = 3.33 \times 10^5$$

$$\theta_L = \frac{0.6642 \cdot L}{\sqrt{\text{Re}_L}}$$

$$\theta_L = 0.115 \cdot \text{cm}$$

## Problem 9.36

[Difficulty: 2]

**\*9.36** Consider flow of air over a flat plate. On one graph, plot the laminar boundary-layer thickness as a function of distance along the plate (up to transition) for freestream speeds  $U = 1$  m/s, 2 m/s, 3 m/s, 4 m/s, 5 m/s, and 10 m/s.

**Given:** Data on flow over flat plate

**Find:** Plot of laminar thickness at various speeds

**Solution:**

Given or available data:  $\nu = 1.5 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$  (from Table A.10 at 20°C)

**Governing Equations:**  $\frac{\delta}{x} = \frac{5.48}{\sqrt{\text{Re}_x}}$  (9.21) and  $\text{Re}_x = \frac{U \cdot x}{\nu}$  so  $\delta = 5.48 \cdot \sqrt{\frac{\nu \cdot x}{U}}$

The critical Reynolds number is  $\text{Re}_{\text{crit}} = 500000$


Hence, for velocity  $U$  the critical length  $x_{\text{crit}}$  is  $x_{\text{crit}} = 500000 \cdot \frac{\nu}{U}$

The calculations and plot were generated in Excel and are shown below:

$U$ (m/s)	1	2	3	4	5	10
$x_{\text{crit}}$ (m)	7.5	3.8	2.5	1.9	1.5	0.75

$x$ (m)	$\delta$ (mm)					
0.000	0.00	0.00	0.00	0.00	0.00	0.00
0.025	3.36	2.37	1.94	1.68	1.50	1.06
0.050	4.75	3.36	2.74	2.37	2.12	1.50
0.075	5.81	4.11	3.36	2.91	2.60	1.84
0.100	6.71	4.75	3.87	3.36	3.00	
0.2	9.49	6.71	5.48	4.75	4.24	
0.5	15.01	10.61	8.66	7.50	6.71	
1.5	25.99	18.38	15.01	13.00	11.62	
1.9	29.26	20.69	16.89	14.63		
2.5	33.56	23.73	19.37			
3.8	41.37	29.26				
5.0	47.46					
6.0	51.99					
7.5	58.12					

### Laminar Boundary Layer Profiles



## Problem 9.37

[Difficulty: 5]

**\*9.37** The Blasius exact solution involves solving a nonlinear equation, Eq. 9.11, with initial and boundary conditions given by Eq. 9.12. Set up an *Excel* workbook to obtain a numerical solution of this system. The workbook should consist of columns for  $\eta$ ,  $f$ ,  $f'$ , and  $f''$ . The rows should consist of values of these, with a suitable step size for  $\eta$  (e.g., for 1000 rows the step size for  $\eta$  would be 0.01 to generate data through  $\eta = 10$ , to go a little beyond the data in Table 9.1). The values of  $f$  and  $f'$  for the first row are zero (from the initial conditions, Eq. 9.12); a guess value is needed for  $f''$  (try 0.5). Subsequent row values for  $f$ ,  $f'$ , and  $f''$  can be obtained from previous row values using the Euler method of Section 5.5 for approximating first derivatives (and Eq. 9.11). Finally, a solution can be found by using *Excel's Goal Seek* or *Solver* functions to vary the initial value of  $f''$  until  $f' = 1$  for large  $\eta$  (e.g.,  $\eta = 10$ , boundary condition of Eq. 9.12). Plot the results. Note: Because the Euler method is relatively crude, the results will agree with Blasius' only to within about 1%.

**Given:** Blasius nonlinear equation

**Find:** Blasius solution using Excel

**Solution:**

The equation to be solved is

$$2 \frac{d^3 f}{d\eta^3} + f \frac{d^2 f}{d\eta^2} = 0 \quad (9.11)$$

The boundary conditions are

$$f = 0 \quad \text{and} \quad \frac{df}{d\eta} = 0 \quad \text{at} \quad \eta = 0$$

$$f' = \frac{df}{d\eta} = 1 \quad \text{at} \quad \eta \rightarrow \infty \quad (9.12)$$

Recall that these somewhat abstract variables are related to physically meaningful variables:

$$\frac{u}{U} = f'$$

and

$$\eta = y \sqrt{\frac{U}{\nu x}} \propto \frac{y}{\delta}$$

Using Euler's numerical method

$$f_{n+1} \approx f_n + \Delta\eta f'_n \quad (1)$$

$$f'_{n+1} \approx f'_n + \Delta\eta f''_n \quad (2)$$

$$f''_{n+1} \approx f''_n + \Delta\eta f'''_n$$

In these equations, the subscripts refer to the  $n^{\text{th}}$  discrete value of the variables, and  $\Delta\eta = 10/N$  is the step size for  $\eta$  ( $N$  is the total number of steps).

But from Eq. 9.11

$$f''' = -\frac{1}{2} f f''$$

so the last of the three equations is

$$f''_{n+1} \approx f''_n + \Delta\eta \left( -\frac{1}{2} f_n f''_n \right) \quad (3)$$

Equations 1 through 3 form a complete set for computing  $f, f', f''$ . All we need is the starting condition for each. From Eqs. 9.12

$$f_0 = 0 \quad \text{and} \quad f'_0 = 0$$

We do NOT have a starting condition for  $f''$ ! Instead we must choose (using *Solver*)  $f''_0$  so that the last condition of Eqs. 9.12 is met:


$$f'_N = 1$$

Computations (only the first few lines of 1000 are shown):

$$\Delta\eta = \quad 0.01$$

Make a guess for the first  $f''$ ; use Solver to vary it until  $f'_N = 1$

Count	$\eta$	$f$	$f'$	$f''$
0	0.00	0.0000	0.0000	0.3303
1	0.01	0.0000	0.0033	0.3303
2	0.02	0.0000	0.0066	0.3303
3	0.03	0.0001	0.0099	0.3303
4	0.04	0.0002	0.0132	0.3303
5	0.05	0.0003	0.0165	0.3303



## Problem 9.38

[Difficulty: 2]

**\*9.38** A thin flat plate,  $L = 9$  in. long and  $b = 3$  ft wide, is installed in a water tunnel as a splitter. The freestream speed is  $U = 5$  ft/s, and the velocity profile in the boundary layer is approximated as parabolic. Plot  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$  for the plate.

**Given:** Parabolic solution for laminar boundary layer

**Find:** Plot of  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$

**Solution:**

Given or available data:  $\nu = 1.08 \times 10^{-5} \frac{\text{ft}^2}{\text{s}}$  (From Table A.8 at 68°F)  $L = 9$  in  $U = 5 \frac{\text{ft}}{\text{s}}$


**Basic equations:**

$$\frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2 \quad \frac{\delta}{x} = \frac{5.48}{\sqrt{Re_x}} \quad c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.730}{\sqrt{Re_x}}$$

Hence: 
$$\delta^* = \int_0^\delta \left(1 - \frac{u}{U}\right) dy = \delta \int_0^1 \left(1 - \frac{u}{U}\right) d\left(\frac{y}{\delta}\right) = \delta \int_0^1 (1 - 2 + \eta^2) d\eta = \delta \left[ \eta - \eta^2 + \frac{1}{3} \eta^3 \right]_0^1 = \frac{\delta}{3}$$

The computed results are from Excel, shown below:

$x$ (in)	$Re_x$	$\delta$ (in)	$\delta^*$ (in)	$\tau_w$ (psi)
0.00	0.00.E+00	0.000	0.000	
0.45	1.74.E+04	0.019	0.006	0.1344
0.90	3.47.E+04	0.026	0.009	0.0950
1.35	5.21.E+04	0.032	0.011	0.0776
1.80	6.94.E+04	0.037	0.012	0.0672
2.25	8.68.E+04	0.042	0.014	0.0601
2.70	1.04.E+05	0.046	0.015	0.0548
3.15	1.22.E+05	0.050	0.017	0.0508
3.60	1.39.E+05	0.053	0.018	0.0475
4.05	1.56.E+05	0.056	0.019	0.0448
4.50	1.74.E+05	0.059	0.020	0.0425
4.95	1.91.E+05	0.062	0.021	0.0405
5.40	2.08.E+05	0.065	0.022	0.0388
5.85	2.26.E+05	0.067	0.022	0.0373
6.30	2.43.E+05	0.070	0.023	0.0359
6.75	2.60.E+05	0.072	0.024	0.0347
7.20	2.78.E+05	0.075	0.025	0.0336
7.65	2.95.E+05	0.077	0.026	0.0326
8.10	3.13.E+05	0.079	0.026	0.0317
8.55	3.30.E+05	0.082	0.027	0.0308
9.00	3.47.E+05	0.084	<b>0.028</b>	<b>0.0300</b>



## Problem 9.39

[Difficulty: 2]

**9.39** Consider flow over the splitter plate of Problem 9.38. Show algebraically that the total drag force on one side of the splitter plate may be written  $F_D = \rho U^2 \theta_L b$ . Evaluate  $\theta_L b$  and the total drag for the given conditions.

**Given:** Parabolic solution for laminar boundary layer

**Find:** Derivation of  $F_D$ ; Evaluate  $F_D$  and  $\theta_L$

**Solution:**

**Basic equations:**

$$\frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2 \quad \frac{\delta}{x} = \frac{5.48}{\sqrt{\text{Re}_x}} \quad \frac{\tau_w}{\rho} = \frac{d}{dx} (U^2 \theta) + \delta^* U \frac{dU}{dx}$$

$$L = 9\text{-in} \quad b = 3\text{-ft} \quad U = 5 \cdot \frac{\text{ft}}{\text{s}} \quad \rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$$

**Assumptions:**

- 1) Flat plate so  $\frac{\partial}{\partial x} p = 0$ , and  $U = \text{const}$
- 2)  $\delta$  is a function of  $x$  only
- 3) Incompressible
- 4) Steady flow

The momentum integral equation then simplifies to  $\frac{\tau_w}{\rho} = \frac{d}{dx} (U^2 \cdot \theta)$  where  $\theta = \int_0^{\delta} \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) dy$

For  $U = \text{const}$   $\tau_w = \rho \cdot U^2 \cdot \frac{d\theta}{dx}$

The drag force is then  $F_D = \int \tau_w dA = \int_0^L \tau_w \cdot b dx = \int_0^L \rho \cdot U^2 \cdot \frac{d\theta}{dx} \cdot b dx = \rho \cdot U^2 \cdot b \cdot \int_0^{\theta_L} 1 d\theta \quad F_D = \rho \cdot U^2 \cdot b \cdot \theta_L$

For the given profile  $\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta = \int_0^1 (2 \cdot \eta - \eta^2) \cdot (1 - 2 \cdot \eta + \eta^2) d\eta = \int_0^1 (2 \cdot \eta - 5 \cdot \eta^2 + 4 \cdot \eta^3 - \eta^4) d\eta = \frac{2}{15}$

$$\theta = \frac{2}{15} \cdot \delta$$

From Table A.7 at 68°F  $\nu = 1.08 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}} \quad \text{Re}_L = \frac{U \cdot L}{\nu} \quad \text{Re}_L = 3.47 \times 10^5$

$$\delta_L = L \cdot \frac{5.48}{\sqrt{\text{Re}_L}} \quad \delta_L = 0.0837 \cdot \text{in}$$

$$\theta_L = \frac{2}{15} \cdot \delta_L \quad \theta_L = 0.01116 \cdot \text{in}$$

$$F_D = \rho \cdot U^2 \cdot b \cdot \theta_L \quad F_D = 0.1353 \cdot \text{lb}_f$$

## Problem 9.40

[Difficulty: 3]

**9.40** A thin flat plate is installed in a water tunnel as a splitter. The plate is 0.3 m long and 1 m wide. The freestream speed is 1.6 m/s. Laminar boundary layers form on both sides of the plate. The boundary-layer velocity profile is approximated as parabolic. Determine the total viscous drag force on the plate assuming that pressure drag is negligible.

**Given:** Thin flat plate installed in a water tunnel. Laminar BL's with parabolic profiles form on both sides of the plate.


$$L = 0.3 \cdot \text{m} \quad b = 1 \cdot \text{m} \quad U = 1.6 \cdot \frac{\text{m}}{\text{s}} \quad \nu = 1 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}} \quad \frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$$

**Find:** Total viscous drag force acting on the plate.

**Solution:** We will determine the drag force from the shear stress at the wall

First we will check the Reynolds number of the flow:  $Re_L = \frac{U \cdot L}{\nu} = 4.8 \times 10^5$

Therefore the flow is laminar throughout.



The viscous drag for the two sides of the plate is:  $F_D = 2 \cdot \int_0^L \tau_w \cdot b \, dx$  The wall shear stress  $\tau_w$  is:

$$\tau_w = \mu \cdot \left(\frac{\partial u}{\partial y}\right) \text{ at } y = 0, \text{ which for the parabolic profile yields: } \tau_w = \mu \cdot U \cdot \left(\frac{2}{\delta} - \frac{2 \times 0}{\delta^2}\right) = \frac{2 \cdot \mu \cdot U}{\delta} \quad \text{The BL thickness } \delta \text{ is:}$$

$$\delta = 5.48 \cdot \sqrt{\frac{\nu}{U}} \cdot x^{\frac{1}{2}} \quad \text{Therefore: } F_D = 2 \cdot b \cdot \int_0^L \frac{2 \cdot \mu \cdot U}{5.48 \cdot \sqrt{\frac{\nu}{U}} \cdot x^{\frac{1}{2}}} \, dx = \frac{4}{5.48} \cdot b \cdot \mu \cdot U \cdot \sqrt{\frac{U}{\nu}} \cdot \int_0^L x^{-\frac{1}{2}} \, dx$$

$$\text{Evaluating this integral: } F_D = \frac{8 \cdot b \cdot \mu \cdot U}{5.48} \cdot \sqrt{\frac{U \cdot L}{\nu}} \quad F_D = 1.617 \text{ N}$$

## Problem 9.41

[Difficulty: 2]

**9.41** In Problems 9.18 and 9.19 the drag on the upper surface of a flat plate, with flow (fluid density  $\rho = 1.5 \text{ slug/ft}^3$ ) at freestream speed  $U = 10 \text{ ft/s}$ , was determined from momentum flux calculations. The drag was determined for the plate with its long edge (10 ft) and its short edge (3 ft) parallel to the flow. If the fluid viscosity  $\mu = 4 \times 10^{-4} \text{ lbf}\cdot\text{s/ft}^2$ , compute the drag using boundary-layer calculations.

**Given:** Data on fluid and plate geometry

**Find:** Drag at both orientations using boundary layer equation

**Solution:**

The given data is  $\rho = 1.5 \cdot \frac{\text{slug}}{\text{ft}^3}$        $\mu = 0.0004 \cdot \frac{\text{lbf}\cdot\text{s}}{\text{ft}^2}$        $U = 10 \cdot \frac{\text{ft}}{\text{s}}$        $L = 10\text{-ft}$        $b = 3\text{-ft}$

First determine the nature of the boundary layer       $Re_L = \frac{\rho \cdot U \cdot L}{\mu}$        $Re_L = 3.75 \times 10^5$

The maximum Reynolds number is less than the critical value of  $5 \times 10^5$

Hence:

Governing equations:       $c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2}$       (9.22)       $c_f = \frac{0.730}{\sqrt{Re_x}}$       (9.23)

The drag (one side) is       $F_D = \int_0^L \tau_w \cdot b \, dx$

Using Eqs. 9.22 and 9.23       $F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot b \cdot \int_0^L \frac{0.73}{\sqrt{\frac{\rho \cdot U \cdot x}{\mu}}} \, dx$

$$F_D = 0.73 \cdot b \cdot \sqrt{\mu \cdot L \cdot \rho \cdot U^3} \qquad F_D = 5.36 \cdot \text{lbf} \quad (\text{Compare to } 6.25 \text{ lbf for Problem 9.18})$$


Repeating for       $L = 3\text{-ft}$        $b = 10\text{-ft}$

$$F_D = 0.73 \cdot b \cdot \sqrt{\mu \cdot L \cdot \rho \cdot U^3} \qquad F_D = 9.79 \cdot \text{lbf} \quad (\text{Compare to } 12.5 \text{ lbf for Problem 9.19})$$

## Problem 9.42

[Difficulty: 3]

**9.42** Assume laminar boundary-layer flow to estimate the drag on the plate shown when it is placed parallel to a 15 ft/s air flow. The air is 70°F and 1 atm.



**Given:** Triangular plate

**Find:** Drag

**Solution:**

**Basic equations:**

$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2}$$

$$c_f = \frac{0.730}{\sqrt{Re_x}}$$

$$L = 2 \cdot \text{ft} \cdot \frac{\sqrt{3}}{2}$$

$$L = 1.732 \cdot \text{ft}$$

$$W = 2 \cdot \text{ft}$$

$$U = 15 \cdot \frac{\text{ft}}{\text{s}}$$

**Assumptions:**

- (1) Parabolic boundary layer profile
- (2) Boundary layer thickness is based on distance from leading edge (the "point" of the triangle).

From Table A.9 at 70°F  $\nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$   $\rho = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3}$

First determine the nature of the boundary layer  $Re_L = \frac{U \cdot L}{\nu}$   $Re_L = 2 \times 10^5$  so definitely laminar

The drag (one side) is  $F_D = \int \tau_w dA$   $F_D = \int_0^L \tau_w \cdot w(x) dx$   $w(x) = W \cdot \frac{x}{L}$

We also have  $\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.730}{\sqrt{Re_x}}$

Hence  $F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{W}{L} \cdot \int_0^L \frac{0.730 \cdot x}{\sqrt{\frac{U \cdot x}{\nu}}} dx = \frac{0.730}{2} \cdot \rho \cdot U^2 \cdot \frac{W}{L} \cdot \sqrt{\nu} \cdot \int_0^L \frac{1}{x^{\frac{1}{2}}} dx$

The integral is  $\int_0^L \frac{1}{x^{\frac{1}{2}}} dx = \frac{2}{3} \cdot L^{\frac{3}{2}}$  so  $F_D = 0.243 \cdot \rho \cdot W \cdot \sqrt{\nu \cdot L} \cdot U^3$   $F_D = 1.11 \times 10^{-3} \cdot \text{lbf}$


Note: For two-sided solution

$$2 \cdot F_D = 2.21 \times 10^{-3} \cdot \text{lbf}$$

## Problem 9.43

[Difficulty: 3]

**9.43** Assume laminar boundary-layer flow to estimate the drag on the plate shown when it is placed parallel to a 15 ft/s air flow, except that the base rather than the tip faces the flow. Would you expect this to be larger than, the same as, or lower than the drag for Problem 9.42?



**Given:** Triangular plate

**Find:** Drag

**Solution:**

Basic equations:

$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \qquad c_f = \frac{0.730}{\sqrt{\text{Re}_x}}$$

$$L = 2 \cdot \text{ft} \cdot \frac{\sqrt{3}}{2} \qquad L = 1.732 \cdot \text{ft} \qquad W = 2 \cdot \text{ft} \qquad U = 15 \cdot \frac{\text{ft}}{\text{s}}$$

From Table A.9 at 70°F

$$\nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \qquad \rho = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3}$$

First determine the nature of the boundary layer

$$\text{Re}_L = \frac{U \cdot L}{\nu} \qquad \text{Re}_L = 2 \times 10^5 \qquad \text{so definitely laminar}$$

The drag (one side) is

$$F_D = \int \tau_w dA \qquad F_D = \int_0^L \tau_w \cdot w(x) dx \qquad w(x) = W \cdot \left(1 - \frac{x}{L}\right)$$

We also have

$$\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.730}{\sqrt{\text{Re}_x}}$$

Hence

$$F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot W \cdot \int_0^L \frac{0.730 \cdot \left(1 - \frac{x}{L}\right)}{\sqrt{\frac{U \cdot x}{\nu}}} dx = \frac{0.730}{2} \cdot \rho \cdot U^{\frac{3}{2}} \cdot W \cdot \sqrt{\nu} \cdot \int_0^L \left( \frac{-\frac{1}{2}}{x} - \frac{\frac{1}{2}}{L} \right) dx$$

The integral is

$$\int_0^L \left( \frac{-\frac{1}{2}}{x} - \frac{\frac{1}{2}}{L} \right) dx = 2 \cdot L^{\frac{1}{2}} - \frac{2}{3} \cdot \frac{L^{\frac{3}{2}}}{L} = \frac{4}{3} \cdot \sqrt{L}$$

$$F_D = 0.487 \cdot \rho \cdot W \cdot \sqrt{\nu \cdot L} \cdot U^3 \qquad F_D = 2.22 \times 10^{-3} \cdot \text{lbf}$$

Note: For two-sided solution


$$2 \cdot F_D = 4.43 \times 10^{-3} \cdot \text{lbf}$$

The drag is much higher (twice as much) compared to Problem 9.42. This is because  $\tau_w$  is largest near the leading edge and falls off rapidly; in this problem the widest area is also at the front

## Problem 9.44

[Difficulty: 3]

**9.44** Assume laminar boundary-layer flow to estimate the drag on the plate shown when it is placed parallel to a 15 ft/s air flow. The air is at 70°F and 1 atm. (Note that the shape is given by  $x = y^2$ , where  $x$  and  $y$  are in feet.)



**Given:** Parabolic plate

**Find:** Drag

**Solution:**

Basic equations:

$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \qquad c_f = \frac{0.730}{\sqrt{\text{Re}_x}}$$

$$W = 1 \cdot \text{ft} \qquad L = \frac{\left(\frac{W}{2}\right)^2}{1 \cdot \text{ft}} \qquad L = 0.25 \cdot \text{ft} \qquad U = 15 \cdot \frac{\text{ft}}{\text{s}}$$

Note: "y" is the equation of the upper and lower surfaces, so  $y = W/2$  at  $x = L$

From Table A.9 at 70°F  $\nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$   $\rho = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3}$

First determine the nature of the boundary layer  $\text{Re}_L = \frac{U \cdot L}{\nu} \qquad \text{Re}_L = 2.3 \times 10^4$  so just laminar

The drag (one side) is  $F_D = \int \tau_w dA$   $F_D = \int_0^L \tau_w \cdot w(x) dx$   $w(x) = W \cdot \sqrt{\frac{x}{L}}$

We also have  $\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.730}{\sqrt{\text{Re}_x}}$

Hence 
$$F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot W \cdot \int_0^L \frac{0.730 \cdot \sqrt{\frac{x}{L}}}{\sqrt{\frac{U \cdot x}{\nu}}} dx = \frac{0.730}{2} \cdot \rho \cdot U^{\frac{3}{2}} \cdot W \cdot \sqrt{\frac{\nu}{L}} \cdot \int_0^L 1 dx$$

$$F_D = 0.365 \cdot \rho \cdot W \cdot \sqrt{\nu \cdot L} \cdot U^{\frac{3}{2}} \qquad F_D = 3.15 \times 10^{-4} \cdot \text{lbf}$$


Note: For two-sided solution

$$2 \cdot F_D = 6.31 \times 10^{-4} \cdot \text{lbf}$$

## Problem 9.45

[Difficulty: 4]

**9.45** Assume laminar boundary-layer flow to estimate the drag on the plate shown when it is placed parallel to a 15 ft/s flow, except that the base rather than the tip faces the flow. Would you expect this to be large than, the same as, or lower than the drag for Problem 9.44?



Note: Plate is now reversed!

**Given:** Parabolic plate

**Find:** Drag

**Solution:**

**Basic equations:**

$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \qquad c_f = \frac{0.730}{\sqrt{\text{Re}_x}}$$

$$W = 1 \cdot \text{ft} \qquad L = \frac{\left(\frac{W}{2}\right)^2}{1 \cdot \text{ft}} \qquad L = 0.25 \cdot \text{ft} \qquad U = 15 \cdot \frac{\text{ft}}{\text{s}}$$

Note: "y" is the equation of the upper and lower surfaces, so  $y = W/2$  at  $x = 0$

From Table A.10 at 70°F  $\nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$   $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$

First determine the nature of the boundary layer  $\text{Re}_L = \frac{U \cdot L}{\nu} \quad \text{Re}_L = 2.3 \times 10^4$  so just laminar

The drag (one side) is  $F_D = \int \tau_w dA$   $F_D = \int_0^L \tau_w \cdot w(x) dx$   $w(x) = W \cdot \sqrt{1 - \frac{x}{L}}$

We also have  $\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.730}{\sqrt{\text{Re}_x}}$

Hence  $F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot W \cdot \int_0^L \frac{0.730 \cdot \sqrt{1 - \frac{x}{L}}}{\sqrt{\frac{U \cdot x}{\nu}}} dx = \frac{0.730}{2} \cdot \rho \cdot U^2 \cdot W \cdot \sqrt{\nu} \cdot \int_0^L \sqrt{\frac{1}{x} - \frac{1}{L}} dx$

The tricky integral is (this might be easier to do numerically!)  $\int \sqrt{\frac{1}{x} - \frac{1}{L}} dx = \sqrt{x - \frac{x^2}{L}} - \frac{i}{2} \cdot \sqrt{L} \cdot \ln\left(\frac{\sqrt{-L-x} - \sqrt{x}}{\sqrt{-L-x} + \sqrt{x}}\right)$  so  $\int_0^L \sqrt{\frac{1}{x} - \frac{1}{L}} dx = 0.434 \cdot \sqrt{m}$

$$F_D = \frac{0.730}{2} \cdot \rho \cdot U^2 \cdot W \cdot \sqrt{\nu} \cdot \int_0^L \sqrt{\frac{1}{x} - \frac{1}{L}} dx \qquad F_D = 4.98 \times 10^{-4} \cdot \text{lbf}$$

Note: For two-sided solution


$$2 \cdot F_D = 9.95 \times 10^{-4} \cdot \text{lbf}$$

The drag is much higher compared to Problem 9.44. This is because  $\tau_w$  is largest near the leading edge and falls off rapidly; in this problem the widest area is also at the front

## Problem 9.46

[Difficulty: 3]

**9.46** Assume laminar boundary-layer flow to estimate the drag on four square plates (each 3 in. × 3 in.) placed parallel to a 3 ft/s water flow, for the two configurations shown. Before calculating, which configuration do you expect to experience the lower drag? Assume that the plates attached with string are far enough apart for wake effects to be negligible and that the water is at 70°F.



**Given:** Pattern of flat plates

**Find:** Drag on separate and composite plates

**Solution:**

**Basic equations:**

$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \qquad c_f = \frac{0.730}{\sqrt{\text{Re}_x}}$$

**Assumption:** Parabolic boundary layer profile

For separate plates  $L = 3 \cdot \text{in}$   $W = 3 \cdot \text{in}$   $U = 3 \cdot \frac{\text{ft}}{\text{s}}$  From Table A.7 at 70°F  $\nu = 1.06 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$   $\rho = 1.93 \cdot \frac{\text{slug}}{\text{ft}^3}$

First determine the nature of the boundary layer  $\text{Re}_L = \frac{U \cdot L}{\nu}$   $\text{Re}_L = 7.08 \times 10^4$  so definitely laminar

The drag (one side) is  $F_D = \int \tau_w dA$   $F_D = \int_0^L \tau_w \cdot W dx$

We also have  $\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.730}{\sqrt{\text{Re}_x}}$

Hence  $F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot W \cdot \int_0^L \frac{0.730}{\sqrt{\frac{U \cdot x}{\nu}}} dx = \frac{0.730}{2} \cdot \rho \cdot U^2 \cdot W \cdot \sqrt{\nu} \cdot \int_0^L x^{-\frac{1}{2}} dx$

The integral is  $\int_0^L x^{-\frac{1}{2}} dx = 2 \cdot L^{\frac{1}{2}}$  so  $F_D = 0.730 \cdot \rho \cdot W \cdot \sqrt{\nu \cdot L} \cdot U^3$   $F_D = 0.0030 \cdot \text{lbf}$

This is the drag on one plate. The total drag is then  $F_{\text{Total}} = 4 \cdot F_D$   $F_{\text{Total}} = 0.0119 \cdot \text{lbf}$

For both sides:  $2 \cdot F_{\text{Total}} = 0.0238 \cdot \text{lbf}$

For the composite plate  $L = 4 \times 3 \cdot \text{in}$   $L = 1.00 \cdot \text{ft}$   $\text{Re}_L = \frac{U \cdot L}{\nu} = 2.83 \times 10^5$  so still laminar

$F_{\text{Composite}} = 0.730 \cdot \rho \cdot W \cdot \sqrt{\nu \cdot L} \cdot U^3$   $F_{\text{Composite}} = 0.0060 \cdot \text{lbf}$

For both sides:  $2 \cdot F_{\text{Composite}} = 0.0119 \cdot \text{lbf}$

The drag is much lower on the composite compared to the separate plates. This is because  $\tau_w$  is largest near the leading edges and falls off rapidly; in this problem the separate plates experience leading edges four times!

## Problem 9.47

[Difficulty: 3]

**9.47** The velocity profile in a laminar boundary-layer flow at zero pressure gradient is approximated by the linear expression given in Problem 9.10. Use the momentum integral equation with this profile to obtain expressions for  $\delta/x$  and  $C_f$ .

**Given:** Laminar boundary layer flow with linear velocity profile:  $\frac{u}{U} = \frac{y}{\delta} = \eta$

**Find:** Expressions for  $\delta/x$  and  $C_f$  using the momentum integral equation

**Solution:** We will apply the momentum integral equation

**Governing Equations:**  $\frac{\tau_w}{\rho} = \frac{d}{dx}(U^2 \cdot \theta) + \delta_{disp} \cdot U \cdot \left(\frac{d}{dx}U\right)$  (Momentum integral equation)

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \quad \text{(Skin friction coefficient)}$$

**Assumptions:** (1) Zero pressure gradient, so  $U$  is constant and  $dp/dx = 0$   
 (2)  $\delta$  is a function of  $x$  only, and  $\delta = 0$  at  $x = 0$   
 (3) Incompressible flow

Applying the assumptions to the momentum integral equation yields:  $\tau_w = \rho \cdot U^2 \cdot \left(\frac{d}{dx}\theta\right) = \rho \cdot U^2 \cdot \left[\frac{d}{dx}\left[\delta \cdot \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta\right]\right]$

Substituting for the velocity profile:  $\tau_w = \rho \cdot U^2 \cdot \left[\frac{d}{dx}\left[\delta \cdot \int_0^1 (\eta - \eta^2) d\eta\right]\right] = \rho \cdot U^2 \cdot \frac{1}{6} \cdot \left(\frac{d}{dx}\delta\right)$

Now the wall shear stress is also:  $\tau_w = \mu \cdot \left(\frac{\partial}{\partial y}u\right)$  at  $y = 0$  Substituting the velocity profile:  $\tau_w = \frac{\mu \cdot U}{\delta}$

Setting both expressions for the wall shear stress equal:  $\rho \cdot U^2 \cdot \frac{1}{6} \cdot \left(\frac{d}{dx}\delta\right) = \frac{\mu \cdot U}{\delta}$  Separating variables:  $\delta \cdot d\delta = \frac{6 \cdot \mu}{\rho \cdot U} \cdot dx$

Integrating this expression:  $\frac{\delta^2}{2} = \frac{6 \cdot \mu}{\rho \cdot U} \cdot x + C$  However, we know that  $C = 0$  since  $\delta = 0$  when  $x = 0$ . Therefore:  $\frac{\delta^2}{2} = \frac{6 \cdot \mu}{\rho \cdot U} \cdot x$

Solving for the boundary layer thickness:  $\delta = \sqrt{\frac{12 \cdot \mu}{\rho \cdot U} \cdot x}$  or  $\frac{\delta}{x} = \sqrt{\frac{12 \cdot \mu}{\rho \cdot U \cdot x}}$   $\frac{\delta}{x} = \frac{3.46}{\sqrt{Re_x}}$

From the definition for skin friction coefficient:  $C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{\mu \cdot U}{\delta} \cdot \frac{2}{\rho \cdot U^2} = \frac{2 \cdot \mu}{\rho \cdot U \cdot \delta} = 2 \cdot \frac{\mu}{\rho \cdot U \cdot x} \cdot \frac{x}{\delta} = \frac{2}{Re_x} \cdot \frac{\sqrt{Re_x}}{3.46}$

Upon simplification:  $C_f = \frac{0.577}{\sqrt{Re_x}}$

## Problem 9.48

[Difficulty: 2]

**9.48** A horizontal surface, with length  $L = 1.8$  m and width  $b = 0.9$  m, is immersed in a stream of standard air flowing at  $U = 3.2$  m/s. Assume a laminar boundary layer forms and approximate the velocity profile as sinusoidal. Plot  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$  for the plate.


**Given:** Horizontal surface immersed in a stream of standard air. Laminar BL with sinusoidal profile forms.

$$L = 1.8 \cdot \text{m} \quad b = 0.9 \cdot \text{m} \quad U = 3.2 \cdot \frac{\text{m}}{\text{s}} \quad \nu = 1.46 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad \frac{u}{U} = \sin\left(\frac{\pi \cdot y}{2 \cdot \delta}\right)$$

**Find:** Plot  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$  for the plate

**Solution:** We will determine the drag force from the shear stress at the wall

**Governing Equations:**  $\tau_w = \rho \cdot U^2 \cdot \left(\frac{d}{dx} \theta\right) = \mu \cdot \left(\frac{\partial}{\partial y} u\right)$  at  $y = 0$  (Wall shear stress)



$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\eta \quad (\text{Displacement thickness})$$

$$\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta \quad (\text{Momentum thickness})$$

For the sinusoidal velocity profile:  $\frac{\theta}{\delta} = \int_0^1 \sin\left(\frac{\pi}{2} \cdot \eta\right) \cdot \left(1 - \sin\left(\frac{\pi}{2} \cdot \eta\right)\right) d\eta = \int_0^1 \left[\sin\left(\frac{\pi}{2} \cdot \eta\right) - \left(\sin\left(\frac{\pi}{2} \cdot \eta\right)\right)^2\right] d\eta$

Evaluating this integral:  $\frac{\theta}{\delta} = \frac{4 - \pi}{2 \cdot \pi} = 0.1366$  Therefore it follows that  $\frac{d}{dx} \theta = \frac{d}{d\delta} \theta \cdot \left(\frac{\partial}{\partial x} \delta\right) = \frac{4 - \pi}{2 \cdot \pi} \cdot \left(\frac{\partial}{\partial x} \delta\right)$

To determine the wall shear stress:  $\tau_w = \mu \cdot U \cdot \cos\left(\frac{\pi}{2} \cdot \frac{0}{\delta}\right) \cdot \frac{\pi}{2 \cdot \delta} = \frac{\pi \cdot \mu \cdot U}{2 \cdot \delta} = \rho \cdot U^2 \cdot \frac{4 - \pi}{2 \cdot \pi} \cdot \left(\frac{\partial}{\partial x} \delta\right)$


Separating variables yields:  $\frac{\pi \cdot \mu \cdot U}{2 \cdot \rho \cdot U^2} \cdot \frac{2 \cdot \pi}{4 - \pi} \cdot dx = \delta \cdot d\delta$  or  $\delta \cdot d\delta = \frac{\pi^2}{4 - \pi} \cdot \frac{\mu}{\rho \cdot U} \cdot dx$  Integrating yields:  $\frac{\delta^2}{2} = \frac{\pi^2}{4 - \pi} \cdot \frac{\mu}{\rho \cdot U} \cdot x$

Solving this expression for  $\delta/x$ :  $\frac{\delta}{x} = \sqrt{\frac{\pi^2}{4 - \pi}} \cdot \sqrt{\frac{\mu}{\rho \cdot U \cdot x}}$   $\frac{\delta}{x} = \frac{4.80}{\sqrt{\text{Re}_x}}$

Also,  $\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left(1 - \sin\left(\frac{\pi}{2} \cdot \eta\right)\right) d\eta$  Evaluating this integral:  $\frac{\delta_{\text{disp}}}{\delta} = 1 - \frac{2}{\pi} = 0.363$   $\frac{\delta_{\text{disp}}}{\delta} = 0.363$

The Reynolds number is related to  $x$  through:  $\text{Re}_x = 2.19 \times 10^5 \cdot x$  where  $x$  is measured in meters.

Plots of  $\delta$ ,  $\delta_{\text{disp}}$  and  $\tau_w$  as functions of  $x$  are shown on the next page.



## Problem 9.49

[Difficulty: 3]

**9.49** Water at 10°C flows over a flat plate at a speed of 0.8 m/s. The plate is 0.35 m long and 1 m wide. The boundary layer on each surface of the plate is laminar. Assume that the velocity profile may be approximated as linear. Determine the drag force on the plate.

**Given:** Water flow over flat plate

**Find:** Drag on plate for linear boundary layer

**Solution:**

**Basic equations:**  $F_D = 2 \cdot \int \tau_w dA$        $\tau_w = \mu \cdot \frac{du}{dy}$       at  $y = 0$ , and also  $\tau_w = \rho \cdot U^2 \cdot \frac{d\delta}{dx} \cdot \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta$

$L = 0.35 \cdot \text{m}$        $W = 1 \cdot \text{m}$        $U = 0.8 \cdot \frac{\text{m}}{\text{s}}$

From Table A.8 at 10°C  $\nu = 1.30 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$        $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$

First determine the nature of the boundary layer  $Re_L = \frac{U \cdot L}{\nu}$        $Re_L = 2.15 \times 10^5$       so laminar

The velocity profile is  $u = U \cdot \frac{y}{\delta} = U \cdot \eta$

Hence  $\tau_w = \mu \cdot \frac{du}{dy} = \mu \cdot \frac{U}{\delta}$       (1)      but we need  $\delta(x)$

We also have  $\tau_w = \rho \cdot U^2 \cdot \frac{d\delta}{dx} \cdot \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta = \rho \cdot U^2 \cdot \frac{d\delta}{dx} \cdot \int_0^1 \eta \cdot (1 - \eta) d\eta$

The integral is  $\int_0^1 (\eta - \eta^2) dx = \frac{1}{6}$       so  $\tau_w = \rho \cdot U^2 \cdot \frac{d\delta}{dx} = \frac{1}{6} \cdot \rho \cdot U^2 \cdot \frac{d\delta}{dx}$       (2)

Comparing Eqs 1 and 2  $\tau_w = \mu \cdot \frac{U}{\delta} = \frac{1}{6} \cdot \rho \cdot U^2 \cdot \frac{d\delta}{dx}$

Separating variables  $\delta \cdot d\delta = \frac{6 \cdot \mu}{\rho \cdot U} \cdot dx$       or  $\frac{\delta^2}{2} = \frac{6 \cdot \mu}{\rho \cdot U} \cdot x + c$       but  $\delta(0) = 0$  so  $c = 0$

Hence  $\delta = \sqrt{\frac{12 \cdot \mu}{\rho \cdot U} \cdot x}$       or  $\frac{\delta}{x} = \sqrt{\frac{12}{Re_x}} = \frac{3.46}{Re_x}$

Then  $F_D = 2 \cdot \int \tau_w dA = 2 \cdot W \cdot \int_0^L \mu \cdot \frac{U}{\delta} dx = 2 \cdot W \cdot \int_0^L \mu \cdot U \cdot \sqrt{\frac{\rho \cdot U}{12 \cdot \mu}} \cdot x^{-\frac{1}{2}} dx = \frac{\mu \cdot W \cdot U}{\sqrt{3}} \cdot \sqrt{\frac{U}{\nu}} \cdot \int_0^L x^{-\frac{1}{2}} dx$

The integral is  $\int_0^L x^{-\frac{1}{2}} dx = 2 \cdot \sqrt{L}$       so  $F_D = \frac{2 \cdot \mu \cdot W \cdot U}{\sqrt{3}} \cdot \sqrt{\frac{U \cdot L}{\nu}}$

$F_D = \frac{2}{\sqrt{3}} \cdot \rho \cdot W \cdot \sqrt{\nu \cdot L} \cdot U^3$        $F_D = 0.557 \text{N}$

## Problem 9.50

[Difficulty: 2]

**9.50** A horizontal surface, with length  $L = 0.8$  m and width  $b = 1.9$  m, is immersed in a stream of standard air flowing at  $U = 5.3$  m/s. Assume a laminar boundary layer forms and approximate the velocity profile as linear. Plot  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$  for the plate.

**Given:** Horizontal surface immersed in a stream of standard air. Laminar BL with linear profile forms.

$$L = 0.8 \cdot \text{m} \quad b = 1.9 \cdot \text{m} \quad U = 5.3 \cdot \frac{\text{m}}{\text{s}} \quad \nu = 1.46 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad \frac{u}{U} = \frac{y}{\delta}$$

**Find:** Plot  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$  for the plate

**Solution:** We will determine the drag force from the shear stress at the wall

**Governing Equations:**  $\tau_w = \rho \cdot U^2 \cdot \left( \frac{d}{dx} \theta \right) = \mu \cdot \left( \frac{\partial}{\partial y} u \right)$  at  $y = 0$  (Wall shear stress)

$$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 \left( 1 - \frac{u}{U} \right) d\eta \quad \text{(Displacement thickness)}$$

$$\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \cdot \left( 1 - \frac{u}{U} \right) d\eta \quad \text{(Momentum thickness)}$$



For the linear velocity profile:  $\frac{\theta}{\delta} = \int_0^1 \eta \cdot (1 - \eta) d\eta = \int_0^1 (\eta - \eta^2) d\eta$  Evaluating this integral:  $\frac{\theta}{\delta} = \frac{1}{6} = 0.1667$


Therefore it follows that  $\frac{d}{dx} \theta = \frac{d}{d\delta} \theta \cdot \left( \frac{\partial}{\partial x} \delta \right) = \frac{1}{6} \cdot \left( \frac{\partial}{\partial x} \delta \right)$  To determine the wall shear stress:  $\tau_w = \frac{\mu \cdot U}{\delta} = \frac{\rho \cdot U^2}{6} \cdot \left( \frac{\partial}{\partial x} \delta \right)$

Separating variables yields:  $\frac{6 \cdot \mu}{\rho \cdot U} \cdot dx = \delta \cdot d\delta$  Integrating yields:  $\frac{\delta^2}{2} = \frac{6 \cdot \mu}{\rho \cdot U} \cdot x$  Solving this expression for  $\delta/x$ :  $\frac{\delta}{x} = \frac{3.46}{\sqrt{\text{Re}_x}}$

Also,  $\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 (1 - \eta) d\eta$  Evaluating this integral:  $\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{2}$   $\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{2}$

The Reynolds number is related to  $x$  through:  $\text{Re}_x = 3.63 \times 10^5 \cdot x$  where  $x$  is measured in meters.

Plots of  $\delta$ ,  $\delta_{\text{disp}}$  and  $\tau_w$  as functions of  $x$  are shown on the next page.



## Problem 9.51

[Difficulty: 2]

**9.51** For the flow conditions of Problem 9.50, develop an algebraic expression for the variation of wall shear stress with distance along the surface. Integrate to obtain an algebraic expression for the total skin-friction drag on the surface. Evaluate the drag for the given conditions.

**Given:** Horizontal surface immersed in a stream of standard air. Laminar BL with linear profile forms.

$$L = 0.8 \cdot \text{m} \quad b = 1.9 \cdot \text{m} \quad U = 5.3 \cdot \frac{\text{m}}{\text{s}} \quad \nu = 1.46 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad \frac{u}{U} = \frac{y}{\delta}$$

**Find:** Algebraic expressions for wall shear stress and drag; evaluate at given conditions

**Solution:** We will determine the drag force from the shear stress at the wall

**Governing Equations:**  $\tau_w = \rho \cdot U^2 \cdot \left( \frac{d}{dx} \theta \right) = \mu \cdot \left( \frac{\partial u}{\partial y} \right) \text{ at } y=0$  (Wall shear stress)



$$\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \cdot \left( 1 - \frac{u}{U} \right) d\eta \quad \text{(Momentum thickness)}$$

For the linear velocity profile:  $\frac{\theta}{\delta} = \int_0^1 \eta \cdot (1 - \eta) d\eta = \int_0^1 (\eta - \eta^2) d\eta$  Evaluating this integral:  $\frac{\theta}{\delta} = \frac{1}{6} = 0.1667$

Therefore it follows that  $\frac{d}{dx} \theta = \frac{d}{d\delta} \theta \cdot \left( \frac{\partial}{\partial x} \delta \right) = \frac{1}{6} \cdot \left( \frac{\partial}{\partial x} \delta \right)$  To determine the wall shear stress:  $\tau_w = \frac{\mu \cdot U}{\delta} = \frac{\rho \cdot U^2}{6} \cdot \left( \frac{\partial}{\partial x} \delta \right)$

Separating variables yields:  $\frac{6 \cdot \mu}{\rho \cdot U} \cdot dx = \delta \cdot d\delta$  Integrating yields:  $\frac{\delta^2}{2} = \frac{6 \cdot \mu}{\rho \cdot U} \cdot x$  Solving this expression for  $\delta/x$ :  $\frac{\delta}{x} = \sqrt{\frac{12}{\text{Re}_x}}$

Substituting this back into the expression for wall shear stress:  $\tau_w = \frac{\mu \cdot U}{\delta} = \frac{\mu \cdot U}{x \cdot \sqrt{\frac{12}{\text{Re}_x}}} = \frac{1}{\sqrt{12}} \cdot \frac{\mu \cdot U}{x} \cdot \sqrt{\text{Re}_x}$   $\tau_w = 0.289 \cdot \frac{\mu \cdot U}{x} \cdot \sqrt{\text{Re}_x}$

The drag force is given by:  $F_D = \int \tau_w dA = \int_0^L \tau_w \cdot b dx = \int_0^L \rho \cdot U^2 \cdot \frac{d\theta}{dx} \cdot b dx = b \cdot \int_0^{\theta_L} \rho \cdot U^2 d\theta$   $F_D = \rho \cdot U^2 \cdot b \cdot \theta_L$

For the given conditions:  $\text{Re}_L = \frac{U \cdot L}{\nu} = 2.90 \times 10^5$

$$\delta_L = L \cdot \sqrt{\frac{12}{\text{Re}_L}} = 5.14 \cdot \text{mm}$$

$$\theta_L = \frac{\delta_L}{6} = 0.857 \cdot \text{mm}$$


$$F_D = \rho \cdot U^2 \cdot b \cdot \theta_L = 0.0563 \text{ N}$$

$$F_D = 0.0563 \text{ N}$$

## Problem 9.52

[Difficulty: 3]

**9.52** Standard air flows from the atmosphere into the wide, flat channel shown. Laminar boundary layers form on the top and bottom walls of the channel (ignore boundary-layer effects on the side walls). Assume the boundary layers behave as on a flat plate, with linear velocity profiles. At any axial distance from the inlet, the static pressure is uniform across the channel. Assume uniform flow at section ①. Indicate where the Bernoulli equation can be applied in this flow field. Find the static pressure (gage) and the displacement thickness at section ②. Plot the stagnation pressure (gage) across the channel at section ②, and explain the result. Find the static pressure (gage) at section ①, and compare to the static pressure (gage) at section ②.



**Given:** Data on flow in a channel

**Find:** Static pressures; plot of stagnation pressure

**Solution:**

The given data is  $h = 1.2 \cdot \text{in}$        $\delta_2 = 0.4 \cdot \text{in}$        $U_2 = 75 \cdot \frac{\text{ft}}{\text{s}}$        $w = 6 \cdot \text{in}$

Appendix A       $\rho = 0.00239 \cdot \frac{\text{slug}}{\text{ft}^3}$

**Governing equations:** Mass       $\frac{\partial}{\partial t} \int_{\text{CV}} \rho dV + \int_{\text{CS}} \rho \vec{V} \cdot d\vec{A} = 0$       (4.12)

Before entering the duct, and in the the inviscid core, the Bernoulli equation holds

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad (4.24)$$

**Assumptions:** (1) Steady flow  
(2) No body force in  $x$  direction

For a linear velocity profile, from Table 9.2 the displacement thickness at location 2 is

$$\delta_{\text{disp}2} = \frac{\delta_2}{2} \quad \delta_{\text{disp}2} = 0.2 \cdot \text{in}$$

From the definition of the displacement thickness, to compute the flow rate, the uniform flow at location 2 is assumed to take place in the entire duct, minus the displacement thicknesses at top and bottom

$$A_2 = w \cdot (h - 2 \cdot \delta_{\text{disp}2}) \quad A_2 = 4.80 \cdot \text{in}^2$$

Then  $Q = A_2 \cdot U_2$        $Q = 2.50 \cdot \frac{\text{ft}^3}{\text{s}}$

Mass conservation (Eq. 4.12) leads to  $U_2$

$$U_1 \cdot A_1 = U_2 \cdot A_2 \quad \text{where} \quad A_1 = w \cdot h \quad A_1 = 7.2 \cdot \text{in}^2$$

$$U_1 = \frac{A_2}{A_1} \cdot U_2 \quad U_1 = 50 \cdot \frac{\text{ft}}{\text{s}}$$

The Bernoulli equation applied between atmosphere and location 1 is

$$\frac{p_{\text{atm}}}{\rho} = \frac{p_1}{\rho} + \frac{U_1^2}{2}$$

or, working in gage pressures

$$p_1 = -\frac{1}{2} \cdot \rho \cdot U_1^2$$

$$p_1 = -0.0207 \cdot \text{psi}$$

(Static pressure)

Similarly, between atmosphere and location 2 (gage pressures)

$$p_2 = -\frac{1}{2} \cdot \rho \cdot U_2^2$$

$$p_2 = -0.0467 \cdot \text{psi}$$

(Static pressure)

The static pressure falls continuously in the entrance region as the fluid in the central core accelerates into a decreasing core. The stagnation pressure at location 2 (measured, e.g., with a Pitot tube as in Eq. 6.12), is indicated by an application of the Bernoulli equation at a point

$$\frac{p_t}{\rho} = \frac{p}{\rho} + \frac{u^2}{2}$$

where  $p_t$  is the total or stagnation pressure,  $p = p_2$  is the static pressure, and  $u$  is the local velocity, given by


$$\frac{u}{U_2} = \frac{y}{\delta_2} \quad y \leq \delta_2$$

$$u = U_2 \quad \delta_2 < y \leq \frac{h}{2}$$

(Flow and pressure distributions are symmetric about centerline)

Hence  $p_t = p_2 + \frac{1}{2} \cdot \rho \cdot u^2$  The plot of stagnation pressure is shown in the *Excel* sheet below

$y$ (in)	$u$ (ft/s)	$p_t$ (psi)
0.00	0.00	0.000
0.04	7.50	0.000
0.08	15.00	0.002
0.12	22.50	0.004
0.16	30.00	0.007
0.20	37.50	0.012
0.24	45.00	0.017
0.28	52.50	0.023
0.32	60.00	0.030
0.36	67.50	0.038
0.40	75.00	0.047
0.44	75.00	0.047
0.48	75.00	0.047
0.52	75.00	0.047
0.56	75.00	0.047
0.60	75.00	0.047




The stagnation pressure indicates total mechanical energy - the curve indicates significant loss close to the walls and no loss of energy in the central core.

## Problem 9.53

[Difficulty: 3]

**9.53** For the flow conditions of Example 9.4, develop an algebraic expression for the variation of wall shear stress with distance along the surface. Integrate to obtain an algebraic expression for the total skin friction drag on the surface. Evaluate the drag for the given conditions.



**Given:** Turbulent boundary layer flow of water, 1/7-power profile

The given or available data (Table A.9) is

$$U = 1 \cdot \frac{\text{m}}{\text{s}} \quad L = 1 \cdot \text{m} \quad \nu = 1.00 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}} \quad \rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$$

**Find:** (a) Expression for wall shear stress  
 (b) Integrate to obtain expression for skin friction drag  
 (c) Evaluate for conditions shown

**Solution:**

**Basic Equation:** 
$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.0594}{\text{Re}_x^{1/5}} \quad (\text{Skin friction factor})$$

**Assumptions:** 1) Steady flow  
 2) No pressure force  
 3) No body force in  $x$  direction  
 4) Uniform flow at  $ab$

Solving the above expression for the wall shear stress: 
$$\tau_w = 0.0594 \cdot \left(\frac{1}{2} \cdot \rho \cdot U^2\right) \cdot \text{Re}_x^{-1/5} \quad \tau_w = 0.0594 \cdot \left(\frac{1}{2} \cdot \rho \cdot U^2\right) \cdot \left(\frac{U}{\nu}\right)^{-1/5} \cdot x^{-1/5}$$

Integrating to find the drag: 
$$F_D = \int_0^L \tau_w \cdot b \, dx = \int_0^L 0.0594 \cdot \left(\frac{1}{2} \cdot \rho \cdot U^2\right) \cdot \left(\frac{U}{\nu}\right)^{-1/5} \cdot x^{-1/5} \cdot b \, dx = c \cdot b \cdot \int_0^L x^{-1/5} \, dx$$
 where  $c$  is defined:

$$c = 0.0594 \cdot \left(\frac{1}{2} \cdot \rho \cdot U^2\right) \cdot \left(\frac{U}{\nu}\right)^{-1/5}$$
 Therefore the drag is: 
$$F_D = \frac{5}{4} \cdot c \cdot b \cdot L^{4/5} = \frac{5}{4} \cdot 0.0594 \cdot \frac{1}{2} \cdot \rho \cdot U^2 \cdot b \cdot L \cdot \left(\frac{U \cdot L}{\nu}\right)^{-1/5}$$


Upon simplification: 
$$F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot b \cdot L \cdot \frac{0.0721}{\text{Re}_L^{1/5}}$$

Evaluating, with  $b = 1 \cdot \text{m}$   $\text{Re}_L = \frac{U \cdot L}{\nu} = 1 \times 10^6$   $F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot b \cdot L \cdot \frac{0.0721}{\text{Re}_L^{1/5}}$   $F_D = 2.27 \text{ N}$

## Problem 9.54

[Difficulty: 3]

**\*9.54** A developing boundary layer of standard air on a flat plate is shown in Fig. P9.18. The freestream flow outside the boundary layer is undisturbed with  $U = 50$  m/s. The plate is 3 m wide perpendicular to the diagram. Assume flow in the boundary layer is turbulent, with a  $\frac{1}{7}$ -power velocity profile, and that  $\delta = 19$  mm at surface  $bc$ . Calculate the mass flow rate across surface  $ad$  and the mass flux across surface  $ab$ . Evaluate the  $x$  momentum flux across surface  $ab$ . Determine the drag force exerted on the flat plate between  $d$  and  $c$ . Estimate the distance from the leading edge at which transition from laminar to turbulent flow may be expected.



Note: Figure data applies to problem 9.18 only


**Given:** Data on fluid and turbulent boundary layer

**Find:** Mass flow rate across  $ab$ ; Momentum flux across  $bc$ ; Distance at which turbulence occurs

**Solution:**

**Basic equations:** Mass 
$$\frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A} = 0$$

Momentum 
$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$



Assumptions: 1) Steady flow 2) No pressure force 3) No body force in  $x$  direction 4) Uniform flow at  $ab$

The given or available data (Table A.10) is

$$U = 50 \frac{\text{m}}{\text{s}} \quad \delta = 19 \cdot \text{mm} \quad b = 3 \cdot \text{m} \quad \rho = 1.23 \frac{\text{kg}}{\text{m}^3} \quad \nu = 1.50 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$$

Consider CV  $abcd$   $m_{ad} = -\rho \cdot U \cdot b \cdot \delta$   $m_{ad} = -3.51 \frac{\text{kg}}{\text{s}}$  (Note: Software cannot render a dot)

Mass  $m_{ad} + \int_0^\delta \rho \cdot u \cdot b \cdot dy + m_{ab} = 0$  and in the boundary layer  $\frac{u}{U} = \left(\frac{y}{\delta}\right)^{\frac{1}{7}} = \eta^{\frac{1}{7}} \quad dy = d\eta \cdot \delta$

Hence  $m_{ab} = \rho \cdot U \cdot b \cdot \delta - \int_0^1 \rho \cdot U \cdot \eta^{\frac{1}{7}} \cdot \delta \cdot d\eta = \rho \cdot U \cdot b \cdot \delta - \frac{7}{8} \cdot \rho \cdot U \cdot b \cdot \delta$   $m_{ab} = \frac{1}{8} \cdot \rho \cdot U \cdot b \cdot \delta$   $m_{ab} = 0.438 \frac{\text{kg}}{\text{s}}$

The momentum flux across  $bc$  is  $mf_{bc} = \int_0^\delta u \cdot \rho \cdot \vec{V} \cdot d\vec{A} = \int_0^\delta u \cdot \rho \cdot u \cdot b \cdot dy = \int_0^1 \rho \cdot U^2 \cdot b \cdot \delta \cdot \eta^{\frac{2}{7}} \cdot d\eta = \rho \cdot U^2 \cdot b \cdot \delta \cdot \frac{7}{9}$

$$mf_{bc} = \frac{7}{9} \cdot \rho \cdot U^2 \cdot b \cdot \delta \quad mf_{bc} = 136.3 \frac{\text{kg} \cdot \text{m}}{\text{s}^2}$$

From momentum  $-R_x = U \cdot (-\rho \cdot U \cdot \delta) + m_{ab} \cdot u_{ab} + mf_{bc}$   $R_x = \rho \cdot U^2 \cdot b \cdot \delta - m_{ab} \cdot U - mf_{bc}$   $R_x = 17.04 \cdot \text{N}$

Transition occurs at  $Re_x = 5 \times 10^5$  and  $Re_x = \frac{U \cdot x}{\nu}$   $x_{trans} = \frac{Re_x \cdot \nu}{U}$   $x_{trans} = 0.1500 \cdot \text{m}$

## Problem 9.55

[Difficulty: 3]

**9.55** Consider flow of air over a flat plate of length 5 m. On one graph, plot the boundary-layer thickness as a function of distance along the plate for freestream speed  $U = 10$  m/s assuming (a) a completely laminar boundary layer, (b) a completely turbulent boundary layer, and (c) a laminar boundary layer that becomes turbulent at  $Re_x = 5 \times 10^5$ . Use *Excel's Goal Seek* or *Solver* to find the speeds  $U$  for which transition occurs at the trailing edge, and at  $x = 4$  m, 3 m, 2 m, and 1 m.

**Given:** Data on flow over a flat plate  $U = 10 \frac{\text{m}}{\text{s}}$   $L = 5 \text{ m}$   $\nu = 1.45 \times 10^{-5} \frac{\text{m}^2}{\text{s}}$  (from Table A.10)

**Find:** Plot of laminar and turbulent boundary layer; Speeds for transition at trailing edge

**Solution:**


**Governing Equations:** For laminar flow  $\frac{\delta}{x} = \frac{5.48}{\sqrt{Re_x}}$  (9.21) and  $Re_x = \frac{U \cdot x}{\nu}$  so  $\delta = 5.48 \cdot \sqrt{\frac{\nu \cdot x}{U}}$  (1)

The critical Reynolds number is  $Re_{crit} = 500000$  Hence, for velocity  $U$  the critical length  $x_{crit}$  is  $x_{crit} = 500000 \cdot \frac{\nu}{U}$  (2)

For turbulent flow  $\frac{\delta}{x} = \frac{0.382}{Re_x^{1/5}}$  (9.26) so  $\delta = 0.382 \cdot \left(\frac{\nu}{U}\right)^{1/5} \cdot x^{4/5}$  (3)

For (a) completely laminar flow Eq. 1 holds; for (b) completely turbulent flow Eq. 3 holds; for (c) transitional flow Eq. 1 or 3 holds depending on  $x_{crit}$  in Eq. 2. Results are shown below from *Excel*.

$x$ (m)	$Re_x$	(a) Laminar $\delta$ (mm)	(b) Turbulent $\delta$ (mm)	(c) Transition $\delta$ (mm)
0.00	0.00E+00	0.00	0.00	0.00
0.125	8.62E+04	2.33	4.92	2.33
0.250	1.72E+05	3.30	8.56	3.30
0.375	2.59E+05	4.04	11.8	4.04
0.500	3.45E+05	4.67	14.9	4.67
0.700	4.83E+05	5.52	19.5	5.5
0.75	5.17E+05	5.71	20.6	20.6
1.00	6.90E+05	6.60	26.0	26.0
1.50	1.03E+06	8.08	35.9	35.9
2.00	1.38E+06	9.3	45.2	45.2
3.00	2.07E+06	11.4	62.5	62.5
4.00	2.76E+06	13.2	78.7	78.7
5.00	3.45E+06	14.8	94.1	94.1




The speeds  $U$  at which transition occurs at specific points are shown below

$x_{\text{trans}}$ (m)	$U$ (m/s)
5	1.45
4	1.81
3	2.42
2	3.63
1	7.25

## Problem 9.56

[Difficulty: 2]

**9.56** Assume the flow conditions given in Example 9.4. Plot  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$  for the plate.



**Given:** Turbulent boundary layer flow of water

$$L = 1 \cdot \text{m} \quad U = 1 \cdot \frac{\text{m}}{\text{s}} \quad \nu = 1.00 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}} \quad \frac{u}{U} = \left(\frac{y}{\delta}\right)^{\frac{1}{7}}$$

**Find:** Plot  $\delta$ ,  $\delta^*$ , and  $\tau_w$  versus  $x/L$  for the plate

**Solution:** We will determine the drag force from the shear stress at the wall

**Governing Equations:**

$$\frac{\delta}{x} = \frac{0.382}{\text{Re}_x^{\frac{1}{5}}} \quad (\text{Boundary layer thickness})$$


$$\frac{\delta_{\text{disp}}}{\delta} = \frac{1}{8} \quad (\text{Displacement thickness})$$

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.0594}{\text{Re}_x^{\frac{1}{5}}} \quad (\text{Skin friction factor})$$

**Assumption:** Boundary layer is turbulent from  $x = 0$

For the conditions given:  $\text{Re}_L = \frac{U \cdot L}{\nu} = 1.0 \times 10^6$   $q = \frac{1}{2} \cdot \rho \cdot U^2 = 500 \text{ Pa}$   $\tau_w = \frac{0.0594}{\text{Re}_x^{\frac{1}{5}}} \cdot q = 29.7 \cdot \text{Pa} \cdot \text{Re}_x^{-\frac{1}{5}}$


Here is the plot of boundary layer thickness and wall shear stress:



## Problem 9.57

[Difficulty: 3]

**9.57** Repeat Problem 9.42, except that the air flow is now at 80 ft/s (assume turbulent boundary-layer flow).



**Given:** Triangular plate

**Find:** Drag

**Solution:**

Basic equations: 
$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2}$$

$$c_f = \frac{0.0594}{\text{Re}_x^{\frac{1}{5}}}$$

$$L = 2 \cdot \text{ft} \cdot \frac{\sqrt{3}}{2}$$

$$L = 1.732 \cdot \text{ft} \quad W = 2 \cdot \text{ft}$$

$$U = 80 \cdot \frac{\text{ft}}{\text{s}}$$

From Table A.10 at 70°F  $\nu = 1.62 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$

$$\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$$

First determine the nature of the boundary layer

$$\text{Re}_L = \frac{U \cdot L}{\nu} \quad \text{Re}_L = 9 \times 10^5$$

so definitely still laminar over a significant portion of the plate, but we are told to assume turbulent!

The drag (one side) is 
$$F_D = \int \tau_w dA$$

$$F_D = \int_0^L \tau_w \cdot w(x) dx$$

$$w(x) = W \cdot \frac{x}{L}$$

We also have

$$\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.0594}{\left(\frac{U \cdot x}{\nu}\right)^{\frac{1}{5}}}$$

Hence

$$F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{W}{L} \cdot \int_0^L \frac{0.0594 \cdot x}{\left(\frac{U \cdot x}{\nu}\right)^{\frac{1}{5}}} dx = \frac{0.0594}{2} \cdot \rho \cdot U^{\frac{9}{5}} \cdot \frac{W}{L} \cdot \nu^{\frac{1}{5}} \cdot \int_0^L x^{\frac{4}{5}} dx$$

The integral is

$$\int_0^L x^{\frac{4}{5}} dx = \frac{5}{9} \cdot L^{\frac{9}{5}} \quad \text{so} \quad F_D = 0.0165 \cdot \rho \cdot W \cdot \left(L^4 \cdot \nu \cdot U^9\right)^{\frac{1}{5}}$$

$$F_D = 0.0557 \cdot \text{lbf}$$


Note: For two-sided solution

$$2 \cdot F_D = 0.1114 \cdot \text{lbf}$$

## Problem 9.58

[Difficulty: 3]

**9.58** Repeat Problem 9.44, except that the air flow is now at 80 ft/s (assume turbulent boundary-layer flow).



**Given:** Parabolic plate

**Find:** Drag

**Solution:**

**Basic equations:**

$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2}$$

$$c_f = \frac{0.0594}{\frac{1}{Re_x^5}}$$

$$W = 1 \cdot \text{ft}$$

$$L = \frac{\left(\frac{W}{2}\right)^2}{1 \cdot \text{ft}}$$

$$L = 3 \cdot \text{in}$$

$$U = 80 \cdot \frac{\text{ft}}{\text{s}}$$

Note: "y" is the equation of the upper and lower surfaces, so  $y = W/2$  at  $x = L$

From Table A.9 at 70°F  $\nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$   $\rho = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3}$

First determine the nature of the boundary layer

$$Re_L = \frac{U \cdot L}{\nu}$$

$$Re_L = 1.23 \times 10^5$$

so still laminar, but we are told to assume turbulent!

The drag (one side) is

$$F_D = \int \tau_w dA$$

$$F_D = \int_0^L \tau_w \cdot w(x) dx$$

$$w(x) = W \cdot \sqrt{\frac{x}{L}}$$

We also have

$$\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.0594}{\frac{1}{Re_x^5}}$$

Hence

$$F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot W \cdot \int_0^L \frac{0.0594 \cdot \sqrt{\frac{x}{L}}}{\left(\frac{U \cdot x}{\nu}\right)^5} dx = \frac{0.0594}{2} \cdot \rho \cdot U^{\frac{9}{5}} \cdot W \cdot L^{-\frac{1}{2}} \cdot \frac{1}{\nu^5} \cdot \int_0^L \frac{3}{x^{\frac{10}{5}}} dx$$

$$F_D = 0.0228 \cdot \rho \cdot W \cdot \left(\nu \cdot L^4 \cdot U^9\right)^{\frac{1}{5}}$$

$$F_D = 0.00816 \cdot \text{lbf}$$


Note: For two-sided solution

$$2 \cdot F_D = 0.01632 \cdot \text{lbf}$$

## Problem 9.59

[Difficulty: 3]

**9.59** Repeat Problem 9.46, except that the air flow is now at 80 ft/s (assume turbulent boundary-layer flow).



**Given:** Pattern of flat plates

**Find:** Drag on separate and composite plates

**Solution:**

Basic equations:

$$c_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \qquad c_f = \frac{0.0594}{\text{Re}_x^{\frac{1}{5}}}$$

For separate plates  $L = 3\text{-in}$   $W = 3\text{-in}$   $U = 80 \cdot \frac{\text{ft}}{\text{s}}$

From Table A.7 at 70°F  $\nu = 1.06 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$   $\rho = 1.93 \cdot \frac{\text{slug}}{\text{ft}^3}$

First determine the nature of the boundary layer  $\text{Re}_L = \frac{U \cdot L}{\nu}$   $\text{Re}_L = 1.89 \times 10^6$  so turbulent

The drag (one side) is  $F_D = \int \tau_w dA$   $F_D = \int_0^L \tau_w \cdot W dx$

We also have  $\tau_w = c_f \cdot \frac{1}{2} \cdot \rho \cdot U^2 = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.0594}{\text{Re}_x^{\frac{1}{5}}}$

Hence 
$$F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot W \cdot \int_0^L \frac{0.0594}{\left(\frac{U \cdot x}{\nu}\right)^{\frac{1}{5}}} dx = \frac{0.0594}{2} \cdot \rho \cdot U^{\frac{9}{5}} \cdot W \cdot \nu^{\frac{1}{5}} \cdot \int_0^L x^{-\frac{1}{5}} dx$$

The integral is  $\int_0^L x^{-\frac{1}{5}} dx = \frac{5}{4} \cdot L^{\frac{4}{5}}$  so  $F_D = 0.0371 \cdot \rho \cdot W \cdot (\nu \cdot L^4 \cdot U^9)^{\frac{1}{5}}$   $F_D = 1.59 \cdot \text{lbf}$

This is the drag on one plate. The total drag is then  $F_{\text{Total}} = 4 \cdot F_D$   $F_{\text{Total}} = 6.37 \cdot \text{lbf}$

For both sides:  $2 \cdot F_{\text{Total}} = 12.73 \cdot \text{lbf}$

For the composite plate  $L = 4 \times 3 \cdot \text{in} = 12.00 \cdot \text{in}$  and since the Reynolds number for the single plate was turbulent, we know that the flow around the composite plate will be turbulent as well.

$$F_{\text{Composite}} = 0.0371 \cdot \rho \cdot W \cdot \left( \nu \cdot L^4 \cdot U^9 \right)^{\frac{1}{5}} \quad F_{\text{Composite}} = 4.82 \cdot \text{lbf}$$

$$\text{For both sides: } 2 \cdot F_{\text{Composite}} = 9.65 \cdot \text{lbf}$$

The drag is much lower on the composite compared to the separate plates. This is because  $\tau_w$  is largest near the leading edges and falls off rapidly; in this problem the separate plates experience leading edges four times!

## Problem 9.60

[Difficulty: 3]

**9.60** The velocity profile in a turbulent boundary-layer flow at zero pressure gradient is approximated by the  $\frac{1}{6}$ -power profile expression,

$$\frac{u}{U} = \eta^{1/6}, \quad \text{where } \eta = \frac{y}{\delta}$$

Use the momentum integral equation with this profile to obtain expressions for  $\delta/x$  and  $C_f$ . Compare with results obtained in Section 9.5 for the  $\frac{1}{7}$ -power profile.

**Given:** Turbulent boundary layer flow with 1/6 power velocity profile:  $\frac{u}{U} = \left(\frac{y}{\delta}\right)^{1/6} = \eta^{1/6}$

**Find:** Expressions for  $\delta/x$  and  $C_f$  using the momentum integral equation; compare to 1/7-power rule results.

**Solution:** We will apply the momentum integral equation

**Governing Equations:**  $\frac{\tau_w}{\rho} = \frac{d}{dx}(U^2 \cdot \theta) + \delta_{\text{disp}} \cdot U \cdot \left(\frac{d}{dx}U\right)$  (Momentum integral equation)

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2}$$
 (Skin friction coefficient)

- Assumptions:**
- (1) Zero pressure gradient, so  $U$  is constant and  $dp/dx = 0$
  - (2)  $\delta$  is a function of  $x$  only, and  $\delta = 0$  at  $x = 0$
  - (3) Incompressible flow
  - (4) Wall shear stress is:

$$\tau_w = 0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{0.25}$$

Applying the assumptions to the momentum integral equation yields:  $\tau_w = \rho \cdot U^2 \cdot \left(\frac{d}{dx}\theta\right) = \rho \cdot U^2 \cdot \left[\frac{d}{dx} \left[ \delta \cdot \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta \right]\right]$

Substituting for the velocity profile:  $\tau_w = \rho \cdot U^2 \cdot \left[\frac{d}{dx} \left[ \delta \cdot \int_0^1 \left(\eta^{1/6} - \eta^{2/6}\right) d\eta \right]\right] = \rho \cdot U^2 \cdot \frac{6}{56} \cdot \left(\frac{d}{dx}\delta\right)$  Setting our two  $\tau_w$ 's equal:

$$0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{0.25} = \rho \cdot U^2 \cdot \frac{6}{56} \cdot \left(\frac{d}{dx}\delta\right)$$

Simplifying and separating variables:  $\delta^{1/4} \cdot d\delta = 0.0233 \cdot \frac{56}{6} \cdot \left(\frac{\nu}{U}\right)^{1/4} \cdot dx$

Integrating both sides:  $\frac{4}{5} \cdot \delta^{5/4} = 0.0233 \cdot \frac{56}{6} \cdot \left(\frac{\nu}{U}\right)^{1/4} \cdot x + C$  but  $C = 0$  since  $\delta = 0$  at  $x = 0$ . Therefore:  $\delta = \left[ \frac{5}{4} \cdot 0.0233 \cdot \frac{56}{6} \cdot \left(\frac{\nu}{U}\right)^{1/4} \cdot x \right]^{4/5}$

In terms of the Reynolds number:  $\frac{\delta}{x} = \frac{0.353}{\text{Re}_x^{\frac{1}{5}}}$

For the skin friction factor:

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{\frac{1}{4}}}{\frac{1}{2} \cdot \rho \cdot U^2} = 0.0466 \cdot \left(\frac{\nu}{U \cdot x}\right)^{\frac{1}{4}} \cdot \left(\frac{x}{\delta}\right)^{\frac{1}{4}} = 0.0466 \cdot \text{Re}_x^{-\frac{1}{4}} \cdot \left(\frac{\frac{1}{0.353}}{\text{Re}_x^{\frac{1}{5}}}\right)^{\frac{1}{4}} \text{ Upon simplification:}$$


$$C_f = \frac{0.0605}{\text{Re}_x^{\frac{1}{5}}}$$

These results compare to  $\frac{\delta}{x} = \frac{0.353}{\text{Re}_x^{\frac{1}{5}}}$  and  $C_f = \frac{0.0605}{\text{Re}_x^{\frac{1}{5}}}$  for the 1/7-power profile.

## Problem 9.61

[Difficulty: 3]

**9.61** For the flow conditions of Example 9.4, but using the  $\frac{1}{6}$  power velocity profile of Problem 9.60, develop an algebraic expression for the variation of wall shear stress with distance along the surface. Integrate to obtain an algebraic expression for the total skin friction drag on the surface. Evaluate the drag for the given conditions.



**Given:**

Turbulent boundary layer flow with  $1/6$  power velocity profile:  $\frac{u}{U} = \left(\frac{y}{\delta}\right)^{\frac{1}{6}} = \eta^{\frac{1}{6}}$

The given or available data (Table A.9) is  $U = 1 \cdot \frac{\text{m}}{\text{s}}$      $L = 1 \cdot \text{m}$      $\nu = 1.00 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$      $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$

**Find:**

Expressions for  $\delta/x$  and  $C_f$  using the momentum integral equation; evaluate drag for the conditions given

**Solution:**

We will apply the momentum integral equation

**Governing Equations:**  $\frac{\tau_w}{\rho} = \frac{d}{dx}(U^2 \cdot \theta) + \delta_{\text{disp}} \cdot U \cdot \left(\frac{d}{dx}U\right)$  (Momentum integral equation)

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \quad \text{(Skin friction coefficient)}$$

**Assumptions:**

- (1) Zero pressure gradient, so  $U$  is constant and  $dp/dx = 0$
- (2)  $\delta$  is a function of  $x$  only, and  $\delta = 0$  at  $x = 0$
- (3) Incompressible flow
- (4) Wall shear stress is:

$$\tau_w = 0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{0.25}$$

Applying the assumptions to the momentum integral equation yields:  $\tau_w = \rho \cdot U^2 \cdot \left(\frac{d}{dx}\theta\right) = \rho \cdot U^2 \cdot \left[\frac{d}{dx}\left[\delta \cdot \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta\right]\right]$

Substituting for the velocity profile:  $\tau_w = \rho \cdot U^2 \cdot \left[\frac{d}{dx}\left[\delta \cdot \int_0^1 \left(\eta^{\frac{1}{6}} - \eta^{\frac{2}{6}}\right) d\eta\right]\right] = \rho \cdot U^2 \cdot \frac{6}{56} \cdot \left(\frac{d}{dx}\delta\right)$     Setting our two  $\tau_w$ 's equal:

$$0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{0.25} = \rho \cdot U^2 \cdot \frac{6}{56} \cdot \left(\frac{d}{dx}\delta\right) \quad \text{Simplifying and separating variables:} \quad \delta^{\frac{1}{4}} \cdot d\delta = 0.0233 \cdot \frac{56}{6} \cdot \left(\frac{\nu}{U}\right)^{\frac{1}{4}} \cdot dx$$

$$\text{Integrating both sides:} \quad \frac{4}{5} \cdot \delta^{\frac{5}{4}} = 0.0233 \cdot \frac{56}{6} \cdot \left(\frac{\nu}{U}\right)^{\frac{1}{4}} \cdot x + C \text{ but } C = 0 \text{ since } \delta = 0 \text{ at } x = 0. \text{ Therefore: } \delta = \left[\frac{5}{4} \cdot 0.0233 \cdot \frac{56}{6} \cdot \left(\frac{\nu}{U}\right)^{\frac{1}{4}} \cdot x\right]^{\frac{4}{5}}$$

In terms of the Reynolds number:  $\frac{\delta}{x} = \frac{0.353}{\text{Re}_x^{1/5}}$

For the skin friction factor:

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{1/4}}{\frac{1}{2} \cdot \rho \cdot U^2} = 0.0466 \cdot \left(\frac{\nu}{U \cdot x}\right)^{1/4} \cdot \left(\frac{x}{\delta}\right)^{1/4} = 0.0466 \cdot \text{Re}_x^{-1/4} \cdot \left(\frac{\text{Re}_x^{1/5}}{0.353}\right)^{1/4}$$

Upon simplification:  $C_f = \frac{0.0605}{\text{Re}_x^{1/5}}$

The drag force is:  $F_D = \int_0^L \tau_w \cdot b \, dx = \int_0^L 0.0605 \cdot \frac{1}{2} \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U}\right)^{1/5} \cdot x^{-1/5} \cdot b \, dx = \frac{0.0605}{2} \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U}\right)^{1/5} \cdot b \cdot \int_0^L x^{-1/5} \, dx$

Evaluating the integral:  $F_D = \frac{0.0605}{2} \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U}\right)^{1/5} \cdot b \cdot \frac{5}{4} \cdot L^{4/5}$  In terms of the Reynolds number:  $F_D = \frac{0.0378 \cdot \rho \cdot U^2 \cdot b \cdot L}{\text{Re}_L^{1/5}}$

For the given conditions and assuming that  $b = 1 \text{ m}$ :  $\text{Re}_L = 1.0 \times 10^6$  and therefore:

$$F_D = 2.38 \text{ N}$$

## Problem 9.62

[Difficulty: 3]

**9.62** Repeat Problem 9.60, using the  $\frac{1}{8}$ -power profile expression.

**Given:** Turbulent boundary layer flow with 1/8 power velocity profile:  $\frac{u}{U} = \left(\frac{y}{\delta}\right)^{\frac{1}{8}} = \eta^{\frac{1}{8}}$

**Find:** Expressions for  $\delta/x$  and  $C_f$  using the momentum integral equation; compare to 1/7-power rule results.

**Solution:** We will apply the momentum integral equation

**Governing Equations:**  $\frac{\tau_w}{\rho} = \frac{d}{dx}(U^2 \cdot \theta) + \delta_{\text{disp}} \cdot U \cdot \left(\frac{d}{dx}U\right)$  (Momentum integral equation)

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} \quad \text{(Skin friction coefficient)}$$

**Assumptions:**

- (1) Zero pressure gradient, so  $U$  is constant and  $dp/dx = 0$
- (2)  $\delta$  is a function of  $x$  only, and  $\delta = 0$  at  $x = 0$
- (3) Incompressible flow
- (4) Wall shear stress is:

$$\tau_w = 0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{0.25}$$

Applying the assumptions to the momentum integral equation yields:  $\tau_w = \rho \cdot U^2 \cdot \left(\frac{d}{dx}\theta\right) = \rho \cdot U^2 \cdot \left[\frac{d}{dx}\left[\delta \cdot \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta\right]\right]$

Substituting for the velocity profile:  $\tau_w = \rho \cdot U^2 \cdot \left[\frac{d}{dx}\left[\delta \cdot \int_0^1 \left(\eta^{\frac{1}{8}} - \eta^{\frac{2}{8}}\right) d\eta\right]\right] = \rho \cdot U^2 \cdot \frac{8}{90} \cdot \left(\frac{d}{dx}\delta\right)$  Setting our two  $\tau_w$ 's equal:

$$0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{0.25} = \rho \cdot U^2 \cdot \frac{6}{56} \cdot \left(\frac{d}{dx}\delta\right) \quad \text{Simplifying and separating variables:} \quad \delta^{\frac{1}{4}} \cdot d\delta = 0.262 \cdot \left(\frac{\nu}{U}\right)^{\frac{1}{4}} \cdot dx$$

Integrating both sides:  $\frac{4}{5} \cdot \delta^{\frac{5}{4}} = 0.262 \cdot \left(\frac{\nu}{U}\right)^{\frac{1}{4}} \cdot x + C$  but  $C = 0$  since  $\delta = 0$  at  $x = 0$ . Therefore:  $\delta = \left[\frac{5}{4} \cdot 0.262 \cdot \left(\frac{\nu}{U}\right)^{\frac{1}{4}} \cdot x\right]^{\frac{4}{5}}$

In terms of the Reynolds number:  $\frac{\delta}{x} = \frac{0.410}{\text{Re}_x^{\frac{1}{5}}}$

For the skin friction factor:

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.0233 \cdot \rho \cdot U^2 \cdot \left(\frac{\nu}{U \cdot \delta}\right)^{\frac{1}{4}}}{\frac{1}{2} \cdot \rho \cdot U^2} = 0.0466 \cdot \left(\frac{\nu}{U \cdot x}\right)^{\frac{1}{4}} \cdot \left(\frac{x}{\delta}\right)^{\frac{1}{4}} = 0.0466 \cdot \text{Re}_x^{-\frac{1}{4}} \cdot \left(\frac{\frac{1}{5}}{0.410}\right)^{\frac{1}{4}} \quad \text{Upon simplification:}$$

$$C_f = \frac{0.0582}{\text{Re}_x^{\frac{1}{5}}}$$

These results compare to  $\frac{\delta}{x} = \frac{0.353}{\text{Re}_x^{\frac{1}{5}}}$  and  $C_f = \frac{0.0605}{\text{Re}_x^{\frac{1}{5}}}$  for the 1/7-power profile.

## Problem 9.63

[Difficulty: 3]

**9.63** Standard air flows over a horizontal smooth flat plate at freestream speed  $U = 20 \text{ m/s}$ . The plate length is  $L = 1.5 \text{ m}$  and its width is  $b = 0.8 \text{ m}$ . The pressure gradient is zero. The boundary layer is tripped so that it is turbulent from the leading edge; the velocity profile is well represented by the  $1/7$ -power expression. Evaluate the boundary-layer thickness,  $\delta$ , at the trailing edge of the plate. Calculate the wall shear stress at the trailing edge of the plate. Estimate the skin friction drag on the portion of the plate between  $x = 0.5 \text{ m}$  and the trailing edge.

**Given:** Turbulent boundary layer flow of water,  $1/7$ -power profile

The given or available data (Table A.9) is

$$U = 20 \cdot \frac{\text{m}}{\text{s}} \quad L = 1.5 \cdot \text{m} \quad b = 0.8 \cdot \text{m} \quad \nu = 1.46 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad \rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \quad x_1 = 0.5 \cdot \text{m}$$

**Find:** (a)  $\delta$  at  $x = L$   
 (b)  $\tau_w$  at  $x = L$   
 (c) Drag force on the portion  $0.5 \text{ m} < x < L$

**Solution:**

**Basic equations:**  $\frac{\delta}{x} = \frac{0.382}{\text{Re}_x^{1/5}}$  (Boundary Layer Thickness)

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.0594}{\text{Re}_x^{1/5}} \quad \text{(Skin friction factor)}$$

**Assumptions:** 1) Steady flow  
 2) No pressure force  
 3) No body force in  $x$  direction

At the trailing edge of the plate:  $\text{Re}_L = \frac{U \cdot L}{\nu} = 2.05 \times 10^6$       Therefore  $\delta_L = L \cdot \frac{0.382}{\text{Re}_L^{1/5}} \quad \delta_L = 31.3 \cdot \text{mm}$

Similarly, the wall shear stress is:  $\tau_{wL} = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.0594}{\text{Re}_L^{1/5}} \quad \tau_{wL} = 0.798 \cdot \text{Pa}$

To find the drag:  $F_D = \int_{x_1}^L \tau_w \cdot b \, dx = \int_{x_1}^L 0.0594 \cdot \left(\frac{1}{2} \cdot \rho \cdot U^2\right) \cdot \left(\frac{U}{\nu}\right)^{-1/5} \cdot x^{-1/5} \cdot b \, dx = c \cdot b \cdot \int_0^L x^{-1/5} \, dx$  where  $c$  is defined:

$$c = 0.0594 \cdot \left(\frac{1}{2} \cdot \rho \cdot U^2\right) \cdot \left(\frac{U}{\nu}\right)^{-1/5} \quad \text{Therefore the drag is: } F_D = \frac{5}{4} \cdot c \cdot b \cdot L^{4/5} = \frac{5}{4} \cdot \frac{1}{2} \cdot \rho \cdot U^2 \cdot b \cdot (L \cdot C_{fL} - x_1 \cdot C_{fx1})$$

$$\text{At } x = x_1: \quad \text{Re}_{x1} = \frac{U \cdot x_1}{\nu} = 6.849 \times 10^5 \quad C_{fx1} = \frac{0.0594}{\text{Re}_{x1}^{1/5}} = 4.043 \times 10^{-3} \quad \text{and at } x = L \quad C_{fL} = \frac{0.0594}{\text{Re}_L^{1/5}} = 3.245 \times 10^{-3}$$

$$\text{Therefore the drag is:} \quad F_D = 0.700 \text{ N}$$

$$\text{Alternately, we could solve for the drag using the momentum thickness:} \quad F_D = \rho \cdot U^2 \cdot b \cdot (\theta_L - \theta_{x1}) \quad \text{where} \quad \theta = \frac{7}{72} \cdot \delta$$

$$\text{At } x = L \quad \delta_L = 31.304 \cdot \text{mm} \quad \theta_L = \frac{7}{72} \cdot \delta_L = 3.043 \cdot \text{mm} \quad \text{At } x = x_1: \quad \delta_{x1} = x_1 \cdot \frac{0.382}{\text{Re}_{x1}^{1/5}} = 12.999 \cdot \text{mm} \quad \theta_{x1} = \frac{7}{72} \cdot \delta_{x1} = 1.264 \cdot \text{mm}$$

$$\text{Therefore the drag is:} \quad F_D = 0.700 \text{ N}$$

## Problem 9.64

[Difficulty: 3]

**9.64** Air at standard conditions flows over a flat plate. The freestream speed is 30 ft/s. Find  $\delta$  and  $\tau_w$  at  $x = 3$  ft from the leading edge assuming (a) completely laminar flow (assume a parabolic velocity profile) and (b) completely turbulent flow (assume a  $\frac{1}{7}$ -power velocity profile).

**Given:** Air at standard conditions flowing over a flat plate

The given or available data (Table A.10) is

$$U = 30 \frac{\text{ft}}{\text{s}} \quad x = 3 \cdot \text{ft} \quad \nu = 1.57 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \quad \rho = 0.00238 \frac{\text{slug}}{\text{ft}^3}$$

**Find:**  $\delta$  and  $\tau_w$  at  $x$  assuming:  
 (a) completely laminar flow (parabolic velocity profile)  
 (b) completely turbulent flow ( $\frac{1}{7}$ -power velocity profile)

**Solution:**

(Laminar Flow)

(Turbulent Flow)

**Basic equations:**

$$\frac{\delta}{x} = \frac{5.48}{\sqrt{\text{Re}_x}}$$

$$\frac{\delta}{x} = \frac{0.382}{\frac{1}{\text{Re}_x^5}}$$

(Boundary Layer Thickness)

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.730}{\sqrt{\text{Re}_x}}$$

$$C_f = \frac{\tau_w}{\frac{1}{2} \cdot \rho \cdot U^2} = \frac{0.0594}{\frac{1}{\text{Re}_x^5}}$$

(Skin friction factor)

The Reynolds number is:  $\text{Re}_x = \frac{U \cdot x}{\nu} = 5.73 \times 10^5$

For laminar flow:  $\delta_{\text{lam}} = x \cdot \frac{5.48}{\sqrt{\text{Re}_x}} \quad \delta_{\text{lam}} = 0.261 \cdot \text{in}$

$$\tau_{w\text{lam}} = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.730}{\sqrt{\text{Re}_x}} \quad \tau_{w\text{lam}} = 7.17 \times 10^{-6} \cdot \text{psi}$$

For turbulent flow:  $\delta_{\text{turb}} = x \cdot \frac{0.382}{\frac{1}{\text{Re}_x^5}} \quad \delta_{\text{turb}} = 0.970 \cdot \text{in}$

$$\tau_{w\text{turb}} = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \frac{0.0594}{\frac{1}{\text{Re}_x^5}} \quad \tau_{w\text{turb}} = 3.12 \times 10^{-5} \cdot \text{psi}$$

Comparing results:  $\frac{\delta_{\text{turb}}}{\delta_{\text{lam}}} = 3.72$

The turbulent boundary layer has a much larger skin friction, which causes it to grow more rapidly than the laminar boundary layer.

$$\frac{\tau_{w\text{turb}}}{\tau_{w\text{lam}}} = 4.34$$

## Problem 9.65


[Difficulty: 3]

**9.65** A uniform flow of standard air at 60 m/s enters a plane-wall diffuser with negligible boundary-layer thickness. The inlet width is 75 mm. The diffuser walls diverge slightly to accommodate the boundary-layer growth so that the pressure gradient is negligible. Assume flat-plate boundary-layer behavior. Explain why the Bernoulli equation is applicable to this flow. Estimate the diffuser width 1.2 m downstream from the entrance.

**Given:** Air at standard conditions flowing through a plane-wall diffuser with negligible BL thickness. Walls diverge slightly to accommodate BL growth, so  $p = \text{constant}$ .

The given or available data (Table A.9) is

$$U = 60 \frac{\text{m}}{\text{s}} \quad L = 1.2 \cdot \text{m} \quad W_1 = 75 \cdot \text{mm} \quad \nu = 1.46 \times 10^{-5} \frac{\text{m}^2}{\text{s}} \quad \rho = 1.23 \frac{\text{kg}}{\text{m}^3}$$



**Find:** (a) why Bernoulli is applicable to this flow.  
(b) diffuser width  $W_2$  at  $x = L$

**Solution:**

**Basic equations:** 
$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g \cdot z_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g \cdot z_2 \quad (\text{Bernoulli Equation})$$

$$\frac{\partial}{\partial t} \int \rho \, dV + \int \rho \cdot \vec{V} \cdot d\vec{A} = 0 \quad (\text{Continuity})$$

- Assumptions:**
- (1) Steady flow
  - (2) Turbulent, 1/7-power velocity profile in boundary layer
  - (3)  $z = \text{constant}$
  - (4)  $p = \text{constant}$

The Bernoulli equation may be applied along a streamline in any steady, incompressible flow in the absence of friction. The given flow is steady and incompressible. Frictional effects are confined to the thin wall boundary layers. Therefore, the Bernoulli equation may be applied along any streamline in the core flow outside the boundary layers. (In addition, since there is no streamline curvature, the pressure is uniform across sections 1 and 2.

From the assumptions, Bernoulli reduces to:  $V_1 = V_2$  and from continuity:  $-\rho \cdot V_1 \cdot A_1 + \rho \cdot V_2 \cdot A_{2\text{eff}} = 0$

$$\text{or } A_{2\text{eff}} = (W_2 - 2 \cdot \delta_{\text{disp}2}) \cdot b = W_1 \cdot b \quad \text{Therefore: } W_2 = W_1 + 2 \cdot \delta_{\text{disp}2}$$

The Reynolds number is:  $Re_L = \frac{U \cdot L}{\nu} = 4.932 \times 10^6$  From turbulent BL theory:  $\delta_2 = L \cdot \frac{0.382}{Re_L^{1/5}} = 21.02 \cdot \text{mm}$

The displacement thickness is determined from:  $\delta_{\text{disp}2} = \delta_2 \cdot \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$  where  $\frac{u}{U} = \eta^{\frac{1}{7}}$   $\eta = \frac{y}{\delta}$


Substituting the velocity profile and valuating the integral:  $\delta_{\text{disp}2} = \delta_2 \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta = \frac{\delta_2}{8}$   $\delta_{\text{disp}2} = 2.628 \cdot \text{mm}$

Therefore:  $W_2 = W_1 + 2 \cdot \delta_{\text{disp}2}$   $W_2 = 80.3 \cdot \text{mm}$

## Problem 9.66

[Difficulty: 3]

**9.66** A laboratory wind tunnel has a flexible upper wall that can be adjusted to compensate for boundary-layer growth, giving zero pressure gradient along the test section. The wall boundary layers are well represented by the  $\frac{1}{7}$ -power-velocity profile. At the inlet the tunnel cross section is square, with height  $H_1$  and width  $W_1$ , each equal to 1 ft. With freestream speed  $U_1 = 90$  ft/s, measurements show that  $\delta_1 = 0.5$  in. and downstream  $\delta_6 = 0.65$  in. Calculate the height of the tunnel walls at (6). Determine the equivalent length of a flat plate that would produce the inlet boundary layer thickness. Estimate the streamwise distance between sections (1) and (6) in the tunnel. Assume standard air.



**Given:** Laboratory wind tunnel has flexible wall to accommodate BL growth. BL's are well represented by  $1/7$ -power profile. Information at two stations are known:

The given or available data (Table A.9) is

$$U = 90 \frac{\text{ft}}{\text{s}} \quad H_1 = 1 \cdot \text{ft} \quad W_1 = 1 \cdot \text{ft} \quad \delta_1 = 0.5 \cdot \text{in} \quad \delta_6 = 0.65 \cdot \text{in} \quad \nu = 1.57 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \quad \rho = 0.00238 \frac{\text{slug}}{\text{ft}^3}$$

**Find:** (a) Height of tunnel walls at section 6.  
 (b) Equivalent length of flat plate that would produce the inlet BL  
 (c) Estimate length of tunnel between stations 1 and 6.

**Solution:**

**Basic equations:**  $\frac{\partial}{\partial t} \int \rho dV + \int \rho \cdot \vec{V} dA = 0$  (Continuity)

**Assumptions:** (1) Steady flow  
 (2) Turbulent,  $1/7$ -power velocity profile in boundary layer  
 (3)  $z = \text{constant}$   
 (4)  $p = \text{constant}$

Applying continuity between 1 and 6:  $A_1 \cdot U_1 = A_6 \cdot U_6$  where  $A$  is the effective flow area. The velocities at 1 and 6 must be equal since pressure is constant. In terms of the duct dimensions:

$$(W_1 - 2 \cdot \delta_{\text{disp}1})(H_1 - 2 \cdot \delta_{\text{disp}1}) = (W_1 - 2 \cdot \delta_{\text{disp}6})(H_6 - 2 \cdot \delta_{\text{disp}6})$$

solving for the height at 6:  $H_6 = \frac{(W_1 - 2 \cdot \delta_{\text{disp}1})(H_1 - 2 \cdot \delta_{\text{disp}1})}{(W_1 - 2 \cdot \delta_{\text{disp}6})} + 2 \cdot \delta_{\text{disp}6}$

The displacement thickness is determined from:  $\delta_{\text{disp}} = \delta \cdot \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$  where  $\frac{u}{U} = \eta^{\frac{1}{7}}$   $\eta = \frac{y}{\delta}$

Substituting the velocity profile and valuating the integral:  $\delta_{\text{disp}} = \delta \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta = \frac{\delta}{8}$  Therefore:  $\delta_{\text{disp}1} = 0.0625 \cdot \text{in}$   
 $\delta_{\text{disp}6} = 0.0813 \cdot \text{in}$

We may now determine the height at 6:  $H_6 = 1.006 \cdot \text{ft}$

For a flat plate turbulent boundary layer with 1/7-power law profile:  $\delta_1 = L_1 \cdot \frac{0.382}{\text{Re}_1^{1/5}} = 0.382 \cdot \left(\frac{\nu}{U}\right)^{1/5} \cdot L_1^{4/5}$  Solving for  $L_1$ :

$$L_1 = \left(\frac{\delta_1}{0.382}\right)^{5/4} \cdot \left(\frac{U}{\nu}\right)^{1/4} \quad L_1 = 1.725 \cdot \text{ft}$$

To estimate the length between 1 and 6, we determine length necessary to build the BL at section 6:

$$L_6 = \left(\frac{\delta_6}{0.382}\right)^{5/4} \cdot \left(\frac{U}{\nu}\right)^{1/4} = 2.394 \cdot \text{ft} \quad \text{Therefore, the distance between 1 and 6 is: } L = L_6 - L_1$$

$$L = 0.669 \cdot \text{ft}$$

## Problem 9.67

[Difficulty: 3]

**9.67** Small wind tunnels in an undergraduate laboratory have 305-mm square test sections. Measurements show the boundary layers on the tunnel walls are fully turbulent and well represented by  $\frac{1}{7}$ -power profiles. At cross section ① with freestream speed  $U_1 = 26.1$  m/s, data show that  $\delta_1 = 12.2$  mm; at section ②, located downstream,  $\delta_2 = 16.6$  mm. Evaluate the change in static pressure between sections ① and ②. Estimate the distance between the two sections.

**Given:** Laboratory wind tunnel has fixed walls. BL's are well represented by 1/7-power profile. Information at two stations are known:

The given or available data (Table A.9) is

$$U_1 = 26.1 \cdot \frac{\text{m}}{\text{s}} \quad H = 305 \cdot \text{mm} \quad W = 305 \cdot \text{mm} \quad \delta_1 = 12.2 \cdot \text{mm} \quad \delta_2 = 16.6 \cdot \text{mm} \quad \nu = 1.46 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad \rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$$

**Find:** (a) Change in static pressure between 1 and 2  
(b) Estimate length of tunnel between stations 1 and 2.

**Solution:**

**Basic equations:**  $\frac{\partial}{\partial t} \int \rho \, dV + \int \rho \cdot \vec{V} \cdot d\vec{A} = 0$  (Continuity)

**Assumptions:** (1) Steady flow  
(2) Turbulent, 1/7-power velocity profile in boundary layer  
(3)  $z = \text{constant}$

Applying continuity between 1 and 2:  $A_1 \cdot U_1 = A_2 \cdot U_2$  where A is the effective flow area. In terms of the duct dimensions:

$$(W - 2 \cdot \delta_{\text{disp1}})(H - 2 \cdot \delta_{\text{disp1}}) \cdot U_1 = (W - 2 \cdot \delta_{\text{disp2}})(H - 2 \cdot \delta_{\text{disp2}}) \cdot U_2$$

solving for the speed at 2:  $U_2 = U_1 \cdot \frac{(W - 2 \cdot \delta_{\text{disp1}})(H - 2 \cdot \delta_{\text{disp1}})}{(W - 2 \cdot \delta_{\text{disp2}})(H - 2 \cdot \delta_{\text{disp2}})}$

The displacement thickness is determined from:  $\delta_{\text{disp}} = \delta \cdot \int_0^1 \left(1 - \frac{u}{U}\right) d\eta$  where  $\frac{u}{U} = \eta^{\frac{1}{7}}$   $\eta = \frac{y}{\delta}$

Substituting the velocity profile and valuating the integral:  $\delta_{\text{disp}} = \delta \cdot \int_0^1 \left(1 - \eta^{\frac{1}{7}}\right) d\eta = \frac{\delta}{8}$  Therefore:  $\delta_{\text{disp1}} = 1.525 \cdot \text{mm}$   
 $\delta_{\text{disp2}} = 2.075 \cdot \text{mm}$

We may now determine the speed at 2:  $U_2 = 26.3 \frac{\text{m}}{\text{s}}$

Applying Bernoulli between 1 and 2:  $\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$  Solving for the pressure change:  $\Delta p = \frac{1}{2} \cdot \rho \cdot (U_1^2 - U_2^2)$

Substituting given values:  $\Delta p = -6.16 \text{ Pa}$

For a flat plate turbulent boundary layer with 1/7-power law profile:  $\delta = x \cdot \frac{0.382}{\text{Re}_x^{1/5}} = 0.382 \cdot \left(\frac{\nu}{U}\right)^{1/5} \cdot x^{4/5}$  Solving for location at 1:

$$x_1 = \left(\frac{\delta_1}{0.382}\right)^{5/4} \cdot \left(\frac{U_1}{\nu}\right)^{1/4} = 0.494 \text{ m}$$

To estimate the length between 1 and 6, we determine length necessary to build the BL at section 2:

$$x_2 = \left(\frac{\delta_2}{0.382}\right)^{5/4} \cdot \left(\frac{U_2}{\nu}\right)^{1/4} = 0.727 \text{ m} \quad \text{Therefore, the distance between 1 and 2 is: } L = x_2 - x_1$$

$$L = 0.233 \text{ m}$$

## Problem 9.68

[Difficulty: 3]

**9.68** Air flows in a cylindrical duct of diameter  $D = 6$  in. At section ①, the turbulent boundary layer is of thickness  $\delta_1 = 0.4$  in. and the velocity in the inviscid central core is  $U_1 = 80$  ft/s. Further downstream, at section ②, the boundary layer is of thickness  $\delta_2 = 1.2$  in. The velocity profile in the boundary layer is approximated well by the  $\frac{1}{7}$ -power expression. Find the velocity,  $U_2$ , in the inviscid central core at the second section, and the pressure drop between the two sections. Does the magnitude of the pressure drop indicate that we are justified in approximating the flow between sections ① and ② as one with zero pressure gradient? Estimate the length of duct between sections ① and ②. Estimate the distance downstream from section ① at which the boundary layer thickness is  $\delta = 0.6$  in. Assume standard air.

**Given:** Data on flow in a duct

**Find:** Velocity at location 2; pressure drop; length of duct; position at which boundary layer is 20 mm

**Solution:**

The given data is  $D = 6 \cdot \text{in}$        $\delta_1 = 0.4 \cdot \text{in}$        $\delta_2 = 1.2 \cdot \text{in}$        $U_1 = 80 \cdot \frac{\text{ft}}{\text{s}}$

Table A.9       $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$        $\nu = 1.56 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$

Governing equations

Mass 
$$\frac{\partial}{\partial t} \int_{\text{CV}} \rho \, dV + \int_{\text{CS}} \rho \vec{V} \cdot d\vec{A} = 0 \quad (4.12)$$

In the boundary layer 
$$\frac{\delta}{x} = \frac{0.382}{\text{Re}_x^{1/5}} \quad (9.26)$$

In the the inviscid core, the Bernoulli equation holds

$$\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{constant} \quad (4.24)$$

Assumptions: (1) Steady flow  
(2) No body force (gravity) in  $x$  direction

For a  $1/7$ -power law profile, from Example 9.4 the displacement thickness is  $\delta_{\text{disp}} = \frac{\delta}{8}$

Hence 
$$\delta_{\text{disp1}} = \frac{\delta_1}{8} \quad \delta_{\text{disp1}} = 0.0500 \cdot \text{in}$$

$$\delta_{\text{disp2}} = \frac{\delta_2}{8} \quad \delta_{\text{disp2}} = 0.1500 \cdot \text{in}$$

From the definition of the displacement thickness, to compute the flow rate, the uniform flow at locations 1 and 2 is assumed to take place in the entire duct, minus the displacement thicknesses

$$A_1 = \frac{\pi}{4} \cdot (D - 2 \cdot \delta_{\text{disp1}})^2 \quad A_1 = 0.1899 \cdot \text{ft}^2$$

$$A_2 = \frac{\pi}{4} \cdot (D - 2 \cdot \delta_{\text{disp}2})^2 \qquad A_2 = 0.1772 \cdot \text{ft}^2$$

Mass conservation (Eq. 4.12) leads to  $U_2$

$$(-\rho \cdot U_1 \cdot A_1) + (\rho \cdot U_2 \cdot A_2) = 0 \qquad \text{or} \qquad U_2 = U_1 \cdot \frac{A_1}{A_2} \qquad U_2 = 85.7 \cdot \frac{\text{ft}}{\text{s}}$$

The Bernoulli equation applied between locations 1 and 2 is

$$\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$$

or the pressure drop is  $p_1 - p_2 = \Delta p = \frac{\rho}{2} \cdot (U_2^2 - U_1^2) \qquad \Delta p = 7.69 \times 10^{-3} \cdot \text{psi}$  (Depends on  $\rho$  value selected)

The static pressure falls continuously in the entrance region as the fluid in the central core accelerates into a decreasing core.

If we assume the stagnation pressure is atmospheric, a change in pressure of about 0.008 psi is not significant; in addition, the velocity changes by about 5%, again not a large change to within engineering accuracy

To compute distances corresponding to boundary layer thicknesses, rearrange Eq.9.26

$$\frac{\delta}{x} = \frac{0.382}{\text{Re}_x^{\frac{1}{5}}} = 0.382 \cdot \left( \frac{\nu}{U \cdot x} \right)^{\frac{1}{5}} \qquad \text{so} \qquad x = \left( \frac{\delta}{0.382} \right)^4 \cdot \left( \frac{U}{\nu} \right)^{\frac{1}{4}}$$

Applying this equation to locations 1 and 2 (using  $U = U_1$  or  $U_2$  as approximations)

$$x_1 = \left( \frac{\delta_1}{0.382} \right)^4 \cdot \left( \frac{U_1}{\nu} \right)^{\frac{1}{4}} \qquad x_1 = 1.269 \cdot \text{ft}$$

$$x_2 = \left( \frac{\delta_2}{0.382} \right)^4 \cdot \left( \frac{U_2}{\nu} \right)^{\frac{1}{4}} \qquad x_2 = 5.098 \cdot \text{ft}$$

$$x_2 - x_1 = 3.83 \cdot \text{ft} \qquad \text{(Depends on } \nu \text{ value selected)}$$

For location 3  $\delta_3 = 0.6 \cdot \text{in} \qquad \delta_{\text{disp}3} = \frac{\delta_3}{8} \qquad \delta_{\text{disp}3} = 0.075 \cdot \text{in}$

$$A_3 = \frac{\pi}{4} \cdot (D - 2 \cdot \delta_{\text{disp}3})^2 \qquad A_3 = 0.187 \cdot \text{ft}^2$$

$$U_3 = U_1 \cdot \frac{A_1}{A_3} \qquad U_3 = 81.4 \cdot \frac{\text{ft}}{\text{s}}$$

$$x_3 = \left( \frac{\delta_3}{0.382} \right)^4 \cdot \left( \frac{U_3}{\nu} \right)^{\frac{1}{4}} \qquad x_3 = 2.143 \cdot \text{ft}$$

$$x_3 - x_1 = 0.874 \cdot \text{ft} \qquad \text{(Depends on } \nu \text{ value selected)}$$

## Problem 9.69

[Difficulty: 3]

**9.69** Consider the linear, sinusoidal, and parabolic laminar boundary-layer approximations of Problem 9.10. Compare the momentum fluxes of these profiles. Which is most likely to separate first when encountering an adverse pressure gradient?

**Given:** Linear, sinusoidal and parabolic velocity profiles

**Find:** Momentum fluxes

**Solution:**

The momentum flux is given by 
$$mf = \int_0^{\delta} \rho \cdot u^2 \cdot w \, dy$$

where  $w$  is the width of the boundary layer

For a linear velocity profile 
$$\frac{u}{U} = \frac{y}{\delta} = \eta \quad (1)$$

For a sinusoidal velocity profile 
$$\frac{u}{U} = \sin\left(\frac{\pi}{2} \cdot \frac{y}{\delta}\right) = \sin\left(\frac{\pi}{2} \cdot \eta\right) \quad (2)$$

For a parabolic velocity profile 
$$\frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2 = 2 \cdot \eta - (\eta)^2 \quad (3)$$

For each of these 
$$u = U \cdot f(\eta) \quad y = \delta \cdot \eta$$

Using these in the momentum flux equation 
$$mf = \rho \cdot U^2 \cdot \delta \cdot w \cdot \int_0^1 f(\eta)^2 \, d\eta \quad (4)$$

For the linear profile Eqs. 1 and 4 give 
$$mf = \rho \cdot U^2 \cdot \delta \cdot w \cdot \int_0^1 \eta^2 \, d\eta \quad mf = \frac{1}{3} \cdot \rho \cdot U^2 \cdot \delta \cdot w$$

For the sinusoidal profile Eqs. 2 and 4 give 
$$mf = \rho \cdot U^2 \cdot \delta \cdot w \cdot \int_0^1 \sin^2\left(\frac{\pi}{2} \cdot \eta\right) \, d\eta \quad mf = \frac{1}{2} \cdot \rho \cdot U^2 \cdot \delta \cdot w$$

For the parabolic profile Eqs. 3 and 4 give 
$$mf = \rho \cdot U^2 \cdot \delta \cdot w \cdot \int_0^1 [2 \cdot \eta - (\eta)^2]^2 \, d\eta \quad mf = \frac{8}{15} \cdot \rho \cdot U^2 \cdot \delta \cdot w$$

The linear profile has the smallest momentum, so would be most likely to separate

## Problem 9.70

[Difficulty: 3]

**9.70** Perform a cost-effectiveness analysis on a typical large tanker used for transporting petroleum. Determine, as a percentage of the petroleum cargo, the amount of petroleum that is consumed in traveling a distance of 2000 miles. Use data from Example 9.5, and the following: Assume the petroleum cargo constitutes 75% of the total weight, the propeller efficiency is 70%, the wave drag and power to run auxiliary equipment constitute losses equivalent to an additional 20%, the engines have a thermal efficiency of 40%, and the petroleum energy is 20,000 Btu/lbm. Also compare the performance of this tanker to that of the Alaskan Pipeline, which requires about 120 Btu of energy for each ton-mile of petroleum delivery.

**Given:** Data on a large tanker

**Find:** Cost effectiveness of tanker; compare to Alaska pipeline

**Solution:**

The given data is  $L = 360\text{-m}$     $B = 70\text{-m}$     $D = 25\text{-m}$     $\rho = 1020 \cdot \frac{\text{kg}}{\text{m}^3}$     $U = 6.69 \cdot \frac{\text{m}}{\text{s}}$     $x = 2000\text{-mi}$

$$P = 9.7\text{-MW} \qquad P = 1.30 \times 10^4 \cdot \text{hp} \quad (\text{Power consumed by drag})$$

The power to the propeller is  $P_{\text{prop}} = \frac{P}{70\%}$     $P_{\text{prop}} = 1.86 \times 10^4 \cdot \text{hp}$

The shaft power is  $P_s = 120\% \cdot P_{\text{prop}}$     $P_s = 2.23 \times 10^4 \cdot \text{hp}$

The efficiency of the engines is  $\eta = 40\%$

Hence the heat supplied to the engines is  $Q = \frac{P_s}{\eta}$     $Q = 1.42 \times 10^8 \cdot \frac{\text{BTU}}{\text{hr}}$

The journey time is  $t = \frac{x}{U}$     $t = 134 \cdot \text{hr}$

The total energy consumed is  $Q_{\text{total}} = Q \cdot t$     $Q_{\text{total}} = 1.9 \times 10^{10} \cdot \text{BTU}$

From buoyancy the total ship weight equals the displaced seawater volume

$$M_{\text{ship}} \cdot g = \rho \cdot g \cdot L \cdot B \cdot D \qquad M_{\text{ship}} = \rho \cdot L \cdot B \cdot D \qquad M_{\text{ship}} = 1.42 \times 10^9 \cdot \text{lb}$$

Hence the mass of oil is  $M_{\text{oil}} = 75\% \cdot M_{\text{ship}}$     $M_{\text{oil}} = 1.06 \times 10^9 \cdot \text{lb}$

The chemical energy stored in the petroleum is  $q = 20000 \cdot \frac{\text{BTU}}{\text{lb}}$

The total chemical energy is  $E = q \cdot M_{\text{oil}}$     $E = 2.13 \times 10^{13} \cdot \text{BTU}$

The equivalent percentage of petroleum cargo used is then  $\frac{Q_{\text{total}}}{E} = 0.089\%$


The Alaska pipeline uses  $e_{\text{pipeline}} = 120 \cdot \frac{\text{BTU}}{\text{ton} \cdot \text{mi}}$  but for the ship  $e_{\text{ship}} = \frac{Q_{\text{total}}}{M_{\text{oil}} \cdot x}$     $e_{\text{ship}} = 17.8 \cdot \frac{\text{BTU}}{\text{ton} \cdot \text{mi}}$

The ship uses only about 15% of the energy of the pipeline!

## Problem 9.71

[Difficulty: 2]

**9.71** Consider the plane-wall diffuser shown in Fig. P9.71. First, assume the fluid is inviscid. Describe the flow pattern, including the pressure distribution, as the diffuser angle  $\phi$  is increased from zero degrees (parallel walls). Second, modify your description to allow for boundary layer effects. Which fluid (inviscid or viscous) will generally have the highest exit pressure?



**Given:** Plane-wall diffuser

**Find:** (a) For inviscid flow, describe flow pattern and pressure distribution as  $\phi$  is increased from zero  
(b) Redo part (a) for a viscous fluid  
(c) Which fluid will have the higher exit pressure?

**Solution:**

For the inviscid fluid:

With  $\phi = 0$  (straight channel) there will be no change in the velocity, and hence no pressure gradient.

With  $\phi > 0$  (diverging channel) the velocity will decrease, and hence the pressure will increase.

For the viscous fluid:

With  $\phi = 0$  (straight channel) the boundary layer will grow, decreasing the effective flow area. As a result, velocity will increase, and the pressure will drop.

With  $\phi > 0$  (diverging channel) the pressure increase due to the flow divergence will cause an increase in the rate of boundary layer growth. If  $\phi$  is too large, the flow will separate from one or both walls.

The inviscid fluid will have the higher exit pressure. (The pressure gradient with the real fluid is reduced by the boundary layer development for all values of  $\phi$ .)

## Problem 9.72

[Difficulty: 4]

**\*9.72** Table 9.1 shows the numerical results obtained from Blasius exact solution of the laminar boundary-layer equations. Plot the velocity distribution (note that from Eq. 9.13 we see that  $\eta \approx 5.0 \frac{y}{\delta}$ ). On the same graph, plot the turbulent velocity distribution given by the  $\frac{1}{7}$ -power expression of Eq. 9.24. Which is most likely to separate first when encountering an adverse pressure gradient? To justify your answer, compare the momentum fluxes of these profiles (the laminar data can be integrated using a numerical method such as Simpson's rule).

**Given:** Laminar (Blasius) and turbulent (1/7-power) velocity distributions

**Find:** Plot of distributions; momentum fluxes

**Solution:**

The momentum flux is given by 
$$mf = \int_0^{\delta} \rho \cdot u^2 dy \quad \text{per unit width of the boundary layer}$$

Using the substitutions 
$$\frac{u}{U} = f(\eta) \quad \frac{y}{\delta} = \eta$$

the momentum flux becomes 
$$mf = \rho \cdot U^2 \cdot \delta \cdot \int_0^1 f(\eta)^2 d\eta$$

For the Blasius solution a numerical evaluation (a Simpson's rule) of the integral is needed

$$mf_{lam} = \rho \cdot U^2 \cdot \delta \cdot \frac{\Delta\eta}{3} \cdot \left( f(\eta_0)^2 + 4 \cdot f(\eta_1)^2 + 2 \cdot f(\eta_2)^2 + f(\eta_N)^2 \right)$$

where  $\Delta\eta$  is the step size and  $N$  the number of steps

The result for the Blasius profile is 
$$mf_{lam} = 0.525 \cdot \rho \cdot U^2 \cdot \delta$$


For a 1/7 power velocity profile 
$$mf_{turb} = \rho \cdot U^2 \cdot \delta \cdot \int_0^1 \eta^{\frac{2}{7}} d\eta \quad mf_{turb} = \frac{7}{9} \cdot \rho \cdot U^2 \cdot \delta$$

The laminar boundary has less momentum, so will separate first when encountering an adverse pressure gradient. The computed results were generated in *Excel* and are shown below:

(Table 9.1) (Simpsons Rule)

$\eta$	Laminar $u/U$	Weight $w$	Weight x $(u/U)^2$
0.0	0.000	1	0.00
0.5	0.166	4	0.11
1.0	0.330	2	0.22
1.5	0.487	4	0.95
2.0	0.630	2	0.79
2.5	0.751	4	2.26
3.0	0.846	2	1.43
3.5	0.913	4	3.33
4.0	0.956	2	1.83
4.5	0.980	4	3.84
5.0	0.992	1	0.98
Simpsons':			<b>0.525</b>


$y/\delta = \eta$	$t$ $u/U$
0.0	0.00
0.0125	0.53
0.025	0.59
0.050	0.65
0.10	0.72
0.15	0.76
0.2	0.79
0.4	0.88
0.6	0.93
0.8	0.97
1.0	1.00



## Problem 9.73

[Difficulty: 5]

**9.73** Cooling air is supplied through the wide, flat channel shown. For minimum noise and disturbance of the outlet flow, laminar boundary layers must be maintained on the channel walls. Estimate the maximum inlet flow speed at which the outlet flow will be laminar. Assuming parabolic velocity profiles in the laminar boundary layers, evaluate the pressure drop,  $p_1 - p_2$ . Express your answer in inches of water.



**Given:** Channel flow with laminar boundary layers

**Find:** Maximum inlet speed for laminar exit; Pressure drop for parabolic velocity in boundary layers

**Solution:**

Basic equations:  $Re_{trans} = 5 \times 10^5$        $\frac{\delta}{x} = \frac{5.48}{\sqrt{Re_x}}$        $\frac{p}{\rho} + \frac{V^2}{2} + g \cdot z = \text{const}$

Assumptions: 1) Steady flow 2) Incompressible 3)  $z = \text{constant}$

From Table A.10 at 20°C  $\nu = 1.50 \times 10^{-5} \frac{m^2}{s}$        $\rho = 1.21 \frac{kg}{m^3}$        $L = 3 \cdot m$        $h = 15 \cdot cm$

Then  $Re_{trans} = \frac{U_{max} \cdot L}{\nu}$        $U_{max} = \frac{Re_{trans} \cdot \nu}{L}$        $U_{max} = 2.50 \frac{m}{s}$        $U_1 = U_{max}$        $U_1 = 2.50 \frac{m}{s}$

For  $Re_{trans} = 5 \times 10^5$        $\delta_2 = L \cdot \frac{5.48}{\sqrt{Re_{trans}}}$        $\delta_2 = 0.0232 \cdot m$

For a parabolic profile  $\frac{\delta_{disp}}{\delta} = \int_0^1 \left(1 - \frac{u}{U}\right) d\lambda = \int_0^1 (1 - 2 \cdot \lambda + \lambda^2) d\lambda = \frac{1}{3}$       where  $\delta_{trans}$  is the displacement thickness

$\delta_{disp2} = \frac{1}{3} \cdot \delta_2$        $\delta_{disp2} = 0.00775 \cdot m$

From continuity  $U_1 \cdot w \cdot h = U_2 \cdot w \cdot (h - 2 \cdot \delta_{disp2})$        $U_2 = U_1 \cdot \frac{h}{h - 2 \cdot \delta_{disp2}}$        $U_2 = 2.79 \frac{m}{s}$

Since the boundary layers do not meet Bernoulli applies in the core

$\frac{p_1}{\rho} + \frac{U_1^2}{2} = \frac{p_2}{\rho} + \frac{U_2^2}{2}$        $\Delta p = p_1 - p_2 = \frac{\rho}{2} \cdot (U_2^2 - U_1^2)$

$\Delta p = \frac{\rho}{2} \cdot (U_2^2 - U_1^2)$        $\Delta p = 0.922 \cdot Pa$

From hydrostatics  $\Delta p = \rho_{H_2O} \cdot g \cdot \Delta h$       with  $\rho_{H_2O} = 1000 \cdot \frac{kg}{m^3}$

$\Delta h = \frac{\Delta p}{\rho_{H_2O} \cdot g}$        $\Delta h = 0.0940 \cdot mm$        $\Delta h = 0.00370 \cdot in$

## Problem 9.74

[Difficulty: 3]

**9.74** Boundary-layer separation occurs when the shear stress at the surface becomes zero. Assume a polynomial representation for the laminar boundary layer of the form,  $u/U = a + b\lambda + c\lambda^2 + d\lambda^3$ , where  $\lambda = y/\delta$ . Specify boundary conditions on the velocity profile at separation. Find appropriate constants,  $a$ ,  $b$ ,  $c$ , and  $d$ , for the separation profile. Calculate the shape factor  $H$  at separation. Plot the profile and compare with the parabolic approximate profile.

**Given:** Laminar boundary layer with velocity profile  $\frac{u}{U} = a + b\lambda + c\lambda^2 + d\lambda^3 \quad \lambda = \frac{y}{\delta}$

Separation occurs when shear stress at the surface becomes zero.

**Find:** (a) Boundary conditions on the velocity profile at separation  
 (b) Appropriate constants  $a$ ,  $b$ ,  $c$ ,  $d$  for the profile  
 (c) Shape factor  $H$  at separation  
 (d) Plot the profile and compare with the parabolic approximate profile

**Solution:**

**Basic equations:**  $\frac{u}{U} = 2 \cdot \left(\frac{y}{\delta}\right) - \left(\frac{y}{\delta}\right)^2$  (Parabolic profile)

The boundary conditions for the separation profile are:

	at $y = 0 \quad u = 0 \quad \tau = \mu \cdot \frac{du}{dy} = 0$	Four boundary conditions for four coefficients $a$ , $b$ , $c$ , $d$
	at $y = \delta \quad u = U \quad \tau = \mu \cdot \frac{du}{dy} = 0$	

The velocity gradient is defined as:  $\frac{du}{dy} = \frac{U}{\delta} \cdot \left[ \frac{d}{d\lambda} \left( \frac{u}{U} \right) \right] = \frac{U}{\delta} \cdot (b + 2 \cdot c \cdot \lambda + 3 \cdot d \cdot \lambda^2)$

Applying the boundary conditions:  $y = 0 \quad \lambda = 0 \quad \frac{u}{U} = a + b \cdot 0 + c \cdot 0^2 + d \cdot 0^3 = 0$  Therefore:  $a = 0$

$\frac{du}{dy} = \frac{U}{\delta} \cdot (b + 2 \cdot c \cdot 0 + 3 \cdot d \cdot 0^2) = 0$  Therefore:  $b = 0$

The velocity profile and gradient may now be written as:  $\frac{u}{U} = c \cdot \lambda^2 + d \cdot \lambda^3 \quad \frac{du}{dy} = \frac{U}{\delta} \cdot (2 \cdot c \cdot \lambda + 3 \cdot d \cdot \lambda^2)$

Applying the other boundary conditions:


$y = \delta \quad \lambda = 1 \quad \frac{u}{U} = c \cdot 1^2 + d \cdot 1^3 = 1$	$c + d = 1$	Solving this system of equations yields: $c = 3 \quad d = -2$
$\frac{du}{dy} = \frac{U}{\delta} \cdot (2 \cdot c \cdot 1 + 3 \cdot d \cdot 1^2) = 0$	$2 \cdot c + 3 \cdot d = 0$	

The velocity profile is:  $\frac{u}{U} = 3 \cdot \lambda^2 - 2 \cdot \lambda^3$  The shape parameter is defined as:  $H = \frac{\delta_{\text{disp}}}{\theta} = \frac{\delta_{\text{disp}}}{\delta} \cdot \frac{\delta}{\theta}$

$\frac{\delta_{\text{disp}}}{\delta} = \int_0^1 (1 - 3 \cdot \lambda^2 + 2 \cdot \lambda^3) d\lambda = 1 - 1 + \frac{1}{2} = \frac{1}{2} \quad \frac{\theta}{\delta} = \int_0^1 (3 \cdot \lambda^2 - 2 \cdot \lambda^3) \cdot (1 - 3 \cdot \lambda^2 + 2 \cdot \lambda^3) d\lambda$  Expanding out the integrand yields:

$\frac{\theta}{\delta} = \int_0^1 (3 \cdot \lambda^2 - 2 \cdot \lambda^3 - 9 \cdot \lambda^4 + 12 \cdot \lambda^5 - 4 \cdot \lambda^6) d\lambda = 1 - \frac{1}{2} - \frac{9}{5} + 2 - \frac{4}{7} = \frac{9}{70}$  Thus  $H = \frac{1}{2} \times \frac{70}{9} \quad H = 3.89$

The two velocity profiles are plotted here:



## Problem 9.75

[Difficulty: 4]

**9.75** For flow over a flat plate with zero pressure gradient, will the shear stress increase, decrease, or remain constant along the plate? Justify your answer. Does the momentum flux increase, decrease, or remain constant as the flow proceeds along the plate? Justify your answer. Compare the behavior of laminar flow and turbulent flow (both from the leading edge) over a flat plate. At a given distance from the leading edge, which flow will have the larger boundary-layer thickness? Does your answer depend on the distance along the plate? How would you justify your answer?

**Discussion:** Shear stress decreases along the plate because the freestream flow speed remains constant while the boundary-layer thickness increases.

The momentum flux decreases as the flow proceeds along the plate. Momentum thickness  $\theta$  (actually proportional to the defect in momentum within the boundary layer) increases, showing that momentum flux decreases. The force that must be applied to hold the plate stationary reduces the momentum flux of the stream and boundary layer.

The laminar boundary layer has less shear stress than the turbulent boundary layer. Therefore laminar boundary layer flow from the leading edge produces a thinner boundary layer and less shear stress everywhere along the plate than a turbulent boundary layer from the leading edge.

Since both boundary layers continue to grow with increasing distance from the leading edge, and the turbulent boundary layer continues to grow more rapidly because of its higher shear stress, this comparison will be the same no matter the distance from the leading edge.

## Problem 9.76

[Difficulty: 5]


**9.76** A laboratory wind tunnel has a test section that is square in cross section, with inlet width  $W_1$  and height  $H_1$ , each equal to 1 ft. At freestream speed  $U_1 = 80$  ft/s, measurements show the boundary-layer thickness is  $\delta_1 = 0.4$  in. with a  $\frac{1}{7}$ -power turbulent velocity profile. The pressure gradient in this region is given approximately by  $dp/dx = -0.035$  in.  $H_2O/in$ . Evaluate the reduction in effective flow area caused by the boundary layers on the tunnel bottom, top, and walls at section ①. Calculate the rate of change of boundary-layer momentum thickness,  $d\theta/dx$ , at section ①. Estimate the momentum thickness at the end of the test section, located at  $L = 10$  in downstream.

**Given:** Laboratory wind tunnel has fixed walls. BL's are well represented by 1/7-power profile. Information at two stations are known:

The given or available data (Table A.9) is

$$U_1 = 80 \frac{\text{ft}}{\text{s}} \quad H_1 = 1 \cdot \text{ft} \quad W_1 = 1 \cdot \text{ft} \quad \delta_1 = 0.4 \cdot \text{in}$$

$$\frac{dp}{dx} = -0.035 \frac{\text{in} \cdot H_2O}{\text{in}} \quad L = 10 \cdot \text{in} \quad \nu = 1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \quad \rho = 0.00234 \frac{\text{slug}}{\text{ft}^3}$$



**Find:** (a) Reduction in effective flow area at section 1  
 (b)  $d\theta/dx$  at section 1  
 (c)  $\theta$  at section 2

**Solution:**

**Basic equations:**  $\frac{\partial}{\partial t} \int \rho dV + \int \rho \cdot \vec{V} dA = 0$  (Continuity)

$$\frac{\tau_w}{\rho} = \frac{d}{dx} (U^2 \cdot \theta) + \delta_{\text{disp}} \cdot U \cdot \left( \frac{d}{dx} U \right) \quad \text{(Momentum integral equation)}$$

**Assumptions:** (1) Steady flow  
 (2) Turbulent, 1/7-power velocity profile in boundary layer  
 (3)  $z = \text{constant}$

The percent reduction in flow area at 1 is given as: 
$$\frac{A_{\text{eff}} - A}{A} = \frac{(W_1 - 2 \cdot \delta_{\text{disp}}) \cdot (H_1 - 2 \cdot \delta_{\text{disp}}) - W_1 \cdot H_1}{W_1 \cdot H_1}$$

The displacement thickness is determined from: 
$$\delta_{\text{disp}} = \delta \cdot \int_0^1 \left( 1 - \frac{u}{U} \right) d\eta \quad \text{where} \quad \frac{u}{U} = \eta^{1/7} \quad \eta = \frac{y}{\delta}$$

Substituting the velocity profile and valuating the integral: 
$$\delta_{\text{disp}} = \delta \cdot \int_0^1 \left( 1 - \eta^{1/7} \right) d\eta = \frac{\delta}{8} \quad \text{Therefore:} \quad \delta_{\text{disp}1} = 0.0500 \cdot \text{in}$$

Thus: 
$$\frac{A_{\text{eff}} - A}{A} = -1.66\%$$

Solving the momentum integral equation for the momentum thickness gradient:  $\frac{d\theta}{dx} = \frac{\tau_w}{\rho \cdot U^2} - (H + 2) \cdot \frac{\theta}{U} \cdot \frac{dU}{dx}$

At station 1:  $\frac{\tau_w1}{\rho \cdot U_1^2} = 0.0233 \cdot \left(\frac{\nu}{U_1 \cdot \delta_1}\right)^{\frac{1}{4}} = 0.0233 \cdot \left(\frac{\nu}{U_1 \cdot \delta_1}\right)^{\frac{1}{4}} = 2.057 \times 10^{-3}$

$$\frac{\theta}{\delta} = \int_0^1 \frac{u}{U} \cdot \left(1 - \frac{u}{U}\right) d\eta = \int_0^L \left(\eta^{\frac{1}{7}} - \eta^{\frac{2}{7}}\right) d\eta = \frac{7}{8} - \frac{7}{9} = \frac{7}{72} \quad \text{Thus: } \theta_1 = \frac{7}{72} \cdot \delta_1 = 0.0389 \cdot \text{in} \quad H = \frac{\delta_{\text{disp}1}}{\theta_1} = 1.286$$

Now outside the boundary layer  $p + \frac{1}{2} \cdot \rho \cdot U^2 = \text{constant}$  from the Bernoulli equation. Then:  $\frac{dp}{dx} = -\rho \cdot U \cdot \frac{dU}{dx}$

Solving for the velocity gradient:  $\frac{1}{U} \cdot \frac{dU}{dx} = -\frac{1}{\rho \cdot U^2} \cdot \frac{dp}{dx} = 0.1458 \cdot \frac{1}{\text{ft}}$  Substituting all of this information into the above expression:

$$\frac{d\theta}{dx} = 4.89 \times 10^{-4} = 0.00587 \cdot \frac{\text{in}}{\text{ft}}$$

We approximate the momentum thickness at 2 from:  $\theta_2 = \theta_1 + \frac{d\theta}{dx} \cdot L$

$$\theta_2 = 0.0438 \cdot \text{in}$$

## Problem 9.77

[Difficulty: 5]

**9.77** The variable-wall concept is proposed to maintain constant boundary-layer thickness in the wind tunnel of Problem 9.76. Beginning with the initial conditions of Problem 9.76, evaluate the freestream velocity distribution needed to maintain constant boundary-layer thickness. Assume constant width,  $W_1$ . Estimate and plot the top-height settings along the test section from  $x = 0$  at section ① to  $x = 10$  in. at section ② downstream.

**Given:** Laboratory wind tunnel of Problem 9.76 with a movable top wall:

The given or available data (Table A.9) is

$$U_1 = 80 \cdot \frac{\text{ft}}{\text{s}} \quad H_1 = 1 \cdot \text{ft} \quad W = 1 \cdot \text{ft} \quad \delta = 0.4 \cdot \text{in} \quad L = 10 \cdot \text{in} \quad \nu = 1.57 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \quad \rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$$

**Find:** (a) Velocity distribution needed for constant boundary layer thickness  
(b) Tunnel height distribution  $h(x)$  from 0 to  $L$

**Solution:**

**Basic equations:**  $\frac{\partial}{\partial t} \int \rho dV + \int \rho \cdot \vec{V} \cdot d\vec{A} = 0$  (Continuity)

$$\frac{\tau_w}{\rho} = \frac{d}{dx} (U^2 \cdot \theta) + \delta_{\text{disp}} \cdot U \cdot \left( \frac{d}{dx} U \right) \quad \text{(Momentum integral equation)}$$

**Assumptions:** (1) Steady flow  
(2) Incompressible flow  
(3) Turbulent, 1/7-power velocity profile in boundary layer  
(4)  $\delta = \text{constant}$

From the 1/7-power profile:  $\delta_{\text{disp}} = \frac{\delta}{8} \quad \theta = \frac{7}{72} \cdot \delta \quad H = \frac{72}{56}$

After applying assumptions, the momentum integral equation is:  $\frac{\tau_w}{\rho \cdot U^2} = (H + 2) \cdot \frac{\theta}{U} \cdot \left( \frac{d}{dx} U \right)$

To integrate, we need to make an assumption about the wall shear stress:

Case 1: assume constant  $\tau_w$ :  $U \cdot dU = \frac{\tau_w}{\rho \cdot \theta \cdot (H + 2)} \cdot dx$  Integrating:  $\frac{U^2 - U_1^2}{2} = \frac{\tau_w}{\rho \cdot \theta \cdot (H + 2)} \cdot x$

$$\frac{U}{U_1} = \sqrt{1 + \frac{2 \cdot \tau_w}{\rho \cdot U_1^2 \cdot \theta \cdot (H + 2)} \cdot x} \quad \text{which may be rewritten as: } \frac{U}{U_1} = \sqrt{1 + \frac{C_f}{\theta \cdot (H + 2)} \cdot x}$$

Case 2: assume  $\tau_w$  has the form:  $\tau_w = 0.0233 \cdot \rho \cdot U^2 \cdot \left( \frac{\nu}{U \cdot \delta} \right)^{\frac{1}{4}}$  Substituting and rearranging yields the following expression:

$$\frac{\tau_w}{\rho \cdot U^2} = 0.0233 \cdot \left( \frac{\nu}{U \cdot \delta} \right)^{\frac{1}{4}} = (H+2) \cdot \frac{\theta}{U} \cdot \left( \frac{d}{dx} U \right) \quad \text{or} \quad \frac{dU}{U^{0.75}} = 0.0233 \cdot \left( \frac{\nu}{\delta} \right)^{0.25} \cdot \frac{dx}{(H+2) \cdot \theta} \quad \text{Integrating this yields:}$$

$$4 \cdot (U^{0.25} - U_1^{0.25}) = 0.0233 \cdot \left( \frac{\nu}{\delta} \right)^{0.25} \cdot \frac{x}{(H+2) \cdot \theta} \quad \text{or:} \quad \frac{U}{U_1} = \left[ 1 + 0.00583 \cdot \left( \frac{\nu}{U_1 \cdot \delta} \right)^{0.25} \cdot \frac{x}{(H+2) \cdot \theta} \right]^4$$


From continuity:  $U_1 \cdot A_1 = U \cdot A$  which may be rewritten as:  $U_1 \cdot (W - 2 \cdot \delta_{\text{disp}})(H_1 - 2 \cdot \delta_{\text{disp}}) = U \cdot (W - 2 \cdot \delta_{\text{disp}}) \cdot (h - 2 \cdot \delta_{\text{disp}})$

$$\text{Thus: } \frac{A}{A_1} = \left( \frac{U}{U_1} \right)^{-1} \quad \text{and} \quad \frac{h - 2 \cdot \delta_{\text{disp}}}{H_1 - 2 \cdot \delta_{\text{disp}}} = \frac{U_1}{U} \quad \text{solving for h:} \quad \frac{h}{W} = \left( 1 - 2 \cdot \frac{\delta_{\text{disp}}}{H_1} \right) \cdot \frac{U_1}{U} + 2 \cdot \frac{\delta_{\text{disp}}}{H_1}$$

$$\text{Evaluating using the given data:} \quad \delta_{\text{disp}} = \frac{\delta}{8} = 0.0500 \cdot \text{in} \quad \theta = \frac{7}{72} \cdot \delta = 0.0389 \cdot \text{in} \quad \text{Re}_{\delta 1} = \frac{U_1 \cdot \delta}{\nu} = 1.699 \times 10^4$$

$$C_f = 0.0466 \cdot \text{Re}_{\delta 1}^{-0.25} = 4.082 \times 10^{-3}$$

The results for both wall profiles are shown in the plot here:



## Problem 9.78

[Difficulty: 3]

**9.78** A flat-bottomed barge, 80 ft long and 35 ft wide, submerged to a depth of 5 ft, is to be pushed up a river (the river water is at 60°F). Estimate and plot the power required to overcome skin friction for speeds ranging up to 15 mph.

**Given:** Barge pushed upriver

$$L = 80\text{-ft} \quad B = 35\text{-ft} \quad D = 5\text{-ft} \quad \text{From Table A.7: } \nu = 1.321 \times 10^{-5} \frac{\text{ft}^2}{\text{s}} \quad \rho = 1.94 \frac{\text{slug}}{\text{ft}^3}$$

**Find:** Power required to overcome friction; Plot power versus speed

**Solution:**

**Basic equations:**


$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot U^2 \cdot A} \quad (9.32) \quad C_D = \frac{0.455}{(\log(Re_L))^{2.58}} - \frac{1610}{Re_L} \quad (9.37b) \quad Re_L = \frac{U \cdot L}{\nu}$$

From Eq. 9.32

$$F_D = C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot U^2 \quad \text{and} \quad A = L \cdot (B + 2 \cdot D) \quad A = 3600 \text{ft}^2$$

The power consumed is  $P = F_D \cdot U = C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot U^3$  The calculated results and the plot were generated in *Excel*:


$U$ (mph)	$Re_L$	$C_D$	$P$ (hp)
1	9.70E+06	0.00285	0.0571
2	1.94E+07	0.00262	0.421
3	2.91E+07	0.00249	1.35
4	3.88E+07	0.00240	3.1
5	4.85E+07	0.00233	5.8
6	5.82E+07	0.00227	9.8
7	6.79E+07	0.00222	15
8	7.76E+07	0.00219	22
9	8.73E+07	0.00215	31
10	9.70E+07	0.00212	42
11	1.07E+08	0.00209	56
12	1.16E+08	0.00207	72
13	1.26E+08	0.00205	90
14	1.36E+08	0.00203	111
15	1.45E+08	0.00201	136



## Problem 9.79

[Difficulty: 3]

**9.79** Repeat Problem 9.46, except that the water flow is now at 30 ft/s. (Use formulas for  $C_D$  from Section 9.7.)



**Given:** Pattern of flat plates

**Find:** Drag on separate and composite plates

**Solution:**

Basic equations: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$$

For separate plates  $L = 3 \cdot \text{in}$   $W = 3 \cdot \text{in}$   $A = W \cdot L$   $A = 9.000 \cdot \text{in}^2$   $V = 30 \cdot \frac{\text{ft}}{\text{s}}$

From Table A.8 at 70°F  $\nu = 1.06 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$   $\rho = 1.93 \cdot \frac{\text{slug}}{\text{ft}^3}$

First determine the Reynolds number  $Re_L = \frac{V \cdot L}{\nu}$   $Re_L = 7.08 \times 10^5$  so use Eq. 9.34

$$C_D = \frac{0.0742}{\frac{1}{Re_L^5}} \quad C_D = 0.00502$$

The drag (one side) is then  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 0.272 \cdot \text{lbf}$

This is the drag on one plate. The total drag is then  $F_{\text{Total}} = 4 \cdot F_D$   $F_{\text{Total}} = 1.09 \cdot \text{lbf}$

For both sides:  $2 \cdot F_{\text{Total}} = 2.18 \cdot \text{lbf}$

For the composite plate  $L = 4 \times 3 \cdot \text{in}$   $L = 12.000 \cdot \text{in}$   $A = W \cdot L$   $A = 36 \cdot \text{in}^2$

First determine the Reynolds number  $Re_L = \frac{V \cdot L}{\nu}$   $Re_L = 2.83 \times 10^6$  so use Eq. 9.34

$$C_D = \frac{0.0742}{\frac{1}{Re_L^5}} \quad C_D = 0.00380$$

The drag (one side) is then  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 0.826 \cdot \text{lbf}$  For both sides:  $2 \cdot F_D = 1.651 \cdot \text{lbf}$

The drag is much lower on the composite compared to the separate plates. This is because  $\tau_w$  is largest near the leading edges and falls off rapidly; in this problem the separate plates experience leading edges four times!

## Problem 9.80

[Difficulty: 3]

**9.80** A towboat for river barges is tested in a towing tank. The towboat model is built at a scale ratio of 1:13.5. Dimensions of the model are overall length 3.5 m, beam 1 m, and draft 0.2 m. (The model displacement in fresh water is 5500 N.) Estimate the average length of wetted surface on the hull. Calculate the skin friction drag force of the prototype at a speed of 7 knots relative to the water.

**Given:** Towboat model at 1:13.5 scale to be tested in towing tank.

$$L_m = 3.5 \cdot \text{m} \quad B_m = 1 \cdot \text{m} \quad d_m = 0.2 \cdot \text{m} \quad U_p = 7 \cdot \text{knot} = 3.601 \frac{\text{m}}{\text{s}} \quad \text{Disp}_m = 5500 \cdot \text{N}$$

**Find:** (a) Estimate average length of wetted surface on the hull  
(b) Calculate skin friction drag force on the prototype

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot U^2 \cdot A$  (Drag)

$$C_D = \frac{0.455}{(\log(\text{Re}_L))^{2.58}} - \frac{1610}{\text{Re}_L} \quad \text{(Drag Coefficient)}$$

We will represent the towboat as a rectangular solid of length  $L_{av}$ , with the displacement of the boat. From buoyancy:

$$W = \rho \cdot g \cdot V = \rho \cdot g \cdot L_{av} \cdot B_m \cdot d_m \quad \text{thus:} \quad L_{av} = \frac{W}{\rho \cdot g \cdot B_m \cdot d_m} \quad L_{av} = 2.80 \cdot \text{m}$$

For the prototype:  $L_p = 13.5 \cdot L_{av} \quad L_p = 37.9 \cdot \text{m}$

The Reynolds number is:  $\text{Re}_L = \frac{U_p \cdot L_p}{\nu} \quad \text{Re}_L = 1.36 \times 10^8$

This flow is predominantly turbulent, so we will use a turbulent analysis.

The drag coefficient is:  $C_D = \frac{0.455}{(\log(\text{Re}_L))^{2.58}} - \frac{1610}{\text{Re}_L} = 0.00203$

The area is:  $A = 13.5^2 \cdot L_{av} \cdot (B_m + 2 \cdot d_m) = 716 \text{ m}^2$

The drag force would then be:  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot U_p^2 \cdot A \quad F_D = 9.41 \cdot \text{kN}$

This is skin friction only.

## Problem 9.81

[Difficulty: 3]

**9.81** A jet transport aircraft cruises at 12 km in steady level flight at 800 km/h. Model the aircraft fuselage as a circular cylinder with diameter  $D = 4$  m and length  $L = 38$  m. Neglecting compressibility effects, estimate the skin friction drag force on the fuselage. Evaluate the power needed to overcome this force.

**Given:** Aircraft cruising at 12 km

**Find:** Skin friction drag force; Power required

**Solution:**

Basic equations: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$$

We "unwrap" the cylinder to obtain an equivalent flat plate

$$L = 38 \cdot \text{m} \qquad D = 4 \cdot \text{m} \qquad A = L \cdot \pi \cdot D \qquad A = 478 \text{ m}^2 \qquad V = 800 \cdot \frac{\text{km}}{\text{hr}}$$

From Table A.3, with  $z = 12000 \cdot \text{m}$   $\frac{\rho}{\rho_{SL}} = 0.2546$   $\rho_{SL} = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$

$$\rho = 0.2546 \cdot \rho_{SL} \qquad \rho = 0.3119 \frac{\text{kg}}{\text{m}^3} \qquad \text{and also} \qquad T = 216.7 \cdot \text{K}$$

From Appendix A-3  $\mu = \frac{b \cdot T^2}{1 + \frac{S}{T}}$  with  $b = 1.458 \times 10^{-6} \cdot \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^2}$   $S = 110.4 \cdot \text{K}$

Hence  $\mu = \frac{b \cdot T^2}{1 + \frac{S}{T}}$   $\mu = 1.42 \times 10^{-5} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2}$

Next we need the Reynolds number  $Re_L = \frac{\rho \cdot V \cdot L}{\mu}$   $Re_L = 1.85 \times 10^8$  so use Eq. 9.35

$$C_D = \frac{0.455}{\log(Re_L)^{2.58}} \qquad C_D = 0.00196$$

The drag is then  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 7189 \text{ N}$

The power consumed is  $P = F_D \cdot V$   $P = 1.598 \cdot \text{MW}$

## Problem 9.82

[Difficulty: 3]

**9.82** Resistance of a barge is to be determined from model test data. The model is constructed to a scale ratio of 1:13.5 and has length, beam, and draft of 7.00 m, 1.4 m, and 0.2 m, respectively. The test is to simulate performance of the prototype at 10 knots. What must the model speed be for the model and prototype to exhibit similar wave drag behavior? Is the boundary layer on the prototype predominantly laminar or turbulent? Does the model boundary layer become turbulent at the comparable point? If not, the model boundary layer could be artificially triggered to turbulent by placing a tripwire across the hull. Where could this be placed? Estimate the skin-friction drag on model and prototype.

**Given:** Towboat model at 1:13.5 scale to be tested in towing tank.

$$L_m = 7.00 \cdot \text{m} \quad B_m = 1.4 \cdot \text{m} \quad d_m = 0.2 \cdot \text{m} \quad V_p = 10 \cdot \text{knot}$$

**Find:** (a) Model speed in order to exhibit similar wave drag behavior  
 (b) Type of boundary layer on the prototype  
 (c) Where to place BL trips on the model  
 (d) Estimate skin friction drag on prototype

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

The test should be conducted to match Froude numbers:  $\frac{V_m}{\sqrt{g \cdot L_m}} = \frac{V_p}{\sqrt{g \cdot L_p}} \quad V_m = V_p \cdot \sqrt{\frac{L_m}{L_p}} \quad V_m = 2.72 \cdot \text{knot}$

The Reynolds number is:  $Re_p = \frac{V_p \cdot L_p}{\nu} \quad Re_p = 4.85 \times 10^8$

Therefore the boundary layer is turbulent. Transition occurs at  $Re_t = 5 \times 10^5$  so  $\frac{x_t}{L} = \frac{Re_t}{Re_p} = 0.00155$

Thus the location of transition would be:  $x_t = 0.00155 \cdot L_m \quad x_t = 0.0109 \text{ m}$

The wetted area is:  $A = L \cdot (B + 2 \cdot d)$  We calculate the drag coefficient from turbulent BL theory:

$$C_D = 1.25 \cdot C_f = 1.25 \times \frac{0.0594}{Re_L^{0.2}} = \frac{0.0743}{Re_L^{0.2}} \quad \text{For the model: } L_m = 7 \text{ m} \quad Re_m = \frac{V_m \cdot L_m}{\nu} = 9.77 \times 10^6 \quad A_m = 12.6 \text{ m}^2$$

Therefore  $C_{Dm} = \frac{0.0743}{Re_m^{0.2}} = 2.97 \times 10^{-3}$  and the drag force is:  $F_{Dm} = C_{Dm} \cdot \frac{1}{2} \cdot \rho \cdot V_m^2 \cdot A_m \quad F_{Dm} = 36.70 \text{ N}$

For the prototype:  $C_{Dp} = \frac{0.455}{(\log(Re_p))^{2.56}} - \frac{1610}{Re_p} \quad C_{Dp} = 1.7944 \times 10^{-3} \quad A_p = 2.30 \times 10^3 \cdot \text{m}^2$

$$F_{Dp} = C_{Dp} \cdot \frac{1}{2} \cdot \rho \cdot V_p^2 \cdot A_p \quad F_{Dp} = 54.5 \cdot \text{kN}$$

## Problem 9.83

[Difficulty: 2]

**9.83** A vertical stabilizing fin on a land-speed-record car is  $L = 1.65$  m long and  $H = 0.785$  m tall. The automobile is to be driven at the Bonneville Salt Flats in Utah, where the elevation is 1340 m and the summer temperature reaches  $50^\circ\text{C}$ . The car speed is 560 km/hr. Evaluate the length Reynolds number of the fin. Estimate the location of transition from laminar to turbulent flow in the boundary layers. Calculate the power required to overcome skin friction drag on the fin.

**Given:** Stabilizing fin on Bonneville land speed record auto

$$z = 1340\text{-m} \quad V = 560 \cdot \frac{\text{km}}{\text{hr}} \quad H = 0.785\text{-m} \quad L = 1.65\text{-m}$$

**Find:** (a) Evaluate Reynolds number of fin  
 (b) Estimate of location for transition in the boundary layer  
 (c) Power required to overcome skin friction drag

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

**Assumptions:** (1) Standard atmosphere (use table A.3)

At this elevation:  $T = 279\text{-K}$   $\rho = 0.877 \times 1.23 \cdot \frac{\text{kg}}{\text{m}^3} = 1.079 \frac{\text{kg}}{\text{m}^3}$   $\mu = 1.79 \times 10^{-5} \cdot \frac{\text{kg}}{\text{m}\cdot\text{s}}$

The Reynolds number on the fin is:  $Re_L = \frac{\rho \cdot V \cdot L}{\mu}$   $Re_L = 1.547 \times 10^7$

Assume transition occurs at:  $Re_t = 5 \times 10^5$  The location for transition would then be:  $x_t = \frac{Re_t \cdot \mu}{\rho \cdot V}$   $x_t = 53.3\text{-mm}$

From Figure 9.8, the drag coefficient is:  $C_D = 0.0029$  The area is:  $A = 2 \cdot L \cdot H = 2.591 \text{ m}^2$  (both sides of the fin)

The drag force would then be:  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 98.0 \text{ N}$

The power required would then be:  $P = F_D \cdot V$   $P = 15.3\text{-kW}$

If we check the drag coefficient using Eq. 9.37b:  $C_D = \frac{0.455}{(\log(Re_L))^{2.58}} - \frac{1610}{Re_L} = 0.0027$

This is slightly less than the graph, but still reasonable agreement.

## Problem 9.84

[Difficulty: 4]

**9.84** A nuclear submarine cruises fully submerged at 27 knots. The hull is approximately a circular cylinder with diameter  $D = 11.0$  m and length  $L = 107$  m. Estimate the percentage of the hull length for which the boundary layer is laminar. Calculate the skin friction drag on the hull and the power consumed.

**Given:** Nuclear submarine cruising submerged. Hull approximated by circular cylinder

$$L = 107 \cdot \text{m} \quad D = 11.0 \cdot \text{m} \quad V = 27 \cdot \text{knot}$$

**Find:** (a) Percentage of hull length for which BL is laminar  
(b) Skin friction drag on hull  
(c) Power consumed

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

Transition occurs at  $Re_t = 5 \times 10^5$  so the location of transition would be:  $\frac{x_t}{L} = \frac{Re_t \cdot \nu}{V \cdot L}$   $\frac{x_t}{L} = 0.0353\%$

We will therefore assume that the BL is completely turbulent.

The Reynolds number at  $x = L$  is:  $Re_L = \frac{V \cdot L}{\nu} = 1.42 \times 10^9$  For this Reynolds number:  $C_D = \frac{0.455}{(\log(Re_L))^{2.58}} = 1.50 \times 10^{-3}$

The wetted area of the hull is:  $A = \pi \cdot D \cdot L = 3698 \cdot \text{m}^2$

So the drag force is:  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 5.36 \times 10^5 \text{ N}$

The power consumed is:  $P = F_D \cdot V$   $P = 7.45 \cdot \text{MW}$

## Problem 9.85

[Difficulty: 3]

**9.85** You are asked by your college crew to estimate the skin friction drag on their eight-seat racing shell. The hull of the shell may be approximated as half a circular cylinder with 457 mm diameter and 7.32 m length. The speed of the shell through the water is 6.71 m/s. Estimate the location of transition from laminar to turbulent flow in the boundary layer on the hull of the shell. Calculate the thickness of the turbulent boundary layer at the rear of the hull. Determine the total skin friction drag on the hull under the given conditions.

**Given:** Racing shell for crew approximated by half-cylinder:

$$L = 7.32 \cdot \text{m} \quad D = 457 \cdot \text{mm} \quad V = 6.71 \cdot \frac{\text{m}}{\text{s}}$$

**Find:** (a) Location of transition on hull  
(b) Thickness of turbulent BL at the rear of the hull  
(c) Skin friction drag on hull

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

Transition occurs at  $Re_t = 5 \times 10^5$  so the location of transition would be:  $x_t = \frac{Re_t \cdot \nu}{V}$   $x_t = 0.0745 \text{ m}$

For the turbulent boundary layer  $\frac{\delta}{x} = \frac{0.382}{Re_x^{0.2}}$  Therefore  $\delta = \frac{0.382 \cdot L}{Re_L^{0.2}}$

The Reynolds number at  $x = L$  is:  $Re_L = \frac{V \cdot L}{\nu} = 4.91 \times 10^7$  so the BL thickness is:  $\delta = \frac{0.382 \cdot L}{Re_L^{0.2}}$   $\delta = 0.0810 \text{ m}$

The wetted area of the hull is:  $A = \frac{\pi \cdot D}{2} \cdot L = 5.2547 \cdot \text{m}^2$  For this Reynolds number:  $C_D = \frac{0.455}{(\log(Re_L))^{2.58}} = 2.36 \times 10^{-3}$

So the drag force is:  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 278 \text{ N}$

Note that the rowers must produce an average power of  $P = F_D \cdot V = 1.868 \cdot \text{kW}$  to move the shell at this speed.

## Problem 9.86

[Difficulty: 3]

**9.86** A sheet of plastic material 0.5 in. thick, with specific gravity  $SG = 1.7$ , is dropped into a large tank containing water. The sheet is  $2 \text{ ft} \times 4 \text{ ft}$ . Estimate the terminal speed of the sheet as it falls with (a) the short side vertical and (b) the long side vertical. Assume that the drag is due only to skin friction, and that the boundary layers are turbulent from the leading edge.

**Given:** Plastic sheet falling in water

**Find:** Terminal speed both ways

**Solution:**

**Basic equations:**  $\Sigma F_y = 0$  for terminal speed

$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} \quad C_D = \frac{0.0742}{\frac{1}{\text{Re}_L^5}} \quad (9.34) \text{ (assuming } 5 \times 10^5 < \text{Re}_L < 10^7)$$

$h = 0.5 \text{ in} \quad W = 4 \text{ ft} \quad L = 2 \text{ ft} \quad SG = 1.7$  From Table A.8 at  $70^\circ\text{F}$   $\nu = 1.06 \times 10^{-5} \frac{\text{ft}^2}{\text{s}} \quad \rho = 1.94 \frac{\text{slug}}{\text{ft}^3}$

$A = W \cdot L$


A free body diagram of the sheet is shown here. Summing the forces in the vertical (y) direction:

$$F_D + F_b - W_{\text{sheet}} = 0 \quad F_D = W_{\text{sheet}} - F_b = \rho \cdot g \cdot h \cdot A \cdot (SG - 1)$$

Also, we can generate an expression for the drag coefficient in terms of the geometry of the sheet and the water properties:

$$F_D = 2 \cdot C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot V^2 = 2 \cdot \frac{0.0742}{\frac{1}{\text{Re}_L^5}} \cdot A \cdot \frac{1}{2} \cdot \rho \cdot V^2 = \frac{0.0742}{\frac{1}{\left(\frac{V \cdot L}{\nu}\right)^5}} \cdot W \cdot L \cdot \rho \cdot V^2 = 0.0742 \cdot W \cdot L \cdot \nu^{\frac{4}{5}} \cdot \frac{1}{V^{\frac{9}{5}}} \cdot \rho \cdot V^2$$

(Note that we double  $F_D$  because drag acts on both sides of the sheet.)



Hence  $\rho_{\text{H}_2\text{O}} \cdot g \cdot h \cdot W \cdot (SG - 1) = 0.0742 \cdot W \cdot L \cdot \nu^{\frac{4}{5}} \cdot \frac{1}{V^{\frac{9}{5}}} \cdot \rho \cdot V^2$  Solving for V  $V = \left[ \frac{g \cdot h \cdot (SG - 1)}{0.0742} \cdot \left(\frac{L}{\nu}\right)^{\frac{1}{5}} \right]^{\frac{5}{9}} \quad V = 15.79 \frac{\text{ft}}{\text{s}}$

Check the Reynolds number  $\text{Re}_L = \frac{V \cdot L}{\nu} \quad \text{Re}_L = 2.98 \times 10^6$  Hence Eq. 9.34 is reasonable

Repeating for  $L = 4 \text{ ft}$   $V = \left[ \frac{g \cdot h \cdot (SG - 1)}{0.0742} \cdot \left(\frac{L}{\nu}\right)^{\frac{1}{5}} \right]^{\frac{5}{9}} \quad V = 17.06 \frac{\text{ft}}{\text{s}}$

Check the Reynolds number  $\text{Re}_L = \frac{V \cdot L}{\nu} \quad \text{Re}_L = 6.44 \times 10^6$  Eq. 9.34 is still reasonable

The short side vertical orientation falls more slowly because the largest friction is at the region of the leading edge ( $\tau$  tails off as the boundary layer progresses); its leading edge area is larger. Note that neither orientation is likely - the plate will flip around in a chaotic manner.

## Problem 9.87

[Difficulty: 4]

**9.87** The 600-seat jet transport aircraft proposed by Airbus Industrie has a fuselage that is 240 ft long and 25 ft in diameter. The aircraft is to operate 14 hr per day, 6 days per week; it will cruise at 575 mph ( $M = 0.87$ ) at 12-km altitude. The engines consume fuel at the rate of 0.6 lbm/hr for each pound force of thrust produced. Estimate the skin friction drag force on the aircraft fuselage at cruise. Calculate the annual fuel savings for the aircraft if friction drag on the fuselage could be reduced by 1 percent by modifying the surface coating.

**Given:** 600-seat jet transport to operate 14 hr/day, 6 day/wk  
 $L = 240 \cdot \text{ft}$   $D = 25 \cdot \text{ft}$   $V = 575 \cdot \text{mph}$   $z = 12 \cdot \text{km}$   $\text{TSFC} = 0.6 \cdot \frac{\text{lbm}}{\text{hr} \cdot \text{lbf}}$

**Find:** (a) Skin friction drag on fuselage at cruise  
 (b) Annual fuel savings if drag is reduced by 1%

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

From the atmosphere model:  $T = 216.7 \cdot \text{K} = 390.1 \cdot \text{R}$   $\rho = 0.2546 \times 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} = 6.0518 \times 10^{-4} \cdot \frac{\text{slug}}{\text{ft}^3}$

From the Sutherland model for viscosity:  $\mu = \frac{b \cdot \sqrt{T}}{1 + \frac{S}{T}} = 1.422 \times 10^{-5} \frac{\text{kg}}{\text{m} \cdot \text{s}}$  So the Reynolds number is

$\text{Re}_L = \frac{\rho \cdot V \cdot L}{\mu} = 4.1247 \times 10^8$  For this Reynolds number:  $C_D = \frac{0.455}{(\log(\text{Re}_L))^{2.58}} = 1.76 \times 10^{-3}$

The wetted area of the fuselage is:  $A = \pi \cdot D \cdot L = 1.885 \times 10^4 \cdot \text{ft}^2$

So the drag force is:  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 7.13 \times 10^3 \cdot \text{lbf}$

If there were a 1% savings in drag, the drop in drag force would be:  $\Delta F_D = 1\% \cdot F_D = 71.31 \cdot \text{lbf}$

The savings in fuel would be:  $\Delta m_{\text{fuel}} = \text{TSFC} \cdot \Delta F_D \times 14 \cdot \frac{\text{hr}}{\text{day}} \times \left(\frac{6}{7} \times 52\right) \cdot \frac{\text{day}}{\text{yr}}$   $\Delta m_{\text{fuel}} = 2.670 \times 10^4 \cdot \frac{\text{lbm}}{\text{yr}}$

If jet fuel costs \$1 per gallon, this would mean a savings of over \$4,400 per aircraft per year.

## Problem 9.88

[Difficulty: 4]

**9.88** A supertanker displacement is approximately 600,000 tons. The ship has length  $L = 1000$  ft, beam (width)  $b = 270$  ft, and draft (depth)  $D = 80$  ft. The ship steams at 15 knots through seawater at 40°F. For these conditions, estimate (a) the thickness of the boundary layer at the stern of the ship, (b) the total skin friction drag acting on the ship, and (c) the power required to overcome the drag force.

**Given:** Supertanker in seawater at 40°F

$$L = 1000 \cdot \text{ft} \quad B = 270 \cdot \text{ft} \quad D = 80 \cdot \text{ft} \quad V = 15 \cdot \text{knot} = 25.32 \cdot \frac{\text{ft}}{\text{s}} \quad \text{SG} = 1.025$$

$$\nu = 1.05 \times 1.65 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}} = 1.73 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}} \quad \rho = 1.9888 \cdot \frac{\text{slug}}{\text{ft}^3}$$

**Find:** (a) Thickness of the boundary layer at the stern of the ship  
 (b) Skin friction drag on the ship  
 (c) Power required to overcome the drag force

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

The Reynolds number is  $Re_L = \frac{V \cdot L}{\nu} = 1.4613 \times 10^9$  So the BL is turbulent. The BL thickness is calculated using:

$$\frac{\delta}{x} = \frac{0.382}{Re_x^{0.20}} \quad \text{At the stern of the ship:} \quad \delta = L \cdot \frac{0.382}{Re_L^{0.20}} \quad \delta = 5.61 \cdot \text{ft}$$

The wetted area of the hull is:  $A = L \cdot (B + 2 \cdot D) = 4.30 \times 10^5 \cdot \text{ft}^2$  For this Reynolds number:  $C_D = \frac{0.455}{(\log(Re_L))^{2.58}} = 1.50 \times 10^{-3}$

So the drag force is:  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$   $F_D = 4.11 \times 10^5 \cdot \text{lb}_f$

The power consumed to overcome the skin friction drag is:  $P = F_D \cdot V$   $P = 1.891 \times 10^4 \cdot \text{hp}$   
 $P = 1.040 \times 10^7 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{s}}$

## Problem 9.89

[Difficulty: 4]

**9.89** In Section 7.6 the wave resistance and viscous resistance on a model and prototype ship were discussed. For the prototype,  $L = 130 \text{ m}$  and  $A = 1800 \text{ m}^2$ . From the data of Figs 7.2 and 7.3, plot on one graph the wave, viscous, and total resistance (N) experienced by the prototype, as a function of speed. Plot a similar graph for the model. Discuss your results. Finally, plot the power (kW) required for the prototype ship to overcome the total resistance.


**Given:** "Resistance" data on a ship

$$L_p = 130 \cdot \text{m} \quad A_p = 1800 \cdot \text{m}^2 \quad \rho = 1023 \cdot \frac{\text{kg}}{\text{m}^3} \quad \mu = 1.08 \times 10^{-3} \cdot \frac{\text{N}\cdot\text{s}}{\text{m}^2}$$


$$L_m = \frac{L_p}{80} = 1.625 \text{ m} \quad A_m = \frac{A_p}{80^2} = 0.281 \text{ m}^2$$

**Find:** Plot of wave, viscous and total drag (prototype and model); power required by prototype

**Solution:**



**Fig. 7.2** Data from test of 1:80 scale model of U.S. Navy guided missile frigate *Oliver Hazard Perry* (FFG-7). (Data from U.S. Naval Academy Hydromechanics Laboratory, courtesy of Professor Bruce Johnson.)



**Fig. 7.3** Resistance of full-scale ship predicted from model test results. (Data from U.S. Naval Academy Hydromechanics Laboratory, courtesy of Professor Bruce Johnson.)

**Basic equations:**

$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot U^2 \cdot A} \quad (9.32)$$

$$Fr = \frac{U}{\sqrt{gL}}$$

From Eq. 9.32

$$F_D = C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot U^2$$

This applies to each component of the drag (wave and viscous) as well as to the total

The power consumed is

$$P = F_D \cdot U \quad P = C_D \cdot A \cdot \frac{1}{2} \cdot \rho \cdot U^3$$



From the Froude number

$$U = Fr \cdot \sqrt{gL}$$

The solution technique is: For each speed  $Fr$  value from the graph, compute  $U$ ; compute the drag from the corresponding "resistance" value from the graph. The results were generated in *Excel* and are shown below:



Model

$Fr$	Wave "Resistance"	Viscous "Resistance"	Total "Resistance"	$U$ (m/s)	Wave Drag (N)	Viscous Drag (N)	Total Drag (N)	Power (W)
0.10	0.00050	0.0052	0.0057	0.40	0.0057	0.0596	0.0654	0.0261
0.20	0.00075	0.0045	0.0053	0.80	0.0344	0.2064	0.2408	0.1923
0.30	0.00120	0.0040	0.0052	1.20	0.1238	0.4128	0.5366	0.6427
0.35	0.00150	0.0038	0.0053	1.40	0.2107	0.5337	0.7444	1.0403
0.40	0.00200	0.0038	0.0058	1.60	0.3669	0.6971	1.0640	1.6993
0.45	0.00300	0.0036	0.0066	1.80	0.6966	0.8359	1.5324	2.7533
0.50	0.00350	0.0035	0.0070	2.00	1.0033	1.0033	2.0065	4.0057
0.60	0.00320	0.0035	0.0067	2.40	1.3209	1.4447	2.7656	6.6252



**Prototype**

$Fr$	Wave "Resistance"	Viscous "Resistance"	Total "Resistance"	$U$ (m/s)	Wave Drag (MN)	Viscous Drag (MN)	Total Drag (MN)	Power (kW)	Power (hp)
0.10	0.00050	0.0017	0.0022	3.6	0.0029	0.0100	0.0129	46.1	61.8
0.20	0.00075	0.0016	0.0024	7.1	0.0176	0.0376	0.0552	394.1	528.5
0.30	0.00120	0.0015	0.0027	10.7	0.0634	0.0793	0.1427	1528.3	2049.5
0.35	0.00150	0.0015	0.0030	12.5	0.1079	0.1079	0.2157	2696.6	3616.1
0.40	0.00200	0.0013	0.0033	14.3	0.1879	0.1221	0.3100	4427.7	5937.6
0.45	0.00300	0.0013	0.0043	16.1	0.3566	0.1545	0.5112	8214.7	11015.9
0.50	0.00350	0.0013	0.0048	17.9	0.5137	0.1908	0.7045	12578.7	16868.1
0.60	0.00320	0.0013	0.0045	21.4	0.6763	0.2747	0.9510	20377.5	27326.3



For the prototype wave resistance is a much more significant factor at high speeds! However, note that for both scales, the primary source of drag changes with speed. At low speeds, viscous effects dominate, and so the primary source of drag is viscous drag. At higher speeds, inertial effects dominate, and so the wave drag is the primary source of drag.

## Problem 9.90

[Difficulty: 2]

**9.90** As part of the 1976 bicentennial celebration, an enterprising group hung a giant American flag (194 ft high and 367 ft wide) from the suspension cables of the Verrazano Narrows Bridge. They apparently were reluctant to make holes in the flag to alleviate the wind force, and hence they effectively had a flat plate normal to the flow. The flag tore loose from its mountings when the wind speed reached 10 mph. Estimate the wind force acting on the flag at this wind speed. Should they have been surprised that the flag blew down?

**Given:** Flag mounted vertically

$$H = 194 \cdot \text{ft} \quad W = 367 \cdot \text{ft} \quad V = 10 \cdot \text{mph} = 14.67 \cdot \frac{\text{ft}}{\text{s}} \quad \rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \nu = 1.62 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$$

**Find:** Force acting on the flag. Was failure a surprise?

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

We should check the Reynolds number to be sure that the data of Fig. 9.10 are applicable:  $Re_W = \frac{V \cdot W}{\nu} = 3.32 \times 10^7$

(We used  $W$  as our length scale here since it is the lesser of the two dimensions of the flag.) Since the Reynolds number is less than 1000, we may use Figure 9.10 to find the drag coefficient.

The area of the flag is:  $A = H \cdot W = 7.12 \times 10^4 \cdot \text{ft}^2$   $AR = \frac{W}{H} = 1.89$  From Fig. 9.10:  $C_D = 1.15$

$$\text{So the drag force is: } F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \quad F_D = 2.06 \times 10^4 \cdot \text{lb}_f$$

This is a large force. Failure should have been expected.

## Problem 9.91

[Difficulty: 3]

**9.91** A fishing net is made of 0.75-mm diameter nylon thread assembled in a rectangular pattern. The horizontal and vertical distances between adjacent thread centerlines are 1 cm. Estimate the drag on a 2 m × 12 m section of this net when it is dragged (perpendicular to the flow) through 15°C water at 6 knots. What is the power required to maintain this motion?

**Given:** Fishing net

**Find:** Drag; Power to maintain motion  $\frac{3}{8} \cdot \text{in} = 9.525 \cdot \text{mm}$

**Solution:**

Basic equations: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$$

We convert the net into an equivalent cylinder (we assume each segment does not interfere with its neighbors)

$L = 12 \cdot \text{m}$        $W = 2 \cdot \text{m}$        $d = 0.75 \cdot \text{mm}$  Spacing:  $D = 1 \cdot \text{cm}$        $V = 6 \cdot \text{knot}$        $V = 3.09 \cdot \frac{\text{m}}{\text{s}}$

Total number of threads of length L is  $n_1 = \frac{W}{D}$        $n_1 = 200$       Total length  $L_1 = n_1 \cdot L$        $L_1 = 2400 \cdot \text{m}$

Total number of threads of length W is  $n_2 = \frac{L}{D}$        $n_2 = 1200$       Total length  $L_2 = n_2 \cdot W$        $L_2 = 2400 \cdot \text{m}$

Total length of thread  $L_T = L_1 + L_2$        $L_T = 4800 \cdot \text{m}$        $L_T = 2.98 \cdot \text{mile}$  A lot!

The frontal area is then  $A = L_T \cdot d$        $A = 3.60 \cdot \text{m}^2$       Note that  $L \cdot W = 24.00 \cdot \text{m}^2$

From Table A.8  $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$        $\nu = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$

The Reynolds number is  $Re_d = \frac{V \cdot d}{\nu}$        $Re_d = 2292$

For a cylinder in a crossflow at this Reynolds number, from Fig. 9.13, approximately  $C_D = 0.8$


Hence  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$        $F_D = 13.71 \cdot \text{kN}$

The power required is  $P = F_D \cdot V$        $P = 42.3 \cdot \text{kW}$

## Problem 9.92

[Difficulty: 2]

**9.92** A rotary mixer is constructed from two circular disks as shown. The mixer is rotated at 60 rpm in a large vessel containing a brine solution (SG = 1.1). Neglect the drag on the rods and the motion induced in the liquid. Estimate the minimum torque and power required to drive the mixer.



**Given:** Rotary mixer rotated in a brine solution

$$R = 0.6 \cdot \text{m} \quad \omega = 60 \cdot \text{rpm} \quad d = 100 \cdot \text{mm} \quad \text{SG} = 1.1 \quad \rho = \rho_w \cdot \text{SG} \quad \rho = 1100 \cdot \frac{\text{kg}}{\text{m}^3}$$

$$\nu = 1.05 \times 1.55 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}} = 1.63 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$$

**Find:** (a) Torque on mixer  
(b) Horsepower required to drive mixer

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

$$T = 2 \cdot R \cdot F_D$$
 (Torque)

$$P = T \cdot \omega$$
 (Power)

**Assumptions:** Drag on rods and motion induced in the brine can be neglected.

The speed of the disks through the brine is:  $V = R \cdot \omega = 3.77 \frac{\text{m}}{\text{s}}$  From Table 9.2:  $C_D = 1.17$  for a disk.

The area of one disk is:  $A = \frac{\pi}{4} \cdot d^2 = 0.00785 \cdot \text{m}^2$


So the drag force is:  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A = 71.8 \text{ N}$  and the torque is:  $T = 2 \cdot R \cdot F_D$   $T = 86.2 \cdot \text{N} \cdot \text{m}$

The power consumed to run the mixer is:  $P = T \cdot \omega = 542 \text{ W}$   $P = 0.726 \cdot \text{hp}$

## Problem 9.93

[Difficulty: 3]

**9.93** As a young design engineer you decide to make the rotary mixer look more “cool” by replacing the disks with rings. The rings may have the added benefit of making the mixer mix more effectively. If the mixer absorbs 350 W at 60 rpm, redesign the device. There is a design constraint that the outer diameter of the rings not exceed 125 mm.



**Given:** Data on a rotary mixer

**Find:** New design dimensions

**Solution:**

The given data or available data is

$$R = 0.6 \cdot \text{m} \quad P = 350 \cdot \text{W} \quad \omega = 60 \cdot \text{rpm} \quad \rho = 1099 \cdot \frac{\text{kg}}{\text{m}^3}$$

For a ring, from Table 9.3  $C_D = 1.2$

The torque at the specified power and speed is

$$T = \frac{P}{\omega} \quad T = 55.7 \cdot \text{N} \cdot \text{m}$$

The drag on *each* ring is then  $F_D = \frac{1}{2} \cdot \frac{T}{R} \quad F_D = 46.4 \text{ N}$

The linear velocity of each ring is  $V = R \cdot \omega \quad V = 3.77 \frac{\text{m}}{\text{s}}$

The drag and velocity of each ring are related using the definition of drag coefficient

$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$$

Solving for the ring area  $A = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot C_D} \quad A = 4.95 \times 10^{-3} \text{ m}^2$

But  $A = \frac{\pi}{4} \cdot (d_o^2 - d_i^2)$

The outer diameter is  $d_o = 125 \cdot \text{mm}$

Hence the inner diameter is  $d_i = \sqrt{d_o^2 - \frac{4 \cdot A}{\pi}} \quad d_i = 96.5 \cdot \text{mm}$

## Problem 9.94

[Difficulty: 2]

**9.94** The vertical component of the landing speed of a parachute is to be less than 20 ft/s. The total weight of the jumper and the chute is 250 lb. Determine the minimum diameter of the open parachute.

**Given:** Man with parachute

$$W = 250 \cdot \text{lbf} \quad V = 20 \cdot \frac{\text{ft}}{\text{s}} \quad \rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$$

**Find:** Minimum diameter of parachute

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)


**Assumptions:** (1) Standard air  
(2) Parachute behaves as open hemisphere  
(3) Vertical speed is constant

For constant speed:  $\Sigma F_y = M \cdot g - F_D = 0$  Therefore:  $F_D = W$

In terms of the drag coefficient:  $C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A = W$

Solving for the area:  $A = \frac{2 \cdot W}{C_D \cdot \rho \cdot V^2}$  From Table 9.2:  $C_D = 1.42$  for an open hemisphere. The area is:  $A = \frac{\pi}{4} \cdot D^2$

Setting both areas equal:  $\frac{\pi}{4} \cdot D^2 = \frac{2 \cdot W}{C_D \cdot \rho \cdot V^2}$  Solving for the diameter of the parachute:  $D = \sqrt{\frac{8}{\pi} \cdot \frac{W}{C_D \cdot \rho \cdot V^2}}$



Therefore the diameter is:  $D = 21.9 \cdot \text{ft}$

## Problem 9.95

[Difficulty: 3]

**9.95** As a young design engineer you are asked to design an emergency braking parachute system for use with a military aircraft of mass 9500 kg. The plane lands at 350 km/hr, and the parachute system alone must slow the airplane to 100 km/hr in less than 1200 m. Find the minimum diameter required for a single parachute, and for three non-interfering parachutes. Plot the airplane speed versus distance and versus time. What is the maximum "g-force" experienced?

**Given:** Data on airplane landing

$$M = 9500 \cdot \text{kg} \quad V_i = 350 \cdot \frac{\text{km}}{\text{hr}} \quad V_f = 100 \cdot \frac{\text{km}}{\text{hr}} \quad x_f = 1200 \cdot \text{m} \quad C_D = 1.43 \text{ (Table 9.3)} \quad \rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$$

**Find:** Single and three-parachute sizes; plot speed against distance and time; maximum "g"s

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

**Assumptions:** (1) Standard air  
(2) Parachute behaves as open hemisphere  
(3) Vertical speed is constant

Newton's second law for the aircraft is  $M \cdot \frac{dV}{dt} = -C_D \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2$

where  $A$  and  $C_D$  are the single parachute area and drag coefficient

Separating variables  $\frac{dV}{V^2} = -\frac{C_D \cdot \rho \cdot A}{2 \cdot M} \cdot dt$

Integrating, with IC  $V = V_i$   $V(t) = \frac{V_i}{1 + \frac{C_D \cdot \rho \cdot A}{2 \cdot M} \cdot V_i \cdot t}$  (1)

Integrating again with respect to  $t$   $x(t) = \frac{2 \cdot M}{C_D \cdot \rho \cdot A} \cdot \ln \left( 1 + \frac{C_D \cdot \rho \cdot A}{2 \cdot M} \cdot V_i \cdot t \right)$  (2)

Eliminating  $t$  from Eqs. 1 and 2  $x = \frac{2 \cdot M}{C_D \cdot \rho \cdot A} \cdot \ln \left( \frac{V_i}{V} \right)$  (3)

To find the minimum parachute area we must solve Eq 3 for  $A$  with  $x = x_f$  when  $V = V_f$

$$A = \frac{2 \cdot M}{C_D \cdot \rho \cdot x_f} \cdot \ln \left( \frac{V_i}{V_f} \right)$$
 (4)

For three parachutes, the analysis is the same except  $A$  is replaced with  $3A$ , leading to

$$A = \frac{2 \cdot M}{3 \cdot C_D \cdot \rho \cdot x_f} \cdot \ln \left( \frac{V_i}{V_f} \right)$$
 (5)

The "g"s are given by  $\frac{dV}{dt} = \frac{-C_D \cdot \rho \cdot A \cdot V^2}{2 \cdot M \cdot g}$  which has a maximum at the initial instant ( $V = V_i$ )



The results generated in *Excel* are shown below:

Single:  $A = 11.4 \text{ m}^2$   
 $D = 3.80 \text{ m}$

Triple:  $A = 3.8 \text{ m}^2$   
 $D = 2.20 \text{ m}$

"g"s = -1.01 Max

$t$ (s)	$x$ (m)	$V$ (km/hr)
0.00	0.0	350
2.50	216.6	279
5.00	393.2	232
7.50	542.2	199
10.0	671.1	174
12.5	784.7	154
15.0	886.3	139
17.5	978.1	126
20.0	1061.9	116
22.5	1138.9	107
24.6	1200.0	100



## Problem 9.96

[Difficulty: 3]

**9.96** An emergency braking parachute system on a military aircraft consists of a large parachute of diameter 6 m. If the airplane mass is 8500 kg, and it lands at 400 km/hr, find the time and distance at which the airplane is slowed to 100 km/hr by the parachute alone. Plot the aircraft speed versus distance and versus time. What is the maximum "g-force" experienced? An engineer proposes that less space would be taken up by replacing the large parachute with three non-interfering parachutes each of diameter 3.75 m. What effect would this have on the time and distance to slow to 100 km/hr?

**Given:** Data on airplane and parachute

**Find:** Time and distance to slow down; plot speed against distance and time; maximum "g"s

**Solution:**

The given data or available data is

$$M = 8500 \cdot \text{kg} \quad V_i = 400 \cdot \frac{\text{km}}{\text{hr}} \quad V_f = 100 \cdot \frac{\text{km}}{\text{hr}} \quad C_D = 1.42 \quad \rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3} \quad D_{\text{single}} = 6 \cdot \text{m} \quad D_{\text{triple}} = 3.75 \cdot \text{m}$$

$$A_{\text{single}} = \frac{\pi}{4} \cdot D_{\text{single}}^2 = 28.274 \text{ m}^2 \quad A_{\text{triple}} = \frac{\pi}{4} \cdot D_{\text{triple}}^2 = 11.045 \text{ m}^2$$

Newton's second law for the aircraft is 
$$M \cdot \frac{dV}{dt} = -C_D \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2$$

where  $A$  and  $C_D$  are the single parachute area and drag coefficient

Separating variables 
$$\frac{dV}{V^2} = -\frac{C_D \cdot \rho \cdot A}{2 \cdot M} \cdot dt$$

Integrating, with IC  $V = V_i$  
$$V(t) = \frac{V_i}{1 + \frac{C_D \cdot \rho \cdot A}{2 \cdot M} \cdot V_i \cdot t} \quad (1)$$

Integrating again with respect to  $t$  
$$x(t) = \frac{2 \cdot M}{C_D \cdot \rho \cdot A} \cdot \ln \left( 1 + \frac{C_D \cdot \rho \cdot A}{2 \cdot M} \cdot V_i \cdot t \right) \quad (2)$$

Eliminating  $t$  from Eqs. 1 and 2 
$$x = \frac{2 \cdot M}{C_D \cdot \rho \cdot A} \cdot \ln \left( \frac{V_i}{V} \right) \quad (3)$$

To find the time and distance to slow down to 100 km/hr, Eqs. 1 and 3 are solved with  $V = 100$  km/hr (or use *Goal Seek*)

The "g"s are given by 
$$\frac{dV}{dt} = \frac{-C_D \cdot \rho \cdot A \cdot V^2}{2 \cdot M \cdot g} \quad \text{which has a maximum at the initial instant } (V = V_i)$$

For three parachutes, the analysis is the same except  $A$  is replaced with  $3A$ . leading to

$$V(t) = \frac{V_i}{1 + \frac{3 \cdot C_D \cdot \rho \cdot A}{2 \cdot M} \cdot V_i \cdot t}$$



$$x(t) = \frac{2 \cdot M}{3 \cdot C_D \cdot \rho \cdot A} \cdot \ln \left( 1 + \frac{3 \cdot C_D \cdot \rho \cdot A}{2 \cdot M} \cdot V_i \cdot t \right)$$

The results generated in *Excel* are shown here:

$t$ (s)	$x$ (m)	$V$ (km/hr)
0.0	0.0	400
1.0	96.3	302
2.0	171	243
3.0	233	203
4.0	285	175
5.0	331	153
6.0	371	136
7.0	407	123
8.0	439	112
9.0	469	102
9.29	477	100

$t$ (s)	$x$ (m)	$V$ (km/hr)
0.0	0.0	400
1.0	94.2	290
2.0	165	228
3.0	223	187
4.0	271	159
5.0	312	138
6.0	348	122
7.0	380	110
7.93	407	100
9.0	436	91
9.3	443	89


"g"s = -3.66 Max



## Problem 9.97

[Difficulty: 2]

**9.97** It has been proposed to use surplus 55 gal oil drums to make simple windmills for underdeveloped countries. (It is a simple Savonius turbine.) Two possible configurations are shown. Estimate which would be better, why, and by how much. The diameter and length of a 55 gal drum are  $D = 24$  in. and  $H = 29$  in.



**Given:** Windmills are to be made from surplus 55 gallon oil drums

$$D = 24 \cdot \text{in} \quad H = 29 \cdot \text{in}$$

**Find:** Which configuration would be better, why, and by how much

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

**Assumptions:** (1) Standard air  
 (2) Neglect friction in the pivot  
 (3) Neglect interference between the flow over the two halves

For the first configuration:

$$\Sigma M = \frac{D}{2} \cdot F_u - \frac{D}{2} \cdot F_d = \frac{D}{2} \cdot (F_u - F_d) \quad \text{Where } F_u \text{ is the force on the half "catching" the wind and } F_d \text{ is the force on the half "spilling" the wind.}$$

$$\Sigma M = \frac{D}{2} \cdot \left( C_{Du} \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A - C_{Dd} \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \right) = \frac{D}{2} \cdot (C_{Du} - C_{Dd}) \cdot \left( \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \right)$$

For the second configuration:

$$\Sigma M = \frac{H}{2} \cdot F_u - \frac{H}{2} \cdot F_d = \frac{H}{2} \cdot (F_u - F_d)$$

$$\Sigma M = \frac{H}{2} \cdot \left( C_{Du} \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A - C_{Dd} \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \right) = \frac{H}{2} \cdot (C_{Du} - C_{Dd}) \cdot \left( \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \right)$$


Since  $H > D$ , the second configuration will be superior.

The improvement will be:  $\frac{H - D}{D} = 20.8\%$

## Problem 9.98

[Difficulty: 2]

**9.98** The resistance to motion of a good bicycle on smooth pavement is nearly all due to aerodynamic drag. Assume that the total weight of rider and bike is  $W = 210$  lbf. The frontal area measured from a photograph is  $A = 5$  ft<sup>2</sup>. Experiments on a hill, where the road grade is 9 percent, show that terminal speed is  $V_t = 50$  ft/s. From these data, the drag coefficient is estimated as  $C_D = 1.25$ . Verify this calculation of drag coefficient. Estimate the distance needed for the bike and rider to decelerate from 50 ft/s to 30 ft/s while coasting after reaching level road.



**Given:** Bike and rider at terminal speed on hill with 8% grade.

$$W = 210 \cdot \text{lbf} \quad A = 5 \cdot \text{ft}^2 \quad V_t = 50 \cdot \frac{\text{ft}}{\text{s}} \quad C_D = 1.25$$

**Find:** (a) Verify drag coefficient  
(b) Estimate distance needed for bike and rider to decelerate to 10 m/s after reaching level road

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

**Assumptions:** (1) Standard air  
(2) Neglect all losses other than aerodynamic drag

The angle of incline is:  $\theta = \text{atan}(9\%) = 5.143 \cdot \text{deg}$  Summing forces in the x-direction:  $\Sigma F_x = F_G - F_D = 0$

Expanding out both force terms:  $M \cdot g \cdot \sin(\theta) = C_D \cdot \frac{1}{2} \cdot \rho \cdot V_t^2 \cdot A$  Solving this expression for the drag coefficient:

$$C_D = \frac{2 \cdot W \cdot \sin(\theta)}{\rho \cdot V_t^2 \cdot A} \quad C_D = 1.26$$

The original estimate for the drag coefficient was good.

Once on the flat surface:  $\Sigma F_x = -F_D = \frac{W}{g} \cdot \left(\frac{d}{dt} V\right) = \frac{W}{g} \cdot V \cdot \left(\frac{d}{ds} V\right)$  Therefore:  $\frac{W}{g} \cdot V \cdot \left(\frac{d}{ds} V\right) = -C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$

Separating variables:  $ds = -\frac{2 \cdot W}{C_D \cdot \rho \cdot g \cdot A} \cdot \frac{dV}{V}$  Integrating both sides yields:  $\Delta s = -\frac{2 \cdot W}{C_D \cdot \rho \cdot g \cdot A} \cdot \ln\left(\frac{V_2}{V_1}\right)$   $\Delta s = 447 \cdot \text{ft}$

## Problem 9.99

[Difficulty: 2]

**9.99** A cyclist is able to attain a maximum speed of 30 km/hr on a calm day. The total mass of rider and bike is 65 kg. The rolling resistance of the tires is  $F_R = 7.5$  N, and the drag coefficient and frontal area are  $C_D = 1.2$  and  $A = 0.25$  m<sup>2</sup>. The cyclist bets that today, even though there is a headwind of 10 km/hr, she can maintain a speed of 24 km/hr. She also bets that, cycling with wind support, she can attain a top speed of 40 km/hr. Which, if any, bets does she win?

**Given:** Data on cyclist performance on a calm day

**Find:** Performance hindered and aided by wind

**Solution:**

The given data or available data is

$$\begin{array}{lll}
 F_R = 7.5 \cdot \text{N} & M = 65 \cdot \text{kg} & A = 0.25 \cdot \text{m}^2 \\
 C_D = 1.2 & \rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3} & V = 30 \cdot \frac{\text{km}}{\text{hr}}
 \end{array}$$

The governing equation is  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$   $F_D = 12.8$  N

The power steady power generated by the cyclist is

$$P = (F_D + F_R) \cdot V \quad P = 169 \text{ W} \quad P = 0.227 \cdot \text{hp}$$

Now, with a headwind we have  $V_w = 10 \cdot \frac{\text{km}}{\text{hr}}$   $V = 24 \cdot \frac{\text{km}}{\text{hr}}$

The aerodynamic drag is greater because of the greater effective wind speed

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot (V + V_w)^2 \cdot C_D \quad F_D = 16.5 \text{ N}$$

The power required is that needed to overcome the total force  $F_D + F_R$ , moving at the cyclist's speed

$$P = V \cdot (F_D + F_R) \quad P = 160 \text{ W}$$

This is less than the power she can generate She wins the bet!

With the wind supporting her the effective wind speed is substantially lower

$$V_w = 10 \cdot \frac{\text{km}}{\text{hr}} \quad V = 40 \cdot \frac{\text{km}}{\text{hr}}$$

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot (V - V_w)^2 \cdot C_D \quad F_D = 12.8 \text{ N}$$

The power required is that needed to overcome the total force  $F_D + F_R$ , moving at the cyclist's speed

$$P = V \cdot (F_D + F_R) \quad P = 226 \text{ W}$$

This is more than the power she can generate She loses the bet

## Problem 9.100

[Difficulty: 2]

**9.100** Ballistic data obtained on a firing range show that aerodynamic drag reduces the speed of a .44 magnum revolver bullet from 250 m/s to 210 m/s as it travels over a horizontal distance of 150 m. The diameter and mass of the bullet are 11.2 mm and 15.6 g, respectively. Evaluate the average drag coefficient for the bullet.

**Given:** Ballistic data for .44 magnum revolver bullet

$$V_i = 250 \cdot \frac{\text{m}}{\text{s}} \quad V_f = 210 \cdot \frac{\text{m}}{\text{s}} \quad \Delta x = 150 \cdot \text{m} \quad M = 15.6 \cdot \text{gm} \quad D = 11.2 \cdot \text{mm}$$

**Find:** Average drag coefficient

**Solution:**

**Basic equations:**  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$  (Drag)

**Assumptions:** (1) Standard air  
(2) Neglect all losses other than aerodynamic drag

Newton's 2nd law:  $\Sigma F_x = -F_D = M \cdot \left( \frac{d}{dt} V \right) = M \cdot V \cdot \left( \frac{d}{ds} V \right)$  Therefore:  $M \cdot V \cdot \left( \frac{d}{dx} V \right) = -C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$

Separating variables:  $dx = -\frac{2 \cdot M}{C_D \cdot \rho \cdot A} \cdot \frac{dV}{V}$  Integrating both sides yields:  $\Delta x = -\frac{2 \cdot M}{C_D \cdot \rho \cdot A} \cdot \ln \left( \frac{V_f}{V_i} \right)$

Solving this expression for the drag coefficient:  $C_D = -\frac{2 \cdot M}{\Delta x \cdot \rho \cdot A} \cdot \ln \left( \frac{V_f}{V_i} \right)$  The area is:  $A = \frac{\pi}{4} \cdot D^2 = 98.52 \cdot \text{mm}^2$

Therefore the drag coefficient is:  $C_D = 0.299$

## Problem 9.101

[Difficulty: 3]

**9.101** Consider the cyclist in Problem 9.99. She is having a bad day, because she has to climb a hill with a  $5^\circ$  slope. What is the speed she is able to attain? What is the maximum speed if there is also a headwind of 10 km/hr? She reaches the top of the hill, and turns around and heads down the hill. If she still pedals as hard as possible, what will be her top speed (when it is calm, and when the wind is present)? What will be her maximum speed if she decides to coast down the hill (with and without the aid of the wind)?

**Given:** Data on cyclist performance on a calm day

**Find:** Performance on a hill with and without wind

**Solution:**

The given data or available data is

$$F_R = 7.5 \cdot \text{N}$$

$$M = 65 \cdot \text{kg}$$

$$A = 0.25 \cdot \text{m}^2$$

$$C_D = 1.2$$

$$\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$$

$$V = 30 \cdot \frac{\text{km}}{\text{hr}}$$

The governing equation is

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$$

$$F_D = 12.8 \text{ N}$$

Power steady power generated by the cyclist is

$$P = (F_D + F_R) \cdot V$$

$$P = 169 \text{ W}$$

$$P = 0.227 \cdot \text{hp}$$

Riding up the hill (no wind)

$$\theta = 5 \cdot \text{deg}$$

For steady speed the cyclist's power is consumed by working against the net force (rolling resistance, drag, and gravity)

Cycling up the hill:

$$P = \left( F_R + \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D + M \cdot g \cdot \sin(\theta) \right) \cdot V$$

This is a cubic equation for the speed which can be solved analytically, or by iteration, or using *Excel's Goal Seek* or *Solver*. The solution is obtained from the associated *Excel* workbook

From *Solver*

$$V = 9.47 \cdot \frac{\text{km}}{\text{hr}}$$

Now, with a headwind we have

$$V_w = 10 \cdot \frac{\text{km}}{\text{hr}}$$

The aerodynamic drag is greater because of the greater effective wind speed

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot (V + V_w)^2 \cdot C_D$$

The power required is that needed to overcome the total force (rolling resistance, drag, and gravity) moving at the cyclist's speed is

Uphill against the wind:

$$P = \left[ F_R + \frac{1}{2} \cdot \rho \cdot A \cdot (V + V_w)^2 \cdot C_D + M \cdot g \cdot \sin(\theta) \right] \cdot V$$

This is again a cubic equation for  $V$

From *Solver*

$$V = 8.94 \cdot \frac{\text{km}}{\text{hr}}$$

Peddalling downhill (no wind) gravity helps increase the speed; the maximum speed is obtained from

$$\text{Cycling down the hill: } P = \left( F_R + \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D - M \cdot g \cdot \sin(\theta) \right) \cdot V$$

This cubic equation for  $V$  is solved in the associated *Excel* workbook

$$\text{From Solver } V = 63.6 \cdot \frac{\text{km}}{\text{hr}}$$

Peddalling downhill (wind assisted) gravity helps increase the speed; the maximum speed is obtained from

$$\text{Wind-assisted downhill: } P = \left[ F_R + \frac{1}{2} \cdot \rho \cdot A \cdot (V - V_w)^2 \cdot C_D - M \cdot g \cdot \sin(\theta) \right] \cdot V$$

This cubic equation for  $V$  is solved in the associated *Excel* workbook

$$\text{From Solver } V = 73.0 \cdot \frac{\text{km}}{\text{hr}}$$

Freewheeling downhill, the maximum speed is obtained from the fact that the net force is zero

$$\text{Freewheeling downhill: } F_R + \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D - M \cdot g \cdot \sin(\theta) = 0$$

$$V = \sqrt{\frac{M \cdot g \cdot \sin(\theta) - F_R}{\frac{1}{2} \cdot \rho \cdot A \cdot C_D}} \quad V = 58.1 \cdot \frac{\text{km}}{\text{hr}}$$

$$\text{Wind assisted: } F_R + \frac{1}{2} \cdot \rho \cdot A \cdot (V - V_w)^2 \cdot C_D - M \cdot g \cdot \sin(\theta) = 0$$

$$V = V_w + \sqrt{\frac{M \cdot g \cdot \sin(\theta) - F_R}{\frac{1}{2} \cdot \rho \cdot A \cdot C_D}} \quad V = 68.1 \cdot \frac{\text{km}}{\text{hr}}$$

## Problem 9.102

[Difficulty: 3]

**9.102** Consider the cyclist in Problem 9.99. Determine the maximum speeds she is actually able to attain today (with the 10 km/hr wind) cycling into the wind, and cycling with the wind. If she were to replace the tires with high-tech ones that had a rolling resistance of only 3.5 N, determine her maximum speed on a calm day, cycling into the wind, and cycling with the wind. If she in addition attaches an aerodynamic fairing that reduces the drag coefficient to  $C_D = 0.9$ , what will be her new maximum speeds?

**Given:** Data on cyclist performance on a calm day

**Find:** Performance hindered and aided by wind; repeat with high-tech tires; with fairing

**Solution:**

The given data or available data is

$$\begin{array}{lll} F_R = 7.5 \cdot \text{N} & M = 65 \cdot \text{kg} & A = 0.25 \cdot \text{m}^2 \\ C_D = 1.2 & \rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3} & V = 30 \cdot \frac{\text{km}}{\text{hr}} \end{array}$$

The governing equation is  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$   $F_D = 12.8 \text{ N}$

Power steady power generated by the cyclist is  $P = (F_D + F_R) \cdot V$   $P = 169 \text{ W}$   $P = 0.227 \cdot \text{hp}$

Now, with a headwind we have  $V_w = 10 \cdot \frac{\text{km}}{\text{hr}}$

The aerodynamic drag is greater because of the greater effective wind speed

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot (V + V_w)^2 \cdot C_D \quad (1)$$

The power required is that needed to overcome the total force  $F_D + F_R$ , moving at the cyclist's speed is

$$P = V \cdot (F_D + F_R) \quad (2)$$

Combining Eqs 1 and 2 we obtain an expression for the cyclist's maximum speed  $V$  cycling into a headwind (where  $P = 169 \text{ W}$  is the cyclist's power)

$$\text{Cycling into the wind: } P = \left[ F_R + \frac{1}{2} \cdot \rho \cdot A \cdot (V + V_w)^2 \cdot C_D \right] \cdot V \quad (3)$$

This is a cubic equation for  $V$ ; it can be solved analytically, or by iterating. It is convenient to use *Excel's Goal Seek* (or *Solver*). From the associated *Excel* workbook

From *Solver*  $V = 24.7 \cdot \frac{\text{km}}{\text{hr}}$

By a similar reasoning:

$$\text{Cycling with the wind: } P = \left[ F_R + \frac{1}{2} \cdot \rho \cdot A \cdot (V - V_w)^2 \cdot C_D \right] \cdot V \quad (4)$$

From *Solver*  $V = 35.8 \cdot \frac{\text{km}}{\text{hr}}$

With improved tires  $F_R = 3.5 \cdot N$

Maximum speed on a calm day is obtained from  $P = \left( F_R + \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D \right) \cdot V$

This is again a cubic equation for  $V$ ; it can be solved analytically, or by iterating. It is convenient to use *Excel's Goal Seek* (or *Solver*). From the associated *Excel* workbook

From *Solver*  $V = 32.6 \cdot \frac{\text{km}}{\text{hr}}$

Equations 3 and 4 are repeated for the case of improved tires

From <i>Solver</i>	Against the wind	$V = 26.8 \cdot \frac{\text{km}}{\text{hr}}$	With the wind	$V = 39.1 \cdot \frac{\text{km}}{\text{hr}}$
--------------------	------------------	--	---------------	--


For improved tires and fairing, from *Solver*

$V = 35.7 \cdot \frac{\text{km}}{\text{hr}}$	Against the wind	$V = 29.8 \cdot \frac{\text{km}}{\text{hr}}$	With the wind	$V = 42.1 \cdot \frac{\text{km}}{\text{hr}}$
--	------------------	--	---------------	--

## Problem 9.103

[Difficulty: 3]

**9.103** At a surprise party for a friend you've tied a series of 20-cm-diameter helium balloons to a flagpole, each tied with a short string. The first one is tied 1 m above the ground, and the other eight are tied at 1 m spacings, so that the last is tied at a height of 9 m. Being quite a nerdy engineer, you notice that in the steady wind, each balloon is blown by the wind so it looks like the angles that the strings make with the vertical are about 10°, 20°, 30°, 35°, 40°, 45°, 50°, 60°, and 65°. Estimate and plot the wind velocity profile for the 9-m range. Assume the helium is at 20°C and 10 kPa gage and that each balloon is made of 3 g of latex.



**Given:** Series of party balloons

**Find:** Wind velocity profile; Plot

**Solution:**

Basic equations:  $C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$        $F_B = \rho_{\text{air}} \cdot g \cdot \text{Vol}$        $\Sigma \vec{F} = 0$       This problem is ideal for computing and plotting in *Excel*, but we will go through the details here.

The above figure applies to each balloon

For the horizontal forces  $F_D - T \cdot \sin(\theta) = 0$  (1)

For the vertical forces  $-T \cdot \cos(\theta) + F_{B\text{net}} - W_{\text{latex}} = 0$  (2)

Here  $F_{B\text{net}} = F_B - W = (\rho_{\text{air}} - \rho_{\text{He}}) \cdot g \cdot \frac{\pi \cdot D^3}{6}$

$D = 20\text{-cm}$        $M_{\text{latex}} = 3\text{-gm}$        $W_{\text{latex}} = M_{\text{latex}} \cdot g$        $W_{\text{latex}} = 0.02942 \cdot \text{N}$

We have (Table A.6)  $R_{\text{He}} = 2077 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}}$        $p_{\text{He}} = 111 \cdot \text{kPa}$        $T_{\text{He}} = 293 \cdot \text{K}$        $\rho_{\text{He}} = \frac{p_{\text{He}}}{R_{\text{He}} \cdot T_{\text{He}}}$        $\rho_{\text{He}} = 0.1824 \cdot \frac{\text{kg}}{\text{m}^3}$

$R_{\text{air}} = 287 \cdot \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}}$        $p_{\text{air}} = 101 \cdot \text{kPa}$        $T_{\text{air}} = 293 \cdot \text{K}$        $\rho_{\text{air}} = \frac{p_{\text{air}}}{R_{\text{air}} \cdot T_{\text{air}}}$        $\rho_{\text{air}} = 1.201 \cdot \frac{\text{kg}}{\text{m}^3}$

$F_{B\text{net}} = (\rho_{\text{air}} - \rho_{\text{He}}) \cdot g \cdot \frac{\pi \cdot D^3}{6}$        $F_{B\text{net}} = 0.0418 \cdot \text{N}$

Applying Eqs 1 and 2 to the top balloon, for which  $\theta = 65 \cdot \text{deg}$

$F_D = T \cdot \sin(\theta) = \frac{F_{B\text{net}} - W_{\text{latex}}}{\cos(\theta)} \cdot \sin(\theta)$

Hence  $F_D = (F_{B\text{net}} - W_{\text{latex}}) \cdot \tan(\theta)$        $F_D = 0.0266 \text{ N}$

But we have  $F_D = C_D \cdot \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2 \cdot A = C_D \cdot \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2 \cdot \frac{\pi \cdot D^2}{4}$  with  $C_D = 0.4$  from Fig. 9.11 (we will check Re later)

$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{\text{air}} \cdot \pi \cdot D^2}}$        $V = 1.88 \cdot \frac{\text{m}}{\text{s}}$


From Table A.9  $\nu = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$  The Reynolds number is  $Re_d = \frac{V \cdot D}{\nu}$        $Re_d = 2.51 \times 10^4$  We are okay!

For the next balloon	$\theta = 60\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.0215 \cdot N$	with	$C_D = 0.4$
	$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{air} \cdot \pi \cdot D^2}}$	$V = 1.69 \frac{m}{s}$			
The Reynolds number is	$Re_d = \frac{V \cdot D}{\nu}$	$Re_d = 2.25 \times 10^4$	We are okay!		
For the next balloon	$\theta = 50\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.01481 N$	with	$C_D = 0.4$
	$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{air} \cdot \pi \cdot D^2}}$	$V = 1.40 \frac{m}{s}$			
The Reynolds number is	$Re_d = \frac{V \cdot D}{\nu}$	$Re_d = 1.87 \times 10^4$	We are okay!		
For the next balloon	$\theta = 45\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.01243 N$	with	$C_D = 0.4$
	$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{air} \cdot \pi \cdot D^2}}$	$V = 1.28 \frac{m}{s}$			
The Reynolds number is	$Re_d = \frac{V \cdot D}{\nu}$	$Re_d = 1.71 \times 10^4$	We are okay!		
For the next balloon	$\theta = 40\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.01043 N$	with	$C_D = 0.4$
	$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{air} \cdot \pi \cdot D^2}}$	$V = 1.18 \frac{m}{s}$			
The Reynolds number is	$Re_d = \frac{V \cdot D}{\nu}$	$Re_d = 1.57 \times 10^4$	We are okay!		
For the next balloon	$\theta = 35\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.00870 N$	with	$C_D = 0.4$
	$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{air} \cdot \pi \cdot D^2}}$	$V = 1.07 \frac{m}{s}$			
The Reynolds number is	$Re_d = \frac{V \cdot D}{\nu}$	$Re_d = 1.43 \times 10^4$	We are okay!		
For the next balloon	$\theta = 30\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.00717 N$	with	$C_D = 0.4$
	$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{air} \cdot \pi \cdot D^2}}$	$V = 0.97 \frac{m}{s}$			
The Reynolds number is	$Re_d = \frac{V \cdot D}{\nu}$	$Re_d = 1.30 \times 10^4$	We are okay!		
For the next balloon	$\theta = 20\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.00452 N$	with	$C_D = 0.4$
	$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{air} \cdot \pi \cdot D^2}}$	$V = 0.77 \frac{m}{s}$			
The Reynolds number is	$Re_d = \frac{V \cdot D}{\nu}$	$Re_d = 1.03 \times 10^4$	We are okay!		
For the next balloon	$\theta = 10\text{-deg}$	$F_D = (F_{Bnet} - W_{latex}) \cdot \tan(\theta)$	$F_D = 0.002191 N$	with	$C_D = 0.4$

$$V = \sqrt{\frac{8 \cdot F_D}{C_D \cdot \rho_{\text{air}} \cdot \pi \cdot D^2}} \quad V = 0.54 \frac{\text{m}}{\text{s}}$$

The Reynolds number is  $Re_d = \frac{V \cdot D}{\nu}$   $Re_d = 7184.21$  We are okay!

In summary we have  $V = (0.54 \ 0.77 \ 0.97 \ 1.07 \ 1.18 \ 1.28 \ 1.40 \ 1.69 \ 1.88) \cdot \frac{\text{m}}{\text{s}}$   
 $h = (1 \ 2 \ 3 \ 4 \ 5 \ 6 \ 7 \ 8 \ 9) \cdot \text{m}$




This does not seem like an unreasonable profile for the lowest portion of an atmospheric boundary layer - over cities or rough terrain the atmospheric boundary layer is typically 300-400 meters, so a near-linear profile over a small fraction of that distance is not out of the question.

## Problem 9.104

[Difficulty: 2]

**9.104** A 0.5-m-diameter hollow plastic sphere containing pollution test equipment is being dragged through the Hudson River in New York by a diver riding an underwater jet device. The sphere (with an effective specific gravity of  $SG = 0.30$ ) is fully submerged, and it is tethered to the diver by a thin 1.5-m-long wire. What is the angle the wire makes with the horizontal if the velocity of the diver and sphere relative to the water is 5 m/s? The water is at  $10^\circ\text{C}$ .



**Given:** Sphere dragged through river

**Find:** Relative velocity of sphere

**Solution:**

Basic equations: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} \quad F_B = \rho \cdot g \cdot \text{Vol} \quad \Sigma \vec{F} = 0$$

The above figure applies to the sphere

For the horizontal forces  $F_D - T \cdot \sin(\theta) = 0 \quad (1)$

For the vertical forces  $-T \cdot \cos(\theta) + F_B - W = 0 \quad (2)$

Here  $V = 5 \cdot \frac{\text{m}}{\text{s}}$   $D = 0.5\text{-m}$   $SG = 0.30$  and from Table A.8  $\nu = 1.30 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$   $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$

The Reynolds number is  $Re_d = \frac{V \cdot D}{\nu} \quad Re_d = 1.92 \times 10^6$  Therefore we estimate the drag coefficient:  $C_D = 0.15$  (Fig 9.11)

$$F_D = T \cdot \sin(\theta) = \frac{F_B - W}{\cos(\theta)} \cdot \sin(\theta) = \rho \cdot g \cdot \text{Vol} \cdot (1 - SG) \cdot \tan(\theta)$$

Hence  $F_D = \rho \cdot g \cdot \frac{\pi \cdot D^3}{6} \cdot (1 - SG) \cdot \tan(\theta)$  But we have  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot \frac{\pi \cdot D^2}{4}$

Therefore  $C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot \frac{\pi \cdot D^2}{4} = \rho \cdot g \cdot \frac{\pi \cdot D^3}{6} \cdot (1 - SG) \cdot \tan(\theta)$


Solving for  $\theta$ : 
$$\tan(\theta) = \frac{3}{4} \cdot \frac{C_D \cdot V^2}{g \cdot D \cdot (1 - SG)}$$

$$\theta = \text{atan} \left[ \frac{3}{4} \cdot \frac{C_D \cdot V^2}{g \cdot D \cdot (1 - SG)} \right] \quad \text{The angle with the horizontal is: } \alpha = 90\text{-deg} - \theta \quad \alpha = 50.7\text{-deg}$$

### Problem 9.105

[Difficulty: 2]

**9.105** A simple but effective anemometer to measure wind speed can be made from a thin plate hinged to deflect in the wind. Consider a thin plate made from brass that is 20 mm high and 10 mm wide. Derive a relationship for wind speed as a function of deflection angle,  $\theta$ . What thickness of brass should be used to give  $\theta = 30^\circ$  at 10 m/s?




Solution: Sum moments about pivot.

$$\Sigma M = F_N \frac{h}{2} - mg \frac{h}{2} \sin \theta = 0$$

$$F_N = C_D A \frac{1}{2} \rho V_n^2 = mg \sin \theta$$

$$C_D A \frac{1}{2} \rho V^2 \cos^2 \theta = mg \sin \theta \quad (1)$$

$$V = \left[ \frac{2mg \sin \theta}{C_D A \rho \cos^2 \theta} \right]^{1/2}$$



From plate geometry,  $m = \rho w h t = SG \rho_{H_2O} w h t$ . From Eq. 1,

$$SG \rho_{H_2O} g w h t \sin \theta = C_D A \frac{1}{2} \rho V^2 \cos^2 \theta \quad \{ \text{From Table A.1, } SG = 8.55 \text{ for brass.} \}$$

$$t = \frac{C_D A \rho V^2 \cos^2 \theta}{2 SG \rho_{H_2O} w h \sin \theta g} = \frac{C_D \rho V^2 \cos^2 \theta}{2 SG \rho_{H_2O} \sin \theta g} \quad \text{since } A = wh$$

From Fig. 9.10,  $C_D = 1.2$  at  $b/h = 2.0$ , so


$$t = \frac{1.2}{8.55} \times \frac{1.23 \text{ kg}}{2 \text{ m}^3} \times \frac{(10)^2 \text{ m}^2}{\text{s}^2} \times \cos^2(30^\circ) \times \frac{\text{m}^3}{999 \text{ kg}} \times \frac{1}{\sin(30^\circ)} \times \frac{1}{9.81 \text{ m}} \times \frac{\text{s}^2}{\text{m}} \times 1000 \frac{\text{mm}}{\text{m}}$$

$$t = 1.30 \text{ mm}$$

## Problem 9.106

[Difficulty: 3]

**9.106** An anemometer to measure wind speed is made from four hemispherical cups of 2-in. diameter, as shown. The center of each cup is placed at  $R = 3$  in. from the pivot. Find the theoretical calibration constant,  $k$ , in the calibration equation  $V = k\omega$ , where  $V$  (mph) is the wind speed and  $\omega$  (rpm) is the rotation speed. In your analysis, base the torque calculations on the drag generated at the instant when two of the cups are orthogonal and the other two cups are parallel, and ignore friction in the bearings. Explain why, in the absence of friction, at any given wind speed, the anemometer runs at constant speed rather than accelerating without limit. If the actual anemometer bearing has (constant) friction such that the anemometer needs a minimum wind speed of 0.5 mph to begin rotating, compare the rotation speeds with and without friction for  $V = 20$  mph.



**Given:** Data on dimensions of anemometer

**Find:** Calibration constant; compare to actual with friction

**Solution:**

The given data or available data is  $D = 2$ -in  $R = 3$ -in  $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$

The drag coefficients for a cup with open end facing the airflow and a cup with open end facing downstream are, respectively, from Table 9.3

$$C_{D\text{open}} = 1.42 \quad C_{D\text{notopen}} = 0.38$$

The equation for computing drag is  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$  (1)

where  $A = \frac{\pi \cdot D^2}{4}$   $A = 0.0218 \cdot \text{ft}^2$

Assuming steady speed  $\omega$  at steady wind speed  $V$  the sum of moments will be zero. The two cups that are momentarily parallel to the flow will exert no moment; the two cups with open end facing and not facing the flow will exert a moment because of their drag forces. For each, the drag is based on Eq. 1 (with the *relative* velocity used!). In addition, friction of the anemometer is neglected

$$\Sigma M = 0 = \left[ \frac{1}{2} \cdot \rho \cdot A \cdot (V - R \cdot \omega)^2 \cdot C_{D\text{open}} \right] \cdot R - \left[ \frac{1}{2} \cdot \rho \cdot A \cdot (V + R \cdot \omega)^2 \cdot C_{D\text{notopen}} \right] \cdot R$$

or  $(V - R \cdot \omega)^2 \cdot C_{D\text{open}} = (V + R \cdot \omega)^2 \cdot C_{D\text{notopen}}$

This indicates that the anemometer reaches a steady speed even in the absence of friction because it is the *relative* velocity on each cup that matters: the cup that has a higher drag coefficient has a lower relative velocity

Rearranging for  $k = \frac{V}{\omega}$   $\left( \frac{V}{\omega} - R \right)^2 \cdot C_{D\text{open}} = \left( \frac{V}{\omega} + R \right)^2 \cdot C_{D\text{notopen}}$

Hence

$$k = \frac{\left(1 + \sqrt{\frac{C_{Dnotopen}}{C_{Dopen}}}\right)}{\left(1 - \sqrt{\frac{C_{Dnotopen}}{C_{Dopen}}}\right)} \cdot R \quad k = 9.43 \cdot \text{in} \quad k = 0.0561 \cdot \frac{\text{mph}}{\text{rpm}}$$

For the actual anemometer (with friction), we first need to determine the torque produced when the anemometer is stationary but about to rotate

Minimum wind for rotation is  $V_{\min} = 0.5 \cdot \text{mph}$

The torque produced at this wind speed is

$$T_f = \left(\frac{1}{2} \cdot \rho \cdot A \cdot V_{\min}^2 \cdot C_{Dopen}\right) \cdot R - \left(\frac{1}{2} \cdot \rho \cdot A \cdot V_{\min}^2 \cdot C_{Dnotopen}\right) \cdot R$$

$$T_f = 3.57 \times 10^{-6} \cdot \text{ft} \cdot \text{lbf}$$

A moment balance at wind speed  $V$ , including this friction, is

$$\Sigma M = 0 = \left[\frac{1}{2} \cdot \rho \cdot A \cdot (V - R \cdot \omega)^2 \cdot C_{Dopen}\right] \cdot R - \left[\frac{1}{2} \cdot \rho \cdot A \cdot (V + R \cdot \omega)^2 \cdot C_{Dnotopen}\right] \cdot R - T_f$$

or

$$(V - R \cdot \omega)^2 \cdot C_{Dopen} - (V + R \cdot \omega)^2 \cdot C_{Dnotopen} = \frac{2 \cdot T_f}{R \cdot \rho \cdot A}$$

This quadratic equation is to be solved for  $\omega$  when  $V = 20 \cdot \text{mph}$

After considerable calculations  $\omega = 356.20 \cdot \text{rpm}$

This must be compared to the rotation for a frictionless model, given by

$$\omega_{\text{frictionless}} = \frac{V}{k} \quad \omega_{\text{frictionless}} = 356.44 \cdot \text{rpm}$$


The error in neglecting friction is

$$\left| \frac{\omega - \omega_{\text{frictionless}}}{\omega} \right| = 0.07\%$$

## Problem 9.107

[Difficulty: 2]

**9.107** A circular disk is hung in an air stream from a pivoted strut as shown. In a wind-tunnel experiment, performed in air at 15 m/s with a 25-mm diameter disk,  $\alpha$  was measured at  $10^\circ$ . For these conditions determine the mass of the disk. Assume the drag coefficient for the disk applies when the component of wind speed normal to the disk is used. Assume drag on the strut and friction in the pivot are negligible. Plot a theoretical curve of  $\alpha$  as a function of air speed.



**Given:** Circular disk in wind

**Find:** Mass of disk; Plot  $\alpha$  versus  $V$

**Solution:**

Basic equations:

$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} \quad \Sigma \vec{M} = 0$$

Summing moments at the pivot  $W \cdot L \cdot \sin(\alpha) - F_n \cdot L = 0$  and  $F_n = \frac{1}{2} \cdot \rho \cdot V_n^2 \cdot A \cdot C_D$


Hence  $M \cdot g \cdot \sin(\alpha) = \frac{1}{2} \cdot \rho \cdot (V \cdot \cos(\alpha))^2 \cdot \frac{\pi \cdot D^2}{4} \cdot C_D$

The data is  $\rho = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$   $V = 15 \cdot \frac{\text{m}}{\text{s}}$   $D = 25 \cdot \text{mm}$   $\alpha = 10 \cdot \text{deg}$   $C_D = 1.17$  (Table 9.3)

$$M = \frac{\pi \cdot \rho \cdot V^2 \cdot \cos^2(\alpha) \cdot D^2 \cdot C_D}{8 \cdot g \cdot \sin(\alpha)} \quad M = 0.0451 \text{ kg}$$

Rearranging  $V = \sqrt{\frac{8 \cdot M \cdot g}{\pi \cdot \rho \cdot D^2 \cdot C_D}} \cdot \sqrt{\frac{\tan(\alpha)}{\cos(\alpha)}}$   $V = 35.5 \cdot \frac{\text{m}}{\text{s}} \cdot \sqrt{\frac{\tan(\alpha)}{\cos(\alpha)}}$

We can plot this by choosing  $\alpha$  and computing  $V$



This graph can be easily plotted in *Excel*


## Problem 9.108

[Difficulty: 2]

**9.108** Experimental data [16] suggest that the maximum and minimum drag area ( $C_D A$ ) for a skydiver varies from about  $9.1 \text{ ft}^2$  for a prone, spread-eagle position to about  $1.2 \text{ ft}^2$  for vertical fall. Estimate the terminal speeds for a 170-lb skydiver in each position. Calculate the time and distance needed for the skydiver to reach 90 percent of terminal speed at an altitude of 9800 ft on a standard day.

**Given:** Mass, maximum and minimum drag areas for a skydiver

**Find:** (a) Terminal speeds for skydiver in each position  
(b) Time and distance needed to reach percentage of terminal speed from given altitude



**Solution:**

Basic equation 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot U^2 \cdot A}$$

The given or available data are:  $W = 170 \cdot \text{lbf}$   $A_{C_{D\text{min}}} = 1.2 \cdot \text{ft}^2$   $A_{C_{D\text{max}}} = 9.1 \cdot \text{ft}^2$   $H = 9800 \cdot \text{ft} = 2987 \text{ m}$

From Table A.3 we can find the density:  $\frac{\rho}{\rho_{\text{SL}}} = 0.7433$   $\rho = 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3} \times 0.7433 = 1.767 \times 10^{-3} \cdot \frac{\text{slug}}{\text{ft}^3}$

To find terminal speed, we take FBD of the skydiver:  $\Sigma F_y = 0$   $M \cdot g - F_D = 0$   $F_D = \frac{1}{2} \cdot \rho \cdot U^2 \cdot A \cdot C_D = M \cdot g = W$

Solving for the speed:  $U_t = \sqrt{\frac{2 \cdot W}{\rho \cdot A \cdot C_D}}$  For the minimum drag area:  $U_{t\text{max}} = \sqrt{\frac{2 \cdot W}{\rho \cdot A_{C_{D\text{min}}}}}$   $U_{t\text{max}} = 400 \cdot \frac{\text{ft}}{\text{s}}$

For the maximum drag area:  $U_{t\text{min}} = \sqrt{\frac{2 \cdot W}{\rho \cdot A_{C_{D\text{max}}}}}$   $U_{t\text{min}} = 145.4 \cdot \frac{\text{ft}}{\text{s}}$

To find the time needed to reach a fraction of the terminal velocity, we re-write the force balance:

$$\Sigma F_y = M \cdot a_y \quad M \cdot g - F_D = M \cdot a_y \quad M \cdot g - \frac{1}{2} \cdot \rho \cdot U^2 \cdot A \cdot C_D = M \cdot \frac{dU}{dt} = M \cdot U \cdot \frac{dU}{dy}$$

In terms of the weight:  $W - \frac{1}{2} \cdot \rho \cdot U^2 \cdot A \cdot C_D = \frac{W}{g} \cdot \frac{dU}{dt} = \frac{W}{g} \cdot U \cdot \frac{dU}{dy}$  To normalize the derivatives by the terminal speed:

$$\frac{W}{g} \cdot \frac{dU}{dt} = \frac{W \cdot U_t}{g} \cdot \frac{d}{dt} \left( \frac{U}{U_t} \right) \quad \text{and} \quad \frac{W}{g} \cdot U \cdot \frac{dU}{dy} = \frac{W \cdot U_t^2}{g} \cdot \left( \frac{U}{U_t} \right) \cdot \frac{d}{dy} \left( \frac{U}{U_t} \right) \quad \text{We may now re-write the above equation as:}$$

$$W - \frac{1}{2} \cdot \rho \cdot \left( \frac{U}{U_t} \right)^2 \cdot A \cdot C_D \cdot \left( \frac{2 \cdot W}{\rho \cdot A \cdot C_D} \right) = \frac{W \cdot U_t}{g} \cdot \frac{d}{dt} \left( \frac{U}{U_t} \right) = \frac{W \cdot U_t^2}{g} \cdot \left( \frac{U}{U_t} \right) \cdot \frac{d}{dy} \left( \frac{U}{U_t} \right) \quad \text{where we have substituted for the terminal speed.}$$

Simplifying this expression:  $1 - \left( \frac{U}{U_t} \right)^2 = \frac{U_t}{g} \cdot \frac{d}{dt} \left( \frac{U}{U_t} \right) = \frac{U_t^2}{g} \cdot \left( \frac{U}{U_t} \right) \cdot \frac{d}{dy} \left( \frac{U}{U_t} \right)$  Now we can integrate with respect to time and distance:

If we let  $U_n = \frac{U}{U_t}$  we can rewrite the equations:

$$1 - U_n^2 = \frac{U_t}{g} \cdot \frac{dU_n}{dt} \quad \text{Separating variables:} \quad \int_0^t \frac{g}{U_t} dt = \int_0^{0.90} \frac{1}{1 - U_n^2} dU_n \quad \text{Integrating we get:} \quad \frac{g \cdot t}{U_t} = \operatorname{atanh}(0.9) - \operatorname{atanh}(0)$$

$$\text{Evaluating the inverse hyperbolic tangents:} \quad t = \frac{1.472 \cdot U_t}{g} \quad \text{so:} \quad t_{\min} = \frac{1.472 \cdot U_{t\min}}{g} = 6.65 \text{ s} \quad t_{\max} = \frac{1.472 \cdot U_{t\max}}{g} = 18.32 \text{ s}$$

$$\text{Now to find the distance:} \quad 1 - U_n^2 = \frac{U_t^2}{g} \cdot U_n \cdot \frac{dU_n}{dy} \quad \text{Separating variables:} \quad \int_0^y \frac{g}{U_t^2} dy = \int_0^{0.9} \frac{U_n}{1 - U_n^2} dU_n$$

$$\text{Integrating we get:} \quad \frac{g \cdot y}{U_t^2} = -\frac{1}{2} \cdot \ln\left(\frac{1 - 0.9^2}{1 - 0}\right) = 0.8304 \quad \text{Solving for the distance:} \quad y = \frac{0.8304 \cdot U_t^2}{g}$$

$$\text{so:} \quad y_{\min} = \frac{0.8304 \cdot U_{t\min}^2}{g} = 166.4 \text{ m} \quad y_{\max} = \frac{0.8304 \cdot U_{t\max}^2}{g} = 1262 \text{ m}$$

## Problem 9.109

[Difficulty: 3]

**9.109** A vehicle is built to try for the land-speed record at the Bonneville Salt Flats, elevation 4400 ft. The engine delivers 500 hp to the rear wheels, and careful streamlining has resulted in a drag coefficient of 0.15, based on a 15 ft<sup>2</sup> frontal area. Compute the theoretical maximum ground speed of the car (a) in still air and (b) with a 20 mph headwind.

Solution: Apply definitions of power, drag coefficient.

Computing equations:  $P = F_D V$ ,  $C_D = \frac{F_D}{\frac{1}{2} \rho (V + V_w)^2 A}$

Assumptions: (1) Neglect rolling drag  
(2)  $\rho \approx 0.878 \rho_0$  (Table A.3)

For no wind case,  $V_w = 0$ , and

$$P = F_D V = C_D \frac{1}{2} \rho V^2 A V = C_D \frac{1}{2} \rho V^3 A$$

$$V = \left[ \frac{2P}{\rho C_D A} \right]^{1/3} = \left[ 2 \times 500 \text{ hp} \times \frac{\text{ft}^2}{(0.878)(0.00238 \text{ slug})} \times \frac{1}{0.15} \times \frac{1}{15 \text{ ft}^2} \times \frac{550 \text{ ft} \cdot \text{lb}}{\text{hp} \cdot \text{s}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb} \cdot \text{s}^2} \right]^{1/3}$$

$$V = 489 \text{ ft/s} \quad (333 \text{ mph})$$


With a head wind,

$$P = F_D V = C_D \frac{1}{2} \rho (V + V_w)^2 A V \quad \text{or} \quad P (\text{hp}) = 4.27 \times 10^{-6} (V + V_w)^2 V (\text{ft}^3/\text{s}^3)$$

This can be solved by iteration. Using  $V_w = 20 \text{ mph}$  or  $29.3 \text{ ft/s}$ ,

V (ft/s)	P (hp)
400	315
470	501
500	599

Plotting:  
Power  
Required  
(hp)



From the plot,  $V \approx 468 \text{ ft/s}$  (319 mph)

{ Note that the maximum speed is not reduced by 20 mph when wind is present, because drag is nonlinear. }

### Problem 9.110

[Difficulty: 3]

**9.110** An F-4 aircraft is slowed after landing by dual parachutes deployed from the rear. Each parachute is 12 ft in diameter. The F-4 weighs 32,000 lbf and lands at 160 knots. Estimate the time and distance required to decelerate the aircraft to 100 knots, assuming that the brakes are not used and the drag of the aircraft is negligible.

Solution: Apply Newton's second law of motion, definition of  $C_D$ .

Basic equations:  $\Sigma F_x = m a_x$

$$C_D = \frac{F_D}{\frac{1}{2} \rho V^2 A}$$



Then

$$\Sigma F_x = -2F_D = -C_D \rho V^2 A = m a_x = \frac{W}{g} \frac{dV}{dt} \quad (1)$$

$$\text{or } \frac{dV}{V^2} = -\frac{C_D \rho g A}{W} dt$$

Integrating,

$$\int_{V_i}^{V_f} \frac{dV}{V^2} = -\left[\frac{1}{V}\right]_{V_i}^{V_f} = \frac{1}{V_i} - \frac{1}{V_f} = \int_0^t -\frac{C_D \rho g A}{W} dt = -\frac{C_D \rho g A}{W} t$$

or

$$t = \frac{W}{C_D \rho g A} \left[ \frac{1}{V_f} - \frac{1}{V_i} \right]$$

Since two chutes (assume hemispheres),

$$A = 2\left(\frac{\pi D^2}{4}\right) = \frac{\pi D^2}{2}$$

From Table 9.3,  $C_D = 1.42$  for hemisphere facing stream. For standard air,  $\rho g = \gamma \approx 0.075 \text{ lbf/ft}^3$ , and

$$t = \frac{32,000 \text{ lbf}}{1.42} \times \frac{1}{0.075 \text{ lbf/ft}^3} \times \frac{2}{\pi} \times \frac{1}{(12)^2 \text{ ft}^2} \left[ \frac{1}{100} - \frac{1}{160} \right] \frac{\text{hr}}{\text{nm}} \times \frac{3600 \text{ s}}{\text{hr}} \times \frac{\text{nm}}{6080 \text{ ft}}$$

or

$$t = 2.95 \text{ s}$$

To find distance, set  $a_x = \frac{dV}{dt} = V \frac{dV}{dx}$ . Then, from Eq. 1,

$$-2C_D \rho V^2 A = \frac{W}{g} V \frac{dV}{dx}$$

$$\text{and } \frac{dV}{V} = -\frac{C_D A \rho g}{W} dx$$

Integrating,

$$\int_{V_i}^{V_f} \frac{dV}{V} = \ln V \Big|_{V_i}^{V_f} = \ln \frac{V_f}{V_i} = -\frac{C_D A \rho g}{W} x \quad \text{or } x = -\frac{W}{C_D A \rho g} \ln \frac{V_f}{V_i}$$

Thus

$$x = -\frac{1}{1.42} \times \frac{32,000 \text{ lbf}}{0.075 \text{ lbf/ft}^3} \times \frac{2}{\pi (12)^2 \text{ ft}^2} \times \frac{1}{0.075 \text{ lbf/ft}^3} \times \ln \left( \frac{100}{160} \right) = 624 \text{ ft}$$

### Problem 9.111

[Difficulty: 3]

**9.111** A tractor-trailer rig has frontal area  $A = 102 \text{ ft}^2$  and drag coefficient  $C_D = 0.9$ . Rolling resistance is 6 lbf per 1000 lbf of vehicle weight. The specific fuel consumption of the diesel engine is 0.34 lbm of fuel per horsepower hour, and drivetrain efficiency is 92 percent. The density of diesel fuel is 6.9 lbm/gal. Estimate the fuel economy of the rig at 55 mph if its gross weight is 72,000 lbf. An air fairing system reduces aerodynamic drag 15 percent. The truck travels 120,000 miles per year. Calculate the fuel saved per year by the roof fairing.

Solution: Tractive force is  $F_T = F_R + F_D$  ← aerodynamic force  
 ↗ rolling resistance force

$$\text{Engine power is } P_e = \frac{P_T}{\eta_d} = \frac{F_T V}{\eta_d}$$

Thus

$$F_R = C_R W = 0.006 \times 72,000 \text{ lbf} = 432 \text{ lbf}$$

$$F_D = C_D A \frac{1}{2} \rho V^2 \quad V = 55 \frac{\text{mi}}{\text{hr}} \times \frac{5280 \text{ ft}}{\text{mi}} \times \frac{\text{hr}}{3600 \text{ s}} = 80.7 \text{ ft/s}$$

$$F_D = 0.9 \times 102 \text{ ft}^2 \times \frac{1}{2} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (80.7)^2 \frac{\text{ft}^2}{\text{s}^2} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} = 711 \text{ lbf}$$

so

$$F_T = F_R + F_D = 432 + 711 = 1140 \text{ lbf}$$

$$P_e = 1140 \text{ lbf} \times 80.7 \frac{\text{ft}}{\text{s}} \times \frac{1}{0.92} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lbf}} = 182 \text{ hp}$$

Finally

$$FE = \frac{\rho V}{P_e \text{ BSFC}} = \frac{6.9 \text{ lbm}}{\text{gal}} \times \frac{55 \text{ mi}}{\text{hr}} \times \frac{1}{182 \text{ hp}} \times \frac{\text{hp} \cdot \text{hr}}{0.34 \text{ lbm}} = 6.13 \text{ mi/gal}$$

FE

With the air deflector,

$$F_D = (1 - 0.15) 711 \text{ lbf} = 604 \text{ lbf}$$

$$F_T = F_R + F_D = 432 + 604 = 1040 \text{ lbf}$$

$$P_e = 1040 \text{ lbf} \times 80.7 \frac{\text{ft}}{\text{s}} \times \frac{1}{0.92} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lbf}} = 166 \text{ hp}$$

$$\text{and } FE = \frac{6.9 \text{ lbm}}{\text{gal}} \times \frac{55 \text{ mi}}{\text{hr}} \times \frac{1}{166 \text{ hp}} \times \frac{\text{hp} \cdot \text{hr}}{0.34 \text{ lbm}} = 6.72 \text{ mi/gal}$$

The fuel saving would be

$$\Delta Q = \left( \frac{1}{FE}_{\text{without}} - \frac{1}{FE}_{\text{with}} \right) \text{ mileage} = \left( \frac{1}{6.13} - \frac{1}{6.72} \right) \frac{\text{gal}}{\text{mi}} \times 120,000 \frac{\text{mi}}{\text{yr}} = 1720 \text{ gal/yr}$$

Q

The percentage saving would be

$$\frac{\Delta Q}{Q} = \frac{\left( \frac{1}{FE}_{\text{without}} - \frac{1}{FE}_{\text{with}} \right)}{\frac{1}{FE}_{\text{without}}} = 0.0878 \text{ or } 8.78 \text{ percent savings}$$

## Problem 9.112

[Difficulty: 3]

**9.112** A bus travels at 80 km/h in standard air. The frontal area of the vehicle is 7.5 m<sup>2</sup>, and the drag coefficient is 0.92. How much power is required to overcome aerodynamic drag? Estimate the maximum speed of the bus if the engine is rated at 465 hp. A young engineer proposes adding fairings on the front and rear of the bus to reduce the drag coefficient. Tests indicate that this would reduce the drag coefficient to 0.86 without changing the frontal area. What would the required power be at 80 km/h and the new top speed? If the fuel cost for the bus is currently \$300/day, how long would the modification take to pay for itself if it costs \$4800 to install?

**Given:** Data on a bus

**Find:** Power to overcome drag; Maximum speed; Recompute with new fairing; Time for fairing to pay for itself

**Solution:**

Basic equation:  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$      $P = F_D \cdot V$

The given data or available data is     $V = 80 \cdot \frac{\text{km}}{\text{hr}}$      $V = 22.2 \cdot \frac{\text{m}}{\text{s}}$      $A = 7.5 \cdot \text{m}^2$      $C_D = 0.92$      $\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$

$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$      $F_D = 2096 \cdot \text{N}$      $P = F_D \cdot V$      $P = 46.57 \cdot \text{kW}$     The power available is     $P_{\text{max}} = 465 \cdot \text{hp} = 346.75 \cdot \text{kW}$

The maximum speed corresponding to this maximum power is obtained from

$$P_{\text{max}} = \left( \frac{1}{2} \cdot \rho \cdot A \cdot V_{\text{max}}^2 \cdot C_D \right) \cdot V_{\text{max}} \quad \text{or} \quad V_{\text{max}} = \left( \frac{P_{\text{max}}}{\frac{1}{2} \cdot \rho \cdot A \cdot C_D} \right)^{\frac{1}{3}}$$

$V_{\text{max}} = 43.4 \cdot \frac{\text{m}}{\text{s}}$      $V_{\text{max}} = 156.2 \cdot \frac{\text{km}}{\text{hr}}$

We repeat these calculations with the new fairing, for which  $C_D = 0.86$

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D \quad F_D = 1959 \cdot \text{N} \quad P_{\text{new}} = F_D \cdot V \quad P_{\text{new}} = 43.53 \cdot \text{kW}$$

The maximum speed is now

$$V_{\text{max}} = \left( \frac{P_{\text{max}}}{\frac{1}{2} \cdot \rho \cdot A \cdot C_D} \right)^{\frac{1}{3}}$$

$V_{\text{max}} = 44.4 \cdot \frac{\text{m}}{\text{s}}$      $V_{\text{max}} = 159.8 \cdot \frac{\text{km}}{\text{hr}}$

The initial cost of the fairing is     $\text{Cost} = 4500 \cdot \text{dollars}$     The fuel cost is     $\text{Cost}_{\text{day}} = 300 \cdot \frac{\text{dollars}}{\text{day}}$

The cost per day is reduced by improvement in the bus performance at 80 km/h     $\text{Gain} = \frac{P_{\text{new}}}{P}$      $\text{Gain} = 93.5\%$

The new cost per day is then     $\text{Cost}_{\text{daynew}} = \text{Gain} \cdot \text{Cost}_{\text{day}}$      $\text{Cost}_{\text{daynew}} = 280 \cdot \frac{\text{dollars}}{\text{day}}$

Hence the savings per day is     $\text{Saving} = \text{Cost}_{\text{day}} - \text{Cost}_{\text{daynew}}$      $\text{Saving} = 19.6 \cdot \frac{\text{dollars}}{\text{day}}$

The initial cost will be paid for in     $\tau = \frac{\text{Cost}}{\text{Saving}}$      $\tau = 7.56 \cdot \text{month}$

## Problem 9.113

[Difficulty: 2]

**9.113** Compare and plot the power (hp) required by a typical large American sedan of the 1970s and a current midsize sedan to overcome aerodynamic drag versus road speed in standard air, for a speed range of 20 mph to 100 mph. Use the following as representative values:

	Weight (lbf)	Drag Coefficient	Frontal Area (ft <sup>2</sup> )
1970s Sedan	4500	0.5	24
Current Sedan	3500	0.3	20

If rolling resistance is 1.5 percent of curb weight, determine for each vehicle the speed at which the aerodynamic force exceeds frictional resistance.

**Given:** Data on 1970's and current sedans

**Find:** Plot of power versus speed; Speeds at which aerodynamic drag exceeds rolling drag

**Solution:**

Basic equation: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$$

The aerodynamic drag is  $F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot V^2 \cdot A$       The rolling resistance is  $F_R = 0.015 \cdot W$

Total resistance  $F_T = F_D + F_R$       The results generated in *Excel* are shown below:

$$\rho = 0.00234 \text{ slug/ft}^3 \quad (\text{Table A.9})$$

Computed results:


<i>V</i> (mph)	1970's Sedan			Current Sedan		
	<i>F<sub>D</sub></i> (lbf)	<i>F<sub>T</sub></i> (lbf)	<i>P</i> (hp)	<i>F<sub>D</sub></i> (lbf)	<i>F<sub>T</sub></i> (lbf)	<i>P</i> (hp)
20	12.1	79.6	4.24	6.04	58.5	3.12
25	18.9	86.4	5.76	9.44	61.9	4.13
30	27.2	94.7	7.57	13.6	66.1	5.29
35	37.0	104	9.75	18.5	71.0	6.63
40	48.3	116	12.4	24.2	76.7	8.18
45	61.2	129	15.4	30.6	83.1	10.0
50	75.5	143	19.1	37.8	90.3	12.0
55	91.4	159	23.3	45.7	98.2	14.4
60	109	176	28.2	54.4	107	17.1
65	128	195	33.8	63.8	116	20.2
70	148	215	40.2	74.0	126	23.6
75	170	237	47.5	84.9	137	27.5
80	193	261	55.6	96.6	149	31.8
85	218	286	64.8	109	162	36.6
90	245	312	74.9	122	175	42.0
95	273	340	86.2	136	189	47.8
100	302	370	98.5	151	204	54.3

<i>V</i> (mph)	<i>F<sub>D</sub></i> (lbf)	<i>F<sub>R</sub></i> (lbf)
<b>47.3</b>	67.5	67.5

<i>V</i> (mph)	<i>F<sub>D</sub></i> (lbf)	<i>F<sub>R</sub></i> (lbf)
<b>59.0</b>	52.5	52.5

The two speeds above were obtained using *Solver*

### Power Consumed by Old and New Sedans



## Problem 9.114

[Difficulty: 4]

**9.114** A 180-hp sports car of frontal area  $1.72 \text{ m}^2$ , with a drag coefficient of 0.31, requires 17 hp to cruise at 100 km/h. At what speed does aerodynamic drag first exceed rolling resistance? (The rolling resistance is 1.2 percent of the car weight, and the car mass is 1250 kg.) Find the drivetrain efficiency. What is the maximum acceleration at 100 km/h? What is the maximum speed? Which redesign will lead to a higher maximum speed: improving the drive train efficiency by 6 percent from its current value, reducing the drag coefficient to 0.29, or reducing the rolling resistance to 0.91 percent of the car weight?

**Given:** Data on a sports car

**Find:** Speed for aerodynamic drag to exceed rolling resistance; maximum speed & acceleration at 100 km/h; Redesign change that has greatest effect

**Solution:**

Basic equation:  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$        $P = F_D \cdot V$

The given data or available data is       $M = 1250 \cdot \text{kg}$        $A = 1.72 \cdot \text{m}^2$        $C_D = 0.31$

$P_{\text{engine}} = 180 \cdot \text{hp} = 134.23 \cdot \text{kW}$        $F_R = 0.012 \times M \cdot g$        $\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$

The rolling resistance is then       $F_R = 147.1 \cdot \text{N}$

To find the speed at which aerodynamic drag first equals rolling resistance, set the two forces equal       $\frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D = F_R$

Hence  $V = \sqrt{\frac{2 \cdot F_R}{\rho \cdot A \cdot C_D}}$        $V = 21.2 \cdot \frac{\text{m}}{\text{s}}$        $V = 76.2 \cdot \frac{\text{km}}{\text{hr}}$

To find the drive train efficiency we use the data at a speed of       $V = 100 \cdot \frac{\text{km}}{\text{hr}}$        $V = 27.8 \cdot \frac{\text{m}}{\text{s}}$        $P_{\text{engine}} = 17 \cdot \text{hp} = 12.677 \cdot \text{kW}$

The aerodynamic drag at this speed is       $F_D = \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D$        $F_D = 253 \cdot \text{N}$

The power consumed by drag and rolling resistance at this speed is       $P_{\text{used}} = (F_D + F_R) \cdot V$        $P_{\text{used}} = 11.1 \cdot \text{kW}$

Hence the drive train efficiency is       $\eta = \frac{P_{\text{used}}}{P_{\text{engine}}}$        $\eta = 87.7\%$

The acceleration is obtained from Newton's second law       $M \cdot a = \Sigma F = T - F_R - F_D$

where  $T$  is the thrust produced by the engine, given by       $T = \frac{P}{V}$

The maximum acceleration at 100 km/h is when full engine power is used.       $P_{\text{engine}} = 180 \cdot \text{hp} = 134.2 \cdot \text{kW}$

Because of drive train inefficiencies the maximum power at the wheels is       $P_{\text{max}} = \eta \cdot P_{\text{engine}}$        $P_{\text{max}} = 118 \cdot \text{kW}$

Hence the maximum thrust is       $T_{\text{max}} = \frac{P_{\text{max}}}{V}$        $T_{\text{max}} = 4237 \cdot \text{N}$

The maximum acceleration is then       $a_{\text{max}} = \frac{T_{\text{max}} - F_D - F_R}{M}$        $a_{\text{max}} = 3.07 \cdot \frac{\text{m}}{\text{s}^2}$

The maximum speed is obtained when the maximum engine power is just balanced by power consumed by drag and rolling resistance

For maximum speed:

$$P_{\max} = \left( \frac{1}{2} \cdot \rho \cdot V_{\max}^2 \cdot A \cdot C_D + F_R \right) \cdot V_{\max}$$

This is a cubic equation that can be solved by iteration or by using *Excel's Goal Seek* or *Solver*  $V_{\max} = 248 \cdot \frac{\text{km}}{\text{hr}}$

We are to evaluate several possible improvements:

For improved drive train  $\eta = \eta + 6\%$   $\eta = 93.7\%$   $P_{\max} = \eta \cdot P_{\text{engine}}$   $P_{\max} = 126 \cdot \text{kW}$

$$P_{\max} = \left( \frac{1}{2} \cdot \rho \cdot V_{\max}^2 \cdot A \cdot C_D + F_R \right) \cdot V_{\max}$$

Solving the cubic (using *Solver*)

$$V_{\max} = 254 \cdot \frac{\text{km}}{\text{hr}}$$

Improved drag coefficient:

$$C_{D\text{new}} = 0.29$$

$$P_{\max} = 118 \cdot \text{kW}$$

$$P_{\max} = \left( \frac{1}{2} \cdot \rho \cdot V_{\max}^2 \cdot A \cdot C_{D\text{new}} + F_R \right) \cdot V_{\max}$$

Solving the cubic (using *Solver*)

$$V_{\max} = 254 \cdot \frac{\text{km}}{\text{hr}} \quad \text{This is the best option!}$$

Reduced rolling resistance:

$$F_{R\text{new}} = 0.91\% \cdot M \cdot g$$

$$F_{R\text{new}} = 111.6 \text{ N}$$

$$P_{\max} = \left( \frac{1}{2} \cdot \rho \cdot V_{\max}^2 \cdot A \cdot C_D + F_{R\text{new}} \right) \cdot V_{\max}$$

Solving the cubic (using *Solver*)

$$V_{\max} = 250 \cdot \frac{\text{km}}{\text{hr}}$$

The improved drag coefficient is the best option.

## Problem 9.115

[Difficulty: 3]

**9.115** Consider a negatively charged spherical particle of radius  $a$  bearing a charge,  $Q_s$ , suspended in a pure dielectric fluid (containing no ions). When subject to a uniform electric field,  $\vec{E}_\infty$ , the particle will translate under the influence of the electric force acting on it. The induced particle motion refers to electrophoresis, which has been widely used to characterize and purify molecules and colloidal particles. The net electrical force on the charged particle will simply be  $\vec{F}_E = Q_s \vec{E}_\infty$ . As soon as the particle starts to move under the influence of this electric force, it encounters an oppositely directed fluid drag force.

- (a) Under the Stokes flow regime and neglecting the gravitational force and the buoyancy force acting on the microparticle, derive an expression to calculate the particle's steady-state translational velocity.
- (b) Based on the above results, explain why electrophoresis can be used to separate biological samples.
- (c) Calculate the translational velocities of two particles of radius  $a = 1 \mu\text{m}$  and  $10 \mu\text{m}$  using  $Q_s = -10^{-12} \text{ C}$ ,  $E_\infty = 1000 \text{ V/m}$ , and  $\mu = 10^{-3} \text{ Pa}\cdot\text{s}$ .

**Given:** zero net force acting on the particle; drag force and electrostatic force

**Find:**


**Solution:**

- (a) Under steady-state, the net force acting on the particle is zero. The forces acting on the particle contain the electrostatic force  $\mathbf{F}_E$  and the drag force  $\mathbf{F}_D$  (Page 418, the first equation right after Fig. 8.11).

$$\mathbf{F}_E + \mathbf{F}_d = 0 \rightarrow Q_s \mathbf{E}_\infty + 6\pi\mu \mathbf{U} a = 0 \quad (1)$$

where  $\mathbf{U}$  is the particle velocity relative to the stationary liquid.

Then one obtains 
$$\mathbf{U} = \frac{Q_s \mathbf{E}_\infty}{6\pi\mu a} \quad (2)$$



- (b) From the solution, we can know that the particle velocity depends on its size. Smaller particles run faster than larger ones, and thus they can be separated.

- (c) Substituting the values of  $a$ ,  $Q_s$ ,  $\mathbf{E}_\infty$ , and  $\mu$  into equation (2), we obtain the velocity for  $a=1 \mu\text{m}$

$$\mathbf{U} = \frac{-10^{-12} \text{ C}}{6\pi \times 10^{-3} \text{ Pa}\cdot\text{s}} \times \frac{1000 \text{ V/m}}{1 \times 10^{-6} \text{ m}} = -0.053 \frac{\text{N}}{\text{Pa}\cdot\text{s}\cdot\text{m}} = -0.053 \text{ m/s}$$


and  $\mathbf{U} = 0.0053 \text{ m/s}$  for  $a = 10 \mu\text{m}$ .

The negatively charged particle moves in the direction opposite to that of the electric field applied.

## Problem 9.116

[Difficulty: 5]

**9.116** Repeat the analysis for the frictionless anemometer of Problem 9.106, except this time base the torque calculations on the more realistic model that the average torque is obtained by integrating, over one revolution, the instantaneous torque generated by each cup (i.e., as the cup's orientation to the wind varies).



**Given:** Data on dimensions of anemometer

**Find:** Calibration constant

**Solution:**

The given data or available data is  $D = 2\text{-in}$   $R = 3\text{-in}$   $\rho = 0.00234 \frac{\text{slug}}{\text{ft}^3}$

The drag coefficients for a cup with open end facing the airflow and a cup with open end facing downstream are, respectively, from Table 9.3

$$C_{Dopen} = 1.42$$


$$C_{Dnotopen} = 0.38$$

Assume the anemometer achieves steady speed  $\omega$  due to steady wind speed  $V$

The goal is to find the calibration constant  $k$ , defined by  $k = \frac{V}{\omega}$

We will analyze each cup separately, with the following assumptions

- 1) Drag is based on the instantaneous normal component of velocity (we ignore possible effects on drag coefficient of velocity component parallel to the cup)
- 2) Each cup is assumed unaffected by the others - as if it were the only object present
- 3) Swirl is neglected
- 4) Effects of struts is neglected




In this more sophisticated analysis we need to compute the instantaneous normal relative velocity. From the sketch, when a cup is at angle  $\theta$ , the normal component of relative velocity is

$$V_n = V \cdot \cos(\theta) - \omega \cdot R \quad (1)$$

The relative velocity is sometimes positive, and sometimes negative. From Eq. 1, this is determined by

$$\theta_c = \arccos\left(\frac{\omega \cdot R}{V}\right) \quad (2)$$

For	$0 < \theta < \theta_c$	$V_n > 0$
	$\theta_c < \theta < 2 \cdot \pi - \theta_c$	$V_n < 0$
	$\theta_c < \theta < 2 \cdot \pi$	$V_n > 0$



The equation for computing drag is

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V_n^2 \cdot C_D \quad (3)$$

where

$$A = \frac{\pi \cdot D^2}{4} \quad A = 3.14 \cdot \text{in}^2$$

In Eq. 3, the drag coefficient, and whether the drag is positive or negative, depend on the sign of the relative velocity

For	$0 < \theta < \theta_c$	$C_D = C_{Dopen}$	$F_D > 0$
	$\theta_c < \theta < 2 \cdot \pi - \theta_c$	$C_D = C_{Dnotopen}$	$F_D < 0$
	$\theta_c < \theta < 2 \cdot \pi$	$C_D = C_{Dopen}$	$F_D > 0$

The torque is

$$T = F_D \cdot R = \frac{1}{2} \cdot \rho \cdot A \cdot V_n^2 \cdot C_D \cdot R$$

The average torque is

$$T_{av} = \frac{1}{2 \cdot \pi} \cdot \int_0^{2 \cdot \pi} T \, d\theta = \frac{1}{\pi} \cdot \int_0^{\pi} T \, d\theta$$

where we have taken advantage of symmetry

Evaluating this, allowing for changes when  $\theta = \theta_c$

$$T_{av} = \frac{1}{\pi} \cdot \int_0^{\theta_c} \frac{1}{2} \cdot \rho \cdot A \cdot V_n^2 \cdot C_{Dopen} \cdot R \, d\theta - \frac{1}{\pi} \cdot \int_{\theta_c}^{\pi} \frac{1}{2} \cdot \rho \cdot A \cdot V_n^2 \cdot C_{Dnotopen} \cdot R \, d\theta$$

Using Eq. 1

$$T_{av} = \frac{\rho \cdot A \cdot R}{2 \cdot \pi} \left[ C_{Dopen} \int_0^{\theta_c} (V \cdot \cos(\theta) - \omega \cdot R)^2 d\theta - C_{Dnotopen} \int_{\theta_c}^{\pi} (V \cdot \cos(\theta) - \omega \cdot R)^2 d\theta \right]$$

$$T_{av} = \frac{\rho \cdot A \cdot R \cdot \omega^2}{2 \cdot \pi} \left[ C_{Dopen} \int_0^{\theta_c} \left( \frac{V}{\omega} \cdot \cos(\theta) - R \right)^2 d\theta - C_{Dnotopen} \int_{\theta_c}^{\pi} \left( \frac{V}{\omega} \cdot \cos(\theta) - R \right)^2 d\theta \right]$$

and note that

$$\frac{V}{\omega} = k$$

The integral is

$$\int (k \cdot \cos(\theta) - R)^2 d\theta = k^2 \cdot \left( \frac{1}{2} \cdot \cos(\theta) \cdot \sin(\theta) + \frac{1}{2} \cdot \theta \right) - 2 \cdot k \cdot R \cdot \sin(\theta) + R^2 \cdot \theta$$

For convenience define

$$f(\theta) = k^2 \cdot \left( \frac{1}{2} \cdot \cos(\theta) \cdot \sin(\theta) + \frac{1}{2} \cdot \theta \right) - 2 \cdot k \cdot R \cdot \sin(\theta) + R^2 \cdot \theta$$

Hence

$$T_{av} = \frac{\rho \cdot A \cdot R}{2 \cdot \pi} \left[ C_{Dopen} \cdot f(\theta_c) - C_{Dnotopen} \cdot (f(\pi) - f(\theta_c)) \right]$$

For steady state conditions the torque (of each cup, and of all the cups) is zero. Hence

$$C_{Dopen} \cdot f(\theta_c) - C_{Dnotopen} \cdot (f(\pi) - f(\theta_c)) = 0$$

or

$$f(\theta_c) = \frac{C_{Dnotopen}}{C_{Dopen} + C_{Dnotopen}} \cdot f(\pi)$$

Hence

$$k^2 \cdot \left( \frac{1}{2} \cdot \cos(\theta_c) \cdot \sin(\theta_c) + \frac{1}{2} \cdot \theta_c \right) - 2 \cdot k \cdot R \cdot \sin(\theta_c) + R^2 \cdot \theta_c = \frac{C_{Dnotopen}}{C_{Dopen} + C_{Dnotopen}} \cdot \left( k^2 \cdot \frac{\pi}{2} + R^2 \cdot \pi \right)$$

Recall from Eq 2 that

$$\theta_c = \arccos\left(\frac{\omega \cdot R}{V}\right) \quad \text{or} \quad \theta_c = \arccos\left(\frac{R}{k}\right)$$

Hence

$$k^2 \cdot \left( \frac{1}{2} \cdot \frac{R}{k} \cdot \sin\left(\arccos\left(\frac{R}{k}\right)\right) + \frac{1}{2} \cdot \arccos\left(\frac{R}{k}\right) \right) - 2 \cdot k \cdot R \cdot \sin\left(\arccos\left(\frac{R}{k}\right)\right) + R^2 \cdot \arccos\left(\frac{R}{k}\right) = \frac{C_{Dnotopen}}{C_{Dopen} + C_{Dnotopen}} \cdot \left( k^2 \cdot \frac{\pi}{2} + R^2 \cdot \pi \right)$$

This equation is to be solved for the coefficient  $k$ . The equation is highly nonlinear; it can be solved by iteration or using *Excel's Goal Seek* or *Solver*

From the associated *Excel* workbook

$$k = 0.990 \cdot \text{ft} \qquad k = 0.0707 \cdot \frac{\text{mph}}{\text{rpm}}$$

The result from Problem 9.106 was  $k = 0.0561 \cdot \frac{\text{mph}}{\text{rpm}}$  This represents a difference of 20.6%. The difference can be attributed

to the fact that we had originally averaged the flow velocity, rather than integrated over a complete revolution.

## Problem 9.117

[Difficulty: 4]

**9.117** A round thin disk of radius  $R$  is oriented perpendicular to a fluid stream. The pressure distributions on the front and back surfaces are measured and presented in the form of pressure coefficients. The data are modeled with the following expressions for the front and back surfaces, respectively:

$$\text{Front Surface} \quad C_p = 1 - \left(\frac{r}{R}\right)^6$$

$$\text{Rear Surface} \quad C_p = -0.42$$

Calculate the drag coefficient for the disk.

Solution: Computing equations are

$$C_p = \frac{p - p_\infty}{\frac{1}{2} \rho V^2} \quad C_D = \frac{F_D}{\frac{1}{2} \rho V^2 A} \quad A = \pi R^2$$

Assumptions: (1) steady, incompressible flow  
(2) Neglect skin friction drag (disk thin, edge area small)

$$\text{Then } C_D = \frac{F_D}{\frac{1}{2} \rho V^2 A} = \frac{\int_A (p_f - p_r) dA}{\frac{1}{2} \rho V^2 \pi R^2} = \frac{\int_0^R (p_f - p_r) 2\pi r dr}{\frac{1}{2} \rho V^2 \pi R^2}$$

$$\text{From def'n of } C_p, \quad p_f = p_\infty + C_{pf} \frac{1}{2} \rho V^2, \quad p_r = p_\infty + C_{pr} \frac{1}{2} \rho V^2$$

$$\text{and} \quad p_f - p_r = (C_{pf} - C_{pr}) \frac{1}{2} \rho V^2$$

Substituting,

$$C_D = \frac{\frac{1}{2} \rho V^2 \int_0^R (C_{pf} - C_{pr}) 2\pi r dr}{\frac{1}{2} \rho V^2 \pi R^2} = \frac{2}{R^2} \int_0^R \left[ 1 - \left(\frac{r}{R}\right)^6 + 0.42 \right] r dr$$

$$= 2 \int_0^1 \left[ 1.42 - \left(\frac{r}{R}\right)^7 \right] \left(\frac{r}{R}\right) d\left(\frac{r}{R}\right) = 2 \left[ \frac{1.42}{2} \left(\frac{r}{R}\right)^2 - \frac{1}{8} \left(\frac{r}{R}\right)^8 \right]_0^1$$

$$= 2 (0.710 - 0.125)$$


$$C_D = 1.17$$

$C_D$

### Problem 9.118

[Difficulty: 4]

**9.118** An object falls in air down a long vertical chute. The speed of the object is constant at 3 m/s. The flow pattern around the object is shown. The static pressure is uniform across sections ① and ②; pressure is atmospheric at section ①. The effective flow area at section ② is 20 percent of the chute area. Frictional effects between sections ① and ② are negligible. Evaluate the flow speed relative to the object at section ②. Calculate the static pressure at section ②. Determine the mass of the object.




Solution: Choose a CV moving with object. Apply continuity, Bernoulli, and y momentum.

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g\phi_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g\phi_2$$

$$F_{Sy} + F_{By} = \frac{\partial}{\partial t} \int_{CV} \rho y dV + \int_{CS} \rho y \vec{V} \cdot d\vec{A}$$



- Assumptions: (1) Steady flow relative to CV (7) No net flow in wake  
 (2) Incompressible flow  
 (3) Neglect friction  
 (4) Flow along a streamline  
 (5) Neglect  $\Delta z$   
 (6) Uniform flow and pressures at ① and ②.

Then from continuity,

$$0 = \{-\rho V_1 A_1\} + \{+\rho V_2 A_2\} \quad \text{so } V_2 = V_1 \frac{A_1}{A_2} = \frac{3 \text{ m}}{\text{s}} \cdot \frac{1}{0.2} = 15 \text{ m/s}$$

From Bernoulli,

$$p_2 = p_1 + \frac{1}{2} \rho V_1^2 - \frac{1}{2} \rho V_2^2 = p_1 + \frac{1}{2} \rho V_1^2 \left[ 1 - \left( \frac{V_2}{V_1} \right)^2 \right]$$

$$p_2(\text{gage}) = \frac{1}{2} \times 1.23 \frac{\text{kg}}{\text{m}^3} \times (3)^2 \frac{\text{m}^2}{\text{s}^2} \left[ 1 - \left( \frac{1}{0.2} \right)^2 \right] \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = -133 \text{ N/m}^2(\text{gage})$$

From momentum

$$p_1 A_1 - p_2 A_2 - Mg = \rho V_1 \{-\rho V_1 A_1\} + \rho V_2 \{+\rho V_2 A_2\} = \rho V_1 A_1 (V_2 - V_1) = \rho V_1^2 A_1 \left( \frac{V_2}{V_1} - 1 \right)$$

$$V_1 = V_1 \quad V_2 = V_2$$

Thus


$$M = \frac{A_1}{g} \left[ -p_1 - p_2 - \rho V_1^2 \left( \frac{V_2}{V_1} - 1 \right) \right]$$

$$M = 0.09 \text{ m}^2 \times \frac{\text{s}^2}{9.81 \text{ m}} \left[ \frac{133 \text{ N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} - \frac{1.23 \text{ kg}}{\text{m}^3} \times \frac{(3)^2 \text{ m}^2}{\text{s}^2} \left( \frac{1}{0.2} - 1 \right) \right] = 0.814 \text{ kg}$$

### Problem 9.119

[Difficulty: 4]

**9.119** An object of mass  $m$ , with cross-sectional area equal to half the size of the chute, falls down a mail chute. The motion is steady. The wake area is  $\frac{3}{4}$  the size of the chute at its maximum area. Use the assumption of constant pressure in the wake. Apply the continuity, Bernoulli, and momentum equations to develop an expression for terminal speed of the object in terms of its mass and other quantities.



Solution: Choose a CV moving with the object.  
Apply continuity, Bernoulli, and y momentum.

Basic equations:

$$0 = \frac{d}{dt} \int_{CV} \rho dV + \int_{CS} \rho \vec{V} \cdot d\vec{A}$$

$$\frac{p_1}{\rho} + \frac{V_1^2}{2} + g \uparrow_1 = \frac{p_2}{\rho} + \frac{V_2^2}{2} + g \uparrow_2$$

$$F_{Sy} + F_{By} = \frac{d}{dt} \int_{CV} \rho v dV + \int_{CS} \rho v \vec{V} \cdot d\vec{A}$$

- Assumptions:
- (1) Steady flow relative to CV
  - (2) Incompressible flow
  - (3) Neglect friction
  - (4) Flow along a streamline
  - (5) Uniform flow and pressures at ① and ②.
  - (6) Neglect  $\Delta z$
  - (7) No net flow in wake

From continuity,

$$0 = \{-\rho V_1 A_1\} + \{\rho V_2 A_2\} \quad \text{so} \quad V_2 = V_1 \frac{A_1}{A_2} = V \frac{A}{A_2}$$

From Bernoulli

$$p_1 - p_2 = \frac{1}{2} \rho V_2^2 - \frac{1}{2} \rho V_1^2 = \frac{1}{2} \rho V^2 \left[ \left( \frac{A}{A_2} \right)^2 - 1 \right] = \frac{1}{2} \rho V^2 \left[ \left( \frac{A}{A_2} \right)^2 - 1 \right]$$

From momentum

$$p_1 A - p_2 A - mg = v_1 \{-\rho V_1 A_1\} + v_2 \{\rho V_2 A_2\} = \rho V A (V_2 - V) = \rho V^2 A \left( \frac{A}{A_2} - 1 \right)$$

$$v_1 = V \quad v_2 = V_2$$

or

$$(p_1 - p_2) A - mg = \rho V^2 A \left( \frac{A}{A_2} - 1 \right)$$

Substituting for  $p_1 - p_2$

$$\frac{1}{2} \rho V^2 A \left[ \left( \frac{A}{A_2} \right)^2 - 1 \right] - mg = \rho V^2 A \left( \frac{A}{A_2} - 1 \right) \quad \text{or} \quad mg = \frac{1}{2} \rho V^2 A \left[ \left( \frac{A}{A_2} \right)^2 - 2 \left( \frac{A}{A_2} \right) + 1 \right]$$

Thus

$$V = \left[ \frac{2mg}{\rho A} \frac{1}{\left( \frac{A}{A_2} \right)^2 - 2 \left( \frac{A}{A_2} \right) + 1} \right]^{1/2}$$

where  $A_2$  is the net flow area at section ②.

## Problem 9.120

[Difficulty: 2]

**9.120** A light plane tows an advertising banner over a football stadium on a Saturday afternoon. The banner is 4 ft tall and 45 ft long. According to Hoerner [16], the drag coefficient based on area ( $Lh$ ) for such a banner is approximated by  $C_D = 0.05 L/h$ , where  $L$  is the banner length and  $h$  is the banner height. Estimate the power required to tow the banner at  $V = 55$  mph. Compare with the drag of a rigid flat plate. Why is the drag larger for the banner?

**Given:** Data on advertising banner

**Find:** Power to tow banner; Compare to flat plate; Explain discrepancy

**Solution:**

Basic equation:  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$      $P = F_D \cdot V$

The given data or available data is	V = 55-mph	V = 80.7 $\frac{\text{ft}}{\text{s}}$	L = 45-ft    h = 4-ft	$\rho = 0.00234 \frac{\text{slug}}{\text{ft}^3}$
	A = L·h	A = 180 ft <sup>2</sup>	$C_D = 0.05 \frac{L}{h}$	$C_D = 0.563$
	$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$	$F_D = 771 \cdot \text{lbf}$	$P = F_D \cdot V$	$P = 6.22 \times 10^4 \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$ P = 113-hp

For a flat plate, check Re     $\nu = 1.62 \times 10^{-4} \frac{\text{ft}^2}{\text{s}}$     (Table A.9, 69°F)

$$Re_L = \frac{V \cdot L}{\nu} \quad Re_L = 2.241 \times 10^7 \quad \text{so flow is fully turbulent. Hence use Eq 9.37b}$$

$$C_D = \frac{0.455}{\log(Re_L)^{2.58}} - \frac{1610}{Re_L} \quad C_D = 0.00258$$

$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D \quad F_D = 3.53 \cdot \text{lbf}$$


This is the drag on one side. The total drag is then  $2 \cdot F_D = 7.06 \cdot \text{lbf}$ . This is VERY much less than the banner drag.

The banner drag allows for banner flutter and other secondary motion which induces significant form drag.

### Problem 9.121

[Difficulty: 5]

**9.121** A large paddle wheel is immersed in the current of a river to generate power. Each paddle has area  $A$  and drag coefficient  $C_D$ ; the center of each paddle is located at radius  $R$  from the centerline of the paddle wheel. Assume the equivalent of one paddle is submerged continuously in the flowing stream. Obtain an expression for the drag force on a single paddle in terms of geometric variables, current speed,  $V$ , and linear speed of the paddle center,  $U = R\omega$ . Develop expressions for the torque and power produced by the paddle wheel. Find the speed at which the paddle wheel should rotate to obtain maximum power output from the wheel in a given current.



Solution: Computing equations  $F_D = C_D A \frac{1}{2} \rho V_{rel}^2$

$$T = F_D R, \quad P = T\omega$$

Assumptions: (1) Neglect air resistance, since  $\rho_{air} \ll \rho_{water}$   
 (2) Use velocity relative to the paddle

Thus  $V_{rel} = V - U = V - R\omega$

$$F_D = C_D A \frac{1}{2} \rho V_{rel}^2 = C_D A \frac{1}{2} \rho (V - U)^2$$

$F_D$

The torque is

$$T = F_D R = C_D A \frac{1}{2} \rho (V - U)^2 R$$

$T$

The power is

$$P = T\omega = C_D A \frac{1}{2} \rho (V - U)^2 R\omega = C_D A \frac{1}{2} \rho (V - U)^2 U$$

$P$

To optimize power, set  $\frac{dP}{dU} = 0$

$$\frac{dP}{dU} = C_D A \frac{1}{2} \rho [2(V - U)U(-1) + (V - U)^2] = 0$$

Cancelling a factor  $(V - U)$  gives  $-2U + V - U = 0$  or  $V - 3U = 0$

Thus  $U = R\omega = \frac{V}{3}$  so

$$\omega_{opt} = \frac{V}{3R}$$

$\omega_{opt}$

## Problem 9.122

[Difficulty: 1]

**9.122** The antenna on a car is 10 mm in diameter and 1.8 m long. Estimate the bending moment that tends to snap it off if the car is driven at 120 km/hr on a standard day.

**Given:** Data on car antenna

**Find:** Bending moment

**Solution:**

Basic equation: 
$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$$

The given or available data is 
$$V = 120 \cdot \frac{\text{km}}{\text{hr}} = 33.333 \frac{\text{m}}{\text{s}} \quad L = 1.8 \cdot \text{m} \quad D = 10 \cdot \text{mm}$$


$$A = L \cdot D \quad A = 0.018 \text{ m}^2$$

$$\rho = 1.225 \cdot \frac{\text{kg}}{\text{m}^3} \quad \nu = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}} \quad (\text{Table A.10, } 20^\circ\text{C})$$

For a cylinder, check Re 
$$\text{Re} = \frac{V \cdot D}{\nu} \quad \text{Re} = 2.22 \times 10^4$$

From Fig. 9.13 
$$C_D = 1.0 \quad F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D \quad F_D = 12.3 \text{ N}$$

The bending moment is then 
$$M = F_D \cdot \frac{L}{2} \quad M = 11.0 \cdot \text{N} \cdot \text{m}$$



## Problem 9.123

[Difficulty: 1]

**9.123** A large three-blade horizontal axis wind turbine (HAWT) can be damaged if the wind speed is too high. To avoid this, the blades of the turbine can be oriented so that they are parallel to the flow. Find the bending moment at the base of each blade when the wind speed is 85 knots. Model each blade as a flat plate 115 ft wide  $\times$  1.5 ft long.

**Given:** Data on wind turbine blade

**Find:** Bending moment

**Solution:**

Basic equation: 
$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$$

The given or available data is 
$$V = 85 \cdot \text{knot} = 143.464 \cdot \frac{\text{ft}}{\text{s}} \quad L = 1.5 \cdot \text{ft} \quad W = 115 \cdot \text{ft}$$

$$A = L \cdot W \quad A = 172.5 \cdot \text{ft}^2$$


$$\rho = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}} \quad (\text{Table A.9, } 70^\circ\text{F})$$

For a flat plate, check Re 
$$\text{Re}_L = \frac{V \cdot L}{\nu} \quad \text{Re}_L = 1.32 \times 10^6 \quad \text{so use Eq. 9.37a}$$

$$C_D = \frac{0.0742}{\frac{1}{\text{Re}_L^5}} - \frac{1740}{\text{Re}_L} \quad C_D = 0.00311$$

$$F_D = 2 \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D \quad F_D = 25.7 \cdot \text{lbf}$$

The bending moment is then 
$$M = F_D \cdot \frac{W}{2} \quad M = 1480 \cdot \text{ft} \cdot \text{lbf}$$



## Problem 9.124

[Difficulty: 4]

**9.124** The HAWT of Problem 9.123 is not self-starting. The generator is used as an electric motor to get the turbine up to the operating speed of 25 rpm. To make this easier, the blades are aligned so that they lie in the plane of rotation. Assuming an overall efficiency of motor and drive train of 60 percent, find the power required to maintain the turbine at the operating speed. As an approximation, model each blade as a series of flat plates (the outer region of each blade moves at a significantly higher speed than the inner region).

**Given:** Data on wind turbine blade

**Find:** Power required to maintain operating speed

**Solution:**

Basic equation: 
$$F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$$

The given or available data is 
$$\omega = 25 \text{ rpm} \qquad L = 1.5 \text{ ft} \qquad W = 115 \text{ ft}$$

$$\rho = 0.00233 \frac{\text{slug}}{\text{ft}^3} \qquad \nu = 1.63 \times 10^{-4} \frac{\text{ft}^2}{\text{s}} \qquad (\text{Table A.9, } 70^\circ\text{F})$$

The velocity is a function of radial position,  $V(r) = r \cdot \omega$ , so  $Re$  varies from 0 to  $Re_{\max} = \frac{V(W) \cdot L}{\nu} \qquad Re_{\max} = 2.77 \times 10^6$

The transition Reynolds number is 500,000 which therefore occurs at about 1/4 of the maximum radial distance; the boundary layer is laminar for the first quarter of the blade. We approximate the entire blade as turbulent - the first 1/4 of the blade will not exert much moment in any event

Hence 
$$Re(r) = \frac{L}{\nu} \cdot V(r) = \frac{L \cdot \omega}{\nu} \cdot r$$

Using Eq. 9.37a 
$$C_D = \frac{0.0742}{\frac{1}{Re_L^5}} - \frac{1740}{Re_L} = \frac{0.0742}{\left(\frac{L \cdot \omega}{\nu} \cdot r\right)^5} - \frac{1740}{\frac{L \cdot \omega}{\nu} \cdot r} = 0.0742 \cdot \left(\frac{\nu}{L \cdot \omega}\right)^5 \cdot r^{-5} - 1740 \cdot \left(\frac{\nu}{L \cdot \omega}\right) \cdot r^{-1}$$

The drag on a differential area is  $dF_D = \frac{1}{2} \cdot \rho \cdot dA \cdot V^2 \cdot C_D = \frac{1}{2} \cdot \rho \cdot L \cdot V^2 \cdot C_D \cdot dr$  The bending moment is then  $dM = dF_D \cdot r$

Hence 
$$M = \int 1 dM = \int_0^W \frac{1}{2} \cdot \rho \cdot L \cdot V^2 \cdot C_D \cdot r \cdot dr \qquad M = \int_0^W \frac{1}{2} \cdot \rho \cdot L \cdot \omega^2 \cdot r^3 \cdot \left[ 0.0742 \cdot \left(\frac{\nu}{L \cdot \omega}\right)^5 \cdot r^{-5} - 1740 \cdot \left(\frac{\nu}{L \cdot \omega}\right) \cdot r^{-1} \right] dr$$

$$M = \frac{1}{2} \cdot \rho \cdot L \cdot \omega^2 \cdot \int_0^W \left[ 0.0742 \cdot \left(\frac{\nu}{L \cdot \omega}\right)^5 \cdot r^{\frac{1}{5} - \frac{14}{5}} - 1740 \cdot \left(\frac{\nu}{L \cdot \omega}\right) \cdot r^2 \right] dr \qquad M = \frac{1}{2} \cdot \rho \cdot L \cdot \omega^2 \cdot \left[ \frac{5 \cdot 0.0742}{19} \cdot \left(\frac{\nu}{L \cdot \omega}\right)^5 \cdot W^{\frac{1}{5} - \frac{19}{5}} - \frac{1740}{3} \cdot \left(\frac{\nu}{L \cdot \omega}\right) \cdot W^3 \right]$$

$M = 1666 \cdot \text{ft} \cdot \text{lb} \cdot \text{f}$       Hence the power is       $P = M \cdot \omega$        $P = 7.93 \cdot \text{hp}$

## Problem 9.125

[Difficulty: 2]

**9.125** A runner maintains a speed of 7.5 mph during a 4-mi run. The runner's route consists of running straight down a road for 2 mi, then turning around and returning the 2 mi straight home. The  $C_D A$  for the runner is  $9 \text{ ft}^2$ . On a windless day, how many calories (kcal) will the runner burn overcoming drag? On a day in which the wind is blowing 5 mph directly along the runner's route how many calories (kcal) will the runner burn overcoming drag?

**Given:** A runner running during different wind conditions.

**Find:** Calories burned for the two different cases

**Solution:**

**Governing equation:**

$$C_D = \frac{F_D}{\frac{1}{2} \rho V^2 A} \quad F_D = \frac{1}{2} C_D \rho V^2 A$$

**Assumption:** 1)  $C_D A = 9 \text{ ft}^2$  2) Runner maintains speed of 7.5 mph regardless of wind conditions

No wind:

$$V = 7.5 \text{ mph} = 11 \text{ ft/s} \quad \rho = 0.00238 \text{ slug/ft}^3$$

The drag force on the runner is:  $F_D = \frac{1}{2} \times 9 \text{ ft}^2 \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (11)^2 \frac{\text{ft}^2}{\text{s}^2} = 1.296 \text{ lbf}$

Energy burned:  $E = \text{Power} \times \text{time} = F_D \times V_{\text{runner}} \times \text{time}$

Where  $\text{time} = 4 \text{ mi} \times \frac{\text{hr}}{7.5 \text{ mi}} \times \frac{3600 \text{ s}}{\text{hr}} = 1920 \text{ s}$

Hence  $E = 1.296 \text{ lbf} \times \frac{11 \text{ ft}}{\text{s}} \times 1920 \text{ s} \times \frac{0.0003238 \text{ kcal}}{\text{ft} \cdot \text{lbf}} \quad E = 8.86 \text{ kcal}$

With 5 mph wind:

Going upwind:  $V_{\text{rel}} = 12.5 \text{ mph} = 18.33 \frac{\text{ft}}{\text{s}}$

The drag force on the runner is:  $F_D = \frac{1}{2} \times 9 \text{ ft}^2 \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (18.33)^2 \frac{\text{ft}^2}{\text{s}^2} = 3.598 \text{ lbf}$

$\text{time} = 2 \text{ mi} \times \frac{\text{hr}}{7.5 \text{ mi}} \times \frac{3600 \text{ s}}{\text{hr}} = 960 \text{ s}$

$$E_{upwind} = 3.598 \text{ lbf} \times \frac{11\text{f}}{\text{s}} \times 960 \text{ s} \times \frac{0.0003238 \text{ kcal}}{\text{ft} \cdot \text{lbf}} = 12.30 \text{ kcal}$$

Going downwind:  $V_{rel} = 2.5 \text{ mph} = 3.67 \frac{\text{ft}}{\text{s}}$

The drag force on the runner is:  $F_D = \frac{1}{2} \times 9 \text{ ft}^2 \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (3.67)^2 \frac{\text{ft}^2}{\text{s}^2} = 0.144 \text{ lbf}$

$$time = 2 \text{ mi} \times \frac{\text{hr}}{7.5 \text{ mi}} \times \frac{3600 \text{ s}}{\text{hr}} = 960 \text{ s}$$

$$E_{downwind} = 0.144 \text{ lbf} \times \frac{11\text{f}}{\text{s}} \times 960 \text{ s} \times \frac{0.0003238 \text{ kcal}}{\text{ft} \cdot \text{lbf}} = 0.49 \text{ kcal}$$

Hence the total energy burned to overcome drag when the wind is 5 mph is:

$$E = 12.30 \text{ kcal} + 0.49 \text{ kcal} = 12.79 \text{ kcal} \quad \text{this is 44\% higher}$$

### Problem 9.126


[Difficulty: 2]

**9.126** Consider small oil droplets ( $SG = 0.85$ ) rising in water. Develop a relation for calculating terminal speed of a droplet (in m/s) as a function of droplet diameter (in mm) assuming Stokes flow. For what range of droplet diameter is Stokes flow a reasonable assumption?

Solution: Draw free-body diagram of droplet, apply Newton's second law.

Basic equation:  $\Sigma F_y = -mg + F_B - F_D = may$

Assume: Stokes' drag law,  $F_D = 3\pi\mu V_t D$ , for  $Re < 10$



Then  $-\rho V g + \rho_{H_2O} V g - 3\pi\mu V_t D = 0$  at terminal speed,  $V_t$ .

Solving,  $V_t = \frac{(\rho_{H_2O} - \rho_0) V g}{3\pi\mu D} = \frac{\rho_{H_2O}(1 - SG_0) \frac{\pi D^3}{6} g}{3\pi\mu D} = \frac{(1 - SG_0) D^2 g}{18 \nu}$

Evaluating,

$$V_t (\text{m/s}) = \frac{(1 - 0.85)}{18} \times D^2 \text{ mm}^2 \times 9.81 \frac{\text{m}}{\text{s}} \times \frac{5}{1.00 \times 10^{-6} \text{ m}^2} \times \frac{\text{m}^2}{10^6 \text{ mm}^2} \quad (T = 20^\circ\text{C})$$

$$V_t (\text{m/s}) = 0.0818 [D (\text{mm})]^2$$

For Stokes flow,  $Re < 1$ , so

$$Re = \frac{\rho V_t D}{\mu} = \frac{V_t D}{\nu} = \frac{(1 - SG_0) D^3 g}{18 \nu^2} \leq 1$$

Thus

$$D^3 \leq \frac{18 \nu^2}{(1 - SG_0) g} \quad \text{or} \quad D \leq \left[ \frac{18 \nu^2}{(1 - SG_0) g} \right]^{1/3}$$

Evaluating,

$$D \leq \left[ \frac{18}{(1 - 0.85)} \frac{(1.00 \times 10^{-6})^2 \text{ m}^4}{\text{s}^2} \times \frac{5}{9.81 \text{ m}} \right]^{1/3} = 2.31 \times 10^{-4} \text{ m} \quad (0.231 \text{ mm})$$

Thus Stokes' flow will be a valid assumption for  $D < 0.231 \text{ mm}$ .



## Problem 9.128

[Difficulty: 2]

**9.128** A spherical helium-filled balloon, 20 in. in diameter, exerts an upward force of 0.3 lbf on a restraining string when held stationary in standard air with no wind. With a wind speed of 10 ft/s, the string holding the balloon makes an angle of  $55^\circ$  with the horizontal. Calculate the drag coefficient of the balloon under these conditions, neglecting the weight of the string.

**Given:** Data on helium-filled balloon, angle balloon string makes when subjected to wind


**Find:** Drag coefficient for the balloon

**Solution:**

Basic equations:  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$        $\Sigma F_y = 0$

The given or available data is       $D = 20 \cdot \text{in}$        $F_B = 0.3 \cdot \text{lbf}$        $V = 10 \cdot \frac{\text{ft}}{\text{s}}$        $\theta = 55 \cdot \text{deg}$

$\rho = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3}$        $\nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$       (Table A.9, 70°F)



Based on a free body diagram of the balloon,  $F_D = F_B \cdot \tan(90 \cdot \text{deg} - \theta) = 0.2101 \cdot \text{lbf}$


The reference area for the balloon is:  $A = \frac{\pi}{4} \cdot D^2 = 2.182 \cdot \text{ft}^2$  so the drag coefficient is:  $C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} = 0.826$

### Problem 9.129

Difficulty: 2

**9.129** A field hockey ball has diameter  $D = 73$  mm and mass  $m = 160$  g. When struck well, it leaves the stick with initial speed  $U_0 = 50$  m/s. The ball is essentially smooth. Estimate the distance traveled in horizontal flight before the speed of the ball is reduced 10 percent by aerodynamic drag.

Solution: Apply Newton's second law of motion:



Basic equation:  $\sum F_x = ma_x = m \frac{dU}{dt} = mU \frac{dU}{dx}$

Thus  $-F_D = -C_D A \frac{1}{2} \rho U^2 = mU \frac{dU}{dx}$  or  $dx = -\frac{2m}{C_D A \rho} \frac{dU}{U}$

Check  $Re$  to find  $C_D$  (use  $\nu$  at  $T = 15^\circ\text{C}$  from Table A.10):

$$Re \leq \frac{U_0 D}{\nu} = \frac{50 \text{ m}}{\text{s}} \times 0.075 \text{ m} \times \frac{\text{s}}{1.46 \times 10^{-6} \text{ m}^2} = 2.57 \times 10^5 \quad (\text{standard air})$$

From Fig. 9.11, flow is subcritical and  $C_D \approx 0.47 = \text{constant}$ .

Thus  $x = \int_0^x dx = \int_{U_0}^U -\frac{2m}{C_D A \rho} \frac{dU}{U} = -\frac{2m}{C_D A \rho} \ln U \Big|_{U_0}^U = -\frac{2m}{C_D A \rho} \ln\left(\frac{U}{U_0}\right)$

or  $x = -2 \times 0.160 \text{ kg} \times \frac{1}{0.47} \times \frac{4}{\pi (0.073)^2 \text{ m}^2} \times \frac{\text{m}^3}{1.23 \text{ kg}} \ln(0.9) = 13.9 \text{ m}$

## Problem 9.130

[Difficulty: 2]

**9.130** Compute the terminal speed of a 3-mm-diameter raindrop (assume spherical) in standard air.

**Given:** 3 mm raindrop

**Find:** Terminal speed

**Solution:**

Basic equation:  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$   $\Sigma F = 0$

Given or available data is  $D = 3 \cdot \text{mm}$   $\rho_{\text{H}_2\text{O}} = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$   $\rho_{\text{air}} = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$  (Table A.10, 20°C)

Summing vertical forces  $M \cdot g - F_D = M \cdot g - \frac{1}{2} \cdot \rho_{\text{air}} \cdot A \cdot V^2 \cdot C_D = 0$  Buoyancy is negligible

$M = \rho_{\text{H}_2\text{O}} \cdot \frac{\pi \cdot D^3}{6}$   $M = 1.41 \times 10^{-5} \text{ kg}$   $A = \frac{\pi \cdot D^2}{4}$   $A = 7.07 \times 10^{-6} \text{ m}^2$

Assume the drag coefficient is in the flat region of Fig. 9.11 and verify Re later  $C_D = 0.4$

$$V = \sqrt{\frac{2 \cdot M \cdot g}{C_D \cdot \rho_{\text{air}} \cdot A}} \quad V = 8.95 \frac{\text{m}}{\text{s}}$$

Check Re  $\text{Re} = \frac{V \cdot D}{\nu}$   $\text{Re} = 1.79 \times 10^3$  which does place us in the flat region of the curve


Actual raindrops are not quite spherical, so their speed will only be approximated by this result

**9.131** A small sphere ( $D = 6 \text{ mm}$ ) is observed to fall through castor oil at a terminal speed of  $60 \text{ mm/s}$ . The temperature is  $20^\circ\text{C}$ . Compute the drag coefficient for the sphere. Determine the density of the sphere. If dropped in water, would the sphere fall slower or faster? Why?

Solution: Apply Newton's second law of motion, definition of  $C_D$ .

Basic equations:  $\Sigma F_y = may$

$$C_D = \frac{F_D}{\frac{1}{2}\rho V^2 A}$$



Assume  $Re \ll 1$ , so Stokes flow,  $F_D = 3\pi\mu DV$ .

From the definition, noting  $A$  is the frontal area,  $A = \frac{\pi D^2}{4}$ ,

$$C_D = \frac{F_D}{\frac{1}{2}\rho V^2 A} = \frac{3\pi\mu DV}{\frac{1}{2}\rho V^2 \frac{\pi D^2}{4}} = \frac{24\mu}{\rho V D} = \frac{24}{Re}$$

For castor oil at  $20^\circ\text{C}$ ,  $\mu = 0.9 \text{ N}\cdot\text{s}/\text{m}^2$  (Fig. A.2) and  $SG \approx 0.97$  (Table A.2).

$$Re = \frac{SG \rho_{H_2O} V D}{\mu} = \frac{(0.97) 999 \frac{\text{kg}}{\text{m}^3} \times 0.06 \frac{\text{m}}{\text{s}} \times 0.006 \text{ m}}{0.9 \text{ N}\cdot\text{s}/\text{m}^2} = 0.388 < 1 \quad \checkmark$$

$$C_D = \frac{24}{Re} = \frac{24}{0.388} = 61.9$$

From Newton's second law,  $F_D + F_{\text{buoyancy}} - mg = 0$  or  $F_D = mg - F_b$ . Thus

$$F_D = C_D \frac{1}{2}\rho V^2 A = mg - F_b = (SG_s - SG_o) \rho_{H_2O} g \frac{\pi}{4} D^3 \quad \text{or} \quad SG_s = SG_o + \frac{C_D \frac{1}{2}\rho V^2 A}{\rho_{H_2O} g \frac{\pi}{4} D^3} = SG_o \left(1 + \frac{C_D V^2}{2gD}\right)$$

But  $\frac{A}{\frac{\pi}{4} D^3} = \frac{\pi r^2}{\frac{\pi}{4} \pi r^3} = \frac{3}{4r} = \frac{3}{2D}$ , so  $SG_s = SG_o \left(1 + \frac{3}{4} \frac{C_D V^2}{gD}\right)$

$$SG_s = 0.97 \left(1 + \frac{3}{4} \times 61.9 \times \frac{(0.06)^2 \frac{\text{m}^2}{\text{s}^2}}{9.81 \text{ m} \times 0.006 \text{ m}}\right) = 3.72, \text{ so } \rho_s = 3720 \frac{\text{kg}}{\text{m}^3}$$

In water, the net weight and drag must balance, or

$$F_D = \frac{1}{2}\rho V^2 C_D A = W - F_b = \rho_{H_2O} (SG_s - 1) \frac{\pi}{4} D^3 \quad \text{or} \quad V = \left[ \frac{4(SG_s - 1) g D}{3 C_D} \right]^{\frac{1}{2}}$$

However,  $C_D$  is a function of  $Re$ , so iteration is needed. From Fig. 9.11,  $C_D \approx 0.4$  over a range of  $Re$ . Using  $C_D = 0.4$ ,

$$V = \left[ \frac{4}{3} \left( \frac{3.72}{0.4} \right) 9.81 \frac{\text{m}}{\text{s}^2} \times 0.006 \text{ m} \right]^{\frac{1}{2}} = 0.731 \text{ m/s}$$

Check  $Re$ :

$$Re = \frac{VD}{\nu} = \frac{0.731 \frac{\text{m}}{\text{s}} \times 0.006 \text{ m}}{1.11 \times 10^{-6} \text{ m}^2/\text{s}} = 3990 \quad \text{ok!}$$

### Problem 9.132


[Difficulty: 3]

**9.132** The following curve-fit for the drag coefficient of a smooth sphere as a function of Reynolds number has been proposed by Chow [36]:

$C_D = 24/Re$	$Re \leq 1$
$C_D = 24/Re^{0.646}$	$1 < Re \leq 400$
$C_D = 0.5$	$400 < Re \leq 3 \times 10^5$
$C_D = 0.000366 Re^{0.4275}$	$3 \times 10^5 < Re \leq 2 \times 10^6$
$C_D = 0.18$	$Re > 2 \times 10^6$

Use data from Fig. 9.11 to estimate the magnitude and location of the maximum error between the curve fit and data.

Solution: The curve-fit segments are plotted on Fig. 9.11 below:




The maximum significant error occurs in the region where  $C_D$  is modeled as equal to the constant value,  $C_D = 0.5$ . The curve fit appears to be about 10 percent high in the region from  $Re \approx 10^3$  to  $Re \approx 10^4$ .

## Problem 9.133

[Difficulty: 3]

**9.133** Problem 9.107 showed a circular disk hung in an air stream from a cylindrical strut. Assume the strut is  $L = 40$  mm long and  $d = 3$  mm in diameter. Solve Problem 9.107 including the effect of drag on the support.



**Given:** Circular disk in wind

**Find:** Mass of disk; Plot  $\alpha$  versus  $V$

**Solution:**

Basic equations: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} \quad \Sigma \vec{M} = 0$$

Summing moments at the pivot  $W \cdot L \cdot \sin(\alpha) - F_{n1} \cdot L - \frac{1}{2} \cdot \left(L - \frac{D}{2}\right) \cdot F_{n2} = 0$  (1) and for each normal drag  $F_n = \frac{1}{2} \cdot \rho \cdot V_n^2 \cdot A \cdot C_D$

Assume 1) No pivot friction 2)  $C_D$  is valid for  $V_n = V \cos(\alpha)$

The data is 
$$\rho = 1.225 \cdot \frac{\text{kg}}{\text{m}^3} \quad \mu = 1.8 \times 10^{-5} \cdot \frac{\text{N} \cdot \text{s}}{\text{m}^2} \quad V = 15 \cdot \frac{\text{m}}{\text{s}}$$

$$D = 25 \cdot \text{mm} \quad d = 3 \cdot \text{mm} \quad L = 40 \cdot \text{mm} \quad \alpha = 10 \cdot \text{deg}$$

$$C_{D1} = 1.17 \text{ (Table 9.3)} \quad Re_d = \frac{\rho \cdot V \cdot d}{\mu} \quad Re_d = 3063 \quad \text{so from Fig. 9.13} \quad C_{D2} = 0.9$$

Hence 
$$F_{n1} = \frac{1}{2} \cdot \rho \cdot (V \cdot \cos(\alpha))^2 \cdot \frac{\pi \cdot D^2}{4} \cdot C_{D1} \quad F_{n1} = 0.077 \text{ N}$$

$$F_{n2} = \frac{1}{2} \cdot \rho \cdot (V \cdot \cos(\alpha))^2 \cdot \left(L - \frac{D}{2}\right) \cdot d \cdot C_{D2} \quad F_{n2} = 0.00992 \text{ N}$$

The drag on the support is much less than on the disk (and moment even less), so results will not be much different from those of Problem 9.105


Hence Eq. 1 becomes 
$$M \cdot L \cdot g \cdot \sin(\alpha) = L \cdot \frac{1}{2} \cdot \rho \cdot (V \cdot \cos(\alpha))^2 \cdot \frac{\pi \cdot D^2}{4} \cdot C_{D1} + \frac{1}{2} \cdot \left(L - \frac{D}{2}\right) \cdot \left[\frac{1}{2} \cdot \rho \cdot (V \cdot \cos(\alpha))^2 \cdot \left(L - \frac{D}{2}\right) \cdot d \cdot C_{D2}\right]$$

$$M = \frac{\rho \cdot V^2 \cdot \cos^2(\alpha)}{4 \cdot g \cdot \sin(\alpha)} \cdot \left[\frac{1}{2} \cdot \pi \cdot D^2 \cdot C_{D1} + \left(1 - \frac{D}{2L}\right) \cdot \left(L - \frac{D}{2}\right) \cdot d \cdot C_{D2}\right] \quad M = 0.0471 \text{ kg}$$

Rearranging

$$V = \sqrt{\frac{4 \cdot M \cdot g}{\rho}} \cdot \frac{\sqrt{\tan(\alpha)}}{\sqrt{\cos(\alpha)}} \cdot \frac{1}{\sqrt{\left[ \frac{1}{2} \cdot \pi \cdot D^2 \cdot C_{D1} + \left( 1 - \frac{D}{2 \cdot L} \right) \cdot \left( L - \frac{D}{2} \right) \cdot d \cdot C_{D2} \right]}}$$
$$V = 35.5 \cdot \frac{\text{m}}{\text{s}} \cdot \frac{\sqrt{\tan(\alpha)}}{\sqrt{\cos(\alpha)}}$$

We can plot this by choosing  $\alpha$  and computing V



This graph can be easily plotted in *Excel*

## Problem 9.134

[Difficulty: 3]

**9.134** A tennis ball with a mass of 57 g and diameter of 64 mm is dropped in standard sea level air. Calculate the terminal velocity of the ball. Assuming as an approximation that the drag coefficient remains constant at its terminal-velocity value, estimate the time and distance required for the ball to reach 95% of its terminal speed.

**Given:** Data on a tennis ball

**Find:** Terminal speed time and distance to reach 95% of terminal speed

**Solution:**

The given data or available data is  $M = 57 \cdot \text{gm}$   $D = 64 \cdot \text{mm}$   $\nu = 1.45 \cdot 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$   $\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$

Then  $A = \frac{\pi \cdot D^2}{4}$   $A = 3.22 \times 10^{-3} \text{ m}^2$

Assuming high Reynolds number  $C_D = 0.5$  (from Fig. 9.11)

At terminal speed drag equals weight  $F_D = M \cdot g$

The drag at speed  $V$  is given by  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$

Hence the terminal speed is  $V_t = \sqrt{\frac{M \cdot g}{\frac{1}{2} \cdot \rho \cdot A \cdot C_D}}$   $V_t = 23.8 \frac{\text{m}}{\text{s}}$

Check the Reynolds number  $Re = \frac{V_t \cdot D}{\nu}$   $Re = 1.05 \times 10^5$  Check!

For motion before terminal speed Newton's second law applies

$M \cdot a = M \cdot \frac{dV}{dt} = M \cdot g - \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D$  or  $\frac{d}{dt}V = g - k \cdot V^2$  where  $k = \frac{\rho \cdot A \cdot C_D}{2 \cdot M}$   $k = 0.0174 \frac{1}{\text{m}}$

Separating variables  $\int_0^V \frac{1}{g - k \cdot V^2} dV = t$   $\int \frac{1}{g - k \cdot V^2} dV = \frac{1}{\sqrt{g \cdot k}} \cdot \text{atanh}\left(\sqrt{\frac{k}{g}} \cdot V\right)$

Hence  $V(t) = \sqrt{\frac{g}{k}} \cdot \tanh(\sqrt{g \cdot k} \cdot t)$

Evaluating at  $V = 0.95 V_t$   $0.95 \cdot V_t = \sqrt{\frac{g}{k}} \cdot \tanh(\sqrt{g \cdot k} \cdot t)$   $t = \frac{1}{\sqrt{g \cdot k}} \cdot \text{atanh}\left(0.95 \cdot V_t \cdot \sqrt{\frac{k}{g}}\right)$   $t = 4.44 \text{ s}$

For distance  $x$  versus time, integrate  $\frac{dx}{dt} = \sqrt{\frac{g}{k}} \cdot \tanh(\sqrt{g \cdot k} \cdot t)$   $x = \int_0^t \sqrt{\frac{g}{k}} \cdot \tanh(\sqrt{g \cdot k} \cdot t) dt$

Note that

$$\int \tanh(a \cdot t) dt = \frac{1}{a} \cdot \ln(\cosh(a \cdot t))$$

Hence

$$x(t) = \frac{1}{k} \cdot \ln(\cosh(\sqrt{g \cdot k} \cdot t))$$

Evaluating at  $V = 0.95V_t$

$$t = 4.44 \text{ s}$$


so

$$x(t) = 67.1 \text{ m}$$

### Problem 9.135

[Difficulty: 4]

**9.135** Consider a cylindrical flag pole of height  $H$ . For constant drag coefficient, evaluate the drag force and bending moment on the pole if wind speed varies as  $u/U = (y/H)^{1/7}$ , where  $y$  is distance measured from the ground. Compare with drag and moment for a uniform wind profile with constant speed  $U$ .



Solution: Apply definition of drag coefficient,  $C_D = \frac{F_D}{\frac{1}{2}\rho V^2 A}$

Assume: (1)  $C_D = \text{constant}$   
 (2)  $C_D$  same as circular cylinder  
 On an element of the pole,

$$dF_D = C_D \frac{1}{2} \rho u^2 dA = C_D \frac{1}{2} \rho U^2 \left(\frac{y}{H}\right)^{2/7} D dy$$

Thus

$$F_D = \int_0^H dF_D = \int_0^H C_D \frac{1}{2} \rho U^2 \left(\frac{y}{H}\right)^{2/7} D dy$$

$$F_D = C_D \frac{1}{2} \rho U^2 D H \int_0^1 \left(\frac{y}{H}\right)^{2/7} d\left(\frac{y}{H}\right) = C_D \frac{1}{2} \rho U^2 D H \left[ \frac{7}{9} \left(\frac{y}{H}\right)^{9/7} \right]_0^1 = \frac{7}{9} C_D \frac{1}{2} \rho U^2 D H \quad F_D$$

On an element of the pole,

$$dM = y dF_D = y C_D \frac{1}{2} \rho u^2 dA = y C_D \frac{1}{2} \rho U^2 D dy$$

Thus

$$M = \int_0^H dM = \int_0^H y C_D \frac{1}{2} \rho U^2 \left(\frac{y}{H}\right)^{2/7} D dy = C_D \frac{1}{2} \rho U^2 D H^2 \int_0^1 \left(\frac{y}{H}\right) \left(\frac{y}{H}\right)^{2/7} d\left(\frac{y}{H}\right)$$

$$M = C_D \frac{1}{2} \rho U^2 D H^2 \int_0^1 \left(\frac{y}{H}\right)^{9/7} d\left(\frac{y}{H}\right) = C_D \frac{1}{2} \rho U^2 D H^2 \left[ \frac{7}{16} \left(\frac{y}{H}\right)^{16/7} \right]_0^1 = \frac{7}{16} C_D \frac{1}{2} \rho U^2 D H^2 \quad M$$

Comparing,


$$\frac{F_D(\text{1/7-profile})}{F_D(\text{uniform})} = \frac{\frac{7}{9} C_D \frac{1}{2} \rho U^2 D H}{C_D \frac{1}{2} \rho U^2 D H} = \frac{7}{9}$$

$$\frac{M(\text{1/7-profile})}{M(\text{uniform})} = \frac{\frac{7}{16} C_D \frac{1}{2} \rho U^2 D H^2}{C_D \frac{1}{2} \rho U^2 D H \frac{H}{2}} = \frac{7/16}{1/2} = \frac{7}{8}$$

### Problem 9.136

[Difficulty: 3]

**9.136** A water tower consists of a 12-m-diameter sphere on top of a vertical tower 30 m tall and 2 m in diameter. Estimate the bending moment exerted on the base of the tower due to the aerodynamic force imposed by a 100 km/hr wind on a standard day. Neglect interference at the joint between the sphere and tower.



Solution: Apply definition of  $C_D$ ,  
sum moments about base.

Computing equations:  $C_D = \frac{F_D}{\frac{1}{2}\rho V^2 A}$ ;  $\sum \vec{M} = \sum F L$

Assumptions! (1)  $F_{D_s}$  acts at center of sphere;  $F_{D_c}$  at center of cylinder  
(2) Neglect interference between sphere and cylinder.

$$\text{Then } M = F_{D_s} \left( h + \frac{D}{2} \right) + F_{D_c} \left( \frac{h}{2} \right) \quad A_s = \frac{\pi D^2}{4} = \frac{\pi (12)^2}{4} \text{ m}^2 = 113 \text{ m}^2$$

$$A_c = h d = 30 \text{ m} \times 2 \text{ m} = 60 \text{ m}^2$$

$$V = 100 \frac{\text{km}}{\text{hr}} \times \frac{1000 \text{ m}}{\text{km}} \times \frac{\text{hr}}{3600 \text{ s}} = 27.8 \text{ m/s}$$

$$q = \frac{1}{2} \rho V^2 = \frac{1}{2} \times 1.23 \frac{\text{kg}}{\text{m}^3} \times (27.8)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 475 \text{ N/m}^2$$

$C_D = C_D(Re)$ . For standard air (Table A.10),  $\nu = 1.46 \times 10^{-5} \text{ m}^2/\text{s}$ , so

$$Re_s = \frac{VD}{\nu} = \frac{27.8 \frac{\text{m}}{\text{s}} \times 12 \text{ m}}{1.46 \times 10^{-5} \text{ m}^2/\text{s}} = 2.28 \times 10^7$$

This  $Re$  is too large for Fig. 9.11. Thus guess  $C_{D_s} = 0.18$  (Problem 9.125).

$$F_{D_s} = C_{D_s} q A_s = 0.18 \times 475 \frac{\text{N}}{\text{m}^2} \times 113 \text{ m}^2 = 9.66 \text{ kN}$$

$$Re_c = \frac{Vd}{\nu} = \frac{27.8 \frac{\text{m}}{\text{s}} \times 2.0 \text{ m}}{1.46 \times 10^{-5} \text{ m}^2/\text{s}} = 3.81 \times 10^6$$

This  $Re$  is too large for Fig. 9.13. Thus guess  $C_{D_c} \approx 0.4$ .

$$F_{D_c} = C_{D_c} q A_c = 0.4 \times 475 \frac{\text{N}}{\text{m}^2} \times 60 \text{ m}^2 = 11.4 \text{ kN}$$

The moment is

$$M = 9.66 \text{ kN} \left( 30 \text{ m} + \frac{12 \text{ m}}{2} \right) + 11.4 \text{ kN} \left( \frac{30 \text{ m}}{2} \right) = 519 \text{ kN} \cdot \text{m}$$

M

## Problem 9.137

[Difficulty: 3]

**9.137** A model airfoil of chord 15 cm and span 60 cm is placed in a wind tunnel with an air flow of 30 m/s (the air is at 20°C). It is mounted on a cylindrical support rod 2 cm in diameter and 25 cm tall. Instruments at the base of the rod indicate a vertical force of 50 N and a horizontal force of 6 N. Calculate the lift and drag coefficients of the airfoil.

**Given:** Data on model airfoil

**Find:** Lift and drag coefficients

**Solution:**

Basic equation: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2} \quad C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$$
 where A is plan area for airfoil, frontal area for rod

Given or available data is  $D = 2 \cdot \text{cm}$        $L = 25 \cdot \text{cm}$  (Rod)       $b = 60 \cdot \text{cm}$        $c = 15 \cdot \text{cm}$  (Airfoil)

$V = 30 \cdot \frac{\text{m}}{\text{s}}$        $F_L = 50 \cdot \text{N}$        $F_H = 6 \cdot \text{N}$

Note that the horizontal force  $F_H$  is due to drag on the airfoil AND on the rod

$$\rho = 1.225 \cdot \frac{\text{kg}}{\text{m}^3} \quad \nu = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$$
 (Table A.10, 20°C)

For the rod  $Re_{\text{rod}} = \frac{V \cdot D}{\nu}$        $Re_{\text{rod}} = 4 \times 10^4$       so from Fig. 9.13  $C_{D\text{rod}} = 1.0$

$A_{\text{rod}} = L \cdot D$        $A_{\text{rod}} = 5 \times 10^{-3} \text{ m}^2$

$F_{D\text{rod}} = C_{D\text{rod}} \cdot \frac{1}{2} \cdot \rho \cdot A_{\text{rod}} \cdot V^2$        $F_{D\text{rod}} = 2.76 \text{ N}$

Hence for the airfoil  $A = b \cdot c$        $F_D = F_H - F_{D\text{rod}}$        $F_D = 3.24 \text{ N}$


$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2} \quad C_D = 0.0654 \quad C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2} \quad C_L = 1.01 \quad \frac{C_L}{C_D} = 15.4$$

**9.138** A cast-iron "12-pounder" cannonball rolls off the deck of a ship and falls into the ocean at a location where the depth is 1000 m. Estimate the time that elapses before the cannonball hits the sea bottom.

Solution: Apply Newton's second law of motion, definition of  $C_D$ .

Computing equations:

$$\Sigma F_y = may \quad C_D = \frac{F_D}{\frac{1}{2} \rho V^2 A}$$



First find diameter of ball. In air,

$$W = mg = \rho V g = 56 \rho_{H_2O} \frac{\pi D^3}{6} g = 12 \text{ lbf} \quad \{\text{From Table A.1, } 56 = 7.08.\}$$

Thus

$$D = \left[ \frac{6W}{\pi 56 \rho_{H_2O} g} \right]^{1/3} = \left[ \frac{6}{\pi} \times 12 \text{ lbf} \times \frac{1}{7.08} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{\text{s}^2}{32.2 \text{ ft}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2} \right]^{1/3} = 0.373 \text{ ft}$$

or

$$D = 0.373 \text{ ft} \times 0.3048 \frac{\text{m}}{\text{ft}} = 0.114 \text{ m}$$

At terminal speed,  $V = V_t$ , and  $a_y = 0$ . Summing forces,

$$mg - F_B - F_D = 56 \rho_{H_2O} V g - 56 \rho_{sw} \rho_{H_2O} V g - C_D A \frac{1}{2} \rho V_t^2 = 0$$

or

$$V_t = \left[ \frac{2(56 \rho_{ci} - 56 \rho_{sw}) \rho_{H_2O} V g}{C_D 56 \rho_{sw} \rho_{H_2O} A} \right]^{1/2}$$

Introducing  $V = \frac{\pi D^3}{6}$  and  $A = \frac{\pi D^2}{4}$ , then

$$V_t = \left[ \frac{4}{3} \frac{(56 \rho_{ci} / 56 \rho_{sw} - 1) D g}{C_D} \right]^{1/2} = \left[ \frac{4}{3} (7.08 / 11.025 - 1) 0.114 \text{ m} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \frac{1}{C_D} \right]^{1/2} = \frac{2.97}{\sqrt{C_D}} \text{ m/s}$$

Choose  $C_D = 0.47$  from flat range of curve:

$$V_t = \frac{2.97}{\sqrt{0.47}} \text{ m/sec} = 4.33 \text{ m/s} \quad \{\text{At } T = 20^\circ\text{C, } \rho_{sw} = 1.05 \rho_{H_2O} \text{ (Table A.2).}\}$$

Then  $Re = \frac{\rho V_t D}{\mu} = \frac{V_t D}{\nu_{sw}} = 4.33 \frac{\text{m}}{\text{s}} \times 0.114 \text{ m} \times \frac{\text{s}}{1.05 \times 10^{-6} \text{ m}^2} = 4.70 \times 10^5$

This is a supercritical  $Re$ , so choose  $C_D \approx 0.09$  (Fig. 9.11). Then

$$V_t = \frac{2.97}{\sqrt{0.09}} \text{ m/s} = 9.90 \text{ m/s}$$

Then  $Re = \frac{9.90 \text{ m}}{\text{s}} \times 0.114 \text{ m} \times \frac{\text{s}}{1.05 \times 10^{-6} \text{ m}^2} = 1.07 \times 10^6$

From Fig. 9.11,  $C_D \approx 0.14$ . Therefore  $V_t = \frac{2.97}{\sqrt{0.14}} = 7.94 \text{ m/s}$


$$t = \frac{d}{V_t} = 1000 \text{ m} \times \frac{\text{s}}{7.94 \text{ m}} = 126 \text{ s}$$

**9.139** The Stokes drag law for smooth spheres is to be verified experimentally by dropping steel ball bearings in glycerin. Evaluate the largest diameter steel ball for which  $Re < 1$  at terminal speed. Calculate the height of glycerin column needed for a bearing to reach 95 percent of terminal speed.

Solution: Draw free-body diagram of ball, apply Newton's second law.

Basic equation:  $\sum F_y = mg - F_B - F_D = m \frac{dv}{dt} = m v \frac{dv}{dy}$  (1)

$V = \frac{\pi D^3}{6}$       $m = \rho_s V$       $F_B = \rho_g V g$       $F_D = 3\pi \mu V D$



At terminal speed,  $V_t$ , acceleration is zero. Thus

$\rho_s V g - \rho_g V g - 3\pi \mu V_t D = 0$  or  $V_t = \frac{(\rho_s - \rho_g) \pi D^3 g}{6 \cdot 3\pi \mu D} = \frac{(\rho_s - \rho_g) D^2 g}{18 \mu}$   
 or  $V_t = \frac{(\rho_s/\rho_g - 1) \rho_g D^2 g}{18 \mu} = \frac{(565/569 - 1) D^2 g}{18 \nu} = \frac{(7.8/1.26 - 1) D^2 g}{18 \nu} = 0.288 D^2 g / \nu$

(from Table A.2,  $569 = 1.26$ ). Stokes' drag law holds for  $Re < 1$ . Thus

$Re = \frac{\rho V_t D}{\mu} = \frac{V_t D}{\nu} = \frac{0.288 D^3 g}{\nu^2} < 1$  or  $D^3 \leq \frac{1}{0.288} \frac{\nu^2}{g}$  or  $D \leq \left[ \frac{3.47 \nu^2}{g} \right]^{1/3}$

Assuming  $T = 20^\circ C$ , then from Fig. A.3,  $\nu = 0.0012 \text{ m}^2/\text{s}$ , so

$D \leq \left[ 3.47 \cdot (0.0012)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{s}^2}{9.81 \text{ m}} \right]^{1/3} = 0.00799 \text{ m} \quad (7.99 \text{ mm})$

From Eq. 1,

$\rho_s V g - \rho_g V g - 3\pi \mu V D = \rho_s V \frac{dv}{dy}$

Dividing by  $(\rho_s - \rho_g) V g$  gives

$1 - \frac{3\pi \mu D}{(\rho_s - \rho_g) \pi D^3 g} v = 1 - \frac{v}{V_t} = \frac{\rho_s V}{(\rho_s - \rho_g) V g} v \frac{dv}{dy} = \left( \frac{\rho_s}{\rho_s - \rho_g} \right) \frac{v}{g} \frac{dv}{dy} = \left( \frac{\rho_s}{\rho_s - \rho_g} \right) \frac{V_t^2}{g} \frac{v}{V_t} \frac{d(V/V_t)}{dy}$

Separating variables,  $dy = \left( \frac{\rho_s}{\rho_s - \rho_g} \right) \frac{V_t^2}{g} \frac{(V/V_t) d(V/V_t)}{1 - V/V_t} = \left( \frac{\rho_s}{\rho_s - \rho_g} \right) \frac{V_t^2}{g} \frac{r dr}{1 - r}$

Integrating,  $\int_0^{0.95} \frac{r dr}{1 - r} = \int_1^{0.05} \frac{(1-x)(-dx)}{x} = \int_1^{0.05} dx - \int_1^{0.05} \frac{dx}{x} = x - \ln x \Big|_1^{0.05} = -0.95 - \ln(0.05)$

Thus

$y = 2.05 \left( \frac{\rho_s}{\rho_s - \rho_g} \right) \frac{V_t^2}{g} = 2.05 \left( \frac{565}{565 - 569} \right) \frac{V_t^2}{g}$

But  $V_t = 0.288 \frac{D^2 g}{\nu} = 0.288 \cdot (0.0172)^2 \frac{\text{m}^2}{\text{s}^2} \cdot \frac{9.81 \text{ m}}{\text{s}^2} \cdot \frac{\text{s}}{0.0012 \text{ m}^2} = 0.697 \text{ m/s}$

so

$y = 2.05 \cdot \frac{7.8}{(7.8 - 1.26)} \cdot (0.697)^2 \frac{\text{m}^2}{\text{s}^2} \cdot \frac{\text{s}^2}{9.81 \text{ m}} = 0.121 \text{ m} \quad (121 \text{ mm})$


### Problem 9.140

[Difficulty: 4]

**9.140** The plot shows pressure difference versus angle, measured for air flow around a circular cylinder at  $Re = 80,000$ . Use these data to estimate  $C_D$  for this flow. Compare with data from Fig. 9.13. How can you explain the difference?

Solution: Consider the geometry sketched.

Apply the definition of drag coefficient.



Computing equation:  $C_D = \frac{F_D}{\frac{1}{2}\rho U^2 A}$

Assumption: Neglect viscous force;  $dF_D = dF \cos\theta = p dA \cos\theta = p w R d\theta \cos\theta$

Then  $F_D = \int_A dF_D = \int_0^{2\pi} p w R d\theta \cos\theta = 2 \int_0^\pi p w R d\theta \cos\theta = \int_0^\pi p \cos\theta (w 2R) d\theta$

Since  $\int_0^\pi p_{\infty} \cos\theta d\theta = 0$ , then  $F_D = \int_0^\pi (p - p_{\infty}) \cos\theta (w 2R) d\theta$

The stagnation pressure is  $p(0) - p_{\infty} = \frac{1}{2}\rho U^2$ , so


$$C_D = \frac{F_D}{\frac{1}{2}\rho U^2 A} = \frac{\int_0^\pi (p - p_{\infty}) \cos\theta (w 2R) d\theta}{(p_0 - p_{\infty})(w 2R)} = \int_0^\pi \left(\frac{p - p_{\infty}}{p_0 - p_{\infty}}\right) \cos\theta d\theta$$

Tabulating:

$\theta$ (deg)	$p - p_{\infty}$ (in. H <sub>2</sub> O)	$\frac{p - p_{\infty}}{p_0 - p_{\infty}}$	$\left(\frac{p - p_{\infty}}{p_0 - p_{\infty}}\right) \cos\theta$
0	0.52	1.00	1.00
10	0.46	0.885	0.871
20	0.33	0.635	0.596
30	0.13	0.250	0.217
40	-0.13	-0.250	-0.192
50	-0.40	-0.769	-0.494
60	-0.57	-1.10	-0.548
70	-0.60	-1.15	-0.395
80	-0.55	-1.06	-0.184
90	-0.52	-1.00	0.00
100	-0.51	-0.981	0.170
110	-0.52	-1.00	0.342
120	-0.52	-1.00	0.500
130	-0.52	-1.00	0.643
140	-0.52	-1.00	0.766
150	-0.52	-1.00	0.866
160	-0.54	-1.04	0.976
170	-0.54	-1.04	1.02
180	-0.54	-1.04	1.04

$\Sigma = 7.194$

Trapezoidal rule:



Half of the end points are subtracted to avoid double counting.

$$C_D \approx \left\{ \sum \left(\frac{p - p_{\infty}}{p_0 - p_{\infty}}\right) \cos\theta - \frac{1}{2}(\cdot)_0 - \frac{1}{2}(\cdot)_{180} \right\} \Delta\theta = \left\{ 7.194 - \frac{1}{2}(1.00 + 1.04) \right\} 10 \text{ deg} \times \frac{\pi \text{ rad}}{180 \text{ deg}} = 1.08 \quad C_D$$

From Fig. 9.13,  $C_D \approx 1.2$ . The difference is due to skin friction effects.

47 TRI-SQUARE SHEETS 5 SQUARE  
42 TRI-SQUARE SHEETS 5 SQUARE  
42 TRI-SQUARE SHEETS 5 SQUARE  
NATIONAL

## Problem 9.141

[Difficulty: 4]

**9.141** Consider the tennis ball of Problem 9.134. Use the equations for drag coefficient given in Problem 9.132, and a numerical integration scheme (e.g., Simpson's rule) to compute the time and distance required for the ball to reach 95% of its terminal speed.

**Given:** Data on a tennis ball

**Find:** Terminal speed time and distance to reach 95% of terminal speed

**Solution:**

The given data or available data is  $M = 57 \cdot \text{gm}$   $D = 64 \text{ mm}$   $\nu = 1.45 \cdot 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$   $\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$

Then  $A = \frac{\pi \cdot D^2}{4}$   $A = 3.22 \times 10^{-3} \text{ m}^2$

From Problem 9.132  $C_D = \frac{24}{\text{Re}}$   $\text{Re} \leq 1$

$C_D = \frac{24}{\text{Re}^{0.646}}$   $1 < \text{Re} \leq 400$

$C_D = 0.5$   $400 < \text{Re} \leq 3 \times 10^5$

$C_D = 0.000366 \cdot \text{Re}^{0.4275}$   $3 \times 10^5 < \text{Re} \leq 2 \times 10^6$

$C_D = 0.18$   $\text{Re} > 2 \times 10^6$

At terminal speed drag equals weight  $F_D = M \cdot g$

The drag at speed  $V$  is given by  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$

Assume  $C_D = 0.5$

Hence the terminal speed is  $V_t = \sqrt{\frac{2 \cdot M \cdot g}{\rho \cdot A \cdot C_D}}$   $V_t = 23.8 \frac{\text{m}}{\text{s}}$

Check the Reynolds number  $\text{Re} = \frac{V_t \cdot D}{\nu}$   $\text{Re} = 1.05 \times 10^5$

This is consistent with the tabulated  $C_D$  values!

For motion before terminal speed, Newton's second law is  $M \cdot a = M \cdot \frac{dV}{dt} = M \cdot g \cdot \left[ 1 - \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D \right]$

Hence the time to reach 95% of terminal speed is obtained by separating variables and integrating

$$t = \int_0^{0.95 \cdot V_t} \frac{1}{g - \frac{\rho \cdot A \cdot C_D}{2 \cdot M} \cdot V^2} dV$$

For the distance to reach terminal speed Newton's second law is written in the form

$$M \cdot a = M \cdot V \cdot \frac{dV}{dx} = M \cdot g \cdot \left[ 1 - \frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D \right]$$

Hence the distance to reach 95% of terminal speed is obtained by separating variables and integrating

$$x = \int_0^{0.95 \cdot V_t} \frac{V}{g - \frac{\rho \cdot A \cdot C_D}{2 \cdot M} \cdot V^2} dV$$

These integrals are quite difficult because the drag coefficient varies with Reynolds number, which varies with speed. They are best evaluated numerically. A form of Simpson's Rule is

$$\int f(V) dV = \frac{\Delta V}{3} \cdot (f(V_0) + 4 \cdot f(V_1) + 2 \cdot f(V_2) + 4 \cdot f(V_3) + f(V_N))$$

where  $\Delta V$  is the step size, and  $V_0, V_1$  etc., are the velocities at points 0, 1, ...  $N$ .

Here  $V_0 = 0$   $V_N = 0.95 \cdot V_t$   $\Delta V = \frac{0.95 \cdot V_t}{N}$

From the associated *Excel* calculations (shown below):

$t = 4.69 \cdot s$   $x = 70.9 \cdot m$

These results compare to 4.44 s and 67.1 m from Problem 9.132, which assumed the drag coefficient was constant and analytically integrated. Note that the drag coefficient IS essentially constant, so numerical integration was not really necessary!

**For the time:**

$V$ (m/s)	$Re$	$C_D$	$W$	$f(V)$	$W \times f(V)$
0	0	5438	1	0.102	0.102
1.13	4985	0.500	4	0.102	0.409
2.26	9969	0.500	2	0.103	0.206
3.39	14954	0.500	4	0.104	0.416
4.52	19938	0.500	2	0.106	0.212
5.65	24923	0.500	4	0.108	0.432
6.78	29908	0.500	2	0.111	0.222
7.91	34892	0.500	4	0.115	0.458
9.03	39877	0.500	2	0.119	0.238
10.2	44861	0.500	4	0.125	0.499
11.3	49846	0.500	2	0.132	0.263
12.4	54831	0.500	4	0.140	0.561
13.6	59815	0.500	2	0.151	0.302
14.7	64800	0.500	4	0.165	0.659
15.8	69784	0.500	2	0.183	0.366
16.9	74769	0.500	4	0.207	0.828
18.1	79754	0.500	2	0.241	0.483
19.2	84738	0.500	4	0.293	1.17
20.3	89723	0.500	2	0.379	0.758
21.5	94707	0.500	4	0.550	2.20
22.6	99692	0.500	1	1.05	1.05

**For the distance:**

$f(V)$	$W \times f(V)$
0.00	0.000
0.115	0.462
0.232	0.465
0.353	1.41
0.478	0.955
0.610	2.44
0.752	1.50
0.906	3.62
1.08	2.15
1.27	5.07
1.49	2.97
1.74	6.97
2.05	4.09
2.42	9.68
2.89	5.78
3.51	14.03
4.36	8.72
5.62	22.5
7.70	15.4
11.8	47.2
23.6	23.6

**Total time: 4.69 s**

**Total distance: 70.9 m**

## Problem 9.142

[Difficulty: 4]

**9.142** The air bubble of Problem 3.10 expands as it rises in water. Find the time it takes for the bubble to reach the surface. Repeat for bubbles of diameter 5 mm and 15 mm. Compute and plot the depth of the bubbles as a function of time.

**Given:** Data on an air bubble

**Find:** Time to reach surface

**Solution:**

The given data or available data is

$$h = 100 \cdot \text{ft} = 30.48 \text{ m} \quad \rho = 1025 \cdot \frac{\text{kg}}{\text{m}^3} \quad (\text{Table A.2}) \quad C_D = 0.5 \quad (\text{Fig. 9.11}) \quad p_{\text{atm}} = 101 \cdot \text{kPa}$$

To find the location we have to integrate the velocity over time:  $dx = V \cdot dt$  where  $V = \sqrt{\frac{4 \cdot g \cdot d_0}{3 \cdot C_D} \left[ \frac{p_{\text{atm}} + \rho \cdot g \cdot h}{p_{\text{atm}} + \rho \cdot g \cdot (h - x)} \right]^{\frac{1}{6}}}$

The results (generated in Excel) for each bubble diameter are shown below:

$$d_0 = 0.3 \text{ in}$$

$$d_0 = 7.62 \text{ mm}$$

$$d_0 = 5 \text{ mm}$$


$$d_0 = 15 \text{ mm}$$

t (s)	x (m)	V (m/s)
0	0	0.446
5	2.23	0.451
10	4.49	0.455
15	6.76	0.460
20	9.1	0.466
25	11.4	0.472
30	13.8	0.478
35	16.1	0.486
40	18.6	0.494
45	21.0	0.504
50	23.6	0.516
63.4	30.5	0.563

t (s)	x (m)	V (m/s)
0	0	0.362
5	1.81	0.364
10	3.63	0.367
15	5.47	0.371
20	7.32	0.374
25	9.19	0.377
30	11.1	0.381
35	13.0	0.386
40	14.9	0.390
45	16.9	0.396
50	18.8	0.401
55	20.8	0.408
60	22.9	0.415
65	25.0	0.424
70	27.1	0.435
75	29.3	0.448
77.8	30.5	0.456

t (s)	x (m)	V (m/s)
0.0	0	0.626
5.0	3.13	0.635
10.0	6.31	0.644
15.0	9.53	0.655
20.0	12.8	0.667
25.0	16.1	0.682
30.0	19.5	0.699
35.0	23.0	0.721
40.0	26.6	0.749
45.1	30.5	0.790

Use *Goal Seek* for the last time step to make  $x = h$ !



## Problem 9.143

[Difficulty: 4]

**9.143** Consider the tennis ball of Problem 9.134. Suppose it is hit so that it has an initial upward speed of 50 m/s. Estimate the maximum height of the ball, assuming (a) a constant drag coefficient and (b) using the equations for drag coefficient given in Problem 9.132, and a numerical integration scheme (e.g., a Simpson's rule).

**Given:** Data on a tennis ball

**Find:** Maximum height

**Solution:**

The given data or available data is  $M = 57\text{ gm}$        $D = 64\text{ mm}$        $V_i = 50 \frac{\text{m}}{\text{s}}$        $\nu = 1.45 \cdot 10^{-5} \frac{\text{m}^2}{\text{s}}$        $\rho = 1.23 \frac{\text{kg}}{\text{m}^3}$

Then  $A = \frac{\pi \cdot D^2}{4}$        $A = 3.22 \times 10^{-3} \text{ m}^2$

From Problem 9.132  $C_D = \frac{24}{\text{Re}}$        $\text{Re} \leq 1$

$C_D = \frac{24}{\text{Re}^{0.646}}$        $1 < \text{Re} \leq 400$

$C_D = 0.5$        $400 < \text{Re} \leq 3 \times 10^5$

$C_D = 0.000366 \cdot \text{Re}^{0.4275}$        $3 \times 10^5 < \text{Re} \leq 2 \times 10^6$

$C_D = 0.18$        $\text{Re} > 2 \times 10^6$

The drag at speed  $V$  is given by  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$

For motion before terminal speed, Newton's second law ( $x$  upwards) is  $M \cdot a = M \cdot \frac{dV}{dt} = -\frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D - M \cdot g$

For the maximum height Newton's second law is written in the form  $M \cdot a = M \cdot V \cdot \frac{dV}{dx} = -\frac{1}{2} \cdot \rho \cdot V^2 \cdot A \cdot C_D - M \cdot g$

Hence the maximum height is 
$$x_{\max} = \int_{V_i}^0 \frac{V}{\frac{\rho \cdot A \cdot C_D}{2 \cdot M} \cdot V^2 - g} dV = \int_0^{V_i} \frac{V}{\frac{\rho \cdot A \cdot C_D}{2 \cdot M} \cdot V^2 + g} dV$$

This integral is quite difficult because the drag coefficient varies with Reynolds number, which varies with speed. It is best evaluated numerically. A form of Simpson's Rule is

$$\int f(V) dV = \frac{\Delta V}{3} \cdot (f(V_0) + 4 \cdot f(V_1) + 2 \cdot f(V_2) + 4 \cdot f(V_3) + f(V_N))$$

where  $\Delta V$  is the step size, and  $V_0, V_1$  etc., are the velocities at points 0, 1, ...  $N$ .

Here  $V_0 = 0$   $V_N = V_i$   $\Delta V = -\frac{V_i}{N}$

From the associated *Excel* workbook  $x_{\max} = 48.7\text{ m}$   
(shown here)

$V$ (m/s)	$Re$	$C_D$	$W$	$f(V)$	$W \cdot x f(V)$
0.0	0	0.000	1	0.000	0.000
2.5	11034	0.500	4	0.252	1.01
5.0	22069	0.500	2	0.488	0.976
7.5	33103	0.500	4	0.695	2.78
10.0	44138	0.500	2	0.866	1.73
12.5	55172	0.500	4	1.00	3.99
15.0	66207	0.500	2	1.09	2.19
17.5	77241	0.500	4	1.16	4.63
20.0	88276	0.500	2	1.19	2.39
22.5	99310	0.500	4	1.21	4.84
25.0	110345	0.500	2	1.21	2.42
27.5	121379	0.500	4	1.20	4.80
30.0	132414	0.500	2	1.18	2.36
32.5	143448	0.500	4	1.15	4.62
35.0	154483	0.500	2	1.13	2.25
37.5	165517	0.500	4	1.10	4.38
40.0	176552	0.500	2	1.06	2.13
42.5	187586	0.500	4	1.03	4.13
45.0	198621	0.500	2	1.00	2.00
47.5	209655	0.500	4	0.970	3.88
50.0	220690	0.500	1	0.940	0.940

If we assume  $C_D = 0.5$

the integral 
$$x_{\max} = \int_0^{V_i} \frac{V}{\frac{\rho \cdot A \cdot C_D}{2 \cdot M} \cdot V^2 + g} dV$$

becomes 
$$x_{\max} = \frac{M}{\rho \cdot A \cdot C_D} \cdot \ln \left( \frac{\rho \cdot A \cdot C_D}{2 \cdot M \cdot g} \cdot V_i^2 + 1 \right) \quad x_{\max} = 48.7 \text{ m}$$


The two results agree very closely! This is because the integrand does not vary much after the first few steps so the numerical integral is accurate, and the analytic solution assumes  $C_D = 0.5$ , which it essentially does!




## Problem 9.145

[Difficulty: 3]

**9.145** Approximate dimensions of a rented rooftop carrier are shown. Estimate the drag force on the carrier ( $r = 10$  cm) at 100 km/hr. If the drivetrain efficiency of the vehicle is 0.85 and the brake specific fuel consumption of its engine is 0.3 kg/(kW · hr), estimate the additional rate of fuel consumption due to the carrier. Compute the effect on fuel economy if the auto achieves 12.75 km/L without the carrier. The rental company offers you a cheaper, square-edged carrier at a price \$5 less than the current carrier. Estimate the extra cost of using this carrier instead of the round-edged one for a 750 km trip, assuming fuel is \$3.50 per gallon. Is the cheaper carrier really cheaper?



Drag coefficient v. radius ratio [37]



**Given:** Data on rooftop carrier

**Find:** Drag on carrier; Additional fuel used; Effect on economy; Effect of "cheaper" carrier

**Solution:**

Basic equation: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$$

Given or available data is	$w = 1\text{ m}$	$h = 50\text{ cm}$	$r = 10\text{ cm}$	$\eta_d = 85\%$
	$V = 100 \cdot \frac{\text{km}}{\text{hr}}$	$V = 27.8 \frac{\text{m}}{\text{s}}$	$FE = 12.75 \cdot \frac{\text{km}}{\text{L}}$	$FE = 30.0 \cdot \frac{\text{mi}}{\text{gal}}$
	$\rho_{\text{H}_2\text{O}} = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$	$A = w \cdot h$	$A = 0.5\text{ m}^2$	$BSFC = 0.3 \cdot \frac{\text{kg}}{\text{kW} \cdot \text{hr}}$
	$\rho = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$	$\nu = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$		(Table A.10, 20°F)

From the diagram	$\frac{r}{h} = 0.2$	$C_D = 0.25$	$F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2$	$F_D = 59.1\text{ N}$
------------------	---------------------	--------------	--	-----------------------

Additional power is	$\Delta P = \frac{F_D \cdot V}{\eta_d}$	$\Delta P = 1.93\text{ kW}$		
---------------------	---	-----------------------------	--	--

Additional fuel is	$\Delta FC = BSFC \cdot \Delta P$	$\Delta FC = 1.61 \times 10^{-4} \frac{\text{kg}}{\text{s}}$	$\Delta FC = 0.00965 \cdot \frac{\text{kg}}{\text{min}}$	
--------------------	-----------------------------------	--	--	--

Fuel consumption of the car only is (with  $SG_{\text{gas}} = 0.72$  from Table A.2)

$FC = \frac{V}{FE} \cdot SG_{\text{gas}} \cdot \rho_{\text{H}_2\text{O}}$	$FC = 1.57 \times 10^{-3} \frac{\text{kg}}{\text{s}}$	$FC = 0.0941 \cdot \frac{\text{kg}}{\text{min}}$	
---	---	--	--

The total fuel consumption is then	$FC_T = FC + \Delta FC$	$FC_T = 1.73 \times 10^{-3} \frac{\text{kg}}{\text{s}}$	$FC_T = 0.104 \cdot \frac{\text{kg}}{\text{min}}$
------------------------------------	-------------------------	---	---

Fuel economy with the carrier is	$FE = \frac{V}{FC_T} \cdot SG_{\text{gas}} \cdot \rho_{\text{H}_2\text{O}}$	$FE = 11.6 \cdot \frac{\text{km}}{\text{L}}$	$FE = 27.2 \cdot \frac{\text{mi}}{\text{gal}}$
----------------------------------	---	--	--

For the square-edged:	$\frac{r}{h} = 0$	$C_D = 0.9$	$F_D = C_D \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2$	$F_D = 213\text{ N}$
-----------------------	-------------------	-------------	--	----------------------

Additional power is	$\Delta P = \frac{F_D \cdot V}{\eta_d}$	$\Delta P = 6.95\text{ kW}$		
---------------------	---	-----------------------------	--	--

Additional fuel is  $\Delta FC = BSFC \cdot \Delta P$   $\Delta FC = 5.79 \times 10^{-4} \frac{\text{kg}}{\text{s}}$   $\Delta FC = 0.0348 \cdot \frac{\text{kg}}{\text{min}}$

The total fuel consumption is then  $FC_T = FC + \Delta FC$   $FC_T = 2.148 \times 10^{-3} \frac{\text{kg}}{\text{s}}$   $FC_T = 0.129 \cdot \frac{\text{kg}}{\text{min}}$

Fuel economy with the carrier is now  $FE = \frac{V}{FC_T} \cdot SG_{\text{gas}} \cdot \rho_{\text{H}_2\text{O}}$   $FE = 9.3 \cdot \frac{\text{km}}{\text{L}}$   $FE = 21.9 \cdot \frac{\text{mi}}{\text{gal}}$

The cost of the trip of distance  $d = 750 \cdot \text{km}$  for fuel costing  $p = \frac{\$ \cdot 3.50}{\text{gal}}$  with a rental discount = \$.5 less than the rounded carrier is then

$$\text{Cost} = \frac{d}{FE} \cdot p - \text{discount} \quad \text{Cost} = 69.47 \quad \text{plus the rental fee}$$

The cost of the trip of with the rounded carrier ( $FE = 11.6 \frac{\text{km}}{\text{L}}$ ) is then

$$\text{Cost} = \frac{d}{FE} \cdot p \quad \text{Cost} = 59.78 \quad \text{plus the rental fee}$$

Hence the "cheaper" carrier is more expensive (AND the environment is significantly more damaged!)

## Problem 9.146

[Difficulty: 4]

**9.146** A barge weighing 8820 kN that is 10 m wide, 30 m long, and 7 m tall has come free from its tug boat in the Mississippi River. It is in a section of river which has a current of 1 m/s, and there is a wind blowing straight upriver at 10 m/s. Assume that the drag coefficient is 1.3 for both the part of the barge in the wind as well as the part below water. Determine the speed at which the barge will be steadily moving. Is it moving upriver or downriver?

**Given:** Data on barge and river current

**Find:** Speed and direction of barge

**Solution:**

**Basic equation:**

$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$$

Given or available data is  $W = 8820 \cdot \text{kN}$   $w = 10 \cdot \text{m}$   $L = 30 \cdot \text{m}$   $h = 7 \cdot \text{m}$   $V_{\text{river}} = 1 \cdot \frac{\text{m}}{\text{s}}$   $V_{\text{wind}} = 10 \cdot \frac{\text{m}}{\text{s}}$   $C_{Dw} = 1.3$

$C_{Da} = 1.3$   $\rho_w = 998 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu_w = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$   $\rho_a = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu_a = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$  (Water data from Table A.8, air data from Table A.10, 20°C)

First we need to calculate the amount of the barge submerged in the water. From Archimedes' Principle:  $W = \rho_w \cdot g \cdot V_{\text{sub}}$

The submerged volume can be expressed as:  $V_{\text{sub}} = w \cdot L \cdot h_{\text{sub}}$  Combining these expressions and solving for the depth:

$$h_{\text{sub}} = \frac{W}{\rho_w \cdot g \cdot w \cdot L} = 3.00 \text{ m} \quad \text{Therefore the height of barge exposed to the wind is: } h_{\text{air}} = h - h_{\text{sub}} = 4.00 \text{ m}$$

Assuming the barge is floating downstream, the velocities of the water and air relative to the barge is:

$$V_w = V_{\text{river}} - V_{\text{barge}} \quad V_a = V_{\text{wind}} + V_{\text{barge}}$$

Assuming that the barge is rectangular, the areas exposed to the air and water are:  $A_a = L \cdot w + 2 \cdot (L + w) \cdot h_{\text{air}} = 620 \text{ m}^2$

$$A_w = L \cdot w + 2 \cdot (L + w) \cdot h_{\text{sub}} = 540 \text{ m}^2$$

In order for the barge to be traveling at a constant speed, the drag forces due to the air and water must match:

$$\frac{1}{2} \cdot C_{Dw} \cdot \rho_w \cdot V_w^2 \cdot A_w = \frac{1}{2} \cdot C_{Da} \cdot \rho_a \cdot V_a^2 \cdot A_a \quad \text{Since the drag coefficients are equal, we can simplify: } \rho_w \cdot V_w^2 \cdot A_w = \rho_a \cdot V_a^2 \cdot A_a$$

Solving for the speed relative to the water:  $V_w^2 = V_a^2 \cdot \frac{\rho_a}{\rho_w} \cdot \frac{A_a}{A_w}$  Since the speeds must be in opposite directions:

$$V_w = -V_a \cdot \sqrt{\frac{\rho_a}{\rho_w} \cdot \frac{A_a}{A_w}} \quad \text{In terms of the barge speed: } V_{\text{river}} - V_{\text{barge}} = -(V_{\text{wind}} + V_{\text{barge}}) \cdot \sqrt{\frac{\rho_a}{\rho_w} \cdot \frac{A_a}{A_w}}$$

$$\text{So solving for the barge speed: } V_{\text{barge}} = \frac{V_{\text{river}} + V_{\text{wind}} \cdot \sqrt{\frac{\rho_a}{\rho_w} \cdot \frac{A_a}{A_w}}}{1 - \sqrt{\frac{\rho_a}{\rho_w} \cdot \frac{A_a}{A_w}}} \quad V_{\text{barge}} = 1.426 \frac{\text{m}}{\text{s}} \quad \text{downstream}$$

### Problem 9.147

[Difficulty: 4]

9.147 Coastdown tests, performed on a level road on a calm day, can be used to measure aerodynamic drag and rolling resistance coefficients for a full-scale vehicle. Rolling resistance is estimated from  $dV/dt$  measured at low speed, where aerodynamic drag is small. Rolling resistance then is deducted from  $dV/dt$  measured at high speed to determine the aerodynamic drag. The following data were obtained during a test with a vehicle, of weight  $W = 25,000$  lbf and frontal area  $A = 79$  ft<sup>2</sup>:

$V$ (mph)	5	55
$\frac{dV}{dt}$ $\left(\frac{\text{mph}}{\text{s}}\right)$	-0.150	-0.475


Estimate the aerodynamic drag coefficient for this vehicle. At what speed does the aerodynamic drag first exceed rolling resistance?

Solution: Apply Newton's second law of motion, definition of  $C_D$ .

Computing equations:

$$\sum F_x = ma_x$$

$$C_D = \frac{F_D}{\frac{1}{2} \rho V^2 A}$$



Summing forces,  $-F_R - F_D = ma_x$

$$\text{At 55 mph} \quad -F_R - F_{D55} = ma_{x55}$$

$$\text{At 5 mph} \quad -F_R - F_{D5} \approx 0 = ma_{x5}$$

Subtracting, obtain  $-F_{D55} = m(a_{x55} - a_{x5}) = m \left[ \left. \frac{dV}{dt} \right|_{55} - \left. \frac{dV}{dt} \right|_5 \right] = -C_D A \rho \frac{V^2}{2}$

Thus

$$C_D = \frac{m \left[ \left. \frac{dV}{dt} \right|_5 - \left. \frac{dV}{dt} \right|_{55} \right]}{\frac{1}{2} \rho V^2 A} = \frac{2W \left[ \left. \frac{dV}{dt} \right|_5 - \left. \frac{dV}{dt} \right|_{55} \right]}{\rho g V^2 A}$$

Evaluating, assuming standard air, with  $\rho g = 0.0765$  lbf/ft<sup>3</sup>

$$C_D = 2 \times 25000 \text{ lbf} \times \frac{\text{ft}^3}{0.0765 \text{ lbf}} \times \frac{\text{hr}^2}{(55)^2 \text{ m}^2} \times \frac{1}{79 \text{ ft}^2} \times [-0.150 - (-0.475)] \frac{\text{mi}}{\text{hr} \cdot \text{s}}$$

$$\times \frac{\text{mi}}{5280 \text{ ft}} \times \frac{3600 \text{ s}}{\text{hr}}$$

$$C_D = 0.606$$

At  $V = 5$  mph,  $F_D \approx 0 \quad \therefore -F_R = ma_{x5}$

$$F_R = -ma_{x5} = -25000 \text{ lbf} \times \frac{\text{s}^2}{32.2 \text{ ft}} \times -0.150 \frac{\text{mi}}{\text{hr} \cdot \text{s}} \times \frac{\text{hr}}{3600} \times \frac{5280 \text{ ft}}{\text{mi}} = 171 \text{ lbf}$$

For  $F_R = F_D = C_D \frac{1}{2} \rho V^2 A$ , then  $V = \left[ \frac{2F_R}{\rho C_D A} \right]^{1/2}$

$$V = \left[ 2 \times 171 \text{ lbf} \times \frac{\text{ft}^3}{0.00238 \text{ slug}} \times \frac{1}{79 \text{ ft}^2} \times \frac{1}{0.606} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb} \cdot \text{s}^2} \right]^{1/2}$$

$$V = 54.8 \frac{\text{ft}}{\text{s}} = 37.4 \text{ mph}$$

## Problem 9.148

[Difficulty: 4]

**9.148** A spherical sonar transducer with 15 in. diameter is to be towed in seawater. The transducer must be fully submerged at 55 ft/s. To avoid cavitation, the minimum pressure on the surface of the transducer must be greater than 5 psia. Calculate the hydrodynamic drag force acting on the transducer at the required towing speed. Estimate the minimum depth to which the transducer must be submerged to avoid cavitation.

**Given:** Data on sonar transducer

**Find:** Drag force at required towing speed; minimum depth necessary to avoid cavitation

**Solution:**

Basic equation: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2} \quad C_P = \frac{p - p_{\text{inf}}}{\frac{1}{2} \cdot \rho \cdot V^2} \quad p = p_{\text{atm}} + \rho \cdot g \cdot h$$

Given or available data is  $D = 15 \cdot \text{in}$   $V = 55 \cdot \frac{\text{ft}}{\text{s}}$   $p_{\text{min}} = 5 \cdot \text{psi}$   $\rho = 1.93 \cdot \frac{\text{slug}}{\text{ft}^3}$   $\nu = 1.06 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$  (Table A.7, 70°F)

The Reynolds number of the flow is:  $Re = \frac{V \cdot D}{\nu} = 6.486 \times 10^6$  From Fig. 9.11, we estimate the drag coefficient:  $C_D = 0.18$

The area is:  $A = \frac{\pi}{4} \cdot D^2 = 1.227 \cdot \text{ft}^2$  Therefore the drag force is:  $F_D = \frac{1}{2} \cdot C_D \cdot \rho \cdot V^2 \cdot A$   $F_D = 645 \cdot \text{lb}_f$

From Fig. 9.12 the minimum pressure occurs where  $C_P = -1.2$  Therefore:  $p_{\text{inf}} = p_{\text{min}} - \frac{1}{2} \cdot C_P \cdot \rho \cdot V^2 = 29.326 \cdot \text{psi}$

Solving for the required depth:  $h = \frac{p_{\text{inf}} - p_{\text{atm}}}{\rho \cdot g}$   $h = 33.9 \cdot \text{ft}$

## Problem 9.149

[Difficulty: 4]

**9.149** While walking across campus one windy day, Floyd Fluids speculates about using an umbrella as a "sail" to propel a bicycle along the sidewalk. Develop an algebraic expression for the speed a bike could reach on level ground, with the umbrella "propulsion system." The frontal area of bike and rider is estimated as  $0.3 \text{ m}^2$ , and the drag coefficient is about 1.2. Assume the rolling resistance is 0.75 percent of the bike and rider weight; the combined mass is 75 kg. Evaluate the bike speed that could be achieved with an umbrella 1.22 m in diameter in a wind that blows at 24 km/hr. Discuss the practicality of this propulsion system.

Sum forces in  $x$  direction:

$$\sum F_x = F_D - F_R = 0$$

But  $F_D = (C_{Du} A_u + C_{Db} A_b) \frac{1}{2} \rho (V_w - V_b)^2$

$$F_R = C_R mg$$

Choose  $C_{Du} = 1.42$  (Table 9.3),

$$C_R = 0.75\%, m = 75 \text{ kg, so } F_R = 0.0075 \times 75 \text{ kg} \times 9.81 \frac{\text{m}}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 5.52 \text{ N}$$

$$\text{Then } V_b = V_w - \left[ \frac{2F_R}{\rho (C_{Du} A_u + C_{Db} A_b)} \right]^{\frac{1}{2}}$$

But

$$V_w = 24 \frac{\text{km}}{\text{hr}} \times \frac{1000 \text{ m}}{\text{km}} \times \frac{\text{hr}}{3600 \text{ s}} = 6.67 \text{ m/s}$$

$$V_b = 6.67 \frac{\text{m}}{\text{s}} - \left[ 2 \times 5.52 \text{ N} \times \frac{\text{m}^3}{1.23 \text{ kg} (1.42) 1.17 \text{ m}^2 + (1.20) 0.3 \text{ m}^2} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2} \right]^{\frac{1}{2}}$$

$$V_b = 6.67 \frac{\text{m}}{\text{s}} - 2.11 \frac{\text{m}}{\text{s}} = 4.56 \frac{\text{m}}{\text{s}} \text{ or } 16.4 \frac{\text{km}}{\text{hr}}$$

Thus Floyd's bicycle (with the umbrella propelling it) travels at 68.3% wind speed.

{ Without the umbrella,  $V_b = 1.68 \frac{\text{m}}{\text{s}}$  or  $6.04 \frac{\text{km}}{\text{hr}}$ , by setting  $C_{Du} = 0$  above. }


**Discussion:** Floyd is confused about his fluid mechanics principles if he thinks he can exceed the wind speed. It is impossible to obtain a propulsive force from aerodynamic drag unless the bicycle is moving more slowly than the wind. The drag force must be sufficient to overcome the rolling resistance of the bike and rider. At equilibrium speed the drag force and rolling resistance force must be equal and opposite.

The only benefit could be achieved by adding drag force more rapidly than rolling resistance. An umbrella, with its relatively high drag and low weight, is ideal for this purpose.

However, one would somehow have to hold the umbrella perpendicular to the wind while riding the bike. This would be dangerous at best, especially if the bike had hand-activated brakes.

Since the umbrella must be held perpendicular to the wind, it would be very effective at blocking the rider's view of the road ahead!

In summary, this "system" of propulsion appears quite impractical.



$$A_u = \frac{\pi D_u^2}{4} = \frac{\pi (1.22)^2}{4} \text{ m}^2 = 1.17 \text{ m}^2$$


17-987  
 42-381  
 42-382  
 42-383  
 42-384  
 42-385  
 42-386  
 42-387  
 42-388  
 42-389  
 42-390  
 42-391  
 42-392  
 42-393  
 42-394  
 42-395  
 42-396  
 42-397  
 42-398  
 42-399  
 42-400  
 42-401  
 42-402  
 42-403  
 42-404  
 42-405  
 42-406  
 42-407  
 42-408  
 42-409  
 42-410  
 42-411  
 42-412  
 42-413  
 42-414  
 42-415  
 42-416  
 42-417  
 42-418  
 42-419  
 42-420  
 42-421  
 42-422  
 42-423  
 42-424  
 42-425  
 42-426  
 42-427  
 42-428  
 42-429  
 42-430  
 42-431  
 42-432  
 42-433  
 42-434  
 42-435  
 42-436  
 42-437  
 42-438  
 42-439  
 42-440  
 42-441  
 42-442  
 42-443  
 42-444  
 42-445  
 42-446  
 42-447  
 42-448  
 42-449  
 42-450  
 42-451  
 42-452  
 42-453  
 42-454  
 42-455  
 42-456  
 42-457  
 42-458  
 42-459  
 42-460  
 42-461  
 42-462  
 42-463  
 42-464  
 42-465  
 42-466  
 42-467  
 42-468  
 42-469  
 42-470  
 42-471  
 42-472  
 42-473  
 42-474  
 42-475  
 42-476  
 42-477  
 42-478  
 42-479  
 42-480  
 42-481  
 42-482  
 42-483  
 42-484  
 42-485  
 42-486  
 42-487  
 42-488  
 42-489  
 42-490  
 42-491  
 42-492  
 42-493  
 42-494  
 42-495  
 42-496  
 42-497  
 42-498  
 42-499  
 42-500  
 42-501  
 42-502  
 42-503  
 42-504  
 42-505  
 42-506  
 42-507  
 42-508  
 42-509  
 42-510  
 42-511  
 42-512  
 42-513  
 42-514  
 42-515  
 42-516  
 42-517  
 42-518  
 42-519  
 42-520  
 42-521  
 42-522  
 42-523  
 42-524  
 42-525  
 42-526  
 42-527  
 42-528  
 42-529  
 42-530  
 42-531  
 42-532  
 42-533  
 42-534  
 42-535  
 42-536  
 42-537  
 42-538  
 42-539  
 42-540  
 42-541  
 42-542  
 42-543  
 42-544  
 42-545  
 42-546  
 42-547  
 42-548  
 42-549  
 42-550  
 42-551  
 42-552  
 42-553  
 42-554  
 42-555  
 42-556  
 42-557  
 42-558  
 42-559  
 42-560  
 42-561  
 42-562  
 42-563  
 42-564  
 42-565  
 42-566  
 42-567  
 42-568  
 42-569  
 42-570  
 42-571  
 42-572  
 42-573  
 42-574  
 42-575  
 42-576  
 42-577  
 42-578  
 42-579  
 42-580  
 42-581  
 42-582  
 42-583  
 42-584  
 42-585  
 42-586  
 42-587  
 42-588  
 42-589  
 42-590  
 42-591  
 42-592  
 42-593  
 42-594  
 42-595  
 42-596  
 42-597  
 42-598  
 42-599  
 42-600  
 42-601  
 42-602  
 42-603  
 42-604  
 42-605  
 42-606  
 42-607  
 42-608  
 42-609  
 42-610  
 42-611  
 42-612  
 42-613  
 42-614  
 42-615  
 42-616  
 42-617  
 42-618  
 42-619  
 42-620  
 42-621  
 42-622  
 42-623  
 42-624  
 42-625  
 42-626  
 42-627  
 42-628  
 42-629  
 42-630  
 42-631  
 42-632  
 42-633  
 42-634  
 42-635  
 42-636  
 42-637  
 42-638  
 42-639  
 42-640  
 42-641  
 42-642  
 42-643  
 42-644  
 42-645  
 42-646  
 42-647  
 42-648  
 42-649  
 42-650  
 42-651  
 42-652  
 42-653  
 42-654  
 42-655  
 42-656  
 42-657  
 42-658  
 42-659  
 42-660  
 42-661  
 42-662  
 42-663  
 42-664  
 42-665  
 42-666  
 42-667  
 42-668  
 42-669  
 42-670  
 42-671  
 42-672  
 42-673  
 42-674  
 42-675  
 42-676  
 42-677  
 42-678  
 42-679  
 42-680  
 42-681  
 42-682  
 42-683  
 42-684  
 42-685  
 42-686  
 42-687  
 42-688  
 42-689  
 42-690  
 42-691  
 42-692  
 42-693  
 42-694  
 42-695  
 42-696  
 42-697  
 42-698  
 42-699  
 42-700  
 42-701  
 42-702  
 42-703  
 42-704  
 42-705  
 42-706  
 42-707  
 42-708  
 42-709  
 42-710  
 42-711  
 42-712  
 42-713  
 42-714  
 42-715  
 42-716  
 42-717  
 42-718  
 42-719  
 42-720  
 42-721  
 42-722  
 42-723  
 42-724  
 42-725  
 42-726  
 42-727  
 42-728  
 42-729  
 42-730  
 42-731  
 42-732  
 42-733  
 42-734  
 42-735  
 42-736  
 42-737  
 42-738  
 42-739  
 42-740  
 42-741  
 42-742  
 42-743  
 42-744  
 42-745  
 42-746  
 42-747  
 42-748  
 42-749  
 42-750  
 42-751  
 42-752  
 42-753  
 42-754  
 42-755  
 42-756  
 42-757  
 42-758  
 42-759  
 42-760  
 42-761  
 42-762  
 42-763  
 42-764  
 42-765  
 42-766  
 42-767  
 42-768  
 42-769  
 42-770  
 42-771  
 42-772  
 42-773  
 42-774  
 42-775  
 42-776  
 42-777  
 42-778  
 42-779  
 42-780  
 42-781  
 42-782  
 42-783  
 42-784  
 42-785  
 42-786  
 42-787  
 42-788  
 42-789  
 42-790  
 42-791  
 42-792  
 42-793  
 42-794  
 42-795  
 42-796  
 42-797  
 42-798  
 42-799  
 42-800  
 42-801  
 42-802  
 42-803  
 42-804  
 42-805  
 42-806  
 42-807  
 42-808  
 42-809  
 42-810  
 42-811  
 42-812  
 42-813  
 42-814  
 42-815  
 42-816  
 42-817  
 42-818  
 42-819  
 42-820  
 42-821  
 42-822  
 42-823  
 42-824  
 42-825  
 42-826  
 42-827  
 42-828  
 42-829  
 42-830  
 42-831  
 42-832  
 42-833  
 42-834  
 42-835  
 42-836  
 42-837  
 42-838  
 42-839  
 42-840  
 42-841  
 42-842  
 42-843  
 42-844  
 42-845  
 42-846  
 42-847  
 42-848  
 42-849  
 42-850  
 42-851  
 42-852  
 42-853  
 42-854  
 42-855  
 42-856  
 42-857  
 42-858  
 42-859  
 42-860  
 42-861  
 42-862  
 42-863  
 42-864  
 42-865  
 42-866  
 42-867  
 42-868  
 42-869  
 42-870  
 42-871  
 42-872  
 42-873  
 42-874  
 42-875  
 42-876  
 42-877  
 42-878  
 42-879  
 42-880  
 42-881  
 42-882  
 42-883  
 42-884  
 42-885  
 42-886  
 42-887  
 42-888  
 42-889  
 42-890  
 42-891  
 42-892  
 42-893  
 42-894  
 42-895  
 42-896  
 42-897  
 42-898  
 42-899  
 42-900  
 42-901  
 42-902  
 42-903  
 42-904  
 42-905  
 42-906  
 42-907  
 42-908  
 42-909  
 42-910  
 42-911  
 42-912  
 42-913  
 42-914  
 42-915  
 42-916  
 42-917  
 42-918  
 42-919  
 42-920  
 42-921  
 42-922  
 42-923  
 42-924  
 42-925  
 42-926  
 42-927  
 42-928  
 42-929  
 42-930  
 42-931  
 42-932  
 42-933  
 42-934  
 42-935  
 42-936  
 42-937  
 42-938  
 42-939  
 42-940  
 42-941  
 42-942  
 42-943  
 42-944  
 42-945  
 42-946  
 42-947  
 42-948  
 42-949  
 42-950  
 42-951  
 42-952  
 42-953  
 42-954  
 42-955  
 42-956  
 42-957  
 42-958  
 42-959  
 42-960  
 42-961  
 42-962  
 42-963  
 42-964  
 42-965  
 42-966  
 42-967  
 42-968  
 42-969  
 42-970  
 42-971  
 42-972  
 42-973  
 42-974  
 42-975  
 42-976  
 42-977  
 42-978  
 42-979  
 42-980  
 42-981  
 42-982  
 42-983  
 42-984  
 42-985  
 42-986  
 42-987  
 42-988  
 42-989  
 42-990  
 42-991  
 42-992  
 42-993  
 42-994  
 42-995  
 42-996  
 42-997  
 42-998  
 42-999  
 43-000



## Problem 9.150

[Difficulty: 4]

**9.150** Motion of a small rocket was analyzed in Example 4.12 assuming negligible aerodynamic drag. This was not realistic at the final calculated speed of 369 m/s. Use the Euler method of Section 5.5 for approximating the first derivatives, in an *Excel* workbook, to solve the equation of motion for the rocket. Plot the rocket speed as a function of time, assuming  $C_D = 0.3$  and a rocket diameter of 700 mm. Compare with the results for  $C_D = 0$ .



**Given:** Data on a rocket

**Find:** Plot of rocket speed with and without drag

**Solution:**

From Example 4.12, with the addition of drag the momentum equation becomes

$$F_{B_y} + F_{S_y} - \int_{CV} a_{r_f y} \rho dV = \frac{\partial}{\partial t} \int_{CV} v_{xyz} \rho dV + \int_{CV} v_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A}$$

where the surface force is

$$F_{S_y} = -\frac{1}{2} \rho A V^2 C_D$$

Following the analysis of the example problem, we end up with

$$\frac{dV_{CV}}{dt} = \frac{V_e \dot{m}_e - \frac{1}{2} \rho A V_{CV}^2 C_D}{M_0 - \dot{m}_e t} - g$$

This can be written (dropping the subscript for convenience)

$$\frac{dV}{dt} = f(V, t) \quad (1)$$

where

$$f(V, t) = \frac{V_e \dot{m}_e - \frac{1}{2} \rho A V^2 C_D}{M_0 - \dot{m}_e t} - g \quad (2)$$

Equation 1 is a differential equation for speed  $V$ .

It can be solved using Euler's numerical method

$$V_{n+1} \approx V_n + \Delta t f_n$$

where  $V_{n+1}$  and  $V_n$  are the  $n + 1^{\text{th}}$  and  $n^{\text{th}}$  values of  $V$ ,  $f_n$  is the function given by Eq. 2 evaluated at the  $n^{\text{th}}$  step, and  $\Delta t$  is the time step.

The initial condition is

$$V_0 = 0 \quad \text{at} \quad t = 0$$

Given or available data:

$$\begin{aligned}
 M_0 &= 400 \text{ kg} \\
 m_e &= 5 \text{ kg/s} \\
 V_e &= 3500 \text{ m/s} \\
 \rho &= 1.23 \text{ kg/m}^3 \\
 D &= 700 \text{ mm} \\
 C_D &= 0.3
 \end{aligned}$$

Computed results:


$$\begin{aligned}
 A &= 0.38 \text{ m}^2 \\
 N &= 20 \\
 \Delta t &= 0.50 \text{ s}
 \end{aligned}$$

**With drag:**

n	$t_n$ (s)	$V_n$ (m/s)	$f_n$	$V_{n+1}$ (m/s)
0	0.0	0.0	33.9	17.0
1	0.5	17.0	34.2	34.1
2	1.0	34.1	34.3	51.2
3	1.5	51.2	34.3	68.3
4	2.0	68.3	34.2	85.5
5	2.5	85.5	34.0	102
6	3.0	102	33.7	119
7	3.5	119	33.3	136
8	4.0	136	32.8	152
9	4.5	152	32.2	168
10	5.0	168	31.5	184
11	5.5	184	30.7	200
12	6.0	200	29.8	214
13	6.5	214	28.9	229
14	7.0	229	27.9	243
15	7.5	243	26.9	256
16	8.0	256	25.8	269
17	8.5	269	24.7	282
18	9.0	282	23.6	293
19	9.5	293	22.5	305
20	10.0	305	21.4	315

**Without drag:**

$V_n$ (m/s)	$f_n$	$V_{n+1}$ (m/s)
0.0	33.9	17.0
17.0	34.2	34.1
34.1	34.5	51.3
51.3	34.8	68.7
68.7	35.1	86.2
86.2	35.4	104
104	35.6	122
122	35.9	140
140	36.2	158
158	36.5	176
176	36.9	195
195	37.2	213
213	37.5	232
232	37.8	251
251	38.1	270
270	38.5	289
289	38.8	308
308	39.1	328
328	39.5	348
348	39.8	368
368	40.2	388



## Problem 9.151

[Difficulty: 4]

**9.151** A baseball is popped straight up with an initial velocity of 25 m/s. The baseball has a diameter of 0.073 m and a mass of 0.143 kg. The drag coefficient for the baseball can be estimated as 0.47 for  $Re < 10^4$  and 0.10 for  $Re > 10^4$ . Determine how long the ball will be in the air and how high it will go.

**Given:** Baseball popped up, drag estimates based on Reynolds number

**Find:** Time of flight and maximum height

**Solution:**

Basic equation: 
$$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2} \quad \Sigma F_y = M \cdot a_y \quad a_y = \frac{dV_y}{dt}$$

Given or available data is  $M = 0.143 \text{ kg}$      $V_{0y} = 25 \frac{\text{m}}{\text{s}}$      $D = 0.073 \text{ m}$

We solve this problem by discretizing the flight of the ball:  $\Delta V_y = a_y \cdot \Delta t = \frac{\Sigma F_y}{M} \cdot \Delta t$      $\Delta y = V_y \cdot \Delta t$

Here are the calculations performed in *Excel*:

Given or available data:

$$\begin{aligned} M &= 0.143 \text{ kg} \\ V_{0y} &= 25 \text{ m/s} \\ D &= 0.073 \text{ m} \\ \rho &= 1.21 \text{ kg/m}^3 \\ \nu &= 1.50\text{E-}05 \text{ m}^2/\text{s} \end{aligned}$$

Computed results:

$$\begin{aligned} A &= 0.00419 \text{ m}^2 \\ \Delta t &= 0.25 \text{ s} \end{aligned}$$


$t_n$ (s)	$y$ (m)	$V_y$ (m/s)	$Re$	$C_D$	$a_y$ (m/s <sup>2</sup> )	$V_{y\text{new}}$ (m/s)
0.00	0.0	25.0	1.22E+05	0.10	-10.917	22.3
0.25	5.9	22.3	1.08E+05	0.10	-10.688	19.6
0.50	11.1	19.6	9.54E+04	0.10	-10.490	17.0
0.75	15.7	17.0	8.26E+04	0.10	-10.320	14.4
1.00	19.6	14.4	7.01E+04	0.10	-10.177	11.9
1.25	22.9	11.9	5.77E+04	0.10	-10.059	9.3
1.50	25.6	9.3	4.54E+04	0.10	-9.964	6.8
1.75	27.6	6.8	3.33E+04	0.10	-9.893	4.4
2.00	29.0	4.4	2.13E+04	0.10	-9.844	1.9
2.25	29.8	1.9	9.30E+03	0.47	-9.840	0.0
2.44	30.0	0.0	0.00E+00	0.47	-9.810	-2.5
2.69	29.7	-2.5	1.19E+04	0.10	-9.799	-4.9
2.94	28.7	-4.9	2.39E+04	0.10	-9.767	-7.3
3.19	27.2	-7.3	3.57E+04	0.10	-9.714	-9.8
3.44	25.1	-9.8	4.76E+04	0.10	-9.641	-12.2
3.69	22.3	-12.2	5.93E+04	0.10	-9.547	-14.6
3.94	19.0	-14.6	7.09E+04	0.10	-9.434	-16.9
4.19	15.0	-16.9	8.24E+04	0.10	-9.303	-19.3
4.44	10.5	-19.3	9.37E+04	0.10	-9.154	-21.5
4.69	5.4	-21.5	1.05E+05	0.10	-8.988	-23.7
4.93	0.0	-23.7	1.15E+05	0.10	-8.816	

The results are plotted below.

The answers are:

$$\begin{aligned} \text{height} &= \boxed{30.0} \text{ m} \\ \text{time} &= \boxed{4.93} \text{ s} \end{aligned}$$

**Trajectory of Baseball**



**9.152** Wiffle™ balls made from light plastic with numerous holes are used to practice baseball and golf. Explain the purpose of the holes and why they work. Explain how you could test your hypothesis experimentally.

**Discussion:** The basic concept of the Wiffle ball is a low-mass, high-drag configuration that can be hit or struck with full force, but will not fly fast or far. Thus the Wiffle ball can be used for practice in a limited space.

The low mass is achieved by making the ball of relatively thin plastic material. This gives it low mass for its size, and is a step toward making the drag force relatively high compared to the weight of the ball.

Even higher drag force is achieved by perforating the surface of the Wiffle ball with numerous large holes. These holes further reduce the mass of the Wiffle ball.

In the sub-critical flow regime (below  $Re_D \approx 2 \times 10^5$ ) skin friction drag accounts for less than 5 percent of the total drag of a sphere. The holes increase the skin friction drag of the ball by allowing boundary-layer fluid to escape into the interior of the ball. Each new bit of surface then sees essentially a new boundary layer developing, with attendant high shear stress.

Pressure drag accounts for the majority of the drag of a sphere at any Reynolds number above about 1000. The holes disrupt the flow pattern around the ball and probably trigger early separation. This ensures that the ball remains in the high-drag sub-critical flow regime no matter what its actual Reynolds number.

This hypothesis could be tested experimentally by comparing the performance of two balls, one with holes and one without. (The balls should have nearly the same mass and diameter.) With the help of an assistant, drop the balls from some height (for example, down a stairwell). After each ball has reached terminal speed, measure the time required for it to fall through a fixed distance. Then calculate and compare the drag coefficients for the two balls. If the drag coefficient for the ball with holes is significantly larger than for the ball without holes, the hypothesis is confirmed.

Several balls of each type might be evaluated experimentally to obtain an idea of the Reynolds number dependence of the results.

500 SHEETS FULLER 4 SQUARE  
42-3811 50 SHEETS EYE-GLASS 4 SQUARE  
100 SHEETS EYE-GLASS 4 SQUARE  
42-3892 100 SHEETS EYE-GLASS 4 SQUARE  
42-3893 100 RECYCLED WHITE 4 SQUARE  
42-3894 200 RECYCLED WHITE 4 SQUARE  
Made in U.S.A.










# Problem 9.155

[Difficulty: 5] Part 1/2

**9.155** Design a wind anemometer that uses aerodynamic ponent. Quantify the relation between wind speed and drag to move or deflect a member or linkage, producing an anemometer output. Present results as a theoretical "calibration curve" of anemometer output versus wind speed. 1 to 10 m/s in standard air. Consider three alternative design Discuss reasons why you rejected the alternative designs and concepts. Select the best concept and prepare a detailed chose your final design concept. design. Specify the shape, size, and material for each com-

**Analysis:** The "target" concept was chosen for analysis. The drag force acting on the target is calculated, then moments are summed about the pivot (see Problem 9.105). The results are:



$$\sum M_o = mgL \sin \alpha - F_D L = 0$$

$$F_D = C_D A \frac{1}{2} \rho (V \cos \alpha)^2 = C_D A \frac{1}{2} \rho V^2 \cos^2 \alpha$$

$$\text{So } C_D A \frac{1}{2} \rho V^2 \cos^2 \alpha = mg \sin \alpha = \rho_m V_m g \sin \alpha = SG \rho_{H_2O} A h g \sin \alpha \tag{1}$$

Assume  $\alpha = 60^\circ$  at highest wind speed (when  $V = 10 \text{ m/s}$ ;  $q = \frac{1}{2} \rho V^2 = 61.5 \text{ N/m}^2$ ).

$$\text{Then } \frac{\sin \alpha}{\cos^2 \alpha} = \frac{C_D A g}{SG \rho_{H_2O} A g h} = \frac{C_D g}{SG \rho_{H_2O} g h} = f(\alpha) \quad \text{At } \alpha = 60^\circ, f(\alpha) = 3.46$$

$$h = \frac{C_D g}{SG \rho_{H_2O} g f(\alpha)} = 1.2 \times 61.5 \frac{\text{N}}{\text{m}^2} \times \frac{\text{m}^3}{\text{m}^3 (SG) 1000 \text{ kg}} \times \frac{\text{s}^2}{9.81 \text{ m}} \times \frac{1}{3.46} \times \frac{\text{kg} \cdot \text{m}}{11.5^2} = \frac{0.00217 \text{ m}}{SG} = \frac{2.17 \text{ mm}}{SG}$$

Choose aluminum, with  $SG = 2.64$  (Table A.1). Then

$$h = \frac{2.17 \text{ mm}}{2.64} = 0.822 \text{ mm}$$

Solve Eq. 1 for velocity

$$V = \left[ \frac{2 SG \rho_{H_2O} h g}{\rho C_D} \times f(\alpha) \right]^{\frac{1}{2}} \quad (\text{see prob})$$

**Discussion:** Concepts considered included a manometer that sensed stagnation pressure, a parallelogram linkage supporting a vertical target, and bending of a thin member in the air stream. The three final concepts chosen were variations on the theme of a single hanging member supported from a single pivot, and were chosen for their simplicity.

The major advantage of the target concept is that different materials can be used for the rod and target; this concept can be tailored to give the largest deflection angle for a given wind speed. Therefore this device should be capable of the most accurate indication at low wind speeds.

Drag force on the target is assumed to depend on the component of wind velocity acting normal to the target. This model could be improved by using actual experimental data for the drag coefficient of a disk at angle of attack.

© 2011 Cengage Learning  
 All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-203  
 National Brand



## Problem 9.156

[Difficulty: 3]

**9.156** A model airfoil of chord 6 in. and span 30 in. is placed in a wind tunnel with an air flow of 100 ft/s (the air is at 70°F). It is mounted on a cylindrical support rod 1 in. in diameter and 10 in. tall. Instruments at the base of the rod indicate a vertical force of 10 lbf and a horizontal force of 1.5 lbf. Calculate the lift and drag coefficients of the airfoil.

**Given:** Data on airfoil and support in wind tunnel, lift and drag measurements

**Find:** Lift and drag coefficients of airfoil

**Solution:**

**Basic equations:**  $C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$

The given or available data is     $L = 6 \cdot \text{in}$        $W = 30 \cdot \text{in}$        $V = 100 \cdot \frac{\text{ft}}{\text{s}}$        $D_{\text{cyl}} = 1 \cdot \text{in}$        $L_{\text{cyl}} = 10 \cdot \text{in}$

$$F_L = 10 \cdot \text{lbf} \qquad F_D = 1.5 \cdot \text{lbf} \qquad \rho = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3} \qquad \nu = 1.63 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$$

We need to determine the cylindrical support's contribution to the total drag force:  $F_D = F_{D_{\text{cyl}}} + F_{D_{\text{airfoil}}}$

Compute the Reynolds number       $Re = \frac{V \cdot D_{\text{cyl}}}{\nu}$        $Re = 5.112 \times 10^4$       Therefore:  $C_{D_{\text{cyl}}} = 1$


So the drag force on the support is:  $F_{D_{\text{cyl}}} = \frac{1}{2} \cdot C_{D_{\text{cyl}}} \cdot \rho \cdot V^2 \cdot L_{\text{cyl}} \cdot D_{\text{cyl}} = 0.809 \cdot \text{lbf}$

So the airfoil drag is:  $F_{D_{\text{airfoil}}} = F_D - F_{D_{\text{cyl}}} = 0.691 \cdot \text{lbf}$       The reference area for the airfoil is:  $A = L \cdot W = 1.25 \cdot \text{ft}^2$

The lift and drag coefficients are:

$$C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} \qquad C_L = 0.687$$

$$C_D = \frac{F_{D_{\text{airfoil}}}}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A} \qquad C_D = 0.0474$$



## Problem 9.157

[Difficulty: 2]

**9.157** An antique airplane carries 50 m of external guy wires stretched normal to the direction of motion. The wire diameter is 5 mm. Estimate the maximum power saving that results from an optimum streamlining of the wires at a plane speed of 175 km/hr in standard air at sea level.

**Given:** Antique airplane guy wires

**Find:** Maximum power saving using optimum streamlining

**Solution:**

Basic equation:  $C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $P = F_D \cdot V$

Given or available data is  $L = 50 \cdot \text{m}$        $D = 5 \cdot \text{mm}$        $V = 175 \cdot \frac{\text{km}}{\text{hr}}$        $V = 48.6 \frac{\text{m}}{\text{s}}$   
 $A = L \cdot D$        $A = 0.25 \text{ m}^2$

$\rho = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$        $\nu = 1.50 \times 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$       (Table A.10, 20°C)

The Reynolds number is  $Re = \frac{V \cdot D}{\nu}$        $Re = 1.62 \times 10^4$       so from Fig. 9.13       $C_D = 1.0$

Hence  $P = \left( C_D \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \right) \cdot V$        $P = 17.4 \cdot \text{kW}$       with standard wires

Figure 9.19 suggests we could reduce the drag coefficient to  $C_D = 0.06$

Hence  $P_{\text{faired}} = \left( C_D \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \right) \cdot V$        $P_{\text{faired}} = 1.04 \cdot \text{kW}$

The maximum power saving is then  $\Delta P = P - P_{\text{faired}}$        $\Delta P = 16.3 \cdot \text{kW}$

Thus  $\frac{\Delta P}{P} = 94. \%$       which is a HUGE savings! It's amazing the antique planes flew!

9.158 Why do modern guns have rifled barrels?

**Discussion:** Almost all projectiles fired by modern guns have smoothly rounded noses and abruptly tapered (“boat-tailed”) or square rear ends. The minimum drag for these shapes is obtained when the projectile travels with its axis parallel to the direction of motion and its nose pointed forward.

Rifling in a gun barrel imparts spin about the longitudinal axis of the projectile. This rotation about the longitudinal axis causes the projectile to act as a gyroscope and stabilizes it during flight to keep its nose pointed in the direction of motion.

Early smoothbore guns primarily used ball projectiles. The balls were spherical and molded from lead. Since the ball shape was spherical and had no preferred orientation, no benefit would have been achieved from rifling that caused spin. Therefore the gun barrels were bored smooth, i.e., without rifling grooves, hence these guns were called “smoothbore” guns.

13 782  
42-381  
42-382  
42-383  
42-384  
42-385  
42-386  
42-387  
42-388  
42-389  
42-390  
42-391  
42-392  
42-393  
42-394  
42-395  
42-396  
42-397  
42-398  
42-399  
42-400  
42-401  
42-402  
42-403  
42-404  
42-405  
42-406  
42-407  
42-408  
42-409  
42-410  
42-411  
42-412  
42-413  
42-414  
42-415  
42-416  
42-417  
42-418  
42-419  
42-420  
42-421  
42-422  
42-423  
42-424  
42-425  
42-426  
42-427  
42-428  
42-429  
42-430  
42-431  
42-432  
42-433  
42-434  
42-435  
42-436  
42-437  
42-438  
42-439  
42-440  
42-441  
42-442  
42-443  
42-444  
42-445  
42-446  
42-447  
42-448  
42-449  
42-450  
42-451  
42-452  
42-453  
42-454  
42-455  
42-456  
42-457  
42-458  
42-459  
42-460  
42-461  
42-462  
42-463  
42-464  
42-465  
42-466  
42-467  
42-468  
42-469  
42-470  
42-471  
42-472  
42-473  
42-474  
42-475  
42-476  
42-477  
42-478  
42-479  
42-480  
42-481  
42-482  
42-483  
42-484  
42-485  
42-486  
42-487  
42-488  
42-489  
42-490  
42-491  
42-492  
42-493  
42-494  
42-495  
42-496  
42-497  
42-498  
42-499  
42-500  
42-501  
42-502  
42-503  
42-504  
42-505  
42-506  
42-507  
42-508  
42-509  
42-510  
42-511  
42-512  
42-513  
42-514  
42-515  
42-516  
42-517  
42-518  
42-519  
42-520  
42-521  
42-522  
42-523  
42-524  
42-525  
42-526  
42-527  
42-528  
42-529  
42-530  
42-531  
42-532  
42-533  
42-534  
42-535  
42-536  
42-537  
42-538  
42-539  
42-540  
42-541  
42-542  
42-543  
42-544  
42-545  
42-546  
42-547  
42-548  
42-549  
42-550  
42-551  
42-552  
42-553  
42-554  
42-555  
42-556  
42-557  
42-558  
42-559  
42-560  
42-561  
42-562  
42-563  
42-564  
42-565  
42-566  
42-567  
42-568  
42-569  
42-570  
42-571  
42-572  
42-573  
42-574  
42-575  
42-576  
42-577  
42-578  
42-579  
42-580  
42-581  
42-582  
42-583  
42-584  
42-585  
42-586  
42-587  
42-588  
42-589  
42-590  
42-591  
42-592  
42-593  
42-594  
42-595  
42-596  
42-597  
42-598  
42-599  
42-600  
42-601  
42-602  
42-603  
42-604  
42-605  
42-606  
42-607  
42-608  
42-609  
42-610  
42-611  
42-612  
42-613  
42-614  
42-615  
42-616  
42-617  
42-618  
42-619  
42-620  
42-621  
42-622  
42-623  
42-624  
42-625  
42-626  
42-627  
42-628  
42-629  
42-630  
42-631  
42-632  
42-633  
42-634  
42-635  
42-636  
42-637  
42-638  
42-639  
42-640  
42-641  
42-642  
42-643  
42-644  
42-645  
42-646  
42-647  
42-648  
42-649  
42-650  
42-651  
42-652  
42-653  
42-654  
42-655  
42-656  
42-657  
42-658  
42-659  
42-660  
42-661  
42-662  
42-663  
42-664  
42-665  
42-666  
42-667  
42-668  
42-669  
42-670  
42-671  
42-672  
42-673  
42-674  
42-675  
42-676  
42-677  
42-678  
42-679  
42-680  
42-681  
42-682  
42-683  
42-684  
42-685  
42-686  
42-687  
42-688  
42-689  
42-690  
42-691  
42-692  
42-693  
42-694  
42-695  
42-696  
42-697  
42-698  
42-699  
42-700  
42-701  
42-702  
42-703  
42-704  
42-705  
42-706  
42-707  
42-708  
42-709  
42-710  
42-711  
42-712  
42-713  
42-714  
42-715  
42-716  
42-717  
42-718  
42-719  
42-720  
42-721  
42-722  
42-723  
42-724  
42-725  
42-726  
42-727  
42-728  
42-729  
42-730  
42-731  
42-732  
42-733  
42-734  
42-735  
42-736  
42-737  
42-738  
42-739  
42-740  
42-741  
42-742  
42-743  
42-744  
42-745  
42-746  
42-747  
42-748  
42-749  
42-750  
42-751  
42-752  
42-753  
42-754  
42-755  
42-756  
42-757  
42-758  
42-759  
42-760  
42-761  
42-762  
42-763  
42-764  
42-765  
42-766  
42-767  
42-768  
42-769  
42-770  
42-771  
42-772  
42-773  
42-774  
42-775  
42-776  
42-777  
42-778  
42-779  
42-780  
42-781  
42-782  
42-783  
42-784  
42-785  
42-786  
42-787  
42-788  
42-789  
42-790  
42-791  
42-792  
42-793  
42-794  
42-795  
42-796  
42-797  
42-798  
42-799  
42-800  
42-801  
42-802  
42-803  
42-804  
42-805  
42-806  
42-807  
42-808  
42-809  
42-810  
42-811  
42-812  
42-813  
42-814  
42-815  
42-816  
42-817  
42-818  
42-819  
42-820  
42-821  
42-822  
42-823  
42-824  
42-825  
42-826  
42-827  
42-828  
42-829  
42-830  
42-831  
42-832  
42-833  
42-834  
42-835  
42-836  
42-837  
42-838  
42-839  
42-840  
42-841  
42-842  
42-843  
42-844  
42-845  
42-846  
42-847  
42-848  
42-849  
42-850  
42-851  
42-852  
42-853  
42-854  
42-855  
42-856  
42-857  
42-858  
42-859  
42-860  
42-861  
42-862  
42-863  
42-864  
42-865  
42-866  
42-867  
42-868  
42-869  
42-870  
42-871  
42-872  
42-873  
42-874  
42-875  
42-876  
42-877  
42-878  
42-879  
42-880  
42-881  
42-882  
42-883  
42-884  
42-885  
42-886  
42-887  
42-888  
42-889  
42-890  
42-891  
42-892  
42-893  
42-894  
42-895  
42-896  
42-897  
42-898  
42-899  
42-900  
42-901  
42-902  
42-903  
42-904  
42-905  
42-906  
42-907  
42-908  
42-909  
42-910  
42-911  
42-912  
42-913  
42-914  
42-915  
42-916  
42-917  
42-918  
42-919  
42-920  
42-921  
42-922  
42-923  
42-924  
42-925  
42-926  
42-927  
42-928  
42-929  
42-930  
42-931  
42-932  
42-933  
42-934  
42-935  
42-936  
42-937  
42-938  
42-939  
42-940  
42-941  
42-942  
42-943  
42-944  
42-945  
42-946  
42-947  
42-948  
42-949  
42-950  
42-951  
42-952  
42-953  
42-954  
42-955  
42-956  
42-957  
42-958  
42-959  
42-960  
42-961  
42-962  
42-963  
42-964  
42-965  
42-966  
42-967  
42-968  
42-969  
42-970  
42-971  
42-972  
42-973  
42-974  
42-975  
42-976  
42-977  
42-978  
42-979  
42-980  
42-981  
42-982  
42-983  
42-984  
42-985  
42-986  
42-987  
42-988  
42-989  
42-990  
42-991  
42-992  
42-993  
42-994  
42-995  
42-996  
42-997  
42-998  
42-999  
43-000



Made in U.S.A.

# Problem 9.159

[Difficulty: 5]

**9.159** How do cab-mounted wind deflectors for tractor-trailer trucks work? Explain using diagrams of the flow pattern around the truck and pressure distribution on the surface of the truck.

**Discussion:** Consider both the cab and the trailer flow patterns and pressure distributions in no-wind and crosswind situations.


**No-wind situation:** Without the deflector, flow separation from the roof and sides of the tractor creates a low-pressure wake and high drag force on the tractor. (Flow patterns and pressure distributions on the tractor and the front of the trailer are sketched below.) The cab-mounted deflector reduces the pressures on the front of the tractor, thus reducing the aerodynamic drag force on the tractor.

Without the deflector, high-speed air separates from the roof of the tractor and impinges on the vertical front face of the trailer. The cab-mounted deflector reduces the amount of high-speed air hitting the front of the trailer, reducing the net aerodynamic drag force on the trailer. (Ideally air from the deflector flows smoothly along the top and sides of the trailer.)


**Crosswind situation:** Without the deflector, flow separates from the lee side of the tractor, altering the pressure field and increasing the drag on the tractor. The cab-mounted deflector, especially in combination with side seals, minimizes the increase in drag by reducing the amount of separation around the tractor.

Without the deflector, the front face of the trailer is impacted by the high-speed air from the freestream flow. Massive separation occurs on the lee side of the trailer, thus altering the pressure field and increasing the drag on the trailer. With the cab-mounted deflector, the amount of high-speed air impacting the trailer is markedly reduced. This alters the flow pattern and minimizes the increase in drag caused by the crosswind.



**Without cab-mounted wind deflector:**



*Trailer face:*



**With cab-mounted wind deflector:**



42-782 500 SHEETS, FILLER, 3 SQUARE  
42-381 50 SHEETS, RELEASER, 3 SQUARE  
42-380 200 SHEETS, RELEASER, 3 SQUARE  
42-382 100 SHEETS, RELEASER, 3 SQUARE  
42-383 100 RECYCLED WHITE, 3 SQUARE  
42-388 200 RECYCLED WHITE, 4 SQUARE  
Made in U.S.A.



## Problem 9.160

[Difficulty: 1]

**9.160** An airplane with an effective lift area of  $25 \text{ m}^2$  is fitted with airfoils of NACA 23012 section (Fig. 9.23). The maximum flap setting that can be used at takeoff corresponds to configuration ② in Fig. 9.23. Determine the maximum gross mass possible for the airplane if its takeoff speed is  $150 \text{ km/hr}$  at sea level (neglect added lift due to ground effect). Find the minimum takeoff speed required for this gross mass if the airplane is instead taking off from Denver (elevation approximately  $1.6 \text{ km}$ ).

Solution: Apply definition of lift coefficient.

Basic equation: 
$$C_L = \frac{F_L}{\frac{1}{2} \rho V^2 A_p}$$

Assumption: Lift force must equal gravity force at takeoff.

$$F_L = mg = C_D A_p \frac{1}{2} \rho V^2$$

For maximum mass, need maximum lift, so use  $C_{L, \max}$ :

$$m_{\max} = \frac{C_{L, \max} A_p \rho V^2}{2g}$$

From Fig. 9.23,  $C_{L, \max} = 2.67$  for condition ②. Then for std. air,

$$m_{\max} = \frac{2.67}{2} \times 25 \text{ m}^2 \times 1.23 \frac{\text{kg}}{\text{m}^3} \left( 150 \times 10^3 \frac{\text{m}}{\text{hr}} \times \frac{\text{hr}}{3600 \text{ s}} \right)^2 \frac{1}{9.81 \text{ m}}$$

$$m_{\max} = 7260 \text{ kg}$$

$m_{\max}$

{ This represents the maximum mass theoretically possible when the aircraft is on the verge of stalling. To attempt takeoff at such a large mass would be ill-advised. }

(b) In Denver,  $z = 1.61 \text{ km}$ . From Table A.3, at  $z = 1.61 \text{ km}$ ,  $\rho/\rho_0 = 0.855$ .

At the same gross mass, the lift force remains the same. Thus

$$F_{L_0} = C_D A \frac{1}{2} \rho_0 V_0^2 = F_{L_D} = C_D A \frac{1}{2} \rho_D V_D^2 \quad \text{or} \quad \rho_0 V_0^2 = \rho_D V_D^2$$

and

$$V_D = V_0 \left( \frac{\rho_0}{\rho_D} \right)^{1/2} = 150 \text{ kph} \left( \frac{1}{0.855} \right)^{1/2} = 162 \text{ kph}$$

$V_D$

{ The takeoff speed must increase about 8 percent. }

## Problem 9.161

[Difficulty: 1]

**9.161** An aircraft is in level flight at 225 km/hr through air at standard conditions. The lift coefficient at this speed is 0.45 and the drag coefficient is 0.065. The mass of the aircraft is 900 kg. Calculate the effective lift area for the craft, and the required engine thrust and power.

**Given:** Aircraft in level flight

**Find:** Effective lift area; Engine thrust and power

**Solution:**

Basic equation:  $C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $P = T \cdot V$

For level, constant speed  $F_D = T$        $F_L = W$

Given or available data is  $V = 225 \cdot \frac{\text{km}}{\text{hr}}$        $V = 62.5 \cdot \frac{\text{m}}{\text{s}}$        $C_L = 0.45$        $C_D = 0.065$        $M = 900 \cdot \text{kg}$   
 $\rho = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$       (Table A.10, 20°C)

Hence  $F_L = C_L \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2 = M \cdot g$        $A = \frac{2 \cdot M \cdot g}{C_L \cdot \rho \cdot V^2}$        $A = 8.30 \cdot \text{m}^2$

Also  $\frac{F_L}{F_D} = \frac{C_L}{C_D}$        $F_L = M \cdot g$        $F_L = 8826 \text{ N}$        $F_D = F_L \cdot \frac{C_D}{C_L}$        $F_D = 1275 \text{ N}$   
 $T = F_D$        $T = 1275 \text{ N}$

The power required is then  $P = T \cdot V$        $P = 79.7 \cdot \text{kW}$

## Problem 9.162


[Difficulty: 2]

**9.162** The foils of a surface-piercing hydrofoil watercraft have a total effective area of  $7.5 \text{ ft}^2$ . Their coefficients of lift and drag are 1.5 and 0.63, respectively. The total weight of the craft in running trim is 4000 lb. Determine the minimum speed at which the craft is supported by the hydrofoils. At this speed, find the power required to overcome water resistance. If the craft is fitted with a 150-hp engine, estimate its top speed.

**Given:** Data on a hydrofoil

**Find:** Minimum speed, power required, top speed

**Solution:**



**Assumption:** The drag on the hydrofoil is much greater than any other drag force on the craft once the foil supports the craft.

The given data or available data is  $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$      $A = 7.5 \text{ ft}^2$      $C_L = 1.5$      $C_D = 0.63$      $W = 4000 \text{ lbf}$      $P_{\text{max}} = 150 \text{ hp}$

To support the hydrofoil, the lift force must equal the weight:  $F_L = W = 4000 \text{ lbf}$

Based on the required lift force, the speed must be:  $V_{\text{min}} = \sqrt{\frac{2 \cdot F_L}{\rho \cdot A \cdot C_L}}$      $V_{\text{min}} = 19.1 \cdot \frac{\text{ft}}{\text{s}}$

The drag force at this speed is  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V_{\text{min}}^2 \cdot C_D$      $F_D = 1680 \cdot \text{lbf}$

Engine thrust required  $T = F_D$      $T = 1680 \cdot \text{lbf}$

The power required is  $P = T \cdot V_{\text{min}}$      $P = 58.5 \cdot \text{hp}$

As the speed increases, the lift will increase such that the lift and weight are still balanced. Therefore:

$P_{\text{max}} = \frac{C_D}{C_L} \cdot W \cdot V_{\text{max}}$     Solving for the maximum speed:  $V_{\text{max}} = \frac{P_{\text{max}}}{W} \cdot \frac{C_L}{C_D}$      $V_{\text{max}} = 49.1 \cdot \frac{\text{ft}}{\text{s}}$

## Problem 9.163

[Difficulty: 2]

**9.163** A high school project involves building a model ultralight airplane. Some of the students propose making an airfoil from a sheet of plastic 5 ft long  $\times$  7 ft wide at an angle of attack of  $10^\circ$ . At this airfoil's aspect ratio and angle of attack the lift and drag coefficients are  $C_L = 0.75$  and  $C_D = 0.19$ . If the airplane is designed to fly at 40 ft/s, what is the maximum total payload? What will be the required power to maintain flight? Does this proposal seem feasible?

**Given:** Data on an airfoil

**Find:** Maximum payload; power required

**Solution:**

The given data or available data is  $\rho = 0.00234 \frac{\text{slug}}{\text{ft}^3}$   $L = 5 \cdot \text{ft}$   $w = 7 \cdot \text{ft}$   $V = 40 \frac{\text{ft}}{\text{s}}$   $C_L = 0.75$   $C_D = 0.19$

Then  $A = w \cdot L$   $A = 35 \cdot \text{ft}^2$

The governing equations for steady flight are  $W = F_L$  and  $T = F_D$

where  $W$  is the model total weight and  $T$  is the thrust

The lift is given by  $F_L = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L$   $F_L = 49.1 \cdot \text{lbf}$

The payload is then given by  $W = M \cdot g = F_L$

or  $M = \frac{F_L}{g}$   $M = 49.1 \cdot \text{lb}$

The drag is given by  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$   $F_D = 12.4 \cdot \text{lbf}$

Engine thrust required  $T = F_D$   $T = 12.4 \cdot \text{lbf}$

The power required is  $P = T \cdot V$   $P = 498 \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $P = 0.905 \text{hp}$

The ultralight model is just feasible: it is possible to find an engine that can produce about 1 hp that weighs less than about 50 lb.

## Problem 9.164

[Difficulty: 3]

**9.164** The U.S. Air Force F-16 fighter aircraft has wing planform area  $A = 300 \text{ ft}^2$ ; it can achieve a maximum lift coefficient of  $C_L = 1.6$ . When fully loaded, its weight is 26,000 lb. The airframe is capable of maneuvers that produce  $9g$  vertical accelerations. However, student pilots are restricted to  $5g$  maneuvers during training. Consider a turn flown in level flight with the aircraft banked. Find the minimum speed in standard air at which the pilot can produce a  $5g$  total acceleration. Calculate the corresponding flight radius. Discuss the effect of altitude on these results.

**Given:** Data on F-16 fighter

**Find:** Minimum speed at which pilot can produce  $5g$  acceleration; flight radius, effect of altitude on results

**Solution:**


The given data or available data is  $\rho = 0.00234 \frac{\text{slug}}{\text{ft}^3}$   $A = 300 \cdot \text{ft}^2$   $C_L = 1.6$   $W = 26000 \cdot \text{lbf}$

At  $5g$  acceleration, the corresponding force is:

$$F_L = 5 \cdot W = 130000 \cdot \text{lbf}$$

The minimum velocity corresponds to the maximum lift coefficient:

$$V_{\min} = \sqrt{\frac{2 \cdot F_L}{\rho \cdot A \cdot C_L}} = 481 \frac{\text{ft}}{\text{s}}$$



$$V_{\min} = 481 \frac{\text{ft}}{\text{s}}$$

To find the flight radius, we perform a vertical force balance:  $F_L \cdot \sin(90\text{-deg} - \beta) - W = 0$   $\beta = 90\text{-deg} - \text{asin}\left(\frac{W}{F_L}\right) = 78.5\text{deg}$

Now set the horizontal force equal to the centripetal acceleration:  $F_L \cdot \cos(90\text{-deg} - \beta) = \frac{W}{g} \cdot a_c$

$$a_c = g \cdot \frac{F_L}{W} \cdot \cos(90\text{-deg} - \beta) \quad a_c = 157.6 \frac{\text{ft}}{\text{s}^2}$$

The flight radius corresponding to this acceleration is:  $R = \frac{V_{\min}^2}{a_c}$   $R = 1469\text{-ft}$

As altitude increases, the density decreases, and both the velocity and radius will increase.

## Problem 9.165

[Difficulty: 3]

**9.165** The teacher of the students designing the airplane of Problem 9.163 is not happy with the idea of using a sheet of plastic for the airfoil. He asks the students to evaluate the expected maximum total payload, and required power to maintain flight, if the sheet of plastic is replaced with a conventional section (NACA 23015) airfoil with the same aspect ratio and angle of attack. What are the results of the analysis?

**Given:** Data on an airfoil

**Find:** Maximum payload; power required

**Solution:**

The given data or available data is  $V = 40 \cdot \frac{\text{ft}}{\text{s}}$        $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$        $c = 5 \cdot \text{ft}$        $b = 7 \cdot \text{ft}$

Then the area is  $A = b \cdot c$        $A = 35.00 \cdot \text{ft}^2$

and the aspect ratio is  $\text{ar} = \frac{b}{c}$        $\text{ar} = 1.4$

The governing equations for steady flight are

$$W = F_L \quad \text{and} \quad T = F_D$$

where  $W$  is the model total weight and  $T$  is the thrust

At a  $10^\circ$  angle of attack, from Fig. 9.17  $C_L = 1.2$        $C_{Di} = 0.010$

where  $C_{Di}$  is the section drag coefficient

The wing drag coefficient is given by Eq. 9.42  $C_D = C_{Di} + \frac{C_L^2}{\pi \cdot \text{ar}}$        $C_D = 0.337$

The lift is given by  $F_L = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L$        $F_L = 78.6 \cdot \text{lbf}$

The payload is then given by  $W = M \cdot g = F_L$

or  $M = \frac{F_L}{g}$        $M = 78.6 \cdot \text{lb}$

The drag is given by  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$        $F_D = 22.1 \cdot \text{lbf}$

Engine thrust required  $T = F_D$        $T = 22.1 \cdot \text{lbf}$

The power required is  $P = T \cdot V$        $P = 1.61 \cdot \text{hp}$

NOTE: Strictly speaking we have TWO extremely stubby wings, so a recalculation of drag effects (lift is unaffected) gives

$$b = 3.5 \cdot \text{ft} \quad c = 5.00 \cdot \text{ft}$$

and  $A = b \cdot c$        $A = 1.63 \text{ m}^{2.00}$        $\text{ar} = \frac{b}{c}$        $\text{ar} = 0.70$

so the wing drag coefficient is

$$C_D = C_{Di} + \frac{C_L^2}{\pi \cdot ar} \quad C_D = 0.665$$

The drag is

$$F_D = 2 \cdot \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D \quad F_D = 43.6 \cdot \text{lbf}$$

Engine thrust is

$$T = F_D \quad T = 43.6 \cdot \text{lbf}$$

The power required is

$$P = T \cdot V \quad P = 3.17 \cdot \text{hp}$$

In this particular case it would seem that the ultralight model makes more sense - we need a smaller engine and smaller lift requirements. However, on a per unit weight basis, the motor required for this aircraft is actually *smaller*. In other words, it should probably be easier to find a 3.5 hp engine that weighs less than 80 lb (22.9 lb/hp) than a 1 hp engine that weighs less than 50 lb (50 lb/hp).

## Problem 9.166

[Difficulty: 3]

**9.166** A light airplane, with mass  $M = 1000$  kg, has a conventional-section (NACA 23015) wing of planform area  $A = 10$  m<sup>2</sup>. Find the angle of attack of the wing for a cruising speed of  $V = 63$  m/s. What is the required power? Find the maximum instantaneous vertical "g force" experienced at cruising speed if the angle of attack is suddenly increased.

**Given:** Data on a light airplane

**Find:** Angle of attack of wing; power required; maximum "g" force

**Solution:**

The given data or available data is

$\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$	$M = 1000 \cdot \text{kg}$	$A = 10 \cdot \text{m}^2$
$V = 63 \cdot \frac{\text{m}}{\text{s}}$	$C_L = 0.72$	$C_D = 0.17$

The governing equations for steady flight are  $W = M \cdot g = F_L$   
 $T = F_D$

where  $W$  is the weight  $T$  is the engine thrust

The lift coefficient is given by  $F_L = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L$

Hence the required lift coefficient is  $C_L = \frac{M \cdot g}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$   
 $C_L = 0.402$

From Fig 9.17, for at this lift coefficient  $\alpha = 3 \cdot \text{deg}$

and the drag coefficient at this angle of attack is  $C_D = 0.0065$

(Note that this does NOT allow for aspect ratio effects on lift and drag!)

Hence the drag is  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$   
 $F_D = 159$  N

and  $T = F_D$   
 $T = 159$  N

The power required is then  $P = T \cdot V$   
 $P = 10 \cdot \text{kW}$

The maximum "g"s occur when the angle of attack is suddenly increased to produce the maximum lift

From Fig. 9.17  $C_{L,max} = 1.72$

$F_{L,max} = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_{L,max}$   
 $F_{L,max} = 42 \cdot \text{kN}$

The maximum "g"s are given by application of Newton's second law

$$M \cdot a_{\text{perp}} = F_{L,max}$$

where  $a_{\text{perp}}$  is the acceleration perpendicular to the flight direction

Hence

$$a_{\text{perp}} = \frac{F_{L\text{max}}}{M} \qquad a_{\text{perp}} = 42 \frac{\text{m}}{\text{s}^2}$$

In terms of "g"s

$$\frac{a_{\text{perp}}}{g} = 4.28$$

Note that this result occurs when the airplane is banking at  $90^\circ$ , i.e, when the airplane is flying momentarily in a circular flight path in the horizontal plane. For a straight horizontal flight path Newton's second law is

$$M \cdot a_{\text{perp}} = F_{L\text{max}} - M \cdot g$$

Hence

$$a_{\text{perp}} = \frac{F_{L\text{max}}}{M} - g \qquad a_{\text{perp}} = 32.2 \frac{\text{m}}{\text{s}^2}$$

In terms of "g"s

$$\frac{a_{\text{perp}}}{g} = 3.28$$

## Problem 9.167

[Difficulty: 3]

**9.167** A light airplane has 35-ft effective wingspan and 5.5-ft chord. It was originally designed to use a conventional (NACA 23015) airfoil section. With this airfoil, its cruising speed on a standard day near sea level is 150 mph. A conversion to a laminar-flow (NACA 66<sub>2</sub>-215) section airfoil is proposed. Determine the cruising speed that could be achieved with the new airfoil section for the same power.

**Given:** Data on a light airplane

**Find:** Cruising speed achieved using a new airfoil design

**Solution:**

The given data or available data is  $V = 150 \cdot \text{mph} = 220.00 \cdot \frac{\text{ft}}{\text{s}}$      $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$      $c = 5.5 \cdot \text{ft}$      $b = 35 \cdot \text{ft}$

Then the area is  $A = b \cdot c$                        $A = 192.50 \cdot \text{ft}^2$

and the aspect ratio is  $\text{ar} = \frac{b}{c}$                        $\text{ar} = 6.36$

The governing equations for steady flight are

$$W = F_L \quad \text{and} \quad T = F_D$$

where  $W$  is the total weight and  $T$  is the thrust

For the NACA 23015 airfoil:  $C_L = 0.3$                        $C_{Di} = 0.0062$

where  $C_{Di}$  is the section drag coefficient

The wing drag coefficient is given by Eq. 9.42  $C_D = C_{Di} + \frac{C_L^2}{\pi \cdot \text{ar}}$                        $C_D = 0.011$

The drag is given by  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$                        $F_D = 116.7 \cdot \text{lbf}$

Engine thrust required  $T = F_D$                        $T = 116.7 \cdot \text{lbf}$

The power required is  $P = T \cdot V$                        $P = 46.66 \cdot \text{hp}$

For the NACA 66<sub>2</sub>-215 airfoil:  $C_L = 0.2$                        $C_{Di} = 0.0031$

The wing drag coefficient is given by Eq. 9.42  $C_D = C_{Di} + \frac{C_L^2}{\pi \cdot \text{ar}}$                        $C_D = 5.101 \times 10^{-3}$

The power is:  $P = \frac{1}{2} \cdot \rho \cdot A \cdot V^3 \cdot C_D$  so the new speed is:  $V_{\text{new}} = \sqrt[3]{\frac{2 \cdot P}{\rho \cdot A \cdot C_D}}$                        $V_{\text{new}} = 282 \cdot \frac{\text{ft}}{\text{s}}$                        $V_{\text{new}} = 192.0 \cdot \text{mph}$

## Problem 9.168

[Difficulty: 3]

**9.168** Instead of a new laminar-flow airfoil, a redesign of the light airplane of Problem 9.167 is proposed in which the current conventional airfoil section is replaced with another conventional airfoil section of the same area, but with aspect ratio  $AR = 8$ . Determine the cruising speed that could be achieved with this new airfoil for the same power.

**Given:** Data on an airfoil

**Find:** Maximum payload; power required

**Solution:**

The given data or available data is  $V_{\text{old}} = 150 \cdot \text{mph}$   $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$   $A = 192.5 \cdot \text{ft}^2$   $ar_{\text{old}} = \frac{35}{5.5}$   $ar_{\text{old}} = 6.36$

Assuming the old airfoil operates at close to design lift, from Fig. 9.19  $C_L = 0.3$   $C_{D_i} = 0.0062$  ( $C_{D_i}$  is the old airfoil's section drag coefficient)

Then 
$$C_{D_{\text{old}}} = C_{D_i} + \frac{C_L^2}{\pi \cdot ar_{\text{old}}} \quad C_{D_{\text{old}}} = 0.0107$$

The new wing aspect ratio is  $ar_{\text{new}} = 8$

Hence 
$$C_{D_{\text{new}}} = C_{D_i} + \frac{C_L^2}{\pi \cdot ar_{\text{new}}} \quad C_{D_{\text{new}}} = 0.00978$$

The power required is  $P = T \cdot V = F_D \cdot V = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D \cdot V$

If the old and new designs have the same available power, then

$$\frac{1}{2} \cdot \rho \cdot A \cdot V_{\text{new}}^2 \cdot C_{D_{\text{new}}} \cdot V_{\text{new}} = \frac{1}{2} \cdot \rho \cdot A \cdot V_{\text{old}}^2 \cdot C_{D_{\text{old}}} \cdot V_{\text{old}}$$

or 
$$V_{\text{new}} = V_{\text{old}} \cdot \sqrt[3]{\frac{C_{D_{\text{old}}}}{C_{D_{\text{new}}}}} \quad V_{\text{new}} = 227 \cdot \frac{\text{ft}}{\text{s}}$$

### Problem 9.169

[Difficulty: 3]

**9.169** Assume the Boeing 727 aircraft has wings with NACA 23012 section, planform area of  $1600 \text{ ft}^2$ , double-slotted flaps, and effective aspect ratio of 6.5. If the aircraft flies at 150 knots in standard air at 175,000 lb gross weight, estimate the thrust required to maintain level flight.

Solution: For steady, level flight, thrust equals drag and lift equals weight.

$$\text{Computing equations: } F_L = W = C_L \frac{1}{2} \rho V^2 A \quad (1)$$

$$F_D = T = C_D \frac{1}{2} \rho V^2 A \quad (2)$$

$$C_D = C_{D,0} + C_{D,i} = C_{D,0} + \frac{C_L^2}{\pi ar}$$

Assumptions: (1) Standard air.  
(2) Data from Fig. 9.23 apply

$$V = 150 \frac{\text{nm}}{\text{hr}} \times \frac{6076 \text{ ft}}{\text{nm}} \times \frac{\text{hr}}{3600 \text{ sec}} = 253 \text{ ft/sec}$$

$$q = \frac{1}{2} \rho V^2 = \frac{1}{2} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (253)^2 \frac{\text{ft}^2}{\text{s}^2} \times \frac{\text{bf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} = 76.2 \text{ lbf/ft}^2$$

$$\text{From Eq. 1, } C_L = \frac{W}{qA} = \frac{175000 \text{ lbf}}{76.2 \text{ lbf/ft}^2 \times 1600 \text{ ft}^2} = 1.44$$

From Fig. 9.23, this corresponds to operation with a single slot open, and  $C_{D,0} \approx 0.04$ . Thus

$$C_D = C_{D,0} + \frac{C_L^2}{\pi ar} = 0.04 + \frac{(1.44)^2}{\pi(6.5)} = 0.142$$

To find thrust, note

$$\frac{T}{F_L} = \frac{C_D}{C_L} \frac{qA}{qA} = \frac{C_D}{C_L} = \frac{0.142}{1.44} = 0.0986$$

Thus

$$T = F_L \frac{C_D}{C_L} = W \frac{C_D}{C_L} = 175,000 \text{ lbf} \times 0.0986 = 17,300 \text{ lbf}$$

T

## Problem 9.170

[Difficulty: 3]

**9.170** An airplane with mass of 10,000 lb is flown at constant elevation and speed on a circular path at 150 mph. The flight circle has a radius of 3250 ft. The plane has lifting area of 225 ft<sup>2</sup> and is fitted with NACA 23015 section airfoils with effective aspect ratio of 7. Estimate the drag on the aircraft and the power required.

**Given:** Aircraft in circular flight

**Find:** Drag and power

**Solution:**

Basic equations:  $C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $P = F_D \cdot V$        $\Sigma \vec{F} = M \cdot \vec{a}$

The given data or available data are

$\rho = 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3}$	$R = 3250 \cdot \text{ft}$	$M = 10000 \cdot \text{lbm}$	$M = 311 \cdot \text{slug}$
$V = 150 \cdot \text{mph}$	$V = 220 \cdot \frac{\text{ft}}{\text{s}}$	$A = 225 \cdot \text{ft}^2$	$ar = 7$

Assuming the aircraft is flying banked at angle  $\beta$ , the vertical force balance is

$$F_L \cdot \cos(\beta) - M \cdot g = 0 \quad \text{or} \quad \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L \cdot \cos(\beta) = M \cdot g \quad (1)$$

The horizontal force balance is

$$-F_L \cdot \sin(\beta) = M \cdot a_r = -\frac{M \cdot V^2}{R} \quad \text{or} \quad \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L \cdot \sin(\beta) = \frac{M \cdot V^2}{R} \quad (2)$$

Equations 1 and 2 enable the bank angle  $\beta$  to be found  $\tan(\beta) = \frac{V^2}{R \cdot g}$   $\beta = \text{atan}\left(\frac{V^2}{R \cdot g}\right)$   $\beta = 24.8 \cdot \text{deg}$

Then from Eq 1  $F_L = \frac{M \cdot g}{\cos(\beta)}$   $F_L = 1.10 \times 10^4 \cdot \text{lbf}$

Hence  $C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$   $C_L = 0.851$

For the section,  $C_{Dinf} = 0.0075$  at  $C_L = 0.851$  (from Fig. 9.19), so  $C_D = C_{Dinf} + \frac{C_L^2}{\pi \cdot ar}$   $C_D = 0.040$

Hence  $F_D = F_L \cdot \frac{C_D}{C_L}$   $F_D = 524 \cdot \text{lbf}$

The power is  $P = F_D \cdot V$   $P = 1.15 \times 10^5 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $P = 209 \cdot \text{hp}$

## Problem 9.171

[Difficulty: 4]

**9.171** Find the minimum and maximum speeds at which the airplane of Problem 9.170 can fly on a 3250 ft radius circular flight path, and estimate the drag on the aircraft and power required at these extremes.

**Given:** Aircraft in circular flight

**Find:** Maximum and minimum speeds; Drag and power at these extremes

**Solution:**

Basic equations:  $C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $P = F_D \cdot V$        $\Sigma \vec{F} = M \cdot \vec{a}$

The given data or available data are

$$\rho = 0.002377 \frac{\text{slug}}{\text{ft}^3} \quad R = 3250 \cdot \text{ft} \quad M = 10000 \cdot \text{lbm} \quad M = 311 \cdot \text{slug}$$

$$A = 225 \cdot \text{ft}^2 \quad ar = 7$$

The minimum velocity will be when the wing is at its maximum lift condition. From Fig. 9.17 or Fig. 9.19

$$C_L = 1.72 \quad C_{Dinf} = 0.02$$

where  $C_{Dinf}$  is the section drag coefficient

The wing drag coefficient is then  $C_D = C_{Dinf} + \frac{C_L^2}{\pi \cdot ar}$        $C_D = 0.155$

Assuming the aircraft is flying banked at angle  $\beta$ , the vertical force balance is

$$F_L \cdot \cos(\beta) - M \cdot g = 0 \quad \text{or} \quad \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L \cdot \cos(\beta) = M \cdot g \quad (1)$$

The horizontal force balance is

$$-F_L \cdot \sin(\beta) = M \cdot a_r = -\frac{M \cdot V^2}{R} \quad \text{or} \quad \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L \cdot \sin(\beta) = \frac{M \cdot V^2}{R} \quad (2)$$

Equations 1 and 2 enable the bank angle  $\beta$  and the velocity  $V$  to be determined

$$\sin(\beta)^2 + \cos(\beta)^2 = \left( \frac{\frac{M \cdot V^2}{R}}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L} \right)^2 + \left( \frac{M \cdot g}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L} \right)^2 = 1$$

or  $\frac{M^2 \cdot V^4}{R^2} + M^2 \cdot g^2 = \frac{\rho^2 \cdot A^2 \cdot V^4 \cdot C_L^2}{4}$

$$V = \sqrt[4]{\frac{M^2 \cdot g^2}{\frac{\rho^2 \cdot A^2 \cdot C_L^2}{4} - \frac{M^2}{R^2}}} \quad V = 149 \frac{\text{ft}}{\text{s}} \quad V = 102 \cdot \text{mph}$$

$$\tan(\beta) = \frac{V^2}{R \cdot g} \quad \beta = \text{atan} \left( \frac{V^2}{R \cdot g} \right) \quad \beta = 12.0 \cdot \text{deg}$$

The drag is then  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$   $F_D = 918 \cdot \text{lbf}$

The power required to overcome drag is  $P = F_D \cdot V$   $P = 1.37 \times 10^5 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $P = 249 \cdot \text{hp}$

The analysis is repeated for the maximum speed case, when the lift/drag coefficient is at its minimum value. From Fig. 9.19, reasonable values are

$C_L = 0.3$   $C_{Dinf} = \frac{C_L}{47.6}$  corresponding to  $\alpha = 2^\circ$  (Fig. 9.17)

The wing drag coefficient is then  $C_D = C_{Dinf} + \frac{C_L^2}{\pi \cdot ar}$   $C_D = 0.0104$

From Eqs. 1 and 2  $V = \sqrt[4]{\frac{M^2 \cdot g^2}{\frac{\rho^2 \cdot A^2 \cdot C_L^2}{4} - \frac{M^2}{R^2}}}$   $V = (309.9 + 309.9i) \cdot \frac{\text{ft}}{\text{s}}$  Obviously unrealistic (lift is just too low, and angle of attack is too low to generate sufficient lift)

We try instead a larger, more reasonable, angle of attack

$C_L = 0.55$   $C_{Dinf} = 0.0065$  corresponding to  $\alpha = 4^\circ$  (Fig. 9.17)

The wing drag coefficient is then  $C_D = C_{Dinf} + \frac{C_L^2}{\pi \cdot ar}$   $C_D = 0.0203$

From Eqs. 1 and 2  $V = \sqrt[4]{\frac{M^2 \cdot g^2}{\frac{\rho^2 \cdot A^2 \cdot C_L^2}{4} - \frac{M^2}{R^2}}}$   $V = 91.2 \cdot \frac{\text{m}}{\text{s}}$   $V = 204 \cdot \text{mph}$

$\tan(\beta) = \frac{V^2}{R \cdot g}$   $\beta = \text{atan}\left(\frac{V^2}{R \cdot g}\right)$   $\beta = 40.6 \cdot \text{deg}$

The drag is then  $F_D = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_D$   $F_D = 485 \cdot \text{lbf}$

The power required to overcome drag is  $P = F_D \cdot V$   $P = 1.45 \times 10^5 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $P = 264 \cdot \text{hp}$

## Problem 9.172

[Difficulty: 3]

9.172 Jim Hall's Chaparral 2F sports-racing cars in the 1960s pioneered use of airfoils mounted above the rear suspension to enhance stability and improve braking performance. The airfoil was effectively 6 ft wide (span) and had a 1-ft chord. Its angle of attack was variable between 0 and minus 12 degrees. Assume lift and drag coefficient data are given by curves (for conventional section) in Fig. 9.17. Consider a car speed of 120 mph on a calm day. For an airfoil deflection of 12° down, calculate (a) the maximum downward force and (b) the maximum increase in deceleration force produced by the airfoil.

Solution: Apply definitions of  $C_L$  and  $C_D$ .

Computing equations:  $C_L = \frac{F_L}{\frac{1}{2}\rho V^2 A}$      $C_D = \frac{F_D}{\frac{1}{2}\rho V^2 A} = C_{D,0} + \frac{C_L^2}{\pi \alpha r}$      $\alpha r = \frac{s}{c}$

From Fig. 9.17, at  $\alpha = 12^\circ$ ,  $C_L = 1.4$  and  $C_{D,0} = 0.013$ . Thus, since  $\alpha = -12^\circ$ ,

$$F_L = -C_L A \frac{1}{2} \rho V^2 \quad A = 5c = 6 \text{ ft}^2$$

$$= -1.4 \times 6 \text{ ft}^2 \times \frac{1}{2} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times \left( 120 \frac{\text{mi}}{\text{hr}} \times \frac{5280 \text{ ft}}{\text{mi}} \times \frac{\text{hr}}{3600 \text{ s}} \right)^2 \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$F_L = -310 \text{ lbf (downward force)}$$

$F_L$

$$\text{Then } F_D = F_L \frac{C_D}{C_L} = \frac{0.013 + \frac{(1.4)^2}{\pi(6)}}{1.4} \times 310 \text{ lbf} = 25.9 \text{ lbf}$$

Braking thrust increases as drag increases and as normal force increases tire adhesion (friction). Thus

$$\Delta F_B = \mu_k F_L + F_D$$

For  $\mu_k = 1.0$  (probably conservative for racing tires),

$$\Delta F_B = 1.0 \times 310 \text{ lbf} + 25.9 \text{ lbf} = 336 \text{ lbf}$$


$\Delta F_B$

### Problem 9.173

[Difficulty: 4]

**9.173** The glide angle for unpowered flight is such that lift, drag, and weight are in equilibrium. Show that the glide slope angle,  $\theta$ , is such that  $\tan \theta = C_D/C_L$ . The minimum glide slope occurs at the speed where  $C_L/C_D$  is a maximum. For the conditions of Example 9.8, evaluate the minimum glide slope angle for a Boeing 727-200. How far could this aircraft glide from an initial altitude of 10 km on a standard day?

Solution: Consider free-body diagram:



Sum forces along (x) and normal to (y) flight path:

$$\left. \begin{aligned} \Sigma F_x &= -F_D + mg \sin \theta = 0 & mg \sin \theta &= F_D \\ \Sigma F_y &= F_L - mg \cos \theta = 0 & mg \cos \theta &= F_L \end{aligned} \right\} \tan \theta = \frac{F_D}{F_L} = \frac{C_D}{C_L}$$

Use relationships from Section 9-8:

Computing equation:  $C_D = C_{D,0} + \frac{C_L^2}{\pi a r} = C_{D,0} + C_{D,i}$

Thus  $\frac{C_D}{C_L} = \frac{C_{D,0}}{C_L} + \frac{C_L}{\pi a r}$  (1)

To minimize, set  $d(C_D/C_L)/dC_L = 0$

$$\frac{d}{dC_L} \left( \frac{C_D}{C_L} \right) = (-1) \frac{C_{D,0}}{C_L^2} + \frac{1}{\pi a r} = 0 \quad \text{when} \quad C_{D,0} = \frac{C_L^2}{\pi a r} = C_{D,i}$$


From Example Problem 9.8,  $C_{D,0} = 0.0182$  and  $a r = 6.5$ . Thus optimum is

$$C_L = (\pi a r C_{D,0})^{1/2} = [\pi(6.5)0.0182]^{1/2} = 0.610$$

and from Eq. 1,

$$\frac{C_D}{C_L} = \frac{0.0182}{0.61} + \frac{0.61}{\pi(6.5)} = 0.0597 = \tan \theta ; \theta = \tan^{-1}(0.0597) = 3.42^\circ$$

Note  $\theta$  is independent of atmospheric conditions. Thus  $\theta = \text{constant}$



$$\frac{z_0}{L} = \tan \theta ; L = \frac{z_0}{\tan \theta} = \frac{10 \text{ km}}{0.0597} = 168 \text{ km}$$

**9.174** The wing loading of the Gossamer Condor is 0.4 lbf/ft<sup>2</sup> of wing area. Crude measurements showed drag was approximately 6 lbf at 12 mph. The total weight of the Condor was 200 lbf. The effective aspect ratio of the Condor is 17. Estimate the minimum power required to fly the aircraft. Compare to the 0.39 hp that pilot Brian Allen could sustain for 2 hr.

Solution: Apply relationships from Section 9-8:

Computing equations:  $W = F_L = C_L A \frac{1}{2} \rho V^2$        $P = V F_D$

$$T = F_D = C_D A \frac{1}{2} \rho V^2 ; C_D = C_{D,0} + \frac{C_L^2}{\pi \text{ar}}$$

The task is to find  $V$  to minimize  $P$ :

$$P = V F_D = V (C_D A \frac{1}{2} \rho V^2) = (C_{D,0} + \frac{C_L^2}{\pi \text{ar}}) A \frac{1}{2} \rho V^3 \tag{1}$$

But  $C_L$  varies with aircraft speed:

$$F_L = W = C_L A \frac{1}{2} \rho V^2 ; C_L = \frac{2W}{\rho V^2 A} ; C_L^2 = (\frac{2W}{\rho A})^2 \frac{1}{V^4}$$

Substituting into Eq. 1,

$$P = \left[ C_{D,0} + \frac{1}{\pi \text{ar}} \left( \frac{2W}{\rho A} \right)^2 \frac{1}{V^4} \right] A \frac{1}{2} \rho V^3$$

To minimize power, set  $dP/dV = 0$ . Then

$$\frac{dP}{dV} = C_{D,0} A \frac{1}{2} \rho V^2 (3) + (-1) \frac{1}{\pi \text{ar}} \left( \frac{2W}{\rho A} \right)^2 \frac{1}{V^5} A \frac{1}{2} \rho = 0$$

Thus at minimum power,

$$3 C_{D,0} = \frac{1}{\pi \text{ar}} \left( \frac{2W}{\rho A} \right)^2 \frac{1}{V^4} = \frac{C_L^2}{\pi \text{ar}} = C_{D,i} \quad \text{or} \quad C_{D,i} = 3 C_{D,0} \quad \begin{array}{l} \text{minimum} \\ \text{power} \end{array}$$

From given data, at 12 mph (17.6 ft/s):

$$\frac{1}{2} \rho V^2 = \frac{1}{2} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (17.6)^2 \frac{\text{ft}^2}{\text{s}^2} \times \frac{1 \text{ lbf} \cdot \text{s}^2}{32 \text{ slug} \cdot \text{ft}} = 0.369 \text{ lbf/ft}^2$$

$$C_L = \frac{F_L}{\frac{1}{2} \rho V^2 A} = \frac{W/A}{\frac{1}{2} \rho V^2} = \frac{0.4 \text{ lbf}}{\text{ft}^2} \times \frac{\text{ft}^2}{0.369 \text{ lbf}} = 1.08 ; A = \frac{W}{W/A} = \frac{200 \text{ lbf}}{0.4 \text{ lbf}} = 500 \text{ ft}^2$$

$$C_D = \frac{F_D}{\frac{1}{2} \rho V^2 A} = \frac{6 \text{ lbf}}{\text{ft}^2} \times \frac{\text{ft}^2}{0.369 \text{ lbf} \times 500 \text{ ft}^2} = 0.0325$$

$$C_{D,0} = C_D - C_{D,i} = C_D - \frac{C_L^2}{\pi \text{ar}} = 0.0325 - \frac{(1.08)^2}{\pi (17)} = 0.0107 \quad (C_{D,0} = \text{constant})$$

At flight speed for minimum power,  $C_{D,i} = 3 C_{D,0}$

# Problem 9.174

[Difficulty: 5] Part 2/2

Thus at minimum power

$$C_{D,i} = \frac{C_L^2}{\pi a r} = 3C_{D,0} = 3(0.0107) = 0.0321$$

so

$$C_L = (0.0321 \pi a r)^{1/2} = 1.31 \quad (\text{minimum power})$$

since

$$F_L = W = C_L A \frac{1}{2} \rho V^2$$

then

$$V = \sqrt{\frac{2W}{C_L \rho A}} \quad \text{and} \quad \frac{V_{min}}{V} = \sqrt{\frac{C_L}{C_{Lmin}}}$$

Thus at minimum power

$$V_{min} = 12 \text{ mph} \sqrt{\frac{1.08}{1.31}} = 10.9 \text{ mph} \quad (16.0 \text{ ft/s}) \quad (\text{minimum power})$$

$V_{min}$

The power requirement would be

$$P_{pilot} = \frac{P_{flight}}{\eta_{drive} \eta_{prop}}$$

$$P_{flight} = V F_D = V C_D A \frac{1}{2} \rho V^2 = (C_{D,0} + 3C_{D,i}) A \frac{1}{2} \rho V^3 = 2C_{D,0} A \rho V^3$$

$$= 2(0.0107) 500 \text{ ft}^2 \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (16.0)^3 \frac{\text{ft}^3}{\text{s}^3} \times \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}}$$

$$P_{flight} = 0.190 \text{ hp} \quad (\text{power for flight})$$

If  $\eta_{drive} = 0.9$  and  $\eta_{prop} = 0.7$ ,

$$P_{pilot} \approx \frac{0.190}{(0.9)(0.7)} = 0.302 \text{ hp} \quad (\text{minimum power})$$

$P_{pilot}$

Thus  $P_{pilot} < 0.39 \text{ hp}$ !

## Problem 9.175

[Difficulty: 4]

**9.175** Some cars come with a “spoiler,” a wing section mounted on the rear of the vehicle that salespeople sometimes claim significantly increases traction of the tires at highway speeds. Investigate the validity of this claim. Are these devices really just cosmetic?

**Given:** Car spoiler

**Find:** Whether they are effective

**Solution:**

To perform the investigation, consider some typical data

For the spoiler, assume  $b = 4\text{-ft}$   $c = 6\text{-in}$   $\rho = 1.23 \frac{\text{kg}}{\text{m}^3}$   $A = b \cdot c$   $A = 2 \cdot \text{ft}^2$

From Fig. 9.17 a reasonable lift coefficient for a conventional airfoil section is  $C_L = 1.4$

Assume the car speed is  $V = 55\text{-mph}$

Hence the "negative lift" is  $F_L = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L$   $F_L = 21.7\text{-lbf}$

This is a relatively minor negative lift force (about four bags of sugar); it is not likely to produce a noticeable difference in car traction

The picture gets worse at 30 mph:  $F_L = 6.5\text{-lbf}$

For a race car, such as that shown on the cover of the text, typical data might be

$b = 5\text{-ft}$   $c = 18\text{-in}$   $A = b \cdot c$   $A = 7.5 \cdot \text{ft}^2$   $V = 200\text{-mph}$

In this case:  $F_L = 1078\text{-lbf}$

Hence, for a race car, a spoiler can generate very significant negative lift!



## Problem 9.177

[Difficulty: 5]

**9.177** How does a Frisbee™ fly? What causes it to curve left or right? What is the effect of spin on its flight?

**Discussion:** When viewed from the side, the Frisbee shape has a rounded upper surface and a flat bottom surface. Such a shape is capable of generating lift as it travels through air.

When a Frisbee is not spinning, the lift vector probably acts slightly forward of the maximum thickness on the profile. When spinning, the motion of the surface likely affects the development and separation of the boundary layers. This may displace the center of lift slightly to the right or left of center, depending on the direction of spin.

A Frisbee is not stable when thrown without spin: it will tend to tumble as it moves through the air. Spin is used to stabilize the motion (just as a spinning gyroscope tends to remain upright). The combination of spin and the off-center lift vector cause the Frisbee to precess as a gyroscope. Therefore its spin axis can change from vertical while in flight, causing the flight path to curve right or left.

The Frisbee also can be thrown intentionally to curve right or left. This is done by inclining the spin axis so that it is not vertical at launch. When the spin axis is inclined to the left (as seen by the thrower), the Frisbee drifts to the left along a more-or-less constant radius path. Inclining the spin axis to the right causes the opposite effect.

15-782  
42-381  
42-382  
42-383  
42-384  
42-385  
42-386  
42-387  
42-388  
42-389  
42-390  
42-391  
42-392  
42-393  
42-394  
42-395  
42-396  
42-397  
42-398  
42-399  
42-400  
42-401  
42-402  
42-403  
42-404  
42-405  
42-406  
42-407  
42-408  
42-409  
42-410  
42-411  
42-412  
42-413  
42-414  
42-415  
42-416  
42-417  
42-418  
42-419  
42-420  
42-421  
42-422  
42-423  
42-424  
42-425  
42-426  
42-427  
42-428  
42-429  
42-430  
42-431  
42-432  
42-433  
42-434  
42-435  
42-436  
42-437  
42-438  
42-439  
42-440  
42-441  
42-442  
42-443  
42-444  
42-445  
42-446  
42-447  
42-448  
42-449  
42-450  
42-451  
42-452  
42-453  
42-454  
42-455  
42-456  
42-457  
42-458  
42-459  
42-460  
42-461  
42-462  
42-463  
42-464  
42-465  
42-466  
42-467  
42-468  
42-469  
42-470  
42-471  
42-472  
42-473  
42-474  
42-475  
42-476  
42-477  
42-478  
42-479  
42-480  
42-481  
42-482  
42-483  
42-484  
42-485  
42-486  
42-487  
42-488  
42-489  
42-490  
42-491  
42-492  
42-493  
42-494  
42-495  
42-496  
42-497  
42-498  
42-499  
42-500  
42-501  
42-502  
42-503  
42-504  
42-505  
42-506  
42-507  
42-508  
42-509  
42-510  
42-511  
42-512  
42-513  
42-514  
42-515  
42-516  
42-517  
42-518  
42-519  
42-520  
42-521  
42-522  
42-523  
42-524  
42-525  
42-526  
42-527  
42-528  
42-529  
42-530  
42-531  
42-532  
42-533  
42-534  
42-535  
42-536  
42-537  
42-538  
42-539  
42-540  
42-541  
42-542  
42-543  
42-544  
42-545  
42-546  
42-547  
42-548  
42-549  
42-550  
42-551  
42-552  
42-553  
42-554  
42-555  
42-556  
42-557  
42-558  
42-559  
42-560  
42-561  
42-562  
42-563  
42-564  
42-565  
42-566  
42-567  
42-568  
42-569  
42-570  
42-571  
42-572  
42-573  
42-574  
42-575  
42-576  
42-577  
42-578  
42-579  
42-580  
42-581  
42-582  
42-583  
42-584  
42-585  
42-586  
42-587  
42-588  
42-589  
42-590  
42-591  
42-592  
42-593  
42-594  
42-595  
42-596  
42-597  
42-598  
42-599  
42-600  
42-601  
42-602  
42-603  
42-604  
42-605  
42-606  
42-607  
42-608  
42-609  
42-610  
42-611  
42-612  
42-613  
42-614  
42-615  
42-616  
42-617  
42-618  
42-619  
42-620  
42-621  
42-622  
42-623  
42-624  
42-625  
42-626  
42-627  
42-628  
42-629  
42-630  
42-631  
42-632  
42-633  
42-634  
42-635  
42-636  
42-637  
42-638  
42-639  
42-640  
42-641  
42-642  
42-643  
42-644  
42-645  
42-646  
42-647  
42-648  
42-649  
42-650  
42-651  
42-652  
42-653  
42-654  
42-655  
42-656  
42-657  
42-658  
42-659  
42-660  
42-661  
42-662  
42-663  
42-664  
42-665  
42-666  
42-667  
42-668  
42-669  
42-670  
42-671  
42-672  
42-673  
42-674  
42-675  
42-676  
42-677  
42-678  
42-679  
42-680  
42-681  
42-682  
42-683  
42-684  
42-685  
42-686  
42-687  
42-688  
42-689  
42-690  
42-691  
42-692  
42-693  
42-694  
42-695  
42-696  
42-697  
42-698  
42-699  
42-700  
42-701  
42-702  
42-703  
42-704  
42-705  
42-706  
42-707  
42-708  
42-709  
42-710  
42-711  
42-712  
42-713  
42-714  
42-715  
42-716  
42-717  
42-718  
42-719  
42-720  
42-721  
42-722  
42-723  
42-724  
42-725  
42-726  
42-727  
42-728  
42-729  
42-730  
42-731  
42-732  
42-733  
42-734  
42-735  
42-736  
42-737  
42-738  
42-739  
42-740  
42-741  
42-742  
42-743  
42-744  
42-745  
42-746  
42-747  
42-748  
42-749  
42-750  
42-751  
42-752  
42-753  
42-754  
42-755  
42-756  
42-757  
42-758  
42-759  
42-760  
42-761  
42-762  
42-763  
42-764  
42-765  
42-766  
42-767  
42-768  
42-769  
42-770  
42-771  
42-772  
42-773  
42-774  
42-775  
42-776  
42-777  
42-778  
42-779  
42-780  
42-781  
42-782  
42-783  
42-784  
42-785  
42-786  
42-787  
42-788  
42-789  
42-790  
42-791  
42-792  
42-793  
42-794  
42-795  
42-796  
42-797  
42-798  
42-799  
42-800  
42-801  
42-802  
42-803  
42-804  
42-805  
42-806  
42-807  
42-808  
42-809  
42-810  
42-811  
42-812  
42-813  
42-814  
42-815  
42-816  
42-817  
42-818  
42-819  
42-820  
42-821  
42-822  
42-823  
42-824  
42-825  
42-826  
42-827  
42-828  
42-829  
42-830  
42-831  
42-832  
42-833  
42-834  
42-835  
42-836  
42-837  
42-838  
42-839  
42-840  
42-841  
42-842  
42-843  
42-844  
42-845  
42-846  
42-847  
42-848  
42-849  
42-850  
42-851  
42-852  
42-853  
42-854  
42-855  
42-856  
42-857  
42-858  
42-859  
42-860  
42-861  
42-862  
42-863  
42-864  
42-865  
42-866  
42-867  
42-868  
42-869  
42-870  
42-871  
42-872  
42-873  
42-874  
42-875  
42-876  
42-877  
42-878  
42-879  
42-880  
42-881  
42-882  
42-883  
42-884  
42-885  
42-886  
42-887  
42-888  
42-889  
42-890  
42-891  
42-892  
42-893  
42-894  
42-895  
42-896  
42-897  
42-898  
42-899  
42-900  
42-901  
42-902  
42-903  
42-904  
42-905  
42-906  
42-907  
42-908  
42-909  
42-910  
42-911  
42-912  
42-913  
42-914  
42-915  
42-916  
42-917  
42-918  
42-919  
42-920  
42-921  
42-922  
42-923  
42-924  
42-925  
42-926  
42-927  
42-928  
42-929  
42-930  
42-931  
42-932  
42-933  
42-934  
42-935  
42-936  
42-937  
42-938  
42-939  
42-940  
42-941  
42-942  
42-943  
42-944  
42-945  
42-946  
42-947  
42-948  
42-949  
42-950  
42-951  
42-952  
42-953  
42-954  
42-955  
42-956  
42-957  
42-958  
42-959  
42-960  
42-961  
42-962  
42-963  
42-964  
42-965  
42-966  
42-967  
42-968  
42-969  
42-970  
42-971  
42-972  
42-973  
42-974  
42-975  
42-976  
42-977  
42-978  
42-979  
42-980  
42-981  
42-982  
42-983  
42-984  
42-985  
42-986  
42-987  
42-988  
42-989  
42-990  
42-991  
42-992  
42-993  
42-994  
42-995  
42-996  
42-997  
42-998  
42-999  
43-000

Made in U.S.A.



# Problem 9.178


[Difficulty: 2]

9.178 Air moving over an automobile is accelerated to speeds higher than the travel speed, as shown in Fig. 9.25. This causes changes in interior pressure when windows are opened or closed. Use the data of Fig. 9.25 to estimate the pressure reduction when a window is opened slightly at a speed of 100 km/hr. What is the air speed in the freestream near the window opening?

Solution: Apply the Bernoulli equation and pressure coefficient definition.

Basic equations:  $\frac{p_{\infty}}{\rho} + \frac{V_{\infty}^2}{2} + g\beta_{\infty} = \frac{p}{\rho} + \frac{V^2}{2} + g\beta$        $C_p = \frac{p - p_{\infty}}{\frac{1}{2}\rho V_{\infty}^2}$

- Assumptions: (1) Steady flow seen from auto  
 (2) Incompressible flow  
 (3) No friction  
 (4) Flow along a streamline  
 (5) Neglect changes in elevation



From Fig. 9.25,  $C_p$  near driver's window ranges between  $-1.23$  and  $-0.40$ .

At  $V_{\infty} = 100 \text{ km/hr}$ ,

$$q = \frac{1}{2}\rho V_{\infty}^2 = \frac{1}{2} \times 1.23 \frac{\text{kg}}{\text{m}^3} \times \left[ \frac{100 \text{ km}}{\text{hr}} \times \frac{1000 \text{ m}}{\text{km}} \times \frac{\text{hr}}{3600 \text{ s}} \right]^2 \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} = 475 \text{ N/m}^2$$

Thus the pressures outside may be between

$$p - p_{\infty} = C_p \frac{1}{2}\rho V_{\infty}^2 = -1.23 \times 475 \frac{\text{N}}{\text{m}^2} = -584 \text{ N/m}^2 \text{ (gage)}$$

$$\text{and } p - p_{\infty} = -0.40 \times 475 \frac{\text{N}}{\text{m}^2} = -190 \text{ N/m}^2 \text{ (gage)}$$

From the Bernoulli equation,

$$\frac{V^2}{2} = \frac{V_{\infty}^2}{2} + \frac{p_{\infty} - p}{\rho} = \frac{V_{\infty}^2}{2} \left( 1 - \frac{p - p_{\infty}}{\frac{1}{2}\rho V_{\infty}^2} \right) = \frac{V_{\infty}^2}{2} (1 - C_p)$$

Thus

$$V = V_{\infty} \sqrt{1 - C_p}$$

The local flow speeds range from

$$V = V_{\infty} \sqrt{1 - (-1.23)} = 100 \frac{\text{km}}{\text{hr}} \sqrt{2.23} = 149 \text{ km/hr (41.5 m/s)}$$

$$V = V_{\infty} \sqrt{1 - (-0.40)} = 100 \frac{\text{km}}{\text{hr}} \sqrt{1.40} = 118 \text{ km/hr (32.9 m/s)}$$

Thus local flow speeds are significantly higher than  $V_{\infty}$ .



## Problem 9.180

[Difficulty: 2]

**9.180** A class demonstration showed that lift is present when a cylinder rotates in an air stream. A string wrapped around a paper cylinder and pulled causes the cylinder to spin and move forward simultaneously. Assume a cylinder of 5 cm diameter and 30 cm length is given a rotational speed of 240 rpm and a forward speed of 1.5 m/s. Estimate the approximate lift force that acts on the cylinder.

**Given:** Data on rotating cylinder

**Find:** Lift force on cylinder

**Solution:**

Basic equations: 
$$C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$$

The given or available data is  $\rho = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$   $v = 1.50 \cdot 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$   $L = 30\text{-cm}$   $D = 5\text{-cm}$   $\omega = 240\text{-rpm}$   $V = 1.5 \cdot \frac{\text{m}}{\text{s}}$

The spin ratio is:  $\frac{\omega \cdot D}{2 \cdot V} = 0.419$  From Fig. 9.29, we can estimate the maximum lift coefficient:  $C_L = 1.0$

The area is  $A = D \cdot L = 0.015 \text{ m}^2$  Therefore, the lift force is:  $F_L = \frac{1}{2} \cdot C_L \cdot \rho \cdot A \cdot V^2$   $F_L = 0.0204 \text{ N}$

# Problem 9.181

[Difficulty: 2]

**9.181** A golf ball (diameter  $D = 43$  mm) with circular dimples is hit from a sand trap at 20 m/s with backspin of 2000 rpm. The mass of the ball is 48 g. Evaluate the lift and drag forces acting on the ball. Express your results as fractions of the weight of the ball.

Solution: Use data from Fig. 9.28 for lift and drag coefficients.

Computing equations:  $F_L = C_L A \frac{1}{2} \rho V^2$      $F_D = C_D A \frac{1}{2} \rho V^2$

At  $V = 20$  m/sec, then  $q = \frac{1}{2} \rho V^2 = \frac{1}{2} \times 1.23 \frac{\text{kg}}{\text{m}^3} \times \frac{(20)^2 \text{m}^2}{\text{s}^2} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 246 \text{ N/m}^2$

From Fig. 9.28,  $C_L = C_L(Re, \frac{\omega D}{2V})$

$Re = \frac{VD}{\nu} = \frac{20 \text{ m}}{\text{s}} \times 0.043 \text{ m} \times \frac{\text{s}}{1.45 \times 10^{-5} \text{ m}^2} = 5.93 \times 10^4$  (assume close to  $1.26 \times 10^5$ )

$\frac{\omega D}{2V} = \frac{1}{2} \times 2000 \frac{\text{rev}}{\text{min}} \times 0.043 \text{ m} \times \frac{\text{s}}{20 \text{ m}} \times \frac{2\pi \text{ rad}}{\text{rev}} \times \frac{\text{min}}{60 \text{ s}} = 0.225$

Then  $C_L \approx 0.23$  and  $F_L = C_L A \frac{1}{2} \rho V^2 = C_L A q$

$F_L = 0.23 \times \frac{\pi (0.043)^2 \text{m}^2}{4} \times 246 \frac{\text{N}}{\text{m}^2} = 0.0822 \text{ N}$

From Fig. 9.28  $C_D = 0.31$ , so

$F_D = \frac{C_D}{C_L} F_L = \frac{0.31}{0.23} \times 0.0822 \text{ N} = 0.111 \text{ N}$

For the ball,  $mg = 0.048 \text{ kg} \times 9.81 \frac{\text{m}}{\text{sec}^2} \times \frac{\text{N} \cdot \text{sec}^2}{\text{kg} \cdot \text{m}} = 0.471 \text{ N}$

Thus  $\frac{F_L}{mg} = \frac{0.0822 \text{ N}}{0.471 \text{ N}} = 0.175$

$\frac{F_D}{mg} = \frac{0.111 \text{ N}}{0.471 \text{ N}} = 0.236$

$F_L$

$F_D$

Ratios

## Problem 9.182

[Difficulty: 2]

**9.182** Rotating cylinders were proposed as a means of ship propulsion in 1924 by the German engineer, Flettner. The original Flettner rotor ship had two rotors, each about 10 ft in diameter and 50 ft high, rotating at up to 800 rpm. Calculate the maximum lift and drag forces that act on each rotor in a 30-mph wind. Compare the total force to that produced at the optimum  $L/D$  at the same wind speed. Estimate the power needed to spin the rotor at 800 rpm.

**Given:** Data on original Flettner rotor ship

**Find:** Maximum lift and drag forces, optimal force at same wind speed, power requirement

**Solution:**

Basic equations: 
$$C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$$

The given or available data is  $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$     $L = 50 \cdot \text{ft}$     $D = 10 \cdot \text{ft}$     $\omega = 800 \cdot \text{rpm}$     $V = 30 \cdot \text{mph} = 44 \cdot \frac{\text{ft}}{\text{s}}$

$$\nu = 1.62 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$$

The spin ratio is:  $\frac{\omega \cdot D}{2 \cdot V} = 9.52$    From Fig. 9.29, we can estimate the lift and drag coefficients:  $C_L = 9.5$     $C_D = 3.5$

The area is  $A = D \cdot L = 500 \cdot \text{ft}^2$    Therefore, the lift force is:  $F_L = \frac{1}{2} \cdot C_L \cdot \rho \cdot A \cdot V^2$     $F_L = 1.076 \times 10^4 \cdot \text{lb}$

The drag force is:  $F_D = \frac{1}{2} \cdot C_D \cdot \rho \cdot A \cdot V^2$     $F_D = 3.964 \times 10^3 \cdot \text{lb}$

This appears to be close to the optimum  $L/D$  ratio. The total force is:  $F = \sqrt{F_L^2 + F_D^2}$     $F = 1.147 \times 10^4 \cdot \text{lb}$

To determine the power requirement, we need to estimate the torque on the cylinder.  $T = \tau \cdot A \cdot R = \tau \cdot \pi \cdot L \cdot D \cdot \frac{D}{2} = \frac{\pi \cdot \tau \cdot D^2 \cdot L}{2}$

In this expression  $\tau$  is the average wall shear stress. We can estimate this stress using the flat plate approximation:

$Re = \frac{\left(V + \omega \cdot \frac{D}{2}\right) \cdot D}{\nu} = 2.857 \times 10^7$    For a cylinder at this Reynolds number:  $C_D = 0.003$    Therefore, the shear stress is:


$\tau = \frac{F_D}{A}$     $\tau = \frac{1}{2} \cdot \rho \cdot V^2 \cdot C_D = 6.795 \times 10^{-3} \cdot \frac{\text{lb}}{\text{ft}^2}$    So the torque is:  $T = \frac{\pi \cdot \tau \cdot D^2 \cdot L}{2} = 53.371 \cdot \text{ft} \cdot \text{lb}$

The power is:  $P = T \cdot \omega = 4471 \cdot \frac{\text{ft} \cdot \text{lb}}{\text{s}}$     $P = 8.13 \cdot \text{hp}$

## Problem 9.183

[Difficulty: 4]

**9.183** A baseball pitcher throws a ball at 80 mph. Home plate is 60 ft away from the pitcher's mound. What spin should be placed on the ball for maximum horizontal deviation from a straight path? (A baseball has a mass of 5 oz and a circumference of 9 in.) How far will the ball deviate from a straight line?



**Given:** Baseball pitch

**Find:** Spin on the ball

**Solution:**

Basic equations:  $C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $\Sigma \vec{F} = M \cdot \vec{a}$

The given or available data is  $\rho = 0.00234 \cdot \frac{\text{slug}}{\text{ft}^3}$        $\nu = 1.62 \times 10^{-4} \cdot \frac{\text{ft}^2}{\text{s}}$        $L = 60 \cdot \text{ft}$

$M = 5 \cdot \text{oz}$        $C = 9 \cdot \text{in}$        $D = \frac{C}{\pi}$        $D = 2.86 \cdot \text{in}$        $A = \frac{\pi \cdot D^2}{4}$        $A = 6.45 \cdot \text{in}^2$        $V = 80 \cdot \text{mph}$

Compute the Reynolds number  $Re = \frac{V \cdot D}{\nu}$        $Re = 1.73 \times 10^5$

This Reynolds number is slightly beyond the range of Fig. 9.27; we use Fig. 9.27 as a rough estimate

The ball follows a trajectory defined by Newton's second law. In the horizontal plane ( $x$  coordinate)

$$F_L = M \cdot a_R = M \cdot a_x = M \cdot \frac{V^2}{R} \quad \text{and} \quad F_L = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L$$

where  $R$  is the instantaneous radius of curvature of the trajectory

From Eq 1 we see the ball trajectory has the smallest radius (i.e. it curves the most) when  $C_L$  is as large as possible. From Fig. 9.27 we see this is when  $C_L = 0.4$

Solving for  $R$        $R = \frac{2 \cdot M}{C_L \cdot A \cdot \rho}$       (1)       $R = 463.6 \cdot \text{ft}$

Also, from Fig. 9.27       $\frac{\omega \cdot D}{2 \cdot V} = 1.5$       to       $\frac{\omega \cdot D}{2 \cdot V} = 1.8$       defines the best range

Hence       $\omega = 1.5 \cdot \frac{2 \cdot V}{D}$        $\omega = 14080 \cdot \text{rpm}$        $\omega = 1.8 \cdot \frac{2 \cdot V}{D}$        $\omega = 16896 \cdot \text{rpm}$

From the trajectory geometry       $x + R \cdot \cos(\theta) = R$       where       $\sin(\theta) = \frac{L}{R}$

Hence       $x + R \cdot \sqrt{1 - \left(\frac{L}{R}\right)^2} = R$

Solving for  $x$        $x = R - R \cdot \sqrt{1 - \left(\frac{L}{R}\right)^2}$        $x = 3.90 \cdot \text{ft}$

# Problem 9.184

[Difficulty: 3]

**9.184** American and British golf balls have slightly different diameters but the same mass (see Problems 1.39 and 1.42). Assume a professional golfer hits each type of ball from a tee at 85 m/s with backspin of 9000 rpm. Evaluate the lift and drag forces on each ball. Express your answers as fractions of the weight of each ball. Estimate the radius of curvature of the trajectory of each ball. Which ball should have the longer range for these conditions?

Solution: Apply definitions of lift and drag coefficients, data from Fig. 9.28.

Computing equations:  $C_L = \frac{F_L}{\frac{1}{2}\rho V^2 A} = \frac{F_L}{qA}$ ;  $C_D = \frac{F_D}{qA}$ ;  $q = \frac{1}{2}\rho V^2$ ;  $A = \frac{\pi D^2}{4}$

The parameters are  $Re_D$  and  $\omega D/\nu$ ; tabulate results:

Ball	m (oz)	D (in.)	$\frac{\omega D}{\nu}$ (---)	$Re$ (---)	$C_L$ (---)	$C_D$ (---)	$F_L$ (N)	$F_D$ (N)
American	1.62	1.68	0.236	$2.50 \times 10^5$	0.27	0.32	1.71	2.03
British	1.62	1.62	0.228	$2.41 \times 10^5$	0.26	0.31	1.53	1.83

Taking ratios for the American ball:

$$F_L/mg = 1.71 \text{ N} \times \frac{1}{1.62 \text{ oz}} \times \frac{16 \text{ oz}}{1 \text{ lb}} \times \frac{1 \text{ lb}}{4.448 \text{ N}} = 3.80$$

$$F_D/mg = 2.03 \text{ N} \times \frac{1}{1.62 \text{ oz}} \times \frac{16 \text{ oz}}{1 \text{ lb}} \times \frac{1 \text{ lb}}{4.448 \text{ N}} = 4.51$$

British ball:

$$F_L/mg = 3.40$$

$$F_D/mg = 4.07$$

Draw FBD to compute trajectory:

$$\Sigma F_{\perp \text{ to path}} = F_L - mg \cos \theta = \frac{mv^2}{R}$$

Assume  $\theta$  small, so  $\cos \theta \approx 1$ . Then

$$R \approx \frac{mv^2}{F_L - mg} = \frac{v^2/g}{F_L/mg - 1} = \frac{1}{3.80 - 1} \times \frac{(85)^2 \text{ m}^2}{\text{s}^2} \times \frac{\text{s}^2}{9.81 \text{ m}} = 263 \text{ m (American)}$$

$$= \frac{1}{3.40 - 1} \times \frac{(85)^2 \text{ m}^2}{\text{s}^2} \times \frac{\text{s}^2}{9.81 \text{ m}} = 307 \text{ m (British)}$$

(Note because  $F_L/mg > 1$ , the balls actually rise!)

Drag probably is more important than lift in affecting range of a drive. Therefore one probably would expect the British ball to carry farther.



$F_L/mg$   
 $F_D/mg$


R

Range

## Problem 9.185

[Difficulty: 4]

**9.185** A soccer player takes a free kick. Over a distance of 10 m, the ball veers to the right by about 1 m. Estimate the spin the player's kick put on the ball if its speed is 30 m/s. The ball has a mass of 420 gm and has a circumference of 70 cm.



**Given:** Soccer free kick

**Find:** Spin on the ball

**Solution:**

Basic equations:  $C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot A \cdot V^2}$        $\Sigma \vec{F} = M \cdot \vec{a}$

The given or available data is  $\rho = 1.21 \cdot \frac{\text{kg}}{\text{m}^3}$        $\nu = 1.50 \cdot 10^{-5} \cdot \frac{\text{m}^2}{\text{s}}$        $L = 10 \cdot \text{m}$        $x = 1 \cdot \text{m}$

$M = 420 \cdot \text{gm}$        $C = 70 \cdot \text{cm}$        $D = \frac{C}{\pi}$        $D = 22.3 \cdot \text{cm}$        $A = \frac{\pi \cdot D^2}{4}$        $A = 0.0390 \cdot \text{m}^2$        $V = 30 \cdot \frac{\text{m}}{\text{s}}$

Compute the Reynolds number  $Re = \frac{V \cdot D}{\nu}$        $Re = 4.46 \times 10^5$

This Reynolds number is beyond the range of Fig. 9.27; however, we use Fig. 9.27 as a rough estimate

The ball follows a trajectory defined by Newton's second law. In the horizontal plane ( $x$  coordinate)

$$F_L = M \cdot a_R = M \cdot a_x = M \cdot \frac{V^2}{R} \quad \text{and} \quad F_L = \frac{1}{2} \cdot \rho \cdot A \cdot V^2 \cdot C_L$$

where  $R$  is the instantaneous radius of curvature of the trajectory

Hence, solving for  $R$   $R = \frac{2 \cdot M}{C_L \cdot A \cdot \rho}$       (1)

From the trajectory geometry  $x + R \cdot \cos(\theta) = R$       where  $\sin(\theta) = \frac{L}{R}$

Hence  $x + R \cdot \sqrt{1 - \left(\frac{L}{R}\right)^2} = R$

Solving for  $R$   $R = \frac{(L^2 + x^2)}{2 \cdot x}$        $R = 50.5 \cdot \text{m}$

Hence, from Eq 1  $C_L = \frac{2 \cdot M}{R \cdot A \cdot \rho}$        $C_L = 0.353$

For this lift coefficient, from Fig. 9.27  $\frac{\omega \cdot D}{2 \cdot V} = 1.2$

Hence  $\omega = 1.2 \cdot \frac{2 \cdot V}{D}$        $\omega = 3086 \cdot \text{rpm}$

(And of course, Beckham still kind of rules!)



## Problem 10.2

[Difficulty: 2]

**10.2** The geometry of a centrifugal water pump is  $r_1 = 10$  cm,  $r_2 = 20$  cm,  $b_1 = b_2 = 4$  cm,  $\beta_1 = 30^\circ$ ,  $\beta_2 = 15^\circ$ , and it runs at speed 1600 rpm. Estimate the discharge required for axial entry, the power generated in the water in watts, and the head produced.

**Given:** Geometry of centrifugal pump

**Find:** Estimate discharge for axial entry; Head

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$\begin{aligned} \rho &= 999 \frac{\text{kg}}{\text{m}^3} & r_1 &= 10 \text{ cm} & r_2 &= 20 \text{ cm} & b_1 &= 4 \text{ cm} & b_2 &= 4 \text{ cm} \\ \omega &= 1600 \text{ rpm} & \beta_1 &= 30 \text{ deg} & \beta_2 &= 15 \text{ deg} \end{aligned}$$

From continuity  $V_n = \frac{Q}{2 \cdot \pi \cdot r \cdot b} = w \cdot \sin(\beta) \quad w = \frac{V_n}{\sin(\beta)}$

From geometry  $V_t = U - w \cdot \cos(\beta) = U - \frac{V_n}{\sin(\beta)} \cdot \cos(\beta) = U - \frac{Q}{2 \cdot \pi \cdot r \cdot b} \cdot \cot(\beta)$

For an axial entry  $V_{t1} = 0 \quad \text{so} \quad U_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1) = 0$

Using given data  $U_1 = \omega \cdot r_1 \quad U_1 = 16.755 \frac{\text{m}}{\text{s}}$

Hence  $Q = 2 \cdot \pi \cdot r_1 \cdot b_1 \cdot U_1 \cdot \tan(\beta_1) \quad Q = 0.2431 \frac{\text{m}^3}{\text{s}}$

To find the power we need  $U_2$ ,  $V_{t2}$ , and  $m_{\text{rate}}$

The mass flow rate is  $m_{\text{rate}} = \rho \cdot Q \quad m_{\text{rate}} = 242.9 \frac{\text{kg}}{\text{s}}$

$$U_2 = \omega \cdot r_2 \quad U_2 = 33.5 \frac{\text{m}}{\text{s}}$$

$$V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2) \quad V_{t2} = 15.5 \frac{\text{m}}{\text{s}}$$

Hence  $W_m = (U_2 \cdot V_{t2} - U_1 \cdot V_{t1}) \cdot m_{\text{rate}} \quad W_m = 1.258 \times 10^5 \frac{\text{J}}{\text{s}} \quad W_m = 126 \text{ kW}$

The head is  $H = \frac{W_m}{m_{\text{rate}} \cdot g} \quad H = 52.8 \text{ m}$

## Problem 10.3

[Difficulty: 2]

**10.3** A centrifugal pump running at 3000 rpm pumps water at a rate of 0.6 m<sup>3</sup>/min. The water enters axially and leaves the impeller at 5.4 m/s relative to the blades, which are radial at the exit. If the pump requires 5 kW and is 72 percent efficient, estimate the basic dimensions (impeller exit diameter and width), using the Euler turbomachine equation.

**Given:** Data on centrifugal pump

**Find:** Estimate basic dimensions

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b, directly derived from the Euler turbomachine equation)

The given or available data is

$$\rho = 999 \frac{\text{kg}}{\text{m}^3} \quad Q = 0.6 \frac{\text{m}^3}{\text{min}} \quad Q = 0.0100 \frac{\text{m}^3}{\text{s}} \quad W_{\text{in}} = 5 \cdot \text{kW} \quad \eta = 72\%$$

$$\omega = 3000 \cdot \text{rpm} \quad w_2 = 5.4 \frac{\text{m}}{\text{s}} \quad \beta_2 = 90 \cdot \text{deg}$$

For an axial inlet

$$V_{t1} = 0$$

From the outlet geometry

$$V_{t2} = U_2 - V_{r2} \cdot \cos(\beta_2) = U_2$$

and

$$U_2 = r_2 \cdot \omega$$

Hence, in Eq. 10.2b

$$W_m = U_2^2 \cdot \dot{m}_{\text{rate}} = r_2^2 \cdot \omega^2 \cdot \dot{m}_{\text{rate}}$$

with

$$W_m = \eta \cdot W_{\text{in}}$$

$$W_m = 3.6 \cdot \text{kW}$$

and

$$\dot{m}_{\text{rate}} = \rho \cdot Q$$

$$\dot{m}_{\text{rate}} = 9.99 \frac{\text{kg}}{\text{s}}$$

Hence

$$r_2 = \sqrt{\frac{W_m}{\dot{m}_{\text{rate}} \cdot \omega^2}}$$

$$r_2 = 0.06043 \cdot \text{m}$$

$$r_2 = 6.04 \cdot \text{cm}$$

Also

$$V_{n2} = w_2 \cdot \sin(\beta_2)$$

$$V_{n2} = 5.40 \frac{\text{m}}{\text{s}}$$

From continuity

$$V_{n2} = \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2}$$

Hence

$$b_2 = \frac{Q}{2 \cdot \pi \cdot r_2 \cdot V_{n2}}$$

$$b_2 = 4.8776 \times 10^{-3} \cdot \text{m}$$

$$b_2 = 0.488 \cdot \text{cm}$$




## Problem 10.5

[Difficulty: 2]

### 10.5 Dimensions of a centrifugal pump impeller are

Parameter	Inlet, Section ①	Outlet, Section ②
Radius, $r$ (in.)	15	45
Blade width, $b$ (in.)	4.75	3.25
Blade angle, $\beta$ (deg)	40	60



The pump is driven at 575 rpm and the fluid is water. Calculate the theoretical head and mechanical power if the flow rate is 80,000 gpm.

**Given:** Geometry of centrifugal pump

**Find:** Theoretical head; Power input for given flow rate

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$	$r_1 = 15 \cdot \text{in}$	$r_2 = 45 \cdot \text{in}$	$b_1 = 4.75 \cdot \text{in}$	$b_2 = 3.25 \cdot \text{in}$
$\omega = 575 \cdot \text{rpm}$	$\beta_1 = 40 \cdot \text{deg}$	$\beta_2 = 60 \cdot \text{deg}$	$Q = 80000 \cdot \text{gpm}$	$Q = 178 \cdot \frac{\text{ft}^3}{\text{s}}$

From continuity  $V_n = \frac{Q}{2 \cdot \pi \cdot r \cdot b} = V_{rb} \cdot \sin(\beta) \quad V_{rb} = \frac{V_n}{\sin(\beta)}$

From geometry  $V_t = U - V_{rb} \cdot \cos(\beta) = U - \frac{V_n}{\sin(\beta)} \cdot \cos(\beta) = U - \frac{Q}{2 \cdot \pi \cdot r \cdot b} \cdot \cot(\beta)$

Using given data  $U_1 = \omega \cdot r_1 \quad U_1 = 75.3 \cdot \frac{\text{ft}}{\text{s}} \quad U_2 = \omega \cdot r_2 \quad U_2 = 226 \cdot \frac{\text{ft}}{\text{s}}$

$$V_{t1} = U_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1) \quad V_{t1} = 6.94 \cdot \frac{\text{ft}}{\text{s}}$$

$$V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2) \quad V_{t2} = 210 \cdot \frac{\text{ft}}{\text{s}}$$

The mass flow rate is  $m_{\text{rate}} = \rho \cdot Q \quad m_{\text{rate}} = 346 \cdot \frac{\text{slug}}{\text{s}}$

Hence  $W_m = (U_2 \cdot V_{t2} - U_1 \cdot V_{t1}) \cdot m_{\text{rate}} \quad W_m = 1.62 \times 10^7 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}} \quad W_m = 2.94 \times 10^4 \cdot \text{hp}$

The head is  $H = \frac{W_m}{m_{\text{rate}} \cdot g} \quad H = 1455 \cdot \text{ft}$

## Problem 10.6

[Difficulty: 2]

**10.6** Dimensions of a centrifugal pump impeller are

Parameter	Inlet, Section ①	Outlet, Section ②
Radius, $r$ (in.)	3	9.75
Blade width, $b$ (in.)	1.5	1.125
Blade angle, $\beta$ (deg)	60	70



The pump is driven at 1250 rpm while pumping water. Calculate the theoretical head and mechanical power input if the flow rate is 1500 gpm.

**Given:** Geometry of centrifugal pump

**Find:** Theoretical head; Power input for given flow rate

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$\rho = 1.94 \frac{\text{slug}}{\text{ft}^3}$	$r_1 = 3 \cdot \text{in}$	$r_2 = 9.75 \cdot \text{in}$	$b_1 = 1.5 \cdot \text{in}$	$b_2 = 1.125 \cdot \text{in}$
$\omega = 1250 \cdot \text{rpm}$	$\beta_1 = 60 \cdot \text{deg}$	$\beta_2 = 70 \cdot \text{deg}$	$Q = 1500 \cdot \text{gpm}$	$Q = 3.34 \frac{\text{ft}^3}{\text{s}}$

From continuity  $V_n = \frac{Q}{2 \cdot \pi \cdot r \cdot b} = V_{rb} \cdot \sin(\beta)$   $V_{rb} = \frac{V_n}{\sin(\beta)}$

From geometry  $V_t = U - V_{rb} \cdot \cos(\beta) = U - \frac{V_n}{\sin(\beta)} \cdot \cos(\beta) = U - \frac{Q}{2 \cdot \pi \cdot r \cdot b} \cdot \cot(\beta)$

Using given data  $U_1 = \omega \cdot r_1$   $U_1 = 32.7 \frac{\text{ft}}{\text{s}}$   $U_2 = \omega \cdot r_2$   $U_2 = 106.4 \frac{\text{ft}}{\text{s}}$

$V_{t1} = U_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1)$   $V_{t1} = 22.9 \frac{\text{ft}}{\text{s}}$

$V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2)$   $V_{t2} = 104 \frac{\text{ft}}{\text{s}}$

The mass flow rate is  $m_{\text{rate}} = \rho \cdot Q$   $m_{\text{rate}} = 6.48 \frac{\text{slug}}{\text{s}}$


Hence  $W_m = (U_2 \cdot V_{t2} - U_1 \cdot V_{t1}) \cdot m_{\text{rate}}$   $W_m = 66728 \frac{\text{ft} \cdot \text{lb}_f}{\text{s}}$   $W_m = 121 \cdot \text{hp}$

The head is  $H = \frac{W_m}{m_{\text{rate}} \cdot g}$   $H = 320 \cdot \text{ft}$

## Problem 10.7

[Difficulty: 2]

**10.7** For the impeller of Problem 10.6, determine the rotational speed for which the tangential component of the inlet velocity is zero if the volume flow rate is 4000 gpm. Calculate the theoretical head and mechanical power input.



**Given:** Geometry of centrifugal pump

**Find:** Rotational speed for zero inlet velocity; Theoretical head; Power input

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$	$r_1 = 3 \cdot \text{in}$	$r_2 = 9.75 \cdot \text{in}$	$b_1 = 1.5 \cdot \text{in}$	$b_2 = 1.125 \cdot \text{in}$
	$\beta_1 = 60 \cdot \text{deg}$	$\beta_2 = 70 \cdot \text{deg}$	$Q = 4000 \cdot \text{gpm}$	$Q = 8.91 \cdot \frac{\text{ft}^3}{\text{s}}$

From continuity  $V_n = \frac{Q}{2 \cdot \pi \cdot r \cdot b} = V_{rb} \cdot \sin(\beta) \quad V_{rb} = \frac{V_n}{\sin(\beta)}$

From geometry  $V_t = U - V_{rb} \cdot \cos(\beta) = U - \frac{V_n}{\sin(\beta)} \cdot \cos(\beta) = U - \frac{Q}{2 \cdot \pi \cdot r \cdot b} \cdot \cot(\beta)$

For  $V_{t1} = 0$  we get  $U_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1) = 0 \quad \text{or} \quad \omega \cdot r_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1) = 0$

Hence, solving for  $\omega$   $\omega = \frac{Q}{2 \cdot \pi \cdot r_1^2 \cdot b_1} \cdot \cot(\beta_1) \quad \omega = 105 \cdot \frac{\text{rad}}{\text{s}} \quad \omega = 1001 \cdot \text{rpm}$

We can now find  $U_2$   $U_2 = \omega \cdot r_2 \quad U_2 = 85.2 \cdot \frac{\text{ft}}{\text{s}}$

$$V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2) \quad V_{t2} = 78.4 \cdot \frac{\text{ft}}{\text{s}}$$

The mass flow rate is  $m_{\text{rate}} = \rho \cdot Q \quad m_{\text{rate}} = 17.3 \cdot \frac{\text{slug}}{\text{s}}$


Hence Eq 10.2b becomes  $W_m = U_2 \cdot V_{t2} \cdot m_{\text{rate}} \quad W_m = 1.15 \times 10^5 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}} \quad W_m = 210 \cdot \text{hp}$

The head is  $H = \frac{W_m}{m_{\text{rate}} \cdot g} \quad H = 208 \cdot \text{ft}$

## Problem 10.8

[Difficulty: 2]

**10.8** A centrifugal water pump, with 15 cm diameter impeller and axial inlet flow, is driven at 1750 rpm. The impeller vanes are backward-curved ( $\beta_2=65^\circ$ ) and have axial width  $b_2 = 2$  cm. For a volume flow rate of 225 m<sup>3</sup>/hr determine the theoretical head rise and power input to the pump.



**Given:** Geometry of centrifugal pump

**Find:** Theoretical head; Power input for given flow rate

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad r_2 = 7.5 \cdot \text{cm} \quad b_2 = 2 \cdot \text{cm} \quad \beta_2 = 65 \cdot \text{deg}$$

$$\omega = 1750 \cdot \text{rpm} \quad Q = 225 \cdot \frac{\text{m}^3}{\text{hr}} \quad Q = 0.0625 \cdot \frac{\text{m}^3}{\text{s}}$$

From continuity  $V_{n2} = \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \quad V_{n2} = 6.63 \cdot \frac{\text{m}}{\text{s}}$

From geometry  $V_{t2} = U_2 - V_{n2} \cdot \cot(\beta_2) = U_2 - \frac{V_{n2}}{\tan(\beta_2)} \cdot \cot(\beta_2)$

Using given data  $U_2 = \omega \cdot r_2 \quad U_2 = 13.7 \cdot \frac{\text{m}}{\text{s}}$

Hence  $V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2) \quad V_{t2} = 10.7 \cdot \frac{\text{m}}{\text{s}} \quad V_{t1} = 0 \quad (\text{axial inlet})$

The mass flow rate is  $\dot{m}_{\text{rate}} = \rho \cdot Q \quad \dot{m}_{\text{rate}} = 62.5 \cdot \frac{\text{kg}}{\text{s}}$

Hence  $\dot{W}_m = U_2 \cdot V_{t2} \cdot \dot{m}_{\text{rate}} \quad \dot{W}_m = 9.15 \cdot \text{kW}$

The head is  $H = \frac{\dot{W}_m}{\dot{m}_{\text{rate}} \cdot g} \quad H = 14.9 \cdot \text{m}$



## Problem 10.10

[Difficulty: 2]

**10.10** Consider the geometry of the idealized centrifugal pump described in Problem 10.11. Draw inlet and outlet velocity diagrams assuming  $b = \text{constant}$ . Calculate the inlet blade angles required for “shockless” entry flow at the design flow rate. Evaluate the theoretical power input to the pump at the design flow rate.

**Given:** Geometry of centrifugal pump

**Find:** Draw inlet and exit velocity diagrams; Inlet blade angle; Power



**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$   $V_n = \frac{Q}{2 \cdot \pi \cdot r \cdot b}$

The given or available data is

$R_1 = 1 \cdot \text{in}$	$R_2 = 7.5 \cdot \text{in}$	$b_2 = 0.375 \cdot \text{in}$	$\omega = 2000 \text{ rpm}$
$\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$	$Q = 800 \cdot \text{gpm}$	$Q = 1.8 \cdot \frac{\text{ft}^3}{\text{s}}$	$\beta_2 = 75 \cdot \text{deg}$
$U_1 = \omega \cdot R_1$	$U_1 = 17.5 \cdot \frac{\text{ft}}{\text{s}}$	$U_2 = \omega \cdot R_2$	$U_2 = 131 \cdot \frac{\text{ft}}{\text{s}}$
$V_{n2} = \frac{Q}{2 \cdot \pi \cdot R_2 \cdot b_2}$	$V_{n2} = 14.5 \cdot \frac{\text{ft}}{\text{s}}$	$V_{n1} = \frac{R_2}{R_1} \cdot V_{n2}$	$V_{n1} = 109 \cdot \frac{\text{ft}}{\text{s}}$

Velocity diagrams:



Then  $\beta_1 = \text{atan}\left(\frac{V_{n1}}{U_1}\right)$   $\beta_1 = 80.9 \cdot \text{deg}$  (Essentially radial entry)

From geometry  $V_{t1} = U_1 - V_{n1} \cdot \cos(\beta_1)$   $V_{t1} = 0.2198 \cdot \frac{\text{ft}}{\text{s}}$   $V_{t2} = U_2 - V_{n2} \cdot \cos(\beta_2)$   $V_{t2} = 127.1 \cdot \frac{\text{ft}}{\text{s}}$

Then  $\dot{W}_m = (U_2 \cdot V_{t2} - U_1 \cdot V_{t1}) \cdot \rho \cdot Q$   $\dot{W}_m = 5.75 \times 10^4 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $\dot{W}_m = 105 \cdot \text{hp}$

## Problem 10.11

[Difficulty: 3]

**10.11** Consider a centrifugal water pump whose geometry and flow conditions are as follows:

Impeller inlet radius, $R_1$	2.5 cm
Impeller outlet radius, $R_2$	18 cm
Impeller outlet width, $b_2$	1 cm
Design speed, $N$	1800 rpm
Design flow rate, $Q$	30 m <sup>3</sup> /min
Backward-curved vanes (outlet blade angle), $\beta_2$	75°
Required flow rate range	50–150% of design

Assume ideal pump behavior with 100 percent efficiency. Find the shutoff head. Calculate the absolute and relative discharge velocities, the total head, and the theoretical power required at the design flow rate.

**Given:** Geometry of centrifugal pump

**Find:** Shutoff head; Absolute and relative exit velocities Theoretical head; Power input

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$$

$$\omega = 1800 \cdot \text{rpm}$$

$$R_1 = 2.5 \cdot \text{cm}$$

$$\beta_2 = 75 \cdot \text{deg}$$

$$R_2 = 18 \cdot \text{cm}$$

$$Q = 30 \cdot \frac{\text{m}^3}{\text{min}}$$

$$b_2 = 1 \cdot \text{cm}$$

$$Q = 0.500 \cdot \frac{\text{m}^3}{\text{s}}$$

At the exit

$$U_2 = \omega \cdot R_2$$

$$U_2 = 33.9 \cdot \frac{\text{m}}{\text{s}}$$

At shutoff

$$V_{t2} = U_2$$

$$V_{t2} = 33.9 \cdot \frac{\text{m}}{\text{s}}$$

$$H_0 = \frac{1}{g} \cdot (U_2 \cdot V_{t2})$$

$$H_0 = 117 \cdot \text{m}$$

At design. from continuity

$$V_{n2} = \frac{Q}{2 \cdot \pi \cdot R_2 \cdot b_2}$$

$$V_{n2} = 44.2 \cdot \frac{\text{m}}{\text{s}}$$

From the velocity diagram

$$V_{n2} = w_2 \cdot \sin(\beta_2)$$

$$w_2 = \frac{V_{n2}}{\sin(\beta_2)}$$

$$w_2 = 45.8 \cdot \frac{\text{m}}{\text{s}}$$

$$V_{t2} = U_2 - V_{n2} \cdot \cot(\beta_2)$$

$$V_{t2} = 22.1 \cdot \frac{\text{m}}{\text{s}}$$

Hence we obtain

$$V_2 = \sqrt{V_{n2}^2 + V_{t2}^2}$$

$$V_2 = 49.4 \cdot \frac{\text{m}}{\text{s}}$$

with

$$\alpha_2 = \text{atan}\left(\frac{V_{t2}}{V_{n2}}\right)$$

$$\alpha_2 = 26.5 \cdot \text{deg}$$

For  $V_{t1} = 0$  we get

$$\dot{W}_m = U_2 \cdot V_{t2} \cdot \rho \cdot Q = 374 \text{ kW}$$

$$H = \frac{\dot{W}_m}{\rho \cdot Q \cdot g} = 76.4 \text{ m}$$

# Problem 10.12

[Difficulty: 3]

**10.12** Consider the centrifugal pump impeller dimensions given in Example 10.1. Construct the velocity diagram for shockless flow at the impeller inlet, if  $b = \text{constant}$ . Calculate the effective flow angle with respect to the radial impeller blades for the case of no inlet swirl. Investigate the effects on flow angle of (a) variations in impeller width and (b) inlet swirl velocities.


Solution:  $Q = 150 \frac{\text{gal}}{\text{min}} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{\text{min}}{60 \text{ s}} = 0.334 \text{ ft}^3/\text{sec}$ ;  $r_1 = 0.0521 \text{ ft}$

$b = 0.0319 \text{ ft}$ ;  $\omega = 3450 \frac{\text{rev}}{\text{min}} \times 2\pi \frac{\text{rad}}{\text{rev}} \times \frac{\text{min}}{60 \text{ s}} = 361 \text{ rad/s}$

From continuity,  $V_{n1} = \frac{Q}{2\pi r_1 b} = \frac{1}{2\pi} \times 0.334 \frac{\text{ft}^3}{\text{s}} \times \frac{1}{0.0521 \text{ ft}} \times \frac{1}{0.0319 \text{ ft}} = 32.0 \text{ ft/s}$

$U_1 = \omega r_1 = 361 \frac{\text{rad}}{\text{s}} \times 0.0521 \text{ ft} = 18.8 \text{ ft/s}$

$\beta_1 = \tan^{-1} \frac{V_{n1}}{U_1} = \tan^{-1} \left( \frac{32.0}{18.8} \right) = 59.6^\circ$




Thus for radial vanes,

$\theta_{\text{eff}} = \frac{\pi}{2} - \beta_1 = 90^\circ - 59.6^\circ = 30.4^\circ$

To change  $\theta_{\text{eff}}$ : (a) Vary  $b$  with no inlet swirl:  $V_1 = V_{n1} = \frac{Q}{2\pi r_1 b}$

$\beta_1 = \tan^{-1} \frac{Q}{2\pi r_1 b U_1}$  so  $\beta_1 \uparrow$  as  $b \downarrow$


$\theta_{\text{eff}} = 90^\circ - \beta_1$



(b) Vary inlet swirl ( $V_{t1}$ ) with  $b = 0.0319 \text{ ft}$ :

$\beta_1 = \tan^{-1} \frac{V_{n1}}{U_1 - V_{t1}}$  so  $\beta_1 \uparrow$  as  $V_{t1} \uparrow$

$\theta_{\text{eff}} = 90^\circ - \beta_1$



## Problem 10.13

[Difficulty: 2]

**10.13** For the impeller of Problem 10.5, determine the inlet blade angle for which the tangential component of the inlet velocity is zero if the volume flow rate is 125,000 gpm. Calculate the theoretical head and mechanical power input.

**Given:** Geometry of centrifugal pump

**Find:** Inlet blade angle for no tangential inlet velocity at 125,000 gpm; Head; Power

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$\begin{aligned} \rho &= 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} & r_1 &= 15 \cdot \text{in} & r_2 &= 45 \cdot \text{in} & b_1 &= 4.75 \cdot \text{in} & b_2 &= 3.25 \cdot \text{in} \\ \omega &= 575 \cdot \text{rpm} & \beta_2 &= 60 \cdot \text{deg} & Q &= 125000 \cdot \text{gpm} & Q &= 279 \cdot \frac{\text{ft}^3}{\text{s}} \end{aligned}$$

From continuity  $V_n = \frac{Q}{2 \cdot \pi \cdot r \cdot b} = V_{rb} \cdot \sin(\beta)$   $V_{rb} = \frac{V_n}{\sin(\beta)}$

From geometry  $V_t = U - V_{rb} \cdot \cos(\beta) = U - \frac{V_n}{\sin(\beta)} \cdot \cos(\beta) = U - \frac{Q}{2 \cdot \pi \cdot r \cdot b} \cdot \cot(\beta)$

For  $V_{t1} = 0$  we obtain  $U_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1) = 0$  or  $\cot(\beta_1) = \frac{2 \cdot \pi \cdot r_1 \cdot b_1 \cdot U_1}{Q}$

Using given data  $U_1 = \omega \cdot r_1$   $U_1 = 75.3 \cdot \frac{\text{ft}}{\text{s}}$

Hence  $\beta_1 = \text{acot}\left(\frac{2 \cdot \pi \cdot r_1 \cdot b_1 \cdot U_1}{Q}\right)$   $\beta_1 = 50 \cdot \text{deg}$

Also  $U_2 = \omega \cdot r_2$   $U_2 = 226 \cdot \frac{\text{ft}}{\text{s}}$

$$V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2) \quad V_{t2} = 201 \cdot \frac{\text{ft}}{\text{s}}$$

The mass flow rate is  $m_{\text{rate}} = \rho \cdot Q$   $m_{\text{rate}} = 540 \cdot \frac{\text{slug}}{\text{s}}$

Hence  $W_m = (U_2 \cdot V_{t2} - U_1 \cdot V_{t1}) \cdot m_{\text{rate}}$   $W_m = 2.45 \times 10^7 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $W_m = 44497 \cdot \text{hp}$

The head is  $H = \frac{W_m}{m_{\text{rate}} \cdot g}$   $H = 1408 \cdot \text{ft}$

## Problem 10.14

[Difficulty: 3]

**10.14** A centrifugal water pump designed to operate at 1300 rpm has dimensions

Parameter	Inlet	Outlet
Radius, $r$ (mm)	100	175
Blade width, $b$ (mm)	10	7.5
Blade angle, $\beta$ (deg)	10	40

Draw the inlet velocity diagram for a volume flow rate of 35 L/s. Determine the inlet blade angle for which the entering velocity has no tangential component. Draw the outlet velocity diagram. Determine the outlet absolute flow angle (measured relative to the normal direction). Evaluate the hydraulic power delivered by the pump, if its efficiency is 75 percent. Determine the head developed by the pump.


Solution: Apply continuity and the Euler turbomachine equation.

Computing equations:  $v_n = \frac{Q}{2\pi r b}$        $\dot{w}_m = \rho Q (U_2 v_{t2} - U_1 v_{t1})$

$$\omega = 1300 \frac{\text{rev}}{\text{min}} \times 2\pi \frac{\text{rad}}{\text{rev}} \times \frac{\text{min}}{60 \text{ s}} = 136 \text{ rad/s}; \quad U_1 = 13.6 \text{ m/s}, \quad U_2 = 23.8 \text{ m/s}$$

$$v_{n1} = \frac{Q}{2\pi r_1 b_1} = \frac{1}{2\pi} \times \frac{35 \text{ L}}{\text{s}} \times \frac{\text{m}^3}{10^3 \text{ L}} \times \frac{1}{0.1 \text{ m}} \times \frac{1}{0.01 \text{ m}} = 5.57 \text{ m/s}$$


$$v_{n2} = \frac{r_1 b_1}{r_2 b_2} v_{n1} = \frac{100}{175} \times \frac{10}{7.5} \times 5.57 \text{ m/s} = 4.24 \text{ m/s}$$



$$\tan \beta_1 = \frac{v_{n1}}{U_1}$$

$$\beta_1 = \tan^{-1} \left( \frac{5.57}{13.6} \right)$$

$$\beta_1 = 22.3^\circ$$



From the outlet diagram,  $v_{t2} = U_2 - v_{n2} \cot \beta_2 = 23.8 \frac{\text{m}}{\text{s}} - 4.24 \frac{\text{m}}{\text{s}} \times \frac{1}{\tan 40^\circ}$

$$v_{t2} = 18.8 \text{ m/s}$$

$$\alpha_2 = \tan^{-1} \frac{v_{t2}}{v_{n2}} = \tan^{-1} \left( \frac{18.8}{4.24} \right) = 77.3^\circ$$

$$\dot{w}_m = \rho Q (U_2 v_{t2} - U_1 v_{t1}) = 999 \frac{\text{kg}}{\text{m}^3} \times 35 \frac{\text{L}}{\text{s}} \times \frac{\text{m}^3}{10^3 \text{ L}} \left[ 23.8 \frac{\text{m}}{\text{s}} \times 18.8 \frac{\text{m}}{\text{s}} - 0 \right] \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times 0.75$$

$$\dot{w}_m = 11.7 \text{ kW}$$

$$H = \frac{\dot{w}_m}{\rho g Q} = \frac{U_2 v_{t2} - U_1 v_{t1}}{g} = \frac{23.8 \frac{\text{m}}{\text{s}} \times 18.8 \frac{\text{m}}{\text{s}}}{9.81 \frac{\text{m}}{\text{s}^2}} \times 0.75 = 34.2 \text{ m}$$

## Problem 10.15

[Difficulty: 3]

**10.15** A centrifugal pump runs at 1750 rpm while pumping water at a rate of 50 L/s. The water enters axially, and leaves tangential to the impeller blades. The impeller exit diameter and width are 300 mm and 10 mm, respectively. If the pump requires 45 kW, and is 75 percent efficient, estimate the exit angle of the impeller blades.

**Given:** Data on a centrifugal pump

**Find:** Estimate exit angle of impeller blades

**Solution:**

The given or available data is

$\rho = 999 \frac{\text{kg}}{\text{m}^3}$	$Q = 50 \frac{\text{L}}{\text{s}}$	$W_{\text{in}} = 45 \text{ kW}$	$\eta = 75\%$
$\omega = 1750 \text{ rpm}$	$b_2 = 10 \text{ mm}$	$D = 300 \text{ mm}$	

The governing equation (derived directly from the Euler turbomachine equation) is

$$\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m} \quad (10.2b)$$

For an axial inlet  $V_{t1} = 0$  hence  $V_{t2} = \frac{W_m}{U_2 \cdot \rho \cdot Q}$

We have  $U_2 = \frac{D}{2} \cdot \omega$   $U_2 = 27.5 \frac{\text{m}}{\text{s}}$  and  $W_m = \eta \cdot W_{\text{in}}$   $W_m = 33.8 \text{ kW}$

Hence  $V_{t2} = \frac{W_m}{U_2 \cdot \rho \cdot Q}$   $V_{t2} = 24.6 \frac{\text{m}}{\text{s}}$

From continuity  $V_{n2} = \frac{Q}{\pi \cdot D \cdot b_2}$   $V_{n2} = 5.31 \frac{\text{m}}{\text{s}}$

With the exit velocities determined,  $\beta$  can be determined from exit geometry

$$\tan(\beta) = \frac{V_{n2}}{U_2 - V_{t2}} \quad \text{or} \quad \beta = \text{atan}\left(\frac{V_{n2}}{U_2 - V_{t2}}\right) \quad \beta = 61.3 \text{ deg}$$

## Problem 10.16

[Difficulty: 3]

**10.16** A centrifugal water pump designed to operate at 1200 rpm has dimensions

Parameter	Inlet	Outlet
Radius, $r$ (mm)	90	150
Blade width, $b$ (mm)	10	7.5
Blade angle, $\beta$ (deg)	25	45

Determine the flow rate at which the entering velocity has no tangential component. Draw the outlet velocity diagram, and determine the outlet absolute flow angle (measured relative to the normal direction) at this flow rate. Evaluate the hydraulic power delivered by the pump if its efficiency is 70 percent. Determine the head developed by the pump.

**Given:** Data on a centrifugal pump

**Find:** Flow rate for zero inlet tangential velocity; outlet flow angle; power; head developed

**Solution:**

The given or available data is  $\rho = 999 \frac{\text{kg}}{\text{m}^3}$        $\omega = 1200 \cdot \text{rpm}$        $\eta = 70\%$

$$r_1 = 90 \cdot \text{mm} \quad b_1 = 10 \cdot \text{mm} \quad \beta_1 = 25 \cdot \text{deg} \quad r_2 = 150 \cdot \text{mm} \quad b_2 = 7.5 \cdot \text{mm} \quad \beta_2 = 45 \cdot \text{deg}$$

The governing equations (derived directly from the Euler turbomachine equation) are

$$\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m} \quad (10.2b)$$

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (10.2c)$$

We also have from geometry  $\alpha_2 = \text{atan}\left(\frac{V_{t2}}{V_{n2}}\right) \quad (1)$

From geometry  $V_{t1} = 0 = U_1 - V_{r1} \cos(\beta_1) = r_1 \cdot \omega \cdot -\frac{V_{n1}}{\sin(\beta_1)} \cdot \cos(\beta_1)$

and from continuity  $V_{n1} = \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1}$

Hence  $r_1 \cdot \omega - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1 \cdot \tan(\beta_1)} = 0$        $Q = 2 \cdot \pi \cdot r_1^2 \cdot b_1 \cdot \omega \cdot \tan(\beta_1)$        $Q = 29.8 \frac{\text{L}}{\text{s}}$        $Q = 0.0298 \frac{\text{m}^3}{\text{s}}$

The power, head and absolute angle  $\alpha$  at the exit are obtained from direct computation using Eqs. 10.2b, 10.2c, and 1 above

$$U_1 = r_1 \cdot \omega \quad U_1 = 11.3 \frac{\text{m}}{\text{s}} \quad U_2 = r_2 \cdot \omega \quad U_2 = 18.8 \frac{\text{m}}{\text{s}} \quad V_{t1} = 0 \frac{\text{m}}{\text{s}}$$

From geometry  $V_{t2} = U_2 - V_{r2} \cos(\beta_2) = r_2 \cdot \omega \cdot -\frac{V_{n2}}{\sin(\beta_2)} \cdot \cos(\beta_2)$

and from continuity  $V_{n2} = \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2}$        $V_{n2} = 4.22 \frac{\text{m}}{\text{s}}$

Hence 
$$V_{t2} = r_2 \cdot \omega - \frac{V_{n2}}{\tan(\beta_2)} \quad V_{t2} = 14.6 \frac{\text{m}}{\text{s}}$$

Using these results in Eq. 1 
$$\alpha_2 = \text{atan}\left(\frac{V_{t2}}{V_{n2}}\right) \quad \alpha_2 = 73.9 \cdot \text{deg}$$

Using them in Eq. 10.2b 
$$W_m = (U_2 \cdot V_{t2} - U_1 \cdot V_{t1}) \cdot \rho \cdot Q \quad W_m = 8.22 \cdot \text{kW}$$

Using them in Eq. 10.2c 
$$H = \frac{1}{g} \cdot (U_2 \cdot V_{t2} - U_1 \cdot V_{t1}) \quad H = 28.1 \text{ m}$$

This is the power and head assuming no inefficiency; with  $\eta = 70\%$ , we have (from Eq. 10.4c)

$$W_h = \eta \cdot W_m \quad W_h = 5.75 \cdot \text{kW}$$

$$H_p = \eta \cdot H \quad H_p = 19.7 \text{ m}$$

(This last result can also be obtained from Eq. 10.4a  $W_h = \rho \cdot Q \cdot g \cdot H_p$ )

## Problem 10.17

[Difficulty: 1]

**10.17** Repeat the analysis for determining the optimum speed for an impulse turbine of Example 10.13, using the Euler turbomachine equation.

**Given:** Impulse turbine

**Find:** Optimum speed using the Euler turbomachine equation

**Solution:**

The governing equation is the Euler turbomachine equation

$$T_{\text{shaft}} = (r_2 V_{t2} - r_1 V_{t1}) \dot{m} \quad (10.1c)$$

In terms of the notation of Example 10.13, for a stationary CV

$$r_1 = r_2 = R \quad U_1 = U_2 = U \quad V_{t1} = V - U \quad V_{t2} = (V - U) \cdot \cos(\theta) \quad \text{and} \quad \dot{m}_{\text{flow}} = \rho \cdot Q$$

Hence  $T_{\text{shaft}} = [R \cdot (V - U) \cdot \cos(\theta) - R \cdot (V - U)] \cdot \rho \cdot Q$   $T_{\text{out}} = T_{\text{shaft}} = \rho \cdot Q \cdot R \cdot (V - U) \cdot (1 - \cos(\theta))$

The power is  $W_{\text{out}} = \omega \cdot T_{\text{out}} = \rho \cdot Q \cdot R \cdot \omega \cdot (V - U) \cdot (1 - \cos(\theta))$   $W_{\text{out}} = \rho \cdot Q \cdot U \cdot (V - U) \cdot (1 - \cos(\theta))$

These results are identical to those of Example 10.13. The proof that maximum power is when  $U = V/2$  is hence also the same and will not be repeated here.

## Problem 10.18

[Difficulty: 1]

**10.18** Kerosene is pumped by a centrifugal pump. When the flow rate is 350 gpm, the pump requires 18 hp input, and its efficiency is 82 percent. Calculate the pressure rise produced by the pump. Express this result as (a) feet of water and (b) feet of kerosene.

**Given:** Data on centrifugal pump

**Find:** Pressure rise; Express as ft of water and kerosene

**Solution:**

Basic equations: 
$$\eta = \frac{\rho \cdot Q \cdot g \cdot H}{W_m}$$

The given or available data is 
$$\rho_w = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad Q = 350 \cdot \text{gpm} \quad Q = 0.780 \cdot \frac{\text{ft}^3}{\text{s}}$$

$$W_m = 18 \cdot \text{hp} \quad \eta = 82\%$$

Solving for H 
$$H = \frac{\eta \cdot W_m}{\rho_w \cdot Q \cdot g} \quad H = 166.8 \cdot \text{ft}$$

For kerosene, from Table A.2 
$$SG = 0.82 \quad H_k = \frac{\eta \cdot W_m}{SG \cdot \rho_w \cdot Q \cdot g} \quad H_k = 203 \cdot \text{ft}$$

## Problem 10.19

[Difficulty: 3]

**10.19** A centrifugal pump designed to deliver water at 70 cfm has dimensions

Parameter	Inlet	Outlet
Radius, $r$ (in.)	14	7
Blade width, $b$ (in.)	0.4	0.3
Blade angle, $\beta$ ( $^\circ$ )	20	45

Draw the inlet velocity diagram. Determine the design speed if the entering velocity has no tangential component. Draw the outlet velocity diagram. Determine the outlet absolute flow angle (measured relative to the normal direction). Evaluate the theoretical head developed by the pump. Estimate the minimum mechanical power delivered to the pump.

**Given:** Geometry of centrifugal pump

**Find:** Draw inlet velocity diagram; Design speed for no inlet tangential velocity; Outlet angle; Head; Power

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)


$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$r_1 = 4 \cdot \text{in} \quad r_2 = 7 \cdot \text{in} \quad b_1 = 0.4 \cdot \text{in} \quad b_2 = 0.3 \cdot \text{in} \quad \beta_1 = 20 \cdot \text{deg} \quad \beta_2 = 45 \cdot \text{deg}$$

$$\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad Q = 70 \cdot \text{cfm} \quad Q = 1.167 \cdot \frac{\text{ft}^3}{\text{s}}$$

Velocity diagrams:



From continuity  $V_n = \frac{Q}{2 \cdot \pi \cdot r \cdot b} = w \cdot \sin(\beta)$   $w = \frac{V_n}{\sin(\beta)}$   $\frac{V_{n1}}{V_{n2}} = \frac{A_2}{A_1} = \frac{r_2 \cdot b_2}{r_1 \cdot b_1}$

From geometry  $V_t = U - V_{rb} \cdot \cos(\beta) = U - \frac{V_n}{\sin(\beta)} \cdot \cos(\beta) = U - \frac{Q}{2 \cdot \pi \cdot r \cdot b} \cdot \cot(\beta)$

For  $V_{t1} = 0$  we obtain  $U_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1) = 0$  or  $\omega \cdot r_1 - \frac{Q}{2 \cdot \pi \cdot r_1 \cdot b_1} \cdot \cot(\beta_1) = 0$

Solving for  $\omega$   $\omega = \frac{Q}{2 \cdot \pi \cdot r_1^2 \cdot b_1} \cdot \cot(\beta_1)$   $\omega = 138 \cdot \frac{\text{rad}}{\text{s}}$   $\omega = 1315 \cdot \text{rpm}$

Hence  $U_1 = \omega \cdot r_1$   $U_1 = 45.9 \cdot \frac{\text{ft}}{\text{s}}$   $U_2 = \omega \cdot r_2$   $U_2 = 80.3 \cdot \frac{\text{ft}}{\text{s}}$

$$V_{n2} = \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \quad V_{n2} = 12.73 \cdot \frac{\text{ft}}{\text{s}} \quad V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2) \quad V_{t2} = 67.6 \cdot \frac{\text{ft}}{\text{s}}$$

From the sketch  $\alpha_2 = \text{atan}\left(\frac{V_{t2}}{V_{n2}}\right)$   $\alpha_2 = 79.3 \cdot \text{deg}$

Hence  $W_m = U_2 \cdot V_{t2} \cdot \rho \cdot Q$   $W_m = 1.230 \times 10^4 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{s}}$   $W_m = 22.4 \cdot \text{hp}$

The head is  $H = \frac{W_m}{\rho \cdot Q \cdot g}$   $H = 169 \cdot \text{ft}$

## Problem 10.20

[Difficulty: 4]

**10.20** In the water pump of Problem 10.8, the pump casing acts as a diffuser, which converts 60 percent of the absolute velocity head at the impeller outlet to static pressure rise. The head loss through the pump suction and discharge channels is 0.75 times the radial component of velocity head leaving the impeller. Estimate the volume flow rate, head rise, power input, and pump efficiency at the maximum efficiency point. Assume the torque to overcome bearing, seal, and spin losses is 10 percent of the ideal torque at  $Q = 0.065 \text{ m}^3/\text{s}$ .

**Given:** Geometry of centrifugal pump with diffuser casing

**Find:** Flow rate; Theoretical head; Power; Pump efficiency at maximum efficiency point

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$\begin{aligned} \rho &= 1000 \frac{\text{kg}}{\text{m}^3} & r_2 &= 7.5 \text{ cm} & b_2 &= 2 \text{ cm} & \beta_2 &= 65 \text{ deg} \\ \omega &= 1750 \text{ rpm} & \omega &= 183 \frac{\text{rad}}{\text{s}} \end{aligned}$$

Using given data  $U_2 = \omega r_2$   $U_2 = 13.7 \frac{\text{m}}{\text{s}}$

Illustrate the procedure with  $Q = 0.065 \frac{\text{m}^3}{\text{s}}$

From continuity  $V_{n2} = \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2}$   $V_{n2} = 6.9 \frac{\text{m}}{\text{s}}$

From geometry  $V_{t2} = U_2 - V_{r2} \cdot \cos(\beta_2) = U_2 - \frac{V_{n2}}{\sin(\beta_2)} \cdot \cos(\beta_2)$

Hence  $V_{t2} = U_2 - \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2} \cdot \cot(\beta_2)$   $V_{t2} = 10.5 \frac{\text{m}}{\text{s}}$   $V_{t1} = 0$  (axial inlet)

$$V_2 = \sqrt{V_{n2}^2 + V_{t2}^2} \quad V_2 = 12.6 \frac{\text{m}}{\text{s}}$$


$$H_{\text{ideal}} = \frac{U_2 \cdot V_{t2}}{g} \quad H_{\text{ideal}} = 14.8 \text{ m}$$

$$T_{\text{friction}} = 10\% \cdot \frac{W_{\text{ideal}}}{\omega} = 10\% \cdot \frac{\rho \cdot Q \cdot H_{\text{ideal}}}{\omega}$$

$$T_{\text{friction}} = 10\% \cdot \frac{Q \cdot \rho \cdot g \cdot H_{\text{ideal}}}{\omega} \quad T_{\text{friction}} = 5.13 \cdot \text{N} \cdot \text{m}$$

$$H_{\text{actual}} = 60\% \cdot \frac{V_2^2}{2 \cdot g} - 0.75 \cdot \frac{V_{n2}^2}{2 \cdot g} \quad H_{\text{actual}} = 3.03 \text{ m}$$

$$\eta = \frac{Q \cdot \rho \cdot g \cdot H_{\text{actual}}}{Q \cdot \rho \cdot g \cdot H_{\text{ideal}} + \omega \cdot T_{\text{friction}}} \quad \eta = 18.7\%$$



The above graph can be plotted in Excel. In addition, Solver can be used to vary Q to maximize  $\eta$ . The results are

$$Q = 0.0282 \cdot \frac{\text{m}^3}{\text{s}} \quad \eta = 22.2\% \quad H_{\text{ideal}} = 17.3 \text{ m} \quad H_{\text{actual}} = 4.60 \text{ m}$$

$$W_m = Q \cdot \rho \cdot g \cdot H_{\text{ideal}} + \omega \cdot T_{\text{friction}} \quad W_m = 5.72 \cdot \text{kW}$$

## Problem 10.21

[Difficulty: 4]

**10.21** The theoretical head delivered by a centrifugal pump at shutoff depends on the discharge radius and angular speed of the impeller. For preliminary design, it is useful to have a plot showing the theoretical shutoff characteristics and approximating the actual performance. Prepare a log-log plot of impeller radius versus theoretical head rise at shutoff with standard motor speeds as parameters. Assume the fluid is water and the actual head at the design flow rate is 70 percent of the theoretical shutoff head. (Show these as dashed lines on the plot.) Explain how this plot might be used for preliminary design.


Solution: Apply the Euler turbomachine equation.

Computing equation:  $H = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1})$   $\uparrow \approx 0(2)$

Assumptions: (1) No through flow, (2) Neglect  $V_{t1}$

Then  $H = \frac{1}{g} (\omega R_2 \omega R_2) = \frac{\omega^2 R_2^2}{g}$  or  $\log H = 2 \log \omega + 2 \log R_2 - \log g$

These will be straight lines on a plot of  $\log R_2$  vs.  $\log H$  (at constant  $\omega$ ):



For a given application, enter the abscissa with the desired head, move up to the desired driver speed, then move left to the ordinate and read the required impeller radius. The example (--- line) illustrates.

## Problem 10.22

[Difficulty: 2]

**10.22** Use data from Appendix D to choose points from the performance curves for a Peerless horizontal split case Type 16A18B pump at 705 and 880 nominal rpm. Obtain and plot curve-fits of total head versus delivery for this pump, with an 18.0-in.-diameter impeller.

Solution: Tabulate data from Figs. D.9 (705 rpm) and D.10 (880 rpm):

705 rpm:	$Q$ (gpm)	0	2000	4000	6000	8000
	$H$ (ft)	59	56	50	43	32

Curve-fit:  $\hat{H}(ft) = 57.8 - 4.09 \times 10^{-7} [Q(gpm)]^2$ ;  $r^2 = 0.994$


$\hat{H}(ft)$	57.8	56.2	51.3	43.1	31.6
---------------	------	------	------	------	------

880 rpm:	$Q$ (gpm)	0	2000	4000	6000	8000	10,000
	$H$ (ft)	92	89	84	78	68	50

Curve-fit:  $\hat{H}(ft) = 91.5 - 4.01 \times 10^{-7} [Q(gpm)]^2$ ;  $r^2 = 0.992$

$\hat{H}(ft)$	91.5	89.9	85.1	77.1	65.9	51.5
---------------	------	------	------	------	------	------

Plot:



## Problem 10.23

[Difficulty: 2]

**10.23** Use data from Appendix D to choose points from the performance curves for a Peerless horizontal split case Type 4AE12 pump at 1750 and 3550 nominal rpm. Obtain and plot curve-fits for total head versus delivery at each speed for this pump, with a 12-in.-diameter impeller.

Solution: Tabulate data from Figs. D.4 (1750 rpm) and D.5 (3550 rpm):

1750 rpm:	$Q$ (gpm)	0	200	400	600
	$H$ (ft)	155	150	137	106

Curve-fit:  $\hat{H}(\text{ft}) = 156 - 1.36 \times 10^{-4} [Q(\text{gpm})]^2$ ;  $r^2 = 0.994$


$\hat{H}$ (ft)	156	151	134	107
----------------	-----	-----	-----	-----

3550 rpm:	$Q$ (gpm)	0	400	800	1200
	$H$ (ft)	635	620	565	445

Curve-fit:  $\hat{H}(\text{ft}) = 641 - 1.33 \times 10^{-4} [Q(\text{gpm})]^2$ ;  $r^2 = 0.994$

$\hat{H}$ (ft)	641	619	556	449
----------------	-----	-----	-----	-----

Plot:



## Problem 10.24

[Difficulty: 3]

**10.24** Data from tests of a water suction pump operated at 2000 rpm with a 12-in. diameter impeller are

Flow rate, $Q$ (cfm)	36	50	74	88	125
Total head, $H$ (ft)	190	195	176	162	120
Power input, $\mathcal{P}$ (hp)	25	30	35	40	46

Plot the performance curves for this pump; include a curve of efficiency versus volume flow rate. Locate the best efficiency point and specify the pump rating at this point.

**Given:** Data on suction pump

**Find:** Plot of performance curves; Best efficiency point

**Solution:**

Basic equations:  $\eta_p = \frac{P_h}{P_m}$        $P_h = \rho \cdot Q \cdot g \cdot H$       (Note: Software cannot render a dot!)

$\rho = 1.94 \text{ slug/ft}^3$

Fitting a 2nd order polynomial to each set of data we find


$H = -0.00759Q^2 + 0.390Q + 189.1$

$\eta = -6.31 \times 10^{-5}Q^2 + 0.01113Q + 0.207$

Finally, we use Solver to maximize  $\eta$  by varying  $Q$ :

$Q$ (cfm)	$H$ (ft)	$\mathcal{P}_m$ (hp)	$\mathcal{P}_h$ (hp)	$\eta$ (%)
36	190	25	12.9	51.7%
50	195	30	18.4	61.5%
74	176	35	24.6	70.4%
88	162	40	27.0	67.4%
125	120	46	28.4	61.7%

$Q$ (cfm)	$H$ (ft)	$\eta$ (%)
88.2	164.5	69.8%



## Problem 10.25

[Difficulty: 3]

**10.25** A 9-in.-diameter centrifugal pump, running at 900 rpm with water at 68°F generates the following performance data:

Flow rate, $Q$ (cfm)	0	200	400	600	800	1000
Total head, $H$ (ft)	23.0	22.3	21.0	19.5	17.0	12.5
Power input, $\mathcal{P}$ (hp)	3.13	3.50	4.06	4.47	4.88	5.09

Plot the performance curves for this pump; include a curve of efficiency versus volume flow rate. Locate the best efficiency point. What is the specific speed for this pump?

**Given:** Data on suction pump

**Find:** Plot of performance curves; Best efficiency point

**Solution:**

Basic equations:  $\eta_p = \frac{P_h}{P_m}$      $P_h = \rho \cdot Q \cdot g \cdot H$      $N_s = \frac{N \cdot \sqrt{Q}}{(g \cdot H)^{0.75}}$     (Note: Software cannot render a dot!)

$\rho = 1.94 \text{ slug/ft}^3$

Fitting a 2nd order polynomial to each set of data we find


$H = -1.062 \times 10^{-5} Q^2 + 6.39 \times 10^{-4} Q + 22.8$

$\eta = -1.752 \times 10^{-6} Q^2 + 0.00237 Q + 0.0246$

Finally, we use Solver to maximize  $\eta$  by varying  $Q$ :

$Q$ (cfm)	$H$ (ft)	$\mathcal{P}_m$ (hp)	$\mathcal{P}_h$ (hp)	$\eta$ (%)
0	23.0	15.2	0.0	0.0%
200	22.3	17.2	8.4	49.0%
400	21.0	24.4	15.9	65.1%
600	19.5	27.0	22.1	82.0%
800	17.0	32.2	25.7	79.9%
1000	12.5	36.4	23.6	65.0%

$Q$ (cfm)	$H$ (ft)	$\eta$ (%)
676	18.4	82.6%



The Specific Speed for this pump is: 2.639

## Problem 10.26

[Difficulty: 3]

**10.26** An axial-flow fan operates in seal-level air at 1350 rpm and has a blade tip diameter of 3 ft and a root diameter of 2.5 ft. The inlet angles are  $\alpha_1 = 55^\circ$ ,  $\beta_1 = 30^\circ$ , and at the exit  $\beta_2 = 60^\circ$ . Estimate the flow volumetric flow rate, horsepower, and the outlet angle,  $\alpha_2$ .

**Given:** Data on axial flow fan

**Find:** Volumetric flow rate, horsepower, flow exit angle

**Solution:**

Basic equations:  $\dot{W}_m = (U_2 V_{t2} - U_1 V_{t1}) \dot{m}$  (Eq. 10.2b)

$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$\rho = 0.002377 \frac{\text{slug}}{\text{ft}^3} \quad \omega = 1350 \cdot \text{rpm} \quad d_{\text{tip}} = 3 \cdot \text{ft} \quad d_{\text{root}} = 2.5 \cdot \text{ft} \quad \alpha_1 = 55 \cdot \text{deg} \quad \beta_1 = 30 \cdot \text{deg} \quad \beta_2 = 60 \cdot \text{deg}$$

The mean radius would be half the mean diameter:  $r = \frac{1}{2} \cdot \frac{d_{\text{tip}} + d_{\text{root}}}{2} \quad r = 1.375 \cdot \text{ft}$

Therefore, the blade speed is:  $U = r \cdot \omega \quad U = 194.39 \frac{\text{ft}}{\text{s}}$

From velocity triangles we can generate the following two equations:  $V_1 \cdot \cos(\alpha_1) = w_1 \cdot \sin(\beta_1)$  (axial component)  
 $V_1 \cdot \sin(\alpha_1) + w_1 \cdot \cos(\beta_1) = U$  (tangential component)

Combining the two equations:  $V_1 = \frac{U}{\sin(\alpha_1) + \frac{\cos(\alpha_1)}{\tan(\beta_1)}} \quad V_1 = 107.241 \cdot \frac{\text{ft}}{\text{s}} \quad w_1 = V_1 \cdot \frac{\cos(\alpha_1)}{\sin(\beta_1)} \quad w_1 = 123.021 \cdot \frac{\text{ft}}{\text{s}}$

So the entrance velocity components are:  $V_{n1} = V_1 \cdot \cos(\alpha_1) \quad V_{n1} = 61.511 \cdot \frac{\text{ft}}{\text{s}} \quad V_{t1} = V_1 \cdot \sin(\alpha_1) \quad V_{t1} = 87.846 \cdot \frac{\text{ft}}{\text{s}}$

The volumetric flow rate would then be:  $Q = V_{n1} \cdot \frac{\pi}{4} \cdot (d_{\text{tip}}^2 - d_{\text{root}}^2) \quad Q = 132.9 \cdot \frac{\text{ft}^3}{\text{s}}$

Since axial velocity does not change:  $V_{n2} = V_{n1}$

The exit speed relative to the blade is:  $w_2 = \frac{V_{n2}}{\sin(\beta_2)} \quad w_2 = 71.026 \cdot \frac{\text{ft}}{\text{s}}$  so the tangential component of absolute velocity is:

$V_{t2} = U - w_2 \cdot \cos(\beta_2) \quad V_{t2} = 158.873 \cdot \frac{\text{ft}}{\text{s}}$  Into the expression for power:  $\dot{W}_m = U \cdot (V_{t2} - V_{t1}) \cdot \rho \cdot Q \quad \dot{W}_m = 7.93 \cdot \text{hp}$

The flow exit angle is:  $\alpha_2 = \text{atan}\left(\frac{V_{t2}}{V_{n2}}\right) \quad \alpha_2 = 68.8 \cdot \text{deg}$

# Problem 10.27

[Difficulty: 2]

10.27 Write the turbine specific speed in terms of the flow coefficient and the head coefficient.

Solution:

$$N_s = \omega \rho^{1/2} / \rho^{1/2} h^{5/4} \quad \dots \quad 10.18a$$

Power coefficient  $\pi_3 = \frac{\rho}{\rho \omega^3 D^5}$

Head coefficient  $\pi_2 = \frac{h}{\omega^2 D^2}$

Then

$$N_s = \left[ \frac{\rho}{\rho \omega^3 D^5} \right]^{1/2} \left[ \frac{\omega^2 D^2}{h} \right]^{5/4} = \frac{\rho^{1/2}}{\rho^{1/2} \omega^{3/2} D^{5/2}} \times \frac{\omega^{5/2} D^{5/2}}{h^{5/4}} = \frac{\rho^{1/2} \omega}{\rho^{1/2} h^{5/4}}$$

$$N_s = \pi_3^{1/2} / \pi_2^{5/4}$$

$N_s$

10.27  
42-382  
42-389  
42-392  
42-393  
42-394  
42-395  
42-396  
42-397  
42-398  
42-399  
42-400  
42-401  
42-402  
42-403  
42-404  
42-405  
42-406  
42-407  
42-408  
42-409  
42-410  
42-411  
42-412  
42-413  
42-414  
42-415  
42-416  
42-417  
42-418  
42-419  
42-420  
42-421  
42-422  
42-423  
42-424  
42-425  
42-426  
42-427  
42-428  
42-429  
42-430  
42-431  
42-432  
42-433  
42-434  
42-435  
42-436  
42-437  
42-438  
42-439  
42-440  
42-441  
42-442  
42-443  
42-444  
42-445  
42-446  
42-447  
42-448  
42-449  
42-450  
42-451  
42-452  
42-453  
42-454  
42-455  
42-456  
42-457  
42-458  
42-459  
42-460  
42-461  
42-462  
42-463  
42-464  
42-465  
42-466  
42-467  
42-468  
42-469  
42-470  
42-471  
42-472  
42-473  
42-474  
42-475  
42-476  
42-477  
42-478  
42-479  
42-480  
42-481  
42-482  
42-483  
42-484  
42-485  
42-486  
42-487  
42-488  
42-489  
42-490  
42-491  
42-492  
42-493  
42-494  
42-495  
42-496  
42-497  
42-498  
42-499  
42-500



## Problem 10.28

[Difficulty: 3]

**10.28** Data measured during tests of a centrifugal pump driven at 3000 rpm are

Parameter	Inlet, Section ①	Outlet, Section ②
Gage pressure, $p$ (psi)	12.5	—
Elevation above datum, $z$ (ft)	6.5	32.5
Average speed of flow, $\bar{V}$ (ft/s)	6.5	15

The flow rate is 65 gpm and the torque applied to the pump shaft is 4.75 lbf·ft. The pump efficiency is 75 percent, and the electric motor efficiency is 85 percent. Find the electric power required, and the gage pressure at section ②.

**Given:** Data on centrifugal pump

**Find:** Electric power required; gage pressure at exit

**Solution:**

Basic equations:  $\dot{W}_h = \rho Q g H_p$  (Eq. 10.8a)

$$H_p = \left( \frac{p}{\rho g} + \frac{\bar{V}^2}{2g} + z \right)_{\text{discharge}} - \left( \frac{p}{\rho g} + \frac{\bar{V}^2}{2g} + z \right)_{\text{suction}} \quad (\text{Eq. 10.8b}) \quad \eta_p = \frac{\dot{W}_h}{\dot{W}_m} = \frac{\rho Q g H_p}{\omega T} \quad (\text{Eq. 10.8c})$$

The given or available data is

$$\begin{array}{llllll} \rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} & \omega = 3000 \cdot \text{rpm} & \eta_p = 75\% & \eta_e = 85\% & Q = 65 \cdot \text{gpm} & Q = 0.145 \cdot \frac{\text{ft}^3}{\text{s}} \\ T = 4.75 \cdot \text{lbf} \cdot \text{ft} & p_1 = 12.5 \cdot \text{psi} & z_1 = 6.5 \cdot \text{ft} & V_1 = 6.5 \cdot \frac{\text{ft}}{\text{s}} & z_2 = 32.5 \cdot \text{ft} & V_2 = 15 \cdot \frac{\text{ft}}{\text{s}} \end{array}$$

From Eq. 10.8c  $H_p = \frac{\omega \cdot T \cdot \eta_p}{\rho \cdot Q \cdot g}$   $H_p = 124 \cdot \text{ft}$

Hence, from Eq. 10.8b  $p_2 = p_1 + \frac{\rho}{2} \cdot (V_1^2 - V_2^2) + \rho \cdot g \cdot (z_1 - z_2) + \rho \cdot g \cdot H_p$   $p_2 = 53.7 \cdot \text{psi}$

Also  $\dot{W}_h = \rho \cdot g \cdot Q \cdot H_p$   $\dot{W}_h = 1119 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $\dot{W}_h = 2.03 \cdot \text{hp}$

The shaft work is then  $\dot{W}_m = \frac{\dot{W}_h}{\eta_p}$   $\dot{W}_m = 1492 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $\dot{W}_m = 2.71 \cdot \text{hp}$

Hence, electrical input is  $\dot{W}_e = \frac{\dot{W}_m}{\eta_e}$   $\dot{W}_e = 1756 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{s}}$   $\dot{W}_e = 2.38 \cdot \text{kW}$

### Problem 10.29

[Difficulty: 2]

**10.29** The kilogram force (kgf), defined as the force exerted by a kilogram mass in standard gravity, is commonly used in European practice. The metric horsepower (hpm) is defined as  $1 \text{ hpm} \equiv 75 \text{ m}\cdot\text{kgf}/\text{s}$ . Develop a conversion relating metric horsepower to U.S. horsepower. Relate the specific speed for a hydraulic turbine—calculated in units of rpm, metric horsepower, and meters—to the specific speed calculated in U.S. customary units.

Solution:

$$1 \text{ hp (U.S.)} = \frac{550 \text{ ft}\cdot\text{lb}_f}{\text{s}} \times \frac{0.305 \text{ m}}{\text{ft}} \times \frac{0.4536 \text{ kgf}}{\text{lb}_f} \times \frac{\text{hpm}\cdot\text{s}}{75 \text{ m}\cdot\text{kgf}} = 1.01 \text{ hpm}$$

hpm

$$\begin{aligned} N_{s_{cu}} &= \frac{N(\rho)^{1/2}}{(h)^{5/4}} = \frac{N(\text{rpm})[\rho(\text{hpUS})]^{1/2}}{[h(\text{ft})]^{5/4}} \\ &= \frac{N(\text{rpm})[\rho(\text{hpUS})]^{1/2}}{[\rho(\text{hpm})]^{1/2}} \times \frac{[\rho(\text{hpm})]^{1/2}}{[h(\text{ft})]^{5/4}} \times \frac{[h(\text{m})]^{5/4}}{[h(\text{m})]^{5/4}} \\ &= \frac{N(\text{rpm})[\rho(\text{hpm})]^{1/2}}{[h(\text{m})]^{5/4}} \times \left[ \frac{\rho(\text{hpUS})}{\rho(\text{hpm})} \right]^{1/2} \times \left[ \frac{h(\text{m})}{h(\text{ft})} \right]^{5/4} \\ &= N_s(\text{rpm, hpm, m}) \times (1.01)^{1/2} \times (0.305)^{5/4} \end{aligned}$$

$$N_{s_{cu}} = 0.228 N_s(\text{rpm, hpm, m})$$

Ns

Check:  $N = 1 \text{ rpm}, \rho = 1 \text{ hp}, h = 1 \text{ ft}; N_s(\text{USCS}) = 1$

$$N = 1 \text{ rpm}, \rho = 1 \text{ hpm}, h = 1 \text{ m}; N_s = \frac{(1)(1.01)^{1/2}}{(0.305)^{5/4}} = 4.39$$

$$\frac{N_s(\text{USCS})}{N_s(\text{rpm, hpm, m})} = \frac{1}{4.39} = 0.228 \quad \checkmark\checkmark$$

# Problem 10.30

[Difficulty: 2]

10.30 Write the pump specific speed in terms of the flow coefficient and the head coefficient.

Solution:

$$N_s = \frac{\omega Q^{1/2}}{h^{3/4}} \quad \text{--- (1.6a)}$$

Flow coefficient  $\pi_1 = \frac{\omega Q}{h}$

Head coefficient  $\pi_2 = \frac{\omega^2}{h}$

Then

$$N_s = \left[ \frac{Q}{\omega D^3} \right]^{1/2} \cdot \left[ \frac{\omega^2 D^2}{h} \right]^{3/4} = \frac{Q^{1/2}}{\omega^{1/2} D^{3/2}} \cdot \frac{\omega^{3/2} D^{3/2}}{h^{3/4}} = \frac{\omega Q^{1/2}}{h^{3/4}}$$

$$N_s = \pi_1^{1/2} / \pi_2^{3/4}$$

$N_s$

14 3/4" 50 SHEETS PER REAM 5 SQUARE  
 17 1/8" 104 SHEETS PER REAM 8 SQUARE  
 20 1/4" 144 SHEETS PER REAM 10 SQUARE  
 22 1/2" 180 SHEETS PER REAM 12 SQUARE  
 24 3/8" 200 RECYCLED WHITE 6 SQUARE



## Problem 10.31

[Difficulty: 2]

**10.31** A small centrifugal pump, when tested at  $N=2875$  rpm with water, delivered  $Q=0.016$  m<sup>3</sup>/s and  $H=40$  m at its best efficiency point ( $\eta=0.70$ ). Determine the specific speed of the pump at this test condition. Sketch the impeller shape you expect. Compute the required power input to the pump.

**Given:** Data on small centrifugal pump

**Find:** Specific speed; Sketch impeller shape; Required power input

**Solution:**


Basic equation:  $N_S = \frac{\omega Q^{1/2}}{h^{3/4}}$  (Eq. 7.22a)       $\eta_p = \frac{\dot{W}_h}{\dot{W}_m} = \frac{\rho Q g H_p}{\omega T}$  (Eq. 10.3c)

The given or available data is

$$\rho = 1000 \frac{\text{kg}}{\text{m}^3} \quad \omega = 2875 \cdot \text{rpm} \quad \eta_p = 70\% \quad Q = 0.016 \frac{\text{m}^3}{\text{s}} \quad H = 40 \cdot \text{m}$$

Hence  $h = g \cdot H$        $h = 392 \frac{\text{m}^2}{\text{s}^2}$       (H is energy/weight. h is energy/mass)

Then  $N_S = \frac{\omega \cdot Q^{1/2}}{h^{3/4}}$        $N_S = 0.432$




From the figure we see the impeller will be centrifugal

The power input is (from Eq. 10.3c)  $W_m = \frac{W_h}{\eta_p}$        $W_m = \frac{\rho \cdot Q \cdot g \cdot H}{\eta_p}$        $W_m = 8.97 \cdot \text{kW}$

### Problem 10.32

[Difficulty: 2]

**10.32** Typical performance curves for a centrifugal pump, tested with three different impeller diameters in a single casing, are shown. Specify the flow rate and head produced by the pump at its best efficiency point with a 12-in. diameter impeller. Scale these data to predict the performance of this pump when tested with 11 in. and 13 in. impellers. Comment on the accuracy of the scaling procedure.



Solution: From the graph, BEP occurs for the 12 in. impeller at  
 $Q \approx 2200$  gpm and  $H \approx 130$  ft

BEP<sub>12</sub>

From Section 10-4.3, scaling rules are

$$Q_2 = Q_1 \left( \frac{D_2}{D_1} \right)^3; \quad Q_{11} = 2200 \text{ gpm} \left( \frac{11}{12} \right)^3 \approx 1690 \text{ gpm}$$

$$Q_{13} = 2200 \text{ gpm} \left( \frac{13}{12} \right)^3 \approx 2800 \text{ gpm}$$

$$H_2 = H_1 \left( \frac{D_2}{D_1} \right)^2; \quad H_{11} = 130 \text{ ft} \left( \frac{11}{12} \right)^2 \approx 109 \text{ ft}$$

$$H_{13} = 130 \text{ ft} \left( \frac{13}{12} \right)^2 \approx 153 \text{ ft}$$

Thus BEP<sub>11</sub> is at  $Q \approx 1690$  gpm,  $H \approx 109$  ft

BEP<sub>11</sub>

BEP<sub>13</sub> is at  $Q \approx 2800$  gpm,  $H \approx 153$  ft

BEP<sub>13</sub>

The complete scaling rules tend to move the volume flow rate too far. Accuracy would be improved using  $Q_2 = Q_1 (D_2/D_1)^2$ , since the impeller width does not change, and  $H_2 = H_1 (D_2/D_1)^2$ , since  $H \approx V^2$ . With these modified rules

$$(Q_{11}, H_{11}) \approx 1850 \text{ gpm}, 109 \text{ ft} \quad \text{and} \quad (Q_{13}, H_{13}) \approx 2580 \text{ gpm}, 153 \text{ ft}$$

These modified scaling points are closer to the measured BEPs.

## Problem 10.33

[Difficulty: 3]

**10.33** A pump with  $D=500$  mm delivers  $Q=0.725$  m<sup>3</sup>/s of water at  $H=10$  m at its best efficiency point. If the specific speed of the pump is 1.74, and the required input power is 90 kW, determine the shutoff head,  $H_0$ , and best efficiency,  $\eta$ . What type of pump is this? If the pump is now run at 900 rpm, by scaling the performance curve, estimate the new flow rate, head, shutoff head, and required power.

**Given:** Data on a pump

**Find:** Shutoff head; best efficiency; type of pump; flow rate, head, shutoff head and power at 900 rpm

**Solution:**

The given or available data is

$$\rho = 999 \frac{\text{kg}}{\text{m}^3} \quad N_s = 1.74 \quad D = 500 \cdot \text{mm} \quad Q = 0.725 \frac{\text{m}^3}{\text{s}} \quad H = 10 \cdot \text{m} \quad W_m = 90 \cdot \text{kW} \quad \omega' = 900 \cdot \text{rpm}$$

The governing equations are

$$W_h = \rho \cdot Q \cdot g \cdot H \quad N_s = \frac{\omega \cdot Q^{\frac{1}{4}}}{h^{\frac{3}{4}}} \quad H_0 = C_1 = \frac{U_2^2}{g}$$

Similarity rules:

$$\frac{Q_1}{\omega_1 \cdot D_1^3} = \frac{Q_2}{\omega_2 \cdot D_2^3} \quad \frac{h_1}{\omega_1^2 \cdot D_1^2} = \frac{h_2}{\omega_2^2 \cdot D_2^2} \quad \frac{P_1}{\rho_1 \cdot \omega_1^3 \cdot D_1^5} = \frac{P_2}{\rho_2 \cdot \omega_2^3 \cdot D_2^5}$$

$$h = g \cdot H = 98.1 \frac{\text{J}}{\text{kg}} \quad \text{Hence} \quad \omega = \frac{N_s \cdot h^{\frac{3}{4}}}{Q^{\frac{1}{4}}} \quad \omega = 63.7 \frac{\text{rad}}{\text{s}} \quad W_h = \rho \cdot Q \cdot g \cdot H = 71.0 \text{ kW} \quad \eta_p = \frac{W_h}{W_m} = 78.9\%$$

The shutoff head is given by

$$H_0 = \frac{U_2^2}{g} \quad U_2 = \frac{D}{2} \cdot \omega \quad U_2 = 15.9 \frac{\text{m}}{\text{s}} \quad \text{Hence} \quad H_0 = \frac{U_2^2}{g} \quad H_0 = 25.8 \text{ m}$$

with  $D_1 = D_2$ :

$$\frac{Q_1}{\omega_1} = \frac{Q_2}{\omega_2} \quad \text{or} \quad \frac{Q}{\omega} = \frac{Q'}{\omega'} \quad Q' = Q \cdot \frac{\omega'}{\omega} = 1.073 \frac{\text{m}^3}{\text{s}} \quad \frac{h_1}{\omega_1^2} = \frac{h_2}{\omega_2^2} \quad \text{or} \quad \frac{H}{\omega^2} = \frac{H'}{\omega'^2} \quad H' = H \cdot \left(\frac{\omega'}{\omega}\right)^2 = 21.9 \text{ m}$$

Also

$$\frac{H_0}{\omega^2} = \frac{H'_0}{\omega'^2} \quad H'_0 = H_0 \cdot \left(\frac{\omega'}{\omega}\right)^2 \quad H'_0 = 56.6 \text{ m}$$

$$\frac{P_1}{\rho \cdot \omega_1^3} = \frac{P_2}{\rho \cdot \omega_2^3} \quad \text{or} \quad \frac{W_m}{\omega^3} = \frac{W'_m}{\omega'^3} \quad W'_m = W_m \cdot \left(\frac{\omega'}{\omega}\right)^3 \quad W'_m = 292 \cdot \text{kW}$$

## Problem 10.34

[Difficulty: 3]

**10.34** At its best efficiency point ( $\eta = 0.87$ ), a mixed-flow pump, with  $D = 16$  in., delivers  $Q = 2500$  cfm of water at  $H = 140$  ft when operating at  $N = 1350$  rpm. Calculate the specific speed of this pump. Estimate the required power input. Determine the curve-fit parameters of the pump performance curve based on the shutoff point and the best efficiency point. Scale the performance curve to estimate the flow, head, efficiency, and power input required to run the same pump at 820 rpm.

**Given:** Data on a pump at BEP

**Find:** (a) Specific Speed  
 (b) Required power input  
 (c) Curve fit parameters for the pump performance curve.  
 (d) Performance of pump at 820 rpm

**Solution:**

The given or available data is

$$\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad \eta = 87\% \quad D = 16 \cdot \text{in} \quad Q = 2500 \cdot \text{cfm} \quad H = 140 \cdot \text{ft} \quad \omega = 1350 \cdot \text{rpm} \quad \omega' = 820 \cdot \text{rpm}$$

The governing equations are

$$N_s = \frac{\omega \sqrt{Q}}{(g \cdot H)^{0.75}} \quad W_h = \rho \cdot Q \cdot g \cdot H \quad W = \frac{W_h}{\eta} \quad H_0 = \frac{U_2^2}{g}$$

The specific speed is:

$$N_s = 1.66$$

The power is:

$$W = 761 \cdot \text{hp}$$

At shutoff  $U_2 = \frac{D}{2} \cdot \omega \quad U_2 = 94.248 \cdot \frac{\text{ft}}{\text{s}} \quad \text{Therefore:} \quad H_0 = \frac{U_2^2}{g} \quad H_0 = 276.1 \cdot \text{ft}$

Since  $H = H_0 - A \cdot Q^2$  it follows that  $A = \frac{H_0 - H}{Q^2} \quad A = 2.18 \times 10^{-5} \cdot \frac{\text{min}^2}{\text{ft}^5}$

Another way to write this is:  $H(\text{ft}) = 276.1 - 2.18 \times 10^{-5} \cdot Q(\text{cfm})^2$

$$\omega' = 820 \cdot \text{rpm} \quad H'_0 = H_0 \cdot \left(\frac{\omega'}{\omega}\right)^2 \quad \text{and} \quad A' = A \quad \text{Thus:} \quad H'_0 = 101.9 \cdot \text{ft} \quad A' = 2.18 \times 10^{-5} \cdot \frac{\text{min}^2}{\text{ft}^5}$$

At BEP:  $Q' = Q \cdot \left(\frac{\omega'}{\omega}\right) \quad Q' = 1519 \cdot \text{cfm} \quad H' = H \cdot \left(\frac{\omega'}{\omega}\right)^2 \quad H' = 51.7 \cdot \text{ft} \quad \eta' = \eta = 87\%$

At  $W_m = W \cdot \left(\frac{\omega'}{\omega}\right)^3 \quad W_m = 170.5 \cdot \text{hp}$

## Problem 10.35

[Difficulty: 3]

**10.35** A pumping system must be specified for a lift station at a wastewater treatment facility. The average flow rate is 110 million liters per day and the required lift is 10 m. Non-clogging impellers must be used; about 65 percent efficiency is expected. For convenient installation, electric motors of 37.5 kW or less are desired. Determine the number of motor/pump units needed and recommend an appropriate operating speed.

**Given:** Data on pumping system

**Find:** Number of pumps needed; Operating speed

**Solution:**

Basic equations:  $W_h = \rho \cdot Q \cdot g \cdot H$       $\eta_p = \frac{W_h}{W_m}$

The given or available data is

$$\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad Q_{\text{total}} = 110 \times 10^6 \cdot \frac{\text{L}}{\text{day}} \quad Q_{\text{total}} = 1.273 \frac{\text{m}^3}{\text{s}} \quad H = 10 \cdot \text{m} \quad \eta = 65\%$$

Then for the system  $W_h = \rho \cdot Q_{\text{total}} \cdot g \cdot H$       $W_h = 125 \cdot \text{kW}$

The required total power is  $W_m = \frac{W_h}{\eta}$       $W_m = 192 \cdot \text{kW}$

Hence the total number of pumps must be  $\frac{192}{37.5} = 5.12$  , or at least six pumps


The flow rate per pump will then be  $Q = \frac{Q_{\text{total}}}{6}$       $Q = 0.212 \frac{\text{m}^3}{\text{s}}$       $Q = 212 \cdot \frac{\text{L}}{\text{s}}$

From Fig. 10.15 the peak efficiency is at a specific speed of about

$$N_{\text{Scu}} = 2000$$

We also need  $H = 32.8 \cdot \text{ft}$       $Q = 3363 \cdot \text{gpm}$

Hence  $N = N_{\text{Scu}} \cdot \frac{H^{3/4}}{Q^{1/2}}$       $N = 473$



The nearest standard speed to  $N = 473$  rpm should be used

## Problem 10.36

[Difficulty: 2]

**10.36** A centrifugal water pump operates at 1750 rpm; the impeller has backward-curved vanes with  $\beta_2=60^\circ$  and  $b_2=1.25$  cm. At a flow rate of  $0.025$  m<sup>3</sup>/s, the radial outlet velocity is  $V_{n2}=3.5$  m/s. Estimate the head this pump could deliver at 1150 rpm.

**Given:** Data on centrifugal pump

**Find:** Head at 1150 rpm

**Solution:**

Basic equation: 
$$H = \frac{\dot{W}_m}{\dot{m}g} = \frac{1}{g} (U_2 V_{t2} - U_1 V_{t1}) \quad (\text{Eq. 10.2c})$$

The given or available data is

$$\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad Q = 0.025 \cdot \frac{\text{m}^3}{\text{s}} \quad \beta_2 = 60\text{-deg} \quad b_2 = 1.25 \cdot \text{cm}$$

$$\omega = 1750 \cdot \text{rpm} \quad \omega' = 1150 \cdot \text{rpm} \quad V_{n2} = 3.5 \cdot \frac{\text{m}}{\text{s}}$$

From continuity 
$$V_{n2} = \frac{Q}{2 \cdot \pi \cdot r_2 \cdot b_2}$$

Hence 
$$r_2 = \frac{Q}{2 \cdot \pi \cdot b_2 \cdot V_{n2}} \quad r_2 = 0.0909 \text{ m} \quad r_2 = 9.09 \cdot \text{cm}$$

Then 
$$V'_{n2} = \frac{\omega'}{\omega} \cdot V_{n2} \quad V'_{n2} = 2.30 \cdot \frac{\text{m}}{\text{s}}$$

Also 
$$U'_2 = \omega' \cdot r_2 \quad U'_2 = 11.0 \cdot \frac{\text{m}}{\text{s}}$$

From the outlet geometry 
$$V'_{t2} = U'_2 - V'_{n2} \cdot \cos(\beta_2) \quad V'_{t2} = 9.80 \cdot \frac{\text{m}}{\text{s}}$$

Finally 
$$H' = \frac{U'_2 \cdot V'_{t2}}{g} \quad H' = 10.9 \text{ m}$$

## Problem 10.37

[Difficulty: 3]

**10.37** A set of eight 30-kW motor-pump units is used to deliver water through an elevation of 30 m. The efficiency of the pumps is specified to be 65 percent. Estimate the delivery (liters per day) and select an appropriate operating speed.

**Given:** Data on pumping system

**Find:** Total delivery; Operating speed

**Solution:**

Basic equations:  $W_h = \rho \cdot Q \cdot g \cdot H$       $\eta_p = \frac{W_h}{W_m}$

The given or available data is

$$\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad W_m = 30 \cdot \text{kW} \quad H = 30 \cdot \text{m} \quad H = 98.425 \cdot \text{ft} \quad \eta = 65\%$$

Then for the system  $W_{mTotal} = 8 \cdot W_m$       $W_{mTotal} = 240 \cdot \text{kW}$

The hydraulic total power is  $W_{hTotal} = W_{mTotal} \cdot \eta$       $W_{hTotal} = 156 \cdot \text{kW}$


The total flow rate will then be  $Q_{Total} = \frac{W_{hTotal}}{\rho \cdot g \cdot H}$       $Q_{Total} = 0.53 \cdot \frac{\text{m}^3}{\text{s}}$       $Q_{Total} = 4.58 \times 10^7 \cdot \frac{\text{L}}{\text{day}}$

The flow rate per pump is  $Q = \frac{Q_{Total}}{8}$       $Q = 0.066 \cdot \frac{\text{m}^3}{\text{s}}$       $Q = 1051 \cdot \text{gpm}$

From Fig. 10.15 the peak efficiency is at a specific speed of about

$$N_{Scu} = 2500$$

Hence  $N = N_{Scu} \cdot \frac{H^{3/4}}{Q^{1/2}}$       $N = 2410$



The nearest standard speed to  $N = 2410$  rpm should be used

## Problem 10.38

[Difficulty: 2]

**10.38** Appendix D contains area bound curves for pump model selection and performance curves for individual pump models. Use these data to verify the similarity rules for a Peerless Type 4AE12 pump, with impeller diameter  $D=11.0$  in., operated at 1750 and 3550 nominal rpm.

Solution: From Figs. D.4 and D.5, at the best efficiency point (BEP):

$N$ (rpm)	$Q$ (gpm)	$H$ (ft)	$W_m$ (hp)	$\eta$ (%)
1750	470	104	17	73 <sup>+</sup>
3550	970	430	135	74 <sup>+</sup>

The similarity rules are

$$\frac{Q_1}{\omega_1 D_1^3} = \frac{Q_2}{\omega_2 D_2^3}, \quad \frac{H_1}{\omega_1^2 D_1^2} = \frac{H_2}{\omega_2^2 D_2^2}, \quad \frac{P_1}{\omega_1^3 D_1^5} = \frac{P_2}{\omega_2^3 D_2^5}, \quad \text{and } \eta_1 = \eta_2$$

Evaluating, with  $D_1 = D_2$ ,

$$Q_1 = Q_2 \frac{\omega_1}{\omega_2} = 970 \text{ gpm} \frac{1750 \text{ rpm}}{3550 \text{ rpm}} = 478 \text{ gpm}$$

$$H_1 = H_2 \left( \frac{\omega_1}{\omega_2} \right)^2 = 430 \text{ ft} \left( \frac{1750 \text{ rpm}}{3550 \text{ rpm}} \right)^2 = 104 \text{ ft}$$

$$P_1 = P_2 \left( \frac{\omega_1}{\omega_2} \right)^3 = 135 \text{ hp} \left( \frac{1750 \text{ rpm}}{3550 \text{ rpm}} \right)^3 = 16.2 \text{ hp}$$

$$\eta_1 = \eta_2 = 0.74^+$$

Comparing shows excellent agreement.

## Problem 10.39

[Difficulty: 3]

**10.39** Appendix D contains area bound curves for pump model selection and performance curves for individual pump models. Use these data and the similarity rules to predict and plot the curves of head  $H$  (ft) versus  $Q$  (gpm) of a Peerless Type 10AE12 pump, with impeller diameter  $D=12$  in., for nominal speeds of 1000, 1200, 1400, and 1600 rpm.

**Given:** Data on Peerless Type 10AE12 pump at 1720 rpm

**Find:** Data at speeds of 1000, 1200, 1400, and 1600 rpm

**Solution:**

The governing equations are the similarity rules: 
$$\frac{Q_1}{\omega_1 \cdot D_1^3} = \frac{Q_2}{\omega_2 \cdot D_2^3} \quad \frac{h_1}{\omega_1^2 \cdot D_1^2} = \frac{h_2}{\omega_2^2 \cdot D_2^2} \quad \text{where} \quad h = g \cdot H$$

For scaling from speed  $\omega_1$  to speed  $\omega_2$ :  $Q_2 = Q_1 \cdot \frac{\omega_2}{\omega_1} \quad H_2 = H_1 \cdot \left(\frac{\omega_2}{\omega_1}\right)^2$  Here are the results generated in *Excel*:


Speed (rpm) = 1760				Speed (rpm) = 1000		Speed (rpm) = 1200		Speed (rpm) = 1400		Speed (rpm) = 1600	
$Q$ (gal/min)	$Q^2$	$H$ (ft)	$H$ (fit)	$Q$ (gal/min)	$H$ (ft)						
0	0	170	161	0	52.0	0	74.9	0	102.0	0	133.2
500	250000	160	160	284	51.7	341	74.5	398	101.3	455	132.4
1000	1000000	155	157	568	50.7	682	73.0	795	99.3	909	129.7
1500	2250000	148	152	852	49.0	1023	70.5	1193	96.0	1364	125.4
2000	4000000	140	144	1136	46.6	1364	67.1	1591	91.3	1818	119.2
2500	6250000	135	135	1420	43.5	1705	62.6	1989	85.3	2273	111.4
3000	9000000	123	123	1705	39.7	2045	57.2	2386	77.9	2727	101.7
3500	12250000	110	109	1989	35.3	2386	50.8	2784	69.2	3182	90.4
4000	16000000	95	93	2273	30.2	2727	43.5	3182	59.1	3636	77.2

Data from Fig. D.8 is "eyeballed"

The fit to data is obtained from a least squares fit to  $H = H_0 - A Q^2$

$$H_0 = 161 \text{ ft}$$

$$A = 4.23E-06 \text{ ft/(gal/min)}^2$$



## Problem 10.40

[Difficulty: 3]

**10.40** Consider the Peerless Type 16A18B horizontal split case centrifugal pump (Appendix D). Use these performance data to verify the similarity rules for (a) impeller diameter change and (b) operating speeds of 705 and 880 rpm (note the scale change between speeds).

Solution: From Figs. D.9 and D.10 at the best efficiency point (BEP):

N (rpm)	D (in.)	Q (gpm)	H (ft)	W <sub>m</sub> (hp)	η (%)
705	18.0	6250	42	76	86 <sup>+</sup>
	17.0	5850	37	63	86 <sup>+</sup>
	16.0	5600	32	54	86
880	18.0	7900	69	155	87 <sup>+</sup>
	17.0	7400	59	125	87
	16.0	7100	50	105	85

The similarity rules are:

$$\frac{Q_1}{\omega_1 D_1^3} = \frac{Q_2}{\omega_2 D_2^3}, \quad \frac{H_1}{\omega_1^2 D_1^2} = \frac{H_2}{\omega_2^2 D_2^2}, \quad \frac{P_1}{\omega_1^3 D_1^5} = \frac{P_2}{\omega_2^3 D_2^5}, \quad \text{and } \eta_1 = \eta_2$$

Evaluating with  $\omega_1 = \omega_2 = 705$  rpm,

$$Q_{17} = Q_{18} \left(\frac{17}{18}\right)^3 = 5270 \text{ gpm}, \quad Q_{16} = 4390 \text{ gpm}; \quad H_{17} = H_{18} \left(\frac{17}{18}\right)^2 = 37.5 \text{ ft},$$

$$H_{16} = 33.2 \text{ ft}; \quad P_{17} = P_{18} \left(\frac{17}{18}\right)^5 = 57.1 \text{ hp}, \quad P_{16} = 42.2 \text{ hp}; \quad \eta = \text{constant}$$

At 880 rpm,  $Q_{17} = 6660$  gpm,  $Q_{16} = 5550$  gpm;  $H_{17} = 61.5$  ft,  $H_{16} = 54.5$  ft;

$$P_{17} = 116 \text{ hp}, \quad P_{16} = 86.0 \text{ hp}; \quad \eta = \text{constant}$$

Evaluating with  $D_1 = D_2 = 18.0$  in.,

$$Q_{705} = Q_{880} \left(\frac{705}{880}\right) = 6330 \text{ gpm}; \quad H_{705} = H_{880} \left(\frac{705}{880}\right)^2 = 44.3 \text{ ft};$$

$$P_{705} = P_{880} \left(\frac{705}{880}\right)^3 = 79.7 \text{ hp}; \quad \eta = \text{constant}$$

Comparing results with data shows at constant speed:

(1) flow rate scales poorly, (2) head scales well, (3) power scales poorly with changes in diameter.

Comparing results with data shows at constant diameter:

all quantities scale well with changes in speed.

Flow rate scaling may be improved using the modified procedure discussed on page 52b, in which  $Q \sim D^2$  and  $P \sim D^4$ .

## Problem 10.41

[Difficulty: 3]

**10.41** Use data from Appendix D to verify the similarity rules for the effect of changing the impeller diameter of a Peerless Type 4AE12 pump operated at 1750 and 3550 nominal rpm.

Solution: From Figs. D.4 and D.5 at the best efficiency point (BEP):

N (rpm)	D (in.)	Q (gpm)	H (ft)	$\dot{W}_m$ (hp)	$\eta$ (%)
1750	10.00	455	87	13	73 <sup>+</sup>
	11.00	470	104	17	73 <sup>+</sup>
	12.12	500	123	22	73 <sup>+</sup>
3550	10.00	930	360	115	74 <sup>+</sup>
	11.00	970	430	135	74 <sup>+</sup>
	12.12	1030	500	180	74 <sup>+</sup>

The similarity rules are:

$$\frac{Q_1}{\omega_1 D_1^3} = \frac{Q_2}{\omega_2 D_2^3}; \quad \frac{H_1}{\omega_1^2 D_1^2} = \frac{H_2}{\omega_2^2 D_2^2}; \quad \frac{P_1}{\omega_1^3 D_1^5} = \frac{P_2}{\omega_2^3 D_2^5}; \quad \text{and } \eta_1 = \eta_2.$$

Evaluating, with  $\omega_1 = \omega_2 = 1750$  rpm,

$$Q_{10} = Q_{11} \left(\frac{10}{11}\right)^3 = 353; \quad Q_{12} = Q_{11} \left(\frac{12.12}{11}\right)^3 = 629; \quad H_{10} = 86.0 \text{ ft}, \quad H_{12} = 126 \text{ ft}$$

$$P_{10} = 10.6 \text{ hp}, \quad P_{12} = 27.6 \text{ hp}; \quad \eta = \text{constant}$$

Evaluating, with  $\omega_1 = \omega_2 = 3550$  rpm,

$$Q_{10} = 729 \text{ gpm}, \quad Q_{12} = 1300 \text{ gpm}; \quad H_{10} = 355 \text{ ft}, \quad H_{12} = 522 \text{ ft}; \quad P_{10} = 83.8 \text{ hp},$$

$$P_{12} = 219 \text{ hp}; \quad \eta = \text{constant}$$

Comparing results with data shows:

- (1) flow rate is scaled poorly
- (2) head is scaled well
- (3) power is scaled poorly (because flow rate is scaled poorly)

Better results are obtained using the modified scaling rules (see p. 526); then

$$Q \sim D^2 \quad \text{so } Q_{10} = 388 \text{ gpm and } P \sim D^4 \quad \text{so } P_{10} = 11.6 \text{ hp at } 1750 \text{ rpm}$$

and 
$$Q_{10} = 802 \text{ gpm and } P_{10} = 92.2 \text{ hp at } 3550 \text{ rpm.}$$

## Problem 10.42

[Difficulty: 3]

**10.42** Performance curves for Peerless horizontal split case pumps are presented in Appendix D. Develop and plot a curve-fit for a Type 10AE12 pump driven at 1150 nominal rpm using the procedure described in Example 10.6.

Solution: Tabulate performance data and curve-fit, for  $D = 12$  in. diameter impeller at 1760 nominal rpm:

$Q$ (gpm)	1500	2000	2500	3000	3500	4000
$H$ (ft)	148	141	133	123	110	95
$\hat{H}$ (ft)	148	141	133	122	110	95.5

Curve-fit:  $\hat{H}(\text{ft}) = 157 - 3.83 \times 10^{-6} [Q(\text{gpm})]^2$ ;  $r^2 = 0.999$

or  $\hat{H} = H_0 - A Q^2$

The similarity rules are

$$\frac{Q_1}{\omega_1 D_1^3} = \frac{Q_2}{\omega_2 D_2^3} ; \frac{H_1}{\omega_1^2 D_1^2} = \frac{H_2}{\omega_2^2 D_2^2}$$

The pump diameter stays constant, so

$$Q_2 = Q_1 \left( \frac{\omega_2}{\omega_1} \right) \text{ and } H_2 = H_1 \left( \frac{\omega_2}{\omega_1} \right)^2 = H_1 \left( \frac{1150}{1760} \right)^2 = 0.427 H_1$$

Following the procedure of Example Problem 10.6, then at 1150 rpm,


$$\hat{H}(\text{ft}) = 0.427 H_0 - A Q^2$$

$$= (0.427) 157 \text{ ft} - 3.83 \times 10^{-6} [Q(\text{gpm})]^2$$

$$\hat{H}(\text{ft}) = 67.0 \text{ ft} - 3.83 \times 10^{-6} [Q(\text{gpm})]^2$$

$\hat{H}(\text{ft})$   
(1150 rpm)

The plot is:



# Problem 10.43

[Difficulty: 3]

**10.43** Performance curves for Peerless horizontal split case pumps are presented in Appendix D. Develop and plot curve-fits for a Type 16A18B pump, with impeller diameter  $D=18.0$  in., driven at 705 and 880 nominal rpm. Verify the effects of pump speed on scaling pump curves using the procedure described in Example 10.6.

Solution: Tabulate performance data and curve-fits:


705 rpm:	$Q$ (gpm)	0	2000	4000	6000	8000	BEP:	6250
	$H$ (ft)	59	56	50	43	32		42

Curve-fit:  $\hat{H}(\text{ft}) = 57.8 - 4.09 \times 10^{-7} [Q(\text{gpm})]^2$ ;  $r^2 = 0.994$

880 rpm:	$Q$ (gpm)	0	2000	4000	6000	8000	BEP:	7900
	$H$ (ft)	92	89	84	78	68		69

Curve-fit:  $\hat{H}(\text{ft}) = 91.5 - 4.01 \times 10^{-7} [Q(\text{gpm})]^2$ ;  $r^2 = 0.992$

Plot:



Using the procedure of Example Problem 10.6:

$$Q_{B'} = Q_B = 0; H_{B'} = H_B \left(\frac{\omega'}{\omega}\right)^2 = 59 \text{ ft} \left(\frac{880}{705}\right)^2 = 91.9 \text{ ft}$$

$$Q_{C'} = Q_C \left(\frac{\omega'}{\omega}\right) = 6250 \text{ gpm} \left(\frac{880}{705}\right) = 7800 \text{ gpm}$$

$$H_{C'} = H_C \left(\frac{\omega'}{\omega}\right)^2 = 42 \text{ ft} \left(\frac{880}{705}\right)^2 = 65.4 \text{ ft}$$

Comparing the curve-fit parameters shows good agreement:

$$\hat{H} = H_0 - A Q^2 \quad H_0 = 91.5 \text{ ft compared to } H_{B'} = 91.9 \text{ ft}$$

$$\left. \begin{aligned} A' &= 4.01 \times 10^{-7} \text{ ft}/(\text{gpm})^2 \\ A &= 4.09 \times 10^{-7} \text{ ft}/(\text{gpm})^2 \end{aligned} \right\} \text{ within } 2.0\%$$

## Problem 10.44

[Difficulty: 4]

**10.44** Catalog data for a centrifugal water pump at design conditions are  $Q=250$  gpm and  $\Delta p=18.6$  psi at 1750 rpm. A laboratory flume requires 200 gpm at 32 ft of head. The only motor available develops 3 hp at 1750 rpm. Is this motor suitable for the laboratory flume? How might the pump/motor match be improved?

Solution: To obtain efficiency and pump power requirement, find specific speed.

$$H = \frac{\Delta p}{\rho g} = 18.6 \frac{\text{lb}_f}{\text{in}^2} \times \frac{\text{ft}^2}{62.4 \text{ lb}_f/\text{ft}^3} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 42.9 \text{ ft} \quad ; \quad Q = \frac{250 \text{ gal}}{\text{min}} = 0.557 \text{ cfs}$$

$$N_{s_{cu}} = \frac{N Q^{1/2}}{H^{3/4}} = \frac{1750 \text{ rpm} (250 \text{ gpm})^{1/2}}{(42.9 \text{ ft})^{3/4}} = 1650$$

From Fig. 10.15,  $\eta \approx 0.73$ . Thus

$$W_m = \frac{W_h}{\eta} = \frac{\rho Q g H}{\eta} = \frac{1}{0.73} \times 62.4 \frac{\text{lb}_f}{\text{ft}^3} \times 0.557 \frac{\text{ft}^3}{\text{s}} \times 42.9 \text{ ft} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}_f} = 3.71 \text{ hp}$$

The motor is not suitable to drive the pump directly. ←

The pump at 1750 rpm produces more head and flow than necessary. It may be run at reduced speed, e.g., by using a belt drive.

To produce  $Q_f = 200$  gpm, solve  $\frac{Q_p}{\omega_p D_p^3} = \frac{Q_f}{\omega_f D_f^3}$ ;  $\omega_f = \frac{200}{250} \times 1750 = 1400$  rpm

To produce  $H_f = 32$  ft, solve  $\frac{H_p}{\omega_p^2 D_p^2} = \frac{H_f}{\omega_f^2 D_f^2}$ ;  $\omega_f = \sqrt{\frac{H_f}{H_p}} \omega_p = \sqrt{\frac{32}{42.9}} \times 1750 = 1510$  rpm

At 1510 rpm the power requirement will be given by  $\frac{P_p}{\omega_p^3 D_p^5} = \frac{P_f}{\omega_f^3 D_f^5}$ , so

$$P_f = P_p \left( \frac{\omega_f}{\omega_p} \right)^3 = 3.71 \text{ hp} \left( \frac{1510}{1750} \right)^3 = 2.38 \text{ hp}$$

This is well within the capability of the 3 hp motor. Therefore run pump at 1510 rpm. ←



# Problem 10.45

Sample	Fig.	Model	Speed (rpm)	$H_0$ (ft)	$H_{BEP}$ (ft)	$H_{BEP}/H_0$ (---)
1	D.3	4AE11	1750	113	95	0.84
2	D.5	4AE12	3550	636	500	0.79
3	D.6	6AE14	1750	209	160	0.77
4	D.7	8AE20G	1770	430	365	0.85
5	D.8	10AE12	1760	170	112	0.66
6	D.9	16A18B	705	59	42	0.71
7	D.10	16A18B	880	92	69	0.75
Average:						0.766





Fig.	Model	Speed (rpm)	$D_{min}$ (in.)	$Q_{BEP}$ (gpm)	$D_{max}$ (in.)	$Q_{BEP}$ (gpm)	$(D_{max}/D_{min})^2$ (---)	$Q_{max}/Q_{min}$ (---)
D.3	4AE11	1750	7.62	740	11.25	960	2.2	1.3
D.5	4AE12	3550	9.5	910	12.12	1040	1.6	1.1
D.6	6AE14	1750	10.38	1375	14.0	1750	1.8	1.3
D.7	8AE20G	1770	16.0	2200	20.0	3450	1.6	1.6
D.8	10AE12	1760	9.0	2500	12.0	3400	1.8	1.4
D.9	16A18B	705	15.0	5100	18.0	6200	1.4	1.2
D.10	16A18B	880	15.0	6500	18.0	7900	1.4	1.2
Correlation:								0.751



15-AUG 4 32 38 PM '81  
 42-383  
 42-384  
 42-385  
 42-386  
 42-387  
 42-388  
 42-389  
 42-390  
 42-391  
 42-392  
 42-393  
 42-394  
 42-395  
 42-396  
 42-397  
 42-398  
 42-399  
 42-400  
 42-401  
 42-402  
 42-403  
 42-404  
 42-405  
 42-406  
 42-407  
 42-408  
 42-409  
 42-410  
 42-411  
 42-412  
 42-413  
 42-414  
 42-415  
 42-416  
 42-417  
 42-418  
 42-419  
 42-420  
 42-421  
 42-422  
 42-423  
 42-424  
 42-425  
 42-426  
 42-427  
 42-428  
 42-429  
 42-430  
 42-431  
 42-432  
 42-433  
 42-434  
 42-435  
 42-436  
 42-437  
 42-438  
 42-439  
 42-440  
 42-441  
 42-442  
 42-443  
 42-444  
 42-445  
 42-446  
 42-447  
 42-448  
 42-449  
 42-450  
 42-451  
 42-452  
 42-453  
 42-454  
 42-455  
 42-456  
 42-457  
 42-458  
 42-459  
 42-460  
 42-461  
 42-462  
 42-463  
 42-464  
 42-465  
 42-466  
 42-467  
 42-468  
 42-469  
 42-470  
 42-471  
 42-472  
 42-473  
 42-474  
 42-475  
 42-476  
 42-477  
 42-478  
 42-479  
 42-480  
 42-481  
 42-482  
 42-483  
 42-484  
 42-485  
 42-486  
 42-487  
 42-488  
 42-489  
 42-490  
 42-491  
 42-492  
 42-493  
 42-494  
 42-495  
 42-496  
 42-497  
 42-498  
 42-499  
 42-500  
 42-501  
 42-502  
 42-503  
 42-504  
 42-505  
 42-506  
 42-507  
 42-508  
 42-509  
 42-510  
 42-511  
 42-512  
 42-513  
 42-514  
 42-515  
 42-516  
 42-517  
 42-518  
 42-519  
 42-520  
 42-521  
 42-522  
 42-523  
 42-524  
 42-525  
 42-526  
 42-527  
 42-528  
 42-529  
 42-530  
 42-531  
 42-532  
 42-533  
 42-534  
 42-535  
 42-536  
 42-537  
 42-538  
 42-539  
 42-540  
 42-541  
 42-542  
 42-543  
 42-544  
 42-545  
 42-546  
 42-547  
 42-548  
 42-549  
 42-550  
 42-551  
 42-552  
 42-553  
 42-554  
 42-555  
 42-556  
 42-557  
 42-558  
 42-559  
 42-560  
 42-561  
 42-562  
 42-563  
 42-564  
 42-565  
 42-566  
 42-567  
 42-568  
 42-569  
 42-570  
 42-571  
 42-572  
 42-573  
 42-574  
 42-575  
 42-576  
 42-577  
 42-578  
 42-579  
 42-580  
 42-581  
 42-582  
 42-583  
 42-584  
 42-585  
 42-586  
 42-587  
 42-588  
 42-589  
 42-590  
 42-591  
 42-592  
 42-593  
 42-594  
 42-595  
 42-596  
 42-597  
 42-598  
 42-599  
 42-600  
 42-601  
 42-602  
 42-603  
 42-604  
 42-605  
 42-606  
 42-607  
 42-608  
 42-609  
 42-610  
 42-611  
 42-612  
 42-613  
 42-614  
 42-615  
 42-616  
 42-617  
 42-618  
 42-619  
 42-620  
 42-621  
 42-622  
 42-623  
 42-624  
 42-625  
 42-626  
 42-627  
 42-628  
 42-629  
 42-630  
 42-631  
 42-632  
 42-633  
 42-634  
 42-635  
 42-636  
 42-637  
 42-638  
 42-639  
 42-640  
 42-641  
 42-642  
 42-643  
 42-644  
 42-645  
 42-646  
 42-647  
 42-648  
 42-649  
 42-650  
 42-651  
 42-652  
 42-653  
 42-654  
 42-655  
 42-656  
 42-657  
 42-658  
 42-659  
 42-660  
 42-661  
 42-662  
 42-663  
 42-664  
 42-665  
 42-666  
 42-667  
 42-668  
 42-669  
 42-670  
 42-671  
 42-672  
 42-673  
 42-674  
 42-675  
 42-676  
 42-677  
 42-678  
 42-679  
 42-680  
 42-681  
 42-682  
 42-683  
 42-684  
 42-685  
 42-686  
 42-687  
 42-688  
 42-689  
 42-690  
 42-691  
 42-692  
 42-693  
 42-694  
 42-695  
 42-696  
 42-697  
 42-698  
 42-699  
 42-700  
 42-701  
 42-702  
 42-703  
 42-704  
 42-705  
 42-706  
 42-707  
 42-708  
 42-709  
 42-710  
 42-711  
 42-712  
 42-713  
 42-714  
 42-715  
 42-716  
 42-717  
 42-718  
 42-719  
 42-720  
 42-721  
 42-722  
 42-723  
 42-724  
 42-725  
 42-726  
 42-727  
 42-728  
 42-729  
 42-730  
 42-731  
 42-732  
 42-733  
 42-734  
 42-735  
 42-736  
 42-737  
 42-738  
 42-739  
 42-740  
 42-741  
 42-742  
 42-743  
 42-744  
 42-745  
 42-746  
 42-747  
 42-748  
 42-749  
 42-750  
 42-751  
 42-752  
 42-753  
 42-754  
 42-755  
 42-756  
 42-757  
 42-758  
 42-759  
 42-760  
 42-761  
 42-762  
 42-763  
 42-764  
 42-765  
 42-766  
 42-767  
 42-768  
 42-769  
 42-770  
 42-771  
 42-772  
 42-773  
 42-774  
 42-775  
 42-776  
 42-777  
 42-778  
 42-779  
 42-780  
 42-781  
 42-782  
 42-783  
 42-784  
 42-785  
 42-786  
 42-787  
 42-788  
 42-789  
 42-790  
 42-791  
 42-792  
 42-793  
 42-794  
 42-795  
 42-796  
 42-797  
 42-798  
 42-799  
 42-800  
 42-801  
 42-802  
 42-803  
 42-804  
 42-805  
 42-806  
 42-807  
 42-808  
 42-809  
 42-810  
 42-811  
 42-812  
 42-813  
 42-814  
 42-815  
 42-816  
 42-817  
 42-818  
 42-819  
 42-820  
 42-821  
 42-822  
 42-823  
 42-824  
 42-825  
 42-826  
 42-827  
 42-828  
 42-829  
 42-830  
 42-831  
 42-832  
 42-833  
 42-834  
 42-835  
 42-836  
 42-837  
 42-838  
 42-839  
 42-840  
 42-841  
 42-842  
 42-843  
 42-844  
 42-845  
 42-846  
 42-847  
 42-848  
 42-849  
 42-850  
 42-851  
 42-852  
 42-853  
 42-854  
 42-855  
 42-856  
 42-857  
 42-858  
 42-859  
 42-860  
 42-861  
 42-862  
 42-863  
 42-864  
 42-865  
 42-866  
 42-867  
 42-868  
 42-869  
 42-870  
 42-871  
 42-872  
 42-873  
 42-874  
 42-875  
 42-876  
 42-877  
 42-878  
 42-879  
 42-880  
 42-881  
 42-882  
 42-883  
 42-884  
 42-885  
 42-886  
 42-887  
 42-888  
 42-889  
 42-890  
 42-891  
 42-892  
 42-893  
 42-894  
 42-895  
 42-896  
 42-897  
 42-898  
 42-899  
 42-900  
 42-901  
 42-902  
 42-903  
 42-904  
 42-905  
 42-906  
 42-907  
 42-908  
 42-909  
 42-910  
 42-911  
 42-912  
 42-913  
 42-914  
 42-915  
 42-916  
 42-917  
 42-918  
 42-919  
 42-920  
 42-921  
 42-922  
 42-923  
 42-924  
 42-925  
 42-926  
 42-927  
 42-928  
 42-929  
 42-930  
 42-931  
 42-932  
 42-933  
 42-934  
 42-935  
 42-936  
 42-937  
 42-938  
 42-939  
 42-940  
 42-941  
 42-942  
 42-943  
 42-944  
 42-945  
 42-946  
 42-947  
 42-948  
 42-949  
 42-950  
 42-951  
 42-952  
 42-953  
 42-954  
 42-955  
 42-956  
 42-957  
 42-958  
 42-959  
 42-960  
 42-961  
 42-962  
 42-963  
 42-964  
 42-965  
 42-966  
 42-967  
 42-968  
 42-969  
 42-970  
 42-971  
 42-972  
 42-973  
 42-974  
 42-975  
 42-976  
 42-977  
 42-978  
 42-979  
 42-980  
 42-981  
 42-982  
 42-983  
 42-984  
 42-985  
 42-986  
 42-987  
 42-988  
 42-989  
 42-990  
 42-991  
 42-992  
 42-993  
 42-994  
 42-995  
 42-996  
 42-997  
 42-998  
 42-999  
 43-000



# Problem 10.46

[Difficulty: 5]

10.46 White [53] suggests modeling the efficiency for a centrifugal pump using the curve-fit,  $\eta = aQ - bQ^3$ , where  $a$  and  $b$  are constants. Describe a procedure to evaluate  $a$  and  $b$  from experimental data. Evaluate  $a$  and  $b$  using data for the Peerless Type 10AE12 pump, with impeller diameter  $D=12.0$  in., at 1760 rpm (Appendix D). Plot and illustrate the accuracy of the curve-fit by comparing measured and predicted efficiencies for this pump.

Solution: From Fig. D.8, data are:

$\eta$ (%)	70	75	80	84	86	86	84
$Q$ (gpm)	1850	2100	2400	2780	3100	3700	4075

Two equations are needed to solve for constants  $a$  and  $b$  directly. A second equation may be obtained by differentiating. At peak efficiency,  $\frac{d\eta}{dQ} = a - 3bQ^2 = 0$

Assume peak efficiency is 87 percent at 3400 gpm. Then


$$\eta_{max} = aQ - bQ^3$$

$$0 = a - 3bQ^2$$

Substituting from the second equation into the first gives

$$\eta_{max} = 3bQ^3 - bQ^3 = 2bQ^3 ; b = \frac{\eta_{max}}{2Q^3} = 1.11 \times 10^{-9} ; a = 3bQ^2 = 0.0384 \quad a, b$$

Plotting:



The curve-fit does a good job near peak efficiency, but tends to underestimate the measured data elsewhere.

{ An alternative curve-fit procedure is to plot  $\eta/Q$  versus  $a - bQ^2$ , then do a least-squares fit (using all the data) to obtain  $a$  and  $b$ . Then  $a = 0.0426 \text{ (gpm)}^{-1}$ ,  $b = -1.56 \times 10^{-9} \text{ (gpm)}^{-2}$ ,  $r^2 = 0.996$ . This underestimates  $\eta$  at  $Q > 3500$  gpm. }

## Problem 10.47

[Difficulty: 3]

**10.47** A fan operates at  $Q = 6.3 \text{ m}^3/\text{s}$ ,  $H = 0.15 \text{ m}$ , and  $N = 1440 \text{ rpm}$ . A smaller, geometrically similar fan is planned in a facility that will deliver the same head at the same efficiency as the larger fan, but at a speed of 1800 rpm. Determine the volumetric flow rate of the smaller fan.

**Given:** Data on a model fan, smaller scale similar fan

**Find:** Scale factor and volumetric flow rate of similar fan

**Solution:**

Basic equations:

$$\frac{Q_1}{\omega_1 \cdot D_1^3} = \frac{Q_2}{\omega_2 \cdot D_2^3} \quad \frac{H_1}{\omega_1^2 \cdot D_1^2} = \frac{H_2}{\omega_2^2 \cdot D_2^2}$$

The given or available data is

$$\omega_1 = 1440 \cdot \text{rpm}$$

$$\omega_2 = 1800 \cdot \text{rpm}$$

$$Q_1 = 6.3 \cdot \frac{\text{m}^3}{\text{s}}$$

$$H_1 = 0.15 \cdot \text{m}$$

$$H_2 = H_1 = 0.15 \text{ m}$$

Solving the head equation for the scale  $D_2/D_1$ :  $\frac{D_2}{D_1} = \frac{\omega_1}{\omega_2} \cdot \sqrt{\frac{H_2}{H_1}} = 0.8$

$$\frac{D_2}{D_1} = 0.8$$

We can use this to find the new flowrate:  $Q_2 = Q_1 \cdot \frac{\omega_2}{\omega_1} \cdot \left(\frac{D_2}{D_1}\right)^3$

$$Q_2 = 4.03 \frac{\text{m}^3}{\text{s}}$$

## Problem 10.48

[Difficulty: 3]

**10.48** A 1/3 scale model of a centrifugal water pump, when running at  $N_m = 5100$  rpm, produces a flow rate of  $Q_m = 1 \text{ m}^3/\text{s}$  with a head of  $H_m = 5.4$  m. Assuming the model and prototype efficiencies are comparable, estimate the flow rate, head, and power requirement if the design speed is 125 rpm.

**Given:** Data on a model pump

**Find:** Prototype flow rate, head, and power at 125 rpm

**Solution:**

Basic equation:

$$W_h = \rho \cdot Q \cdot g \cdot H \quad \text{and similarity rules}$$

$$\frac{Q_1}{\omega_1 \cdot D_1^3} = \frac{Q_2}{\omega_2 \cdot D_2^3}$$

$$(10.19a) \quad \frac{h_1}{\omega_1^2 \cdot D_1^2} = \frac{h_2}{\omega_2^2 \cdot D_2^2} \quad (10.19b) \quad \frac{P_1}{\rho_1 \cdot \omega_1^3 \cdot D_1^5} = \frac{P_2}{\rho_2 \cdot \omega_2^3 \cdot D_2^5} \quad (10.19a)$$

The given or available data is

$$N_m = 100 \cdot \text{rpm} \quad N_p = 125 \cdot \text{rpm} \quad \rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$$

$$Q_m = 1 \cdot \frac{\text{m}^3}{\text{s}} \quad H_m = 4.5 \cdot \text{m}$$

From Eq. 10.8a

$$W_{hm} = \rho \cdot Q_m \cdot g \cdot H_m \quad W_{hm} = 44.1 \cdot \text{kW}$$

From Eq. 10.19a (with  $D_m/D_p = 1/3$ )

$$\frac{Q_p}{\omega_p \cdot D_p^3} = \frac{Q_m}{\omega_m \cdot D_m^3} \quad \text{or} \quad Q_p = Q_m \cdot \frac{\omega_p}{\omega_m} \cdot \left(\frac{D_p}{D_m}\right)^3 = 3^3 \cdot Q_m \cdot \frac{\omega_p}{\omega_m}$$

$$Q_p = 27 \cdot Q_m \cdot \frac{N_p}{N_m} \quad Q_p = 33.8 \frac{\text{m}^3}{\text{s}}$$

From Eq. 10.19b (with  $D_m/D_p = 1/3$ )

$$\frac{h_p}{\omega_p^2 \cdot D_p^2} = \frac{h_m}{\omega_m^2 \cdot D_m^2} \quad \text{or} \quad \frac{g \cdot H_p}{\omega_p^2 \cdot D_p^2} = \frac{g \cdot H_m}{\omega_m^2 \cdot D_m^2}$$

$$H_p = H_m \cdot \left(\frac{\omega_p}{\omega_m}\right)^2 \cdot \left(\frac{D_p}{D_m}\right)^2 = 3^2 \cdot H_m \cdot \left(\frac{\omega_p}{\omega_m}\right)^2 \quad H_p = 9 \cdot H_m \cdot \left(\frac{N_p}{N_m}\right)^2 \quad H_p = 63.3 \text{ m}$$

From Eq. 10.19c (with  $D_m/D_p = 1/3$ )

$$\frac{P_p}{\rho \cdot \omega_p^3 \cdot D_p^5} = \frac{P_m}{\rho \cdot \omega_m^3 \cdot D_m^5} \quad \text{or} \quad W_{hp} = W_{hm} \cdot \left(\frac{\omega_p}{\omega_m}\right)^3 \cdot \left(\frac{D_p}{D_m}\right)^5 = 3^5 \cdot W_{hm} \cdot \left(\frac{\omega_p}{\omega_m}\right)^3$$

$$W_{hp} = 243 \cdot W_{hm} \cdot \left(\frac{N_p}{N_m}\right)^3 \quad W_{hp} = 20.9 \cdot \text{MW}$$

## Problem 10.49

[Difficulty: 2]

**10.49** Sometimes the variation of water viscosity with temperature can be used to achieve dynamic similarity. A model pump delivers  $0.10 \text{ m}^3/\text{s}$  of water at  $15^\circ\text{C}$  against a head of  $27 \text{ m}$ , when operating at  $3600 \text{ rpm}$ . Determine the water temperature that must be used to obtain dynamically similar operation at  $1800 \text{ rpm}$ . Estimate the volume flow rate and head produced by the pump at the lower-speed test condition. Comment on the *NPSH* requirements for the two tests.

**Given:** Data on a model pump

**Find:** Temperature for dynamically similar operation at  $1800 \text{ rpm}$ ; Flow rate and head; Comment on *NPSH*

**Solution:**

Basic equation:  $Re_1 = Re_2$  and similarity rules  $\frac{Q_1}{\omega_1 \cdot D_1^3} = \frac{Q_2}{\omega_2 \cdot D_2^3}$   $\frac{H_1}{\omega_1^2 \cdot D_1^2} = \frac{H_2}{\omega_2^2 \cdot D_2^2}$

The given or available data is  $\omega_1 = 3600 \cdot \text{rpm}$   $\omega_2 = 1800 \cdot \text{rpm}$   $Q_1 = 0.1 \cdot \frac{\text{m}^3}{\text{s}}$   $H_1 = 27 \cdot \text{m}$

From Table A.8 at  $15^\circ\text{C}$   $\nu_1 = 1.14 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$

For  $D = \text{constant}$   $Re_1 = \frac{V_1 \cdot D}{\nu_1} = \frac{\omega_1 \cdot D \cdot D}{\nu_1} = Re_2 = \frac{\omega_2 \cdot D \cdot D}{\nu_2}$  or  $\nu_2 = \nu_1 \cdot \frac{\omega_2}{\omega_1}$   $\nu_2 = 5.7 \times 10^{-7} \frac{\text{m}^2}{\text{s}}$

From Table A.8, at  $\nu_2 = 5.7 \times 10^{-7} \frac{\text{m}^2}{\text{s}}$ , we find, by linear interpolation

$$T_2 = 45 + \frac{(50 - 45)}{(5.52 - 6.02)} \cdot (5.70 - 6.02) \quad T_2 = 48 \text{ degrees C}$$

From similar operation  $\frac{Q_1}{\omega_1 \cdot D^3} = \frac{Q_2}{\omega_2 \cdot D^3}$  or  $Q_2 = Q_1 \cdot \frac{\omega_2}{\omega_1}$   $Q_2 = 0.0500 \cdot \frac{\text{m}^3}{\text{s}}$

and also  $\frac{H_1}{\omega_1^2 \cdot D^2} = \frac{H_2}{\omega_2^2 \cdot D^2}$  or  $H_2 = H_1 \cdot \left(\frac{\omega_2}{\omega_1}\right)^2$   $H_2 = 6.75 \text{ m}$

The water at  $48^\circ\text{C}$  is closer to boiling. The inlet pressure would have to be changed to avoid cavitation. The increase between runs 1 and 2 would have to be  $\Delta p = p_{v2} - p_{v1}$  where  $p_{v2}$  and  $p_{v1}$  are the vapor pressures at  $T_2$  and  $T_1$ . From the steam tables:

$$p_{v1} = 1.71 \cdot \text{kPa} \quad p_{v2} = 11.276 \cdot \text{kPa} \quad \Delta p = p_{v2} - p_{v1} \quad \Delta p = 9.57 \cdot \text{kPa}$$

## Problem 10.50

[Difficulty: 4]

**10.50** A large deep fryer at a snack-food plant contains hot oil that is circulated through a heat exchanger by pumps. Solid particles and water droplets coming from the food product are observed in the flowing oil. What special factors must be considered in specifying the operating conditions for the pumps?

**Discussion:** Any solid particles must be able to pass through the pumps without clogging. If the particles are large, this may require larger than normal clearances within the pumps.

If the water droplets flashed to steam, they would form local pockets of water vapor. The pockets of water vapor would disrupt the flow patterns in the pumps in the same way as cavitation in a homogeneous liquid. To prevent this "cavitation" from occurring, static pressure everywhere in the flow circuit must be maintained above the saturation pressure of the water droplets at the temperature of the flowing oil.

The net positive suction head at the pump inlets must be sufficiently high to prevent any problems from occurring within the pumps themselves.

The solid particles may act as nucleation sites, which would foster the development of vapor pockets in the flow. This might increase the net positive suction head required by the pump above that measured in tests using water. The system must be sized to maintain a large net positive suction head at the design flow rate.

Finally, the viscosity of the oil must be considered. If viscosity is high, pump performance will be degraded compared to pumping water. Then a larger pump must be specified to handle the flow requirement of the hot oil circulation system.

71 710  
42 382  
42 383  
42 389  
42 392  
42 399  
300 RECYCLED PAPER  
300 RECYCLED WHITE PAPER



Made in U.S.A.

## Problem 10.51

[Difficulty: 2]

**10.51** Data from tests of a pump operated at 1450 rpm, with a 12.3-in. diameter impeller, are

Flow rate, $Q$ (cfm)	20	40	60	80	100	120	140
Net positive suction head required, $NPSR$ (ft)	7.1	8.0	8.9	10.3	11.8	12.3	16.9

Develop and plot a curve-fit equation for  $NPSHR$  versus volume flow rate in the form  $NPSHR = a + bQ^2$ , where  $a$  and  $b$  are constants. If the  $NPSHA = 20$  ft, estimate the maximum allowable flow rate of this pump.

**Given:** Data on a  $NPSHR$  for a pump


**Find:** Curve fit; Maximum allowable flow rate

**Solution:** The results were generated in *Excel*:

$Q$ (cfm)	$Q^2$	$NPSHR$ (ft)	$NPSHR$ (ft)
20	4.00E+02	7.1	7.2
40	1.60E+03	8.0	7.8
60	3.60E+03	8.9	8.8
80	6.40E+03	10.3	10.2
100	1.00E+04	11.8	12.0
120	1.44E+04	14.3	14.2
140	1.96E+04	16.9	16.9

The fit to data is obtained from a least squares fit to  $NPSHR = a + bQ^2$

$a =$	7.04	ft	$Q$ (cfm)	$NPSHR$ (ft)	
$b =$	5.01E-04	ft/(cfm) <sup>2</sup>	160.9	20.00	Use <i>Goal Seek</i> to find $Q$ !



## Problem 10.52

[Difficulty: 3]

**10.52** A four-stage boiler feed pump has suction and discharge lines of 10 cm and 7.5 cm inside diameter. At 3500 rpm, the pump is rated at 0.025 m<sup>3</sup>/s against a head of 125 m while handling water at 115°C. The inlet pressure gage, located 50 cm below the impeller centerline, reads 150 kPa. The pump is to be factory certified by tests at the same flow rate, head rise, and speed, but using water at 27°C. Calculate the *NPSHA* at the pump inlet in the field installation. Evaluate the suction head that must be used in the factory test to duplicate field suction conditions.

**Given:** Data on a boiler feed pump

**Find:** *NPSHA* at inlet for field temperature water; Suction head to duplicate field conditions

**Solution:**

Basic equation: 
$$NPSHA = p_t - p_v = p_g + p_{atm} + \frac{1}{2} \cdot \rho \cdot V^2 - p_v$$

Given or available data is

$D_s = 10 \cdot \text{cm}$	$D_d = 7.5 \cdot \text{cm}$	$H = 125 \cdot \text{m}$	$Q = 0.025 \cdot \frac{\text{m}^3}{\text{s}}$	
$p_{inlet} = 150 \cdot \text{kPa}$	$p_{atm} = 101 \cdot \text{kPa}$	$z_{inlet} = -50 \cdot \text{cm}$	$\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$	$\omega = 3500 \cdot \text{rpm}$

For field conditions 
$$p_g = p_{inlet} + \rho \cdot g \cdot z_{inlet} \quad p_g = 145 \cdot \text{kPa}$$

From continuity 
$$V_s = \frac{4 \cdot Q}{\pi \cdot D_s^2} \quad V_s = 3.18 \frac{\text{m}}{\text{s}}$$

From steam tables (try Googling!) at 115°C 
$$p_v = 169 \cdot \text{kPa}$$

Hence 
$$NPSHA = p_g + p_{atm} + \frac{1}{2} \cdot \rho \cdot V_s^2 - p_v \quad NPSHA = 82.2 \cdot \text{kPa}$$

Expressed in meters or feet of water 
$$\frac{NPSHA}{\rho \cdot g} = 8.38 \text{m} \quad \frac{NPSHA}{\rho \cdot g} = 27.5 \cdot \text{ft}$$

In the laboratory we must have the same *NPSHA*. From Table A.8 (or steam tables - try Googling!) at 27°C 
$$p_v = 3.57 \cdot \text{kPa}$$

Hence 
$$p_g = NPSHA - p_{atm} - \frac{1}{2} \cdot \rho \cdot V_s^2 + p_v \quad p_g = -20.3 \cdot \text{kPa}$$

The absolute pressure is 
$$p_g + p_{atm} = 80.7 \cdot \text{kPa}$$


## Problem 10.53

[Difficulty: 3]

**10.53** The net positive suction head required (*NPSHR*) by a pump may be expressed approximately as a parabolic function of volume flow rate. The *NPSHR* for a particular pump operating at 1800 rpm is given as  $H_r = H_0 = A Q^2$ , where  $H_0 = 10$  ft of water and  $A = 7.9$  ft/cfs<sup>2</sup>. Assume the pipe system supplying the pump suction consists of a reservoir, whose surface is 22 ft above the pump centerline, a square entrance, 20 ft of 6-in. (nominal) cast-iron pipe, and a 90° elbow. Calculate the maximum volume flow rate at 70°F for which the suction head is sufficient to operate this pump without cavitation.

**Given:** Pump and supply pipe system  
**Find:** Maximum operational flow rate

**Solution:**



Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT}$$

$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$$

$L_e$  for the elbow, and  $K$  for the square entrance

$$NPSHA = \frac{p_t - p_v}{\rho \cdot g}$$

$$H_r = H_0 + A \cdot Q^2$$

Assumptions: 1)  $p_1 = 0$  2)  $V_1 = 0$  3)  $\alpha_2 = 1$  4)  $z_2 = 0$

We must match the *NPSHR* ( $=H_r$ ) and *NPSHA* From the energy equation

$$g \cdot H - \left( \frac{p_2}{\rho} + \frac{V^2}{2} \right) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$$

$$\frac{p_2}{\rho \cdot g} = H - \frac{V^2}{2 \cdot g} \cdot \left[ 1 + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right]$$

$$NPSHA = \frac{p_t - p_v}{\rho \cdot g} = \frac{p_2}{\rho \cdot g} + \frac{p_{atm}}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} - \frac{p_v}{\rho \cdot g}$$

$$NPSHA = H - \frac{V^2}{2 \cdot g} \cdot \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] + \frac{(p_{atm} - p_v)}{\rho \cdot g}$$

Calculated results and plot were generated using *Excel*:

Given data:

Computed results:


$L = 20$  ft  
 $e = 0.00085$  ft  
 $D = 6.065$  in  
 $K_{ent} = 0.5$   
 $L_e/D = 30$   
 $H_0 = 10$  ft  
 $A = 7.9$  ft/(cfs)<sup>2</sup>  
 $H = 22$  ft  
 $p_{atm} = 14.7$  psia  
 $p_v = 0.363$  psia  
 $\nu = 1.93$  slug/ft<sup>3</sup>  
 $\nu = 1.06E-05$  ft<sup>2</sup>/s

$Q$ (cfs)	$V$ (ft/s)	$Re$	$f$	$NPSHA$ (ft)	$NPSHR$ (ft)
0.2	1.00	4.75E+04	0.0259	55.21	10.32
0.4	1.99	9.51E+04	0.0243	55.11	11.26
0.6	2.99	1.43E+05	0.0237	54.95	12.84
0.8	3.99	1.90E+05	0.0234	54.72	15.06
1.0	4.98	2.38E+05	0.0232	54.43	17.90
1.2	5.98	2.85E+05	0.0231	54.08	21.38
1.4	6.98	3.33E+05	0.0230	53.66	25.48
1.6	7.98	3.80E+05	0.0229	53.18	30.22
1.8	8.97	4.28E+05	0.0229	52.63	35.60
2.0	9.97	4.75E+05	0.0228	52.02	41.60
2.2	10.97	5.23E+05	0.0228	51.35	48.24
2.4	11.96	5.70E+05	0.0227	50.62	55.50
2.6	12.96	6.18E+05	0.0227	49.82	63.40

**Error**

<b>Crossover point:</b>	2.28	11.36	5.42E+05	0.0228	51.07	51.07	0.00
-------------------------	------	-------	----------	--------	-------	-------	------

### NPSHA and NPSHR



# Problem 10.54

[Difficulty: 2]

10.54 A centrifugal pump, operating at  $N=2265$  rpm, lifts water between two reservoirs connected by 300 ft of 6 in. and 100 ft of 3 in. cast-iron pipe in series. The gravity lift is 25 ft. Estimate the head requirement, power needed, and hourly cost of electrical energy to pump water at 200 gpm to the higher reservoir. Assume that electricity costs 12¢/kWhr, and that the electric motor efficiency is 85 percent.

## Solution:

Apply the energy equation to the total system for steady, incompressible flow using (3) and (4) at reservoir surfaces.

Computing eq.: 
$$\frac{p_3}{\rho g} + \alpha_3 \frac{V_3^2}{2g} + z_3 + H_a = \frac{p_4}{\rho g} + \alpha_4 \frac{V_4^2}{2g} + z_4 + h_{eT} \quad (10.24b)$$

$$h_{eT} = f_1 \frac{L_1}{D_1} \frac{V_1^2}{2g} + f_2 \frac{L_2}{D_2} \frac{V_2^2}{2g}$$

Assumptions: (1)  $p_3 = p_4 = p_{atm}$ ,  $V_3 = V_4 = 0$   
 (2) neglect minor losses

Then 
$$H_a = z_4 - z_3 + f_1 \frac{L_1}{D_1} \frac{V_1^2}{2g} + f_2 \frac{L_2}{D_2} \frac{V_2^2}{2g} \quad \dots \dots \dots (1)$$

$$V_1 = \frac{Q}{A_1} = \frac{200 \text{ gal}}{\text{min}} \times \frac{\text{ft}^3}{1.48 \text{ gal}} \times \frac{\text{min}}{60 \text{ s}} \times \frac{1}{\pi (0.50 \text{ ft})^2} = 2.27 \text{ ft/s}$$

$$V_2 = 9.08 \text{ ft/s} \quad \text{For water at } 59^\circ \text{F}, \nu = 1.23 \times 10^{-5} \text{ ft}^2/\text{s} \text{ (Table 8.1)}$$

$$Re_1 = \frac{V_1 D_1}{\nu} = \frac{2.27 \text{ ft/s} \times 6 \text{ in}}{1.23 \times 10^{-5} \text{ ft}^2/\text{s}} = 9.23 \times 10^4$$

$$Re_2 = 1.85 \times 10^5 \quad \text{From Table 8.1 for cast iron, } e = 0.00085 \text{ ft}$$

$$e/D_1 = 0.0017, \quad e/D_2 = 0.0034$$

From Eq. 8.37,  $f_1 = 0.0244$ ,  $f_2 = 0.0278$ . Substituting into (1)

$$H_a = 25 \text{ ft} + 0.0244 \times \frac{300 \times 12}{6} \times \frac{(2.27)^2}{2 \times 32.2} + 0.0278 \times \frac{100 \times 12}{3} \times \frac{(9.08)^2}{2 \times 32.2} = 32.2 \text{ ft}$$

$$H_a = 40.4 \text{ ft}$$

Specific speed:  $N_{su} = \frac{N \sqrt{Q}}{H^{3/4}} = \frac{2265 \sqrt{200}}{(40.4)^{3/4}} = 2000$

From Fig 10.15,  $\eta_p \approx 0.75$ . Then  $P_p = \frac{\gamma Q H}{\eta_p} = \frac{\rho g Q H}{\eta_p}$

$$P_p = \frac{1}{0.75} \times \frac{200 \text{ gal}}{\text{min}} \times \frac{\text{ft}^3}{1.48 \text{ gal}} \times \frac{\text{min}}{60 \text{ s}} \times 62.4 \frac{\text{lb}}{\text{ft}^3} \times 40.4 \text{ ft} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}} = 2.72 \text{ hp} \leftarrow P_m$$

Cost =  $c P_e$ . Since  $c = \$0.12 / \text{kWhr}$  &  $\eta_m = 0.85$


Then  $P_e = \frac{P_m}{\eta_m}$  and

$$\text{Cost} = c \frac{P_m}{\eta_m} = \frac{\$0.12}{\text{kWhr}} \times \frac{2.72 \text{ hp}}{0.85} \times 0.746 \frac{\text{kWh}}{\text{hp}} = 28.7 \text{ ¢/hr} \leftarrow C$$



Given data:			Computed results:										
$L$			$T$ (°C)	$p_v$ (kPa)	$\rho$ (kg/m <sup>3</sup> )	$\nu$ (m <sup>2</sup> /s)	$Q$ (m <sup>3</sup> /s)	$V$ (m/s)	$Re$	$f$	$NPSHA$ (m)	$NPSHR$ (m)	$Error$
$L =$	6	m	0	0.661	1000	1.76E-06	0.06290	3.56	3.03E+05	0.0232	14.87	14.87	0.00
$e =$	0.26	mm	5	0.872	1000	1.51E-06	0.06286	3.56	3.53E+05	0.0231	14.85	14.85	0.00
$D =$	15	cm	10	1.23	1000	1.30E-06	0.06278	3.55	4.10E+05	0.0230	14.82	14.82	0.00
$K_{ent} =$	0.5		15	1.71	999	1.14E-06	0.06269	3.55	4.67E+05	0.0230	14.79	14.79	0.00
$L_e/D =$	30		20	2.34	998	1.01E-06	0.06257	3.54	5.26E+05	0.0229	14.75	14.75	0.00
$H_0 =$	3	m	25	3.17	997	8.96E-07	0.06240	3.53	5.91E+05	0.0229	14.68	14.68	0.00
$A =$	3000	m/(m <sup>3</sup> /s) <sup>2</sup>	30	4.25	996	8.03E-07	0.06216	3.52	6.57E+05	0.0229	14.59	14.59	0.00
$H =$	6	m	35	5.63	994	7.25E-07	0.06187	3.50	7.24E+05	0.0228	14.48	14.48	0.00
$p_{atm} =$	101	kPa	40	7.38	992	6.59E-07	0.06148	3.48	7.92E+05	0.0228	14.34	14.34	0.00
$\pi =$	1000	kg/m <sup>3</sup>	45	9.59	990	6.02E-07	0.06097	3.45	8.60E+05	0.0228	14.15	14.15	0.00
$\pi =$	1.01E-06	m <sup>2</sup> /s	50	12.4	988	5.52E-07	0.06031	3.41	9.27E+05	0.0228	13.91	13.91	0.00
			55	15.8	986	5.09E-07	0.05948	3.37	9.92E+05	0.0228	13.61	13.61	0.00
			60	19.9	983	4.72E-07	0.05846	3.31	1.05E+06	0.0228	13.25	13.25	0.00
			65	25.0	980	4.40E-07	0.05716	3.23	1.10E+06	0.0227	12.80	12.80	0.00
			70	31.2	978	4.10E-07	0.05548	3.14	1.15E+06	0.0227	12.24	12.24	0.00
			75	38.6	975	3.85E-07	0.05342	3.02	1.18E+06	0.0227	11.56	11.56	0.00
			80	47.4	972	3.62E-07	0.05082	2.88	1.19E+06	0.0227	10.75	10.75	0.00
			85	57.8	969	3.41E-07	0.04754	2.69	1.18E+06	0.0227	9.78	9.78	0.00
			90	70.1	965	3.23E-07	0.04332	2.45	1.14E+06	0.0227	8.63	8.63	0.00
			95	84.6	962	3.06E-07	0.03767	2.13	1.05E+06	0.0228	7.26	7.26	0.00
			100	101	958	2.92E-07	0.02998	1.70	8.71E+05	0.0228	5.70	5.70	0.00
Use Solver to make the sum of absolute errors between $NPSHA$ and $NPSHR$ zero by varying the $Q$ 's													0.00

$NPSHR$  increases with temperature because the  $p_v$  increases;  $NPSHA$  decreases because  $\rho$  decreases and  $p_v$  increases



## Problem 10.56

[Difficulty: 3]

**10.56** A centrifugal pump is installed in a piping system with  $L=300$  m of  $D=40$  cm cast-iron pipe. The downstream reservoir surface is 15 m lower than the upstream reservoir. Determine and plot the system head curve. Find the volume flow rate (magnitude and direction) through the system when the pump is not operating. Estimate the friction loss, power requirement, and hourly energy cost to pump water at  $1$  m<sup>3</sup>/s through this system.

**Given:** Pump and reservoir system

**Find:** System head curve; Flow rate when pump off; Loss, Power required and cost for 1 m<sup>3</sup>/s flow rate

**Solution:**

Basic equations: 
$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \Sigma \cdot K \cdot \frac{V^2}{2} \text{ (K for the exit)}$$

where points 1 and 2 are the reservoir free surfaces, and  $h_p$  is the pump head

Note also  $H = \frac{h}{g}$  Pump efficiency:  $\eta_p = \frac{W_h}{W_m}$

Assumptions: 1)  $p_1 = p_2 = p_{atm}$  2)  $V_1 = V_2 = 0$  3)  $\alpha_2 = 0$  4)  $z_1 = 0, z_2 = -15 \cdot \text{m}$  4)  $K = K_{ent} + K_{ent} = 1.5$

From the energy equation  $-g \cdot z_2 = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} - h_p + K \cdot \frac{V^2}{2} \quad h_p = g \cdot z_2 + f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2} \quad H_p = z_2 + f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g} + K \cdot \frac{V^2}{2 \cdot g}$


Given or available data  $L = 300 \cdot \text{m}$   $D = 40 \cdot \text{cm}$   $e = 0.26 \cdot \text{mm}$  (Table 8.1)

$\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$  (Table A.8)

The set of equations to solve for each flow rate  $Q$  are

$V = \frac{4 \cdot Q}{\pi \cdot D^2}$   $Re = \frac{V \cdot D}{\nu}$   $\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$   $H_p = z_2 + f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g} + K \cdot \frac{V^2}{2 \cdot g}$

For example, for  $Q = 1 \cdot \frac{\text{m}^3}{\text{s}}$   $V = 7.96 \cdot \frac{\text{m}}{\text{s}}$   $Re = 3.15 \times 10^6$   $f = 0.0179$   $H_p = 33.1 \cdot \text{m}$



The above graph can be plotted in Excel. In Excel, Solver can be used to find Q for  $H_p = 0$   $Q = 0.557 \frac{\text{m}^3}{\text{s}}$  (Zero power rate)

At  $Q = 1 \cdot \frac{\text{m}^3}{\text{s}}$  we saw that  $H_p = 33.1 \cdot \text{m}$

Assuming optimum efficiency at  $Q = 1.59 \times 10^4 \cdot \text{gpm}$  from Fig. 10.15  $\eta_p = 92\%$

Then the hydraulic power is  $W_h = \rho \cdot g \cdot H_p \cdot Q$   $W_h = 325 \cdot \text{kW}$

The pump power is then  $W_m = \frac{W_h}{\eta_p}$   $W_m \cdot 2 = 706 \cdot \text{kW}$

If electricity is 10 cents per kW-hr then the hourly cost is about \$35

If electricity is 15 cents per kW-hr then the hourly cost is about \$53

If electricity is 20 cents per kW-hr then the hourly cost is about \$71

# Problem 10.57

[Difficulty: 2]

**10.57** Part of the water supply for the South Rim of Grand Canyon National Park is taken from the Colorado River [54]. A flow rate of 600 gpm, taken from the river at elevation 3734 ft, is pumped to a storage tank atop the South Rim at 7022 ft elevation. Part of the pipeline is above ground and part is in a hole directionally drilled at angles up to 70° from the vertical; the total pipe length is approximately 13,200 ft. Under steady flow operating conditions, the frictional head loss is 290 ft of water in addition to the static lift. Estimate the diameter of the commercial steel pipe in the system. Compute the pumping power requirement if the pump efficiency is 61 percent.

Solution:

Apply the energy equation to the total system for steady incompressible flow using ① and ② at inlet and reservoir surface respectively.

Computing eq.: 
$$\frac{p_1}{\rho g} + \alpha_1 \frac{V_1^2}{2g} + z_1 + H_a = \frac{p_2}{\rho g} + \alpha_2 \frac{V_2^2}{2g} + z_2 + \frac{h_{fr}}{g} \quad (10.24b)$$

$h_{fr} = f \frac{L}{D} \frac{V^2}{2g}$

Assumptions: (1)  $p_1 = p_2 = p_{atm}$ ,  $V_1 = V_2 = 0$   
 (2) neglect minor losses.

Then 
$$H_a = z_2 - z_1 + \frac{h_{fr}}{g} \quad \dots \dots (1) \quad \text{and} \quad \frac{h_{fr}}{g} = f \frac{L}{D} \frac{V^2}{2g} = 290 \text{ ft}$$

Since  $f = f(Re, e/D)$  and  $D$  is unknown, we must iterate.

For commercial steel,  $e = 0.00015 \text{ ft}$ .

The procedure is

- assume  $D$ , calculate  $V, Re$ ; determine  $f$  (Eqs 8.36a, b); calculate  $h_{fr}/g$  and compare to value of 290 ft.

D (in.)	V (ft/s)	Re	$f_0$	$f^{0.5}$	f	$h_{fr}/g$ (ft)
12	1.70	1.46E+06	0.0139	8.517	0.0138	8.2
10	2.45	1.75E+06	0.0141	8.433	0.0141	20.8
8	3.83	2.19E+06	0.0146	8.306	0.0145	65.3
6	6.81	2.92E+06	0.0153	8.111	0.0152	289

Thus  $D = 6.0 \text{ in}$

The total pump head is  $H_a = 7022 - 3734 + 290 = 3578 \text{ ft}$ .

The pump power is  $P_m = \frac{W_{sh}}{\eta_p} = \frac{\rho g Q H}{\eta_p}$

$$P_m = \frac{1}{0.61} \times 62.4 \frac{\text{lb}}{\text{ft}^3} \times 600 \frac{\text{gal}}{\text{min}} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{1 \text{ min}}{60 \text{ s}} \times 3578 \text{ ft} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}}$$

$P_m = 890 \text{ hp}$

# Problem 10.58

**10.58** A Peerless horizontal split-case type 4AE12 pump with 11.0-in.-diameter impeller, operating at 1750 rpm, lifts water between two reservoirs connected by 200 ft of 4 in. and 200 ft of 3 in. cast-iron pipe in series. The gravity lift is 10 ft. Plot the system head curve and determine the pump operating point.

Solution:

Apply the energy equation to the total system for steady, incompressible flow using (3) and (4) at reservoir surfaces.

Computing eq.: 
$$\frac{p_3}{\rho g} + \alpha_3 \frac{V_3^2}{2g} + z_3 + H_a = \frac{p_4}{\rho g} + \alpha_4 \frac{V_4^2}{2g} + z_4 + \frac{h_{ET}}{g} \quad (10.24b)$$

$$h_{ET} = f_1 \frac{L_1}{D_1} \frac{V_1^2}{2g} + f_2 \frac{L_2}{D_2} \frac{V_2^2}{2g}$$

Assumptions: (1)  $p_3 = p_4 = p_{atm}$ ,  $V_3 = V_4 = 0$   
 (2) neglect minor losses

then 
$$H_a = z_4 - z_3 + f_1 \frac{L_1}{D_1} \frac{V_1^2}{2g} + f_2 \frac{L_2}{D_2} \frac{V_2^2}{2g} \quad \dots (1)$$

Express  $V$  as a function of  $Q$ .

$$V_1 = \frac{Q}{A_1} = \frac{4Q}{\pi D_1^2} = \frac{4}{\pi} \times \left(\frac{12}{4}\right)^2 Q \left(\frac{\text{ft}^3/\text{min}}{\text{min}}\right) \times \frac{1.48 \text{ gal}}{60 \text{ s}} = 0.0255 Q (\text{gpm})$$

$$V_2 = 0.0454 Q (\text{gpm})$$

The friction factor is determined from the Colebrook eq.

$$\frac{1}{f_0.5} = -2.0 \log \left( \frac{\epsilon/D}{3.7} + \frac{2.51}{Re f_0.5} \right) \quad (8.37a)$$

using the equation of Miller for the original estimate

$$f_0 = 0.25 \left[ \log \left( \frac{\epsilon/D}{3.7} + \frac{5.74}{Re^{0.9}} \right) \right]^2 \quad (8.37b)$$

Assuming  $T = 59^\circ \text{F}$ ,  $\nu = 1.23 \times 10^{-5} \text{ ft}^2/\text{s}$  (Table A.7)

$$Re_1 = \frac{D_1 V_1}{\nu} = \frac{4}{12} \times \frac{10^5}{1.23} V_1 = 2.71 \times 10^4 V_1, \quad Re_2 = 2.03 \times 10^4 V_2$$

For cast iron,  $\epsilon = 0.00085 \text{ ft}$  (Table 8.1)

$$\epsilon/D_1 = 0.00255 \quad \epsilon/D_2 = 0.00340$$

$$H_a = 10 \text{ ft} + f_1 \times 9.317 V_1^2 + f_2 \times 12.42 V_2^2$$


The pump curve is obtained from Fig. D.4

# Problem 10.58

[Difficulty: 3] Part 2/2

Q (gpm)	V <sub>1</sub> (ft/s)	Re <sub>1</sub>	f <sub>0,1</sub>	f <sup>0.5</sup> <sub>1</sub>	f <sub>1</sub>	V <sub>2</sub> (ft/s)	Re <sub>2</sub>	f <sub>0,2</sub>	f <sup>0.5</sup> <sub>2</sub>	f <sub>2</sub>	H <sub>a</sub> (ft)
0	0.0	0.00E+00				0					10.0
50	1.3	3.46E+04	0.0290	5.905	0.0287	2.3	4.61E+04	0.0299	5.817	0.0295	12
100	2.6	6.91E+04	0.0273	6.063	0.0270	4.5	9.22E+04	0.0287	5.933	0.0284	19
150	3.8	1.04E+05	0.0266	6.154	0.0264	6.8	1.38E+05	0.0282	5.977	0.0280	30
200	5.1	1.38E+05	0.0263	6.193	0.0261	9.1	1.84E+05	0.0280	6.000	0.0278	45
250	6.4	1.73E+05	0.0261	6.217	0.0259	11.4	2.30E+05	0.0278	6.014	0.0277	64
300	7.7	2.07E+05	0.0259	6.233	0.0257	13.6	2.76E+05	0.0277	6.023	0.0276	88
350	8.9	2.42E+05	0.0258	6.245	0.0256	15.9	3.23E+05	0.0276	6.030	0.0275	115
400	10.2	2.76E+05	0.0257	6.255	0.0256	18.2	3.69E+05	0.0276	6.036	0.0275	147
450	11.5	3.11E+05	0.0256	6.262	0.0255	20.4	4.15E+05	0.0275	6.040	0.0274	183

Q (gpm)	H <sub>p</sub> (ft)
0	126
100	126
200	125
300	120
400	113
500	100
600	85



Pump operates at  $Q \approx 350$  gpm.  
 $H \approx 115$  ft

McGraw-Hill Education  
 1221 Avenue of the Americas  
 New York, NY 10020-1095  
 Copyright 2014 McGraw-Hill Education  
 All rights reserved.

## Problem 10.59

[Difficulty: 3]

**10.59** A pump transfers water from one reservoir to another through two cast-iron pipes in series. The first is 3000 ft of 9 in. pipe and the second is 1000 ft of 6 in. pipe. A constant flow rate of 75 gpm is tapped off at the junction between the two pipes. Obtain and plot the system head versus flow rate curve. Find the delivery if the system is supplied by the pump of Example 10.6, operating at 1750 rpm.

**Given:** Data on pump and pipe system

**Find:** Delivery through system

**Solution:**

Governing Equations:

For the pump and system

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + gz_2 \right) = h_{iT} - \Delta h_{\text{pump}} \quad (8.49)$$

where the total head loss is comprised of major and minor losses

$$h_l = f \frac{L}{D} \frac{\bar{V}^2}{2} \quad (8.34)$$

$$h_{lm} = K \frac{\bar{V}^2}{2} \quad (8.40a)$$

and the pump head (in energy/mass) is given by (from Example 10.6)

$$H_{\text{pump}}(\text{ft}) = 55.9 - 3.44 \times 10^{-5} \cdot Q(\text{gpm})^2$$

Hence, applied between the two reservoir free surfaces ( $p_1 = p_2 = 0$ ,  $V_1 = V_2 = 0$ ,  $z_1 = z_2$ ) we have

$$0 = h_{IT} - \Delta h_{\text{pump}}$$

$$h_{IT} = g \cdot H_{\text{system}} = \Delta h_{\text{pump}} = g \cdot H_{\text{pump}}$$

or

$$H_{IT} = H_{\text{pump}} \quad (1)$$

where

$$H_{IT} = \left( f_1 \cdot \frac{L_1}{D_1} + K_{\text{ent}} \right) \cdot \frac{V_1^2}{2 \cdot g} + \left( f_2 \cdot \frac{L_2}{D_2} + K_{\text{exit}} \right) \cdot \frac{V_2^2}{2}$$

Results generated in *Excel* are shown on the next page.

Given or available data:									
$L_1 =$	3000	ft	$v =$	1.23E-05	ft <sup>2</sup> /s (Table A.7)				
$D_1 =$	9	in	$K_{ent} =$	0.5	(Fig. 8.14)				
$L_2 =$	1000	ft	$K_{exp} =$	1					
$D_2 =$	6	in	$Q_{loss} =$	75	gpm				
$e =$	0.00085	ft (Table 8.1)							


The system and pump heads are computed and plotted below.

To find the operating condition, *Goal Seek* is used to vary  $Q_1$

so that the error between the two heads is zero.

$Q_1$ (gpm)	$Q_2$ (gpm)	$V_1$ (ft/s)	$V_2$ (ft/s)	$Re_1$	$Re_2$	$f_1$	$f_2$	$H_{IT}$ (ft)	$H_{pump}$ (ft)
100	25	0.504	0.284	30753	11532	0.0262	0.0324	0.498	55.6
200	125	1.01	1.42	61506	57662	0.0238	0.0254	3.13	54.5
300	225	1.51	2.55	92260	103792	0.0228	0.0242	8.27	52.8
400	325	2.02	3.69	123013	149922	0.0222	0.0237	15.9	50.4
500	425	2.52	4.82	153766	196052	0.0219	0.0234	26.0	47.3
600	525	3.03	5.96	184519	242182	0.0216	0.0233	38.6	43.5
700	625	3.53	7.09	215273	288312	0.0215	0.0231	53.6	39.0

$Q_1$ (gpm)	$Q_2$ (gpm)	$V_1$ (ft/s)	$V_2$ (ft/s)	$Re_1$	$Re_2$	$f_1$	$f_2$	$H_{IT}$ (ft)	$H_{pump}$ (ft)	Error
627	552	3.162	6.263	192785	254580	0.0216	0.0232	42.4	42.4	0%



## Problem 10.60

[Difficulty: 3]

**10.60** Performance data for a pump are

<b><i>H</i> (ft)</b>	90	87	81	70	59	43	22
<b><i>Q</i> (cfm)</b>	0	50	100	150	200	250	300

The pump is to be used to move water between two open reservoirs with an elevation increase of 24 ft. The connecting pipe system consists of 1750 ft of commercial steel pipe containing two 90° elbows and an open gate valve. Find the flow rate if we use (a) 8-in., (b) 10-in., and (c) 12-in. (nominal) pipe.

**Given:** Pump and reservoir/pipe system

**Find:** Flow rate using different pipe sizes

**Solution:**

Basic equations:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p$$

$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \Sigma \cdot f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + \Sigma \cdot K \cdot \frac{V^2}{2} \quad L_e \text{ for the elbows, and } K \text{ for the square entrance and exit}$$

and also  $H = \frac{h}{g}$

Assumptions: 1)  $p_1 = p_2 = p_{atm}$  2)  $V_1 = V_2 = 0$  3)  $\alpha = 1$  4)  $z_1 = 0, z_2 = 24 \text{ ft}$  4)  $K = K_{ent} + K_{exp}$  5)  $\frac{L_e}{D}$  is for two elbows

Hence 
$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2} \quad \text{and also} \quad -z_2 = H_{IT} - H_p \quad \text{or} \quad H_{IT} = H_p - z_2$$

We want to find a flow that satisfies these equations, rewritten as energy/weight rather than energy/mass

$$H_{IT} = \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \cdot \frac{V^2}{2 \cdot g} \quad H_{IT} + z_2 = H_p$$

Here are the results calculated in *Excel*:

Given or available data (**Note: final results will vary depending on fluid data selected**):

$L = 1750 \text{ ft}$	$K_{ent} = 0.5 \text{ (Fig. 8.14)}$
$e = 0.00015 \text{ ft (Table 8.1)}$	$K_{exp} = 1$
$D = 7.981 \text{ in}$	$L_e/D_{elbow} = 60 \text{ (Two)}$
$\nu = 1.06E-05 \text{ ft}^2/\text{s (Table A.8)}$	$L_e/D_{valve} = 8 \text{ (Table 8.4)}$
$z_2 = 24 \text{ ft}$	

The pump data is curve-fitted to  $H_{\text{pump}} = H_0 - AQ^2$ .

The system and pump heads are computed and plotted below.

To find the operating condition, *Solver* is used to vary  $Q$  so that the error between the two heads is minimized.

A plot of the pump and system heads is shown for the 8 in case - the others will look similar.

$Q$ (cfm)	$Q^2$	$H_p$ (ft)
0.000	0	90.0
50.000	2500	87.0
100.000	10000	81.0
150.000	22500	70.0
200.000	40000	59.0
250.000	62500	43.0
300.000	90000	22.0

$V$ (ft/s)	$Re$	$f$
0.00	0	0.0000
2.40	150504	0.0180
4.80	301007	0.0164
7.20	451511	0.0158
9.59	602014	0.0154
11.99	752518	0.0152
14.39	903022	0.0150

$H_p$ (fit)	$H_{T+z_2}$ (ft)
89	24.0
87	28.5
81	40.4
72	59.5
59	85.8
42.3	119.1
21.9	159.5

$$H_0 = 89 \text{ ft}$$

$$A = 7.41\text{E-}04 \text{ ft/(cfm)}^2$$


$Q$ (cfm)	$V$ (ft/s)	$Re$	$f$	$H_p$ (fit)	$H_{T+z_2}$ (ft)	Error
167.5	8.03	504063	0.0157	67.9	67.9	0.00%

Repeating for:  $D = 10.02 \text{ in}$

$Q$ (cfm)	$V$ (ft/s)	$Re$	$f$	$H_p$ (fit)	$H_{T+z_2}$ (ft)	Error
179.8	8.63	541345	0.0156	64.7	64.7	0.00%

Repeating for:  $D = 12 \text{ in}$

$Q$ (cfm)	$V$ (ft/s)	$Re$	$f$	$H_p$ (fit)	$H_{T+z_2}$ (ft)	Error
189.4	9.09	570077	0.0155	62.1	62.1	0.00%



## Problem 10.61

[Difficulty: 3]

**10.61** Performance data for a pump are

<i>H</i> (ft)	179	176	165	145	119	84	43
<i>Q</i> (gpm)	0	500	1000	1500	2000	2500	3000

Estimate the delivery when the pump is used to move water between two open reservoirs, through 1200 ft of 12 in. commercial steel pipe containing two 90° elbows and an open gate valve, if the elevation increase is 50 ft. Determine the gate valve loss coefficient needed to reduce the volume flow rate by half.

**Given:** Data on pump and pipe system

**Find:** Delivery through system, valve position to reduce delivery by half

**Solution:**

Governing Equations:

For the pump and system

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\tilde{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\tilde{V}_2^2}{2} + gz_2 \right) = h_{IT} - \Delta h_{\text{pump}} \quad (8.49)$$

where the total head loss is comprised of major and minor losses

$$h_l = f \frac{L}{D} \frac{\tilde{V}^2}{2} \quad (8.34)$$

$$h_{lm} = f \frac{L_e}{D} \frac{\tilde{V}^2}{2} \quad (8.40b)$$

$$h_{lm} = K \frac{\tilde{V}^2}{2} \quad (8.40a)$$

Hence, applied between the two reservoir free surfaces ( $p_1 = p_2 = 0$ ,  $V_1 = V_2 = 0$ ,  $z_1 - z_2 = \Delta z$ ) we have

$$g \cdot \Delta z = h_{IT} - \Delta h_{\text{pump}}$$

$$h_{IT} + g \cdot \Delta z = g \cdot H_{\text{system}} + g \cdot \Delta z = \Delta h_{\text{pump}} = g \cdot H_{\text{pump}}$$

or

$$H_{IT} + \Delta z = H_{\text{pump}}$$

where

$$H_{IT} = \left[ f \cdot \left( \frac{L}{D} + 2 \cdot \frac{L_e}{D_{\text{elbow}}} + \frac{L_e}{D_{\text{valve}}} \right) + K_{\text{ent}} + K_{\text{exit}} \right] \cdot \frac{V^2}{2 \cdot g}$$

The calculations performed using *Excel* are shown on the next page:

Given or available data (Note: final results will vary depending on fluid data selected):

$$\begin{aligned}
 L &= 1200 \text{ ft} & K_{\text{ent}} &= 0.5 \text{ (Fig. 8.14)} \\
 D &= 12 \text{ in} & K_{\text{exp}} &= 1 \\
 e &= 0.00015 \text{ ft (Table 8.1)} & L/D_{\text{elbow}} &= 30 \\
 \nu &= 1.23\text{E-}05 \text{ ft}^2/\text{s (Table A.7)} & L/D_{\text{valve}} &= 8 \text{ (Table 8.4)} \\
 H_z &= -50 \text{ ft}
 \end{aligned}$$

The pump data is curve-fitted to  $H_{\text{pump}} = H_0 - A Q^2$ .

The system and pump heads are computed and plotted below.

To find the operating condition, *Solver* is used to vary  $Q$  so that the error between the two heads is minimized.


$Q$ (gpm)	$Q^2$ (gpm)	$H_{\text{pump}}$ (ft)
0	0	179
500	250000	176
1000	1000000	165
1500	2250000	145
2000	4000000	119
2500	6250000	84
3000	9000000	43

$V$ (ft/s)	$Re$	$f$
0.00	0	0.0000
1.42	115325	0.0183
2.84	230649	0.0164
4.26	345974	0.0156
5.67	461299	0.0151
7.09	576623	0.0147
8.51	691948	0.0145

$H_{\text{pump}}$ (fit)	$H_{\text{IT}} + H_z$ (ft)
180	50.0
176	50.8
164	52.8
145	56.0
119	60.3
84.5	65.8
42.7	72.4

$$\begin{aligned}
 H_0 &= 180 \text{ ft} \\
 A &= 1.52\text{E-}05 \text{ ft}/(\text{gpm})^2
 \end{aligned}$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT}} + H_z$ (ft)	Error
2705	7.67	623829	0.0146	68.3	68.3	0%



For the valve setting to reduce the flow by half, use *Solver* to vary the value below to minimize the error.

$$L/D_{\text{valve}} = 26858$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT}} + H_z$ (ft)	Error
1352	3.84	311914	0.0158	151.7	151.7	0%

## Problem 10.62

[Difficulty: 3]

**10.62** Consider again the pump and piping system of Problem 10.61. Determine the volume flow rate and gate valve loss coefficient for the case of two identical pumps installed in *series*.

**Given:** Data on pump and pipe system

**Find:** Delivery through series pump system; valve position to reduce delivery by half

**Solution:**

Governing Equations:

For the pumps and system

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\tilde{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\tilde{V}_2^2}{2} + gz_2 \right) = h_{IT} - \Delta h_{\text{pump}} \quad (8.49)$$

where the total head loss is comprised of major and minor losses

$$h_l = f \frac{L}{D} \frac{\tilde{V}^2}{2} \quad (8.34)$$

$$h_{lm} = f \frac{L_e}{D} \frac{\tilde{V}^2}{2} \quad (8.40b)$$

$$h_{lm} = K \frac{\tilde{V}^2}{2} \quad (8.40a)$$

Hence, applied between the two reservoir free surfaces ( $p_1 = p_2 = 0$ ,  $V_1 = V_2 = 0$ ,  $z_1 - z_2 = \Delta z$ ) we have

$$g \cdot \Delta z = h_{IT} - \Delta h_{\text{pump}}$$

$$h_{IT} + g \cdot \Delta z = g \cdot H_{\text{system}} + g \cdot \Delta z = \Delta h_{\text{pump}} = g \cdot H_{\text{pump}}$$

or

$$H_{IT} + \Delta z = H_{\text{pump}}$$

where

$$H_{IT} = \left[ f \cdot \left( \frac{L}{D} + 2 \cdot \frac{L_e}{D_{\text{elbow}}} + \frac{L_e}{D_{\text{valve}}} \right) + K_{\text{ent}} + K_{\text{exit}} \right] \cdot \frac{V^2}{2 \cdot g}$$

For pumps in series

$$H_{\text{pump}} = 2 \cdot H_0 - 2 \cdot A \cdot Q^2$$

where for a single pump

$$H_{\text{pump}} = H_0 - A \cdot Q^2$$

The calculations in *Excel* are shown on the next page.

Given or available data (Note: final results will vary depending on fluid data selected):

$L =$	1200	ft	$K_{ent} =$	0.5	(Fig. 8.14)
$D =$	12	in	$K_{exp} =$	1	
$e =$	0.00015	ft (Table 8.1)	$L_e/D_{elbow} =$	30	
$\nu =$	1.23E-05	ft <sup>2</sup> /s (Table A.7)	$L_e/D_{valve} =$	8	(Table 8.4)
$\Delta z =$	-50	ft			

The pump data is curve-fitted to  $H_{pump} = H_0 - AQ^2$ .

The system and pump heads are computed and plotted below.


To find the operating condition, *Solver* is used to vary  $Q$  so that the error between the two heads is minimized.

$Q$ (gpm)	$Q^2$ (gpm)	$H_{pump}$ (ft)	$H_{pump}$ (fit)	$V$ (ft/s)	$Re$	$f$
0	0	179	180	0.00	0	0.0000
500	250000	176	176	1.42	115325	0.0183
1000	1000000	165	164	2.84	230649	0.0164
1500	2250000	145	145	4.26	345974	0.0156
2000	4000000	119	119	5.67	461299	0.0151
2500	6250000	84	85	7.09	576623	0.0147
3000	9000000	43	43	8.51	691948	0.0145
3250				9.22	749610	0.0144

$H_{pumps}$ (par)	$H_{IT} + \Delta z$ (ft)
359	50.0
351	50.8
329	52.8
291	56.0
237	60.3
169	65.8
85	72.4
38	76.1

$H_0 =$	180	ft
$A =$	1.52E-05	ft/(gpm) <sup>2</sup>

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{pumps}$ (par)	$H_{IT} + \Delta z$ (ft)	Error
3066	8.70	707124	0.0145	73.3	73.3	0%



For the valve setting to reduce the flow by half, use *Solver* to vary the value below to minimize the error.

$$L_e/D_{valve} = 50723$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{pumps}$ (par)	$H_{IT} + \Delta z$ (ft)	Error
1533	4.35	353562	0.0155	287.7	287.7	0%

## Problem 10.63

[Difficulty: 4]

**10.63** The resistance of a given pipe increases with age as deposits form, increasing the roughness and reducing the pipe diameter (see Fig. 8.14). Typical multipliers to be applied to the friction factor are given in [15]:

Pipe Age (years)	Small Pipes, 4–10 in.	Large Pipes, 12–60 in.
New	1.00	1.00
10	2.20	1.60
20	5.00	2.00
30	7.25	2.20
40	8.75	2.40
50	9.60	2.86
60	10.0	3.70
70	10.1	4.70

Consider again the pump and piping system of Problem 10.61. Estimate the percentage reductions in volume flow rate that occur after (a) 20 years and (b) 40 years of use, if the pump characteristics remain constant. Repeat the calculation if the pump head is reduced 10 percent after 20 years of use and 25 percent after 40 years.

**Given:** Data on pump and pipe system, and their aging

**Find:** Reduction in delivery through system after 20 and 40 years (aging and non-aging pumps)

**Solution:**

Given or available data (**Note: final results will vary depending on fluid data selected**):

$L = 1200 \text{ ft}$	$K_{\text{ent}} = 0.5 \text{ (Fig. 8.14)}$
$D = 12 \text{ in}$	$K_{\text{exp}} = 1$
$e = 0.00015 \text{ ft (Table 8.1)}$	$L/D_{\text{elbow}} = 30$
$v = 1.23\text{E-}05 \text{ ft}^2/\text{s (Table A.7)}$	$L/D_{\text{valve}} = 8 \text{ (Table 8.4)}$
$\Delta z = -50 \text{ ft}$	

Governing Equations:

For the pump and system

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + gz_2 \right) = h_{i_T} - \Delta h_{\text{pump}} \quad (8.49)$$

where the total head loss is comprised of major and minor losses

$$h_i = f \frac{L}{D} \frac{\bar{V}^2}{2} \quad (8.34)$$

$$h_{i_m} = f \frac{L_e}{D} \frac{\bar{V}^2}{2} \quad (8.40b)$$

$$h_{i_m} = K \frac{\bar{V}^2}{2} \quad (8.40a)$$

Hence, applied between the two reservoir free surfaces ( $p_1 = p_2 = 0$ ,  $V_1 = V_2 = 0$ ,  $z_1 - z_2 = \Delta z$ ) we have

$$g \cdot \Delta z = h_{i_T} - \Delta h_{\text{pump}}$$

$$h_{i_T} + g \cdot \Delta z = g \cdot H_{\text{system}} + g \cdot \Delta z = \Delta h_{\text{pump}} = g \cdot H_{\text{pump}}$$

or

$$H_{i_T} + \Delta z = H_{\text{pump}}$$

where

$$H_{i_T} = \left[ f \left( \frac{L}{D} + 2 \cdot \frac{L_e}{D_{\text{elbow}}} + \frac{L_e}{D_{\text{valve}}} \right) + K_{\text{ent}} + K_{\text{exit}} \right] \frac{V^2}{2g}$$

The pump data is curve-fitted to  $H_{\text{pump}} = H_0 - A Q^2$ .

The system and pump heads are computed and plotted below.

To find the operating condition, *Solver* is used to vary  $Q$

so that the error between the two heads is minimized.

**New System:**


$Q$ (gpm)	$Q^2$ (gpm)	$H_{\text{pump}}$ (ft)
0	0	179
500	250000	176
1000	1000000	165
1500	2250000	145
2000	4000000	119
2500	6250000	84
3000	9000000	43

$V$ (ft/s)	$Re$	$f$
0.00	0	0.0000
1.42	115325	0.0183
2.84	230649	0.0164
4.26	345974	0.0156
5.67	461299	0.0151
7.09	576623	0.0147
8.51	691948	0.0145

$H_{\text{pump}}$ (ft)	$H_{\text{IT}} + \Delta z$ (ft)
180	50.0
176	50.8
164	52.8
145	56.0
119	60.3
84.5	65.8
42.7	72.4

$H_0 = 180$  ft  
 $A = 1.52E-05$  ft/(gpm)<sup>2</sup>

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (ft)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2705	7.67	623829	0.0146	68.3	68.3	0%



**20-Year Old System:**

$f = 2.00 f_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (ft)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2541	7.21	586192	0.0295	81.4	81.4	0%

**Flow reduction:**  
 163 gpm  
 6.0% Loss

**40-Year Old System:**

$f = 2.40 f_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (ft)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2484	7.05	572843	0.0354	85.8	85.8	0%

**Flow reduction:**  
 221 gpm  
 8.2% Loss

**20-Year Old System and Pump:**

$f = 2.00 f_{\text{new}}$        $H_{\text{pump}} = 0.90 H_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (ft)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2453	6.96	565685	0.0296	79.3	79.3	0%

**Flow reduction:**  
 252 gpm  
 9.3% Loss

**40-Year Old System and Pump:**

$f = 2.40 f_{\text{new}}$        $H_{\text{pump}} = 0.75 H_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (ft)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2214	6.28	510754	0.0358	78.8	78.8	0%

**Flow reduction:**  
 490 gpm  
 18.1% Loss

## Problem 10.64

[Difficulty: 3]

**10.64** Consider again the pump and piping system of Problem 10.61. Determine the volume flow rate and gate valve loss coefficient for the case of two identical pumps installed in *parallel*.

**Given:** Data on pump and pipe system

**Find:** Delivery through parallel pump system; valve position to reduce delivery by half

**Solution:**

Governing Equations:

For the pumps and system

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\tilde{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\tilde{V}_2^2}{2} + gz_2 \right) = h_{IT} - \Delta h_{\text{pump}} \quad (8.49)$$

where the total head loss is comprised of major and minor losses

$$h_l = f \frac{L}{D} \frac{\tilde{V}^2}{2} \quad (8.34)$$

$$h_{lm} = f \frac{L_e}{D} \frac{\tilde{V}^2}{2} \quad (8.40b)$$

$$h_{lm} = K \frac{\tilde{V}^2}{2} \quad (8.40a)$$

Hence, applied between the two reservoir free surfaces ( $p_1 = p_2 = 0$ ,  $V_1 = V_2 = 0$ ,  $z_1 - z_2 = \Delta z$ ) we have

$$g \cdot \Delta z = h_{IT} - \Delta h_{\text{pump}}$$

$$h_{IT} + g \cdot \Delta z = g \cdot H_{\text{system}} + g \cdot \Delta z = \Delta h_{\text{pump}} = g \cdot H_{\text{pump}}$$

or

$$H_{IT} + \Delta z = H_{\text{pump}}$$

where

$$H_{IT} = \left[ f \cdot \left( \frac{L}{D} + 2 \cdot \frac{L_e}{D_{\text{elbow}}} + \frac{L_e}{D_{\text{valve}}} \right) + K_{\text{ent}} + K_{\text{exit}} \right] \cdot \frac{V^2}{2 \cdot g}$$

For pumps in parallel

$$H_{\text{pump}} = H_0 - \frac{1}{4} \cdot A \cdot Q^2$$

where for a single pump

$$H_{\text{pump}} = H_0 - A \cdot Q^2$$

The calculations performed using *Excel* are shown on the next page.

Given or available data (Note: final results will vary depending on fluid data selected):

$L =$	1200	ft	$K_{ent} =$	0.5	(Fig. 8.14)
$D =$	12	in	$K_{exp} =$	1	
$e =$	0.00015	ft (Table 8.1)	$L_e/D_{elbow} =$	30	
$\nu =$	1.23E-05	ft <sup>2</sup> /s (Table A.7)	$L_e/D_{valve} =$	8	(Table 8.4)
$\Delta z =$	-50	ft			

The pump data is curve-fitted to  $H_{pump} = H_0 - AQ^2$ .

The system and pump heads are computed and plotted below.


To find the operating condition, *Solver* is used to vary  $Q$  so that the error between the two heads is minimized.

$Q$ (gpm)	$Q^2$ (gpm)	$H_{pump}$ (ft)	$H_{pump}$ (fit)	$V$ (ft/s)	$Re$	$f$
0	0	179	180	0.00	0	0.0000
500	250000	176	176	1.42	115325	0.0183
1000	1000000	165	164	2.84	230649	0.0164
1500	2250000	145	145	4.26	345974	0.0156
2000	4000000	119	119	5.67	461299	0.0151
2500	6250000	84	85	7.09	576623	0.0147
3000	9000000	43	43	8.51	691948	0.0145
3500				9.93	807273	0.0143
4000				11.35	922597	0.0142
4500				12.77	1037922	0.0141
5000				14.18	1153247	0.0140

$H_{pumps}$ (par)	$H_{IT} + \Delta z$ (ft)
180	50.0
179	50.8
176	52.8
171	56.0
164	60.3
156	65.8
145	72.4
133	80.1
119	89.0
103	98.9
85	110.1

$H_0 =$	180	ft
$A =$	1.52E-05	ft/(gpm) <sup>2</sup>

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{pumps}$ (par)	$H_{IT} + \Delta z$ (ft)	Error)
4565	12.95	1053006	0.0141	100.3	100.3	0%



For the valve setting to reduce the flow by half, use *Solver* to vary the value below to minimize the error.

$L_e/D_{valve} =$  9965

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{pumps}$ (par)	$H_{IT} + \Delta z$ (ft)	Error)
2283	6.48	526503	0.0149	159.7	159.7	0%

## Problem 10.65

[Difficulty: 4]

**10.65** Consider again the pump and piping system of Problem 10.64. Estimate the percentage reductions in volume flow rate that occur after (a) 20 years and (b) 40 years of use, if the pump characteristics remain constant. Repeat the calculation if the pump head is reduced 10 percent after 20 years of use and 25 percent after 40 years. (Use the data of Problem 10.63 for increase in pipe friction factor with age.)

**Given:** Data on pump and pipe system

**Find:** Delivery through parallel pump system; reduction in delivery after 20 and 40 years

**Solution:**

Given or available data (**Note: final results will vary depending on fluid data selected**) :

$L =$	1200	ft	$K_{ent} =$	0.5	(Fig. 8.14)
$D =$	12	in	$K_{exp} =$	1	
$e =$	0.00015	ft (Table 8.1)	$L_e/D_{elbow} =$	30	
$\nu =$	1.23E-05	ft <sup>2</sup> /s (Table A.7)	$L_e/D_{valve} =$	8	(Table 8.4)
$\Delta z =$	-50	ft			

Governing Equations:

For the pumps and system

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\hat{V}_1^2}{2} + gz_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\hat{V}_2^2}{2} + gz_2 \right) = h_{Tf} - \Delta h_{\text{pump}} \quad (8.49)$$

where the total head loss is comprised of major and minor losses

$$h_{Tf} = f \frac{L}{D} \frac{\hat{V}^2}{2} \quad (8.34)$$

$$h_{Tm} = f \frac{L_e}{D} \frac{\hat{V}^2}{2} \quad (8.40b)$$

$$h_{Tm} = K \frac{\hat{V}^2}{2} \quad (8.40a)$$

Hence, applied between the two reservoir free surfaces ( $p_1 = p_2 = 0$ ,  $V_1 = V_2 = 0$ ,  $z_1 - z_2 = \Delta z$ ) we have

$$g \cdot \Delta z = h_{Tf} - \Delta h_{\text{pump}}$$

$$h_{Tf} + g \cdot \Delta z = g \cdot H_{\text{system}} + g \cdot \Delta z = \Delta h_{\text{pump}} = g \cdot H_{\text{pump}}$$

or

$$H_{Tf} + \Delta z = H_{\text{pump}}$$

where

$$H_{Tf} = \left[ f \cdot \left( \frac{L}{D} + 2 \cdot \frac{L_e}{D_{\text{elbow}}} + \frac{L_e}{D_{\text{valve}}} \right) + K_{ent} + K_{exit} \right] \frac{V^2}{2 \cdot g}$$

For pumps in parallel

$$H_{\text{pump}} = H_0 - \frac{1}{4} \cdot A \cdot Q^2$$

where for a single pump

$$H_{\text{pump}} = H_0 - A \cdot Q^2$$

The pump data is curve-fitted to  $H_{\text{pump}} = H_0 - A Q^2$ .

The system and pump heads are computed and plotted below.

To find the operating condition, *Solver* is used to vary  $Q$


so that the error between the two heads is minimized.

$Q$ (gpm)	$Q^2$ (gpm)	$H_{\text{pump}}$ (ft)	$H_{\text{pump}}$ (fit)	$V$ (ft/s)	$Re$	$f$
0	0	179	180	0.00	0	0.0000
500	250000	176	176	1.42	115325	0.0183
1000	1000000	165	164	2.84	230649	0.0164
1500	2250000	145	145	4.26	345974	0.0156
2000	4000000	119	119	5.67	461299	0.0151
2500	6250000	84	85	7.09	576623	0.0147
3000	9000000	43	43	8.51	691948	0.0145
3500				9.93	807273	0.0143
4000				11.35	922597	0.0142
4500				12.77	1037922	0.0141
5000				14.18	1153247	0.0140

$H_{\text{pumps (par)}}$	$H_{\text{IT} + \Delta z}$ (ft)
180	50.0
179	50.8
176	52.8
171	56.0
164	60.3
156	65.8
145	72.4
133	80.1
119	89.0
103	98.9
85	110.1

$H_0 = 180$  ft  
 $A = 1.52E-05$  ft/(gpm)<sup>2</sup>

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pumps (par)}}$	$H_{\text{IT} + \Delta z}$ (ft)	Error
4565	12.95	1053006	0.0141	100.3	100.3	0%



**20-Year Old System:**

$f = 2.00 f_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pumps (par)}}$	$H_{\text{IT} + \Delta z}$ (ft)	Error
3906	11.08	900891	0.0284	121.6	121.6	0%

**Flow reduction:**  
 660 gpm  
 14.4% Loss

**40-Year Old System:**

$f = 2.40 f_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT} + \Delta z}$ (ft)	Error
3710	10.52	855662	0.0342	127.2	127.2	0%

**Flow reduction:**  
 856  
 18.7%

**20-Year Old System and Pumps:**

$f = 2.00 f_{\text{new}}$        $H_{\text{pump}} = 0.90 H_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT} + \Delta z}$ (ft)	Error
3705	10.51	854566	0.0285	114.6	114.6	0%

**Flow reduction:**  
 860 gpm  
 18.8% Loss

**40-Year Old System and Pumps:**

$f = 2.40 f_{\text{new}}$        $H_{\text{pump}} = 0.75 H_{\text{new}}$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT} + \Delta z}$ (ft)	Error
3150	8.94	726482	0.0347	106.4	106.4	0%

**Flow reduction:**  
 1416  
 31.0%

## Problem 10.66

[Difficulty: 4]

**10.66** Consider again the pump and piping system of Problem 10.62. Estimate the percentage reductions in volume flow rate that occur after (a) 20 years and (b) 40 years of use, if the pump characteristics remain constant. Repeat the calculation if the pump head is reduced 10 percent after 20 years of use and 25 percent after 40 years. (Use the data of Problem 10.63 for increase in pipe friction factor with age.)

**Given:** Data on pump and pipe system

**Find:** Delivery through series pump system; reduction after 20 and 40 years

**Solution:**

Given or available data (**Note: final results will vary depending on fluid data selected**):

$L =$	1200	ft	$K_{ent} =$	0.5	(Fig. 8.14)
$D =$	12	in	$K_{exp} =$	1	
$e =$	0.00015	ft (Table 8.1)	$L_e/D_{elbow} =$	30	
$\nu =$	1.23E-05	ft <sup>2</sup> /s (Table A.7)	$L_e/D_{valve} =$	8	(Table 8.4)
$\Delta z =$	-50	ft			

Governing Equations:

For the pumps and system

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{\bar{V}_1^2}{2} + g z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{\bar{V}_2^2}{2} + g z_2 \right) = h_{IT} - \Delta h_{\text{pump}} \quad (8.49)$$

where the total head loss is comprised of major and minor losses

$$h_f = f \frac{L}{D} \frac{\bar{V}^2}{2} \quad (8.34)$$

$$h_{fm} = f \frac{L_e}{D} \frac{\bar{V}^2}{2} \quad (8.40b)$$

$$h_{fm} = K \frac{\bar{V}^2}{2} \quad (8.40a)$$

Hence, applied between the two reservoir free surfaces ( $p_1 = p_2 = 0$ ,  $V_1 = V_2 = 0$ ,  $z_1 - z_2 = \Delta z$ ) we have

$$g \cdot \Delta z = h_{IT} - \Delta h_{\text{pump}}$$

$$h_{IT} + g \cdot \Delta z = g \cdot H_{\text{system}} + g \cdot \Delta z = \Delta h_{\text{pump}} = g \cdot H_{\text{pump}}$$

or

$$H_{IT} + \Delta z = H_{\text{pump}}$$

where

$$H_{IT} = \left[ f \left( \frac{L}{D} + 2 \cdot \frac{L_e}{D_{elbow}} + \frac{L_e}{D_{valve}} \right) + K_{ent} + K_{exit} \right] \cdot \frac{V^2}{2 \cdot g}$$

For pumps in series

$$H_{\text{pump}} = 2 \cdot H_0 - 2 \cdot A \cdot Q^2$$

where for a single pump

$$H_{\text{pump}} = H_0 - A \cdot Q^2$$

The pump data is curve-fitted to  $H_{\text{pump}} = H_0 - A Q^2$ .

The system and pump heads are computed and plotted below.

To find the operating condition, *Solver* is used to vary  $Q$

so that the error between the two heads is minimized.


$Q$ (gpm)	$Q^2$ (gpm <sup>2</sup> )	$H_{\text{pump}}$ (ft)	$H_{\text{pump}}$ (fit)	$V$ (ft/s)	$Re$	$f$
0	0	179	180	0.00	0	0.0000
500	250000	176	176	1.42	115325	0.0183
1000	1000000	165	164	2.84	230649	0.0164
1500	2250000	145	145	4.26	345974	0.0156
2000	4000000	119	119	5.67	461299	0.0151
2500	6250000	84	85	7.09	576623	0.0147
3000	9000000	43	43	8.51	691948	0.0145
3250				9.22	749610	0.0144

$H_{\text{pumps}}$ (par)	$H_{IT} + \Delta z$ (ft)
359	50.0
351	50.8
329	52.8
291	56.0
237	60.3
169	65.8
85	72.4
38	76.1

$$H_0 = 180 \text{ ft}$$

$$A = 1.52E-05 \text{ ft}/(\text{gpm})^2$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pumps}}$ (par)	$H_{\text{IT}} + \Delta z$ (ft)	Error
3066	8.70	707124	0.0145	73.3	73.3	0%



#### 20-Year Old System:

$$f = 2.00 f_{\text{new}}$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pumps}}$ (par)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2964	8.41	683540	0.0291	92.1	92.1	0%

#### Flow reduction:

102 gpm  
3.3% Loss

#### 40-Year Old System:

$$f = 2.40 f_{\text{new}}$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2925	8.30	674713	0.0349	98.9	98.9	0%

#### Flow reduction:

141 gpm  
4.6% Loss

#### 20-Year Old System and Pumps:

$$f = 2.00 f_{\text{new}} \quad H_{\text{pump}} = 0.90 H_{\text{new}}$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2915	8.27	672235	0.0291	90.8	90.8	0%

#### Flow reduction:

151 gpm  
4.9% Loss

#### 40-Year Old System and Pumps:

$$f = 2.40 f_{\text{new}} \quad H_{\text{pump}} = 0.75 H_{\text{new}}$$

$Q$ (gpm)	$V$ (ft/s)	$Re$	$f$	$H_{\text{pump}}$ (fit)	$H_{\text{IT}} + \Delta z$ (ft)	Error
2772	7.86	639318	0.0351	94.1	94.1	0%

#### Flow reduction:

294 gpm  
9.6% Loss

## Problem 10.67

[Difficulty: 3]

**10.67** The city of Englewood, Colorado, diverts water for municipal use from the South Platte River at elevation 1610 m [54]. The water is pumped to storage reservoirs at 1620-m elevation. The inside diameter of the steel water line is 68.5 cm; its length is 1770 m. The facility is designed for an initial capacity (flow rate) of 3200 m<sup>3</sup>/hr, with an ultimate capacity of 3900 m<sup>3</sup>/hr. Calculate and plot the system resistance curve. Ignore entrance losses. Specify an appropriate pumping system. Estimate the pumping power required for steady-state operation, at both the initial and ultimate flow rates.

**Given:** Water supply for Englewood, CO

**Find:** (a) system resistance curve  
(b) specify appropriate pumping system  
(c) estimate power required for steady-state operation at two specified flow rates

**Solution:**

Basic equations:

$$\left( \frac{p_1}{\rho} + \alpha_1 \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p$$

$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \Sigma \cdot f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + \Sigma \cdot K \cdot \frac{V^2}{2} \quad H = \frac{h}{g} \quad W_p = \frac{\rho \cdot Q \cdot g \cdot H_p}{\eta_p}$$

Assumptions: 1)  $p_1 = p_2 = p_{atm}$  2)  $V_1 = V_2 = 0$  3)  $K_{ent} = 0$  4)  $K_{exit} = 1$  5)  $L_e/D = 0$

Hence  $g \cdot (z_1 - z_2) = \left( f \cdot \frac{L}{D} + 1 \right) \cdot \frac{V^2}{2} - h_p$  or  $H_p = (z_2 - z_1) + \left( f \cdot \frac{L}{D} + 1 \right) \cdot \frac{V^2}{2 \cdot g}$


The results calculated using Excel are shown below:

Given or available data (**Note: final results will vary depending on fluid data selected**):

$L = 1770 \text{ m}$	$z_1 = 1610 \text{ m}$
$e = 0.046 \text{ mm (Table 8.1)}$	$z_2 = 1620 \text{ m}$
$D = 68.5 \text{ cm}$	$\rho = 998 \text{ kg/m}^3$
$\nu = 1.01\text{E-}06 \text{ m}^2/\text{s (Table A.8)}$	

The required pump head is computed and plotted below.

$Q$ (m <sup>3</sup> /hr)	$V$ (m/s)	$Re$	$f$	$H_p$ (m)
0	0.00	0.00E+00	0.0000	10.0
500	0.38	2.56E+05	0.0155	10.3
1000	0.75	5.11E+05	0.0140	11.1
1500	1.13	7.67E+05	0.0133	12.3
2000	1.51	1.02E+06	0.0129	14.0
2500	1.88	1.28E+06	0.0126	16.1
3000	2.26	1.53E+06	0.0124	18.6
3200	2.41	1.64E+06	0.0124	19.8
3500	2.64	1.79E+06	0.0123	21.6
3900	2.94	1.99E+06	0.0122	24.3
4000	3.01	2.04E+06	0.0122	25.0



The maximum flow rate is: 17172 gpm

The associated head is: 80 ft

Based on these data and the data of Figures D.1 and D.2, we could choose two 16A 18B pumps in parallel, or three 10AE14 (G) pumps in parallel. The efficiency will be approximately 90%

Therefore, the required power would be: 191.21 kW at  $Q = 3200 \text{ m}^3/\text{hr}$

286.47 kW at  $Q = 3900 \text{ m}^3/\text{hr}$

## Problem 10.68

[Difficulty: 3]

**10.68** A pump in the system shown draws water from a sump and delivers it to an open tank through 400 m of new, 10-cm-diameter steel pipe. The vertical suction pipe is 2 m long and includes a foot valve with hinged disk and a 90° standard elbow. The discharge line includes two 90° standard elbows, an angle lift check valve, and a fully open gate valve. The design flow rate is 800 L/min. Find the head losses in the suction and discharge lines. Calculate the *NPSHA*. Select a pump suitable for this application.

**Given:** System shown, design flow rate

**Find:** Head losses for suction and discharge lines, *NPSHA*, select a suitable pump


**Solution:**

We will apply the energy equation for steady, incompressible pipe flow.

Basic equations:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p$$

$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \Sigma \cdot f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + \Sigma \cdot K \cdot \frac{V^2}{2} \quad H = \frac{h}{g}$$



Assumptions: 1)  $p_{ent} = p_{exit} = p_{atm}$  2)  $V_{ent} = V_{exit} = 0$

The given or available data is  $Q = 800 \cdot \frac{L}{min}$   $D = 10 \cdot cm$   $e = 0.046 \cdot mm$   $p_{atm} = 101.3 \cdot kPa$

From Table A.8 at 20°C  $\nu = 1.01 \times 10^{-6} \cdot \frac{m^2}{s}$   $p_v = 2.34 \cdot kPa$   $\rho = 998 \cdot \frac{kg}{m^3}$

At the specified flow rate, the speed of the water is:  $V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V = 1.698 \frac{m}{s}$   $Re = \frac{V \cdot D}{\nu} = 1.681 \times 10^5$

$\frac{e}{D} = 4.6 \times 10^{-4}$  Therefore we can calculate the friction factor:  $f = \left[ -1.8 \cdot \log \left[ \left( \frac{e}{3.7 \cdot D} \right)^{1.11} + \frac{6.9}{Re} \right] \right]^{-2} = 0.019$

At the inlet:  $g \cdot z_1 - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} + \Sigma \cdot K \cdot \frac{V^2}{2}$  In this case:  $L_e = 75 \cdot D$   $K = 0.78$   $L = 2 \cdot m$   
 $z_2 = 8.7 \cdot m$   $z_1 = 7.2 \cdot m$

Solving for total pressure at 2:  $p_{2t} = -\rho \cdot \left[ g \cdot (z_2 - z_1) + f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2} \right]$   $p_{2t} = -18.362 \cdot kPa$  (gage)

The *NPSHA* can be calculated:  $NPSHA = \frac{p_{2t} + p_{atm} - p_v}{\rho \cdot g}$   $NPSHA = \frac{p_{2t} + p_{atm} - p_v}{\rho \cdot g}$   $NPSHA = 8.24 \cdot m$

For the entire system:  $g \cdot (z_1 - z_2) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2} - h_p$

In this case:  $z_1 = 7.2 \cdot \text{m}$   $z_2 = 88 \cdot \text{m}$   $L = 2 \cdot \text{m} + 400 \cdot \text{m} = 402 \text{ m}$   $L_e = (75 + 55 + 8 + 2 \times 30) \cdot D$   $K = 0.78 + 1$

Solving for the required head at the pump:  $H_p = (z_2 - z_1) + \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \cdot \frac{V^2}{2 \cdot g}$   $H_p = 92.7 \text{ m}$

In U.S. Customary units:  $Q = 211 \cdot \text{gpm}$   $H_p = 304 \cdot \text{ft}$

A pump would be selected by finding one for which the NPSHR is less than the NPSHA. Based on these data and the information in Appendix D, a 2AE11 or a 4AE12 pump would be capable of supplying the required head at the given flow rate. The pump should be operated at a speed between 1750 and 3500 rpm, but the efficiency may not be acceptable. One should consult a complete catalog to make a better selection.

### Problem 10.69

[Difficulty: 3]

10.69 Consider the flow system described in Problem 8.175.

Select a pump appropriate for this application. Check the NPSHR versus the NPSHA for this system.

Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equation:  $\frac{p_1}{\rho g} + \alpha_1 \frac{V_1^2}{2g} + z_1 + H_p = \frac{p_2}{\rho g} + \alpha_2 \frac{V_2^2}{2g} + z_2 + \frac{h_{LT}}{g}$ ;  $h_{LT} = \left[ f \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \frac{V^2}{2}$

Assumptions: (1)  $V_1 \approx 0$ , (2)  $K_{ent} = 0.5$ , (3)  $\frac{L_e}{D} = 2(8) + 1(150) + 7(30) = 376$ ;  $D = 2.47$  in.

(4) Galvanized pipe,  $e = 0.0005$  ft;  $\frac{e}{D} = \frac{0.0005 \text{ ft} \times 12 \text{ in.}}{2.47 \text{ in.}} = 0.00243$

Then

$$H_p = \frac{p_2 - p_1}{\rho g} + \frac{\alpha_2 V_2^2}{2g} + z_2 - z_1 + \left[ f \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \frac{V^2}{2g}; \quad \bar{V} = \frac{Q}{A} = 13.2 \text{ ft/s}; \quad Re = \frac{\bar{V} D}{\nu} = 2.54 \times 10^5; \quad f = 0.02$$

$$H_p = (0 - 20) \frac{\text{lb}_f}{\text{in.}^2} \times \frac{144 \text{ in.}^2}{\text{ft}^2} \times \frac{\text{ft}^3}{62.4 \text{ lb}_f} + \frac{1}{2} \times \frac{(13.2)^2 \text{ ft}^2}{32} \times \frac{\text{s}^2}{32.2 \text{ ft}} + (94.0 - 50.0) \text{ ft} \\ + \left[ 0.025 \left( \frac{290}{2.47/12} + 376 \right) + 0.5 \right] \frac{1}{2} \times \frac{(13.2)^2 \text{ ft}^2}{32} \times \frac{\text{s}^2}{32.2 \text{ ft}} = 123 \text{ ft}$$

$H_p$

The pump requirement is  $Q = 197$  gpm at  $H = 123$  ft. This could be supplied by a Peerless Type 4AE12 pump, with impeller  $D = 11$  in., operating at 1750 rpm.

(This pump may be slightly too large, since this operating point is at a flow rate below that for best efficiency.)

The NPSHR for this pump at  $Q = 197$  gpm is about 5 ft.

The NPSHA is  $\frac{p_1}{\rho g} + \frac{p_{atm}}{\rho g} + \alpha_1 \frac{V_1^2}{2g} - p_{fv} = 46.2 + 33.9 + 2.71 - 0.782 \text{ ft} = 82.0 \text{ ft}$

Thus  $NPSHA \gg NPSHR$

$NPSH$

Cavitation-free operation is assured.

## Problem 10.70

[Difficulty: 3]

**10.70** Consider the flow system and data of Problem 10.68 and the data for pipe aging given in Problem 10.63. Select pump(s) that will maintain the system flow at the desired rate for (a) 10 years and (b) 20 years. Compare the delivery produced by these pumps with the delivery by the pump sized for new pipes only.

**Given:** Flow system and data of Problem 10.68; data for pipe aging from Problem 10.63

**Find:** Pumps to maintain system flow rates; compare delivery to that with pump sized for new pipes only

**Solution:**

We will apply the energy equation for steady, incompressible pipe flow.

Basic equations:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p$$

$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \sum f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + \sum K \cdot \frac{V^2}{2} \quad H = \frac{h}{g}$$

Assumptions: 1)  $p_{ent} = p_{exit} = p_{atm}$  2)  $V_{ent} = V_{exit} = 0$

The given or available data is  $Q = 800 \frac{L}{min}$   $D = 10\text{-cm}$   $e = 0.046\text{mm}$   $p_{atm} = 101.3\text{kPa}$

From Table A.8 at 20°C  $\nu = 1.01 \times 10^{-6} \frac{m^2}{s}$   $p_v = 2.34\text{kPa}$   $\rho = 998 \frac{kg}{m^3}$

At the specified flow rate, the speed of the water is:  $V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V = 1.698 \frac{m}{s}$   $Re = \frac{V \cdot D}{\nu} = 1.681 \times 10^5$

$\frac{e}{D} = 4.6 \times 10^{-4}$  Therefore we can calculate the friction factor:  $f = \left[ -1.8 \cdot \log \left[ \left( \frac{e}{3.7 \cdot D} \right)^{1.11} + \frac{6.9}{Re} \right] \right]^{-2} = 0.019$


For the entire system:  $g \cdot (z_1 - z_2) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2} - h_p$

In this case:  $z_1 = 7.2\text{-m}$   $z_2 = 87\text{-m}$   $L = 2\text{-m} + 400\text{-m} = 402\text{ m}$   $L_e = (75 + 55 + 8 + 2 \times 30) \cdot D$   $K = 0.78 + 1$

Solving for the required head at the pump:  $H_p = (z_2 - z_1) + \left[ f \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \cdot \frac{V^2}{2 \cdot g}$

For old pipes, we apply the multipliers from Problem 10.63:  $f_{20} = 5.00 \cdot f_{new}$   $f_{40} = 8.75 \cdot f_{new}$

The results of the analysis, computed in *Excel*, are shown on the next page.




The required pump head is computed and plotted below.

$Q$ (L/min)	$V$ (m/s)	$Re$	$f$	New		New		20 yo	40 yo	Pump (ft)
				$H_p$ (m)	$Q$ (gpm)	$H_p$ (ft)	$H_p$ (ft)	$H_p$ (ft)		
0	0.000	0.00E+00	0.0000	79.80	0.00	261.81	261.81	261.81	856.54	
200	0.424	4.20E+04	0.0231	80.71	52.84	264.81	276.57	287.59	840.48	
400	0.849	8.40E+04	0.0207	83.07	105.68	272.52	314.52	353.89	792.30	
600	1.273	1.26E+05	0.0196	86.77	158.52	284.67	374.19	458.10	712.00	
800	1.698	1.68E+05	0.0189	91.80	211.36	301.17	455.19	599.58	599.58	
922	1.957	1.94E+05	0.0187	95.52	243.64	313.38	515.10	704.21	515.10	
1000	2.122	2.10E+05	0.0185	98.14	264.20	321.99	557.37	778.03	455.04	
1136	2.410	2.39E+05	0.0183	103.20	300.08	338.59	638.8	920.2	338.59	
1200	2.546	2.52E+05	0.0182	105.80	317.04	347.12	680.64	993.31	278.38	
1400	2.971	2.94E+05	0.0180	114.77	369.88	376.54	824.95	1245.3	69.59	
1600	3.395	3.36E+05	0.0178	125.04	422.72	410.25	990.27	1534.0	-171.31	
1800	3.820	3.78E+05	0.0177	136.62	475.56	448.24	1176.6	1859.4	-444.33	
2000	4.244	4.20E+05	0.0176	149.51	528.40	490.51	1383.9	2221.4	-749.47	

If we assume that the head at 800 L/min for 40 year old pipe is 70% of the maximum head for the pump, and that the pump curve has the form  $H = H_0 - A Q^2$ :

$H_{800} = 599.58$  ft      We plot the pump curve along with the head loss on the graph below:  
 $H_0 = 856.54$  ft  
 $A = 0.005752$  ft/gpm<sup>2</sup>




Sizing the pump for 800 L/min for at 40 years would (assuming no change in the pump characteristics) produce 922 L/min at 20 years and 1136 L/min for new pipe.

Since the head increases by a factor of two, the extra head could be obtained by placing a second identical pump in series with the pump of Problem 10.68.

## Problem 10.71

[Difficulty: 3]

**10.71** Consider the flow system shown in Problem 8.176. Select an appropriate pump for this application. Check the pump efficiency and power requirement compared with those in the problem statement.



Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equation:  $\frac{p_1}{\rho g} + \alpha_1 \frac{V_1^2}{2g} + z_1 + H_p = \frac{p_2}{\rho g} + \alpha_2 \frac{V_2^2}{2g} + z_2 + \frac{h_{LT}}{g}$ ;  $h_{LT} = \left[ f \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \frac{V^2}{2}$

Assumptions: (1)  $p_1 = p_2 = p_{atm}$ , (2)  $V_1 \approx 0$ , (3) Neglect elbow and nozzle losses, (4)  $\frac{L_e}{D} (\text{valve}) = 8$

$$\bar{V} = \frac{Q}{A} = \frac{600 \text{ gal}}{\text{min}} \times \frac{4 \left( \frac{12}{4} \right) \frac{1}{\text{ft}^2} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{\text{min}}{60 \text{ s}} = 15.3 \frac{\text{ft}}{\text{s}}; \quad \frac{\bar{V}^2}{2g} = \frac{1}{2} \times \frac{(15.3)^2 \frac{\text{ft}^2}{\text{s}^2}}{32.2 \frac{\text{ft}}{\text{s}^2}} = 3.63 \text{ ft}$$

$$Re = \frac{\bar{V}D}{\nu} = \frac{15.3 \frac{\text{ft}}{\text{s}} \left( \frac{4}{12} \right) \text{ft} \times \frac{\text{s}}{1.08 \times 10^{-5} \text{ft}^2}} = 4.77 \times 10^5; \text{ smooth}; f = 0.013 \quad (T = 68^\circ\text{F})$$

$$H_p = z_2 - z_1 + \alpha_2 \frac{\bar{V}_2^2}{2g} + \frac{h_{LT}}{g} = z_2 - z_1 + \frac{\bar{V}_2^2}{2g} + \left[ f \left( \frac{L}{D} + \frac{L_e}{D} \right) + 15 K_j \right] \frac{\bar{V}^2}{2g}$$

$$H_p = 400 \text{ ft} + \frac{1}{2} \times \frac{(120)^2 \frac{\text{ft}^2}{\text{s}^2}}{32.2 \frac{\text{ft}}{\text{s}^2}} + \left[ 0.013 \left( \frac{700}{4/12} + 8 \right) + 15 \right] 3.63 \text{ ft} = 778 \text{ ft}$$


Thus the pump requirement is  $H_p = 778 \text{ ft}$  at  $Q = 600 \text{ gpm}$ . This head is too great to be developed by a single-stage pump (Fig. D.1). From Fig. D.12, the flow could be supplied by a 5TUT168 3-stage pump, driven at 1750 rpm.

Single-stage pumps have peak efficiencies of 86 percent at 1750 rpm (Fig. D.8). Thus 70 percent efficiency might be reasonable for a 3-stage pump, since  $(0.86)^3 = 0.636$ .

## Problem 10.72

[Difficulty: 3]

**10.72** Consider the flow system shown in Problem 8.124. Assume the minimum *NPSHR* at the pump inlet is 15 ft of water. Select a pump appropriate for this application. Use the data for increase in friction factor with pipe age given in Problem 10.65 to determine and compare the system flow rate after 10 years of operation.



**Given:** Flow from pump to reservoir

**Find:** Select a pump to satisfy NPSHR

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p \quad h_{IT} = h_l + h_{lm} = f \cdot \frac{L}{D} \cdot \frac{V_1^2}{2} + K_{exit} \cdot \frac{V_1^2}{2}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 is approximately 1 4)  $V_2 \ll V_1$

Note that we compute head per unit weight,  $H$ , not head per unit mass,  $h$ , so the energy equation between Point 1 and the free surface (Point 2) becomes 
$$\left( \frac{p_1}{\rho \cdot g} + \frac{V^2}{2 \cdot g} \right) - (z_2) = f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g} + K_{exit} \cdot \frac{V^2}{2 \cdot g} - H_p$$

Solving for  $H_p$  
$$H_p = z_2 - \frac{p_1}{\rho \cdot g} - \frac{V^2}{2 \cdot g} + f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g} + K_{exit} \cdot \frac{V^2}{2 \cdot g}$$

From Table A.7 (68°F)  $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$   $\nu = 1.08 \times 10^{-5} \cdot \frac{\text{ft}^2}{\text{s}}$   $Re = \frac{V \cdot D}{\nu}$   $Re = 6.94 \times 10^5$

For commercial steel pipe  $e = 0.00015 \cdot \text{ft}$  (Table 8.1) so  $\frac{e}{D} = 0.0002$

Flow is turbulent: Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{Re \cdot \sqrt{f}} \right)$$
  $f = 0.0150$

For the exit  $K_{exit} = 1.0$  so we find 
$$H_p = z_2 - \frac{p_1}{\rho \cdot g} + f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g}$$

Note that for an NPSHR of 15 ft this means  $\frac{p_1}{\rho \cdot g} = 15 \cdot \text{ft}$  
$$H_p = z_2 - \frac{p_1}{\rho \cdot g} + f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g}$$
  $H_p = 691 \cdot \text{ft}$

Note that  $Q = \frac{\pi \cdot D^2}{4} \cdot V$   $Q = 4.42 \cdot \frac{\text{ft}^3}{\text{s}}$   $Q = 1983 \cdot \text{gpm}$

For this combination of  $Q$  and  $H_p$ , from Fig. D.11 the best pump appears to be a Peerless two-stage 10TU22C operating at 1750 rpm

After 10 years, from Problem 10.63, the friction factor will have increased by a factor of 2.2  $f = 2.2 \times 0.0150$   $f = 0.330$

We now need to solve 
$$H_p = z_2 - \frac{p_1}{\rho \cdot g} + f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g}$$
 for the new velocity

$$V = \sqrt{\frac{2 \cdot D \cdot g}{f \cdot L} \cdot \left( H_p - z_2 + \frac{p_1}{\rho \cdot g} \right)}$$

$V = 2.13 \cdot \frac{\text{ft}}{\text{s}}$  and  $f$  will still be  $2.2 \times 0.0150$

$$Q = \frac{\pi \cdot D^2}{4} \cdot V$$

$Q = 0.94 \cdot \frac{\text{ft}^3}{\text{s}}$   $Q = 423 \cdot \text{gpm}$  Much less!

## Problem 10.73

[Difficulty: 3]

**10.73** Consider the pipe network of Problem 8.189. Select a pump suitable to deliver a total flow rate of 300 gpm through the pipe network.

**Given:** Water pipe system

**Find:** Pump suitable for 300 gpm

**Solution:**

$$\left( \frac{p_1}{\rho} + \alpha_1 \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) = h_l \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$

$$f = \frac{64}{Re} \quad (\text{Laminar}) \qquad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad (\text{Turbulent})$$

The energy equation can be simplified to  $\Delta p = \rho \cdot f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$

This can be written for each pipe section

Pipe A (first section)  $\Delta p_A = \rho \cdot f_A \cdot \frac{L_A}{D_A} \cdot \frac{V_A^2}{2} \qquad (1)$

Pipe B (1.5 in branch)  $\Delta p_B = \rho \cdot f_B \cdot \frac{L_B}{D_B} \cdot \frac{V_B^2}{2} \qquad (2)$

Pipe C (1 in branch)  $\Delta p_C = \rho \cdot f_C \cdot \frac{L_C}{D_C} \cdot \frac{V_C^2}{2} \qquad (3)$

Pipe D (last section)  $\Delta p_D = \rho \cdot f_D \cdot \frac{L_D}{D_D} \cdot \frac{V_D^2}{2} \qquad (4)$

In addition we have the following constraints

$$Q_A = Q_D = Q \qquad (5)$$

$$Q = Q_B + Q_C \qquad (6)$$

$$\Delta p = \Delta p_A + \Delta p_B + \Delta p_D \qquad (7)$$

$$\Delta p_B = \Delta p_C \qquad (8)$$

We have 2 unknown flow rates (or, equivalently, velocities); We solve the above eight equations simultaneously

Once we compute the flow rates and pressure drops, we can compute data for the pump

$$\Delta p_{\text{pump}} = \Delta p \quad \text{and} \quad Q_{\text{pump}} = Q_A \quad W_{\text{pump}} = \Delta p_{\text{pump}} \cdot Q_{\text{pump}}$$

The calculations, performed in *Excel*, are shown on the next page.

Pipe Data:				
Pipe	$L$ (ft)	$D$ (in)	$e$ (ft)	
$A$	150	1.5	0.00085	
$B$	150	1.5	0.00085	
$C$	150	1	0.00085	
$D$	150	1.5	0.00085	
Fluid Properties:				
$\rho =$	1.94	slug/ft <sup>3</sup>		
$\mu =$	2.10E-05	lb-f-s/ft <sup>2</sup>		
Flow Rate:				
$Q =$	300	gpm		
$=$	0.668	ft <sup>3</sup> /s		
Flows:	$Q_A$ (ft <sup>3</sup> /s)	$Q_B$ (ft <sup>3</sup> /s)	$Q_C$ (ft <sup>3</sup> /s)	$Q_D$ (ft <sup>3</sup> /s)
	0.668	0.499	0.169	0.668
	$V_A$ (ft/s)	$V_B$ (ft/s)	$V_C$ (ft/s)	$V_D$ (ft/s)
	54.47	40.67	31.04	54.47
	$Re_A$	$Re_B$	$Re_C$	$Re_D$
	6.29E+05	4.70E+05	2.39E+05	6.29E+05
	$f_A$	$f_B$	$f_C$	$f_D$
	0.0335	0.0336	0.0384	0.0335
Heads:	$\Delta p_A$ (psi)	$\Delta p_B$ (psi)	$\Delta p_C$ (psi)	$\Delta p_D$ (psi)
	804.0	448.8	448.8	804.0
Constraints:	<b>(6) <math>Q = Q_B + Q_C</math></b>		<b>(8) <math>\Delta p_B = \Delta p_C</math></b>	
	0.00%		0.00%	
	<b>Error:</b>	0.00%	Vary $Q_B$ and $Q_C$ using <i>Solver</i> to minimize total error	
	For the pump:	$\Delta p$ (psi)	$Q$ (gpm)	$\mathcal{P}$ (hp)
		2057	300	360
This is a very high pressure; a sequence of pumps would be needed				

# Problem 10.74

[Difficulty: 3]

10.74 A fire nozzle is supplied through 300 ft of 3-in.-diameter canvas hose (with  $e=0.001$  ft). Water from a hydrant is supplied at 50 psig to a booster pump on board the pumper truck. At design operating conditions, the pressure at the nozzle inlet is 100 psig, and the pressure drop along the hose is 33 psi per 100 ft of length. Calculate the design flow rate and the maximum nozzle exit speed. Select a pump appropriate for this application, determine its efficiency at this operating condition, and calculate the power required to drive the pump.

Solution: Apply the energy equation for pipe flow:

$$\text{Computing equation: } \left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g z_2 \right) = h_L = h_e + h_{Lm}$$

$$h_e = f \frac{L}{D} \frac{V^2}{2}$$

Assumptions: (1)  $V_1 = V_2$ ; (2)  $z_1 = z_2$ ; (3)  $h_{Lm} = 0$

$$\text{Then } \frac{p_1}{\rho} - \frac{p_2}{\rho} = \frac{\Delta p}{\rho} = f \frac{L}{D} \frac{V^2}{2}; \quad V = \left[ \frac{2 D \Delta p}{f \rho L} \right]^{1/2}; \quad \frac{e}{D} = \frac{0.001 \text{ ft} \times 12 \text{ in.}}{3 \text{ in.} \times \text{ft}} = 0.004; \quad f = 0.028 \text{ (fully rough)}$$

$$\bar{V} = \left[ \frac{2}{0.028} \times 3 \text{ in.} \times 3(33) \frac{\text{lb}_f}{\text{in}^2} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{1}{300 \text{ ft}} \times \frac{12 \text{ in.}}{\text{ft}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb}_f \cdot \text{s}^2} \right]^{1/2} = 20.9 \text{ ft/s}$$

$$Q = \bar{V} A; \quad A = \frac{\pi D^2}{4} = \frac{\pi (3/12)^2 \text{ ft}^2}{4} = 0.0491 \text{ ft}^2$$

$$Q = 20.9 \frac{\text{ft}}{\text{s}} \times 0.0491 \text{ ft}^2 \times 7.48 \frac{\text{gal}}{\text{ft}^3} \times \frac{60 \text{ s}}{\text{min}} = 461 \text{ gpm (design flow rate)}$$

Apply Bernoulli to nozzle.

$$\frac{p_2}{\rho} + \frac{V_2^2}{2} + g z_2 = \frac{p_{atm}}{\rho} + \frac{V_n^2}{2} + g z_n; \quad V_n = \left[ \frac{2 p_2}{\rho} + V_2^2 \right]^{1/2}$$

$$V_n = \left[ 2 \times 100 \frac{\text{lb}_f}{\text{in}^2} \times \frac{\text{ft}^3}{1.94 \text{ slug}} \times \frac{144 \text{ in}^2}{\text{ft}^2} + (20.9)^2 \frac{\text{ft}^2}{\text{s}^2} \right]^{1/2} = 124 \text{ ft/s}$$

The pump head requirement (neglecting  $V$  and  $z$ ) will be

$$H_p = \frac{p_1 - p_0}{\rho g} = \frac{[100 + 3(33) - 50] \text{ lb}_f}{\text{in}^2} \times \frac{\text{ft}^3}{62.4 \text{ lb}_f} \times \frac{144 \text{ in.}}{\text{ft}} = 344 \text{ ft}$$

From the pump selector chart (Fig. D.1) choose 3AE96 or 4AE 10 pump, 3500 rpm.


Based on 4AE12 at 3550 rpm (Fig. D.5), expect  $\eta \approx 0.75$

$$P = \frac{Q \Delta p}{\eta} = \frac{Q \rho g \Delta h}{\eta} = \frac{1}{0.75} \times 20.9 \frac{\text{ft}}{\text{s}} \times 0.0491 \text{ ft}^2 \times 62.4 \frac{\text{lb}_f}{\text{ft}^3} \times 344 \text{ ft} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}_f} = 53.4 \text{ hp}$$

## Problem 10.75

[Difficulty: 4]

**10.75** A pumping system with two different static lifts is shown. Each reservoir is supplied by a line consisting of 1000 ft of 6-in. cast-iron pipe. Evaluate and plot the system head versus flow curve. Explain what happens when the pump head is less than the height of the upper reservoir. Calculate the flow rate delivered at a pump head of 85 ft.



**Given:** Pump and supply pipe system

**Find:** Head versus flow curve; Flow for a head of 85 ft

**Solution:**

$$\text{Basic equations: } \left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_{\text{pump}} \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$$

$$\text{Applying to the 70 ft branch (branch a)} \quad -g \cdot H_a = f \cdot \frac{L}{D} \cdot \frac{V_a^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V_a^2}{2} + K \cdot \frac{V_a^2}{2} - g \cdot H_{\text{pump}}$$

where  $H_a = 70 \cdot \text{ft}$  and  $\frac{L_{ea}}{D}$  is due to a standard T branch (= 60) and a standard elbow (= 30) from Table 8.4, and

$K = K_{\text{ent}} + K_{\text{exit}} = 1.5$  from Fig. 8.14

$$H_{\text{pump}} = H_a + \left[ f \cdot \left( \frac{L}{D} + \frac{L_{ea}}{D} \right) + K \right] \cdot \frac{V_a}{2 \cdot g} \quad (1)$$

$$\text{Applying to the 50 ft branch (branch b)} \quad H_{\text{pump}} = H_b + \left[ f \cdot \left( \frac{L}{D} + \frac{L_{eb}}{D} \right) + K \right] \cdot \frac{V_b}{2 \cdot g} \quad (2)$$

where  $H_b = 50 \cdot \text{ft}$  and  $\frac{L_{eb}}{D}$  is due to a standard T run (= 20) and two standard elbows (= 60), and  $K = K_{\text{ent}} + K_{\text{exit}} = 1.5$

Here are the calculations, performed in *Excel*:

Given data:


Computed results: Set up Solver so that it varies all flow rates to make the total head error zero

$L = 1000 \text{ ft}$   
 $e = 0.00085 \text{ ft}$   
 $D = 6.065 \text{ in}$   
 $K = 1.5$   
 $L_{ea}/D = 90$   
 $L_{eb}/D = 80$   
 $H_a = 70 \text{ ft}$   
 $H_b = 50 \text{ ft}$   
 $\rho = 1.94 \text{ slug/ft}^3$   
 $\nu = 1.06\text{E-}05 \text{ ft}^2/\text{s}$

$H_{\text{pump}}$ (ft)	$Q$ (ft <sup>3</sup> /s)	$Q_a$ (ft <sup>3</sup> /s)	$V_a$ (ft/s)	$Re_a$	$f_a$	$H_{\text{pump}}$ (Eq. 1)	$Q_b$ (ft <sup>3</sup> /s)	$V_b$ (ft/s)	$Re_b$	$f_b$	$H_{\text{pump}}$ (Eq. 2)	$H$ (Errors)
72.0	1.389	0.313	1.561	7.44E+04	0.0248	72.0	1.076	5.364	2.56E+05	0.0232	72.0	0.00
74.0	1.574	0.449	2.237	1.07E+05	0.0241	74.0	1.125	5.607	2.67E+05	0.0231	74.0	0.00
76.0	1.724	0.553	2.756	1.31E+05	0.0238	76.0	1.171	5.839	2.78E+05	0.0231	76.0	0.00
78.0	1.857	0.641	3.195	1.52E+05	0.0237	78.0	1.216	6.063	2.89E+05	0.0231	78.0	0.00
80.0	1.978	0.718	3.581	1.71E+05	0.0235	80.0	1.260	6.279	2.99E+05	0.0231	80.0	0.00
82.0	2.090	0.789	3.931	1.87E+05	0.0234	82.0	1.302	6.487	3.09E+05	0.0230	82.0	0.00
84.0	2.195	0.853	4.252	2.03E+05	0.0234	84.0	1.342	6.690	3.19E+05	0.0230	84.0	0.00
85.0	2.246	0.884	4.404	2.10E+05	0.0233	85.0	1.362	6.789	3.24E+05	0.0230	85.0	0.00
86.0	2.295	0.913	4.551	2.17E+05	0.0233	86.0	1.382	6.886	3.28E+05	0.0230	86.0	0.00
88.0	2.389	0.970	4.833	2.30E+05	0.0233	88.0	1.420	7.077	3.37E+05	0.0230	88.0	0.00
90.0	2.480	1.023	5.099	2.43E+05	0.0232	90.0	1.457	7.263	3.46E+05	0.0230	90.0	0.00
92.0	2.567	1.074	5.352	2.55E+05	0.0232	92.0	1.494	7.445	3.55E+05	0.0230	92.0	0.00
94.0	2.651	1.122	5.593	2.67E+05	0.0231	94.0	1.529	7.622	3.63E+05	0.0229	94.0	0.00

For the pump head less than the upper reservoir head flow will be out of the reservoir (into the lower one)


Total Error: 0.00



## Problem 10.76

[Difficulty: 4]

**10.76** Consider the flow system shown in Problem 8.90. Evaluate the *NPSHA* at the pump inlet. Select a pump appropriate for this application. Use the data on pipe aging from Problem 10.63 to estimate the reduction in flow rate after 10 years of operation.



**Given:** Data on flow from reservoir/pump

**Find:** Appropriate pump; Reduction in flow after 10 years

**Solution:**

Basic equation: 
$$\left( \frac{p_1}{\rho \cdot g} + \alpha \cdot \frac{V_1^2}{2 \cdot g} + z_1 \right) - \left( \frac{p_4}{\rho \cdot g} + \alpha \cdot \frac{V_4^2}{2 \cdot g} + z_4 \right) = H_{IT} - H_p \quad \text{for flow from 1 to 4}$$

$$H_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2 \cdot g} + K \cdot \frac{V^2}{2 \cdot g}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4)  $V_2 = V_3 = V_4$  (constant area pipe)

Given or available data  $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$   $\nu = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$   $p_v = 2.34 \cdot \text{kPa}$  (Table A.8)

$p_2 = 150 \cdot \text{kPa}$   $p_3 = 450 \cdot \text{kPa}$   $D = 15 \cdot \text{cm}$   $e = 0.046 \cdot \text{mm}$   $Q = 0.075 \cdot \frac{\text{m}^3}{\text{s}}$

$z_1 = 20 \cdot \text{m}$   $z_4 = 35 \cdot \text{m}$   $V = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V = 4.24 \cdot \frac{\text{m}}{\text{s}}$

For minor losses we have Four elbows:  $\frac{L_e}{D} = 4 \times 12 = 48$  (Fig. 8.16) Square inlet:  $K_{ent} = 0.5$

At the pump inlet 
$$\text{NPSHA} = \frac{p_2 + \frac{1}{2} \cdot \rho \cdot V^2 - p_v}{\rho \cdot g} \quad \text{NPSHA} = 16.0 \text{ m}$$

The head rise through the pump is  $H_p = \frac{p_3 - p_2}{\rho \cdot g}$   $H_p = 30.6 \text{ m}$

Hence for a flow rate of  $Q = 0.075 \cdot \frac{\text{m}^3}{\text{s}}$  or  $Q = 1189 \cdot \text{gpm}$  and  $H_p = 30.6 \text{ m}$  or  $H_p = 100 \cdot \text{ft}$ , from

Appendix D. Fig. D3 a Peerless4AE11 would suffice

We do not know the pipe length  $L$ ! Solving the energy equation for  $z_1 - z_4 = H_{IT} - H_p = f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2 \cdot g} + K_{ent} \cdot \frac{V^2}{2 \cdot g} - H_p$

For  $f$   $Re = \frac{V \cdot D}{\nu}$   $Re = 6.303 \times 10^5$  and  $\frac{e}{D} = 3.07 \times 10^{-4}$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7 \cdot D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0161$$

Hence, substituting values

$$L = \frac{2 \cdot g \cdot D}{f \cdot V^2} \cdot (z_1 - z_4 + H_p) - D \cdot \left( \frac{L_e}{D} \right) - \frac{K_{ent} \cdot D}{f}$$

$L = 146 \text{ m}$

From Problem 10.63, for a pipe  $D = 0.15 \text{ m}$  or  $D = 5.91 \cdot \text{in}$ , the aging over 10 years leads to

$f_{\text{worn}} = 2.2 \cdot f$

We need to solve the energy equation for a new  $V$

$$V_{\text{worn}} = \sqrt{\frac{2 \cdot g \cdot (z_1 - z_4 + H_p)}{f_{\text{worn}} \cdot \left( \frac{L}{D} + \frac{L_e}{D} \right) + K_{ent}}}$$

$V_{\text{worn}} = 2.88 \frac{\text{m}}{\text{s}}$

Hence

$$Q_{\text{worn}} = \frac{\pi \cdot D^2}{4} \cdot V_{\text{worn}} \quad Q_{\text{worn}} = 0.0510 \cdot \frac{\text{m}^3}{\text{s}}$$

$$\Delta Q = Q_{\text{worn}} - Q \quad \Delta Q = -0.0240 \cdot \frac{\text{m}^3}{\text{s}} \quad \frac{\Delta Q}{Q} = -32.0\%$$

Check  $f$

$$\text{Re}_{\text{worn}} = \frac{V_{\text{worn}} \cdot D}{\nu} \quad \text{Given} \quad \frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{\frac{e}{D}}{3.7} + \frac{2.51}{\text{Re}_{\text{worn}} \cdot \sqrt{f}} \right)$$

$f = 0.0165$

Hence using  $2.2 \times 0.0161$  is close enough to using  $2.2 \times 0.0165$

10.77 Consider the gasoline pipeline flow of Problem 8.142.

Select pumps that, combined in parallel, supply the total flow requirement. Calculate the power required for 4 pumps in parallel. Also calculate the volume flow rates and power required when only 1, 2, or 3 of these pumps operates.

Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equation:  $\frac{p_i}{\rho g} + \frac{\alpha_i \bar{V}_i^2}{2g} + z_i + H_p = \frac{p_j}{\rho g} + \frac{\alpha_j \bar{V}_j^2}{2g} + z_j + \frac{h_{LT}}{g}$ ;  $h_{LT} = \left[ f \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \frac{\bar{V}^2}{2}$

Assumptions: (1)  $\bar{V}_1 = \bar{V}_2$ ,  $\alpha_1 = \alpha_2$ , (2)  $z_1 = z_2$ , (3) Neglect minor losses,  $\frac{L_e}{D} \approx 0$ ,  $K \approx 0$

Find flow rate to size pump. From 1 to 2,  $H_p = 0$ , so  $D = 0.6 \text{ m} \times \frac{\text{ft}}{0.305 \text{ m}} = 1.97 \text{ ft}$

$\frac{p_i}{\rho g} = \frac{p_2}{\rho g} + \frac{h_{LT}}{g}$ ;  $\Delta p = \rho h_{LT} = \rho f \frac{L}{D} \frac{\bar{V}^2}{2}$ ;  $\bar{V} = \left[ \frac{2 \Delta p D}{\rho f L} \right]^{1/2}$   $\frac{e}{D} = \frac{0.00015 \text{ m}}{0.6 \text{ m}} = 2.5 \times 10^{-4}$

But  $f = f(Re, e/D)$ ;  $Re$  is not known. Choose  $f$  from fully-rough region,  $f = 0.014$ .

$\Delta p = 1.4 \times 10^6 \text{ Pa} \times \frac{14.7 \text{ psi}}{101 \times 10^3 \text{ Pa}} = 204 \text{ psi}$ ;  $\rho = 0.72 \rho_{H_2O} = 0.72 \times 1.94 \frac{\text{slug}}{\text{ft}^3} = 1.40 \text{ slug/ft}^3$

$\bar{V} = \left[ 2 \times 204 \frac{\text{lb}_f}{\text{in}^2} \times 1.97 \text{ ft} \times \frac{\text{ft}^3}{1.40 \text{ slug}} \times \frac{1}{0.014} \times \frac{1}{42,600 \text{ ft}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb}_f \cdot \text{s}^2} \times 144 \frac{\text{in}^2}{\text{ft}^2} \right]^{1/2} = 11.8 \text{ ft/s}$

Check:  $Re = \frac{\bar{V} D}{\nu} = \frac{11.8 \text{ ft}}{\text{s}} \times 1.97 \text{ ft} \times \frac{\text{s}}{8.6 \times 10^{-6} \text{ ft}^2} = 2.70 \times 10^6$ ;  $f = 0.0146$  (see Note below.)

$\bar{V} = \left[ \frac{0.014}{0.0146} \right]^{1/2} 11.8 \frac{\text{ft}}{\text{s}} = 11.6 \text{ ft/s}$ ,  $Q = \bar{V} A = 35.3 \frac{\text{ft}^3}{\text{s}} = 15,700 \text{ gpm}$  Q

For parallel operation with four pumps, each must supply  $\frac{Q}{4} = 3930 \text{ gpm}$ .

The head requirement is  $H_p = \frac{p_i - p_2}{\rho g} = \frac{204 \text{ lb}_f}{\text{in}^2} \times \frac{\text{ft}^3}{(0.72) 62.4 \text{ lb}_f} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 654 \text{ ft (gasoline)}$

This combination of head and flow rate cannot be supplied by a single-stage pump. From Fig. D.11, the two-stage Peerless Type 10 TU 22C pump may be chosen. Pump

The input power requirement is  $\dot{W}_m = \frac{\rho g Q H}{\eta_p}$ . Assuming  $\eta_p = 0.65$ ,

$\dot{W}_m = \frac{1}{0.65} \times 15,700 \frac{\text{gal}}{\text{min}} \times 204 \frac{\text{lb}_f}{\text{in}^2} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{\text{min}}{60 \text{ s}} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}_f} = 2870 \text{ hp (total)}$   $\dot{W}_m$

Flow rates with fewer pumps operating may be found from a plot. The pump characteristic may be approximated as (assume  $H = 0.7 H_0$ ):

$\hat{H}_p \approx 934 - 1.81 \times 10^{-5} Q^2$   $\{ H_0 = \frac{654}{0.7} = 934; B = \frac{H_0 - H}{Q^2} = \frac{(0.3) 934}{(3930)^2} = 1.81 \times 10^{-5} \}$

{Note: gasoline is between octane and heptane, Fig. A.3. For  $T = 15^\circ \text{C}$ ,  $\nu \approx 8 \times 10^{-7} \text{ m}^2/\text{s} = 8.6 \times 10^{-6} \frac{\text{ft}^2}{\text{s}}$ }

32 SHEETS 5 SQUARE  
25 SHEETS 3 SQUARE  
25 SHEETS 3 SQUARE  
NATIONAL  
MFG. CO. U.S.A.



10.78 Consider the chilled water circulation system of Problem 8.178. Select pumps that may be combined in parallel to supply the total flow requirement. Calculate the power required for 3 pumps in parallel. Also calculate the volume flow rates and power required when only 1 or 2 of these pumps operates.

Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equation:  $\frac{p_1}{\rho g} + \alpha_1 \frac{V_1^2}{2g} + z_1 + H_a = \frac{p_2}{\rho g} + \alpha_2 \frac{V_2^2}{2g} + z_2 + \frac{h_{LT}}{g}$ ;  $h_{LT} = [f(\frac{L}{D} + \frac{L_e}{D}) + \sum K] \frac{V^2}{2}$

Assumptions: (1)  $p_1 = p_2$ , (2)  $\alpha_1 V_1^2 = \alpha_2 V_2^2$ , (3)  $z_1 = z_2$ , (4) Neglect minor losses,  $\frac{L_e}{D} \approx 0$ ,  $K \approx 0$

$\bar{V} = \frac{Q}{A} = \frac{11,200 \text{ gal}}{\text{min}} \times \frac{4}{\pi(2)^2 \text{ ft}^2} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{\text{min}}{60 \text{ sec}} = 7.94 \text{ ft/s}$ ;  $\frac{V^2}{2g} = \frac{1}{2} \times (7.94)^2 \frac{\text{ft}^2}{\text{s}^2} \times \frac{\text{s}^2}{32.2 \text{ ft}} = 0.979 \text{ ft}$

Assume  $T = 40 \text{ F}$ , so  $\nu = 1.64 \times 10^{-5} \text{ ft}^2/\text{s}$ ;  $Re = \frac{VD}{\nu} = 9.68 \times 10^5$ ;  $\frac{L}{D} = 7.5 \times 10^{-5}$ ;  $f = 0.013$


$H_a = f \frac{L}{D} \frac{V^2}{2g} = 0.013 \times \frac{3(5280) \text{ ft}}{2 \text{ ft}} \times 0.979 \text{ ft} = 101 \text{ ft}$

$H_p$

For three pumps in parallel, each will operate at  $Q/3 = 3730 \text{ gpm}$ . The requirement for each pump is  $H = 101 \text{ ft}$  at  $Q = 3730 \text{ gpm}$ . This can be supplied by Peerless Type 10AE12 pumps with impellers of  $D = 12 \text{ in.}$  diameter, operating at  $N = 1760 \text{ nominal rpm}$ . The efficiency at this operating point is  $\eta \approx 0.85$ .

3 pump.

Find operating points graphically for 1, 2, and 3 pumps:



The graphical solution is shown

$Q_1 = \text{not satisfactory}$ ,  $Q_2 = 9400 \text{ gpm (marginal)}$ ,  $Q_3 = 11,200 \text{ gpm (OK)}$

$Q$

Assuming  $\eta_p \approx 0.7$ , then  $W_{m1} = \frac{\rho Q g H}{\eta} \approx 78 \text{ hp}$ ,  $W_{m2} \approx 241 \text{ hp}$ , and  $W_{m3} \approx 409 \text{ hp}$

## Problem 10.79

[Difficulty: 4]

**10.79** Water for the sprinkler system at a lakeside summer home is to be drawn from the adjacent lake. The home is located on a bluff 33 m above the lake surface. The pump is located on level ground 3 m above the lake surface. The sprinkler system requires 40 L/min at 300 kPa (gage). The piping system is to be 2-cm-diameter galvanized iron. The inlet section (between the lake and pump inlet) includes a reentrant inlet, one standard 45° elbow, one standard 90° elbow, and 20 m of pipe. The discharge section (between the pump outlet and the sprinkler connection) includes two


standard 45° elbows and 45 m of pipe. Evaluate the head loss on the suction side of the pump. Calculate the gage pressure at the pump inlet. Determine the hydraulic power requirement of the pump. If the pipe diameter were increased to 4 cm, would the power requirement of the pump increase, decrease, or stay the same? What difference would it make if the pump were located halfway up the hill?

**Given:** Sprinkler system for lakeside home

- Find:**
- Head loss on suction side of pump
  - Gage pressure at pump inlet
  - Hydraulic power requirement for the pump
  - Change in power requirement if pipe diameter is changed
  - Change in power requirement if the pump were moved

**Solution:**

We will apply the energy equation for steady, incompressible pipe flow.



Basic equations:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p$$

$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \sum f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + \sum K \cdot \frac{V^2}{2} \quad H = \frac{h}{g}$$

Assumptions: 1)  $p_1 = p_{atm}$  2)  $V_1 = 0$

The given or available data is  $Q = 40 \cdot \frac{L}{min}$   $D = 2 \cdot cm$   $e = 0.15 \cdot mm$   $p_{atm} = 101.3 \cdot kPa$   $p_4 = 300 \cdot kPa$  (gage)

$$z_1 = 0 \cdot m \quad z_2 = 3 \cdot m \quad z_3 = z_2 \quad z_4 = 33 \cdot m \quad L_{12} = 20 \cdot m \quad L_{34} = 45 \cdot m$$

From Table A.8 at 20°C  $\nu = 1.01 \times 10^{-6} \cdot \frac{m^2}{s}$   $p_v = 2.34 \cdot kPa$   $\rho = 998 \cdot \frac{kg}{m^3}$

At the specified flow rate, the speed of the water is:  $V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V = 2.122 \cdot \frac{m}{s}$   $Re = \frac{V \cdot D}{\nu} = 4.202 \times 10^4$

$$\frac{e}{D} = 7.5 \times 10^{-3} \quad \text{Therefore we can calculate the friction factor: } f = \left[ -1.8 \cdot \log \left[ \left( \frac{e}{3.7 \cdot D} \right)^{1.11} + \frac{6.9}{Re} \right] \right]^{-2} = 0.036$$

Between 1 and 2:  $-\left( \frac{p_2}{\rho} + \alpha_2 \frac{V^2}{2} + g \cdot z_2 \right) = f \cdot \left( \frac{L_{12}}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$  In this case:  $L_e = (30 + 16) \cdot D$   $K = 0.78$

The head loss before the pump is:  $H_{IT12} = f \cdot \left( \frac{L_{12}}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2 \cdot g} + K \cdot \frac{V^2}{2 \cdot g}$   $H_{IT12} = 8.844 \text{ m}$

Solving for pressure at 2:  $p_2 = \rho \cdot \left[ \frac{V^2}{2} + g \cdot z_2 - f \cdot \left( \frac{L_{12}}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} - K \cdot \frac{V^2}{2} \right]$   $p_2 = -54.946 \cdot \text{kPa (gage)}$

To find the pump power, we need to analyze between 3 and 4:

$\left( \frac{p_3}{\rho} + g \cdot z_3 \right) - \left( \frac{p_4}{\rho} + g \cdot z_4 \right) = f \cdot \left( \frac{L_{34}}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2}$  In this case:  $L_e = (16 + 16) \cdot D$   $K = 0$

$p_3 = p_4 + \rho \cdot \left[ g \cdot (z_4 - z_3) + f \cdot \left( \frac{L_{34}}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} \right]$   $p_3 = 778.617 \cdot \text{kPa}$  Thus the pump head is:  $H_p = \frac{p_3 - p_2}{\rho \cdot g} = 85.17 \text{ m}$

Now we can calculate the power:  $W_p = \rho \cdot g \cdot Q \cdot H_p$   $W_p = 556 \text{ W}$

Changing to 4 centimeter pipe would reduce the mean velocity and hence the head loss and minor loss:  $D = 4 \cdot \text{cm}$

$V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$   $V = 0.531 \frac{\text{m}}{\text{s}}$   $Re = \frac{V \cdot D}{\nu} = 2.101 \times 10^4$   $\frac{e}{D} = 3.75 \times 10^{-3}$   $f = \left[ -1.8 \cdot \log \left[ \left( \frac{e}{3.7 \cdot D} \right)^{1.11} + \frac{6.9}{Re} \right] \right]^{-2} = 0.032$

$L_e = (30 + 16) \cdot D$   $K = 0.78$   $p_2 = \rho \cdot \left[ \frac{V^2}{2} + g \cdot z_2 - f \cdot \left( \frac{L_{12}}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} - K \cdot \frac{V^2}{2} \right]$   $p_2 = 26.922 \cdot \text{kPa (gage)}$

$L_e = (16 + 16) \cdot D$   $K = 0$   $p_3 = p_4 + \rho \cdot \left[ g \cdot (z_4 - z_3) + f \cdot \left( \frac{L_{34}}{D} + \frac{L_e}{D} \right) \cdot \frac{V^2}{2} \right]$   $p_3 = 778.617 \cdot \text{kPa (gage)}$

$H_p = \frac{p_3 - p_2}{\rho \cdot g} = 58.44 \text{ m}$   $W_{pnew} = \rho \cdot g \cdot Q \cdot H_p = 381.283 \text{ W}$   $\Delta W_p = \frac{W_{pnew} - W_p}{W_p} = -31. \%$


The pump should not be moved up the hill. The NPSHA is:  $NPSHA = \frac{p_2 + p_{atm} + \rho \cdot \frac{V^2}{2} - p_v}{\rho \cdot g} = 4.512 \text{ m}$  for 2-cm pipe.

If anything, the pump should be moved down the hill to increase the NPSHA.

## Problem 10.80

[Difficulty: 4]

**10.80** Consider the fire hose and nozzle of Problem 8.179. Specify an appropriate pump to supply four such hoses simultaneously. Calculate the power input to the pump.



**Given:** Fire nozzle/pump system

**Find:** Appropriate pump; Impeller diameter; Pump power input needed

**Solution:**

Basic equations 
$$\left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) - \left( \frac{p_3}{\rho} + \alpha \cdot \frac{V_3^2}{2} + g \cdot z_3 \right) = h_f = f \cdot \frac{L}{D} \cdot \frac{V_2^2}{2} \quad \text{for the hose}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 2 and 3 is approximately 1 4) No minor loss

$$\left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) - \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) = h_{\text{pump}} \quad \text{for the pump}$$

Assumptions: 1) Steady flow 2) Incompressible flow 3)  $\alpha$  at 1 and 2 is approximately 1 4) No minor loss

The first thing we need is the flow rate. Below we repeat Problem 8.179 calculations

Hence for the hose 
$$\frac{\Delta p}{\rho} = \frac{p_2 - p_3}{\rho} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} \quad \text{or} \quad V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}}$$

We need to iterate to solve this for  $V$  because  $f$  is unknown until  $Re$  is known. This can be done using *Excel's Solver*, but here:

$\Delta p = 750 \cdot \text{kPa} \quad L = 100 \cdot \text{m} \quad e = 0 \quad D = 3.5 \cdot \text{cm} \quad \rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3} \quad \nu = 1.01 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$

Make a guess for  $f = 0.01 \quad V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 7.25 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.51 \times 10^5$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0150$$

$V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 5.92 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.05 \times 10^5$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0156$$

$V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 5.81 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.01 \times 10^5$

Given 
$$\frac{1}{\sqrt{f}} = -2.0 \cdot \log \left( \frac{e}{3.7D} + \frac{2.51}{Re \cdot \sqrt{f}} \right) \quad f = 0.0156$$

$V = \sqrt{\frac{2 \cdot \Delta p \cdot D}{\rho \cdot f \cdot L}} \quad V = 5.80 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} \quad Re = 2.01 \times 10^5$

$$Q = \frac{\pi \cdot D^2}{4} \cdot v \quad Q = 5.578 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q = 0.335 \cdot \frac{\text{m}^3}{\text{min}}$$

We have

$$p_1 = 350 \cdot \text{kPa} \quad p_2 = 700 \cdot \text{kPa} + 750 \cdot \text{kPa} \quad p_2 = 1450 \cdot \text{kPa}$$

For the pump

$$\left( \frac{p_2}{\rho} + \alpha \cdot \frac{V_2^2}{2} + g \cdot z_2 \right) - \left( \frac{p_1}{\rho} + \alpha \cdot \frac{V_1^2}{2} + g \cdot z_1 \right) = h_{\text{pump}}$$

$$\text{so } h_{\text{pump}} = \frac{p_2 - p_1}{\rho} \quad \text{or} \quad H_{\text{pump}} = \frac{p_2 - p_1}{\rho \cdot g} \quad H_{\text{pump}} = 112 \text{ m}$$

We need a pump that can provide a flow of  $Q = 0.335 \cdot \frac{\text{m}^3}{\text{min}}$  or  $Q = 88.4 \cdot \text{gpm}$ , with a head of  $H_{\text{pump}} = 112 \text{ m}$  or  $H_{\text{pump}} = 368 \cdot \text{ft}$

From Appendix D, Fig. D.1 we see that a Peerless 2AE11 can provide this kind of flow/head combination; it could also handle four such hoses (the flow rate would be  $4 \cdot Q = 354 \cdot \text{gpm}$ ). An impeller diameter could be chosen from proprietary curves.

The required power input is  $W_m = \frac{W_h}{\eta_p}$  where we choose  $\eta_p = 75\%$  from Fig. 10.15

$$W_m = \frac{\rho \cdot Q \cdot g \cdot H_{\text{pump}}}{\eta_p} \quad W_m = 8.18 \cdot \text{kW} \quad \text{for one hose or} \quad 4 \cdot W_m = 32.7 \cdot \text{kW} \quad \text{for four}$$

$$P_{\text{required}} = \frac{P_{\text{pump}}}{\eta} \quad P_{\text{required}} = \frac{6.14 \cdot \text{kW}}{70\%} \quad P_{\text{required}} = 8.77 \cdot \text{kW} \quad \text{or} \quad 4 \cdot P_{\text{required}} = 35.1 \cdot \text{kW} \quad \text{for four}$$

## Problem 10.81

[Difficulty: 4]

**10.81** Manufacturer's data for a submersible utility pump are

Discharge height (ft)	0.3	0.7	1.5	3.0	4.5	6.0	8.0
Water flow rate (L/min)	77.2	75	71	61	51	26	0

The owner's manual also states, "Note: These ratings are based on discharge into 25-mm pipe with friction loss neglected. Using 20-mm garden hose adaptor, performance will be reduced approximately 15 percent." Plot a performance curve for the pump. Develop a curve-fit equation for the performance curve; show the curve-fit on the plot. Calculate and plot the pump delivery versus discharge height through a 15-m length of smooth 20-mm garden hose. Compare with the curve for delivery into 25-mm pipe.

**Given:** Manufacturer data for a pump

**Find:** (a) Plot performance and develop curve-fit equation.  
(b) Calculate pump delivery vs discharge height for length of garden hose

**Solution:**

Basic equations: 
$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + K \cdot \frac{V^2}{2} \quad H = \frac{h}{g} \quad H_p = H_0 - A \cdot Q^2$$

For this case,  $L_e = K = 0$ , therefore: 
$$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$$
 Here are the results calculated in *Excel*:

Given data:


$L = 15 \text{ m}$   
 $e = 0 \text{ ft}$   
 $D = 20 \text{ mm}$   
 $\rho = 998 \text{ kg/m}^3$   
 $\nu = 1.01\text{E-}06 \text{ m}^2/\text{s}$

$H_0 = 7.48727 \text{ m}$   
 $A = 0.0012 \text{ m}/(\text{L}/\text{min})^2$

Here are the data for the head generated by the pump, as well as the head losses for the hose and the pipe:

$D = 20 \text{ mm}$                        $D = 25 \text{ mm}$   
 $e = 0 \text{ mm}$                                $e = 0.15 \text{ mm}$

$z \text{ (m)}$	$Q \text{ (L/min)}$	$Q^2$	$z_{fit} \text{ (m)}$	$V \text{ (m/s)}$	$Re_a$	$f_a$	$H_L \text{ (m)}$	$V \text{ (m/s)}$	$Re_a$	$f_a$	$H_L \text{ (m)}$
0.3	77.2	5959.840	0.320	4.096	8.11E+04	0.0188	12.1	2.621	6.49E+04	0.0334	7.0
0.7	75.0	5625.000	0.722	3.979	7.88E+04	0.0189	11.4	2.546	6.30E+04	0.0334	6.6
1.5	71.0	5041.000	1.425	3.767	7.46E+04	0.0191	10.4	2.411	5.97E+04	0.0335	6.0
3.0	61.0	3721.000	3.012	3.236	6.41E+04	0.0198	7.9	2.071	5.13E+04	0.0337	4.4
4.5	51.0	2601.000	4.359	2.706	5.36E+04	0.0206	5.8	1.732	4.29E+04	0.0340	3.1
6.0	26.0	676.000	6.674	1.379	2.73E+04	0.0240	1.7	0.883	2.19E+04	0.0356	0.8
8.0	0.0	0.000	7.487	0.000	0.00E+00	0.0000	0.0	0.000	0.00E+00	0.0000	0.0




To determine the discharge heights for the hose and the pipe, we subtract the head loss from the head generated by the pump.

For the hose:

For the pipe:

$Q$ (L/min)	$V$ (m/s)	$Re_a$	$f_a$	$H_L$ (m)	Disch (m)	$V$ (m/s)	$Re_a$	$f_a$	$H_L$ (m)	Disch (m)	% Diff
0.0	0.000	0.00E+00	0.0000	0.000	7.487	0.000	0.00E+00	0.0000	0.000	7.487	0%
10.0	0.531	1.05E+04	0.0305	0.328	7.039	0.340	8.40E+03	0.0398	0.140	7.227	-3%
20.0	1.061	2.10E+04	0.0256	1.101	5.906	0.679	1.68E+04	0.0364	0.514	6.492	-9%
30.0	1.592	3.15E+04	0.0232	2.248	4.157	1.019	2.52E+04	0.0351	1.115	5.290	-21%
40.0	2.122	4.20E+04	0.0217	3.740	1.823	1.358	3.36E+04	0.0345	1.943	3.620	-50%
50.0	2.653	5.25E+04	0.0207	5.558	-1.077	1.698	4.20E+04	0.0340	2.998	1.483	
60.0	3.183	6.30E+04	0.0199	7.689	-4.531	2.037	5.04E+04	0.0337	4.279	-1.122	



The results show that the 15% performance loss is an okay "ball park" guess at the lower flow rates, but not very good at flow rates above 30 L/min.

## Problem 10.82

[Difficulty: 4]


**10.82** Consider the swimming pool filtration system of Problem 8.190. Assume the pipe used is 20-mm PVC (smooth plastic). Specify the speed and impeller diameter and estimate the efficiency of a suitable pump.

**Given:** Swimming pool filtration system, filter pressure drop is  $\Delta p = 0.6Q^2$ , with  $\Delta p$  in psi and  $Q$  in gpm

**Find:** Speed and impeller diameter of suitable pump; estimate efficiency

**Solution:**

We will apply the energy equation for steady, incompressible pipe flow.



Basic equations:

$$\left( \frac{p_1}{\rho} + \alpha_1 \frac{V_1^2}{2} + g \cdot z_1 \right) - \left( \frac{p_2}{\rho} + \alpha_2 \frac{V_2^2}{2} + g \cdot z_2 \right) = h_{IT} - h_p \quad h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2} + \sum f \cdot \frac{L_e}{D} \cdot \frac{V^2}{2} + \sum K \cdot \frac{V^2}{2} \quad H = \frac{h}{g}$$

The given or available data are:  $Q = 30 \text{ gpm} \quad Q = 1.893 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad \nu = 1.06 \times 10^{-5} \frac{\text{ft}^2}{\text{s}} \quad \nu = 9.848 \times 10^{-7} \frac{\text{m}^2}{\text{s}}$

$$\rho = 1.93 \frac{\text{slug}}{\text{ft}^3} \quad \rho = 995 \frac{\text{kg}}{\text{m}^3} \quad D = 20 \text{ mm} \quad e = 0 \text{ mm}$$

Setting state 1 at the pump discharge, state 2 at the tee, state 3a downstream of the filter, and state 3b after the 40 ft pipe, we can look at the pressure drop between 1 and 2:

$$V_1 = V_2 \quad \frac{e}{D} = 0 \quad V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2} \quad V = 6.025 \frac{\text{m}}{\text{s}} \quad Re = \frac{V \cdot D}{\nu} = 1.224 \times 10^5$$

$$\frac{e}{D} = 0 \quad \text{Therefore we can calculate the friction factor:} \quad f = \left[ -1.8 \cdot \log \left[ \left( \frac{e}{3.7 \cdot D} \right)^{1.11} + \frac{6.9}{Re} \right] \right]^{-2} = 0.017$$

Since this is a straight run of pipe:  $L_e = 0 \quad K = 0$  and therefore the pressure drop is:  $\Delta p_{12} = \rho \cdot f \cdot \frac{V^2}{2} \cdot \frac{L}{D} \quad \Delta p_{12} = 47.04 \text{ kPa}$

Since both legs exhaust to the same pressure, the pressure drops between the two must be equal, and the flow rates must equal the total flow rate of the system. This requires an iterative solution, using *Solver* in Excel. The result is:

$$Q_a = 1.094 \times 10^{-3} \frac{\text{m}^3}{\text{s}} \quad Q_b = 7.99 \times 10^{-4} \frac{\text{m}^3}{\text{s}} \quad \text{The resulting pressure drop is} \quad \Delta p_{23} = 42.96 \text{ kPa}$$

Neglecting any pressure at the pump inlet, the pump must supply:  $\Delta p_{\text{pump}} = \Delta p_{12} + \Delta p_{23} = 90.0 \text{ kPa}$

The resulting head is:  $H_{\text{pump}} = \frac{\Delta p_{\text{pump}}}{\rho \cdot g} = 9.226 \text{ m}$  in U.S. units:  $H_{\text{pump}} = 30.269 \text{ ft}$

This head is too low for any of the pumps in Fig. D.1. Therefore, assuming a speed of 3500 rpm:  $N = \frac{\omega \cdot \sqrt{Q}}{(g \cdot H_{\text{pump}})^{0.75}} = 0.544$

In customary units:  $N_{\text{cu}} = 2733 \cdot N = 1485$  So from Figure 10.9 we can estimate the efficiency:  $\eta = 65\%$


The pump power is:  $W_p = \frac{\rho \cdot Q \cdot g \cdot H_{\text{pump}}}{\eta} = 262.056 \text{ W}$

$$W_p = 262.1 \text{ W}$$

### Problem 10.83

[Difficulty: 4] Part 1/2

**10.83** Water is pumped from a lake (at  $z=0$ ) to a large storage tank located on a bluff above the lake. The pipe is 3-in.-diameter galvanized iron. The inlet section (between the lake and the pump) includes one rounded inlet, one standard  $90^\circ$  elbow, and 50 ft of pipe. The discharge section (between the pump outlet and the discharge to the open tank) includes two standard  $90^\circ$  elbows, one gate valve, and 150 ft of pipe. The pipe discharge (into the side of the tank) is at  $z=70$  ft. Calculate the system flow curve. Estimate the system operating point. Determine the power input to the pump if its efficiency at the operating point is 80 percent. Sketch the system curve when the water level in the upper tank reaches  $z=90$  ft. If the water level in the upper tank is at  $z=75$  ft and the valve is partially closed to reduce the flow rate to  $0.1 \text{ ft}^3/\text{s}$ , sketch the system curve for this operating condition. Would you expect the pump efficiency to be higher for the first or second operating condition? Why?



Solution: Apply the energy equation for pipe flow. The pump must overcome the gravity lift plus the head losses in the pipe and fittings.

Assume: (1) Nominal speed is  $\bar{V} = 12 \text{ ft/s}$ ,  $T = 60^\circ\text{F}$ ,  $\nu = 1.21 \times 10^{-5} \text{ ft}^2/\text{s}$  (Table A.7)

(2) Flow in fully rough zone ( $e = 0.0005 \text{ ft}$  (Table 8.1),  $e/D = 0.002$ ,  $f \approx 0.024$ )

(3) Cases: (1) Water in tank below ③ } Valve open  
(2) Water in tank at  $z = 90 \text{ ft}$  }  
(3) Valve closed so  $Q = 0.1 \text{ ft}^3/\text{s}$ , valve part closed.

Then

$$H_{RT} = \frac{h_{RT}}{g} = \left[ K_{ent} + f \left( \frac{L}{D} + 3 \frac{L_e(\text{elbow})}{D} + \frac{L_e(\text{gate valve})}{D} \right) + K_{exit} \right] \frac{\bar{V}^2}{2g}$$

$$H_{RT} = \left[ 0.04 + 0.024 \left( \frac{200 \text{ ft} \times 12 \frac{\text{in.}}{\text{ft}}}{3.068 \text{ in.}} + 3(30) + 8 \right) + 1 \right] \frac{\bar{V}^2}{2g} = 22.2 \frac{\bar{V}^2}{2g}$$

$$\text{and } H_s = z_{end} + 22.2 \frac{\bar{V}^2}{2g}$$

$$\text{Assume } \bar{V} = 12 \text{ ft/s}, Q = 276 \text{ gpm}, \frac{\bar{V}^2}{2g} = 2.24 \text{ ft}, H_s = 70 + 22.2(2.24) = 120 \text{ ft}$$

Case 1:  $z_{end} = 70 \text{ ft}$  Operating point:  $Q = 276 \text{ gpm}$ ,  $H_P = H_s = 120 \text{ ft}$

$$P = \frac{\rho g Q H}{\eta_P} = \frac{62.4 \frac{\text{lb}}{\text{ft}^3} \times 12.0 \frac{\text{ft}}{\text{s}} \times 0.0513 \text{ ft}^3 \times 120 \text{ ft} \times \frac{1}{0.8} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}}}{0.8} = 10.5 \text{ hp}$$

Case 2:  $z_{end} = 90 \text{ ft}$ ;  $H_s = 90 + 22.2(2.24) = 140 \text{ ft}$

$$H_s = 90 + \frac{50.0 [Q(\text{gpm})]^2}{(276)^2 (\text{gpm})^2} = 90 + 6.56 \times 10^{-4} [Q(\text{gpm})]^2$$

Case 3:  $Q = 0.1 \text{ ft}^3/\text{s} = 44.9 \text{ gpm}$ ;  $H_s = H_P$ ; Assume  $H_{PEP} = 0.7 H_0$

$$H_P = H_0 + \frac{(H_0 - H_{op})}{Q_{op}^2} Q^2 = \frac{120}{0.7} - \frac{(120/0.7 - 120)}{(276)^2} Q^2 = 169 - 6.75 \times 10^{-4} Q^2$$

$$H_P = 168 \text{ ft at } Q = 44.9 \text{ gpm}$$

$H_s$

Oper. Pt.

P

$H_s$

$H_P$

over



## Problem 10.84

[Difficulty: 3]

**10.84** Performance data for a centrifugal fan of 3-ft diameter, tested at 750 rpm, are

Volume flow rate $Q$ (ft <sup>3</sup> /s)	106	141	176	211	246	282
Static pressure rise, $\Delta p$ (psi)	0.075	0.073	0.064	0.050	0.033	0.016
Power output $\mathcal{P}$ (hp)	2.75	3.18	3.50	3.51	3.50	3.22

Plot the performance data versus volume flow rate. Calculate static efficiency, and show the curve on the plot. Find the best efficiency point, and specify the fan rating at this point.

**Given:** Data on centrifugal fan

**Find:** Plot of performance curves; Best efficiency point

**Solution:**

Basic equations:  $\eta_p = \frac{W_h}{W_m}$        $W_h = Q \cdot \Delta p$        $\Delta p = \rho_w \cdot g \cdot \Delta h$  (Note: Software cannot render a dot!)

Here are the results, calculated using *Excel*:

$$\rho_w = 1.94 \text{ slug/ft}^3$$

Fitting a 2nd order polynomial to each set of data we find


$$\Delta p = -1.51 \times 10^{-6} Q^2 + 2.37 \times 10^{-4} Q + 0.0680$$

$$\eta = -3.37 \times 10^{-5} Q^2 + 0.0109 Q - 0.0151$$

Finally, we use Solver to maximize  $\eta$  by varying  $Q$ :

$Q$ (ft <sup>3</sup> /s)	$\Delta p$ (psi)	$\mathcal{P}_m$ (hp)	$\mathcal{P}_h$ (hp)	$\eta$ (%)
106	0.075	2.75	2.08	75.7%
141	0.073	3.18	2.69	84.7%
176	0.064	3.50	2.95	84.3%
211	0.050	3.51	2.76	78.7%
246	0.033	3.50	2.13	60.7%
282	0.016	3.22	1.18	36.7%

$Q$ (ft <sup>3</sup> /s)	$\Delta p$ (psi)	$\eta$ (%)
161.72	0.0668	86.6%



## Problem 10.85

[Difficulty: 3]

**10.85** Using the fan of Problem 10.84, determine the minimum size square sheet-metal duct that will carry a flow of 200 ft<sup>3</sup>/s over a distance of 50 ft. Estimate the increase in delivery if the fan speed is increased to 1000 rpm.

**Given:** Data on centrifugal fan and square metal duct

**Find:** Minimum duct geometry for flow required; Increase if fan speed is increased

**Solution:**

Basic equations:  $\eta_p = \frac{W_h}{W_m}$        $W_h = Q \cdot \Delta p$        $\Delta p = \rho_w \cdot g \cdot \Delta h$       (Note: Software cannot render a dot!)

and for the duct  $\Delta p = \rho_{air} \cdot f \cdot \frac{L}{D_h} \cdot \frac{V^2}{2}$        $D_h = \frac{4 \cdot A}{P} = \frac{4 \cdot H^2}{4 \cdot H} = H$

and fan scaling  $Q = 200 \cdot \frac{ft^3}{s}$        $\omega = 750 \cdot rpm$        $\omega' = 1000 \cdot rpm$        $Q' = \frac{\omega'}{\omega} \cdot Q$        $Q' = 266.67 \cdot \frac{ft^3}{s}$

Here are the results, calculated using *Excel*:

$\rho_w = 1.94 \text{ slug/ft}^3$

$\rho_{air} = 0.00237 \text{ slug/ft}^3$

$v_{air} = 1.58E-04 \text{ ft}^2/s$

$L = 50 \text{ ft}$

Assume smooth ducting

**Note: Efficiency curve not needed for this problem.**

**We use the data to get a relationship for pressure increase.**

$Q$ (ft <sup>3</sup> /s)	$\Delta p$ (psi)	$\mathcal{P}_m$ (hp)	$\mathcal{P}_h$ (hp)	$\eta$ (%)
106	0.075	2.75	2.08	75.7%
141	0.073	3.18	2.69	84.7%
176	0.064	3.50	2.95	84.3%
211	0.050	3.51	2.76	78.7%
246	0.033	3.50	2.13	60.7%
282	0.016	3.22	1.18	36.7%

Fitting a 2nd order polynomial to each set of data we find

$\Delta p = -1.51 \times 10^{-6} Q^2 + 2.37 \times 10^{-4} Q + 0.0680$

Now we need to match the pressure loss in the duct with the pressure rise across the fan. To do this, we use

Solver to vary  $H$  so the error in  $\delta p$  is zero

Fan	
$Q$ (ft <sup>3</sup> /s)	$\Delta p$ (psi)
266.67	0.0238

Duct				
$H$ (ft)	$V$ (ft/s)	$Re$	$f$	$\Delta p$ (psi)
1.703	91.94	9.91.E+05	0.0117	0.0238

Error in  $\Delta p$  = 0.00%


**Answers:**

$Q$ (ft <sup>3</sup> /s)	$H$ (ft)
200.00	1.284

$Q$ (ft <sup>3</sup> /s)	$H$ (ft)
266.67	1.703

A plot of the performance curve is shown on the next page.

### Fan Performance Curve



## Problem 10.86

[Difficulty: 3]

**10.86** The performance data of Problem 10.84 are for a 36-in.-diameter fan wheel. The fan also is manufactured with 42-, 48-, 54-, and 60-in. diameter wheels. Pick a standard fan to deliver 600 ft<sup>3</sup>/s against a 1-in. H<sub>2</sub>O static pressure rise. Determine the required fan speed and input power required.

**Given:** Data on centrifugal fan and various sizes

**Find:** Suitable fan; Fan speed and input power

**Solution:**

Basic equations: 
$$\frac{Q'}{Q} = \left(\frac{\omega'}{\omega}\right) \cdot \left(\frac{D'}{D}\right)^3 \quad \frac{h'}{h} = \left(\frac{\omega'}{\omega}\right)^2 \cdot \left(\frac{D'}{D}\right)^2 \quad \frac{P'}{P} = \left(\frac{\omega'}{\omega}\right)^3 \cdot \left(\frac{D'}{D}\right)^5$$

We choose data from the middle of the table above as being in the region of the best efficiency

$$Q = 176 \cdot \frac{\text{ft}^3}{\text{s}} \quad \Delta p = 0.064 \cdot \text{psi} \quad P = 3.50 \cdot \text{hp} \quad \text{and} \quad \omega = 750 \cdot \text{rpm} \quad D = 3 \cdot \text{ft} \quad \rho_w = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$$

The flow and head are  $Q' = 600 \cdot \frac{\text{ft}^3}{\text{s}}$   $h' = 1 \cdot \text{in}$  At best efficiency point:  $h = \frac{\Delta p}{\rho_w \cdot g} = 1.772 \cdot \text{in}$

These equations are the scaling laws for scaling from the table data to the new fan. Solving for scaled fan speed, and diameter using the first two equations

$$\omega' = \omega \cdot \left(\frac{Q}{Q'}\right)^{\frac{1}{2}} \cdot \left(\frac{h'}{h}\right)^{\frac{3}{4}} \quad \omega' = 265 \cdot \text{rpm} \quad D' = D \cdot \left(\frac{Q'}{Q}\right)^{\frac{1}{2}} \cdot \left(\frac{h}{h'}\right)^{\frac{1}{4}} \quad D' = 76.69 \cdot \text{in}$$

This size is too large; choose (by trial and error)

$$Q = 246 \cdot \frac{\text{ft}^3}{\text{s}} \quad h = \frac{0.033 \cdot \text{psi}}{\rho_w \cdot g} = 0.914 \cdot \text{in} \quad P = 3.50 \cdot \text{hp}$$

$$\omega' = \omega \cdot \left(\frac{Q}{Q'}\right)^{\frac{1}{2}} \cdot \left(\frac{h'}{h}\right)^{\frac{3}{4}} \quad \omega' = 514 \cdot \text{rpm} \quad D' = D \cdot \left(\frac{Q'}{Q}\right)^{\frac{1}{2}} \cdot \left(\frac{h}{h'}\right)^{\frac{1}{4}} \quad D' = 54.967 \cdot \text{in}$$

Hence it looks like the 54-inch fan will work; it must run at about 500 rpm. Note that it will NOT be running at best efficiency. The power will be

$$P' = P \cdot \left(\frac{\omega'}{\omega}\right)^3 \cdot \left(\frac{D'}{D}\right)^5 \quad P' = 9.34 \cdot \text{hp}$$

## Problem 10.87

[Difficulty: 3]

**10.87** Consider the fan and performance data of Problem 10.84. At  $Q = 200 \text{ ft}^3/\text{s}$ , the dynamic pressure is equal to 0.25 in. of water. Evaluate the fan outlet area. Plot total pressure rise and input horsepower for this fan versus volume flow rate. Calculate the fan total efficiency, and show the curve on the plot. Find the best efficiency point, and specify the fan rating at this point.

**Given:** Data on centrifugal fan

**Find:** Fan outlet area; Plot total pressure rise and power; Best efficiency point

**Solution:**

Basic equations:  $\eta_p = \frac{W_h}{W_m}$        $W_h = Q \cdot \Delta p_t$        $\Delta p = \rho_w \cdot g \cdot \Delta h_t$       (Note: Software cannot render a dot!)

$$p_{\text{dyn}} = \frac{1}{2} \cdot \rho_{\text{air}} \cdot V^2$$

At  $Q = 200 \cdot \frac{\text{ft}^3}{\text{s}}$  we have  $h_{\text{dyn}} = 0.25 \text{ in}$        $Q = V \cdot A$       and       $h_{\text{dyn}} = \frac{p_{\text{dyn}}}{\rho_w \cdot g} = \frac{\rho_{\text{air}}}{\rho_w} \cdot \frac{V^2}{2}$

Hence  $V = \sqrt{\frac{\rho_w}{\rho_{\text{air}}} \cdot 2 \cdot g \cdot h_{\text{dyn}}}$       and       $A = \frac{Q}{V}$

The velocity  $V$  is directly proportional to  $Q$ , so the dynamic pressure at any flow rate  $Q$  is  $h_{\text{dyn}} = 0.25 \cdot \text{in} \cdot \left( \frac{Q}{200 \cdot \frac{\text{ft}^3}{\text{s}}} \right)^2$

The total pressure  $\Delta h_t$  will then be  $\Delta h_t = \Delta h + h_{\text{dyn}}$        $\Delta h$  is the tabulated static pressure rise

Here are the results, generated in *Excel*:

At  $Q = 200 \text{ ft}^3/\text{s}$   
 $h_{\text{dyn}} = 0.25 \text{ in}$       Hence       $V = 33.13 \text{ ft/s}$   
 $A = 6.03749 \text{ ft}^2$

$\rho_w = 1.94 \text{ slug/ft}^3$        $\rho_{\text{air}} = 0.00237 \text{ slug/ft}^3$       Fitting a 2nd order polynomial to each set of data we find

$$h_t = -3.56 \times 10^{-5} Q^2 + 6.57 \times 10^{-3} Q + 1.883$$

$$\mathcal{P}_h = -1.285 \times 10^{-4} Q^2 + 0.0517 Q - 1.871$$

$$\eta = -3.37 \times 10^{-5} Q^2 + 0.0109 Q - 0.0151$$


$Q \text{ (ft}^3/\text{s)}$	$\Delta p \text{ (psi)}$	$\mathcal{P}_m \text{ (hp)}$	$h_{\text{dyn}} \text{ (in)}$	$h_t \text{ (in)}$	$\mathcal{P}_h \text{ (hp)}$	$\eta \text{ (\%)}$
106	0.075	2.75	0.07	2.15	2.15	78.2%
141	0.073	3.18	0.12	2.15	2.86	90.0%
176	0.064	3.50	0.19	1.97	3.27	93.5%
211	0.050	3.51	0.28	1.66	3.32	94.5%
246	0.033	3.50	0.38	1.29	3.01	85.9%
282	0.016	3.22	0.50	0.94	2.51	77.9%

Finally, we use Solver to maximize  $\eta$  by varying  $Q$ :

$Q \text{ (ft}^3/\text{s)}$	$h_t \text{ (in)}$	$\mathcal{P}_h \text{ (hp)}$	$\eta \text{ (\%)}$
161.72	2.01	3.13	86.6%

A plot of the performance curves is shown on the next page.


### Fan Performance Curve



# Problem 10.88

[Difficulty: 4]

**10.88** Performance characteristics of a Howden Buffalo axial flow fan are presented below. The fan is used to power a wind tunnel with 1-ft square test section. The tunnel consists of a smooth inlet contraction, two screens (each with loss coefficient  $K=0.12$ ), the test section, and a diffuser where the cross section is expanded to 24 in. diameter at the fan inlet. Flow from the fan is discharged back to the room. Calculate and plot the system characteristic curve of pressure loss versus volume flow rate. Estimate the maximum air flow speed available in this wind tunnel test section.



Solution: Apply energy

Computing equation:  $\frac{p_0}{\rho} + \frac{V_0^2}{2} + g z_0 \approx 0 \approx (2) = \frac{p_1}{\rho} + \alpha \frac{V_1^2}{2} + g z_1 + h_{LT}; h_{LT} = \left[ f \left( \frac{L}{D} + \frac{L_e}{D} \right) + K \right] \frac{V^2}{2}$

Assumptions: (1)  $p_0 = p_{atm}$ , (2)  $V_0 \approx 0$ ,  $\alpha \approx 1$ , (3)  $z_0 = z_1$ , (4) Losses in diffuser, screens

$$\frac{\Delta p_{fan}}{\rho} = \frac{p_{atm} - p_1}{\rho} = \frac{V_1^2}{2} + h_{LT} = \frac{V^2}{2} + (2K_{screen} + K_{diffuser}) \frac{V^2}{2} = [2K_s + K_d + \left(\frac{A}{A_1}\right)^2] \frac{Q^2}{2A^2}$$

From continuity,  $V_1 A_1 = V A$ ;  $V_1^2 = V^2 \left(\frac{A}{A_1}\right)^2$ ;  $V = \frac{Q}{A}$ ;  $V^2 = \frac{Q^2}{A^2}$ ;  $A = 1 \text{ ft}^2$ ;  $A_1 = \frac{\pi}{4} D_1^2 = 3.14 \text{ ft}^2$

From Fig. 8.19,  $K_d = C_{pi} - C_p = 1 - \left(\frac{A}{A_1}\right)^2 = 1 - \left(\frac{1}{3.14}\right)^2 = 0.199$

$$\Delta p_{fan} = [2(0.12) + 0.199 + 0.101] \frac{1}{2} \times \frac{Q^2}{\text{min}^2} \times \frac{1}{(1)^2 \text{ft}^4} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times \frac{16 \text{ft} \cdot \text{s}^2}{\text{min}^2} \times \frac{\text{min}^2}{3600 \text{ s}^2}$$

$$\Delta h_{fan} = \frac{\Delta p}{\rho g} = 1.79 \times 10^{-7} [Q(\text{cfm})^2] \frac{16 \text{ft}}{\text{ft}^3} \times \frac{\text{ft}^3}{62.4 \text{ lbf}} \times \frac{12 \text{ in.}}{\text{ft}} = 3.43 \times 10^{-8} [Q(\text{cfm})^2]$$

The resulting curve is plotted above; computed values are tabulated below.

The system will operate where the fan curve and system curve cross. The approximate operating point is  $Q = 7400 \text{ cfm}$  at  $h = 1.9 \text{ in. H}_2\text{O}$ .

The test section speed is

$$V = \frac{Q}{A} = \frac{7400 \text{ ft}^3}{\text{min}} \times \frac{1}{1 \text{ ft}^2} \times \frac{\text{min}}{60 \text{ s}} = 123 \text{ ft/s}$$

Q (1000 cfm)	1	2	3	4	5	6	7	8	9	10
$\Delta p$ (in. H <sub>2</sub> O)	0.03	0.14	0.31	0.55	0.86	1.24	1.68	2.20	2.78	3.43

## Problem 10.89

[Difficulty: 4]

**10.89** Consider again the axial-flow fan and wind tunnel of Problem 10.88. Scale the performance of the fan as it varies with operating speed. Develop and plot a "calibration curve" showing test section flow speed (in m/s) versus fan speed (in rpm).


Solution: From the solution to Problem 10.88,  $\Delta h_{fan} \propto Q^2 \propto V^2$

The scaling laws for varying fan speed suggest  $Q \propto \omega$  and  $p \propto \omega^2$ .

Thus  $\Delta h_{fan} \propto Q^2 \propto p \propto \omega^2$  or  $Q \propto \omega$ . The volume flow rate (and the test section flow speed) should vary directly with  $\omega$ .

From the results of Problem 10.88,  $V = 123 \text{ ft/s}$  when  $N = 1835 \text{ rpm}$ .

Plotting:



The slope of the linear relationship is  $\frac{V}{N} = 123 \frac{\text{ft}}{\text{s}} \times \frac{1}{1835 \text{ rpm}} = 0.0670 \text{ ft/s/rpm}$ .

Thus  $V(\text{ft/s}) = 0.0670 N(\text{rpm})$

V

# Problem 10.90

[Difficulty: 3]


10.90 Experimental test data for an aircraft engine fuel pump are presented below. This gear pump is required to supply jet fuel at 450 pounds per hour and 150 psig to the engine fuel controller. Tests were conducted at 10, 96, and 100 percent of the rated pump speed of 4536 rpm. At each constant speed, the back pressure on the pump was set, and the flow rate measured. On one graph, plot curves of pressure versus delivery at the three constant speeds. Estimate the pump displacement volume per revolution. Calculate the volumetric efficiency at each test point and sketch contours of constant  $\eta_v$ . Evaluate the energy loss caused by valve throttling at 100 percent speed and full delivery to the engine.

Pump Speed (rpm)	Back Pressure (psig)	Fuel Flow (pph*)	Pump Speed (rpm)	Back Pressure (psig)	Fuel Flow (pph)	Pump Speed (rpm)	Back Pressure (psig)	Fuel Flow (pph)
	200	1810		200	1730		200	89
4536 (100%)	300	1810	4355 (96%)	300	1750	453 (10%)	250	73
	400	1810		400	1735		300	58.5
	500	1790		500	1720		350	45
	900	1720		900	1635		400	30

\* Fuel flow rate measured in pounds per hour (pph).

Solution:

Back Pressure,  $p$  (psig)



For the pump,  $\dot{m} = \rho \dot{V} N$ , so  $\dot{V} = \frac{\dot{m}}{\rho N}$ . Analyzing the 4536 rpm case,

$$\dot{V} \approx \frac{1810 \text{ lbm}}{\text{hr}} \times \frac{\text{gal}}{6.8 \text{ lbm}} \times \frac{\text{min}}{4536 \text{ rev}} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{1728 \text{ in}^3}{\text{ft}^3} \times \frac{\text{hr}}{60 \text{ min}} = 0.226 \text{ in}^3/\text{rev}$$

At constant speed,  $\eta_v = \frac{\dot{V}_{\text{actual}}}{\dot{V}_{\text{geometric}}} = \frac{\dot{m}}{\dot{m}(p=0)}$ . Calculation shows  $\eta_v$

decreases as speed is reduced, see below.

$$\text{Energy loss is } \dot{W}_L = \left( \frac{\dot{m}_p - \dot{m}_L}{\rho} \right) p_L = \frac{(1810 - 450) \text{ lbm}}{\text{hr}} \times \frac{\text{gal}}{6.8 \text{ lbm}} \times \frac{150 \text{ lbf}}{\text{in}^2} \times \frac{\text{ft}^3}{7.48 \text{ gal}} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lbf}} \times \frac{\text{hr}}{3600 \text{ s}}$$

$$\dot{W}_L = 0.292 \text{ hp}$$

At 453 rpm, the best volumetric efficiency is

$$\eta_v \approx \frac{\dot{m}}{\dot{m}(p=0)} \times \frac{4536}{453} \approx \frac{89 \text{ pph}}{1810 \text{ pph}} \times \frac{4536}{453} = 0.0492, \text{ or about } 5\%$$

At 4355 rpm,

$$\eta_v \approx \frac{1730 \text{ pph}}{1810 \text{ pph}} \times \frac{4536}{4355} = 0.996, \text{ or more than } 99\% \text{ (this is doubtful).}$$

## Problem 10.91

[Difficulty: 3]

**10.91** A hydraulic turbine is designed to produce 36,000 hp at 95 rpm under 50 ft of head. Laboratory facilities are available to provide 15 ft of head and to absorb 50 hp from the model turbine. Determine (a) the appropriate model test speed and scale ratio and (b) volume flow rate, assuming a model efficiency of 86 percent.

**Given:** Data on turbine system

**Find:** Model test speed; Scale; Volume flow rate

**Solution:**

Basic equations:  $W_h = \rho \cdot Q \cdot g \cdot H$        $\eta = \frac{W_{\text{mech}}}{W_h}$        $N_S = \frac{\omega \cdot P^{\frac{1}{2}}}{\rho^{\frac{1}{2}} \cdot h^{\frac{5}{4}}}$

The given or available data is

$$\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3} \quad W_p = 36000 \cdot \text{hp} \quad H_p = 50 \cdot \text{ft} \quad \omega_p = 95 \cdot \text{rpm} \quad H_m = 15 \cdot \text{ft} \quad W_m = 50 \cdot \text{hp}$$

where sub p stands for prototype and sub m stands for model

Note that we need h (energy/mass), not H (energy/weight)  $h_p = H_p \cdot g$      $h_p = 1609 \cdot \frac{\text{ft}^2}{\text{s}^2}$      $h_m = H_m \cdot g$      $h_m = 482.6 \cdot \frac{\text{ft}^2}{\text{s}^2}$

Hence for the prototype  $N_S = \frac{\omega_p \cdot W_p^{\frac{1}{2}}}{\rho^{\frac{1}{2}} \cdot h_p^{\frac{5}{4}}}$        $N_S = 3.12$


Then for the model  $N_S = \frac{\omega_m \cdot W_m^{\frac{1}{2}}}{\rho^{\frac{1}{2}} \cdot h_m^{\frac{5}{4}}}$        $\omega_m = N_S \cdot \frac{\rho^{\frac{1}{2}} \cdot h_m^{\frac{5}{4}}}{W_m^{\frac{1}{2}}}$        $\omega_m = 59.3 \cdot \frac{\text{rad}}{\text{s}}$      $\omega_m = 566 \cdot \text{rpm}$

For dynamically similar conditions  $\frac{H_p}{\omega_p^2 \cdot D_p^2} = \frac{H_m}{\omega_m^2 \cdot D_m^2}$     so     $\frac{D_m}{D_p} = \frac{\omega_p}{\omega_m} \cdot \sqrt{\frac{H_m}{H_p}} = 0.092$

Also  $\frac{Q_p}{\omega_p \cdot D_p^3} = \frac{Q_m}{\omega_m \cdot D_m^3}$     so     $Q_m = Q_p \cdot \frac{\omega_m}{\omega_p} \cdot \left(\frac{D_m}{D_p}\right)^3$

To find  $Q_p$  we need efficiency. At  $W_p = 36000 \cdot \text{hp}$  and  $H_p = 50 \cdot \text{ft}$  from Fig. 10.17 we find (see below), for

$$N_{Scu} = \frac{N(\text{rpm}) \cdot P(\text{hp})^{\frac{1}{2}}}{H(\text{ft})^{\frac{5}{4}}} = 135.57 \quad \eta = 93\%$$



Hence from

$$\eta = \frac{W_{\text{mech}}}{W_h} = \frac{W_{\text{mech}}}{\rho \cdot Q \cdot g \cdot H}$$

$$Q_p = \frac{W_p}{\rho \cdot g \cdot H_p \cdot \eta}$$

$$Q_p = 3.06 \times 10^6 \cdot \text{gpm}$$

and also

$$Q_m = \frac{W_m}{\rho \cdot g \cdot H_m \cdot \eta}$$

$$Q_m = 1.418 \times 10^4 \cdot \text{gpm}$$

## Problem 10.92

[Difficulty: 2]

**10.92** Preliminary calculations for a hydroelectric power generation site show a net head of 2350 ft is available at a water flow rate of 75 ft<sup>3</sup>/s. Compare the geometry and efficiency of Pelton wheels designed to run at (a) 450 rpm and (b) 600 rpm.

Solution: Apply specific speed equation to classify performance.

Computing equation:  $N_{scu} = \frac{N \rho^{1/2}}{H^{5/4}}$  (rpm, hp, and ft units)

From Fig. 10.17,  $\eta_{max} \approx 0.89$  at  $N_{scu} = 5$ . The output power (used to define  $N_{scu}$ ) is

$$P_{out} = \eta \rho Q g H = 0.89 \times 62.4 \frac{\text{lb}}{\text{ft}^3} \times 75 \frac{\text{ft}^3}{\text{s}} \times 2350 \text{ ft} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lb}} = 17,800 \text{ hp}$$

At  $N = 450$  rpm

$$N_{scu} = \frac{450 \text{ rpm} (17,800 \text{ hp})^{1/2}}{(2350)^{5/4}} = 3.67, \text{ so } \eta \approx 0.88$$

Neglect nozzle losses and elevation above the tailrace. Then

$$V_j \approx \sqrt{2gH} = \left[ 2 \times 32.2 \frac{\text{ft}}{\text{s}^2} \times 2350 \text{ ft} \right]^{1/2} = 389 \text{ ft/s}$$

From Fig. 10.10,  $U = R\omega \approx 0.47 V_j = 183 \text{ ft/s}$ . Thus

$$D = 2R = \frac{2(0.47 V_j)}{\omega} = 2 \times 183 \frac{\text{ft}}{\text{s}} \times \frac{\text{s}}{47.1 \text{ rad}} = 7.77 \text{ ft}$$

The jet diameter is found from  $Q = V_j A_j = \pi V_j D_j^2 / 4$ , so

$$D_j = \sqrt{\frac{4Q}{\pi V_j}} = \left[ \frac{4}{\pi} \times \frac{75 \text{ ft}^3/\text{s}}{389 \text{ ft}} \right]^{1/2} = 0.495 \text{ ft} \text{ (5.95 in.)}$$

The ratio of jet diameter to wheel diameter is

$$r = \frac{D_j}{D} = \frac{0.495 \text{ ft}}{7.77 \text{ ft}} = 0.0637 \text{ or } 1:15.7 \text{ (this is reasonable)}$$

Results from similar computations at  $N = 600$  rpm are:


N (rpm)	$N_{scu}$ (USCS)	D (ft)	$D_j/D$ (---)	$\eta$ (---)
450	3.67	7.77	1:15.7	0.88
600	4.89	5.83	1:11.8	0.89

The unit operating at 600 rpm is closer to  $N_{scu} = 5$ , where peak hydraulic efficiency is expected.

## Problem 10.93

[Difficulty: 2]

**10.93** Conditions at the inlet to the nozzle of a Pelton wheel are  $p=700$  psig and  $V=15$  mph. The jet diameter is  $d=7.5$  in, and the nozzle loss coefficient is  $K_{\text{nozzle}}=0.04$ . The wheel diameter is  $D=8$  ft. At this operating condition,  $\eta=0.86$ . Calculate (a) the power output, (b) the normal operating speed, (c) the approximate runaway speed, (d) the torque at normal operating speed, and (e) the approximate torque at zero speed.



**Given:** Pelton turbine

**Find:** 1) Power 2) Operating speed 3) Runaway speed 4) Torque 5) Torque at zero speed

**Solution:**

Basic equations 
$$\left( \frac{p_1}{\rho \cdot g} + \alpha \cdot \frac{V_1^2}{2 \cdot g} + z_1 \right) - \left( \frac{p_j}{\rho \cdot g} + \alpha \cdot \frac{V_j^2}{2 \cdot g} + z_j \right) = \frac{h_{IT}}{g}$$
 
$$h_{IT} = h_l + h_{lm} = K \cdot \frac{V^2}{2}$$

and from Example 10.5 
$$T_{\text{ideal}} = \rho \cdot Q \cdot R \cdot (V_j - U) \cdot (1 - \cos(\theta)) \quad \theta = 165 \cdot \text{deg}$$

Assumptions: 1)  $p_j = p_{\text{amt}}$  2) Incompressible flow 3)  $\alpha$  at 1 and j is approximately 1 4) Only minor loss at nozzle 5)  $z_1 = z_j$

Given data 
$$p_{1g} = 700 \cdot \text{psi} \quad V_1 = 15 \cdot \text{mph} \quad V_1 = 22 \cdot \frac{\text{ft}}{\text{s}} \quad \eta = 86\%$$

$$d = 7.5 \cdot \text{in} \quad D = 8 \cdot \text{ft} \quad R = \frac{D}{2} \quad K = 0.04 \quad \rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$$

Then 
$$\frac{p_{1g}}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} - \frac{V_j^2}{2 \cdot g} = \frac{K}{g} \cdot \frac{V_j^2}{2}$$
 or 
$$V_j = \sqrt{\frac{2 \cdot \left( \frac{p_{1g}}{\rho} + \frac{V_1^2}{2} \right)}{1 + K}} \quad V_j = 317 \cdot \frac{\text{ft}}{\text{s}}$$

and 
$$Q = V_j \cdot \frac{\pi \cdot d^2}{4} \quad Q = 97.2 \cdot \frac{\text{ft}^3}{\text{s}} \quad H = \frac{p_{1g}}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} \quad H = 1622 \cdot \text{ft}$$

Hence 
$$P = \eta \cdot \rho \cdot Q \cdot g \cdot H \quad P = 15392 \cdot \text{hp}$$

From Fig. 10.10, normal operating speed is around  $U = 0.47 \cdot V_j$  
$$U = 149 \cdot \frac{\text{ft}}{\text{s}} \quad \omega = \frac{U}{R} \quad \omega = 37.2 \cdot \frac{\text{rad}}{\text{s}} \quad \omega = 356 \cdot \text{rpm}$$

At runaway 
$$U_{\text{run}} = V_j \quad \omega_{\text{run}} = \frac{U_{\text{run}}}{\left( \frac{D}{2} \right)} \quad \omega_{\text{run}} = 79.2 \cdot \frac{\text{rad}}{\text{s}} \quad \omega_{\text{run}} = 756 \cdot \text{rpm}$$

From Example 10.5 
$$T_{\text{ideal}} = \rho \cdot Q \cdot R \cdot (V_j - U) \cdot (1 - \cos(\theta)) \quad T_{\text{ideal}} = 2.49 \times 10^5 \cdot \text{ft} \cdot \text{lbf}$$

Hence 
$$T = \eta \cdot T_{\text{ideal}} \quad T = 2.14 \times 10^5 \cdot \text{ft} \cdot \text{lbf}$$

Stall occurs when 
$$U = 0 \quad T_{\text{stall}} = \eta \cdot \rho \cdot Q \cdot R \cdot V_j \cdot (1 - \cos(\theta)) \quad T_{\text{stall}} = 4.04 \times 10^5 \cdot \text{ft} \cdot \text{lbf}$$

## Problem 10.94

[Difficulty: 2]

**10.94** The reaction turbines at Niagara Falls are of the Francis type. The impeller outside diameter is 4.5 m. Each turbine produces 54 MW at 107 rpm, with 93.8 percent efficiency under 65 m of net head. Calculate the specific speed of these units. Evaluate the volume flow rate to each turbine. Estimate the penstock size if it is 400 m long and the net head is 83 percent of the gross head.

**Given:** Data on Francis turbines at Niagra Falls

**Find:** Specific speed, volume flow rate to each turbine, penstock size

**Solution:**

Basic equations:  $W_h = \rho \cdot Q \cdot g \cdot H$        $\eta = \frac{W_{\text{mech}}}{W_h}$        $N_S = \frac{\omega \cdot P^{\frac{1}{2}}}{\rho^{\frac{1}{2}} \cdot h^{\frac{5}{4}}}$        $h = g \cdot H$        $h_{IT} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2}$

The given or available data is

$\rho = 998 \cdot \frac{\text{kg}}{\text{m}^3}$      $W_{\text{mech}} = 54 \cdot \text{MW}$      $\omega = 107 \cdot \text{rpm}$      $\eta = 93.8\%$      $H = 65 \cdot \text{m}$      $L_{\text{penstock}} = 400 \cdot \text{m}$      $H_{\text{net}} = H \cdot 83\%$

The specific energy of the turbine is:  $h = g \cdot H = 637.4 \frac{\text{m}^2}{\text{s}^2}$     The specific speed is:  $N_S = \frac{\omega \cdot W_{\text{mech}}^{\frac{1}{2}}}{\rho^{\frac{1}{2}} \cdot h^{\frac{5}{4}}}$      $N_S = 0.814$

Solving for the flow rate of the turbine:  $Q = \frac{W_{\text{mech}}}{\rho \cdot h \cdot \eta} = 90.495 \frac{\text{m}^3}{\text{s}}$      $Q = 90.5 \frac{\text{m}^3}{\text{s}}$

Based on the head loss:  $h_{IT} = g \cdot (H - H_{\text{net}}) = 108.363 \frac{\text{m}^2}{\text{s}^2}$     Since  $V = \frac{Q}{A} = \frac{4 \cdot Q}{\pi \cdot D^2}$  into the head loss equation:

$h_{IT} = f \cdot \frac{L}{D} \cdot \frac{1}{2} \cdot \left( \frac{4 \cdot Q}{\pi \cdot D^2} \right)^2 = \frac{8}{\pi^2} \cdot \frac{f \cdot L \cdot Q^2}{D^5}$     Solving for the diameter:  $D = \left( \frac{8 \cdot f \cdot L \cdot Q^2}{\pi^2 \cdot h_{IT}} \right)^{\frac{1}{5}}$     This will require an iterative solution.

Assuming concrete-lined penstocks:  $e = 3 \cdot \text{mm}$     If we assume a diameter of 2 m, we can iterate to find the actual diameter:

$D$ (m)	$V$ (m/s)	Re	$e/D$	$f$	$D$ (m)
2.000	28.807	5.70E+07	0.001500	0.02173	3.510
3.510	9.354	3.25E+07	0.000855	0.01892	3.414
3.414	9.888	3.34E+07	0.000879	0.01904	3.418
3.418	9.862	3.34E+07	0.000878	0.01904	3.418

$D = 3.42 \cdot \text{m}$

## Problem 10.95

[Difficulty: 2]

**10.95** Francis turbine Units 19, 20, and 21, installed at the Grand Coulee Dam on the Columbia River, are very large [55]. Each runner is 32.6 ft in diameter and contains 550 tons of cast steel. At rated conditions, each turbine develops 820,000 hp at 72 rpm under 285 ft of head. Efficiency is nearly 95 percent at rated conditions. The turbines operate at heads from 220 to 355 ft. Calculate the specific speed at rated operating conditions. Estimate the maximum water flow rate through each turbine.

Solution: Apply definitions of specific speed and efficiency.

Computing equations:  $N_{s_{cu}} = \frac{N \Omega^{1/2}}{H^{5/4}} \quad \eta = \frac{P}{\rho g Q H}$

Thus 
$$N_{s_{cu}} = \frac{72 \text{ rpm} (820,000 \text{ hp})^{1/2}}{(285 \text{ ft})^{5/4}} = 55.7$$

From  $\eta$ ,

$$Q = \frac{P}{\eta \rho g H}$$

so  $Q$  is maximum at minimum head. Assuming  $\eta = 0.95$ , the

$$Q \approx \frac{1}{0.95} \times 820,000 \text{ hp} \times \frac{\text{ft}^3}{62.4 \text{ lb/ft}^3} \times \frac{1}{220 \text{ ft}} \times \frac{550 \text{ ft} \cdot \text{lb/ft}^3}{\text{hp} \cdot \text{s}} = 34,600 \text{ ft}^3/\text{s} \quad (\text{max})$$

{ This is an estimate because  $\eta$  may not be constant, nor may it be possible to develop full power at  $H = 220 \text{ ft}$ . }

# Problem 10.96

[Difficulty: 3]

**10.96** Measured data for performance of the reaction turbines at Shasta Dam near Redding, California, are shown in Fig. 10.39. Each turbine is rated at 103,000 hp when operating at 138.6 rpm under a net head of 380 ft. Evaluate the specific speed and compute the shaft torque developed by each turbine at rated operating conditions. Calculate and plot the water flow rate per turbine required to produce rated output power as a function of head.

Solution: Apply the definitions of specific speed and efficiency, use data from Fig. 10.39:

Computing equations:  $N_{s_{cu}} = \frac{N \rho^{\frac{1}{2}}}{H^{\frac{5}{4}}}$       $\eta = \frac{P}{\rho g Q H}$       $P = \omega T$

At rated conditions,  $N_{s_{cu}} = \frac{(138.6 \text{ rpm})(103,000 \text{ hp})^{\frac{1}{2}}}{(380 \text{ ft})^{\frac{5}{4}}} = 26.5$

$T = \frac{P}{\omega} = 103,000 \text{ hp} \times \frac{5}{14.5 \text{ rad}} \times \frac{550 \text{ ft} \cdot \text{lb}}{\text{hp} \cdot \text{s}} = 3.91 \times 10^6 \text{ ft} \cdot \text{lb}$

Find  $Q$  from definition of  $\eta$ ; at rated conditions,  $\eta \approx 0.93$  (Fig. 10.39):


$Q = \frac{P}{\eta \rho g H} = \frac{1}{0.93} \times 103,000 \text{ hp} \times \frac{\text{ft}^3}{62.4 \text{ lb}} \times \frac{1}{380 \text{ ft}} \times \frac{550 \text{ ft} \cdot \text{lb}}{\text{hp} \cdot \text{s}} = 2570 \text{ ft}^3/\text{s}$

Tabulating similar calculations:

H (ft)	P (hp)	$\eta$ (---)	Q (ft <sup>3</sup> /s)
238	*	-	-
280	*	-	-
330	103,000	0.86	3200
380	103,000	0.93	2570
430	103,000	0.90	2350
475	103,000	0.87	2200

\* cannot produce rated power at this head

Plotting:



## Problem 10.97

[Difficulty: 3]

**10.97** Figure 10.37 contains data for the efficiency of a large Pelton waterwheel installed in the Tiger Creek Power House of Pacific Gas & Electric Company near Jackson, California. This unit is rated at 26.8 MW when operated at 225 rpm under a net head of 360 m of water. Assume reasonable flow angles and nozzle loss coefficient, and water at 15°C. Determine the rotor radius, and estimate the jet diameter and the mass flow rate of water.

**Given:** Data on Pelton wheel

**Find:** Rotor radius, jet diameter, water flow rate.

**Solution:**

The given or available data is

$$\rho = 999 \frac{\text{kg}}{\text{m}^3} \quad W_{\text{mech}} = 26.8 \cdot \text{MW} \quad \omega = 225 \cdot \text{rpm} \quad H = 360 \cdot \text{m} \quad \nu = 1.14 \times 10^{-6} \frac{\text{m}^2}{\text{s}}$$

From Bernoulli, the jet velocity is:  $V_j = \sqrt{2 \cdot g \cdot H}$  Assuming a velocity coefficient of  $C_v = 0.98$  (4% loss in the nozzle):

$V_j = C_v \cdot \sqrt{2 \cdot g \cdot H} = 82.35 \frac{\text{m}}{\text{s}}$  From Fig. 10.36, at maximum efficiency:  $U = R \cdot \omega = 0.47 \cdot V_j$  So the radius can be calculated:

$$R = 0.47 \cdot \frac{V_j}{\omega} = 1.643 \text{m}$$

From Fig. 10.37 the efficiency at full load is  $\eta = 86\%$  Thus:  $\eta = \frac{W_{\text{mech}}}{Q \cdot \rho \cdot g \cdot H}$  Solving for the flow rate:

$$Q = \frac{W_{\text{mech}}}{\eta \cdot \rho \cdot g \cdot H} = 8.836 \frac{\text{m}^3}{\text{s}}$$

We can now calculate the jet velocity:  $A_j = \frac{\pi}{4} \cdot D_j^2 = \frac{Q}{V_j}$  Therefore,  $D_j = 2 \cdot \sqrt{\frac{Q}{\pi \cdot V_j}} = 0.37 \text{m}$   $D_j = 37.0 \cdot \text{cm}$

$$m_{\text{rate}} = \rho \cdot Q = 8.83 \times 10^3 \frac{\text{kg}}{\text{s}}$$

## Problem 10.98

[Difficulty: 3]

**10.98** An impulse turbine is to develop 15 MW from a single wheel at a location where the net head is 350 m. Determine the appropriate speed, wheel diameter, and jet diameter for single- and multiple-jet operation. Compare with a double-overhung wheel installation. Estimate the required water consumption.

**Given:** Impulse turbine requirements

**Find:** 1) Operating speed 2) Wheel diameter 4) Jet diameter 5) Compare to multiple-jet and double-overhung

**Solution:**

Basic equations:  $V_j = \sqrt{2 \cdot g \cdot H}$        $N_S = \frac{\omega \cdot P^{\frac{1}{5}}}{\rho^{\frac{2}{5}} \cdot h^{\frac{4}{5}}}$        $\eta = \frac{P}{\rho \cdot Q \cdot g \cdot H}$        $Q = V_j \cdot A_j$

Model as optimum. This means, from Fig. 10.10  $U = 0.47 \cdot V_j$  and from Fig. 10.17  $N_{Scu} = 5$  with  $\eta = 89\%$

Given or available data  $H = 350 \cdot \text{m}$        $P = 15 \cdot \text{MW}$        $\rho = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$

Then  $V_j = \sqrt{2 \cdot g \cdot H}$        $V_j = 82.9 \frac{\text{m}}{\text{s}}$        $U = 0.47 \cdot V_j$        $U = 38.9 \frac{\text{m}}{\text{s}}$

We need to convert from  $N_{Scu}$  (from Fig. 10.17) to  $N_S$  (see discussion after Eq. 10.18b).  $N_S = \frac{N_{Scu}}{43.46}$        $N_S = 0.115$

The water consumption is  $Q = \frac{P}{\eta \cdot \rho \cdot g \cdot H}$        $Q = 4.91 \frac{\text{m}^3}{\text{s}}$

For a single jet  $\omega = N_S \cdot \frac{\rho^{\frac{1}{2}} \cdot (g \cdot H)^{\frac{5}{4}}}{P^{\frac{1}{2}}}$  (1)       $\omega = 236 \cdot \text{rpm}$        $D_j = \sqrt{\frac{4 \cdot Q}{\pi \cdot V_j}}$  (2)       $D_j = 0.275 \text{ m}$

The wheel radius is  $D = \frac{2 \cdot U}{\omega}$  (3)       $D = 3.16 \text{ m}$

For multiple (n) jets, we use the power and flow per jet

From Eq 1  $\omega_n = \omega \cdot \sqrt{n}$       From Eq. 2  $D_{jn} = \frac{D_j}{\sqrt{n}}$       and  $D_n = \frac{D}{\sqrt{n}}$       from Eq. 3

Results:

n =	$\omega_n(n) =$	$D_{jn}(n) =$	$D_n(n) =$
1	236 ·rpm	0.275 m	3.16 m
2	333	0.194	2.23
3	408	0.159	1.82
4	471	0.137	1.58
5	527	0.123	1.41

A double-hung wheel is equivalent to having a single wheel with two jets

## Problem 10.99

[Difficulty: 2]

**10.99** An impulse turbine under a net head of 33 ft was tested at a variety of speeds. The flow rate and the brake force needed to set the impeller speed were recorded:

Wheel Speed (rpm)	Flow rate (cfm)	Brake Force (lbf) ( $R = 0.5$ ft)
0	7.74	2.63
1000	7.74	2.40
1500	7.74	2.22
1900	7.44	1.91
2200	7.02	1.45
2350	5.64	0.87
2600	4.62	0.34
2700	4.08	0.09

Calculate and plot the machine power output and efficiency as a function of water turbine speed.

**Given:** Data on impulse turbine

**Find:** Plot of power and efficiency curves


**Solution:**

Basic equations:  $T = F \cdot R$      $P = \omega \cdot T$      $\eta = \frac{P}{\rho \cdot Q \cdot g \cdot H}$

Here are the results calculated in *Excel*:

$H = 33$  ft  
 $\rho = 1.94$  slug/ft<sup>3</sup>  
 $R = 0.50$  ft

$\omega$ (rpm)	$Q$ (cfm)	$F$ (lbf)	$T$ (ft-lbf)	$\mathcal{P}$ (hp)	$\eta$ (%)
0	7.74	2.63	1.32	0.000	0.0%
1000	7.74	2.40	1.20	0.228	47.3%
1500	7.74	2.22	1.11	0.317	65.6%
1900	7.44	1.91	0.96	0.345	74.4%
2200	7.02	1.45	0.73	0.304	69.3%
2350	5.64	0.87	0.44	0.195	55.3%
2600	4.62	0.34	0.17	0.084	29.2%
2700	4.08	0.09	0.05	0.023	9.1%



# Problem 10.100

[Difficulty: 4]

**10.100** In U.S. customary units, the common definition of specific speed for a hydraulic turbine is given by Eq. 10.13b. Develop a conversion between this definition and a truly dimensionless one in SI units. Evaluate the specific speed of an impulse turbine, operating at 400 rpm under a net head of 1190 ft with 86 percent efficiency, when supplied by a single 6-in.-diameter jet. Use both U.S. customary and SI units. Estimate the wheel diameter.

Solution: Apply definitions of specific speed and efficiency.

Computing equations:  $N_{s_{cu}} = \frac{N P^{1/2}}{H^{5/4}}$       $\eta = \frac{P}{\rho Q g H}$       $N_s = \frac{\omega P^{1/2}}{\rho^{1/2} g^{3/4} H^{5/4}}$

From dimensional analysis, recall that for pumps,  $N_s = \frac{N Q^{1/2}}{H^{3/4}}$  was dimensionless only when  $H$  is expressed as  $gH$ , energy per unit mass. Thus the dimensions are

$$[N_s] = \left[ \frac{N Q^{1/2}}{(gH)^{3/4}} \right] = \frac{1}{t} \left( \frac{L^3}{t^3} \right)^{1/2} \left( \frac{L^2}{t^2} \right)^{3/4} = \frac{1}{t} \frac{L^{3/2}}{t^{3/2}} \frac{t^{3/2}}{L^{3/2}} = 1 \quad \checkmark$$

To form the  $N_s$  for turbines,  $Q$  must be multiplied by  $\rho g H$  to obtain power. Thus for turbines, the dimensionless specific speed is

$$[N_s] = \left[ \frac{N Q^{1/2}}{(gH)^{3/4}} \times \frac{(\rho g H)^{1/2}}{(\rho g H)^{1/2}} \right] = \left[ \frac{N P^{1/2}}{\rho^{1/2} (gH)^{5/4}} \right] = \frac{1}{t} \left( \frac{FL}{t} \times \frac{ML}{Ft^2} \right)^{1/2} \left( \frac{L^3}{M} \right)^{1/2} \left( \frac{L^2}{t^2} \right)^{5/4} = \frac{M^{1/2} L^{5/2} t^{5/2}}{M^{1/2} L^{5/2} t^{5/2}} = 1 \quad \checkmark$$

The simplest way to convert is to evaluate each specific speed, then take the ratio.

The jet speed will be approximately  $V_j = \sqrt{2gH} = \left[ 2 \times 32.2 \frac{ft}{s^2} \times 1190 ft \right]^{1/2} = 277 ft/s$

and  $Q = V_j \frac{\pi D_j^2}{4} = 277 \frac{ft}{s} \times \frac{\pi}{4} \left( \frac{1}{2} \right)^2 ft^2 = 54.4 ft^3/s$ . Thus

$$P = \eta \rho Q g H = 0.86 \times 62.4 \frac{lb}{ft^3} \times 54.4 \frac{ft^3}{s} \times 1190 ft \times \frac{hp \cdot s}{550 ft \cdot lb} = 6320 hp (4.71 MW)$$

For the wheel,  $U = 0.47 V_j = R\omega$ ;  $R = 3.10 ft$ ;  $D = 6.20 ft$

In U.S. units,  $N_{s_{cu}} = \frac{400 rpm (6320 hp)^{1/2}}{(1190 ft)^{5/4}} = 4.55$

In S.I. units,  $\omega = 41.9 rad/s$  and  $gH = 3560 m^2/s^2$ , so

$$N_s = \frac{\omega P^{1/2}}{\rho^{1/2} (gH)^{5/4}} = \frac{41.9 \frac{rad}{s} (4.71 \times 10^6 W)^{1/2}}{\left( \frac{999 kg}{m^3} \right)^{1/2} \left( \frac{3560 m^2}{s^2} \right)^{5/4}} = 0.105$$

The conversion is  $\frac{N_{s_{cu}}}{N_s} = \frac{4.55}{0.105} = 43.5$

D

$N_s$

$N_s$

Ratio

## Problem 10.101

[Difficulty: 3]

**10.101** According to a spokesperson for Pacific Gas & Electric Company, the Tiger Creek plant, located east of Jackson, California, is one of 71 PG&E hydroelectric powerplants. The plant has 373 m of gross head, consumes 21 m<sup>3</sup>/s of water, is rated at 60 MW, and operates at 58 MW. The plant is claimed to produce 0.785 kW·hr/(m<sup>2</sup>·m) of water and 336.4 × 10<sup>6</sup> kW·hr/yr of operation. Estimate the net head at the site, the turbine specific speed, and its efficiency. Comment on the internal consistency of these data.

**Given:** Published data for the Tiger Creek Power Plant

**Find:** (a) Estimate net head at the site, turbine specific speed, and turbine efficiency  
(b) Comment on consistency of the published data

**Solution:**

Basic Equations: 
$$N_{\text{Scu}} = \frac{N \cdot \sqrt{P}}{\frac{5}{H^4}} \quad N_S = \frac{N \cdot \sqrt{P}}{\sqrt{\rho} \cdot (g \cdot H)^{\frac{5}{4}}} \quad \eta = \frac{P}{\rho \cdot Q \cdot g \cdot H_{\text{net}}}$$

The given or available data is

$$\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3} \quad P = 58 \cdot \text{MW} \quad Q = 21 \cdot \frac{\text{m}^3}{\text{s}} \quad H_{\text{gross}} = 373 \cdot \text{m} \quad \nu = 1.14 \times 10^{-6} \cdot \frac{\text{m}^2}{\text{s}}$$

Using data from Fig. 10.37, we will assume  $\eta = 87\%$ . We can take this to estimate the net head: 
$$H_{\text{net}} = \frac{P}{\rho \cdot Q \cdot g \cdot \eta} = 324 \text{ m}$$

Therefore: 
$$\frac{H_{\text{net}}}{H_{\text{gross}}} = 86.875\%$$
 This is close to 87%, so the assumption for the efficiency was a good one.

From the same figure, we will assume  $N_{\text{Scu}} = 5$ . Therefore the dimensionless specific speed is 
$$N_S = \frac{N_{\text{Scu}}}{43.46} = 0.115$$

We may then calculate the rotational speed for the turbine: 
$$N = \frac{N_S \cdot \sqrt{\rho} \cdot (g \cdot H_{\text{net}})^{\frac{5}{4}}}{\sqrt{P}} = 108.8 \cdot \text{rpm}$$

The power output seems low for a turbine used for electricity generation; several turbines are probably used in this one plant.

To check the claims: 
$$58 \cdot \text{MW} \times \frac{24 \cdot \text{hr}}{1 \cdot \text{day}} \times \frac{365 \cdot \text{day}}{\text{yr}} = 5.081 \times 10^8 \cdot \frac{\text{kW} \cdot \text{hr}}{\text{yr}}$$
 This number is 50% higher than the claim.

$$58 \cdot \text{MW} \times \frac{\text{s}}{21 \cdot \text{m}^3} \times \frac{\text{hr}}{3600 \cdot \text{s}} = 0.767 \cdot \frac{\text{kW} \cdot \text{hr}}{\text{m}^2 \cdot \text{m}}$$
 This is in excellent agreement with the claim.

## Problem 10.102

[Difficulty: 4]

**10.102** Design the piping system to supply a water turbine from a mountain reservoir. The reservoir surface is 320 m above the turbine site. The turbine efficiency is 83 percent, and it must produce 30 kW of mechanical power. Define the minimum standard-size pipe required to supply water to the turbine and the required volume flow rate of water. Discuss the effects of turbine efficiency, pipe roughness, and installing a diffuser at the turbine exit on the performance of the installation.

**Given:** Hydraulic turbine site

**Find:** Minimum pipe size; Flow rate; Discuss

**Solution:**

Basic equations:  $H_l = \frac{h_l}{g} = f \cdot \frac{L}{D} \cdot \frac{V^2}{2 \cdot g}$  and also, from Example 10.15 the optimum is when  $H_l = \frac{\Delta z}{3}$

As in Fig. 10.41 we assume  $L = 2 \cdot \Delta z$  and  $f = 0.02$

Then, for a given pipe diameter  $D$   $V = \sqrt{\frac{2 \cdot g \cdot D \cdot H_l}{f \cdot L}} = \sqrt{\frac{g \cdot D}{3 \cdot f}}$

Also  $Q = V \cdot \frac{\pi \cdot D^2}{4}$   $P_h = \rho \cdot Q \cdot \frac{V^2}{2}$   $P_m = \eta \cdot P_h$  Here are the results in *Excel*:


$f = 0.02$   
 $\rho = 998.00 \text{ kg/m}^3$   
 $\eta = 83\%$

$D$ (cm)	$V$ (m/s)	$Q$ (m <sup>3</sup> /s)	$P_h$ (kW)	$P_m$ (kW)
25	6.39	0.314	6.40	5.31
30	7.00	0.495	12.12	10.06
35	7.56	0.728	20.78	17.25
40	8.09	1.016	33.16	27.53
45	8.58	1.364	50.09	41.57
50	9.04	1.775	72.42	60.11

Turbine efficiency varies with specific speed  
 Pipe roughness appears to the 1/2 power, so has a secondary effect.  
 A 20% error in  $f$  leads to a 10% change in water speed and 30% change in power.  
 A Pelton wheel is an impulse turbine that does not flow full of water; it directs the stream with open buckets.  
 A diffuser could not be used with this system.

41.0	8.19	1.081	36.14	30.00
------	------	-------	-------	-------

Use Goal Seek or Solver to vary  $D$  to make  $P_m$  30 kW!



# Problem 10.103

[Difficulty: 4]

**10.103** A small hydraulic impulse turbine is supplied with water through a penstock with diameter  $D$  and length  $L$ ; the jet diameter is  $d$ . The elevation difference between the reservoir surface and nozzle centerline is  $Z$ . The nozzle head loss coefficient is  $K_{\text{nozzle}}$  and the loss coefficient from the reservoir to the penstock entrance is  $K_{\text{entrance}}$ . Determine the water jet speed, the volume flow rate, and the hydraulic power of the jet, for the case where  $Z=300$  ft,  $L=1000$  ft,  $D=6$  in.,  $K_{\text{entrance}}=0.5$ ,  $K_{\text{nozzle}}=0.04$ , and  $d=2$  in., if the pipe is made from commercial steel. Plot the jet power as a function of jet diameter to determine the optimum jet diameter and the resulting hydraulic power of the jet. Comment on the effects of varying the loss coefficients and pipe roughness.

Solution: Apply the energy equation for steady, incompressible pipe flow.

Computing equation:  $\frac{p_1}{\rho g} + \alpha_1 \frac{\bar{V}_1^2}{2g} + z_1 = \frac{p_2}{\rho g} + \frac{\alpha_2 \bar{V}_2^2}{2g} + z_2 + \frac{h_{\text{ET}}}{g}$ ;  $h_{\text{ET}} = \left[ f \left( \frac{L}{D} + \frac{L}{d} \right) + K \right] \frac{\bar{V}^2}{2}$

Assumptions: (1)  $p_1 = p_2 = p_{\text{atm}}$ , (2)  $\bar{V}_1 \approx 0$ ,  $\alpha_2 = 1$ , (3)  $L_e/D = 0$ , (4)  $K_{\text{nozzle}}$  based on  $V_j^2$

Then  $H = \frac{V_j^2}{2g} + \left( f \frac{L}{D} + K_{\text{entrance}} \right) \frac{\bar{V}^2}{2g} + K_{\text{nozzle}} \frac{V_j^2}{2g}$

From continuity,  $\bar{V}A = V_j A_j$ , so  $\bar{V} = V_j A_j/A = V_j (d/D)^2$ ;  $\bar{V}^2 = V_j^2 (d/D)^4$ , and

$$H = \left[ \left( f \frac{L}{D} + K_{\text{ent}} \right) \left( \frac{d}{D} \right)^4 + 1 + K_{\text{nozzle}} \right] \frac{V_j^2}{2g}; \quad V_j = \left[ \frac{2gH}{\left( f \frac{L}{D} + K_{\text{ent}} \right) \left( \frac{d}{D} \right)^4 + 1 + K_n} \right]^{\frac{1}{2}}$$

Assume  $e = 0.00015$  ft (Table 8.1), so  $e/D = 0.0003$ . From Fig. 8.13, in the fully rough zone,  $f = 0.015$ . Then for  $d_j = 2$  in.


$$V_j = \left[ 2 \times 32.2 \frac{\text{ft}}{\text{s}^2} \times 300 \text{ ft} \times \frac{1}{\left( 0.015 \frac{1000 \text{ ft}}{0.5 \text{ ft}} + 0.5 \right) \left( \frac{2}{6} \right)^4 + 1 + 0.04} \right]^{\frac{1}{2}} = 117 \text{ ft/sec}$$

( $\bar{V} = 13.0$  ft/s,  $Re = \bar{V}D/\nu = 6.05 \times 10^5$ , so  $f = 0.016$ , which makes  $V_j = 116$  ft/s.)

The jet flow rate is  $Q = V_j A_j = \frac{116 \text{ ft}}{\text{s}} \times \frac{\pi}{4} \left( \frac{2}{12} \right)^2 \text{ ft}^2 = 2.53 \text{ ft}^3/\text{s}$ , and the jet power is

$$P_h = \rho Q \frac{V_j^2}{2} = \frac{1}{2} \times 1.94 \frac{\text{slug}}{\text{ft}^3} \times (116)^2 \frac{\text{ft}^4}{\text{s}^2} \times 2.53 \frac{\text{ft}^3}{\text{s}} \times \frac{1 \text{ ft} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lbft}} = 60.0 \text{ hp}$$

Repeating these calculations using a computer program gives:



Peak power,  $P_j \approx 60.3$  hp, occurs for  $2.15 < d < 2.20$  in.

Opt

Loss coefficients have a minor effect. Making both  $K_{\text{ent}}$  and  $K_n$  zero increases  $P_j$  by 4.8 percent.

Pipe roughness causes larger changes;  $P_j$  increased 12.8 percent with  $e = 0$  (smooth).

## Problem 10.104


[Difficulty: 3]

**10.104** The propeller on a fanboat used in the Florida Everglades moves air at the rate of 50 kg/s. When at rest, the speed of the slipstream behind the propeller is 45 m/s at a location where the pressure is atmospheric. Calculate (a) the propeller diameter, (b) the thrust produced at rest, and (c) the thrust produced when the fanboat is moving ahead at 15 m/s if the mass flow rate through the propeller remains constant.

**Given:** Data on boat and propeller

**Find:** Propeller diameter; Thrust at rest; Thrust at 15 m/s

**Solution:**



Basic equation: 
$$\vec{F} = \vec{F}_s + \vec{F}_B = \frac{\partial}{\partial t} \int_{CV} \vec{V}_{xyz} \rho dV + \int_{CS} \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \quad (4.26)$$

Assumption: 1) Atmospheric pressure on CS 2) Horizontal 3) Steady w.r.t. the CV 4) Use velocities relative to CV

The x-momentum is then  $T = u_1 \cdot (-m_{\text{rate}}) + u_4 \cdot (m_{\text{rate}}) = (V_4 - V_1) \cdot m_{\text{rate}}$  where  $m_{\text{rate}} = 50 \cdot \frac{\text{kg}}{\text{s}}$  is the mass flow rate

It can be shown (see Example 10.13) that 
$$V = \frac{1}{2} \cdot (V_4 + V_1)$$

For the static case  $V_1 = 0 \cdot \frac{\text{m}}{\text{s}}$   $V_4 = 45 \cdot \frac{\text{m}}{\text{s}}$  so  $V = \frac{1}{2} \cdot (V_4 + V_1)$   $V = 22.5 \cdot \frac{\text{m}}{\text{s}}$

From continuity  $m_{\text{rate}} = \rho \cdot V \cdot A = \rho \cdot V \cdot \frac{\pi \cdot D^2}{4}$  with  $\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$

Hence  $D = \sqrt{\frac{4 \cdot m_{\text{rate}}}{\rho \cdot \pi \cdot V}}$   $D = 1.52 \cdot \text{m}$

For  $V_1 = 0$   $T = m_{\text{rate}} \cdot (V_4 - V_1)$   $T = 2250 \cdot \text{N}$

When in motion  $V_1 = 15 \cdot \frac{\text{m}}{\text{s}}$  and  $V = \frac{1}{2} \cdot (V_4 + V_1)$  so  $V_4 = 2 \cdot V - V_1$   $V_4 = 30 \cdot \frac{\text{m}}{\text{s}}$

Hence for  $V_1 = 15 \text{ m/s}$   $T = m_{\text{rate}} \cdot (V_4 - V_1)$   $T = 750 \cdot \text{N}$

## Problem 10.105

[Difficulty: 3]

**10.105** A fanboat in the Florida Everglades is powered by a propeller, with  $D=1.5$  m, driven at maximum speed,  $N=1800$  rpm, by a 125 kW engine. Estimate the maximum thrust produced by the propeller at (a) standstill and (b)  $V=12.5$  m/s.

**Given:** Data on fanboat and propeller

**Find:** Thrust at rest; Thrust at 12.5 m/s

**Solution:**

Assume the aircraft propeller coefficients in Fig. 10.40 are applicable to this propeller.

At  $V = 0$ ,  $J = 0$ . Extrapolating from Fig. 10.40b  $C_F = 0.16$

We also have  $D = 1.5$  m  $n = 1800$  rpm  $n = 30 \cdot \frac{\text{rev}}{\text{s}}$  and  $\rho = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$

The thrust at standstill ( $J = 0$ ) is found from  $F_T = C_F \cdot \rho \cdot n^2 \cdot D^4$  (Note:  $n$  is in rev/s)  $F_T = 893 \cdot \text{N}$

At a speed  $V = 12.5 \cdot \frac{\text{m}}{\text{s}}$   $J = \frac{V}{n \cdot D}$   $J = 0.278$  and so from Fig. 10.40b  $C_P = 0.44$  and  $C_F = 0.145$

The thrust and power at this speed can be found  $F_T = C_F \cdot \rho \cdot n^2 \cdot D^4$   $F_T = 809 \cdot \text{N}$   $P = C_P \cdot \rho \cdot n^3 \cdot D^5$   $P = 111 \cdot \text{kW}$


## Problem 10.106

[Difficulty: 3]

**10.106** A jet-propelled aircraft traveling at 225 m/s takes in 50 kg/s of air. If the propulsive efficiency (defined as the ratio of the useful work output to the mechanical energy input to the fluid) of the aircraft is 45 percent, determine the speed at which the exhaust is discharged relative to the aircraft.

**Given:** Data on jet-propelled aircraft

**Find:** Propulsive efficiency



**Solution:**

Basic equation: 
$$\bar{F} = \bar{F}_s + \bar{F}_B = \frac{\partial}{\partial t} \int_{CV} \bar{V}_{xyz} \rho dV + \int_{CS} \bar{V}_{xyz} \rho \bar{V}_{xyz} \cdot d\bar{A} \quad (4.26)$$

$$\dot{Q} - \dot{W}_s - \dot{W}_{\text{shear}} - \dot{W}_{\text{other}} = \frac{\partial}{\partial t} \int_{CV} e \rho dV + \int_{CS} \left( u + pv + \frac{V^2}{2} + gz \right) \rho \bar{V} \cdot d\bar{A} \quad (4.56)$$

Assumption: 1) Atmospheric pressure on CS 2) Horizontal 3) Steady w.r.t. the CV 4) Use velocities relative to CV

The x-momentum is then 
$$-F_D = u_1 \cdot (-m_{\text{rate}}) + u_2 \cdot (m_{\text{rate}}) = (-U) \cdot (-m_{\text{rate}}) + (-V) \cdot (m_{\text{rate}})$$

or 
$$F_D = m_{\text{rate}} \cdot (V - U) \quad \text{where } m_{\text{rate}} = 50 \cdot \frac{\text{kg}}{\text{s}} \text{ is the mass flow rate}$$

The useful work is then 
$$F_D \cdot U = m_{\text{rate}} \cdot (V - U) \cdot U$$

The energy equation simplifies to 
$$-W = \left( \frac{U^2}{2} \right) \cdot (-m_{\text{rate}}) + \left( \frac{V^2}{2} \right) \cdot (m_{\text{rate}}) = \frac{m_{\text{rate}}}{2} \cdot (V^2 - U^2)$$

Hence 
$$\eta = \frac{m_{\text{rate}} \cdot (V - U) \cdot U}{\frac{m_{\text{rate}}}{2} \cdot (V^2 - U^2)} = \frac{2 \cdot (V - U) \cdot U}{(V^2 - U^2)} = \frac{2}{1 + \frac{V}{U}}$$


With 
$$U = 225 \cdot \frac{\text{m}}{\text{s}} \quad \text{and} \quad \eta = 45\% \quad V = U \cdot \left( \frac{2}{\eta} - 1 \right) \quad V = 775 \frac{\text{m}}{\text{s}}$$



## Problem 10.108

[Difficulty: 4]

**10.108** The propulsive efficiency,  $\eta$ , of a propeller is defined as the ratio of the useful work produced to the mechanical energy input to the fluid. Determine the propulsive efficiency of the moving fanboat of Problem 10.104. What would be the efficiency if the boat were not moving?



**Given:** Definition of propulsion efficiency  $\eta$

**Find:**  $\eta$  for moving and stationary boat

**Solution:**

Assumption: 1) Atmospheric pressure on CS 2) Horizontal 3) Steady w.r.t. the CV 4) Use velocities relative to CV

The x-momentum (Example 10.3):  $T = u_1 \cdot (-m_{\text{rate}}) + u_4 \cdot (m_{\text{rate}}) = m_{\text{rate}} \cdot (V_4 - V_1)$

Applying the energy equation to steady, incompressible, uniform flow through the moving CV gives the minimum power input requirement

$$P_{\text{min}} = m_{\text{rate}} \cdot \left( \frac{V_4^2}{2} - \frac{V_1^2}{2} \right)$$

On the other hand, useful work is done at the rate of

$$P_{\text{useful}} = V_1 \cdot T = V_1 \cdot m_{\text{rate}} \cdot (V_4 - V_1)$$

Combining these expressions

$$\eta = \frac{V_1 \cdot m_{\text{rate}} \cdot (V_4 - V_1)}{m_{\text{rate}} \cdot \left( \frac{V_4^2}{2} - \frac{V_1^2}{2} \right)} = \frac{V_1 \cdot (V_4 - V_1)}{\frac{1}{2} \cdot (V_4 - V_1) \cdot (V_4 + V_1)}$$

or

$$\eta = \frac{2 \cdot V_1}{V_1 + V_4}$$

When in motion	$V_1 = 30\text{-mph}$	and	$V_4 = 90\text{-mph}$	$\eta = \frac{2 \cdot V_1}{V_1 + V_4}$	$\eta = 50\%$
----------------	-----------------------	-----	-----------------------	--	---------------

For the stationary case	$V_1 = 0\text{-mph}$		$\eta = \frac{2 \cdot V_1}{V_1 + V_4}$	$\eta = 0\%$
-------------------------	----------------------	--	--	--------------

# Problem 10.109

[Difficulty: 4]

**10.109** The propeller for the Gossamer Condor human-powered aircraft has  $D=12$  ft and rotates at  $N=107$  rpm. Additional details on the aircraft are given in Problem 9.174. Estimate the dimensionless performance characteristics and efficiency of this propeller at cruise conditions. Assume the pilot expends 70 percent of maximum power at cruise. (See Reference [56] for more information on human-powered flight.)

Solution: From the solution to Problem 9.174, minimum power to propel the aircraft occurs at  $V=10.7$  mph (16.0 ft/s). Assume this is the cruise condition.

From the given data, at 12 mph (17.6 ft/s),  $F_D = 6$  lbf

$$\frac{1}{2}\rho V^2 = \frac{1}{2} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (17.6)^2 \frac{\text{ft}^2}{\text{s}^2} \times \frac{16\text{ft} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} = 0.369 \text{ lbf/ft}^2$$

$$C_L = \frac{F_L}{\frac{1}{2}\rho V^2 A} = \frac{W}{qA} = \frac{W/A}{q} = \frac{0.4 \text{ lbf/ft}^2}{0.369 \text{ lbf/ft}^2} = 1.08$$

$$C_D = C_L \frac{F_D}{F_L} = 1.08 \frac{6 \text{ lbf}}{200 \text{ lbf}} = 0.0324$$

$$C_{D,0} = C_D - C_{D,i} = C_D - \frac{C_L^2}{\pi A r} = 0.0324 - \frac{(1.08)^2}{\pi(17)} = 0.0106$$

At  $V=10.7$  mph (16.0 ft/s),  $q = 0.305$  lbf/ft<sup>2</sup>

$$C_L = \frac{W}{qA} = \frac{W/A}{q} = \frac{0.4 \text{ lbf/ft}^2}{0.305 \text{ lbf/ft}^2} = 1.31; \quad C_{D,i} = \frac{C_L^2}{\pi A r} = 0.0321$$

$$C_D = C_{D,0} + C_{D,i} = 0.0106 + 0.0321 = 0.0427; \quad F_D = F_L \frac{C_D}{C_L} = 200 \text{ lbf} \frac{0.0427}{1.31} = 6.52 \text{ lbf}$$

For the propeller,

$$J = \frac{V}{nD} = \frac{16.0 \text{ ft/s}}{\frac{60}{107} \text{ rev/s} \times 12.0 \text{ ft}} = 0.748 \quad J$$

$$C_F = \frac{F_D}{\rho n^2 D^4} = \frac{6.52 \text{ lbf}}{0.00238 \text{ slug/ft}^3 \times \left(\frac{60}{107}\right)^2 \text{ rev}^2/\text{s}^2 \times (12.0)^4 \text{ ft}^4 \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2}} = 0.0415 \quad C_F$$

Assume a 30 percent reserve for climbing and maneuvers. Then if  $\eta_d = 0.9$ ,

$$\eta_p = \frac{P_{out}}{P_{in} \eta_d} = \frac{F_D V}{(0.7) 0.39 \text{ hp} (0.9)} = \frac{1}{0.246 \text{ hp}} \times 6.52 \text{ lbf} \times \frac{16.0 \text{ ft}}{\text{s}} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ ft} \cdot \text{lbf}} = 0.771 \quad \eta$$

Finally,  $P_{prop} = \eta_d P_{in} = 0.246 \text{ hp} = \omega T$ ;  $T = \frac{0.246 \text{ hp}}{\omega} = 12.1 \text{ ft} \cdot \text{lbf}$

$$C_T = \frac{T}{\rho n^2 D^5} = \frac{12.1 \text{ ft} \cdot \text{lbf}}{0.00238 \text{ slug/ft}^3 \times \left(\frac{60}{107}\right)^2 \text{ rev}^2/\text{s}^2 \times (12.0)^5 \text{ ft}^5 \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2}} = 0.00642 \quad C_T$$

$$C_p = \frac{C_T}{n} = 0.00642 \times \frac{60}{107} = 0.0036 \quad C_p$$

42 SHEETS 5 SQUARE  
42 SHEETS 100 SQUARE  
42 SHEETS 200 SQUARE  
NATIONAL

## Problem 10.110

[Difficulty: 5]

**10.110** Equations for the thrust, power, and efficiency of propulsion devices were derived in Section 10.6. Show that these equations may be combined for the condition of constant thrust to obtain

$$\eta = \frac{2}{1 + \left(1 + \frac{F_T}{\frac{\rho V^2 \pi D^2}{4}}\right)^{1/2}}$$

Interpret this result physically.


Solution: Apply 1-D forms of momentum and energy to CV of Fig. 10.38:

Computing equations:

Continuity  $\dot{m} = \rho \left(V + \frac{\Delta V}{2}\right) \frac{\pi D^2}{4}$

Momentum  $F_T = \dot{m} \Delta V$  (10.28)

Energy  $\dot{P}_{in} = \dot{m} V \Delta V \left(1 + \frac{\Delta V}{2V}\right)$  (10.29)



Assumptions: (1) Steady flow, (2) Incompressible flow, (3) Uniform flow, (4) Frictionless flow

Propulsion efficiency is  $\eta_p = \frac{\dot{P}_{out}}{\dot{P}_{in}} = \frac{F_T V}{\dot{m} V \Delta V \left(1 + \frac{\Delta V}{2V}\right)} = \frac{\dot{m} V \Delta V}{\dot{m} V \Delta V \left(1 + \frac{\Delta V}{2V}\right)} = \frac{1}{1 + \frac{\Delta V}{2V}}$  (1)

$F_T$  may be written using continuity as

$$F_T = \dot{m} \Delta V = \rho \left(V + \frac{\Delta V}{2}\right) \frac{\pi D^2}{4} \Delta V = 2\rho V \frac{\pi D^2}{4} \left(1 + \frac{\Delta V}{2V}\right) \left(\frac{\Delta V}{2V}\right) = 2\rho V^2 \frac{\pi D^2}{4} (1 + \lambda) \lambda$$

where  $\lambda = \frac{\Delta V}{2V}$ . For constant  $F_T$ ,

$$\lambda^2 + \lambda - \frac{F_T}{2\rho V^2 \frac{\pi D^2}{4}} = 0$$

Solving via the quadratic equation, and choosing the positive root

$$\lambda = \frac{-1 \pm \sqrt{1 + 4 \frac{F_T}{2\rho V^2 \frac{\pi D^2}{4}}}}{2} = \frac{1}{2} \left\{ -1 + \sqrt{1 + \frac{F_T}{\rho V^2 \frac{\pi D^2}{4}}} \right\}$$

From Eq. 1,  $\eta_p = \frac{1}{1 + \lambda} = \frac{1}{1 + \frac{1}{2} \left\{ \dots \right\}} = \frac{2}{2 + \left\{ \dots \right\}} = \frac{2}{1 + \left(1 + \frac{F_T}{\rho V^2 \frac{\pi D^2}{4}}\right)^{1/2}}$   $\eta_p$

The ratio,  $F_T / \frac{\pi D^2}{4}$ , may be interpreted as the disk loading: the force developed per unit area of the actuator disk. Note  $\eta_p \rightarrow 1$  as  $\frac{\pi D^2}{4}$  increases.

## Problem 10.111

[Difficulty: 2]

**10.111** The National Aeronautics & Space Administration (NASA) and the U.S. Department of Energy (DOE) cosponsor a large demonstration wind turbine generator at Plum Brook, near Sandusky, Ohio [47]. The turbine has two blades, with a radius of 63 ft, and delivers maximum power when the wind speed is above  $V = 16$  knots. It is designed to produce 135 hp with powertrain efficiency of 74 percent. The rotor is designed to operate at a constant speed of 45 rpm in winds over 5 knots by controlling system load and adjusting blade angles. For the maximum power condition, estimate the rotor tip speed and power coefficient.

**Given:** NASA-DOE wind turbine generator

**Find:** Estimate rotor tip speed and power coefficient at maximum power condition

**Solution:**

Basic equations:

$$C_P = \frac{P_m}{\frac{1}{2} \cdot \rho \cdot V^3 \cdot \pi \cdot R^2} \quad X = \frac{\omega \cdot R}{V} \quad U = \omega \cdot R \quad \eta = \frac{P_m}{P_{\text{ideal}}}$$

and we have  $\rho = 0.00237 \cdot \frac{\text{slug}}{\text{ft}^3}$   $\omega = 45 \cdot \text{rpm} = 4.712 \cdot \frac{\text{rad}}{\text{s}}$   $R = 63 \cdot \text{ft}$   $V = 16 \cdot \text{knot} = 27.005 \cdot \frac{\text{ft}}{\text{s}}$   $P = 135 \cdot \text{hp}$   $\eta = 74\%$

The blade tip speed is:  $U = \omega \cdot R = 297 \cdot \frac{\text{ft}}{\text{s}}$

The tip speed ratio is:  $X = \frac{\omega \cdot R}{V} = 10.994$  (X will decrease at the wind speed increases.)

The mechanical work out is:  $P_m = \frac{P}{\eta} = 182.4 \cdot \text{hp}$  From this we can calculate the power coefficient:

$$C_P = \frac{P_m}{\frac{1}{2} \cdot \rho \cdot V^3 \cdot \pi \cdot R^2} = 0.345$$

## Problem 10.112

[Difficulty: 3]

**10.112** A typical American multiblade farm windmill has  $D=7$  ft and is designed to produce maximum power in winds with  $V=15$  mph. Estimate the rate of water delivery, as a function of the height to which the water is pumped, for this windmill.

Solution: Assume the efficiency trends shown in Fig. 10.45.

Computing equations:  $C_p = \frac{P}{\frac{1}{2}\rho V^3 \pi R^2}$        $X = WR/V$

From Fig. 10.45,  $C_p \max \approx 0.3$  at  $X = 0.8$ .  $V = 15$  mph (22.0 ft/s). Then the power developed is

$$P = \frac{\pi}{2} \times 0.3 \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times (22.0)^3 \frac{\text{ft}^3}{\text{s}^3} \times \left(\frac{7}{2}\right)^2 \text{ft}^2 \times \frac{1 \text{bf} \cdot \text{s}^2}{31.49 \cdot \text{ft}} \times \frac{\text{hp} \cdot \text{s}}{550 \text{ft} \cdot \text{lb}} = 0.266 \text{ hp}$$

Converting this mechanical power to pumping gives hydraulic power as

$$P_h = \rho Q g h = \eta P_m$$

$$\text{Thus } Qh = \frac{\eta P_m}{\rho g} = 0.7 \times 0.266 \text{ hp} \times \frac{\text{ft}^3}{62.4 \text{ lb}} \times \frac{550 \text{ ft} \cdot \text{lb}}{\text{hp} \cdot \text{s}} \times \frac{7.48 \text{ gal}}{\text{ft}^3} \times \frac{60 \text{ s}}{\text{min}}$$

$$Qh = 737 \text{ gpm} \cdot \text{ft}$$

$Qh$

$Q$  varies inversely with the distance lifted,  $h$ . The volume flow rate actually delivered would be less, due to suction lift, pipe friction, and minor losses.

## Problem 10.113

[Difficulty: 2]

**10.113** A model of an American multiblade farm windmill is to be built for display. The model, with  $D=1$  m, is to develop full power at  $V=10$  m/s wind speed. Calculate the angular speed of the model for optimum power generation. Estimate the power output.

**Given:** Model of farm windmill

**Find:** Angular speed for optimum power; Power output

**Solution:**

Basic equations: 
$$C_P = \frac{P}{\frac{1}{2} \cdot \rho \cdot V^3 \cdot \pi \cdot R^2} \quad X = \frac{\omega \cdot R}{V} \quad \text{and we have} \quad \rho = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$$

From Fig. 10.45 
$$C_{P_{\max}} = 0.3 \quad \text{at} \quad X = 0.8 \quad \text{and} \quad D = 1 \cdot \text{m} \quad R = \frac{D}{2} \quad R = 0.5 \text{ m}$$

Hence, for 
$$V = 10 \cdot \frac{\text{m}}{\text{s}} \quad \omega = \frac{X \cdot V}{R} \quad \omega = 16 \cdot \frac{\text{rad}}{\text{s}} \quad \omega = 153 \cdot \text{rpm}$$

Also 
$$P = C_{P_{\max}} \cdot \frac{1}{2} \cdot \rho \cdot V^3 \cdot \pi \cdot R^2 \quad P = 144 \text{ W}$$

## Problem 10.114

[Difficulty: 2]

**10.114** A large Darrieus vertical axis wind turbine was built by the U.S. Department of Energy near Sandia, New Mexico [48]. This machine is 18 m tall and has a 5-m radius; the area swept by the rotor is over 110 m<sup>2</sup>. If the rotor is constrained to rotate at 70 rpm, plot the power this wind turbine can produce in kilowatts for wind speeds between 5 and 50 knots.

**Given:** NASA-DOE wind turbine generator

**Find:** Estimate rotor tip speed and power coefficient at maximum power condition

**Solution:**

Basic equations: 
$$C_P = \frac{P_m}{\frac{1}{2} \cdot \rho \cdot V^3 \cdot \pi \cdot R^2} \quad X = \frac{\omega \cdot R}{V} \quad U = \omega \cdot R \quad \eta = \frac{P_m}{P_{ideal}}$$

and we have  $\rho = 1.23 \cdot \frac{\text{kg}}{\text{m}^3}$      $\omega = 70 \cdot \text{rpm}$      $R = 5 \cdot \text{m}$      $H = 18 \cdot \text{m}$      $A = 110 \cdot \text{m}^2$      $U = \omega \cdot R = 36.652 \frac{\text{m}}{\text{s}}$


From Fig. 10.45:  $C_P = 0.34$  when  $X = 5.3$  (maximum power condition) If we replace the  $\pi \cdot R^2$  term in the power coefficient

with the swept area we will get:  $P = \frac{1}{2} \cdot C_P \cdot \rho \cdot V^3 \cdot A$

Here are the results, calculated using *Excel*:

$A = 110.00 \text{ m}^2$       Power coefficient data were taken from Fig. 10.45  
 $\rho = 1.23 \text{ kg/m}^3$   
 $U = 36.65 \text{ m/s}$

V (kt)	V (m/s)	X	C <sub>P</sub>	P (kW)
10.0	5.14	7.125	0.00	0.00
12.5	6.43	5.700	0.30	5.40
15.0	7.72	4.750	0.32	9.95
17.5	9.00	4.071	0.20	9.87
20.0	10.29	3.562	0.10	7.37
22.5	11.57	3.167	0.05	4.72
25.0	12.86	2.850	0.02	2.88
30.0	15.43	2.375	0.00	0.00





### Problem 10.115

[Difficulty: 5] Part 2/3

$$V_{rel} = [(80.9)^2 + (29.4)^2]^{1/2} = 86.1 \text{ ft/s}; \quad q = \frac{1}{2} \rho V_{rel}^2 = 8.82 \text{ lb/ft}^2; \quad A_p = w c = 0.5 \text{ ft}^2$$

$$\theta = \tan^{-1}(29.4/80.9) = 20.0^\circ; \quad \alpha = \theta - \beta = 20.0 - 5.0 = 15.0^\circ; \quad C_L = 1.65; \quad C_D = 0.017$$


$$F_L = 1.65 \times 8.82 \frac{\text{lb}}{\text{ft}^2} \times 0.5 \text{ ft}^2 = 7.28 \text{ lb}; \quad F_D = 0.017 \times 8.82 \frac{\text{lb}}{\text{ft}^2} \times 0.5 \text{ ft}^2 = 0.075 \text{ lb}$$

$$T = 2 \times 5.5 \text{ ft} (7.28 \sin 20^\circ - 0.075 \cos 20^\circ) \text{ lb} = 26.6 \text{ ft} \cdot \text{lb}$$

Similar calculations for the other blade elements show that torque for the complete propeller is  $T_p = 159 \text{ ft} \cdot \text{lb}$ . The power coefficient is

$$C_p = \frac{P}{\frac{1}{2} \rho V_w^3 \pi R^2} = \frac{w T_p}{\frac{1}{2} \rho V_w^3 \pi R^2} = \frac{2}{\pi} \times \frac{14.7 \text{ rad}}{5} \times \frac{159 \text{ ft} \cdot \text{lb}}{0.00238 \text{ slug} \times (29.4)^3 \text{ ft}^3} \times \frac{1}{(10)^4 \text{ ft}^2} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb} \cdot \text{s}^2} = 0.246$$

Calculated results are tabulated on the next page, plotted and discussed below:



Trends shown are similar to Fig. 10.45. At small  $X$ , the blade is entirely stalled so useful output is low. At large  $X$ ,  $\alpha$  becomes negative near the tips, reducing output.

This model does not include: (1) axial interference that reduces normal velocity below  $V_w$  as loading increases, or (2) swirl introduced by blade drag. Both these effects reduce performance. For more details, see Division L, Section XI of [30].



# Problem 10.116


**10.116** Aluminum extrusions, patterned after NACA symmetric airfoil sections, frequently are used to form Darrieus wind turbine "blades." Below are section lift and drag coefficient data [57] for a NACA 0012 section, tested at  $Re = 6 \times 10^6$  with standard roughness (the section stalled for  $\alpha > 12^\circ$ ):

Angle of attack, $\alpha$ (deg)	0	2	4	6	8	10	12
Lift coefficient, $C_L$ (—)	0	0.23	0.45	0.68	0.82	0.94	1.02
Drag coefficient, $C_D$ (—)	0.0098	0.0100	0.0119	0.0147	0.0194	—	—

Analyze the air flow relative to a blade element of a Darrieus wind turbine rotating about its troposkien axis. Develop a numerical model for the blade element. Calculate the power coefficient developed by the blade element as a function of tip-speed ratio. Compare your result with the general trend of power output for Darrieus rotors shown in Fig. 10.50.

Solution: Consider plan view of rotor element, absolute velocities:

Computing equations:  $F_L = C_L \frac{1}{2} \rho V_r^2 A_p$ ,  $V_r =$  relative velocity  
 $F_D = C_D \frac{1}{2} \rho V_r^2 A_p$   $A_p =$  planform area,  $A_s =$  swept area  
 $C_P = \frac{P}{\frac{1}{2} \rho V^3 A_s}$   $V =$  wind velocity



Resolve to relative velocity, for position shown:

$$\vec{V}_{abs} = \vec{V}_{blade} + \vec{V}_{rel}; \quad \vec{V}_{rel} = \vec{V}_{abs} - \vec{V}_{blade}$$


To compute  $V_{rel}$ , resolve into components along (a) and transverse (t) to the airfoil chord:

$$V_{rel(a)} = WR + V_w \cos \theta$$

$$V_{rel(t)} = V_w \sin \theta$$

$$V_{rel} = [V_{rel(a)}^2 + V_{rel(t)}^2]^{1/2}$$

$$\alpha = \tan^{-1}[V_{rel(t)} / V_{rel(a)}]$$



Lift force ( $F_L$ ) is normal to  $\vec{V}_{rel}$  and drag force ( $F_D$ ) is parallel to  $\vec{V}_{rel}$ . Thus

$$T = R(F_L \sin \alpha - F_D \cos \alpha) \quad (\text{torque, } T > 0 \text{ when } F_L/F_D > \cot \alpha)$$

Both  $C_L$  and  $C_D$  must be modeled as functions of angle of attack,  $\alpha$ . From a graph of  $C_L$  and  $C_D$  versus  $\alpha$ , a satisfactory representation is

$$C_L = 0.12 \alpha - 0.0026 |\alpha| \alpha, \quad -12 < \alpha < 12 \text{ degrees}; \quad C_L = 0, \quad |\alpha| > 12 \text{ degrees}$$

$$C_D = 0.00952 + 1.52 \times 10^{-4} \alpha^2, \quad -12 < \alpha < 12 \text{ degrees}; \quad C_D = 0.0314, \quad |\alpha| > 12 \text{ degrees}$$

(The models in the stalled region,  $|\alpha| > 12$  degrees, obviously are crude.)

### Problem 10.116

[Difficulty: 5] Part 2/3

Sample calculation: Choose  $R = 10 \text{ ft}$ ,  $c = 0.5 \text{ ft}$ ,  $w = 1 \text{ ft}$ ,  $X = 5$ ,  $V_w = 20 \text{ mph}$

At  $\theta = 30^\circ$ , with  $V_w = 20 \text{ mph}$  ( $29.3 \text{ ft/s}$ )

$$X = \omega R / V_w ; \omega = \frac{X V_w}{R} = 5 \times \frac{29.3 \text{ ft}}{\text{s}} \times \frac{1}{10 \text{ ft}} = 14.7 \text{ rad/s} \quad (N = 140 \text{ rpm})$$

$$\omega R = 14.7 \frac{\text{rad}}{\text{s}} \times 10 \text{ ft} = 147 \text{ ft/s}$$

$$V_{rel,a} = \omega R + V_w \cos \theta = 147 + 29.3 \cos 30^\circ = 172 \text{ ft/s}$$

$$V_{rel,t} = V_w \sin \theta = 29.3 \sin \theta = 14.7 \text{ ft/s}$$

$$V_{rel} = [V_{rel,a}^2 + V_{rel,t}^2]^{1/2} = [(172)^2 + (14.7)^2]^{1/2} = 173 \text{ ft/s}$$

$$\alpha = \tan^{-1}[V_{rel,t} / V_{rel,a}] = \tan^{-1}(14.7 / 172) = 4.88 \text{ degrees}$$

$$q = \frac{1}{2} \rho V_{rel}^2 = \frac{1}{2} \times 0.00238 \frac{\text{slug}}{\text{ft}^3} \times \frac{(173)^2 \text{ ft}^2}{\text{s}^2} \times \frac{1 \text{ lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} = 35.6 \text{ lb/ft}^2$$

$$A_p \text{ (projected area of airfoil section)} = cw = 0.5 \text{ ft} \times 1 \text{ ft} = 0.5 \text{ ft}^2$$

$$C_L = 0.12 \alpha - 0.0026 \alpha^2 = 0.12 \times 4.88 - 0.0026 / 4.88 / 4.88 = 0.524$$

$$C_D = 0.00952 + 1.52 \times 10^{-4} \alpha^2 = 0.00952 + 1.52 \times 10^{-4} (4.88)^2 = 0.0131$$

$$F_L = C_L q A_p = 0.524 \times 35.6 \frac{\text{lb}}{\text{ft}^2} \times 0.5 \text{ ft}^2 = 9.33 \text{ lb}$$

$$F_D = C_D q A_p = 0.0131 \times 35.6 \frac{\text{lb}}{\text{ft}^2} \times 0.5 \text{ ft}^2 = 0.233 \text{ lb}$$

$$\left. \begin{array}{l} F_L \\ F_D \end{array} \right\} F_L / F_D = 40.0$$

$$T = R(F_L \sin \alpha - F_D \cos \alpha) = 10 \text{ ft} (9.33 \sin(4.88^\circ) - 0.233 \cos(4.88^\circ)) \text{ lb} = 5.62 \text{ ft} \cdot \text{lb}$$

$$\dot{\Phi} = \omega T = 14.7 \frac{\text{rad}}{\text{s}} \cdot 5.62 \text{ ft} \cdot \text{lb} = 82.6 \frac{\text{ft} \cdot \text{lb}}{\text{s}} \quad (0.150 \text{ hp})$$

$$C_p = \frac{\dot{\Phi}}{\frac{1}{2} \rho V_w^3 A_s} ; A_s = \text{area swept by element} = 2 R w = 2 \times 10 \text{ ft} \times 1 \text{ ft} = 20 \text{ ft}^2$$

$$C_p = \frac{82.6 \text{ ft} \cdot \text{lb}}{\text{s}} \times \frac{\text{ft}^3}{(\frac{1}{2}) 0.00238 \text{ slug}} \times \frac{\text{s}^3}{(29.3)^3 \text{ ft}^3} \times \frac{1}{20 \text{ ft}^2} \times \frac{\text{slug} \cdot \text{ft}}{1 \text{ lb} \cdot \text{s}^2} = 0.138 \text{ (at } \theta = 15^\circ)$$

Obtain  $\bar{C}_p$  for a complete rotor revolution by integrating numerically. Such results are presented on the next page, and plotted versus tip speed ratio,  $X = \omega R / V_w$ .

From the plot,  $\bar{C}_p$  is small at low  $X$ . It increases as  $X$  is raised, then peaks and decreases again. Comparison with Fig. 10.45 shows the trends are similar, but the model predicts useful power at larger  $X$  than observed experimentally. Blade elements at smaller radii on the rotor would produce less power, since  $\omega = \text{constant}$  along rotor.  $\bar{C}_p$  at large  $X$  is also sensitive to  $C_D$ .

Low  $\bar{C}_p$  at small  $X$  occurs because the airfoil is stalled.

# Problem 10.116

Computed results:

\* Alan T. McDonald \*  
 \* School of Mechanical Engineering \*  
 \* PURDUE UNIVERSITY \*  
 \* West Lafayette, Indiana 47907 \*  
 \*

Airfoil: NACA 0012 Section; Chord,  $c = 6$  in.

Blade element: Span,  $w = 1$  ft; Radius,  $R = 10$  ft


Input data: Tip speed ratio,  $X = 5.0$  (---)  
 Wind speed,  $V_w = 20$  mph (29.3 ft/sec)

Calculated: Rotor speed,  $\omega = 140.4$  rpm

theta (deg)	Vrel (ft/s)	alpha (deg)	C <sub>l</sub> (---)	C <sub>d</sub> (---)	F <sub>l</sub> (lbf)	F <sub>d</sub> (lbf)	T (ft-lbf)	C <sub>p</sub> (---)
0	176	0.00	0.00	0.010	0.0	0.176	-1.8	-0.043
30	173	4.87	0.52	0.013	9.3	0.233	5.6	0.136
60	164	8.95	0.87	0.022	13.8	0.343	18.1	0.439
90	150	11.31	1.02	0.029	13.7	0.384	23.1	0.562
120	135	10.89	1.00	0.027	10.8	0.295	17.5	0.425
150	122	6.90	0.70	0.017	6.3	0.148	6.1	0.147
180	118	-0.00	-0.00	0.010	-0.0	0.078	-0.8	-0.019
210	122	-6.90	-0.70	0.017	-6.3	0.148	6.1	0.147
240	135	-10.89	-1.00	0.027	-10.8	0.295	17.5	0.425
270	150	-11.31	-1.02	0.029	-13.7	0.384	23.1	0.562
300	164	-8.95	-0.87	0.022	-13.8	0.343	18.1	0.439
330	173	-4.87	-0.52	0.013	-9.3	0.233	5.6	0.136
360	176	0.00	0.00	0.010	0.0	0.176	-1.8	-0.043

Average power coefficient for complete revolution:  $C_{p,bar} = 0.280$

Plotting results of similar calculations at various tip speed ratios give:



## Problem 10.117

[Difficulty: 2]

**10.117** A prototype air compressor with a compression ratio of 7 is designed to take 8.9 kg/s air at 1 atmosphere and 20°C. The design point speed, power requirement, and efficiency are 600 rpm, 5.6 MW, and 80 percent, respectively. A 1:5-scale model of the prototype is built to help determine operability for the prototype. If the model takes in air at identical conditions to the prototype design point, what will the mass flow and power requirement be for operation at 80 percent efficiency?

**Given:** Prototype air compressor, 1/5 scale model to be built

**Find:** Mass flow rate and power requirements for operation at equivalent efficiency

**Solution:**

Basic equations: 
$$\eta = f_1 \left( \frac{M \cdot \sqrt{R \cdot T_{01}}}{\rho_{01} \cdot D^2}, \frac{\omega \cdot D}{c_{01}} \right) \quad \frac{W_c}{\rho_{01} \cdot \omega^3 \cdot D^5} = f_2 \left( \frac{M \cdot \sqrt{R \cdot T_{01}}}{\rho_{01} \cdot D^2}, \frac{\omega \cdot D}{c_{01}} \right) \quad \frac{D_m}{D_p} = \frac{1}{5}$$

Given data:  $M_p = 8.9 \frac{\text{kg}}{\text{s}} \quad \omega_p = 600 \cdot \text{rpm} \quad W_{cp} = 5.6 \cdot \text{MW}$

Since the efficiencies are the same for the prototype and the model, it follows that:

$$\frac{M_m \cdot \sqrt{R_m \cdot T_{01m}}}{\rho_{01m} \cdot D_m^2} = \frac{M_p \cdot \sqrt{R_p \cdot T_{01p}}}{\rho_{01p} \cdot D_p^2} \quad \frac{\omega_m \cdot D_m}{c_{01m}} = \frac{\omega_p \cdot D_p}{c_{01p}} \quad \frac{W_{cm}}{\rho_{01m} \cdot \omega_m^3 \cdot D_m^5} = \frac{W_{cp}}{\rho_{01p} \cdot \omega_p^3 \cdot D_p^5}$$

Given identical entrance conditions for model and prototype and since the working fluid for both is air:

$$\frac{M_m}{D_m^2} = \frac{M_p}{D_p^2} \quad \text{Solving for the mass flow rate of the model:} \quad M_m = M_p \cdot \left( \frac{D_m}{D_p} \right)^2 \quad M_m = 0.356 \frac{\text{kg}}{\text{s}}$$

$$\omega_m \cdot D_m = \omega_p \cdot D_p \quad \text{Solving for the speed of the model:} \quad \omega_m = \omega_p \cdot \frac{D_p}{D_m} = 3000 \cdot \text{rpm}$$

$$\frac{W_{cm}}{\omega_m^3 \cdot D_m^5} = \frac{W_{cp}}{\omega_p^3 \cdot D_p^5} \quad \text{Solving for the power requirement for the model:} \quad W_{cm} = W_{cp} \cdot \left( \frac{\omega_m}{\omega_p} \right)^3 \cdot \left( \frac{D_m}{D_p} \right)^5$$

$$W_{cm} = 0.224 \cdot \text{MW}$$

## Problem 10.118

[Difficulty: 3]

**10.118** A compressor has been designed for entrance conditions of 14.7 psia and 70°F. To economize on the power required, it is being tested with a throttle in the entry duct to reduce the entry pressure. The characteristic curve for its normal design speed of 3200 rpm is being obtained on a day when the ambient temperature is 58°F. At what speed should the compressor be run? At the point on the characteristic curve at which the mass flow would normally be 125 lbm/s, the entry pressure is 8.0 psia. Calculate the actual mass flow rate during the test.

**Given:** Prototype air compressor equipped with throttle to control entry pressure

**Find:** Speed and mass flow rate of compressor at off-design entrance conditions

**Solution:**

Basic equations: 
$$\eta = f_1\left(\frac{M \cdot \sqrt{T_{01}}}{p_{01}}, \frac{\omega}{\sqrt{T_{01}}}\right) \quad \frac{\Delta T_{01}}{T_{01}} = f_2\left(\frac{M \cdot \sqrt{T_{01}}}{p_{01}}, \frac{\omega}{\sqrt{T_{01}}}\right)$$

Given data:  $p_{01d} = 14.7 \cdot \text{psi} \quad T_{01d} = 70^\circ\text{F} \quad \omega_d = 3200 \cdot \text{rpm} \quad T_{01} = 58^\circ\text{F} \quad M_d = 125 \cdot \frac{\text{lbm}}{\text{s}} \quad p_{01} = 8.0 \cdot \text{psi}$

Since the normalized speed is equal to that of the design point, it follows that: 
$$\frac{\omega}{\sqrt{T_{01}}} = \frac{\omega_d}{\sqrt{T_{01d}}}$$

Solving for the required speed: 
$$\omega = \omega_d \cdot \sqrt{\frac{T_{01}}{T_{01d}}} \quad \omega = 3164 \cdot \text{rpm}$$

At similar conditions: 
$$\frac{M \cdot \sqrt{T_{01}}}{p_{01}} = \frac{M_d \cdot \sqrt{T_{01d}}}{p_{01d}} \quad \text{Solving for the actual mass flow rate: } M = M_d \cdot \sqrt{\frac{T_{01d}}{T_{01}}} \cdot \frac{p_{01}}{p_{01d}} \quad M = 68.8 \cdot \frac{\text{lbm}}{\text{s}}$$

## Problem 10.119

[Difficulty: 3]

**10.119** The turbine for a new jet engine was designed for entrance conditions of 160 psia and 1700°F, ingesting 500 lbm/s at a speed of 500 rpm, and exit conditions of 80 psia and 1350°F. If the altitude and fueling for the engine were changed such that the entrance conditions were now 140 psia and 1600°F, calculate the new operating speed, mass flow rate, and exit conditions for similar operation, i.e., equal efficiency.

**Given:** Design conditions for jet turbine, off-design actual conditions

**Find:** New operating speed, mass flow rate, and exit conditions for similar operation

**Solution:**

Basic equations: 
$$\eta = f_1\left(\frac{M \cdot \sqrt{T_{01}}}{P_{01}}, \frac{\omega}{\sqrt{T_{01}}}\right) \quad \frac{\Delta T_0}{T_{01}} = f_2\left(\frac{M \cdot \sqrt{T_{01}}}{P_{01}}, \frac{\omega}{\sqrt{T_{01}}}\right) \quad \frac{P_{01}}{P_{02}} = f_3\left(\frac{M \cdot \sqrt{T_{01}}}{P_{01}}, \frac{\omega}{\sqrt{T_{01}}}\right)$$

Given data:  $p_{01d} = 160 \text{ psi} \quad T_{01d} = 1700 \text{ }^\circ\text{F} \quad \omega_d = 500 \text{ rpm} \quad M_d = 500 \frac{\text{lbm}}{\text{s}} \quad p_{02d} = 80 \text{ psi} \quad T_{02d} = 1350 \text{ }^\circ\text{F}$

$p_{01} = 140 \text{ psi} \quad T_{01} = 1600 \text{ }^\circ\text{F}$

At similar conditions:  $\frac{\omega}{\sqrt{T_{01}}} = \frac{\omega_d}{\sqrt{T_{01d}}}$  Solving for the required speed:  $\omega = \omega_d \cdot \sqrt{\frac{T_{01}}{T_{01d}}} \quad \omega = 488 \text{ rpm}$

$\frac{M \cdot \sqrt{T_{01}}}{P_{01}} = \frac{M_d \cdot \sqrt{T_{01d}}}{P_{01d}}$  Solving for the actual mass flow rate:  $M = M_d \cdot \sqrt{\frac{T_{01d}}{T_{01}}} \cdot \frac{P_{01}}{P_{01d}} \quad M = 448 \frac{\text{lbm}}{\text{s}}$

$\frac{\Delta T_0}{T_{01}} = \frac{\Delta T_{0d}}{T_{01d}}$  Solving for the temperature drop:  $\Delta T_0 = \Delta T_{0d} \cdot \frac{T_{01}}{T_{01d}}$  Substituting in temperatures:

$T_{01} - T_{02} = (T_{01d} - T_{02d}) \cdot \frac{T_{01}}{T_{01d}} \quad T_{02} = T_{01} - (T_{01d} - T_{02d}) \cdot \frac{T_{01}}{T_{01d}} \quad T_{02} = 1266 \text{ }^\circ\text{F}$

$\frac{P_{01}}{P_{02}} = \frac{P_{01d}}{P_{02d}}$  Solving for the exit pressure:  $P_{02} = P_{01} \cdot \frac{P_{02d}}{P_{01d}} \quad P_{02} = 70 \text{ psi}$

## Problem 10.120

[Difficulty: 4]

**10.120** We have seen many examples in Chapter 7 of replacing working fluids in order to more easily achieve similitude between models and prototypes. Describe the effects of testing an air compressor using helium as the working fluid on the dimensionless and dimensional parameters we have discussed for compressible flow machines.

**Discussion:** When we change the working fluid, we need to be sure that we use the correct similitude relationships. Specifically, we would need to keep fluid-specific parameters (gas constant and specific heat ratio) in the relationships. The functional relationships are:

$$\frac{\Delta h_{0s}}{(ND)^2}, \eta, \frac{P}{\rho_{01} N^3 D^5} = f_1 \left( \frac{\dot{m}}{\rho_{01} ND^3}, \frac{\rho_{01} ND^2}{\mu}, \frac{ND}{c_{01}}, k \right)$$


So these dimensionless groups need to be considered. When we replace air with helium, both the gas constant  $R$  and the specific heat ratio  $k$  will increase. Given a fixed inflow pressure and temperature and a fixed geometry, the effect would be to decrease density and increase sound speed. Therefore, replacing air with helium should result in decreased mass flow rate and power, and an increased operating speed.

When considering dimensional parameters, the important thing to remember is that the operability maps for compressors and/or turbines were constructed for a single working fluid. Therefore, to be safe, an engineer should reconstruct an operability map for a new working fluid.

## Problem 11.1

[Difficulty: 2]

**11.1** Verify the equation given in Table 11.1 for the hydraulic radius of a trapezoidal channel. Plot the ratio  $R/y$  for  $b = 2$  m with side slope angles of  $30^\circ$  and  $60^\circ$  for  $0.5 \text{ m} < y < 3 \text{ m}$ .



**Given:** Trapezoidal channel

**Find:** Derive expression for hydraulic radius; Plot  $R/y$  versus  $y$  for two different side slopes

**Solution:**

Available data  $b = 2 \cdot \text{m}$   $\alpha_1 = 30\text{-deg}$   $\alpha_2 = 60\text{-deg}$


The area is (from simple geometry of a rectangle and triangles)  $A = b \cdot y + 2 \cdot \frac{1}{2} \cdot y \cdot y \cdot \cot(\alpha) = y \cdot (b + y \cdot \cot(\alpha))$

The wetted perimeter is (from simple geometry)  $P = b + 2 \cdot \frac{y}{\sin(\alpha)}$

Hence the hydraulic radius is  $R = \frac{A}{P} = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + 2 \cdot \frac{y}{\sin(\alpha)}}$  which is the same as that listed in Table 11.1

We are to plot  $\frac{R}{y} = \frac{b + y \cdot \cot(\alpha)}{b + 2 \cdot \frac{y}{\sin(\alpha)}}$  with  $b = 2 \cdot \text{m}$  for  $\alpha = 30^\circ$  and  $60^\circ$ , and  $0.5 < y < 3 \text{ m}$ .

The graph is shown below; it can be plotted in *Excel*.



As the depth increases, the hydraulic radius becomes smaller relative to depth  $y$  - wetted perimeter becomes dominant over area

## Problem 11.2


[Difficulty: 2]

**11.2** Verify the equation given in Table 11.1 for the hydraulic radius of a circular channel. Evaluate and plot the ratio  $R/D$ , for liquid depths between 0 and  $D$ .

**Given:** Circular channel

**Find:** Derive expression for hydraulic radius; Plot  $R/D$  versus  $D$  for a range of depths

**Solution:**



The area is (from simple geometry - a segment of a circle plus two triangular sections)

$$A = \frac{D^2}{8} \cdot \alpha + 2 \cdot \frac{1}{2} \cdot \frac{D}{2} \cdot \sin\left(\pi - \frac{\alpha}{2}\right) \cdot \frac{D}{2} \cdot \cos\left(\pi - \frac{\alpha}{2}\right) = \frac{D^2}{8} \cdot \alpha + \frac{D^2}{4} \cdot \sin\left(\pi - \frac{\alpha}{2}\right) \cdot \cos\left(\pi - \frac{\alpha}{2}\right)$$

$$A = \frac{D^2}{8} \cdot \alpha + \frac{D^2}{8} \cdot \sin(2 \cdot \pi - \alpha) = \frac{D^2}{8} \cdot \alpha - \frac{D^2}{8} \cdot \sin(\alpha) = \frac{D^2}{8} \cdot (\alpha - \sin(\alpha))$$

The wetted perimeter is (from simple geometry)

$$P = \frac{D}{2} \cdot \alpha$$

Hence the hydraulic radius is  $R = \frac{A}{P} = \frac{\frac{D^2}{8} \cdot (\alpha - \sin(\alpha))}{\frac{D}{2} \cdot \alpha} = \frac{1}{4} \cdot \left(1 - \frac{\sin(\alpha)}{\alpha}\right) \cdot D$  which is the same as that listed in Table 11.1


We are to plot

$$\frac{R}{D} = \frac{1}{4} \cdot \left(1 - \frac{\sin(\alpha)}{\alpha}\right)$$

We will need  $y$  as a function of  $\alpha$ :

$$y = \frac{D}{2} + \frac{D}{2} \cdot \cos\left(\pi - \frac{\alpha}{2}\right) = \frac{D}{2} \cdot \left(1 - \cos\left(\frac{\alpha}{2}\right)\right) \quad \text{or} \quad \frac{y}{D} = \frac{1}{2} \cdot \left(1 - \cos\left(\frac{\alpha}{2}\right)\right)$$

The graph can be plotted in *Excel*.



## Problem 11.3

[Difficulty: 1]

---

**11.3** A wave from a passing boat in a lake is observed to travel at 10 mph. Determine the approximate water depth at this location.

---

**Given:** Wave from a passing boat

**Find:** Estimate of water depth

**Solution:**

Basic equation  $c = \sqrt{g \cdot y}$

Available data  $c = 10 \cdot \text{mph}$  or  $c = 14.7 \frac{\text{ft}}{\text{s}}$

We assume a shallow water wave (long wave compared to water depth)

$$c = \sqrt{g \cdot y} \quad \text{so} \quad y = \frac{c^2}{g} \quad y = 6.69 \text{ ft}$$

## Problem 11.4

[Difficulty: 1]

---

**11.4** A pebble is dropped into a stream of water that flows in a rectangular channel at 2 m depth. In one second, a ripple caused by the stone is carried 7 m downstream. What is the speed of the flowing water?

---

**Given:** Pebble dropped into flowing stream

**Find:** Estimate of water speed

**Solution:**

Basic equation  $c = \sqrt{g \cdot y}$  and relative speeds will be  $V_{\text{wave}} = V_{\text{stream}} + c$

Available data  $y = 2 \cdot \text{m}$  and  $V_{\text{wave}} = \frac{7 \cdot \text{m}}{1 \cdot \text{s}}$   $V_{\text{wave}} = 7 \frac{\text{m}}{\text{s}}$

We assume a shallow water wave (long wave compared to water depth)

$$c = \sqrt{g \cdot y} \quad \text{so} \quad c = 4.43 \frac{\text{m}}{\text{s}}$$

Hence  $V_{\text{stream}} = V_{\text{wave}} - c$   $V_{\text{stream}} = 2.57 \frac{\text{m}}{\text{s}}$

## Problem 11.5

[Difficulty: 2]

**11.5** A pebble is dropped into a stream of water of uniform depth. A wave is observed to travel upstream 5 ft in 1 s, and 13 ft downstream in the same time. Determine the flow speed and depth.

**Given:** Pebble dropped into flowing stream

**Find:** Estimate of water depth and speed

**Solution:**

Basic equation  $c = \sqrt{g \cdot y}$  and relative speeds will be  $V_{\text{wave}} = V_{\text{stream}} + c$

Available data  $V_{\text{waveupstream}} = \frac{-5 \cdot \text{ft}}{1 \cdot \text{s}}$   $V_{\text{waveupstream}} = -5 \frac{\text{ft}}{\text{s}}$

$V_{\text{wavedownstream}} = \frac{13 \cdot \text{ft}}{1 \cdot \text{s}}$   $V_{\text{wavedownstream}} = 13 \frac{\text{ft}}{\text{s}}$

But we have  $V_{\text{wavedownstream}} = V_{\text{stream}} + c$  and  $V_{\text{waveupstream}} = V_{\text{stream}} - c$

Adding  $V_{\text{stream}} = \frac{V_{\text{wavedownstream}} + V_{\text{waveupstream}}}{2}$   $V_{\text{stream}} = 4 \frac{\text{ft}}{\text{s}}$

Subtracting  $c = \frac{V_{\text{wavedownstream}} - V_{\text{waveupstream}}}{2}$   $c = 9 \frac{\text{ft}}{\text{s}}$

We assume a shallow water wave (long wave compared to water depth)

Hence  $c = \sqrt{g \cdot y}$  so  $y = \frac{c^2}{g}$   $y = 2.52 \cdot \text{ft}$

## Problem 11.6

[Difficulty: 3]

**11.6** Solution of the complete differential equations for wave motion without surface tension shows that wave speed is given by

$$c = \sqrt{\frac{g\lambda}{2\pi} \tanh\left(\frac{2\pi y}{\lambda}\right)}$$

where  $\lambda$  is the wave wavelength and  $y$  is the liquid depth. Show that when  $\lambda/y \ll 1$ , wave speed becomes proportional to  $\sqrt{\lambda}$ . In the limit as  $\lambda/y \rightarrow \infty$ ,  $V_w = \sqrt{gy}$ . Determine the value of  $\lambda/y$  for which  $V_w > 0.99\sqrt{gy}$ .

**Given:** Speed of surface waves with no surface tension

**Find:** Speed when  $\lambda/y$  approaches zero or infinity; Value of  $\lambda/y$  for which speed is 99% of this latter value

**Solution:**

Basic equation 
$$c = \sqrt{\frac{g\lambda}{2\pi \cdot \tanh\left(\frac{2\pi \cdot y}{\lambda}\right)}} \quad (1)$$

For  $\lambda/y \ll 1$   $\tanh\left(\frac{2\pi \cdot y}{\lambda}\right)$  approaches 1  $\tanh(\infty) \rightarrow 1$  so  $c = \sqrt{\frac{g\lambda}{2\pi}}$

Hence  $c$  is proportional to  $\sqrt{\lambda}$  so as  $\lambda/y$  approaches  $\infty$   $c = \sqrt{g \cdot y}$

We wish to find  $\lambda/y$  when  $c = 0.99 \cdot \sqrt{g \cdot y}$

Combining this with Eq 1 
$$0.99 \cdot \sqrt{g \cdot y} = \sqrt{\frac{g\lambda}{2\pi \cdot \tanh\left(\frac{2\pi \cdot y}{\lambda}\right)}} \quad \text{or} \quad 0.99^2 \cdot g \cdot y = \frac{g\lambda}{2\pi \cdot \tanh\left(\frac{2\pi \cdot y}{\lambda}\right)}$$

Hence 
$$0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi \cdot y}{\lambda}\right) = \frac{\lambda}{y} \quad \text{Letting } \lambda/y = x \quad \text{we find} \quad 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right) = x$$

This is a nonlinear equation in  $x$  that can be solved by iteration or using *Excel's Goal Seek* or *Solver*

x = 1	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 6.16	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 4.74
-------	--	----------	--	----------

x = 4.74	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.35	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.09
----------	--	----------	--	----------

x = 5.09	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.2	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.15
----------	--	---------	--	----------

x = 5.15	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.17	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.16
----------	--	----------	--	----------

x = 5.16	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.17	$x = 0.99^2 \cdot 2\pi \cdot \tanh\left(\frac{2\pi}{x}\right)$	x = 5.16
----------	--	----------	--	----------

Hence 
$$\frac{\lambda}{y} = 5.16$$

## Problem 11.7

[Difficulty: 1]

**11.7** Capillary waves (ripples) are small amplitude and wavelength waves, commonly seen, for example, when an insect or small particle hits the water surface. They are waves generated due to the interaction of the inertia force of the fluid  $\rho$  and the fluid surface tension  $\sigma$ . The wave speed is

$$c = 2\pi\sqrt{\frac{\sigma}{\rho g}}$$

Find the speed of capillary waves in water and mercury.

**Given:** Expression for capillary wave length

**Find:** Length of water and mercury waves

**Solution:**

Basic equation 
$$\lambda = 2 \cdot \pi \cdot \sqrt{\frac{\sigma}{\rho \cdot g}}$$

Available data Table A.2 (20°C)  $SG_{Hg} = 13.55$   $SG_w = 0.998$   $\rho = 1000 \cdot \frac{kg}{m^3}$

Table A.4 (20°C)  $\sigma_{Hg} = 484 \times 10^{-3} \cdot \frac{N}{m}$   $\sigma_w = 72.8 \times 10^{-3} \cdot \frac{N}{m}$

Hence 
$$\lambda_{Hg} = 2 \cdot \pi \cdot \sqrt{\frac{\sigma_{Hg}}{SG_{Hg} \cdot \rho \cdot g}}$$
  $\lambda_{Hg} = 12 \text{ mm}$   $\lambda_{Hg} = 0.472 \text{ in}$

$$\lambda_w = 2 \cdot \pi \cdot \sqrt{\frac{\sigma_w}{SG_w \cdot \rho \cdot g}}$$
  $\lambda_w = 17.1 \text{ mm}$   $\lambda_w = 0.675 \text{ in}$

## Problem 11.8

[Difficulty: 2]

**11.8** Solution of the complete differential equations for wave motion in quiescent liquid, including the effects of surface tension, shows that wave speed is given by

$$c = \sqrt{\left(\frac{g\lambda}{2\pi} + \frac{2\pi\sigma}{\rho\lambda}\right) \tanh\left(\frac{2\pi y}{\lambda}\right)}$$

where  $\lambda$  is the wave wavelength,  $y$  is the liquid depth, and  $\sigma$  is the surface tension. Plot wave speed versus wavelength for the range  $1 \text{ mm} < \lambda < 100 \text{ mm}$  for (a) water and (b) mercury. Assume  $y = 7 \text{ mm}$  for both liquids.

**Given:** Expression for surface wave speed

**Find:** Plot speed versus wavelength for water and mercury waves


**Solution:**

Basic equation 
$$c = \sqrt{\left(\frac{g\lambda}{2\pi} + \frac{2\pi\sigma}{\rho\lambda}\right) \cdot \tanh\left(\frac{2\pi y}{\lambda}\right)}$$

Available data      Table A.2 (20°C)                       $SG_{\text{Hg}} = 13.55$                        $SG_{\text{W}} = 0.998$                        $\rho = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$

Table A.4 (20°C)                       $\sigma_{\text{Hg}} = 484 \times 10^{-3} \cdot \frac{\text{N}}{\text{m}}$                        $\sigma_{\text{W}} = 72.8 \times 10^{-3} \cdot \frac{\text{N}}{\text{m}}$                        $y = 7 \cdot \text{mm}$


Hence 
$$c_{\text{W}}(\lambda) = \sqrt{\left(\frac{g\lambda}{2\pi} + \frac{2\pi\sigma_{\text{W}}}{SG_{\text{W}}\rho\lambda}\right) \cdot \tanh\left(\frac{2\pi y}{\lambda}\right)}$$
                      
$$c_{\text{Hg}}(\lambda) = \sqrt{\left(\frac{g\lambda}{2\pi} + \frac{2\pi\sigma_{\text{Hg}}}{SG_{\text{Hg}}\rho\lambda}\right) \cdot \tanh\left(\frac{2\pi y}{\lambda}\right)}$$



## Problem 11.9

[Difficulty: 1]

**11.9** Surface waves are caused by a sharp object that just touches the free surface of a stream of flowing water, forming the wave pattern shown. The stream depth is 150 mm. Determine the flow speed and Froude number. Note that the wave travels at speed  $c$  (Eq. 11.6) normal to the wave front, as shown in the velocity diagram.



**Given:** Sharp object causing waves

**Find:** Flow speed and Froude number

**Solution:**


Basic equation  $c = \sqrt{g \cdot y}$

Available data  $y = 150 \cdot \text{mm}$   $\theta = 30\text{-deg}$

We assume a shallow water wave (long wave compared to water depth)

$$c = \sqrt{g \cdot y} \quad \text{so} \quad c = 1.21 \frac{\text{m}}{\text{s}}$$

From geometry



Hence  $\sin(\theta) = \frac{c}{V}$  so  $V = \frac{c}{\sin(\theta)}$   $V = 2.43 \frac{\text{m}}{\text{s}}$

Also  $\text{Fr} = \frac{V}{c}$   $\text{Fr} = 2$  or  $\text{Fr} = \frac{1}{\sin(\theta)}$   $\text{Fr} = 2$

## Problem 11.10

[Difficulty: 2]

**11.10** The Froude number characterizes flow with a free surface. Plot on a log-log scale the speed versus depth for  $0.1 \text{ m/s} < V < 3 \text{ m/s}$  and  $0.001 < y < 1 \text{ m}$ ; plot the line  $Fr = 1$ , and indicate regions that correspond to tranquil and rapid flow.


**Given:** Shallow water waves

**Find:** Speed versus depth

**Solution:**

Basic equation  $c(y) = \sqrt{g \cdot y}$

We assume a shallow water wave (long wave compared to water depth)



## Problem 11.11

[Difficulty: 2]

**11.11** A submerged body traveling horizontally beneath a liquid surface at a Froude number (based on body length) about 0.5 produces a strong surface wave pattern if submerged less than half its length. (The wave pattern of a surface ship also is pronounced at this Froude number.) On a log-log plot of speed versus body (or ship) length for  $1 \text{ m/s} < V < 30 \text{ m/s}$  and  $1 \text{ m} < x < 300 \text{ m}$ , plot the line  $Fr = 0.5$ .

**Given:** Motion of submerged body

**Find:** Speed versus ship length


**Solution:**

Basic equation  $c = \sqrt{g \cdot y}$

We assume a shallow water wave (long wave compared to water depth)

In this case we want the Froude number to be 0.5, with  $Fr = 0.5 = \frac{V}{c}$  and  $c = \sqrt{g \cdot x}$  where  $x$  is the ship length

Hence  $V = 0.5 \cdot c = 0.5 \cdot \sqrt{g \cdot x}$



## Problem 11.12

[Difficulty: 1]

---

**11.12** Water flows in a rectangular channel at a depth of 750 mm. If the flow speed is (a) 1 m/s and (b) 4 m/s, compute the corresponding Froude numbers.

---

**Given:** Flow in a rectangular channel

**Find:** Froude numbers

**Solution:**

Basic equation 
$$Fr = \frac{V}{\sqrt{g \cdot y}}$$

Available data 
$$y = 750 \cdot \text{mm} \qquad V_1 = 1 \cdot \frac{\text{m}}{\text{s}} \qquad V_2 = 4 \cdot \frac{\text{m}}{\text{s}}$$

Hence 
$$Fr_1 = \frac{V_1}{\sqrt{g \cdot y}} \qquad Fr_1 = 0.369 \qquad \text{Subcritical flow}$$

$$Fr_2 = \frac{V_2}{\sqrt{g \cdot y}} \qquad Fr_2 = 1.47 \qquad \text{Supercritical flow}$$

## Problem 11.12

[Difficulty: 2]

**11.13** A long rectangular channel 10 ft wide is observed to have a wavy surface at a depth of about 6 ft. Estimate the rate of discharge.

**Given:** Flow in a rectangular channel with wavy surface

**Find:** Froude numbers

**Solution:**

Basic equation  $Fr = \frac{V}{\sqrt{g \cdot y}}$

Available data  $b = 10\text{-ft}$   $y = 6\text{-ft}$

A "wavy" surface indicates an unstable flow, which suggests critical flow  $Fr = 1$


Hence  $V = Fr \cdot \sqrt{g \cdot y}$   $V = 13.9 \frac{\text{ft}}{\text{s}}$

Then  $Q = V \cdot b \cdot y$   $Q = 834 \frac{\text{ft}^3}{\text{s}}$   $Q = 3.74 \times 10^5 \text{ gpm}$

## Problem 11.14

[Difficulty: 2]

**11.14** A partially open sluice gate in a 5-m-wide rectangular channel carries water at 10 m<sup>3</sup>/s. The upstream depth is 2.5 m. Find the downstream depth and Froude number.



**Given:** Data on sluice gate

**Find:** Downstream depth; Froude number

**Solution:**

Basic equation:  $\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2 + h$       The Bernoulli equation applies because we have steady, incompressible, frictionless flow.

Noting that  $p_1 = p_2 = p_{\text{atm}}$ , (1 = upstream, 2 = downstream) the Bernoulli equation becomes

$$\frac{V_1^2}{2 \cdot g} + y_1 = \frac{V_2^2}{2 \cdot g} + y_2$$

The given data is       $b = 5 \cdot \text{m}$        $y_1 = 2.5 \cdot \text{m}$        $Q = 10 \cdot \frac{\text{m}^3}{\text{s}}$

For mass flow       $Q = V \cdot A$       so       $V_1 = \frac{Q}{b \cdot y_1}$       and       $V_2 = \frac{Q}{b \cdot y_2}$

Using these in the Bernoulli equation       $\frac{\left(\frac{Q}{b \cdot y_1}\right)^2}{2 \cdot g} + y_1 = \frac{\left(\frac{Q}{b \cdot y_2}\right)^2}{2 \cdot g} + y_2$       (1)

The only unknown on the right is  $y_2$ . The left side evaluates to       $\frac{\left(\frac{Q}{b \cdot y_1}\right)^2}{2 \cdot g} + y_1 = 2.53 \text{ m}$

To find  $y_2$  we need to solve the non-linear equation. We must do this numerically; we may use the Newton method or similar, or *Excel's Solver* or *Goal Seek*. Here we iterate manually, starting with an arbitrary value less than  $y_1$ .

For       $y_2 = 0.25 \cdot \text{m}$        $\frac{\left(\frac{Q}{b \cdot y_2}\right)^2}{2 \cdot g} + y_2 = 3.51 \text{ m}$       For       $y_2 = 0.3 \cdot \text{m}$        $\frac{\left(\frac{Q}{b \cdot y_2}\right)^2}{2 \cdot g} + y_2 = 2.57 \text{ m}$

For       $y_2 = 0.305 \cdot \text{m}$        $\frac{\left(\frac{Q}{b \cdot y_2}\right)^2}{2 \cdot g} + y_2 = 2.50 \text{ m}$       For       $y_2 = 0.302 \cdot \text{m}$        $\frac{\left(\frac{Q}{b \cdot y_2}\right)^2}{2 \cdot g} + y_2 = 2.54 \text{ m}$

Hence       $y_2 = 0.302 \text{ m}$       is the closest to three figs.

Then       $V_2 = \frac{Q}{b \cdot y_2}$        $V_2 = 6.62 \frac{\text{m}}{\text{s}}$        $\text{Fr}_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$        $\text{Fr}_2 = 3.85$

## Problem 11.15

[Difficulty: 3]

**11.15** For a rectangular channel of width  $b = 20$  ft, construct a family of specific energy curves for  $Q = 0, 25, 75, 125,$  and  $200$  ft<sup>3</sup>/s. What are the minimum specific energies for these curves?

**Given:** Rectangular channel

**Find:** Plot of specific energy curves; Critical depths; Critical specific energy

**Solution:**


Given data:  $b = 20$  ft

Specific energy: 
$$E = y + \left( \frac{Q^2}{2gb^2} \right) \frac{1}{y^2}$$

Critical depth: 
$$y_c = \left( \frac{Q^2}{gb^2} \right)^{\frac{1}{3}}$$

Specific Energy, $E$ (ft lb/lb)					
$y$ (ft)	$Q = 0$	$Q = 25$	$Q = 75$	$Q = 125$	$Q = 200$
0.5	0.50	0.60	1.37	2.93	6.71
0.6	0.60	0.67	1.21	2.28	4.91
0.8	0.80	0.84	1.14	1.75	3.23
1.0	1.00	1.02	1.22	1.61	2.55
1.2	1.20	1.22	1.35	1.62	2.28
1.4	1.40	1.41	1.51	1.71	2.19
1.6	1.60	1.61	1.69	1.84	2.21
1.8	1.80	1.81	1.87	1.99	2.28
2.0	2.00	2.01	2.05	2.15	2.39
2.2	2.20	2.21	2.25	2.33	2.52
2.4	2.40	2.40	2.44	2.51	2.67
2.6	2.60	2.60	2.63	2.69	2.83
2.8	2.80	2.80	2.83	2.88	3.00
3.0	3.00	3.00	3.02	3.07	3.17
3.5	3.50	3.50	3.52	3.55	3.63
4.0	4.00	4.00	4.01	4.04	4.10
4.5	4.50	4.50	4.51	4.53	4.58
5.0	5.00	5.00	5.01	5.02	5.06


$y_c$ (ft)	<b>0.365</b>	<b>0.759</b>	<b>1.067</b>	<b>1.46</b>
$E_c$ (ft)	<b>0.547</b>	<b>1.14</b>	<b>1.60</b>	<b>2.19</b>



## Problem 11.16

[Difficulty: 1]

**11.16** Find the critical depth for flow at  $3 \text{ m}^3/\text{s}$  in a rectangular channel of width  $2.5 \text{ m}$ .



**Given:** Rectangular channel flow

**Find:** Critical depth

**Solution:**

Basic equations:

$$y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}}$$

Given data:

$$b = 2.5 \text{ m} \qquad Q = 3 \cdot \frac{\text{m}^3}{\text{s}}$$


Hence

$$y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}} \qquad y_c = 0.528 \text{ m}$$

## Problem 11.17

[Difficulty: 3]

**11.17** A trapezoidal channel with a bottom width of 20 ft, side slopes of 1 to 2, channel bottom slope of 0.0016, and a Manning's  $n$  of 0.025 carries a discharge of 400 cfs. Compute the critical depth and velocity of this channel.



**Given:** Data on trapezoidal channel

**Find:** Critical depth and velocity

**Solution:**

Basic equation: 
$$E = y + \frac{V^2}{2 \cdot g}$$

The given data is:  $b = 20\text{-ft}$      $\alpha = \text{atan}(2)$      $\alpha = 63.4\text{deg}$      $S_0 = 0.0016$      $n = 0.025$      $Q = 400 \frac{\text{ft}^3}{\text{s}}$

In terms of flow rate 
$$E = y + \frac{Q^2}{2 \cdot A^2 \cdot g}$$
    where (Table 11.1)     $A = y \cdot (b + y \cdot \cot(\alpha))$

Hence in terms of  $y$  
$$E = y + \frac{Q^2}{2 \cdot (b + y \cdot \cot(\alpha))^2 \cdot y^2 \cdot g}$$

For critical conditions 
$$\frac{dE}{dy} = 0 = 1 - \frac{Q^2}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^2} - \frac{Q^2 \cdot \cot(\alpha)}{g \cdot y^2 \cdot (b + y \cdot \cot(\alpha))^3} = 1 - \frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3}$$

Hence 
$$g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3 - Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha)) = 0$$

Let 
$$f(y) = g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3 - Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))$$

We can iterate or use *Excel's Goal Seek* or Solver to find  $y$  when  $f(y) = 0$

Guess     $y = 2\text{-ft}$      $f(y) = -1.14 \times 10^6 \frac{\text{ft}^7}{\text{s}^2}$      $y = 2.25\text{-ft}$      $f(y) = -1.05 \times 10^5 \frac{\text{ft}^7}{\text{s}^2}$      $y = 2.35\text{-ft}$      $f(y) = 3.88 \times 10^5 \frac{\text{ft}^7}{\text{s}^2}$

The solution is somewhere between  $y = 2.25$  ft and  $y = 2.35$  ft, as the sign of  $f(y)$  changes here.

$y = 2.3\text{-ft}$      $f(y) = 1.36 \times 10^5 \frac{\text{ft}^7}{\text{s}^2}$      $y = 2.275\text{-ft}$      $f(y) = 1.38 \times 10^4 \frac{\text{ft}^7}{\text{s}^2}$      $y = 2.272\text{-ft}$      $f(y) = -657 \frac{\text{ft}^7}{\text{s}^2}$


Hence critical depth is  $y = 2.27\text{-ft}$     and     $A = y \cdot (b + y \cdot \cot(\alpha))$      $A = 48.0 \text{ft}^2$

and critical speed is  $V = \frac{Q}{A}$      $V = 8.34 \cdot \frac{\text{ft}}{\text{s}}$

## Problem 11.18

[Difficulty: 2]

**11.18** A rectangular channel carries a discharge of  $10 \text{ ft}^3/\text{s}$  per foot of width. Determine the minimum specific energy possible for this flow. Compute the corresponding flow depth and speed.



**Given:** Data on rectangular channel

**Find:** Minimum specific energy; Flow depth; Speed

**Solution:**

Basic equation: 
$$E = y + \frac{V^2}{2 \cdot g}$$

In Section 11-2 we prove that the minimum specific energy is when we have critical flow; here we rederive the minimum energy point

For a rectangular channel 
$$Q = V \cdot b \cdot y \quad \text{or} \quad V = \frac{Q}{b \cdot y} \quad \text{with} \quad \frac{Q}{b} = 10 \cdot \frac{\text{ft}^3}{\text{s} \cdot \text{ft}} = \text{constant}$$

Hence, using this in the basic equation 
$$E = y + \left( \frac{Q}{b \cdot y} \right)^2 \cdot \frac{1}{2 \cdot g} = y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2}$$

E is a minimum when 
$$\frac{dE}{dy} = 1 - \left( \frac{Q^2}{b^2 \cdot g} \right) \cdot \frac{1}{y^3} = 0 \quad \text{or} \quad y = \left( \frac{Q^2}{b^2 \cdot g} \right)^{\frac{1}{3}} \quad y = 1.46 \cdot \text{ft}$$

The speed is then given by 
$$V = \frac{Q}{b \cdot y} \quad V = 6.85 \cdot \frac{\text{ft}}{\text{s}}$$


Note that from Eq. 11.22 we also have 
$$V_c = \left( \frac{g \cdot Q}{b} \right)^{\frac{1}{3}} \quad V_c = 6.85 \cdot \frac{\text{ft}}{\text{s}} \quad \text{which agrees with the above}$$

The minimum energy is then 
$$E_{\min} = y + \frac{V^2}{2 \cdot g} \quad E_{\min} = 2.19 \cdot \text{ft}$$

## Problem 11.19

[Difficulty: 3]

**11.19** Flow in the channel of Problem 11.18 ( $E_{\min} = 2.19$  ft) is to be at twice the minimum specific energy. Compute the alternate depths for this  $E$ .



**Given:** Data on rectangular channel

**Find:** Depths for twice the minimum energy

**Solution:**

Basic equation: 
$$E = y + \frac{V^2}{2 \cdot g}$$

For a rectangular channel  $Q = V \cdot b \cdot y$  or  $V = \frac{Q}{b \cdot y}$  with  $\frac{Q}{b} = 10 \cdot \frac{\text{ft}^3}{\text{s} \cdot \text{ft}} = \text{constant}$

Hence, using this in the basic eqn. 
$$E = y + \left( \frac{Q}{b \cdot y} \right)^2 \cdot \frac{1}{2 \cdot g} = y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2}$$
 and  $E = 2 \times 2.19 \cdot \text{ft} \quad E = 4.38 \cdot \text{ft}$

We have a nonlinear implicit equation for  $y$  
$$y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = E$$

This is a nonlinear implicit equation for  $y$  and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with a  $y$  larger than the critical, and evaluate the left side of the equation so that it is equal to  $E = 4.38$  ft

For  $y = 2 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 2.39 \cdot \text{ft}$       For  $y = 4 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 4.10 \cdot \text{ft}$

For  $y = 4.5 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 4.58 \cdot \text{ft}$       For  $y = 4.30 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 4.38 \cdot \text{ft}$

Hence  $y = 4.30 \cdot \text{ft}$

For the shallow depth

For  $y = 1 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 2.55 \cdot \text{ft}$       For  $y = 0.5 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 6.72 \cdot \text{ft}$


For  $y = 0.6 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 4.92 \cdot \text{ft}$       For  $y = 0.65 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 4.33 \cdot \text{ft}$

For  $y = 0.645 \cdot \text{ft}$   $y + \left( \frac{Q^2}{2 \cdot b^2 \cdot g} \right) \cdot \frac{1}{y^2} = 4.38 \cdot \text{ft}$       Hence  $y = 0.645 \cdot \text{ft}$

## Problem 11.20

[Difficulty: 2]

**11.20** For a channel of nonrectangular cross section, critical depth occurs at minimum specific energy. Obtain a general equation for critical depth in a trapezoidal section in terms of  $Q$ ,  $g$ ,  $b$ , and  $\theta$ . It will be implicit in  $y_c$ !



**Given:** Trapezoidal channel

**Find:** Critical depth

**Solution:**

Basic equation: 
$$E = y + \frac{V^2}{2 \cdot g}$$

The critical depth occurs when the specific energy is minimized

For a trapezoidal channel (Table 11.1)  $A = y \cdot (b + \cot(\alpha) \cdot y)$

Hence for  $V$  
$$V = \frac{Q}{A} = \frac{Q}{y \cdot (b + \cot(\alpha) \cdot y)}$$

Using this in Eq. 11.14 
$$E = y + \left[ \frac{Q}{y \cdot (b + \cot(\alpha) \cdot y)} \right]^2 \cdot \frac{1}{2 \cdot g}$$

$E$  is a minimum when 
$$\frac{dE}{dy} = 1 - \frac{Q^2 \cdot \cot(\alpha)}{g \cdot y^2 \cdot (b + y \cdot \cot(\alpha))^3} - \frac{Q^2}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^2} = 0$$

Hence we obtain for  $y$  
$$\frac{Q^2 \cdot \cot(\alpha)}{g \cdot y^2 \cdot (b + y \cdot \cot(\alpha))^3} + \frac{Q^2}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^2} = 1$$


This can be simplified to 
$$\frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3} = 1$$

This expression is the simplest one for  $y$ ; it is implicit

## Problem 11.21

[Difficulty: 3]

**11.21** Water flows at 400 ft<sup>3</sup>/s in a trapezoidal channel with bottom width of 10 ft. The sides are sloped at 3:1. Find the critical depth for this channel.



**Given:** Data on trapezoidal channel

**Find:** Critical depth

**Solution:**

Basic equation: 
$$E = y + \frac{V^2}{2 \cdot g}$$

In Section 11-2 we prove that the minimum specific energy is when we have critical flow; here we rederive the minimum energy point

For a trapezoidal channel (Table 11.1)  $A = (b + \cot(\alpha) \cdot y) \cdot y$  and  $b = 10 \cdot \text{ft}$   $\alpha = \text{atan}\left(\frac{3}{1}\right)$   $\alpha = 71.6 \text{ deg}$

Hence for V 
$$V = \frac{Q}{A} = \frac{Q}{(b + \cot(\alpha) \cdot y) \cdot y} \text{ and } Q = 400 \cdot \frac{\text{ft}^3}{\text{s}}$$

Using this in the basic equation 
$$E = y + \left[ \frac{Q}{(b + \cot(\alpha) \cdot y) \cdot y} \right]^2 \cdot \frac{1}{2 \cdot g}$$

E is a minimum when 
$$\frac{dE}{dy} = 1 - \frac{Q^2 \cdot \cot(\alpha)}{g \cdot y^2 \cdot (b + y \cdot \cot(\alpha))^3} - \frac{Q^2}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^2} = 0$$

Hence we obtain for y 
$$\frac{Q^2 \cdot \cot(\alpha)}{g \cdot y^2 \cdot (b + y \cdot \cot(\alpha))^3} + \frac{Q^2}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^2} = 1 \quad \text{or} \quad \frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3} = 1$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below, to make the left side equal unity

$y = 5 \cdot \text{ft} \quad \frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3} = 0.3$

$y = 4 \cdot \text{ft} \quad \frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3} = 0.7$

$y = 3.5 \cdot \text{ft} \quad \frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3} = 1.03$

$y = 3.55 \cdot \text{ft} \quad \frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3} = 0.98$


$y = 3.53 \cdot \text{ft} \quad \frac{Q^2 \cdot (b + 2 \cdot y \cdot \cot(\alpha))}{g \cdot y^3 \cdot (b + y \cdot \cot(\alpha))^3} = 1.00$

The critical depth is  $y = 3.53 \cdot \text{ft}$

## Problem 11.22

[2]

**11.22** Consider the Venturi flume shown. The bed is horizontal, and flow may be considered frictionless. The upstream depth is 1 ft, and the downstream depth is 0.75 ft. The upstream breadth is 2 ft, and the breadth of the throat is 1 ft. Estimate the flow rate through the flume.



**Given:** Data on venturi flume

**Find:** Flow rate

**Solution:**

Basic equation: 
$$\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2$$
 The Bernoulli equation applies because we have steady, incompressible, frictionless flow

At each section  $Q = V \cdot A = V \cdot b \cdot y$  or  $V = \frac{Q}{b \cdot y}$

The given data is  $b_1 = 2 \cdot \text{ft}$   $y_1 = 1 \cdot \text{ft}$   $b_2 = 1 \cdot \text{ft}$   $y_2 = 0.75 \cdot \text{ft}$


Hence the Bernoulli equation becomes (with  $p_1 = p_2 = p_{\text{atm}}$ ) 
$$\frac{\left(\frac{Q}{b_1 \cdot y_1}\right)^2}{2 \cdot g} + y_1 = \frac{\left(\frac{Q}{b_2 \cdot y_2}\right)^2}{2 \cdot g} + y_2$$

Solving for Q 
$$Q = \sqrt{\frac{2 \cdot g \cdot (y_1 - y_2)}{\left(\frac{1}{b_2 \cdot y_2}\right)^2 - \left(\frac{1}{b_1 \cdot y_1}\right)^2}}$$
 
$$Q = 3.24 \cdot \frac{\text{ft}^3}{\text{s}}$$

## Problem 11.23

[Difficulty: 3]

**11.23** A rectangular channel 10 ft wide carries 100 cfs on a horizontal bed at 1.0 ft depth. A smooth bump across the channel rises 4 in. above the channel bottom. Find the elevation of the liquid free surface above the bump.



**Given:** Data on rectangular channel and a bump

**Find:** Elevation of free surface above the bump

**Solution:**

Basic equation:  $\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2 + h$  The Bernoulli equation applies because we have steady, incompressible, frictionless flow. Note that at location 2 (the bump), the potential is  $y_2 + h$ , where  $h$  is the bump height

Recalling the specific energy  $E = \frac{V^2}{2 \cdot g} + y$  and noting that  $p_1 = p_2 = p_{\text{atm}}$ , the Bernoulli equation becomes  $E_1 = E_2 + h$

At each section  $Q = V \cdot A = V \cdot b \cdot y$  or  $V = \frac{Q}{b \cdot y}$

The given data is  $b = 10 \cdot \text{ft}$   $y_1 = 1 \cdot \text{ft}$   $h = 4 \cdot \text{in}$   $Q = 100 \cdot \frac{\text{ft}^3}{\text{s}}$

Hence we find  $V_1 = \frac{Q}{b \cdot y_1}$   $V_1 = 10 \cdot \frac{\text{ft}}{\text{s}}$

and  $E_1 = \frac{V_1^2}{2 \cdot g} + y_1$   $E_1 = 2.554 \cdot \text{ft}$

Hence  $E_1 = E_2 + h = \frac{V_2^2}{2 \cdot g} + y_2 + h = \frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 + h$  or  $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = E_1 - h$

This is a nonlinear implicit equation for  $y_2$  and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We select  $y_2$  so the left side of the equation equals  $E_1 - h = 2.22 \cdot \text{ft}$

For  $y_2 = 1 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 2.55 \cdot \text{ft}$  For  $y_2 = 1.5 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 2.19 \cdot \text{ft}$

For  $y_2 = 1.4 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 2.19 \cdot \text{ft}$  For  $y_2 = 1.3 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 2.22 \cdot \text{ft}$

Hence  $y_2 = 1.30 \cdot \text{ft}$

Note that  $V_2 = \frac{Q}{b \cdot y_2}$   $V_2 = 7.69 \cdot \frac{\text{ft}}{\text{s}}$

so we have  $Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$   $Fr_1 = 1.76$  and  $Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$   $Fr_2 = 1.19$

## Problem 11.24

[Difficulty: 3]

**11.24** A rectangular channel 10 ft wide carries a discharge of  $20 \text{ ft}^3/\text{s}$  at 1.0 ft depth. A smooth bump 0.25 ft high is placed on the floor of the channel. Estimate the local change in flow depth caused by the bump.

**Given:** Data on rectangular channel and a bump

**Find:** Local change in flow depth caused by the bump

**Solution:**

Basic equation:  $\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2 + h$  The Bernoulli equation applies because we have steady, incompressible, frictionless flow. Note that at location 2 (the bump), the potential is  $y_2 + h$ , where  $h$  is the bump height

Recalling the specific energy  $E = \frac{V^2}{2 \cdot g} + y$  and noting that  $p_1 = p_2 = p_{\text{atm}}$ , the Bernoulli equation becomes  $E_1 = E_2 + h$

At each section  $Q = V \cdot A = V \cdot b \cdot y$  or  $V = \frac{Q}{b \cdot y}$

The given data is  $b = 10 \cdot \text{ft}$   $y_1 = 1 \cdot \text{ft}$   $h = 0.25 \cdot \text{ft}$   $Q = 20 \cdot \frac{\text{ft}^3}{\text{s}}$

Hence we find  $V_1 = \frac{Q}{b \cdot y_1}$   $V_1 = 2 \cdot \frac{\text{ft}}{\text{s}}$

and  $E_1 = \frac{V_1^2}{2 \cdot g} + y_1$   $E_1 = 1.062 \cdot \text{ft}$

Hence  $E_1 = E_2 + h = \frac{V_2^2}{2 \cdot g} + y_2 + h = \frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 + h$  or  $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = E_1 - h$

This is a nonlinear implicit equation for  $y_2$  and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We select  $y_2$  so the left side of the equation equals  $E_1 - h = 0.812 \cdot \text{ft}$

For  $y_2 = 0.75 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.861 \cdot \text{ft}$  For  $y_2 = 0.7 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.827 \cdot \text{ft}$

For  $y_2 = 0.65 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.797 \cdot \text{ft}$  For  $y_2 = 0.676 \cdot \text{ft}$   $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.812 \cdot \text{ft}$

Hence  $y_2 = 0.676 \cdot \text{ft}$  and  $\frac{y_2 - y_1}{y_1} = -32.4\%$

Note that  $V_2 = \frac{Q}{b \cdot y_2}$   $V_2 = 2.96 \cdot \frac{\text{ft}}{\text{s}}$

so we have  $Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$   $Fr_1 = 0.353$  and  $Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$   $Fr_2 = 0.634$

## Problem 11.25

[Difficulty: 3]

**11.25** At a section of a 10-ft-wide rectangular channel, the depth is 0.3 ft for a discharge of 20 ft<sup>3</sup>/s. A smooth bump 0.1 ft high is placed on the floor of the channel. Determine the local change in flow depth caused by the bump.

**Given:** Data on rectangular channel and a bump

**Find:** Local change in flow depth caused by the bump

**Solution:**

Basic equation:  $\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2 + h$       The Bernoulli equation applies because we have steady, incompressible, frictionless flow. Note that at location 2 (the bump), the potential is  $y_2 + h$ , where  $h$  is the bump height

Recalling the specific energy  $E = \frac{V^2}{2 \cdot g} + y$  and noting that  $p_1 = p_2 = p_{\text{atm}}$ , the Bernoulli equation becomes  $E_1 = E_2 + h$

At each section  $Q = V \cdot A = V \cdot b \cdot y$       or       $V = \frac{Q}{b \cdot y}$

The given data is  $b = 10 \cdot \text{ft}$        $y_1 = 0.3 \cdot \text{ft}$        $h = 0.1 \cdot \text{ft}$        $Q = 20 \cdot \frac{\text{ft}^3}{\text{s}}$

Hence we find  $V_1 = \frac{Q}{b \cdot y_1}$        $V_1 = 6.67 \cdot \frac{\text{ft}}{\text{s}}$

and  $E_1 = \frac{V_1^2}{2 \cdot g} + y_1$        $E_1 = 0.991 \cdot \text{ft}$

Hence  $E_1 = E_2 + h = \frac{V_2^2}{2 \cdot g} + y_2 + h = \frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 + h$       or       $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = E_1 - h$

This is a nonlinear implicit equation for  $y_2$  and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We select  $y_2$  so the left side of the equation equals  $E_1 - h = 0.891 \cdot \text{ft}$

For  $y_2 = 0.3 \cdot \text{ft}$        $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.991 \cdot \text{ft}$       For  $y_2 = 0.35 \cdot \text{ft}$        $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.857 \cdot \text{ft}$

For  $y_2 = 0.33 \cdot \text{ft}$        $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.901 \cdot \text{ft}$       For  $y_2 = 0.334 \cdot \text{ft}$        $\frac{Q^2}{2 \cdot g \cdot b^2 \cdot y_2^2} + y_2 = 0.891 \cdot \text{ft}$

Hence  $y_2 = 0.334 \cdot \text{ft}$       and       $\frac{y_2 - y_1}{y_1} = 11.3 \cdot \%$


Note that  $V_2 = \frac{Q}{b \cdot y_2}$        $V_2 = 5.99 \cdot \frac{\text{ft}}{\text{s}}$

so we have  $Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$        $Fr_1 = 2.15$       and       $Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$        $Fr_2 = 1.83$

## Problem 11.26

[Difficulty: 3]

**11.26** Water, at 3 ft/s and 2 ft depth, approaches a smooth rise in a wide channel. Estimate the stream depth after the 0.5 ft rise.



**Given:** Data on wide channel

**Find:** Stream depth after rise

**Solution:**

Basic equation:  $\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2 + h$       The Bernoulli equation applies because we have steady, incompressible, frictionless flow. Note that at location 2 (the bump), the potential is  $y_2 + h$ , where  $h$  is the bump height

Recalling the specific energy  $E = \frac{V^2}{2 \cdot g} + y$  and noting that  $p_1 = p_2 = p_{atm}$ , the Bernoulli equation becomes  $E_1 = E_2 + h$

At each section  $Q = V \cdot A = V_1 \cdot b \cdot y_1 = V_2 \cdot b \cdot y_2$        $V_2 = V_1 \cdot \frac{y_1}{y_2}$

The given data is  $y_1 = 2 \cdot \text{ft}$        $V_1 = 3 \cdot \frac{\text{ft}}{\text{s}}$        $h = 0.5 \cdot \text{ft}$

Hence  $E_1 = \frac{V_1^2}{2 \cdot g} + y_1$        $E_1 = 2.14 \cdot \text{ft}$

Then  $E_1 = E_2 + h = \frac{V_2^2}{2 \cdot g} + y_2 + h = \frac{V_1^2 \cdot y_1^2}{2 \cdot g} \cdot \frac{1}{y_2^2} + y_2 + h$  or  $\frac{V_1^2 \cdot y_1^2}{2 \cdot g} \cdot \frac{1}{y_2^2} + y_2 = E_1 - h$

This is a nonlinear implicit equation for  $y_2$  and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We select  $y_2$  so the left side of the equation equals  $E_1 - h = 1.64 \cdot \text{ft}$

For  $y_2 = 2 \cdot \text{ft}$        $\frac{V_1^2 \cdot y_1^2}{2 \cdot g} \cdot \frac{1}{y_2^2} + y_2 = 2.14 \cdot \text{ft}$       For  $y_2 = 1.5 \cdot \text{ft}$        $\frac{V_1^2 \cdot y_1^2}{2 \cdot g} \cdot \frac{1}{y_2^2} + y_2 = 1.75 \cdot \text{ft}$

For  $y_2 = 1.3 \cdot \text{ft}$        $\frac{V_1^2 \cdot y_1^2}{2 \cdot g} \cdot \frac{1}{y_2^2} + y_2 = 1.63 \cdot \text{ft}$       For  $y_2 = 1.31 \cdot \text{ft}$        $\frac{V_1^2 \cdot y_1^2}{2 \cdot g} \cdot \frac{1}{y_2^2} + y_2 = 1.64 \cdot \text{ft}$

Hence  $y_2 = 1.31 \cdot \text{ft}$


Note that  $V_2 = V_1 \cdot \frac{y_1}{y_2}$        $V_2 = 4.58 \cdot \frac{\text{ft}}{\text{s}}$

so we have  $Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$        $Fr_1 = 0.37$       and       $Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$        $Fr_2 = 0.71$

## Problem 11.27

[Difficulty: 2]

**11.27** Water issues from a sluice gate at 1.25 m depth. The discharge per unit width is  $10 \text{ m}^3/\text{s}/\text{m}$ . Estimate the water level far upstream where the flow speed is negligible. Calculate the maximum rate of flow per unit width that could be delivered through the sluice gate.



**Given:** Data on sluice gate

**Find:** Water level upstream; Maximum flow rate

**Solution:**

Basic equation: 
$$\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2 + h$$
 The Bernoulli equation applies because we have steady, incompressible, frictionless flow.

Noting that  $p_1 = p_2 = p_{\text{atm}}$ , and  $V_1$  is approximately zero (1 = upstream, 2 = downstream) the Bernoulli equation becomes

$$y_1 = \frac{V_2^2}{2 \cdot g} + y_2$$

The given data is 
$$\frac{Q}{b} = 10 \cdot \frac{\text{m}^2}{\text{s}} \quad y_2 = 1.25 \cdot \text{m}$$

Hence 
$$Q = V_2 \cdot A_2 = V_2 \cdot b \cdot y_2 \quad \text{or} \quad V_2 = \frac{Q}{b \cdot y_2} \quad V_2 = 8 \frac{\text{m}}{\text{s}}$$

Then upstream 
$$y_1 = \left( \frac{V_2^2}{2 \cdot g} + y_2 \right) \quad y_1 = 4.51 \text{ m}$$

The maximum flow rate occurs at critical conditions (see Section 11-2), for constant specific energy

In this case 
$$V_2 = V_c = \sqrt{g \cdot y_c}$$

Hence we find 
$$y_1 = \frac{V_c^2}{2 \cdot g} + y_c = \frac{g \cdot y_c}{2 \cdot g} + y_c = \frac{3}{2} \cdot y_c$$


Hence 
$$y_c = \frac{2}{3} \cdot y_1 \quad y_c = 3.01 \text{ m} \quad V_c = \sqrt{g \cdot y_c} \quad V_c = 5.43 \frac{\text{m}}{\text{s}}$$

$$\frac{Q}{b} = V_c \cdot y_c \quad \frac{Q}{b} = 16.3 \cdot \frac{\text{m}^3}{\text{s}} \quad \text{(Maximum flow rate)}$$

## Problem 11.28

[Difficulty: 2]

**11.28** A horizontal rectangular channel 3 ft wide contains a sluice gate. Upstream of the gate the depth is 6 ft; the depth downstream is 0.9 ft. Estimate the volume flow rate in the channel.



**Given:** Data on sluice gate

**Find:** Flow rate

**Solution:**

Basic equation: 
$$\frac{p_1}{\rho \cdot g} + \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} + y_2$$

The Bernoulli equation applies because we have steady, incompressible, frictionless flow.

Noting that  $p_1 = p_2 = p_{\text{atm}}$ , (1 = upstream, 2 = downstream) the Bernoulli equation becomes

$$\frac{V_1^2}{2 \cdot g} + y_1 = \frac{V_2^2}{2 \cdot g} + y_2$$

The given data is  $b = 3 \cdot \text{ft}$                        $y_1 = 6 \cdot \text{ft}$                        $y_2 = 0.9 \cdot \text{ft}$

Also  $Q = V \cdot A$                       so  $V_1 = \frac{Q}{b \cdot y_1}$                       and                       $V_2 = \frac{Q}{b \cdot y_2}$

Using these in the Bernoulli equation 
$$\frac{\left(\frac{Q}{b \cdot y_1}\right)^2}{2 \cdot g} + y_1 = \frac{\left(\frac{Q}{b \cdot y_2}\right)^2}{2 \cdot g} + y_2$$

Solving for Q 
$$Q = \sqrt{\frac{2 \cdot g \cdot b^2 \cdot y_1^2 \cdot y_2^2}{y_1 + y_2}} \quad Q = 49.5 \cdot \frac{\text{ft}^3}{\text{s}}$$


Note that  $V_1 = \frac{Q}{b \cdot y_1}$                        $V_1 = 2.75 \cdot \frac{\text{ft}}{\text{s}}$                        $Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$                        $Fr_1 = 0.198$

$V_2 = \frac{Q}{b \cdot y_2}$                        $V_2 = 18.3 \cdot \frac{\text{ft}}{\text{s}}$                        $Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$                        $Fr_2 = 3.41$

## Problem 11.29

[Difficulty: 2]

**11.29** Flow through a sluice gate is shown. Estimate the water depth and velocity after the gate (well before the hydraulic jump).



**Given:** Data on sluice gate

**Find:** Water depth and velocity after gate

**Solution:**

Basic equation: 
$$E_1 = \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} = E_2$$

For the gate

$$\frac{y_3}{y_2} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_2^2} \right)$$

For the jump (state 2 before, state 3 after)

The given data is 
$$y_1 = 1.5 \cdot \text{m} \quad V_1 = 0.2 \cdot \frac{\text{m}}{\text{s}}$$

Hence 
$$q = y_1 \cdot V_1 \quad q = 0.3 \frac{\text{m}^2}{\text{s}} \quad E_1 = \frac{V_1^2}{2 \cdot g} + y_1 \quad E_1 = 1.50 \text{ m}$$

Then we need to solve 
$$\frac{V_2^2}{2 \cdot g} + y_2 = E_1 \quad \text{or} \quad \frac{q^2}{2 \cdot g \cdot y_2^2} + y_2 = E_1 \quad \text{with} \quad E_1 = 1.50 \text{ m}$$

We can solve this equation iteratively (or use *Excel's Goal Seek* or *Solver*)

For 
$$y_2 = 0.5 \cdot \text{m} \quad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 0.518 \text{ m} \quad \text{For} \quad y_2 = 0.05 \cdot \text{m} \quad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.89 \text{ m}$$

For 
$$y_2 = 0.055 \cdot \text{m} \quad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.57 \text{ m} \quad \text{For} \quad y_2 = 0.057 \cdot \text{m} \quad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.47 \text{ m}$$

For 
$$y_2 = 0.0563 \cdot \text{m} \quad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.50 \text{ m} \quad \text{Hence} \quad y_2 = 0.056 \text{ m} \quad \text{is the closest to three figs.}$$

Then 
$$V_2 = \frac{q}{y_2} \quad V_2 = 5.33 \frac{\text{m}}{\text{s}} \quad \text{Note that} \quad Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}} \quad Fr_2 = 7.17$$

## Problem 11.30

[Difficulty: 2]

**11.30** Rework Example 11.4 for a 350-mm-high bump and a side wall constriction that reduces the channel width to 1.5 m.

**Given:** Rectangular channel flow with hump and/or side wall restriction

**Find:** Whether critical flow occurs

**Solution:**

Basic equations:  $y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}}$        $E = y + \frac{Q^2}{2 \cdot g \cdot A^2}$        $A = b \cdot y$        $E_{\min} = \frac{3}{2} \cdot y_c$       (From Example 11.4)

Given data:       $b = 2 \cdot \text{m}$        $y = 1 \cdot \text{m}$        $h = 350 \cdot \text{mm}$        $Q = 2.4 \cdot \frac{\text{m}^3}{\text{s}}$

(a) For a hump with       $h = 35 \cdot \text{cm}$        $E_1 = y + \frac{Q^2}{2 \cdot g \cdot b^2} \cdot \frac{1}{y^2}$        $E_1 = 1.07 \text{ m}$

Then for the bump       $E_{\text{bump}} = E_1 - h$        $E_{\text{bump}} = 0.723 \text{ m}$       (1)

For the minimum specific energy       $y_c = \left[ \frac{\left( \frac{Q}{b} \right)^2}{g} \right]^{\frac{1}{3}}$        $y_c = 0.528 \text{ m}$        $E_{\min} = \frac{3}{2} \cdot y_c$        $E_{\min} = 0.791 \text{ m}$       (2)

Comparing Eqs. 1 and 2 we see that the bump IS sufficient for critical flow

(b) For the sidewall restriction with       $b_{\text{const}} = 1.5 \cdot \text{m}$       as in Example 11.4 we have       $E_{\text{const}} = E_1$        $E_{\text{const}} = 1.073 \text{ m}$       (3)

With  $b_{\text{const}}$ :       $y_c = \left[ \frac{\left( \frac{Q}{b_{\text{const}}} \right)^2}{g} \right]^{\frac{1}{3}}$        $y_c = 0.639 \text{ m}$        $E_{\text{minconst}} = \frac{3}{2} \cdot y_c$        $E_{\text{minconst}} = 0.959 \text{ m}$       (4)

Comparing Eqs. 3 and 4 we see that the constriction is NOT sufficient for critical flow

(c) For both, following Example 11.4       $E_{\text{both}} = E_1 - h$        $E_{\text{both}} = 0.723 \text{ m}$       (5)

$E_{\text{minboth}} = E_{\text{minconst}}$        $E_{\text{minboth}} = 0.959 \text{ m}$       (6)

Comparing Eqs. 5 and 6 we see that the bump AND constriction ARE sufficient for critical flow (not surprising, as the bump alone is sufficient!)

## Problem 11.31

[Difficulty: 2]

**11.31** Find the rate at which energy is being consumed (kW) by the hydraulic jump of Example 11.5. Is this sufficient to produce a significant temperature rise in the water?

**Given:** Hydraulic jump data

**Find:** Energy consumption; temperature rise

**Solution:**

Basic equations:  $P = \rho \cdot g \cdot H_1 \cdot Q$  (1)

$H_1$  is the head loss in m of fluid); multiplying by  $\rho g$  produces energy/vol; multiplying by  $Q$  produces energy/time, or power

$$U_{\text{rate}} = \rho \cdot Q \cdot c_{\text{H}_2\text{O}} \cdot \Delta T \quad (2)$$

$U_{\text{rate}}$  is the rate of increase of internal energy of the flow;  $c_{\text{H}_2\text{O}} \Delta T$  is the energy increase per unit mass due to a  $\Delta T$  temperature rise; multiplying by  $\rho Q$  converts to energy rise of the entire flow/time

Given data: From Example 11.5  $Q = 9.65 \cdot \frac{\text{m}^3}{\text{s}}$   $H_1 = 0.258 \cdot \text{m}$   $\rho = 999 \cdot \frac{\text{kg}}{\text{m}^3}$  and  $c_{\text{H}_2\text{O}} = 1 \cdot \frac{\text{kcal}}{\text{kg} \cdot \text{K}}$

From Eq. 1  $P = \rho \cdot g \cdot H_1 \cdot Q$   $P = 24.4 \text{ kW}$  a significant energy consumption

Equating Eqs. 1 and 2  $\rho \cdot g \cdot H_1 \cdot Q = \rho \cdot Q \cdot c_{\text{H}_2\text{O}} \cdot \Delta T$  or  $\Delta T = \frac{g \cdot H_1}{c_{\text{H}_2\text{O}}}$   $\Delta T = 6.043 \times 10^{-4} \Delta^\circ\text{C}$


The power consumed by friction is quite large, but the flow is very large, so the rise in temperature is insignificant.  
In English units:

$$P = 32.7 \text{ hp} \quad Q = 1.53 \times 10^5 \text{ gpm} \quad \Delta T = 1.088 \times 10^{-3} \Delta^\circ\text{F}$$

## Problem 11.32

[Difficulty: 2]

**11.32** A hydraulic jump occurs in a rectangular channel 4.0 m wide. The water depth before the jump is 0.4 m and 1.7 m after the jump. Compute the flow rate in the channel, the critical depth, and the head loss in the jump.



**Given:** Data on rectangular channel and hydraulic jump

**Find:** Flow rate; Critical depth; Head loss

**Solution:**

Basic equations: 
$$\frac{y_2}{y_1} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \quad H_1 = E_1 - E_2 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right) \quad y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}}$$

The given data is  $b = 4 \cdot \text{m}$   $y_1 = 0.4 \cdot \text{m}$   $y_2 = 1.7 \cdot \text{m}$

We can solve for  $Fr_1$  from the basic equation 
$$\sqrt{1 + 8 \cdot Fr_1^2} = 1 + 2 \cdot \frac{y_2}{y_1}$$

$$Fr_1 = \sqrt{\frac{\left(1 + 2 \cdot \frac{y_2}{y_1}\right)^2 - 1}{8}} \quad Fr_1 = 3.34 \quad \text{and} \quad Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$$

Hence  $V_1 = Fr_1 \cdot \sqrt{g \cdot y_1}$   $V_1 = 6.62 \frac{\text{m}}{\text{s}}$

Then  $Q = V_1 \cdot b \cdot y_1$   $Q = 10.6 \frac{\text{m}^3}{\text{s}}$

The critical depth is  $y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}}$   $y_c = 0.894 \text{ m}$

Also  $V_2 = \frac{Q}{b \cdot y_2}$   $V_2 = 1.56 \frac{\text{m}}{\text{s}}$   $Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$   $Fr_2 = 0.381$


The energy loss is  $H_1 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right)$   $H_1 = 0.808 \text{ m}$

Note that we could used  $H_1 = \frac{(y_2 - y_1)^3}{4 \cdot y_1 \cdot y_2}$   $H_1 = 0.808 \text{ m}$

## Problem 11.33

[Difficulty: 2]

**11.33** A wide channel carries  $10 \text{ m}^3/\text{s}$  per foot of width at a depth of 1 m at the toe of a hydraulic jump. Determine the depth of the jump and the head loss across it.



**Given:** Data on wide channel and hydraulic jump

**Find:** Jump depth; Head loss

**Solution:**

Basic equations: 
$$\frac{y_2}{y_1} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \quad H_1 = E_1 - E_2 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right)$$

The given data is 
$$\frac{Q}{b} = 10 \cdot \frac{\frac{\text{m}^3}{\text{s}}}{\text{m}} \quad y_1 = 1 \cdot \text{m}$$

Also 
$$Q = V \cdot A = V \cdot b \cdot y$$

Hence 
$$V_1 = \frac{Q}{b \cdot y_1} \quad V_1 = 10.0 \frac{\text{m}}{\text{s}} \quad Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}} \quad Fr_1 = 3.19$$

Then 
$$y_2 = \frac{y_1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \quad y_2 = 4.04 \text{ m}$$

$$V_2 = \frac{Q}{b \cdot y_2} \quad V_2 = 2.47 \frac{\text{m}}{\text{s}} \quad Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}} \quad Fr_2 = 0.393$$


The energy loss is 
$$H_1 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right) \quad H_1 = 1.74 \text{ m}$$

Note that we could use 
$$H_1 = \frac{(y_2 - y_1)^3}{4 \cdot y_1 \cdot y_2} \quad H_1 = 1.74 \text{ m}$$

## Problem 11.34

[Difficulty: 1]

**11.34** A hydraulic jump occurs in a wide horizontal channel. The discharge is  $2 \text{ m}^3/\text{s}$  per meter of width. The upstream depth is  $750 \text{ mm}$ . Determine the depth of the jump.



**Given:** Data on wide channel and hydraulic jump

**Find:** Jump depth

**Solution:**

Basic equations: 
$$\frac{y_2}{y_1} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right)$$

The given data is 
$$\frac{Q}{b} = 2 \cdot \frac{\frac{\text{m}^3}{\text{s}}}{\text{m}} \quad y_1 = 500 \cdot \text{mm}$$

Also 
$$Q = V \cdot A = V \cdot b \cdot y$$

Hence 
$$V_1 = \frac{Q}{b \cdot y_1} \quad V_1 = 4.00 \frac{\text{m}}{\text{s}} \quad Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}} \quad Fr_1 = 1.806$$


Then 
$$y_2 = \frac{y_1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \quad y_2 = 1.05 \cdot \text{m}$$

Note: 
$$V_2 = \frac{Q}{b \cdot y_2} \quad V_2 = 6.24 \cdot \frac{\text{ft}}{\text{s}} \quad Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}} \quad Fr_2 = 0.592$$

## Problem 11.35

[Difficulty: 2]

**11.35** A hydraulic jump occurs in a rectangular channel. The flow rate is  $200 \text{ ft}^3/\text{s}$ , and the depth before the jump is 1.2 ft. Determine the depth behind the jump and the head loss, if the channel is 10 ft wide.



**Given:** Data on wide channel and hydraulic jump

**Find:** Jump depth; Head loss

**Solution:**

Basic equations: 
$$\frac{y_2}{y_1} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \quad H_1 = E_1 - E_2 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right)$$

The given data is 
$$Q = 200 \cdot \frac{\text{ft}^3}{\text{s}} \quad b = 10 \text{ ft} \quad y_1 = 1.2 \text{ ft}$$

Also 
$$Q = V \cdot A = V \cdot b \cdot y$$

Hence 
$$V_1 = \frac{Q}{b \cdot y_1} \quad V_1 = 16.7 \cdot \frac{\text{ft}}{\text{s}} \quad Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}} \quad Fr_1 = 2.68$$

Then 
$$y_2 = \frac{y_1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \quad y_2 = 3.99 \text{ ft}$$

$$V_2 = \frac{Q}{b \cdot y_2} \quad V_2 = 5.01 \cdot \frac{\text{ft}}{\text{s}} \quad Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}} \quad Fr_2 = 0.442$$


The energy loss is 
$$H_1 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right) \quad H_1 = 1.14 \text{ ft}$$

Note that we could use 
$$H_1 = \frac{(y_2 - y_1)^3}{4 \cdot y_1 \cdot y_2} \quad H_1 = 1.14 \text{ ft}$$

## Problem 11.36

[Difficulty: 2]

**11.36** The hydraulic jump may be used as a crude flow meter. Suppose that in a horizontal rectangular channel 5 ft wide the observed depths before and after a hydraulic jump are 0.66 and 3.0 ft. Find the rate of flow and the head loss.



**Given:** Data on wide channel and hydraulic jump

**Find:** Flow rate; Head loss

**Solution:**

Basic equations: 
$$\frac{y_2}{y_1} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \quad H_1 = E_1 - E_2 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right)$$

The given data is  $b = 5 \text{ ft}$

$$y_1 = 0.66 \text{ ft}$$

$$y_2 = 3.0 \text{ ft}$$

We can solve for  $Fr_1$  from the basic equation

$$\sqrt{1 + 8 \cdot Fr_1^2} = 1 + 2 \cdot \frac{y_2}{y_1}$$

$$Fr_1 = \sqrt{\frac{\left( 1 + 2 \cdot \frac{y_2}{y_1} \right)^2 - 1}{8}}$$

$$Fr_1 = 3.55$$

and

$$Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$$

Hence

$$V_1 = Fr_1 \cdot \sqrt{g \cdot y_1}$$

$$V_1 = 16.4 \frac{\text{ft}}{\text{s}}$$

Then

$$Q = V_1 \cdot b \cdot y_1$$

$$Q = 54.0 \frac{\text{ft}^3}{\text{s}}$$

Also

$$V_2 = \frac{Q}{b \cdot y_2}$$

$$V_2 = 3.60 \frac{\text{ft}}{\text{s}}$$

$$Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}}$$

$$Fr_2 = 0.366$$

The energy loss is 
$$H_1 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right)$$

$$H_1 = 1.62 \text{ ft}$$

Note that we could use


$$H_1 = \frac{(y_2 - y_1)^3}{4 \cdot y_1 \cdot y_2}$$

$$H_1 = 1.62 \text{ ft}$$

## Problem 11.37

[Difficulty: 2]

**11.37** A hydraulic jump occurs on a horizontal apron downstream from a wide spillway, at a location where depth is 0.9 m and speed is 25 m/s. Estimate the depth and speed downstream from the jump. Compare the specific energy downstream of the jump to that upstream.



**Given:** Data on wide spillway flow

**Find:** Depth after hydraulic jump; Specific energy change

**Solution:**

Basic equations: 
$$\frac{y_2}{y_1} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right)$$
 
$$H_l = E_1 - E_2 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right)$$

The given data is 
$$y_1 = 0.9 \cdot \text{m}$$
 
$$V_1 = 25 \frac{\text{m}}{\text{s}}$$

Then  $Fr_1$  is 
$$Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}}$$
 
$$Fr_1 = 8.42$$

Hence 
$$y_2 = \frac{y_1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right)$$
 
$$y_2 = 10.3 \text{ m}$$

Then 
$$Q = V_1 \cdot b \cdot y_1 = V_2 \cdot b \cdot y_2$$
 
$$V_2 = V_1 \cdot \frac{y_1}{y_2}$$
 
$$V_2 = 2.19 \frac{\text{m}}{\text{s}}$$

For the specific energies 
$$E_1 = y_1 + \frac{V_1^2}{2 \cdot g}$$
 
$$E_1 = 32.8 \text{ m}$$

$$E_2 = y_2 + \frac{V_2^2}{2 \cdot g}$$

$$E_2 = 10.5 \text{ m}$$

$$\frac{E_2}{E_1} = 0.321$$


The energy loss is 
$$H_l = E_1 - E_2$$
 
$$H_l = 22.3 \text{ m}$$

Note that we could use 
$$H_l = \frac{(y_2 - y_1)^3}{4 \cdot y_1 \cdot y_2}$$
 
$$H_l = 22.3 \cdot \text{m}$$

## Problem 11.38

[Difficulty: 2]

**11.38** A hydraulic jump occurs in a rectangular channel. The flow rate is  $50 \text{ m}^3/\text{s}$ , and the depth before the jump is  $2 \text{ m}$ . Determine the depth after the jump and the head loss, if the channel is  $1 \text{ m}$  wide.



**Given:** Data on rectangular channel flow

**Find:** Depth after hydraulic jump; Specific energy change

**Solution:**

Basic equations: 
$$\frac{y_2}{y_1} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right)$$
 
$$H_1 = E_1 - E_2 = \left( y_1 + \frac{V_1^2}{2 \cdot g} \right) - \left( y_2 + \frac{V_2^2}{2 \cdot g} \right)$$

The given data is 
$$y_1 = 0.4 \text{ m} \qquad b = 1 \text{ m} \qquad Q = 6.5 \frac{\text{m}^3}{\text{s}}$$

Then 
$$Q = V_1 \cdot b \cdot y_1 = V_2 \cdot b \cdot y_2 \qquad V_1 = \frac{Q}{b \cdot y_1} \qquad V_1 = 16.3 \frac{\text{m}}{\text{s}}$$

Then  $Fr_1$  is 
$$Fr_1 = \frac{V_1}{\sqrt{g \cdot y_1}} \qquad Fr_1 = 8.20$$

Hence 
$$y_2 = \frac{y_1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_1^2} \right) \qquad y_2 = 4.45 \text{ m}$$

and 
$$V_2 = \frac{Q}{b \cdot y_2} \qquad V_2 = 1.46 \frac{\text{m}}{\text{s}}$$

For the specific energies 
$$E_1 = y_1 + \frac{V_1^2}{2 \cdot g} \qquad E_1 = 13.9 \text{ m}$$

$$E_2 = y_2 + \frac{V_2^2}{2 \cdot g} \qquad E_2 = 4.55 \text{ m}$$


The energy loss is 
$$H_1 = E_1 - E_2 \qquad H_1 = 9.31 \text{ m}$$

Note that we could use 
$$H_1 = \frac{(y_2 - y_1)^3}{4 \cdot y_1 \cdot y_2} \qquad H_1 = 9.31 \text{ m}$$

## Problem 11.39

[Difficulty: 3]

**11.39** Estimate the depth of water before and after the jump for the hydraulic jump downstream of the sluice gate of Fig. P11.29.



**Given:** Data on sluice gate

**Find:** Water depth before and after the jump

**Solution:**

Basic equation: 
$$E_1 = \frac{V_1^2}{2 \cdot g} + y_1 = \frac{p_2}{\rho \cdot g} + \frac{V_2^2}{2 \cdot g} = E_2$$

For the gate

$$\frac{y_3}{y_2} = \frac{1}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_2^2} \right)$$

For the jump (state 2 before, state 3 after)

The given data is 
$$y_1 = 1.5 \cdot \text{m} \qquad V_1 = 0.2 \cdot \frac{\text{m}}{\text{s}}$$

Hence 
$$q = y_1 \cdot V_1 \qquad q = 0.3 \frac{\text{m}^2}{\text{s}} \qquad E_1 = \frac{V_1^2}{2 \cdot g} + y_1 \qquad E_1 = 1.50 \text{ m}$$

Then we need to solve 
$$\frac{V_2^2}{2 \cdot g} + y_2 = E_1 \qquad \text{or} \qquad \frac{q^2}{2 \cdot g \cdot y_2^2} + y_2 = E_1 \qquad \text{with} \qquad E_1 = 1.50 \text{ m}$$

We can solve this equation iteratively (or use *Excel's Goal Seek* or *Solver*)

For 
$$y_2 = 0.5 \cdot \text{m} \qquad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 0.518 \text{ m} \qquad \text{For} \qquad y_2 = 0.05 \cdot \text{m} \qquad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.89 \text{ m}$$

For 
$$y_2 = 0.055 \cdot \text{m} \qquad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.57 \text{ m} \qquad \text{For} \qquad y_2 = 0.057 \cdot \text{m} \qquad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.47 \text{ m}$$

For 
$$y_2 = 0.0563 \cdot \text{m} \qquad \frac{\left(\frac{q}{y_2}\right)^2}{2 \cdot g} + y_2 = 1.50 \text{ m} \qquad \text{Hence} \qquad y_2 = 0.056 \text{ m} \qquad \text{is the closest to three figs.}$$


Then 
$$V_2 = \frac{q}{y_2} \qquad V_2 = 5.33 \frac{\text{m}}{\text{s}} \qquad \text{Note that} \qquad Fr_2 = \frac{V_2}{\sqrt{g \cdot y_2}} \qquad Fr_2 = 7.17$$

For the jump (States 2 to 3) 
$$y_3 = \frac{y_2}{2} \cdot \left( -1 + \sqrt{1 + 8 \cdot Fr_2^2} \right) \qquad y_3 = 0.544 \text{ m}$$

## Problem 11.40

[Difficulty: 3]

**11.40** A positive surge wave, or moving hydraulic jump, can be produced in the laboratory by suddenly opening a sluice gate. Consider a surge of depth  $y_2$  advancing into a quiescent channel of depth  $y_1$ . Obtain an expression for surge speed in terms of  $y_1$  and  $y_2$




**Given:** Surge wave

**Find:** Surge speed

**Solution:**

Basic equations: 
$$\frac{V_1^2 \cdot y_1}{g} + \frac{y_1^2}{2} = \frac{V_2^2 \cdot y_2}{g} + \frac{y_2^2}{2}$$



(This is the basic momentum equation for the flow)

$$V_1 \cdot y_1 = V_2 \cdot y_2 \quad \text{or} \quad \frac{V_1}{V_2} = \frac{y_2}{y_1}$$

Then 
$$y_2^2 - y_1^2 = \frac{2}{g} \cdot (V_1^2 \cdot y_1 - V_2^2 \cdot y_2) = \frac{2 \cdot V_2^2}{g} \cdot \left[ \left( \frac{V_1}{V_2} \right)^2 \cdot y_1 - y_2 \right] = \frac{2 \cdot V_2^2}{g} \cdot \left[ \left( \frac{y_2}{y_1} \right)^2 \cdot y_1 - y_2 \right]$$

$$y_2^2 - y_1^2 = \frac{2 \cdot V_2^2}{g} \cdot \left( \frac{y_2^2}{y_1} - y_2 \right) = \frac{2 \cdot V_2^2 \cdot y_2}{g} \cdot \frac{(y_2 - y_1)}{y_1}$$

Dividing by  $(y_2 - y_1)$  
$$y_2 + y_1 = 2 \cdot \frac{V_2^2}{g} \cdot \frac{y_2}{y_1} \quad \text{or} \quad V_2^2 = \frac{g}{2} \cdot y_1 \cdot \frac{(y_2 + y_1)}{y_2}$$


$$V_2 = \sqrt{\frac{g \cdot y_1}{2} \cdot \left( 1 + \frac{y_1}{y_2} \right)}$$

But 
$$V_2 = V_{\text{Surge}} \quad \text{so} \quad V_{\text{Surge}} = \sqrt{\frac{g \cdot y_1}{2} \cdot \left( 1 + \frac{y_1}{y_2} \right)}$$

## Problem 11.41

[Difficulty: 3]

**11.41** A tidal bore (an abrupt translating wave or moving hydraulic jump) often forms when the tide flows into the wide estuary of a river. In one case, a bore is observed to have a height of 12 ft above the undisturbed level of the river that is 8 ft deep. The bore travels upstream at  $V_{bore} = 18$  mph. Determine the approximate speed  $V_r$  of the current of the undisturbed river.




**Given:** Tidal bore

**Find:** Speed of undisturbed river

**Solution:**

Basic equations: 
$$\frac{V_2^2 \cdot y_2}{g} + \frac{y_2^2}{2} = \frac{V_1^2 \cdot y_1}{g} + \frac{y_1^2}{2}$$



(This is the basic momentum equation for the flow)

$$V_2 \cdot y_2 = V_1 \cdot y_1 \quad \text{or} \quad \frac{V_2}{V_1} = \frac{y_1}{y_2}$$

Given data  $V_{bore} = 18 \cdot \text{mph}$      $V_{bore} = 26.4 \cdot \frac{\text{ft}}{\text{s}}$      $y_1 = 8 \cdot \text{ft}$      $y_2 = y_1 + 12 \cdot \text{ft}$      $y_2 = 20 \cdot \text{ft}$

Then 
$$y_1^2 - y_2^2 = \frac{2}{g} \cdot (V_2^2 \cdot y_2 - V_1^2 \cdot y_1) = \frac{2 \cdot V_1^2}{g} \cdot \left[ \left( \frac{V_2}{V_1} \right)^2 \cdot y_2 - y_1 \right] = \frac{2 \cdot V_1^2}{g} \cdot \left[ \left( \frac{y_1}{y_2} \right)^2 \cdot y_2 - y_1 \right]$$

$$y_1^2 - y_2^2 = \frac{2 \cdot V_1^2}{g} \cdot \left( \frac{y_1^2}{y_2} - y_1 \right) = \frac{2 \cdot V_1^2 \cdot y_1}{g} \cdot \frac{(y_1 - y_2)}{y_2}$$

Dividing by  $(y_2 - y_1)$   $y_1 + y_2 = 2 \cdot \frac{V_1^2}{g} \cdot \frac{y_1}{y_2}$     or     $V_1^2 = \frac{g}{2} \cdot y_2 \cdot \frac{(y_1 + y_2)}{y_1}$


$$V_1 = \sqrt{\frac{g \cdot y_2}{2} \cdot \left( 1 + \frac{y_2}{y_1} \right)} \quad V_1 = 33.6 \cdot \frac{\text{ft}}{\text{s}} \quad V_1 = 22.9 \cdot \text{mph}$$

But  $V_1 = V_r + V_{bore}$     or     $V_r = V_1 - V_{bore}$      $V_r = 7.16 \cdot \frac{\text{ft}}{\text{s}}$      $V_r = 4.88 \cdot \text{mph}$

## Problem 11.42

[Difficulty: 1]

**11.42** A 2-m-wide rectangular channel with a bed slope of 0.0005 has a depth of flow of 1.5 m. Manning's roughness coefficient is 0.015. Determine the steady uniform discharge in the channel.



**Given:** Rectangular channel flow

**Find:** Discharge

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For a rectangular channel of width  $b = 2 \cdot \text{m}$  and depth  $y = 1.5 \cdot \text{m}$  we find from Table 11.1

$$A = b \cdot y \quad A = 3.00 \cdot \text{m}^2 \quad R_h = \frac{b \cdot y}{b + 2 \cdot y} \quad R_h = 0.600 \cdot \text{m}$$


Manning's roughness coefficient is  $n = 0.015$  and  $S_b = 0.0005$

$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} \quad Q = 3.18 \cdot \frac{\text{m}^3}{\text{s}}$$

## Problem 11.43

[Difficulty: 3]

**11.43** Determine the uniform flow depth in a rectangular channel 2.5 m wide with a discharge of 3 m<sup>3</sup>/s. The slope is 0.0004 and Manning's roughness factor is 0.015.



**Given:** Data on rectangular channel

**Find:** Depth of flow

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For a rectangular channel of width  $b = 2.5$  m and flow rate  $Q = 3 \cdot \frac{\text{m}^3}{\text{s}}$  we find from Table 11.1  $A = b \cdot y$   $R = \frac{b \cdot y}{b + 2 \cdot y}$

Manning's roughness coefficient is  $n = 0.015$  and  $S_b = 0.0004$

Hence the basic equation becomes 
$$Q = \frac{1}{n} \cdot b \cdot y \cdot \left( \frac{b \cdot y}{b + 2 \cdot y} \right)^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Solving for y 
$$y \cdot \left( \frac{b \cdot y}{b + 2 \cdot y} \right)^{\frac{2}{3}} = \frac{Q \cdot n}{b \cdot S_b^{\frac{1}{2}}}$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below, to make the

left side evaluate to  $\frac{Q \cdot n}{b \cdot S_b^{\frac{1}{2}}} = 0.900$  .

For  $y = 1$  (m)  $y \cdot \left( \frac{b \cdot y}{b + 2 \cdot y} \right)^{\frac{2}{3}} = 0.676$       For  $y = 1.2$  (m)  $y \cdot \left( \frac{b \cdot y}{b + 2 \cdot y} \right)^{\frac{2}{3}} = 0.865$


For  $y = 1.23$  (m)  $y \cdot \left( \frac{b \cdot y}{b + 2 \cdot y} \right)^{\frac{2}{3}} = 0.894$       For  $y = 1.24$  (m)  $y \cdot \left( \frac{b \cdot y}{b + 2 \cdot y} \right)^{\frac{2}{3}} = 0.904$

The solution to three figures is  $y = 1.24$  (m)

## Problem 11.44

[Difficulty: 3]

**11.44** Determine the uniform flow depth in a trapezoidal channel with a bottom width of 8 ft and side slopes of 1 vertical to 2 horizontal. The discharge is 100 ft<sup>3</sup>/s. Manning's roughness factor is 0.015 and the channel bottom slope is 0.0004.



**Given:** Data on trapezoidal channel

**Find:** Depth of flow

**Solution:**

Basic equation: 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $b = 8 \text{ ft}$        $\alpha = \text{atan}\left(\frac{1}{2}\right) = 26.6 \text{ deg}$        $Q = 100 \frac{\text{ft}^3}{\text{s}}$        $S_0 = 0.0004$

$n = 0.015$

Hence from Table 11.1  $A = y \cdot (b + y \cdot \cot(\alpha)) = y \cdot (8 + 2 \cdot y)$        $R_h = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\sin(\alpha)}} = \frac{y \cdot (8 + 2 \cdot y)}{8 + 2 \cdot y \cdot \sqrt{5}}$

Hence 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1.49}{0.015} \cdot y \cdot (8 + 2 \cdot y) \cdot \left[ \frac{y \cdot (8 + 2 \cdot y)}{8 + 2 \cdot y \cdot \sqrt{5}} \right]^{\frac{2}{3}} \cdot 0.0004^{\frac{1}{2}} = 100 \text{ (Note that we don't use units!)}$$

Solving for y 
$$\frac{[y \cdot (8 + 2 \cdot y)]^{\frac{5}{3}}}{(8 + 2 \cdot y \cdot \sqrt{5})^3} = 50.3$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below.

For  $y = 2$  (ft) 
$$\frac{[y \cdot (8 + 2 \cdot y)]^{\frac{5}{3}}}{(8 + 2 \cdot y \cdot \sqrt{5})^3} = 30.27$$
      For  $y = 3$  (ft) 
$$\frac{[y \cdot (8 + 2 \cdot y)]^{\frac{5}{3}}}{(8 + 2 \cdot y \cdot \sqrt{5})^3} = 65.8$$

For  $y = 2.6$  (ft) 
$$\frac{[y \cdot (8 + 2 \cdot y)]^{\frac{5}{3}}}{(8 + 2 \cdot y \cdot \sqrt{5})^3} = 49.81$$
      For  $y = 2.61$  (ft) 
$$\frac{[y \cdot (8 + 2 \cdot y)]^{\frac{5}{3}}}{(8 + 2 \cdot y \cdot \sqrt{5})^3} = 50.18$$


The solution to three figures is

$y = 2.61$  (ft)

## Problem 11.45

[Difficulty: 3]

**11.45** Determine the uniform flow depth in a trapezoidal channel with a bottom width of 2.5 m and side slopes of 1 vertical to 2 horizontal with a discharge of 3 m<sup>3</sup>/s. The slope is 0.0004 and Manning's roughness factor is 0.015.



**Given:** Data on trapezoidal channel

**Find:** Depth of flow

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $b = 2.5 \text{ m}$      $\alpha = \text{atan}\left(\frac{1}{2}\right)$      $\alpha = 26.6 \text{ deg}$      $Q = 3 \cdot \frac{\text{m}^3}{\text{s}}$      $S_0 = 0.0004$

$n = 0.015$

Hence from Table 11.1  $A = y \cdot (b + \cot(\alpha) \cdot y) = y \cdot (2.5 + 2 \cdot y)$      $R = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\cot(\alpha)}} = \frac{y \cdot (2.5 + 2 \cdot y)}{2.5 + 2 \cdot y \cdot \sqrt{5}}$

Hence 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{0.015} \cdot y \cdot (2.5 + 2 \cdot y) \cdot \left[ \frac{(2.5 + 2 \cdot y) \cdot y}{2.5 + 2 \cdot y \cdot \sqrt{5}} \right]^{\frac{2}{3}} \cdot 0.0004^{\frac{1}{2}} = 3 \quad (\text{Note that we don't use units!})$$

Solving for y 
$$\frac{[y \cdot (2.5 + 2 \cdot y)]^{\frac{5}{3}}}{(2.5 + 2 \cdot y \cdot \sqrt{5})^3} = 2.25$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below.

For  $y = 1 \text{ (m)}$      $\frac{[y \cdot (2.5 + 2 \cdot y)]^{\frac{5}{3}}}{(2.5 + 2 \cdot y \cdot \sqrt{5})^3} = 3.36$     For  $y = 0.8 \text{ (m)}$      $\frac{[y \cdot (2.5 + 2 \cdot y)]^{\frac{5}{3}}}{(2.5 + 2 \cdot y \cdot \sqrt{5})^3} = 2.17$


For  $y = 0.81 \text{ (m)}$      $\frac{[y \cdot (2.5 + 2 \cdot y)]^{\frac{5}{3}}}{(2.5 + 2 \cdot y \cdot \sqrt{5})^3} = 2.23$     For  $y = 0.815 \text{ (m)}$      $\frac{[y \cdot (2.5 + 2 \cdot y)]^{\frac{5}{3}}}{(2.5 + 2 \cdot y \cdot \sqrt{5})^3} = 2.25$

The solution to three figures is  $y = 0.815 \text{ (m)}$

## Problem 11.46

[Difficulty: 1]

**11.46** A rectangular flume built of concrete, with 1 ft per 1000 ft slope, is 6 ft wide. Water flows at a normal depth of 3 ft. Compute the discharge.



**Given:** Data on flume

**Find:** Discharge

**Solution:**

Basic equation: 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For a rectangular channel of width  $b = 6 \cdot \text{ft}$  and depth  $y = 3 \cdot \text{ft}$  we find from Table 11.1

$$A = b \cdot y \qquad A = 18 \cdot \text{ft}^2 \qquad R_h = \frac{b \cdot y}{b + 2 \cdot y} \qquad R_h = 1.50 \cdot \text{ft}$$


For concrete (Table 11.2)  $n = 0.013$  and  $S_b = \frac{1 \cdot \text{ft}}{1000 \cdot \text{ft}} \qquad S_b = 0.001$

$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} \qquad Q = 85.5 \cdot \frac{\text{ft}^3}{\text{s}}$$

## Problem 11.47

[Difficulty: 1]

**11.47** A rectangular flume built of timber is 3 ft wide. The flume is to handle a flow of  $90 \text{ ft}^3/\text{s}$  at a normal depth of 6 ft. Determine the slope required.



**Given:** Data on flume

**Find:** Slope

**Solution:**

Basic equation: 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For a rectangular channel of width  $b = 3 \cdot \text{ft}$  and depth  $y = 6 \cdot \text{ft}$  we find

$$A = b \cdot y \quad A = 18 \cdot \text{ft}^2 \quad R_h = \frac{b \cdot y}{b + 2 \cdot y} \quad R_h = 1.20 \cdot \text{ft}$$


For wood (not in Table 11.2) a Google search finds  $n = 0.012$  to  $0.017$ ; we use  $n = 0.0145$  with  $Q = 90 \cdot \frac{\text{ft}^3}{\text{s}}$

$$S_b = \left( \frac{n \cdot Q}{1.49 \cdot A \cdot R_h^{\frac{2}{3}}} \right)^2 \quad S_b = 1.86 \times 10^{-3}$$

## Problem 11.48

[Difficulty: 2]

**11.48** A channel with square cross section is to carry  $20 \text{ m}^3/\text{s}$  of water at normal depth on a slope of 0.003. Compare the dimensions of the channel required for (a) concrete and (b) soil cement.



**Given:** Data on square channel

**Find:** Dimensions for concrete and soil cement

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For a square channel of width  $b$  we find  $A = b^2$

$$R = \frac{b \cdot y}{b + 2 \cdot y} = \frac{b^2}{b + 2 \cdot b} = \frac{b}{3}$$

Hence 
$$Q = \frac{1}{n} \cdot b^2 \cdot \left(\frac{b}{3}\right)^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{S_b^{\frac{1}{2}}}{n \cdot 3^{\frac{2}{3}}} \cdot b^{\frac{8}{3}}$$
 or

$$b = \left( \frac{\left(\frac{2}{3}\right)^{\frac{3}{8}} \cdot Q \cdot n}{S_b^{\frac{1}{2}}} \right)^{\frac{3}{8}}$$

The given data is  $Q = 20 \cdot \frac{\text{m}^3}{\text{s}}$

$$S_b = 0.003$$

For concrete, from Table 11.2 (assuming large depth)

$$n = .013$$

$$b = 2.36 \text{ m}$$

For soil cement from Table 11.2 (assuming large depth)


$$n = .020$$

$$b = 2.77 \text{ m}$$

## Problem 11.49

[Difficulty: 1]

**11.49** Water flows in a trapezoidal channel at a normal depth of 1.2 m. The bottom width is 2.4 m and the sides slope at 1:1 (45°). The flow rate is 7.1 m<sup>3</sup>/s. The channel is excavated from bare soil. Find the bed slope.



**Given:** Data on trapezoidal channel

**Find:** Bed slope

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $b = 2.4 \text{ m}$        $\alpha = 45^\circ$        $y = 1.2 \text{ m}$        $Q = 7.1 \frac{\text{m}^3}{\text{s}}$

For bare soil (Table 11.2)  $n = 0.020$


Hence from Table 11.1  $A = y \cdot (b + \cot(\alpha) \cdot y)$        $A = 4.32 \text{ m}^2$        $R_h = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\sin(\alpha)}}$        $R_h = 0.746 \text{ m}$

Hence 
$$S_b = \left( \frac{Q \cdot n}{A \cdot R_h^{\frac{2}{3}}} \right)^2$$
       $S_b = 1.60 \times 10^{-3}$

## Problem 11.50

[Difficulty: 1]

**11.50** A triangular channel with side angles of  $45^\circ$  is to carry  $10 \text{ m}^3/\text{s}$  at a slope of 0.001. The channel is concrete. Find the required dimensions.



**Given:** Data on triangular channel

**Find:** Required dimensions

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the triangular channel we have  $\alpha = 45^\circ$        $S_b = 0.001$        $Q = 10 \cdot \frac{\text{m}^3}{\text{s}}$

For concrete (Table 11.2)       $n = 0.013$       (assuming  $y > 60 \text{ cm}$ : verify later)

Hence from Table 11.1       $A = y^2 \cdot \cot(\alpha) = y^2$        $R_h = \frac{y \cdot \cos(\alpha)}{2} = \frac{y}{2 \cdot \sqrt{2}}$


Hence 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{n} \cdot y^2 \cdot \left( \frac{y}{2 \cdot \sqrt{2}} \right)^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{n} \cdot y^{\frac{8}{3}} \cdot \left( \frac{1}{8} \right)^{\frac{1}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{2 \cdot n} \cdot y^{\frac{8}{3}} \cdot S_b^{\frac{1}{2}}$$

Solving for  $y$       
$$y = \left( \frac{2 \cdot n \cdot Q}{\sqrt{S_b}} \right)^{\frac{3}{8}}$$
       $y = 2.20 \text{ m}$       (The assumption that  $y > 60 \text{ cm}$  is verified)

## Problem 11.51

[Difficulty: 2]

**11.51** A semicircular trough of corrugated steel, with diameter  $D = 1$  m, carries water at depth  $y = 0.25$  m. The slope is 0.01. Find the discharge.



**Given:** Data on semicircular trough

**Find:** Discharge

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the semicircular channel  $D = 1 \cdot \text{m}$   $y = 0.25 \cdot \text{m}$   $S_b = 0.01$

Hence, from geometry 
$$\alpha = 2 \cdot \arcsin \left( \frac{y - \frac{D}{2}}{\frac{D}{2}} \right) + 180 \cdot \text{deg}$$
  $\alpha = 120 \cdot \text{deg}$

For corrugated steel, a Google search leads to  $n = 0.022$

Hence from Table 11.1 
$$A = \frac{1}{8} \cdot (\alpha - \sin(\alpha)) \cdot D^2$$
  $A = 0.154 \text{ m}^2$


$$R_h = \frac{1}{4} \cdot \left( 1 - \frac{\sin(\alpha)}{\alpha} \right) \cdot D$$
  $R_h = 0.147 \text{ m}$

Then the discharge is 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} \cdot \frac{\text{m}^3}{\text{s}}$$
  $Q = 0.194 \frac{\text{m}^3}{\text{s}}$

## Problem 11.52

[Difficulty: 1]

**11.52** Find the discharge at which the channel of Problem 11.51 flows full.



**Given:** Data on semicircular trough

**Find:** Discharge

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the semicircular channel  $D = 1 \cdot \text{m}$   $\alpha = 180 \cdot \text{deg}$   $S_b = 0.01$

For corrugated steel, a Google search leads to (Table 11.2)  $n = 0.022$

Hence from Table 11.1  $A = \frac{1}{8} \cdot (\alpha - \sin(\alpha)) \cdot D^2$   $A = 0.393 \text{ m}^2$


$$R_h = \frac{1}{4} \cdot \left( 1 - \frac{\sin(\alpha)}{\alpha} \right) \cdot D \quad R_h = 0.25 \text{ m}$$

Then the discharge is  $Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} \cdot \frac{\text{m}^3}{\text{s}}$   $Q = 0.708 \frac{\text{m}^3}{\text{s}}$

## Problem 11.53

[Difficulty: 3]

**11.53** The flume of Problem 11.46 is fitted with a new plastic film liner ( $n = 0.010$ ). Find the new depth of flow if the discharge remains constant at  $85.5 \text{ ft}^3/\text{s}$ .



**Given:** Data on flume with plastic liner

**Find:** Depth of flow

**Solution:**

Basic equation: 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For a rectangular channel of width  $b = 6 \cdot \text{ft}$  and depth  $y$  we find from Table 11.1

$$A = b \cdot y = 6 \cdot y \qquad R = \frac{b \cdot y}{b + 2 \cdot y} = \frac{6 \cdot y}{6 + 2 \cdot y}$$

and also  $n = 0.010$  and  $S_b = \frac{1 \cdot \text{ft}}{1000 \cdot \text{ft}} \qquad S_b = 0.001$

Hence 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1.49}{0.010} \cdot 6 \cdot y \cdot \left( \frac{6 \cdot y}{6 + 2 \cdot y} \right)^{\frac{2}{3}} \cdot 0.001^{\frac{1}{2}} = 85.5 \quad (\text{Note that we don't use units!})$$

Solving for  $y$  
$$\frac{y^{\frac{5}{3}}}{(6 + 2 \cdot y)^{\frac{2}{3}}} = \frac{85.5 \cdot 0.010}{1.49 \cdot 0.001^{\frac{1}{2}} \cdot 6 \cdot 6^{\frac{2}{3}}} \quad \text{or} \quad \frac{y^{\frac{5}{3}}}{(6 + 2 \cdot y)^{\frac{2}{3}}} = 0.916$$

This is a nonlinear implicit equation for  $y$  and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with Problem 11.46's depth

For  $y = 3$  (feet) 
$$\frac{y^{\frac{5}{3}}}{(6 + 2 \cdot y)^{\frac{2}{3}}} = 1.191$$
 For  $y = 2$  (feet) 
$$\frac{y^{\frac{5}{3}}}{(6 + 2 \cdot y)^{\frac{2}{3}}} = 0.684$$


For  $y = 2.5$  (feet) 
$$\frac{y^{\frac{5}{3}}}{(6 + 2 \cdot y)^{\frac{2}{3}}} = 0.931$$
 For  $y = 2.45$  (feet) 
$$\frac{y^{\frac{5}{3}}}{(6 + 2 \cdot y)^{\frac{2}{3}}} = 0.906$$

For  $y = 2.47$  (feet) 
$$\frac{y^{\frac{5}{3}}}{(6 + 2 \cdot y)^{\frac{2}{3}}} = 0.916$$
  $y = 2.47$  (feet)

## Problem 11.54

[Difficulty: 3]

**11.54** Discharge through the channel of Problem 11.49 is increased to  $10 \text{ m}^3/\text{s}$ . Find the corresponding normal depth if the bed slope is 0.00193.



**Given:** Data on trapezoidal channel

**Find:** New depth of flow

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $b = 2.4\text{-m}$        $\alpha = 45\text{-deg}$        $Q = 10 \cdot \frac{\text{m}^3}{\text{s}}$        $S_b = 0.00193$

For bare soil (Table 11.2)  $n = 0.020$

Hence from Table 11.1  $A = y \cdot (b + \cot(\alpha) \cdot y) = y \cdot (2.4 + y)$        $R = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\sin(\alpha)}} = \frac{y \cdot (2.4 + y)}{2.4 + 2 \cdot y \cdot \sqrt{2}}$

Hence 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{0.020} \cdot y \cdot (2.4 + y) \cdot \left[ \frac{y \cdot (2.4 + y)}{2.4 + 2 \cdot y \cdot \sqrt{2}} \right]^{\frac{2}{3}} \cdot 0.00193^{\frac{1}{2}} = 10 \quad (\text{Note that we don't use units!})$$

Solving for y 
$$\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 4.55$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with a larger depth than Problem 11.49's.

For  $y = 1.5$  (m) 
$$\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 5.37$$
      For  $y = 1.4$  (m) 
$$\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 4.72$$

For  $y = 1.35$  (m) 
$$\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 4.41$$
      For  $y = 1.37$  (m) 
$$\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 4.536$$


The solution to three figures is

$y = 1.37$  (m)

## Problem 11.55

[Difficulty: 3]

**11.55** The channel of Problem 11.49 has 0.00193 bed slope. Find the normal depth for the given discharge after a new plastic liner ( $n = 0.010$ ) is installed.



**Given:** Data on trapezoidal channel

**Find:** New depth of flow

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $b = 2.4\text{ m}$        $\alpha = 45\text{-deg}$        $Q = 7.1 \frac{\text{m}^3}{\text{s}}$        $S_b = 0.00193$

For bare soil (Table 11.2)       $n = 0.010$

Hence from Table 11.1       $A = y \cdot (b + y \cdot \cot(\alpha)) = y \cdot (2.4 + y)$        $R_h = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\sin(\alpha)}} = \frac{y \cdot (2.4 + y)}{2.4 + 2 \cdot y \cdot \sqrt{2}}$

Hence 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{0.010} \cdot y \cdot (2.4 + y) \cdot \left[ \frac{y \cdot (2.4 + y)}{2.4 + 2 \cdot y \cdot \sqrt{2}} \right]^{\frac{2}{3}} \cdot 0.00193^{\frac{1}{2}} = 7.1 \quad (\text{Note that we don't use units!})$$

Solving for y 
$$\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 1.62$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with a shallower depth than that of Problem 11.49.

For  $y = 1$  (m)       $\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 2.55$       For  $y = 0.75$  (m)       $\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 1.53$

For  $y = 0.77$  (m)       $\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 1.60$       For  $y = 0.775$  (m)       $\frac{[y \cdot (2.4 + y)]^{\frac{5}{3}}}{(2.4 + 2 \cdot y \cdot \sqrt{2})^{\frac{2}{3}}} = 1.62$


The solution to three figures is

$y = 0.775$  (m)

## Problem 11.56

[Difficulty: 4]

**11.56** Consider again the semicircular channel of Problem 11.51. Find the normal depth that corresponds to a discharge of  $0.5 \text{ m}^3/\text{s}$ .



**Given:** Data on semicircular trough

**Find:** New depth of flow

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the semicircular channel  $D = 1 \text{ m}$   $S_b = 0.01$   $Q = 0.5 \frac{\text{m}^3}{\text{s}}$

For corrugated steel, a Google search leads to (Table 11.2)  $n = 0.022$

From Table 11.1  $A = \frac{1}{8} \cdot (\alpha - \sin(\alpha)) \cdot D^2 = \frac{1}{8} \cdot (\alpha - \sin(\alpha))$   $R_h = \frac{1}{4} \cdot \left(1 - \frac{\sin(\alpha)}{\alpha}\right) \cdot D = \frac{1}{4} \cdot \left(1 - \frac{\sin(\alpha)}{\alpha}\right)$

Hence 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{0.022} \cdot \left[\frac{1}{8} \cdot (\alpha - \sin(\alpha))\right] \cdot \left[\frac{1}{4} \cdot \left(1 - \frac{\sin(\alpha)}{\alpha}\right)\right]^{\frac{2}{3}} \cdot 0.01^{\frac{1}{2}} = 0.5 \quad (\text{Note that we don't use units!})$$

Solving for  $\alpha$  
$$\alpha^{\frac{2}{3}} \cdot (\alpha - \sin(\alpha))^{\frac{5}{3}} = 2.21$$

This is a nonlinear implicit equation for  $\alpha$  and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with a half-full channel

For  $\alpha = 180 \cdot \text{deg}$   $\alpha^{\frac{2}{3}} \cdot (\alpha - \sin(\alpha))^{\frac{5}{3}} = 3.14$       For  $\alpha = 160 \cdot \text{deg}$   $\alpha^{\frac{2}{3}} \cdot (\alpha - \sin(\alpha))^{\frac{5}{3}} = 2.25$

For  $\alpha = 159 \cdot \text{deg}$   $\alpha^{\frac{2}{3}} \cdot (\alpha - \sin(\alpha))^{\frac{5}{3}} = 2.20$       For  $\alpha = 159.2 \cdot \text{deg}$   $\alpha^{\frac{2}{3}} \cdot (\alpha - \sin(\alpha))^{\frac{5}{3}} = 2.212$


The solution to three figures is  $\alpha = 159 \cdot \text{deg}$

From geometry 
$$y = \frac{D}{2} \cdot \left(1 - \cos\left(\frac{\alpha}{2}\right)\right)$$
  $y = 0.410 \text{ m}$

## Problem 11.57

[Difficulty: 3]

**11.57** Consider a symmetric open channel of triangular cross section. Show that for a given flow area, the wetted perimeter is minimized when the sides meet at a right angle.



**Given:** Triangular channel

**Find:** Proof that wetted perimeter is minimized when sides meet at right angles

**Solution:**

From Table 11.1  $A = y^2 \cdot \cot(\alpha)$   $P = \frac{2 \cdot y}{\sin(\alpha)}$

We need to vary  $z$  to minimize  $P$  while keeping  $A$  constant, which means that  $y = \sqrt{\frac{A}{\cot(\alpha)}}$  with  $A = \text{constant}$

Hence we eliminate  $y$  in the expression for  $P$   $P = 2 \cdot \sqrt{\frac{A}{\cot(\alpha)}} \cdot \frac{1}{\sin(\alpha)}$

For optimizing  $P$   $\frac{dP}{d\alpha} = -\frac{2 \cdot (A \cdot \cos(\alpha) - A \cdot \sin(\alpha) \cdot \tan(\alpha))}{\sin(2 \cdot \alpha) \cdot \sqrt{A \cdot \tan(\alpha)}} = 0$


or  $A \cdot \cos(\alpha) - A \cdot \sin(\alpha) \cdot \tan(\alpha) = 0$   $\frac{1}{\tan(\alpha)} = \tan(\alpha)$   $\tan(\alpha) = 1$   $\alpha = 45 \cdot \text{deg}$

For  $\alpha = 45^\circ$  we find from the figure that we have the case where the sides meet at  $90^\circ$ . Note that we have only proved that this is a minimum OR maximum of  $P$ ! It makes sense that it's the minimum, as, for constant  $A$ , we get a huge  $P$  if we set  $\alpha$  to a large number (almost vertical walls); hence we can't have a maximum value at  $\alpha = 45^\circ$ .

## Problem 11.58

[Difficulty: 3]

**11.58** Compute the normal depth and velocity of the channel of Problem 11.17.



**Given:** Data on trapezoidal channel

**Find:** Normal depth and velocity

**Solution:**

Basic equation: 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $b = 20\text{-ft}$     $\alpha = \text{atan}(2)$     $\alpha = 63.4 \text{ deg}$     $Q = 400 \cdot \frac{\text{ft}^3}{\text{s}}$     $S_b = 0.0016$     $n = 0.025$

Hence from Table 11.2  $A = y \cdot (b + y \cdot \cot(\alpha)) = y \cdot \left(20 + \frac{1}{2} \cdot y\right)$     $R_h = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\sin(\alpha)}} = \frac{y \cdot \left(20 + \frac{1}{2} \cdot y\right)}{20 + y \cdot \sqrt{5}}$

Hence  $Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{0.025} \cdot y \cdot \left(20 + \frac{1}{2} \cdot y\right) \cdot \left[ \frac{y \cdot \left(20 + \frac{1}{2} \cdot y\right)}{20 + y \cdot \sqrt{5}} \right]^{\frac{2}{3}} \cdot 0.0016^{\frac{1}{2}} = 400$  (Note that we don't use units!)

Solving for y 
$$\frac{\left[ y \cdot \left(20 + \frac{1}{2} \cdot y\right) \right]^{\frac{5}{3}}}{(20 + y \cdot \sqrt{5})^3} = 250$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with an arbitrary depth

For  $y = 5$  (ft) 
$$\frac{\left[ y \cdot \left(20 + \frac{1}{2} \cdot y\right) \right]^{\frac{5}{3}}}{(20 + y \cdot \sqrt{5})^3} = 265$$
   For  $y = 4.9$  (ft) 
$$\frac{\left[ y \cdot \left(20 + \frac{1}{2} \cdot y\right) \right]^{\frac{5}{3}}}{(20 + y \cdot \sqrt{5})^3} = 256$$

For  $y = 4.85$  (ft) 
$$\frac{\left[ y \cdot \left(20 + \frac{1}{2} \cdot y\right) \right]^{\frac{5}{3}}}{(20 + y \cdot \sqrt{5})^3} = 252$$
   For  $y = 4.83$  (ft) 
$$\frac{\left[ y \cdot \left(20 + \frac{1}{2} \cdot y\right) \right]^{\frac{5}{3}}}{(20 + y \cdot \sqrt{5})^3} = 250$$

The solution to three figures is  $y = 4.83\text{-ft}$

Then  $A = (b + y \cdot \cot(\alpha)) \cdot y$     $A = 108 \cdot \text{ft}^2$


Finally, the normal velocity is  $V = \frac{Q}{A}$

$V = 3.69 \cdot \frac{\text{ft}}{\text{s}}$

## Problem 11.59

[Difficulty: 5]

**11.59** Determine the cross section of the greatest hydraulic efficiency for a trapezoidal channel with side slope of 1 vertical to 2 horizontal if the design discharge is 250 m<sup>3</sup>/s. The channel slope is 0.001 and Manning's roughness factor is 0.020.



**Given:** Data on trapezoidal channel

**Find:** Geometry for greatest hydraulic efficiency

**Solution:**

Basic equation: 
$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $\alpha = \text{atan}\left(\frac{1}{2}\right) \quad \alpha = 26.6\text{-deg} \quad Q = 250 \frac{\text{m}^3}{\text{s}} \quad S_b = 0.001 \quad n = 0.020$

From Table 11.1 
$$A = y \cdot (b + y \cdot \cot(\alpha)) \quad P = b + \frac{2 \cdot y}{\sin(\alpha)}$$

We need to vary  $b$  and  $y$  to obtain optimum conditions. These are when the area and perimeter are optimized. Instead of two independent variables  $b$  and  $y$ , we eliminate  $b$  by doing the following

$$b = \frac{A}{y} - y \cdot \cot(\alpha) \quad \text{and so} \quad P = \frac{A}{y} - y \cdot \cot(\alpha) + \frac{2 \cdot y}{\sin(\alpha)}$$

Taking the derivative w.r.t.  $y$  
$$\frac{\partial}{\partial y} P = \frac{1}{y} \cdot \frac{\partial}{\partial y} A - \frac{A}{y^2} - \cot(\alpha) + \frac{2}{\sin(\alpha)}$$

But at optimum conditions 
$$\frac{\partial}{\partial y} P = 0 \quad \text{and} \quad \frac{\partial}{\partial y} A = 0$$

Hence 
$$0 = -\frac{A}{y^2} - \cot(\alpha) + \frac{2}{\sin(\alpha)} \quad \text{or} \quad A = \frac{2 \cdot y^2}{\sin(\alpha)} - y^2 \cdot \cot(\alpha)$$

Comparing to 
$$A = y \cdot (b + y \cdot \cot(\alpha)) \quad \text{we find} \quad A = y \cdot (b + y \cdot \cot(\alpha)) = \frac{2 \cdot y^2}{\sin(\alpha)} - y^2 \cdot \cot(\alpha)$$

Hence 
$$b = \frac{2 \cdot y}{\sin(\alpha)} - 2 \cdot y \cdot \cot(\alpha)$$

Then 
$$A = y \cdot (b + y \cdot \cot(\alpha)) = y \cdot \left( \frac{2 \cdot y}{\sin(\alpha)} - 2 \cdot y \cdot \cot(\alpha) + y \cdot \cot(\alpha) \right) = y^2 \cdot \left( \frac{2}{\sin(\alpha)} - \cot(\alpha) \right)$$

$$P = b + \frac{2 \cdot y}{\sin(\alpha)} = \frac{4 \cdot y}{\sin(\alpha)} - 2 \cdot y \cdot \cot(\alpha) = 2 \cdot y \cdot \left( \frac{2}{\sin(\alpha)} - \cot(\alpha) \right)$$

and

$$R_h = \frac{A}{P} = \frac{y^2 \cdot \left( \frac{2}{\sin(\alpha)} - \cot(\alpha) \right)}{2 \cdot y \cdot \left( \frac{2}{\sin(\alpha)} - \cot(\alpha) \right)} = \frac{y}{2}$$

Hence

$$Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{n} \cdot \left[ y^2 \cdot \left( \frac{2}{\sin(\alpha)} - \cot(\alpha) \right) \right] \cdot \left( \frac{y}{2} \right)^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

$$Q = \left( \frac{2}{\sin(\alpha)} - \cot(\alpha) \right) \cdot \frac{y^{\frac{8}{3}} \cdot S_b^{\frac{1}{2}}}{n \cdot 2^{\frac{3}{2}}}$$

Solving for y

$$y = \left[ \frac{\frac{2}{3} \cdot n \cdot Q}{\left( \frac{2}{\sin(\alpha)} - \cot(\alpha) \right) \cdot S_b^{\frac{1}{2}}} \right]^{\frac{3}{8}} \quad y = 5.66 \quad (\text{m})$$


Finally

$$b = \frac{2 \cdot y}{\sin(\alpha)} - 2 \cdot y \cdot \cot(\alpha) \quad b = 2.67 \quad (\text{m})$$

## Problem 11.60

[Difficulty: 3]

**11.60** For a trapezoidal shaped channel ( $n = 0.014$  and slope  $S_b = 0.0002$  with a 20-ft bottom width and side slopes of 1 vertical to 1.5 horizontal), determine the normal depth for a discharge of 1000 cfs.



**Given:** Data on trapezoidal channel

**Find:** Normal depth

**Solution:**

Basic equation: 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

Note that this is an "engineering" equation, to be used without units!

For the trapezoidal channel we have  $b = 20\text{-ft}$      $\alpha = \text{atan}\left(\frac{1}{1.5}\right)$      $\alpha = 33.7\text{ deg}$      $Q = 1000 \cdot \frac{\text{ft}^3}{\text{s}}$

$S_0 = 0.0002$      $n = 0.014$

Hence from Table 11.1

$A = y \cdot (b + y \cdot \cot(\alpha)) = y \cdot (20 + 1.5 \cdot y)$      $R_h = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\sin(\alpha)}} = \frac{y \cdot (20 + 1.5 \cdot y)}{20 + 2 \cdot y \cdot \sqrt{3.25}}$

Hence 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1.49}{0.014} \cdot y \cdot (20 + 1.5 \cdot y) \cdot \left[ \frac{y \cdot (20 + 1.5 \cdot y)}{20 + 2 \cdot y \cdot \sqrt{3.25}} \right]^{\frac{2}{3}} \cdot 0.0002^{\frac{1}{2}} = 1000 \quad (\text{Note that we don't use units!})$$

Solving for y 
$$\frac{[(20 + 1.5 \cdot y) \cdot y]^{\frac{5}{3}}}{(20 + 2 \cdot y \cdot \sqrt{3.25})^3} = 664$$

This is a nonlinear implicit equation for y and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below.

For  $y = 7.5$  (ft) 
$$\frac{[(20 + 1.5 \cdot y) \cdot y]^{\frac{5}{3}}}{(20 + 2 \cdot y \cdot \sqrt{3.25})^3} = 684$$
    For  $y = 7.4$  (ft) 
$$\frac{[(20 + 1.5 \cdot y) \cdot y]^{\frac{5}{3}}}{(20 + 2 \cdot y \cdot \sqrt{3.25})^3} = 667$$


For  $y = 7.35$  (ft) 
$$\frac{[(20 + 1.5 \cdot y) \cdot y]^{\frac{5}{3}}}{(20 + 2 \cdot y \cdot \sqrt{3.25})^3} = 658$$
    For  $y = 7.38$  (ft) 
$$\frac{[(20 + 1.5 \cdot y) \cdot y]^{\frac{5}{3}}}{(20 + 2 \cdot y \cdot \sqrt{3.25})^3} = 663$$

The solution to three figures is  $y = 7.38$  (ft)

## Problem 11.61

[Difficulty: 5]

**11.61** Show that the best hydraulic trapezoidal section is one-half of a hexagon.



**Given:** Trapezoidal channel

**Find:** Geometry for greatest hydraulic efficiency

**Solution:**

From Table 11.1  $A = y \cdot (b + y \cdot \cot(\alpha))$   $P = b + \frac{2 \cdot y}{\sin(\alpha)}$

We need to vary  $b$  and  $y$  (and then  $\alpha$ ) to obtain optimum conditions. These are when the area and perimeter are optimized. Instead of two independent variables  $b$  and  $y$ , we eliminate  $b$  by doing the following

$$b = \frac{A}{y} - y \cdot \cot(\alpha) \quad \text{and so} \quad P = \frac{A}{y} - y \cdot \cot(\alpha) + \frac{2 \cdot y}{\sin(\alpha)}$$

Taking the derivative w.r.t.  $y$   $\frac{\partial}{\partial y} P = \frac{1}{y} \cdot \frac{\partial}{\partial y} A - \frac{A}{y^2} - \cot(\alpha) + \frac{2}{\sin(\alpha)}$

But at optimum conditions  $\frac{\partial}{\partial y} P = 0$  and  $\frac{\partial}{\partial y} A = 0$

Hence  $0 = -\frac{A}{y^2} - \cot(\alpha) + \frac{2}{\sin(\alpha)}$  or  $A = \frac{2 \cdot y^2}{\sin(\alpha)} - y^2 \cdot \cot(\alpha)$  (1)

Now we optimize  $A$  w.r.t.  $\alpha$   $\frac{\partial}{\partial \alpha} A = -\frac{2 \cdot y^2 \cdot \cos(\alpha)}{\sin(\alpha)^2} - y^2 \cdot (-1 - \cot(\alpha)^2) = 0$  or  $-\frac{2 \cdot \cos(\alpha)}{\sin(\alpha)^2} + (\cot(\alpha)^2 + 1) = 0$

But  $\cot(\alpha)^2 + 1 = \frac{\cos(\alpha)^2}{\sin(\alpha)^2} + 1 = \frac{\sin(\alpha)^2 + \cos(\alpha)^2}{\sin(\alpha)^2} = \frac{1}{\sin(\alpha)^2}$

Hence  $-2 \cdot \cos(\alpha) = -1$   $\alpha = \arccos\left(\frac{1}{2}\right)$   $\alpha = 60 \text{ deg}$

We can now evaluate  $A$  from Eq 1  $A = \frac{2 \cdot y^2}{\sin(\alpha)} - y^2 \cdot \cot(\alpha) = \frac{2 \cdot y^2}{\frac{\sqrt{3}}{2}} - \frac{1}{\sqrt{3}} \cdot y^2 = \left(\frac{4}{\sqrt{3}} - \frac{1}{\sqrt{3}}\right) \cdot y^2 = \sqrt{3} \cdot y^2$

But for a trapezoid  $A = y \cdot (b + y \cdot \cot(\alpha)) = y \cdot \left(b + \frac{1}{\sqrt{3}} \cdot y\right)$

Comparing the two  $A$  expressions  $A = \left(b + \frac{1}{\sqrt{3}} \cdot y\right) \cdot y = \sqrt{3} \cdot y^2$  we find  $b = \left(\sqrt{3} - \frac{1}{\sqrt{3}}\right) \cdot y = \frac{2}{\sqrt{3}} \cdot y$

But the perimeter is 
$$P = b + \frac{2 \cdot y}{\sin(\alpha)} = b + 2 \cdot y \cdot \frac{2}{\sqrt{3}} = b + \frac{4}{\sqrt{3}} \cdot y = b + 2 \cdot b = 3 \cdot b$$

In summary we have 
$$\alpha = 60 \text{ deg}$$


and 
$$b = \frac{1}{3} \cdot P \quad \text{so each of the symmetric sides is} \quad \frac{P - \frac{1}{3} \cdot P}{2} = \frac{1}{3} \cdot P$$

We have proved that the optimum shape is equal side and bottom lengths, with 60 angles i.e., half a hexagon!

## Problem 11.62

[Difficulty: 1]

**11.62** Compute the critical depth for the channel in Problem 11.41.



**Given:** Rectangular channel flow

**Find:** Critical depth

**Solution:**

Basic equations: 
$$y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}} \quad Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$$

For a rectangular channel of width  $b = 2 \cdot \text{m}$  and depth  $y = 1.5 \cdot \text{m}$  we find from Table 11.1

$$A = b \cdot y \quad A = 3.00 \cdot \text{m}^2 \quad R_h = \frac{b \cdot y}{b + 2 \cdot y} \quad R_h = 0.600 \cdot \text{m}$$

Manning's roughness coefficient is  $n = 0.015$  and  $S_b = 0.0005$


$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} \quad Q = 3.18 \cdot \frac{\text{m}^3}{\text{s}}$$

Hence 
$$y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}} \quad y_c = 0.637 \text{ m}$$

## Problem 11.63

[Difficulty: 4]

**11.63** Consider a 2.45-m-wide rectangular channel with a bed slope of 0.0004 and a Manning's roughness factor of 0.015. A weir is placed in the channel, and the depth upstream of the weir is 1.52 m for a discharge of 5.66 m<sup>3</sup>/s. Determine whether a hydraulic jump forms upstream of the weir.



**Given:** Data on rectangular channel and weir

**Find:** If a hydraulic jump forms upstream of the weir

**Solution:**

Basic equations:  $Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$        $y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}}$

Note that the Q equation is an "engineering" equation, to be used without units!

For a rectangular channel of width  $b = 2.45$  m and depth  $y$  we find from Table 11.1

$$A = b \cdot y = 2.45 \cdot y \quad R_h = \frac{b \cdot y}{b + 2 \cdot y} = \frac{2.45 \cdot y}{2.45 + 2 \cdot y} \quad \text{and also} \quad n = 0.015 \quad \text{and} \quad S_b = 0.0004 \quad Q = 5.66 \frac{\text{m}^3}{\text{s}}$$

Hence  $Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{0.015} \cdot 2.45 \cdot y \cdot \left( \frac{2.45 \cdot y}{2.45 + 2 \cdot y} \right)^{\frac{2}{3}} \cdot 0.0004^{\frac{1}{2}} = 5.66$  (Note that we don't use units!)

Solving for  $y$   $\frac{y^{\frac{5}{3}}}{(2.45 + 2 \cdot y)^{\frac{2}{3}}} = \frac{5.66 \cdot 0.015}{0.0004^{\frac{1}{2}} \cdot 2.45 \cdot 2.45^{\frac{2}{3}}}$  or  $\frac{y^{\frac{5}{3}}}{(2.54 + 2 \cdot y)^{\frac{2}{3}}} = 0.898$

This is a nonlinear implicit equation for  $y$  and must be solved numerically. We can use one of a number of numerical root finding techniques, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with the given depth

For  $y = 1.52$  (m)  $\frac{y^{\frac{5}{3}}}{(2.54 + 2 \cdot y)^{\frac{2}{3}}} = 0.639$       For  $y = 2$  (m)  $\frac{y^{\frac{5}{3}}}{(2.54 + 2 \cdot y)^{\frac{2}{3}}} = 0.908$

For  $y = 1.95$  (m)  $\frac{y^{\frac{5}{3}}}{(2.54 + 2 \cdot y)^{\frac{2}{3}}} = 0.879$       For  $y = 1.98$  (m)  $\frac{y^{\frac{5}{3}}}{(2.54 + 2 \cdot y)^{\frac{2}{3}}} = 0.896$


$y = 1.98$  (m) This is the normal depth. We also have the critical depth:  $y_c = \left( \frac{Q^2}{g \cdot b^2} \right)^{\frac{1}{3}} = 0.816$  m

Hence the given depth is  $1.52 \text{ m} > y_c$ , but  $1.52 \text{ m} < y_n$ , the normal depth. This implies the flow is subcritical (far enough upstream it is depth 1.98 m), and that it draws down to 1.52 m as it gets close to the weir. There is no jump.

## Problem 11.64

[Difficulty: 2]

**11.64** An above-ground rectangular flume is to be constructed of timber. For a drop of 10 ft/mile, what will be the depth and width for the most economical flume if it is to discharge 40 cfs?



**Given:** Data on rectangular flume

**Find:** Optimum geometry

**Solution:**

Basic equations:  $Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$  and from Table 11.3, for optimum geometry  $b = 2 \cdot y_n$

Note that the Q equation is an "engineering" equation, to be used without units!

Available data  $S_b = 10 \cdot \frac{\text{ft}}{\text{mile}} \quad S_b = 0.00189 \quad Q = 40 \cdot \frac{\text{ft}^3}{\text{s}}$

For wood (unplaned), a Google search gives  $n = 0.013$

Hence  $A = b \cdot y_n = 2 \cdot y_n^2 \quad R_h = \frac{A}{P} = \frac{2 \cdot y_n^2}{y_n + 2 \cdot y_n + y_n} = \frac{y_n}{2}$

Then  $Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1.49}{n} \cdot 2 \cdot y_n^2 \cdot \left(\frac{y_n}{2}\right)^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$


Solving for  $y_n$   $y_n = \left( \frac{Q \cdot n \cdot 2^{\frac{2}{3}}}{4 \cdot 1.49 \cdot S_b^{\frac{1}{2}}} \right)^{\frac{3}{5}} \quad y_n = 2.00 \quad (\text{ft}) \quad b = 2y_n \quad b = 4.01 \quad (\text{ft})$

## Problem 11.65

[Difficulty: 2]

**11.65** Consider flow in a rectangular channel. Show that, for flow at critical depth and optimum aspect ratio ( $b = 2y$ ), the volume flow rate and bed slope are given by the expressions:

$$Q = 62.6y_c^{5/2} \quad \text{and} \quad S_c = 24.7 \frac{n^2}{y_c^{1/3}}$$



**Given:** Data on rectangular channel

**Find:** Expressions valid for critical depth at optimum geometry

**Solution:**

Basic equations:  $Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$  and from Table 11.3, for optimum geometry  $b = 2 \cdot y_n$

Note that the Q equation is an "engineering" equation, to be used without units!

Hence  $A = b \cdot y_n = 2 \cdot y_n^2$   $R_h = \frac{A}{P} = \frac{2 \cdot y_n^2}{y_n + 2 \cdot y_n + y_n} = \frac{y_n}{2}$

Then  $Q = \frac{1}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1}{n} \cdot 2 \cdot y_n^2 \cdot \left(\frac{y_n}{2}\right)^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$  or  $Q = \frac{2^{\frac{1}{3}}}{n} \cdot y_n^{\frac{8}{3}} \cdot S_b^{\frac{1}{2}}$

We can write the Froude number in terms of Q

$$Fr = \frac{V}{\sqrt{g \cdot y}} = \frac{Q}{A \cdot \sqrt{g \cdot y}} = \frac{Q}{2 \cdot y_n^2 \cdot \sqrt{g \cdot y_n^{\frac{1}{2}}}}$$
or  $Fr = \frac{Q}{2 \cdot \sqrt{g \cdot y_n^{\frac{5}{2}}}}$

Hence for critical flow,  $Fr = 1$  and  $y_n = y_c$ , so  $1 = \frac{Q}{2 \cdot \sqrt{g \cdot y_c^{\frac{5}{2}}}}$  or  $Q = 2 \cdot \sqrt{g \cdot y_c^{\frac{5}{2}}}$   $Q = 6.26 \cdot y_c^{\frac{5}{2}}$


To find  $S_c$ , equate the expressions for Q and set  $S_b = S_c$

$$Q = \frac{2^{\frac{1}{3}}}{n} \cdot y_c^{\frac{8}{3}} \cdot S_c^{\frac{1}{2}} = 2 \cdot \sqrt{g \cdot y_c^{\frac{5}{2}}}$$
or  $S_c = 2^{\frac{4}{3}} \cdot g \cdot n^2 \cdot y_c^{-\frac{1}{3}}$   $S_c = \frac{24.7 \cdot n^2}{y_c^{\frac{1}{3}}}$

## Problem 11.66

[Difficulty: 3]

**11.66** A trapezoidal canal lined with brick has side slopes of 2:1 and bottom width of 10 ft. It carries 600 ft<sup>3</sup>/s at critical speed. Determine the critical slope (the slope at which the depth is critical).



**Given:** Data on trapezoidal canal

**Find:** Critical slope

**Solution:**

Basic equations: 
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} \quad \text{and} \quad A = y \cdot b + y \cdot \cot(\alpha) \quad R_h = \frac{y \cdot (b + y \cdot \cot(\alpha))}{b + \frac{2 \cdot y}{\sin(\alpha)}}$$

Note that the Q equation is an "engineering" equation, to be used without units!

Available data 
$$b = 10 \cdot \text{ft} \quad \alpha = \text{atan}\left(\frac{2}{1}\right) \quad \alpha = 63.4 \cdot \text{deg} \quad Q = 600 \frac{\text{ft}^3}{\text{s}}$$

For brick, a Google search gives 
$$n = 0.015$$

For critical flow 
$$y = y_c \quad V_c = \sqrt{g \cdot y_c}$$

so 
$$Q = A \cdot V_c = (y_c \cdot b + y_c \cdot \cot(\alpha)) \cdot \sqrt{g \cdot y_c} \quad (y_c \cdot b + y_c \cdot \cot(\alpha)) \cdot \sqrt{g \cdot y_c} = Q \quad \text{with} \quad Q = 600 \frac{\text{ft}^3}{\text{s}}$$

This is a nonlinear implicit equation for  $y_c$  and must be solved numerically. We can use one of a number of numerical root finding techniques, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below. We start with the given depth

For  $y_c = 5$  (ft)  $(y_c \cdot b + y_c \cdot \cot(\alpha)) \cdot \sqrt{g \cdot y_c} = 666$  For  $y_c = 4.5$  (ft)  $(y_c \cdot b + y_c \cdot \cot(\alpha)) \cdot \sqrt{g \cdot y_c} = 569$

For  $y_c = 4.7$  (ft)  $(y_c \cdot b + y_c \cdot \cot(\alpha)) \cdot \sqrt{g \cdot y_c} = 607$  For  $y_c = 4.67$  (ft)  $(y_c \cdot b + y_c \cdot \cot(\alpha)) \cdot \sqrt{g \cdot y_c} = 601$

Hence  $y_c = 4.67$  (ft) and  $A_{\text{crit}} = y_c \cdot b + y_c \cdot \cot(\alpha) \quad A_{\text{crit}} = 49.0 \quad (\text{ft}^2)$


$$R_{\text{hcrit}} = \frac{y_c \cdot (b + y_c \cdot \cot(\alpha))}{b + \frac{2 \cdot y_c}{\sin(\alpha)}} \quad R_{\text{hcrit}} = 2.818 \quad (\text{ft})$$

Solving the basic equation for  $S_c$  
$$Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} \quad S_{\text{bcrit}} = \left( \frac{n \cdot Q}{1.49 \cdot A_{\text{crit}} \cdot R_{\text{hcrit}}^{\frac{2}{3}}} \right)^2 \quad S_{\text{bcrit}} = 0.00381$$

## Problem 11.67

[Difficulty: 2]

**11.67** A wide flat unfinished concrete channel discharges water at 20 ft<sup>3</sup>/s per foot of width. Find the critical slope (the slope at which depth is critical).



**Given:** Data on wide channel

**Find:** Critical slope

**Solution:**

Basic equations:  $Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$  and  $A = b \cdot y$   $R_h = y$

Note that the Q equation is an "engineering" equation, to be used without units!

Available data  $q = 20 \cdot \frac{\frac{\text{ft}^3}{\text{s}}}{\text{ft}}$

From Table 11.2  $n = 0.015$

For critical flow  $y = y_c$   $V_c = \sqrt{g \cdot y_c}$

so  $Q = A \cdot V_c = b \cdot y_c \cdot \sqrt{g \cdot y_c}$  or  $y_c = \left( \frac{Q}{b \cdot \sqrt{g}} \right)^{\frac{2}{3}}$   $y_c = \left( \frac{q}{\sqrt{g}} \right)^{\frac{2}{3}}$

Hence  $y_c = 2.316$  (ft)

Solving the basic equation for  $S_c$   $Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1.49}{n} \cdot b \cdot y_c \cdot y_c^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$

$$S_{\text{bcrit}} = \left( \frac{n \cdot Q}{1.49 \cdot b \cdot y_c \cdot y_c^{\frac{2}{3}}} \right)^2 \quad S_{\text{bcrit}} = \left( \frac{n \cdot q}{1.49 \cdot y_c^{\frac{5}{3}}} \right)^2 \quad S_{\text{bcrit}} = 0.00247$$


Note from Table 11.2 that a better roughness is  $n = 0.013$

and then  $S_{\text{bcrit}} = \left( \frac{n \cdot q}{1.49 \cdot y_c^{\frac{5}{3}}} \right)^2$   $S_{\text{bcrit}} = 0.00185$

## Problem 11.68

[Difficulty: 2]

**11.68** An optimum rectangular storm sewer channel made of unfinished concrete is to be designed to carry a maximum flow rate of 100 ft<sup>3</sup>/s, at which the flow is at critical condition. Determine the channel width and slope.



**Given:** Data on optimum rectangular channel

**Find:** Channel width and slope

**Solution:**

Basic equations:  $Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}}$  and from Table 11.3, for optimum geometry  $b = 2 \cdot y_n$

Note that the Q equation is an "engineering" equation, to be used without units!

Available data  $Q = 100 \frac{\text{ft}^3}{\text{s}}$   $n = 0.015$  (Table 11.2)

Hence  $A = b \cdot y_n = 2 \cdot y_n^2$   $R_h = \frac{A}{P} = \frac{2 \cdot y_n^2}{y_n + 2 \cdot y_n + y_n} = \frac{y_n}{2}$

We can write the Froude number in terms of Q

$$Fr = \frac{V}{\sqrt{g \cdot y}} = \frac{Q}{A \cdot \sqrt{g \cdot y}} = \frac{Q}{2 \cdot y_n^2 \cdot \sqrt{g \cdot y_n^{\frac{1}{2}}}} \quad \text{or} \quad Fr = \frac{Q}{2 \cdot \sqrt{g} \cdot y_n^{\frac{5}{2}}}$$

Hence for critical flow,  $Fr = 1$  and  $y_n = y_c$ , so  $1 = \frac{Q}{2 \cdot \sqrt{g} \cdot y_c^{\frac{5}{2}}}$  or  $Q = 2 \cdot \sqrt{g} \cdot y_c^{\frac{5}{2}}$

Hence  $y_c = \left( \frac{Q}{2 \cdot \sqrt{g}} \right)^{\frac{2}{5}}$   $y_c = 2.39$  (ft) and  $b = 2 \cdot y_c$   $b = 4.78$  (ft)

Then  $Q = \frac{1.49}{n} \cdot A \cdot R_h^{\frac{2}{3}} \cdot S_b^{\frac{1}{2}} = \frac{1.49}{n} \cdot 2 \cdot y_c^2 \cdot \left( \frac{y_c}{2} \right)^{\frac{2}{3}} \cdot S_c^{\frac{1}{2}}$  or  $Q = \frac{1.49 \cdot 2^{\frac{1}{3}}}{n} \cdot y_c^{\frac{8}{3}} \cdot S_c^{\frac{1}{2}}$


Hence  $S_c = \left( \frac{n \cdot Q}{\frac{1}{2^{\frac{1}{3}}} \cdot y_c^{\frac{8}{3}}} \right)^2$   $S_c = 0.00615$

Using (from Table 11.2)  $n = 0.013$   $S_c = \left( \frac{n \cdot Q}{\frac{1}{2^{\frac{1}{3}}} \cdot y_c^{\frac{8}{3}}} \right)^2$   $S_c = 0.00462$

## Problem 11.69

[Difficulty: 1]

**11.69** The crest of a broad-crested weir is 1 ft below the level of an upstream reservoir, where the water depth is 8 ft. For  $C_w \approx 3.4$ , what is the maximum flow rate per unit width that could pass over the weir?



**Given:** Data on broad-crested weir

**Find:** Maximum flow rate/width

**Solution:**

Basic equation: 
$$Q = C_w \cdot b \cdot H^{\frac{3}{2}}$$


Available data  $H = 1 \cdot \text{ft}$        $P = 8 \cdot \text{ft} - 1 \cdot \text{ft}$        $P = 7 \cdot \text{ft}$        $C_w = 3.4$

Then 
$$\frac{Q}{b} = q = C_w \cdot H^{\frac{3}{2}} = 3.4 \cdot \frac{\text{ft}^3}{\text{ft}}$$

## Problem 11.70

[Difficulty: 3]

**11.70** A rectangular, sharp-crested weir with end contraction is 1.6 m long. How high should it be placed in a channel to maintain an upstream depth of 2.5 m for 0.5 m<sup>3</sup>/s flow rate?



**Given:** Data on rectangular, sharp-crested weir

**Find:** Required weir height

**Solution:**

Basic equations:  $Q = C_d \cdot \frac{2}{3} \cdot \sqrt{2 \cdot g} \cdot b' \cdot H^{\frac{3}{2}}$  where  $C_d = 0.62$  and  $b' = b - 0.1 \cdot n \cdot H$  with  $n = 2$

Given data:  $b = 1.6 \cdot \text{m}$   $Q = 0.5 \cdot \frac{\text{m}^3}{\text{s}}$

Hence we find  $Q = C_d \cdot \frac{2}{3} \cdot \sqrt{2 \cdot g} \cdot b' \cdot H^{\frac{3}{2}} = C_d \cdot \frac{2}{3} \cdot \sqrt{2 \cdot g} \cdot (b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}}$

Rearranging  $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = \frac{3 \cdot Q}{2 \cdot \sqrt{2 \cdot g} \cdot C_d}$

This is a nonlinear implicit equation for H and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below.

The right side evaluates to  $\frac{3 \cdot Q}{2 \cdot \sqrt{2 \cdot g} \cdot C_d} = 0.273 \cdot \text{m}^{\frac{5}{2}}$

For  $H = 1 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 1.40 \cdot \text{m}^{\frac{5}{2}}$  For  $H = 0.5 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.530 \cdot \text{m}^{\frac{5}{2}}$

For  $H = 0.3 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.253 \cdot \text{m}^{\frac{5}{2}}$  For  $H = 0.35 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.317 \cdot \text{m}^{\frac{5}{2}}$

For  $H = 0.31 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.265 \cdot \text{m}^{\frac{5}{2}}$  For  $H = 0.315 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.272 \cdot \text{m}^{\frac{5}{2}}$


For  $H = 0.316 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.273 \cdot \text{m}^{\frac{5}{2}}$   $H = 0.316 \cdot \text{m}$

But from the figure  $H + P = 2.5 \cdot \text{m}$   $P = 2.5 \cdot \text{m} - H$   $P = 2.18 \cdot \text{m}$

## Problem 11.71

[Difficulty: 1]

**11.71** For a sharp-crested suppressed weir ( $C_w \approx 3.33$ ) of length  $B = 8.0$  ft,  $P = 2.0$  ft, and  $H = 1.0$  ft, determine the discharge over the weir. Neglect the velocity of approach head.



**Given:** Data on rectangular, sharp-crested weir

**Find:** Discharge

**Solution:**

Basic equation:  $Q = C_w \cdot b \cdot H^{\frac{3}{2}}$  where  $C_w = 3.33$  and  $b = 8 \cdot \text{ft}$   $P = 2 \cdot \text{ft}$   $H = 1 \cdot \text{ft}$


Note that this is an "engineering" equation, to be used without units!

$$Q = C_w \cdot b \cdot H^{\frac{3}{2}} \quad Q = 26.6 \frac{\text{ft}^3}{\text{s}}$$

## Problem 11.72

[Difficulty: 3]

**11.72** A rectangular sharp-crested weir with end contractions is 1.5 m long. How high should the weir crest be placed in a channel to maintain an upstream depth of 2.5 m for 0.5 m<sup>3</sup>/s flow rate?



**Given:** Data on rectangular, sharp-crested weir

**Find:** Required weir height

**Solution:**

Basic equations:  $Q = C_d \cdot \frac{2}{3} \cdot \sqrt{2 \cdot g} \cdot b' \cdot H^{\frac{3}{2}}$  where  $C_d = 0.62$  and  $b' = b - 0.1 \cdot n \cdot H$  with  $n = 2$

Given data:  $b = 1.5 \cdot \text{m}$   $Q = 0.5 \cdot \frac{\text{m}^3}{\text{s}}$

Hence we find  $Q = C_d \cdot \frac{2}{3} \cdot \sqrt{2 \cdot g} \cdot b' \cdot H^{\frac{3}{2}} = C_d \cdot \frac{2}{3} \cdot \sqrt{2 \cdot g} \cdot (b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}}$

Rearranging  $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = \frac{3 \cdot Q}{2 \cdot \sqrt{2 \cdot g} \cdot C_d}$

This is a nonlinear implicit equation for H and must be solved numerically. We can use one of a number of numerical root finding techniques, such as Newton's method, or we can use *Excel's Solver* or *Goal Seek*, or we can manually iterate, as below.

The right side evaluates to  $\frac{3 \cdot Q}{2 \cdot \sqrt{2 \cdot g} \cdot C_d} = 0.273 \cdot \text{m}^{\frac{5}{2}}$

For  $H = 1 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 1.30 \cdot \text{m}^{\frac{5}{2}}$  For  $H = 0.5 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.495 \cdot \text{m}^{\frac{5}{2}}$

For  $H = 0.3 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.237 \cdot \text{m}^{\frac{5}{2}}$  For  $H = 0.35 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.296 \cdot \text{m}^{\frac{5}{2}}$

For  $H = 0.34 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.284 \cdot \text{m}^{\frac{5}{2}}$  For  $H = 0.33 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.272 \cdot \text{m}^{\frac{5}{2}}$


For  $H = 0.331 \cdot \text{m}$   $(b - 0.1 \cdot n \cdot H) \cdot H^{\frac{3}{2}} = 0.273 \cdot \text{m}^{\frac{5}{2}}$   $H = 0.331 \text{ m}$

But from the figure  $H + P = 2.5 \cdot \text{m}$   $P = 2.5 \cdot \text{m} - H$   $P = 2.17 \text{ m}$

## Problem 11.73

[Difficulty: 1]

**11.73** Determine the head on a  $60^\circ$  V-notch weir for a discharge of 150 L/s. Take  $C_d \approx 0.58$ .



**Given:** Data on V-notch weir

**Find:** Flow head

**Solution:**

Basic equation: 
$$Q = C_d \cdot \frac{8}{15} \cdot \sqrt{2 \cdot g} \cdot \tan\left(\frac{\theta}{2}\right) \cdot H^{\frac{5}{2}}$$
 where  $C_d = 0.58$      $\theta = 60\text{-deg}$      $Q = 150 \frac{\text{L}}{\text{s}}$


$$H = \left( \frac{Q}{C_d \cdot \frac{8}{15} \cdot \sqrt{2 \cdot g} \cdot \tan\left(\frac{\theta}{2}\right)} \right)^{\frac{2}{5}}$$

$H = 0.514\text{m}$

## Problem 11.74

[Difficulty: 1]

**11.74** The head on a 90° V-notch weir is 1.5 ft. Determine the discharge.



**Given:** Data on V-notch weir

**Find:** Discharge

**Solution:**

Basic equation:  $Q = C_w \cdot H^{\frac{5}{2}}$  where  $H = 1.5 \text{ ft}$   $C_w = 2.50$  for  $\theta = 90\text{-deg}$


Note that this is an "engineering" equation in which we ignore units!

$$Q = C_w \cdot H^{\frac{5}{2}} \qquad Q = 6.89 \frac{\text{ft}^3}{\text{s}}$$

## Problem 11.75

[Difficulty: 1]

**11.75** Determine the weir coefficient of a 90° V-notch weir for a head of 180 mm for a flow rate of 20 L/s.



**Given:** Data on V-notch weir

**Find:** Weir coefficient

**Solution:**

Basic equation:  $Q = C_w \cdot H^{\frac{5}{2}}$  where  $H = 180 \cdot \text{mm}$   $Q = 20 \cdot \frac{\text{L}}{\text{s}}$

Note that this is an "engineering" equation in which we ignore units!

$$C_w = \frac{Q}{H^{\frac{5}{2}}} \quad C_w = 1.45$$

## Problem 12.1

[Difficulty: 2]

**12.1** An air flow in a duct passes through a thick filter. What happens to the pressure, temperature, and density of the air as it does so? *Hint:* This is a throttling process.

**Given:** Air flow through a filter

**Find:** Change in  $p$ ,  $T$  and  $\rho$

**Solution:**

Basic equations:  $h_2 - h_1 = c_p \cdot (T_2 - T_1)$   $p = \rho \cdot R \cdot T$

Assumptions: 1) Ideal gas 2) Throttling process

In a throttling process enthalpy is constant. Hence  $h_2 - h_1 = 0$  so  $T_2 - T_1 = 0$  or  $T = \text{constant}$

The filter acts as a resistance through which there is a pressure drop (otherwise there would be no flow. Hence  $p_2 < p_1$

From the ideal gas equation  $\frac{p_1}{p_2} = \frac{\rho_1 \cdot T_1}{\rho_2 \cdot T_2}$  so  $\rho_2 = \rho_1 \cdot \left(\frac{T_1}{T_2}\right) \cdot \left(\frac{p_2}{p_1}\right) = \rho_1 \cdot \left(\frac{p_2}{p_1}\right)$  Hence  $\rho_2 < \rho_1$

The governing equation for entropy is  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$

Hence  $\Delta s = -R \cdot \ln\left(\frac{p_2}{p_1}\right)$  and  $\frac{p_2}{p_1} < 1$  so  $\Delta s > 0$

Entropy increases because throttling is an irreversible adiabatic process

## Problem 12.2

[Difficulty: 2]

**12.2** Air is expanded in a steady flow process through a turbine. Initial conditions are 1300°C and 2.0 MPa (abs). Final conditions are 500°C and atmospheric pressure. Show this process on a  $Ts$  diagram. Evaluate the changes in internal energy, enthalpy, and specific entropy for this process.

Solution:

$$\Delta u = u_2 - u_1 = c_v (T_2 - T_1) = 717.4 \frac{\text{J}}{\text{kg}\cdot\text{K}} (500 - 1300) \text{K} = -574 \text{ kJ/kg} \quad \leftarrow u_2 - u_1$$

$$\Delta h = h_2 - h_1 = c_p (T_2 - T_1) = 1004 \frac{\text{J}}{\text{kg}\cdot\text{K}} (-800 \text{K}) = -803 \text{ kJ/kg} \quad \leftarrow h_2 - h_1$$

To calculate the entropy change, we use the Tds equation


$$T ds = dh - v dp = c_p dT - RT \frac{dp}{p}$$

$$\therefore ds = c_p \frac{dT}{T} - R \frac{dp}{p}$$

$$s_2 - s_1 = c_p \ln \frac{T_2}{T_1} - R \ln \frac{p_2}{p_1}$$

$$= 1004 \frac{\text{J}}{\text{kg}\cdot\text{K}} \ln \frac{500 + 273}{1300 + 273} - 286.9 \frac{\text{J}}{\text{kg}\cdot\text{K}} \ln \frac{0.101}{2.0}$$

$$s_2 - s_1 = (-713.3 + 856.6) \text{ J/kg}\cdot\text{K} = 143 \text{ J/kg}\cdot\text{K} \quad \leftarrow s_2 - s_1$$



## Problem 12.3

[Difficulty: 2]

**12.3** A vendor claims that an adiabatic air compressor takes in air at atmosphere pressure and 50°F and delivers the air at 150 psig and 200°F. Is this possible? Justify your answer by calculation. Sketch the process on a  $Ts$  diagram.

**Given:** Data on an air compressor

**Find:** Whether or not the vendor claim is feasible

**Solution:**

Basic equation: 
$$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$$

The data provided, or available in the Appendices, is:

$$p_1 = 14.7 \cdot \text{psi}$$

$$T_1 = (50 + 460) \cdot \text{R}$$

$$p_2 = (150 + 14.7) \cdot \text{psi}$$

$$T_2 = (200 + 460) \cdot \text{R}$$

$$c_p = 0.2399 \cdot \frac{\text{BTU}}{\text{lb} \cdot \text{R}}$$


$$R_{\text{gas}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lb} \cdot \text{R}} = 0.0685 \cdot \frac{\text{BTU}}{\text{lb} \cdot \text{R}}$$

Then 
$$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{gas}} \cdot \ln\left(\frac{p_2}{p_1}\right) \quad \Delta s = -0.1037 \cdot \frac{\text{BTU}}{\text{lb} \cdot \text{R}}$$

We have plotted the actual process in red (1-2) on this temperature-entropy diagram, and the ideal compression (isentropic) in blue (1-2s). The line of constant pressure equal to 150 psig is shown in green. However, can this process actually occur? The second law of thermodynamics states that, for an adiabatic process

$$\Delta s \geq 0 \quad \text{or for all real processes} \quad \Delta s > 0$$

Hence the process is NOT feasible!



## Problem 12.4

[Difficulty: 2]

**12.4** A turbine manufacturer claims that an adiabatic gas turbine can take flow at 10 atmospheres and 2200°F and exhaust to atmospheric pressure at a temperature of 850°F. Sketch the process on a  $Ts$  diagram, and prove whether the manufacturer's claims are possible. Assume that the gas has the same properties as air.

**Given:** Data on turbine inlet and exhaust

**Find:** Whether or not the vendor claim is feasible

**Solution:**

Basic equation: 
$$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$$

The data provided, or available in the Appendices, is:

$$p_1 = 10 \cdot \text{atm} = 146.959 \cdot \text{psi} \qquad T_1 = (2200 + 460) \cdot \text{R} \qquad T_1 = 1.478 \times 10^3 \text{ K}$$

$$p_2 = 1 \cdot \text{atm} = 14.696 \cdot \text{psi} \qquad T_2 = (850 + 460) \cdot \text{R} \qquad T_2 = 727.778 \text{ K}$$


$$c_p = 0.2399 \cdot \frac{\text{BTU}}{\text{lb} \cdot \text{R}} \qquad R_{\text{gas}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lb} \cdot \text{R}} = 0.0685 \cdot \frac{\text{BTU}}{\text{lb} \cdot \text{R}}$$

Then 
$$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{gas}} \cdot \ln\left(\frac{p_2}{p_1}\right) \qquad \Delta s = -0.0121 \cdot \frac{\text{BTU}}{\text{lb} \cdot \text{R}}$$

An example of this type of process is plotted in green on the graph. Also plotted are an isentropic process (blue - 1-2s) and one with an increase in entropy (red: 1-2i). All three processes expand to the same pressure. The constant pressure curve is drawn in purple. The second law of thermodynamics states that, for an adiabatic process

$$\Delta s \geq 0 \quad \text{or for all real processes} \quad \Delta s > 0$$

Hence the process is NOT feasible!



## Problem 12.5

[Difficulty: 2]

**12.5** Air initially at 50 psia and 660°R expands to atmospheric pressure. The process by which this expansion occurs is defined by the expression  $pV^{1.3} = \text{constant}$ . Calculate the final temperature and the change in entropy through this process.

**Given:** Air before and after expansion; process

**Find:** Final temperature and change in entropy

**Solution:**

Basic equations:  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$   $p \cdot V = m \cdot R \cdot T$

The data provided, or available in the Appendices, is:

$$p_1 = 50 \cdot \text{psi}$$

$$T_1 = 660 \cdot \text{R}$$

$$p_2 = 1 \cdot \text{atm} = 14.696 \cdot \text{psi}$$

$$c_p = 0.2399 \cdot \frac{\text{Btu}}{\text{lb} \cdot \text{R}}$$

$$R_{\text{gas}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lb} \cdot \text{R}} = 0.0685 \cdot \frac{\text{Btu}}{\text{lb} \cdot \text{R}}$$

From the process given:  $p_1 \cdot V_1^{1.3} = p_2 \cdot V_2^{1.3}$  From the ideal gas equation of state:  $\frac{p_2 \cdot V_2}{p_1 \cdot V_1} = \frac{T_2}{T_1}$   $\frac{V_1}{V_2} = \frac{p_2}{p_1} \cdot \frac{T_1}{T_2}$

When we combine these two equations we get:  $\frac{p_2}{p_1} = \left(\frac{V_1}{V_2}\right)^{1.3} = \left(\frac{p_2}{p_1} \cdot \frac{T_1}{T_2}\right)^{1.3}$  Solving for temperature ratio:  $\frac{T_1}{T_2} = \left(\frac{p_2}{p_1}\right)^{\frac{1}{1.3}-1}$

So the final temperature is:  $T_2 = T_1 \cdot \left(\frac{p_1}{p_2}\right)^{\frac{1}{1.3}-1}$   $T_2 = 497.5 \cdot \text{R}$

Then  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{gas}} \cdot \ln\left(\frac{p_2}{p_1}\right)$   $\Delta s = 0.0161 \cdot \frac{\text{Btu}}{\text{lb} \cdot \text{R}}$

## Problem 12.6

[Difficulty: 2]

**12.6** What is the lowest possible delivery temperature generated by an adiabatic air compressor, starting with standard atmosphere conditions and delivering the air at 500 kPa (gage)? Sketch the process on a  $Ts$  diagram.

**Given:** Adiabatic air compressor

**Find:** Lowest delivery temperature; Sketch the process on a  $Ts$  diagram

**Solution:**

Basic equation: 
$$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$$


The lowest temperature implies an ideal (reversible) process; it is also adiabatic, so  $\Delta s = 0$ , and

$$T_2 = T_1 \cdot \left(\frac{p_1}{p_2}\right)^{\frac{1-k}{k}}$$

The data provided, or available in the Appendices, is:  $p_1 = 101 \cdot \text{kPa}$   $p_2 = (500 + 101) \cdot \text{kPa}$   $T_1 = 288.2 \cdot \text{K}$   $k = 1.4$

Hence 
$$T_2 = T_1 \cdot \left(\frac{p_1}{p_2}\right)^{\frac{1-k}{k}} \quad T_2 = 864 \cdot \text{R}$$

The process is



## Problem 12.7

[Difficulty: 2]

**12.7** Air expands without heat transfer through a turbine from a pressure of 10 bars and a temperature of 1400 K to a pressure of 1 bar. If the turbine has an efficiency of 80 percent, determine the exit temperature, and the changes in enthalpy and entropy across the turbine. If the turbine is generating 1 MW of power, what is the mass flow rate of air through the turbine?

**Given:** Data on turbine inlet and exhaust

**Find:** Whether or not the vendor claim is feasible

**Solution:**

Basic equations:  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$        $\Delta h = c_p \cdot \Delta T$        $\frac{T_2}{T_1} = \left(\frac{p_2}{p_1}\right)^{\frac{k-1}{k}}$  when s = constant

$$\eta = \frac{h_1 - h_2}{h_1 - h_{2s}} = \frac{T_1 - T_2}{T_1 - T_{2s}}$$

The data provided, or available in the Appendices, is:

$$p_1 = 10 \cdot \text{bar} = 1 \times 10^3 \cdot \text{kPa} \qquad T_1 = 1400 \cdot \text{K} \qquad \eta = 80\% \qquad P = 1 \cdot \text{MW}$$

$$p_2 = 1 \cdot \text{bar} = 100 \cdot \text{kPa}$$

$$c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \qquad R_{\text{gas}} = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \qquad k = 1.4$$

If the expansion were isentropic, the exit temperature would be:  $T_{2s} = T_1 \cdot \left(\frac{p_2}{p_1}\right)^{\frac{k-1}{k}} = 725.126 \text{ K}$

Since the turbine is not isentropic, the final temperature is higher:  $T_2 = T_1 - \eta \cdot (T_1 - T_{2s}) = 860.101 \text{ K}$

Then  $\Delta h = c_p \cdot (T_1 - T_2) = 542.058 \cdot \frac{\text{kJ}}{\text{kg}}$        $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{gas}} \cdot \ln\left(\frac{p_2}{p_1}\right)$        $\Delta s = 171.7157 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

The mass flow rate is:  $m = \frac{P}{\Delta h} = 1.845 \frac{\text{kg}}{\text{s}}$

## Problem 12.8

[Difficulty: 2]

**12.8** A test chamber is separated into two equal chambers by a rubber diaphragm. One contains air at 20°C and 200 kPa (absolute), and the other has a vacuum. If the diaphragm is punctured, find the pressure and temperature of the air after it expands to fill the chamber. *Hint:* This is a rapid, violent event, so is irreversible but adiabatic.

**Given:** Test chamber with two chambers

**Find:** Pressure and temperature after expansion

**Solution:**

Basic equation:  $p = \rho \cdot R \cdot T$   $\Delta u = q - w$  (First law - closed system)  $\Delta u = c_v \cdot \Delta T$

Assumptions: 1) Ideal gas 2) Adiabatic 3) No work

For no work and adiabatic the first law becomes  $\Delta u = 0$  or for an Ideal gas  $\Delta T = 0$   $T_2 = T_1$

We also have  $M = \rho \cdot \text{Vol} = \text{const}$  and  $\text{Vol}_2 = 2 \cdot \text{Vol}_1$  so  $\rho_2 = \frac{1}{2} \cdot \rho_1$

From the ideal gas equation  $\frac{p_2}{p_1} = \frac{\rho_2}{\rho_1} \cdot \frac{T_2}{T_1} = \frac{1}{2}$  so  $p_2 = \frac{1}{2} \cdot p_1$

Hence  $T_2 = 20^\circ\text{F}$   $p_2 = \frac{200 \cdot \text{kPa}}{2}$   $p_2 = 100 \cdot \text{kPa}$

Note that  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right) = -R \cdot \ln\left(\frac{1}{2}\right) = 0.693 \cdot R$  so entropy increases (irreversible adiabatic)

## Problem 12.9

[Difficulty: 2]

**12.9** An automobile supercharger is a device that pressurizes the air that is used by the engine for combustion to increase the engine power (how does it differ from a turbocharger?). A supercharger takes in air at 70°F and atmospheric pressure and boosts it to 200 psig, at an intake rate of 0.5 ft<sup>3</sup>/s. What are the pressure, temperature, and volume flow rate at the exit? (The relatively high exit temperature is the reason an inter-cooler is also used.) Assuming a 70 percent efficiency, what is the power drawn by the supercharger? *Hint:* The efficiency is defined as the ratio of the isentropic power to actual power.

**Given:** Supercharger

**Find:** Pressure, temperature and flow rate at exit; power drawn

**Solution:**

Basic equation:  $p = \rho \cdot R_{\text{air}} \cdot T$   $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$

$\Delta h = q - w$  (First law - open system)  $\Delta h = c_p \cdot \Delta T$

Assumptions: 1) Ideal gas 2) Adiabatic

In an ideal process (reversible and adiabatic) the first law becomes  $\Delta h = w$  or for an ideal gas  $w_{\text{ideal}} = c_p \cdot \Delta T$

For an isentropic process  $\Delta s = 0 = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$  or  $\frac{T_2}{T_1} = \left(\frac{p_2}{p_1}\right)^{\frac{k-1}{k}}$

The given or available data is  $T_1 = (70 + 460) \cdot R$   $p_1 = 14.7 \cdot \text{psi}$   $p_2 = (200 + 14.7) \cdot \text{psi}$   $\eta = 70\%$

$Q_1 = 0.5 \cdot \frac{\text{ft}^3}{\text{s}}$   $k = 1.4$   $c_p = 0.2399 \cdot \frac{\text{Btu}}{\text{lbm} \cdot \text{R}}$   $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$

Hence  $T_2 = \left(\frac{p_2}{p_1}\right)^{\frac{k-1}{k}} \cdot T_1$   $T_2 = 1140 \cdot R$   $T_2 = 681 \cdot ^\circ\text{F}$   $p_2 = 215 \cdot \text{psi}$

We also have  $m_{\text{rate}} = \rho_1 \cdot Q_1 = \rho_2 \cdot Q_2$   $Q_2 = Q_1 \cdot \frac{\rho_1}{\rho_2}$   $Q_2 = Q_1 \cdot \frac{p_1}{p_2} \cdot \frac{T_2}{T_1}$   $Q_2 = 0.0737 \cdot \frac{\text{ft}^3}{\text{s}}$

For the power we use  $P_{\text{ideal}} = m_{\text{rate}} \cdot w_{\text{ideal}} = \rho_1 \cdot Q_1 \cdot c_p \cdot \Delta T$

From the ideal gas equation  $\rho_1 = \frac{p_1}{R_{\text{air}} \cdot T_1}$   $\rho_1 = 0.00233 \cdot \frac{\text{slug}}{\text{ft}^3}$  or  $\rho_1 = 0.0749 \cdot \frac{\text{lbm}}{\text{ft}^3}$

Hence  $P_{\text{ideal}} = \rho_1 \cdot Q_1 \cdot c_p \cdot (T_2 - T_1)$   $P_{\text{ideal}} = 5.78 \cdot \text{kW}$

The actual power needed is  $P_{\text{actual}} = \frac{P_{\text{ideal}}}{\eta}$   $P_{\text{actual}} = 8.26 \cdot \text{kW}$

A supercharger is a pump that forces air into an engine, but generally refers to a pump that is driven directly by the engine, as opposed to a turbocharger that is driven by the pressure of the exhaust gases.

## Problem 12.10

[Difficulty: 2]

**12.10** Five kilograms of air is cooled in a closed tank from 250 to 50°C. The initial pressure is 3 MPa. Compute the changes in entropy, internal energy, and enthalpy. Show the process state points on a  $Ts$  diagram.

**Given:** Cooling of air in a tank

**Find:** Change in entropy, internal energy, and enthalpy

**Solution:**

Basic equation:	$p = \rho \cdot R \cdot T$	$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$
	$\Delta u = c_v \cdot \Delta T$	$\Delta h = c_p \cdot \Delta T$

Assumptions: 1) Ideal gas 2) Constant specific heats


Given or available data	M = 5·kg	T <sub>1</sub> = (250 + 273)·K	T <sub>2</sub> = (50 + 273)·K	p <sub>1</sub> = 3·MPa
	$c_p = 1004 \frac{\text{J}}{\text{kg}\cdot\text{K}}$	$c_v = 717.4 \frac{\text{J}}{\text{kg}\cdot\text{K}}$	$k = \frac{c_p}{c_v} = 1.4$	$R = c_p - c_v = 287 \frac{\text{J}}{\text{kg}\cdot\text{K}}$

For a constant volume process the ideal gas equation gives:  $\frac{p_2}{p_1} = \frac{T_2}{T_1}$       $p_2 = \frac{T_2}{T_1} \cdot p_1$       $p_2 = 1.85 \text{ MPa}$

Then	$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$	$\Delta s = -346 \frac{\text{J}}{\text{kg}\cdot\text{K}}$
	$\Delta u = c_v \cdot (T_2 - T_1)$	$\Delta u = -143 \frac{\text{kJ}}{\text{kg}}$
	$\Delta h = c_p \cdot (T_2 - T_1)$	$\Delta h = -201 \frac{\text{kJ}}{\text{kg}}$

Total amounts are	$\Delta S = M \cdot \Delta s$	$\Delta S = -1729 \frac{\text{J}}{\text{K}}$
	$\Delta U = M \cdot \Delta u$	$\Delta U = -717 \text{ kJ}$
	$\Delta H = M \cdot \Delta h$	$\Delta H = -1004 \text{ kJ}$

Here is a plot of the T-s diagram:



## Problem 12.11

[Difficulty: 3]

**12.11** Air is contained in a piston-cylinder device. The temperature of the air is 100°C. Using the fact that for a reversible process the heat transfer  $q = \int T ds$ , compare the amount of heat (J/kg) required to raise the temperature of the air to 1200°C at (a) constant pressure and (b) constant volume. Verify your results using the first law of thermodynamics. Plot the processes on a  $Ts$  diagram.

**Given:** Air in a piston-cylinder

**Find:** Heat to raise temperature to 1200°C at a) constant pressure and b) constant volume

**Solution:**

The data provided, or available in the Appendices, is:

$$T_1 = (100 + 273) \cdot \text{K} \quad T_2 = (1200 + 273) \cdot \text{K} \quad R = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad c_v = c_p - R \quad c_v = 717 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$$

a) For a constant pressure process we start with  $T \cdot ds = dh - v \cdot dp$

Hence, for  $p = \text{const.}$   $ds = \frac{dh}{T} = c_p \cdot \frac{dT}{T}$

But  $\delta q = T \cdot ds$

Hence  $\delta q = c_p \cdot dT \quad q = \int c_p dT \quad q = c_p \cdot (T_2 - T_1) \quad q = 1104 \cdot \frac{\text{kJ}}{\text{kg}}$

b) For a constant volume process we start  $T \cdot ds = du + p \cdot dv$

Hence, for  $v = \text{const.}$   $ds = \frac{du}{T} = c_v \cdot \frac{dT}{T}$

But  $\delta q = T \cdot ds$

Hence  $\delta q = c_v \cdot dT \quad q = \int c_v dT \quad q = c_v \cdot (T_2 - T_1) \quad q = 789 \cdot \frac{\text{kJ}}{\text{kg}}$

Heating to a higher temperature at constant pressure requires more heat than at constant volume: some of the heat is used to do work in expanding the gas; hence for constant pressure less of the heat is available for raising the temperature.

From the first law:      Constant pressure:  $q = \Delta u + w$       Constant volume:  $q = \Delta u$


The two processes can be plotted using Eqs. 11.11b and 11.11a, simplified for the case of constant pressure and constant volume.

a) For constant pressure  $s_2 - s_1 = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$       so       $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right)$

b) For constant volume  $s_2 - s_1 = c_v \cdot \ln\left(\frac{T_2}{T_1}\right) + R \cdot \ln\left(\frac{v_2}{v_1}\right)$       so       $\Delta s = c_v \cdot \ln\left(\frac{T_2}{T_1}\right)$

The processes are plotted in *Excel* and shown on the next page

### T-s Diagram for Constant Pressure and Constant Volume Processes



## Problem 12.12

[Difficulty: 4]

**12.12** The four-stroke Otto cycle of a typical automobile engine is sometimes modeled as an ideal air-standard closed system. In this simplified system the combustion process is modeled as a heating process, and the exhaust-intake process as a cooling process of the working fluid (air). The cycle consists of: isentropic compression from state ① ( $p_1 = 100$  kPa (abs),  $T_1 = 20^\circ\text{C}$ ,  $V_1 = 500$  cc) to state ② ( $V_2 = V_1/8.5$ ); isometric (constant volume) heat addition to state ③ ( $T_3 = 2750^\circ\text{C}$ ); isentropic expansion to state ④ ( $V_4 = V_1$ ); and isometric cooling back to state ①. Plot the  $pV$  and  $Ts$  diagrams for this cycle, and find the efficiency, defined as the net work (the cycle area in  $pV$  space) divided by the heat added.

**Given:** Data on Otto cycle

**Find:** Plot of  $pV$  and  $Ts$  diagrams; efficiency

**Solution:**

The data provided, or available in the Appendices, is:

$$c_p = 1004 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad R = 287 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad c_v = c_p - R \quad c_v = 717 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad k = \frac{c_p}{c_v} \quad k = 1.4$$

$$p_1 = 100 \cdot \text{kPa} \quad T_1 = (20 + 273) \cdot \text{K} \quad T_3 = (2750 + 273) \cdot \text{K} \quad V_1 = 500 \cdot \text{cc} \quad V_2 = \frac{V_1}{8.5} \quad V_2 = 58.8 \cdot \text{cc}$$

$$V_4 = V_1$$

Computed results:  $M = \frac{p_1 \cdot V_1}{R \cdot T_1} \quad M = 5.95 \times 10^{-4} \text{ kg}$

For process 1-2 we have isentropic behavior  $T \cdot v^{k-1} = \text{constant} \quad p \cdot v^k = \text{constant} \quad (12.12 \text{ a and } 12.12 \text{ b})$

Hence  $T_2 = T_1 \cdot \left(\frac{V_1}{V_2}\right)^{k-1} \quad T_2 = 690 \text{ K} \quad p_2 = p_1 \cdot \left(\frac{V_1}{V_2}\right)^k \quad p_2 = 2002 \cdot \text{kPa}$

The process from 1 -2 is  $p(V) = p_1 \cdot \left(\frac{V_1}{V}\right)^k$  and  $s = \text{constant}$

The work is  $W_{12} = \left( \int_{V_1}^{V_2} p(V) dV = \frac{p_1 \cdot V_1 - p_2 \cdot V_2}{k - 1} \right) \quad W_{12} = -169 \text{ J} \quad Q_{12} = 0 \cdot \text{J} \quad (\text{Isentropic})$

For process 2 - 3 we have constant volume  $V_3 = V_2 \quad V_3 = 58.8 \cdot \text{cc}$

Hence  $p_3 = p_2 \cdot \frac{T_3}{T_2} \quad p_3 = 8770 \cdot \text{kPa}$

The process from 2 - 3 is  $V = V_2 = \text{constant}$  and  $\Delta s = c_v \cdot \ln\left(\frac{T}{T_2}\right)$   $W_{23} = 0 \cdot \text{J}$   
 (From 12.11a)

$$Q_{23} = M \cdot \Delta u = M \cdot \int c_v dT \quad Q_{23} = M \cdot c_v \cdot (T_3 - T_2) \quad Q_{23} = 995 \text{ J}$$

For process 3 - 4 we again have isentropic behavior

Hence  $T_4 = T_3 \cdot \left(\frac{V_3}{V_4}\right)^{k-1}$   $T_4 = 1284 \text{ K}$   $p_4 = p_3 \cdot \left(\frac{V_3}{V_4}\right)^k$   $p_4 = 438 \cdot \text{kPa}$

The process from 3 - 4 is  $p(V) = p_3 \cdot \left(\frac{V_3}{V}\right)^k$  and  $s = \text{constant}$

The work is  $W_{34} = \frac{p_3 \cdot V_3 - p_4 \cdot V_4}{k - 1}$   $W_{34} = 742 \text{ J}$   $Q_{34} = 0 \cdot \text{J}$

For process 4-1 we again have constant volume

The process from 4 - 1 is  $V = V_4 = \text{constant}$  and  $\Delta s = c_v \cdot \ln\left(\frac{T}{T_4}\right)$   $W_{41} = 0 \cdot \text{J}$   
 (From 12.11a)

$$Q_{41} = M \cdot c_v \cdot (T_1 - T_4) \quad Q_{41} = -422 \text{ J}$$

The net work is  $W_{\text{net}} = W_{12} + W_{23} + W_{34} + W_{41}$   $W_{\text{net}} = 572 \text{ J}$



The efficiency is  $\eta = \frac{W_{\text{net}}}{Q_{23}}$   $\eta = 57.5 \cdot \%$

This is consistent with the expression for the Otto efficiency  $\eta_{\text{Otto}} = 1 - \frac{1}{r^{k-1}}$

where  $r$  is the compression ratio  $r = \frac{V_1}{V_2}$   $r = 8.5$

$$\eta_{\text{Otto}} = 57.5 \cdot \%$$

Plots of the cycle in  $pV$  and  $Ts$  space, generated using *Excel*, are shown on the next page.



## Problem 12.13

[Difficulty: 4]

**12.13** The four-stroke cycle of a typical diesel engine is sometimes modeled as an ideal air-standard closed system. In this simplified system the combustion process is modeled as a heating process, and the exhaust-intake process as a cooling process of the working fluid (air). The cycle consists of: isentropic compression from state ① ( $p_1 = 100 \text{ kPa (abs)}$ ,  $T_1 = 20^\circ\text{C}$ ,  $V_1 = 500 \text{ cc}$ ) to state ② ( $V_2 = V_1/12.5$ ); isometric (constant volume) heat addition to state ③ ( $T_3 = 3000^\circ\text{C}$ ); isobaric heat addition to state ④ ( $V_4 = 1.75V_3$ ); isentropic expansion to state ⑤; and isometric cooling back to state ①. Plot the  $pV$  and  $Ts$  diagrams for this cycle, and find the efficiency, defined as the net work (the cycle area in  $pV$  space) divided by the heat added.

**Given:** Data on diesel cycle

**Find:** Plot of  $pV$  and  $Ts$  diagrams; efficiency

**Solution:**

The data provided, or available in the Appendices, is:

$$c_p = 1004 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad R = 287 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad c_v = c_p - R \quad c_v = 717 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad k = \frac{c_p}{c_v} \quad k = 1.4$$

$$p_1 = 100 \cdot \text{kPa} \quad T_1 = (20 + 273) \cdot \text{K} \quad T_3 = (3000 + 273) \cdot \text{K} \quad V_1 = 500 \cdot \text{cc}$$

$$V_2 = \frac{V_1}{12.5} \quad V_2 = 40 \cdot \text{cc} \quad V_3 = V_2 \quad V_4 = 1.75 \cdot V_3 \quad V_4 = 70 \cdot \text{cc} \quad V_5 = V_1$$

Computed results:  $M = \frac{p_1 \cdot V_1}{R \cdot T_1} \quad M = 5.95 \times 10^{-4} \text{ kg}$

For process 1-2 we have isentropic behavior  $T \cdot v^{k-1} = \text{constant} \quad (12.12a) \quad p \cdot v^k = \text{constant} \quad (12.12c)$

Hence  $T_2 = T_1 \cdot \left(\frac{V_1}{V_2}\right)^{k-1} \quad T_2 = 805 \text{ K} \quad p_2 = p_1 \cdot \left(\frac{V_1}{V_2}\right)^k \quad p_2 = 3435 \cdot \text{kPa}$

The process from 1-2 is  $p(V) = p_1 \cdot \left(\frac{V_1}{V}\right)^k$  and  $s = \text{constant}$

The work is  $W_{12} = \int_{V_1}^{V_2} p(V) dV = \frac{p_1 \cdot V_1 - p_2 \cdot V_2}{k - 1} \quad W_{12} = -218 \text{ J} \quad Q_{12} = 0 \cdot \text{J} \quad (\text{Isentropic})$

For process 2-3 we have constant volume  $V_3 = V_2 \quad V_3 = 40 \cdot \text{cc}$

Hence  $p_3 = p_2 \cdot \frac{T_3}{T_2} \quad p_3 = 13963 \cdot \text{kPa}$

The process from 2 -3 is  $V = V_2 = \text{constant}$  and  $\Delta s = c_v \cdot \ln\left(\frac{T}{T_2}\right)$   $W_{23} = 0 \cdot \text{J}$   
 (From Eq. 12.11a)

$$Q_{23} = M \cdot \Delta u = M \cdot \int c_v dT \quad Q_{23} = M \cdot c_v \cdot (T_3 - T_2) \quad Q_{23} = 1052 \text{ J}$$

For process 3 - 4 we have constant pressure  $p_4 = p_3$   $p_4 = 13963 \cdot \text{kPa}$   $T_4 = T_3 \cdot \left(\frac{V_4}{V_3}\right)$   $T_4 = 5728 \text{ K}$

The process from 3 - 4 is  $p = p_3 = \text{constant}$  and  $\Delta s = c_p \cdot \ln\left(\frac{T}{T_3}\right)$   
 (From Eq. 12.11b)

$$W_{34} = p_3 \cdot (V_4 - V_3) \quad W_{34} = 419 \text{ J} \quad Q_{34} = M \cdot c_p \cdot (T_4 - T_3) \quad Q_{34} = 1465 \text{ J}$$

For process 4 - 5 we again have isentropic behavior  $T_5 = T_4 \cdot \left(\frac{V_4}{V_5}\right)^{k-1}$   $T_5 = 2607 \cdot \text{K}$

Hence  $p_5 = p_4 \cdot \left(\frac{V_4}{V_5}\right)^k$   $p_5 = 890 \cdot \text{kPa}$

The process from 4 - 5 is  $p(V) = p_4 \cdot \left(\frac{V_4}{V}\right)^k$  and  $s = \text{constant}$

The work is  $W_{45} = \frac{p_4 \cdot V_4 - p_5 \cdot V_5}{k - 1}$   $W_{45} = 1330 \text{ J}$   $Q_{45} = 0 \cdot \text{J}$

For process 5-1 we again have constant volume

The process from 5 -1 is  $V = V_5 = \text{constant}$  and  $\Delta s = c_v \cdot \ln\left(\frac{T}{T_5}\right)$   
 (From Eq. 12.11a)

$$Q_{51} = M \cdot c_v \cdot (T_1 - T_5) \quad Q_{51} = -987 \text{ J} \quad W_{51} = 0 \cdot \text{J}$$

The net work is  $W_{\text{net}} = W_{12} + W_{23} + W_{34} + W_{45} + W_{51}$   $W_{\text{net}} = 1531 \text{ J}$

The heat added is  $Q_{\text{added}} = Q_{23} + Q_{34}$   $Q_{\text{added}} = 2517 \text{ J}$

The efficiency is  $\eta = \frac{W_{\text{net}}}{Q_{\text{added}}}$   $\eta = 60.8 \cdot \%$

This is consistent with the expression from thermodynamics for the diesel efficiency



$$\eta_{\text{diesel}} = 1 - \frac{1}{r^{k-1}} \cdot \left[ \frac{r_c^k - 1}{k \cdot (r_c - 1)} \right]$$

where  $r$  is the compression ratio  $r = \frac{V_1}{V_2} \quad r = 12.5$

and  $r_c$  is the cutoff ratio  $r_c = \frac{V_4}{V_3} \quad r_c = 1.75$

$$\eta_{\text{diesel}} = 58.8\%$$

The plots of the cycle in  $pV$  and  $Ts$  space, generated using *Excel*, are shown here:



## Problem 12.14

[Difficulty: 3]

**12.14** A 1-m<sup>3</sup> tank contains air at 0.1 MPa (abs) and 20°C. The tank is pressurized to 2 MPa. Assuming that the tank is filled adiabatically and reversibly, calculate the final temperature of the air in the tank. Now assuming that the tank is filled isothermally, how much heat is lost by the air in the tank during filling? Which process (adiabatic or isothermal) results in a greater mass of air in the tank?

**Given:** Air is compressed from standard conditions to fill a tank

**Find:** (a) Final temperature of air if tank is filled adiabatically and reversibly  
 (b) Heat lost if tank is filled isothermally  
 (c) Which process results in a greater mass of air in the tank

**Solution:**

The data provided, or available in the Appendices, is:

$$c_p = 1004 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad R = 287 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad c_v = c_p - R \quad c_v = 717 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad k = \frac{c_p}{c_v} \quad k = 1.4$$

$$V = 1 \cdot \text{m}^3 \quad p_1 = 0.1 \cdot \text{MPa} \quad T_1 = (20 + 273) \cdot \text{K} \quad p_2 = 2 \cdot \text{MPa}$$

$$\text{Adiabatic, reversible process is isentropic: } T_{2s} = T_1 \cdot \left( \frac{p_2}{p_1} \right)^{\frac{k-1}{k}} \quad T_{2s} = 689.9 \text{ K}$$

For the isothermal process, we look at the first law:  $\Delta u = q - w = c_v \cdot \Delta T$  but  $\Delta T = 0$  so:  $\Delta u = 0$  and  $q = w$

$$\text{The work is equal to: } w = \int p \, dv = \int \frac{R \cdot T_1}{v} \, dv = R \cdot T_1 \cdot \int_{v_1}^{v_2} \frac{1}{v} \, dv = R \cdot T_1 \cdot \ln \left( \frac{v_2}{v_1} \right)$$

$$\text{From Boyle's law: } p_1 \cdot v_1 = p_2 \cdot v_2 \quad \frac{v_2}{v_1} = \frac{p_1}{p_2} \quad \text{substituting this into the above equation: } w = R \cdot T_1 \cdot \ln \left( \frac{p_1}{p_2} \right)$$

$$w = -252 \cdot \frac{\text{kJ}}{\text{kg}} \quad \text{Therefore the heat transfer is } q = w = -252 \cdot \frac{\text{kJ}}{\text{kg}} \quad (\text{The negative sign indicates heat loss})$$

$$\text{The mass of the air can be calculated from the ideal gas equation of state: } p \cdot V = M \cdot R \cdot T \quad M = \frac{p_2 \cdot V}{R \cdot T_1} = 23.8 \text{ kg}$$

$$\text{So the actual heat loss is equal to: } Q = M \cdot q \quad Q = -5.99 \times 10^3 \cdot \text{kJ}$$

$$\text{The mass in the tank after compression isothermally is: } M_t = 23.8 \text{ kg}$$

$$\text{For the isentropic compression: } M = \frac{p_2 \cdot V}{R \cdot T_{2s}} = 10.1 \text{ kg}$$

Therefore the isothermal compression results in more mass in the tank.

# Problem 12.15

[Difficulty: 3]

**12.15** A tank of volume  $V = 10 \text{ m}^3$  contains compressed air at  $15^\circ\text{C}$ . The gage pressure in the tank is  $4.50 \text{ MPa}$ . Evaluate the work required to fill the tank by compressing air from standard atmosphere conditions for (a) isothermal compression and (b) isentropic compression followed by cooling at constant pressure. What is the peak temperature of the isentropic compression process? Calculate the energy removed during cooling for process (b). Assume ideal gas behavior and reversible processes. Label state points on a  $Ts$  diagram and a  $pV$  diagram for each process.

Solution: Apply ideal gas, energy, isentropic process equations.

Computing equations:  $Q - W = \Delta E = m(u_2 - u_1)$ ,  $W = -\int p dV$

$p/p^k = \text{constant}$ ,  $p = pRT$

The tank contains  $m = \rho V$

$$\rho = \frac{p}{RT} = \frac{(4.5 + 0.101) \times 10^6 \text{ N/m}^2 \times \text{kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m} \cdot (273 + 15) \text{ K}} = 55.7 \frac{\text{kg}}{\text{m}^3}$$

$$m = \rho V = 55.7 \frac{\text{kg}}{\text{m}^3} \times 10 \text{ m}^3 = 557 \text{ kg}$$

For process  $1 \rightarrow 2$ ,

$$-W = -\int p dV = -m \int p dV = -m \int RT \frac{dp}{p} = -mRT \ln(p_2/p_1)$$

$$W_{12} = -557 \text{ kg} \times 287 \frac{\text{J}}{\text{kg} \cdot \text{K}} \times (273 + 15) \text{ K} \times \ln\left(\frac{4.5 + 0.101}{0.101}\right) = 176 \text{ MJ}$$

For process  $2 \rightarrow 2s$ ,  $\frac{p_{2s}}{p_1} = \left(\frac{p_{2s}}{p_1}\right)^k \rightarrow \frac{T_{2s}}{T_1} = \left(\frac{p_{2s}}{p_1}\right)^{\frac{k-1}{k}} = \left(\frac{4.601}{0.101}\right)^{0.286} = 2.98$

$$T_{2s} = 2.98 T_1 = 2.98 (273 + 15) \text{ K} = 858 \text{ K}$$



$$W_{12s} = m(u_{2s} - u_1) - Q_{12s} = m c_v (T_{2s} - T_1)$$

$$W_{12s} = 557 \text{ kg} \times 0.717 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} (858 - 288) \text{ K} = 228 \text{ MJ}$$

Process  $2s \rightarrow 2$  is at constant pressure

$$Q_{2s2} = m(u_2 - u_{2s}) - W_{2s2} = m(u_2 - u_{2s}) - m p (v_2 - v_{2s}) = m(h_2 - h_{2s}) = m c_p (T_2 - T_{2s})$$

$$Q_{2s2} = 557 \text{ kg} \times 1.00 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} \times (288 - 858) \text{ K} = -317 \text{ MJ (out of air)}$$



42,381 50 SHEETS 5 SQUARE  
42,382 100 SHEETS 5 SQUARE  
42,389 200 SHEETS 5 SQUARE  
NATIONAL

# Problem 12.16

[Difficulty: 2]

12.16 Air enters a turbine in steady flow at 0.5 kg/s with negligible velocity. Inlet conditions are 1300°C and 2.0 MPa (abs). The air is expanded through the turbine to atmospheric pressure. If the actual temperature and velocity at the turbine exit are 500°C and 200 m/s, determine the power produced by the turbine. Label state points on a  $Ts$  diagram for this process.

Solution:

For an isentropic expansion through the turbine,

$$T_{2s=c} = T_1 \left( \frac{P_2}{P_1} \right)^{\frac{\gamma-1}{\gamma}}$$

$$T_{2s=c} = (1300 + 273) \text{K} \left( \frac{0.101 \text{ MPa}}{2.0 \text{ MPa}} \right)^{\frac{1.4-1}{1.4}}$$

$$T_{2s=c} = 670 \text{ K} \quad (397^\circ\text{C})$$

Writing the first law of thermodynamics between the turbine inlet and outlet:

$$\dot{w} + \dot{q} = \dot{m} \left[ \left( h_2 + \frac{V_2^2}{2} \right) - \left( h_1 + \frac{V_1^2}{2} \right) \right]$$

(Assume  $\dot{q} = 0$ )


For an ideal gas with constant specific heats,  $h_2 - h_1 = c_p(T_2 - T_1)$

$$\therefore \dot{w} = \dot{m} \left[ c_p(T_2 - T_1) - \frac{V_2^2}{2} \right]$$

$$= 0.5 \frac{\text{kg}}{\text{s}} \left[ 1004 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} (773 - 1573) \text{K} - \frac{1}{2} (200)^2 \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} \right]$$

$$\dot{w} = -392 \times 10^3 \frac{\text{N}\cdot\text{m}}{\text{s}} \quad (\text{negative sign indicates work out}).$$

$$\therefore \dot{w}_{\text{out}} = 392 \text{ kW}$$



## Problem 12.17

[Difficulty: 3]

**12.17** Natural gas, with the thermodynamic properties of methane, flows in an underground pipeline of 0.6 m diameter. The gage pressure at the inlet to a compressor station is 0.5 MPa; outlet pressure is 8.0 MPa (gage). The gas temperature and speed at inlet are 13°C and 32 m/s, respectively. The compressor efficiency is  $\eta = 0.85$ . Calculate the mass flow rate of natural gas through the pipeline. Label state points on a  $Ts$  diagram for compressor inlet and outlet. Evaluate the gas temperature and speed at the compressor outlet and the power required to drive the compressor.

Solution:

The mass flow rate is given by  $\dot{m} = \rho VA$  where  $\rho = \frac{p}{RT}$

$$\dot{m} = \frac{p_1}{RT_1} V_1 \pi \frac{D^2}{4} = \frac{(500+101) \times 10^3 \text{ N}}{8.314 \text{ J/mol}\cdot\text{K} \times 286 \text{ K}} \times \frac{1}{4} \times 32 \frac{\text{m}}{\text{s}} \times \pi (0.6 \text{ m})^2$$

$$\dot{m} = 36.7 \text{ kg/s}$$


For an isentropic compression

$$T_{2s} = T_1 \left( \frac{p_2}{p_1} \right)^{\frac{\gamma-1}{\gamma}} = 286 \text{ K} \left( \frac{8.101 \text{ MPa}}{0.601 \text{ MPa}} \right)^{\frac{1.31-1}{1.31}} = 529 \text{ K}$$

$$\eta_c = \frac{T_{2s} - T_1}{T_2 - T_1} \quad \therefore T_2 - T_1 = \frac{T_{2s} - T_1}{\eta_c}$$

$$T_2 = T_1 + \frac{T_{2s} - T_1}{\eta_c} = 286 \text{ K} + \frac{(529 - 286) \text{ K}}{0.85}$$

$$T_2 = 572 \text{ K}$$



From continuity,  $\dot{m} = \rho_1 V_1 A_1 = \rho_2 V_2 A_2$ . Assuming  $A_1 = A_2$ , then

$$V_2 = \frac{\rho_1}{\rho_2} V_1 = \frac{p_1}{p_2} \frac{T_2}{T_1} V_1 = \frac{0.601}{8.101} \times \frac{572}{286} \times 32 \frac{\text{m}}{\text{s}} = 4.75 \text{ m/s}$$

Writing the first law of thermodynamics between compressor inlet-outlet

$$\dot{W} + \dot{Q} = \dot{m} \left[ \left( h_2 + \frac{V_2^2}{2} \right) - \left( h_1 + \frac{V_1^2}{2} \right) \right] \quad (\text{Assume } \dot{Q} = 0)$$

$$\dot{W} = \dot{m} \left[ (h_2 - h_1) + \frac{1}{2} (V_2^2 - V_1^2) \right] = \dot{m} \left[ c_p (T_2 - T_1) + \frac{1}{2} (V_2^2 - V_1^2) \right]$$

$$\dot{W} = 36.7 \frac{\text{kg}}{\text{s}} \left[ 2190 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} (572 - 286) \text{ K} + \frac{1}{2} \left\{ (4.75)^2 - (32)^2 \right\} \frac{\text{m}^2}{\text{s}^2} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} \right]$$

$$\dot{W} = 36.7 \left[ 626 \times 10^3 - 501 \right] \frac{\text{N}\cdot\text{m}}{\text{s}}$$

$$\dot{W} = 23 \text{ MW}$$

## Problem 12.18

[Difficulty: 3]

**12.18** Over time the efficiency of the compressor of Problem 12.17 drops. At what efficiency will the power required to attain 8.0 MPa (gage) exceed 30 MW? Plot the required power and the gas exit temperature as functions of efficiency.

**Given:** Data on flow through compressor

**Find:** Efficiency at which power required is 30 MW; plot required efficiency and exit temperature as functions of efficiency

**Solution:**

The data provided, or available in the Appendices, is:

$$R = 518.3 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad c_p = 2190 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad c_v = c_p - R \quad c_v = 1672 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad k = \frac{c_p}{c_v} \quad k = 1.31$$

$$T_1 = (13 + 273) \cdot \text{K} \quad p_1 = 0.5 \cdot \text{MPa} + 101 \cdot \text{kPa} \quad V_1 = 32 \cdot \frac{\text{m}}{\text{s}}$$

$$p_2 = 8 \cdot \text{MPa} + 101 \cdot \text{kPa} \quad W_{\text{comp}} = 30 \cdot \text{MW} \quad D = 0.6 \cdot \text{m}$$

The governing equation is the first law of thermodynamics for the compressor

$$M_{\text{flow}} \cdot \left[ \left( h_2 + \frac{V_2^2}{2} \right) - \left( h_1 + \frac{V_1^2}{2} \right) \right] = W_{\text{comp}} \quad \text{or} \quad W_{\text{comp}} = M_{\text{flow}} \cdot \left[ c_p \cdot (T_2 - T_1) + \frac{V_2^2 - V_1^2}{2} \right]$$

We need to find the mass flow rate and the temperature and velocity at the exit

$$M_{\text{flow}} = \rho_1 \cdot A_1 \cdot V_1 = \frac{p_1}{R \cdot T_1} \cdot \frac{\pi}{4} \cdot D^2 \cdot V_1 \quad M_{\text{flow}} = \frac{p_1}{R \cdot T_1} \cdot \frac{\pi}{4} \cdot D^2 \cdot V_1 \quad M_{\text{flow}} = 36.7 \frac{\text{kg}}{\text{s}}$$

The exit velocity is then given by

$$M_{\text{flow}} = \frac{p_2}{R \cdot T_2} \cdot \frac{\pi}{4} \cdot D^2 \cdot V_2 \quad V_2 = \frac{4 \cdot M_{\text{flow}} \cdot R \cdot T_2}{\pi \cdot p_2 \cdot D^2} \quad (1)$$

The exit velocity cannot be computed until the exit temperature is determined!

Using Eq. 1 in the first law

$$W_{\text{comp}} = M_{\text{flow}} \cdot \left[ c_p \cdot (T_2 - T_1) + \frac{\left( \frac{4 \cdot M_{\text{flow}} \cdot R \cdot T_2}{\pi \cdot p_2 \cdot D^2} \right)^2 - V_1^2}{2} \right]$$

In this complicated expression the only unknown is  $T_2$ , the exit temperature. The equation is a quadratic, so is solvable explicitly for  $T_2$ , but instead we use *Excel's Goal Seek* to find the solution (the second solution is mathematically correct but physically unrealistic - a very large negative absolute temperature). The exit temperature is

$$T_2 = 660 \cdot \text{K}$$

If the compressor was ideal (isentropic), the exit temperature would be given by

$$T \cdot p^{\frac{1-k}{k}} = \text{constant} \quad (12.12b)$$



Hence  $T_{2s} = T_1 \cdot \left(\frac{p_1}{p_2}\right)^{\frac{1-k}{k}}$   $T_{2s} = 529 \text{ K}$

For a compressor efficiency  $\eta$ , we have  $\eta = \frac{h_{2s} - h_1}{h_2 - h_1}$  or  $\eta = \frac{T_{2s} - T_1}{T_2 - T_1}$   $\eta = 65.1\%$

To plot the exit temperature and power as a function of efficiency we use  $T_2 = T_1 + \frac{T_{2s} - T_1}{\eta}$

with  $V_2 = \frac{4 \cdot M_{\text{flow}} \cdot R \cdot T_2}{\pi \cdot p_2 \cdot D^2}$  and  $W_{\text{comp}} = M_{\text{flow}} \cdot \left[ c_p \cdot (T_2 - T_1) + \frac{V_2^2 - V_1^2}{2} \right]$

The dependencies of  $T_2$  and  $W_{\text{comp}}$  on efficiency are plotted in *Excel* and shown here:



## Problem 12.19

[Difficulty: 3]

**12.19** Improper maintenance on the turbine of Problem 12.7 has resulted in a gradual decrease in its efficiency over time. Assuming that the efficiency drops by 1 percent per year, how long would it take for the power output of the turbine to drop to 950 kW, assuming that entrance conditions, flow rate, and exhaust pressure were all kept constant?

**Given:** Data on performance degradation of turbine

**Find:** Time necessary for power output to drop to 950 kW

**Solution:**

The data provided, or available in the Appendices, is:

$$p_1 = 10 \cdot \text{bar} = 1 \times 10^3 \cdot \text{kPa} \quad T_1 = 1400 \cdot \text{K} \quad \eta_{\text{initial}} = 80\% \quad P_{\text{initial}} = 1 \cdot \text{MW}$$

$$p_2 = 1 \cdot \text{bar} = 100 \cdot \text{kPa} \quad P_{\text{final}} = 950 \cdot \text{kW}$$

$$c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad R_{\text{gas}} = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad k = 1.4$$

If the turbine expansion were isentropic, the actual output would be:  $P_{\text{ideal}} = \frac{P_{\text{initial}}}{\eta_{\text{initial}}} = 1.25 \text{ MW}$

So when the power output drops to 950 kW, the new efficiency is:  $\eta_{\text{final}} = \frac{P_{\text{final}}}{P_{\text{ideal}}} = 76\%$

Since the efficiency drops by 1% per year, the time elapsed is:  $\Delta t = 4 \text{ yr}$

## Problem 12.20

[Difficulty: 4]

**12.20** In an isothermal process, 0.1 cubic feet of standard air per minute (SCFM) is pumped into a balloon. Tension in the rubber skin of the balloon is given by  $\sigma = kA$ , where  $k = 200 \text{ lbf/ft}^2$ , and  $A$  is the surface area of the balloon in  $\text{ft}^2$ . Compute the time required to increase the balloon radius from 5 to 7 in.


Solution: The mass flow rate is  $\dot{m} = \rho_{\text{std}} Q = \text{constant}$ , so

Computing equation:  $\Delta t = \frac{\Delta m}{\dot{m}} \quad p = \rho RT$

Assume: (1) Standard air,  $\rho = 0.0765 \text{ lbm/ft}^3$ ; (2) Ideal gas

Then  $\dot{m} = \rho Q = 0.0765 \frac{\text{lbm}}{\text{ft}^3} \times 0.10 \frac{\text{ft}^3}{\text{min}} \times \frac{\text{min}}{60 \text{ s}} = 1.28 \times 10^{-4} \text{ lbm/s}$

From a force balance on the balloon:



$$(p - p_{\text{atm}}) \pi r^2 = \sigma 2\pi r = k(4\pi r^2) 2\pi r = 8\pi^2 k r^3$$

or  $p = p_{\text{atm}} + 8\pi k r$

For  $r = 5 \text{ in.}$ ,  $p = 14.7 + 8\pi \times 200 \frac{\text{lbf}}{\text{ft}^2} \times 5 \text{ in.} \times \frac{\text{ft}^3}{1728 \text{ in.}^3} = 29.2 \text{ psia}$

$$\rho = \frac{p}{RT} = \frac{29.2 \frac{\text{lbf}}{\text{in.}^2} \times \frac{\text{lbm} \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lbf}} \times \frac{1}{519^\circ \text{R}} \times 144 \frac{\text{in.}^2}{\text{ft}^2}}{1} = 0.152 \text{ lbm/ft}^3$$

$$V = \frac{4}{3} \pi r^3 = \frac{4\pi}{3} \times (5)^3 \text{ in.}^3 \times \frac{\text{ft}^3}{1728 \text{ in.}^3} = 0.303 \text{ ft}^3$$

$$m = \rho V = 0.152 \frac{\text{lbm}}{\text{ft}^3} \times 0.303 \text{ ft}^3 = 0.0461 \text{ lbm}$$

For  $r = 7 \text{ in.}$ ,  $p = 14.7 \frac{\text{lbf}}{\text{in.}^2} + 8\pi \times 200 \frac{\text{lbf}}{\text{ft}^2} \times 7 \text{ in.} \times \frac{\text{ft}^3}{1728 \text{ in.}^3} = 35.1 \text{ psia}$

Tabulating,

$r$ (in.)	$p$ (psia)	$\rho$ (lbm/ft <sup>3</sup> )	$V$ (ft <sup>3</sup> )	$m$ (lbm)
5	29.2	0.152	0.303	0.0461
7	35.1	0.183	0.831	0.152

Then  $\Delta m = m_7 - m_5 = 0.152 - 0.0461 \text{ lbm} = 0.106 \text{ lbm}$

and

$$\Delta t = 0.106 \text{ lbm} \times \frac{\text{s}}{1.28 \times 10^{-4} \text{ lbm}} = 828 \text{ s} \quad (\approx 14 \text{ min})$$

$\Delta t$

## Problem 12.21

[Difficulty: 3]

**12.21** For the balloon process of Problem 12.20 we could define a "volumetric ratio" as the ratio of the volume of standard air supplied to the volume increase of the balloon, per unit time. Plot this ratio over time as the balloon radius is increased from 5 to 7 in.

**Given:** Data on flow rate and balloon properties

**Find:** "Volumetric ratio" over time

**Solution:**

The given or available data are:  $R_{\text{air}} = 53.3 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$      $T_{\text{atm}} = 519 \cdot \text{R}$      $p_{\text{atm}} = 14.7 \cdot \text{psi}$      $k = 200 \cdot \frac{\text{lbf}}{\text{ft}^3}$      $V_{\text{rate}} = 0.1 \cdot \frac{\text{ft}^3}{\text{min}}$

Basic equation:

Standard air density  $\rho_{\text{air}} = \frac{p_{\text{atm}}}{R_{\text{air}} \cdot T_{\text{atm}}} = 0.0765 \frac{\text{lbm}}{\text{ft}^3}$

Mass flow rate  $M_{\text{rate}} = V_{\text{rate}} \cdot \rho_{\text{air}} = 1.275 \times 10^{-4} \frac{\text{lbm}}{\text{s}}$

From a force balance on each hemisphere  $(p - p_{\text{atm}}) \cdot \pi \cdot r^2 = \sigma \cdot 2 \cdot \pi \cdot r$     where     $\sigma = k \cdot A = k \cdot 4 \cdot \pi \cdot r^2$

Hence  $p = p_{\text{atm}} + \frac{2 \cdot \sigma}{r}$     or     $p = p_{\text{atm}} + 8 \cdot \pi \cdot k \cdot r$

Density in balloon  $\rho = \frac{p}{R_{\text{air}} \cdot T_{\text{air}}}$

The instantaneous volume is  $V_{\text{ball}} = \frac{4}{3} \cdot \pi \cdot r^3$


The instantaneous mass is  $M_{\text{ball}} = V_{\text{ball}} \cdot \rho$

The time to fill to radius  $r$  from  $r = 5$  in is  $t = \frac{M_{\text{ball}}(r) - M_{\text{ball}}(r = 5 \text{ in})}{M_{\text{rate}}}$

The volume change between time steps  $\Delta t$  is  $\Delta V = V_{\text{ball}}(t + \Delta t) - V_{\text{ball}}(t)$

The results, calculated using *Excel*, are shown on the next page:

$r$ (in)	$p$ (psi)	$\rho$ (lb/ft <sup>3</sup> )	$V_{\text{ball}}$ (ft <sup>3</sup> )	$M_{\text{ball}}$ (lb)	$t$ (s)	$\Delta V/V_{\text{rate}}$
5.00	29.2	0.152	0.303	0.0461	0.00	0.00
5.25	30.0	0.156	0.351	0.0547	67.4	42.5%
5.50	30.7	0.160	0.403	0.0645	144	41.3%
5.75	31.4	0.164	0.461	0.0754	229	40.2%
6.00	32.2	0.167	0.524	0.0876	325	39.2%
6.25	32.9	0.171	0.592	0.101	433	38.2%
6.50	33.6	0.175	0.666	0.116	551	37.3%
6.75	34.3	0.179	0.746	0.133	683	36.4%
7.00	35.1	0.183	0.831	0.152	828	35.5%



## Problem 12.22

[Difficulty: 3]

**12.22** A sound pulse level above about 20 Pa can cause permanent hearing damage. Assuming such a sound wave travels through air at 20°C and 100 kPa, estimate the density, temperature, and velocity change immediately after the sound wave passes.

**Given:** Sound wave

**Find:** Estimate of change in density, temperature, and velocity after sound wave passes

**Solution:**

Basic equation:  $p = \rho \cdot R \cdot T$                        $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$

$du = c_v \cdot dT$                                        $dh = c_p \cdot dT$

Assumptions: 1) Ideal gas 2) Constant specific heats 3) Isentropic process 4) infinitesimal changes

Given or available data

$$T_1 = (20 + 273) \cdot K \quad p_1 = 100 \cdot \text{kPa} \quad dp = 20 \cdot \text{Pa} \quad k = 1.4 \quad R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$$

$$c = \sqrt{k \cdot R \cdot T_1} \quad c = 343 \frac{\text{m}}{\text{s}}$$

For small changes, from Section 11-2       $dp = c^2 \cdot d\rho$       so       $d\rho = \frac{dp}{c^2}$        $d\rho = 1.70 \times 10^{-4} \cdot \frac{\text{kg}}{\text{m}^3}$  a very small change!

The air density is  $\rho_1 = \frac{p_1}{R \cdot T_1}$                        $\rho_1 = 1.19 \frac{\text{kg}}{\text{m}^3}$

Then  $dV_x = \frac{1}{\rho_1 \cdot c} \cdot dp$                        $dV_x = 0.049 \frac{\text{m}}{\text{s}}$                       This is the velocity of the air after the sound wave!

For the change in temperature we start with the ideal gas equation  $p = \rho \cdot R \cdot T$  and differentiate  $dp = d\rho \cdot R \cdot T + \rho \cdot R \cdot dT$

Dividing by the ideal gas equation we find  $\frac{dp}{p} = \frac{d\rho}{\rho} + \frac{dT}{T}$

Hence  $dT = T_1 \cdot \left( \frac{dp}{p_1} - \frac{d\rho}{\rho_1} \right)$        $dT = 0.017 \text{ K}$        $dT = 0.030 \cdot \Delta^\circ\text{F}$       a very small change!

## Problem 12.23

[Difficulty: 3]

**12.23** Calculate the speed of sound at 20°C for (a) hydrogen, (b) helium, (c) methane, (d) nitrogen, and (e) carbon dioxide.

**Given:** Five different gases at specified temperature

**Find:** Sound speeds for each gas at that temperature

**Solution:** Basic equation:  $c = \sqrt{k \cdot R \cdot T}$

The data provided, or available in the Appendices, is:  $T = (20 + 273) \cdot K$

$$k_{H_2} = 1.41 \quad R_{H_2} = 4124 \cdot \frac{J}{kg \cdot K} \quad k_{He} = 1.66 \quad R_{He} = 2077 \cdot \frac{J}{kg \cdot K}$$

$$k_{CH_4} = 1.31 \quad R_{CH_4} = 518.3 \cdot \frac{J}{kg \cdot K} \quad k_{N_2} = 1.40 \quad R_{N_2} = 296.8 \cdot \frac{J}{kg \cdot K}$$

$$k_{CO_2} = 1.29 \quad R_{CO_2} = 188.9 \cdot \frac{J}{kg \cdot K}$$

$$c_{H_2} = \sqrt{k_{H_2} \cdot R_{H_2} \cdot T} \quad c_{H_2} = 1305 \frac{m}{s}$$

$$c_{He} = \sqrt{k_{He} \cdot R_{He} \cdot T} \quad c_{He} = 1005 \frac{m}{s}$$

$$c_{CH_4} = \sqrt{k_{CH_4} \cdot R_{CH_4} \cdot T} \quad c_{CH_4} = 446 \frac{m}{s}$$

$$c_{N_2} = \sqrt{k_{N_2} \cdot R_{N_2} \cdot T} \quad c_{N_2} = 349 \frac{m}{s}$$

$$c_{CO_2} = \sqrt{k_{CO_2} \cdot R_{CO_2} \cdot T} \quad c_{CO_2} = 267 \frac{m}{s}$$

## Problem 12.24

[Difficulty: 3]

**12.24** The bulk modulus  $E_v$  of a material indicates how hard it is to compress the material; a large  $E_v$  indicates the material requires a large pressure to compress. Is air "stiffer" when suddenly or slowly compressed? To answer this, find expressions in terms of instantaneous pressure  $p$  for the bulk modulus of air (kPa) when it is (a) rapidly compressed and (b) slowly compressed. *Hint:* Rapid compression is approximately isentropic (it is adiabatic because it is too quick for heat transfer to occur), and slow compression is isothermal (there is plenty of time for the air to equilibrate to ambient temperature).

**Given:** Sound wave

**Find:** Estimate of change in density, temperature, and velocity after sound wave passes

**Solution:**

Basic equations:  $p = \rho \cdot R \cdot T$   $E_v = \frac{dp}{\frac{d\rho}{\rho}}$

Assumptions: 1) Ideal gas 2) Constant specific heats 3) Infinitesimal changes

To find the bulk modulus we need  $\frac{dp}{d\rho}$  in  $E_v = \frac{dp}{\frac{d\rho}{\rho}} = \rho \cdot \frac{dp}{d\rho}$

For rapid compression (isentropic)  $\frac{p}{\rho^k} = \text{const}$  and so  $\frac{dp}{d\rho} = k \cdot \frac{p}{\rho}$

Hence  $E_v = \rho \cdot \left( k \cdot \frac{p}{\rho} \right)$   $E_v = k \cdot p$

For gradual compression (isothermal) we can use the ideal gas equation  $p = \rho \cdot R \cdot T$  so  $dp = d\rho \cdot R \cdot T$

Hence  $E_v = \rho \cdot (R \cdot T) = p$   $E_v = p$

We conclude that the "stiffness" ( $E_v$ ) of air is equal to  $kp$  when rapidly compressed and  $p$  when gradually compressed. To give an idea of values:

For water  $E_v = 2.24 \cdot \text{GPa}$

For air ( $k = 1.4$ ) at  $p = 101 \cdot \text{kPa}$     Rapid compression     $E_v = k \cdot p$      $E_v = 141 \cdot \text{kPa}$

   Gradual compression     $E_v = p$      $E_v = 101 \cdot \text{kPa}$

## Problem 12.25

[Difficulty: 2]

**12.25** You have designed a device for determining the bulk modulus,  $E_v$ , of a material. It works by measuring the time delay between sending a sound wave into a sample of the material and receiving the wave after it travels through the sample and bounces back. As a test, you use a 1-m rod of steel ( $E_v \approx 200 \text{ GN/m}^2$ ). What time delay should your device indicate? You now test a 1-m rod (1 cm diameter) of an unknown material and find a time delay of 0.5 ms. The mass of the rod is measured to be 0.25 kg. What is this material's bulk modulus?

**Given:** Device for determining bulk modulus

**Find:** Time delay; Bulk modulus of new material

**Solution:**

Basic equation: 
$$c = \sqrt{\frac{E_v}{\rho}}$$

Hence for given data  $E_v = 200 \cdot \frac{\text{GN}}{\text{m}^2}$        $L = 1 \cdot \text{m}$       and for steel       $SG = 7.83$        $\rho_w = 1000 \cdot \frac{\text{kg}}{\text{m}^3}$

For the steel 
$$c = \sqrt{\frac{E_v}{SG \cdot \rho_w}} \quad c = 5054 \frac{\text{m}}{\text{s}}$$

Hence the time to travel distance L is 
$$\Delta t = \frac{L}{c} \quad \Delta t = 1.98 \times 10^{-4} \cdot \text{s} \quad \Delta t = 0.198 \cdot \text{ms} \quad \Delta t = 198 \cdot \mu\text{s}$$

For the unknown material  $M = 0.25 \cdot \text{kg}$        $D = 1 \cdot \text{cm}$        $\Delta t = 0.5 \cdot \text{ms}$

The density is then 
$$\rho = \frac{M}{L \cdot \frac{\pi \cdot D^2}{4}} \quad \rho = 3183 \frac{\text{kg}}{\text{m}^3}$$

The speed of sound in it is 
$$c = \frac{L}{\Delta t} \quad c = 2000 \frac{\text{m}}{\text{s}}$$

Hence th bulk modulus is 
$$E_v = \rho \cdot c^2 \quad E_v = 12.7 \cdot \frac{\text{GN}}{\text{m}^2}$$

## Problem 12.26

[Difficulty: 2]

**12.26** Dolphins often hunt by listening for sounds made by their prey. They “hear” with the lower jaw, which conducts the sound vibrations to the middle ear via a fat-filled cavity in the lower jaw bone. If the prey is half a mile away, how long after a sound is made does a dolphin hear it? Assume the seawater is at 68°F.

**Given:** Hunting dolphin

**Find:** Time delay before it hears prey at 1/2 mile

**Solution:**

Basic equation: 
$$c = \sqrt{\frac{E_v}{\rho}}$$

Given (and Table A.2) data  $L = 0.5 \cdot \text{mi} = 2.64 \times 10^3 \cdot \text{ft}$   $SG = 1.025$   $E_v = 3.20 \times 10^5 \cdot \text{psi}$   $\rho_w = 1.94 \cdot \frac{\text{slug}}{\text{ft}^3}$

For the seawater 
$$c = \sqrt{\frac{E_v}{SG \cdot \rho_w}} \quad c = 4814 \cdot \frac{\text{ft}}{\text{s}}$$

Hence the time for sound to travel distance  $L$  is  $\Delta t = \frac{L}{c} \quad \Delta t = 0.548 \cdot \text{s} \quad \Delta t = 548 \cdot \text{ms}$

## Problem 12.27

[Difficulty: 2]

**12.27** A submarine sends a sonar signal to detect the enemy. The reflected wave returns after 3.25 s. Estimate the separation between the submarines. (As an approximation, assume the seawater is at 20°C.)

**Given:** Submarine sonar

**Find:** Separation between submarines

**Solution:**

Basic equation: 
$$c = \sqrt{\frac{E_v}{\rho}}$$

Given (and Table A.2) data  $\Delta t = 3.25 \cdot s$   $SG = 1.025$   $E_v = 2.42 \cdot \frac{GN}{m^2}$   $\rho_w = 1000 \cdot \frac{kg}{m^3}$

For the seawater 
$$c = \sqrt{\frac{E_v}{SG \cdot \rho_w}}$$
  $c = 1537 \frac{m}{s}$

Hence the distance sound travels in time  $\Delta t$  is  $L = c \cdot \Delta t$   $L = 5 \cdot km$

The distance between submarines is half of this  $x = \frac{L}{2}$   $x = 2.5 \cdot km$

## Problem 12.28

[Difficulty: 1]

**12.28** An airplane flies at 550 km/hr at 1500 m altitude on a standard day. The plane climbs to 15,000 m and flies at 1200 km/h. Calculate the Mach number of flight in both cases.

**Given:** Airplane cruising at two different elevations

**Find:** Mach numbers

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$

Available data     $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$      $k = 1.4$

At                     $z = 1500 \cdot \text{m}$      $T = 278.4 \cdot \text{K}$       from Table A.3

Hence               $c = \sqrt{k \cdot R \cdot T}$        $c = 334 \frac{\text{m}}{\text{s}}$                $c = 1204 \cdot \frac{\text{km}}{\text{hr}}$       and we have     $V = 550 \cdot \frac{\text{km}}{\text{hr}}$

The Mach number is               $M = \frac{V}{c}$                $M = 0.457$

Repeating at       $z = 15000 \cdot \text{m}$                                $T = 216.7 \cdot \text{K}$

Hence               $c = \sqrt{k \cdot R \cdot T}$        $c = 295 \frac{\text{m}}{\text{s}}$                $c = 1062 \cdot \frac{\text{km}}{\text{hr}}$       and we have     $V = 1200 \cdot \frac{\text{km}}{\text{hr}}$

The Mach number is               $M = \frac{V}{c}$                $M = 1.13$

## Problem 12.29

[Difficulty: 2]

**12.29** Next-generation missiles will use scramjet engines to travel at Mach numbers as high as 7. If a scramjet-powered missile travels at Mach 7 at an altitude of 85,000 ft, how long will it take for the missile to travel 600 nautical miles? Assume standard atmospheric conditions. (*Note:* This is the range for the Tomahawk missile, which uses a conventional propulsion system, but it takes 90 min to cover that same distance.)

**Given:** Scramjet-powered missile traveling at fixed Mach number and altitude

**Find:** Time necessary to cover specified range

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$

Available data     $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$      $k = 1.4$      $M = 7$      $\Delta x = 600 \cdot \text{nmi} = 3.65 \times 10^6 \cdot \text{ft}$

At                     $z = 85000 \cdot \text{ft}$      $z = 25908 \text{ m}$     interpolating from Table A.3     $T = 220.6 \cdot \text{K} + (222.5 \cdot \text{K} - 220.6 \cdot \text{K}) \cdot \frac{25908 - 24000}{26000 - 24000}$   
 $T = 222 \text{ K}$

Hence               $c = \sqrt{k \cdot R \cdot T}$        $c = 299 \frac{\text{m}}{\text{s}}$        $c = 981 \cdot \frac{\text{ft}}{\text{s}}$     and we have       $V = M \cdot c = 6864 \cdot \frac{\text{ft}}{\text{s}}$

The time needed to cover the range is:     $\Delta t = \frac{\Delta x}{V} = 531 \text{ s}$      $\Delta t = 8.85 \cdot \text{min}$     This is about ten times as fast as the Tomahawk!

## Problem 12.30

[Difficulty: 1]

**12.30** Actual performance characteristics of the Lockheed SR-71 "Blackbird" reconnaissance aircraft never were released. However, it was thought to cruise at  $M=3.3$  at 85,000 ft altitude. Evaluate the speed of sound and flight speed for these conditions. Compare to the muzzle speed of a 30-06 rifle bullet (700 m/s).

Solution:

$$\text{Alt altitude, } z = 85,000 \text{ ft} \times 0.3048 \frac{\text{m}}{\text{ft}} = 25.9 \text{ km}$$

$$\text{From Table A.3, } T = 222 \text{ K}$$

$$\therefore c = \sqrt{\gamma RT} = \left[ 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} + 222 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right]^{1/2} = 299 \text{ m/s} \quad \leftarrow c$$

$$V = Mc = 3.3 \times 299 \text{ m/s} = 987 \text{ m/s} \quad \leftarrow V$$

$$\frac{V}{V_{\text{bullet}}} = \frac{987}{700} = 1.41 \quad \leftarrow$$



## Problem 12.32

[Difficulty: 2]

**12.32** Investigate the effect of altitude on Mach number by plotting the Mach number of a 500 mph airplane as it flies at altitudes ranging from sea level to 10 km.

**Given:** Airplane cruising at 550 mph

**Find:** Mach number versus altitude


**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$       Here are the results, generated using *Excel*:

$$\begin{aligned} V &= 500 \text{ mph} \\ R &= 286.90 \text{ J/kg-K} && \text{(Table A.6)} \\ k &= 1.40 \end{aligned}$$

Data on temperature versus height obtained from Table A.3

$z$ (m)	$T$ (K)	$c$ (m/s)	$c$ (mph)	$M$
0	288.2	340	661	0.756
500	284.9	338	658	0.760
1000	281.7	336	654	0.765
1500	278.4	334	650	0.769
2000	275.2	332	646	0.774
2500	271.9	330	642	0.778
3000	268.7	329	639	0.783
3500	265.4	326	635	0.788
4000	262.2	325	631	0.793
4500	258.9	322	627	0.798
5000	255.7	320	623	0.803
6000	249.2	316	615	0.813
7000	242.7	312	607	0.824
8000	236.2	308	599	0.835
9000	229.7	304	590	0.847
10000	223.3	299	582	0.859



## Problem 12.33

[Difficulty: 2]

**12.33** You are watching a July 4th fireworks display from a distance of one mile. How long after you see an explosion do you hear it? You also watch New Year's fireworks (same place and distance). How long after you see an explosion do you hear it? Assume it's 75°F in July and 5°F in January.

**Given:** Fireworks displays!

**Find:** How long after seeing them do you hear them?

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$

Assumption: Speed of light is essentially infinite (compared to speed of sound)

The given or available data is  $T_{\text{July}} = (75 + 460) \cdot R$        $L = 1 \cdot \text{mi}$        $k = 1.4$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot R}$

Hence  $c_{\text{July}} = \sqrt{k \cdot R_{\text{air}} \cdot T_{\text{July}}}$        $c_{\text{July}} = 1134 \cdot \frac{\text{ft}}{\text{s}}$

Then the time is  $\Delta t_{\text{July}} = \frac{L}{c_{\text{July}}}$        $\Delta t_{\text{July}} = 4.66 \text{ s}$

In January  $T_{\text{Jan}} = (5 + 460) \cdot R$

Hence  $c_{\text{Jan}} = \sqrt{k \cdot R_{\text{air}} \cdot T_{\text{Jan}}}$        $c_{\text{Jan}} = 1057 \cdot \frac{\text{ft}}{\text{s}}$

Then the time is  $\Delta t_{\text{Jan}} = \frac{L}{c_{\text{Jan}}}$        $\Delta t_{\text{Jan}} = 5.00 \text{ s}$

## Problem 12.34

[Difficulty: 2]

**12.34** The X-15 North American rocket plane held the record for the fastest manned flight. In 1967, the X-15 flew at a speed of 7270 km/h at an altitude of 58.4 km. At what Mach number did the X-15 fly?

**Given:** X-15 rocket plane speed and altitude

**Find:** Mach number

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$

Available data     $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$      $k = 1.4$      $V = 7270 \cdot \frac{\text{km}}{\text{hr}}$

At                     $z = 58400 \cdot \text{m}$     interpolating from Table A.3     $T = 270.7 \cdot \text{K} + (255.8 \cdot \text{K} - 270.7 \cdot \text{K}) \cdot \frac{58400 - 50000}{60000 - 50000}$

$$T = 258 \text{ K}$$

Hence               $c = \sqrt{k \cdot R \cdot T}$        $c = 322 \frac{\text{m}}{\text{s}}$        $c = 1159 \cdot \frac{\text{km}}{\text{hr}}$  and we have       $M = \frac{V}{c} = 6.27$

## Problem 12.35

[Difficulty: 2]

**12.35** You need to estimate the speed of a hypersonic aircraft traveling at Mach 7 and 120,000 ft. Not having a table of atmospheric tables handy, you remember that through the stratosphere (approximately 36,000 ft to 72,000 ft) the temperature of air is nearly constant at 390°R, and you assume this temperature for your calculation. Later, you obtain the appropriate data and recalculate the speed. What was the percentage error? What would the percentage error have been if you used the air temperature at sea level?

**Given:** Mach number and altitude of hypersonic aircraft

**Find:** Speed assuming stratospheric temperature, actual speed, speed assuming sea level static temperature

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$

Available data  $R_{\text{air}} = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$      $k = 1.4$      $M = 7$

Assuming  $T = 390 \cdot \text{R} = 217 \text{ K}$

Hence  $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$      $c = 295 \frac{\text{m}}{\text{s}}$  and we have  $V_{\text{strat}} = M \cdot c = 2065 \frac{\text{m}}{\text{s}}$

At  $z = 120000 \cdot \text{ft}$      $z = 36576 \text{ m}$  interpolating from Table A.3     $T = 226.5 \cdot \text{K} + (250.4 \cdot \text{K} - 226.5 \cdot \text{K}) \cdot \frac{36576 - 30000}{40000 - 30000}$

$T = 242 \text{ K}$

Hence  $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$      $c = 312 \frac{\text{m}}{\text{s}}$  and we have  $V_{\text{actual}} = M \cdot c = 2183 \frac{\text{m}}{\text{s}}$

The error is:  $\frac{V_{\text{strat}} - V_{\text{actual}}}{V_{\text{actual}}} = -5.42\%$

Assuming  $T = 288.2 \cdot \text{K}$

Hence  $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$      $c = 340 \frac{\text{m}}{\text{s}}$  and we have  $V_{\text{sls}} = M \cdot c = 2382 \frac{\text{m}}{\text{s}}$

The error is:  $\frac{V_{\text{sls}} - V_{\text{actual}}}{V_{\text{actual}}} = 9.08\%$

## Problem 12.36

[Difficulty: 2]

**12.36** The grandstand at the Kennedy Space Center is located 3.5 mi away from the Space Shuttle Launch Pad. On a day when the air temperature is 80°F, how long does it take the sound from a blastoff to reach the spectators? If the launch was early on a winter morning, the temperature may be as low as 50°F. How long would the sound take to reach the spectators under those conditions?

**Given:** Shuttle launch

**Find:** How long after seeing it do you hear it?

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$

Assumption: Speed of light is essentially infinite (compared to speed of sound)

The given or available data is  $T = (80 + 460) \cdot R$        $L = 3.5 \cdot \text{mi}$        $k = 1.4$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot R}$

Hence  $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$        $c = 1139 \cdot \frac{\text{ft}}{\text{s}}$

Then the time is  $\Delta t = \frac{L}{c}$        $\Delta t = 16.23 \text{ s}$

In the winter:  $T = (50 + 460) \cdot R$

Hence  $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$        $c = 1107 \cdot \frac{\text{ft}}{\text{s}}$

Then the time is  $\Delta t = \frac{L}{c}$        $\Delta t = 16.7 \text{ s}$

## Problem 12.37

[Difficulty: 2]

**12.37** While working on a pier on a mountain lake, you notice that the sounds of your hammering are echoing from the mountains in the distance. If the temperature is  $25^{\circ}\text{C}$  and the echoes reach you 3 seconds after the hammer strike, how far away are the mountains?

**Given:** Echo heard while hammering near mountain lake, time delay of echo is known

**Find:** How far away are the mountains

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$

Assumption: Speed of light is essentially infinite (compared to speed of sound)

The given or available data is  $T = (25 + 273) \cdot \text{K}$   $k = 1.4$   $R_{\text{air}} = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$   $\Delta t = 3 \cdot \text{s}$

Hence  $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$   $c = 346 \frac{\text{m}}{\text{s}}$

The distance covered by the sound is:  $L = c \cdot \Delta t$   $L = 1038 \text{ m}$  but the distance to the mountains is half that distance:

$$\frac{L}{2} = 519 \text{ m}$$

## Problem 12.38

[Difficulty: 2]

**12.38** Use data for specific volume to calculate and plot the speed of sound in saturated liquid water over the temperature range from 0 to 200°C.

**Given:** Data on water specific volume

**Find:** Speed of sound over temperature range

**Solution:**

Basic equation:  $c = \sqrt{\frac{\partial}{\partial \rho} p}$  at isentropic conditions

As an approximation for a liquid  $c = \sqrt{\frac{\Delta p}{\Delta \rho}}$  using available data.

We use compressed liquid data at adjacent pressures of 5 MPa and 10 MPa, and estimate the change in density between these pressures from the corresponding specific volume changes


$$\Delta p = p_2 - p_1 \quad \Delta \rho = \frac{1}{v_2} - \frac{1}{v_1} \quad \text{and} \quad c = \sqrt{\frac{\Delta p}{\Delta \rho}} \quad \text{at each temperature}$$

Here are the results, calculated using *Excel*:

$$\begin{aligned} p_2 &= 10 \text{ MPa} \\ p_1 &= 5 \text{ MPa} \\ \eta p &= 5 \text{ MPa} \end{aligned}$$

Data on specific volume versus temperature can be obtained from any good thermodynamics text (try the Web!)

	$p_1$	$p_2$		
$T$ (°C)	$v$ (m <sup>3</sup> /kg)	$v$ (m <sup>3</sup> /kg)	$\Delta \rho$ (kg/m <sup>3</sup> )	$c$ (m/s)
0	0.0009977	0.0009952	2.52	1409
20	0.0009996	0.0009973	2.31	1472
40	0.0010057	0.0010035	2.18	1514
60	0.0010149	0.0010127	2.14	1528
80	0.0010267	0.0010244	2.19	1512
100	0.0010410	0.0010385	2.31	1470
120	0.0010576	0.0010549	2.42	1437
140	0.0010769	0.0010738	2.68	1366
160	0.0010988	0.0010954	2.82	1330
180	0.0011240	0.0011200	3.18	1254
200	0.0011531	0.0011482	3.70	1162




### Problem 12.39


[Difficulty: 3]

**12.39** Re-derive the equation for sonic speed (Eq. 12.18) assuming that the direction of fluid motion behind the sound wave is  $dV_x$  to the right. Show that the result is identical to that given by Eq. 12.18.

Solution:



(a) Propagating Wave.



(b) Inertial CV moving with wave

Apply continuity to CV (b)

$$0 = \{-\rho c A\} + \{(\rho + d\rho)(c + dV_x) A\}$$

$$0 = -\rho c A + \rho c A + \rho dV_x A + c A d\rho + d\rho dV_x A$$

Then

$$\rho dV_x + c d\rho = 0 \quad \text{or} \quad dV_x = -\frac{c}{\rho} d\rho \quad \dots (1)$$

Applying  $x$ -momentum equation to same CV gives

$$\sum F_x = -pA - (p + dp)A = \int_{CV} \rho \vec{V}_x \cdot \vec{n} dA = c \{-\rho p A\} + (c + dV_x) \{(\rho + d\rho) p A\}$$

(in = out)

$$\therefore -A dp = \rho A c dV_x, \quad \text{and}$$

$$dV_x = -\frac{dp}{\rho c} \quad \dots (2)$$

Combining equations (1) and (2) we obtain

$$-\frac{c}{\rho} d\rho = -\frac{dp}{\rho c}$$

or

$$c^2 = \frac{dp}{d\rho}$$

This is the same result as obtained in the derivation of Section 12-2 with the direction of the fluid motion behind the wave to the left.

## Problem 12.40

[Difficulty: 2]

**12.40** Compute the speed of sound at sea level in standard air. By scanning data from Table A.3 into your PC (or using Fig. 3.3), evaluate the speed of sound and plot for altitudes to 90 km.

Given: Data on atmospheric temperature variation with altitude

Find: Sound of speed at sea level; plot speed as function of altitude

### Solution

The given or available data is:

$$R = 286.9 \text{ J/kg}\cdot\text{K}$$
$$k = 1.4$$


Computing equation:

$$c = \sqrt{kRT}$$

Computed results:

(Only partial data is shown in table)

$z$ (m)	$T$ (K)	$c$ (m/s)
0	288.2	340
500	284.9	338
1000	281.7	336
1500	278.4	334
2000	275.2	332
2500	271.9	330
3000	268.7	329
3500	265.4	326
4000	262.2	325
4500	258.9	322
5000	255.7	320
6000	249.2	316
7000	242.7	312
8000	236.2	308
9000	229.7	304
10000	223.3	299



## Problem 12.41

[Difficulty: 3]

**12.41** The temperature varies linearly from sea level to approximately 11 km altitude in the standard atmosphere. Evaluate the *lapse rate*—the rate of decrease of temperature with altitude—in the standard atmosphere. Derive an expression for the rate of change of sonic speed with altitude in an ideal gas under standard atmospheric conditions. Evaluate and plot from sea level to 10 km altitude.

**Given:** Data on atmospheric temperature variation with altitude

**Find:** Lapse rate; plot rate of change of sonic speed with altitude

**Solution:**

The given or available data is:  $R_{\text{air}} = 286.9 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}}$   $k = 1.4$   $T_0 = 288.2\cdot\text{K}$   $T_{10\text{k}} = 223.3\cdot\text{K}$   $z = 10000\cdot\text{m}$

For a linear temperature variation  $T = T_0 + m\cdot z$

$$\frac{dT}{dz} = m = \frac{T - T_0}{z} \quad \text{which can be evaluated at } z = 10 \text{ km}$$


$$m = \frac{T_{10\text{k}} - T_0}{z} = -6.49 \times 10^{-3} \frac{\text{K}}{\text{m}}$$

For an ideal gas

$$c = \sqrt{k\cdot R\cdot T} = \sqrt{k\cdot R\cdot (T_0 + m\cdot z)}$$

Hence  $\frac{dc}{dz} = \frac{m\cdot k\cdot R}{2\cdot c}$  Here are the results, calculated using *Excel*:

$z$ (km)	$T$ (K)	$dc/dz$ ( $\text{s}^{-1}$ )
0	288.2	-0.00383
1	281.7	-0.00387
2	275.2	-0.00392
3	268.7	-0.00397
4	262.2	-0.00402
5	255.8	-0.00407
6	249.3	-0.00412
7	242.8	-0.00417
8	236.3	-0.00423
9	229.8	-0.00429
10	223.3	-0.00435



## Problem 12.42

[Difficulty: 1]

---

**12.42** Air at 77°F flows at  $M = 1.9$ . Determine the air speed and the Mach angle.

---

**Given:** Air flow at  $M = 1.9$

**Find:** Air speed; Mach angle

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\alpha = \text{asin}\left(\frac{1}{M}\right)$

The given or available data is  $T = (77 + 460) \cdot R$        $M = 1.9$        $k = 1.4$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot R}$

Hence  $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$        $c = 1136 \cdot \frac{\text{ft}}{\text{s}}$


Then the air speed is  $V = M \cdot c$        $V = 2158 \cdot \frac{\text{ft}}{\text{s}}$        $V = 1471 \cdot \text{mph}$

The Mach angle is given by  $\alpha = \text{asin}\left(\frac{1}{M}\right)$        $\alpha = 31.8 \cdot \text{deg}$

## Problem 12.43

[Difficulty: 3]

**12.43** Consider the hypersonic aircraft of Problem 12.35. How long would it take for an observer to hear the aircraft after it flies over the observer? In that elapsed time, how far did the aircraft travel?



**Given:** Hypersonic aircraft flying overhead

**Find:** Time at which airplane is heard, how far aircraft travelled

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\alpha = \text{asin}\left(\frac{1}{M}\right)$

Given or available data       $M = 7$        $k = 1.4$        $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$

The time it takes to fly from directly overhead to where you hear it is  $\Delta t = \frac{x}{V}$

If the temperature is constant then  $x = \frac{h}{\tan(\alpha)}$

At  $h = 120000 \cdot \text{ft}$      $h = 36576 \text{ m}$     interpolating from Table A.3     $T = 226.5 \cdot \text{K} + (250.4 \cdot \text{K} - 226.5 \cdot \text{K}) \cdot \frac{36576 - 30000}{40000 - 30000}$

$T = 242.2 \text{ K}$

Using this temperature       $c = \sqrt{k \cdot R \cdot T}$        $c = 312 \frac{\text{m}}{\text{s}}$     and     $V = M \cdot c$      $V = 2183 \frac{\text{m}}{\text{s}}$

Hence       $\alpha = \text{asin}\left(\frac{1}{M}\right)$        $\alpha = 8.2 \cdot \text{deg}$        $x = \frac{h}{\tan(\alpha)}$        $x = 253.4 \cdot \text{km}$

$\Delta t = \frac{x}{V}$        $\Delta t = 116.06 \text{ s}$

## Problem 12.44

[Difficulty: 3]

**12.44** A projectile is fired into a gas (ratio of specific heats  $k = 1.625$ ) in which the pressure is 450 kPa (abs) and the density is  $4.5 \text{ kg/m}^3$ . It is observed experimentally that a Mach cone emanates from the projectile with  $25^\circ$  total angle. What is the speed of the projectile with respect to the gas?

**Given:** Projectile fired into a gas, Mach cone formed

**Find:** Speed of projectile

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\alpha = \text{asin}\left(\frac{1}{M}\right)$        $p = \rho \cdot R \cdot T$

Given or available data       $p = 450 \cdot \text{kPa}$        $\rho = 4.5 \cdot \frac{\text{kg}}{\text{m}^3}$        $k = 1.625$        $\alpha = \frac{25}{2} \cdot \text{deg} = 12.5 \cdot \text{deg}$

Combining ideal gas equation of state and the sonic speed:       $c = \sqrt{k \cdot \frac{p}{\rho}}$        $c = 403.1 \frac{\text{m}}{\text{s}}$

From the Mach cone angle:       $M = \frac{1}{\sin(\alpha)}$        $M = 4.62$       Therefore the speed is:       $V = M \cdot c$        $V = 1862 \frac{\text{m}}{\text{s}}$

## Problem 12.45

[Difficulty: 1]

**12.45** A photograph of a bullet shows a Mach angle of  $32^\circ$ .

Determine the speed of the bullet for standard air.

Solution:

Computing equations,  $\sin \alpha = \frac{1}{M}$        $c = \sqrt{kRT}$

Assumptions: (1) air behaves as an ideal gas  
(2) constant specific heats.

$$M = \frac{1}{\sin \alpha}, \quad M = \frac{V}{c} \quad \therefore V = cM = \frac{c}{\sin \alpha}$$

Since  $c = \sqrt{kRT}$ , then

$$V = \frac{1}{\sin \alpha} (kRT)^{1/2} = \frac{1}{\sin 32^\circ} \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 288 \text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right)^{1/2}$$

$$V = 642 \text{ m/s} \quad (2110 \text{ ft/s})$$

## Problem 12.46

[Difficulty: 2]

**12.46** The National Transonic Facility (NTF) is a high-speed wind tunnel designed to operate with air at cryogenic temperatures to reduce viscosity, thus raising the unit Reynolds number ( $Re/x$ ) and reducing pumping power requirements. Operation is envisioned at temperatures of  $-270^\circ\text{F}$  and below. A schlieren photograph taken in the NTF shows a Mach angle of  $57^\circ$  where  $T = -270^\circ\text{F}$  and  $p = 1.3$  psia. Evaluate the local Mach number and flow speed. Calculate the unit Reynolds number for the flow.

Solution:

$$\sin \alpha = \frac{1}{M} \quad \therefore M = \frac{1}{\sin \alpha} = \frac{1}{\sin 57^\circ} = 1.19 \quad M$$

$$c = \sqrt{\gamma RT} = \left[ 1.4 \times 53.3 \frac{\text{ft} \cdot \text{bf}}{\text{lbm} \cdot ^\circ\text{R}} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times 190^\circ\text{R} \times \frac{\text{slug} \cdot \text{ft}^2}{\text{lbm} \cdot \text{s}^2} \right]^{1/2} = 676 \text{ ft/s}$$

$$V = Mc = 1.19 (676 \text{ ft/s}) = 804 \text{ ft/s} \quad V$$

$$Re_x = \frac{\rho V x}{\mu}$$

$$\rho = \frac{p}{RT} = 1.3 \frac{\text{lb}}{\text{in}^2} \times \frac{\text{in}^2}{57^2} \times 53.3 \frac{\text{ft} \cdot \text{bf}}{\text{lbm} \cdot ^\circ\text{R}} \times \frac{1}{190^\circ\text{R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.085 \text{ lbm/ft}^3$$

From Eq. A.1 (Appendix A)

$$\mu = \frac{bT^{1/2}}{1 + s/T} \quad b = 1.458 \times 10^{-6} \text{ kg/m} \cdot \text{s} \cdot \text{K}^{1/2}$$

$$s = 110.4 \text{ K}$$

T in K

$$T = -270^\circ\text{F} = -167^\circ\text{C} = 106 \text{ K}$$

$$\mu = 1.458 \times 10^{-6} \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^{1/2}} (106 \text{ K})^{1/2} \times \frac{1}{1 + \frac{110.4}{106}} = 7.35 \times 10^{-6} \text{ kg/m} \cdot \text{s}$$

$$\mu = 7.35 \times 10^{-6} \frac{\text{kg}}{\text{m} \cdot \text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} \times \frac{2.089 \times 10^{-2} \text{ (bf} \cdot \text{s)} / \text{ft}^2}{1 \text{ N} \cdot \text{s}}$$

$$\mu = 1.54 \times 10^{-7} \text{ (bf} \cdot \text{s)} / \text{ft}^2$$

$$\therefore \frac{Re_x}{x} = \frac{\rho V}{\mu} = 0.085 \frac{\text{lbm}}{\text{ft}^3} \times 804 \frac{\text{ft}}{\text{s}} \times \frac{\text{ft}^2}{1.54 \times 10^{-7} \text{ (bf} \cdot \text{s)}} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{bf} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$\frac{Re_x}{x} = 3.00 \times 10^6 \text{ ft}^{-1} = 9.84 \times 10^6 \text{ m}^{-1} \quad Re/x$$



## Problem 12.47

[Difficulty: 2]


**12.47** An F-4 aircraft makes a high-speed pass over an airfield on a day when  $T = 35^\circ\text{C}$ . The aircraft flies at  $M = 1.4$  and 200 m altitude. Calculate the speed of the aircraft. How long after it passes directly over point A on the ground does its Mach cone pass over point A?

Solution: Assume  $T = \text{constant}$  over 200m elevation.

$$T = 35^\circ\text{C} = 308\text{ K}$$

$$c = \sqrt{\gamma RT} = \left[ 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 308\text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right]^{1/2} = 352\text{ m/s}$$

$$v = Mc = 1.4 \times 352\text{ m/s} = 493\text{ m/s} \quad \leftarrow v$$



From the instant the aircraft is directly overhead until the Mach cone reaches the ground, the plane travels a distance  $\Delta x$  at speed  $v = 493\text{ m/s}$

$$\sin \alpha = \frac{1}{M} = \frac{1}{1.4} = 0.7143$$

$$\alpha = 45.6^\circ$$

$$\frac{h}{\Delta x} = \tan \alpha \quad \therefore \Delta x = \frac{h}{\tan \alpha} = \frac{200\text{ m}}{\tan 45.6^\circ} = 196\text{ m}$$

Since the plane moves at constant speed  $v$


$$\Delta x = v \Delta t \quad \text{and} \quad \Delta t = \frac{\Delta x}{v} = \frac{196\text{ m}}{493\text{ m/s}}$$

$$\Delta t = 0.398\text{ s} \quad \leftarrow \Delta t$$

## Problem 12.48

[Difficulty: 2]

**12.48** While jogging on the beach (it's a warm summer day, about 25°C) a high-speed jet flies overhead. You guesstimate that it's at an altitude of about 3000 m, and count off about 7.5 s before you hear it. Estimate the speed and Mach number of the jet.



**Given:** High-speed jet flying overhead

**Find:** Estimate speed and Mach number of jet

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\alpha = \text{asin}\left(\frac{1}{M}\right)$

Given or available data     $T = (25 + 273) \cdot \text{K}$      $h = 3000 \cdot \text{m}$      $k = 1.4$        $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$

The time it takes to fly from directly overhead to where you hear it is  $\Delta t = 7.5 \cdot \text{s}$

The distance traveled, moving at speed  $V$ , is  $x = V \cdot \Delta t$

The Mach angle is related to height  $h$  and distance  $x$  by  $\tan(\alpha) = \frac{\sin(\alpha)}{\cos(\alpha)} = \frac{h}{x} = \frac{h}{V \cdot \Delta t}$       (1)

and also we have  $\sin(\alpha) = \frac{1}{M} = \frac{c}{V}$       (2)

Dividing Eq. 2 by Eq 1  $\cos(\alpha) = \frac{c}{V} \cdot \frac{V \cdot \Delta t}{h} = \frac{c \cdot \Delta t}{h}$

Note that we could have written this equation from geometry directly!

We have  $c = \sqrt{k \cdot R \cdot T}$        $c = 346 \frac{\text{m}}{\text{s}}$       so  $\alpha = \text{acos}\left(\frac{c \cdot \Delta t}{h}\right)$        $\alpha = 30.1 \cdot \text{deg}$

Hence  $M = \frac{1}{\sin(\alpha)}$        $M = 1.99$

Then the speed is  $V = M \cdot c$        $V = 689 \frac{\text{m}}{\text{s}}$

Note that we assume the temperature of the air is uniform. In fact the temperature will vary over 3000 m, so the Mach cone will be curved. This speed and Mach number are only rough estimates.

## Problem 12.49

[Difficulty: 2]

**12.49** An aircraft passes overhead at 3 km altitude. The aircraft flies at  $M = 1.5$ ; assume air temperature is constant at  $20^\circ\text{C}$ . Find the air speed of the aircraft. A headwind blows at 30 m/s. How long after the aircraft passes directly overhead does its sound reach a point on the ground?

Solution:


$$T = \text{constant} = 20^\circ\text{C} = 293\text{ K}$$

$$c = (\gamma RT)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 293\text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 343\text{ m/s}$$

$$v = Mc = 1.5 \times 343 \frac{\text{m}}{\text{sec}} = 515\text{ m/s} \quad \leftarrow \text{airspeed}$$

The airspeed is the velocity of the plane relative to the air

The ground speed is then  $\vec{v}_p = \vec{v}_{\text{air}} + \vec{v}_{\text{pla}}$  or  $v_p = 485\text{ m/sec}$



From the instant the aircraft is directly overhead until the Mach cone reaches the ground, the plane travels a distance,  $D$ , at speed  $v_p = 485\text{ m/s}$ .

The value of the time,  $t$ , is then  $t = D/v_p$

Since the air temperature is constant, the Mach line is straight and  $D = h/\tan\alpha$ , where  $\alpha = \sin^{-1}(1/M)$


$$\alpha = \sin^{-1}\left(\frac{1}{M}\right) = \sin^{-1}\left(\frac{1}{1.5}\right) = 41.8^\circ$$

$$\text{Then, } t = \frac{D}{v_p} = \frac{h}{\tan\alpha v_p} = \frac{3000\text{ m}}{\tan 41.8^\circ \times 485\text{ m/s}} = 6.92\text{ s} \quad \leftarrow t$$

## Problem 12.50

[Difficulty: 3]

**12.50** A supersonic aircraft flies at 3 km altitude at a speed of 1000 m/s on a standard day. How long after passing directly above a ground observer is the sound of the aircraft heard by the ground observer?



**Given:** Supersonic aircraft flying overhead

**Find:** Time at which airplane heard

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\alpha = \text{asin}\left(\frac{1}{M}\right)$

Given or available data       $V = 1000 \frac{\text{m}}{\text{s}}$        $h = 3 \cdot \text{km}$        $k = 1.4$        $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$

The time it takes to fly from directly overhead to where you hear it is  $\Delta t = \frac{x}{V}$

If the temperature is constant then  $x = \frac{h}{\tan(\alpha)}$

The temperature is not constant so the Mach line will not be straight. We can find a range of  $\Delta t$  by considering the temperature range

At  $h = 3 \cdot \text{km}$  we find from Table A.3 that  $T = 268.7 \text{K}$

Using this temperature       $c = \sqrt{k \cdot R \cdot T}$        $c = 329 \frac{\text{m}}{\text{s}}$       and       $M = \frac{V}{c}$        $M = 3.04$

Hence       $\alpha = \text{asin}\left(\frac{1}{M}\right)$        $\alpha = 19.2 \text{deg}$        $x = \frac{h}{\tan(\alpha)}$        $x = 8625 \text{m}$        $\Delta t = \frac{x}{V}$        $\Delta t = 8.62 \text{s}$

At sea level we find from Table A.3 that  $T = 288.2 \text{K}$

Using this temperature       $c = \sqrt{k \cdot R \cdot T}$        $c = 340 \frac{\text{m}}{\text{s}}$       and       $M = \frac{V}{c}$        $M = 2.94$


Hence       $\alpha = \text{asin}\left(\frac{1}{M}\right)$        $\alpha = 19.9 \text{deg}$        $x = \frac{h}{\tan(\alpha)}$        $x = 8291 \text{m}$        $\Delta t = \frac{x}{V}$        $\Delta t = 8.29 \text{s}$

Thus we conclude that the time is somewhere between 8.62 and 8.29 s. Taking an average  $\Delta t = 8.55 \text{s}$

## Problem 12.51

[Difficulty: 3]

**12.51** For the conditions of Problem 12.50, find the location at which the sound wave that first reaches the ground observer was emitted.



**Given:** Supersonic aircraft flying overhead

**Find:** Location at which first sound wave was emitted

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\alpha = \text{asin}\left(\frac{1}{M}\right)$

Given or available data       $V = 1000 \cdot \frac{\text{m}}{\text{s}}$        $h = 3 \cdot \text{km}$        $k = 1.4$        $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$

We need to find  $\Delta x$  as shown in the figure       $\Delta x = h \cdot \tan(\alpha)$

The temperature is not constant so the Mach line will not be straight ( $\alpha$  is not constant). We can find a range of  $\alpha$  and  $\Delta x$  by considering the temperature range

At  $h = 3 \cdot \text{km}$  we find from Table A.3 that       $T = 268.7 \cdot \text{K}$

Using this temperature       $c = \sqrt{k \cdot R \cdot T}$        $c = 329 \frac{\text{m}}{\text{s}}$       and       $M = \frac{V}{c}$        $M = 3.04$

Hence       $\alpha = \text{asin}\left(\frac{1}{M}\right)$        $\alpha = 19.2 \cdot \text{deg}$        $\Delta x = h \cdot \tan(\alpha)$        $\Delta x = 1043 \text{ m}$

At sea level we find from Table A.3 that       $T = 288.2 \cdot \text{K}$

Using this temperature       $c = \sqrt{k \cdot R \cdot T}$        $c = 340 \frac{\text{m}}{\text{s}}$       and       $M = \frac{V}{c}$        $M = 2.94$

Hence       $\alpha = \text{asin}\left(\frac{1}{M}\right)$        $\alpha = 19.9 \cdot \text{deg}$        $\Delta x = h \cdot \tan(\alpha)$        $\Delta x = 1085 \text{ m}$

Thus we conclude that the distance is somewhere between 1043 and 1085 m. Taking an average       $\Delta x = 1064 \cdot \text{m}$

## Problem 12.52

[Difficulty: 4] Part 1/2

**12.52** The Concorde supersonic transport cruised at  $M = 2.2$  at 17 km altitude on a standard day. How long after the aircraft passed directly above a ground observer was the sound of the aircraft heard?

Solution:

At altitude,  $T = 216.7 \text{ K}$   $c = (kRT)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 216.7 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 295 \text{ m/s}$


$v = Mc = 2.2 \times 295 \text{ m/s} = 649 \text{ m/s}$

If the speed of sound were constant all the way to the ground, the Mach line would remain straight. The Mach angle,  $\alpha$ , would be constant with

$\alpha = \sin^{-1}\left(\frac{1}{M}\right) = \sin^{-1}\left(\frac{1}{2.2}\right) = 27^\circ$

Then, from the diagram  $y = \frac{h}{\tan \alpha}$

and  $t = \frac{y}{v} = \frac{17000 \text{ m}}{\tan 27^\circ \times 649 \text{ m/s}} = 51.4 \text{ s}$



However, the speed of sound varies over the altitude because the temperature varies with altitude.

At sea level,  $T = 288.2 \text{ K}$

$c = (kRT)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 288.2 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 340 \text{ m/s}$

The corresponding value of Mach number for  $v = 649 \text{ m/s}$  is

$M = \frac{v}{c} = \frac{649}{340} = 1.91$

$\alpha = \sin^{-1}\left(\frac{1}{M}\right) = \sin^{-1}\left(\frac{1}{1.91}\right) = 31.6^\circ$

Thus, if the speed of sound were constant (at the sea level) value over the entire altitude, then

$t = \frac{y}{v} = \frac{h}{\tan \alpha \times v} = \frac{17000 \text{ m}}{\tan 31.6^\circ \times 649 \text{ m/s}} = 42.6 \text{ s}$

We can obtain a better approximate by considering the variation of temperature with altitude.

From Table A.3

$11 \text{ km} \leq y < 20 \text{ km}$

$T = 216.7 \text{ K}$

$0 < y \leq 11 \text{ km}$


$T$  varies linearly with  $y$ .

$T = T_0 - by$


$T_0 = 288.2 \text{ K}$

$b = 6.50 \times 10^{-5} \text{ K/m}$

# Problem 12.52



Since  $T$  is constant for  $y > y_0 = 11 \text{ km}$ , the second approximation which assumes the Mach line at sea level for  $0 < y \leq 11 \text{ km}$  gives the minimum time



$$D_1 = \frac{h_1}{\tan \alpha_1} = \frac{6 \text{ km}}{\tan 27^\circ} = 11.77 \text{ km}$$

$$D_2 = \frac{h_2}{\tan \alpha_2} = \frac{11 \text{ km}}{\tan 31.6^\circ} = 17.88 \text{ km}$$

$$D = D_1 + D_2$$

$$t = \frac{D}{v} = \frac{29.65 \text{ km}}{649 \text{ m/s}} = 45.7 \text{ s}$$

Consequently,  $45.7 \leq t \leq 51.4 \text{ s}$   
 Since the two values are reasonably close, it is appropriate to take the average value and say  $t = 48.5 \text{ s}$

t

## Problem 12.53

[Difficulty: 2]

**12.53** The airflow around an automobile is assumed to be incompressible. Investigate the validity of this assumption for an automobile traveling at 60 mph. (Relative to the automobile the minimum air velocity is zero, and the maximum is approximately 120 mph.)

**Given:** Speed of automobile

**Find:** Whether flow can be considered incompressible

**Solution:**

Consider the automobile at rest with 60 mph air flowing over it. Let state 1 be upstream, and point 2 the stagnation point on the automobile

The data provided, or available in the Appendices, is:

$$R = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad k = 1.4 \quad V_1 = 60 \cdot \text{mph} \quad p_1 = 101 \cdot \text{kPa} \quad T_1 = (20 + 273) \cdot \text{K}$$

The basic equation for the density change is

$$\frac{\rho_0}{\rho} = \left[ 1 + \frac{(k-1)}{2} \cdot M^2 \right]^{\frac{1}{k-1}} \quad (12.20c)$$

or

$$\rho_0 = \rho_1 \cdot \left[ 1 + \frac{(k-1)}{2} \cdot M_1^2 \right]^{\frac{1}{k-1}}$$

$$\rho_1 = \frac{p_1}{R \cdot T_1} \quad \rho_1 = 1.201 \frac{\text{kg}}{\text{m}^3}$$

For the Mach number we need c

$$c_1 = \sqrt{k \cdot R \cdot T_1} \quad c_1 = 343 \frac{\text{m}}{\text{s}}$$

$$V_1 = 26.8 \frac{\text{m}}{\text{s}} \quad M_1 = \frac{V_1}{c_1} \quad M_1 = 0.0782$$

$$\rho_0 = \rho_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)^{\frac{1}{k-1}} \quad \rho_0 = 1.205 \frac{\text{kg}}{\text{m}^3} \quad \text{The percentage change in density is} \quad \left| \frac{\rho_0 - \rho_1}{\rho_0} \right| = 0.305\%$$

This is an insignificant change, so the flow can be considered incompressible. Note that  $M < 0.3$ , the usual guideline for incompressibility

For the maximum speed present

$$V_1 = 120 \cdot \text{mph} \quad V_1 = 53.6 \frac{\text{m}}{\text{s}} \quad M_1 = \frac{V_1}{c_1} \quad M_1 = 0.156$$

$$\rho_0 = \rho_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)^{\frac{1}{k-1}} \quad \rho_0 = 1.216 \frac{\text{kg}}{\text{m}^3} \quad \text{The percentage change in density is} \quad \left| \frac{\rho_0 - \rho_1}{\rho_0} \right| = 1.21\%$$

This is still an insignificant change, so the flow can be considered incompressible.

## Problem 12.54

[Difficulty: 5]

---

**12.54** Opponents of supersonic transport aircraft claim that sound waves can be refracted in the upper atmosphere and that, as a result, sonic booms can be heard several hundred miles away from the ground track of the aircraft. Explain the phenomenon of sound wave refraction.

---

**Given:** Supersonic transport aircraft

**Find:** Explanation of sound wave refraction

**Solution:**

A sound wave is refracted when the speed of sound varies with altitude in the atmosphere. (The variation in sound speed is caused by temperature variations in the atmosphere, as shown in Fig. 3.3)

Imagine a plane wave front that initially is vertical. When the wave encounters a region where the temperature increase with altitude (such as between 20.1 km and 47.3 km altitude in Fig. 3.3), the sound speed increases with elevation. Therefore the upper portion of the wave travels faster than the lower portion. The wave front turns gradually and the sound wave follows a curved path through the atmosphere. Thus a wave that initially is horizontal bends and follows a curved path, tending to reach the ground some distance from the source.

The curvature and the path of the sound could be calculated for any specific temperature variation in the atmosphere. However, the required analysis is beyond the scope of this text.

## Problem 12.55

[Difficulty: 2]

**12.55** Plot the percentage discrepancy between the density at the stagnation point and the density at a location where the Mach number is  $M$ , of a compressible flow, for Mach numbers ranging from 0.05 to 0.95. Find the Mach numbers at which the discrepancy is 1 percent, 5 percent, and 10 percent.

**Given:** Mach number range from 0.05 to 0.95

**Find:** Plot of percentage density change; Mach number for 1%, 5% and 10% density change

**Solution:**

The given or available data is:  $k = 1.4$

Basic equation:

$$\frac{\rho_0}{\rho} = \left[ 1 + \frac{(k-1)}{2} \cdot M^2 \right]^{\frac{1}{k-1}} \quad (12.20c) \quad \text{Hence} \quad \frac{\Delta\rho}{\rho_0} = \frac{\rho_0 - \rho}{\rho_0} = 1 - \frac{\rho}{\rho_0} \quad \text{so} \quad \frac{\Delta\rho}{\rho_0} = 1 - \left[ 1 + \frac{(k-1)}{2} \cdot M^2 \right]^{\frac{1}{1-k}}$$

Here are the results, generated using *Excel*:


$M$	$\Delta\rho/\rho_0$
0.05	0.1%
0.10	0.5%
0.15	1.1%
0.20	2.0%
0.25	3.1%
0.30	4.4%
0.35	5.9%
0.40	7.6%
0.45	9.4%
0.50	11%
0.55	14%
0.60	16%
0.65	18%
0.70	21%
0.75	23%
0.80	26%
0.85	29%
0.90	31%
0.95	34%

To find  $M$  for specific density changes use *Goal Seek* repeatedly

$M$	$\Delta\rho/\rho_0$
0.142	1%
0.322	5%
0.464	10%

Note: Based on  $\rho$  (not  $\rho_0$ ) the results are:

0.142	0.314	0.441
-------	-------	-------



## Problem 12.56

[Difficulty: 2]

**12.56** Find the stagnation temperature at the nose of the missile described in Problem 12.29.

**Given:** Scramjet-powered missile traveling at fixed Mach number and altitude

**Find:** Stagnation temperature at the nose of the missile

**Solution:**

Basic equation: 
$$T_0 = T \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right)$$

Available data  $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$   $k = 1.4$   $M = 7$

At  $z = 85000 \cdot \text{ft}$   $z = 25908 \text{ m}$  interpolating from Table A.3  $T = 220.6 \cdot \text{K} + (222.5 \cdot \text{K} - 220.6 \cdot \text{K}) \cdot \frac{25908 - 24000}{26000 - 24000}$

$$T = 222 \text{ K}$$

So the stagnation temperature is 
$$T_0 = T \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right) \quad T_0 = 2402 \text{ K}$$

## Problem 12.57

[Difficulty: 2]

**12.57** Find the stagnation temperature at the nose of the aircraft described in Problem 12.34.

**Given:** X-15 rocket plane traveling at fixed Mach number and altitude

**Find:** Stagnation temperature at the nose of the plane

**Solution:**

Basic equation:  $T_0 = T \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right)$     $c = \sqrt{k \cdot R \cdot T}$     $M = \frac{V}{c}$

Available data    $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$     $k = 1.4$     $V = 7270 \cdot \frac{\text{km}}{\text{hr}}$

At    $z = 58400 \cdot \text{m}$    interpolating from Table A.3    $T = 270.7 \cdot \text{K} + (255.8 \cdot \text{K} - 270.7 \cdot \text{K}) \cdot \frac{58400 - 50000}{60000 - 50000}$

$$T = 258 \text{ K}$$

Hence    $c = \sqrt{k \cdot R \cdot T}$     $c = 322 \frac{\text{m}}{\text{s}}$     $c = 1159 \cdot \frac{\text{km}}{\text{hr}}$  and we have    $M = \frac{V}{c} = 6.27$

So the stagnation temperature is    $T_0 = T \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right)$     $T_0 = 2289 \text{ K}$

## Problem 12.58

[Difficulty: 1]

**12.58** Find the ratio of static to total pressure for a car moving at 55 mph and for a Formula One race car traveling at 220 mph at sea level. Do you expect the flow over either car to experience compressibility effects?

**Given:** Car and F-1 race car traveling at sea level

**Find:** Ratio of static to total pressure in each case; are compressibility effects experienced?

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$

Given or available data       $V_{\text{car}} = 55 \cdot \text{mph}$        $V_{\text{car}} = 80.7 \cdot \frac{\text{ft}}{\text{s}}$        $V_{\text{F1}} = 220 \cdot \text{mph}$        $V_{\text{F1}} = 323 \cdot \frac{\text{ft}}{\text{s}}$   
 $k = 1.4$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$

At sea level, from Table A.3       $T = 288.2 \cdot \text{K}$       or       $T = 519 \cdot \text{R}$        $\rho = 0.002377 \cdot \frac{\text{slug}}{\text{ft}^3}$        $p = 14.696 \cdot \text{psi}$

Hence       $c = \sqrt{k \cdot R_{\text{air}} \cdot T}$        $c = 1116 \cdot \frac{\text{ft}}{\text{s}}$        $M_{\text{car}} = \frac{V_{\text{car}}}{c}$        $M_{\text{car}} = 0.0723$

The pressure ratio is       $\frac{p}{p_0} = \left(1 + \frac{k-1}{2} \cdot M_{\text{car}}^2\right)^{-\frac{k}{k-1}} = 0.996$

Note that the Bernoulli equation would give the same result!       $\frac{p}{p_0} = \left(1 + \frac{\rho \cdot V_{\text{car}}^2}{2 \cdot p}\right)^{-1} = 0.996$

For the Formula One car:       $M_{\text{F1}} = \frac{V_{\text{F1}}}{c}$        $M_{\text{F1}} = 0.289$

The pressure ratio is       $\frac{p}{p_0} = \left(1 + \frac{k-1}{2} \cdot M_{\text{F1}}^2\right)^{-\frac{k}{k-1}} = 0.944$

Note that the Bernoulli equation would give almost the same result:       $\frac{p}{p_0} = \left(1 + \frac{\rho \cdot V_{\text{F1}}^2}{2 \cdot p}\right)^{-1} = 0.945$

Incompressible flow can be assumed for both cases, but the F1 car gets very close to the Mach 0.3 rule of thumb for compressible vs. incompressible flow.

## Problem 12.59

[Difficulty: 2]

**12.59** Find the dynamic and stagnation pressures for the missile described in Problem 12.29.

**Given:** Scramjet-powered missile traveling at fixed Mach number and altitude

**Find:** Stagnation and dynamic pressures

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p_{\text{dyn}} = \frac{1}{2} \cdot \rho \cdot V^2$

Available data     $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$      $k = 1.4$      $M = 7$      $p_{\text{SL}} = 14.696 \cdot \text{psi}$      $\rho_{\text{SL}} = 0.2377 \cdot \frac{\text{slug}}{\text{ft}^3}$

At                     $z = 85000 \cdot \text{ft}$      $z = 25908 \text{ m}$     interpolating from Table A.3     $T = 220.6 \cdot \text{K} + (222.5 \cdot \text{K} - 220.6 \cdot \text{K}) \cdot \frac{25908 - 24000}{26000 - 24000}$   
 $T = 222 \text{ K}$

Hence               $c = \sqrt{k \cdot R \cdot T}$                $c = 299 \frac{\text{m}}{\text{s}}$                $c = 981 \cdot \frac{\text{ft}}{\text{s}}$     and we have               $V = M \cdot c = 6864 \cdot \frac{\text{ft}}{\text{s}}$

The static pressure and density can be found by interpolation:

$$p = p_{\text{SL}} \cdot \left[0.02933 + (0.02160 - 0.02933) \cdot \frac{25908 - 24000}{26000 - 24000}\right] p = 0.323 \cdot \text{psi} \quad p_0 = p \cdot \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}} \quad p_0 = 1336 \cdot \text{psi}$$

$$\rho = \rho_{\text{SL}} \cdot \left[0.03832 + (0.02797 - 0.03832) \cdot \frac{25908 - 24000}{26000 - 24000}\right] \rho = 0.00676 \cdot \frac{\text{slug}}{\text{ft}^3} \quad p_{\text{dyn}} = \frac{1}{2} \cdot \rho \cdot V^2 \quad p_{\text{dyn}} = 1106 \cdot \text{psi}$$

## Problem 12.60

[Difficulty: 2]

**12.60** Find the dynamic and stagnation pressures for the aircraft described in Problem 12.34.

**Given:** X-15 rocket plane traveling at fixed Mach number and altitude

**Find:** Stagnation and dynamic pressures

**Solution:**

Basic equation:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p_{\text{dyn}} = \frac{1}{2} \cdot \rho \cdot V^2$

Available data       $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $k = 1.4$        $V = 7270 \frac{\text{km}}{\text{hr}}$        $p_{\text{SL}} = 101.3 \cdot \text{kPa}$        $\rho_{\text{SL}} = 1.225 \frac{\text{kg}}{\text{m}^3}$

At       $z = 58400 \cdot \text{m}$  interpolating from Table A.3       $T = 270.7 \cdot \text{K} + (255.8 \cdot \text{K} - 270.7 \cdot \text{K}) \cdot \frac{58400 - 50000}{60000 - 50000}$

$T = 258 \text{ K}$

Hence       $c = \sqrt{k \cdot R \cdot T}$        $c = 322 \frac{\text{m}}{\text{s}}$        $c = 1159 \frac{\text{km}}{\text{hr}}$  and we have       $M = \frac{V}{c} = 6.27$

The static pressure and density can be found by interpolation:

$p = p_{\text{SL}} \cdot \left[0.0007874 + (0.0002217 - 0.0007874) \cdot \frac{58400 - 50000}{60000 - 50000}\right]$        $p = 0.0316 \cdot \text{kPa}$

$p_0 = p \cdot \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p_0 = 65.6 \cdot \text{kPa}$

$\rho = \rho_{\text{SL}} \cdot \left[0.0008383 + (0.0002497 - 0.0008383) \cdot \frac{58400 - 50000}{60000 - 50000}\right]$        $\rho = 4.21 \times 10^{-4} \frac{\text{kg}}{\text{m}^3}$

$p_{\text{dyn}} = \frac{1}{2} \cdot \rho \cdot V^2$        $p_{\text{dyn}} = 0.86 \cdot \text{kPa}$

## Problem 12.61

[Difficulty: 1]

**12.61** An aircraft flies at 250 m/s in air at 28 kPa and  $-50^{\circ}\text{C}$ .  
Find the stagnation pressure at the nose of the aircraft.

**Given:** Aircraft flying at 250 m/s

**Find:** Stagnation pressure

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$

Given or available data       $V = 250 \cdot \frac{\text{m}}{\text{s}}$        $T = (-50 + 273) \cdot \text{K}$        $p = 28 \cdot \text{kPa}$        $k = 1.4$        $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$

First we need       $c = \sqrt{k \cdot R \cdot T}$        $c = 299 \frac{\text{m}}{\text{s}}$       then       $M = \frac{V}{c}$        $M = 0.835$

Finally we solve for  $p_0$        $p_0 = p \cdot \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p_0 = 44.2 \cdot \text{kPa}$

## Problem 12.62

[Difficulty: 2]

**12.62** Compute the air density in the undisturbed air, and at the stagnation point, of Problem 12.61. What is the percentage increase in density? Can we approximate this as an incompressible flow?

**Given:** Pressure data on aircraft in flight

**Find:** Change in air density; whether flow can be considered incompressible

**Solution:**

The data provided, or available in the Appendices, is:

$$k = 1.4 \quad p_0 = 48 \cdot \text{kPa} \quad p = 27.6 \cdot \text{kPa} \quad T = (-55 + 273) \cdot \text{K}$$

Governing equation (assuming isentropic flow):

$$\frac{p}{\rho^k} = \text{constant} \quad (12.12c)$$

Hence

$$\frac{\rho}{\rho_0} = \left( \frac{p}{p_0} \right)^{\frac{1}{k}}$$

so

$$\frac{\Delta\rho}{\rho} = \frac{\rho_0 - \rho}{\rho} = \frac{\rho_0}{\rho} - 1 = \left( \frac{p_0}{p} \right)^{\frac{1}{k}} - 1 \quad \frac{\Delta\rho}{\rho} = 48.5\% \quad \text{NOT an incompressible flow!}$$

## Problem 12.63

[Difficulty: 2]

**12.63** For an aircraft traveling at  $M = 2$  at an elevation of 12 km, find the dynamic and stagnation pressures.

**Given:** Aircraft flying at 12 km

**Find:** Dynamic and stagnation pressures

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p_{\text{dyn}} = \frac{1}{2} \cdot \rho \cdot V^2$

Given or available data       $M = 2$        $h = 12 \cdot \text{km}$        $k = 1.4$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

$\rho_{\text{SL}} = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$        $p_{\text{SL}} = 101.3 \cdot \text{kPa}$

At  $h = 12 \cdot \text{km}$ , from Table A.3       $\rho = 0.2546 \cdot \rho_{\text{SL}}$        $\rho = 0.312 \frac{\text{kg}}{\text{m}^3}$        $p = 0.1915 \cdot p_{\text{SL}}$        $p = 19.4 \cdot \text{kPa}$        $T = 216.7 \cdot \text{K}$

Hence  $p_0 = p \cdot \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p_0 = 152 \cdot \text{kPa}$

Also  $c = \sqrt{k \cdot R \cdot T}$        $c = 295 \frac{\text{m}}{\text{s}}$        $V = M \cdot c$        $V = 590 \frac{\text{m}}{\text{s}}$

Hence  $p_{\text{dyn}} = \frac{1}{2} \cdot \rho \cdot V^2$        $p_{\text{dyn}} = 54.3 \cdot \text{kPa}$

## Problem 12.64

[Difficulty: 1]

**12.64** A body moves through standard air at 200 m/s. What is the stagnation pressure on the body? Assume (a) compressible flow and (b) incompressible flow.

Solution:

For standard air,  $P = 101 \text{ kPa}$ ,  $T = 15^\circ\text{C}$

Computing equations:  $P_0 = P + \frac{1}{2}\rho V^2$  (incompressible)

$$\frac{P_0}{P} = \left[1 + \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}} \text{ (compressible)}$$

a) Incompressible flow

$$P_0 = P + \frac{1}{2}\rho V^2 = 101 \text{ kPa} + \frac{1}{2} \times 1.225 \frac{\text{kg}}{\text{m}^3} \times \frac{(200)^2 \text{ m}^2}{\text{s}^2} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} \times \frac{\text{kPa}}{10^3 \text{ N}}$$

$$P_0 = 125.5 \text{ kPa} \quad \leftarrow P_{0, \text{inc}}$$

b) Compressible flow

$$M = \frac{V}{c} \quad c = (\gamma R T)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 288 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 340 \text{ m/s}$$

$$M = \frac{200}{340} = 0.588$$

$$P_0 = P \left[1 + \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}} = 101 \text{ kPa} \left[1 + 0.2(0.588)^2\right]^{3.5} = 127.6 \text{ kPa} \quad \leftarrow P_{0, \text{comp}}$$

## Problem 12.65

[Difficulty: 1]


**12.65** Consider flow of standard air at 600 m/s. What is the local isentropic stagnation pressure? The stagnation enthalpy? The stagnation temperature?

Solution:

Computing equations:  $\frac{P_0}{P} = \left[1 + \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}}$

$$\frac{T_0}{T} = 1 + \frac{\gamma-1}{2} M^2$$

$$c = \sqrt{\gamma R T}$$



Assumption: air behaves as an ideal gas,  $\gamma = 1.4$

$$c = (\gamma R T)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 288\text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 340 \text{ m/s}$$

$$M = \frac{V}{c} = \frac{600}{340} = 1.76$$

$$P_0 = P \left[1 + \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}} = 101 \text{ kPa} \left[1 + 0.2(1.76)^2\right]^{3.5} = 546 \text{ kPa}$$

$$T_0 = T \left[1 + \frac{\gamma-1}{2} M^2\right] = 288 \text{ K} \left[1 + 0.2(1.76)^2\right] = 466 \text{ K}$$

$dh = c_p dT$ . For  $c_p = \text{constant}$

$$h_0 - h = \int_h^{h_0} dh = \int_T^{T_0} c_p dT = c_p (T_0 - T) = 1000 \frac{\text{J}}{\text{kg}\cdot\text{K}} (466 - 288) \text{ K}$$

$$h_0 - h = 178 \text{ kJ/kg}$$

## Problem 12.66

[Difficulty: 1]

**12.66** A DC-10 aircraft cruises at 12 km altitude on a standard day. A pitot-static tube on the nose of the aircraft measures stagnation and static pressures of 29.6 kPa and 19.4 kPa. Calculate (a) the flight Mach number of the aircraft, (b) the speed of the aircraft, and (c) the stagnation temperature that would be sensed by a probe on the aircraft.

Solution:

Computing equations:  $\frac{p_0}{p} = 1 + \frac{k-1}{2} M^2$        $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$

Solving the first equation for M

$$M = \left\{ \frac{2}{k-1} \left[ \left( \frac{p_0}{p} \right)^{\frac{k-1}{k}} - 1 \right] \right\}^{1/2} = \left\{ \frac{2}{1.4-1} \left[ \left( \frac{29.6}{19.4} \right)^{\frac{1.4-1}{1.4}} - 1 \right] \right\}^{1/2} = 0.801 \quad \leftarrow M$$

At  $z = 12 \text{ km}$ ,  $T = 216.7 \text{ K}$  (Table A.3)

$$c = (kRT)^{1/2} = \left( 1.4 \times 286.9 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 216.7 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right)^{1/2} = 295 \text{ m/s}$$

$$V = Mc = 0.801 \times 295 \text{ m/s} = 236 \text{ m/s} \quad \leftarrow V$$

$$T_0 = T \left( 1 + \frac{k-1}{2} M^2 \right) = 216.7 \text{ K} \left[ 1 + \frac{1.4-1}{2} (0.801)^2 \right] = 245 \text{ K} \quad \leftarrow T_0$$

## Problem 12.67

[Difficulty: 2]

**12.67** An aircraft cruises at  $M = 0.65$  at 10 km altitude on a standard day. The aircraft speed is deduced from measurement of the difference between the stagnation and static pressures. What is the value of this difference? Compute the air speed from this actual difference assuming (a) compressibility and (b) incompressibility. Is the discrepancy in air-speed computations significant in this case?

**Given:** Mach number of aircraft

**Find:** Pressure difference; air speed based on a) compressible b) incompressible assumptions

**Solution:**

The data provided, or available in the Appendices, is:

$$R = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad k = 1.4 \quad M = 0.65$$

From Table A.3, at 10 km altitude  $T = 223.3 \cdot \text{K}$   $p = 0.2615 \cdot 101 \cdot \text{kPa}$   $p = 26.4 \cdot \text{kPa}$

The governing equation for pressure change is: 
$$\frac{p_0}{p} = \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}} \quad (12.20a)$$

Hence 
$$p_0 = p \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}} \quad p_0 = 35.1 \cdot \text{kPa}$$

The pressure difference is  $p_0 - p = 8.67 \cdot \text{kPa}$

a) Assuming compressibility  $c = \sqrt{k \cdot R \cdot T}$   $c = 300 \frac{\text{m}}{\text{s}}$   $V = M \cdot c$   $V = 195 \frac{\text{m}}{\text{s}}$

b) Assuming incompressibility

Here the Bernoulli equation applies in the form 
$$\frac{p}{\rho} + \frac{V^2}{2} = \frac{p_0}{\rho} \quad \text{so} \quad V = \sqrt{\frac{2 \cdot (p_0 - p)}{\rho}}$$

For the density 
$$\rho = \frac{p}{R \cdot T} \quad \rho = 0.412 \frac{\text{kg}}{\text{m}^3} \quad V = \sqrt{\frac{2 \cdot (p_0 - p)}{\rho}}$$

Hence 
$$V = 205 \frac{\text{m}}{\text{s}}$$

In this case the error at  $M = 0.65$  in computing the speed of the aircraft using Bernoulli equation is 
$$\frac{205 - 195}{195} = 5.13\%$$

## Problem 12.68

[Difficulty: 1]

**12.68** The Anglo-French Concorde supersonic transport cruised at  $M = 2.2$  at 20 km altitude. Evaluate the speed of sound, aircraft flight speed, and Mach angle. What was the maximum air temperature at stagnation points on the aircraft structure?

Solution:

At  $z = 20 \text{ km}$ ,  $T = 216.7 \text{ K}$  (Table A.3).

$$c = (\gamma RT)^{1/2} = \left[ 1.4 \times 286.9 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 216.7 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right]^{1/2} = 295 \text{ m/s} \quad \leftarrow c$$

$$V = Mc = 2.2 \times 295 \text{ m/s} = 649 \text{ m/s} \quad \leftarrow V$$

$$\alpha = \sin^{-1}\left(\frac{1}{M}\right) = \sin^{-1}\left(\frac{1}{2.2}\right) = 27.0^\circ \quad \leftarrow \alpha$$

$$T_0 = T \left(1 + \frac{\gamma-1}{2} M^2\right) = 216.7 \text{ K} \left[1 + \frac{1.4-1}{2} (2.2)^2\right] = 426 \text{ K} \quad \leftarrow T_0$$

## Problem 12.69

[Difficulty: 2]

**12.69** Modern high-speed aircraft use “air data computers” to compute air speed from measurement of the difference between the stagnation and static pressures. Plot, as a function of actual Mach number  $M$ , for  $M = 0.1$  to  $M = 0.9$ , the percentage error in computing the Mach number assuming incompressibility (i.e., using the Bernoulli equation), from this pressure difference. Plot the percentage error in speed, as a function of speed, of an aircraft cruising at 12 km altitude, for a range of speeds corresponding to the actual Mach number ranging from  $M = 0.1$  to  $M = 0.9$ .

**Given:** Flight altitude of high-speed aircraft

**Find:** Mach number and aircraft speed errors assuming incompressible flow; plot

**Solution:**

The governing equation for pressure change is: 
$$\frac{p_0}{p} = \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}} \quad (12.20a)$$

Hence 
$$\Delta p = p_0 - p = p \cdot \left( \frac{p_0}{p} - 1 \right) \quad \Delta p = p \cdot \left[ \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}} - 1 \right] \quad (1)$$

For each Mach number the actual pressure change can be computed from Eq. 1

Assuming incompressibility, the Bernoulli equation applies in the form 
$$\frac{p}{\rho} + \frac{V^2}{2} = \frac{p_0}{\rho} \quad \text{so} \quad V = \sqrt{\frac{2 \cdot (p_0 - p)}{\rho}} = \sqrt{\frac{2 \cdot \Delta p}{\rho}}$$

and the Mach number based on this is 
$$M_{\text{incomp}} = \frac{V}{c} = \frac{\sqrt{\frac{2 \cdot \Delta p}{\rho}}}{\sqrt{k \cdot R \cdot T}} = \sqrt{\frac{2 \cdot \Delta p}{k \cdot \rho \cdot R \cdot T}}$$

Using Eq. 1 
$$M_{\text{incomp}} = \sqrt{\frac{2}{k} \cdot \left[ \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}} - 1 \right]}$$

The error in using Bernoulli to estimate the Mach number is 
$$\frac{\Delta M}{M} = \frac{M_{\text{incomp}} - M}{M}$$

For errors in speed:

Actual speed: 
$$V = M \cdot c \quad V = M \cdot \sqrt{k \cdot R \cdot T}$$

Speed assuming incompressible flow: 
$$V_{\text{inc}} = M_{\text{incomp}} \cdot \sqrt{k \cdot R \cdot T}$$

The error in using Bernoulli to estimate the speed from the pressure difference is 
$$\frac{\Delta V}{V} = \frac{V_{\text{incomp}} - V}{V}$$

The computations and plots are shown below, generated using *Excel*:



The given or available data is:

$R = 286.9 \text{ J/kg}\cdot\text{K}$   
 $k = 1.4$   
 $T = 216.7 \text{ K}$  (At 12 km, Table A.3)

Computed results:

$c = 295 \text{ m/s}$

$M$	$M_{\text{incomp}}$	$\Delta M/M$	$V \text{ (m/s)}$	$V_{\text{incomp}} \text{ (m/s)}$	$\Delta V/V$
0.1	0.100	0.13%	29.5	29.5	0.13%
0.2	0.201	0.50%	59.0	59.3	0.50%
0.3	0.303	1.1%	88.5	89.5	1.1%
0.4	0.408	2.0%	118	120	2.0%
0.5	0.516	3.2%	148	152	3.2%
0.6	0.627	4.6%	177	185	4.6%
0.7	0.744	6.2%	207	219	6.2%
0.8	0.865	8.2%	236	255	8.2%
0.9	0.994	10.4%	266	293	10.4%



## Problem 12.70

[Difficulty: 2]

**12.70** A supersonic wind tunnel test section is designed to have  $M = 2.5$  at  $15^\circ\text{C}$  and  $35\text{ kPa}$  (abs). The fluid is air. Determine the required inlet stagnation conditions,  $T_0$  and  $p_0$ . Calculate the required mass flow rate for a test section area of  $0.175\text{ m}^2$ .

**Given:** Wind tunnel at  $M = 2.5$

**Find:** Stagnation conditions; mass flow rate

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$

Given or available data       $M = 2.5$        $T = (15 + 273) \cdot \text{K}$        $p = 35 \cdot \text{kPa}$        $A = 0.175 \cdot \text{m}^2$

$k = 1.4$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

Then       $T_0 = T \cdot \left(1 + \frac{k-1}{2} \cdot M^2\right)$        $T_0 = 648\text{ K}$        $T_0 = 375 \cdot ^\circ\text{C}$

Also       $p_0 = p \cdot \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p_0 = 598 \cdot \text{kPa}$

The mass flow rate is given by       $m_{\text{rate}} = \rho \cdot A \cdot V$

We need       $c = \sqrt{k \cdot R \cdot T}$        $c = 340 \frac{\text{m}}{\text{s}}$        $V = M \cdot c$        $V = 850 \frac{\text{m}}{\text{s}}$

and also       $\rho = \frac{p}{R \cdot T}$        $\rho = 0.424 \frac{\text{kg}}{\text{m}^3}$

Then       $m_{\text{rate}} = \rho \cdot A \cdot V$        $m_{\text{rate}} = 63.0 \frac{\text{kg}}{\text{s}}$

### Problem 12.71

[Difficulty: 2]

**12.71** Air flows steadily through a length (① denotes inlet and ② denotes exit) of insulated constant-area duct. Properties change along the duct as a result of friction.

(a) Beginning with the control volume form of the first law of thermodynamics, show that the equation can be reduced to

$$h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2} = \text{constant}$$


(b) Denoting the constant by  $h_0$  (the stagnation enthalpy), show that for adiabatic flow of an ideal gas with friction

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$$

(c) For this flow does  $T_{01} = T_{02}$ ?  $p_{01} = p_{02}$ ? Explain these results.

Solution: Apply the energy equation to the CV shown:

$$\text{BE } \dot{Q} + \dot{W}_s + \dot{W}_{\text{shear}} = \frac{\partial}{\partial t} \int_{CV} \rho p dV + \int_{CS} (\rho p \vec{v}) \cdot \vec{dA}$$



- Assumptions:
- (1)  $\dot{Q} = 0$  (adiabatic)
  - (2)  $\dot{W}_s = 0$
  - (3)  $\dot{W}_{\text{shear}} = 0$
  - (4) steady flow
  - (5) Uniform flow at each section
  - (6) Neglect  $\Delta z$

Then

$$0 = (u_1 + p_1 v_1 + \frac{V_1^2}{2}) \{-\rho_1 v_1 A\} + (u_2 + p_2 v_2 + \frac{V_2^2}{2}) \{\rho_2 v_2 A\}$$

But  $h \equiv u + pv$ , and  $|\rho_1 v_1 A| = |\rho_2 v_2 A| = |\rho v A| = \dot{m}$ , so

$$h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2} = h + \frac{V^2}{2} = h_0 = \text{constant}$$


Assumption (7) Ideal gas;  $h_0 - h = C_p(T_0 - T)$ ,  $C_p = \frac{kR}{k-1}$ ,  $C^2 = kRT$

Thus  $C_p T_0 = C_p T + \frac{V^2}{2}$

$$\frac{T_0}{T} = 1 + \frac{V^2}{2C_p T} = 1 + \frac{(k-1)V^2}{2kRT} = 1 + \frac{k-1}{2} \frac{V^2}{C^2} = 1 + \frac{k-1}{2} M^2$$

From the energy equation,  $T_{01} = T_{02} = T_0 = \text{constant}$

The  $T_0$  diagram is



Since flow is frictional,  $x_2 > x_1$ . Therefore  $p_{02} < p_{01}$

## Problem 12.72

[Difficulty: 3]

**12.72** A new design for a supersonic transport is tested in a wind tunnel at  $M = 1.8$ . Air is the working fluid. The stagnation temperature and pressure for the wind tunnel are 200 psia and 500°F, respectively. The model wing area is 100 in<sup>2</sup>. The measured lift and drag are 12,000 lbf and 1600 lbf, respectively. Find the lift and drag coefficients.

**Given:** Wind tunnel test of supersonic transport

**Find:** Lift and drag coefficients

**Solution:**

Basic equations:	$c = \sqrt{k \cdot R \cdot T}$	$M = \frac{V}{c}$	$\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$	$\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$	
	$C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$	$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$			
Given or available data	$M = 1.8$	$T_0 = (500 + 460) \cdot R$	$p_0 = 200 \cdot \text{psi}$	$F_L = 12000 \cdot \text{lbf}$	$F_D = 1600 \cdot \text{lbf}$
	$A = 100 \cdot \text{in}^2$	$k = 1.4$	$R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot R}$		
We need local conditions	$p = p_0 \cdot \left(1 + \frac{k-1}{2} \cdot M^2\right)^{-\frac{k}{k-1}}$	$T = \frac{T_0}{1 + \frac{k-1}{2} \cdot M^2}$	$p = 34.8 \cdot \text{psi}$	$T = 583 \cdot R$	$T = 123 \cdot ^\circ\text{F}$
Then	$c = \sqrt{k \cdot R_{\text{air}} \cdot T}$	$V = M \cdot c$	$c = 1183 \cdot \frac{\text{ft}}{\text{s}}$	$V = 2129 \cdot \frac{\text{ft}}{\text{s}}$	$c = 807 \cdot \text{mph}$
and	$\rho = \frac{p}{R_{\text{air}} \cdot T}$	$C_L = \frac{F_L}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$	$\rho = 0.00501 \cdot \frac{\text{slug}}{\text{ft}^3}$	$C_L = 1.52$	
We also need	$C_D = \frac{F_D}{\frac{1}{2} \cdot \rho \cdot V^2 \cdot A}$	$C_D = 0.203$			
Finally					

## Problem 12.73

[Difficulty: 2]

**12.73** For aircraft flying at supersonic speeds, lift and drag coefficients are functions of Mach number only. A supersonic transport with wingspan of 75 m is to fly at 780 m/s at 20 km altitude on a standard day. Performance of the aircraft is to be measured from tests of a model with 0.9 m wingspan in a supersonic wind tunnel. The wind tunnel is to be supplied from a large reservoir of compressed air, which can be heated if desired. The static temperature of air in the test section is to be 10°C to avoid freezing of moisture. At what air speed should the wind tunnel tests be run to duplicate the Mach number of the prototype? What must be the stagnation temperature in the reservoir? What pressure is required in the reservoir if the test section pressure is to be 10 kPa (abs)?

Solution:

$$\text{At } z = 20 \text{ km}, T = 216.7 \text{ K} \quad (\text{Table A.3}).$$

$$c = (kRT)^{1/2} = \left( 1.4 \times 286.9 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 216.7 \text{ K} \times \frac{0.9 \text{ m}}{0.9 \text{ m}} \right)^{1/2} = 295 \text{ m/s}$$

$$\text{Thus for aircraft, } M = \frac{V}{c} = \frac{780}{295} = 2.64$$

This Mach number must be duplicated in the model test. In the tunnel,

$$c = (kRT)^{1/2} = \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 283 \text{ K} \times \frac{0.9 \text{ m}}{0.9 \text{ m}} \right)^{1/2} = 337 \text{ m/s}$$

$$\therefore V = Mc = 2.64 (337 \text{ m/s}) = 890 \text{ m/s}$$

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2 \quad \therefore T_0 = T \left( 1 + \frac{k-1}{2} M^2 \right)$$

$$T_0 = 283 \text{ K} \left[ 1 + \frac{(1.4-1)}{2} (2.64)^2 \right] = 677 \text{ K}$$

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad \therefore p_0 = p \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$

$$p_0 = 10 \text{ kPa} \left[ 1 + 0.2 (2.64)^2 \right]^{3.5} = 212 \text{ kPa}$$



## Problem 12.74

[Difficulty: 2]

**12.74** Actual performance characteristics of the Lockheed SR-71 "Blackbird" reconnaissance aircraft were classified. However, it was thought to cruise at  $M = 3.3$  at 26 km altitude. Calculate the aircraft flight speed for these conditions. Determine the local isentropic stagnation pressure. Because the aircraft speed is supersonic, a normal shock occurs in front of a total-head tube. The stagnation pressure decreases by 74.7 percent across the shock. Evaluate the stagnation pressure sensed by a probe on the aircraft. What is the maximum air temperature at stagnation points on the aircraft structure?

Solution:

At altitude  $z = 26 \text{ km}$ ,  $T = 222.5 \text{ K}$ ,  $p/p_{s_0} = 0.0216$  (Table A.2).

$$c = (\gamma RT)^{1/2} = \left[ 1.4 \times 286.9 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 222.5 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right]^{1/2} = 299 \text{ m/s}$$

$$V = Mc = 3.3 \times 299 \text{ m/s} = 987 \text{ m/s}$$

The stagnation pressure ahead of the shock (designated  $p_{0_1}$ ) is given by

$$p_{0_1} = p \left[ 1 + \frac{\gamma-1}{2} M^2 \right]^{\frac{\gamma}{\gamma-1}} = 0.0216 p_{s_0} \left[ 1 + \frac{\gamma-1}{2} M^2 \right]^{\frac{\gamma}{\gamma-1}}$$

$$p_{0_1} = 0.0216 \times 101.3 \text{ kPa} \left[ 1 + \frac{(1.4-1)}{2} (3.3)^2 \right]^{\frac{1.4}{0.4}} = 125 \text{ kPa} \quad \leftarrow p_{0_1}$$

Designating the stagnation pressure behind the shock as  $p_{0_2}$ , then

$$\frac{p_{0_1} - p_{0_2}}{p_{0_1}} = 0.747 \quad \text{or} \quad p_{0_2} = p_{0_1} - 0.747 p_{0_1} = 0.253 p_{0_1}$$

$$p_{0_2} = 0.253 \times 125 \text{ kPa} = 31.6 \text{ kPa} \quad \leftarrow p_{0_2}$$

The stagnation temperature does not change across a shock.

$$T_0 = T \left[ 1 + \frac{\gamma-1}{2} M^2 \right] = 222.5 \text{ K} \left[ 1 + \frac{(1.4-1)}{2} (3.3)^2 \right] = 707 \text{ K} \quad \leftarrow T_0$$

## Problem 12.75

[Difficulty: 2]

**12.75** The NASA X-43A Hyper-X experimental vehicle traveled at  $M = 9.68$  at an altitude of 110,000 ft. Calculate the flight speed for these conditions. Determine the local stagnation pressure. Because the aircraft speed is supersonic, a normal shock wave occurs in front of a total-head tube. However, the shock wave results in a stagnation pressure decrease of 99.6 percent. Evaluate the stagnation pressure sensed by a probe on the aircraft. What is the maximum air temperature at stagnation points on the aircraft structure?

**Given:** Data on air flow in a duct

**Find:** Stagnation pressures and temperatures; explain velocity increase; isentropic or not?

**Solution:**

The data provided, or available in the Appendices, is:

$$R_{\text{air}} = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad k = 1.4 \quad M = 9.68 \quad p_{\text{SL}} = 101.3 \cdot \text{kPa} \quad \rho_{\text{SL}} = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$$

At altitude:  $z = 110000 \cdot \text{ft} \quad z = 33528 \text{ m} \quad T_1 = 226.5 \cdot \text{K} + (250.4 \cdot \text{K} - 226.5 \cdot \text{K}) \cdot \frac{33528 - 30000}{40000 - 30000} \quad T_1 = 234.9 \text{ K}$

$$p_1 = p_{\text{SL}} \cdot \left[ 0.01181 + (0.002834 - 0.01181) \cdot \frac{33528 - 30000}{40000 - 30000} \right] \quad p_1 = 0.8756 \cdot \text{kPa}$$

The sound speed is:  $c = \sqrt{k \cdot R_{\text{air}} \cdot T_1} = 307.239 \frac{\text{m}}{\text{s}}$  so the flight speed is:  $V = M \cdot c = 2974 \frac{\text{m}}{\text{s}} \quad V = 9757 \cdot \frac{\text{ft}}{\text{s}}$

So the stagnation temperature and pressure are:  $T_{01} = T_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right) \quad T_{01} = 4638 \text{ K} \quad T_{01} = 8348 \cdot \text{R}$

$$p_{01} = p_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}} \quad p_{01} = 29.93 \cdot \text{MPa}$$

As the air passes through the shock wave, stagnation pressure decreases:  $p_{02} = p_{01} \cdot (1 - 0.996)$

Therefore, the total head probe sees a pressure of  $p_{02} = 119.7 \cdot \text{kPa}$

Since there is no heat transfer through the shock wave, the stagnation temperature remains the same:  $T_{02} = T_{01}$

$T_{02} = 8348 \cdot \text{R}$

## Problem 12.76

[Difficulty: 2]

**12.76** Air flows in an insulated duct. At point ① the conditions are  $M_1 = 0.1$ ,  $T_1 = 20^\circ\text{C}$ , and  $p_1 = 1.0$  MPa (abs). Downstream, at point ②, because of friction the conditions are  $M_2 = 0.7$ ,  $T_2 = -5.62^\circ\text{C}$ , and  $p_2 = 136.5$  kPa (abs). (Four significant figures are given to minimize roundoff errors.) Compare the stagnation temperatures at points ① and ②, and explain the result. Compute the stagnation pressures at points ① and ②. Can you explain how it can be that the velocity *increases* for this frictional flow? Should this process be isentropic or not? Justify your answer by computing the change in entropy between points ① and ②. Plot static and stagnation state points on a  $Ts$  diagram.

**Given:** Data on air flow in a duct

**Find:** Stagnation pressures and temperatures; explain velocity increase; isentropic or not?

**Solution:**

The data provided, or available in the Appendices, is:

$$R = 287 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad c_p = 1004 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}} \quad k = 1.4$$

$$M_1 = 0.1 \quad T_1 = (20 + 273)\cdot\text{K} \quad p_1 = 1000\cdot\text{kPa} \quad M_2 = 0.7 \quad T_2 = (-5.62 + 273)\cdot\text{K} \quad p_2 = 136.5\cdot\text{kPa}$$

For stagnation temperatures:  $T_{01} = T_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)$   $T_{01} = 293.6$  K  $T_{01} = 20.6$  C

$$T_{02} = T_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right) \quad T_{02} = 293.6$$
 K  $T_{02} = 20.6$  C

(Because the stagnation temperature is constant, the process is adiabatic)

For stagnation pressures:  $p_{01} = p_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)^{\frac{k}{k-1}}$   $p_{01} = 1.01$  MPa

$$p_{02} = p_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)^{\frac{k}{k-1}} \quad p_{02} = 189$$
 kPa

The entropy change is:  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$   $\Delta s = 480 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}}$

Note that  $V_1 = M_1 \cdot \sqrt{k \cdot R \cdot T_1}$   $V_1 = 34.3$   $\frac{\text{m}}{\text{s}}$   $V_2 = M_2 \cdot \sqrt{k \cdot R \cdot T_2}$   $V_2 = 229$   $\frac{\text{m}}{\text{s}}$

Although there is friction, suggesting the flow should decelerate, because the static pressure drops so much, the net effect is flow acceleration!

The entropy increases because the process is adiabatic but irreversible (friction).

From the second law of thermodynamics  $ds \geq \frac{\delta q}{T}$ : becomes  $ds > 0$

## Problem 12.77

[Difficulty: 2]

**12.77** Air is cooled as it flows without friction at a rate of 0.05 kg/s in a duct. At point ① the conditions are  $M_1 = 0.5$ ,  $T_1 = 500^\circ\text{C}$ , and  $p_1 = 500\text{ kPa (abs)}$ . Downstream, at point ②, the conditions are  $M_2 = 0.2$ ,  $T_2 = -18.57^\circ\text{C}$ , and  $p_2 = 639.2\text{ kPa (abs)}$ . (Four significant figures are given to minimize roundoff errors.) Compare the stagnation temperatures at points ① and ②, and explain the result. Compute the rate of cooling. Compute the stagnation pressures at points ① and ②. Should this process be isentropic or not? Justify your answer by computing the change in entropy between points ① and ②. Plot static and stagnation state points on a  $Ts$  diagram.

**Given:** Data on air flow in a duct

**Find:** Stagnation temperatures; explain; rate of cooling; stagnation pressures; entropy change

**Solution:**

The data provided, or available in the Appendices, is:  $R = 287 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}}$        $c_p = 1004 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}}$        $k = 1.4$

$$T_1 = (500 + 273)\cdot\text{K} \quad p_1 = 500\cdot\text{kPa} \quad T_2 = (-18.57 + 273)\cdot\text{K} \quad p_2 = 639.2\cdot\text{kPa}$$

$$M_1 = 0.5 \quad M_2 = 0.2 \quad M_{\text{rate}} = 0.05 \cdot \frac{\text{kg}}{\text{s}}$$

For stagnation temperatures:  $T_{01} = T_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)$        $T_{01} = 811.7\text{ K}$        $T_{01} = 539\cdot\text{C}$

$$T_{02} = T_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right) \quad T_{02} = 256.5\text{ K} \quad T_{02} = -16.5\cdot\text{C}$$

The fact that the stagnation temperature (a measure of total energy) decreases suggests cooling is taking place.

For the heat transfer:  $Q = M_{\text{rate}} \cdot c_p \cdot (T_{02} - T_{01})$        $Q = -27.9\cdot\text{kW}$

For stagnation pressures:  $p_{01} = p_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)^{\frac{k}{k-1}}$        $p_{01} = 593\cdot\text{kPa}$

$$p_{02} = p_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)^{\frac{k}{k-1}} \quad p_{02} = 657\cdot\text{kPa}$$

The entropy change is:  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$        $\Delta s = -1186 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}}$

The entropy decreases because the process is a cooling process ( $Q$  is negative).

From the second law of thermodynamics:  $ds \geq \frac{\delta q}{T}$  becomes  $ds \geq -ve$

Hence, if the process is reversible, the entropy must decrease; if it is irreversible, it may increase or decrease

# Problem 12.78

[Difficulty: 3]

**12.78** Consider steady, adiabatic flow of air through a long straight pipe with  $A = 0.05 \text{ m}^2$ . At the inlet (section ①) the air is at 200 kPa (abs),  $60^\circ\text{C}$ , and 146 m/s. Downstream at section ②, the air is at 95.6 kPa (abs) and 280 m/s. Determine  $p_{01}$ ,  $p_{02}$ ,  $T_{01}$ ,  $T_{02}$ , and the entropy change for the flow. Show static and stagnation state points on a  $Ts$  diagram.

Solution:

Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$        $\frac{P_0}{P} = \left[1 + \frac{k-1}{2} M^2\right]^{\frac{k}{k-1}}$

Basic equations:  $0 = \frac{\partial}{\partial t} \int_{cv} \rho dV + \int_{cs} \rho \vec{v} \cdot d\vec{A}$   
 $0 = \frac{\partial}{\partial t} \int_{cv} \rho e dV + \int_{cs} \left(e + \frac{P}{\rho}\right) \rho \vec{v} \cdot d\vec{A}$

- Assumptions: (1)  $\dot{Q} = 0$  (adiabatic flow)      (5) uniform flow at each section  
 (2)  $\dot{W}_e = 0$       (6)  $\Delta z = 0$   
 (3)  $\dot{W}_{shear} = 0$       (7) ideal gas,  $k = 1.4$   
 (4) steady flow      (8)  $A_1 = A_2 = A = \text{constant}$

$M_1 = \frac{V_1}{c_1}$        $c_1 = (kRT_1)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 333\text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 366 \text{ m/s}$

$M_1 = \frac{V_1}{c_1} = \frac{146}{366} = 0.399$        $T_{01} = T_1 \left[1 + \frac{k-1}{2} M_1^2\right] = 333\text{K} \left[1 + 0.2(0.399)^2\right] = 344\text{K} \leftarrow T_{01}$   
 $P_{01} = P_1 \left[1 + \frac{k-1}{2} M_1^2\right]^{\frac{k}{k-1}} = 200\text{kPa} \left[1 + 0.2(0.399)^2\right]^{3.5} = 223\text{kPa}$

From the energy equation,  $0 = (u_1 + P_1 v_1 + \frac{V_1^2}{2}) \{-\rho_1 V_1 A\} + (u_2 + P_2 v_2 + \frac{V_2^2}{2}) (\rho_2 V_2 A)$

From continuity,  $0 = -\rho_1 V_1 A + \rho_2 V_2 A$  or  $\rho_1 V_1 = \rho_2 V_2$

Then, using  $h = u + Pv$ ,  $h_1 + \frac{V_1^2}{2} = h_{01} = h_2 + \frac{V_2^2}{2} = h_{02}$  or  $h_{01} = h_{02}$

For an ideal gas with constant specific heats,  $T_{02} = T_{01} = 344\text{K} \leftarrow T_{02}$

From continuity,  $\rho_2 = \rho_1 \frac{V_1}{V_2} = \frac{P_2}{RT_2} \frac{V_1}{V_2} = \frac{200 \times 10^3 \text{ N}}{\text{m}^2} \times \frac{\text{kg}\cdot\text{K}}{287 \text{ N}\cdot\text{m}} \times \frac{1}{333\text{K}} \times \frac{146}{280} = 1.09 \text{ kg/m}^3$

Then,  $T_2 = \frac{P_2}{\rho_2 R} = \frac{95.6 \times 10^3 \text{ N}}{\text{m}^2} \times \frac{\text{m}^3}{1.09 \text{ kg}} \times \frac{\text{kg}\cdot\text{K}}{287 \text{ N}\cdot\text{m}} = 306\text{K} (33^\circ\text{C})$

$c_2 = (kRT_2)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 306\text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 351 \text{ m/s}$

$M_2 = \frac{V_2}{c_2} = \frac{280}{351} = 0.798$

$P_{02} = P_2 \left[1 + \frac{k-1}{2} M_2^2\right]^{\frac{k}{k-1}} = 95.6\text{kPa} \left[1 + 0.2(0.798)^2\right]^{3.5}$


$P_{02} = 145 \text{ kPa}$

$T ds = dh - v dp = c_p dT - \frac{RT}{P} dP$

$ds = c_p \frac{dT}{T} - R \frac{dP}{P} = ds_0 = -R \frac{dP}{P_0}$

$s_{02} - s_{01} = s_2 - s_1 = -R \ln \frac{P_{02}}{P_{01}}$

$s_2 - s_1 = -287 \frac{\text{J}}{\text{kg}\cdot\text{K}} \ln \frac{145}{223} = 0.124 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} \leftarrow s_2 - s_1$



## Problem 12.79

[Difficulty: 3]

**12.79** Air flows steadily through a constant-area duct. At section ①, the air is at 400 kPa (abs), 325 K, and 150 m/s. As a result of heat transfer and friction, the air at section ② downstream is at 275 kPa (abs), 450 K. Calculate the heat transfer per kilogram of air between sections ① and ②, and the stagnation pressure at section ②.

**Given:** Air flow in duct with heat transfer and friction

**Find:** Heat transfer; Stagnation pressure at location 2

**Solution:**

Basic equations:  $c = \sqrt{k \cdot R \cdot T}$        $M = \frac{V}{c}$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$

$$\rho \cdot V \cdot A = \text{const} \quad h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$$

Given or available data     $p_1 = 400 \cdot \text{kPa}$        $T_1 = 325 \cdot \text{K}$        $V_1 = 150 \cdot \frac{\text{m}}{\text{s}}$

$$p_2 = 275 \cdot \text{kPa} \quad T_2 = 450 \cdot \text{K}$$

$$c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad k = 1.4 \quad R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$$

Then       $\rho_1 = \frac{p_1}{R \cdot T_1}$        $\rho_1 = 4.29 \frac{\text{kg}}{\text{m}^3}$        $\rho_2 = \frac{p_2}{R \cdot T_2}$        $\rho_2 = 2.13 \frac{\text{kg}}{\text{m}^3}$

and from       $\rho \cdot V \cdot A = \text{const}$        $V_2 = V_1 \cdot \frac{\rho_1}{\rho_2}$        $V_2 = 302 \frac{\text{m}}{\text{s}}$

Also       $\frac{\delta Q}{dm} = q = h_2 - h_1 + \frac{V_2^2 - V_1^2}{2}$

$$q = c_p \cdot (T_2 - T_1) + \frac{V_2^2 - V_1^2}{2} \quad q = 160 \cdot \frac{\text{kJ}}{\text{kg}}$$

We also have       $c_2 = \sqrt{k \cdot R \cdot T_2}$        $c_2 = 425 \frac{\text{m}}{\text{s}}$        $M_2 = \frac{V_2}{c_2}$        $M_2 = 0.711$

Hence       $p_{02} = p_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)^{\frac{k}{k-1}}$        $p_{02} = 385 \cdot \text{kPa}$

## Problem 12.80

[Difficulty: 2]

**12.80** The combustion process in a ramjet engine is modeled as simple heat addition to air in a frictionless duct. Consider such a combustor, with air flowing at a rate of 0.1 lbm/s. At point ① the conditions are  $M_1 = 0.2$ ,  $T_1 = 600^\circ\text{F}$ , and  $p_1 = 7$  psia. Downstream, at point ②, the conditions are  $M_2 = 0.9$ ,  $T_2 = 1890^\circ\text{F}$ , and  $p_2 = 4.1$  psia. Compare the stagnation temperatures at points ① and ②, and explain the result. Compute the rate of heat addition to the flow. Compute the stagnation pressures at points ① and ②. Should this process be isentropic or not? Justify your answer by computing the change in entropy between points ① and ②. Plot static and stagnation state points on a  $Ts$  diagram.

**Given:** Data on air flow in a ramjet combustor

**Find:** Stagnation pressures and temperatures; isentropic or not?

**Solution:**

The data provided, or available in the Appendices, is:

$$R_{\text{air}} = 53.33 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \quad c_p = 0.2399 \frac{\text{BTU}}{\text{lbm} \cdot \text{R}} \quad k = 1.4 \quad M_{\text{rate}} = 0.1 \frac{\text{lbm}}{\text{s}}$$

$$M_1 = 0.2 \quad T_1 = (600 + 460) \cdot \text{R} \quad p_1 = 7 \cdot \text{psi} \quad M_2 = 0.9 \quad T_2 = (1890 + 460) \cdot \text{R} \quad p_2 = 4.1 \cdot \text{psi}$$

For stagnation temperatures:  $T_{01} = T_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)$   $T_{01} = 1068.5 \cdot \text{R}$   $T_{01} = 608.8 \cdot ^\circ\text{F}$

$$T_{02} = T_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right) \quad T_{02} = 2730.7 \cdot \text{R} \quad T_{02} = 2271 \cdot ^\circ\text{F}$$


Since we are modeling heat addition, the stagnation temperature should increase.

The rate of heat addition is:  $Q = M_{\text{rate}} \cdot c_p \cdot (T_{02} - T_{01})$   $Q = 39.9 \frac{\text{BTU}}{\text{s}}$

For stagnation pressures:  $p_{01} = p_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)^{\frac{k}{k-1}} = 7.20 \text{ psi}$   $p_{02} = p_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)^{\frac{k}{k-1}} = 6.93 \text{ psi}$

The entropy change is:  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{air}} \cdot \ln\left(\frac{p_2}{p_1}\right) = 0.228 \frac{\text{BTU}}{\text{lbm} \cdot \text{R}}$

The entropy increases because heat is being added. Here is a  $Ts$  diagram of the process:



## Problem 12.81

[Difficulty: 2]

**12.81** Let us revisit the ramjet combustor in Problem 12.80. To more accurately model the flow, we now include the effects of friction in the duct. Once the effects of friction have been included, we find that the conditions at state ② are now  $M_2 = 0.9$ ,  $T_2 = 1660^\circ\text{F}$ , and  $p_2 = 1.6$  psia. Recalculate the heat transfer per pound of air between sections ① and ②, and the stagnation pressure at section ②.

**Given:** Data on air flow in a ramjet combustor

**Find:** Stagnation pressures and temperatures; isentropic or not?

**Solution:**

The data provided, or available in the Appendices, is:

$$R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \quad c_p = 0.2399 \cdot \frac{\text{BTU}}{\text{lbm} \cdot \text{R}} \quad k = 1.4 \quad M_{\text{rate}} = 0.1 \cdot \frac{\text{lbm}}{\text{s}}$$

$$M_1 = 0.2 \quad T_1 = (600 + 460) \cdot \text{R} \quad p_1 = 7 \cdot \text{psi} \quad M_2 = 0.9 \quad T_2 = (1660 + 460) \cdot \text{R} \quad p_2 = 1.6 \cdot \text{psi}$$

For stagnation temperatures:  $T_{01} = T_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)$   $T_{01} = 1068.5 \cdot \text{R}$   $T_{01} = 608.8 \cdot ^\circ\text{F}$

$$T_{02} = T_2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_2^2 \right) \quad T_{02} = 2463.4 \cdot \text{R} \quad T_{02} = 2003.8 \cdot ^\circ\text{F}$$

The rate of heat addition is:  $Q = M_{\text{rate}} \cdot c_p \cdot (T_{02} - T_{01})$   $Q = 33.5 \cdot \frac{\text{BTU}}{\text{s}}$

For stagnation pressures:  $p_{01} = p_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)^{\frac{k}{k-1}}$   $p_{01} = 7.20 \cdot \text{psi}$

$$p_{02} = p_2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_2^2 \right)^{\frac{k}{k-1}} \quad p_{02} = 2.71 \cdot \text{psi}$$

The entropy change is:  $\Delta s = c_p \cdot \ln \left( \frac{T_2}{T_1} \right) - R_{\text{air}} \cdot \ln \left( \frac{p_2}{p_1} \right)$   $\Delta s = 0.267 \cdot \frac{\text{BTU}}{\text{lbm} \cdot \text{R}}$

The friction has increased the entropy increase across the duct, even though the heat addition has decreased.



## Problem 12.83

[Difficulty: 2]

**12.83** Air enters a turbine at  $M_1 = 0.4$ ,  $T_1 = 1250^\circ\text{C}$ , and  $p_1 = 625$  kPa (abs). Conditions leaving the turbine are  $M_2 = 0.8$ ,  $T_2 = 650^\circ\text{C}$ , and  $p_2 = 20$  kPa (abs). Evaluate local isentropic stagnation conditions (a) at the turbine inlet and (b) at the turbine outlet. Calculate the change in specific entropy across the turbine. Plot static and stagnation state points on a  $Ts$  diagram.

**Given:** Air flow through turbine

**Find:** Stagnation conditions at inlet and exit; change in specific entropy; Plot on  $Ts$  diagram

**Solution:**

Basic equations: 
$$\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}} \qquad \frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2 \qquad \Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$$

Given or available data  $M_1 = 0.4$   $p_1 = 625$  kPa  $T_1 = (1250 + 273) \cdot \text{K}$

$M_2 = 0.8$   $p_2 = 20$  kPa  $T_2 = (650 + 273) \cdot \text{K}$

$c_p = 1004 \frac{\text{J}}{\text{kg} \cdot \text{K}}$   $k = 1.4$   $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$


Then  $T_{01} = T_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)$   $T_{01} = 1572 \text{K}$   $T_{01} = 1299^\circ\text{C}$

$p_{01} = p_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)^{\frac{k}{k-1}}$   $p_{01} = 698$  kPa

$T_{02} = T_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)$   $T_{02} = 1041 \text{K}$   $T_{02} = 768^\circ\text{C}$

$p_{02} = p_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)^{\frac{k}{k-1}}$   $p_{02} = 30$  kPa

$\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$   $\Delta s = 485 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$



## Problem 12.84

[Difficulty: 3]


**12.84** A Boeing 747 cruises at  $M=0.87$  at an altitude of 13 km on a standard day. A window in the cockpit is located where the external flow Mach number is 0.2 relative to the plane surface. The cabin is pressurized to an equivalent altitude of 2500 m in a standard atmosphere. Estimate the pressure difference across the window. Be sure to specify the direction of the net pressure force.

Solution: Apply isentropic stagnation relations.

Computing equation:  $p_0 = p \left(1 + \frac{k-1}{2} M^2\right)^{k/k-1}$

Assumptions: (1) Ideal gas  
(2) Isentropic flow

Consider observer on aircraft: air is decelerated isentropically from  $M_{\infty} = 0.87$  to  $M = 0.2$ .



From Table A.3:

Calculated:  $p = \left(\frac{p}{p_0}\right) p_0$

$p_0 = 101.3 \text{ kPa}$

Altitude (km)	$p/p_0$ (---)	$p$ (kPa)
2.5	0.7372	74.7
13.0	0.1636	16.6

For isentropic stagnation:

$$p_0 = p_{\infty} \left(1 + \frac{k-1}{2} M_{\infty}^2\right)^{k/k-1} = 16.6 \text{ kPa} \left(1 + \frac{1.4-1}{2} (0.87)^2\right)^{3.5} = 27.2 \text{ kPa (abs)}$$

From stagnation to  $M=0.2$ :


$$p_{out} = \frac{p_0}{\left(1 + \frac{k-1}{2} M^2\right)^{k/k-1}} = \frac{27.2 \text{ kPa}}{\left(1 + 0.2(0.2)^2\right)^{3.5}} = 26.5 \text{ kPa (abs)}$$

Pressure difference across window is:

$$\Delta p = p_{in} - p_{out} = (74.7 - 26.5) \text{ kPa} = 48.2 \text{ kPa}$$

{ Inside pressure is higher; window force is toward outside. }

The corresponding Ts diagram is:



## Problem 12.85

[Difficulty: 2]

**12.85** If a window of the cockpit in Problem 12.84 develops a tiny leak the air will start to rush out at critical speed. Find the mass flow rate if the leak area is  $1 \text{ mm}^2$ .

**Given:** Air flow leak in window of airplane

**Find:** Mass flow rate

**Solution:**

Basic equations:  $m_{\text{rate}} = \rho \cdot V \cdot A$        $V_{\text{crit}} = \sqrt{\frac{2 \cdot k}{k + 1} \cdot R \cdot T_0}$        $\frac{\rho_0}{\rho_{\text{crit}}} = \left(\frac{k + 1}{2}\right)^{\frac{1}{k-1}}$

The interior conditions are the stagnation conditions for the flow

Given or available data     $T_0 = 271.9 \cdot \text{K}$        $\rho_{\text{SL}} = 1.225 \cdot \frac{\text{kg}}{\text{m}^3}$        $\rho_0 = 0.7812 \cdot \rho_{\text{SL}}$        $\rho_0 = 0.957 \cdot \frac{\text{kg}}{\text{m}^3}$

(Above data from Table A.3 at an altitude of 2500 m)

$A = 1 \cdot \text{mm}^2$        $c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $k = 1.4$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

Then       $\rho_{\text{crit}} = \frac{\rho_0}{\left(\frac{k + 1}{2}\right)^{\frac{1}{k-1}}}$        $\rho_{\text{crit}} = 0.607 \cdot \frac{\text{kg}}{\text{m}^3}$        $V_{\text{crit}} = \sqrt{\frac{2 \cdot k}{k + 1} \cdot R \cdot T_0}$        $V_{\text{crit}} = 302 \cdot \frac{\text{m}}{\text{s}}$

The mass flow rate is     $m_{\text{rate}} = \rho_{\text{crit}} \cdot V_{\text{crit}} \cdot A$        $m_{\text{rate}} = 1.83 \times 10^{-4} \cdot \frac{\text{kg}}{\text{s}}$

## Problem 12.86

[Difficulty: 2]

**12.86** Space debris impact is a real concern for spacecraft. If a piece of space debris were to create a hole of  $0.001 \text{ in.}^2$  area in the hull of the International Space Station (ISS), at what rate would air leak from the ISS? Assume that the atmosphere in the International Space Station (ISS) is air at a pressure of 14.7 psia and a temperature of  $65^\circ\text{F}$ .

**Given:** Air leak in ISS

**Find:** Mass flow rate

**Solution:**

Basic equations:  $m_{\text{rate}} = \rho \cdot V \cdot A$        $V_{\text{crit}} = \sqrt{\frac{2 \cdot k}{k + 1} \cdot R \cdot T_0}$        $\frac{\rho_0}{\rho_{\text{crit}}} = \left(\frac{k + 1}{2}\right)^{\frac{1}{k-1}}$

The interior conditions are the stagnation conditions for the flow

Given or available data     $T_0 = (65 + 460) \cdot R$      $p_0 = 14.7 \cdot \text{psi}$      $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot R}$      $k = 1.4$      $A = 0.001 \cdot \text{in}^2$

The density of air inside the ISS would be:     $\rho_0 = \frac{p_0}{R_{\text{air}} \cdot T_0}$        $\rho_0 = 2.35 \times 10^{-3} \cdot \frac{\text{slug}}{\text{ft}^3}$

Then       $\rho_{\text{crit}} = \frac{\rho_0}{\left(\frac{k + 1}{2}\right)^{\frac{1}{k-1}}}$        $\rho_{\text{crit}} = 1.49 \times 10^{-3} \cdot \frac{\text{slug}}{\text{ft}^3}$        $V_{\text{crit}} = \sqrt{\frac{2 \cdot k}{k + 1} \cdot R_{\text{air}} \cdot T_0}$        $V_{\text{crit}} = 1025 \cdot \frac{\text{ft}}{\text{s}}$

The mass flow rate is     $m_{\text{rate}} = \rho_{\text{crit}} \cdot V_{\text{crit}} \cdot A$        $m_{\text{rate}} = 1.061 \times 10^{-5} \cdot \frac{\text{slug}}{\text{s}}$        $m_{\text{rate}} = 3.41 \times 10^{-4} \cdot \frac{\text{lbm}}{\text{s}}$

## Problem 12.87

[Difficulty: 1]

**12.87** A CO<sub>2</sub> cartridge is used to propel a toy rocket. Gas in the cartridge is pressurized to 45 MPa (gage) and is at 25°C. Calculate the critical conditions (temperature, pressure, and flow speed) that correspond to these stagnation conditions.

Solution:

Computing equations:  $\frac{T}{T_0} = 1 + \frac{\gamma-1}{2} M^2$        $\frac{p}{p_0} = \left(1 + \frac{\gamma-1}{2} M^2\right)^{\frac{\gamma}{\gamma-1}}$

For CO<sub>2</sub>,  $\gamma = 1.29$ . At critical conditions,  $M = 1$

$$\frac{T}{T_0} = 1 + \frac{\gamma-1}{2} = 1.145 \quad \therefore T^* = \frac{T_0}{1.145} = \frac{298\text{K}}{1.145} = 260\text{K} \quad \leftarrow T^*$$

$$\frac{p}{p_0} = \left[1 + \frac{\gamma-1}{2}\right]^{\frac{\gamma}{\gamma-1}} = [1.145]^{4.448} = 1.826$$

$$\therefore p^* = \frac{p_0}{1.826} = \frac{45.101\text{ MPa}}{1.826} = 24.7\text{ MPa (abs)} \quad \leftarrow p^*$$

$$V^* = C^* = \left(\gamma R T^*\right)^{1/2} = \left(1.29 \times 189 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 260\text{K} \times \frac{10^3\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 252\text{ m/s} \quad \leftarrow V^*$$

## Problem 12.88

[Difficulty: 1]

**12.88** The gas storage reservoir for a high-speed wind tunnel contains helium at 3600° R and 725 psig. Calculate the critical conditions (temperature, pressure, and flow speed) that correspond to these stagnation conditions.

**Given:** Data on helium in reservoir

**Find:** Critical conditions

**Solution:**

The data provided, or available in the Appendices, is:

$$R_{\text{He}} = 386.1 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \quad k = 1.66$$

$$T_0 = 3600 \cdot \text{R}$$

$$p_0 = (725 + 14.7) \text{psi} \quad p_0 = 740 \cdot \text{psi}$$

For critical conditions

$$\frac{T_0}{T_{\text{crit}}} = \frac{k + 1}{2}$$

$$T_{\text{crit}} = \frac{T_0}{\frac{k+1}{2}}$$

$$T_{\text{crit}} = 2707 \cdot \text{R}$$

$$\frac{p_0}{p_{\text{crit}}} = \left( \frac{k + 1}{2} \right)^{\frac{k}{k-1}}$$

$$p_{\text{crit}} = \frac{p_0}{\left( \frac{k + 1}{2} \right)^{\frac{k}{k-1}}}$$

$$p_{\text{crit}} = 361 \cdot \text{psi} \quad \text{absolute}$$

$$V_{\text{crit}} = \sqrt{k \cdot R_{\text{He}} \cdot T_{\text{crit}}}$$

$$V_{\text{crit}} = 7471 \cdot \frac{\text{ft}}{\text{s}}$$

# Problem 12.89

[Difficulty: 1]

**12.89** Stagnation conditions in a solid propellant rocket motor are  $T_0 = 3000 \text{ K}$  and  $p_0 = 45 \text{ MPa}$  (gage). Critical conditions occur in the throat of the rocket nozzle where the Mach number is equal to one. Evaluate the temperature, pressure, and flow speed at the throat. Assume ideal gas behavior with  $R = 323 \text{ J/(kg}\cdot\text{K)}$  and  $k = 1.2$ .

Solution:

Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} M^2\right)^{\frac{k}{k-1}}$

Assume flow to throat is isentropic.

At throat,  $M = 1$

$$\therefore T_0 = T \left(1 + \frac{k-1}{2}\right) = 1.1 T \quad \therefore T = \frac{T_0}{1.1} = \frac{3000 \text{ K}}{1.1} = 2730 \text{ K} \quad \leftarrow T$$

$$\frac{p_0}{p} = \left(1 + \frac{k-1}{2}\right)^{\frac{k}{k-1}} = (1.1)^{\frac{1.2}{0.2}} = 1.7716$$

$$\therefore p = \frac{p_0}{1.7716} = \frac{45.101 \text{ MPa}}{1.7716} = 25.5 \text{ MPa (abs)} \quad \leftarrow p$$

$$v = (kRT)^{1/2} = \left[1.2 \cdot 323 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \cdot 2730 \text{ K} \cdot \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right]^{1/2} = 1020 \text{ m/s} \quad \leftarrow v$$

## Problem 12.90

[Difficulty: 1]

**12.90** The hot gas stream at the turbine inlet of a JT9-D jet engine is at 1500°C, 140 kPa (abs), and  $M = 0.32$ . Calculate the critical conditions (temperature, pressure, and flow speed) that correspond to these conditions. Assume the fluid properties of pure air.

**Given:** Data on hot gas stream

**Find:** Critical conditions

**Solution:**

The data provided, or available in the Appendices, is:

$$R = 287 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$$

$$k = 1.4$$

$$T_0 = (1500 + 273) \cdot \text{K}$$

$$T_0 = 1773 \text{K}$$

$$p_0 = 140 \text{ kPa}$$

For critical conditions

$$\frac{T_0}{T_{\text{crit}}} = \frac{k + 1}{2}$$

$$T_{\text{crit}} = \frac{T_0}{\frac{k + 1}{2}}$$

$$T_{\text{crit}} = 1478 \text{K}$$

$$\frac{p_0}{p_{\text{crit}}} = \left( \frac{k + 1}{2} \right)^{\frac{k}{k - 1}}$$

$$p_{\text{crit}} = \frac{p_0}{\left( \frac{k + 1}{2} \right)^{\frac{k}{k - 1}}}$$

$$p_{\text{crit}} = 74.0 \cdot \text{kPa}$$

absolute

$$V_{\text{crit}} = \sqrt{k \cdot R \cdot T_{\text{crit}}}$$

$$V_{\text{crit}} = 770 \frac{\text{m}}{\text{s}}$$

## Problem 12.91

[Difficulty: 1]

**12.91** Certain high-speed wind tunnels use combustion air heaters to generate the extreme pressures and temperatures required to accurately simulate flow at high Mach numbers. In one set of tests, a combustion air heater supplied stagnation conditions of 1.7 MPa and 1010 K. Calculate the critical pressure and temperature corresponding to these stagnation conditions.

**Given:** Data on air flow in a ramjet combustor

**Find:** Critical temperature and pressure at nozzle exit

**Solution:**

The data provided, or available in the Appendices, is:  $k = 1.4$   $p_0 = 1.7 \text{ MPa}$   $T_0 = 1010 \text{ K}$

The critical temperature and pressure are:

$$\frac{T_0}{T_{\text{crit}}} = \frac{k+1}{2} \quad T_{\text{crit}} = \frac{T_0}{\frac{k+1}{2}} \quad T_{\text{crit}} = 841.7 \text{ K}$$
$$\frac{p_0}{p_{\text{crit}}} = \left( \frac{k+1}{2} \right)^{\frac{k}{k-1}} \quad p_{\text{crit}} = \frac{p_0}{\left( \frac{k+1}{2} \right)^{\frac{k}{k-1}}} \quad p_{\text{crit}} = 0.898 \text{ MPa}$$

## Problem 12.92

[Difficulty: 1]

**12.92** The ramjet combustor exhaust from Problem 12.81 is accelerated through a nozzle to critical conditions. Calculate the temperature, pressure, and flow velocity at the nozzle exit. Assume fluid properties of pure air.

**Given:** Data on air flow in a ramjet combustor

**Find:** Critical temperature and pressure at nozzle exit

**Solution:**

The data provided, or available in the Appendices, is:  $k = 1.4$   $M_2 = 0.9$   $T_2 = (1660 + 460) \cdot R$   $p_2 = 1.6 \cdot \text{psi}$

Stagnation conditions are:  $T_{02} = T_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)$   $T_{02} = 2463.4 R$   $T_{02} = 2003.8^\circ F$

$$p_{02} = p_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)^{\frac{k}{k-1}} \quad p_{02} = 2.71 \cdot \text{psi}$$

The critical temperature and pressure are:

$$\frac{T_{02}}{T_{\text{crit}2}} = \frac{k+1}{2} \quad T_{\text{crit}2} = \frac{T_{02}}{\frac{k+1}{2}} \quad T_{\text{crit}2} = 2052.9 \cdot R \quad T_{\text{crit}2} = 1593.2^\circ F$$
$$\frac{p_{02}}{p_{\text{crit}2}} = \left(\frac{k+1}{2}\right)^{\frac{k}{k-1}} \quad p_{\text{crit}2} = \frac{p_{02}}{\left(\frac{k+1}{2}\right)^{\frac{k}{k-1}}} \quad p_{\text{crit}2} = 1.430 \cdot \text{psi}$$

## Problem 13.1

[Difficulty: 2]

**13.1** Air is extracted from a large tank in which the temperature and pressure are 70°C and 101 kPa (abs), respectively, through a nozzle. At one location in the nozzle the static pressure is 25 kPa and the diameter is 15 cm. What is the mass flow rate? Assume isentropic flow.

**Given:** Air extracted from a large tank

**Find:** Mass flow rate

**Solution:**

Basic equations:  $m_{\text{rate}} = \rho \cdot V \cdot A$        $h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2}$        $\frac{p}{\rho^k} = \text{const}$        $T \cdot p^{\frac{1-k}{k}} = \text{const}$

Given or available data       $T_0 = (70 + 273) \cdot \text{K}$        $p_0 = 101 \cdot \text{kPa}$        $p = 25 \cdot \text{kPa}$

$D = 15 \cdot \text{cm}$        $c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $k = 1.4$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

The mass flow rate is given by       $m_{\text{rate}} = \rho \cdot A \cdot V$        $A = \frac{\pi \cdot D^2}{4}$        $A = 0.0177 \text{ m}^2$

We need the density and velocity at the nozzle. In the tank       $\rho_0 = \frac{p_0}{R \cdot T_0}$        $\rho_0 = 1.026 \frac{\text{kg}}{\text{m}^3}$

From the isentropic relation       $\rho = \rho_0 \cdot \left(\frac{p}{p_0}\right)^{\frac{1}{k}}$        $\rho = 0.379 \frac{\text{kg}}{\text{m}^3}$

We can apply the energy equation between the tank (stagnation conditions) and the point in the nozzle to find the velocity

$h_0 = h + \frac{V^2}{2}$        $V = \sqrt{2 \cdot (h_0 - h)} = \sqrt{2 \cdot c_p \cdot (T_0 - T)}$


For T we again use isentropic relations       $T = T_0 \cdot \left(\frac{p_0}{p}\right)^{\frac{1-k}{k}}$        $T = 230.167 \text{ K}$        $T = -43.0 \cdot ^\circ\text{C}$

Then       $V = \sqrt{2 \cdot c_p \cdot (T_0 - T)}$        $V = 476 \frac{\text{m}}{\text{s}}$

The mass flow rate is       $m_{\text{rate}} = \rho \cdot A \cdot V$        $m_{\text{rate}} = 3.18 \frac{\text{kg}}{\text{s}}$

Note that the flow is supersonic at this point       $c = \sqrt{k} \cdot c = 304 \frac{\text{m}}{\text{s}}$        $M = \frac{V}{c}$        $M = 1.57$

Hence we must have a converging-diverging nozzle



### Problem 13.2

[Difficulty: 2]

13.2 Steam flows steadily and isentropically through a nozzle.

At an upstream section where the speed is negligible, the temperature and pressure are 900°F and 900 psia. At a section where the nozzle diameter is 0.188 in., the steam pressure is 600 psia. Determine the speed and Mach number at this section and the mass flow rate of steam. Sketch the passage shape.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2} = h_0 = \text{constant}$   
 $pAV = \text{constant} = \dot{m}$

- Assumptions:
- (1) steady flow
  - (2) isentropic flow
  - (3) uniform flow at a section
  - (4) superheated steam can be treated as an ideal gas,  $R = 85.8 \text{ ft}\cdot\text{lb}/\text{lbm}\cdot\text{R}$ ,  $k = 1.28$
  - (5)  $\Delta z = 0$

From steam tables for superheated vapor with  $T_0 = 900^\circ\text{F}$ ,  $p_0 = 900 \text{ psia}$ ,  
 $h_0 = 1451.8 \text{ Btu}/\text{lbm}$      $s_0 = 1.6257 \text{ Btu}/\text{lbm}\cdot\text{R}$

From steam tables for superheated vapor with  $s_1 = 1.6257 \text{ Btu}/\text{lbm}\cdot\text{R}$ ,  
 and  $p_1 = 600 \text{ psia}$ ,  
 $T_1 = 780^\circ\text{F}$      $h_1 = 1396.5 \text{ Btu}/\text{lbm}$ ,     $v_1 = 1.167 \text{ ft}^3/\text{lbm}$

From the first law,

$$V_2 = [2(h_0 - h_1)]^{1/2} = [2(1451.8 - 1396.5) \frac{\text{Btu}}{\text{lbm}} \times 778 \frac{\text{ft}\cdot\text{lb}}{\text{Btu}} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug}\cdot\text{ft}}{\text{lbm}\cdot\text{s}^2}]^{1/2}$$

$$V_2 = 1660 \text{ ft/s}$$

$$\dot{m} = pAV = \frac{1}{v} \pi \frac{D^2}{4} V = \frac{1 \text{ lbm}}{1.167 \text{ ft}^3} \times \frac{\pi}{4} \times \left(\frac{0.188}{12}\right)^2 \text{ ft}^2 \times 1660 \frac{\text{ft}}{\text{s}} = 0.274 \text{ lbm/s}$$

$$M_2 = \frac{V_2}{c_2} \quad c_2 = (\gamma RT)^{1/2} = (1.30 \times 85.8 \frac{\text{ft}\cdot\text{lb}}{\text{lbm}\cdot\text{R}} \times 1240 \text{ R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug}\cdot\text{ft}}{\text{lbm}\cdot\text{s}^2})^{1/2}$$

$$c_2 = 2110 \text{ ft/s}$$

$$M_2 = \frac{V_2}{c_2} = \frac{1660}{2110} = 0.787$$

Since  $M_2 < 1.0$ , passage converges as shown above

### Problem 13.3

[Difficulty: 2]

**13.3** Steam flows steadily and isentropically through a nozzle. At an upstream section where the speed is negligible, the temperature and pressure are 450°C and 6 MPa (abs). At a section where the nozzle diameter is 2 cm, the steam pressure is 2 MPa (abs). Determine the speed and Mach number at this section and the mass flow rate of steam. Sketch the passage shape.

**Given:** Steam flow through a nozzle

**Find:** Speed and Mach number; Mass flow rate; Sketch the shape

**Solution:**

Basic equations:  $m_{\text{rate}} = \rho \cdot V \cdot A$   $h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2}$

Assumptions: 1) Steady flow 2) Isentropic 3) Uniform flow 4) Superheated steam can be treated as ideal gas

Given or available data  $T_0 = (450 + 273) \cdot K$   $p_0 = 6 \cdot \text{MPa}$   $p = 2 \cdot \text{MPa}$   
 $D = 2 \cdot \text{cm}$   $k = 1.30$   $R = 461.4 \frac{\text{J}}{\text{kg} \cdot \text{K}}$  (Table A.6)

From the steam tables (try finding interactive ones on the Web!), at stagnation conditions

$s_0 = 6720 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$   $h_0 = 3.302 \times 10^6 \cdot \frac{\text{J}}{\text{kg}}$

Hence at the nozzle section  $s = s_0 = 6720 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$  and  $d$   $p = 2 \cdot \text{MPa}$

From these values we find from the steam tables that  $T = 289 \text{ }^\circ\text{C}$   $h = 2.997 \times 10^6 \cdot \frac{\text{J}}{\text{kg}}$   $v = 0.1225 \cdot \frac{\text{m}^3}{\text{kg}}$


Hence the first law becomes  $V = \sqrt{2 \cdot (h_0 - h)}$   $V = 781 \frac{\text{m}}{\text{s}}$

The mass flow rate is given by  $m_{\text{rate}} = \rho \cdot A \cdot V = \frac{A \cdot V}{v}$   $A = \frac{\pi \cdot D^2}{4}$   $A = 3.14 \times 10^{-4} \text{ m}^2$

Hence  $m_{\text{rate}} = \frac{A \cdot V}{v}$   $m_{\text{rate}} = 2.00 \frac{\text{kg}}{\text{s}}$

For the Mach number we need  $c = \sqrt{k \cdot R \cdot T}$   $c = 581 \frac{\text{m}}{\text{s}}$   $M = \frac{V}{c}$   $M = 1.35$

The flow is supersonic starting from rest, so must be converging-diverging



## Problem 13.4

[Difficulty: 2]

**13.4** Nitrogen flows through a diverging section of duct with  $A_1 = 0.15 \text{ m}^2$  and  $A_2 = 0.45 \text{ m}^2$ . If  $M_1 = 0.7$  and  $p_1 = 450 \text{ kPa}$ , find  $M_2$  and  $p_2$ .

**Given:** Data on flow in a passage

**Find:** Pressure and Mach number at downstream location

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 296.8 && \text{J/kg-K} \\ k &= 1.4 \\ p_1 &= 450 && \text{kPa} \\ M_1 &= 0.7 \\ A_1 &= 0.15 && \text{m}^2 \\ A_2 &= 0.45 && \text{m}^2 \end{aligned}$$

Equations and Computations:

From  $M_1$  and  $p_1$ , and Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$
$$p_{01} = 624 \quad \text{kPa}$$

From  $M_1$ , and Eq. 13.7d  
(using built-in function  $IsenA(M, k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)}$$
$$A_1^* = 0.1371 \quad \text{m}^2$$

For isentropic flow ( $p_{01} = p_{02}$ ,  $A_2^* = A_1^*$ )

$$\begin{aligned} p_{02} &= 624 && \text{kPa} \\ A_2^* &= 0.1371 && \text{m}^2 \\ A_2/A_2^* &= 3.2831 \end{aligned}$$

From  $A_2/A_2^*$ , and Eq. 13.7d  
(using built-in function  $IsenMsubfromA(M, k)$ )

Since there is no throat, the flow stays subsonic

$$M_2 = 0.1797$$

From  $M_2$  and  $p_{02}$ , and Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$p_2 = 610 \quad \text{kPa}$$

## Problem 13.5

[Difficulty: 2]

**13.5** Nitrogen flows through a diverging section of duct with  $A_1 = 0.15 \text{ m}^2$  and  $A_2 = 0.45 \text{ m}^2$ . If  $M_1 = 1.7$  and  $T_1 = 30^\circ\text{C}$ , find  $M_2$  and  $T_2$ .

**Given:** Data on flow in a passage

**Find:** Temperature and Mach number at downstream location

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 296.8 && \text{J/kg-K} \\k &= 1.4 \\T_1 &= 30 && ^\circ\text{C} \\T_1 &= 303 && \text{K} \\M_1 &= 1.7 \\A_1 &= 0.15 && \text{m}^2 \\A_2 &= 0.45 && \text{m}^2\end{aligned}$$

Equations and Computations:

From  $M_1$  and  $T_1$ , and Eq. 13.7b  
(using built-in function  $Isent(M,k)$ )

$$\begin{aligned}\frac{T_0}{T} &= 1 + \frac{k-1}{2} M^2 \\T_{01} &= 478 && \text{K}\end{aligned}$$

From  $M_1$ , and Eq. 13.7d  
(using built-in function  $IsenA(M,k)$ )

$$\begin{aligned}\frac{A}{A^*} &= \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)} \\A_1^* &= 0.1121 && \text{m}^2\end{aligned}$$

For isentropic flow ( $T_{01} = T_{02}$ ,  $A_2^* = A_1^*$ )

$$\begin{aligned}T_{02} &= 478 && \text{K} \\A_2^* &= 0.1121 && \text{m}^2 \\A_2/A_2^* &= 4.0128\end{aligned}$$

From  $A_2/A_2^*$ , and Eq. 13.7d  
(using built-in function  $IsenMsupfromA(M,k)$ )

Since there is no throat, the flow stays supersonic!

$$M_2 = 2.94$$

From  $M_2$  and  $T_{02}$ , and Eq. 13.7b  
(using built-in function  $Isent(M,k)$ )

$$\begin{aligned}T_2 &= 175 && \text{K} \\T_2 &= -98 && ^\circ\text{C}\end{aligned}$$

## Problem 13.6

[Difficulty: 2]

**13.6** At a section in a passage, the pressure is 150 kPa (abs), the temperature is 10°C, and the speed is 120 m/s. For isentropic flow of air, determine the Mach number at the point where the pressure is 50 kPa (abs). Sketch the passage shape.

**Given:** Air flow in a passage

**Find:** Mach number; Sketch shape

**Solution:**

Basic equations: 
$$\frac{p_0}{p} = \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}}$$

$$c = \sqrt{k \cdot R \cdot T}$$

Given or available data  $T_1 = (10 + 273) \cdot K$

$$p_1 = 150 \cdot \text{kPa}$$

$$V_1 = 120 \cdot \frac{\text{m}}{\text{s}}$$

$$p_2 = 50 \cdot \text{kPa}$$

$$k = 1.4$$

$$R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$$

The speed of sound at state 1 is  $c_1 = \sqrt{k \cdot R \cdot T_1}$

$$c_1 = 337 \frac{\text{m}}{\text{s}}$$

Hence 
$$M_1 = \frac{V_1}{c_1}$$

$$M_1 = 0.356$$

For isentropic flow stagnation pressure is constant. Hence at state 2

$$\frac{p_0}{p_2} = \left( 1 + \frac{k-1}{2} \cdot M_2^2 \right)^{\frac{k}{k-1}}$$


Hence 
$$p_0 = p_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)^{\frac{k}{k-1}}$$

$$p_0 = 164 \cdot \text{kPa}$$

Solving for  $M_2$  
$$M_2 = \sqrt{\frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_2} \right)^{\frac{k-1}{k}} - 1 \right]}$$

$$M_2 = 1.42$$

Hence, as we go from subsonic to supersonic we must have a converging-diverging nozzle



## Problem 13.7

[Difficulty: 2]

**13.7** At a section in a passage, the pressure is 30 psia, the temperature is 100°F, and the speed is 1750 ft/s. At a section downstream the Mach number is 2.5. Determine the pressure at this downstream location for isentropic flow of air. Sketch the passage shape.

**Given:** Data on flow in a passage

**Find:** Pressure at downstream location

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft lbf/lbm } ^\circ\text{R} \\k &= 1.4 \\T_1 &= 560 && ^\circ\text{R} \\p_1 &= 30 && \text{psi} \\V_1 &= 1750 && \text{ft/s} \\M_2 &= 2.5\end{aligned}$$

Equations and Computations:

From  $T_1$  and Eq. 12.18

$$c = \sqrt{kRT}$$

$$c_1 = 1160 \quad \text{ft/s}$$

Then

$$M_1 = 1.51$$

From  $M_1$  and  $p_1$ , and Eq. 13.7a

(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$

$$p_{01} = 111 \quad \text{psi}$$

For isentropic flow ( $p_{01} = p_{02}$ )

$$p_{02} = 111 \quad \text{psi}$$

From  $M_2$  and  $p_{02}$ , and Eq. 13.7a

(using built-in function  $Isenp(M, k)$ )

$$p_2 = 6.52 \quad \text{psi}$$

## Problem 13.8

[Difficulty: 2]

**13.8** Oxygen flows into an insulated duct with initial conditions of 200 kPa, 420 K, and 200 m/s. The area changes from  $A_1 = 0.6 \text{ m}^2$  to  $A_2 = 0.5 \text{ m}^2$ . Compute  $M_1$ ,  $p_{01}$ , and  $T_{01}$ . Is this duct a nozzle or a diffuser? Calculate the exit conditions (pressure, temperature, and Mach number) provided that there are no losses.

**Given:** Data on flow in a passage

**Find:** Stagnation conditions; whether duct is a nozzle or diffuser; exit conditions

**Solution:**

The given or available data is:

$R =$	259.8	J/kg-K
$k =$	1.4	
$p_1 =$	200	kPa
$T_1 =$	420	K
$V_1 =$	200	m/s
$A_1 =$	0.6	$\text{m}^2$
$A_2 =$	0.5	$\text{m}^2$

Equations and Computations:

From  $T_1$  and Eq. 12.18

$$c = \sqrt{kRT}$$

$$c_1 = 391 \text{ m/s}$$

Then

$$M_1 = 0.512$$

From  $M_1$  and  $T_1$ , and Eq. 13.7b  
(using built-in function  $Isent(M, k)$ )

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$$

$$T_{01} = 442 \text{ K}$$

From  $M_1$  and  $p_1$ , and Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$

$$p_{01} = 239 \text{ kPa}$$

Since the flow is subsonic and the area is decreasing, this duct is a nozzle.

From  $M_1$ , and Eq. 13.7d  
(using built-in function  $IsenA(M, k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)}$$

$$A_1^* = 0.4552 \text{ m}^2$$

For isentropic flow ( $p_{01} = p_{02}$ ,  $T_{01} = T_{02}$ ,  $A_1^* = A_2^*$ )

$$p_{02} = 239 \text{ kPa}$$

$$T_{02} = 442 \text{ K}$$

$$A_2^* = 0.4552 \text{ m}^2$$

$$A_2/A_2^* = 1.0984$$

From  $A_2/A_2^*$ , and Eq. 13.7d  
(using built-in function  $IsenMsubfromA(M, k)$ )

Since there is no throat, the flow stays subsonic!

$$M_2 = 0.69$$

From  $M_2$  and stagnation conditions:  
(using built-in functions)

$$p_2 = 173 \text{ kPa}$$

$$T_2 = 403 \text{ K}$$

## Problem 13.9

[Difficulty: 3]

**13.9** Air is flowing in an adiabatic system at 20 lbm/s. At one section, the pressure is 30 psia, the temperature is 1200°F, and the area is 8 in<sup>2</sup>. At a downstream section,  $M_2 = 1.2$ . Sketch the flow passage. Find the exit area provided the flow is reversible.

**Given:** Data on flow in a passage

**Find:** Shape of flow passage; exit area provided the flow is reversible

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 53.33 && \text{ft}\cdot\text{lb}/\text{lbm}\cdot^\circ\text{R} \\ k &= 1.4 \\ m &= 20 && \text{lbm/s} \\ p_1 &= 30 && \text{psia} \\ T_1 &= 1200 && ^\circ\text{F} \\ T_1 &= 1660 && ^\circ\text{R} \\ A_1 &= 8 && \text{in}^2 \\ M_2 &= 1.2 \end{aligned}$$

Equations and Computations:

Using the ideal gas law we calculate the density at station 1:

$$\rho_1 = 0.04880 \text{ lbm/ft}^3$$

Now we can use the area and density to get the velocity from the mass flow rate:

$$V_1 = 7377 \text{ ft/s}$$

From  $T_1$  and Eq. 12.18


$$c = \sqrt{kRT}$$

$$c_1 = 1998 \text{ ft/s}$$

Then

$$M_1 = 3.69$$

Since the flow is supersonic and the velocity is decreasing, this duct is converging.



From  $M_1$ , and Eq. 13.7d

(using built-in function  $IsenA(M, k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)}$$

$$A_1^* = 0.9857 \text{ in}^2$$

For isentropic flow ( $A_2^* = A_1^*$ )

$$A_2^* = 0.9857 \text{ in}^2$$

$$A_2/A_2^* = 1.0304$$

Therefore the exit area is:

$$A_2 = 1.016 \text{ in}^2$$

## Problem 13.10

[Difficulty: 3]

**13.10** Air flows isentropically through a converging-diverging nozzle from a large tank containing air at 250°C. At two locations where the area is 1 cm<sup>2</sup>, the static pressures are 200 kPa and 50 kPa. Find the mass flow rate, the throat area, and the Mach numbers at the two locations.

**Given:** Data on flow in a nozzle

**Find:** Mass flow rate; Throat area; Mach numbers

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg K} \\ k &= 1.4 \\ T_0 &= 523 && \text{K} \\ p_1 &= 200 && \text{kPa} && p_2 = 50 && \text{kPa} \\ A &= 1 && \text{cm}^2 \end{aligned}$$

Equations and Computations:

We don't know the two Mach numbers. We do know for each that Eq. 13.7a applies:

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$

Hence we can write two equations, but have three unknowns ( $M_1$ ,  $M_2$ , and  $p_0$ )!

We also know that states 1 and 2 have the same area. Hence we can write Eq. 13.7d twice:

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)}$$

We now have four equations for four unknowns ( $A^*$ ,  $M_1$ ,  $M_2$ , and  $p_0$ )!

We make guesses (using Solver) for  $M_1$  and  $M_2$ , and make the errors in computed  $A^*$  and  $p_0$  zero.

For:	$M_1 = 0.512$	$M_2 = 1.68$	<b>Errors</b>
from Eq. 13.7a:	$p_0 = 239 \text{ kPa}$	$p_0 = 239 \text{ kPa}$	0.00%
and from Eq. 13.7d:	$A^* = 0.759 \text{ cm}^2$	$A^* = 0.759 \text{ cm}^2$	0.00%
Note that the throat area is the critical area			<b>Sum</b> 0.00%

The stagnation density is then obtained from the ideal gas equation

$$\rho_0 = 1.59 \text{ kg/m}^3$$

The density at critical state is obtained from Eq. 13.7a (or 12.22c)

$$\rho^* = 1.01 \text{ kg/m}^3$$

The velocity at critical state can be obtained from Eq. 12.23)

$$V^* = c^* = \sqrt{\frac{2k}{k+1} RT_0}$$

$$V^* = 418 \text{ m/s}$$

The mass flow rate is  $\rho^* V^* A^*$

$$m_{\text{rate}} = 0.0321 \text{ kg/s}$$

### Problem 13.11

[Difficulty: 2]

**13.11** Air flows steadily and isentropically through a passage. At section ①, where the cross-sectional area is  $0.02 \text{ m}^2$ , the air is at  $40.0 \text{ kPa}$  (abs),  $60^\circ\text{C}$ , and  $M = 2.0$ . At section ② downstream, the speed is  $519 \text{ m/s}$ . Calculate the Mach number at section ②. Sketch the shape of the passage between sections ① and ②.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2}$

Assumptions: (1) steady flow (4)  $\Delta s = 0$   
 (2) isentropic flow (5) ideal gas  
 (3) uniform flow at a section

$M_2 = \frac{V_2}{c_2}$  where  $c_2 = (\gamma R T_2)^{1/2}$ . Hence  $T_2$  must be found

$h_2 = h_1 + \frac{1}{2} (V_1^2 - V_2^2)$

$V_1 = M_1 c_1 = M_1 (\gamma R T_1)^{1/2} = 2.0 (1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 323 \text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2})^{1/2} = 732 \text{ m/s}$


$T_2 = T_1 + \frac{1}{2\gamma} (V_1^2 - V_2^2)$   
 $= 323 \text{K} + \frac{1}{2 \times 1.4} [(732)^2 - (519)^2] \frac{\text{m}^2}{\text{s}^2} \times \frac{1}{10^3 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}}} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}$

$T_2 = 466 \text{ K}$

$c_2 = (\gamma R T_2)^{1/2} = (1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 466 \text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2})^{1/2} = 433 \text{ m/s}$

$M_2 = \frac{V_2}{c_2} = \frac{519}{433} = 1.20$

Since  $M_2 < M_1$  and  $M_2 > 1.0$ , then passage from ① to ② is a supersonic diffuser as shown above



$M_2$

## Problem 13.12

[Difficulty: 3]

**13.12** Air flows steadily and isentropically through a passage at 150 lbf/s. At the section where the diameter is  $D = 3$  ft,  $M = 1.75$ ,  $T = 32^\circ\text{F}$ , and  $p = 25$  psia. Determine the speed and cross-sectional area downstream where  $T = 225^\circ\text{F}$ . Sketch the flow passage.

**Given:** Air flow in a passage

**Find:** Speed and area downstream; Sketch flow passage

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $c = \sqrt{k \cdot R \cdot T}$        $\frac{A}{A_{\text{crit}}} = \frac{1}{M} \cdot \left( \frac{1 + \frac{k-1}{2} \cdot M^2}{\frac{k+1}{2}} \right)^{\frac{k+1}{2 \cdot (k-1)}}$

Given or available data     $T_1 = (32 + 460) \cdot R$        $p_1 = 25 \cdot \text{psi}$        $M_1 = 1.75$   
 $T_2 = (225 + 460) \cdot R$        $k = 1.4$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot R}$   
 $D_1 = 3 \cdot \text{ft}$        $A_1 = \frac{\pi \cdot D_1^2}{4}$        $A_1 = 7.07 \cdot \text{ft}^2$

Hence  $T_0 = T_1 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)$        $T_0 = 793 \cdot R$        $T_0 = 334 \cdot ^\circ\text{F}$

For isentropic flow stagnation conditions are constant. Hence

$$M_2 = \sqrt{\frac{2}{k-1} \cdot \left( \frac{T_0}{T_2} - 1 \right)} \quad M_2 = 0.889$$


We also have  $c_2 = \sqrt{k \cdot R_{\text{air}} \cdot T_2}$        $c_2 = 1283 \cdot \frac{\text{ft}}{\text{s}}$

Hence  $V_2 = M_2 \cdot c_2$        $V_2 = 1141 \cdot \frac{\text{ft}}{\text{s}}$

From state 1  $A_{\text{crit}} = \frac{A_1 \cdot M_1}{\frac{k+1}{\left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)^{\frac{k+1}{2 \cdot (k-1)}}}}$        $A_{\text{crit}} = 5.10 \cdot \text{ft}^2$

Hence at state 2  $A_2 = \frac{A_{\text{crit}}}{M_2} \cdot \left( \frac{1 + \frac{k-1}{2} \cdot M_2^2}{\frac{k+1}{2}} \right)^{\frac{k+1}{2 \cdot (k-1)}}$        $A_2 = 5.15 \cdot \text{ft}^2$

Hence, as we go from supersonic to subsonic we must have a converging-diverging diffuser



### Problem 13.13

[Difficulty: 2]

13.13 Air, at an absolute pressure of 60.0 kPa and 27°C, enters a passage at 486 m/s, where  $A = 0.02 \text{ m}^2$ . At section ② downstream,  $p = 78.8 \text{ kPa}$  (abs). Assuming isentropic flow, calculate the Mach number at section ②. Sketch the flow passage.

Solution:

Computing equations:  $\frac{P_0}{P} = \left[1 + \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}}$   $c = \sqrt{\gamma RT}$

Assumptions: 1) steady flow 2) isentropic flow 3) uniform flow at a section 4) ideal gas

For isentropic flow,  $P_{01} = P_{02} = P_0 = \text{constant}$

$$M_1 = \frac{V_1}{c_1} \quad c_1 = (\gamma RT_1)^{1/2} = \left(1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 300\text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right)^{1/2} = 347 \text{ m/s}$$

$$M_1 = \frac{V_1}{c_1} = \frac{486}{347} = 1.40$$

$$P_{01} = P_1 \left[1 + \frac{\gamma-1}{2} M_1^2\right]^{\frac{\gamma}{\gamma-1}} = 60.2 \text{ kPa} \left[1 + 0.2(1.40)^2\right]^{3.5}$$


$$P_{01} = 191 \text{ kPa}$$

$$\frac{P_{02}}{P_2} = \left[1 + \frac{\gamma-1}{2} M_2^2\right]^{\frac{\gamma}{\gamma-1}}$$

$$P_{02} = P_{01}$$

$$M_2 = \left\{ \frac{2}{\gamma-1} \left[ \frac{P_{01}}{P_2} \right]^{\frac{\gamma-1}{\gamma}} - 1 \right\}^{1/2} = \left\{ \frac{2}{0.4} \left[ \frac{191}{78.8} \right]^{0.286} - 1 \right\}^{1/2} = 1.20 \quad \leftarrow M_2$$

Since  $M_2 < M_1$ , and  $M_2 > 1.0$ , then passage from ① to ② is a supersonic diffuser as shown above



## Problem 13.14

[Difficulty: 3]

**13.14** Air flows adiabatically through a duct. At the entrance, the static temperature and pressure are 310 K and 200 kPa, respectively. At the exit, the static and stagnation temperatures are 294 K and 316 K, respectively, and the static pressure is 125 kPa. Find (a) the Mach numbers of the flow at the entrance and exit and (b) the area ratio  $A_2/A_1$ .

**Given:** Data on flow in a passage

**Find:** Mach numbers at entrance and exit; area ratio of duct

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\k &= 1.4 \\T_1 &= 310 && \text{K} \\p_1 &= 200 && \text{kPa} \\T_2 &= 294 && \text{K} \\T_{02} &= 316 && \text{K} \\p_2 &= 125 && \text{kPa}\end{aligned}$$

Equations and Computations:

Since the flow is adiabatic, the stagnation temperature is constant:

$$T_{01} = 316 \quad \text{K}$$

Solving for the Mach numbers at 1 and 2 using Eq. 13.7b  
(using built-in function  $IsenMfromT(Tratio, k)$ )

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$$

$$\begin{aligned}\text{Then} \quad M_1 &= 0.311 \\M_2 &= 0.612\end{aligned}$$

Using the ideal gas equation of state, we can calculate the densities of the gas:

$$\begin{aligned}\rho_1 &= 2.249 && \text{kg/m}^3 \\ \rho_2 &= 1.482 && \text{kg/m}^3\end{aligned}$$

From static temperatures and Eq. 12.18  $c = \sqrt{kRT}$

$$\begin{aligned}c_1 &= 352.9 && \text{m/s} \\c_2 &= 343.6 && \text{m/s} \\V_1 &= 109.8 && \text{m/s} \\V_2 &= 210.2 && \text{m/s}\end{aligned}$$

Since flow is steady, the mass flow rate must be equal at 1 and 2.

So the area ratio may be calculated from the densities and velocities:

$$A_2/A_1 = 0.792$$

Note that we can not assume isentropic flow in this problem. While the flow is adiabatic, it is not reversible. There is a drop in stagnation pressure from state 1 to 2 which would invalidate the assumption of isentropic flow.

## Problem 13.15

[Difficulty: 3]

**13.15** Atmospheric air (101 kPa and 20°C) is drawn into a receiving pipe via a converging nozzle. The throat cross-section diameter is 1 cm. Plot the mass flow rate delivered for the receiving pipe pressure ranging from 100 kPa down to 5 kPa.

**Given:** Flow in a converging nozzle to a pipe

**Find:** Plot of mass flow rate

**Solution:**

The given or available data is

$$\begin{aligned}
 R &= 287 \text{ J/kg}\cdot\text{K} \\
 k &= 1.4 \\
 T_0 &= 293 \text{ K} \\
 p_0 &= 101 \text{ kPa} \\
 D_t &= 1 \text{ cm} \\
 A_t &= 0.785 \text{ cm}^2
 \end{aligned}$$

Equations and Computations:

The critical pressure is given by

$$\frac{p_0}{p^*} = \left[ \frac{k+1}{2} \right]^{k/(k-1)} \quad (12.22a)$$

$$p^* = 53.4 \text{ kPa}$$


Hence for  $p = 100 \text{ kPa}$  down to this pressure the flow gradually increases; then it is constant

$p$ (kPa)	$M$ (Eq. 13.7a)	$T$ (K) (Eq. 13.7b)	$c$ (m/s)	$V = M c$ (m/s)	$\rho = p/RT$ (kg/m <sup>3</sup> )	Flow Rate (kg/s)
100	0.119	292	343	41	1.19	0.00383
99	0.169	291	342	58	1.18	0.00539
98	0.208	290	342	71	1.18	0.00656
97	0.241	290	341	82	1.17	0.00753
96	0.270	289	341	92	1.16	0.00838
95	0.297	288	340	101	1.15	0.0091
90	0.409	284	337	138	1.11	0.0120
85	0.503	279	335	168	1.06	0.0140
80	0.587	274	332	195	1.02	0.0156
75	0.666	269	329	219	0.971	0.0167
70	0.743	264	326	242	0.925	0.0176
65	0.819	258	322	264	0.877	0.0182
60	0.896	252	318	285	0.828	0.0186
55	0.974	246	315	306	0.778	0.0187
53.4	1.000	244	313	313	0.762	0.0187
53	1.000	244	313	313	0.762	0.0187
52	1.000	244	313	313	0.762	0.0187
51	1.000	244	313	313	0.762	0.0187
50	1.000	244	313	313	0.762	0.0187

Using critical conditions, and Eq. 13.9 for mass flow rate:

53.4	1.000	244	313	313	0.762	0.0185
------	-------	-----	-----	-----	-------	--------

(Note: discrepancy in mass flow rate is due to round-off error)



## Problem 13.16

[Difficulty: 2]

**13.16** For isentropic flow of air, at a section in a passage,  $A = 0.25 \text{ m}^2$ ,  $p = 15 \text{ kPa (abs)}$ ,  $T = 10^\circ\text{C}$ , and  $V = 590 \text{ m/s}$ . Find the Mach number and the mass flow rate. At a section downstream the temperature is  $137^\circ\text{C}$  and the Mach number is 0.75. Determine the cross-sectional area and pressure at this downstream location. Sketch the passage shape.

**Given:** Data on flow in a passage

**Find:** Flow rate; area and pressure at downstream location; sketch passage shape

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg}\cdot\text{K} \\ k &= 1.4 \\ A_1 &= 0.25 && \text{m}^2 \\ T_1 &= 283 && \text{K} \\ p_1 &= 15 && \text{kPa} \\ V_1 &= 590 && \text{m/s} \\ T_2 &= 410 \\ M_2 &= 0.75 \end{aligned}$$


Equations and Computations:

$$\text{From } T_1 \text{ and Eq. 12.18} \quad c = \sqrt{kRT} \quad (12.18)$$

$$c_1 = 337 \quad \text{m/s}$$

$$\text{Then} \quad M_1 = 1.75$$

Because the flow decreases isentropically from supersonic to subsonic the passage shape must be convergent-divergent



From  $p_1$  and  $T_1$  and the ideal gas equation

$$\rho_1 = 0.185 \quad \text{kg/m}^3$$

The mass flow rate is  $m_{\text{rate}} = \rho_1 A_1 V_1$

$$m_{\text{rate}} = 27.2 \quad \text{kg/s}$$

From  $M_1$  and  $A_1$ , and Eq. 13.7d  
(using built-in function  $IsenA(M,k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)} \quad (13.7d)$$

$$A^* = 0.180 \text{ m}^2$$

From  $M_2$  and  $A^*$ , and Eq. 13.7d  
(using built-in function  $IsenA(M,k)$ )

$$A_2 = 0.192 \text{ m}^2$$

From  $M_1$  and  $p_1$ , and Eq. 13.7a  
(using built-in function  $Isenp(M,k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$p_{01} = 79.9 \text{ kPa}$$

For isentropic flow ( $p_{01} = p_{02}$ )

$$p_{02} = 79.9 \text{ kPa}$$

From  $M_2$  and  $p_{02}$ , and Eq. 13.7a  
(using built-in function  $Isenp(M,k)$ )

$$p_2 = 55.0 \text{ kPa}$$

## Problem 13.17

[Difficulty: 3]

**13.17** A passage is designed to expand air isentropically to atmospheric pressure from a large tank in which properties are held constant at 40°F and 45 psia. The desired flow rate is 2.25 lbm/s. Assuming the passage is 20 ft long, and that the Mach number increases linearly with position in the passage, plot the cross-sectional area and pressure as functions of position.

**Given:** Data on tank conditions; isentropic flow

**Find:** Plot cross-section area and pressure distributions

**Solution:**

The given or available data is:

$R =$	53.33	ft lbf/lbm °R
$k =$	1.4	
$T_0 =$	500	°R
$p_0 =$	45	psia
$p_e =$	14.7	psia
$m_{\text{rate}} =$	2.25	lbm/s

Equations and Computations:

From  $p_0$ ,  $p_e$  and Eq. 13.7a (using built-in function  $IsenMfromp(M,k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$M_e = 1.37$$

Because the exit flow is supersonic, the passage must be a CD nozzle  
We need a scale for the area.

From  $p_0$ ,  $T_0$ ,  $m_{\text{flow}}$ , and Eq. 13.10c

$$\dot{m}_{\text{choked}} = 76.6 \frac{A_t p_0}{\sqrt{T_0}} \quad (13.10c)$$

Then  $A_t = A^* = 0.0146 \text{ ft}^2$



For each  $M$ , and  $A^*$ , and Eq. 13.7d  
(using built-in function  $IsenA(M,k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)} \quad (13.7d)$$

we can compute each area  $A$ .

From each  $M$ , and  $p_0$ , and Eq. 13.7a  
(using built-in function  $Isenp(M,k)$ )  
we can compute each pressure  $p$ .

$L$ (ft)	$M$	$A$ (ft <sup>2</sup> )	$p$ (psia)
1.00	0.069	0.1234	44.9
1.25	0.086	0.0989	44.8
1.50	0.103	0.0826	44.7
1.75	0.120	0.0710	44.5
2.00	0.137	0.0622	44.4
2.50	0.172	0.0501	44.1
3.00	0.206	0.0421	43.7
4.00	0.274	0.0322	42.7
5.00	0.343	0.0264	41.5
6.00	0.412	0.0227	40.0
7.00	0.480	0.0201	38.4
8.00	0.549	0.0183	36.7
9.00	0.618	0.0171	34.8
10.00	0.686	0.0161	32.8
11.00	0.755	0.0155	30.8
12.00	0.823	0.0150	28.8
13.00	0.892	0.0147	26.8
14.00	0.961	0.0146	24.9
<b>14.6</b>	<b>1.000</b>	<b>0.0146</b>	<b>23.8</b>
16.00	1.098	0.0147	21.1
17.00	1.166	0.0149	19.4
18.00	1.235	0.0152	17.7
19.00	1.304	0.0156	16.2
20.00	1.372	0.0161	14.7



## Problem 13.18

[Difficulty: 2]

**13.18** Repeat Problem 13.15 if the converging nozzle is replaced with a converging-diverging nozzle with an exit diameter of 2.5 cm (same throat area).

**Given:** Flow in a converging-diverging nozzle to a pipe

**Find:** Plot of mass flow rate

**Solution:**

The given or available data is

$R =$	286.9	J/kg K		
$k =$	1.4			
$T_0 =$	293	K		
$p_0 =$	101	kPa		
$D_t =$	1	cm	$D_e =$	2.5 cm
$A_t =$	0.785	cm <sup>2</sup>	$A_e =$	4.909 cm <sup>2</sup>

Equations and Computations:

The critical pressure is given by 
$$\frac{p_0}{p^*} = \left[ \frac{k+1}{2} \right]^{k/(k-1)} \quad (12.22a)$$

$p^* = 53.4 \text{ kPa}$       This is the minimum throat pressure

For the CD nozzle, we can compute the pressure at the exit required for this to happen

$A^* =$	0.785	cm <sup>2</sup>	$(= A_t)$
$A_e/A^* =$	6.25		
$M_e =$	0.0931	or	3.41 (Eq. 13.7d)
$p_e =$	100.4	or	67.2 kPa (Eq. 13.7a)

Hence we conclude flow occurs in regimes *iii* down to *v* (Fig. 13.8); the flow is ALWAYS choked!

$p^*$	$M$	$T^*$ (K)	$c^*$	$V^* = c^*$	$\rho = p/RT$	Flow Rate
(kPa)	(Eq. 13.7a)	(Eq. 13.7b)	(m/s)	(m/s)	(kg/m <sup>3</sup> )	(kg/s)
53.4	1.000	244	313	313	0.762	0.0187
(Note: discrepancy in mass flow rate is due to round-off error)						0.0185

(Using Eq. 13.9)

## Problem 13.19

[Difficulty: 2]

**13.19** Air flows isentropically through a converging nozzle into a receiver where the pressure is 250 kPa (abs). If the pressure is 350 kPa (abs) and the speed is 150 m/s at the nozzle location where the Mach number is 0.5, determine the pressure, speed, and Mach number at the nozzle throat.

**Given:** Isentropic air flow in converging nozzle

**Find:** Pressure, speed and Mach number at throat

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$

Given or available data       $p_1 = 350 \cdot \text{kPa}$        $V_1 = 150 \cdot \frac{\text{m}}{\text{s}}$        $M_1 = 0.5$        $p_b = 250 \cdot \text{kPa}$

$k = 1.4$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

The flow will be choked if  $p_b/p_0 < 0.528$

$p_0 = p_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)^{\frac{k}{k-1}}$        $p_0 = 415 \cdot \text{kPa}$        $\frac{p_b}{p_0} = 0.602$       (Not choked)

Hence  $\frac{p_0}{p_t} = \left(1 + \frac{k-1}{2} \cdot M_t^2\right)^{\frac{k}{k-1}}$  where  $p_t = p_b$        $p_t = 250 \cdot \text{kPa}$

so  $M_t = \sqrt{\frac{2}{k-1} \cdot \left[ \left(\frac{p_0}{p_t}\right)^{\frac{k-1}{k}} - 1 \right]}$        $M_t = 0.883$

Also  $V_1 = M_1 \cdot c_1 = M_1 \cdot \sqrt{k \cdot R \cdot T_1}$  or  $T_1 = \frac{1}{k \cdot R} \cdot \left(\frac{V_1}{M_1}\right)^2$        $T_1 = 224 \text{ K}$        $T_1 = -49.1 \cdot ^\circ\text{C}$

Then  $T_0 = T_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)$        $T_0 = 235 \text{ K}$        $T_0 = -37.9 \cdot ^\circ\text{C}$

Hence  $T_t = \frac{T_0}{1 + \frac{k-1}{2} \cdot M_t^2}$        $T_t = 204 \text{ K}$        $T_t = -69.6 \cdot ^\circ\text{C}$

Then  $c_t = \sqrt{k \cdot R \cdot T_t}$        $c_t = 286 \frac{\text{m}}{\text{s}}$

Finally  $V_t = M_t \cdot c_t$        $V_t = 252 \frac{\text{m}}{\text{s}}$

## Problem 13.20

[Difficulty: 2]

**13.20** Air flows isentropically through a converging nozzle into a receiver in which the absolute pressure is 35 psia. The air enters the nozzle with negligible speed at a pressure of 60 psia and a temperature of 200°F. Determine the mass flow rate through the nozzle for a throat diameter of 4 in.

**Given:** Air flow in a converging nozzle

**Find:** Mass flow rate

**Solution:**

Basic equations:  $m_{\text{rate}} = \rho \cdot V \cdot A$        $p = \rho \cdot R \cdot T$        $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$

Given or available data  $p_b = 35 \cdot \text{psi}$        $p_0 = 60 \cdot \text{psi}$        $T_0 = (200 + 460) \cdot \text{R}$        $D_t = 4 \cdot \text{in}$

$k = 1.4$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$        $A_t = \frac{\pi}{4} \cdot D_t^2$        $A_t = 0.0873 \cdot \text{ft}^2$

Since  $\frac{p_b}{p_0} = 0.583$  is greater than 0.528, the nozzle is not choked and  $p_t = p_b$

Hence 
$$M_t = \sqrt{\frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_t} \right)^{\frac{k-1}{k}} - 1 \right]}$$
  $M_t = 0.912$

and  $T_t = \frac{T_0}{1 + \frac{k-1}{2} \cdot M_t^2}$        $T_t = 566 \cdot \text{R}$        $T_t = 106 \cdot ^\circ\text{F}$

$c_t = \sqrt{k \cdot R_{\text{air}} \cdot T_t}$        $V_t = c_t$        $V_t = 1166 \cdot \frac{\text{ft}}{\text{s}}$

$\rho_t = \frac{p_t}{R_{\text{air}} \cdot T_t}$        $\rho_t = 5.19 \times 10^{-3} \cdot \frac{\text{slug}}{\text{ft}^3}$

$m_{\text{rate}} = \rho_t \cdot A_t \cdot V_t$        $m_{\text{rate}} = 0.528 \cdot \frac{\text{slug}}{\text{s}}$        $m_{\text{rate}} = 17.0 \cdot \frac{\text{lbm}}{\text{s}}$

## Problem 13.21

[Difficulty: 2]

---

**13.21** Air flows through a diverging duct. At the entrance to the duct, the Mach number is 1 and the area is  $0.2 \text{ m}^2$ . At the exit to the duct, the area is  $0.5 \text{ m}^2$ . What are the two possible exit Mach numbers for this duct?

---

**Given:** Data on flow in a passage

**Find:** Possible Mach numbers at downstream location

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\k &= 1.4 \\M_1 &= 1 \\A_1 &= 0.2 && \text{m}^2 \\A_2 &= 0.5 && \text{m}^2\end{aligned}$$

Equations and Computations:

Since the flow is sonic at the entrance:

$$A_1^* = 0.2 \text{ m}^2$$

For isentropic flow ( $A_2^* = A_1^*$ )

$$\begin{aligned}A_2^* &= 0.2 \text{ m}^2 \\A_2/A_2^* &= 2.5\end{aligned}$$

Now there are two Mach numbers which could result from this area change, one subsonic and one supersonic.

From  $A_2/A_2^*$ , and Eq. 13.7d  
(using built-in functions)

$$\begin{aligned}M_{2sub} &= 0.2395 \\M_{2sup} &= 2.4428\end{aligned}$$

## Problem 13.22

[Difficulty: 3]

**13.22** Air is flowing steadily through a series of three tanks. The first very large tank contains air at 650 kPa and 35°C. Air flows from it to a second tank through a converging nozzle with exit area 1 cm<sup>2</sup>. Finally the air flows from the second tank to a third very large tank through an identical nozzle. The flow rate through the two nozzles is the same, and the flow in them is isentropic. The pressure in the third tank is 65 kPa. Find the mass flow rate, and the pressure in the second tank.

**Given:** Data on three tanks

**Find:** Mass flow rate; Pressure in second tank

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg.K} \\ k &= 1.4 \\ A_t &= 1 && \text{cm}^2 \end{aligned}$$

We need to establish whether each nozzle is choked. There is a large total pressure drop so this is likely. However, BOTH cannot be choked and have the same flow rate. This is because Eq. 13.9a, below

$$\dot{m}_{\text{choked}} = 0.04 \frac{A_e p_0}{\sqrt{T_0}} \quad (13.9b)$$

indicates that the choked flow rate depends on stagnation temperature (which is constant) but also stagnation pressure, which drops because of turbulent mixing in the middle chamber. Hence BOTH nozzles cannot be choked. We assume the second one only is choked (why?) and verify later.

Temperature and pressure in tank 1:

$$\begin{aligned} T_{01} &= 308 && \text{K} \\ p_{01} &= 650 && \text{kPa} \end{aligned}$$

We make a guess at the pressure at the first nozzle exit:

$$p_{e1} = 527 \quad \text{kPa}$$

NOTE: The value shown is the final answer! It was obtained using *Solver*!

This will also be tank 2 stagnation pressure:

$$p_{02} = 527 \quad \text{kPa}$$

Pressure in tank 3:

$$p_3 = 65 \quad \text{kPa}$$

Equations and Computations:

$$\begin{aligned} \text{From the } p_{e1} \text{ guess and Eq. 13.17a:} &&& M_{e1} = 0.556 \\ \text{Then at the first throat (Eq.13.7b):} &&& T_{e1} = 290 \quad \text{K} \\ \text{The density at the first throat (Ideal Gas) is:} &&& \rho_{e1} = 6.33 \quad \text{kg/m}^3 \\ \text{Then } c \text{ at the first throat (Eq. 12.18) is:} &&& c_{e1} = 341 \quad \text{m/s} \\ \text{Then } V \text{ at the first throat is:} &&& V_{e1} = 190 \quad \text{m/s} \\ \text{Finally the mass flow rate is:} &&& m_{\text{rate}} = 0.120 \quad \text{kg/s} \quad \text{First Nozzle!} \end{aligned}$$

For the presumed choked flow at the second nozzle we use Eq. 13.9a, with  $T_{01} = T_{02}$  and  $p_{02}$ :

$$m_{\text{rate}} = 0.120 \quad \text{kg/s} \quad \text{Second Nozzle!}$$

For the guess value for  $p_{e1}$  we compute the error between the two flow rates:

$$\Delta m_{\text{rate}} = 0.000 \quad \text{kg/s}$$

Use Solver to vary the guess value for  $p_{e1}$  to make this error zero!

Note that this could also be done manually.

### Problem 13.23

[Difficulty: 2]

**13.23** Air flowing isentropically through a converging nozzle discharges to the atmosphere. At the section where the absolute pressure is 250 kPa, the temperature is 20°C and the air speed is 200 m/s. Determine the nozzle throat pressure.

Solution:

Computing equations:  $\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}$   $c = \sqrt{kRT}$

- Assumptions:
- (1) steady flow
  - (2) isentropic flow in the nozzle
  - (3) uniform flow at a section
  - (4) ideal gas

The nozzle will be choked, i.e.  $M_t = 1.0$  if  $\frac{P_0}{P_a} \geq 0.528$


$$M_1 = \frac{V_1}{c_1}, \quad c_1 = \sqrt{kRT_1} = \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 293\text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right)^{1/2} = 343 \text{ m/s}$$

$$M_1 = \frac{V_1}{c_1} = \frac{200}{343} = 0.583$$

$$\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}} \quad P_0 = P_1 \left[ 1 + \frac{k-1}{2} M_1^2 \right]^{\frac{k}{k-1}} = 250 \text{ kPa} \left[ 1 + 0.2(0.583)^2 \right]^{3.5} = 315 \text{ kPa}$$

$$\text{Then, } \frac{P_0}{P_a} = \frac{315}{101} = 0.321 < 0.528 \quad \therefore M_t = 1.0$$

$$\text{For } M_t = 1.0, \quad \frac{P_t}{P_0} = 0.528 \quad P_t = 0.528 P_0 = 0.528 \times 315 \text{ kPa} = 166 \text{ kPa} \quad \leftarrow P_t$$



### Problem 13.24

[Difficulty: 2]

13.24 Air flows from a large tank ( $p = 650 \text{ kPa (abs)}$ ,  $T = 550^\circ \text{C}$ ) through a converging nozzle, with a throat area of  $600 \text{ mm}^2$ , and discharges to the atmosphere. Determine the mass rate of flow for isentropic flow through the nozzle.

Solution:

Basic equations:  $\dot{m} = \rho VA = \text{const}$        $P = \rho RT$   
 Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$        $\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}$        $c = \sqrt{kRT}$

Assumptions: (1) steady flow      (3) uniform flow at a section  
 (2) isentropic flow in nozzle      (4) ideal gas

Since  $P_0/P_0 = \frac{650}{650} = 1 < 0.528$ , the nozzle is choked and  $M_t = 1.0$

From the continuity equation  $\dot{m} = \rho VA$  and hence we need to determine  $\rho_t$  and  $V_t$


$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2; \quad T_t = \frac{T_0}{1 + \frac{k-1}{2} M_t^2} = \frac{823 \text{ K}}{1 + 0.2(1.0)^2} = 686 \text{ K}$$

$$V_t = M_t c_t = M_t \left( \sqrt{kRT_t} \right) = 1.0 \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 686 \text{ K} \right)^{1/2} = 525 \text{ m/s}$$

$$\frac{P_0}{P_t} = \left[ 1 + \frac{k-1}{2} M_t^2 \right]^{\frac{k}{k-1}}; \quad P_t = \frac{P_0}{\left[ 1 + \frac{k-1}{2} M_t^2 \right]^{\frac{k}{k-1}}} = \frac{650 \text{ kPa}}{\left[ 1 + 0.2(1.0)^2 \right]^{\frac{1.4}{0.4}}} = 343 \text{ kPa}$$

$$\rho_t = \frac{P_t}{RT_t} = \frac{343 \times 10^3 \text{ N}}{\text{m}^2} \times \frac{1 \text{ kg}\cdot\text{m}}{287 \text{ N}\cdot\text{m}} \times \frac{1}{686 \text{ K}} = 1.74 \text{ kg/m}^3$$

Finally  $\dot{m} = \rho_t V_t A_t = 1.74 \frac{\text{kg}}{\text{m}^3} \times 525 \frac{\text{m}}{\text{s}} \times 6 \times 10^{-4} \text{ m}^2 = 0.548 \text{ kg/s}$



## Problem 13.25

[Difficulty: 2]

**13.25** Air flowing isentropically through a converging nozzle discharges to the atmosphere. At a section the area is  $A = 0.05 \text{ m}^2$ ,  $T = 3.3^\circ\text{C}$ , and  $V = 200 \text{ m/s}$ . If the flow is just choked, find the pressure and the Mach number at this location. What is the throat area? What is the mass flow rate?

**Given:** Data on converging nozzle; isentropic flow

**Find:** Pressure and Mach number; throat area; mass flow rate

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg}\cdot\text{K} \\k &= 1.4 \\A_1 &= 0.05 && \text{m}^2 \\T_1 &= 276.3 && \text{K} \\V_1 &= 200 && \text{m/s} \\p_{\text{atm}} &= 101 && \text{kPa}\end{aligned}$$

Equations and Computations:

$$\text{From } T_1 \text{ and Eq. 12.18} \quad c = \sqrt{kRT} \quad (12.18)$$

$$c_1 = 333 \quad \text{m/s}$$

$$\text{Then} \quad M_1 = 0.60$$

To find the pressure, we first need the stagnation pressure.

If the flow is just choked

$$p_e = p_{\text{atm}} = p^* = 101 \quad \text{kPa}$$

From  $p_e = p^*$  and Eq. 12.22a

$$\frac{p_0}{p^*} = \left[ \frac{k+1}{2} \right]^{k/(k-1)} \quad (12.22a)$$

$$p_0 = 191 \quad \text{kPa}$$

From  $M_1$  and  $p_0$ , and Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$\text{Then} \quad p_1 = 150 \quad \text{kPa}$$

The mass flow rate is  $m_{\text{rate}} = \rho_1 A_1 V_1$

Hence, we need  $\rho_1$  from the ideal gas equation.

$$\rho_1 = 1.89 \text{ kg/m}^3$$

The mass flow rate  $m_{\text{rate}}$  is then

$$m_{\text{rate}} = 18.9 \text{ kg/s}$$

The throat area  $A_t = A^*$  because the flow is choked.

From  $M_1$  and  $A_1$ , and Eq. 13.7d

(using built-in function  $IsenA(M, k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)} \quad (13.7d)$$

$$A^* = 0.0421 \text{ m}^2$$

Hence

$$A_t = 0.0421 \text{ m}^2$$

# Problem 13.26

[Difficulty: 2]

13.26 A converging nozzle is connected to a large tank that contains compressed air at 15°C. The nozzle exit area is 0.001 m<sup>2</sup>. The exhaust is discharged to the atmosphere. To obtain a satisfactory shadow photograph of the flow pattern leaving the nozzle exit, the pressure in the exit plane must be greater than 325 kPa (gage). What pressure is required in the tank? What mass flow rate of air must be supplied if the system is to run continuously? Show static and stagnation state points on a *Ts* diagram.

Solution:

Basic equations:  $\dot{m} = \rho AV$        $P = \rho RT$   
 Computing equations:  $\frac{P_0}{P} = \left[1 + \frac{k-1}{2} M^2\right]^{\frac{k}{k-1}}$        $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$

Assumptions: (1) steady flow      (3) uniform flow at a section  
 (2) isentropic flow      (4) ideal gas behavior

Since  $P_e > P_b$ , nozzle is choked and  $M_e = 1.0$

$$P_0 = P_e \left[1 + \frac{k-1}{2} M_e^2\right]^{\frac{k}{k-1}} = 426 \text{ psia} [1 + 0.2]^{3.5} = 806 \text{ kPa} \leftarrow P_0$$


$$\frac{T_0}{T_e} = 1 + \frac{k-1}{2} M_e^2 \quad \therefore T_e = \frac{T_0}{1.2} = \frac{288 \text{ K}}{1.2} = 240 \text{ K}$$

$$V_e = c_e = (kRT_e)^{1/2} = \left[1.4 \times 287 \frac{\text{J}}{\text{kg}\cdot\text{K}} \times 240 \text{ K} + \frac{\text{N}\cdot\text{m}}{\text{J}} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right]^{1/2} = 311 \text{ m/s}$$

$$\rho_e = \frac{P_e}{RT_e} = 426 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg}}{287 \text{ J}} \times \frac{1}{240 \text{ K}} \times \frac{\text{J}}{\text{N}\cdot\text{m}} = 6.18 \text{ kg/m}^3$$

Then,  $\dot{m} = \rho_e V_e A_e = 6.18 \frac{\text{kg}}{\text{m}^3} \times 311 \frac{\text{m}}{\text{s}} \times 0.001 \text{ m}^2 = 1.92 \text{ kg/s}$

For steady flow,  $\dot{m} = 1.92 \text{ kg/s}$  must be supplied to the tank  $\leftarrow \dot{m}$



The corresponding volume flow rate of standard air is

$$Q = \frac{\dot{m}}{\rho_{\text{std}}} = 1.92 \frac{\text{kg}}{\text{s}} \times \frac{\text{m}^3}{1.2 \text{ kg}} = 1.6 \text{ m}^3/\text{s}$$

$$Q = 0.31 \text{ m}^3/\text{s}$$

### Problem 13.27

[Difficulty: 2]

13.27 Air, with  $p_0 = 650$  kPa (abs) and  $T_0 = 350$  K, flows isentropically through a converging nozzle. At the section in the nozzle where the area is  $2.6 \times 10^{-3}$  m<sup>2</sup>, the Mach number is 0.5. The nozzle discharges to a back pressure of 270 kPa (abs). Determine the exit area of the nozzle.

Solution:

Computing equations:

$$p_0/p = \left[ 1 + \frac{\gamma-1}{2} M^2 \right]^{\gamma/(\gamma-1)}$$


$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{\gamma-1}{2} M^2}{1 - \frac{\gamma-1}{2} M^2} \right]^{(\gamma+1)/(2(\gamma-1))} \quad (12.6)$$

Assumptions: (1) steady flow  
 (2) isentropic flow in nozzle  
 (3) uniform flow at a section  
 (4) ideal gas

Since  $p_0/p_0 = \frac{270 \text{ kPa}}{650 \text{ kPa}} = 0.415 < 0.528$ , the nozzle is choked and  $M_e = 1.0$

From Eq 12.6 with  $M_1 = 0.5$ ,  $A_1/A^* = 1.340$

Then  $A_e = A^* = A_1 / 1.340 = \frac{2.6 \times 10^{-3} \text{ m}^2}{1.340} = 1.94 \times 10^{-3} \text{ m}^2 \leftarrow A_e$



## Problem 13.28

[Difficulty: 3]

**13.28** Air flows through a converging duct. At the entrance, the static temperature is  $450^\circ\text{R}$ , the static pressure is 45 psia, the stagnation pressure is 51 psia, and the area is  $4\text{ ft}^2$ . At the exit, the area is  $3\text{ ft}^2$ . Assuming isentropic flow through the duct, what are the exit temperature and the mass flow rate of air through the duct?

**Given:** Data on flow in a passage

**Find:** Exit temperature and mass flow rate of air assuming isentropic flow

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft}\cdot\text{lbf}/\text{lbm}\cdot^\circ\text{R} \\k &= 1.4 \\T_1 &= 450 && ^\circ\text{R} \\p_1 &= 45 && \text{psia} \\p_{01} &= 51 && \text{psia} \\A_1 &= 4 && \text{ft}^2 \\A_2 &= 3 && \text{ft}^2\end{aligned}$$

Equations and Computations:

From the static and stagnation pressures we can calculate  $M_1$ :

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$

$$M_1 = 0.427$$

From the  $M_1$  and  $T_1$  we can get  $T_{01}$ :

$$T_{01} = 466.38 \quad ^\circ\text{R}$$

From  $M_1$ , and Eq. 13.7d

(using built-in function  $IsenA(M, k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)}$$

$$A_1^* = 2.649 \quad \text{ft}^2$$

For isentropic flow ( $p_{02} = p_{01}$ ,  $T_{02} = T_{01}$ ,  $A_2^* = A_1^*$ )

$$p_{02} = 51 \quad \text{psia}$$

$$T_{02} = 466.38 \quad ^\circ\text{R}$$

$$A_2^* = 2.649 \quad \text{ft}^2$$

$$A_2/A_2^* = 1.1325$$

Given subsonic flow in the duct, we can find the exit Mach number using Equation 13.7d

$$M_2 = 0.653$$

From the Mach number and stagnation state we can calculate the static pressure and temperature:

$$\begin{aligned} p_2 &= 38.28 \text{ psia} \\ T_2 &= 430 \text{ }^\circ\text{R} \end{aligned}$$

From  $T_2$  and Eq. 12.18

$$c = \sqrt{kRT}$$

$$\begin{aligned} c_2 &= 1016.38 \text{ ft/s} \\ V_2 &= 664.11 \text{ ft/s} \end{aligned}$$

Using the ideal gas law we calculate the density at station 2:

$$\rho_2 = 0.2406 \text{ lbm/ft}^3$$

Now we can use the area, density, and velocity to calculate the mass flow rate:

$$m = 479 \text{ lbm/s}$$

## Problem 13.29

[Difficulty: 2]

**13.29** Air at  $0^\circ\text{C}$  is contained in a large tank on the space shuttle. A converging section with exit area  $1 \times 10^{-3} \text{ m}^2$  is attached to the tank, through which the air exits to space at a rate of 2 kg/s. What are the pressure in the tank, and the pressure, temperature, and speed at the exit?

**Given:** Temperature in and mass flow rate from a tank

**Find:** Tank pressure; pressure, temperature and speed at exit

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg.K} \\ k &= 1.4 \\ T_0 &= 273 && \text{K} \\ A_t &= 0.001 && \text{m}^2 \\ m_{\text{rate}} &= 2 && \text{kg/s} \end{aligned}$$

Equations and Computations:

Because  $p_b = 0$   
Hence the flow is choked!

$$p_e = p^*$$

Hence

$$T_e = T^*$$

From  $T_0$ , and Eq. 12.22b

$$\frac{T_0}{T^*} = \frac{k+1}{2} \quad (12.22b)$$

$$T^* = 228 \quad \text{K}$$

$$\begin{aligned} T_e &= 228 && \text{K} \\ &= -45.5 && ^\circ\text{C} \end{aligned}$$

Also  $M_e = 1$   
Hence  $V_e = V^* = c_e$

From  $T_e$  and Eq. 12.18  $c = \sqrt{kRT}$  (12.18)

$c_e = 302 \text{ m/s}$

Then  $V_e = 302 \text{ m/s}$

To find the exit pressure we use the ideal gas equation after first finding the exit density.

The mass flow rate is  $m_{\text{rate}} = \rho_e A_e V_e$

Hence  $\rho_e = 6.62 \text{ kg/m}^3$

From the ideal gas equation  $p_e = \rho_e R T_e$

$p_e = 432 \text{ kPa}$

From  $p_e = p^*$  and Eq. 12.22a

$$\frac{p_0}{p^*} = \left[ \frac{k+1}{2} \right]^{k/(k-1)} \quad (12.22a)$$

$p_0 = 817 \text{ kPa}$

We can check our results:

From  $p_0, T_0, A_t$ , and Eq. 13.9a

$$\dot{m}_{\text{choked}} = A_e p_0 \sqrt{\frac{k}{RT_0}} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)} \quad (13.9a)$$

Then  $m_{\text{choked}} = 2.00 \text{ kg/s}$   
 $m_{\text{choked}} = m_{\text{rate}} \text{ Correct!}$

### Problem 13.30

[Difficulty: 2]

**13.30** A large tank supplies air to a converging nozzle that discharges to atmospheric pressure. Assume the flow is reversible and adiabatic. For what range of tank pressures will the flow at the nozzle exit be sonic? If the tank pressure is 600 kPa (abs) and the temperature is 600 K, determine the mass flow rate through the nozzle, if the exit area is  $1.29 \times 10^{-3} \text{ m}^2$ .

Solution:

Basic equations:  $\dot{m} = \rho VA = \text{const}$

$P = \rho RT$

Computing equations:  $\frac{T_0}{T} = 1 + \frac{\gamma-1}{2} M^2$

$\frac{P_0}{P} = \left[ 1 + \frac{\gamma-1}{2} M^2 \right]^{\frac{\gamma}{\gamma-1}}$

Assumptions: (1) steady flow

(3) uniform flow at a section

(2) isentropic flow in nozzle

(4) ideal gas

The nozzle will be choked, i.e.  $M_L = 1.0$  for  $P_b/P_0 \leq 0.528$

Since  $P_b = 101 \text{ kPa}$ , nozzle is choked for

$$P_0 \geq \frac{P_b}{0.528} = \frac{101 \text{ kPa}}{0.528} = 191 \text{ kPa} \leftarrow P_0$$

Thus for  $P_0 = 600 \text{ kPa}$ ,  $M_L = 1.0$


$$\frac{T_0}{T} = 1 + \frac{\gamma-1}{2} M^2 \quad ; \quad T_L = \frac{T_0}{1 + \frac{\gamma-1}{2} M_L^2} = \frac{600 \text{ K}}{1 + 0.2(1.0)^2} = 500 \text{ K}$$

$$V_L = M_L c_L = M_L \sqrt{\gamma R T_L} = 1.0 \sqrt{1.4 \frac{287 \text{ N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 500 \text{ K}} = 448 \text{ m/s}$$

$$\frac{P_0}{P_L} = \left[ 1 + \frac{\gamma-1}{2} M_L^2 \right]^{\frac{\gamma}{\gamma-1}} \quad ; \quad P_L = \frac{P_0}{\left[ 1 + \frac{\gamma-1}{2} M_L^2 \right]^{\frac{\gamma}{\gamma-1}}} = \frac{600 \text{ kPa}}{\left[ 1 + 0.2(1.0)^2 \right]^{\frac{1.4}{0.4}}} = 317 \text{ kPa}$$

$$\rho_L = \frac{P_L}{RT_L} = 317 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{1 \text{ kg}\cdot\text{K}}{287 \text{ N}\cdot\text{m}} \times \frac{1}{500 \text{ K}} = 2.21 \frac{\text{kg}}{\text{m}^3}$$

Finally,  $\dot{m} = \rho_L V_L A_L = 2.21 \frac{\text{kg}}{\text{m}^3} \times 448 \frac{\text{m}}{\text{s}} \times 1.29 \times 10^{-3} \text{ m}^2 = 1.28 \text{ kg/s} \leftarrow \dot{m}$



## Problem 13.31

[Difficulty: 3]

---

**13.31** Nitrogen is stored in a large chamber at 450 K and 150 kPa. The gas leaves the chamber through a converging-only nozzle with an outlet area of 30 cm<sup>2</sup>. The ambient room pressure is 100 kPa, and the flow through the nozzle is isentropic. What is the mass flow rate of the nitrogen? If the room pressure could be lowered, what is the maximum possible mass flow rate for the nitrogen?

---

**Given:** Temperature and pressure in a tank; nozzle with specific area

**Find:** Mass flow rate of gas; maximum possible flow rate

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 296.8 && \text{J/kg}\cdot\text{K} \\k &= 1.4 \\T_0 &= 450 && \text{K} \\p_0 &= 150 && \text{kPa} \\A_t &= 30 && \text{cm}^2 \\A_t &= 0.003 && \text{m}^2 \\p_b &= 100 && \text{kPa}\end{aligned}$$

Equations and Computations:

Assuming that the nozzle exit pressure is the back pressure:

$$p_e = 100 \quad \text{kPa}$$

Then the nozzle exit Mach number is:

$$M_e = 0.7837$$

This nozzle is not choked. The exit temperature is:

$$T_e = 400.78 \quad \text{K}$$

From  $T_e$  and Eq. 12.18

$$c = \sqrt{kRT} \quad (12.18)$$

$$c_e = 408.08 \quad \text{m/s}$$

Then

$$V_e = 319.80 \quad \text{m/s}$$

From the ideal gas equation of state, we can calculate the density:

$$\rho_e = 0.8407 \quad \text{kg/m}^3$$

Therefore the mass flow rate is:

$$m = 0.807 \quad \text{kg/s}$$

When the room pressure can be lowered, we can choke the nozzle.

$$\begin{aligned}p_e &= p^* \\T_e &= T^*\end{aligned}$$

From  $T_0$ , and Eq. 12.22b

$$\frac{T_0}{T^*} = \frac{k+1}{2} \quad (12.22b)$$

$$\begin{aligned} T^* &= 375 \quad \text{K} \\ p^* &= 79.24 \quad \text{kPa} \end{aligned}$$

$$T_e = 375 \quad \text{K}$$

Also

$$M_e = 1$$

Hence

$$V_e = V^* = c_e$$

From  $T_e$  and Eq. 12.18

$$c = \sqrt{kRT} \quad (12.18)$$

$$c_e = 395 \quad \text{m/s}$$

Then

$$V_e = 395 \quad \text{m/s}$$

To find the mass flow rate we calculate the density from the ideal gas equation of state:

$$\text{Hence} \quad \rho_e = 0.7120 \quad \text{kg/m}^3$$

Therefore the mass flow rate is:

$$m_{\max} = 0.843 \quad \text{kg/s}$$

We can check our results:

From  $p_0$ ,  $T_0$ ,  $A_t$ , and Eq. 13.9a

$$\dot{m}_{\text{choked}} = A_e p_0 \sqrt{\frac{k}{RT_0} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)}} \quad (13.9a)$$

Then

$$m_{\text{choked}} = 0.843 \quad \text{kg/s}$$

$$m_{\text{choked}} = m_{\text{rate}} \quad \text{Correct!}$$

## Problem 13.32

[Difficulty: 2]

**13.32** A large tank initially is evacuated to  $-10$  kPa (gage). (Ambient conditions are 101 kPa at  $20^\circ\text{C}$ .) At  $t = 0$ , an orifice of 5 mm diameter is opened in the tank wall; the vena contracta area is 65 percent of the geometric area. Calculate the mass flow rate at which air initially enters the tank. Show the process on a  $Ts$  diagram. Make a schematic plot of mass flow rate as a function of time. Explain why the plot is nonlinear.

**Given:** Isentropic air flow into a tank

**Find:** Initial mass flow rate;  $Ts$  process; explain nonlinear mass flow rate

**Solution:**

Basic equations:	$\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$	$\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$	$m_{\text{rate}} = \rho \cdot A \cdot V$
Given or available data	$p_0 = 101 \cdot \text{kPa}$	$p_b = p_0 - 10 \cdot \text{kPa}$	$p_b = 91 \cdot \text{kPa}$
	$k = 1.4$	$R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$	$D = 5 \cdot \text{mm}$
Then	$A = \frac{\pi}{4} \cdot D^2$	$A_{\text{vena}} = 65\% \cdot A$	$A_{\text{vena}} = 12.8 \cdot \text{mm}^2$
The flow will be choked if $p_b/p_0 < 0.528$	$\frac{p_b}{p_0} = 0.901$	(Not choked)	$T_0 = (20 + 273) \cdot \text{K}$
Hence	$\frac{p_0}{p_{\text{vena}}} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$	where	$p_{\text{vena}} = p_b$
so	$M_{\text{vena}} = \sqrt{\frac{2}{k-1} \left[ \left(\frac{p_0}{p_{\text{vena}}}\right)^{\frac{k-1}{k}} - 1 \right]}$		$p_{\text{vena}} = 91 \cdot \text{kPa}$
Then	$T_{\text{vena}} = \frac{T_0}{1 + \frac{k-1}{2} \cdot M_{\text{vena}}^2}$	$M_{\text{vena}} = 0.389$	$T_{\text{vena}} = 284 \text{ K}$
Then	$c_{\text{vena}} = \sqrt{k \cdot R \cdot T_{\text{vena}}}$		$T_{\text{vena}} = 11.3 \cdot ^\circ\text{C}$
and	$V_{\text{vena}} = M_{\text{vena}} \cdot c_{\text{vena}}$		$c_{\text{vena}} = 338 \frac{\text{m}}{\text{s}}$
Also	$\rho_{\text{vena}} = \frac{p_{\text{vena}}}{R \cdot T_{\text{vena}}}$		$V_{\text{vena}} = 131 \frac{\text{m}}{\text{s}}$
Finally	$m_{\text{rate}} = \rho_{\text{vena}} \cdot A_{\text{vena}} \cdot V_{\text{vena}}$		$\rho_{\text{vena}} = 1.12 \frac{\text{kg}}{\text{m}^3}$
			$m_{\text{rate}} = 1.87 \times 10^{-3} \frac{\text{kg}}{\text{s}}$

The  $Ts$  diagram will be a vertical line ( $T$  decreases and  $s = \text{const}$ ). After entering the tank there will be turbulent mixing ( $s$  increases) and the flow comes to rest ( $T$  increases). The mass flow rate versus time will look like the curved part of Fig. 13.6b; it is nonlinear because  $V$  AND  $\rho$  vary

## Problem 13.33

[Difficulty: 3]

**13.33** A 50-cm-diameter spherical cavity initially is evacuated. The cavity is to be filled with air for a combustion experiment. The pressure is to be 45 kPa (abs), measured after its temperature reaches  $T_{\text{atm}}$ . Assume the valve on the cavity is a converging nozzle with throat diameter of 1 mm, and the surrounding air is at standard conditions. For how long should the valve be opened to achieve the desired final pressure in the cavity? Calculate the entropy change for the air in the cavity.

**Given:** Spherical cavity with valve

**Find:** Time to reach desired pressure; Entropy change

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$

$p = \rho \cdot R \cdot T$        $c = \sqrt{k \cdot R \cdot T}$        $m_{\text{rate}} = \rho \cdot A \cdot V$        $m_{\text{choked}} = A_t \cdot p_0 \cdot \sqrt{\frac{k}{R \cdot T_0} \cdot \left(\frac{2}{k+1}\right)^{\frac{k+1}{2 \cdot (k-1)}}$

Given or available data     $p_0 = 101 \cdot \text{kPa}$        $T_{\text{atm}} = (20 + 273) \cdot \text{K}$        $T_0 = T_{\text{atm}}$        $d = 1 \cdot \text{mm}$        $D = 50 \cdot \text{cm}$

$p_f = 45 \cdot \text{kPa}$        $T_f = T_{\text{atm}}$        $k = 1.4$        $R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $c_p = 1004 \frac{\text{J}}{\text{kg} \cdot \text{K}}$

Then the inlet area is     $A_t = \frac{\pi}{4} \cdot d^2$        $A_t = 0.785 \cdot \text{mm}^2$       and tank volume is  $V = \frac{\pi}{3} \cdot D^3$        $V = 0.131 \cdot \text{m}^3$

The flow will be choked if  $p_b/p_0 < 0.528$ ; the MAXIMUM back pressure is  $p_b = p_f$       so       $\frac{p_b}{p_0} = 0.446$       (Choked)

The final density is     $\rho_f = \frac{p_f}{R \cdot T_f}$        $\rho_f = 0.535 \frac{\text{kg}}{\text{m}^3}$       and final mass is  $M = \rho_f \cdot V$        $M = 0.0701 \text{ kg}$

Since the mass flow rate is constant (flow is always choked)       $M = m_{\text{rate}} \cdot \Delta t$       or       $\Delta t = \frac{M}{m_{\text{rate}}}$

We have choked flow so  $m_{\text{rate}} = A_t \cdot p_0 \cdot \sqrt{\frac{k}{R \cdot T_0} \cdot \left(\frac{2}{k+1}\right)^{\frac{k+1}{2 \cdot (k-1)}}$        $m_{\text{rate}} = 1.873 \times 10^{-4} \frac{\text{kg}}{\text{s}}$

Hence       $\Delta t = \frac{M}{m_{\text{rate}}}$        $\Delta t = 374 \text{ s}$        $\Delta t = 6.23 \cdot \text{min}$

The air in the tank will be cold when the valve is closed. Because  $\rho = M/V$  is constant,  $p = \rho RT = \text{const} \times T$ , so as the temperature rises to ambient, the pressure will rise too.

For the entropy change during the charging process is given by  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$  where  $T_1 = T_{\text{atm}}$      $T_2 = T_{\text{atm}}$

and     $p_1 = p_0$        $p_2 = p_f$       Hence       $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R \cdot \ln\left(\frac{p_2}{p_1}\right)$        $\Delta s = 232 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

### Problem 13.34

[Difficulty: 3]

13.34 Air flows isentropically through a converging nozzle attached to a large tank, where the absolute pressure is 171 kPa and the temperature is 27°C. At the inlet section the Mach number is 0.2. The nozzle discharges to the atmosphere; the discharge area is 0.015 m<sup>2</sup>. Determine the magnitude and direction of the force that must be applied to hold the nozzle in place.

Solution:

Basic equations:  $F_{Rx} = P_1 A_1 - P_2 A_2 - P_{atm} (A_1 - A_2) - R_x = \dot{m} (V_2 - V_1)$   
 $\dot{m} = \rho VA = \text{const}$        $P = \rho RT$

Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$        $\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}$

Assumptions: (1) steady flow      (3) uniform flow at a section  
 (2) isentropic flow      (4) ideal gas

$$M_2 = \left\{ \frac{2}{k-1} \left[ \left( \frac{P_0}{P_2} \right)^{\frac{k-1}{k}} - 1 \right] \right\}^{1/2} = \left\{ \frac{2}{0.4} \left[ \left( \frac{171}{101} \right)^{0.286} - 1 \right] \right\}^{1/2} = 0.901 \quad \text{Hence flow not choked}$$

$$T_2 = T_0 / \left[ 1 + \frac{k-1}{2} M_2^2 \right] = 300 \text{ K} / \left[ 1 + 0.2(0.901)^2 \right] = 258 \text{ K}$$

$$V_2 = M_2 c_2 = M_2 (kRT_2)^{1/2} = 0.901 \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 258 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right)^{1/2} = 290 \text{ m/s}$$

$$\rho_2 = \frac{P_2}{RT_2} = 101 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg}\cdot\text{K}}{287 \text{ N}\cdot\text{m}} \times \frac{1}{258 \text{ K}} = 1.36 \text{ kg/m}^3$$

$$\dot{m} = \rho_2 V_2 A_2 = 1.36 \frac{\text{kg}}{\text{m}^3} \times 290 \frac{\text{m}}{\text{s}} \times 0.015 \text{ m}^2 = 5.92 \text{ kg/s}$$

$$T_1 = T_0 / \left[ 1 + \frac{k-1}{2} M_1^2 \right] = 300 \text{ K} / \left[ 1 + 0.2(0.2)^2 \right] = 298 \text{ K}$$

$$V_1 = M_1 c_1 = M_1 (kRT_1)^{1/2} = 0.2 \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 298 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right)^{1/2} = 69.2 \text{ m/s}$$

$$P_1 = P_0 / \left[ 1 + \frac{k-1}{2} M_1^2 \right]^{\frac{k}{k-1}} = 171 \text{ kPa} / \left[ 1 + 0.2(0.2)^2 \right]^{2.5} = 166 \text{ kPa}$$


$$\rho_1 = \frac{P_1}{RT_1} = 166 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg}\cdot\text{K}}{287 \text{ N}\cdot\text{m}} \times \frac{1}{298 \text{ K}} = 1.94 \text{ kg/m}^3$$

$$A_1 = \dot{m} / \rho_1 V_1 = 5.92 \frac{\text{kg}}{\text{s}} \times \frac{\text{m}^3}{1.94 \text{ kg}} \times \frac{\text{s}}{69.2 \text{ m}} = 0.0441 \text{ m}^2$$

$$R_x = P_1 A_1 - P_2 A_2 - P_{atm} (A_1 - A_2) - \dot{m} (V_2 - V_1) = P_1 A_1 - P_2 A_2 - \dot{m} (V_2 - V_1)$$

$$= (166 - 101) \times 10^3 \frac{\text{N}}{\text{m}^2} \times 0.0441 \text{ m}^2 - 5.92 \frac{\text{kg}}{\text{s}} (290 - 69.2) \frac{\text{m}}{\text{s}} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}}$$

$$R_x = 1560 \text{ N} \quad (\text{to the left})$$



$R_x$

# Problem 13.35

[Difficulty: 3]

**13.35** Consider a "rocket cart" propelled by a jet supplied from a tank of compressed air on the cart. Initially, air in the tank is at 1.3 MPa (abs) and 20°C, and the mass of the cart and tank is  $M_0 = 25$  kg. The air exhausts through a converging nozzle with exit area  $A_e = 30$  mm<sup>2</sup>. Rolling resistance of the cart is  $F_R = 6$  N; aerodynamic resistance is negligible. For the instant after air begins to flow through the nozzle: (a) compute the pressure in the nozzle exit plane, (b) evaluate the mass flow rate of air through the nozzle, and (c) calculate the acceleration of the tank and cart assembly.

Solution: Assume steady, one-dimensional flow of an ideal gas.

Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$ ;  $\frac{p_0}{p} = (1 + \frac{k-1}{2} M^2)^{\frac{k}{k-1}}$ ;  $c = \sqrt{kRT}$ ;  $p = \rho RT$

Check for choking:  $\frac{p_{atm}}{p_0} = \frac{101 \times 10^3}{1.3 \times 10^6} = 0.0777 < 0.528$ , so Choked.  $M_e = 1$

Thus  $T_e = \frac{T_0}{1 + \frac{k-1}{2} M_e^2} = \frac{(273+20)K}{1 + \frac{1.4-1}{2}} = 244 K$

$p_e = \frac{p_0}{(1 + \frac{k-1}{2} M_e^2)^{\frac{k}{k-1}}} = \frac{1.3 \times 10^6 Pa}{(1.2)^{3.5}} = \frac{1.3 \times 10^6 Pa}{(1.2)^{3.5}} = 687 kPa (abs)$   $p_e$


$\dot{m} = \rho_e V_e A_e$ ;  $\rho_e = \frac{p_e}{RT_e} = \frac{687 \times 10^3 N/m^2}{287 N \cdot m / kg \cdot K} \times \frac{1}{244 K} = 9.81 kg/m^3$

$V_e = M_e c_e = c_e = \sqrt{kRT_e} = \left[ 1.4 \times 287 \frac{N \cdot m}{kg \cdot K} \times 244 K \times \frac{kg \cdot m}{N \cdot s^2} \right]^{1/2} = 313 m/s$

$\dot{m} = 9.81 \frac{kg}{m^3} \times 313 \frac{m}{s} \times 30 \times 10^{-6} m^2 = 0.0921 kg/s$   $\dot{m}$

Apply momentum to find acceleration of assembly.

Basic equation:  $F_{sx} + F_{Bx} - \int_{CV} a_{rfx} \rho dV = \frac{d}{dt} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{v} \cdot d\vec{A}$




Assume: (4) Horizontal; (5)  $u \approx 0$  within CV; (5) Uniform flow at exit.

Then  $-F_R + (p_e - p_{atm}) A_e - M a_{rfx} = u_e \{ \dot{m} \} = -V_e \dot{m}$

$u_e = -V_e$

$a_{rfx} = \frac{V_e \dot{m} - F_R + (p_e - p_{atm}) A_e}{M} = \left[ \frac{313 \frac{m}{s} \times 0.0921 \frac{kg}{s} - 6 N + (687 - 101) \frac{N}{m^2} \times 30 \times 10^{-6} m^2}{25 kg} \right] \times \frac{1}{25 kg} = 1.62 m/s^2$   $a_{rfx}$



### Problem 13.36

[Difficulty: 3]

**13.36** A stream of air flowing in a duct ( $A = 5 \times 10^{-4} \text{ m}^2$ ) is at  $p = 300 \text{ kPa}$  (abs), has  $M = 0.5$ , and flows at  $\dot{m} = 0.25 \text{ kg/s}$ . Determine the local isentropic stagnation temperature. If the cross-sectional area of the passage were reduced downstream, determine the maximum percentage reduction of area allowable without reducing the flow rate (assume isentropic flow). Determine the speed and pressure at the minimum area location.

Solution:

Basic equations:  $\dot{m} = \rho VA$        $P = \rho RT$

Computing equations:  $\frac{T_0}{T} = 1 + \frac{\gamma-1}{2} M^2$        $\frac{P_0}{P} = \left[1 + \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}}$   
 $\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{\gamma-1}{2} M^2}{1 + \frac{\gamma-1}{2}} \right]^{\frac{\gamma+1}{2(\gamma-1)}} \quad (12.7d)$

- Assumptions: (1) steady flow      (3) uniform flow at a section  
 (2) isentropic flow      (4) ideal gas

To determine  $T_0$ , we first need to find  $T_1$ .

$$\dot{m} = \rho_1 V_1 A_1 = \frac{P_1}{RT_1} M_1 c_1 A_1 = \frac{P_1}{RT_1} M_1 \left(\frac{R T_1}{\gamma}\right)^{1/2} A_1 = P_1 M_1 A_1 \left(\frac{R}{\gamma T_1}\right)^{1/2}$$

Solving for  $T_1$ ,

$$T_1 = \frac{R}{\gamma} \left( \frac{P_1 M_1 A_1}{\dot{m}} \right)^2 = 1.4 \times \frac{287 \text{ J}}{\text{kg} \cdot \text{K}} \left[ \frac{300 \times 10^3 \text{ N/m}^2 \times 0.5 \times 5 \times 10^{-4} \text{ m}^2}{0.25 \text{ kg/s}} \right]^2 \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}$$

$$T_1 = 439 \text{ K}$$

$$T_0 = T_1 \left[ 1 + \frac{\gamma-1}{2} M_1^2 \right] = 439 \text{ K} \left[ 1 + 0.2(0.5)^2 \right] = 461 \text{ K} \quad \leftarrow T_0$$

Maximum area reduction occurs where  $M_2 = 1$ .

For  $M_1 = 0.5$ , from Eq. 12.7d  $A_1/A^* = 1.34 \therefore A^* = A_2 = \frac{A_1}{1.34} = 3.73 \times 10^{-4} \text{ m}^2$

$$\% \Delta A = \frac{A_2 - A_1}{A_1} \times 100 = \frac{3.73 - 5}{5} \times 100 = -25.4\% \quad \leftarrow \% \Delta A$$


$$T_2 = T_0 / \left[ 1 + \frac{\gamma-1}{2} M_2^2 \right] = 461 \text{ K} / \left[ 1 + 0.2(1)^2 \right] = 384 \text{ K}$$

$$V_2 = M_2 c_2 = M_2 \left(\frac{R T_2}{\gamma}\right)^{1/2} = 1.10 \left( 1.4 \times 287 \frac{\text{J}}{\text{kg} \cdot \text{K}} \times 384 \text{ K} \right)^{1/2} \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}$$

$$V_2 = 393 \text{ m/s} \quad \leftarrow V_2$$

$$P_{01} = P_{02} = P_1 \left[ 1 + \frac{\gamma-1}{2} M_1^2 \right]^{\frac{\gamma}{\gamma-1}} = 300 \text{ kPa} \left[ 1 + 0.2(0.5)^2 \right]^{3.5} = 356 \text{ kPa}$$

$$P_2 = P_{02} / \left[ 1 + \frac{\gamma-1}{2} M_2^2 \right]^{\frac{\gamma}{\gamma-1}} = 356 \text{ kPa} / \left[ 1 + 0.2(1)^2 \right]^{3.5} = 188 \text{ kPa} \quad \leftarrow P_2$$



## Problem 13.37

[Difficulty: 3]

**13.37** An air-jet-driven experimental rocket of 25 kg mass is to be launched from the space shuttle into space. The temperature of the air in the rocket's tank is 125°C. A converging section with exit area 25 mm<sup>2</sup> is attached to the tank, through which the air exits to space at a rate of 0.05 kg/s. What is the pressure in the tank, and the pressure, temperature, and air speed at the exit when the rocket is first released? What is the initial acceleration of the rocket?

**Given:** Air-driven rocket in space

**Find:** Tank pressure; pressure, temperature and speed at exit; initial acceleration

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg}\cdot\text{K} \\k &= 1.4 \\T_0 &= 398 && \text{K} \\A_t &= 25 && \text{mm}^2 \\M &= 25 && \text{kg} \\m_{\text{rate}} &= 0.05 && \text{kg/s}\end{aligned}$$

Equations and Computations:

Because  $p_b = 0$   
Hence the flow is choked!

$$p_e = p^*$$

Hence

$$T_e = T^*$$

From  $T_0$ , and Eq. 12.22b

$$\frac{T_0}{T^*} = \frac{k+1}{2} \quad (12.22b)$$

$$T^* = 332 \quad \text{K}$$

$$\begin{aligned}T_e &= 332 && \text{K} \\&= 58.7 && ^\circ\text{C}\end{aligned}$$

Also

$$M_e = 1$$

Hence

$$V_e = V^* = c_e$$

From  $T_e$  and Eq. 12.18

$$c = \sqrt{kRT} \quad (12.18)$$

$$c_e = 365 \quad \text{m/s}$$

Then

$$V_e = 365 \quad \text{m/s}$$

To find the exit pressure we use the ideal gas equation after first finding the exit density.

The mass flow rate is  $m_{\text{rate}} = \rho_e A_e V_e$

Hence  $\rho_e = 0.0548 \text{ kg/m}^3$

From the ideal gas equation  $p_e = \rho_e R T_e$

$p_e = 5.21 \text{ kPa}$

From  $p_e = p^*$  and Eq. 12.22a

$$\frac{p_0}{p^*} = \left[ \frac{k+1}{2} \right]^{k/(k-1)} \quad (12.22a)$$

$p_0 = 9.87 \text{ kPa}$

We can check our results:

From  $p_0, T_0, A_t$ , and Eq. 13.9a

$$\dot{m}_{\text{choked}} = A_e p_0 \sqrt{\frac{k}{RT_0}} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)} \quad (13.9a)$$

Then  $m_{\text{choked}} = 0.050 \text{ kg/s}$   
 $m_{\text{choked}} = m_{\text{rate}} \text{ Correct!}$

The initial acceleration is given by:

$$\vec{F} - \int_{\text{CV}} \vec{a}_{\text{rf}} \rho \, d\mathcal{V} = \frac{\partial}{\partial t} \int_{\text{CV}} \vec{V}_{\text{xyz}} \rho \, d\mathcal{V} + \int_{\text{CS}} \vec{V}_{\text{xyz}} \rho \vec{V}_{\text{xyz}} \cdot d\vec{A} \quad (4.33)$$

which simplifies to:  $p_e A_t - M a_x = m_{\text{rate}} V$  or:  $a_x = \frac{m_{\text{rate}} V + p_e A_t}{M}$

$a_x = 1.25 \text{ m/s}^2$

## Problem 13.38

[Difficulty: 3]

**13.38** Air enters a converging-diverging nozzle at 2 MPa (abs) and 313 K. At the exit of the nozzle, the pressure is 200 kPa (abs). Assume adiabatic, frictionless flow through the nozzle. The throat area is 20 cm<sup>2</sup>. What is the area at the nozzle exit? What is the mass flow rate of the air?

**Given:** Air flow through a converging-diverging nozzle

**Find:** Nozzle exit area and mass flow rate

**Solution:**

The given or available data is:

$R =$	286.9	J/kg-K
$k =$	1.4	
$p_0 =$	2	MPa
$T_0 =$	313	K
$p_e =$	200	kPa
$A_t =$	20	cm <sup>2</sup>

Equations and Computations:

Using the stagnation to exit static pressure ratio, we can find the exit Mach number:  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$
$$M_e = 2.1572$$

From  $M_e$ , and Eq. 13.7d  
(using built-in function  $IsenA(M, k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)}$$
$$A_e/A^* = 1.9307$$

At the throat the flow is sonic, so  $A_t = A^*$ . Therefore:

$$A_e = 38.6 \text{ cm}^2$$

To find the mass flow rate at the exit, we will use the choked flow equation:  
From  $p_0$ ,  $T_0$ ,  $A_t$ , and Eq. 13.9a

$$\dot{m}_{\text{choked}} = A_e p_0 \sqrt{\frac{k}{RT_0}} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)} \quad (13.9a)$$
$$m = 17.646 \text{ kg/s}$$

## Problem 13.39

[Difficulty: 1]

---

**13.39** Hydrogen is expanded adiabatically, without friction from 100 psia, at 540°F, and at negligible velocity to 20 psia via a converging-diverging nozzle. What is the exit Mach number?

---

**Given:** Hydrogen flow through a converging-diverging nozzle

**Find:** Nozzle exit Mach number

**Solution:**

The given or available data is:

$R =$	766.5	ft-lbf/lbm-°R
$k =$	1.41	
$p_0 =$	100	psia
$T_0 =$	540	°F
$T_0 =$	1000	°R
$p_e =$	20	psia

Equations and Computations:

Using the stagnation to exit static pressure ratio, we can find the exit Mach number:  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$

$$M_e = 1.706$$

## Problem 13.40

[Difficulty: 3]

**13.40** A cylinder of gas used for welding contains helium at 20 MPa (gage) and room temperature. The cylinder is knocked over, its valve is broken off, and gas escapes through a converging passage. The minimum flow diameter is 10 mm at the outlet section where the gas flow is uniform. Find (a) the mass flow rate at which gas leaves the cylinder and (b) the instantaneous acceleration of the cylinder (assume the cylinder axis is horizontal and its mass is 65 kg). Show static and stagnation states and the process path on a  $Ts$  diagram.

**Given:** Gas cylinder with broken valve

**Find:** Mass flow rate; acceleration of cylinder

**Solution:**

Basic equations: 
$$\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2 \quad \frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}} \quad p = \rho \cdot R \cdot T \quad c = \sqrt{k \cdot R \cdot T} \quad m_{\text{rate}} = \rho \cdot A \cdot V$$

$$\vec{F}_S + \vec{F}_B - \int_{CV} \vec{a}_{rf} \rho \, dV = \frac{\partial}{\partial t} \int_{CV} \vec{V}_{xyz} \rho \, dV + \int_{CS} \vec{V}_{xyz} \rho \vec{V}_{xyz} \cdot d\vec{A} \quad (4.33)$$

Given or available data  $p_{\text{atm}} = 101 \cdot \text{kPa}$   $p_0 = 20 \cdot \text{MPa} + p_{\text{atm}} = 20.101 \text{ MPa}$   $T_0 = (20 + 273) \cdot \text{K}$

$$k = 1.66 \quad R = 2077 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}} \quad d = 10 \cdot \text{mm} \quad \text{so the nozzle area is} \quad A_e = \frac{\pi}{4} \cdot d^2 \quad A_e = 78.5 \cdot \text{mm}^2 \quad M_{CV} = 65 \cdot \text{kg}$$

The flow will be choked if  $p_b/p_0 < 0.528$ :  $p_b = p_{\text{atm}}$  so  $\frac{p_b}{p_0} = 5.025 \times 10^{-3}$  (Choked: Critical conditions)

The exit temperature is  $T_e = \frac{T_0}{\left(1 + \frac{k-1}{2}\right)}$   $T_e = 220 \text{ K}$   $T_e = -52.8 \cdot ^\circ\text{C}$   $c_e = \sqrt{k \cdot R \cdot T_e}$

The exit speed is  $V_e = c_e$   $V_e = 872 \frac{\text{m}}{\text{s}}$

The exit pressure is  $p_e = \frac{p_0}{\left(1 + \frac{k-1}{2}\right)^{\frac{k}{k-1}}}$   $p_e = 9.8 \cdot \text{MPa}$  and exit density is  $\rho_e = \frac{p_e}{R \cdot T_e}$   $\rho_e = 21 \frac{\text{kg}}{\text{m}^3}$

Then  $m_{\text{rate}} = \rho_e \cdot A_e \cdot V_e$   $m_{\text{rate}} = 1.468 \frac{\text{kg}}{\text{s}}$

The momentum equation (Eq. 4.33) simplifies to  $(p_e - p_{\text{atm}}) \cdot A_e - M_{CV} \cdot a_x = -V_e \cdot m_{\text{rate}}$

Hence  $a_x = \frac{(p_e - p_{\text{atm}}) \cdot A_e + V_e \cdot m_{\text{rate}}}{M_{CV}}$   $a_x = 31.4 \frac{\text{m}}{\text{s}^2}$

The process is isentropic, followed by nonisentropic expansion to atmospheric pressure

### Problem 13.41

[Difficulty: 3]

**13.41** A converging nozzle is bolted to the side of a large tank. Air inside the tank is maintained at a constant 50 psia and 100°F. The inlet area of the nozzle is 10 in.<sup>2</sup> and the exit area is 1 in.<sup>2</sup>. The nozzle discharges to the atmosphere. For isentropic flow in the nozzle, determine the total force on the bolts, and indicate whether the bolts are in tension or compression.

Solution:

$$\text{Basic equations: } F_{sx} = P_1 A_1 - P_2 A_2 - P_{atm}(A_1 - A_2) - R_x = \dot{m}(V_2 - V_1)$$

$$\dot{m} = \rho V A = \text{const}$$

$$P = \rho R T$$

$$\text{Computing equations: } \frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$$

$$\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}$$

Assumptions: (1) steady flow

$$(4) F_{2x} = 0$$

(2) isentropic flow in nozzle

$$(5) V_1 \neq 0$$

(3) uniform flow at a section

First check for choking

$$\frac{P_0}{P_0^*} = \frac{14.7}{50} = 0.294 < 0.528 \quad \text{and hence the nozzle is choked}$$

$$M_2 = 1.0 \quad \text{and} \quad P_2 = 0.528 P_0 = 0.528 (50 \text{ psia}) = 26.4 \text{ psia}$$

$$T_0 = T = 14 \frac{R}{2} M^2; \quad T_2 = T_0 / \left[ 1 + \frac{k-1}{2} M_2^2 \right] = 560 R / \left[ 1 + 0.2(1.0)^2 \right] = 467 R$$

$$P_2 = \frac{P_0}{RT_2} = \frac{26.4 \frac{\text{lb}}{\text{in}^2} \cdot \frac{\text{lbm} \cdot \text{ft}}{\text{s}^2} \cdot \frac{1}{467 R} \cdot \frac{144 \text{ in}^2}{\text{ft}^2}}{53.34 \frac{\text{ft} \cdot \text{lbm}}{\text{lbm} \cdot \text{R}}} = 0.153 \frac{\text{lbm}}{\text{ft}^3}$$


$$V_2 = M_2 C_2 = M_2 \left( \sqrt{k R T_2} \right) = 1.0 \left( \sqrt{1.4 \cdot 53.34 \frac{\text{ft} \cdot \text{lbm}}{\text{lbm} \cdot \text{R}} \cdot 467 R \cdot 32.2 \frac{\text{ft} \cdot \text{lbm}}{\text{slug} \cdot \text{ft}^2} \cdot \frac{1}{\text{lbm} \cdot \text{ft}^2}} \right) = 1060 \frac{\text{ft}}{\text{s}}$$

$$\dot{m} = P_2 V_2 A_2 = 0.153 \frac{\text{lbm}}{\text{ft}^3} \cdot 1060 \frac{\text{ft}}{\text{s}} \cdot 1.0 \text{ in}^2 \cdot \frac{\text{ft}^2}{144 \text{ in}^2} = 1.13 \frac{\text{lbm}}{\text{s}}$$

$$R_x = P_1 A_1 - P_2 A_2 - P_{atm}(A_1 - A_2) - \dot{m}(V_2 - V_1) = P_0 A_1 - P_2 A_2 - \dot{m} V_2$$

$$R_x = (50 - 14.7) \frac{\text{lbm}}{\text{in}^2} \cdot 10 \text{ in}^2 - (26.4 - 14.7) \frac{\text{lbm}}{\text{in}^2} \cdot 1.0 \text{ in}^2 - 1.13 \frac{\text{lbm}}{\text{s}} \cdot 1060 \frac{\text{ft}}{\text{s}} \cdot \frac{\text{slug}}{32.2 \text{ lbm}} = \frac{\text{lbm} \cdot \text{ft}}{\text{ft} \cdot \text{slug}} = \frac{\text{lbm} \cdot \text{ft}}{\text{ft} \cdot \text{slug}}$$

$R_x = 304 \text{ lbf}$  Since  $R_x$  acts to the left on CV, bolts are in tension



## Problem 13.42

[Difficulty: 4]

**13.42** An insulated spherical air tank with diameter  $D = 2$  m is used in a blowdown installation. Initially the tank is charged to 2.75 MPa (abs) at 450 K. The mass flow rate of air from the tank is a function of time; during the first 30 s of blowdown 30 kg of air leaves the tank. Determine the air temperature in the tank after 30 s of blowdown. Estimate the nozzle throat area.

**Given:** Spherical air tank

**Find:** Air temperature after 30s; estimate throat area

**Solution:**

Basic equations: 
$$\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2 \quad \frac{p}{\rho^k} = \text{const} \quad \frac{\partial}{\partial t} \int \rho dV_{CV} + \int \rho \cdot \vec{V} dA_{CS} = 0 \quad (4.12)$$

Assumptions: 1) Large tank (stagnation conditions) 2) isentropic 3) uniform flow

Given or available data

	$p_{\text{atm}} = 101 \cdot \text{kPa}$	$p_1 = 2.75 \cdot \text{MPa}$	$T_1 = 450 \cdot \text{K}$	$D = 2 \cdot \text{m}$	$V = \frac{\pi}{6} \cdot D^3$	$V = 4.19 \cdot \text{m}^3$
	$\Delta M = 30 \cdot \text{kg}$	$\Delta t = 30 \cdot \text{s}$	$k = 1.4$	$R = 286.9 \frac{\text{J}}{\text{kg} \cdot \text{K}}$		

The flow will be choked if  $p_b/p_1 < 0.528$ :  $p_b = p_{\text{atm}}$  so  $\frac{p_b}{p_1} = 0.037$  (Initially choked: Critical conditions)

We need to see if the flow is still choked after 30s

The initial (State 1) density and mass are

	$\rho_1 = \frac{p_1}{R \cdot T_1}$	$\rho_1 = 21.3 \frac{\text{kg}}{\text{m}^3}$	$M_1 = \rho_1 \cdot V$	$M_1 = 89.2 \text{ kg}$
--	------------------------------------	--	------------------------	-------------------------

The final (State 2) mass and density are then

	$M_2 = M_1 - \Delta M$	$M_2 = 59.2 \text{ kg}$	$\rho_2 = \frac{M_2}{V}$	$\rho_2 = 14.1 \frac{\text{kg}}{\text{m}^3}$
--	------------------------	-------------------------	--------------------------	--

For an isentropic process  $\frac{p}{\rho^k} = \text{const}$  so  $p_2 = p_1 \cdot \left( \frac{\rho_2}{\rho_1} \right)^k$   $p_2 = 1.55 \cdot \text{MPa}$   $\frac{p_b}{p_2} = 0.0652$  (Still choked)

The final temperature is  $T_2 = \frac{p_2}{\rho_2 \cdot R}$   $T_2 = 382 \text{ K}$   $T_2 = 109 \cdot ^\circ\text{C}$

To estimate the throat area we use  $\frac{\Delta M}{\Delta t} = m_{\text{tave}} = \rho_{\text{tave}} \cdot A_t \cdot V_{\text{tave}}$  or  $A_t = \frac{\Delta M}{\Delta t \cdot \rho_{\text{tave}} \cdot V_{\text{tave}}}$

where we use average values of density and speed at the throat.

The average stagnation temperature is  $T_{0\text{ave}} = \frac{T_1 + T_2}{2}$   $T_{0\text{ave}} = 416 \text{ K}$

The average stagnation pressure is  $p_{0\text{ave}} = \frac{p_1 + p_2}{2}$   $p_{0\text{ave}} = 2.15 \cdot \text{MPa}$

Hence the average temperature and pressure (critical) at the throat are

$$T_{\text{tave}} = \frac{T_{0\text{ave}}}{\left(1 + \frac{k-1}{2}\right)} \quad T_{\text{tave}} = 347 \text{ K} \quad \text{and} \quad p_{\text{tave}} = \frac{p_{0\text{ave}}}{\left(1 + \frac{k-1}{2}\right)^{\frac{k}{k-1}}} \quad p_{\text{tave}} = 1.14 \cdot \text{MPa}$$

Hence

$$V_{\text{tave}} = \sqrt{k \cdot R \cdot T_{\text{tave}}} \quad V_{\text{tave}} = 373 \frac{\text{m}}{\text{s}} \quad \rho_{\text{tave}} = \frac{p_{\text{tave}}}{R \cdot T_{\text{tave}}} \quad \rho_{\text{tave}} = 11.4 \frac{\text{kg}}{\text{m}^3}$$

Finally

$$A_t = \frac{\Delta M}{\Delta t \cdot \rho_{\text{tave}} \cdot V_{\text{tave}}} \quad A_t = 2.35 \times 10^{-4} \text{ m}^2 \quad A_t = 235 \cdot \text{mm}^2$$

This corresponds to a diameter


$$D_t = \sqrt{\frac{4 \cdot A_t}{\pi}} \quad D_t = 0.0173 \text{ m} \quad D_t = 17.3 \cdot \text{mm}$$

The process is isentropic, followed by nonisentropic expansion to atmospheric pressure

### Problem 13.43

[Difficulty: 4]

**13.43** An ideal gas, with  $k = 1.25$ , flows isentropically through the converging nozzle shown and discharges into a large duct where the pressure is  $p_2 = 25$  psia. The gas is *not* air and the gas constant,  $R$ , is unknown. Flow is steady and uniform at all cross sections. Find the exit area of the nozzle,  $A_2$ , and the exit speed,  $V_2$ .



**Given:** Ideal gas flow in a converging nozzle

**Find:** Exit area and speed

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $\frac{A}{A_{\text{crit}}} = \frac{1}{M} \cdot \left(\frac{1 + \frac{k-1}{2} \cdot M^2}{\frac{k+1}{2}}\right)^{\frac{k+1}{2 \cdot (k-1)}}$

Given or available data       $p_1 = 35 \cdot \text{psi}$        $\rho_1 = 0.1 \cdot \frac{\text{lbm}}{\text{ft}^3}$        $V_1 = 500 \cdot \frac{\text{ft}}{\text{s}}$        $A_1 = 1 \cdot \text{ft}^2$        $p_2 = 25 \cdot \text{psi}$        $k = 1.25$

Check for choking:       $c_1 = \sqrt{k \cdot R \cdot T_1}$  or, replacing  $R$  using the ideal gas equation       $c_1 = \sqrt{k \cdot \frac{p_1}{\rho_1}}$        $c_1 = 1424 \cdot \frac{\text{ft}}{\text{s}}$

Hence       $M_1 = \frac{V_1}{c_1}$        $M_1 = 0.351$

Then       $p_0 = p_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)^{\frac{k}{k-1}}$        $p_0 = 37.8 \cdot \text{psi}$

The critical pressure is then       $p_{\text{crit}} = \frac{p_0}{\left(\frac{k+1}{2}\right)^{\frac{k}{k-1}}}$        $p_{\text{crit}} = 21.0 \cdot \text{psi}$       Hence  $p_2 > p_{\text{crit}}$  so NOT choked

Then we have       $M_2 = \sqrt{\frac{2}{k-1} \cdot \left[\left(\frac{p_0}{p_2}\right)^{\frac{k-1}{k}} - 1\right]}$        $M_2 = 0.830$

From  $M_1$  we find       $A_{\text{crit}} = \frac{M_1 \cdot A_1}{\left(\frac{1 + \frac{k-1}{2} \cdot M_1^2}{\frac{k+1}{2}}\right)^{\frac{k+1}{2 \cdot (k-1)}}$        $A_{\text{crit}} = 0.557 \cdot \text{ft}^2$        $A_2 = \frac{A_{\text{crit}}}{M_2} \cdot \left(\frac{1 + \frac{k-1}{2} \cdot M_2^2}{\frac{k+1}{2}}\right)^{\frac{k+1}{2 \cdot (k-1)}}$        $A_2 = 0.573 \cdot \text{ft}^2$

For isentropic flow       $p \cdot \rho^k = \text{const}$       so       $\rho_2 = \rho_1 \cdot \left(\frac{p_1}{p_2}\right)^{\frac{1}{k}}$        $\rho_2 = 0.131 \cdot \frac{\text{lbm}}{\text{ft}^3}$

Finally from continuity       $\rho \cdot A \cdot V = \text{const}$       so       $V_2 = V_1 \cdot \frac{A_1 \cdot \rho_1}{A_2 \cdot \rho_2}$        $V_2 = 667 \cdot \frac{\text{ft}}{\text{s}}$

### Problem 13.44

[Difficulty: 4] Part 1/3

13.44 A jet transport aircraft, with pressurized cabin, cruises at 11 km altitude. The cabin temperature and pressure initially are at 25°C and equivalent to 2.5 km altitude. The interior volume of the cabin is 25 m<sup>3</sup>. Air escapes through a small hole with effective flow area of 0.002 m<sup>2</sup>. Calculate the time required for the cabin pressure to decrease by 40 percent. Plot the cabin pressure as a function of time.

Solution:

Basic equations: 
$$\frac{d}{dt} \int_{CV} p \, dV + \int_{CS} p \vec{V} \cdot d\vec{A} = 0$$

$$\frac{p}{\rho^{\gamma}} = \text{constant} \quad p = \rho R T$$

Assumptions: (1) model flow as isentropic flow through a converging nozzle.  
 (2) assume uniform properties within the cabin, isentropic expansion  
 (3) ideal gas behavior.

Stagnation conditions within the cabin are  
 $T_i = 298 \text{ K}$       $P_i = P_{atm}$  at 2.5 km = 74.7 kPa (Table A.3)  
 $P_e = 0.60 P_i = 44.8 \text{ kPa}$

Back pressure  $P_b = P_{atm}$  at 11 km = 22.7 kPa.

Then  $P_b/P_e = 0.304$  and  $P_b/P_i = 0.507$ . Flow is choked.

Note: conditions in cabin are stagnation conditions.

From continuity,

$$\frac{d}{dt} \int_{CV} p \, dV + \int_{CS} p \vec{V} \cdot d\vec{A} = -p_e V_e A_e$$

$$+ \frac{dp}{dt} = -p_e V_e A_e$$

For choked flow,  $M_e = 1.0$

$$\frac{p}{P_e} = \left[ 1 + \frac{\gamma-1}{2} M_e^2 \right]^{\frac{\gamma}{\gamma-1}} = (1.20)^{2.5} = 1.5774 \quad \therefore p_e = 0.6339 p$$

$$\frac{T}{T_e} = 1 + \frac{\gamma-1}{2} M_e^2 = 1.2 \quad \therefore T_e = 0.8333 T$$

$$V_e = (R T_e)^{1/2} = (R T)^{1/2} (0.8333)^{1/2} = 0.9129 (R T)^{1/2}$$

Then

$$+ \frac{dp}{dt} = -p_e V_e A_e = -0.6339 p (0.9129) (R T)^{1/2} A_e$$

$$+ \frac{dp}{dt} = -0.5787 (R T)^{1/2} A_e p T^{1/2}$$

For an isentropic expansion  $p$  and  $T$  can be related

$$\frac{p}{\rho^{\gamma}} = \text{const} = \frac{p R T}{p^{\gamma}} \quad \therefore p^{(1-\gamma)} T = \text{constant}$$

Problem 13.44

Then,  $p^{(1-k)} T = p_i T_i$  or  $T = T_i \left(\frac{p_i}{p}\right)^{(1-k)}$  and  $T^{1/2} = \frac{T_i^{1/2}}{p^{(k-1)/2}}$

Substituting we obtain

$$+ \frac{dp}{dt} = -0.5787 (kR)^{1/2} A_e p \frac{T_i^{1/2}}{p^{(k-1)/2}}$$

$$\frac{dp}{dt} = -0.5787 \frac{(kR)^{1/2}}{4} A_e \frac{T_i^{1/2}}{p^{(k-1)/2}} p^{\frac{k+1}{2}} = c_1 p^{(k+1)/2}$$

$$\frac{dp}{p^{(k+1)/2}} = -c_1 dt \quad \text{where } c_1 = 0.5787 (kR)^{1/2} \frac{A_e}{4} \frac{T_i^{1/2}}{p^{(k-1)/2}}$$

To integrate, we write

$$-c_1 t = \int p^{-\frac{(k+1)}{2}} dp = \frac{1}{1-\frac{(k+1)}{2}} p^{-\frac{(k+1)}{2}} \Big|_{p_i}^{p_f} = \frac{2}{(1-k)} p^{-\frac{(k+1)}{2}} \Big|_{p_i}^{p_f}$$

$$-c_1 t = \frac{2}{(k-1)} \left[ p_i^{-(k+1)/2} - p_f^{-(k+1)/2} \right] = \frac{2}{(k-1)} p_i^{-(k+1)/2} \left[ 1 - \left(\frac{p_f}{p_i}\right)^{-(k+1)/2} \right]$$

$$c_1 t = \frac{2}{(k-1)} p_i^{(k+1)/2} \left[ \left(\frac{p_i}{p_f}\right)^{(k+1)/2} - 1 \right]$$

$$0.5787 (kR)^{1/2} \frac{A_e}{4} \frac{T_i^{1/2}}{p_i^{(k-1)/2}} t = \frac{2}{(k-1)} p_i^{(k+1)/2} \left[ \left(\frac{p_i}{p_f}\right)^{(k+1)/2} - 1 \right]$$

$$0.5787 (kR)^{1/2} \frac{A_e}{4} T_i^{1/2} t = \frac{2}{(k-1)} \left[ \left(\frac{p_i}{p_f}\right)^{\frac{(k+1)}{2}} - 1 \right]$$

Since  $p/p^k = \text{const}$ ,  $\frac{p_i}{p_f} = \left(\frac{p_i}{p_f}\right)^{1/k}$

and  $0.5787 (kR)^{1/2} \frac{A_e}{4} T_i^{1/2} t = \frac{2}{(k-1)} \left[ \left(\frac{p_i}{p_f}\right)^{\frac{(k+1)}{2k}} - 1 \right] \tag{1}$

Substituting numerical values

$$0.5787 \left[ 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 292\text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right]^{1/2} 0.002\text{m}^2 \times \frac{1}{25\text{m}^3} t = \frac{2}{0.4} \left[ \left(\frac{1}{0.6}\right)^{0.1429} - 1 \right]$$

$$0.01602 t = 0.3786$$

$$t = 23.6 \text{ s.}$$

t


42,381 30 SHEETS 3 SQUARE  
42,382 100 SHEETS 3 SQUARE  
42,383 200 SHEETS 3 SQUARE  
NATIONAL

# Problem 13.44

Equation 1 is plotted using Excel

Note that it's easier to compute  $t$  from  $p$  values!

$t$ (s)	$p$ (kPa)
0.000	74.7
1.03	73
2.27	71
3.56	69
4.89	67
6.26	65
7.69	63
9.17	61
10.7	59
12.3	57
14.0	55
15.7	53
17.5	51
19.4	49
21.4	47
23.6	44.8
25.6	43
27.9	41
30.4	39
33.0	37
35.7	35
38.6	33
41.8	31
45.2	29
48.8	27
52.8	25
57.2	23
62.0	21
67.4	19
73.5	17
80.5	15
90.0	12.7



## Problem 13.45

[Difficulty: 3]

**13.45** At some point upstream of the throat of a converging-diverging duct, air flows at a speed of 50 ft/s, with pressure and temperature of 15 psia and 70°F, respectively. If the throat area is 1 ft<sup>2</sup>, and the discharge from the duct is supersonic, find the mass flow rate of air, assuming frictionless, adiabatic flow.

**Given:** Air flow through a converging-diverging nozzle

**Find:** Nozzle mass flow rate

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.4 \\V_1 &= 50 && \text{ft/s} \\p_1 &= 15 && \text{psia} \\T_1 &= 70 && ^\circ\text{F} \\T_1 &= 530 && ^\circ\text{R} \\A_t &= 1 && \text{ft}^2\end{aligned}$$

Equations and Computations:

At station 1 the local sound speed is:

$$c_1 = 1128.80 \quad \text{ft/s}$$

So the upstream Mach number is:

$$M_1 = 0.0443$$

So now we can calculate the stagnation temperature and pressure:

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)}$$

$$\begin{aligned}p_0 &= 15.021 && \text{psia} \\T_0 &= 530.21 && ^\circ\text{R}\end{aligned}$$

To find the mass flow rate, we will use the choked flow equation:

From  $p_0$ ,  $T_0$ ,  $A_t$ , and Eq. 13.10a

$$\dot{m}_{\text{choked}} = A_t p_0 \sqrt{\frac{k}{RT_0} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)}} \quad (13.10a)$$
$$m = 50.0 \quad \text{lbm/s}$$

## Problem 13.46

[Difficulty: 2]

**13.46** A converging-diverging nozzle is attached to a very large tank of air in which the pressure is 150 kPa and the temperature is 35°C. The nozzle exhausts to the atmosphere where the pressure is 101 kPa. The exit diameter of the nozzle is 2.75 cm. What is the flow rate through the nozzle? Assume the flow is isentropic.

**Given:** CD nozzle attached to large tank

**Find:** Flow rate

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $m_{\text{rate}} = \rho \cdot V \cdot A$

Given or available data       $p_0 = 150 \cdot \text{kPa}$        $T_0 = (35 + 273) \cdot \text{K}$        $p_e = 101 \cdot \text{kPa}$        $D = 2.75 \cdot \text{cm}$

$k = 1.4$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $A_e = \frac{\pi}{4} \cdot D^2$        $A_e = 5.94 \cdot \text{cm}^2$

For isentropic flow       $M_e = \sqrt{\frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_e} \right)^{\frac{k-1}{k}} - 1 \right]}$        $M_e = 0.773$

Then       $T_e = \frac{T_0}{\left(1 + \frac{k-1}{2} \cdot M_e^2\right)}$        $T_e = 275 \text{ K}$        $T_e = 1.94 \cdot \text{°C}$

Also       $c_e = \sqrt{k \cdot R \cdot T_e}$        $c_e = 332 \frac{\text{m}}{\text{s}}$        $V_e = M_e \cdot c_e$        $V_e = 257 \frac{\text{m}}{\text{s}}$

$\rho_e = \frac{p_e}{R \cdot T_e}$        $\rho_e = 1.28 \frac{\text{kg}}{\text{m}^3}$

Finally       $m_{\text{rate}} = \rho_e \cdot V_e \cdot A_e$        $m_{\text{rate}} = 0.195 \frac{\text{kg}}{\text{s}}$

### Problem 13.47

[Difficulty: 4]

13.47 A large insulated tank, pressurized to 620 kPa (gage), supplies air to a converging nozzle which discharges to atmosphere. The initial temperature in the tank is 127°C. When flow through the nozzle is initiated, what is the Mach number in the exit plane of the nozzle? What is the pressure in the exit plane when the flow is initiated? At what condition will the exit-plane Mach number change? How will the exit-plane pressure vary with time? How will flow rate through the nozzle vary with time? What would you estimate the air temperature in the tank to be when flow through the nozzle approaches zero?


Solution: Assume stagnation conditions in tank,  $p_0 = p_{atm}$ . Then

$$\frac{p_0}{p_0} = \frac{101.3 \text{ kPa}}{(620 + 101.3) \text{ kPa (abs)}} = 0.140 < 0.523, \text{ so flow is choked! } Me = 1 \quad \leftarrow Me$$

At exit plane,  $Me = 1$ , so

$$p_e = p_0 \left( \frac{1}{1 + \frac{k-1}{2} Me^2} \right)^{\frac{k}{k-1}} = (620 + 101.3) \text{ kPa (abs)} \left( \frac{1}{1.2} \right)^{3.5} = 381 \text{ kPa (abs)} \quad \leftarrow p_e$$

Exit plane pressure decreases with time, asymptotically approaching  $p_{atm}$ .



Flow rate varies similarly.


When flow rate approaches zero,  $p_0 \rightarrow p_{atm}$ . Assume tank behaves as a reversible adiabatic process. Thus

$$\frac{p_f}{p_0} = \left( \frac{T_f}{T_0} \right)^{\frac{k}{k-1}}$$


$$\text{Thus } T_f = T_0 \left( \frac{p_f}{p_0} \right)^{\frac{k-1}{k}} = (273 + 127) \text{ K} \left( \frac{101.3}{620 + 101.3} \right)^{0.286} = 228 \text{ K}$$

$$T_f = (228 - 273)^\circ \text{C} = -45^\circ \text{C} \quad \leftarrow T_f$$


The Ts diagram for air in the tank is:



The Ts diagrams for air flowing from the tank are:



While choked  
( $p_e > p_{atm}/0.523$ )



No longer choked  
( $p_e \leq p_{atm}/0.523$ )




### Problem 13.48

[Difficulty: 4] Part 2/2

Equation 1 is plotted using *Excel*

Note that it's easier to compute  $t$  from  $p$  values!

$t$ (s)	$p$ (kPa)
0.000	620
0.584	610
1.18	600
1.78	590
2.39	580
3.00	570
3.63	560
4.27	550
4.92	540
5.57	530
6.24	520
6.92	510
7.61	500
8.31	490
9.03	480
9.75	470
10.5	460
11.2	450
12.0	440
12.8	430
13.6	420
14.4	410
15.2	400
16.1	390
16.9	380
17.8	370
18.7	360
19.6	350
20.6	340
21.5	330
22.5	320
23.5	310
24.5	300
25.6	290
26.7	280
27.8	270
28.9	260
30.0	251



## Problem 13.49

[Difficulty: 2]

**13.49** At the design condition of the system of Problem 13.46, the exit Mach number is  $M_e = 2.0$ . Find the pressure in the tank of Problem 13.46 (keeping the temperature constant) for this condition. What is the flow rate? What is the throat area?

**Given:** Design condition in a converging-diverging nozzle

**Find:** Tank pressure; flow rate; throat area

**Solution:**

The given or available data is:

$$\begin{aligned}
 R &= 53.33 && \text{ft.lbf/lbm.}^\circ\text{R} \\
 k &= 1.4 \\
 T_0 &= 560 && ^\circ\text{R} \\
 A_e &= 1 && \text{in}^2 \\
 p_b &= 14.7 && \text{psia} \\
 M_e &= 2
 \end{aligned}$$

Equations and Computations:

At design condition

$$\begin{aligned}
 p_e &= p_b \\
 p_e &= 14.7 && \text{psia}
 \end{aligned}$$

From  $M_e$  and  $p_e$ , and Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$p_0 = 115 \quad \text{psia}$$

From  $M_e$  and  $A_e$ , and Eq. 13.7d  
(using built-in function  $IsenA(M, k)$ )

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{\frac{k+1}{2}} \right]^{(k+1)/2(k-1)} \quad (13.7d)$$

$$A^* = 0.593 \quad \text{in}^2$$

Hence

$$A_t = 0.593 \quad \text{in}^2$$

From  $p_0$ ,  $T_0$ ,  $A_t$ , and Eq. 13.10a

$$\dot{m}_{\text{choked}} = A_t p_0 \sqrt{\frac{k}{RT_0}} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)} \quad (13.10a)$$

$$\dot{m}_{\text{choked}} = 1.53 \quad \text{lb/s}$$

## Problem 13.50

[Difficulty: 3]

**13.50** When performing tests in a wind tunnel at conditions near Mach 1, the effects of model blockage become very important. Consider a wind tunnel with a test section of  $1 \text{ ft}^2$  cross section. If the test section conditions are  $M = 1.20$  and  $T = 70^\circ\text{F}$ , how much area blockage could be tolerated before the flow choked in the test section? If a model with  $3 \text{ in.}^2$  projected frontal area were inserted in the tunnel, what would the air velocity be in the test section?

**Given:** Wind tunnel test section with blockage

**Find:** Maximum blockage that can be tolerated; air speed given a fixed blockage

**Solution:**

The given or available data is:

$R =$	53.33	ft-lbf/lbm-°R
$k =$	1.4	
$M_1 =$	1.2	
$T_1 =$	70	°F
$T_1 =$	530	°R
$A_1 =$	1	ft <sup>2</sup>

Equations and Computations:

The test section will choke if the blockage decreases the area to  $A^*$ . In the test section:

$$A_1/A^* = 1.0304$$

So the minimum area would be

$$A^* = 0.9705 \text{ ft}^2$$

And the blockage would be the difference between this and the test section area:

$$\begin{aligned} A_1 - A^* &= 0.0295 \text{ ft}^2 \\ A_1 - A^* &= 4.25 \text{ in}^2 \end{aligned}$$

If we have a blockage of:

$$A_1 - A = 3.0000 \text{ in}^2$$

Then the actual area would be:

$$A_{\text{actual}} = 0.9792 \text{ ft}^2$$

The resulting isentropic area ratio is:

$$A_{\text{actual}}/A^* = 1.0090$$

and the actual Mach number is:

$$M_{\text{actual}} = 1.1066$$

(remember that since we're already supersonic, we should use the supersonic solution)

The stagnation temperature for the wind tunnel is (based on test section conditions)

$$T_0 = 682.64 \text{ °R}$$

So the actual static temperature in the tunnel is:

$$T_{\text{actual}} = 548.35 \text{ °R}$$

The sound speed would then be:

$$c_{\text{actual}} = 1148.17 \text{ ft/s}$$

And so the speed in the test section is:

$$V_{\text{actual}} = 1270.5 \text{ ft/s}$$

## Problem 13.51

[Difficulty: 3]

---

**13.51** A pitot static probe is placed in a converging-diverging duct through which air flows. The duct is fed by a reservoir kept at 20°C. If the probe reads a static pressure of 75 kPa and a stagnation pressure of 100 kPa at a location where the area is 0.00645 m<sup>2</sup>, what is the local velocity and the mass flow rate of air?

---

**Given:** Air flow through a converging-diverging nozzle equipped with pitot-static probe

**Find:** Nozzle velocity and mass flow rate

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\k &= 1.4 \\p_1 &= 75 && \text{kPa} \\p_{01} &= 100 && \text{kPa} \\T_1 &= 20 && ^\circ\text{C} \\T_1 &= 293 && \text{K} \\A_1 &= 10 && \text{in}^2 \\A_1 &= 0.006452 && \text{m}^2\end{aligned}$$

Equations and Computations:

At station 1 the local sound speed is:

$$c_1 = 343.05 \text{ m/s}$$

Based on the static and pitot pressures, the Mach number is:

$$M_1 = 0.6545$$

Therefore the velocity is:

$$V_1 = 225 \text{ m/s}$$

The local density can be calculated using the ideal gas equation of state:

$$\rho_1 = 0.8922 \text{ kg/m}^3$$

So the mass flow rate is:

$$m = 1.292 \text{ kg/s}$$

### Problem 13.52

[Difficulty: 2]

**13.52** A converging-diverging nozzle, with a throat area of 2 in.<sup>2</sup>, is connected to a large tank in which air is kept at a pressure of 80 psia and a temperature of 60°F. If the nozzle is to operate at design conditions (flow is isentropic) and the ambient pressure outside the nozzle is 12.9 psia, calculate the exit area of the nozzle and the mass flow rate.

Solution

Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$   
 $\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{1 + \frac{k-1}{2} M^2} \right]^{k/2} \left( \frac{r_1}{r_2} \right)^{k/2}$  (12.6)

Assumptions: (1) steady flow (2) isentropic flow (3) uniform flow at a section (4) ideal gas

$$P_0/P = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/2} ; M_1 = \left\{ \frac{2}{k-1} \left[ \left( \frac{P_0}{P_1} \right)^{k-1/k} - 1 \right] \right\}^{1/2} = \left\{ \frac{2}{0.4} \left[ \left( \frac{80}{12.9} \right)^{0.286} - 1 \right] \right\}^{1/2} = 1.85$$

$$T_0/T = 1 + \frac{k-1}{2} M^2 ; T_1 = \frac{T_0}{1 + \frac{k-1}{2} M^2} = \frac{520^\circ R}{1 + 0.2(1.85)^2} = 309^\circ R$$


$$V_1 = M_1 c_1 = M_1 (kRT_1)^{1/2} = 1.85 \left( 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lb} \cdot \text{R}} \times 309^\circ R \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb} \cdot \text{s}^2} \right)^{1/2} = 1594 \text{ ft/s}$$

$$p_1 = \frac{P_1}{RT_1} = 12.9 \frac{\text{lb}}{\text{in}^2} \times \frac{\text{in}^2}{144 \text{ ft}^2} \times \frac{\text{lbm} \cdot \text{R}}{32.2 \text{ ft} \cdot \text{lb}} \times \frac{1}{309^\circ R} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.113 \text{ lbm/ft}^3$$

Since  $M_1 = 1.85$ , nozzle must be choked and  $M_2 = 1.0$ ;  $A_2 = A^*$

For  $M_1 = 1.85$ , from Eq. 12.6 (and Fig. E.1),  $A_1/A^* = 1.496$ ;  $\therefore A_1 = 2.99 \text{ in}^2$  ←  $A_1$

$$\dot{m} = p_1 V_1 A_1 = 0.113 \frac{\text{lbm}}{\text{ft}^3} \times 1594 \frac{\text{ft}}{\text{s}} \times 2.99 \text{ in}^2 \times \frac{\text{ft}^2}{144 \text{ in}^2} = 3.74 \text{ lbm/s}$$
 ←  $\dot{m}$



### Problem 13.53

[Difficulty: 2]

**13.53** A converging-diverging nozzle, designed to expand air to  $M = 3.0$ , has a  $250 \text{ mm}^2$  exit area. The nozzle is bolted to the side of a large tank and discharges to standard atmosphere. Air in the tank is pressurized to  $4.5 \text{ MPa}$  (gage) at  $750 \text{ K}$ . Assume flow within the nozzle is isentropic. Evaluate the pressure in the nozzle exit plane. Calculate the mass flow rate of air through the nozzle.

Solution: Assume stagnation conditions in tank, isentropic flow in nozzle.

Computing equations:  $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} M^2\right)^{\frac{k}{k-1}}$ ;  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$ ;  $c = \sqrt{kRT}$

For  $M_e = 3.0$ ,  $\frac{p_0}{p_e} = \left[1 + \frac{k-1}{2} (3.0)^2\right]^{\frac{k}{k-1}} = 36.7$

$$p_e = \frac{p_0}{36.7} = \frac{(4.5 \times 10^6 + 101 \times 10^3) \text{ Pa}}{36.7} = 125 \text{ kPa (abs) or } 24 \text{ kPa (gage)} \quad p_e$$

Thus the nozzle is underexpanded. For steady, 1-D flow,  $\dot{m} = \rho_e V_e A_e$ .

$$T_e = \frac{T_0}{1 + \frac{k-1}{2} (3.0)^2} = \frac{750 \text{ K}}{1 + 0.2(3)^2} = 268 \text{ K}$$


$$c_e = \sqrt{kRT_e} = \left[1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 268 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}\right]^{1/2} = 322 \text{ m/s}$$

$$\rho_e = \frac{p_e}{RT_e} = \frac{125 \times 10^3 \text{ N}}{\text{m}^2} \times \frac{\text{kg}\cdot\text{K}}{287 \text{ N}\cdot\text{m}} \times \frac{1}{268 \text{ K}} = 1.63 \text{ kg/m}^3$$

Finally,  $V_e = M_e c_e = 3.0 \times 322 \text{ m/s} = 984 \text{ m/s}$

$$\dot{m} = \rho_e V_e A_e = 1.63 \frac{\text{kg}}{\text{m}^3} \times 984 \frac{\text{m}}{\text{s}} \times 250 \text{ mm}^2 \times \frac{\text{m}^2}{10^6 \text{ mm}^2} = 0.401 \text{ kg/s} \quad \dot{m}$$

TS diagram:



- 0 = tank conditions
- \* = throat conditions
- e = exit plane conditions

## Problem 13.54

[Difficulty: 3]

**13.54** Methane is stored in a tank at 75 psia and 80°F. It discharges to another tank via a converging-only nozzle, with exit area 1 in.<sup>2</sup>. What is the initial mass flow rate of methane when the discharge tank is at a pressure of (a) 15 psia, and (b) 60 psia?

**Given:** Methane discharging from one tank to another via a converging nozzle

**Find:** Mass flow rate at two different back pressures

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 96.32 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.31 \\p_0 &= 75 && \text{psia} \\T_0 &= 80 && ^\circ\text{F} \\T_0 &= 540 && ^\circ\text{R} \\A_e &= 1 && \text{in}^2\end{aligned}$$

Equations and Computations:

If the nozzle were choked, the exit Mach number is 1 and the pressure would be:

$$p^* = 40.79 \text{ psia}$$

Therefore, in part a, when

$$p_e = 15 \text{ psia}$$

The nozzle is choked, and we can use the choked flow equation:

From  $p_0$ ,  $T_0$ ,  $A_e$ , and Eq. 13.9a

$$\dot{m}_{\text{choked}} = A_e p_0 \sqrt{\frac{k}{RT_0} \left(\frac{2}{k+1}\right)^{(k+1)/2(k-1)}} \quad (13.9a)$$

$$m = 1.249 \text{ lbm/s}$$

In part b, when

$$p_e = 60 \text{ psia}$$

The nozzle is not choked. The exit Mach number is:

$$M_e = 0.5915$$

The exit temperature can be found from the Mach number:

$$T_e = 512.2 \text{ }^\circ\text{R}$$

The sound speed at the exit is:

$$c_e = 1442.6 \text{ ft/s}$$

And so the exit flow speed is:

$$V_e = 853.3 \text{ ft/s}$$

The density can be calculated using the ideal gas equation of state:

$$\rho_e = 0.1751 \text{ lbm/ft}^3$$

The mass flow rate can then be calculated directly from continuity:

$$m = 1.038 \text{ lbm/s}$$

### Problem 13.55

[Difficulty: 2]

13.55 Air, at a stagnation pressure of 7.20 MPa (abs) and a stagnation temperature of 1100 K, flows isentropically through a converging-diverging nozzle having a throat area of 0.01 m<sup>2</sup>. Determine the speed and the mass flow rate at the downstream section where the Mach number is 4.0.

Solution:

Basic equations:  $\dot{m} = \rho VA$        $P = \rho RT$

Computing equations:  $\frac{T_0}{T} = 1 + \frac{\gamma-1}{2} M^2$        $\frac{P_0}{P} = \left[ 1 + \frac{\gamma-1}{2} M^2 \right]^{\frac{\gamma}{\gamma-1}}$

Assumptions: (1) steady flow      (3) uniform flow at a section  
 (2) isentropic flow      (4) ideal gas

$$\frac{T_0}{T_1} = 1 + \frac{\gamma-1}{2} M_1^2 \quad ; \quad T_1 = \frac{T_0}{1 + \frac{\gamma-1}{2} M_1^2} = \frac{1100 \text{ K}}{1 + 0.2(4.0)^2} = 262 \text{ K}$$

$$V_1 = M_1 c_1 = M_1 \left( \gamma R T_1 \right)^{1/2} = 4.0 \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 262 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right)^{1/2} = 1300 \text{ m/s} \quad \leftarrow V_1$$

Since  $M_1 = 4.0$ , nozzle must be choked and  $M_t = 1.0$


$$P_t = \frac{P_0}{\left[ 1 + \frac{\gamma-1}{2} M_t^2 \right]^{\frac{\gamma}{\gamma-1}}} = \frac{7.2 \times 10^6 \text{ Pa}}{\left[ 1 + 0.2(1.0)^2 \right]^{3.5}} = 3.80 \text{ MPa}$$

$$T_t = \frac{T_0}{1 + \frac{\gamma-1}{2} M_t^2} = \frac{1100 \text{ K}}{1 + 0.2(1.0)^2} = 917 \text{ K}$$

$$\rho_t = \frac{P_t}{R T_t} = 3.80 \times 10^6 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg}\cdot\text{K}}{287 \text{ N}\cdot\text{m}} \times \frac{1}{917 \text{ K}} = 14.4 \text{ kg/m}^3$$

$$V_t = M_t c_t = M_t \left( \gamma R T_t \right)^{1/2} = 1.0 \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 917 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right)^{1/2} = 607 \text{ m/s}$$

$$\dot{m} = \rho_t V_t A_t = 14.4 \frac{\text{kg}}{\text{m}^3} \times 607 \frac{\text{m}}{\text{s}} \times 0.01 \text{ m}^2 = 87.4 \text{ kg/s} \quad \leftarrow \dot{m}$$



### Problem 13.56

[Difficulty: 2]

13.56 Air is to be expanded through a converging-diverging nozzle by a frictionless adiabatic process, from a pressure of 1.10 MPa (abs) and a temperature of 115°C, to a pressure of 141 kPa (abs). Determine the throat and exit areas for a well-designed shockless nozzle, if the mass flow rate is 2 kg/s.

Solution:

Computing equations:  $\frac{T}{T_0} = 1 - \frac{\gamma-1}{2} M^2$ ,  $\frac{p}{p_0} = \left[1 - \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}}$   
 $\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{\gamma-1}{2} M^2}{1 - \frac{\gamma-1}{2} M^2} \right]^{\frac{\gamma+1}{2(\gamma-1)}} \quad (12.6)$

Assumptions: 1) steady flow 2) isentropic flow 3) uniform flow at a section 4) ideal gas

$$p_0/p = \left[1 + \frac{\gamma-1}{2} M^2\right]^{\frac{\gamma}{\gamma-1}} \quad ; \quad M_1 = \left\{ \frac{2}{\gamma-1} \left[ \left( \frac{p_0}{p} \right)^{\frac{\gamma-1}{\gamma}} - 1 \right] \right\}^{1/2} = \left\{ \frac{2}{0.4} \left[ \left( \frac{1.1}{0.141} \right)^{0.286} - 1 \right] \right\}^{1/2} = 2.0$$

$$T_0/T = 1 + \frac{\gamma-1}{2} M^2 \quad ; \quad T_1 = \frac{T_0}{1 + \frac{\gamma-1}{2} M^2} = \frac{328 \text{ K}}{1 + 0.2(2.0)^2} = 216 \text{ K}$$


$$v_1 = M_1 c_1 = M_1 \left( \sqrt{\gamma R T_1} \right)^{1/2} = 2.0 \cdot 1.4 \cdot \sqrt{287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \cdot 216 \text{ K} + \frac{20 \cdot \text{m}}{\text{N}\cdot\text{s}^2}}^{1/2} = 589 \text{ m/s}$$

$$p_1 = \frac{p_0}{1 + \frac{\gamma-1}{2} M^2} = \frac{1.1 \times 10^6 \text{ N/m}^2}{1 + 0.2(2.0)^2} = 2.27 \text{ kg/m}^3$$

$$A_1 = \frac{\dot{m}}{\rho_1 v_1} = \frac{2.0 \frac{\text{kg}}{\text{s}}}{2.27 \frac{\text{kg}}{\text{m}^3} \cdot 589 \frac{\text{m}}{\text{s}}} = 1.50 \times 10^{-3} \text{ m}^2 \quad A_1$$

For  $M_1 = 2.0$ , from Eq. 12.6 and Fig. E.1,  $A_1/A^* = 1.688$

$$\text{Then } A_t = A^* = A_1 / 1.688 = 8.89 \times 10^{-4} \text{ m}^2 \quad A_t$$



# Problem 13.57

13.57 Air flows isentropically through a converging-diverging nozzle attached to a large tank, in which the pressure is 251 psia and the temperature is 500°R. The nozzle is operating at design conditions for which the nozzle exit pressure,  $p_e$ , is equal to the surrounding atmospheric pressure,  $p_a$ . The exit area of the nozzle is  $A_e = 1.575 \text{ in}^2$ . Calculate the flow rate through the nozzle. Plot the mass flow rate as the temperature of the tank is progressively increased to 2000°R (all pressures remaining the same). Explain this result (e.g., compare the mass flow rates at 500°R and 2000°R).

Solution:

Basic equations:  $\dot{m} = \rho VA$        $P = \rho RT$   
 Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$        $\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}$

Assumptions: (1) steady flow      (3) uniform flow at a section  
 (2) isentropic flow      (4) ideal gas

$$\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}} ; M_e = \left\{ \frac{2}{k-1} \left[ \left( \frac{P_0}{P_e} \right)^{\frac{k-1}{k}} - 1 \right] \right\}^{\frac{1}{2}} = \left\{ \frac{2}{0.4} \left[ \left( \frac{251}{14.7} \right)^{0.286} - 1 \right] \right\}^{\frac{1}{2}} = 2.50$$

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2 ; T_e = \frac{T_0}{1 + \frac{k-1}{2} M_e^2} = \frac{500^\circ\text{R}}{1 + 0.2(2.50)^2} = 222^\circ\text{R}$$

$$V_e = M_e c_e = M_e (kRT_e)^{\frac{1}{2}} = 2.5 \left( 1.4 \cdot 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot ^\circ\text{R}} \cdot 222^\circ\text{R} \cdot 32.2 \frac{\text{lb}_m}{\text{slug}} \cdot \frac{\text{slug} \cdot \text{ft}}{\text{lb}_f \cdot \text{s}^2} \right)^{\frac{1}{2}} = 1826 \text{ ft/s}$$


$$p_e = \frac{P_0}{\frac{P_0}{P_e}} = \frac{251 \text{ lb}_f}{\text{in}^2} \cdot \frac{1 \text{ lb}_m \cdot ^\circ\text{R}}{53.3 \text{ ft} \cdot \text{lb}_f} \cdot \frac{1}{222^\circ\text{R}} \cdot 14.7 \frac{\text{in}^2}{\text{ft}^2} = 0.179 \text{ lb}_m/\text{ft}^3$$

$$\dot{m} = p_e V_e A_e = 0.179 \frac{\text{lb}_m}{\text{ft}^3} \cdot 1826 \frac{\text{ft}}{\text{s}} \cdot 1.575 \text{ in}^2 \cdot \frac{\text{ft}^2}{144 \text{ in}^2} = 3.57 \text{ lb}_m/\text{s} \quad \leftarrow \dot{m}$$

$\dot{m} = p_e V_e A_e$  If  $T_0$  is increased by a factor of 4 (holding pressures constant)

- (1)  $T_e$  will increase by a factor of 4 (since  $T_0/T = \text{const}$ )
- (2)  $V_e$  " " " " " " 2 (since  $V_e \propto T_e^{1/2}$ )
- (3)  $p_e$  " decrease " " " " 4 (since  $p_e \propto 1/T_e$ )

Thus the mass flow rate,  $\dot{m}$ , will decrease by a factor of 2  $\leftarrow$




## Problem 13.57

[Difficulty: 3] Part 2/2

The calculations from page 1 are repeated for various  $T_0$  values and plotted using *Excel*

$T_0$ ( $^{\circ}\text{R}$ )	$T_e$ ( $^{\circ}\text{R}$ )	$\rho_e$ ( $\text{lbm}/\text{ft}^3$ )	$V_e$ ( $\text{ft}/\text{s}$ )	$m_{\text{rate}}$ ( $\text{lbm}/\text{s}$ )
500	222	0.179	1827	3.57
550	244	0.162	1916	3.40
600	267	0.149	2001	3.26
650	289	0.137	2083	3.13
700	311	0.128	2161	3.02
750	333	0.119	2237	2.92
800	356	0.112	2311	2.82
850	378	0.105	2382	2.74
900	400	0.0993	2451	2.66
950	422	0.0941	2518	2.59
1000	444	0.0894	2583	2.52
1050	467	0.0851	2647	2.46
1100	489	0.0812	2710	2.41
1150	511	0.0777	2770	2.35
1200	533	0.0745	2830	2.30
1250	556	0.0715	2888	2.26
1300	578	0.0687	2946	2.21
1350	600	0.0662	3002	2.17
1400	622	0.0638	3057	2.13
1450	644	0.0616	3111	2.10
1500	667	0.0596	3164	2.06
1550	689	0.0577	3216	2.03
1600	711	0.0558	3268	2.00
1650	733	0.0542	3319	1.97
1700	756	0.0526	3368	1.94
1750	778	0.0511	3418	1.91
1800	800	0.0496	3466	1.88
1850	822	0.0483	3514	1.86
1900	844	0.0470	3561	1.83
1950	867	0.0458	3608	1.81
2000	889	0.0447	3654	1.79



## Problem 13.58

[Difficulty: 3]

**13.58** A small, solid fuel rocket motor is tested on a thrust stand. The chamber pressure and temperature are 4 MPa and 3250 K. The propulsion nozzle is designed to expand the exhaust gases isentropically to a pressure of 75 kPa. The nozzle exit diameter is 25 cm. Treat the gas as ideal with  $k = 1.25$  and  $R = 300 \text{ J}/(\text{kg}\cdot\text{K})$ . Determine the mass flow rate of propellant gas and the thrust force exerted against the test stand.

**Given:** Rocket motor on test stand

**Find:** Mass flow rate; thrust force

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p = \rho \cdot R \cdot T$        $c = \sqrt{k \cdot R \cdot T}$        $m_{\text{rate}} = \rho \cdot A \cdot V$

$(p_{\text{atm}} - p_e) \cdot A_e + R_x = m_{\text{rate}} \cdot V_e$       Momentum for pressure  $p_e$  and velocity  $V_e$  at exit;  $R_x$  is the reaction force

Given or available data     $p_e = 75 \cdot \text{kPa}$      $p_{\text{atm}} = 101 \cdot \text{kPa}$      $p_0 = 4 \cdot \text{MPa}$      $T_0 = 3250 \cdot \text{K}$      $k = 1.25$      $R = 300 \cdot \frac{\text{J}}{\text{kg}\cdot\text{K}}$

$d = 25 \cdot \text{cm}$       so the nozzle exit area is       $A_e = \frac{\pi}{4} \cdot d^2$        $A_e = 491 \cdot \text{cm}^2$

From the pressures       $M_e = \sqrt{\frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_e} \right)^{\frac{k-1}{k}} - 1 \right]}$        $M_e = 3.12$

The exit temperature is     $T_e = \frac{T_0}{\left(1 + \frac{k-1}{2} \cdot M_e^2\right)}$      $T_e = 1467 \text{ K}$      $c_e = \sqrt{k \cdot R \cdot T_e}$      $c_e = 742 \frac{\text{m}}{\text{s}}$

The exit speed is       $V_e = M_e \cdot c_e$        $V_e = 2313 \frac{\text{m}}{\text{s}}$       and       $\rho_e = \frac{p_e}{R \cdot T_e}$        $\rho_e = 0.170 \frac{\text{kg}}{\text{m}^3}$

Then       $m_{\text{rate}} = \rho_e \cdot A_e \cdot V_e$        $m_{\text{rate}} = 19.3 \frac{\text{kg}}{\text{s}}$

The momentum equation (Eq. 4.33) simplifies to       $(p_e - p_{\text{atm}}) \cdot A_e - M_{\text{CV}} \cdot a_x = -V_e \cdot m_{\text{rate}}$

Hence       $R_x = (p_e - p_{\text{atm}}) \cdot A_e + V_e \cdot m_{\text{rate}}$        $R_x = 43.5 \cdot \text{kN}$

### Problem 13.59

[Difficulty: 3]

13.59 Nitrogen, at a pressure and temperature of 371 kPa (abs) and 400 K, enters a nozzle with negligible speed. The exhaust jet is directed against a large flat plate that is perpendicular to the jet axis. The flow leaves the nozzle at atmospheric pressure. The exit area is 0.003 m<sup>2</sup>. Find the force required to hold the plate.

Solution:

Basic equations:  $F_R = -R_x = -\dot{m}V_1$  (momentum eq. for CV shown)

$$\dot{m} = \rho VA = \text{const}$$

$$P = \rho RT$$

Compressibility equations:

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$$

$$\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}$$

Assumptions: 1) steady flow

4) Patm over entire CV

2) isentropic flow in nozzle

5)  $F_{Rx} = 0$

3) uniform flow at a section

6) ideal gas  $k = 1.40$

$$\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}} \quad ; \quad M_1 = \left\{ \frac{2}{k-1} \left[ \left( \frac{P_0}{P} \right)^{\frac{k-1}{k}} - 1 \right] \right\}^{1/2} = \left\{ \frac{2}{0.4} \left[ \left( \frac{371}{101} \right)^{0.286} - 1 \right] \right\}^{1/2} = 1.50$$


$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2 \quad ; \quad T_1 = \frac{T_0}{1 + \frac{k-1}{2} M^2} = \frac{400 \text{ K}}{1 + 0.2(1.50)^2} = 276 \text{ K}$$

$$V_1 = M_1 c_1 = M_1 \left( \sqrt{kRT_1} \right)^{1/2} = 1.5 \cdot 1.4 \cdot 297 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \cdot 276 \text{ K} \cdot \frac{1}{1.5^2}^{1/2} = 508 \text{ m/s}$$

$$P_1 = \frac{P_0}{\left( 1 + \frac{k-1}{2} M^2 \right)^{\frac{k}{k-1}}} = \frac{371 \cdot 10^3 \text{ N/m}^2}{\left( 1 + 0.2(1.50)^2 \right)^{1.4} \cdot 1.4} = 123 \frac{\text{N}}{\text{m}^2}$$

$$\dot{m} = \rho_1 V_1 A_1 = 123 \frac{\text{kg}}{\text{m}^3} \cdot 508 \frac{\text{m}}{\text{s}} \cdot 0.003 \text{ m}^2 = 1.87 \frac{\text{kg}}{\text{s}}$$

$$R_x = \dot{m} V_1 = 1.87 \frac{\text{kg}}{\text{s}} \cdot 508 \frac{\text{m}}{\text{s}} \cdot \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} = 950 \text{ N} \quad \leftarrow \text{(to the left as shown). } R_x$$



### Problem 13.60

[Difficulty: 3]

**13.60** A liquid rocket motor is fueled with hydrogen and oxygen. The chamber temperature and absolute pressure are 3300 K and 6.90 MPa. The nozzle is designed to expand the exhaust gases isentropically to a design back pressure corresponding to an altitude of 10 km on a standard day. The thrust produced by the motor is to be 100 kN at design conditions. Treat the exhaust gases as water vapor and assume ideal gas behavior. Determine the propellant mass flow rate needed to produce the desired thrust, the nozzle exit area, and the area ratio,  $A_e/A_t$ .

#### Solution

Basic equations:  $F_{R_x} = R_x = \dot{m} V_e$        $\dot{m} = \rho V A$        $P = \rho R T$

Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$        $\frac{P_0}{P} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}$

$$\frac{A}{A^*} = \frac{1}{M} \left[ \frac{1 + \frac{k-1}{2} M^2}{1 + \frac{k-1}{2}} \right]^{\frac{k+1}{2(k-1)}} \quad (12.6)$$

Assumptions: (1) steady flow      (4) thrust specified at altitude

(2) isentropic flow      (5)  $F_{R_x} = 0$

(3) uniform flow at section      (6) ideal gas,  $k=1.3$ ,  $R=461 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}}$

$$P_0/P = \left[ 1 + \frac{k-1}{2} M^2 \right]^{\frac{k}{k-1}}; \quad M_e = \left\{ \frac{2}{k-1} \left[ \left( \frac{P_0}{P} \right)^{\frac{k-1}{k}} - 1 \right] \right\}^{\frac{1}{2}} = \left\{ \frac{2}{0.30} \left[ (2.164)^{0.231} - 1 \right] \right\}^{\frac{1}{2}} = 4.18$$

$$T_0/T = 1 + \frac{k-1}{2} M^2; \quad T_e = \frac{T_0}{1 + \frac{k-1}{2} M_e^2} = \frac{3300 \text{ K}}{1 + 0.15(4.18)^2} = 911 \text{ K}$$


$$V_e = M_e c_e = M_e (k R T_e)^{\frac{1}{2}} = 4.18 \left[ 1.3 \times 461 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 911 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{kg}\cdot\text{s}^2} \right]^{\frac{1}{2}} = 3090 \text{ m/s}$$

$$R_x = \dot{m} V_e; \quad \dot{m} = \frac{R_x}{V_e} = \frac{10^5 \text{ N}}{3090 \text{ m/s}} = \frac{\text{kg}\cdot\text{m}}{\text{s}^2} \times \frac{\text{s}}{\text{kg}\cdot\text{m}} = 32.4 \text{ kg/s} \quad \leftarrow \dot{m}$$

$$\rho_e = \frac{P_e}{R T_e} = \frac{26.4 \times 10^3 \frac{\text{N}}{\text{m}^2}}{461 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 911 \text{ K}} = 6.29 \times 10^{-2} \frac{\text{kg}}{\text{m}^3}$$

$$\dot{m} = \rho_e V_e A_e; \quad A_e = \frac{\dot{m}}{\rho_e V_e} = \frac{32.4 \frac{\text{kg}}{\text{s}}}{6.29 \times 10^{-2} \frac{\text{kg}}{\text{m}^3} \times 3090 \frac{\text{m}}{\text{s}}} = 0.167 \text{ m}^2 \quad \leftarrow A_e$$

$$\text{For } M_e = 4.18, \text{ from Eq. (12.6), } A_0/A^* = A_0/A_e = 19.4 \quad \leftarrow A_0/A_e$$



### Problem 13.61

[Difficulty: 3]

**13.61** A small rocket motor, fueled with hydrogen and oxygen, is tested on a thrust stand at a simulated altitude of 10 km. The motor is operated at chamber stagnation conditions of 1500 K and 8.0 MPa (gage). The combustion product is water vapor, which may be treated as an ideal gas. Expansion occurs through a converging-diverging nozzle with design Mach number of 3.5 and exit area of 700 mm<sup>2</sup>. Evaluate the pressure at the nozzle exit plane. Calculate the mass flow rate of exhaust gas. Determine the force exerted by the rocket motor on the thrust stand.

Solution:

Basic equations:  $\dot{m} = \rho VA$ ,  $P = \rho RT$

Assumptions: (1) steady flow (3) ideal gas behavior  
(2) isentropic flow  $k = 1.3$ ,  $R = 461 \text{ J/kg}\cdot\text{K}$

At 10 km altitude,  $P_b = 26.5 \text{ kPa}$  (Table A.3)

Evaluate design pressure at exit

$$\frac{P_0}{P} = \left[ 1 + \frac{(k-1)M^2}{2} \right]^{\frac{k}{k-1}} \therefore P_d = \frac{8.10 \times 10^6 \text{ Pa}}{\left[ 1 + 0.15(3.5)^2 \right]^{4.333}} = 88.3 \text{ kPa (abs)}$$

Since  $P_b < P_d$ ,  $P_e = P_d = 88.3 \text{ kPa}$

$$\frac{T_0}{T_e} = 1 + \frac{k-1}{2} M_e^2 \therefore T_e = \frac{T_0}{1 + \frac{k-1}{2} M_e^2} = \frac{1500 \text{ K}}{1 + 0.15(3.5)^2} = 529 \text{ K}$$

$$P_e = \frac{\rho_e R T_e}{1} = 88.3 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg}\cdot\text{K}}{461 \text{ N}\cdot\text{m}} \times \frac{1}{529 \text{ K}} = 0.362 \frac{\text{kg}}{\text{m}^3}$$

$$V_e = M_e c_e = 3.5 \left[ 1.30 \times 461 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 529 \text{ K} \right]^{\frac{1}{2}} = 1970 \text{ m/s}$$

$$\dot{m} = \rho_e V_e A_e = 0.362 \frac{\text{kg}}{\text{m}^3} \times 1970 \frac{\text{m}}{\text{s}} \times 700 \text{ mm}^2 \times \frac{\text{m}^2}{10^6 \text{ mm}^2} = 0.499 \frac{\text{kg}}{\text{s}}$$

To determine force on test stand apply a momentum equation to CV shown

Basic equation:  $F_{s_x} + F_{R_x} = \frac{\partial}{\partial t} \int_{CV} V_x \rho dV + \int_{CS} V_x \rho \vec{V} \cdot d\vec{A}$


$$R_x + P_b A_e - P_e A_e = \dot{m} V_e$$

Force on test stand is  $K_x = -R_x$

$$\therefore K_x = -R_x = -\dot{m} V_e - A_e (P_e - P_b)$$

$$K_x = -0.499 \frac{\text{kg}}{\text{s}} \times 1970 \frac{\text{m}}{\text{s}} \times \frac{\text{N}\cdot\text{s}^2}{\text{kg}\cdot\text{m}} - 700 \text{ mm}^2 \times \frac{\text{m}^2}{10^6 \text{ mm}^2} (88.3 - 26.5) \times 10^3 \frac{\text{N}}{\text{m}^2}$$

$$K_x = -1,026 \text{ N (to left)}$$



## Problem 13.62

[Difficulty: 4]

**13.62** A CO<sub>2</sub> cartridge is used to propel a small rocket cart. Compressed gas, stored at 35 MPa and 20°C, is expanded through a smoothly contoured converging nozzle with 0.5 mm throat diameter. The back pressure is atmospheric. Calculate the pressure at the nozzle throat. Evaluate the mass flow rate of carbon dioxide through the nozzle. Determine the thrust available to propel the cart. How much would the thrust increase if a diverging section were added to the nozzle to expand the gas to atmospheric pressure? What is the exit area? Show stagnation states, static states, and the processes on a *Ts* diagram.

**Given:** Compressed CO<sub>2</sub> in a cartridge expanding through a nozzle

**Find:** Throat pressure; Mass flow rate; Thrust; Thrust increase with diverging section; Exit area

**Solution:**

Basic equations: 
$$F_x = F_{S_x} + F_{B_x} = \frac{\partial}{\partial t} \int_{CV} u \rho dV + \int_{CS} u \rho \vec{V} \cdot d\vec{A}$$

Assumptions: 1) Isentropic flow 2) Stagnation in cartridge 3) Ideal gas 4) Uniform flow

Given or available data:  $k = 1.29$        $R = 188.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $p_{\text{atm}} = 101 \cdot \text{kPa}$

$p_0 = 35 \cdot \text{MPa}$        $T_0 = (20 + 273) \cdot \text{K}$        $d_t = 0.5 \cdot \text{mm}$

From isentropic relations 
$$p_{\text{crit}} = \frac{p_0}{\left(1 + \frac{k-1}{2}\right)^{\frac{k}{k-1}}}$$
       $p_{\text{crit}} = 19.2 \cdot \text{MPa}$

Since  $p_b \ll p_{\text{crit}}$ , then  $p_t = p_{\text{crit}}$        $p_t = 19.2 \cdot \text{MPa}$

Throat is critical so  $m_{\text{rate}} = \rho_t \cdot V_t \cdot A_t$

$$T_t = \frac{T_0}{1 + \frac{k-1}{2}}$$
       $T_t = 256 \text{ K}$

$$V_t = \sqrt{k \cdot R \cdot T_t}$$
       $V_t = 250 \frac{\text{m}}{\text{s}}$

$$A_t = \frac{\pi \cdot d_t^2}{4}$$
       $A_t = 1.963 \times 10^{-7} \text{ m}^2$

$$\rho_t = \frac{p_t}{R \cdot T_t}$$
       $\rho_t = 396 \frac{\text{kg}}{\text{m}^3}$

$$m_{\text{rate}} = \rho_t \cdot V_t \cdot A_t$$
       $m_{\text{rate}} = 0.0194 \frac{\text{kg}}{\text{s}}$

For 1D flow with no body force the momentum equation reduces to

$$R_x - p_{tgage} \cdot A_t = m_{rate} \cdot V_t \quad p_{tgage} = p_t - p_{atm}$$

$$R_x = m_{rate} \cdot V_t + p_{tgage} \cdot A_t \quad R_x = 8.60 \text{ N}$$

When a diverging section is added the nozzle can exit to atmospheric pressure

$$p_e = p_{atm}$$

Hence the Mach number at exit is

$$M_e = \left[ \frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_e} \right)^{\frac{k-1}{k}} - 1 \right] \right]^{\frac{1}{2}} \quad M_e = 4.334$$

$$T_e = \frac{T_0}{1 + \frac{k-1}{2} \cdot M_e^2} \quad T_e = 78.7 \text{ K}$$

$$c_e = \sqrt{k \cdot R \cdot T_e} \quad c_e = 138 \frac{\text{m}}{\text{s}}$$

$$V_e = M_e \cdot c_e \quad V_e = 600 \frac{\text{m}}{\text{s}}$$

The mass flow rate is unchanged (choked flow)

From the momentum equation

$$R_x = m_{rate} \cdot V_e \quad R_x = 11.67 \text{ N}$$

The percentage increase in thrust is


$$\frac{11.67 \cdot \text{N} - 8.60 \cdot \text{N}}{8.60 \cdot \text{N}} = 35.7\%$$

The exit area is obtained from

$$m_{rate} = \rho_e \cdot V_e \cdot A_e \quad \text{and}$$

$$\rho_e = \frac{p_e}{R \cdot T_e} \quad \rho_e = 6.79 \frac{\text{kg}}{\text{m}^3}$$

$$A_e = \frac{m_{rate}}{\rho_e \cdot V_e} \quad A_e = 4.77 \times 10^{-6} \text{ m}^2 \quad A_e = 4.77 \cdot \text{mm}^2$$



## Problem 13.63

[Difficulty: 3]

**13.63** A rocket motor is being tested at sea level where the pressure is 14.7 psia. The chamber pressure is 175 psia, the chamber temperature is 5400°R, and the nozzle has a throat area of 1 in<sup>2</sup>. The exhaust gas has a ratio of specific heats of  $k = 1.25$  and a gas constant  $R = 70.6$  ft·lbf/lbm·°R. Assuming adiabatic, frictionless flow in the nozzle, determine (a) the nozzle exit area and velocity and (b) the thrust generated.

**Given:** Rocket motor

**Find:** Nozzle exit area, velocity, and thrust generated

**Solution:**

The given or available data is:

$R =$	70.6	ft·lbf/lbm·°R
$k =$	1.25	
$p_0 =$	175	psia
$T_0 =$	5400	°R
$A_t =$	1	in <sup>2</sup>
$p_e =$	14.7	psia

Equations and Computations:

The exit Mach number can be calculated based on the pressure ratio:

$$M_e = 2.2647$$

The isentropic area ratio at this Mach number is:

$$A_e/A_t^* = 2.4151$$

So the nozzle exit area is:

$$A_e = 2.42 \text{ in}^2$$

The exit temperature can be found from the Mach number:

$$T_e = 3290.4 \text{ °R}$$

The sound speed at the exit is:

$$c_e = 3057.8 \text{ ft/s}$$

And so the exit flow speed is:

$$V_e = 6925.2 \text{ ft/s}$$

The density can be calculated using the ideal gas equation of state:

$$\rho_e = 0.009112 \text{ lbm/ft}^3$$

The nozzle is choked, and we can use the choked flow equation:

From  $p_0$ ,  $T_0$ ,  $A_t$ , and Eq. 13.10a

$$\dot{m}_{\text{choked}} = A_t p_0 \sqrt{\frac{k}{RT_0} \left(\frac{2}{k+1}\right)^{(k+1)/2(k-1)}} \quad (13.10a)$$
$$m = 1.058 \text{ lbm/s}$$

Based on the momentum equation, we can calculate the thrust generated:

$$R_x = 228 \text{ lbf}$$

Note that since the flow expanded perfectly (the nozzle exit pressure is equal to the ambient pressure), the pressure terms drop out of the thrust calculation.

## Problem 13.64

[Difficulty: 4]

---

**13.64** If the rocket motor of Problem 13.63 is modified by cutting off the diverging portion of the nozzle, what will be the exit pressure and thrust?

---

**Given:** Rocket motor with converging-only nozzle

**Find:** Nozzle exit pressure and thrust

**Solution:**

The given or available data is:

$R =$	70.6	ft-lbf/lbm-°R
$k =$	1.25	
$p_0 =$	175	psia
$T_0 =$	5400	°R
$A_t =$	1	in <sup>2</sup>
$p_b =$	14.7	psia

Equations and Computations:

If the diverging portion of the nozzle is removed, the exit Mach number is 1:

The exit Mach number can be calculated based on the pressure ratio:

$$M_e = 1.0000$$

The isentropic area ratio at this Mach number is:

$$A_e/A^* = 1.0000$$

So the nozzle exit area is:

$$A_t = 1.00 \text{ in}^2$$

The exit temperature and pressure can be found from the Mach number:

$$\begin{aligned} T_e &= 4800.0 \text{ °R} \\ p_e &= 97.1 \text{ psia} \end{aligned}$$

The sound speed at the exit is:

$$c_e = 3693.2 \text{ ft/s}$$

And so the exit flow speed is:

$$V_e = 3693.2 \text{ ft/s}$$

The nozzle is choked, and we can use the choked flow equation:

From  $p_0$ ,  $T_0$ ,  $A_t$ , and Eq. 13.9a

$$\dot{m}_{\text{choked}} = A_e p_0 \sqrt{\frac{k}{RT_0}} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)} \quad (13.9a)$$

$$m = 1.058 \text{ lbf/s}$$

Based on the momentum equation, we can calculate the thrust generated:

$$F = 204 \text{ lbf}$$

## Problem 13.65

[Difficulty: 3]

---

**13.65** Consider the converging-diverging option of Problem 13.62. To what pressure would the compressed gas need to be raised (keeping the temperature at 20°C) to develop a thrust of 15N? (Assume isentropic flow.)

---

**Given:** CO<sub>2</sub> cartridge and convergent nozzle

**Find:** Tank pressure to develop thrust of 15 N

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 188.9 \text{ J/kg K} \\k &= 1.29 \\T_0 &= 293 \text{ K} \\p_b &= 101 \text{ kPa} \\D_t &= 0.5 \text{ mm}\end{aligned}$$

Equations and Computations:

$$A_t = 0.196 \text{ mm}^2$$

The momentum equation gives

$$R_x = m_{\text{flow}} V_e$$

Hence, we need  $m_{\text{flow}}$  and  $V_e$

For isentropic flow

$$\begin{aligned}p_e &= p_b \\p_e &= 101 \text{ kPa}\end{aligned}$$

If we knew  $p_0$  we could use it and  $p_e$ , and Eq. 13.7a, to find  $M_e$ .

Once  $M_e$  is known, the other exit conditions can be found.

**Make a guess for  $p_0$ , and eventually use *Goal Seek* (see below).**

$$p_0 = 44.6 \text{ MPa}$$

From  $p_0$  and  $p_e$ , and Eq. 13.7a

(using built-in function *IsenMfromp* ( $M, k$ ))

$$\begin{aligned}\frac{p_0}{p} &= \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \\M_e &= 4.5\end{aligned} \quad (13.7a)$$

From  $M_e$  and  $T_0$  and Eq. 13.7b  
(using built-in function  $IsenT(M,k)$ )

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2 \quad (13.7b)$$

$$T_e = 74.5 \quad \text{K}$$

From  $T_e$  and Eq. 12.18

$$c = \sqrt{kRT} \quad (12.18)$$

$$c_e = 134.8 \quad \text{m/s}$$

Then

$$V_e = 606 \quad \text{m/s}$$

The mass flow rate is obtained from  $p_0$ ,  $T_0$ ,  $A_t$ , and Eq. 13.10a

$$\dot{m}_{\text{choked}} = A_t p_0 \sqrt{\frac{k}{RT_0}} \left( \frac{2}{k+1} \right)^{(k+1)/2(k-1)} \quad (13.10a)$$

$$m_{\text{choked}} = 0.0248 \quad \text{kg/s}$$

Finally, the momentum equation gives

$$\begin{aligned} R_x &= m_{\text{flow}} V_e \\ &= 15.0 \quad \text{N} \end{aligned}$$

We need to set  $R_x$  to 15 N. To do this use *Goal Seek* to vary  $p_0$  to obtain the result!

## Problem 13.66


[Difficulty: 3]

**13.66** Testing of a demolition explosion is to be evaluated. Sensors indicate that the shock wave generated at the instant of explosion is 30 MPa (abs). If the explosion occurs in air at 20°C and 101 kPa, find the speed of the shock wave, and the temperature and speed of the air just after the shock passes. As an approximation assume  $k = 1.4$ . (Why is this an approximation?)

**Given:** Normal shock due to explosion

**Find:** Shock speed; temperature and speed after shock

**Solution:**



Basic equations:

$$M_2^2 = \frac{M_1^2 + \frac{2}{k-1}}{\left(\frac{2 \cdot k}{k-1}\right) \cdot M_1^2 - 1}$$

$$V = M \cdot c = M \cdot \sqrt{k \cdot R \cdot T}$$

$$\frac{p_2}{p_1} = \frac{2 \cdot k}{k+1} \cdot M_1^2 - \frac{k-1}{k+1}$$

$$\frac{T_2}{T_1} = \frac{\left(1 + \frac{k-1}{2} \cdot M_1^2\right) \cdot \left(k \cdot M_1^2 - \frac{k-1}{2}\right)}{\left(\frac{k+1}{2}\right)^2 \cdot M_1^2}$$

Given or available data     $k = 1.4$                        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$                        $p_2 = 30 \cdot \text{MPa}$                        $p_1 = 101 \cdot \text{kPa}$                        $T_1 = (20 + 273) \cdot \text{K}$

From the pressure ratio     $M_1 = \sqrt{\left(\frac{k+1}{2 \cdot k}\right) \cdot \left(\frac{p_2}{p_1} + \frac{k-1}{k+1}\right)}$                        $M_1 = 16.0$

Then we have     $T_2 = T_1 \cdot \frac{\left(1 + \frac{k-1}{2} \cdot M_1^2\right) \cdot \left(k \cdot M_1^2 - \frac{k-1}{2}\right)}{\left(\frac{k+1}{2}\right)^2 \cdot M_1^2}$                        $T_2 = 14790 \text{ K}$                        $T_2 = 14517 \cdot ^\circ\text{C}$

$$M_2 = \sqrt{\frac{M_1^2 + \frac{2}{k-1}}{\left(\frac{2 \cdot k}{k-1}\right) \cdot M_1^2 - 1}}$$

$M_2 = 0.382$

Then the speed of the shock ( $V_s = V_1$ ) is     $V_1 = M_1 \cdot \sqrt{k \cdot R \cdot T_1}$                        $V_1 = 5475 \frac{\text{m}}{\text{s}}$                        $V_s = V_1$                        $V_s = 5475 \frac{\text{m}}{\text{s}}$

After the shock ( $V_2$ ) the speed is     $V_2 = M_2 \cdot \sqrt{k \cdot R \cdot T_2}$                        $V_2 = 930 \frac{\text{m}}{\text{s}}$

But we have     $V_2 = V_s - V$                        $V = V_s - V_2$                        $V = 4545 \frac{\text{m}}{\text{s}}$

These results are unrealistic because at the very high post-shock temperatures experienced, the specific heat ratio will NOT be constant! The extremely high initial air velocity and temperature will rapidly decrease as the shock wave expands in a spherical manner and thus weakens.

## Problem 13.67

[Difficulty: 2]

---

**13.67** A standing normal shock occurs in air which is flowing at a Mach number of 1.75. What are the pressure and temperature ratios across the shock? What is the increase in entropy across the shock?

---

**Given:** Standing normal shock

**Find:** Pressure and temperature ratios; entropy increase

**Solution:**

The given or available data is:

$R =$	286.9	J/kg-K
$c_p =$	1004	J/kg-K
$k =$	1.4	
$M_1 =$	1.75	

Equations and Computations:

The pressure ratio is:

$$p_2/p_1 = 3.41$$

The temperature ratio is:

$$T_2/T_1 = 1.495$$

The entropy increase across the shock is:

$$\Delta s = 51.8 \text{ J/kg-K}$$

## Problem 13.68

[Difficulty: 3]

---

**13.68** Air flows into a converging duct, and a normal shock stands at the exit of the duct. Downstream of the shock, the Mach number is 0.54. If  $p_2/p_1 = 2$ , compute the Mach number at the entrance of the duct and the area ratio  $A_1/A_2$ .

---

**Given:** Air flowing into converging duct, normal shock standing at duct exit

**Find:** Mach number at duct entrance, duct area ratio

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\c_p &= 1004 && \text{J/kg-K} \\k &= 1.4 \\M_3 &= 0.54 \\p_2/p_1 &= 2\end{aligned}$$

Equations and Computations:

For the given post-shock Mach number, there can be only one Mach number upstream of the shock wave:

$$\begin{aligned}M_2 &= 2.254 \\M_3 &= 0.5400\end{aligned}$$

(We used Solver to match the post-shock Mach number by varying  $M_2$ .)

The stagnation pressure is constant in the duct:

$$\begin{aligned}p_0/p_2 &= 11.643 \\p_0/p_1 &= 23.285\end{aligned}$$

So the duct entrance Mach number is:

$$M_1 = 2.70$$

The isentropic area ratios at stations 1 and 2 are:

$$\begin{aligned}A_1/A^* &= 3.1832 \\A_2/A^* &= 2.1047\end{aligned}$$


So the duct area ratio is:

$$A_1/A_2 = 1.512$$

## Problem 13.69

[Difficulty: 2]

**13.69** A normal shock occurs when a pitot-static tube is inserted into a supersonic wind tunnel. Pressures measured by the tube are  $p_{02} = 10$  psia and  $p_2 = 8$  psia. Before the shock,  $T_1 = 285^\circ\text{R}$  and  $p_1 = 1.75$  psia. Calculate the air speed in the wind tunnel.



**Given:** Normal shock near pitot tube

**Find:** Air speed

**Solution:**

Basic equations:  $p_1 - p_2 = \rho_1 \cdot V_1 \cdot (V_2 - V_1)$  (Momentum)  $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$

Given or available data  $T_1 = 285 \cdot \text{R}$   $p_1 = 1.75 \cdot \text{psi}$   $p_{02} = 10 \cdot \text{psi}$   $p_2 = 8 \cdot \text{psi}$

$k = 1.4$   $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}}$

At state 2  $M_2 = \sqrt{\frac{2}{k-1} \cdot \left[ \left( \frac{p_{02}}{p_2} \right)^{\frac{k-1}{k}} - 1 \right]}$   $M_2 = 0.574$

From momentum  $p_1 - p_2 = \rho_2 \cdot V_2^2 - \rho_1 \cdot V_1^2$  but  $\rho \cdot V^2 = \rho \cdot c^2 \cdot M^2 = \frac{p}{R \cdot T} \cdot k \cdot R \cdot T \cdot M^2 = k \cdot p \cdot M^2$

$p_1 - p_2 = k \cdot p_2 \cdot M_2^2 - k \cdot p_1 \cdot M_1^2$  or  $p_1 \cdot (1 + k \cdot M_1^2) = p_2 \cdot (1 + k \cdot M_2^2)$

Hence  $M_1 = \sqrt{\frac{1}{k} \cdot \left[ \frac{p_2}{p_1} \cdot (1 + k \cdot M_2^2) - 1 \right]}$   $M_1 = 2.01$

Also  $c_1 = \sqrt{k \cdot R_{\text{air}} \cdot T_1}$   $c_1 = 827 \cdot \frac{\text{ft}}{\text{s}}$

Then  $V_1 = M_1 \cdot c_1$   $V_1 = 1666 \cdot \frac{\text{ft}}{\text{s}}$

Note: With  $p_1 = 1.5$  psi we obtain  $V_1 = 1822 \cdot \frac{\text{ft}}{\text{s}}$

(Using normal shock functions, for  $\frac{p_2}{p_1} = 4.571$  we find  $M_1 = 2.02$   $M_2 = 0.573$  Check!

## Problem 13.70

[Difficulty: 3]

**13.70** A large tank containing air at 125 psia and 175°F is attached to a converging-diverging nozzle that has a throat area of 1.5 in.<sup>2</sup> through which the air is exiting. A normal shock sits at a point in the nozzle where the area is 2.5 in.<sup>2</sup>. The nozzle exit area is 3.5 in.<sup>2</sup>. What are the Mach numbers just after the shock and at the exit? What are the stagnation and static pressures before and after the shock?

**Given:** C-D nozzle with normal shock

**Find:** Mach numbers at the shock and at exit; Stagnation and static pressures before and after the shock

**Solution:**

Basic equations: Isentropic flow  $\frac{A}{A_{\text{crit}}} = \frac{1}{M} \cdot \left( \frac{1 + \frac{k-1}{2} \cdot M^2}{\frac{k+1}{2}} \right)^{\frac{k+1}{2 \cdot (k-1)}}$   $\frac{p_0}{p} = \left( 1 + \frac{k-1}{2} \cdot M^2 \right)^{\frac{k}{k-1}}$

Normal shock  $M_2^2 = \frac{M_1^2 + \frac{2}{k-1}}{\left( \frac{2 \cdot k}{k-1} \right) \cdot M_1^2 - 1}$   $\frac{p_2}{p_1} = \frac{2 \cdot k}{k+1} \cdot M_1^2 - \frac{k-1}{k+1}$   $\frac{p_{02}}{p_{01}} = \frac{\left( \frac{\frac{k+1}{2} \cdot M_1^2}{1 + \frac{k-1}{2} \cdot M_1^2} \right)^{\frac{k}{k-1}}}{\left( \frac{2 \cdot k}{k+1} \cdot M_1^2 - \frac{k-1}{k+1} \right)^{\frac{1}{k-1}}}$

Given or available data  $k = 1.4$   $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$   $p_{01} = 125 \cdot \text{psi}$   $T_0 = (175 + 460) \cdot \text{R}$

$A_t = 1.5 \cdot \text{in}^2$   $A_s = 2.5 \cdot \text{in}^2$  (Shock area)  $A_e = 3.5 \cdot \text{in}^2$

Because we have a normal shock the CD must be accelerating the flow to supersonic so the throat is at critical state.

$$A_{\text{crit}} = A_t$$

At the shock we have  $\frac{A_s}{A_{\text{crit}}} = 1.667$

At this area ratio we can find the Mach number before the shock from the isentropic relation  $\frac{A_s}{A_{\text{crit}}} = \frac{1}{M_1} \cdot \left( \frac{1 + \frac{k-1}{2} \cdot M_1^2}{\frac{k+1}{2}} \right)^{\frac{k+1}{2 \cdot (k-1)}}$

Solving iteratively (or using *Excel's Solver*, or even better the function *isenMsupfromA* from the Web site!)  $M_1 = 1.985$

The stagnation pressure before the shock was given:  $p_{01} = 125 \cdot \text{psi}$

The static pressure is then  $p_1 = \frac{p_{01}}{\left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)^{\frac{k}{k-1}}}$   $p_1 = 16.4 \cdot \text{psi}$

After the shock we have

$$M_2 = \sqrt{\frac{M_1^2 + \frac{2}{k-1}}{\left(\frac{2 \cdot k}{k-1}\right) \cdot M_1^2 - 1}} \quad M_2 = 0.580$$

Also

$$p_{02} = p_{01} \cdot \frac{\left(\frac{\frac{k+1}{2} \cdot M_1^2}{1 + \frac{k-1}{2} \cdot M_1^2}\right)^{\frac{k}{k-1}}}{\left(\frac{2 \cdot k}{k+1} \cdot M_1^2 - \frac{k-1}{k+1}\right)^{\frac{1}{k-1}}} \quad p_{02} = 91.0 \cdot \text{psi}$$

and

$$p_2 = p_1 \cdot \left(\frac{2 \cdot k}{k+1} \cdot M_1^2 - \frac{k-1}{k+1}\right) \quad p_2 = 72.4 \cdot \text{psi}$$

Finally, for the Mach number at the exit, we could find the critical area change across the shock; instead we find the new critical area from isentropic conditions at state 2.

$$A_{\text{crit}2} = A_s \cdot M_2 \cdot \left(\frac{1 + \frac{k-1}{2} \cdot M_2^2}{\frac{k+1}{2}}\right)^{-\frac{k+1}{2 \cdot (k-1)}} \quad A_{\text{crit}2} = 2.06 \cdot \text{in}^2$$

At the exit we have

$$\frac{A_e}{A_{\text{crit}2}} = 1.698$$

At this area ratio we can find the Mach number before the shock from the isentropic relation

$$\frac{A_e}{A_{\text{crit}2}} = \frac{1}{M_e} \cdot \left(\frac{1 + \frac{k-1}{2} \cdot M_e^2}{\frac{k+1}{2}}\right)^{\frac{k+1}{2 \cdot (k-1)}}$$

Solving iteratively (or using *Excel's Solver*, or even better the function *isenMsubfromA* from the Web site!)  $M_e = 0.369$

These calculations are obviously a LOT easier using the *Excel* functions available on the Web site!

# Problem 13.71

[Difficulty: 2]

13.71 A total-pressure probe is placed in a supersonic wind tunnel where  $T = 530^\circ\text{R}$  and  $M = 2.0$ . A normal shock stands in front of the probe. Behind the shock,  $M_2 = 0.577$  and  $p_2 = 5.76$  psia. Find (a) the downstream stagnation pressure and stagnation temperature and (b) all fluid properties upstream from the shock. Show static and stagnation state points and the process path on a  $Ts$  diagram.

Solution:

Computing equations:  $\rho(1+kM^2) = \text{const.}$  (across shock)

$$\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2 \quad \frac{p_0}{p} = \left(\frac{T_0}{T}\right)^{\frac{k+1}{k-1}}$$

Assumptions: (1) steady flow (2) ideal gas (3) uniform flow at a section

Across the shock  $\rho(1+kM^2) = \text{const.}$

$$\therefore p_1 = p_2 \frac{(1+kM_2^2)}{(1+kM_1^2)} = 5.76 \text{ psia} \frac{[1+1.4(0.577)^2]}{[1+1.4(2)^2]} = 1.28 \text{ psia} \quad p_1$$

$$p_1 = \frac{p_1}{RT_1} = 1.28 \frac{\text{lb}_f}{\text{in}^2} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{1}{530^\circ\text{R}} = 0.00653 \text{ lb}_f/\text{ft}^3 \quad p_1$$


$$V_1 = M_1 c_1 = M_1 (kRT)^{1/2} = 2.0 [1.4 \times 530^\circ\text{R} \times 32.2 \frac{\text{ft} \cdot \text{lb}_f}{\text{slug} \cdot \text{ft}^2}]^{1/2} = 2260 \text{ ft/s} \quad V_1$$

$$T_{01} = T_1 (1 + \frac{k-1}{2} M_1^2) = 530^\circ\text{R} [1 + 0.2(2)^2] = 954^\circ\text{R} \quad T_{01}$$

$$p_{01} = p_1 (1 + \frac{k-1}{2} M_1^2)^{\frac{k+1}{k-1}} = 1.28 \text{ psia} (1.8)^{3.5} = 10.0 \text{ psia} \quad p_{01}$$

$$p_{02} = p_2 (1 + \frac{k-1}{2} M_2^2)^{\frac{k+1}{k-1}} = 5.76 \text{ psia} [1 + 0.2(0.577)^2]^{\frac{1.4+1}{1.4-1}} = 7.22 \text{ psia} \quad p_{02}$$

$$T_{02} = T_{01} = 954^\circ\text{R}$$



Compressible-Flow Functions (Appendix E)

For  $M_1 = 2.0$ , from App. E.4

$$M_2 = 0.577 \quad (12.34b)$$

$$p_2/p_1 = 4.50 \quad (12.36) \quad \therefore p_1 = 1.28 \text{ psia}$$

$$p_{02}/p_{01} = 0.721 \quad (12.37)$$

For  $M_1 = 2.0$ , from App. E.1

$$p_1/p_{01} = 0.1278 \quad (11.70) \quad \therefore p_{01} = 10.0 \text{ psia}$$

$$\text{and } p_{02} = 0.721 p_{01} = 7.21 \text{ psia}$$

$$T/T_{01} = 0.556 \quad (11.70) \quad \therefore T_{01} = 954^\circ\text{R}$$

Note: In using the tables it is not necessary to know the downstream Mach number.

# Problem 13.72

[Difficulty: 2]

13.72 Air flows steadily through a long, insulated constant-area pipe. At section ①,  $M_1 = 2.0$ ,  $T_1 = 140^\circ\text{F}$ , and  $p_1 = 35.9$  psia. At section ②, downstream from a normal shock,  $V_2 = 1080$  ft/s. Determine the density and Mach number at section ②. Make a qualitative sketch of the pressure distribution along the pipe.

Solution:

Basic equation:  $h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2}$

- Assumptions:
- (1) steady flow
  - (2) uniform flow at a section
  - (3)  $\dot{Q} = \dot{W}_s = \dot{W}_{shear} = 0$
  - (4)  $g = 0$
  - (5) ideal gas
  - (6)  $A_1 = A_2 = A$

$$V_1 = V_1 = M_1 \sqrt{\gamma R T_1} = 2.0 \left( 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \times 600^\circ\text{R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}^2}{\text{lbm} \cdot \text{s}^2} \right)^{1/2} = 2400 \text{ ft/s}$$

$$h_1 + \frac{V_1^2}{2} = h_2 + \frac{V_2^2}{2} \quad T_2 = T_1 + \frac{1}{2\gamma} (V_1^2 - V_2^2)$$

$$T_2 = 600^\circ\text{R} + \frac{1}{2} \left[ (2400)^2 - (1080)^2 \right] \times 10^{-6} \frac{\text{ft}^2}{\text{s}^2} \times \frac{\text{lbm} \cdot \text{R}}{0.24 \text{ Btu}} \times \frac{\text{Btu}}{778 \text{ ft} \cdot \text{lb}_f} \times \frac{\text{slug}}{32.2 \text{ lbm}} \times \frac{\text{lb}_f \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$T_2 = 982^\circ\text{R}$$



$$M_2 = \frac{V_2}{c_2} \quad c_2 = (\gamma R T_2)^{1/2} = \left( 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \times 982^\circ\text{R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}^2}{\text{lbm} \cdot \text{s}^2} \right)^{1/2} = 1540 \text{ ft/s}$$

$$M_2 = \frac{1080}{1540} = 0.701$$

From continuity  $\rho_1 V_1 = \rho_2 V_2$

$$p_2 = \frac{V_1}{V_2} p_1 = \frac{V_1}{V_2} \frac{p_1}{RT_1}$$

$$p_2 = \frac{2400}{1080} \times 35.9 \frac{\text{lb}_f}{\text{ft}^2} \times \frac{\text{lbm} \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lb}_f} \times \frac{1}{600^\circ\text{R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.359 \text{ lbm/ft}^3$$



## Problem 13.73

[Difficulty: 3]

**13.73** A wind tunnel nozzle is designed to operate at a Mach number of 5. To check the flow velocity, a pitot probe is placed at the nozzle exit. Since the probe tip is blunt, a normal shock stands off the tip of the probe. If the nozzle exit static pressure is 10 kPa, what absolute pressure should the pitot probe measure? If the stagnation temperature before the nozzle is 1450 K, what is the nozzle exit velocity?

**Given:** Pitot probe used in supersonic wind tunnel nozzle

**Find:** Pressure measured by pitot probe; nozzle exit velocity

**Solution:**

The given or available data is:

$R =$	286.9	J/kg-K
$k =$	1.4	
$M_1 =$	5	
$p_1 =$	10	kPa
$T_0 =$	1450	K

Equations and Computations:

Downstream of the normal shock wave, the Mach number is:

$$M_2 = 0.4152$$

The static and stagnation pressure ratios are:

$$p_2/p_1 = 29.000$$

$$p_{02}/p_{01} = 0.06172$$

So the static pressure after the shock is:

$$p_2 = 290 \text{ kPa}$$

The pitot pressure, however, is the stagnation pressure:

$$p_{02}/p_2 = 1.12598$$

$$p_{02} = 327 \text{ kPa}$$

The static temperature at the nozzle exit can be calculated:

$$T_{01}/T_1 = 6.000$$

$$T_1 = 241.67 \text{ K}$$

At the nozzle exit the sound speed is:

$$c_2 = 311.56 \text{ m/s}$$

Therefore the flow velocity at the nozzle exit is:

$$V_2 = 1558 \text{ m/s}$$

## Problem 13.74

[Difficulty: 3]

---

**13.74** Air approaches a normal shock at  $V_1 = 900$  m/s,  $p_1 = 50$  kPa, and  $T_1 = 220$  K. What are the velocity and pressure after the shock? What would the velocity and pressure be if the flow were decelerated isentropically to the same Mach number?

---

**Given:** Air approaching a normal shock

**Find:** Pressure and velocity after the shock; pressure and velocity if flow were decelerated isentropically

**Solution:**

The given or available data is:

$R =$	286.9	J/kg-K
$k =$	1.4	
$V_1 =$	900	m/s
$p_1 =$	50	kPa
$T_1 =$	220	K

Equations and Computations:

The sonic velocity at station 1 is:

$$c_1 = 297.26 \text{ m/s}$$

So the Mach number at 1 is:

$$M_1 = 3.028$$

Downstream of the normal shock wave, the Mach number is:

$$M_2 = 0.4736$$

The static pressure and temperature ratios are:

$$p_2/p_1 = 10.528$$

$$T_2/T_1 = 2.712$$

So the exit temperature and pressure are:

$$p_2 = 526 \text{ kPa}$$

$$T_2 = 596.6 \text{ K}$$

At station 2 the sound speed is:

$$c_2 = 489.51 \text{ m/s}$$

Therefore the flow velocity is:

$$V_2 = 232 \text{ m/s}$$

If we decelerate the flow isentropically to

$$M_{2s} = 0.4736$$

The isentropic pressure ratios at station 1 and 2s are:

$$p_0/p_1 = 38.285$$

$$p_0/p_{2s} = 1.166$$

$$p_{2s}/p_1 = 32.834$$

So the final pressure is:

$$p_{2s} = 1642 \text{ kPa}$$

The temperature ratios are:

$$T_0/T_1 = 2.833$$

$$T_0/T_{2s} = 1.045$$

$$T_{2s}/T_1 = 2.712$$

So the final temperature is:

$$T_{2s} = 596.6 \text{ K}$$

The sonic velocity at station 2s is:

$$c_{2s} = 489.51 \text{ m/s}$$

Therefore the flow velocity is:

$$V_{2s} = 232 \text{ m/s}$$

## Problem 13.75

[Difficulty: 3]

**13.75** Air with stagnation conditions of 150 psia and 400°F accelerates through a converging-diverging nozzle with throat area 3 in.<sup>2</sup>. A normal shock is located where the area is 6 in.<sup>2</sup>. What is the Mach number before and after the shock? What is the rate of entropy generation through the nozzle, if there is negligible friction between the flow and the nozzle walls?

**Given:** Air accelerating through a converging-diverging nozzle, passes through a normal shock

**Find:** Mach number before and after shock; entropy generation

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.4 \\p_{01} &= 150 && \text{psia} \\T_{01} &= 400 && ^\circ\text{F} \\T_{01} &= 860 && ^\circ\text{R} \\A_t &= 3 && \text{in}^2 \\A_1 = A_2 &= 6 && \text{in}^2\end{aligned}$$

Equations and Computations:

The isentropic area ratio at the station of interest is:

$$A_1/A_1^* = 2.00$$

So the Mach number at 1 is:

$$M_1 = 2.20$$

Downstream of the normal shock wave, the Mach number is:

$$M_2 = 0.547$$

The total pressure ratio across the normal shock is:

$$p_{02}/p_{01} = 0.6294$$

Since stagnation temperature does not change across a normal shock, the increase in entropy is related to the stagnation pressure loss only:

$$\begin{aligned}\Delta s_{1-2} &= 24.7 && \text{ft-lbf/lbm-}^\circ\text{R} \\ \Delta s_{1-2} &= 0.0317 && \text{Btu/lbm-}^\circ\text{R}\end{aligned}$$

## Problem 13.76

[Difficulty: 2]

**13.76** Air approaches a normal shock at  $M_1 = 2.5$ , with  $T_{01} = 1250^\circ\text{R}$  and  $p_1 = 20$  psia. Determine the speed and temperature of the air leaving the shock and the entropy change across the shock.

**Given:** Normal shock

**Find:** Speed and temperature after shock; Entropy change

**Solution:**

The given or available data is:

$R =$	53.33	ft lbf/lbm R	0.0685	Btu/lbm R
$k =$	1.4			
$c_p =$	0.2399	Btu/lbm R		
$T_{01} =$	1250	$^\circ\text{R}$		
$p_1 =$	20	psi		
$M_1 =$	2.5			

Equations and Computations:

From  $p_1 = \rho_1 R T_1$

$\rho_1 =$	0.0432	slug/ft <sup>3</sup>
$V_1 =$	4334	ft/s

Using built-in function *IsenT*(M,k):

$T_{01}/T_1 =$	2.25	$T_1 =$	556	$^\circ\text{R}$
			96	$^\circ\text{F}$

Using built-in function *NormM2fromM*(M,k):

$M_2 =$	0.513
---------	-------

Using built-in function *NormTfromM*(M,k):

$T_2/T_1 =$	2.14	$T_2 =$	1188	$^\circ\text{R}$
			728	$^\circ\text{F}$

Using built-in function *NormpfromM*(M,k):

$p_2/p_1 =$	7.13	$p_2 =$	143	psi
-------------	------	---------	-----	-----

From  $V_2 = M_2 \sqrt{kRT_2}$

$V_2 =$	867	ft/s
---------	-----	------

From  $\Delta s = c_p \ln\left(\frac{T_2}{T_1}\right) - R \ln\left(\frac{p_2}{p_1}\right)$

$\Delta s =$	0.0476	Btu/lbm R
	37.1	ft lbf/lbm R

# Problem 13.77

[Difficulty: 2]

13.77 Air undergoes a normal shock. Upstream,  $T_1 = 35^\circ\text{C}$ ,  $p_1 = 229 \text{ kPa}$  (abs), and  $V_1 = 704 \text{ m/s}$ . Determine the temperature and stagnation pressure of the air stream leaving the shock.

Solution:

Compressible flow functions (Appendix E) to be used in solution

- Assumptions:
- 1) steady flow
  - 2) uniform flow at a section
  - 3)  $\dot{Q} = \dot{W}_e = \dot{W}_{\text{shear}} = 0$
  - 4)  $\dot{Q}_2 = 0$
  - 5)  $F_{\text{ext}} = 0$
  - 6) no friction forces
  - 7) ideal gas
  - 8)  $A_1 = A_2 = A$

$$M_1 = \frac{V_1}{c_1} = \frac{V_1}{\sqrt{\gamma R T_1}} = \frac{704}{\sqrt{1.4 \cdot 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \cdot 308 \text{ K}}} = 2.22$$

From App. E.1


$$P_{01}/P_{01} = 0.1278$$

From App. E.4

$$P_{02}/P_{01} = 0.7209 \quad T_2/T_1 = 1.687$$

$$T_2 = \frac{T_2}{T_1} \cdot T_1 = 1.687 \cdot 308 \text{ K} = 520 \text{ K}$$

$$P_{02} = \frac{P_{02}}{P_{01}} \cdot \frac{P_{01}}{P_{01}} \cdot P_{01} = 0.7209 \cdot \frac{1}{0.1278} \cdot 229 \text{ kPa} = 1.29 \text{ MPa (abs)}$$



## Problem 13.78

[Difficulty: 2]

---

**13.78** A normal shock stands in a constant-area duct. Air approaches the shock with  $T_{01} = 550 \text{ K}$ ,  $p_{01} = 650 \text{ kPa (abs)}$ , and  $M_1 = 2.5$ . Determine the static pressure downstream from the shock. Compare the downstream pressure with that reached by decelerating isentropically to the same subsonic Mach number.

---

**Given:** Normal shock

**Find:** Pressure after shock; Compare to isentropic deceleration

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg K} \\ k &= 1.4 \\ T_{01} &= 550 && \text{K} \\ p_{01} &= 650 && \text{kPa} \\ M_1 &= 2.5 \end{aligned}$$

Equations and Computations:

Using built-in function *Isenp* (M,k):

$$p_{01}/p_1 = 17.09 \qquad p_1 = 38 \text{ kPa}$$

Using built-in function *NormM2fromM* (M,k):

$$M_2 = 0.513$$

Using built-in function *NormpfromM* (M,k):

$$p_2/p_1 = 7.13 \qquad p_2 = 271 \text{ kPa}$$

Using built-in function *Isenp* (M,k) at  $M_2$ :

$$p_{02}/p_2 = 1.20$$

But for the isentropic case:

$$p_{02} = p_{01}$$

Hence for isentropic deceleration:

$$p_2 = 543 \text{ kPa}$$

## Problem 13.79

[Difficulty: 2]

**13.79** A normal shock occurs in air at a section where  $V_1 = 2000$  mph,  $T_1 = -15^\circ\text{F}$ , and  $p_1 = 5$  psia. Determine the speed and Mach number downstream from the shock, and the change in stagnation pressure across the shock.

**Given:** Normal shock

**Find:** Speed and Mach number after shock; Change in stagnation pressure

**Solution:**

The given or available data is:

$R =$	53.33	ft lbf/lbm R	0.0685	Btu/lbm R
$k =$	1.4			
$T_1 =$	445	$^\circ\text{R}$		
$p_1 =$	5	psi		
$V_1 =$	2000	mph	2933	ft/s

Equations and Computations:

From  $c_1 = \sqrt{kRT_1}$   $c_1 = 1034$  ft/s  
 Then  $M_1 = 2.84$

Using built-in function *NormM2fromM*(M,k):  
 $M_2 = 0.486$

Using built-in function *NormdfromM*(M,k):  
 $\rho_2 / \rho_1 = 3.70$

Using built-in function *Normp0fromM*(M,k):  
 $p_{02} / p_{01} = 0.378$

Then  $V_2 = \frac{\rho_1}{\rho_2} V_1$   $V_2 = 541$  mph 793 ft/s

Using built-in function *Isenp*(M,k) at  $M_1$ :  
 $p_{01} / p_1 = 28.7$

From the above ratios and given  $p_1$ :

$p_{01} =$	143	psi
$p_{02} =$	54.2	psi
$p_{01} - p_{02} =$	89.2	psi

## Problem 13.80

[Difficulty: 2]

**13.80** Air approaches a normal shock with  $T_1 = -7.5^\circ\text{F}$ ,  $p_1 = 14.7$  psia, and  $V_1 = 1750$  mph. Determine the speed immediately downstream from the shock and the pressure change across the shock. Calculate the corresponding pressure change for a frictionless, shockless deceleration between the same speeds.

**Given:** Normal shock

**Find:** Speed; Change in pressure; Compare to shockless deceleration

**Solution:**

The given or available data is:

$R =$	53.33	ft lbf/lbm R	0.0685	Btu/lbm R
$k =$	1.4			
$T_1 =$	452.5	$^\circ\text{R}$		
$p_1 =$	14.7	psi		
$V_1 =$	1750	mph	2567	ft/s

Equations and Computations:

From	$c_1 = \sqrt{kRT_1}$	$c_1 =$	1043	ft/s
Then		$M_1 =$	2.46	

Using built-in function *NormM2fromM*(M,k):

$M_2 =$	0.517
---------	-------

Using built-in function *NormdfromM*(M,k):

$\rho_2 / \rho_1 =$	3.29
---------------------	------

Using built-in function *NormpfromM*(M,k):

$p_2 / p_1 =$	6.90	$p_2 =$	101	psi
---------------	------	---------	-----	-----

$p_2 - p_1 =$	86.7	psi
---------------	------	-----

Then	$V_2 = \frac{\rho_1}{\rho_2} V_1$	$V_2 =$	532	mph	781	ft/s
------	-----------------------------------	---------	-----	-----	-----	------

Using built-in function *Isenp*(M,k) at  $M_1$ :

$p_{01} / p_1 =$	16.1
------------------	------

Using built-in function *Isenp*(M,k) at  $M_2$ :

$p_{02} / p_2 =$	1.20
------------------	------

From above ratios and $p_1$ , for isentropic flow ( $p_0 = \text{const}$ ):	$p_2 =$	197	psi
---	---------	-----	-----

$p_2 - p_1 =$	182	psi
---------------	-----	-----

# Problem 13.81

[Difficulty: 2]

13.81 A supersonic aircraft cruises at  $M = 2.2$  at 12 km altitude. A pitot tube is used to sense pressure for calculating air speed. A normal shock stands in front of the tube. Evaluate the local isentropic stagnation conditions in front of the shock. Estimate the stagnation pressure sensed by the pitot tube. Show static and stagnation state points and the process path on a  $Ts$  diagram.

Solution:


Compressible flow functions (Appendix E) to be used in solution

- Assumptions: (1) steady flow (2) uniform flow at a section  
 (3) thin shock  
 (4) ideal gas

Use table H.2 to determine properties at state ① At 12 km altitude,  
 $T_1 = 216.7 \text{ K}$        $p_1 = 19.4 \text{ kPa}$

From App. E.1, for  $M_1 = 2.2$ ,  
 $T_1/T_{01} = 0.5081$        $\therefore T_{01} = 426 \text{ K}$   
 $p_1/p_{01} = 0.09352$        $\therefore p_{01} = 207 \text{ kPa (abs)}$

From App. E.4, for  $M_1 = 2.2$ ,  $M_2 = 0.5471$   
 $p_{02}/p_{01} = 0.6281$        $\therefore p_{02} = 130 \text{ kPa (abs)}$



# Problem 13.82

[Difficulty: 2]

13.82 The Concorde supersonic transport flew at  $M = 2.2$  at 20 km altitude. Air is decelerated isentropically by the engine inlet system to a local Mach number of 1.3. The air passed through a normal shock and was decelerated further to  $M = 0.4$  at the engine compressor section. Assume, as a first approximation, that this subsonic diffusion process was isentropic and use standard atmosphere data for freestream conditions. Determine the temperature, pressure, and stagnation pressure of the air entering the engine compressor.

Solution:

Compressible flow functions (Appendix E) to be used in solution

- Assumptions:
1. Steady flow
  2. Ideal gas
  3. Flow is isentropic until across the shock.

At 20 km altitude  $T_0 = 223 \text{ K}$ ,  $P_0 = 5.53 \text{ kPa}$  (Table A.3)

$M_0 = 2.2$  From App. E.1,  $T_0/T_0 = 0.5081$ ,  $P_0/P_0 = 0.09352$   
 $\therefore T_0 = 427 \text{ K}$ ,  $P_0 = 59.1 \text{ kPa}$


$M_1 = 1.3$  From App. E.1,  $T_1/T_0 = 0.7474$ ,  $P_1/P_0 = 0.2607$   
 $\therefore T_1 = 319 \text{ K}$ ,  $P_1 = 21.3 \text{ kPa}$

From App. E.4,  $M_2 = 0.786$ ,  $P_{02}/P_{01} = 0.9794$ ,  $T_2/T_1 = 1.191$ ,  $P_2/P_1 = 1.805$   
 $\therefore P_{02} = 57.9 \text{ kPa}$ ,  $T_2 = 380 \text{ K}$ ,  $P_2 = 38.4 \text{ kPa}$

$P_{02} = P_{02} = 57.9 \text{ kPa (abs)}$

$M_3 = 0.4$  From App. E.1,  $T_3/T_2 = 0.9690$ ,  $P_3/P_{03} = 0.8956$   
 $\therefore T_3 = 414 \text{ K}$

$P_3 = 0.8956 P_{03} = 0.8956 P_{02} = 51.9 \text{ kPa (abs)}$



# Problem 13.83

[Difficulty: 2]

**13.83** Stagnation pressure and temperature probes are located on the nose of a supersonic aircraft. At 35,000 ft altitude a normal shock stands in front of the probes. The temperature probe indicates  $T_0 = 420^\circ\text{F}$  behind the shock. Calculate the Mach number and air speed of the plane. Find the static and stagnation pressures behind the shock. Show the process and the static and stagnation state points on a  $Ts$  diagram.

Solution:

Compressible flow functions (Appendix E) to be used in solution

- Assumptions: (1) steady flow (2) uniform flow at a section  
 (3) thin shock,  $R_s = 0$   
 (4) ideal gas.

Use table A.3 to determine properties at state ①.

$$\text{Altitude} = 35000 \text{ ft} \times 0.3048 \frac{\text{m}}{\text{ft}} = 10,670 \text{ m}$$

$$\text{From Table A.3} \quad T_1 = 219 \text{ K} = -54^\circ\text{C} = -65^\circ\text{F}$$

$$p_1 = 23.9 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{lb}}{4.448 \text{ N}} \times \left( \frac{0.3048 \text{ m}}{\text{ft}} \right)^2 = 499 \text{ psfa}$$

$$\text{At state ②} \quad T_1/T_0 = 395/880 = 0.4489$$

$$\text{From App. E.1, for } T_1/T_0 = 0.4489, \quad M_1 = 2.48 \quad \leftarrow M_1$$


$$V_1 = M_1 c_1 = M_1 (\sqrt{kRT_1}) = 2.48 \left[ 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lb} \cdot \text{mol} \cdot \text{R}} \times 395 \text{ R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}^2/\text{s}^2}{\text{lb} \cdot \text{ft}} \right]^{1/2} = 2420 \text{ ft/s} \quad \leftarrow V_1$$

$$\text{From App. E.1, for } M_1 = 2.48, \quad p_1/p_0 = 0.06038 \quad \therefore p_0 = 57.4 \text{ psia}$$

$$\text{From App. E.4, for } M_1 = 2.48, \quad M_2 = 0.5149$$

$$p_02/p_01 = 0.5071 \quad \therefore p_02 = 29.1 \text{ psia} \quad \leftarrow p_02$$

$$p_2/p_1 = 7.009 \quad \therefore p_2 = 24.3 \text{ psia} \quad \leftarrow p_2$$



## Problem 13.84

[Difficulty: 3]

---

**13.84** The NASA X-43A *Hyper-X* experimental hypersonic vehicle flew at Mach 9.68 at an altitude of 110,000 ft. Stagnation pressure and temperature probes were located on the nose of the aircraft. A normal shock wave stood in front of these probes. Estimate the stagnation pressure and temperature measured by the probes.

---

**Given:** Stagnation pressure and temperature probes on the nose of the Hyper-X

**Find:** Pressure and temperature read by those probes

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft}\cdot\text{lbf}/\text{lbm}\cdot^{\circ}\text{R} \\k &= 1.4 \\M_1 &= 9.68 \\z &= 110000 && \text{ft} \\z &= 33528 && \text{m} \\p_{\text{SL}} &= 14.696 && \text{psia} \\T_{\text{SL}} &= 518.76 && ^{\circ}\text{R}\end{aligned}$$

Equations and Computations:

At this altitude the local pressure and temperature are:

$$\begin{aligned}p/p_{\text{SL}} &= 0.008643 \\p_1 &= 0.12702 && \text{psia} \\T_1 &= 422.88 && ^{\circ}\text{R}\end{aligned}$$

The stagnation pressure and temperature at these conditions are:

$$\begin{aligned}p_{01}/p_1 &= 34178.42 \\p_{01} &= 4341.36 && \text{psia} \\T_{01}/T_1 &= 19.74 \\T_{01} &= 8347.81 && ^{\circ}\text{R}\end{aligned}$$

Downstream of the normal shock wave, the Mach number is:

$$M_2 = 0.3882$$

The total pressure ratio across the normal shock is:

$$p_{02}/p_{01} = 0.003543$$

So the pressure read by the probe is:

$$p_{02} = 15.38 \quad \text{psia}$$

Since stagnation temperature is constant across the shock, the probe reads:

$$T_{02} = 8348 \quad ^{\circ}\text{R}$$

## Problem 13.85

[Difficulty: 4]

**13.85** Equations 13.20 are a useful set of equations for analyzing flow through a normal shock. Derive another useful equation, the Rankine-Hugoniot relation,

$$\frac{p_2}{p_1} = \frac{(k+1)\frac{\rho_2}{\rho_1} - (k-1)}{(k+1) - (k-1)\frac{\rho_2}{\rho_1}}$$

and use it to find the density ratio for air as  $p_2/p_1 \rightarrow \infty$ .

**Given:** Normal shock

**Find:** Rankine-Hugoniot relation

**Solution:**

Basic equations:      Momentum:  $p_1 + \rho_1 \cdot V_1^2 = p_2 + \rho_2 \cdot V_2^2$       Mass:  $\rho_1 \cdot V_1 = \rho_2 \cdot V_2$

Energy:  $h_1 + \frac{1}{2} \cdot V_1^2 = h_2 + \frac{1}{2} \cdot V_2^2$       Ideal Gas:  $p = \rho \cdot R \cdot T$

From the energy equation  $2 \cdot (h_2 - h_1) = 2 \cdot c_p \cdot (T_2 - T_1) = V_1^2 - V_2^2 = (V_1 - V_2) \cdot (V_1 + V_2)$  (1)

From the momentum equation  $p_2 - p_1 = \rho_1 \cdot V_1^2 - \rho_2 \cdot V_2^2 = \rho_1 \cdot V_1 \cdot (V_1 - V_2)$  where we have used the mass equation

Hence  $V_1 - V_2 = \frac{p_2 - p_1}{\rho_1 \cdot V_1}$

Using this in Eq 1  $2 \cdot c_p \cdot (T_2 - T_1) = \frac{p_2 - p_1}{\rho_1 \cdot V_1} \cdot (V_1 + V_2) = \frac{p_2 - p_1}{\rho_1} \cdot \left(1 + \frac{V_2}{V_1}\right) = \frac{p_2 - p_1}{\rho_1} \cdot \left(1 + \frac{\rho_1}{\rho_2}\right) = (p_2 - p_1) \cdot \left(\frac{1}{\rho_1} + \frac{1}{\rho_2}\right)$

where we again used the mass equation

Using the ideal gas equation  $2 \cdot c_p \cdot \left(\frac{p_2}{\rho_2 \cdot R} - \frac{p_1}{\rho_1 \cdot R}\right) = (p_2 - p_1) \cdot \left(\frac{1}{\rho_1} + \frac{1}{\rho_2}\right)$

Dividing by  $p_1$  and multiplying by  $\rho_2$ , and using  $R = c_p - c_v$ ,  $k = c_p/c_v$

$$2 \cdot \frac{c_p}{R} \cdot \left(\frac{p_2}{p_1} - \frac{\rho_2}{\rho_1}\right) = 2 \cdot \frac{k}{k-1} \cdot \left(\frac{p_2}{p_1} - \frac{\rho_2}{\rho_1}\right) = \left(\frac{p_2}{p_1} - 1\right) \cdot \left(\frac{\rho_2}{\rho_1} + 1\right)$$

Collecting terms

$$\frac{p_2}{p_1} \cdot \left(\frac{2 \cdot k}{k-1} - 1 - \frac{\rho_2}{\rho_1}\right) = \frac{2 \cdot k}{k-1} \cdot \frac{\rho_2}{\rho_1} - \frac{\rho_2}{\rho_1} - 1$$

$$\frac{p_2}{p_1} = \frac{\frac{2 \cdot k}{k-1} \cdot \frac{\rho_2}{\rho_1} - \frac{\rho_2}{\rho_1} - 1}{\left(\frac{2 \cdot k}{k-1} - 1 - \frac{\rho_2}{\rho_1}\right)} = \frac{\frac{(k+1)}{(k-1)} \cdot \frac{\rho_2}{\rho_1} - 1}{\frac{(k+1)}{(k-1)} - \frac{\rho_2}{\rho_1}} \quad \text{or} \quad \frac{p_2}{p_1} = \frac{(k+1) \cdot \frac{\rho_2}{\rho_1} - (k-1)}{(k+1) - (k-1) \cdot \frac{\rho_2}{\rho_1}}$$

For an infinite pressure ratio  $(k+1) - (k-1) \cdot \frac{\rho_2}{\rho_1} = 0$       or       $\frac{\rho_2}{\rho_1} = \frac{k+1}{k-1}$       (= 6 for air)

# Problem 13.86

[Difficulty: 3]

13.86 A supersonic aircraft cruises at  $M = 2.7$  at 60,000 ft altitude. A normal shock stands in front of a pitot tube on the aircraft; the tube senses a stagnation pressure of 10.4 psia. Calculate the static pressure and temperature behind the shock. Evaluate the loss in stagnation pressure through the shock. Determine the change in specific entropy across the shock. Show static and stagnation states and the process path on a  $Ts$  diagram.

## Solution

Compressible flow functions (Appendix E) to be used in solution

Basic equation:  $Tds = dh - vdp$

- Assumptions: (1) steady flow (2) uniform flow at a section  
 (3) Air shock,  $R_c = 0$   
 (4) ideal gas

Use table A.3 to determine properties at state 1

Altitude = 60,000 ft  $\times 0.3048 \frac{m}{ft} = 18,290 \text{ m}$

From table A.3  $T_1 = 216.7 \text{ K} = -56.3^\circ\text{C} = -69^\circ\text{F}$

$\rho_1 = 7.25 \times 10^{-3} \frac{\text{N}}{\text{m}^2} \times \frac{1 \text{ lb}}{4.448 \text{ N}} \times \left( \frac{0.3048 \text{ m}}{\text{ft}} \right)^2 = 151 \text{ lb/ft}^2$

From App. E.1 for  $M_1 = 2.7$   $\rho_1/\rho_0 = 0.04295 \therefore \rho_0 = 24.4 \text{ lb/in}^2$

From App. E.4 for  $M_1 = 2.7$   $M_2 = 0.47526$

$\rho_2/\rho_0 = 0.4236 \therefore \rho_2 = 10.3 \text{ psia}$

$T_2/T_1 = 2.343 \therefore T_2 = 916 \text{ K} \xrightarrow{T_2}$

$\rho_2/\rho_1 = 8.339 \therefore \rho_2 = 2.74 \text{ psia} \xrightarrow{\rho_2}$


$\rho_2 - \rho_0 = 10.3 \text{ psia} - 24.4 \text{ psia} = -14.1 \text{ psia} \xrightarrow{\rho_2 - \rho_0}$

From the  $Tds$  equation,  $Tds = dh - vdp = c_p dT - RT \frac{dp}{p}$

$\therefore ds = c_p \frac{dT}{T} - R \frac{dp}{p}$

Then  $s_2 - s_1 = s_{02} - s_{01} = c_p \ln \frac{T_{02}}{T_{01}} - R \ln \frac{p_{02}}{p_{01}}$

$s_2 - s_1 = -53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lb} \cdot \text{R}} \ln \frac{10.3}{24.4} + \frac{1716 \text{ ft} \cdot \text{lb}}{778 \text{ ft} \cdot \text{lb}} \ln \frac{2.74}{10.3} = 0.0591 \frac{\text{Btu}}{\text{lb} \cdot \text{R}} \xrightarrow{s_2 - s_1}$



### Problem 13.87

[Difficulty: 3]


13.87 An aircraft is in supersonic flight at 10 km altitude on a standard day. The true air speed of the plane is 659 m/s. Calculate the flight Mach number of the aircraft. A total-head tube attached to the plane is used to sense stagnation pressure which is converted to flight Mach number by an on-board computer. However, the computer programmer has ignored the normal shock that stands in front of the total-head tube and has assumed isentropic flow. Evaluate the pressure sensed by the total-head tube. Determine the erroneous air speed calculated by the computer program.

Solution: (using compressible flow functions - Appendix E)

From Table A.3 at  $z = 10 \text{ km}$ ,  $T = 223.3 \text{ K}$ ,  $p/p_{sl} = 0.2615$

Thus  $T = 223 \text{ K}$ ,  $p = 0.2615 p_{sl} = 0.2615 \times 101.3 \text{ kPa} = 26.5 \text{ kPa}$

$$c_1 = (\gamma R T)^{1/2} = \left[ 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 223 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right]^{1/2} = 299 \text{ m/s}$$



$$M_1 = \frac{v_1}{c_1} = \frac{659}{299} = 2.20 \quad M_1$$

From App. E.1 at  $M_1 = 2.20$ ,  $p/p_0 = 0.09352 \therefore p_0 = 283 \text{ kPa}$


From App. E.4 at  $M_1 = 2.20$ ,  $p_{02}/p_{01} = 0.6281$ ,  $p_2/p_1 = 5.480$

$$\therefore p_{02} = 0.6281 p_{01} = 0.6281 \times 283 \text{ kPa} = 178 \text{ kPa (abs)} \quad p_{02}$$

If Mach number is calculated neglecting the shock then  $M$  is calculated with  $p = 26.5 \text{ kPa}$  and  $p_0 = 178 \text{ kPa}$ .

For  $p/p_0 = 26.5/178 = 0.149$ , from App. E.1,  $M_s = 1.90$

$$v_{1s} = M_s c_s = 1.90 \times 299 \text{ m/s} = 568 \text{ m/s} \quad v_{1s}$$



# Problem 13.88

[Difficulty: 3]

**13.88** A supersonic aircraft flies at  $M_1 = 2.7$  at 20 km altitude on a standard day. Air enters the engine inlet system, where it is slowed isentropically to  $M_2 = 1.3$ . A normal shock occurs at that location. The resulting subsonic flow is decelerated further to  $M_4 = 0.40$ . The subsonic diffusion is adiabatic but not isentropic; the final pressure is 104 kPa (abs). Evaluate (a) the stagnation temperature for the flow, (b) the pressure change across the shock, (c) the entropy change,  $s_4 - s_1$ , and (d) the final stagnation pressure. Sketch the process path on a  $Ts$  diagram, indicating all static and stagnation states.

Solution:

Compressible flow functions (Appendix E) to be used in solution

Assumptions: (1) steady flow (2) uniform flow at a section  
 (3) Air in shock,  $A_2 = A_3$   
 (4) ideal gas

For  $M_1 = 2.7$ , from App. E.1,  $T_{01}/T_1 = 2.458 \quad \therefore T_{01} = 533 \text{ K}$   
 $p_{01}/p_1 = 23.283 \quad \therefore p_{01} = 128.8 \text{ kPa}$   
 Note:  $T_0 = \text{constant}$ ,  $p_{02} = p_{01}$

For  $M_2 = 1.3$ , from App. E.1,  $T_{02}/T_2 = 1.338 \quad \therefore T_2 = 398 \text{ K}$   
 $p_{02}/p_2 = 2.771 \quad p_2 = 46.48 \text{ kPa}$


For  $M_3 = 1.3$ , from App. E.4,  $M_3 = 0.786$   
 $p_3/p_2 = 1.805 \quad \therefore p_3 = 83.9 \text{ kPa}$   
 $p_{03}/p_{02} = 0.9794 \quad p_{03} = 126 \text{ kPa}$   
 $T_3/T_2 = 1.191 \quad T_3 = 474 \text{ K}$

$p_3 - p_2 = (83.9 - 46.5) \text{ kPa} = 37.4 \text{ kPa}$

For  $M_4 = 0.4$ , from App. E.1,  $p_{04}/p_4 = 1.117 \quad \therefore p_{04} = 116 \text{ kPa}$

$s_4 - s_1 = s_{04} - s_{01} = c_p \ln \frac{T_{04}}{T_{01}} - R \ln \frac{p_{04}}{p_{01}} = -287 \frac{\text{J}}{\text{kg} \cdot \text{K}} \ln \frac{116}{129}$

$s_4 - s_1 = -30.5 \text{ J/kg} \cdot \text{K}$



### Problem 13.89

[Difficulty: 4]

**13.89** A blast wave propagates outward from an explosion. At large radii, curvature is small and the wave may be treated as a strong normal shock. (The pressure and temperature rise associated with the blast wave decrease as the wave travels outward.) At one instant, a blast wave front travels at  $M = 1.60$  with respect to undisturbed air at standard conditions. Find (a) the speed of the air behind the blast wave with respect to the wave and (b) the speed of the air behind the blast wave as seen by an observer on the ground. Draw a  $Ts$  diagram for the process as seen by an observer on the wave, indicating static and stagnation state points and property values.

Solution:

Compressible flow functions (Appendix E) to be used in solution

- Assumptions: (1) steady flow as seen by an observer on the wave  
 (2) uniform flow at a section  
 (3) Air stock,  $R_x = 0$   
 (4) ideal gas

At state ①

$$v_1 = M_1 c_1 = M_1 (kRT_1)^{1/2} = 1.6 \left[ 1.4 \times 287 \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 288 \text{K} \right]^{1/2} = 544 \text{ m/s}$$


For  $M_1 = 1.6$ , from Appendix E.4,  $v_1/v_2 = p_2/p_1 = 2.032$

$$\therefore v_2 = 268 \text{ m/s} \quad \leftarrow \vec{v}_{2, \text{rel wave}}$$

The wave moves to the right at  $v_1 = 544 \text{ m/s}$ . Air moves to the left with respect to the wave at  $v_{2, \text{rel}} = 268 \text{ m/s}$ .

$$\vec{v}_{2, \text{abs}} = \vec{v}_{2, \text{wave}} + \vec{v}_{2, \text{rel}} = -544\hat{i} + 268\hat{i} = -276\hat{i} \text{ m/s} \quad \leftarrow \vec{v}_{2, \text{abs}}$$


{relative to ground, air behind wave moves to right}



### Problem 13.90

[Difficulty: 3]

**13.90** Consider a supersonic wind tunnel starting as shown. The nozzle throat area is  $1.25 \text{ ft}^2$ , and the test section design Mach number is 2.50. As the tunnel starts, a normal shock stands in the divergence of the nozzle where the area is  $3.05 \text{ ft}^2$ . Upstream stagnation conditions are  $T_0 = 1080^\circ\text{R}$  and  $p_0 = 115 \text{ psia}$ . Find the minimum theoretically possible diffuser throat area at this instant. Calculate the entropy increase across the shock.



Solution: Use functions for steady, one-dimensional compressible flow.

Computing equations:  $A/A^*$  vs.  $M$  from isentropic flow functions (App. E.1)

$p_02/p_01$  vs.  $M$  from shock flow functions (App. E.4)

- Assumptions: (1) steady flow (5) Adiabatic flow  
 (2) Uniform flow at each section (6)  $F_{Bx} = 0$   
 (3) Ideal gas (7)  $\Delta\beta = 0$   
 (4) Isentropic except across shock

Then from App. E.1,  $M_1 = 2.416$  at  $\frac{A_1}{A^*} = \frac{A_1}{A_t} = \frac{3.05 \text{ ft}^2}{1.25 \text{ ft}^2} = 2.44$ .

From App. E.4, at  $M_1 = 2.416$ ,  $\frac{p_02}{p_01} = 0.5395$ . Thus  $p_0d = 0.5395 p_01 = 62.0 \text{ psia}$ .

For adiabatic flow,  $T_0 = \text{constant}$  and  $T^* = \frac{T_0}{1.2} = \frac{1080 \text{ R}}{1.2} = 900 \text{ R} = \text{constant}$ .

From continuity,  $\dot{m} = \rho_t A_t V_t = \rho_d V_d A_d$ . Substituting  $\rho = \frac{p}{RT}$  and  $V = M\sqrt{kRT}$ ,

$$\frac{p_t}{RT_t} \sqrt{kRT_t} A_t = \frac{p_d}{RT_d} \sqrt{kRT_d} A_d; A_d = A_t \frac{p_t}{p_d} = A_t \frac{p_{0t}}{p_{0d}} = \frac{A_t}{0.5395}$$


$$A_d = \frac{1.25 \text{ ft}^2}{0.5395} = 2.32 \text{ ft}^2$$

From the Gibbs equation,

$$T ds = dh - v dp; ds = c_p \frac{dT}{T} - R \frac{dp}{p}$$

$$\Delta s = c_p \ln \frac{T_02}{T_01} - R \ln \frac{p_02}{p_01}$$

Since  $T_0 = \text{constant}$ ,  $\ln(T_02/T_01) = 0$ , and



$$\Delta s = -53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lbm} \cdot \text{R}} \times \ln(0.5395) \times \frac{\text{Btu}}{778 \text{ ft} \cdot \text{lb}} = 0.0423 \text{ Btu/lbm} \cdot \text{R}$$

{ Note a slightly stronger shock could occur at  $M = 2.50$ ; a larger diffuser throat ( $A_d \approx 2.51 \text{ ft}^2$ ) would be needed to start this tunnel.

## Problem 13.91

[Difficulty: 4]

**13.91** Air enters a wind tunnel with stagnation conditions of 14.7 psia and 75°F. The test section has a cross-sectional area of 1 ft<sup>2</sup> and a Mach number of 2.3. Find (a) the throat area of the nozzle, (b) the mass flow rate, (c) the pressure and temperature in the test section, and (d) the minimum possible throat area for the diffuser to ensure starting.

**Given:** Air flowing through a wind tunnel, stagnation and test section conditions known


**Find:** Throat area, mass flow rate, static conditions in test section, minimum diffuser area

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\ k &= 1.4 \\ p_{01} &= 14.7 && \text{psia} \\ T_{01} &= 75 && ^\circ\text{F} \\ T_{01} &= 535 && ^\circ\text{R} \\ A_1 &= 1 && \text{ft}^2 \\ M_1 &= 2.3 \end{aligned}$$

A schematic of this wind tunnel is shown here:



Equations and Computations:

For the Mach number in the test section, the corresponding area ratio is:

$$A_1/A_1^* = 2.193$$

So the throat area is:

$$A_t = 0.456 \text{ ft}^2$$

The mass flow rate can be calculated using the choked flow equation:

$$m = 22.2 \text{ lbm/s}$$

The static conditions in the test section are:

$$p_{01}/p_1 = 12.5043$$

$$T_{01}/T_1 = 2.0580$$

$$p_1 = 1.176 \text{ psia}$$

$$T_1 = 260 \text{ }^\circ\text{R}$$

The strongest possible shock that can occur downstream of the first throat is when the shock wave is in the test section. The post-shock Mach number is then

$$M_2 = 0.5344$$

The area ratio corresponding to this Mach number is:

$$A_2/A_2^* = 1.2792$$

Therefore, the minimum diffuser throat area is

$$A_2^* = 0.782 \text{ ft}^2$$

# Problem 13.92

[Difficulty: 2]

**13.92** Air flows through a converging-diverging nozzle with  $A_2/A_1 = 3.5$ . The upstream stagnation conditions are atmospheric; the back pressure is maintained by a vacuum pump. Determine the back pressure required to cause a normal shock to stand in the nozzle exit plane and the flow speed leaving the shock.

Solution:

Compressible flow tables to be used in the solution

Assumptions: (1) steady flow (2) uniform flow at a section  
(3) ideal gas (4) isentropic flow except across the shock

$$A_2/A_1^* = 3.5$$

From Fig. E.1 and Eq. 12.6,  $M_1 = 2.80$ ;  $P_1/P_{01} = 0.03665$       $P_1/P_{01} = 0.03665$


$$\therefore T_1 = 112 \text{ K} \quad P_1 = 3.72 \text{ kPa (abs)}$$

For  $M_1 = 2.80$ , from App. E.4,  $M_2 = 0.488$       $T_2/T_1 = 2.451$       $P_2/P_1 = 8.980$

$$\therefore P_2 = 8.98 P_1 = 8.98 \times 3.72 \text{ kPa} = 33.4 \text{ kPa (abs)}$$

$$T_2 = 2.451 T_1 = 275 \text{ K}$$

$$V_2 = M_2 c_2 = M_2 \left( \sqrt{\gamma R T_2} \right) = 0.488 \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 275 \text{ K} \right)^{1/2} = 162 \text{ m/s}$$



### Problem 13.93

[Difficulty: 3]

**13.93** A supersonic wind tunnel is to be operated at  $M = 2.2$  in the test section. Upstream from the test section, the nozzle throat area is  $0.07 \text{ m}^2$ . Air is supplied at stagnation conditions of  $500 \text{ K}$  and  $1.0 \text{ MPa (abs)}$ . At one flow condition, while the tunnel is being brought up to speed, a normal shock stands at the nozzle exit plane. The flow is steady. For this starting condition, immediately downstream from the shock find (a) the Mach number, (b) the static pressure, (c) the stagnation pressure, and (d) the minimum area theoretically possible for the second throat downstream from the test section. On a  $Ts$  diagram show static and stagnation state points and the process path.

Solution:

Compressible flow functions (Appendix E) to be used in solution.

Assumptions: (1) steady flow (2) uniform flow at a section  
 (3) isentropic flow in nozzles, adiabatic flow across shock  
 (4) ideal gas.

At  $M_{2u} = 2.2$ , from App E.1,  $p_{2u}/p_0 = 0.09352 \quad \therefore p_{2u} = 93.5 \text{ kPa}$

At  $M_{2u} = 2.2$ , from App E.4,  $M_{2d} = 0.547$  (12.34b)  $\xrightarrow{M_{2d}}$

$p_2/p_1 = 5.480 \quad \therefore p_{2d} = 512 \text{ kPa}$   $\xrightarrow{p_{2d}}$

$p_{02}/p_{01} = 0.6281 \quad \therefore p_{02d} = 628 \text{ kPa}$   $\xrightarrow{p_{02d}}$

At  $M_{2u} = 2.2$ , from App E.1,  $A_2/A^* = A_2/A_1 = 2.005 \quad \therefore A_2 = 0.1404 \text{ m}^2$

At  $M_{2d} = 0.547$ , from App E.1,  $A_2/A^* = A_2/A_5^* = 1.259 \quad \therefore A_5^* = 0.111 \text{ m}^2$   $\xrightarrow{A_5^*}$

# Problem 13.94

[Difficulty: 2]

13.94 A converging-diverging nozzle is attached to a large tank of air, in which  $T_{01} = 300 \text{ K}$  and  $p_{01} = 250 \text{ kPa (abs)}$ . At the nozzle throat the pressure is  $132 \text{ kPa (abs)}$ . In the diverging section, the pressure falls to  $68.1 \text{ kPa}$  before rising suddenly across a normal shock. At the nozzle exit the pressure is  $180 \text{ kPa}$ . Find the Mach number immediately behind the shock. Determine the pressure immediately downstream from the shock. Calculate the entropy change across the shock. Sketch the  $Ts$  diagram for this flow, indicating static and stagnation state points for conditions at the nozzle throat, both sides of the shock, and the exit plane.

Solution: Compressible flow functions (Appendix E) to be used in solution

Assumptions: (1) steady flow (2) uniform flow at each section  
 (3) ideal gas (4) isentropic flow, except across shock

At section 0  $p_0 = 250 \text{ kPa (abs)}$ ,  $p_1 = 68.1 \text{ kPa (abs)}$   $\therefore p_1/p_0 = 0.2724$

From App. E.1  $M_1 = 1.50$

From App. E.4 with  $M_1 = 1.50$ ,  $M_2 = 0.701$   $M_2$


$p_2/p_1 = 2.458$   $\therefore p_2 = 167 \text{ kPa (abs)}$   $p_2$

$p_{02}/p_0 = 0.9298$

From the  $Tds$  equation,  $Tds = dh - vdp = c_p dT - R T \frac{dT}{T}$   
 $\therefore ds = c_p dT - R \frac{dT}{T}$

$s_2 - s_1 = s_{02} - s_{01} = c_p \ln \frac{T_{02}}{T_{01}} - R \ln \frac{p_{02}}{p_{01}}$

$s_2 - s_1 = -287 \frac{\text{J}}{\text{kg}\cdot\text{K}} \ln 0.9298 = 20.9 \text{ J/kg}\cdot\text{K}$   $s_2 - s_1$






# Problem 13.96

[Difficulty: 2]

13.96 A converging-diverging nozzle, with throat area  $A_t = 1.0 \text{ in.}^2$ , is attached to a large tank in which the pressure and temperature are maintained at 100 psia and 600°R. The nozzle exit area is 1.58 in.<sup>2</sup> Determine the exit Mach number at design conditions. Referring to Fig. 13.12, determine the back pressures corresponding to the boundaries of Regimes I, II, III, and IV. Sketch the corresponding plot for this nozzle.



Find:  $M_e$  at design conditions;  $P_b$  corresponding to regime boundaries of Fig. 13.12, sketch  $P(x)$

Solution:

Compressible flow functions (Appendix E) to be used in solution

- Assumptions: (1) steady flow (2) ideal gas  
 (3) uniform flow at a section  
 (4) isentropic flow except across shock

For  $A_e/A_t^* = 1.58$ ,

from Fig. E.1 and Eq. 12.6,

$$M_e = 0.402$$

$$P_e/P_0 = 0.8940$$

$$\text{or } M_e = 1.92$$


$$P_e/P_0 = 0.1447$$

$$P_{b1} = \frac{P_e}{P_0} \cdot P_0 = 0.8940 \times 100 \text{ psia} = 89.4 \text{ psia}$$

$$P_{b2} = \frac{P_e}{P_0} \cdot P_0 = 0.1447 \times 100 \text{ psia} = 14.5 \text{ psia}$$

For  $M_e = 1.92$ , from App. E.4,  $\frac{P_2}{P_1} = 4.045$

$$P_{b2} = \frac{P_2}{P_1} \cdot P_{b1} = 4.045 \times 14.5 \text{ psia} = 58.6 \text{ psia}$$



## Problem 13.97

[Difficulty: 3]

**13.97** A converging-diverging nozzle is designed to produce a Mach number of 2.5 with air. What operating pressure ratios ( $p_b/p_{t, \text{inlet}}$ ) will cause this nozzle to operate with isentropic flow throughout and supersonic flow at the exit (the so-called “third critical point”), with isentropic flow throughout and subsonic flow at the exit (the “first critical point”), and with a normal shock at the nozzle exit (the “second critical point”)?

**Given:** Air accelerating through a converging-diverging nozzle

**Find:** Pressure ratios needed to operate with isentropic flow throughout, supersonic flow at exit (third critical); isentropic flow throughout, subsonic flow at exit (first critical point); and isentropic flow throughout, supersonic flow in the diverging portion, and a normal shock at the exit (second critical point).

**Solution:**

The given or available data is:

$$\begin{aligned}k &= 1.4 \\M_d &= 2.5\end{aligned}$$

Equations and Computations:

The pressure ratio for the third critical can be found from the design point Mach number:

$$\begin{aligned}p_{0\text{inlet}}/p_{b,3\text{rd}} &= 17.0859 \\p_{b,3\text{rd}}/p_{0\text{inlet}} &= 0.0585\end{aligned}$$

The area ratio for this nozzle is:

$$A/A^* = 2.637$$

So to operate at first critical the exit Mach number would be:

$$M_{1\text{st}} = 0.226$$

Since at first critical the flow is isentropic, the pressure ratio is:

$$\begin{aligned}p_{0\text{inlet}}/p_{b,1\text{st}} &= 1.0363 \\p_{b,1\text{st}}/p_{0\text{inlet}} &= 0.9650\end{aligned}$$

At second critical, the flow is isentropic to the exit, followed by a normal shock.

At the design Mach number, the pressure ratio is:

$$p_{b,2\text{nd}}/p_{b,3\text{rd}} = 7.125$$

Therefore, the back pressure ratio at the second critical is:

$$p_{b,2\text{nd}}/p_{0\text{inlet}} = 0.4170$$

$$p_{b,1\text{st}}/p_{0\text{inlet}} = 0.9650$$

$$p_{b,2\text{nd}}/p_{0\text{inlet}} = 0.4170$$

$$p_{b,3\text{rd}}/p_{0\text{inlet}} = 0.0585$$

## Problem 13.98

[Difficulty: 3]

**13.98** Oxygen flows through a converging-diverging nozzle with a exit-to-throat area ratio of 3.0. The stagnation pressure at the inlet is 120 psia, and the back pressure is 50 psia. Compute the pressure ratios for the nozzle and demonstrate that a normal shock wave should be located within the diverging portion of the nozzle. Compute the area ratio at which the shock occurs, the pre- and post-shock Mach numbers, and the Mach number at the nozzle exit.

**Given:** Oxygen accelerating through a converging-diverging nozzle

**Find:** Pressure ratios for critical points, show that a shock forms in the nozzle, pre- and post-shock Mach numbers, exit Mach number

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 48.29 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.4 \\p_{0\text{inlet}} &= 120 && \text{psia} \\p_b &= 50 && \text{psia} \\A_e/A_t &= 3\end{aligned}$$

Equations and Computations:

Based on the area ratio, the design Mach number is:

$$M_d = 2.637$$

The pressure ratio for the third critical can be found from the design point Mach number:

$$\begin{aligned}p_{0\text{inlet}}/p_{b,3\text{rd}} &= 21.1422 \\p_{b,3\text{rd}}/p_{0\text{inlet}} &= 0.04730\end{aligned}$$

If a normal shock exists in the nozzle, the pressure ratio should be between the first and second critical points. At the first critical point the exit Mach number is

$$M_{1\text{st}} = 0.197$$

Since at first critical the flow is isentropic, the pressure ratio is:

$$\begin{aligned}p_{0\text{inlet}}/p_{b,1\text{st}} &= 1.0276 \\p_{b,1\text{st}}/p_{0\text{inlet}} &= 0.9732\end{aligned}$$

At second critical, the flow is isentropic to the exit, followed by a normal shock.

At the design Mach number, the pressure ratio is:

$$p_{b,2\text{nd}}/p_{b,3\text{rd}} = 7.949$$

Therefore, the back pressure ratio at the second critical is:

$$p_{b,2\text{nd}}/p_{0\text{inlet}} = 0.3760$$

The actual back pressure ratio is

$$p_b/p_{0\text{inlet}} = 0.4167$$

This pressure ratio is between those for the first and second critical points, so a shock exists in the nozzle. We need to use an iterative solution to find the exact location of the shock wave. Specifically, we iterate on the pre-shock Mach number until we match the exit pressure to the given back pressure:


$$\begin{aligned}
 M_1 &= 2.55 \\
 A_1/A_t &= 2.759 \\
 p_{0\text{inlet}}/p_1 &= 18.4233 \\
 p_1 &= 6.513 \text{ psia} \\
 M_2 &= 0.508 \\
 p_2/p_1 &= 7.4107 \\
 p_2 &= 48.269 \text{ psia} \\
 A_e/A_2 &= 1.0873 \\
 A_2/A_2^* &= 1.324 \\
 A_e/A_2^* &= 1.440 \\
 M_e &= 0.454 \\
 p_{02}/p_2 &= 1.193 \\
 p_{02}/p_e &= 1.152 \\
 p_e &= 50.000 \text{ psia}
 \end{aligned}$$

(We used *Goal Seek* in *Excel* for this solution.)

### Problem 13.99

[Difficulty: 2]

13.99 A converging-diverging nozzle, with  $A_e/A_t = 4.0$ , is designed to expand air isentropically to atmospheric pressure. Determine the exit Mach number at design conditions and the required inlet stagnation pressure. Referring to Fig. 13.20, determine the back pressures that correspond to the boundaries of Regimes I, II, III, and IV. Sketch the plot of pressure ratio versus axial distance for this nozzle.



Solution:

Compressible flow functions (Appendix E) to be used in solution

- Assumptions: (1) steady flow (2) ideal gas  
 (3) uniform flow at a section  
 (4) isentropic flow except across a shock

For  $A_e/A_t^* = 4.00$ ,  
 from Fig. E.1 and Eq. 12.6,  $M_e = 2.94$   $P/P_0 = 0.0298$   
 $\alpha$   $M_e = 0.147$   $P/P_0 = 0.9887$


Then  $M_{e,d} = 2.94$   $P_{0,d} = \frac{P_e}{0.0298} = \frac{101 \text{ kPa}}{0.0298} = 3.39 \text{ MPa (abs)}$   $M_e, P_0$

$P_{b1} = \frac{P_{e1}}{P_0} \cdot P_0 = 0.9887 \cdot 3.39 \text{ MPa} = 3.35 \text{ MPa (abs)}$   $P_{b1}$

$P_{b3} = 101 \text{ kPa (abs)}$   $P_{b3}$

For  $M_e = 2.94$  from App. E.4,  $P_{2/1} = 9.918$

$P_{b2} = \frac{P_2}{P_1} \cdot P_{e3} = 9.918 \cdot 101 \text{ kPa} = 1.00 \text{ MPa (abs)}$   $P_{b2}$



42 SHEETS SQUARE

## Problem 13.100

[Difficulty: 3]

**13.100** A normal shock occurs in the diverging section of a converging-diverging nozzle where  $A = 25 \text{ cm}^2$  and  $M = 2.75$ . Upstream,  $T_0 = 550 \text{ K}$  and  $p_0 = 700 \text{ kPa (abs)}$ . The nozzle exit area is  $40 \text{ cm}^2$ . Assume the flow is isentropic except across the shock. Determine the nozzle exit pressure, throat area, and mass flow rate.

**Given:** Normal shock in CD nozzle

**Find:** Exit pressure; Throat area; Mass flow rate

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg K} \\k &= 1.4 \\T_{01} &= 550 && \text{K} \\p_{01} &= 700 && \text{kPa} \\M_1 &= 2.75 \\A_1 &= 25 && \text{cm}^2 \\A_e &= 40 && \text{cm}^2\end{aligned}$$

Equations and Computations (assuming State 1 and 2 before and after the shock):

Using built-in function *Isenp* (M,k):

$$p_{01}/p_1 = 25.14 \qquad p_1 = 28 \text{ kPa}$$

Using built-in function *IsenT* (M,k):

$$T_{01}/T_1 = 2.51 \qquad T_1 = 219 \text{ K}$$

Using built-in function *IsenA* (M,k):

$$A_1/A_1^* = 3.34 \qquad A_1^* = A_t = 7.49 \text{ cm}^2$$

Then from the Ideal Gas equation:

$$\rho_1 = 0.4433 \text{ kg/m}^3$$

Also:

$$c_1 = 297 \text{ m/s}$$

So:

$$V_1 = 815 \text{ m/s}$$

Then the mass flow rate is:

$$\begin{aligned}m_{\text{rate}} &= \rho_1 V_1 A_1 \\m_{\text{rate}} &= 0.904 \text{ kg/s}\end{aligned}$$

For the normal shock:

Using built-in function *NormM2fromM* (M,k):

$$M_2 = 0.492$$

Using built-in function *Normp0fromM* (M,k) at  $M_1$ :

$$p_{02}/p_{01} = 0.41 \qquad p_{02} = 284 \text{ kPa}$$

For isentropic flow after the shock:

Using built-in function  $IsenA$  (M,k):

$$A_2 / A_2^* = 1.356$$

But:  $A_2 = A_1$

Hence:  $A_2^* = 18.44 \text{ cm}^2$

Using built-in function  $IsenAMsubfromA$  (Aratio,k):

For:  $A_e / A_2^* = 2.17$   $M_e = 0.279$

Using built-in function  $Isenp$  (M,k):

$$p_{02} / p_e = 1.06$$
  $p_e = 269 \text{ kPa}$

# Problem 13.101

[Difficulty: 2]

13.101 Air flows adiabatically from a reservoir, where  $T = 60^\circ\text{C}$  and  $p = 600\text{ kPa (abs)}$ , through a converging-diverging nozzle with  $A_2/A_1 = 4.0$ . A normal shock occurs where  $M = 2.42$ . Assuming isentropic flow before and after the shock, determine the back pressure downstream from the nozzle. Sketch the pressure distribution.

Solution:

Compressible flow functions (Appendix E) to be used in solution

- Assumptions
- (1) steady flow
  - (2) uniform flow at a section
  - (3) ideal gas
  - (4) isentropic flow except across the shock

$M_1 = 2.42$  From App. E.1,  $P/P_0 = 0.04630$        $A_1/A_1^* = A_2/A_2^* = 2.448$   
 $P_1 = 39.8\text{ kPa (abs)}$



From App. E.4,  $M_2 = 0.521$        $P_2/P_1 = 6.666$        $P_{02}/P_{01} = 0.5318$   
 $\therefore P_2 = 265\text{ kPa (abs)}$        $P_{02} = 319\text{ kPa (abs)}$

$M_2 = 0.521$  From App. E.1,  $A_2/A_2^* = 1.301 = A_1/A_1^*$

Then  $\frac{A_2}{A_1} = \frac{A_2}{A_2^*} \times \frac{A_1^*}{A_1} = 1.301 \times \frac{1}{2.448} = 2.126$

For  $A_2/A_1 = 2.126$ , from Fig. E.1 and Eq. 12.6,  $M_2 = 0.286$ ,  $P_e/P_0 = 0.9447$

Then  $P_b = P_e = 0.9447 P_0 = 0.9447 \times 319\text{ kPa} = 301\text{ kPa}$  ←  $P_e$



### Problem 13.102

[Difficulty: 3]

**13.102** A converging-diverging nozzle is designed to expand air isentropically to atmospheric pressure from a large tank, where  $T_0 = 150^\circ\text{C}$  and  $p_0 = 790 \text{ kPa (abs)}$ . A normal shock stands in the diverging section, where  $p = 160 \text{ kPa (abs)}$  and  $A = 600 \text{ mm}^2$ . Determine the nozzle back pressure, exit area, and throat area.

Solution:

Compressible flow functions (Appendix E) to be used in solution  
 Assumptions: (1) steady flow (2) uniform flow at a section  
 (3) ideal gas (4) isentropic flow except across the shock

At design conditions,

$$P_3/P_0 = 101/790 = 0.1278, \text{ From App. E.1 } M_{3 \text{ design}} = 2.00 \quad \frac{A_3}{A_t} = 1.688$$

At section (2),  $\frac{P_2}{P_0} = \frac{160}{790} = 0.2025$ . From App. E.1,  $M_2 = 1.70$   $A_2/A_2^* = 1.338$

$$A_t = A_2^* = \frac{A_2}{1.338} = \frac{600 \text{ mm}^2}{1.338} = 448 \text{ mm}^2$$

Then  $A_3 = 1.688 A_t = 1.688 (448 \text{ mm}^2) = 756 \text{ mm}^2$


$M_1 = 1.70$  From App. E.4,  $M_2 = 0.641$   $P_{02}/P_{01} = 0.8557$   $P_2/P_1 = 3.205$

$\therefore P_{02} = 676 \text{ kPa (abs)}$   $P_2 = 513 \text{ kPa (abs)}$

$M_2 = 0.641$  From App. E.1,  $A_2/A_2^* = 1.145$   $\therefore A_2^* = \frac{A_2}{1.145} = 524 \text{ mm}^2$

$A_3/A_2^* = \frac{756}{524} = 1.443$ . From Fig. E.1 and Eq. 12.6,  $M_3 = 0.453$ ;  $\frac{P_{03}}{P_{02}} = 0.8668$

$\therefore P_b = P_3 = 0.8668 P_{03} = 0.8668 P_{02} = 587 \text{ kPa (abs)}$



# Problem 13.103

[Difficulty: 3]

**13.103** A converging-diverging nozzle, with design pressure ratio  $p_e/p_0 = 0.128$ , is operated with a back pressure condition such that  $p_e/p_0 = 0.830$ , causing a normal shock to stand in the diverging section. Determine the Mach number at which the shock occurs.

Solution:

Compressible flow functions (Appendix E) to be used in solution  
 Assumptions: 1) steady flow 2) uniform flow at a section  
 3) ideal gas 4) isentropic flow except across the shock

At design conditions,  $P_e/P_{01} = 0.1278$


From App. E.1,  $M_d = 2.0$  and  $A_e/A_1^* = 1.688$

$$\text{Now } \frac{P_e}{P_{01}} = \frac{P_e}{P_{02}} \cdot \frac{P_{02}}{P_{01}} \quad \text{and} \quad \frac{A_e}{A_1^*} = \frac{A_e}{A_2^*} \cdot \frac{A_2^*}{A_1^*} \quad \frac{A_2^*}{A_1^*} = \frac{A_2}{A_1} \cdot \frac{A_1^*}{A_2^*}$$

We thus have a trial and error solution to determine  $M_1$ .

$M_1$	$A_1/A_1^*$ (a)	$M_2$ (b)	$P_{02}/P_{01}$ (c)	$A_2/A_2^*$ (d)	$A_2^*/A_1^*$ (e)	$A_e/A_2^*$ (f)	$M_e$ (g)	$P_e/P_{02}$ (h)	$P_e/P_{01} = 0.8300$ (i)
1.60	1.25	0.67	0.8952	1.119	1.117	1.511	0.42	0.8957	0.7927
1.40	1.150	0.74	0.9582	1.068	1.071	1.567	0.41	0.8907	0.8534
1.50	1.176	0.70	0.9298	1.094	1.075	1.570	0.403	0.8923	0.820 ✓

$\therefore M_1 = 1.50$



- a. App. E.1 (12.6)
- b. App. E.4 (12.34b)
- c. App. E.4 (12.37)
- d. App. E.1 (12.6)
- e. App. E.1 Fig. E.1 = Eq. 12.6
- f. App. E.1 (11.17a)

### Problem 13.104

[Difficulty: 3]

**13.104** Air flows through a converging-diverging nozzle, with  $A_c/A_t = 3.5$ . The upstream stagnation conditions are atmospheric; the back pressure is maintained by a vacuum system. Determine the range of back pressures for which a normal shock will occur within the nozzle and the corresponding mass flow rate, if  $A_t = 500 \text{ mm}^2$ .

Solution: Use compressible flow functions in solution.

Computing equation:  $\dot{m} = \rho VA$

- Assumptions: (1) Steady flow (2) Ideal gas (3) Uniform flow at a section (4) Isentropic, except across shock

A normal shock will occur within the nozzle for back pressure conditions in Regime II of Fig. 12.20. For isentropic flow, with  $A_c/A_t = 3.5$ , from Fig. E.1 and Eq. 12.6,

M	$p/p_0$	$p_0$
0.169	0.9858	99.6 kPa
2.80	0.03685	

From Appendix E.4,

$M_1$	$M_2$	$p_2/p_1$
2.80	0.4882	8.980

Thus  $p_b = p_2 = p_0 \frac{p_1}{p_0} \frac{p_2}{p_1} = 101 \text{ kPa} (0.03685)(8.980) = 33.4 \text{ kPa}$


$33.4 \text{ kPa} < p_b < 99.6 \text{ kPa (abs)}$  (for normal shock in nozzle)

Flow is choked throughout this regime. Thus

$$\dot{m} = \rho_t V_t A_t \quad \rho_t = \frac{p_t}{RT_t} = (0.5283) \frac{1.01 \times 10^5 \text{ N}}{\text{m}^2} \frac{\text{kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m}} \frac{1}{(0.8333) 288 \text{ K}} = 0.775 \frac{\text{kg}}{\text{m}^3}$$

$$V_t = c_t = \sqrt{kRT_t} = \left[ 1.4 \frac{287 \text{ N} \cdot \text{m}}{\text{kg} \cdot \text{K}} (0.8333) 288 \text{ K} \right]^{\frac{1}{2}} = 311 \text{ m/s}$$

$$\dot{m} = 0.775 \frac{\text{kg}}{\text{m}^3} \times 311 \frac{\text{m}}{\text{s}} \times 500 \text{ mm}^2 \times \frac{\text{m}^2}{10^6 \text{ mm}^2} = 0.121 \frac{\text{kg}}{\text{s}}$$



### Problem 13.105

[Difficulty: 3]

**13.105** A converging-diverging nozzle, with  $A_e/A_t = 1.633$ , is designed to operate with atmospheric pressure at the exit plane. Determine the range(s) of inlet stagnation pressures for which the nozzle will be free from normal shocks.

Solution: Use compressible flow tables in solution.

Assume flow in nozzle is isentropic when shock-free.

From Appendix E.1 and Eq. 12.6,

$M$	$p/p_0$	$A/A^*$
1.96	0.1360	1.633
0.38	0.9052	1.659
0.40	0.8956	1.590

At design conditions,  $Me = 1.96$ , and

$$p_0 \gg \frac{p_e}{(p/p_0)_e} = \frac{101 \text{ kPa}}{0.1360} = 743 \text{ kPa (abs)}$$

By iteration, then the given area ratio corresponds to isentropic choked flow with  $Me = 0.388$  and  $(p/p_0)_e = 0.9014$ . The corresponding stagnation pressure is


$$p_0 = \frac{p_e}{(p/p_0)_e} = \frac{101 \text{ kPa}}{0.9014} = 112 \text{ kPa (abs)}$$

Flow will be isentropic and shock-free for

(a)  $p_{atm} < p_0 < 112 \text{ kPa (abs)}$  ( $0 < Me < 0.388$ )

(b)  $p_0 > 743 \text{ kPa (abs)}$  ( $Me = 1.96$ )

The corresponding Ts diagrams are:



### Problem 13.106

[Difficulty: 3]

**13.106** Air flows through a converging-diverging nozzle with  $A_e/A_t = 1.87$ . Upstream,  $T_0 = 240^\circ\text{F}$  and  $p_0 = 100$  psia. The back pressure is maintained at 40 psia. Determine the Mach number and flow speed in the nozzle exit plane.

Solution: Use compressible flow functions in solution. Assume ideal gas.

For isentropic flow through the nozzle to  $A_e/A_t = 1.87$ , from Fig. E.1 and Eq. 12.6,

$M$	$T/T_0$	$p/p_0$	$p_b$ (psia)
2.12	0.5266	0.1060	10.6
~0.33	~0.98	~0.92	~92.0

Neither of these conditions matches the back pressure. Check the case of a shock (at  $M = 2.12$ ) in the exit plane. From Appendix E.4,

$M_1$	$M_2$	$p_2/p_1$
2.12	0.5583	5.077

Then  $p_e = 5.077 p_b = 5.077 (10.6 \text{ psia}) = 53.8 \text{ psia}$ .

The back pressure of 40 psia is therefore between the design pressure and the pressure that would exist downstream from a normal shock in the exit plane. The flow is in regime III of Fig. 12.20: supersonic in the exit plane with external compression. Thus


$$M_e = M_d = 2.12$$

$$V_e = M_e C_e = M_e \sqrt{kRT_e}$$

$$T_e = \frac{T}{T_0} T_0 = 0.5266 (460 + 240)^\circ\text{R} = 369^\circ\text{R}$$

$$V_e = 2.12 \left[ 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot ^\circ\text{R}} \times 369^\circ\text{R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb}_f \cdot \text{s}^2} \right]^{1/2} = 2000 \frac{\text{ft}}{\text{s}}$$

The Ts diagram is



# Problem 13.107

[Difficulty: 3]

**13.107** A normal shock occurs in the diverging section of a converging-diverging nozzle where  $A = 4.0 \text{ in.}^2$  and  $M = 2.00$ . Upstream,  $T_{01} = 1000^\circ\text{R}$  and  $p_{01} = 100 \text{ psia}$ . The nozzle exit area is  $6.0 \text{ in.}^2$ . Assume that flow is isentropic except across the shock. Find the nozzle exit pressure. Show the processes on a  $Ts$  diagram, and indicate the static and stagnation state points.

Solution:

Compressible flow functions (Appendix E) to be used in solution

Assumptions: (1) steady flow (2) ideal gas (3) uniform flow at each section (4) isentropic flow, except across shock.

For  $M_1 = 2.0$ , from App. E.1,  $p_1/p_{01} = 0.1278 \quad \therefore p_1 = 12.78 \text{ psia}$

For  $M_1 = 2.0$ , from App. E.4,  $M_2 = 0.5774$   
 $p_2/p_1 = 4.50 \quad \therefore p_2 = 57.5 \text{ psia}$   
 $p_{02}/p_{01} = 0.7209 \quad \therefore p_{02} = 72.1 \text{ psia}$


For  $M_2 = 0.5774$ , from App. E.1,  $A_2/A_2^* = 1.216 \quad \therefore A_2^* = 3.288 \text{ in.}^2$

Then  $A_3/A_2^* = 6.0/3.288 = 1.825$

With  $A_3/A_2^* = 1.825$ , from App. E.1 (Fig. E.1 and Eq. 12.16)  $M_3 = 0.340$

With  $M_3 = 0.340$ , from App. E.1,  $p_{03}/p_3 = 1.083$

$$p_3 = \frac{p_{03}}{1.083} = \frac{p_{02}}{1.083} = \frac{72.1 \text{ psia}}{1.083} = 66.6 \text{ psia} \quad \leftarrow p_3$$







### Problem 13.108

[Difficulty: 4]

**13.108** Consider flow of air through a converging-diverging nozzle. Sketch the approximate behavior of the mass flow rate versus back pressure ratio,  $p_b/p_0$ . Sketch the variation of pressure with distance along the nozzle, and the  $Ts$  diagram for the nozzle flow, when the back pressure is  $p^*$ .

Solution: When  $p_b = p^*$ , flow in the nozzle will be choked and a shock will stand in the diverging section.



## Problem 13.109

[Difficulty: 3]

**13.109** Air enters a converging-diverging nozzle with an area ratio of 1.76. Entrance stagnation conditions are 150 psia and 200°F. A normal shock stands at a location where the area is 1.2 times the throat area. Determine the exit Mach number and static pressure. What is the design point exit pressure?

**Given:** Air flowing through a converging-diverging nozzle with standing normal shock

**Find:** Exit Mach number and static pressure; design point pressure

**Solution:**

The given or available data is:

$R =$	53.33	ft-lbf/lbm-°R
$k =$	1.4	
$p_{0\text{inlet}} =$	150	psia
$T_{01} =$	200	°F
$T_{01} =$	660	°R
$A_c/A_t =$	1.76	
$A_1/A_t =$	1.2	

Equations and Computations:

The pre-shock Mach number can be found based on the area ratio:

$$M_1 = 1.5341$$

The static pressure before the shock wave is:

$$p_{0\text{inlet}}/p_1 = 3.8580$$
$$p_1 = 38.881 \text{ psia}$$

The Mach number and static pressure after the shock wave are:

$$M_2 = 0.689$$
$$p_2/p_1 = 2.5792$$
$$p_2 = 100.282 \text{ psia}$$

The area ratio for the remainder of the nozzle is:

$$A_c/A_2 = 1.4667$$

Based on this and the post-shock Mach number, we can determine the exit Mach number:

$$A_2/A_2^* = 1.102$$
$$A_c/A_2^* = 1.617$$
$$M_e = 0.392$$

Therefore the exit pressure is:

$$p_{02}/p_2 = 1.374$$
$$p_{02}/p_e = 1.112$$
$$p_e = 123.9 \text{ psia}$$

Based on the area ratio, the design Mach number is:

$$M_d = 2.050$$

The pressure ratio for the third critical can be found from the design point Mach number:

$$p_{0\text{inlet}}/p_{b,3\text{rd}} = 8.4583$$
$$p_{b,3\text{rd}}/p_{0\text{inlet}} = 0.1182$$

So the design pressure is:

$$p_d = 17.73 \text{ psia}$$

### Problem 13.110

[Difficulty: 4]

**13.110** A stationary normal shock stands in the diverging section of a converging-diverging nozzle. The Mach number ahead of the shock is 3.0. The nozzle area at the shock is 500 mm<sup>2</sup>. The nozzle is fed from a large tank where the pressure is 1000 kPa (gage) and the temperature is 400 K. Find the Mach number, stagnation pressure, and static pressure after the shock. Calculate the nozzle throat area. Evaluate the entropy change across the shock. Finally, if the nozzle exit area is 600 mm<sup>2</sup>, estimate the exit Mach number. Would the actual exit Mach number be higher, lower, or the same as your estimate? Why?

Solution:

Compressible flow functions (Appendix E) to be used in solution

Assumptions: (1) steady flow (2) ideal gas (3) uniform flow at each section (4) isentropic flow, except across shock

For  $M_1 = 3.0$ , from Appendix E.1,  $P_1/P_0 = 0.02722 \therefore P_1 = 29.97 \text{ kPa}$   
 $A_1/A^* = 4.235 \therefore A^* = A_1 = 118 \text{ mm}^2$   $A_t$

For  $M_1 = 3.0$ , from Appendix E.4,  $M_2 = 0.475$   $M_2$   
 $P_{02}/P_{01} = 0.3283 \therefore P_{02} = 361 \text{ kPa (abs)}$   $P_{02}$   
 $P_2/P_1 = 10.33 \therefore P_2 = 310 \text{ kPa (abs)}$   $P_2$


Since  $T_{02} = T_{01}$ , then

$$s_2 - s_1 = s_{02} - s_{01} = c_p \ln \frac{T_{02}}{T_{01}} - R \ln \frac{P_{02}}{P_{01}} = -287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \ln 0.3283$$

$$s_2 - s_1 = -0.320 \text{ kJ/kg}\cdot\text{K}$$
  $s_2 - s_1$

At  $M_2 = 0.475$ , from App. E.1  $A_2/A_2^* = 1.391 \therefore A_2^* = 359.5 \text{ mm}^2$

At exit  $A_e/A_2^* = \frac{600}{359.5} = 1.669$ . From App. E.1 (Fig. E.1) = Eq. 12.6  
 $M_e = 0.377$   $M_e$



The actual exit Mach number would be higher than the estimate based on isentropic flow downstream from the shock.

Flow downstream from the shock is subsonic. Flow slows in the diverging passage, which acts as a subsonic diffuser, causing pressure to increase in the direction of flow.

The result will be rapid growth of boundary layers on the channel walls. The boundary layers reduce the effective flow area of the passage. Because the boundary layers thicken rapidly, the area ratio for slowing the flow will be less than for isentropic flow. Therefore the actual flow will not slow as much as the isentropic model predicts.

The actual exit Mach number will be higher than the estimate based on isentropic flow.

# Problem 13.111

[Difficulty: 3]

**13.111** Air flows adiabatically from a reservoir, where  $T_{01} = 60^\circ\text{C}$  and  $p_{01} = 600\text{ kPa (abs)}$ , through a converging-diverging nozzle. The design Mach number of the nozzle is 2.94. A normal shock occurs at the location in the nozzle where  $M = 2.42$ . Assuming isentropic flow before and after the shock, determine the back pressure downstream from the nozzle. Sketch the pressure distribution.

Solution:

Compressible flow tables (Appendix E) to be used in solution.

Assumptions: (1) steady flow (2) uniform flow at each section (3) ideal gas (4) isentropic flow, except across shock.

At design,  $M_0 = 2.94$ , from Appendix E.1,  $A_2/A_0^* = 3.999$

For  $M_1 = 2.42$ , from Appendix E.1,  $p_1/p_{01} = 0.06630$   
 $A_1/A_1^* = 2.448$



For  $M_1 = 2.42$ , from Appendix E.4,  $M_2 = 0.521$   
 $p_{02}/p_{01} = 0.5318$   
 $p_2/p_1 = 6.666$

For  $M_2 = 0.521$ , from Appendix E.1,  $A_2/A_2^* = A_1/A_2^* = 1.302$

Then, 
$$\frac{A_2}{A_2^*} = \frac{A_0}{A_0^*} \times \frac{A_1}{A_1^*} \times \frac{A_1}{A_2^*} = 3.999 \times \frac{1}{2.448} \times 1.302 = 2.127$$

For  $A_2/A_2^* = 2.127$ , from App. E.1 (Fig. E.1c Eq. 12.6),  $M_2 = 0.287$ ,  $p_e/p_{02} = 0.9447$

$$\therefore p_b = p_e = \frac{p_e}{p_{02}} \times \frac{p_{02}}{p_{01}} \times p_{01} = 0.9447 \times 0.5318 \times 600\text{ kPa} = 301\text{ kPa}$$



## Problem 13.112

[Difficulty: 5]

**\*13.112** Air flows through a converging-diverging nozzle with an area ratio of 2.5. Stagnation conditions at the inlet are 1 MPa and 320 K. A constant-area, adiabatic duct with  $L/D = 10$  and  $f = 0.03$  is attached to the nozzle outlet. (a) Compute the back pressure that would place a normal shock at the nozzle exit. (b) What back pressure would place the normal shock at the duct exit? (c) What back pressure would result in shock-free flow?

**Given:** Air flowing through a converging-diverging nozzle followed by duct with friction

**Find:** Back pressure needed for (a) normal shock at nozzle exit, (b) normal shock at duct exit, (c) back pressure for shock-free flow

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\k &= 1.4 \\p_{0\text{inlet}} &= 1 && \text{MPa} \\T_{0\text{inlet}} &= 320 && \text{K} \\A_c/A_t &= 2.5 \\L/D &= 10 \\f &= 0.03\end{aligned}$$

Equations and Computations:

(a) For a shock wave at the nozzle exit:

The pre-shock Mach number can be found based on the area ratio:

$$M_1 = 2.4428$$

The static pressure before the shock wave is:

$$\begin{aligned}p_{0\text{inlet}}/p_1 &= 15.6288 \\p_1 &= 63.984 && \text{kPa}\end{aligned}$$

The Mach number and static pressure after the shock wave are:

$$\begin{aligned}M_2 &= 0.5187 \\p_2/p_1 &= 6.7950 \\p_2 &= 434.770 && \text{kPa}\end{aligned}$$

The friction length and critical pressure ratio after the shock wave are:

$$\begin{aligned}fL/D_2 &= 0.9269 \\p_2/p_2^* &= 2.0575\end{aligned}$$

The friction length for the duct is:

$$fL/D_{2-3} = 0.3000$$

Therefore, the friction length at the duct exit is:

$$fL/D_3 = 0.6269$$

Iterating on Mach number with *Solver* to match this friction length yields:

$$\begin{aligned}M_3 &= 0.5692 \\fL/D_3 &= 0.6269\end{aligned}$$

The critical pressure ratio for this condition is:

$$p_3/p_3^* = 1.8652$$

Since the critical pressure at 2 and 3 are equal, the back pressure is:

$$p_b = p_3 = 394 \quad \text{kPa}$$

(b) For a shock wave at the duct exit:

We use the same nozzle exit Mach number and pressure:

$$M_1 = 2.443$$

$$p_1 = 63.984 \text{ kPa}$$

The friction length and critical pressure ratio at this condition are:

$$fL/D_1 = 0.4195$$

$$p_1/p_1^* = 0.3028$$

The friction length for the duct is:

$$fL/D_{1-2} = 0.3000$$

Therefore, the friction length at the duct exit is:

$$fL/D_2 = 0.1195$$

Iterating on Mach number with *Solver* to match this friction length yields:

$$M_2 = 1.4547$$

$$fL/D_2 = 0.1195$$

The critical pressure ratio for this condition is:

$$p_2/p_2^* = 0.6312$$

Since the critical pressure at 1 and 2 are equal, the pressure is:

$$p_2 = 133.388 \text{ kPa}$$

The Mach number and static pressure after the shock wave are:

$$M_3 = 0.7178$$

$$p_3/p_2 = 2.3021$$

$$p_b = p_3 = 307 \text{ kPa}$$

(c) For shock-free flow, we use the conditions from part b before the shock wave:

$$p_b = p_3 = 133.4 \text{ kPa}$$

## Problem 13.113

[Difficulty: 4]

**\*13.113** Consider the setup of Problem 13.112, except that the constant-area duct is frictionless and no longer adiabatic. A normal shock stands at the duct exit, after which the temperature is 350 K. Calculate the Mach number after the shock wave, and the heat addition in the constant-area duct.

**Given:** Air flowing through a converging-diverging nozzle followed by diabatic duct

**Find:** Mach number at duct exit and heat addition in duct

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\c_p &= 1004 && \text{J/kg-K} \\k &= 1.4 \\p_{0\text{inlet}} &= 1 && \text{MPa} \\T_{0\text{inlet}} &= 320 && \text{K} \\A_1/A_t &= 2.5 \\T_e &= 350 && \text{K}\end{aligned}$$

Equations and Computations:

The Mach number at the nozzle exit can be found based on the area ratio:

$$M_1 = 2.4428$$

The static temperature is:

$$\begin{aligned}T_{0\text{inlet}}/T_1 &= 2.1934 \\T_1 &= 145.891 && \text{K}\end{aligned}$$

The Rayleigh flow critical ratios at this condition are:

$$\begin{aligned}T_1/T_1^* &= 0.39282 \\T_{01}/T_{01}^* &= 0.71802\end{aligned}$$

Since all we know is the static temperature at the exit, we need to iterate on a solution. We can guess at a pre-shock Mach number at the duct exit, and iterate on that value until we match the exit temperature:

$$\begin{aligned}M_2 &= 1.753 \\T_2/T_2^* &= 0.62964 \\T_{02}/T_{02}^* &= 0.84716 \\T_2 &= 233.844 && \text{K} \\T_{02} &= 377.553 && \text{K} \\M_3 &= 0.6274 \\T_3/T_2 &= 1.4967 \\T_3 &= 350.000 && \text{K}\end{aligned}$$

In this case we used *Solver* to match the exit temperature.

Therefore, the exit Mach number is:

$$M_3 = 0.627$$

The rate of heat addition is calculated from the rise in stagnation temperature:




$$q_{1-2} = 57.78 \quad \text{kJ/kg}$$

# Problem 13.114

[Difficulty: 2]

\*13.114 A normal shock stands in a section of insulated constant-area duct. The flow is frictional. At section ①, some distance upstream from the shock,  $T_1 = 470^\circ\text{R}$ . At section ④, some distance downstream from the shock,  $T_4 = 750^\circ\text{R}$  and  $M_4 = 1.0$ . Denote conditions immediately upstream and downstream from the shock by subscripts ② and ③, respectively. Sketch the pressure distribution along the duct, indicating clearly the locations of sections ① through ④. Sketch a  $Ts$  diagram for the flow. Determine the Mach number at section ①.

Solution:



For adiabatic flow,  $T_0 = \text{constant}$  (from energy eq.).

$$\text{Thus, } T_{0,1} = T_{0,4} = T_4 \left[ 1 + \frac{k-1}{2} M_4^2 \right] = 750^\circ\text{R} [1.2] = 900^\circ\text{R}$$

$$\text{Since } T_{0,1} = T_1 \left[ 1 + \frac{k-1}{2} M_1^2 \right], \text{ then}$$

$$M_1^2 = \frac{2}{k-1} \left[ \frac{T_{0,1}}{T_1} - 1 \right] = \frac{2}{0.4} \left[ \frac{900^\circ\text{R}}{470^\circ\text{R}} - 1 \right] = 4.57$$

$$M_1 = \sqrt{4.57} = 2.14$$

$M_1$



# Problem 13.116

[Difficulty: 4]

\*13.116 A normal shock stands in a section of insulated constant-area duct. The flow is frictional. At section ①, some distance upstream from the shock,  $T_1 = 668^\circ\text{R}$ ,  $p_0 = 78.2$  psia, and  $M_1 = 2.05$ . At section ④, some distance downstream from the shock,  $M_4 = 1.00$ . Calculate the air speed,  $V_2$ , immediately ahead of the shock, where  $T_2 = 388^\circ\text{F}$ . Evaluate the entropy change,  $s_4 - s_1$ .

Solution: Use functions for steady, one-dimensional compressible flow.

Computing equations:  $\frac{T}{T_0}$  from isentropic functions (Appendix E.1)

$\frac{p}{p^*}$  from Fanno-line functions (Appendix E.2)

- Assumptions: (1) Steady flow (4) Fanno line flow  
 (2) Uniform flow at each cross-section (5)  $F_{Bx} = 0$   
 (3) Ideal gas (6)  $\Delta z = 0$

For adiabatic flow on Fanno line and across shock,  $T_0 = \text{constant}$ . At  $M_1 = 2.05$ ,  $T/T_0 = 0.5433$  (Eq. 11.17b). Thus

$$T_0 = T_{01} = \frac{T_1}{(T/T_0)_1} = \frac{668^\circ\text{R}}{0.5433} = 1230^\circ\text{R}$$

Using  $T_2 = 388^\circ\text{F}$  ( $848^\circ\text{R}$ ),  $\frac{T}{T_0} = \frac{848^\circ\text{R}}{1230^\circ\text{R}} = 0.6894$  and  $M_2 = 1.50$  (Table E.1).

$$V_2 = M_2 C_2 = M_2 \sqrt{kRT_2} = 1.50 \left[ 1.4 \times \frac{53.3 \text{ ft} \cdot \text{lb}_f}{\text{lbm} \cdot ^\circ\text{R}} \times 848^\circ\text{R} \times \frac{32.2 \text{ lbm} \times \text{slug} \cdot \text{ft}}{\text{slug} \times \text{lb}_f \cdot \text{s}^2} \right]^{1/2}$$

$$V_2 = 2140 \text{ ft/s}$$

Flow must stay on the same Fanno line. Thus  $(p/p_0^*)_1 = 1.760$  at  $M_1 = 2.05$  (Eq. 12.18e). Thus


$$p_0^* = \frac{p_{01}}{(p/p_0^*)_1} = \frac{78.2 \text{ psia}}{1.760} = 44.4 \text{ psia}$$

From the Gibbs equation

$$T ds = dh - v dp; \quad ds = c_p \frac{dT}{T} - R \frac{dp}{p}$$

$$\Delta s = c_p \ln \frac{T_04}{T_01} - R \ln \frac{p_04}{p_01}$$

$$\Delta s = -53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot ^\circ\text{R}} \times \ln \left( \frac{44.4}{78.2} \right) \times \frac{\text{Btu}}{778 \text{ ft} \cdot \text{lb}_f} = 0.0388 \text{ Btu/lbm} \cdot ^\circ\text{R}$$



{ This problem could be solved without using functions, but the solution would require more calculations. }

## Problem 13.117

[Difficulty: 2]

---

**13.117** Nitrogen is discharged from a 30-cm-diameter duct at  $M_2 = 0.85$ ,  $T_2 = 300$  K, and  $p_2 = 200$  kPa. The temperature at the inlet of the duct is  $T_1 = 330$  K. Compute the pressure at the inlet and the mass flow rate.

---

**Given:** Nitrogen traveling through duct

**Find:** Inlet pressure and mass flow rate

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 296.8 && \text{J/kg-K} \\k &= 1.4 \\D &= 30 && \text{cm} \\M_2 &= 0.85 \\T_2 &= 300 && \text{K} \\p_2 &= 200 && \text{kPa} \\T_1 &= 330 && \text{K}\end{aligned}$$

Equations and Computations:

We can find the critical temperature and pressure for choking at station 2:

$$\begin{aligned}T_2/T^* &= 1.0485 \\T^* &= 286.1 && \text{K} \\p_2/p^* &= 1.2047 \\p^* &= 166.0 && \text{kPa}\end{aligned}$$

Knowing the critical state, the Mach number at station 1 can be found:

(we will use *Goal Seek* to match the Mach number)

$$\begin{aligned}T_1/T^* &= 1.1533 \\M_1 &= 0.4497 \\T_1/T^* &= 1.1533\end{aligned}$$

The static to critical pressure ratio is a function of Mach number. Therefore:

$$p_1 = 396 \quad \text{kPa}$$

The sound speed at station 1 is:

$$c_1 = 370.30 \quad \text{m/s}$$

So the velocity at 1 is:

$$V_1 = 166.54 \quad \text{m/s}$$

The density at 1 can be calculated from the ideal gas equation of state:

$$\rho_1 = 4.0476 \quad \text{kg/m}^3$$

The area of the duct is:

$$A = 0.0707 \quad \text{m}^2$$

So the mass flow rate is:

$$m = 47.6 \quad \text{kg/s}$$

## Problem 13.118

[Difficulty: 2]

**13.118** Room air is drawn into an insulated duct of constant area through a smoothly contoured converging nozzle. Room conditions are  $T = 80^\circ\text{F}$  and  $p = 14.7$  psia. The duct diameter is  $D = 1$  in. The pressure at the duct inlet (nozzle outlet) is  $p_1 = 13$  psia. Find (a) the mass flow rate in the duct and (b) the range of exit pressures for which the duct exit flow is choked.



**Given:** Air flow in an insulated duct

**Find:** Mass flow rate; Range of choked exit pressures

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$      $c = \sqrt{k \cdot R \cdot T}$      $\frac{A}{A_{\text{crit}}} = \frac{1}{M} \cdot \left( \frac{1 + \frac{k-1}{2} \cdot M^2}{\frac{k+1}{2}} \right)^{\frac{k+1}{2 \cdot (k-1)}}$

Given or available data     $T_0 = (80 + 460) \cdot R$      $p_0 = 14.7 \cdot \text{psi}$      $p_1 = 13 \cdot \text{psi}$      $D = 1 \cdot \text{in}$

$k = 1.4$      $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot R}$      $A = \frac{\pi \cdot D^2}{4}$      $A = 0.785 \cdot \text{in}^2$

Assuming isentropic flow, stagnation conditions are constant. Hence

$$M_1 = \sqrt{\frac{2}{k-1} \left[ \left( \frac{p_0}{p_1} \right)^{\frac{k-1}{k}} - 1 \right]}$$

$M_1 = 0.423$      $T_1 = \frac{T_0}{1 + \frac{k-1}{2} \cdot M_1^2}$      $T_1 = 521 \cdot R$      $T_1 = 61.7^\circ\text{F}$

$c_1 = \sqrt{k \cdot R_{\text{air}} \cdot T_1}$      $c_1 = 341 \frac{\text{m}}{\text{s}}$      $V_1 = M_1 \cdot c_1$      $V_1 = 144 \frac{\text{m}}{\text{s}}$

Also     $\rho_1 = \frac{p_1}{R_{\text{air}} \cdot T_1}$      $\rho_1 = 0.0673 \cdot \frac{\text{lb}_m}{\text{ft}^3}$

Hence     $m_{\text{rate}} = \rho_1 \cdot V_1 \cdot A$      $m_{\text{rate}} = 0.174 \cdot \frac{\text{lb}_m}{\text{s}}$

When flow is choked     $M_2 = 1$  hence     $T_2 = \frac{T_0}{1 + \frac{k-1}{2}}$      $T_2 = 450 \cdot R$      $T_2 = -9.7^\circ\text{F}$

We also have     $c_2 = \sqrt{k \cdot R_{\text{air}} \cdot T_2}$      $c_2 = 1040 \cdot \frac{\text{ft}}{\text{s}}$      $V_2 = c_2$      $V_2 = 1040 \cdot \frac{\text{ft}}{\text{s}}$

From continuity     $\rho_1 \cdot V_1 = \rho_2 \cdot V_2$      $\rho_2 = \rho_1 \cdot \frac{V_1}{V_2}$      $\rho_2 = 0.0306 \cdot \frac{\text{lb}_m}{\text{ft}^3}$

Hence     $p_2 = \rho_2 \cdot R_{\text{air}} \cdot T_2$      $p_2 = 5.11 \cdot \text{psi}$

The flow will therefore choke for any back pressure (pressure at the exit) less than or equal to this pressure

(From Fanno line function     $\frac{p_1}{p_{\text{crit}}} = 2.545$     at     $M_1 = 0.423$     so     $p_{\text{crit}} = \frac{p_1}{2.545}$      $p_{\text{crit}} = 5.11 \cdot \text{psi}$     Check!)

### Problem 13.119

[Difficulty: 4]

**13.119** Air from a large reservoir at 25 psia and 250°F flows isentropically through a converging nozzle into an insulated pipe at 24 psia. The pipe flow experiences friction effects. Obtain a plot of the  $Ts$  diagram for this flow, until  $M = 1$ . Also plot the pressure and speed distributions from the entrance to the location at which  $M = 1$ .

**Given:** Air flow from converging nozzle into pipe

**Find:** Plot  $Ts$  diagram and pressure and speed curves

**Solution:**

The given or available data is:

$R =$	53.33	ft lbf/lbm °R
$k =$	1.4	
$c_p =$	0.2399	Btu/lbm °R
	187	ft lbf/lbm °R
$T_0 =$	710	°R
$p_0 =$	25	psi
$p_e =$	24	psi

Equations and Computations:

From  $p_0$  and  $p_e$ , and Eq. 13.7a

(using built-in function  $IsenMfromp(M,k)$ )  $M_e = 0.242$


Using built-in function  $IsenT(M,k)$   $T_e = 702$  °R

Using  $p_e$ ,  $M_e$ , and function  $Fannop(M,k)$   $p^* = 5.34$  psi


Using  $T_e$ ,  $M_e$ , and function  $FannoT(M,k)$   $T^* = 592$  °R

We can now use Fanno-line relations to compute values for a range of Mach numbers:


$M$	$T/T^*$	$T$ (°R)	$c$ (ft/s)	$V$ (ft/s)	$p/p^*$	$p$ (psi)	$\Delta s$ (ft lbf/lbm °R) ) Eq. (12.11b)
0.242	1.186	702	1299	315	4.50	24.0	0.00
0.25	1.185	701	1298	325	4.35	23.2	1.57
0.26	1.184						
0.27	1.183						
0.28	1.181						
0.29	1.180						
0.3	1.179						
0.31	1.177						
0.32	1.176						
0.33	1.174						
0.34	1.173						
0.35	1.171						
0.36	1.170						
0.37	1.168						
0.38	1.166						
0.39	1.165						
0.4	1.163						
0.41	1.161						
0.42	1.159						
0.43	1.157						
0.44	1.155						
0.45	1.153						



0.46	1.151	681	1280	589	2.33	12.4	29.44
0.47	1.149	680	1279	601	2.28	12.2	30.31
0.48	1.147						
0.49	1.145						
0.5	1.143						
0.51	1.141						
0.52	1.138						
0.53	1.136						
0.54	1.134						
0.55	1.132						
0.56	1.129						
0.57	1.127						
0.58	1.124						
0.59	1.122						
0.6	1.119						
0.61	1.117						
0.62	1.114						
0.63	1.112						
0.64	1.109						
0.65	1.107						
0.66	1.104						
0.67	1.101						



0.68	1.098	650	1250	850	1.54	8.2	42.77
0.69	1.096	648	1248	861	1.52	8.1	43.15
0.7	1.093						
0.71	1.090						
0.72	1.087						
0.73	1.084						
0.74	1.082						
0.75	1.079						
0.76	1.076						
0.77	1.073						
0.78	1.070						
0.79	1.067						
0.8	1.064						
0.81	1.061						
0.82	1.058						
0.83	1.055						
0.84	1.052						
0.85	1.048						
0.86	1.045						
0.87	1.042						
0.88	1.039						
0.89	1.036						



0.9	1.033	611	1212	1091	1.13	6.0	47.84
0.91	1.029	609	1210	1101	1.11	6.0	47.94
0.92	1.026	607	1208	1112	1.10	5.9	48.02
0.93	1.023	605	1206	1122	1.09	5.8	48.09
0.94	1.020	603	1204	1132	1.07	5.7	48.15
0.95	1.017	601	1202	1142	1.06	5.7	48.20
0.96	1.013	600	1201	1153	1.05	5.6	48.24
0.97	1.010	598	1199	1163	1.04	5.5	48.27
0.98	1.007	596	1197	1173	1.02	5.5	48.30
0.99	1.003	594	1195	1183	1.01	5.4	48.31
1	1.000	592	1193	1193	1.00	5.3	48.31

## Problem 13.120

[Difficulty: 4]

**13.120** Repeat Problem 13.119 except the nozzle is now a converging-diverging nozzle delivering the air to the pipe at 2.5 psia.

**Given:** Air flow from converging-diverging nozzle into pipe

**Find:** Plot Ts diagram and pressure and speed curves

**Solution:**

The given or available data is:

$$\begin{aligned}
 R &= 53.33 \text{ ft}\cdot\text{lb}/\text{lbm}\cdot^\circ\text{R} \\
 k &= 1.4 \\
 c_p &= 0.2399 \text{ Btu}/\text{lbm}\cdot^\circ\text{R} \\
 &= 187 \text{ ft}\cdot\text{lb}/\text{lbm}\cdot^\circ\text{R} \\
 T_0 &= 710 \text{ }^\circ\text{R} \\
 p_0 &= 25 \text{ psi} \\
 p_e &= 2.5 \text{ psi}
 \end{aligned}$$

Equations and Computations:

From  $p_0$  and  $p_e$ , and Eq. 13.7a  
(using built-in function  $IsenMfromp(M,k)$ )  $M_e = 2.16$


Using built-in function  $IsenT(M,k)$   $T_e = 368 \text{ }^\circ\text{R}$

Using  $p_e$ ,  $M_e$ , and function  $Fannop(M,k)$   $p^* = 6.84 \text{ psi}$

Using  $T_e$ ,  $M_e$ , and function  $FannoT(M,k)$   $T^* = 592 \text{ }^\circ\text{R}$


We can now use Fanno-line relations to compute values for a range of Mach numbers:

$M$	$T/T^*$	$T$ ( $^\circ\text{R}$ )	$c$ (ft/s)	$V$ (ft/s)	$p/p^*$	$p$ (psi)	$\Delta s$ (ft·lb/·lbm· $^\circ\text{R}$ ) Eq. (12.11b)
2.157	0.622	368	940	2028	0.37	2.5	0.00
2	0.667	394	974	1948	0.41	2.8	7.18
1.99	0.670						
1.98	0.673						
1.97	0.676						
1.96	0.679						
1.95	0.682						
1.94	0.685						
1.93	0.688						
1.92	0.691						
1.91	0.694						
1.9	0.697						
1.89	0.700						
1.88	0.703						
1.87	0.706						
1.86	0.709						
1.85	0.712						
1.84	0.716						
1.83	0.719						
1.82	0.722						
1.81	0.725						
1.8	0.728						
1.79	0.731	433	1020	1826	0.48	3.3	16.08
1.78	0.735	435	1022	1819	0.48	3.3	16.48
1.77	0.738	436	1024	1813	0.49	3.3	16.88
1.76	0.741	438	1027	1807	0.49	3.3	17.27
1.75	0.744	440	1029	1801	0.49	3.4	17.66
1.74	0.747	442	1031	1794	0.50	3.4	18.05
1.73	0.751	444	1033	1788	0.50	3.4	18.44
1.72	0.754	446	1036	1781	0.50	3.5	18.82
1.71	0.757	448	1038	1775	0.51	3.5	19.20




1.7	0.760	450	1040	1768	0.51	3.5	19.58
1.69	0.764	452	1042	1761	0.52	3.5	19.95
1.68	0.767	454	1045	1755	0.52	3.6	20.32
1.67	0.770	456	1047	1748	0.53	3.6	20.69
1.66	0.774	458	1049	1741	0.53	3.6	21.06
1.65	0.777	460	1051	1735	0.53	3.7	21.42
1.64	0.780	462	1054	1728	0.54	3.7	21.78
1.63	0.784	464	1056	1721	0.54	3.7	22.14

1.62	0.787
1.61	0.790
1.6	0.794
1.59	0.797
1.58	0.800
1.57	0.804
1.56	0.807
1.55	0.811
1.54	0.814
1.53	0.817
1.52	0.821
1.51	0.824
1.5	0.828
1.49	0.831
1.48	0.834
1.47	0.838
1.46	0.841
1.45	0.845
1.44	0.848
1.43	0.852



1.42	0.855	506	1103	1566	0.65	4.5	28.76
1.41	0.859	508	1105	1558	0.66	4.5	29.03

1.4	0.862
1.39	0.866
1.38	0.869
1.37	0.872
1.36	0.876
1.35	0.879
1.34	0.883
1.33	0.886
1.32	0.890
1.31	0.893
1.3	0.897
1.29	0.900
1.28	0.904
1.27	0.907
1.26	0.911
1.25	0.914
1.24	0.918
1.23	0.921
1.22	0.925
1.21	0.928



1.2	0.932	551	1151	1381	0.80	5.5	33.50
1.19	0.935	553	1153	1372	0.81	5.6	33.65
1.18	0.939	555	1155	1363	0.82	5.6	33.79
1.17	0.942	557	1158	1354	0.83	5.7	33.93
1.16	0.946	559	1160	1345	0.84	5.7	34.05
1.15	0.949	561	1162	1336	0.85	5.8	34.18
1.14	0.952	564	1164	1327	0.86	5.9	34.29
1.13	0.956	566	1166	1318	0.87	5.9	34.40
1.12	0.959	568	1168	1308	0.87	6.0	34.50
1.11	0.963	570	1170	1299	0.88	6.0	34.59
1.1	0.966	572	1172	1290	0.89	6.1	34.68
1.09	0.970	574	1174	1280	0.90	6.2	34.76
1.08	0.973	576	1176	1271	0.91	6.2	34.83
1.07	0.976	578	1179	1261	0.92	6.3	34.89
1.06	0.980	580	1181	1251	0.93	6.4	34.95
1.05	0.983	582	1183	1242	0.94	6.5	34.99
1.04	0.987	584	1185	1232	0.96	6.5	35.03
1.03	0.990	586	1187	1222	0.97	6.6	35.06
1.02	0.993	588	1189	1212	0.98	6.7	35.08
1.01	0.997	590	1191	1203	0.99	6.8	35.10
1	1.000	592	1193	1193	1.00	6.8	35.10

## Problem 13.121

[Difficulty: 3]

**13.121** A 5-m duct 35 cm in diameter contains oxygen flowing at the rate of 40 kg/s. The inlet conditions are  $p_1 = 200$  kPa and  $T_1 = 450$  K. The exit pressure is  $p_2 = 160$  kPa. Calculate the inlet and exit Mach number, and the exit stagnation pressure and temperature. Determine the friction factor, and estimate the absolute roughness of the duct material.

**Given:** Oxygen traveling through duct

**Find:** Inlet and exit Mach numbers, exit stagnation conditions, friction factor and absolute roughness

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 259.8 && \text{J/kg-K} \\k &= 1.4 \\D &= 35 && \text{cm} \\L &= 5 && \text{m} \\m &= 40.0 && \text{kg/s} \\p_1 &= 200 && \text{kPa} \\T_1 &= 450 && \text{K} \\p_2 &= 160 && \text{kPa}\end{aligned}$$

Equations and Computations:

The area of the duct is:

$$A = 0.0962 \quad \text{m}^2$$

The sound speed at station 1 is:

$$c_1 = 404.57 \quad \text{m/s}$$

The density at 1 can be calculated from the ideal gas equation of state:

$$\rho_1 = 1.7107 \quad \text{kg/m}^3$$

So the velocity at 1 is:

$$V_1 = 243.03 \quad \text{m/s}$$

and the Mach number at 1 is:

$$M_1 = 0.601$$

The critical temperature and pressure may then be calculated:

$$\begin{aligned}p_1/p^* &= 1.7611 \\p^* &= 113.6 && \text{kPa} \\T_1/T^* &= 1.1192 \\T^* &= 402.1 && \text{K}\end{aligned}$$

Since the critical pressure is equal at 1 and 2, we can find the pressure ratio at 2:

$$p_2/p^* = 1.4089$$

The static to critical pressure ratio is a function of Mach number. Therefore:

$$\begin{aligned}M_2 &= 0.738 \\p_2/p^* &= 1.4089\end{aligned}$$

(we used *Solver* to find the correct Mach number to match the pressure ratio)

The exit temperature is:

$$\begin{aligned}T_2/T^* &= 1.0820 \\T_2 &= 435.0 && \text{K}\end{aligned}$$

Based on the exit Mach number, pressure, and temperature, stagnation conditions are:

$$p_{02} = 230 \text{ kPa}$$

$$T_{02} = 482 \text{ K}$$

The maximum friction lengths at stations 1 and 2 are:

$$fL_1/D = 0.48802$$

$$fL_2/D = 0.14357$$

So the friction length for this duct is:

$$fL/D = 0.34445$$

and the friction factor is:

$$f = 0.02411$$

Now to find the roughness of the pipe, we need the Reynolds number.

From the LMNO Engineering website, we can find the viscosities of oxygen:

$$\mu_1 = 2.688\text{E-}05 \text{ N-s/m}^2$$

$$\mu_2 = 2.802\text{E-}05 \text{ N-s/m}^2$$

Therefore the Reynolds number at station 1 is:

$$\text{Re}_1 = 5.413\text{E}+06$$

At station 2, we will need to find density and velocity first. From ideal gas equation:

$$\rho_2 = 1.4156 \text{ kg/m}^3$$

The sound speed at 2 is:

$$c_2 = 397.79 \text{ m/s}$$

So the velocity at 2 is:

$$V_2 = 293.69 \text{ m/s}$$

and the Reynolds number is:

$$\text{Re}_2 = 5.193\text{E}+06$$

So the Reynolds number does not change significantly over the length of duct.

We will use an average of the two to find the relative roughness:

$$\text{Re} = 5.303\text{E}+06$$

The relative roughness for this pipe is:

$$e/D = 0.00222$$

$$f = 0.02411$$

(we used *Solver* to find the correct roughness to match the friction factor.)

Therefore, the roughness of the duct material is:

$$e = 0.0776 \text{ cm}$$

## Problem 13.122

[Difficulty: 3]

**13.122** Air flows steadily and adiabatically from a large tank through a converging nozzle connected to an insulated constant-area duct. The nozzle may be considered frictionless. Air in the tank is at  $p = 145$  psia and  $T = 250^\circ\text{F}$ . The absolute pressure at the nozzle exit (duct inlet) is 125 psia. Determine the pressure at the end of the duct, if the temperature there is  $150^\circ\text{F}$ . Find the entropy increase.



**Given:** Air flow in a converging nozzle and insulated duct

**Find:** Pressure at end of duct; Entropy increase

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{air}} \cdot \ln\left(\frac{p_2}{p_1}\right)$        $c = \sqrt{k \cdot R \cdot T}$

Given or available data       $T_0 = (250 + 460) \cdot \text{R}$        $p_0 = 145 \cdot \text{psi}$        $p_1 = 125 \cdot \text{psi}$        $T_2 = (150 + 460) \cdot \text{R}$

$k = 1.4$        $c_p = 0.2399 \cdot \frac{\text{BTU}}{\text{lbm} \cdot \text{R}}$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}}$

Assuming isentropic flow in the nozzle

$$M_1 = \sqrt{\frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_1} \right)^{\frac{k-1}{k}} - 1 \right]}$$

$M_1 = 0.465$        $T_1 = \frac{T_0}{1 + \frac{k-1}{2} \cdot M_1^2}$        $T_1 = 681 \cdot \text{R}$        $T_1 = 221 \cdot ^\circ\text{F}$

In the duct  $T_0$  (a measure of total energy) is constant, so  $M_2 = \sqrt{\frac{2}{k-1} \cdot \left[ \left( \frac{T_0}{T_2} \right) - 1 \right]}$        $M_2 = 0.905$

At each location       $c_1 = \sqrt{k \cdot R_{\text{air}} \cdot T_1}$        $c_1 = 1279 \cdot \frac{\text{ft}}{\text{s}}$        $V_1 = M_1 \cdot c_1$        $V_1 = 595 \cdot \frac{\text{ft}}{\text{s}}$

$c_2 = \sqrt{k \cdot R_{\text{air}} \cdot T_2}$        $c_2 = 1211 \cdot \frac{\text{ft}}{\text{s}}$        $V_2 = M_2 \cdot c_2$        $V_2 = 1096 \cdot \frac{\text{ft}}{\text{s}}$

Also       $\rho_1 = \frac{p_1}{R_{\text{air}} \cdot T_1}$        $\rho_1 = 0.4960 \cdot \frac{\text{lbm}}{\text{ft}^3}$

Hence       $m_{\text{rate}} = \rho_1 \cdot V_1 \cdot A = \rho_2 \cdot V_2 \cdot A$       so       $\rho_2 = \rho_1 \cdot \frac{V_1}{V_2}$        $\rho_2 = 0.269 \cdot \frac{\text{lbm}}{\text{ft}^3}$

Then       $p_2 = \rho_2 \cdot R_{\text{air}} \cdot T_2$        $p_2 = 60.8 \cdot \text{psi}$       Finally       $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{air}} \cdot \ln\left(\frac{p_2}{p_1}\right)$        $\Delta s = 0.0231 \cdot \frac{\text{BTU}}{\text{lbm} \cdot \text{R}}$

(Note: Using Fanno line relations, at  $M_1 = 0.465$        $\frac{T_1}{T_{\text{crit}}} = 1.150$        $T_{\text{crit}} = \frac{T_1}{1.150}$        $T_{\text{crit}} = 329 \text{ K}$

$\frac{p_1}{p_{\text{crit}}} = 2.306$        $p_{\text{crit}} = \frac{p_1}{2.3060}$        $p_{\text{crit}} = 54.2 \cdot \text{psi}$

Then       $\frac{T_2}{T_{\text{crit}}} = 1.031$       so       $M_2 = 0.907$        $\frac{p_2}{p_{\text{crit}}} = 1.119$        $p_2 = 1.119 \cdot p_{\text{crit}}$        $p_2 = 60.7 \cdot \text{psi}$       Check!

### Problem 13.123

[Difficulty: 2]

**13.123** A Fanno-line flow apparatus in an undergraduate fluid mechanics laboratory consists of a smooth brass tube of 7.16 mm inside diameter, fed by a converging nozzle. The lab temperature and uncorrected barometer reading are 23.5°C and 755.1 mm of mercury. The pressure at the exit from the converging nozzle (entrance to the constant-area duct) is -20.8 mm of mercury (gage). Compute the Mach number at the entrance to the constant-area tube. Calculate the mass flow rate in the tube. Evaluate the pressure at the location in the tube where the Mach number is 0.4.

Solution: Apply equations for steady, 1-D compressible flow:

Computing equations:  $T_0 = T(1 + \frac{k-1}{2} M^2)$  {Entire flow adiabatic}

$p_0 = p(1 + \frac{k-1}{2} M^2)^{\frac{k}{k-1}}$  {Isentropic in nozzle}

Assume: (1) Stagnation conditions in laboratory;  
(2) Ideal gas

Then 
$$\frac{p_0}{p_1} = \left(1 + \frac{k-1}{2} M_1^2\right)^{\frac{k}{k-1}} = \frac{755.1 \text{ mm Hg}}{(755.1 - 20.8) \text{ mm Hg}} = 1.03$$

$$M_1 = \left\{ \frac{2}{k-1} \left[ \left( \frac{p_0}{p_1} \right)^{\frac{k-1}{k}} - 1 \right] \right\}^{1/2} = \left\{ 5 \left[ \left( \frac{755.1}{734.3} \right)^{0.286} - 1 \right] \right\}^{1/2} = 0.200 \quad M_1$$

From continuity,  $\dot{m} = \rho_1 V_1 A_1$ ;  $\rho_1 = \frac{p_1}{RT_1}$

$$p_1 = \rho Hg g h_1 = (13.5) 1000 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.734 \text{ m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 97.2 \text{ kPa (abs)}$$

$$T_1 = \frac{T_0}{1 + \frac{k-1}{2} M_1^2} = \frac{(273 + 23) \text{ K}}{1 + 0.2(0.200)^2} = 294 \text{ K}; c_1 = \sqrt{kRT_1} = 344 \text{ m/s}$$

$$\rho_1 = \frac{97.2 \times 10^3 \text{ N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m}} \times \frac{1}{294 \text{ K}} = 1.15 \text{ kg/m}^3$$

$$V_1 = M_1 c_1 = 0.200 \times 344 \text{ m/s} = 68.8 \text{ m/s}$$

$$A_1 = \frac{\pi D^2}{4} = \frac{\pi (0.00716)^2 \text{ m}^2}{4} = 4.03 \times 10^{-5} \text{ m}^2$$


$$\dot{m} = 1.15 \frac{\text{kg}}{\text{m}^3} \times 68.8 \frac{\text{m}}{\text{s}} \times 4.03 \times 10^{-5} \text{ m}^2 = 3.19 \times 10^{-3} \text{ kg/s} \quad \dot{m}$$

Since  $T_0 = \text{constant}$ ,  $T_2 = T_0 / (1 + \frac{k-1}{2} M_2^2) = 287 \text{ K}$ ;  $c_2 = 340 \text{ m/s}$ ;  $V_2 = M_2 c_2 = 136 \text{ m/s}$

$$p_2 = \rho_1 \frac{V_1}{V_2} = 1.15 \frac{\text{kg}}{\text{m}^3} \times \frac{68.8}{136} = 0.582 \text{ kg/m}^3$$

Then  $p_2 = \rho_2 RT_2$

$$p_2 = 0.582 \frac{\text{kg}}{\text{m}^3} \times \frac{287 \text{ N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 287 \text{ K} = 47.9 \text{ kPa (abs)}$$



### Problem 13.124

[Difficulty: 3]

**13.124** Measurements are made of compressible flow in a long smooth 7.16 mm i.d. tube. Air is drawn from the surroundings (20°C and 101 kPa) by a vacuum pump downstream. Pressure readings along the tube become steady when the downstream pressure is reduced to 626 mm Hg (vacuum) or below. For these conditions, determine (a) the maximum mass flow rate possible through the tube, (b) the stagnation pressure of the air leaving the tube, and (c) the entropy change of the air in the tube. Show static and stagnation state points and the process path on a  $Ts$  diagram.

Solution:

Basic equations:  $\dot{m} = \rho VA$        $p = \rho RT$        $Tds = dh - v dp$

Computing equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$        $\frac{p}{p_0} = \left(\frac{T}{T_0}\right)^{\frac{k}{k-1}}$

Assumptions: (1) steady flow (2) ideal gas  
(3) adiabatic flow through tube  
(4) uniform flow at a section

Since pressure distribution does not change when  $p_e$  reaches 626 mmHg (vacuum), flow is choked,  $M_e = 1.0$  and  $p_e = p_0$

$$p_e = p_{\text{atm}} - \rho g \Delta h = 101 \times 10^3 \frac{\text{N}}{\text{m}^2} - 13.55 \times 999 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.1626 \text{ m} = 17.87 \times 10^3 \frac{\text{N}}{\text{m}^2}$$

$$T_e = \frac{T_0}{1 + \frac{k-1}{2} M_e^2} = \frac{(273.20 \text{ K})}{1 + 0.2} = 244 \text{ K}$$

$$\rho_e = \frac{p_e}{RT_e} = 17.87 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m}} \times \frac{1}{244 \text{ K}} = 0.255 \frac{\text{kg}}{\text{m}^3}$$

$$V_e = (kRT_e)^{1/2} = (1.4 \times 287 \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 244 \text{ K} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2})^{1/2} = 313 \text{ m/s}$$

$$\dot{m} = \rho_e V_e A = 0.255 \frac{\text{kg}}{\text{m}^3} \times 313 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} (0.00716 \text{ m})^2 = 0.00321 \frac{\text{kg}}{\text{s}}$$


$$p_{0e} = p_e \left(1 + \frac{k-1}{2} M_e^2\right)^{\frac{k}{k-1}} = 17.87 \text{ kPa} (1 + 0.2)^{3.5} = 33.8 \text{ kPa (abs)}$$

For an ideal gas, the  $Tds$  equation can be written as

$$Tds = dh - v dp = c_p dT - RT \frac{dp}{p} \quad \therefore ds = c_p \frac{dT}{T} - R \frac{dp}{p}$$

Then,  $s_e - s_1 = s_{0e} - s_{01} = c_p \ln \frac{T_{0e}}{T_{01}} - R \ln \frac{p_{0e}}{p_{01}}$

$$s_e - s_1 = -287 \frac{\text{J}}{\text{kg} \cdot \text{K}} \ln \left(\frac{33.8}{101}\right) = 314 \text{ J/kg} \cdot \text{K}$$



# Problem 13.125

[Difficulty: 3]

13.125 Air flows through a smooth well-insulated 4-in.-diameter pipe at 600 lbm/min. At one section the air is at 100 psia and 80°F. Determine the minimum pressure and the maximum speed that can occur in the pipe.

Solution:

Basic equations:  $\dot{m} = \rho VA$        $P = \rho RT$

Computing equations:  $T_0/T = 1 + \frac{k-1}{2} M^2$        $T_0 = \text{constant}$

Assumptions: (1) steady flow      (3) uniform flow at a section  
 (2) adiabatic flow      (4) ideal gas

$$P_1 = \frac{P}{RT} = 100 \frac{\text{lb}_f}{\text{in}^2} \times \frac{\text{lb}_m \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lb}_f} \times \frac{1}{540 \text{ R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.500 \text{ lbm/ft}^3$$

$$\dot{m} = \rho VA \quad ; \quad A = \pi \left(\frac{D}{2}\right)^2$$

$$V_1 = \frac{\dot{m}}{\rho_1 A} = \frac{600 \text{ lbm/min}}{\pi \left(\frac{4}{12}\right)^2 \text{ ft}^2 \times 0.500 \text{ lbm/ft}^3} \times \frac{\text{min}}{60 \text{ s}} = 229 \text{ ft/s}$$

$$M_1 = \frac{V_1}{c_1} \quad c_1 = (RT_1)^{1/2} = \left(14 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot \text{R}} \times 540 \text{ R} \times \frac{32.2 \text{ lbm}}{\text{slug}} \times \frac{\text{ft}}{\text{lb}_f} \right)^{1/2} = 1140 \text{ ft/s}$$

$$M_1 = \frac{229}{1140} = 0.201$$

Since  $M_1 < 1.0$ , the minimum pressure and max velocity occur for  $M_2 = 1.0$


$$T_0/T = 1 + \frac{k-1}{2} M^2 \quad ; \quad \frac{T_2}{T_1} = \frac{1 + \frac{k-1}{2} M_1^2}{1 + \frac{k-1}{2} M_2^2} = \frac{1 + 0.2(0.201)^2}{1 + 0.2(1.0)^2} = 0.840$$

$$T_2 = 0.840 (T_1) = 0.840 (540 \text{ R}) = 454 \text{ R}$$

$$V_2 = M_2 c_2 = M_2 (RT_2)^{1/2} = 1.0 \left(14 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot \text{R}} \times 454 \text{ R} \times \frac{32.2 \text{ lbm}}{\text{slug}} \times \frac{\text{ft}}{\text{lb}_f}\right)^{1/2} = 1040 \text{ ft/s} \quad \leftarrow V_{\text{max}}$$

$$\dot{m} = \rho_1 V_1 A = \rho_2 V_2 A \quad ; \quad P_2 = \frac{V_1}{V_2} P_1 = \frac{229}{1040} \times 0.500 \frac{\text{lbm}}{\text{ft}^3} = 0.110 \text{ lbm/ft}^3$$

$$P_2 = \rho_2 RT_2 = 0.110 \frac{\text{lbm}}{\text{ft}^3} \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot \text{R}} \times 454 \text{ R} \times \frac{\text{ft}^2}{144 \text{ in}^2} = 18.5 \text{ psia} \quad \leftarrow P_{\text{min}}$$



\*Fanno-line Flow Functions

From Appendix E with  $M_1 = 0.20$ ,

$$T/T^* = 1.191 \text{ (12.18a)} \quad ; \quad T_2 = T^* = 453 \text{ R}$$

$$P/P^* = 5.456 \text{ (12.18d)} \quad ; \quad P_2 = P^* = 18.3 \text{ psia}$$

$$V/V^* = 0.2182 \text{ (12.18c)} \quad ; \quad V_2 = V^* = 1050 \text{ ft/s}$$

## Problem 13.126

[Difficulty: 3]

**13.126** Nitrogen at stagnation conditions of 105 psia and 100°F flows through an insulated converging-diverging nozzle without friction. The nozzle, which has an exit-to-throat area ratio of 4, discharges supersonically into a constant area duct, which has a friction length  $fL/D = 0.355$ . Determine the temperature and pressure at the exit of the duct.

**Given:** Nitrogen traveling through C-D nozzle and constant-area duct with friction

**Find:** Exit temperature and pressure

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 55.16 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.4 \\p_{01} &= 105 && \text{psia} \\T_{01} &= 100 && ^\circ\text{F} \\T_{01} &= 560 && ^\circ\text{R} \\A_e/A_t &= 4 \\fL/D &= 0.355\end{aligned}$$

Equations and Computations:

Based on the area ratio of the nozzle, we can find the nozzle exit Mach number:

$$M_1 = 2.940$$

The pressure and temperature at station 1 are therefore:

$$\begin{aligned}p_1 &= 3.128 && \text{psia} \\T_1 &= 205.2 && ^\circ\text{R}\end{aligned}$$

The critical temperature, pressure, and maximum friction length at 1 are:

$$\begin{aligned}p_1/p^* &= 0.2255 \\p^* &= 13.867 && \text{psia} \\T_1/T^* &= 0.4397 \\T^* &= 466.7 && ^\circ\text{R} \\fL_1/D &= 0.51293\end{aligned}$$

Based on the maximum and actual friction lengths, the maximum friction length at station 2 is:

$$fL_2/D = 0.15793$$

So the exit Mach number is:

$$\begin{aligned}M_2 &= 1.560 \\fL_2/D &= 0.15793\end{aligned}$$

(we used *Solver* to find the correct Mach number to match the friction length)

The critical pressure and temperature ratios at station 2 are:

$$\begin{aligned}p_2/p^* &= 0.5759 \\T_2/T^* &= 0.8071\end{aligned}$$

So the exit temperature and pressure are:

$$\begin{aligned}p_2 &= 7.99 && \text{psia} \\T_2 &= 377 && ^\circ\text{R}\end{aligned}$$

## Problem 13.127

[Difficulty: 3]

**13.127** A converging-diverging nozzle discharges air into an insulated pipe with area  $A = 1 \text{ in}^2$ . At the pipe inlet,  $p = 18.5 \text{ psia}$ ,  $T = 100^\circ\text{F}$ , and  $M = 2.0$ . For shockless flow to a Mach number of unity at the pipe exit, calculate the exit temperature, the net force of the fluid on the pipe, and the entropy change.



**Given:** Air flow in a CD nozzle and insulated duct

**Find:** Temperature at end of duct; Force on duct; Entropy increase

**Solution:**

Basic equations:  $F_s = p_1 \cdot A - p_2 \cdot A + R_x = m_{\text{rate}} \cdot (V_2 - V_1)$        $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{air}} \cdot \ln\left(\frac{p_2}{p_1}\right)$

Given or available data     $T_1 = (100 + 460) \cdot \text{R}$        $p_1 = 18.5 \cdot \text{psi}$        $M_1 = 2$        $M_2 = 1$        $A = 1 \cdot \text{in}^2$   
 $k = 1.4$        $c_p = 0.2399 \cdot \frac{\text{BTU}}{\text{lbm} \cdot \text{R}}$        $R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}}$

Assuming isentropic flow in the nozzle

$$\frac{T_0}{T_1} \cdot \frac{T_2}{T_0} = \frac{1 + \frac{k-1}{2} \cdot M_1^2}{1 + \frac{k-1}{2} \cdot M_2^2} \text{ so } T_2 = T_1 \cdot \frac{1 + \frac{k-1}{2} \cdot M_1^2}{1 + \frac{k-1}{2} \cdot M_2^2}$$

$T_2 = 840 \cdot \text{R}$        $T_2 = 380 \cdot ^\circ\text{F}$

Also  $c_1 = \sqrt{k \cdot R_{\text{air}} \cdot T_1}$      $V_1 = M_1 \cdot c_1$        $V_1 = 2320 \cdot \frac{\text{ft}}{\text{s}}$        $c_2 = \sqrt{k \cdot R_{\text{air}} \cdot T_2}$      $V_2 = M_2 \cdot c_2$        $V_2 = 1421 \cdot \frac{\text{ft}}{\text{s}}$

$$\rho_1 = \frac{p_1}{R_{\text{air}} \cdot T_1} \quad \rho_1 = 0.0892 \cdot \frac{\text{lbm}}{\text{ft}^3} \quad m_{\text{rate}} = \rho_1 \cdot V_1 \cdot A = \rho_2 \cdot V_2 \cdot A_2 \quad \text{so} \quad \rho_2 = \rho_1 \cdot \frac{V_1}{V_2} \quad \rho_2 = 0.146 \cdot \frac{\text{lbm}}{\text{ft}^3}$$

$$m_{\text{rate}} = \rho_1 \cdot V_1 \cdot A \quad m_{\text{rate}} = 1.44 \cdot \frac{\text{lbm}}{\text{s}} \quad p_2 = \rho_2 \cdot R_{\text{air}} \cdot T_2 \quad p_2 = 45.3 \cdot \text{psi}$$

Hence  $R_x = (p_2 - p_1) \cdot A + m_{\text{rate}} \cdot (V_2 - V_1)$        $R_x = -13.3 \cdot \text{lbf}$     (Force is to the right)

Finally  $\Delta s = c_p \cdot \ln\left(\frac{T_2}{T_1}\right) - R_{\text{air}} \cdot \ln\left(\frac{p_2}{p_1}\right)$        $\Delta s = 0.0359 \cdot \frac{\text{BTU}}{\text{lbm} \cdot \text{R}}$

(Note: Using Fanno line relations, at  $M_1 = 2$        $\frac{T_1}{T_{\text{crit}}} = \frac{T_1}{T_2} = 0.6667$        $T_2 = \frac{T_1}{0.667}$        $T_2 = 840 \cdot \text{R}$

$$\frac{p_1}{p_{\text{crit}}} = \frac{p_1}{p_2} = 0.4083 \quad p_2 = \frac{p_1}{0.4083} \quad p_2 = 45.3 \cdot \text{psi} \quad \text{Check!)$$

# Problem 13.128

[Difficulty: 3]

**13.128** Air is drawn from the atmosphere (20°C and 101 kPa) through a converging nozzle into a long insulated 20-mm-diameter tube of constant area. Flow in the nozzle is isentropic. The pressure at the inlet to the constant-area tube is  $p_1 = 99.4$  kPa. Evaluate the mass flow rate through the tube. Calculate  $T^*$  and  $p^*$  for the isentropic process. Calculate  $T^*$  and  $p^*$  for flow leaving the constant-area tube. Show the corresponding static and stagnation state points on a  $Ts$  diagram.

Solution:

Basic equations:  $p = \rho RT$        $\dot{m} = \rho VA$   
 Computing equations:  $\frac{T_0}{T} = 1 + \frac{\gamma-1}{2} M^2$        $\frac{p_0}{p} = \left(\frac{T_0}{T}\right)^{\frac{\gamma}{\gamma-1}}$

Assumptions: (1) steady flow (2) ideal gas  
 (3) uniform flow at a section  
 (4) isentropic flow in nozzle, adiabatic flow in tube.

Since flow in nozzle is isentropic,  $T_{01} = T_0$  and  $p_{01} = p_0$

$$T_1 = \frac{T_{01}}{1 + \frac{\gamma-1}{2} M_1^2} = \frac{293 \text{ K}}{1 + 0.2(0.15)^2} = 291.7 \text{ K}; \quad M_1 = \left\{ \frac{2}{\gamma-1} \left[ \frac{p_0}{p_1} \right]^{\frac{\gamma-1}{\gamma}} - 1 \right\}^{1/2} = 0.151$$

$$V_1 = M_1 c_1 = M_1 \left( \sqrt{\gamma R T_1} \right)^{1/2} = 0.151 \left[ 1.4 \times 287 \frac{\text{N}}{\text{kg} \cdot \text{K}} \times 291.7 \text{ K} \right]^{1/2} = 51.7 \text{ m/s}$$

$$\rho_1 = \frac{p_1}{RT_1} = \frac{99.4 \times 10^3 \frac{\text{N}}{\text{m}^2}}{287 \text{ N} \cdot \text{m} / \text{kg} \cdot \text{K} \times 291.7 \text{ K}} = 1.187 \text{ kg/m}^3$$

$$\dot{m} = \rho_1 V_1 A_1 = 1.187 \frac{\text{kg}}{\text{m}^3} \times 51.7 \frac{\text{m}}{\text{s}} \times \frac{\pi}{4} (0.020 \text{ m})^2 = 0.0193 \text{ kg/s}$$


b) For isentropic flow,  $\frac{T_0}{T^*} = 1 + \frac{\gamma-1}{2} = 1.20$        $\therefore T^* = \frac{T_0}{1.20} = \frac{293 \text{ K}}{1.20} = 244 \text{ K}$   
 $\frac{p_0}{p^*} = \left( \frac{T_0}{T^*} \right)^{\frac{\gamma}{\gamma-1}} = 1.20^{\frac{1.4}{0.4}} = 11.2$        $\therefore p^* = \frac{101 \text{ kPa}}{11.2} = 9.02 \text{ kPa (abs)}$

c) For Fanno line flow  $T_0 = T_0^*$        $\therefore T^* = T_{0, \text{Fanno}} = 244 \text{ K}$

At  $T^*$ ,  $M=1$ ,  $\therefore V=c = \left( \sqrt{\gamma R T^*} \right)^{1/2} = \left[ 1.4 \times 287 \frac{\text{N}}{\text{kg} \cdot \text{K}} \times 244 \text{ K} \right]^{1/2} = 313 \text{ m/s}$

From continuity  $\rho_1 V_1 = \rho^* V^* \therefore \rho^* = \frac{V_1}{V^*} \rho_1 = \frac{51.4}{313} \times 1.187 \frac{\text{kg}}{\text{m}^3} = 0.1949 \text{ kg/m}^3$

$$p^* = \rho^* R T^* = 0.1949 \frac{\text{kg}}{\text{m}^3} \times 287 \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 244 \text{ K} = 13.6 \text{ kPa (abs)}$$



\* Fanno-Line Flow Functions (Appendix E.2)

For  $M_1 = 0.151$ , Eq. 12.18d gives  $f/p^* = 7.238$

$$\therefore p^* = 13.7 \text{ kPa} \checkmark$$

# Problem 13.129


[Difficulty: 4]

**13.129** Air flows through a converging nozzle and then a length of insulated duct. The air is supplied from a tank where the temperature is constant at 59°F and the pressure is variable. The outlet end of the duct exhausts to atmosphere. When the exit flow is just choked, pressure measurements show the duct inlet pressure and Mach number are 53.2 psia and 0.30. Determine the pressure in the tank and the temperature, stagnation pressure, and mass flow rate of the outlet flow, if the tube diameter is 0.249 in. Show on a  $Ts$  diagram the effect of raising the tank pressure to 100 psia. Sketch the pressure distribution versus distance along the channel for this new flow condition.

Solution: Assume conditions in tank are stagnation properties; flow is isentropic in nozzle, Fanno flow in duct.

Basic equations:  $T_0 = T(1 + \frac{k-1}{2} M^2) = \text{const}$  (energy)

$$p_0 = p(1 + \frac{k-1}{2} M^2)^{\frac{k}{k-1}} \text{ (isentropic)}$$



Assume steady, 1-D compressible flow, with constant stagnation temperature,  $T_0 = 15^\circ\text{C}$  (59°F)

$$T_0 = (460 + 59)^\circ\text{R} = 519^\circ\text{R}$$

$$p_{0t} = p_1 (1 + \frac{k-1}{2} M_1^2)^{\frac{k}{k-1}} = 53.2 \text{ psia} (1 + 0.2(0.3)^2)^{3.5} = 56.6 \text{ psia}$$

At exit plane,  $M_2 = 1$

$$T_2 = \frac{T_0}{(1 + \frac{k-1}{2} M_2^2)} = \frac{519^\circ\text{R}}{1 + 0.2(1)^2} = 433^\circ\text{R}$$

$$p_{02} = p_2 (1 + \frac{k-1}{2} M_2^2)^{\frac{k}{k-1}} = 14.7 \text{ psia} (1 + 0.2(1)^2)^{3.5} = 27.8 \text{ psia}$$

At exit plane,  $V = V^* = C^* = \sqrt{kRT^*} = 1020 \text{ ft/s}$


$$\rho_2 = \frac{p_2}{RT_2} = \frac{14.7 \text{ lbf}}{\text{in}^2} \times \frac{1 \text{ lbm} \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lbf}} \times \frac{1}{433^\circ\text{R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.0917 \text{ lbm/ft}^3$$

$$\dot{m} = \rho_2 V_2 A = 0.0917 \frac{\text{lbm}}{\text{ft}^3} \times 1020 \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} (0.249 \text{ ft})^2 = 0.0316 \text{ lbm/s}$$

When  $p_t$  is increased, density and mass flow rate increase. Flow will shift to a new Fanno line as shown dashed in the  $Ts$  diagram above.

$T_0$  is fixed, so  $T^*$  remains fixed.

{ Since  $\rho$  and  $\dot{m}$  increase,  $p_2' > p_2 = p_{\text{atm}}$ . The plot of  $p$  vs.  $x$  is as shown.



## Problem 13.130

[Difficulty: 4]

**13.130** A constant-area duct is fed by a converging-only nozzle. The nozzle receives air from a large chamber at  $p_1 = 600$  kPa and  $T_1 = 550$  K. The duct has a friction length of 5.3, and it is choked at the exit. What is the pressure at the end of the duct? If 80 percent of the duct is removed, and the conditions at station 1 and the friction factor remain constant, what is the new exit pressure and Mach number? Sketch both of these processes on a  $Ts$  diagram.

**Given:** Air traveling through converging nozzle and constant-area duct with friction; choked flow at duct exit.

**Find:** Pressure at end of duct; exit conditions if 80% of duct were removed

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\k &= 1.4 \\p_1 &= 600 && \text{kPa} \\T_1 &= 550 && \text{K}\end{aligned}$$

Equations and Computations:

Station 1 is a stagnation state, station 2 is between the nozzle and friction duct, and station 3 is at the duct exit.

For part (a) we know:

$$\begin{aligned}fL_{2-3}/D &= 5.3 \\M_3 &= 1\end{aligned}$$

Therefore, we can make the following statements:

$$\begin{aligned}fL_3/D &= 0 \\fL_2/D &= 5.300\end{aligned}$$

So the Mach number at the duct entrance is:

$$\begin{aligned}M_2 &= 0.300 \\fL_2/D &= 5.300\end{aligned}$$

(we used *Solver* to find the correct Mach number to match the friction length)

The pressure at station 2 can be found from the Mach number and stagnation state:

$$\begin{aligned}p_1/p_2 &= 1.0644 \\p_2 &= 563.69 && \text{kPa}\end{aligned}$$

Since state 3 is the critical state, we can find the pressure at state 3:

$$\begin{aligned}p_2/p^* &= 3.6193 \\p^* &= 155.75 && \text{kPa} \\p_3 &= 155.7 && \text{kPa}\end{aligned}$$

For part (a) we know that if we remove 80% of the duct:

$$\begin{aligned}fL_{2-3}/D &= 1.06 \\M_2 &= 0.300 \\fL_2/D &= 5.300 \\p_2 &= 563.69 && \text{kPa}\end{aligned}$$

Since we know state 2 and the friction length of the duct, we can find state 3:

$$fL_3/D = 4.240$$

So the Mach number at the duct exit is:

$$M_3 = 0.326$$
$$fL_2/D = 4.240$$

(we used *Solver* to find the correct Mach number to match the friction length)

To find the exit pressure:

$$p_2/p^* = 3.6193$$
$$p^* = 155.75 \text{ kPa}$$


At state 3 the pressure ratio is:

$$p_3/p^* = 3.3299$$

So the pressure is:

$$p_3 = 519 \text{ kPa}$$

These processes are plotted in the  $Ts$  diagram below:



### Problem 13.131

[Difficulty: 4]

**13.131** We wish to build a supersonic wind tunnel using an insulated nozzle and constant-area duct assembly. Shock-free operation is desired, with  $M_1 = 2.1$  at the test section inlet and  $M_2 = 1.1$  at the test section outlet. Stagnation conditions are  $T_0 = 295$  K and  $p_0 = 101$  kPa (abs). Calculate the outlet pressure and temperature and the entropy change through the test section.

Solution: Consider steady, 1-D, comp. flow, ideal gas.

Computing equations:  $T_0 = T(1 + \frac{k-1}{2} M^2)$ ;  $p_0 = p(1 + \frac{k-1}{2} M^2)^{k/(k-1)}$  ( $s = \text{const}$ )

$$T ds = dh - v dp \quad \rho VA = \text{constant}$$

Assumptions: (1) Isentropic flow in nozzle  
(2) Insulated, so  $T_0 = \text{constant}$

$$\text{Then } T_2 = \frac{T_0}{1 + \frac{k-1}{2} M_2^2} = \frac{295 \text{ K}}{1 + 0.2(1.1)^2} = 238 \text{ K}$$

From continuity,  $\rho_1 V_1 = \rho_2 V_2$ , since  $A_1 = A_2$ . But  $V = Mc = M\sqrt{kRT}$  and  $\rho = p/RT$ , so

$$\frac{p_1}{RT_1} M_1 \sqrt{kRT_1} = \frac{p_2}{RT_2} M_2 \sqrt{kRT_2} \quad ; \quad \frac{p_1}{\sqrt{T_1}} M_1 = \frac{p_2}{\sqrt{T_2}} M_2 \quad ; \quad p_2 = p_1 \frac{M_1 \sqrt{T_2}}{M_2 \sqrt{T_1}}$$

From isentropic relations,


$$T_1 = \frac{T_0}{1 + \frac{k-1}{2} M_1^2} = \frac{295 \text{ K}}{1 + 0.2(2.1)^2} = 157 \text{ K} \quad ; \quad p_1 = \frac{p_0}{(1 + \frac{k-1}{2} M_1^2)^{k/(k-1)}} = \frac{101 \text{ kPa}}{(1.88)^{3.5}} = 11.1 \text{ kPa}$$

$$\text{Thus } p_2 = \frac{2.1}{1.1} \sqrt{\frac{238 \text{ K}}{157 \text{ K}}} 11.1 \text{ kPa} = 26.1 \text{ kPa (abs)}$$

$$ds = \frac{dh}{T} - \frac{v dp}{T} = C_p \frac{dT}{T} - \frac{RT dp}{p T} = C_p \frac{dT}{T} - R \frac{dp}{p}$$

$$\Delta s = C_p \ln \frac{T_2}{T_1} - R \ln \frac{p_2}{p_1} = 1004 \frac{\text{J}}{\text{kg} \cdot \text{K}} \ln \left( \frac{238}{157} \right) - 287 \frac{\text{J}}{\text{kg} \cdot \text{K}} \ln \left( \frac{26.1}{11.1} \right) = 172 \text{ J/kg} \cdot \text{K}$$

The  $T_0$  diagram is



\* Fanno-Line Flow Functions (Appendix E.2):

For  $M_1 = 2.1$ , Eq. 12.18d gives  $p_1/p^* = 0.380$ , so  $p_2 = 26.1$  kPa (abs)  
 $M_2 = 1.1$   $p_2/p^* = 0.894$

# Problem 13.132

[Difficulty: 3]

**13.132** Consider adiabatic flow of air in a constant-area pipe with friction. At one section of the pipe,  $p_0 = 100$  psia,  $T_0 = 500^\circ\text{R}$ , and  $M = 0.70$ . If the cross-sectional area is  $1\text{ ft}^2$  and the Mach number at the exit is  $M_2 = 1$ , find the friction force exerted on the fluid by the pipe.

Solution:

Basic equations:  $F_{s,x} = P_1 A - P_2 A - F_f = \dot{m}(V_2 - V_1)$   $\dot{m} = \rho V A$

Computing equations:  $T_0/T = 1 + \frac{\gamma-1}{2} M^2$   $P_0/P = [1 + \frac{\gamma-1}{2} M^2]^{\frac{\gamma}{\gamma-1}}$

- Assumptions: (1) steady flow (4)  $F_{s,x} = 0$   
 (2) adiabatic flow,  $T_0 = \text{const}$  (5) ideal gas  
 (3) uniform flow at a section

$$P_0/P = [1 + \frac{\gamma-1}{2} M^2]^{\frac{\gamma}{\gamma-1}} \quad P_1 = \frac{P_0}{[1 + \frac{\gamma-1}{2} M^2]^{\frac{\gamma}{\gamma-1}}} = \frac{100 \text{ psia}}{[1 + 0.2(0.70)^2]^{\frac{1.4}{0.4}}} = 72.1 \text{ psia}$$

$$T_0/T = 1 + \frac{\gamma-1}{2} M^2 \quad T_1 = \frac{T_0}{1 + \frac{\gamma-1}{2} M^2} = \frac{500^\circ\text{R}}{1 + 0.2(0.70)^2} = 455^\circ\text{R}$$

$$\rho_1 = \frac{P_1}{RT_1} = 72.1 \frac{\text{lb}}{\text{in}^2} \cdot \frac{\text{in}^2}{53.3 \text{ ft} \cdot \text{lb}} \cdot \frac{1}{455^\circ\text{R}} \cdot \frac{144 \text{ in}^2}{\text{ft}^2} = 0.428 \text{ lbm/ft}^3$$

$$V_1 = M_1 C_1 = M_1 (\sqrt{\gamma RT_1})^{1/2} = 0.70 (1.4 \cdot 53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lbm} \cdot \text{R}} \cdot 455^\circ\text{R} \cdot 32.2 \frac{\text{lbm}}{\text{slug}} \cdot \frac{\text{slug} \cdot \text{ft}^2}{\text{lb} \cdot \text{s}^2})^{1/2} = 732 \text{ ft/s}$$

$$\dot{m} = \rho_1 V_1 A = 0.428 \frac{\text{lbm}}{\text{ft}^3} \cdot 732 \frac{\text{ft}}{\text{s}} \cdot 1.0 \text{ ft}^2 = 313 \text{ lbm/s}$$

$$T_0/T = 1 + \frac{\gamma-1}{2} M^2 \quad T_0 = T_0 \quad T_2 = \frac{T_0}{1 + \frac{\gamma-1}{2} M_2^2} = \frac{500^\circ\text{R}}{1 + 0.2(1.0)^2} = 417^\circ\text{R}$$

$$V_2 = M_2 C_2 = M_2 (\sqrt{\gamma RT_2})^{1/2} = 1.0 (1.4 \cdot 53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lbm} \cdot \text{R}} \cdot 417^\circ\text{R} \cdot 32.2 \frac{\text{lbm}}{\text{slug}} \cdot \frac{\text{slug} \cdot \text{ft}^2}{\text{lb} \cdot \text{s}^2})^{1/2} = 1000 \text{ ft/s}$$

$$\dot{m} = \rho_2 V_2 A = \rho_2 V_2 A \quad \rho_2 = \frac{\dot{m}}{V_2 A} = \frac{313}{1000} = 0.313 \text{ lbm/ft}^3$$

$$P_2 = \rho_2 RT_2 = 0.313 \frac{\text{lbm}}{\text{ft}^3} \cdot 53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lbm} \cdot \text{R}} \cdot 417^\circ\text{R} \cdot \frac{\text{ft}^2}{144 \text{ in}^2} = 48.3 \text{ psia}$$

Solving the momentum equation for  $F_f$


$$F_f = (P_1 - P_2) A - \dot{m}(V_2 - V_1)$$

$$= (72.1 - 48.3) \frac{\text{lb}}{\text{in}^2} \cdot 1 \text{ ft}^2 \cdot \frac{144 \text{ in}^2}{\text{ft}^2} - 313 \frac{\text{lbm}}{\text{s}} (1000 - 732) \frac{\text{ft}}{\text{s}} \cdot \frac{\text{slug}}{32.2 \text{ lbm}} \cdot \frac{\text{lb} \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$$

$$F_f = 822 \text{ lbf}$$

$F_f$

$F_f$  is the force on the control volume from the surroundings. Consequently,  $F_f$  is the force on the fluid from the pipe:  $F_f$  opposes the friction.



### \* Fanno-Line Flow Functions

From Appendix E.2 with  $M_1 = 0.70$ ,

$$P_1/P^* = 1.493 (12.186) \quad \therefore P^* = P_2 = 48.3 \text{ psia}$$

$$V_1/V^* = 0.732 (12.186) \quad \therefore V^* = V_2 = 1000 \text{ ft/s}$$

## Problem 13.133

[Difficulty: 2]

**13.133** For the conditions of Problem 13.122, find the length,  $L$ , of commercial steel pipe of 2 in. diameter between sections ① and ②.



**Given:** Air flow in a converging nozzle and insulated duct

**Find:** Length of pipe

**Solution:**

Basic equations: Fanno-line flow equations, and friction factor

Given or available data

$$T_0 = (250 + 460) \cdot R \quad p_0 = 145 \cdot \text{psi} \quad p_1 = 125 \cdot \text{psi} \quad T_2 = (150 + 460) \cdot R$$

$$D = 2 \cdot \text{in} \quad k = 1.4 \quad c_p = 0.2399 \cdot \frac{\text{BTU}}{\text{lbm} \cdot R} \quad R_{\text{air}} = 53.33 \cdot \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot R}$$

From isentropic relations

$$M_1 = \left[ \frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_1} \right)^{\frac{k-1}{k}} - 1 \right] \right]^{\frac{1}{2}} \quad M_1 = 0.465$$

$$\frac{T_0}{T_1} = 1 + \frac{k-1}{2} \cdot M_1^2 \quad \text{so} \quad T_1 = \frac{T_0}{\left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)} \quad T_1 = 681 \cdot R \quad T_1 = 221 \cdot ^\circ F$$

Then for Fanno-line flow

$$\frac{f_{\text{ave}} \cdot L_{\text{max}1}}{D_h} = \frac{1 - M_1^2}{k \cdot M_1^2} + \frac{k+1}{2 \cdot k} \cdot \ln \left[ \frac{(k+1) \cdot M_1^2}{2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)} \right] = 1.3923$$

$$\frac{p_1}{p_{\text{crit}}} = \frac{p_1}{p_2} = \frac{1}{M_1} \cdot \left( \frac{\frac{k+1}{2}}{1 + \frac{k-1}{2} \cdot M_1^2} \right)^{\frac{1}{2}} = 2.3044 \quad \frac{T_1}{T_{\text{crit}}} = \frac{\frac{k+1}{2}}{1 + \frac{k-1}{2} \cdot M_1^2} = 1.150 \quad T_{\text{crit}} = \frac{T_1}{1.150}$$

$$p_{\text{crit}} = \frac{p_1}{2.3044} \quad p_{\text{crit}} = 54.2 \cdot \text{psi} \quad T_{\text{crit}} = 592 \cdot R \quad T_{\text{crit}} = 132 \cdot ^\circ F$$

Also, for

$$\frac{T_2}{T_{\text{crit}}} = 1.031 \quad \frac{T_2}{T_{\text{crit}}} = \frac{\frac{k+1}{2}}{1 + \frac{k-1}{2} \cdot M_2^2} \quad \text{leads to} \quad M_2 = \sqrt{\frac{2}{k-1} \cdot \left( \frac{k+1}{2} \cdot \frac{T_{\text{crit}}}{T_2} - 1 \right)} \quad M_2 = 0.906$$

Then

$$\frac{f_{\text{ave}} \cdot L_{\text{max}2}}{D_h} = \frac{1 - M_2^2}{k \cdot M_2^2} + \frac{k+1}{2 \cdot k} \cdot \ln \left[ \frac{(k+1) \cdot M_2^2}{2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_2^2 \right)} \right] = 0.01271$$

Also

$$\rho_1 = \frac{p_1}{R_{\text{air}} \cdot T_1} \quad \rho_1 = 0.496 \cdot \frac{\text{lbm}}{\text{ft}^3} \quad V_1 = M_1 \cdot \sqrt{k \cdot R_{\text{air}} \cdot T_1} \quad V_1 = 595 \cdot \frac{\text{ft}}{\text{s}}$$

For air at  $T_1 = 221 \cdot ^\circ\text{F}$ , from Table A.9 (approximately)  $\mu = 4.48 \times 10^{-7} \cdot \frac{\text{lb} \cdot \text{s}}{\text{ft}^2}$  so  $\text{Re}_1 = \frac{\rho_1 \cdot V_1 \cdot D}{\mu}$

For commercial steel pipe (Table 8.1)  $e = 0.00015 \cdot \text{ft}$   $\frac{e}{D} = 9 \times 10^{-4}$  and  $\text{Re}_1 = 3.41 \times 10^6$

Hence at this Reynolds number and roughness (Eq. 8.37)  $f = 0.01924$

Combining results  $L_{12} = \frac{D}{f} \cdot \left( \frac{f_{\text{ave}} \cdot L_{\text{max}2}}{D_h} - \frac{f_{\text{ave}} \cdot L_{\text{max}1}}{D_h} \right) = \frac{2}{12} \cdot \text{ft} \cdot 0.01924 \cdot (1.3923 - 0.01271) \quad L_{12} = 12.0 \cdot \text{ft}$

These calculations are a LOT easier using the *Excel* Add-ins!

### Problem 13.134

[Difficulty: 2]

**13.134** Consider the laboratory Fanno-line flow channel of Problem 13.123. Assume laboratory conditions are 22.5°C and 760 mm of mercury (uncorrected). The manometer reading at a pressure tap at the end of the converging nozzle is -11.8 mm of mercury (gage). Calculate the Mach number at this location. Determine the duct length required to attain choked flow. Calculate the temperature and stagnation pressure at the choked state in the constant-area duct.

Solution: \* Compressible flow functions to be used

- Assumptions: (1) steady flow (5)  $\Delta z = 0$   
 (2) isentropic flow in nozzle (6) ideal gas, air  
 (3) adiabatic " in duct (7) uniform flow at a section  
 (4)  $\dot{W}_{\text{shear}} = 0$

$$\frac{p_1}{p_0} = \frac{p_1}{p_{\text{atm}}} = \frac{\rho g h_1}{\rho g \Delta h_{\text{atm}}} = \frac{(760 - 11.8) \text{ mm}}{760 \text{ mm}} = 0.9845$$

From App. E.1 (Eq. 11.17a)  $M_1 = 0.150$   $M_1$

$$p_1 = \rho_{\text{Hg}} g h_1 = (13.5) 1000 \frac{\text{kg}}{\text{m}^3} \times 9.81 \frac{\text{m}}{\text{s}^2} \times 0.748 \text{ m} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 99.1 \text{ kPa (abs)}$$

From App. E.1 (Eq. 11.17b),  $T_1/T_0 = 0.9555 \quad \therefore T_1 = 294 \text{ K}$

From App. E.2, with  $M_1 = 0.150$

$$p_1/p^* = 7.287, \quad T_1/T^* = 1.195, \quad \frac{f L_{\text{max}}}{D} = 27.93$$

$$p_2 = p^* = 13.60 \text{ and } p_{02} = 0.5283 p_2 = 25.7 \text{ kPa}, \quad T^* = T_2 = 247 \text{ K}$$
  $p_2, T_2$

$$f = f(Re), \quad Re = \frac{\rho V D}{\mu}$$

$$\rho_1 = \frac{p_1}{RT_1} = \frac{99.1 \times 10^3 \text{ N/m}^2}{287 \text{ N} \cdot \text{m} / \text{kg} \cdot \text{K}} \times \frac{1}{294 \text{ K}} = 1.17 \text{ kg/m}^3$$

$$V_1 = M_1 c_1 = M_1 (kRT_1)^{1/2} = 0.149 (1.4 \times 287 \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 294 \text{ K} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2})^{1/2} = 51.2 \text{ m/s}$$

From Table A.10 @  $T_1 = 21^\circ \text{C}$ ,  $\mu = 1.82 \times 10^{-5} \text{ N} \cdot \text{s} / \text{m}^2$


$$Re_1 = \frac{\rho_1 V_1 D}{\mu} = \frac{1.17 \frac{\text{kg}}{\text{m}^3} \times 51.2 \frac{\text{m}}{\text{s}} \times 7.16 \times 10^{-3} \text{ m}}{1.82 \times 10^{-5} \frac{\text{N} \cdot \text{s}}{\text{m}^2}} = 2.36 \times 10^4$$

$$Re_1 = 2.36 \times 10^4$$

From Fig. 8.13, friction factor  $f = 0.0245$

$$\therefore L_{12} = 27.93 \frac{D}{f} = 27.93 \times 7.16 \times 10^{-3} \text{ m} \times \frac{1}{0.0245}$$

$$L_{12} = 8.2 \text{ m}$$



## Problem 13.135

[Difficulty: 3]

**13.135** A 2 ft  $\times$  2 ft duct is 40 ft long. Air enters at  $M_1 = 3.0$  and leaves at  $M_2 = 1.7$ , with  $T_2 = 500^\circ\text{R}$  and  $p_2 = 110$  psia. Find the static and stagnation conditions at the entrance. What is the friction factor for the duct?

**Given:** Air traveling through a square duct

**Find:** Entrance static and stagnation conditions; friction factor

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft}\cdot\text{lbf}/\text{lbm}\cdot^\circ\text{R} \\k &= 1.4 \\s &= 2 && \text{ft} \\L &= 40 && \text{ft} \\M_1 &= 3 \\M_2 &= 1.7 \\T_2 &= 500 && ^\circ\text{R} \\p_2 &= 110 && \text{psia}\end{aligned}$$

Equations and Computations:

From the entrance Mach number we can calculate:

$$\begin{aligned}p_{01}/p_1 &= 36.7327 \\T_{01}/T_1 &= 2.8000 \\p_1/p^* &= 0.2182 \\T_1/T^* &= 0.4286 \\fL_1/D &= 0.52216\end{aligned}$$

From the exit Mach number we can calculate:

$$\begin{aligned}p_2/p^* &= 0.5130 \\T_2/T^* &= 0.7605 \\fL_2/D &= 0.20780\end{aligned}$$

Since we know static conditions at 2, we can find the critical pressure and temperature:

$$\begin{aligned}p^* &= 214.4 && \text{psia} \\T^* &= 657.5 && ^\circ\text{R}\end{aligned}$$

Therefore, the static conditions at the duct entrance are:

$$\begin{aligned}p_1 &= 46.8 && \text{psia} \\T_1 &= 282 && ^\circ\text{R}\end{aligned}$$

and from the isentropic relations we can find stagnation conditions:

$$\begin{aligned}p_{01} &= 1719 && \text{psia} \\T_{01} &= 789 && ^\circ\text{R}\end{aligned}$$

To find the friction factor of the duct, first we need to friction length:

$$fL_{1-2}/D = 0.31436$$

The area and perimeter of the duct are:

$$\begin{aligned}A &= 4.0 && \text{ft}^2 \\P &= 8.0 && \text{ft}\end{aligned}$$

Therefore the hydraulic diameter of the duct is:

$$D_H = 2.0 \text{ ft}$$

From the hydraulic diameter, length, and friction length, the friction factor is:

$$f = 0.01572$$

## Problem 13.136

[Difficulty: 3]

**13.136** Air flows in a 3-in. (nominal) i.d. pipe that is 10 ft long. The air enters with a Mach number of 0.5 and a temperature of 70°F. What friction factor would cause the flow to be sonic at the exit? If the exit pressure is 14.7 psia and the pipe is made of cast iron, estimate the inlet pressure.

**Given:** Air traveling through a cast iron pipe

**Find:** Friction factor needed for sonic flow at exit; inlet pressure

**Solution:**

The given or available data is:	$R =$	53.33	ft-lbf/lbm-°R
	$k =$	1.4	
	$D =$	3.068	in
	$L =$	10	ft
	$M_1 =$	0.5	
	$T_1 =$	70	°F
	$T_1 =$	530	°R
	$M_2 =$	1	
	$p_2 =$	14.7	psia

Equations and Computations:

From the entrance Mach number we can calculate:

$$\begin{aligned}p_1/p^* &= 2.1381 \\fL_1/D &= 1.06906\end{aligned}$$

From the exit Mach number we can calculate:

$$\begin{aligned}p_2/p^* &= 1.0000 \\fL_2/D &= 0.00000\end{aligned}$$

To find the friction factor of the duct, first we need to friction length:

$$fL_{1-2}/D = 1.06906$$

Based on this, and the pipe length and diameter, the friction factor is:

$$f = 0.0273$$

We can calculate the critical pressure from the exit pressure:

$$p^* = 14.7 \text{ psia}$$

Therefore, the static pressure at the duct entrance is:

$$p_1 = 31.4 \text{ psia}$$

### Problem 13.137

[Difficulty: 3] Part 1/2

13.137 For the conditions of Problem 13.132, determine the duct length. Assume the duct is circular and made from commercial steel. Plot the variations of pressure and Mach number versus distance along the duct.

Solution:

Compressible flow functions to be used in the solution

Assumptions: (1) steady flow (2) adiabatic flow,  $T_0 = \text{const}$  (3) uniform flow at a section (4) ideal gas

For  $M_1 = 0.70$ , from Appendix E.1,  $T_0/T_1 = 1.098$  (11.17b)  $\therefore T_1 = 455^\circ\text{R}$   
 $p_0/p_1 = 1.387$  (11.17a)  $\therefore p_1 = 72.1 \text{ psia}$

For  $M_1 = 0.70$ , from Appendix E.2,  $f L_{\text{max}}/D_h = 0.2081$  (12.117)  $\therefore f^* = 48.3 \text{ psia}$

For  $M_2 = 1.0$ ,  $f L_{\text{max}}/D_h = 0 \therefore f L_{12}/D_h = 0.2081$

$f = f(Re, e/D)$   
 $A = \frac{\pi D^2}{4} \therefore D = \left(\frac{4A}{\pi}\right)^{1/2} = \left[\frac{4}{\pi} \times 1.0 \text{ ft}^2\right]^{1/2} = 1.13 \text{ ft}$

For commercial steel from Table 8.1,  $e = 0.00015 \text{ ft} \therefore \frac{e}{D} = 0.00013$

$\rho = \frac{p_1}{RT_1} = \frac{72.1 \text{ lbf}}{\text{in}^2} \times \frac{\text{lbm} \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lbf}} \times \frac{1}{455^\circ\text{R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.428 \text{ lbm/ft}^3$

$V_1 = M_1 c_1 = M_1 (kRT_1)^{1/2} = 0.7 \left(1.4 \times 53.3 \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}} \times 455^\circ\text{R} \times \frac{32.2 \text{ lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbf} \cdot \text{s}^2}\right)^{1/2} = 732 \text{ ft/s}$

$T_1 = 455^\circ\text{R} = -5^\circ\text{F} = -20^\circ\text{C} = 253 \text{ K}$

From the Sutherland correlation,  $\mu = \frac{bT^{1/2}}{1+S/T}$  (A.1)

$\mu = 1.458 \times 10^{-6} \frac{\text{lb}}{\text{m} \cdot \text{s}} \times \frac{\text{kg}}{\text{m} \cdot \text{s} \cdot \text{K}^{1/2}} \times \frac{(253 \text{ K})^{1/2}}{1 + 110/253} = 1.62 \times 10^{-5} \frac{\text{kg}}{\text{m} \cdot \text{s}} \times \frac{\text{N} \cdot \text{s}^2}{\text{kg} \cdot \text{m}} = 1.62 \times 10^{-5} \frac{\text{N} \cdot \text{s}}{\text{m}^2}$

$\mu = 1.62 \times 10^{-5} \frac{\text{N} \cdot \text{s}}{\text{m}^2} \times \frac{0.0209 \text{ lbf} \cdot \text{s}}{\text{N} \cdot \text{ft}} \times \frac{\text{ft}^2}{\text{m}^2} = 3.39 \times 10^{-7} \text{ lbf} \cdot \text{s/ft}^2$

$Re = \frac{\rho V_1 D}{\mu} = \frac{0.428 \text{ lbm}}{\text{ft}^3} \times \frac{732 \text{ ft}}{\text{s}} \times \frac{1.13 \text{ ft}}{3.39 \times 10^{-7} \text{ lbf} \cdot \text{s}} \times \frac{\text{ft}^2}{\text{slug}} \times \frac{\text{slug}}{32.2 \text{ lbm}} \times \frac{\text{lbf} \cdot \text{s}^2}{\text{ft} \cdot \text{slug}}$

$Re = 3.24 \times 10^7$

From Fig 8.13, friction factor  $f = 0.0125$

$f \frac{L_{12}}{D} = 0.2081 \therefore L_{12} = \frac{0.2081 D}{f} = \frac{0.2081 \times 1.13 \text{ ft}}{0.0125} = 18.8 \text{ ft} \leftarrow L_{12}$



# Problem 13.138

[Difficulty: 3]

**13.138** Using coordinates  $T/T_0$  and  $(s - s^*)/c_p$ , where  $s^*$  is the entropy at  $M = 1$ , plot the Fanno line starting from the inlet conditions specified in Example 13.8. Proceed to  $M = 1$ .

Solution:

\* Compressible flow functions to be used in the solution  
 Basic equations:  $Tds = dh - vdp$ ,  $P = \rho RT$

$$Tds = dh - vdp = c_p dT - \frac{1}{\rho} dP$$


$$ds = c_p \frac{dT}{T} - \frac{dP}{P}$$

$$s - s^* = s_0 - s_0^* = c_p \int_{T_0}^{T_0^*} \frac{dT}{T} - R \int_{P_0}^{P_0^*} \frac{dP}{P} = c_p \ln \frac{T_0}{T_0^*} - R \ln \frac{P_0}{P_0^*} = -(c_p - c_v) \ln \frac{P_0}{P_0^*}$$

$$\frac{s - s^*}{c_p} = - \frac{(c_p - c_v)}{c_p} \ln \frac{P_0}{P_0^*} = - \frac{(k-1)}{k} \ln \frac{P_0}{P_0^*} = - \frac{0.4}{1.4} \ln \frac{P_0}{P_0^*} = -0.286 \ln \frac{P_0}{P_0^*}$$

For a given value of  $M$ ,  $T/T_0$  is found from Appendix E.1 (11.17b)  
 $P_0/P_0^*$  " " " " E.2 (12.18e)

M	$T/T_0$	$P_0/P_0^*$	$(s - s^*)/c_p$
0.19	0.993	3.112	-0.325
0.30	0.982	2.035	-0.203
0.40	0.969	1.590	-0.133
0.50	0.952	1.340	-0.084
0.60	0.933	1.188	-0.049
0.70	0.911	1.094	-0.026
0.80	0.887	1.038	-0.011
0.90	0.861	1.009	-0.003
1.00	0.833	1.000	0.000



# Problem 13.139

[Difficulty: 3]




**13.139** Consider the flow described in Example 13.8. Using the flow functions for Fanno-line flow of an ideal gas, plot static pressure, temperature, and Mach number versus  $L/D$  measured from the tube inlet; continue until the choked state is reached.

Solution:

= Compressible flow functions to be used in the solution  
 Assumptions: (1) steady flow (4) uniform flow at a section  
 (2) isentropic flow in nozzle (5) ideal gas  
 (3)  $\dot{q} = 0$  in duct

From the solution of Example 13.8 we know that  
 $M_1 = 0.190$ ,  $T_1 = 294 \text{ K}$ ,  $P_1 = 98.8 \text{ kPa}$ ,  $P_{0,1} = 101 \text{ kPa}$ ,  $\bar{f} = 0.0235$   
 To determine  $P(x)$ ,  $T(x)$ ,  $M(x)$ , use Appendix E.2

M	(fL/D) <sub>M</sub>	Δ(fL/D)	x/D	T/T*	T(K)	P/P*	P(kPa)
0.19	16.38	0	0	1.191	294	5.745	98
0.30	5.30	11.08	469	1.179	291	3.619	62
0.40	2.31	14.07	596	1.163	287	2.696	46
0.50	1.07	15.31	649	1.143	282	2.138	37
0.60	0.49	15.88	673	1.119	276	1.763	30
0.70	0.21	16.17	685	1.093	270	1.493	26
0.80	0.07	16.30	691	1.064	263	1.289	22
0.90	0.01	16.36	693	1.033	255	1.129	19
1.00	0.00	16.38	694	1.000	247	1.000	17



# Problem 13.140

[Difficulty: 3]

**13.140** Using coordinates  $T/T^*$  and  $(s-s^*)/c_p$ , where  $s^*$  is the entropy at  $M = 1$ , plot the Fanno line for air flow for  $0.1 < M < 3.0$ .

Solution:

\* Compressible flow functions to be used in the solution.

Basic equation:  $T ds = dh - v dp$ ,  $P = \rho RT$

$$T ds = dh - v dp = c_p dT - \frac{1}{\rho} dP$$


$$ds = c_p \frac{dT}{T} - \frac{dP}{\rho T}$$

$$s - s^* = s_0 - s_0^* = c_p \int_{T_0^*}^{T_0} \frac{dT}{T} - R \int_{P_0^*}^{P_0} \frac{dP}{P} = c_p \ln \frac{T_0}{T_0^*} - R \ln \frac{P_0}{P_0^*} = -(c_p - c_v) \ln \frac{P_0}{P_0^*}$$

$$\frac{s - s^*}{c_p} = -\frac{(c_p - c_v)}{c_p} \ln \frac{P_0}{P_0^*} = -\left(\frac{\gamma - 1}{\gamma}\right) \ln \frac{P_0}{P_0^*} = -\frac{(0.4)}{1.4} \ln \frac{P_0}{P_0^*} = -0.286 \ln \frac{P_0}{P_0^*}$$


For a given value of  $M$ , use Appendix E.2 to determine  $T/T^*$  (12.18a) -  $P_0/P_0^*$  (12.18e).

M	T/T*	P <sub>0</sub> /P <sub>0</sub> *	(s-s*)/c <sub>p</sub>
0.10	1.198	5.822	-0.504
0.14	1.195	4.182	-0.409
0.20	1.190	2.964	-0.311
0.30	1.179	2.035	-0.203
0.40	1.163	1.590	-0.133
0.50	1.143	1.340	-0.084
0.60	1.119	1.188	-0.049
0.70	1.093	1.094	-0.026
0.80	1.064	1.038	-0.011
0.90	1.033	1.009	-0.003
1.00	1.000	1.000	0.000
1.20	0.932	1.030	-0.009
1.40	0.862	1.115	-0.031
1.60	0.794	1.250	-0.064
1.80	0.728	1.439	-0.104
2.00	0.667	1.688	-0.150
2.20	0.610	2.005	-0.199
2.40	0.558	2.403	-0.251
2.60	0.510	2.896	-0.304
2.80	0.467	3.500	-0.358
3.00	0.429	4.235	-0.413



13.141 Air flows through a 40 ft length of insulated constant-area duct with  $D = 2.12$  ft. The relative roughness is  $e/D = 0.002$ . At the duct inlet,  $T_1 = 100^\circ\text{F}$  and  $p_1 = 17.0$  psia. At a location downstream,  $p_2 = 14.7$  psia, and the flow is subsonic. Is sufficient information given to solve for  $M_1$  and  $M_2$ ? Prove your answer graphically. Find the mass flow rate in the duct and  $T_2$ .

Solution:



(a) It is possible to solve for  $M_1$  and  $M_2$ . There is a different Fanno line for each different flow rate (or  $M_1$ ).  
 • need to find the value of  $M_1$  that gives the pressure drop  $p_1 - p_2$  over the length  $L_{12}$ .

(b) Procedure for trial and error solution is to assume  $M_1$  and calculate  $p_2$ .

Use Fanno-line flow functions of Appendix E-2.

Assume  $M_1$ ,

- determine  $p^*$ , Appendix E (12.18d)
- $\bar{f}L/D = \frac{1}{f} (Re)$  (12.17)

- calculate  $\bar{f}L/D_1$  and  $\bar{f}L/D_2 = \bar{f}L/D_1 - \bar{f}L/D$
- knowing  $\bar{f}L/D_2$ , iterate (12.17) to determine  $M_2$
- determine  $p_2$  from  $M_2$  (12.18d) and check vs known  $p_2$

Repeat with another assumed value of  $M_1$ .

Additional computing equations:

$$V_1 = M_1 c_1 = M_1 (RT_1)^{1/2} = M_1 (1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot ^\circ\text{R}} \times 560^\circ\text{R} \times 32.2 \frac{\text{lb}_m \cdot \text{slug}}{\text{ft} \cdot \text{s}^2})^{1/2} = 1160 M_1$$

$$p_1 = \frac{p_1}{RT_1} = \frac{17 \text{ lb}_f}{\text{in}^2} \times 144 \frac{\text{in}^2}{\text{ft}^2} \times \frac{\text{lb}_m \cdot ^\circ\text{R}}{53.3 \text{ ft} \cdot \text{lb}_f \times 560^\circ\text{R}} \times \frac{1}{32.2 \text{ lb}_m} = 2.55 \times 10^{-3} \frac{\text{slug}}{\text{ft}^3}$$

From Table A.9,  $\mu = 3.97 \times 10^{-7} \text{ lb}_f \cdot \text{s} / \text{ft}^2$

$$Re = \frac{\rho_1 V_1 D}{\mu} = \frac{2.55 \times 10^{-3} \frac{\text{slug}}{\text{ft}^3} \times 1160 M_1 \frac{\text{ft}}{\text{s}} \times 2.12 \text{ ft}}{3.97 \times 10^{-7} \frac{\text{lb}_f \cdot \text{s}}{\text{ft}^2}} \times \frac{\text{ft}^2}{\text{ft} \cdot \text{slug}} = 7.45 \times 10^6 M_1$$

For  $M_1 = 0.4$ ,  $Re = 3.0 \times 10^6$ . With  $e/D = 0.002$ , Fig. 8.13 gives  $f = 0.023$ .

Assume  $f$  is constant.

# Problem 13.141

[Difficulty: 4] Part 2/2

$M_1$	$T_1/T^*$	$P_1/P^*$	$P^*$ (psia)	$(fL_m/D)_1$	$V_1$ (ft/s)	$Re(10^6)$	$f$	$fL_{12}/D$	$(fL_m/D)_2$	$M_2$	$T_2/T^*$	$P_2/P^*$	$P_2$ (psia)	
0.400	1.163	2.6958	6.30606	0.186	2.31	464	2.98	0.0230	0.434	1.875	0.427	1.158	2.520	15.9
0.450	1.153	2.3865	7.12347	0.234	1.57	522	3.35	0.0230	0.434	1.132	0.493	1.144	2.170	15.5
0.500	1.143	2.1381	7.95102	0.286	1.07	580	3.73	0.0230	0.434	0.635	0.568	1.127	1.869	14.9
0.510	1.141	2.0942	8.118	0.297	0.99	592	3.80	0.023	0.434	0.556	0.585	1.123	1.812	14.7

Iterate to determine  $M_2$  for known  $M_1$

$M_1$	$(fL_m/D)_2$	$(M_2)_{guess}$	$(fL_m/D)_2$
0.400	1.875	0.427	0.211
0.450	1.132	0.493	0.278
0.500	0.635	0.568	0.364
0.510	0.556	0.585	0.384

$$M_1 = 0.510 \quad \frac{T_1}{T^*} = 1.141, \quad \frac{T_2}{T^*} = 1.123, \quad \therefore \frac{T_2}{T_1} = 0.984$$

$$T_2 = 551^\circ R$$

$$\dot{m} = \rho \cdot V \cdot A = 2.55 \times 10^{-3} \frac{\text{slug}}{\text{ft}^3} \times 592 \frac{\text{ft}}{\text{s}} \times \frac{\pi}{4} (2.12)^2 \text{ft}^2 = 5.33 \text{ slug/s}$$

## Problem 13.142

[Difficulty: 2]

**13.142** Air brought into a tube through a converging-diverging nozzle initially has stagnation temperature and pressure of 550 K and 1.35 MPa (abs). Flow in the nozzle is isentropic; flow in the tube is adiabatic. At the junction between the nozzle and tube the pressure is 15 kPa. The tube is 1.5 m long and 2.5 cm in diameter. If the outlet Mach number is unity, find the average friction factor over the tube length. Calculate the change in pressure between the tube inlet and discharge.

**Given:** Air flow through a CD nozzle and tube.

**Find:** Average friction factor; Pressure drop in tube

**Solution:**

Assumptions: 1) Isentropic flow in nozzle 2) Adiabatic flow in tube 3) Ideal gas 4) Uniform flow

Given or available data:  $k = 1.40$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $p_1 = 15 \cdot \text{kPa}$       where State 1 is the nozzle exit  
 $p_0 = 1.35 \cdot \text{MPa}$        $T_0 = 550 \cdot \text{K}$        $D = 2.5 \cdot \text{cm}$        $L = 1.5 \cdot \text{m}$

From isentropic relations  $M_1 = \left[ \frac{2}{k-1} \cdot \left[ \left( \frac{p_0}{p_1} \right)^{\frac{k-1}{k}} - 1 \right] \right]^{\frac{1}{2}}$        $M_1 = 3.617$

Then for Fanno-line flow (for choking at the exit)

$$\frac{f_{\text{ave}} \cdot L_{\text{max}}}{D_h} = \frac{1 - M_1^2}{k \cdot M_1^2} + \frac{k+1}{2 \cdot k} \cdot \ln \left[ \frac{(k+1) \cdot M_1^2}{2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)} \right] = 0.599$$

Hence  $f_{\text{ave}} = \frac{D}{L} \cdot \left[ \frac{1 - M_1^2}{k \cdot M_1^2} + \frac{k+1}{2 \cdot k} \cdot \ln \left[ \frac{(k+1) \cdot M_1^2}{2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)} \right] \right]$        $f_{\text{ave}} = 0.0100$

$$\frac{p_1}{p_{\text{crit}}} = \frac{p_1}{p_2} = \frac{1}{M_1} \cdot \left( \frac{\frac{k+1}{2}}{1 + \frac{k-1}{2} \cdot M_1^2} \right)^{\frac{1}{2}} = 0.159$$

$$p_2 = \frac{p_1}{0.159} \quad p_2 = 94.2 \cdot \text{kPa}$$

$$\Delta p = p_1 - p_2 = \left[ \frac{1}{M_1} \cdot \left( \frac{\frac{k+1}{2}}{1 + \frac{k-1}{2} \cdot M_1^2} \right)^{\frac{1}{2}} \right] \cdot p_1 - p_1$$

$$\Delta p = -79.2 \cdot \text{kPa}$$

These calculations are a LOT easier using the Excel Add-ins!

## Problem 13.143

[Difficulty: 3]

**13.143** For the conditions of Problem 13.127, determine the duct length. Assume the duct is circular and made from commercial steel. Plot the variations of pressure and Mach number versus distance along the duct.



**Given:** Air flow in a CD nozzle and insulated duct

**Find:** Duct length; Plot of  $M$  and  $p$

**Solution:**

Basic equations: Fanno-line flow equations, and friction factor

Given or available data  $T_1 = (100 + 460) \cdot R$        $p_1 = 18.5 \text{ psi}$        $M_1 = 2$        $M_2 = 1$        $A = 1 \cdot \text{in}^2$   
 $k = 1.4$        $c_p = 0.2399 \frac{\text{BTU}}{\text{lbm} \cdot R}$        $R_{\text{air}} = 53.33 \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot R}$

Then for Fanno-line flow at  $M_1 = 2$

$$\frac{p_1}{p_{\text{crit}}} = \frac{p_1}{p_2} = \frac{1}{M_1} \cdot \left( \frac{\frac{k+1}{2}}{1 + \frac{k-1}{2} \cdot M_1^2} \right)^{\frac{1}{2}} = 0.4082 \quad \frac{f_{\text{ave}} \cdot L_{\text{max}1}}{D_h} = \frac{1 - M_1^2}{k \cdot M_1^2} + \frac{k+1}{2 \cdot k} \cdot \ln \left[ \frac{(k+1) \cdot M_1^2}{2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_1^2 \right)} \right] = 0.305$$

so  $p_{\text{crit}} = \frac{p_1}{0.4082} \quad p_{\text{crit}} = 45.3 \cdot \text{psi}$

and at  $M_2 = 1$   $\frac{f_{\text{ave}} \cdot L_{\text{max}2}}{D_h} = \frac{1 - M_2^2}{k \cdot M_2^2} + \frac{k+1}{2 \cdot k} \cdot \ln \left[ \frac{(k+1) \cdot M_2^2}{2 \cdot \left( 1 + \frac{k-1}{2} \cdot M_2^2 \right)} \right] = 0$

Also  $\rho_1 = \frac{p_1}{R_{\text{air}} \cdot T} \rho_1 = 0.089 \cdot \frac{\text{lbm}}{\text{ft}^3} \quad V_1 = M_1 \cdot \sqrt{k \cdot R_{\text{air}} \cdot T_1} \quad V_1 = 2320 \cdot \frac{\text{ft}}{\text{s}} \quad D = \sqrt{\frac{4 \cdot A}{\pi}} \quad D = 1.13 \cdot \text{in}$

For air at  $T_1 = 100 \cdot ^\circ\text{F}$ , from Table A.9  $\mu = 3.96 \times 10^{-7} \cdot \frac{\text{lbf} \cdot \text{s}}{\text{ft}^2}$  so  $Re_1 = \frac{\rho_1 \cdot V_1 \cdot D}{\mu}$

For commercial steel pipe (Table 8.1)  $e = 0.00015 \cdot \text{ft} \quad \frac{e}{D} = 1.595 \times 10^{-3}$  and  $Re_1 = 1.53 \times 10^6$


Hence at this Reynolds number and roughness (Eq. 8.37)  $f = .02222$

Combining results  $L_{12} = \frac{D}{f} \cdot \left( \frac{f_{\text{ave}} \cdot L_{\text{max}2}}{D_h} - \frac{f_{\text{ave}} \cdot L_{\text{max}1}}{D_h} \right) = \frac{1.13}{.02222} \cdot \text{ft} \cdot (0.3050 - 0) \quad L_{12} = 1.29 \cdot \text{ft} \quad L_{12} = 15.5 \cdot \text{in}$

These calculations are a LOT easier using the *Excel* Add-ins! The  $M$  and  $p$  plots are shown in the *Excel* spreadsheet on the next page.

The given or available data is:  $f = 0.0222$   
 $p^* = 45.3 \text{ kPa}$   
 $D = 1.13 \text{ in}$

$M$	$fL_{max}/D$	$\Delta fL_{max}/D$	$x \text{ (in)}$	$p/p^*$	$p \text{ (psi)}$
2.00	0.305	0.000	0	0.408	18.49
1.95	0.290	0.015	0.8	0.423	19.18
1.90	0.274	0.031	1.6	0.439	19.90
1.85	0.258	0.047	2.4	0.456	20.67
1.80	0.242	0.063	3.2	0.474	21.48
1.75	0.225	0.080	4.1	0.493	22.33
1.70	0.208	0.097	4.9	0.513	23.24
1.65	0.190	0.115	5.8	0.534	24.20
1.60	0.172	0.133	6.7	0.557	25.22
1.55	0.154	0.151	7.7	0.581	26.31
1.50	0.136	0.169	8.6	0.606	27.47
1.45	0.118	0.187	9.5	0.634	28.71
1.40	0.100	0.205	10.4	0.663	30.04
1.35	0.082	0.223	11.3	0.695	31.47
1.30	0.065	0.240	12.2	0.728	33.00
1.25	0.049	0.256	13.0	0.765	34.65
1.20	0.034	0.271	13.8	0.804	36.44
1.15	0.021	0.284	14.5	0.847	38.37
1.10	0.010	0.295	15.0	0.894	40.48
1.05	0.003	0.302	15.4	0.944	42.78
1.00	0.000	0.305	15.5	1.000	45.30



# Problem 13.144

[Difficulty: 3]

13.144 A smooth constant-area duct assembly ( $D = 150$  mm) is to be fed by a converging-diverging nozzle from a tank containing air at 295 K and 1.0 MPa (abs). Shock-free operation is desired. The Mach number at the duct inlet is to be 2.1 and the Mach number at the duct outlet is to be 1.4. The entire assembly will be insulated. Find (a) the pressure required at the duct outlet, (b) the duct length required, and (c) the change in specific entropy. Show the static and stagnation state points and the process path on a  $Ts$  diagram.

Solution: • Compressible flow functions to be used in solution.

Assumptions: (1) steady flow (2) uniform flow at a section (3) isentropic flow in nozzle, adiabatic flow in duct (4) ideal gas

(a) From App. E.1 for  $M_1 = 2.1$   $T/T_0 = 0.5314$   $\therefore T_1 = 156.7$  K  
 $p/p_0 = 0.1094$   $\therefore p_1 = 109.4$  kPa  
 $V_1 = M_1 c_1 = M_1 (\gamma R T)^{1/2} = 2.1 \left[ 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 156.7 \text{ K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \right]^{1/2} = 527$  m/s

For App. E.2 for  $M = 2.1$   $p_0/p^* = 1.837$   $\therefore p_0^* = 544.4$  kPa  
 $\rho/\rho^* = 0.3802$   $\therefore \rho^* = 287.7$  kg/m<sup>3</sup>

for  $M_2 = 1.4$   $p_2/p^* = 0.6632$   $\therefore p_2 = 190.8$  kPa  $\leftarrow p_2$   
 $\rho_2/\rho_0^* = 1.115$   $\therefore \rho_0^* = 320.8$  kPa  $\leftarrow$

(b) From App. E.2 for  $M_1 = 2.1$   $f L_{max}/D_h = 0.3339$   
 $M_2 = 1.4$   $f L_{max}/D_h = 0.09974$   
 $\therefore f L_{12}/D_h = 0.3339 - 0.09974 = 0.2342$

To obtain  $L_{12}$ , we need  $f$ ;  $f = f(Re)$ ;  $Re = \frac{\rho V D_h}{\mu}$  (use conditions at ①)

To obtain  $\mu$  at 156.7 K, use Sutherland correlation (Appendix A)


$$\mu = \frac{b T^{1/2}}{1 + S/T} = 1.458 \times 10^{-6} \frac{\text{kg}}{\text{m}\cdot\text{s}} \times (156.7 \text{ K})^{1/2} \times \frac{1}{1 + \frac{110.4}{156.7}} = 1.071 \times 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2}$$

$$Re = \frac{\rho_1 V_1 D_h}{\mu} = \frac{\rho_1 V_1}{RT_1 \mu} = \frac{109.4 \times 10^3 \frac{\text{N}}{\text{m}^2} \times 527 \frac{\text{m}}{\text{s}} \times (0.15 \text{ m})}{287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 156.7 \text{ K} \times 1.071 \times 10^{-5} \frac{\text{N}\cdot\text{s}}{\text{m}^2}} = 1.80 \times 10^7$$

$Re = 1.80 \times 10^7$  For smooth pipe from Fig 8.13 friction factor,  $f \approx 0.007$

$$\therefore 0.007 L_{12}/D_h = 0.2342$$

$$L_{12} = \frac{0.2342}{0.007} D_h = 5.02 \text{ m} \leftarrow L_{12}$$



From the Tds eq.

$$s_2 - s_1 = s_0 - s_0 = c_p \ln \frac{T_0}{T_1} - R \ln \frac{p_0}{p_1}$$

$$s_2 - s_1 = -287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \ln \frac{320.8}{1000} = 0.326 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} \leftarrow s_2 - s_1$$

## Problem 13.145

[Difficulty: 4]

**\*13.145** Natural gas is to be pumped through 60 mi of 30-in.-diameter pipe with an average friction factor of 0.025. The temperature of the gas remains constant at 140°F, and the mass flow rate is 40 lbm/s. The downstream pressure of the gas is 150 kPa. Estimate the required entrance pressure, and the power needed to pump the gas through the pipe.

**Given:** Natural gas pumped through a pipe

**Find:** Required entrance pressure and power needed to pump gas through the pipe

**Solution:**

The given or available data is:

$R =$	96.32	ft-lbf/lbm-°R
$c_p =$	0.5231	Btu/lbm-°R
$k =$	1.31	
$D =$	30	in
$L =$	60	mi
$f =$	0.025	
$T_1 =$	140	°F
$T_1 =$	600	°R
$T_2 =$	600	°R
$m =$	40	lbm/s
$p_2 =$	150	kPa

Equations and Computations:

At the exit of the pipe we can calculate the density:

$$p_2 = 21.756 \text{ psia}$$
$$\rho_2 = 0.05421 \text{ lbm/ft}^3$$

The pipe area is:

$$A = 4.909 \text{ ft}^2$$

Therefore, the flow velocity is:

$$V_2 = 150.32 \text{ ft/s}$$

The local sound speed is:

$$c_2 = 1561.3 \text{ ft/s}$$

So the Mach number is:

$$M_2 = 0.09628$$

From the exit Mach number we can calculate:

$$T_{02}/T_2 = 1.0014$$
$$fL_2/D = 76.94219$$

Given the length, diameter, and friction factor, we know:

$$fL_{1-2}/D = 3168.0$$

Therefore:

$$fL_1/D = 3244.9$$

So from this information we can calculate the entrance Mach number:

$$M_1 = 0.01532$$
$$fL_1/D = 3244.9$$

(We use *Solver* to calculate the Mach number based on the friction length)

The entrance sound speed is the same as that at the exit:

$$c_1 = 1561.3 \text{ ft/s}$$

So the flow velocity is:

$$V_1 = 23.91 \text{ ft/s}$$

We can calculate the pressure ratio from the velocity ratio:

$$p_1 = 136.8 \text{ psi}$$

From the entrance Mach number we can calculate:

$$T_{01}/T_1 = 1.0000$$

So the entrance and exit stagnation temperatures are:

$$T_{01} = 600.02 \text{ }^\circ\text{R}$$
$$T_{02} = 600.86 \text{ }^\circ\text{R}$$

The work needed to pump the gas through the pipeline would be:

$$W = 17.5810 \text{ Btu/s}$$
$$W = 24.9 \text{ hp}$$

## Problem 13.146

[Difficulty: 5]

**\*13.146** Air flows through a 1-in.-diameter, 10-ft-long tube. The friction factor of the tube is 0.03. If the entrance conditions are 15 psia and 530°R, calculate the mass flow rate for (a) incompressible flow (using the methods of Chapter 8), (b) adiabatic (Fanno) flow, and (c) isothermal flow. Assume for parts (b) and (c) that the exit pressure is 14.7 psia.

**Given:** Air flowing through a tube

**Find:** Mass flow rate assuming incompressible, adiabatic, and isothermal flow

**Solution:**

The given or available data is:

$$\begin{aligned}
 R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\
 k &= 1.4 \\
 \nu &= 0.000163 && \text{ft}^2/\text{s} \\
 D &= 1 && \text{in} \\
 L &= 10 && \text{ft} \\
 f &= 0.03 \\
 p_1 &= 15 && \text{psia} \\
 T_1 &= 530 && ^\circ\text{R} \\
 p_2 &= 14.7 && \text{psia}
 \end{aligned}$$

Equations and Computations:

The tube flow area is:

$$A = 0.005454 \text{ ft}^2$$

For incompressible flow, the density is:

$$\rho_1 = 0.07642 \text{ lbf/ft}^3$$

The velocity of the flow is:

$$V_1 = 100.56 \text{ ft/s}$$

The mass flow rate is:

$$m_{\text{incomp}} = 0.0419 \text{ lbf/s}$$

For Fanno flow, the duct friction length is:

$$fL_{1-2}/D = 3.600$$

and the pressure ratio across the duct is:

$$p_1/p_2 = 1.0204$$

To solve this problem, we have to guess  $M_1$ . Based on this and the friction length, we can determine a corresponding  $M_2$ . The pressure ratios for  $M_1$  and  $M_2$  will be used to check the validity of our guess.

$M_1$	$M_2$	$fL_1/D$	$fL_2/D$	$fL_{1-2}/D$	$p_1/p_2$
0.0800	0.0813	106.72	103.12	3.600	1.0167
0.0900	0.0919	83.50	79.90	3.600	1.0213
0.1000	0.1027	66.92	63.32	3.600	1.0266
0.1100	0.1136	54.69	51.09	3.600	1.0326

Here we used Solver to match the friction length. When both the friction length and the pressure ratios match the constraints set above, we have our solution.

Therefore our entrance and exit Mach numbers are:

$$M_1 = 0.0900$$

$$M_2 = 0.0919$$

The density at 1 was already determined. The sound speed at 1 is:

$$c_1 = 1128.8 \text{ ft/s}$$

so the velocity at 1 is:

$$V_1 = 101.59 \text{ ft/s}$$

and the mass flow rate is:

$$m_{\text{Fanno}} = 0.0423 \text{ lbm/s}$$

To solve this problem for isothermal flow, we perform a calculation similar to that done above for the Fanno flow. The only difference is that we use the friction length relation and pressure ratio relation for isothermal flow:

$M_1$	$M_2$	$fL_1/D$	$fL_2/D$	$fL_{1-2}/D$	$p_1/p_2$
0.0800	0.0813	105.89216	102.29216	3.600	1.0167
0.0900	0.0919	82.70400	79.10400	3.600	1.0213
0.1000	0.1027	66.15987	62.55987	3.600	1.0266
0.1100	0.1136	53.95380	50.35380	3.600	1.0326

Here we used Solver to match the friction length. When both the friction length and the pressure ratios match the constraints set above, we have our solution.

Therefore our entrance and exit Mach numbers are:

$$M_1 = 0.0900$$

$$M_2 = 0.0919$$

The density and sound speed at 1 were already determined. The velocity at 1 is:

$$V_1 = 101.59 \text{ ft/s}$$

and the mass flow rate is:

$$m_{\text{Isothermal}} = 0.0423 \text{ lbm/s}$$

Note that in this situation, since the Mach number was low, the assumption of incompressible flow was a good one. Also, since the Fanno flow solution shows a very small change in Mach number, the temperature does not change much, and so the isothermal solution gives almost identical results.

## Problem 13.147

[Difficulty: 4]

**\*13.147** A 15-m umbilical line for an astronaut on a space walk is held at a constant temperature of 20°C. Oxygen is supplied to the astronaut at a rate of 10 L/min, through a 1-cm tube in the umbilical line with an average friction factor of 0.01. If the oxygen pressure at the downstream end is 30 kPa, what does the upstream pressure need to be? How much power is needed to feed the oxygen to the astronaut?

**Given:** Oxygen supplied to astronaut via umbilical

**Find:** Required entrance pressure and power needed to pump gas through the tube

**Solution:**

The given or available data is:

$R =$	259.8	J/kg-K
$c_p =$	909.4	J/kg-K
$k =$	1.4	
$Q =$	10	L/min
$D =$	1	cm
$L =$	15	m
$f =$	0.01	
$T_1 =$	20	°C
$T_1 =$	293	K
$T_2 =$	293	K
$p_2 =$	30	kPa

Equations and Computations:

At the exit of the pipe we can calculate the density:

$$\rho_2 = 0.39411 \text{ kg/m}^3$$

so the mass flow rate is:

$$m = 6.568\text{E-}05 \text{ kg/s}$$

The pipe area is:

$$A = 7.854\text{E-}05 \text{ m}^2$$

Therefore, the flow velocity is:

$$V_2 = 2.12 \text{ m/s}$$

The local sound speed is:

$$c_2 = 326.5 \text{ m/s}$$

So the Mach number is:

$$M_2 = 0.006500$$

From the exit Mach number we can calculate:

$$T_{02}/T_2 = 1.0000$$

$$fL_2/D = 16893.2$$

Given the length, diameter, and friction factor, we know:

$$fL_{1-2}/D = 15.0$$

Therefore:

$$fL_1/D = 16908.2$$

So from this information we can calculate the entrance Mach number:

$$M_1 = 0.006498$$
$$fL_1/D = 16908.2$$

(We use *Solver* to calculate the Mach number based on the friction length)

The entrance sound speed is the same as that at the exit:

$$c_1 = 326.5 \text{ m/s}$$

So the flow velocity is:

$$V_1 = 2.12 \text{ m/s}$$

We can calculate the pressure ratio from the velocity ratio:

$$p_1 = 30.0 \text{ kPa}$$

From the entrance Mach number we can calculate:

$$T_{01}/T_1 = 1.0000$$

So the entrance and exit stagnation temperatures are:

$$T_{01} = 293.00 \text{ K}$$

$$T_{02} = 293.00 \text{ K}$$

The work needed to pump the gas through the pipeline would be:

$$W = 1.3073\text{E-}07 \text{ W}$$

$$W = 0.1307 \text{ microwatts}$$

## Problem 13.148

[Difficulty: 5]

**\*13.148** Air enters a 15-cm-diameter pipe at 15°C, 1.5 MPa, and 60 m/s. The average friction factor is 0.013. Flow is isothermal. Calculate the local Mach number and the distance from the entrance of the channel, at the point where the pressure reaches 500 kPa.

**Given:** Isothermal air flow in a pipe

**Find:** Mach number and location at which pressure is 500 kPa

**Solution:**

Basic equations:	$m_{\text{rate}} = \rho \cdot V \cdot A$	$p = \rho \cdot R \cdot T$	$\frac{f \cdot L_{\text{max}}}{D} = \frac{1 - k \cdot M^2}{k \cdot M^2} + \ln(k \cdot M^2)$
Given or available data	$T_1 = (15 + 273) \cdot \text{K}$	$p_1 = 1.5 \cdot \text{MPa}$	$V_1 = 60 \cdot \frac{\text{m}}{\text{s}} \quad f = 0.013 \quad p_2 = 500 \cdot \text{kPa}$
	$D = 15 \cdot \text{cm}$	$k = 1.4$	$R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$
From continuity	$\rho_1 \cdot V_1 = \rho_2 \cdot V_2$	or	$\frac{p_1}{T_1} \cdot V_1 = \frac{p_2}{T_2} \cdot V_2$
Since	$T_1 = T_2$	and	$V = M \cdot c = M \cdot \sqrt{k \cdot R \cdot T} \quad M_2 = M_1 \cdot \frac{p_1}{p_2}$
	$c_1 = \sqrt{k \cdot R \cdot T_1}$	$c_1 = 340 \frac{\text{m}}{\text{s}}$	$M_1 = \frac{V_1}{c_1} \quad M_1 = 0.176$
Then	$M_2 = M_1 \cdot \frac{p_1}{p_2}$	$M_2 = 0.529$	
At $M_1 = 0.176$	$\frac{f \cdot L_{\text{max}1}}{D} = \frac{1 - k \cdot M_1^2}{k \cdot M_1^2} + \ln(k \cdot M_1^2) = 18.819$		
At $M_2 = 0.529$	$\frac{f \cdot L_{\text{max}2}}{D} = \frac{1 - k \cdot M_2^2}{k \cdot M_2^2} + \ln(k \cdot M_2^2) = 0.614$		
Hence	$\frac{f \cdot L_{12}}{D} = \frac{f \cdot L_{\text{max}2}}{D} - \frac{f \cdot L_{\text{max}1}}{D} = 18.819 - 0.614 = 18.2$		
	$L_{12} = 18.2 \cdot \frac{D}{f}$	$L_{12} = 210 \text{ m}$	

## Problem 13.149

[Difficulty: 2]

**\*13.149** In long, constant-area pipelines, as used for natural gas, temperature is constant. Assume gas leaves a pumping station at 350 kPa and 20°C at  $M = 0.10$ . At the section along the pipe where the pressure has dropped to 150 kPa, calculate the Mach number of the flow. Is heat added to or removed from the gas over the length between the pressure taps? Justify your answer: Sketch the process on a  $Ts$  diagram. Indicate (qualitatively)  $T_{01}$ ,  $T_{02}$ , and  $p_{02}$ .

**Given:** Isothermal air flow in a duct

**Find:** Downstream Mach number; Direction of heat transfer; Plot of  $Ts$  diagram

**Solution:**

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$      $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$      $m_{\text{rate}} = \rho \cdot V \cdot A$

Given or available data     $T_1 = (20 + 273) \cdot \text{K}$      $p_1 = 350 \cdot \text{kPa}$      $M_1 = 0.1$      $p_2 = 150 \cdot \text{kPa}$

From continuity     $m_{\text{rate}} = \rho_1 \cdot V_1 \cdot A = \rho_2 \cdot V_2 \cdot A$     so     $\rho_1 \cdot V_1 = \rho_2 \cdot V_2$

Also     $p = \rho \cdot R \cdot T$     and     $M = \frac{V}{c}$     or     $V = M \cdot c$

Hence continuity becomes     $\frac{p_1}{R \cdot T_1} \cdot M_1 \cdot c_1 = \frac{p_2}{R \cdot T_2} \cdot M_2 \cdot c_2$

Since     $T_1 = T_2$      $c_1 = c_2$     so     $p_1 \cdot M_1 = p_2 \cdot M_2$


Hence     $M_2 = \frac{p_1}{p_2} \cdot M_1$      $M_2 = 0.233$

From energy     $\frac{\delta Q}{dm} = \left( h_2 + \frac{V_2^2}{2} \right) - \left( h_1 + \frac{V_1^2}{2} \right) = h_{02} - h_{01} = c_p \cdot (T_{02} - T_{01})$

But at each state     $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$     or     $T_0 = T \cdot \left( 1 + \frac{k-1}{2} \cdot M^2 \right)$

Since  $T = \text{const}$ , but  $M_2 > M_1$ , then  $T_{02} > T_{01}$ , and

$\frac{\delta Q}{dm} > 0$     so energy is ADDED to the system



\*13.150 A clean steel pipe is 950 ft long and 5.25 in. inside diameter. Air at 80°F, 120 psia, and 80 ft/s enters the pipe. Calculate and compare the pressure drops through the pipe for (a) incompressible, (b) isothermal, and (c) adiabatic flows.

Solution:

Basic equations:  $\dot{m} = \rho VA$        $p = \rho RT$

Computing equations:  $p_1 - p_2 = \rho f \frac{L}{D} \frac{V^2}{2}$       ( $\rho = \text{constant}$ )

$f \frac{L_{max}}{D} = \frac{1 - kM^2}{kM^2} + \ln kM^2$       ( $T = \text{constant}$ )

$\frac{f L_{max}}{D} = \frac{1 - M^2}{kM^2} + \frac{k+1}{2k} \ln \left[ \frac{(k+1)M^2}{2(1 + \frac{k-1}{2}M^2)} \right]$       ( $\dot{Q} = 0$ )

$p_1 = \frac{p_1}{RT_1} = 120 \frac{\text{lb}_f}{\text{in}^2} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot \text{R}} \times 540 \text{ R} = 0.600 \text{ lb}_m / \text{ft}^3$

From Table A.9 {at  $T = 80^\circ \text{F}$ }  $\mu = 3.86 \times 10^{-7} \text{ lb}_f \cdot \text{s} / \text{ft}^2$

$Re_1 = \frac{\rho V D}{\mu} = 0.600 \frac{\text{lb}_m}{\text{ft}^3} \times \frac{5.25 \text{ ft}}{12} \times \frac{80 \text{ ft}}{\text{s}} \times \frac{\text{ft}^2}{3.86 \times 10^{-7} \text{ lb}_f \cdot \text{s}} \times \frac{\text{slug}}{32.2 \text{ lb}_m} \times \frac{\text{lb}_f \cdot \text{s}^2}{\text{slug} \cdot \text{ft}}$

$Re_1 = 1.69 \cdot 10^6$

For commercial steel (Table 8.1),  $e = 0.00015 \text{ ft}$ .  $\therefore e/D = 0.00034$

From Fig. 8.13,  $f = 0.0155$

(a) For incompressible flow

$p_1 - p_2 = \rho f \frac{L}{D} \frac{V^2}{2} = 0.60 \frac{\text{lb}_m}{\text{ft}^3} \times 0.0155 \times \frac{950 \times 12}{5.25} \times \frac{(80)^2 \text{ ft}^2}{2 \text{ s}^2} \times \frac{\text{slug}}{32.2 \text{ lb}_m} \times \frac{\text{lb}_f \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \frac{\text{ft}^2}{144 \text{ in}^2}$

$p_1 - p_2 = 13.9 \text{ psia}$        $(p_1 - p_2)_{\rho = c}$

(b) For isothermal flow

$c_1 = (kRT_1)^{1/2} = (1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lb}_m \cdot \text{R}} \times 540 \text{ R} \times 32.2 \frac{\text{lb}_m}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb}_f \cdot \text{s}^2})^{1/2} = 1140 \text{ ft/s}$

$M_1 = \frac{V_1}{c_1} = \frac{80}{1140} = 0.0702$

At state ①  $(f \frac{L_{max}}{D})_1 = \frac{1 - kM_1^2}{kM_1^2} + \ln kM_1^2$   
 $= \frac{1 - 1.4(0.0702)^2}{1.4(0.0702)^2} + \ln [1.4(0.0702)^2]$   
 $f \frac{L_{max}}{D} = 139$

### Problem 13.150

[Difficulty: 4] Part 2/2

$$f \frac{L}{D} = 0.0155 \times \frac{950 \times 12}{5.25} = 33.6$$

$$\therefore f \left( \frac{L_{max}}{D} \right)_2 = 139 - 33.6 = 105 = \frac{1 - k M_2^2}{k M_2^2} + \ln k M_2^2$$

Trial and error solution for  $M_2$

$M_2$	$f \left( \frac{L_{max}}{D} \right)_2$
0.10	66.2
0.08	106
0.081	103
0.0805	105

$$V_2 = M_2 C_2 = M_2 C_1 = 0.0805 \times 1140 \text{ ft/sec} = 91.8 \text{ ft/s}$$

$$P_1 V_1 = P_2 V_2 \quad \text{or} \quad \frac{P_1}{T_1} V_1 = \frac{P_2}{T_2} V_2 \quad \dots (1)$$

Since  $T_2 = T_1$ ,  $P_2 = P_1 \frac{V_1}{V_2} = 120 \text{ psia} \times \frac{80}{91.8} = 105 \text{ psia}$

$$P_1 - P_2 = 15.0 \text{ psia}$$

$$(P_2 - P_1)_{T=c}$$

(c) For adiabatic flow,  $M_1 = 0.0702$

$$f \left( \frac{L_{max}}{D} \right)_1 = \frac{1 - (0.0702)^2}{1.4(0.0702)^2} + \frac{1.4+1}{2(1.4)} \ln \left[ \frac{(2.4)(0.0702)^2}{2(1+0.2(0.0702)^2)} \right] = 139.8$$

$$\therefore f \left( \frac{L_{max}}{D} \right)_2 = 139.8 - 33.6 = 106.2 = \frac{1 - M_2^2}{1.4 M_2^2} + \frac{2.4}{2.8} \ln \left[ \frac{2.4 M_2^2}{2(1+0.2 M_2^2)} \right]$$

Trial and error solution for  $M_2$

$M_2$	$f \left( \frac{L_{max}}{D} \right)_2$
0.085	94.1
0.080	106.7
0.0802	106.2 ✓

For adiabatic flow,  $T_0 = \text{constant}$

$$\therefore \frac{T_2}{T_1} = \frac{1 + \frac{k-1}{2} M_1^2}{1 + \frac{k-1}{2} M_2^2} = \frac{1 + 0.2(0.0702)^2}{1 + 0.2(0.0802)^2} = 1.00$$

$$\therefore V_2 = M_2 C_2 = M_2 C_1 = 0.0802 \times 1140 \text{ ft/sec} = 91.4 \text{ ft/s}$$

From continuity (Eq. 1)

$$P_2 = P_1 \frac{V_1}{V_2} = 120 \text{ psia} \times \frac{80}{91.4} = 105 \text{ psia}$$

$$\therefore P_1 - P_2 = 15.0 \text{ psia}$$

$$(P_2 - P_1)_{a=0}$$

Note:  $P_2$  is essentially the same for isothermal and adiabatic flow; the value is higher than for incompressible flow.

# Problem 13.151

[Difficulty: 2]

\*13.151 Air enters a horizontal channel of constant area at 200°F, 600 psia, and 350 ft/s. Determine the limiting pressure for isothermal flow. Compare with the limiting pressure for frictional adiabatic flow.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$   $\dot{m} = \rho VA$

Computing equation:  $T_0/T = 1 + \frac{\gamma-1}{2} M^2$

Assumptions: (1) steady flow (2) ideal gas  
(3) uniform flow at a section (4)  $\mu = \mu_{shear} = 0$

$$c_1 = (kRT_1)^{1/2} = (1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \times 660 \text{R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbm} \cdot \text{s}^2})^{1/2} = 1260 \text{ ft/s}$$

$$M_1 = \frac{V_1}{c_1} = \frac{350}{1260} = 0.278$$

$$V_2 = M_2 c_2 = M_2 c_1 = \frac{1}{1.4} \times 1260 \text{ ft/s} = 1060 \text{ ft/s}$$

$$p_1 V_1 = p_2 V_2 \quad \text{or} \quad \frac{p_1}{RT_1} V_1 = \frac{p_2}{RT_2} V_2 \quad \dots (1)$$

Since  $T_1 = T_2$ ,  $p_2 = p_1 \frac{V_1}{V_2} = 600 \text{ psia} \times \frac{350}{1060} = 198 \text{ psia} \xrightarrow{p_2/T=c}$

For adiabatic flow,  $T_0 = \text{constant}$  and  $M_2 = 1.0$

$$T_{02} = T_{01} = T_1 (1 + \frac{\gamma-1}{2} M_1^2) = T_2 (1 + \frac{\gamma-1}{2} M_2^2)$$

$$\frac{T_2}{T_1} = \frac{1 + 0.2(0.278)^2}{1 + 0.2} = 0.846$$


$$T_2 = 558^\circ \text{R}$$

$$V_2 = c_2 = (kRT_2)^{1/2} = (1.4 \times 53.3 \times 558 \times 32.2)^{1/2} = 1160 \text{ ft/s}$$

From continuity (Eq. 1)

$$p_2 = p_1 \frac{V_1}{V_2} \frac{T_2}{T_1} = 600 \text{ psia} \times \frac{350}{1160} \times 0.846$$

$$p_2 = 153 \text{ psia} \xrightarrow{p_2/\dot{q}=0}$$



# Problem 13.152

[Difficulty: 5] Part 1/2

\*13.152 Natural gas (molecular mass  $M_m = 18$  and  $k = 1.3$ ) is to be pumped through a 36 in. i.d. pipe connecting two compressor stations 40 miles apart. At the upstream station the pressure is not to exceed 90 psig, and at the downstream station it is to be at least 10 psig. Calculate the maximum allowable rate of flow (ft<sup>3</sup>/day at 70°F and 1 atm) assuming sufficient heat exchange through the pipe to maintain the gas at 70°F.

Solution:

Basic equations:  $\dot{m} = \rho VA$   $P = \rho RT$

Computing equation:  $f \frac{L_{max}}{D} = \frac{1 - kM^2}{kM^2} + \ln kM^2$

Then,  $f \frac{L_{12}}{D} = f \frac{L_{max}}{D} \Big|_1 - f \frac{L_{max}}{D} \Big|_2 = \frac{1 - kM_1^2}{kM_1^2} - \frac{1 - kM_2^2}{kM_2^2} + \ln \frac{M_1^2}{M_2^2}$

Since information on pressures is known, we relate  $P$  and  $M$

From the ideal gas equation of state, for  $T = \text{constant}$

$$\frac{P_1}{P_2} = \frac{\rho_1}{\rho_2}$$

From the continuity equation

$$\frac{A_1}{A_2} = \frac{V_2}{V_1}$$

and for  $T = \text{constant}$ ,

$$\frac{V_2}{V_1} = \frac{M_2}{M_1}$$

Hence  $\frac{P_1}{P_2} = \frac{M_2}{M_1}$  and  $M_2 = \frac{P_1}{P_2} M_1$

Substituting for  $M_2$  into the equation for  $f \frac{L_{12}}{D}$  and rearranging we obtain

$$f \frac{L_{12}}{D} = \frac{1 - (P_2/P_1)^2}{kM_1^2} - \ln \left( \frac{P_1}{P_2} \right)^2$$

Solving this equation for  $M_1$ , then

$$M_1 = \left\{ \frac{1}{k} \left[ \frac{1 - (P_2/P_1)^2}{f \frac{L_{12}}{D} + \ln \left( \frac{P_1}{P_2} \right)^2} \right] \right\}^{1/2}$$

$$\frac{L_{12}}{D} = 40 \text{ mi} \times \frac{5280 \text{ ft}}{\text{mi}} \times \frac{1}{3 \text{ ft}} = 70,400$$

Assume pipe is commercial steel. From Table 8.1,  $e = 0.00015 \text{ ft}$  and hence

$e/D = 0.00005$ . Assume  $Re > 3.0 \times 10^7$ , then  $f = 0.0105$ . Solving for  $M_1$ ,

$$M_1 = \left\{ \frac{1}{1.3} \left[ \frac{1 - \left( \frac{24.7}{104.7} \right)^2}{0.0105(70,400) + \ln \left( \frac{104.7}{24.7} \right)^2} \right] \right\}^{1/2} = 0.0313$$

$$R_{\text{nat gas}} = \frac{R_u}{M} = \frac{1544 \text{ ft} \cdot \text{lb}_f}{\text{lb} \cdot \text{mol} \cdot \text{R}} \cdot \frac{\text{lb} \cdot \text{mol}}{18 \text{ lbm}} = 85.8 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}}$$

$$c_1 = (kRT_1)^{1/2} = \left( 1.3 \times 85.8 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot \text{R}} \cdot 530 \text{ R} \cdot \frac{32.2 \text{ lbm}}{\text{slug}} \cdot \frac{\text{slug} \cdot \text{ft}}{\text{lb}_f \cdot \text{s}^2} \right)^{1/2} = 1380 \text{ ft/s}$$

$$V_1 = M_1 c_1 = 0.0313 \times 1380 \text{ ft/s} = 43.2 \text{ ft/s}$$

$$P_1 = \frac{P_2}{RT_1} = 104.7 \frac{\text{lb}_f}{\text{in}^2} \times \frac{\text{lbm} \cdot \text{R}}{85.8 \text{ ft} \cdot \text{lb}_f} \times \frac{1}{530 \text{ R}} \times 144 \frac{\text{in}^2}{\text{ft}^2} = 0.332 \text{ lbm/ft}^3$$

Check assumption on  $Re$ : from Fig 9.2 (for methane),  $\mu = 1.08 \times 10^{-5} \times 2.09 \times 10^{-2} \text{ lb}_f \cdot \text{s/ft}^2$

$$Re = \frac{\rho V D}{\mu} = 0.332 \frac{\text{lbm}}{\text{ft}^3} \times 43.2 \frac{\text{ft}}{\text{s}} \times 3 \text{ ft} = 2.26 \times 10^7 \frac{\text{ft}^2}{\text{lb}_f \cdot \text{s}} \times \frac{\text{slug}}{32.2 \text{ lbm}} \times \frac{\text{lb}_f \cdot \text{s}^2}{\text{ft} \cdot \text{slug}} = 5.91 \times 10^6$$

42.381 30 SHEETS 3 SQUARE  
42.382 120 SHEETS 3 SQUARE  
42.383 120 SHEETS 3 SQUARE  
42.384 120 SHEETS 3 SQUARE  
42.385 120 SHEETS 3 SQUARE  
42.386 120 SHEETS 3 SQUARE  
42.387 120 SHEETS 3 SQUARE  
42.388 120 SHEETS 3 SQUARE  
42.389 120 SHEETS 3 SQUARE  
42.390 120 SHEETS 3 SQUARE  
42.391 120 SHEETS 3 SQUARE  
42.392 120 SHEETS 3 SQUARE  
42.393 120 SHEETS 3 SQUARE  
42.394 120 SHEETS 3 SQUARE  
42.395 120 SHEETS 3 SQUARE  
42.396 120 SHEETS 3 SQUARE  
42.397 120 SHEETS 3 SQUARE  
42.398 120 SHEETS 3 SQUARE  
42.399 120 SHEETS 3 SQUARE  
42.400 120 SHEETS 3 SQUARE

### Problem 13.152

[Difficulty: 5] Part 2/2


Then  $f = 0.011$  and  $\frac{f_{\text{air}}}{f} = 774$   $M_1 = 0.0205$  and  $V_1 = 42.1 \text{ ft/sec}$

$$\dot{m} = \rho \cdot V_1 \cdot A = 0.322 \frac{\text{lbm}}{\text{ft}^3} \cdot 42.1 \frac{\text{ft}}{\text{sec}} \cdot \pi (3)^2 \text{ft}^2 = 98.8 \text{ lbm/sec}$$

$$P_{\text{atm}} = \frac{P_{\text{atm}}}{RT} = 14.7 \frac{\text{lb}_f}{\text{in}^2} \cdot \frac{\text{lbm} \cdot \text{ft}}{\text{sec}^2} \cdot \frac{1}{53.35} \cdot \frac{144 \text{ in}^2}{\text{ft}^2} = 4.65 \times 10^{-2} \text{ lbm/ft}^3$$

Volume flowrate at atmospheric pressure

$$Q = \frac{\dot{m}}{\rho_{\text{atm}}} = 98.8 \frac{\text{lbm}}{\text{sec}} \cdot \frac{\text{ft}^3}{\text{lbm}} \cdot \frac{3600 \text{ sec}}{\text{hr}} \cdot \frac{24 \text{ hr}}{\text{day}} = 1.84 \times 10^8 \text{ ft}^3/\text{day} \leftarrow Q$$



## Problem 13.153

[Difficulty: 4]

**13.153** Air from a large reservoir at 25 psia and 250°F flows isentropically through a converging nozzle into a frictionless pipe at 24 psia. The flow is heated as it flows along the pipe. Obtain a plot of the  $Ts$  diagram for this flow, until  $M = 1$ . Also plot the pressure and speed distributions from the entrance to the location at which  $M = 1$ .

**Given:** Air flow from converging nozzle into heated pipe

**Find:** Plot  $Ts$  diagram and pressure and speed curves

**Solution:**

The given or available data is:

$$\begin{aligned}
 R &= 53.33 && \text{ft lbf/lbm } ^\circ\text{R} \\
 k &= 1.4 \\
 c_p &= 0.2399 && \text{Btu/lbm } ^\circ\text{R} \\
 &= 187 && \text{ft lbf/lbm } ^\circ\text{R} \\
 T_0 &= 710 && ^\circ\text{R} \\
 p_0 &= 25 && \text{psi} \\
 p_e &= 24 && \text{psi}
 \end{aligned}$$

Equations and Computations:


From  $p_0$  and  $p_e$ , and Eq. 13.7a  
(using built-in function  $IsenMfromp(M,k)$ )  $M_e = 0.242$

Using built-in function  $IsenT(M,k)$   $T_e = 702$   $^\circ\text{R}$



Using  $p_e$ ,  $M_e$ , and function  $Rayp(M,k)$   $p^* = 10.82$  psi

Using  $T_e$ ,  $M_e$ , and function  $RayT(M,k)$   $T^* = 2432$   $^\circ\text{R}$

We can now use Rayleigh-line relations to compute values for a range of Mach numbers:



0.47	0.742	1805	2083	979	1.83	19.8	186.57
0.48	0.759						
0.49	0.775						
0.5	0.790						
0.51	0.805						
0.52	0.820						
0.53	0.834						
0.54	0.847						
0.55	0.860						
0.56	0.872						
0.57	0.884						
0.58	0.896						
0.59	0.906						
0.6	0.917						
0.61	0.927						
0.62	0.936						
0.63	0.945						
0.64	0.953						
0.65	0.961						
0.66	0.968						
0.67	0.975						
0.68	0.981	2387	2396	1629	1.46	15.8	250.96
0.69	0.987	2401	2403	1658	1.44	15.6	252.70
0.7	0.993						
0.71	0.998						
0.72	1.003						
0.73	1.007						
0.74	1.011						
0.75	1.014						
0.76	1.017						
0.77	1.020						
0.78	1.022						
0.79	1.024						
0.8	1.025						
0.81	1.027						
0.82	1.028						
0.83	1.028						
0.84	1.029						
0.85	1.029						
0.86	1.028						
0.87	1.028						
0.88	1.027						
0.89	1.026						
0.9	1.025	2492	2448	2203	1.12	12.2	272.78
0.91	1.023	2488	2446	2226	1.11	12.0	273.13
0.92	1.021	2484	2444	2248	1.10	11.9	273.43
0.93	1.019	2479	2441	2270	1.09	11.7	273.70
0.94	1.017	2474	2439	2292	1.07	11.6	273.92
0.95	1.015	2468	2436	2314	1.06	11.5	274.11
0.96	1.012	2461	2433	2335	1.05	11.3	274.26
0.97	1.009	2455	2429	2356	1.04	11.2	274.38
0.98	1.006	2448	2426	2377	1.02	11.1	274.46
0.99	1.003	2440	2422	2398	1.01	10.9	274.51
1	1.000	2432	2418	2418	1.00	10.8	274.52



## Problem 13.154

[Difficulty: 2]

**13.154** Air enters a constant-area duct with  $M_1 = 3.0$  and  $T_1 = 250$  K. Heat transfer decreases the outlet Mach number to  $M_2 = 1.60$ . Compute the exit static and stagnation temperatures, and find the magnitude and direction of the heat transfer.

**Given:** Air flow through a duct with heat transfer

**Find:** Exit static and stagnation temperatures; magnitude and direction of heat transfer

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\c_p &= 1004 && \text{J/kg-K} \\k &= 1.4 \\M_1 &= 3 \\T_1 &= 250 && \text{K} \\M_2 &= 1.6\end{aligned}$$

Equations and Computations:

We can determine the stagnation temperature at the entrance:

$$T_{01}/T_1 = 2.8000$$

So the entrance stagnation temperature is:

$$T_{01} = 700.00 \quad \text{K}$$

The reference stagnation temperature for Rayleigh flow can be calculated:

$$T_{01}/T_0^* = 0.6540$$

$$T_0^* = 1070.4 \quad \text{K}$$

Since the reference state is the same at stations 1 and 2, state 2 is:

$$T_{02}/T_0^* = 0.8842$$

$$T_{02} = 946 \quad \text{K}$$

$$T_{02}/T_2 = 1.5120$$

$$T_2 = 626 \quad \text{K}$$

The heat transfer is related to the change in stagnation temperature:

$$q_{1-2} = 247 \quad \text{kJ/kg}$$

## Problem 13.155

[Difficulty: 4]

**13.155** Repeat Problem 13.153 except the nozzle is now a converging-diverging nozzle delivering the air to the pipe at 2.5 psia.

**Given:** Air flow from converging-diverging nozzle into heated pipe

**Find:** Plot Ts diagram and pressure and speed curves

**Solution:**

The given or available data is:

$$\begin{aligned}
 R &= 53.33 \text{ ft}\cdot\text{lb}/\text{lbm}\cdot^\circ\text{R} \\
 k &= 1.4 \\
 c_p &= 0.2399 \text{ Btu}/\text{lbm}\cdot^\circ\text{R} \\
 &= 187 \text{ ft}\cdot\text{lb}/\text{lbm}\cdot^\circ\text{R} \\
 T_0 &= 710 \text{ }^\circ\text{R} \\
 p_0 &= 25 \text{ psi} \\
 p_e &= 2.5 \text{ psi}
 \end{aligned}$$

Equations and Computations:

From  $p_0$  and  $p_e$ , and Eq. 13.7a  
(using built-in function  $IsenMfromp(M,k)$ )  $M_e = 2.16$


Using built-in function  $IsenT(M,k)$   $T_e = 368 \text{ }^\circ\text{R}$

Using  $p_e$ ,  $M_e$ , and function  $Rayp(M,k)$   $p^* = 7.83 \text{ psi}$

Using  $T_e$ ,  $M_e$ , and function  $RayT(M,k)$   $T^* = 775 \text{ }^\circ\text{R}$


We can now use Rayleigh-line relations to compute values for a range of Mach numbers:

$M$	$T/T^*$	$T$ ( $^\circ\text{R}$ )	$c$ (ft/s)	$V$ (ft/s)	$p/p^*$	$p$ (psi)	$\Delta s$ (ft·lb/lbm· $^\circ\text{R}$ ) Eq. (12.11b)
2.157	0.475	368	940	2028	0.32	2.5	0.00
2	0.529	410	993	1985	0.36	2.8	13.30
1.99	0.533						
1.98	0.536						
1.97	0.540						
1.96	0.544						
1.95	0.548						
1.94	0.552						
1.93	0.555						
1.92	0.559						
1.91	0.563						
1.9	0.567						
1.89	0.571						
1.88	0.575						
1.87	0.579						
1.86	0.584						
1.85	0.588						
1.84	0.592						
1.83	0.596						
1.82	0.600						
1.81	0.605						
1.8	0.609						
1.79	0.613	475	1069	1913	0.44	3.4	31.06
1.78	0.618	479	1073	1909	0.44	3.5	31.90
1.77	0.622	482	1076	1905	0.45	3.5	32.73
1.76	0.626	485	1080	1901	0.45	3.5	33.57
1.75	0.631	489	1084	1897	0.45	3.6	34.40
1.74	0.635	492	1088	1893	0.46	3.6	35.23
1.73	0.640	496	1092	1889	0.46	3.6	36.06
1.72	0.645	499	1096	1885	0.47	3.7	36.89
1.71	0.649	503	1100	1880	0.47	3.7	37.72




1.7	0.654	507	1104	1876	0.48	3.7	38.54
1.69	0.658	510	1107	1872	0.48	3.8	39.36
1.68	0.663	514	1111	1867	0.48	3.8	40.18
1.67	0.668	517	1115	1863	0.49	3.8	41.00
1.66	0.673	521	1119	1858	0.49	3.9	41.81
1.65	0.677	525	1123	1853	0.50	3.9	42.62
1.64	0.682	529	1127	1849	0.50	3.9	43.43
1.63	0.687	532	1131	1844	0.51	4.0	44.24

1.62	0.692
1.61	0.697
1.6	0.702
1.59	0.707
1.58	0.712
1.57	0.717
1.56	0.722
1.55	0.727
1.54	0.732
1.53	0.737
1.52	0.742
1.51	0.747
1.5	0.753
1.49	0.758
1.48	0.763
1.47	0.768
1.46	0.773
1.45	0.779
1.44	0.784
1.43	0.789



1.42	0.795	616	1217	1728	0.63	4.9	60.18
1.41	0.800	620	1221	1721	0.63	5.0	60.88

1.4	0.805
1.39	0.811
1.38	0.816
1.37	0.822
1.36	0.827
1.35	0.832
1.34	0.838
1.33	0.843
1.32	0.848
1.31	0.854
1.3	0.859
1.29	0.865
1.28	0.870
1.27	0.875
1.26	0.881
1.25	0.886
1.24	0.891
1.23	0.896
1.22	0.902
1.21	0.907



1.2	0.912	706	1303	1564	0.80	6.2	73.21
1.19	0.917	710	1307	1555	0.80	6.3	73.65
1.18	0.922	714	1310	1546	0.81	6.4	74.08
1.17	0.927	718	1314	1537	0.82	6.4	74.50
1.16	0.932	722	1318	1528	0.83	6.5	74.89
1.15	0.937	726	1321	1519	0.84	6.6	75.27
1.14	0.942	730	1324	1510	0.85	6.7	75.63
1.13	0.946	733	1328	1500	0.86	6.7	75.96
1.12	0.951	737	1331	1491	0.87	6.8	76.28
1.11	0.956	741	1334	1481	0.88	6.9	76.58
1.1	0.960	744	1337	1471	0.89	7.0	76.86
1.09	0.965	747	1341	1461	0.90	7.1	77.11
1.08	0.969	751	1344	1451	0.91	7.1	77.34
1.07	0.973	754	1347	1441	0.92	7.2	77.55
1.06	0.978	757	1349	1430	0.93	7.3	77.73
1.05	0.982	761	1352	1420	0.94	7.4	77.88
1.04	0.986	764	1355	1409	0.95	7.5	78.01
1.03	0.989	767	1358	1398	0.97	7.6	78.12
1.02	0.993	769	1360	1387	0.98	7.6	78.19
1.01	0.997	772	1362	1376	0.99	7.7	78.24
1	1.000	775	1365	1365	1.00	7.8	78.25

# Problem 13.156

[Difficulty: 2]

13.156 Consider frictionless flow of air in a constant-area duct. At section ①,  $M_1 = 0.50$ ,  $p_1 = 1.10$  MPa (abs), and  $T_0_1 = 333$  K. Through the effect of heat exchange, the Mach number at section ② is  $M_2 = 0.90$  and the stagnation temperature is  $T_0_2 = 478$  K. Determine the amount of heat exchange per unit mass to or from the fluid between sections ① and ② and the pressure difference,  $p_1 - p_2$ .

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$   $P_1 A - P_2 A = \dot{m}(V_2 - V_1)$

Computing equation:  $T_0/T = 1 + \frac{\gamma-1}{2} M^2$

- Assumptions:
- (1) steady flow
  - (2) frictionless flow
  - (3) uniform flow at a section
  - (4) ideal gas
  - (5)  $F_{2x} = 0$
  - (6)  $\dot{W}_s = \dot{W}_{shear} = 0$
  - (7)  $\dot{Q} = 0$

$$h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2} \quad \frac{\delta Q}{dm} = h_{02} - h_{01} = c_p(T_{02} - T_{01}) = 10 \frac{J}{kg \cdot K} (478 - 333) K = 145 \frac{kJ}{kg}$$

$P_1 A - P_2 A = \dot{m}(V_2 - V_1) = \rho_1 V_1 A (V_2 - V_1)$  and  $P_1 - P_2 = \rho_1 V_1 (V_2 - V_1)$

$T_0/T = 1 + \frac{\gamma-1}{2} M^2 \quad T_1 = \frac{T_{01}}{1 + \frac{\gamma-1}{2} M_1^2} = \frac{333 K}{1 + 0.2(0.50)^2} = 317 K$


$T_2 = \frac{T_{02}}{1 + \frac{\gamma-1}{2} M_2^2} = \frac{478 K}{1 + 0.2(0.90)^2} = 411 K$

$V_1 = M_1 c_1 = M_1 (\gamma R T_1)^{1/2} = 0.50 \left( 1.4 \cdot 287 \frac{N \cdot m}{kg \cdot K} \cdot 317 K \cdot \frac{kg \cdot m}{N \cdot s^2} \right)^{1/2} = 178 \text{ m/s}$

$V_2 = M_2 c_2 = M_2 (\gamma R T_2)^{1/2} = 0.90 \left( 1.4 \cdot 287 \frac{N \cdot m}{kg \cdot K} \cdot 411 K \cdot \frac{kg \cdot m}{N \cdot s^2} \right)^{1/2} = 366 \text{ m/s}$

$\rho_1 = \frac{P_1}{R T_1} = \frac{1.10 \cdot 10^6 \frac{N}{m^2}}{287 \frac{N \cdot m}{kg \cdot K} \cdot 317 K} = 12.1 \frac{kg}{m^3}$

$P_1 - P_2 = \rho_1 V_1 (V_2 - V_1) = 12.1 \frac{kg}{m^3} \cdot 178 \frac{m}{s} \cdot (366 - 178) \frac{m}{s} = 405 \text{ kPa}$



\* Rayleigh-Line Flow Functions  
 From Appendix E.3  
 • for  $M_1 = 0.5$ ,  $P_1/P^* = 1.718$  (12.30a)  
 $\therefore P^* = 619 \text{ kPa}$   
 • for  $M_2 = 0.90$ ,  $P_2/P^* = 1.125$  (12.30a)  
 $\therefore P_2 = 616 \text{ kPa} = P_1 - P_2 = 404 \text{ kPa}$

# Problem 13.157

[Difficulty: 2]

**13.157** Air flows without friction through a short duct of constant area. At the duct entrance,  $M_1 = 0.30$ ,  $T_1 = 50^\circ\text{C}$ , and  $\rho_1 = 2.16\text{ kg/m}^3$ . As a result of heating, the Mach number and pressure at the tube outlet are  $M_2 = 0.60$  and  $p_2 = 150\text{ kPa}$ . Determine the heat addition per unit mass and the entropy change for the process.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta q}{dm} = h_2 + \frac{V_2^2}{2}$   $T ds = dh - v dp$

Computing equations:  $T_0/T = 1 + \frac{\gamma-1}{2} M^2$

- Assumptions: (1) steady flow (4) ideal gas  
 (2) frictionless flow (5)  $\dot{W}_s = \dot{W}_{\text{heat}} = 0$   
 (3) uniform flow at a section (6)  $\dot{q}_g = 0$

$$V_1 = M_1 c_1 = M_1 (\gamma R T_1)^{1/2} = 0.30 \sqrt{1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 323\text{K} \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2}}^{1/2} = 108\text{ m/sec}$$

$$p_1 = \rho_1 R T_1 = 2.16 \frac{\text{kg}}{\text{m}^3} \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 323\text{K} = 200\text{ kPa}$$

$$p_1 V_1 = p_2 V_2 \quad p_2 = \frac{p_1}{RT_2} \quad V_2 = M_2 c_2 = M_2 (\gamma R T_2)^{1/2}$$

$$p_1 V_1 = \frac{p_2}{RT_2} M_2 (\gamma R T_2)^{1/2} = p_2 M_2 \left(\frac{\gamma}{RT_2}\right)^{1/2} \quad \text{Solving for } T_2.$$

$$T_2 = \frac{p_1 V_1}{R} \left(\frac{RT_2}{p_2 M_2}\right)^2 = 1.4 \times \frac{\text{kg}\cdot\text{m}}{\text{N}\cdot\text{s}^2} \left[ \frac{150 \times 10^3}{\text{N/m}^2} \times 0.60 \times \frac{\text{m}^2}{2.16 \text{ kg} \times 108 \text{ m} \times \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}}} \right]^2 \times \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}}$$

$$T_2 = 726\text{ K}$$


$$s_2 - s_1 = \int_1^2 ds = \int_1^2 C_p \frac{dT}{T} - \int_1^2 R \frac{dp}{p} = C_p \ln \frac{T_2}{T_1} - R \ln \frac{p_2}{p_1}$$

$$s_2 - s_1 = 1.0 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} \ln \frac{726}{323} - 0.287 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} \ln \frac{150}{200} = 0.892\text{ kJ/kg}\cdot\text{K}$$

$$T_{01} = T_1 \left[ 1 + \frac{\gamma-1}{2} M_1^2 \right] = 323\text{K} \left[ 1 + 0.2(0.3)^2 \right] = 329\text{K}$$

$$T_{02} = T_2 \left[ 1 + \frac{\gamma-1}{2} M_2^2 \right] = 726\text{K} \left[ 1 + 0.2(0.6)^2 \right] = 778\text{K}$$

$$\frac{\delta q}{dm} = h_{02} - h_{01} = C_p (T_{02} - T_{01}) = 1.0 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} (778 - 329)\text{K} = 449\text{ kJ/kg}$$



\* Rayleigh-Line Flow Functions (App E.3)

For  $M_1 = 0.30$   $T_0/T_0^* = 0.3489 \therefore T_0^* = 948\text{K}$

$T_1/T_0^* = 0.4089 \therefore T_1^* = 790\text{K}$

$p_1/p_0^* = 2.131 \therefore p_0^* = 93.9\text{ kPa}$

For  $M_2 = 0.60$   $T_2/T_0^* = 0.8189 \therefore T_0^* = 716\text{K}$

$T_2/T_0^* = 0.9167 \therefore T_2 = 724\text{K}$

$p_2/p_0^* = 1.596 \therefore p_2 = 150\text{ kPa}$

Note: In using the flow functions, it is not necessary to know  $p_2 = 150\text{ kPa}$ .

## Problem 13.158

[Difficulty: 3]

---

**13.158** Air enters a 6-in.-diameter duct with a velocity of 300 ft/s. The entrance conditions are 14.7 psia and 200°F. How much heat must be added to the flow to yield (a) maximum static temperature at the exit, and (b) sonic flow at the exit?

---

**Given:** Air flow through a duct with heat transfer

**Find:** Heat addition needed to yield maximum static temperature and choked flow

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\c_p &= 0.2399 && \text{Btu/lbm-}^\circ\text{R} \\k &= 1.4 \\D &= 6 && \text{in} \\V_1 &= 300 && \text{ft/s} \\p_1 &= 14.7 && \text{psia} \\T_1 &= 200 && ^\circ\text{F} \\T_1 &= 660 && ^\circ\text{R}\end{aligned}$$

Equations and Computations:

The sound speed at station 1 is:

$$c_1 = 1259.65 \quad \text{ft/s}$$

So the Mach number is:

$$M_1 = 0.2382$$

We can determine the stagnation temperature at the entrance:

$$T_{01}/T_1 = 1.0113$$

So the entrance stagnation temperature is:

$$T_{01} = 667.49 \quad ^\circ\text{R}$$

The reference stagnation temperature for Rayleigh flow can be calculated:

$$T_{01}/T_0^* = 0.2363$$

$$T_0^* = 2824.4 \quad ^\circ\text{R}$$

For the maximum static temperature, the corresponding Mach number is:

$$M_2 = 0.8452$$

Since the reference state is the same at stations 1 and 2, state 2 is:

$$T_{02}/T_0^* = 0.9796$$

$$T_{02} = 2767 \quad ^\circ\text{R}$$

The heat transfer is related to the change in stagnation temperature:

$$q_{1-2} = 504 \quad \text{Btu/lb}$$


For acceleration to sonic flow the exit state is the \* state:

$$q_{1-*} = 517 \quad \text{Btu/lb}$$

## Problem 13.159

[Difficulty: 2]

**13.159** Liquid Freon, used to cool electronic components, flows steadily into a horizontal tube of constant diameter,  $D = 0.65$  in. Heat is transferred to the flow, and the liquid boils and leaves the tube as vapor. The effects of friction are negligible compared with the effects of heat addition. Flow conditions are shown. Find (a) the rate of heat transfer and (b) the pressure difference,  $p_1 - p_2$ .



**Given:** Frictionless flow of Freon in a tube

**Find:** Heat transfer; Pressure drop

NOTE:  $\rho_2$  is NOT as stated; see below

**Solution:**

Basic equations:  $m_{\text{rate}} = \rho \cdot V \cdot A$      $p = \rho \cdot R \cdot T$      $Q = m_{\text{rate}} \cdot (h_{02} - h_{01})$      $h_0 = h + \frac{V^2}{2}$      $p_1 - p_2 = \rho_1 \cdot V_1 \cdot (V_2 - V_1)$

Given or available data     $h_1 = 25 \cdot \frac{\text{BTU}}{\text{lbm}}$      $\rho_1 = 100 \cdot \frac{\text{lbm}}{\text{ft}^3}$      $h_2 = 65 \cdot \frac{\text{BTU}}{\text{lbm}}$      $\rho_2 = 0.850 \cdot \frac{\text{lbm}}{\text{ft}^3}$

$D = 0.65 \cdot \text{in}$      $A = \frac{\pi}{4} \cdot D^2$      $A = 0.332 \text{ in}^2$      $m_{\text{rate}} = 1.85 \cdot \frac{\text{lbm}}{\text{s}}$

Then     $V_1 = \frac{m_{\text{rate}}}{\rho_1 \cdot A}$      $V_1 = 8.03 \cdot \frac{\text{ft}}{\text{s}}$      $h_{01} = h_1 + \frac{V_1^2}{2}$      $h_{01} = 25.0 \cdot \frac{\text{BTU}}{\text{lbm}}$

$V_2 = \frac{m_{\text{rate}}}{\rho_2 \cdot A}$      $V_2 = 944 \cdot \frac{\text{ft}}{\text{s}}$      $h_{02} = h_2 + \frac{V_2^2}{2}$      $h_{02} = 82.8 \cdot \frac{\text{BTU}}{\text{lbm}}$

The heat transfer is     $Q = m_{\text{rate}} \cdot (h_{02} - h_{01})$      $Q = 107 \cdot \frac{\text{BTU}}{\text{s}}$     (74 Btu/s with the wrong  $\rho_2$ !)

The pressure drop is     $\Delta p = \rho_1 \cdot V_1 \cdot (V_2 - V_1)$      $\Delta p = 162 \cdot \text{psi}$     (-1 psi with the wrong  $\rho_2$ !)

## Problem 13.160

[Difficulty: 2]

**13.160** Air flows through a 5-cm inside diameter pipe with negligible friction. Inlet conditions are  $T_1 = 15^\circ\text{C}$ ,  $p_1 = 1$  MPa (abs), and  $M_1 = 0.35$ . Determine the heat exchange per kg of air required to produce  $M_2 = 1.0$  at the pipe exit, where  $p_2 = 500$  kPa.

**Given:** Frictionless air flow in a pipe

**Find:** Heat exchange per lb (or kg) at exit, where 500 kPa

**Solution:**

Basic equations:  $m_{\text{rate}} = \rho \cdot V \cdot A$     $p = \rho \cdot R \cdot T$     $\frac{\delta Q}{dm} = c_p \cdot (T_{02} - T_{01})$  (Energy)    $p_1 - p_2 = \rho_1 \cdot V_1 \cdot (V_2 - V_1)$  (Momentum)

Given or available data    $T_1 = (15 + 273) \cdot \text{K}$     $p_1 = 1 \cdot \text{MPa}$     $M_1 = 0.35$     $p_2 = 500 \cdot \text{kPa}$     $M_2 = 1$

$D = 5 \cdot \text{cm}$     $k = 1.4$     $c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$     $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

At section 1    $\rho_1 = \frac{p_1}{R \cdot T_1}$     $\rho_1 = 12.1 \frac{\text{kg}}{\text{m}^3}$     $c_1 = \sqrt{k \cdot R \cdot T_1}$     $c_1 = 340 \frac{\text{m}}{\text{s}}$

$V_1 = M_1 \cdot c_1$     $V_1 = 119 \frac{\text{m}}{\text{s}}$

From momentum    $V_2 = \frac{p_1 - p_2}{\rho_1 \cdot V_1} + V_1$     $V_2 = 466 \frac{\text{m}}{\text{s}}$

From continuity    $\rho_1 \cdot V_1 = \rho_2 \cdot V_2$     $\rho_2 = \rho_1 \cdot \frac{V_1}{V_2}$     $\rho_2 = 3.09 \frac{\text{kg}}{\text{m}^3}$

Hence    $T_2 = \frac{p_2}{\rho_2 \cdot R}$     $T_2 = 564 \text{ K}$     $T_2 = 291 \cdot ^\circ\text{C}$

and    $T_{02} = T_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)$     $T_{02} = 677 \text{ K}$     $T_{02} = 403 \cdot ^\circ\text{C}$

with    $T_{01} = T_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)$     $T_{01} = 295 \text{ K}$     $T_{01} = 21.9 \cdot ^\circ\text{C}$

Then    $\frac{\delta Q}{dm} = c_p \cdot (T_{02} - T_{01}) = 164 \cdot \frac{\text{Btu}}{\text{lbm}} = 383 \cdot \frac{\text{kJ}}{\text{kg}}$

(Note: Using Rayleigh line functions, for  $M_1 = 0.3$   $\frac{T_0}{T_{0\text{crit}}} = 0.4389$

so    $T_{0\text{crit}} = \frac{T_{01}}{0.4389}$     $T_{0\text{crit}} = 672 \text{ K}$  close to  $T_2$  ... Check!)

# Problem 13.161

[Difficulty: 3]

**13.161** Air flows at 1.42 kg/s through a 100-mm-diameter duct. At the inlet section, the temperature and absolute pressure are 52°C and 60.0 kPa. At the section downstream where the flow is choked,  $T_2 = 45^\circ\text{C}$ . Determine the heat addition per unit mass, the entropy change, and the change in stagnation pressure for the process, assuming frictionless flow.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$   $Tds = dh - vdp$   
 Computing equations:  $T_0/T = 1 + \frac{\gamma-1}{2} M^2$   $P_0/P = [1 + \frac{\gamma-1}{2} M^2]^{\frac{\gamma}{\gamma-1}}$   
 Assumptions: (1) steady flow (4) ideal gas  
 (2) frictionless flow (5)  $W_{\text{flow}} = W_{\text{shaft}} = 0$   
 (3) uniform flow at a section (6)  $Q = 0$

$A = \frac{\pi D^2}{4} = \frac{\pi (0.1)^2}{4} \text{ m}^2 = 7.85 \times 10^{-3} \text{ m}^2$

$P = PRT \quad P_1 = \frac{P}{RT_1} = 60.0 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{1}{287 \text{ N/m} \cdot \text{K}} \times 325 \text{ K} = 0.643 \text{ kg/m}^3$

$\dot{m} = \rho VA \quad V_1 = \frac{\dot{m}}{\rho A} = 1.42 \frac{\text{kg}}{\text{s}} \times \frac{1}{0.643 \text{ kg/m}^3 \times 7.85 \times 10^{-3} \text{ m}^2} = 281 \text{ m/s}$

$V_2 = M_2 C_2 = M_2 (\gamma RT_2)^{1/2} = 1.0 (1.4 \times 287 \frac{\text{N/m} \cdot \text{K}}{\text{kg} \cdot \text{K}} \times 318 \text{ K})^{1/2} = 357 \text{ m/s}$

$\dot{m} = \rho_2 V_2 A = \rho_2 V_2 A \quad \rho_2 = \frac{\dot{m}}{V_2 A} = \frac{1.42}{357 \times 7.85 \times 10^{-3}} = 0.506 \text{ kg/m}^3$

$P = PRT \quad P_2 = \rho_2 RT_2 = 0.506 \frac{\text{kg}}{\text{m}^3} \times 287 \frac{\text{N/m} \cdot \text{K}}{\text{kg} \cdot \text{K}} \times 318 \text{ K} = 46.2 \text{ kPa}$

$Tds = dh - vdp = c_p dT - \frac{1}{P} dp$

$ds = c_p \frac{dT}{T} - R \frac{dp}{P}$

$s_2 - s_1 = \int_{s_1}^{s_2} ds = \int_{T_1}^{T_2} c_p \frac{dT}{T} - \int_{P_1}^{P_2} R \frac{dp}{P} = c_p \ln \frac{T_2}{T_1} - R \ln \frac{P_2}{P_1} = 1.0 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} \ln \frac{318}{325} - 0.287 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} \ln \frac{46.2}{60}$

$s_2 - s_1 = 0.0522 \text{ kJ/kg} \cdot \text{K}$

$s_2 - s_1$

$M_1 = \frac{V_1}{C_1} = \frac{281}{(1.4 \times 287 \frac{\text{N/m} \cdot \text{K}}{\text{kg} \cdot \text{K}} \times 325 \text{ K})^{1/2}} = 0.778, \quad M_2 = \frac{V_2}{C_2} = \frac{357}{357} = 1.0$

$T_0/T = 1 + \frac{\gamma-1}{2} M^2 \quad T_{01} = T_1 [1 + 0.2(0.778)^2] = 325 \text{ K} [1 + 0.2(0.778)^2] = 364 \text{ K}$

$T_{02} = T_2 [1 + \frac{\gamma-1}{2} M_2^2] = 318 \text{ K} [1 + 0.2(1.0)^2] = 382 \text{ K}$


$h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2} \quad \frac{\delta Q}{dm} = h_{02} - h_{01} = c_p (T_{02} - T_{01}) = 1.0 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} (382 - 364) \text{ K} = 18 \text{ kJ/kg}$

$P_{01} = P_1 [1 + \frac{\gamma-1}{2} M_1^2]^{\frac{\gamma}{\gamma-1}} = 60 \text{ kPa} [1 + 0.2(0.778)^2]^{\frac{1.4}{0.4}} = 89.5 \text{ kPa}$

$P_{02} = P_2 [1 + \frac{\gamma-1}{2} M_2^2]^{\frac{\gamma}{\gamma-1}} = 46.2 \text{ kPa} [1 + 0.2(1.0)^2]^{\frac{1.4}{0.4}} = 87.5 \text{ kPa}$

$P_{01} - P_{02} = (89.5 - 87.5) \text{ kPa} = 2.0 \text{ kPa}$

$P_{01} - P_{02}$



**Rayleigh-Line Flow Functions**  
 From Appendix E.3 for  $M_1 = 0.778$   
 $T_{01}/T_0^* = 0.954$  (12.30d)  $\therefore T_0^* = T_{02} = 381 \text{ K}$   
 $P_{01}/P_0^* = 1.024$  (12.30e)  $\therefore P_0^* = P_{02} = 87.4 \text{ kPa}$   
 $P_1/P_0^* = 1.299$  (12.30a)  $\therefore P^* = P_2 = 46.2 \text{ kPa}$

# Problem 13.162

[Difficulty: 3]

13.162 Consider frictionless flow of air in a duct of constant area,  $A = 0.087 \text{ ft}^2$ . At one section, the static properties are  $500^\circ\text{R}$  and  $15.0 \text{ psia}$  and the Mach number is  $0.2$ . At a section downstream, the static pressure is  $10.0 \text{ psia}$ . Draw a  $Ts$  diagram showing the static and stagnation states. Calculate the flow speed and temperature at the downstream location. Evaluate the rate of heat exchange for the process.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$   $P_1 A = P_2 A = \dot{m}(V_2 - V_1)$

Computing equation:  $\frac{T}{T_0} = 1 - \frac{\gamma-1}{2} M^2$

Assumptions: (1) steady flow (2) uniform flow at a section (3) ideal gas  
(4) frictionless flow (5)  $F_{B_x} = 0$  (6)  $\dot{w}_s = \dot{w}_{\text{shear}} = 0$

$$P_1 = \frac{P_1}{RT_1} = \frac{15 \text{ lbf}}{\text{in}^2} \times \frac{1 \text{ lbm} \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lbm} \cdot \text{R}} \times \frac{1}{500 \text{ R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.0811 \text{ lbm/ft}^3$$

$$V_1 = M_1 c_1 = M_1 (\gamma R T_1)^{1/2} = 0.2 \left[ 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lbm}}{\text{lbm} \cdot \text{R}} \times 500 \text{ R} \times \frac{32.2 \text{ lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbm} \cdot \text{s}^2} \right]^{1/2} = 219 \text{ ft/s}$$

From the momentum eq.  $(P_1 - P_2)A = \dot{m}(V_2 - V_1) = P_1 V_1 A (V_2 - V_1)$

$$\therefore V_2 = \frac{(P_1 - P_2)}{P_1 V_1} + V_1 = \frac{(15 - 10) \text{ lbf}}{\text{in}^2} \times \frac{\text{ft}^3}{0.0811 \text{ lbm}} \times \frac{\text{s}}{219 \text{ ft}} \times \frac{144 \text{ in}^2}{\text{ft}^2} \times \frac{32.2 \text{ lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbm} \cdot \text{s}^2} + 219 \text{ ft/s}$$

$$V_2 = 1520 \text{ ft/s}$$

From continuity  $P_2 = \frac{V_1}{V_2} P_1 = \frac{219}{1520} \times 0.0811 \frac{\text{lbm}}{\text{ft}^3} = 0.0117 \text{ lbm/ft}^3$

$$T_2 = \frac{P_2}{P_2 R} = \frac{10 \text{ lbf}}{\text{in}^2} \times \frac{\text{ft}^3}{0.0117 \text{ lbm}} \times \frac{1 \text{ lbm} \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lbm} \cdot \text{R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 2310^\circ\text{R}$$

$$T_{01} = T_1 \left( 1 + \frac{\gamma-1}{2} M_1^2 \right) = 500 \left[ 1 + 0.2(0.2)^2 \right] = 504^\circ\text{R}$$

$$c_2 = (\gamma R T_2)^{1/2} = \left[ 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lbm}}{\text{lbm} \cdot \text{R}} \times 2310 \text{ R} \times \frac{32.2 \text{ lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbm} \cdot \text{s}^2} \right]^{1/2} = 2360 \text{ ft/s}$$

$$M_2 = \frac{V_2}{c_2} = \frac{1520}{2360} = 0.644$$


$$T_{02} = T_2 \left( 1 + \frac{\gamma-1}{2} M_2^2 \right) = 2310 \left[ 1 + 0.2(0.644)^2 \right] = 2500^\circ\text{R}$$

Since  $h_0 = h + \frac{V^2}{2}$ , the energy eq. can be written as  $\frac{\delta Q}{dm} = h_{02} - h_{01}$ .

$$\therefore \dot{Q} = \dot{m} \frac{\delta Q}{dm} = \dot{m} (h_{02} - h_{01}) = \dot{m} c_p (T_{02} - T_{01}) = P_1 V_1 A c_p (T_{02} - T_{01})$$

$$\dot{Q} = 0.0811 \frac{\text{lbm}}{\text{ft}^3} \times 219 \frac{\text{ft}}{\text{s}} \times 0.087 \text{ ft}^2 \times 0.24 \frac{\text{Btu}}{\text{lbm} \cdot \text{R}} \times (2500 - 504) \text{ R}$$

$$\dot{Q} = 740 \text{ Btu/s}$$



\* Rayleigh-Line Flow Functions (App. E.3)

At  $M_1 = 0.2$

$$P_1/P^* = 2.213 \text{ (12.130)} \therefore P^* = 6.60 \text{ psia}$$

$$T_1/T^* = 0.2066 \text{ (12.130)} \therefore T^* = 2420 \text{ R}$$

$$T_{01}/T_0^* = 0.1736 \text{ (12.130)} \therefore T_0^* = 2900 \text{ R}$$

At (2)  $P_2/P^* = 1.515 \therefore M_2 = 0.646$

$$\text{Also } T_{02}/T_0^* = 0.8644 \therefore T_{02} = 2510 \text{ R and } T_2/T^* = 0.9408 \therefore T_2 = 2280 \text{ R}$$

## Problem 13.163

[Difficulty: 3]

**13.163** Nitrogen flows through a frictionless duct. At the entrance of the duct, the conditions are  $M_1 = 0.75$ ,  $T_{0_1} = 500^\circ \text{R}$ , and  $p_1 = 24$  psia. At the exit of the duct the pressure is  $p_2 = 40$  psia. Determine the direction and the amount of the heat transfer with the nitrogen.

**Given:** Nitrogen flow through a duct with heat transfer

**Find:** Heat transfer

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 55.16 && \text{ft-lbf/lbm-}^\circ\text{R} \\ c_p &= 0.2481 && \text{Btu/lbm-}^\circ\text{R} \\ k &= 1.4 \\ M_1 &= 0.75 \\ T_{0_1} &= 500 && ^\circ\text{R} \\ p_1 &= 24 && \text{psia} \\ p_2 &= 40 && \text{psia} \end{aligned}$$

Equations and Computations:

We can find the pressure and stagnation temperature at the reference state:

$$\begin{aligned} p_1/p^* &= 1.3427 \\ T_{0_1}/T_0^* &= 0.9401 \end{aligned}$$

So the reference pressure and stagnation temperature are:

$$\begin{aligned} p^* &= 17.875 && \text{psia} \\ T_0^* &= 531.9 && ^\circ\text{R} \end{aligned}$$

We can now find the exit Mach number through the reference pressure:

$$\begin{aligned} p_2/p^* &= 2.2378 \\ M_2 &= 0.2276 \\ p_2/p^* &= 2.2378 \end{aligned}$$

(We used Solver to match the reference pressure ratio by varying  $M_2$ .)

Since the reference state is the same at stations 1 and 2, state 2 is:

$$\begin{aligned} T_{0_2}/T_0^* &= 0.2183 \\ T_{0_2} &= 116 && ^\circ\text{R} \end{aligned}$$

The heat transfer is related to the change in stagnation temperature:

$$q_{1-2} = -95.2 \quad \text{Btu/lb}$$

(The negative number indicates heat loss from the nitrogen)

# Problem 13.164

[Difficulty: 3]

13.164 A combustor from a JT8D jet engine (as used on the Douglas DC-9 aircraft) has an air flow rate of 15 lbm/s. The area is constant and frictional effects are negligible. Properties at the combustor inlet are 1260°R, 235 psia, and 609 ft/s. At the combustor outlet,  $T = 1840^\circ\text{R}$  and  $M = 0.476$ . The heating value of the fuel is 18,000 Btu/lbm; the air-fuel ratio is large enough so properties are those of air. Calculate the pressure at the combustor outlet. Determine the rate of energy addition to the air stream. Find the mass flow rate of fuel required; compare it to the air flow rate. Show the process on a  $Ts$  diagram, indicating static and stagnation states and the process path.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$   $p_1 A - p_2 A = \dot{m}(V_2 - V_1)$

Computing equation:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} M^2$

- Assumptions: 1) steady flow 2) frictionless flow  
 3) ideal gas, properties are those of air  
 4) uniform flow at a section  
 $\dot{m}_e = \dot{m}_{shear} = 0$

$$p_1 = \frac{p_1}{RT_1} = \frac{235 \frac{\text{lb}}{\text{in}^2}}{1716 \frac{\text{ft} \cdot \text{lb}}{\text{slug} \cdot \text{R}}} \times \frac{1}{1260 \text{ R}} \times 144 \frac{\text{in}^2}{\text{ft}^2} = 0.504 \frac{\text{lbm}}{\text{ft}^3}$$

$$c_1 = (\frac{kRT_1}{M_1})^{1/2} = [1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lbm} \cdot \text{R}} \times 1260 \text{ R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbm} \cdot \text{s}^2}]^{1/2} = 1740 \text{ ft/s}$$

$$M_1 = 4, k_1 = 609/1740 = 0.350 \quad T_{01} = T_1 [1 + \frac{k-1}{2} M_1^2] = 1260 \text{ R} [1 + 0.2(0.35)^2] = 1290 \text{ R}$$

$$T_{02} = T_2 [1 + \frac{k-1}{2} M_2^2] = 1840 [1 + 0.2(0.476)^2] = 1920 \text{ R}$$

From energy eq.  $\dot{q} = \dot{m}(h_{02} - h_{01}) = \dot{m}c_p(T_{02} - T_{01}) = 15 \frac{\text{lbm}}{\text{s}} \times 0.24 \frac{\text{Btu}}{\text{lbm} \cdot \text{R}} (1920 - 1290) \text{ R}$   
 $\dot{q} = 2270 \text{ Btu/s}$

But  $\dot{q} = \dot{m}_{fuel} h_{fuel} \therefore \dot{m}_{fuel} = \frac{\dot{q}}{h_{fuel}} = \frac{2270 \text{ Btu/s}}{18,000 \text{ Btu/lbm}} = 0.126 \text{ lbm/s}$

$$\dot{m}_{fuel}/\dot{m}_{air} = 0.126/15 = 0.0084$$

From momentum  $V_2 = M_2 c_2 = M_2 (\frac{kRT_2}{M_2})^{1/2} = 0.476 [1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}}{\text{lbm} \cdot \text{R}} \times 1840 \text{ R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lbm} \cdot \text{s}^2}]^{1/2} = 1000 \text{ ft/s}$

$$p_2 = p_1 - \frac{\dot{m}}{A}(V_2 - V_1) = p_1 - p_1 V_1 (V_2 - V_1)$$

$$p_2 = 235 \frac{\text{lb}}{\text{in}^2} - 0.504 \frac{\text{lbm}}{\text{ft}^3} \times 609 \frac{\text{ft}}{\text{s}} \times (1000 - 609) \frac{\text{ft}}{\text{s}} \times \frac{\text{slug}}{32.2 \text{ lbm}} \times \frac{\text{lbm} \cdot \text{s}^2}{\text{ft} \cdot \text{slug}} \times \frac{\text{ft}^2}{144 \text{ in}^2} = 209 \text{ psia}$$

\* Rayleigh-Line Flow Functions (App. E.3)

For  $M_1 = 0.35$ ,

$$T_0/T_0^* = 0.4389 \quad (12.30d) \therefore T_0^* = 2940 \text{ R}$$

$$T_1/T_0^* = 0.5141 \quad (12.30b) \therefore T_1^* = 2450 \text{ R}$$


$$p_1/p_0^* = 2.0487 \quad (12.30a) \therefore p_0^* = 114.7 \text{ psia}$$

For  $M_2 = 0.476$

$$T_{02}/T_0^* = 0.6551 \therefore T_{02} = 1920 \text{ R}$$

$$T_2/T_0^* = 0.7522 \therefore T_2 = 1840 \text{ R}$$

$$p_2/p_0^* = 1.822 \therefore p_2 = 209 \text{ psia}$$



## Problem 13.165

[Difficulty: 3]

**13.165** Consider frictionless flow of air in a duct with  $D = 10$  cm. At section ①, the temperature and pressure are  $0^\circ\text{C}$  and  $70$  kPa; the mass flow rate is  $0.5$  kg/s. How much heat may be added without choking the flow? Evaluate the resulting change in stagnation pressure.

**Given:** Frictionless flow of air in a duct

**Find:** Heat transfer without choking flow; change in stagnation pressure

**Solution:**

Basic equations:  $\frac{T_0}{T} = 1 + \frac{k-1}{2} \cdot M^2$        $\frac{p_0}{p} = \left(1 + \frac{k-1}{2} \cdot M^2\right)^{\frac{k}{k-1}}$        $p = \rho \cdot R \cdot T$        $m_{\text{rate}} = \rho \cdot A \cdot V$

$p_1 - p_2 = \frac{m_{\text{rate}}}{A} \cdot (V_2 - V_1)$        $\frac{\delta Q}{dm} = c_p \cdot (T_{02} - T_{01})$

Given or available data  $T_1 = (0 + 273) \cdot \text{K}$        $p_1 = 70 \cdot \text{kPa}$        $m_{\text{rate}} = 0.5 \cdot \frac{\text{kg}}{\text{s}}$        $D = 10 \cdot \text{cm}$

$A = \frac{\pi}{4} \cdot D^2$        $A = 78.54 \cdot \text{cm}^2$        $k = 1.4$        $M_2 = 1$        $c_p = 1004 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$        $R = 286.9 \cdot \frac{\text{J}}{\text{kg} \cdot \text{K}}$

At state 1  $\rho_1 = \frac{p_1}{R \cdot T_1}$        $\rho_1 = 0.894 \cdot \frac{\text{kg}}{\text{m}^3}$        $c_1 = \sqrt{k \cdot R \cdot T_1}$        $c_1 = 331 \cdot \frac{\text{m}}{\text{s}}$

From continuity  $V_1 = \frac{m_{\text{rate}}}{\rho_1 \cdot A}$        $V_1 = 71.2 \cdot \frac{\text{m}}{\text{s}}$       then  $M_1 = \frac{V_1}{c_1}$        $M_1 = 0.215$

From momentum  $p_1 - p_2 = \frac{m_{\text{rate}}}{A} \cdot (V_2 - V_1) = \rho_2 \cdot V_2^2 - \rho_1 \cdot V_1^2$  but  $\rho \cdot V^2 = \rho \cdot c^2 \cdot M^2 = \frac{p}{R \cdot T} \cdot k \cdot R \cdot T \cdot M^2 = k \cdot p \cdot M^2$

Hence  $p_1 - p_2 = k \cdot p_2 \cdot M_2^2 - k \cdot p_1 \cdot M_1^2$       or  $p_2 = p_1 \cdot \left(\frac{1 + k \cdot M_1^2}{1 + k \cdot M_2^2}\right)$        $p_2 = 31.1 \cdot \text{kPa}$

From continuity  $\rho_1 \cdot V_1 = \frac{p_1}{R \cdot T_1} \cdot M_1 \cdot c_1 = \frac{p_1}{R \cdot T_1} \cdot M_1 \cdot \sqrt{k \cdot R \cdot T_1} = \sqrt{\frac{k}{R}} \cdot \frac{p_1 \cdot M_1}{\sqrt{T_1}} = \rho_2 \cdot V_2 = \sqrt{\frac{k}{R}} \cdot \frac{p_2 \cdot M_2}{\sqrt{T_2}}$

Hence  $\frac{p_1 \cdot M_1}{\sqrt{T_1}} = \frac{p_2 \cdot M_2}{\sqrt{T_2}}$        $T_2 = T_1 \cdot \left(\frac{p_2 \cdot M_2}{p_1 \cdot M_1}\right)^2$        $T_2 = 1161 \text{ K}$        $T_2 = 888 \cdot ^\circ\text{C}$

Then  $T_{02} = T_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)$        $T_{02} = 1394 \text{ K}$        $T_{01} = T_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)$        $T_{01} = 276 \text{ K}$

$p_{02} = p_2 \cdot \left(1 + \frac{k-1}{2} \cdot M_2^2\right)^{\frac{k}{k-1}}$        $p_{02} = 58.8 \cdot \text{kPa}$        $p_{01} = p_1 \cdot \left(1 + \frac{k-1}{2} \cdot M_1^2\right)^{\frac{k}{k-1}}$        $p_{01} = 72.3 \cdot \text{kPa}$

Finally  $\frac{\delta Q}{dm} = c_p \cdot (T_{02} - T_{01}) = 1.12 \cdot \frac{\text{MJ}}{\text{kg}}$        $\Delta p_0 = p_{02} - p_{01}$        $\Delta p_0 = -13.5 \cdot \text{kPa}$

(Using Rayleigh functions, at  $M_1 = 0.215$        $\frac{T_{01}}{T_{0\text{crit}}} = \frac{T_{01}}{T_{02}} = 0.1975$        $T_{02} = \frac{T_{01}}{0.1975}$        $T_{02} = 1395 \text{ K}$  and ditto for  $p_{02}$  ...Check!)

# Problem 13.166

[Difficulty: 3]

**13.166** A constant-area duct is fed with air from a converging-diverging nozzle. At the entrance to the duct, the following properties are known:  $p_{01} = 800$  kPa (abs),  $T_{01} = 700$  K, and  $M_1 = 3.0$ . A short distance down the duct (at section ②)  $p_2 = 46.4$  kPa. Assuming frictionless flow, determine the speed and Mach number at section ②, and the heat exchange between the inlet and section ②.

Solution:

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{g z_1}{g_c} = h_2 + \frac{V_2^2}{2} + \frac{g z_2}{g_c}$

Computing equations:  $T_0/T = 1 + \frac{\gamma-1}{2} M^2$

- Assumptions: (1) steady flow  
 (2) frictionless flow  
 (3) uniform flow at a section  
 (4) ideal gas

$P_1 A_1 - P_2 A_2 = \dot{m} (V_2 - V_1)$   
 $P_0/P = [1 + \frac{\gamma-1}{2} M^2]^{\frac{\gamma}{\gamma-1}}$

- (5)  $F_{B_x} = 0$   
 (6)  $\dot{W}_s = \dot{W}_{shear} = 0$   
 (7)  $\dot{E} = 0$

$T_0/T = 1 + \frac{\gamma-1}{2} M^2$       $T_1 = \frac{T_{01}}{1 + \frac{\gamma-1}{2} M_1^2} = \frac{700 \text{ K}}{1 + 0.2(3.0)^2} = 250 \text{ K}$

$P_0/P = [1 + \frac{\gamma-1}{2} M^2]^{\frac{\gamma}{\gamma-1}}$       $P_1 = \frac{P_{01}}{[1 + \frac{\gamma-1}{2} M_1^2]^{\frac{\gamma}{\gamma-1}}} = \frac{800 \text{ kPa}}{[1 + 0.2(3.0)^2]^{\frac{1.4}{0.4}}} = 21.8 \text{ kPa}$

$V_1 = M_1 c_1 = M_1 (\gamma R T_1)^{1/2} = 3.0 (1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 250 \text{ K})^{1/2} = 951 \text{ m/s}$

$\rho = p/RT$       $\rho_1 = \frac{P_1}{RT_1} = \frac{21.8 \times 10^3 \frac{\text{N}}{\text{m}^2}}{287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 250 \text{ K}} = 0.304 \text{ kg/m}^3$

$(P_1 - P_2)A = \rho_1 A (V_2 - V_1)$       $\therefore V_2 = V_1 + \frac{(P_1 - P_2)}{\rho_1 \rho_1}$      Solving for  $V_2$

$V_2 = 951 \text{ m/s} + \frac{(21.8 - 46.4) \times 10^3 \frac{\text{N}}{\text{m}^2}}{0.304 \frac{\text{kg}}{\text{m}^3} \times 951 \text{ m/s}} = 866 \text{ m/s}$       $\rightarrow V_2$


From continuity,  $\rho_2 = \rho_1 \frac{V_1}{V_2} = 0.304 \frac{\text{kg}}{\text{m}^3} \times \frac{951}{866} = 0.334 \text{ kg/m}^3$

$T_2 = \frac{P_2}{\rho_2 R} = \frac{46.4 \times 10^3 \frac{\text{N}}{\text{m}^2}}{0.334 \frac{\text{kg}}{\text{m}^3} \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}}} = 484 \text{ K}$

$c_2 = (\gamma R T_2)^{1/2} = [1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 484 \text{ K}]^{1/2} = 441 \text{ m/s}$  ;  $M_2 = \frac{V_2}{c_2} = \frac{866}{441} = 1.96$       $\rightarrow M_2$

$T_{02} = T_2 [1 + \frac{\gamma-1}{2} M_2^2] = 484 [1 + 0.2(1.96)^2] = 856 \text{ K}$

$q/dm = h_{02} - h_{01} = c_p (T_{02} - T_{01}) = 1 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} (856 \text{ K} - 700 \text{ K}) = 156 \text{ kJ/kg}$       $\rightarrow \frac{q}{dm}$



\* Rayleigh-line Flow Functions (Appendix E.3)

For  $M_1 = 3.0$ ,  $T_0/T_0^* = 0.6540$ ,  $\therefore T_0^* = 1070 \text{ K}$   
 $T_1/T_0^* = 0.2803$ ,  $\therefore T_1 = 892 \text{ K}$   
 $P_1/P_0^* = 0.1765$ ,  $\therefore P_1 = 124 \text{ kPa}$   
 $V_1/V_0^* = 1.588$ ,  $\therefore V_1 = 599 \text{ m/s}$

At section ② for  $P_2/P_0^* = 0.3742$

$M_2 = 1.966$  ✓  
 $T_{02}/T_0^* = 0.800$ ,  $\therefore T_{02} = 856 \text{ K}$  ✓  
 $T_2/T_0^* = 0.542$ ,  $\therefore T_2 = 483 \text{ K}$   
 $V_2/V_0^* = 1.447$ ,  $\therefore V_2 = 867 \text{ m/s}$

# Problem 13.167

[Difficulty: 2]

13.167 Air flows steadily and without friction at 1.83 kg/s through a duct with cross-sectional area of 0.02 m<sup>2</sup>. At the duct inlet, the temperature and absolute pressure are 260°C and 126 kPa. The exit flow discharges subsonically to atmospheric pressure. Determine the Mach number, temperature, and stagnation temperature at the duct outlet and the heat exchange rate.

Solution:

\* Compressible flow functions (Appendix E) to be used in solution

Basic equation:  $h_1 + \frac{V_1^2}{2} + \frac{g_0}{g} z_1 = h_2 + \frac{V_2^2}{2} + \frac{g_0}{g} z_2$

- Assumptions:
- 1) steady flow
  - 2) frictionless flow
  - 3) uniform flow at a section
  - 4) ideal gas
  - 5)  $F_{R1} = 0$
  - 6)  $\dot{W}_b = \dot{W}_{elect} = 0$
  - 7)  $E = 0$

$$\rho_1 = \frac{P_1}{RT_1} = 126 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m} \cdot \text{K}} \times \frac{1}{533 \text{ K}} = 0.8237 \text{ kg/m}^3$$

$$\dot{m} = \rho_1 V_1 A \quad V_1 = \frac{\dot{m}}{\rho_1 A} = 1.83 \frac{\text{kg}}{\text{s}} \times \frac{\text{m}^3}{0.8237 \text{ kg} \cdot 0.02 \text{ m}^2} = 111 \text{ m/s}$$

$$M_1 = \frac{V_1}{c_1} \quad c_1 = (kRT_1)^{1/2} = 1.4 \times 287 \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 533 \text{ K} \times \left(\frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2}\right)^{1/2} = 463 \text{ m/s}$$

$$M_1 = \frac{111}{463} = 0.240$$

From App. E.1,  $T_0/T_1 = 1.012$  (11.17b)  $\therefore T_{01} = 539 \text{ K}$

From App E.2,  $T_0/T_0^* = 0.2395$  (12.30d),  $T/T_0^* = 0.2841$  (12.30b),  $P/P_0^* = 2.21$  (12.30a)


$$\therefore T_0^* = 2250 \text{ K} \quad T^* = 1876 \text{ K} \quad P^* = 56.73 \text{ kPa}$$

At section 2  $\frac{P_2}{P^*} = \frac{101}{56.73} = 1.780$  From App E.2 (Eq. 12.30a),  $M = 0.50$   $M_2$

Also,  $T_02/T_0^* = 0.6044$  (12.30d),  $T_2/T_0^* = 0.7901$ . Therefore:  $T_{02} = 1556 \text{ K}$ ,  $T_2 = 1480 \text{ K}$   $T_{02}, T_2$

$$\dot{Q} = \dot{m} \frac{dh}{dm} = \dot{m} (h_{02} - h_{01}) = \dot{m} c_p (T_{02} - T_{01}) = 1.83 \frac{\text{kg}}{\text{s}} \times 1.0 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} \times (1556 - 539) \text{ K}$$

$$\dot{Q} = 1.86 \text{ MJ/s}$$
  $\dot{Q}$



## Problem 13.168

[Difficulty: 3]

---

**13.168** 20 kg/s of air enters a 0.06 m<sup>2</sup> duct at a pressure of 320 kPa, and a temperature of 350 K. Find the exit conditions (pressure, temperature, and Mach number) if heat is added to the duct at a rate of 650 kJ/kg of air.

---

**Given:** Air flow through a duct with heat transfer

**Find:** Exit conditions

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\c_p &= 1004 && \text{J/kg-K} \\k &= 1.4 \\m &= 20 && \text{kg/s} \\A &= 0.06 && \text{m}^2 \\p_1 &= 320 && \text{kPa} \\T_1 &= 350 && \text{K} \\q_{1-2} &= 650 && \text{kJ/kg}\end{aligned}$$

Equations and Computations:

The density at the entrance is:

$$\rho_1 = 3.1868 \quad \text{kg/m}^3$$

So the entrance velocity is:

$$V_1 = 104.5990 \quad \text{m/s}$$

The sonic velocity is:

$$c_1 = 374.9413 \quad \text{m/s}$$

So the Mach number is:

$$M_1 = 0.2790$$

We can determine the stagnation temperature at the entrance:

$$T_{01}/T_1 = 1.0156$$

So the entrance stagnation temperature is:

$$T_{01} = 355.45 \quad \text{K}$$

The reference conditions for Rayleigh flow can be calculated:

$$T_{01}/T_0^* = 0.3085$$

$$T_0^* = 1152.2 \quad \text{K}$$

$$T_1/T_0^* = 0.3645$$

$$T^* = 960.2 \quad \text{K}$$

$$p_1/p^* = 2.1642$$

$$p^* = 147.9 \quad \text{kPa}$$

The heat transfer is related to the change in stagnation temperature:

$$T_{02} = 1002.86 \quad \text{K}$$

The stagnation temperature ratio at state 2 is:

$$T_{02}/T_0^* = 0.8704$$

We can now find the exit Mach number:

$$M_2 = 0.652$$

$$T_{02}/T_0^* = 0.8704$$

(We used Solver to match the reference pressure ratio by varying  $M_2$ .)

We can now calculate the exit temperature and pressure:

$$T_2/T_0^* = 0.9625$$

$$T_2 = 924 \quad \text{K}$$

$$p_2/p^* = 1.5040$$

$$p_2 = 222 \quad \text{kPa}$$

## Problem 13.169

[Difficulty: 3]

---

**13.169** Air enters a frictionless, constant-area duct with  $p_1 = 135$  kPa,  $T_1 = 500$  K, and  $V_1 = 540$  m/s. How much heat transfer is needed to choke the flow? Is the heat transfer into or out of the duct?

---

**Given:** Air flow through a duct with heat transfer

**Find:** Heat transfer needed to choke the flow

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg-K} \\c_p &= 1004 && \text{J/kg-K} \\k &= 1.4 \\p_1 &= 135 && \text{kPa} \\T_1 &= 500 && \text{K} \\V_1 &= 540 && \text{m/s}\end{aligned}$$

Equations and Computations:

The sonic velocity at state 1 is:

$$c_1 = 448.1406 \text{ m/s}$$

So the Mach number is:

$$M_1 = 1.2050$$

We can determine the stagnation temperature at the entrance:

$$T_{01}/T_1 = 1.2904$$

So the entrance stagnation temperature is:

$$T_{01} = 645.20 \text{ K}$$

The reference conditions for Rayleigh flow can be calculated:

$$T_{01}/T_0^* = 0.9778$$

$$T_0^* = 659.9 \text{ K}$$

Since the flow is choked, state 2 is:

$$M_2 = 1.000$$

$$T_{02} = 659.85 \text{ K}$$

The heat transfer is related to the change in stagnation temperature:

$$q_{1-2} = 14.71 \text{ kJ/kg}$$

To choke a flow, heat must *always* be *added*.

# Problem 13.170

[Difficulty: 2]

**13.170** In the frictionless flow of air through a 100-mm-diameter duct, 1.42 kg/s enters at 52°C and 60.0 kPa (abs). Determine the amount of heat that must be added to choke the flow, and the fluid properties at the choked state.

Solution:

\* Compressible flow functions (Appendix E) to be used in solution

Basic equation:  $h_1 + \frac{V_1^2}{2} + \frac{h_0}{\rho_1} = h_2 + \frac{V_2^2}{2}$

- Assumptions: (1) steady flow (4) ideal gas  
 (2) frictionless flow (5)  $\dot{W}_s = \dot{W}_{shear} = 0$   
 (3) uniform flow at a section (6)  $\dot{Q} = 0$

$$A = \frac{\pi D^2}{4} = \frac{\pi (0.1)^2}{4} \text{ m}^2 = 7.85 \times 10^{-3} \text{ m}^2$$

$$P = \rho RT \quad \rho_1 = \frac{P_1}{RT_1} = 60 \times 10^3 \frac{\text{N}}{\text{m}^2} \times \frac{\text{kg} \cdot \text{K}}{287 \text{ N} \cdot \text{m}} \times \frac{1}{325 \text{ K}} = 0.643 \frac{\text{kg}}{\text{m}^3}$$

$$\dot{m} = \rho VA \quad V_1 = \frac{\dot{m}}{\rho A} = 1.42 \frac{\text{kg}}{\text{s}} \times \frac{\text{m}^3}{0.643 \text{ kg} \times 7.85 \times 10^{-3} \text{ m}^2} = 281 \text{ m/s}$$

$$M_1 = \frac{V_1}{c_1} \quad c_1 = (\gamma RT_1)^{1/2} = (1.4 \times 287 \frac{\text{N} \cdot \text{m}}{\text{kg} \cdot \text{K}} \times 325 \text{ K} \times \frac{\text{kg} \cdot \text{m}}{\text{N} \cdot \text{s}^2})^{1/2} = 362 \text{ m/s}$$


$$M_1 = \frac{V_1}{c_1} = \frac{281}{362} = 0.776$$

From App E.1,  $T_1/T_0 = 0.8925$   $P_1/P_0 = 0.6717$   $\therefore T_0 = 364 \text{ K}$ ,  $P_0 = 89.3 \text{ kPa}$

From App E.3,  $T_0/T_2 = 0.9535$   $P_0/P_2 = 1.024$   $T_1/T_2 = 1.022$   $P_1/P_2 = 1.302$   $V_1/V_2 = \frac{P_2}{P_1} = 0.7844$

$$\therefore T_0 = 382 \text{ K}, P_0 = 87.2 \text{ kPa}, T_2 = 318 \text{ K}, P_2 = 46.1 \text{ kPa}, \rho_2 = 0.504 \frac{\text{kg}}{\text{m}^3}, V_2 = 358 \frac{\text{m}}{\text{s}}$$

$$\frac{dQ}{dm} = h_02 - h_01 = c_p(T_02 - T_01) = 1.0 \frac{\text{kJ}}{\text{kg} \cdot \text{K}} (382 - 364) \text{ K} = 18.0 \text{ kJ/kg}$$



# Problem 13.171

[Difficulty: 2]

13.171 Air flows without friction in a short section of constant-area duct. At the duct inlet,  $M_1 = 0.30$ ,  $T_1 = 50^\circ\text{C}$ , and  $p_1 = 2.16 \text{ kg/m}^3$ . At the duct outlet,  $M_2 = 0.60$ . Determine the heat addition per unit mass, the entropy change, and the change in stagnation pressure for the process.

Solution:

\* Compressible flow functions (Appendix E) to be used in solution

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{6Q}{\dot{m}} = h_2 + \frac{V_2^2}{2}$   $Tds = dh - vdp$

- Assumptions: (1) steady flow (4) ideal gas  
 (2) frictionless flow (5)  $W_s = W_s^{\text{shaft}} = 0$   
 (3) uniform flow at a section (6)  $\Delta z = 0$

$P_1 = \rho_1 RT_1 = 2.16 \frac{\text{kg}}{\text{m}^3} \cdot 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 323 \text{ K} = 200 \text{ kPa}$

$M_1 = 0.30$  From App. E.1  $T_1/T_{01} = 0.9823$  (11.17b),  $P_1/P_{01} = 0.9395$  (11.17a)  
 $\therefore T_{01} = 329 \text{ K}$   $P_{01} = 213 \text{ kPa}$

From App. E.3  $T_1/T_0^* = 0.3469$  (12.30d),  $P_1/P_0^* = 1.199$  (12.30e)  
 $\therefore T_0^* = 948 \text{ K}$   $P_0^* = 178 \text{ kPa}$

$M_2 = 0.60$  From App. E.3  $T_2/T_0^* = 0.8189$  (12.30d),  $P_2/P_0^* = 1.1075$  (12.30e)  
 $\therefore T_{02} = 776 \text{ K}$   $P_{02} = 191 \text{ kPa}$

$P_{01} - P_{02} = (213 - 191) \text{ kPa} = 22 \text{ kPa}$   $P_{01} - P_{02}$


$q/dm = h_{02} - h_{01} = c_p(T_{02} - T_{01}) = 1.0 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} \cdot (776 - 329) \text{ K} = 447 \text{ kJ/kg}$   $q/dm$

$Tds = dh - vdp = c_p dT - \frac{1}{p} dp$

$ds = c_p \frac{dT}{T} - R \frac{dp}{p}$

$s_2 - s_1 = s_{02} - s_{01} = \int_{s_{01}}^{s_{02}} ds = \int_{T_{01}}^{T_{02}} c_p \frac{dT}{T} - \int_{P_{01}}^{P_{02}} R \frac{dp}{p} = c_p \ln \frac{T_{02}}{T_{01}} - R \ln \frac{P_{02}}{P_{01}}$

$s_2 - s_1 = 1.0 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} \ln \frac{776}{329} - 0.287 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} \ln \frac{191}{213} = 0.889 \text{ kJ/kg}\cdot\text{K}$   $s_2 - s_1$



# Problem 13.172

[Difficulty: 2]

13.172 Air, from an aircraft inlet system, enters the engine combustion chamber, where heat is added during a frictionless process in a tube with constant area of  $0.01 \text{ m}^2$ . The local isentropic stagnation temperature and Mach number entering the combustor are  $427 \text{ K}$  and  $0.3$ . The mass flow rate is  $0.5 \text{ kg/s}$ . When the rate of heat addition is set at  $404 \text{ kW}$ , flow leaves the combustor at  $1026 \text{ K}$  and  $22.9 \text{ kPa}$  (abs). Determine for this process (a) the Mach number at the combustor inlet, (b) the static pressure at the combustor inlet, and (c) the change in local isentropic stagnation pressure during the heat addition process. Show static and stagnation state points and indicate the process path on a  $Ts$  diagram.

Solution: \* Compressible flow functions (Appendix E) to be used in solution

Basic equations:  $h_{01} + \frac{V_1^2}{2} = h_{02}$        $\dot{m} = \rho VA$        $p = \rho RT$

- Assumptions: (1) steady flow (2) frictionless flow  
 (3) ideal gas (4) uniform flow at a section  
 (5)  $\dot{m}_2 = \dot{m}_{\text{heat}} = 0$

From the energy equation,  $\dot{q} = \dot{m}(h_{02} - h_{01}) = \dot{m}c_p(T_{02} - T_{01})$

$\therefore T_{02} = T_{01} + \frac{\dot{q}}{\dot{m}c_p} = 427 \text{ K} + \frac{404 \times 10^3 \text{ W}}{0.5 \text{ kg/s} \times 1004 \text{ J/kg}\cdot\text{K}} = 1232 \text{ K}$

At  $M_1 = 0.3$ , from App. E.3,  $T_{01}/T_1^* = 0.3469$        $\therefore T_1^* = 1231 \text{ K}$   
 Since  $T_{02} \neq T_1^*$ , then  $M_2 = 1.0$   $M_2$


$\therefore p_2 = p^* = 22.9 \text{ kPa}$

From Appendix E.3 for  $M_1 = 0.3$ ,  $p_1/p^* = 2.131$        $\therefore p_1 = 48.8 \text{ kPa}$   $p_1$   
 " " E.1 "  $M_1 = 0.3$ ,  $p_{01}/p_1 = 0.9395$        $\therefore p_{01} = 51.9 \text{ kPa}$

From Appendix E.1 for  $M_2 = 1.0$ ,  $p_2/p_{02} = 0.5283$        $\therefore p_{02} = 43.3 \text{ kPa}$

$\therefore p_{02} - p_{01} = (43.3 - 51.9) \text{ kPa} = -8.6 \text{ kPa}$

$\frac{\Delta p_{02}}{p_{01}} = \frac{-8.6}{51.9} = -0.166$  (or  $-16.6\%$ )  $\Delta p_{02}$



## Problem 13.173

[Difficulty: 4]

**13.173** Air enters a frictionless, constant-area duct with  $M_1 = 2.0$ ,  $T_1 = 300^\circ\text{R}$ , and  $p_1 = 70$  psia. Heat transfer occurs as the air travels down the duct. A converging section ( $A_2/A_3 = 1.5$ ) is placed at the end of the constant area duct and  $M_3 = 1.0$ . Assuming isentropic flow (aside from the heat transfer through the duct), calculate the amount and direction of heat transfer.

**Given:** Air flow through a duct with heat transfer followed by converging duct, sonic at exit

**Find:** Magnitude and direction of heat transfer

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\c_p &= 0.2399 && \text{Btu/lbm-}^\circ\text{R} \\k &= 1.4 \\M_1 &= 2 \\T_1 &= 300 && ^\circ\text{R} \\p_1 &= 70 && \text{psia} \\A_2/A_3 &= 1.5 \\M_3 &= 1\end{aligned}$$

Equations and Computations:

We can determine the stagnation temperature at the entrance:

$$T_{01}/T_1 = 1.8000$$

So the entrance stagnation temperature is:

$$T_{01} = 540.00 \quad ^\circ\text{R}$$

The reference stagnation temperature ratio at state 1 is:

$$T_{01}/T_0^* = 0.7934$$

The reference conditions for Rayleigh flow can be calculated:

$$T_0^* = 680.6 \quad ^\circ\text{R}$$

Since the flow is sonic at state 3, we can find the Mach number at state 2:

$$M_2 = 1.8541$$

We know that the flow must be supersonic at 2 since the flow at  $M_1 > 1$ .

The reference stagnation temperature ratio at state 2 is:

$$T_{02}/T_0^* = 0.8241$$

Since the reference stagnation temperature at 1 and 2 are the same:

$$T_{02} = 560.92 \quad ^\circ\text{R}$$

The heat transfer is related to the change in stagnation temperature:

$$q_{1-2} = 5.02 \quad \text{Btu/lbm}$$

The heat is being added to the flow.

# Problem 13.174

[Difficulty: 3]

13.174 Consider steady, one-dimensional flow of air in a combustor with constant area of  $0.5 \text{ ft}^2$ , where hydrocarbon fuel, added to the air stream, burns. The process is equivalent to simple heating because the amount of fuel is small compared to the amount of air; heating occurs over a short distance so that friction is negligible. Properties at the combustor inlet are  $818^\circ\text{R}$ ,  $200 \text{ psia}$ , and  $M = 0.3$ . The speed at the combustor outlet must not exceed  $2000 \text{ ft/s}$ . Find the properties at the combustor outlet and the heat addition rate. Show the process path on a  $T$ - $s$  diagram, indicating static and stagnation state points before and after the heat addition.

Solution: (using compressible flow functions - Appendix E)

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\dot{q}_0}{\dot{m}} = h_2 + \frac{V_2^2}{2}$       $p = \rho RT$       $\dot{m} = \rho VA$

- Assumptions: (1) steady flow (2) frictionless flow  
 (3) ideal gas, properties are those of air  
 (4) uniform flow at a section  
 (5)  $W_s = W_{shear} = 0$

$$p_1 = \frac{p_1}{RT_1} = \frac{200 \text{ lbf}}{\text{ft}^2} = \frac{\text{lbm} \cdot \text{R}}{53.3 \text{ ft} \cdot \text{lbf}} \times \frac{1}{818 \text{ R}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 0.6606 \text{ lbm/ft}^3$$

$$V_1 = M_1 c_1 = M_1 (kRT_1)^{1/2} = 0.3 \left[ 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lbf}}{\text{lbm} \cdot \text{R}} \times 818 \text{ R} \times 32.2 \frac{\text{lbm} \cdot \text{slug}}{\text{slug} \cdot \text{ft}^2} \right]^{1/2} = 421 \text{ ft/s}$$

From App. E.1      $M_1 = 0.3$       $T_1/T_0^* = 0.9823$       $\therefore T_0^* = 832.17 \text{ R}$   
 $p_1/p_0^* = 0.9395$       $\therefore p_0^* = 212.9 \text{ psia}$

From continuity,  $p_1 V_1 = p_2 V_2$   
 $\therefore p_2 = \frac{V_1}{V_2} p_1 = \frac{421}{2000} \times 0.6606 \text{ lbm/ft}^3 = 0.139 \text{ lbm/ft}^3$

From App. E.3      $M_1 = 0.3$       $T_0^*/T_0^* = 0.3469$       $p_0^*/p_0^* = 1.199$       $T_1/T_0^* = 0.4589$       $p_1/p_0^* = 2.131$       $V_1/V_0^* = 0.1976$   
 $\therefore T_0^* = 2400 \text{ R}$       $p_0^* = 177.6 \text{ psia}$       $T^* = 2000 \text{ R}$       $p^* = 93.85 \text{ psia}$       $V^* = 2193 \frac{\text{ft}}{\text{sec}}$

At section ②      $V_2/V^* = 2000/2193 = 0.9120$


From App. E.3      $M_2 = 0.90$       $T_0^*/T_0^* = 0.9921$       $p_0^*/p_0^* = 1.005$       $T_2/T_0^* = 1.025$       $p_2/p_0^* = 1.125$   
 $\therefore T_0^* = 2380 \text{ R}$       $p_0^* = 178 \text{ psia}$       $T_2 = 2050 \text{ R}$       $p_2 = 106 \text{ psia}$

From the energy equation,

$$\dot{q} = \dot{m} \frac{\dot{q}_0}{\dot{m}} = \rho_1 V_1 A (h_{02} - h_{01}) = \rho_1 V_1 A C_p (T_0^* - T_0^*)$$

$$\dot{q} = 0.6606 \frac{\text{lbm}}{\text{ft}^3} \times 420.6 \frac{\text{ft}}{\text{s}} \times 0.5 \text{ ft}^2 \times 0.24 \frac{\text{Btu}}{\text{lbm} \cdot \text{R}} \times (2380 - 832) \text{ R}$$

$$\dot{q} = 5.16 \times 10^4 \text{ Btu/s} \quad \leftarrow \dot{q}$$



## Problem 13.175

[Difficulty: 3]

**13.175** Flow in a gas turbine combustor is modeled as steady, one-dimensional, frictionless heating of air in a channel of constant area. For a certain process, the inlet conditions are 500°C, 1.5 MPa (abs), and  $M = 0.5$ . Calculate the maximum possible heat addition. Find all fluid properties at the outlet section and the reduction in stagnation pressure. Show the process path on a  $Ts$  diagram, indicating all static and stagnation state points.

**Given:** Data on flow through gas turbine combustor

**Find:** Maximum heat addition; Outlet conditions; Reduction in stagnation pressure; Plot of process

**Solution:**


The given or available data is:

$R =$	286.9	J/kg K
$k =$	1.4	
$c_p =$	1004	J/kg K
$T_1 =$	773	K
$p_1 =$	1.5	MPa
$M_1 =$	0.5	

Equations and Computations:

From  $p_1 = \rho_1 R T_1$        $\rho_1 = 6.76$     kg/m<sup>3</sup>

From  $V_1 = M_1 \sqrt{k R T_1}$        $V_1 = 279$     m/s



Using built-in function  $IsenT(M,k)$ :

$$T_{01}/T_1 = 1.05 \qquad T_{01} = 812 \text{ K}$$

Using built-in function  $Isenp(M,k)$ :

$$p_{01}/p_1 = 1.19 \qquad p_{01} = 1.78 \text{ MPa}$$

For maximum heat transfer:  $M_2 = 1$

Using built-in function  $rayT0(M,k)$ ,  $rayp0(M,k)$ ,  $rayT(M,k)$ ,  $rayp(M,k)$ ,  $rayV(M,k)$ :

$T_{01}/T_0^* =$	0.691	$T_0^* =$	1174 K	(= $T_{02}$ )
$p_{01}/p_0^* =$	1.114	$p_0^* =$	1.60 MPa	(= $p_{02}$ )
$T/T^* =$	0.790	$T^* =$	978 K	(= $T_{02}$ )
$p/p^* =$	1.778	$p^* =$	0.844 MPa	(= $p_2$ )
$\rho^*/\rho =$	0.444	$\rho^* =$	3.01 kg/m <sup>3</sup>	(= $\rho_2$ )

Note that at state 2 we have critical conditions!

Hence:  $p_{012} - p_{01} = -0.182$  MPa       $-182$  kPa

From the energy equation:  $\frac{\delta Q}{dm} = c_p (T_{02} - T_{01})$

$$\delta Q/dm = 364 \text{ kJ/kg}$$

# Problem 13.176

[Difficulty: 3]

13.176 A supersonic wind tunnel is supplied from a high-pressure tank of air at 25°C. The test section temperature is to be maintained above 0°C to prevent formation of ice particles. To accomplish this, air from the tank is heated before it flows into a converging-diverging nozzle which feeds the test section. The heating is done in a short section with constant area. The heater output is  $\dot{Q} = 10 \text{ kW}$ . The design Mach number in the wind tunnel test section is to be 3.0. Evaluate the stagnation temperature required at the heater exit. Calculate the maximum mass flow rate at which air can be supplied to the wind tunnel test section. Determine the area ratio,  $A_e/A_t$ .

### Solution:

(using compressible flow functions)

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{s_0}{dm} = h_2 + \frac{V_2^2}{2}$        $\dot{m} = \rho V A$        $p = \rho R T$

- Assumptions: (1) steady flow (2) uniform flow at a section  
 (3) frictionless flow in the heater  
 (4) isentropic flow through the nozzle  
 (5) ideal gas (6)  $w_s = w_{shnoz} = 0$

$T_{01} = T = 298 \text{ K}$

From Appendix E.1 at  $M=3$ ,  $T/T_0 = 0.3571$ ,  $A_e/A^* = A_e/A_t = 4.23$   $\frac{A}{A^*}$


With  $T_e = 273 \text{ K}$ ,  $T_{02} = T_{01} = 273 \text{ K} / 0.3571 = 764 \text{ K}$   $T_{02}$

From the energy equation  $\frac{ds}{dm} = h_{02} - h_{01} = c_p (T_{02} - T_{01})$

Since  $\dot{Q} = \dot{m} \frac{ds}{dm}$ , then  $\dot{m} = \frac{\dot{Q}}{c_p (T_{02} - T_{01})}$

and


$\dot{m} = 10 \text{ kW} \times 10^3 \frac{\text{N}\cdot\text{m}}{\text{s}\cdot\text{kW}} \times \frac{\text{kg}\cdot\text{K}}{1000 \text{ N}\cdot\text{m}} \times \frac{1}{(764 - 298) \text{ K}} = 0.0215 \frac{\text{kg}}{\text{s}}$   $\dot{m}$



### Problem 13.177

[Difficulty: 3]

**13.177** Consider steady flow of air in a combustor where thermal energy is added by burning fuel. Neglect friction. Assume thermodynamic properties are constant and equal to those of pure air. Calculate the stagnation temperature at the burner exit. Compute the Mach number at the burner exit. Evaluate the heat addition per unit mass and the heat exchange rate. Express the rate of heat addition as a fraction of the maximum rate of heat addition possible with this inlet Mach number.



Solution:

(using compressible flow functions - Appendix E)

Basic equations:  $h_1 + \frac{V_1^2}{2} + \frac{\delta Q}{dm} = h_2 + \frac{V_2^2}{2}$       $\dot{m} = \rho VA$       $p = \rho RT$

Assumptions: (1) steady flow     (2) ideal gas  
(3) uniform flow at a section  
(4)  $w_s = w_{shear} = 0$

$$\rho_1 = \frac{p_1}{RT_1} = \frac{557 \times 10^3 \text{ N/m}^2}{287 \text{ N}\cdot\text{m}/\text{kg}\cdot\text{K} \times 604 \text{ K}} = 3.21 \text{ kg/m}^3$$

$$V_1 = M_1 c_1 = M_1 (kRT_1)^{1/2} = 0.4 \left( 1.4 \times 287 \frac{\text{N}\cdot\text{m}}{\text{kg}\cdot\text{K}} \times 604 \text{ K} \right)^{1/2} = 197 \text{ m/s}$$

$$\dot{m} = \rho_1 V_1 A = 3.21 \frac{\text{kg}}{\text{m}^3} \times 197 \frac{\text{m}}{\text{s}} \times 0.0185 \text{ m}^2 = 11.7 \text{ kg/s}$$

From App. E.1 at  $M_1 = 0.4$ ,  $T_1/T_{0,1} = 0.969$       $\therefore T_{0,1} = 623 \text{ K}$

From App. E.3 at  $M_1 = 0.4$ ,  $T/T^* = 0.6152$ ,  $T_0/T_0^* = 0.5290$   
 $\therefore T^* = 982$      and  $T_0^* = 1180 \text{ K}$

At section 2  $T_2 = 900 \text{ K}$       $\therefore (T/T^*)_2 = 0.916$

From App. E.3,  $M_2 = 0.60$ ,  $T_0/T_0^* = 0.8189$

$\therefore T_{0,2} = 966 \text{ K}$ ,  $M_2 = 0.60$       $M_2, T_{0,2}$


From the energy equation,

$$\frac{\delta Q}{dm} = h_{0,2} - h_{0,1} = c_p (T_{0,2} - T_{0,1}) = 1.005 \frac{\text{kJ}}{\text{kg}\cdot\text{K}} (966 - 623) \text{ K} = 343 \frac{\text{kJ}}{\text{kg}}$$

$$\dot{Q} = \dot{m} \frac{\delta Q}{dm} = 11.7 \frac{\text{kg}}{\text{sec}} \times 343 \frac{\text{kJ}}{\text{kg}} = 4010 \frac{\text{kJ}}{\text{sec}} = 4010 \text{ kW}$$

The heat transfer may be expressed as a fraction of the maximum possible heat addition

$$\frac{\delta Q/dm}{(\delta Q/dm)_{\text{max}}} = \frac{T_{0,2} - T_{0,1}}{T_0^* - T_{0,1}} = \frac{966 - 623}{1180 - 623} = 0.616$$



# Problem 13.178

13.178 A jet transport aircraft cruises at  $M = 0.85$  at an altitude of 40,000 ft. Air for the cabin pressurization system is taken aboard through an inlet duct and slowed isentropically to 100 ft/s relative to the aircraft. Then it enters a compressor, where its pressure is raised adiabatically to provide a cabin pressure equivalent to 8000 ft altitude. The air temperature increase across the compressor is  $170^\circ\text{F}$ . Finally, the air is cooled to  $70^\circ\text{F}$  (in a heat exchanger with negligible friction) before it is added to the cabin air. Sketch a diagram of the system, labeling all components and numbering appropriate cross sections. Determine the stagnation and static temperature and pressure at each cross section. Sketch to scale and label a  $Ts$  diagram showing the static and stagnation state points and indicating the process paths. Evaluate the work added in the compressor and the energy rejected in the heat exchanger.

Solution: From the standard atmosphere, at  $z_1 = 40,000$  ft,  
 $T_1 = -70^\circ\text{F}$  and  $p_1 = 2.73$  psia

$$C_1 = \sqrt{kRT_1} = \left[ 1.4 \times 53.3 \frac{\text{ft} \cdot \text{lb}_f}{\text{lbm} \cdot ^\circ\text{R}} \times (460 - 70)^\circ\text{R} \times 32.2 \frac{\text{lbm}}{\text{slug}} \times \frac{\text{slug} \cdot \text{ft}}{\text{lb}_f \cdot \text{s}^2} \right]^{\frac{1}{2}} = 968 \frac{\text{ft}}{\text{s}}$$

$$V_1 = M_1 C_1 = 0.85 \times 968 \frac{\text{ft}}{\text{s}} = 823 \frac{\text{ft}}{\text{s}}$$

For isentropic deceleration  $T_{01} = T_1 + \frac{V_1^2}{2C_p} = T_{02} = T_2 + \frac{V_2^2}{2C_p}$

$$T_2 = T_1 + \frac{1}{2C_p} (V_1^2 - V_2^2)$$

$$T_2 = 390^\circ\text{R} + \frac{1}{2} \times \frac{1 \text{ lbm} \cdot ^\circ\text{R}}{0.240 \text{ Btu}} \left[ (823)^2 - (100)^2 \right] \frac{\text{ft}^2}{\text{s}^2} \times \frac{\text{Btu}}{778 \text{ ft} \cdot \text{lb}_f} \times \frac{1 \text{ lb}_f \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \frac{\text{slug}}{32.2 \text{ lbm}} = 445^\circ\text{R}$$


For isentropic deceleration,

$$p_2 = p_1 \left( \frac{T_2}{T_1} \right)^{\frac{\gamma}{\gamma-1}} = 2.73 \text{ psia} \left( \frac{445}{390} \right)^{3.5} = 4.33 \text{ psia}$$

The compressor raises the air the equivalent of  $z_3 - z_4 = 8,000$  ft; from the Standard Atmosphere

$$p_3 = p_4 = 10.92 \text{ psia}; p_{03} = p_3 \left( 1 + \frac{\gamma-1}{2} M_3^2 \right)^{\frac{\gamma}{\gamma-1}} = 10.92 \left( 1 + 0.2(0.823)^2 \right)^{3.5} = 10.97 \text{ psia}$$

Assume  $V_2 \approx V_3 \approx V_4$  since no other data are known. The system is



### Problem 13.178

[Difficulty: 4] Part 2/2

Evaluating properties:  $T_{01} = T_1 (1 + \frac{k-1}{2} M_1^2) = 390^\circ R (1 + 0.2(0.85)^2) = 446^\circ R = T_{02}$

$p_{01} = p_1 (1 + \frac{k-1}{2} M_1^2)^{\frac{k}{k-1}} = 2.73 \text{ psia} (1 + 0.2(0.85)^2)^{3.5} = 4.38 \text{ psia} = p_{02}$

$T_3 = T_2 + 170^\circ R = 445 + 170^\circ R = 615^\circ R$ ;  $T_{03} = T_{02} + 170^\circ R = 616^\circ R$  (since  $V_2 \approx \text{const}$ )

From the energy equation

$\dot{W}_{in} = m(h_3 - h_2) = m c_p (T_3 - T_2)$

$\dot{W}_{in} = \frac{0.75 \text{ lbm}}{s} \cdot 0.240 \frac{\text{Btu}}{\text{lbm}^\circ R} (170^\circ R) \times \frac{778 \text{ ft} \cdot \text{lb}}{\text{Btu}} \times \frac{\text{hp} \cdot s}{550 \text{ ft} \cdot \text{lb}} = 43.3 \text{ hp}$

$\dot{W}_{in}$

$\dot{Q}_{in} = m(h_4 - h_3) = m c_p (T_4 - T_3)$

$\dot{Q}_{in} = \frac{0.75 \text{ lbm}}{s} \cdot 0.240 \frac{\text{Btu}}{\text{lbm}^\circ R} (530 - 615)^\circ R = -15.3 \text{ Btu/s}$  (out)


$\dot{Q}_{in}$

The entropy changes are computed using  $T ds = dh - v dp$ , as

$\Delta s_{23} = c_p \ln \frac{T_{03}}{T_{02}} - R \ln \frac{p_{03}}{p_{02}} = 0.240 \frac{\text{Btu}}{\text{lbm}^\circ R} \ln \left( \frac{616}{446} \right) - \frac{53.3 \text{ ft} \cdot \text{lb}}{\text{lbm}^\circ R} \ln \left( \frac{10.97}{4.38} \right) \frac{\text{Btu}}{778 \text{ ft} \cdot \text{lb}} = 0.0146 \frac{\text{Btu}}{\text{lbm}^\circ R}$

$\Delta s_{34} = c_p \ln \frac{T_{04}}{T_{03}} - R \ln \frac{p_{04}}{p_{03}} = 0.240 \frac{\text{Btu}}{\text{lbm}^\circ R} \ln \left( \frac{530}{616} \right) - \frac{53.3 \text{ ft} \cdot \text{lb}}{778 \text{ lbm}^\circ R} \ln \left( \frac{10.97}{10.97} \right) = -0.0361 \frac{\text{Btu}}{\text{lbm}^\circ R}$

The Ts diagram is:



# Problem 13.179

[Difficulty: 4] Part 1/2

13.179 Frictionless flow of air in a constant-area duct discharges to atmospheric pressure at section ②. Upstream at section ①,  $M_1 = 3.0$ ,  $T_1 = 215^\circ\text{R}$ , and  $p_1 = 1.73$  psia. Between sections ① and ②, 48.5 Btu/lbm of air is added to the flow. Determine  $M_2$  and  $p_2$ . In addition to a  $Ts$  diagram, sketch the pressure distribution versus distance along the channel, labeling sections ① and ②.

Solution: Apply equations for Rayleigh line flow of an ideal gas.

Basic equations:  $c_p T_{01} + \frac{\delta Q}{dm} = c_p T_{02}$        $p_1 A - p_2 A = \dot{m}(V_2 - V_1)$

Computing equation:  $T_0 = T(1 + \frac{k-1}{2} M^2)$

- Assumptions: (1) Steady flow (5)  $F_{B_x} = 0$   
 (2) Frictionless flow (6)  $\dot{W}_s = \dot{W}_{\text{shear}} = 0$   
 (3) Uniform flow at each section (7)  $\Delta z = 0$   
 (4) Ideal gas

The minimum possible Mach number for supersonic flow with heating is  $M_2 = 1$ .

$$T_{01} = T_1(1 + \frac{k-1}{2} M_1^2) = 215^\circ\text{R}(1 + 0.2(3.0)^2) = 613^\circ\text{R}$$

$$T_{02} = T_{01} + \frac{1}{c_p} \frac{\delta Q}{dm} = 613^\circ\text{R} + \frac{1 \text{ lbm} \cdot \text{R}}{0.240 \text{ Btu}} \times \frac{48.5 \text{ Btu}}{1 \text{ lbm}} = 815^\circ\text{R}$$

Check for  $M_2 = 1.0$ :  $T_2 = \frac{T_{02}}{1 + 0.2(1)^2} = \frac{815^\circ\text{R}}{1.2} = 679^\circ\text{R}$

$$V_2 = c_2 = \sqrt{kRT_2} = 1,280 \text{ ft/s}$$


Thus  $p_2 = p_1 + \frac{\dot{m}}{A}(V_1 - V_2) = p_1 + \rho_1 V_1(V_1 - V_2)$

$$V_1 = M_1 c_1 = M_1 \sqrt{kRT_1} = 3.0 \times 719 \frac{\text{ft}}{\text{s}} = 2,160 \text{ ft/s}; \quad \rho_1 = \frac{p_1}{RT_1} = 0.0217 \text{ lbm/ft}^3$$


$$p_2 = 1.73 \frac{\text{lb}_f}{\text{in}^2} + 0.0217 \frac{\text{lbm}}{\text{ft}^3} \times 2,160 \frac{\text{ft}}{\text{s}} (2,160 - 1,280) \frac{\text{ft}}{\text{s}} \times \frac{\text{slug}}{32.2 \text{ lbm}} \times \frac{\text{lb}_f \cdot \text{s}^2}{\text{slug} \cdot \text{ft}} \times \frac{144 \text{ in}^2}{\text{ft}^2} = 10.6 \text{ psia}$$

Thus if  $M_2 = 1.0$ , the  $p_2 < p_{\text{atm}}$ , which is not possible for sonic flow. Therefore

$p_2 < p_{\text{atm}}$  and  $M_2 > 1.0$  for this flow.



The pressure vs. distance plot is:



{ This problem could be solved quantitatively, but only by either iteration or by use of compressible flow functions; that solution is presented on the next page. }

$p_2$   
 $M_2$

### Problem 13.179

[Difficulty: 4] Part 2/2

For  $M_1 = 3.0$ , from App. E.3:  $\frac{T_0}{T_0^*} = 0.6540$ , and  $\frac{p}{p^*} = 0.1765$

$$\text{Thus } T_0^* = \frac{T_{01}}{(\frac{T_0}{T_0^*})_1} = \frac{613^\circ R}{0.6540} = 937^\circ R; \quad p^* = \frac{p_1}{(p/p^*)_1} = \frac{1.73 \text{ psia}}{0.1765} = 9.80 \text{ psia}$$

$$\text{At section 2, } T_{02} = 815 \text{ R and } \frac{T_{02}}{T_0^*} = \frac{815^\circ R}{937^\circ R} = 0.870$$

From App. E.3 this corresponds to  $M_2 = 1.74$ . At this Mach number,  $\frac{p}{p^*} = 0.4581$ .

$$\text{Thus } p_2 = p^* \left(\frac{p}{p^*}\right)_2 = 9.80 \text{ psia} \times 0.4581 = 4.49 \text{ psia}$$

$p_2$

{ These calculations confirm that  $M_2 > 1$  and  $p_2 < p_{\text{atm}}$ . }



## Problem 13.180

[Difficulty: 3]

**13.180** Show that as the upstream Mach number approaches infinity, the Mach number after an oblique shock becomes

$$M_2 \approx \sqrt{\frac{k-1}{2k \sin^2(\beta - \theta)}}$$

**Given:** Normal shock

**Find:** Approximation for downstream Mach number as upstream one approaches infinity

**Solution:**

Basic equations: 
$$M_{2n}^2 = \frac{M_{1n}^2 + \frac{2}{k-1}}{\left(\frac{2 \cdot k}{k-1}\right) \cdot M_{1n}^2 - 1} \quad (13.48a) \quad M_{2n} = M_2 \cdot \sin(\beta - \theta) \quad (13.47b)$$

Combining the two equations 
$$M_2 = \frac{M_{2n}}{\sin(\beta - \theta)} = \frac{\sqrt{\frac{M_{1n}^2 + \frac{2}{k-1}}{\left(\frac{2 \cdot k}{k-1}\right) \cdot M_{1n}^2 - 1}}}{\sin(\beta - \theta)} = \sqrt{\frac{M_{1n}^2 + \frac{2}{k-1}}{\left[\left(\frac{2 \cdot k}{k-1}\right) \cdot M_{1n}^2 - 1\right] \cdot \sin^2(\beta - \theta)}}$$

$$M_2 = \sqrt{\frac{1 + \frac{2}{(k-1) \cdot M_{1n}^2}}{\left[\left(\frac{2 \cdot k}{k-1}\right) - \frac{1}{M_{1n}^2}\right] \cdot \sin^2(\beta - \theta)}}$$

As  $M_1$  goes to infinity, so does  $M_{1n}$ , so

$$M_2 = \sqrt{\frac{1}{\left(\frac{2 \cdot k}{k-1}\right) \cdot \sin^2(\beta - \theta)}} \quad M_2 = \sqrt{\frac{k-1}{2 \cdot k \cdot \sin^2(\beta - \theta)}}$$

## Problem 13.181

[Difficulty: 3]

**13.181** Air at 400 K and 100 kPa is flowing at a Mach number of 1.8 and is deflected through a  $14^\circ$  angle. The directional change is accompanied by an oblique shock. What are the possible shock angles? For each of these shock angles, what is the pressure and temperature after the shock?

**Given:** Air deflected at an angle, causing an oblique shock

**Find:** Possible shock angles; pressure and temperature corresponding to those angles

**Solution:**

The given or available data is:

$R =$	286.9	J/kg-K
$k =$	1.4	
$M_1 =$	1.8	
$T_1 =$	400	K
$p_1 =$	100	kPa
$\theta =$	14	$^\circ$

Equations and Computations:

There are two possible shock angles for a given deflection, corresponding to the weak and strong shock solutions. To find the shock angle, we have to iterate on the shock angle until we match the deflection angle, which is a function of Mach number, specific heat ratio, and shock angle.

The weak shock solution is:

$$\begin{aligned}\beta_{\text{weak}} &= 49.7^\circ \\ \theta &= 14.0000^\circ\end{aligned}$$

The strong shock solution is:

$$\begin{aligned}\beta_{\text{strong}} &= 78.0^\circ \\ \theta &= 14.0000^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angles.

For the weak shock, the pre-shock Mach number normal to the wave is:

$$M_{1\text{weak}} = 1.3720$$

The pressure and temperature ratios across the shock wave are:

$$p_2/p_{1\text{weak}} = 2.0295$$

$$T_2/T_{1\text{weak}} = 1.2367$$

Therefore, the post-shock temperature and pressure are:

$$p_{2\text{weak}} = 203 \text{ kPa}$$

$$T_{2\text{weak}} = 495 \text{ K}$$

For the strong shock, the pre-shock Mach number normal to the wave is:

$$M_{1\text{strong}} = 1.7608$$

The pressure and temperature ratios across the shock wave are:

$$p_2/p_{1\text{strong}} = 3.4505$$

$$T_2/T_{1\text{strong}} = 1.5025$$

Therefore, the post-shock temperature and pressure are:

$$p_{2\text{strong}} = 345 \text{ kPa}$$

$$T_{2\text{strong}} = 601 \text{ K}$$

## Problem 13.182

[Difficulty: 3]

---

**13.182** Consider supersonic flow of air at  $M_1 = 3.0$ . What is the range of possible values of the oblique shock angle  $\beta$ ? For this range of  $\beta$ , plot the pressure ratio across the shock.

---

**Given:** Oblique shock in flow at  $M = 3$

**Find:** Minimum and maximum  $\beta$ , plot of pressure rise across shock

**Solution:**

The given or available data is:

$R =$	286.9	J/kg.K
$k =$	1.4	
$M_1 =$	3	

Equations and Computations:

The smallest value of  $\beta$  is when the shock is a Mach wave (no deflection)

$$\beta = \sin^{-1}(1/M_1)$$

$$\beta = 19.5^\circ$$

The largest value is  $\beta = 90.0^\circ$

The normal component of Mach number is


$$M_{1n} = M_1 \sin(\beta) \quad (13.47a)$$

For each  $\beta$ ,  $p_2/p_1$  is obtained from  $M_{1n}$ , and Eq. 13.48d (using built-in function *NormpfromM(M,k)*)

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

Computed results:

$\beta$ (°)	$M_{1n}$	$p_2/p_1$
19.5	1.00	1.00
20	1.03	1.06
30	1.50	2.46
40	1.93	4.17
50	2.30	5.99
60	2.60	7.71
70	2.82	9.11
75	2.90	9.63
80	2.95	10.0
85	2.99	10.3
90	3.00	10.3



## Problem 13.183

[Difficulty: 3]

**13.183** Supersonic air flow at  $M_1 = 2.5$  and 80 kPa (abs) is deflected by an oblique shock with angle  $\beta = 35^\circ$ . Find the Mach number and pressure after the shock, and the deflection angle. Compare these results to those obtained if instead the flow had experienced a normal shock. What is the smallest possible value of angle  $\beta$  for this upstream Mach number?

**Given:** Data on an oblique shock

**Find:** Mach number and pressure downstream; compare to normal shock

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg}\cdot\text{K} \\ k &= 1.4 \\ p_1 &= 80 && \text{kPa} \\ M_1 &= 2.5 \\ \beta &= 35 && ^\circ \end{aligned}$$

Equations and Computations:

$$\begin{aligned} \text{From } M_1 \text{ and } \beta \quad M_{1n} &= 1.43 \\ M_{1t} &= 2.05 \end{aligned}$$

From  $M_{1n}$  and  $p_1$ , and Eq. 13.48d  
(using built-in function  $NormpfromM(M,k)$ )

$$\begin{aligned} \frac{p_2}{p_1} &= \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} && (13.48d) \\ p_2 &= 178.6 && \text{kPa} \end{aligned}$$

The tangential velocity is unchanged

$$V_{t1} = V_{t2}$$

Hence

$$\begin{aligned} c_{t1} M_{t1} &= c_{t2} M_{t2} \\ (T_1)^{1/2} M_{t1} &= (T_2)^{1/2} M_{t2} \\ M_{2t} &= (T_1/T_2)^{1/2} M_{t1} \end{aligned}$$

From  $M_{1n}$ , and Eq. 13.48c  
(using built-in function  $NormTfromM(M,k)$ )

$$T_2/T_1 = 1.28$$

$$\text{Hence} \quad M_{2t} = 1.81$$

Also, from  $M_{1n}$ , and Eq. 13.48a  
(using built-in function  $NormM2fromM(M,k)$ )

$$M_{2n}^2 = \frac{M_{1n}^2 + \frac{2}{k-1}}{\frac{2k}{k-1}M_{1n}^2 - 1} \quad (13.48a)$$

$$M_{2n} = 0.726$$

The downstream Mach number is then

$$M_2 = (M_{2t}^2 + M_{2n}^2)^{1/2}$$

$$M_2 = 1.95$$

Finally, from geometry

$$V_{2n} = V_2 \sin(\beta - \theta)$$

Hence 
$$\theta = \beta - \sin^{-1}(V_{2n}/V_2)$$

or 
$$\theta = \beta - \sin^{-1}(M_{2n}/M_2)$$

$$\theta = 13.2^\circ$$

**For the normal shock:**

From  $M_1$  and  $p_1$ , and Eq. 13.48d  
(using built-in function  $NormpfromM(M,k)$ )

$$p_2 = 570 \text{ kPa}$$

Also, from  $M_1$ , and Eq. 13.48a  
(using built-in function  $NormM2fromM(M,k)$ )

$$M_2 = 0.513$$

**For the minimum  $\beta$ :**

The smallest value of  $\beta$  is when the shock is a Mach wave (no deflection)

$$\beta = \sin^{-1}(1/M_1)$$

$$\beta = 23.6^\circ$$

## Problem 13.184

[Difficulty: 3]

**13.184** The temperature and Mach number before an oblique shock are  $T_1 = 10^\circ\text{C}$  and  $M_1 = 3.25$ , respectively, and the pressure ratio across the shock is 5. Find the deflection angle,  $\theta$ , the shock angle,  $\beta$ , and the Mach number after the shock,  $M_2$ .

**Given:** Data on an oblique shock

**Find:** Deflection angle  $\theta$ ; shock angle  $\beta$ ; Mach number after shock

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 286.9 && \text{J/kg.K} \\k &= 1.4 \\M_1 &= 3.25 \\T_1 &= 283 && \text{K} \\p_2/p_1 &= 5\end{aligned}$$

Equations and Computations:

From  $p_2/p_1$ , and Eq. 13.48d  
(using built-in function *NormpfromM(M,k)*  
and *Goal Seek* or *Solver*)

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

For  $p_2/p_1 = 5.00$

$$M_{1n} = 2.10$$

From  $M_1$  and  $M_{1n}$ , and Eq 13.47a

$$M_{1n} = M_1 \sin(\beta) \quad (13.47a)$$

$$\beta = 40.4^\circ$$

From  $M_1$  and  $\beta$ , and Eq. 13.49  
 (using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

$$\theta = 23.6^\circ$$

To find  $M_2$  we need  $M_{2n}$ . From  $M_{1n}$ , and Eq. 13.48a  
 (using built-in function  $\text{NormM2fromM}(M, k)$ )

$$M_{2n}^2 = \frac{M_{1n}^2 + \frac{2}{k-1}}{\frac{2k}{k-1} M_{1n}^2 - 1} \quad (13.48a)$$

$$M_{2n} = 0.561$$

The downstream Mach number is then obtained from  
 from  $M_{2n}$ ,  $\theta$  and  $\beta$ , and Eq. 13.47b

$$M_{2n} = M_2 \sin(\beta - \theta) \quad (13.47b)$$

Hence  $M_2 = 1.94$

## Problem 13.185

[Difficulty: 3]

---

**13.185** The air velocities before and after an oblique shock are 1250 m/s and 650 m/s, respectively, and the deflection angle is  $\theta = 35^\circ$ . Find the oblique shock angle  $\beta$ , and the pressure ratio across the shock.

---

**Given:** Velocities and deflection angle of an oblique shock

**Find:** Shock angle  $\beta$ ; pressure ratio across shock

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg.K} \\ k &= 1.4 \\ V_1 &= 1250 && \text{m/s} \\ V_2 &= 650 && \text{m/s} \\ \theta &= 35 && ^\circ \end{aligned}$$

Equations and Computations:

From geometry we can write two equations for tangential velocity:

$$\text{For } V_{1t} \qquad V_{1t} = V_1 \cos(\beta) \qquad (1)$$

$$\text{For } V_{2t} \qquad V_{2t} = V_2 \cos(\beta - \theta) \qquad (2)$$

For an oblique shock  $V_{2t} = V_{1t}$ , so Eqs. 1 and 2 give

$$V_1 \cos(\beta) = V_2 \cos(\beta - \theta) \qquad (3)$$

$$\text{Solving for } \beta \qquad \beta = \tan^{-1}((V_1 - V_2 \cos(\theta))/(V_2 \sin(\theta)))$$

$$\beta = 62.5 \quad ^\circ$$

(Alternatively, solve Eq. 3 using *Goal Seek* !)

For  $p_2/p_1$ , we need  $M_{1n}$  for use in Eq. 13.48d

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

We can compute  $M_1$  from  $\theta$  and  $\beta$ , and Eq. 13.49  
(using built-in function  $Theta(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

For

$$\begin{aligned} \theta &= 35.0^\circ \\ \beta &= 62.5^\circ \\ M_1 &= 3.19 \end{aligned}$$

This value of  $M_1$  was obtained by using *Goal Seek* :

Vary  $M_1$  so that  $\theta$  becomes the required value.

(Alternatively, find  $M_1$  from Eq. 13.49 by explicitly solving for it!)

We can now find  $M_{1n}$  from  $M_1$ . From  $M_1$  and Eq. 13.47a

$$M_{1n} = M_1 \sin(\beta) \quad (13.47a)$$

Hence

$$M_{1n} = 2.83$$


Finally, for  $p_2/p_1$ , we use  $M_{1n}$  in Eq. 13.48d  
(using built-in function  $NormpfromM(M, k)$ )

$$p_2/p_1 = 9.15$$

## Problem 13.186

[Difficulty: 4]

**13.186** An airfoil has a sharp leading edge with an included angle of  $\delta = 60^\circ$ . It is being tested in a wind tunnel running at 1200 m/s (the air pressure and temperature upstream are 75 kPa and  $3.5^\circ\text{C}$ ). Plot the pressure and temperature in the region adjacent to the upper surface as functions of angle of attack,  $\alpha$ , ranging from  $\alpha = 0^\circ$  to  $30^\circ$ . What are the maximum pressure and temperature? (Ignore the possibility of a detached shock developing if  $\alpha$  is too large; see Problem 13.189.)



**Given:** Airfoil with included angle of  $60^\circ$

**Find:** Plot of temperature and pressure as functions of angle of attack

**Solution:**

The given or available data is:

$$\begin{aligned}
 R &= 286.9 && \text{J/kg}\cdot\text{K} \\
 k &= 1.4 \\
 T_1 &= 276.5 && \text{K} \\
 p_1 &= 75 && \text{kPa} \\
 V_1 &= 1200 && \text{m/s} \\
 \delta &= 60 && ^\circ
 \end{aligned}$$

Equations and Computations:

$$\text{From } T_1 \qquad c_1 = 333 \quad \text{m/s}$$

$$\text{Then} \qquad M_1 = 3.60$$

Computed results:



$\alpha$ ( $^\circ$ )	$\beta$ ( $^\circ$ )	$\theta$ ( $^\circ$ ) Needed	$\theta$ ( $^\circ$ )	Error	$M_{1n}$	$p_2$ (kPa)	$T_2$ ( $^\circ\text{C}$ )
0.00	47.1	30.0	30.0	0.0%	2.64	597	357
2.00	44.2	28.0	28.0	0.0%	2.51	539	321
4.00	41.5	26.0	26.0	0.0%	2.38	485	287
6.00	38.9	24.0	24.0	0.0%	2.26	435	255
8.00	36.4	22.0	22.0	0.0%	2.14	388	226
10.00	34.1	20.0	20.0	0.0%	2.02	344	198
12.00	31.9	18.0	18.0	0.0%	1.90	304	172
14.00	29.7	16.0	16.0	0.0%	1.79	267	148
16.00	27.7	14.0	14.0	0.0%	1.67	233	125
18.00	25.7	12.0	12.0	0.0%	1.56	202	104
20.00	23.9	10.0	10.0	0.0%	1.46	174	84
22.00	22.1	8.0	8.0	0.0%	1.36	149	66
24.00	20.5	6.0	6.0	0.0%	1.26	126	49
26.00	18.9	4.0	4.0	0.0%	1.17	107	33
28.00	17.5	2.0	2.0	0.0%	1.08	90	18
30.00	16.1	0.0	-	0.0%	1.00	75	3

Sum: 0.0%

Max: 597 357

To compute this table:

- 1) Type the range of  $\alpha$
- 2) Type in guess values for  $\beta$
- 3) Compute  $\theta_{\text{Needed}}$  from  $\theta = \delta/2 - \alpha$
- 4) Compute  $\theta$  from Eq. 13.49  
(using built-in function  $\text{Theta}(M, \beta, k)$ )
- 5) Compute the absolute error between each  $\theta$  and  $\theta_{\text{Needed}}$
- 6) Compute the sum of the errors
- 7) Use *Solver* to minimize the sum by varying the  $\beta$  values  
(Note: You may need to interactively type in new  $\beta$  values if *Solver* generates  $\beta$  values that lead to no  $\theta$ )
- 8) For each  $\alpha$ ,  $M_{1n}$  is obtained from  $M_1$ , and Eq. 13.47a
- 9) For each  $\alpha$ ,  $p_2$  is obtained from  $p_1$ ,  $M_{1n}$ , and Eq. 13.48d  
(using built-in function  $\text{NormpfromM}(M, k)$ )
- 10) For each  $\alpha$ ,  $T_2$  is obtained from  $T_1$ ,  $M_{1n}$ , and Eq. 13.48c  
(using built-in function  $\text{NormTfromM}(M, k)$ )



## Problem 13.187

[Difficulty: 4]

**13.187** An airfoil at zero angle of attack has a sharp leading edge with an included angle of  $20^\circ$ . It is being tested over a range of speeds in a wind tunnel. The air temperature upstream is maintained at  $15^\circ\text{C}$ . Determine the Mach number and corresponding air speed at which a detached normal shock first attaches to the leading edge, and the angle of the resulting oblique shock. Plot the oblique shock angle  $\beta$  as a function of upstream Mach number  $M_1$ , from the minimum attached-shock value through  $M_1 = 7$ .

**Given:** Airfoil with included angle of  $20^\circ$

**Find:** Mach number and speed at which oblique shock forms

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg}\cdot\text{K} \\ k &= 1.4 \\ T_1 &= 288 && \text{K} \\ \theta &= 10 && ^\circ \end{aligned}$$

Equations and Computations:




Fig. 13.29 Oblique shock deflection angle.

From Fig. 13.29 the smallest Mach number for which an oblique shock exists at a deflection  $\theta = 10^\circ$  is approximately  $M_1 = 1.4$ .

By trial and error, a more precise answer is  
(using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\begin{aligned} M_1 &= 1.42 \\ \beta &= 67.4 && ^\circ \\ \theta &= 10.00 && ^\circ \\ c_1 &= 340 && \text{m/s} \\ V_1 &= 483 && \text{m/s} \end{aligned}$$

A suggested procedure is:

- 1) Type in a guess value for  $M_1$
- 2) Type in a guess value for  $\beta$

- 3) Compute  $\theta$  from Eq. 13.49  
 (using built-in function  $Theta(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

- 4) Use *Solver* to maximize  $\theta$  by varying  $\beta$   
 5) If  $\theta$  is not  $10^\circ$ , make a new guess for  $M_1$   
 6) Repeat steps 1 - 5 until  $\theta = 10^\circ$


Computed results:

$M_1$	$\beta$ ( $^\circ$ )	$\theta$ ( $^\circ$ )	Error
1.42	67.4	10.0	0.0%
1.50	56.7	10.0	0.0%
1.75	45.5	10.0	0.0%
2.00	39.3	10.0	0.0%
2.25	35.0	10.0	0.0%
2.50	31.9	10.0	0.0%
3.00	27.4	10.0	0.0%
4.00	22.2	10.0	0.0%
5.00	19.4	10.0	0.0%
6.00	17.6	10.0	0.0%
7.00	16.4	10.0	0.0%

Sum:

To compute this table:

- 1) Type the range of  $M_1$
- 2) Type in guess values for  $\beta$
- 3) Compute  $\theta$  from Eq. 13.49  
 (using built-in function  $Theta(M, \beta, k)$ )
- 4) Compute the absolute error between each  $\theta$  and  $\theta = 10^\circ$
- 5) Compute the sum of the errors
- 6) Use *Solver* to minimize the sum by varying the  $\beta$  values  
 (Note: You may need to interactively type in new  $\beta$  values  
 if *Solver* generates  $\beta$  values that lead to no  $\theta$ , or to  
 $\beta$  values that correspond to a strong rather than weak shock)




## Problem 13.188

[Difficulty: 3]

**13.188** The wedge-shaped airfoil shown has chord  $c = 1.5$  m and included angle  $\delta = 7^\circ$ . Find the lift per unit span at a Mach number of 2.75 in air for which the static pressure is 70 kPa.

**Given:** Data on airfoil flight

**Find:** Lift per unit span



**Solution:**

The given or available data is:

$R =$	286.9	J/kg.K
$k =$	1.4	
$p_1 =$	70	kPa
$M_1 =$	2.75	
$\delta =$	7	°
$c =$	1.5	m

Equations and Computations:

The lift per unit span is

$$L = (p_L - p_U)c \quad (1)$$

(Note that  $p_L$  acts on area  $c/\cos(\delta)$ , but its normal component is multiplied by  $\cos(\delta)$ )

**For the upper surface:**

$$p_U = p_1$$
$$p_U = 70.0 \quad \text{kPa}$$

**For the lower surface:**

We need to find  $M_{1n}$

The deflection angle is  $\theta = \delta$

$$\theta = 7^\circ$$

From  $M_1$  and  $\theta$ , and Eq. 13.49

(using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

$$\begin{aligned} \text{For } \theta &= 7.0^\circ \\ \beta &= 26.7^\circ \end{aligned}$$

(Use *Goal Seek* to vary  $\beta$  so that  $\theta = \delta$ )

From  $M_1$  and  $\beta$   $M_{1n} = 1.24$

From  $M_{1n}$  and  $p_1$ , and Eq. 13.48d

(using built-in function  $\text{NormpfromM}(M, k)$ )

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

$$p_2 = 113 \text{ kPa}$$

$$p_L = p_2$$


$$p_L = 113 \text{ kPa}$$

From Eq 1  $L = 64.7 \text{ kN/m}$

### Problem 13.189

[Difficulty: 4]

**13.189** The airfoil of Problem 13.186 will develop a detached shock on the lower surface if the angle of attack,  $\alpha$ , exceeds a certain value. What is this angle of attack? Plot the pressure and temperature in the region adjacent to the lower surface as functions of angle of attack,  $\alpha$ , ranging from  $\alpha = 0^\circ$  to the angle at which the shock becomes detached. What are the maximum pressure and temperature?



**Given:** Airfoil with included angle of  $60^\circ$

**Find:** Angle of attack at which oblique shock becomes detached

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg}\cdot\text{K} \\ k &= 1.4 \\ T_1 &= 276.5 && \text{K} \\ p_1 &= 75 && \text{kPa} \\ V_1 &= 1200 && \text{m/s} \\ \delta &= 60 && ^\circ \end{aligned}$$

Equations and Computations:

$$\text{From } T_1 \quad c_1 = 333 \quad \text{m/s}$$

$$\text{Then} \quad M_1 = 3.60$$

From Fig. 13.29, at this Mach number the smallest deflection angle for which an oblique shock exists is approximately  $\theta = 35^\circ$ .




Fig. 13.29 Oblique shock deflection angle.

By using *Solver*, a more precise answer is  
(using built-in function  $\Theta(M, \beta, k)$ )

$$\begin{aligned} M_1 &= 3.60 \\ \beta &= 65.8 && ^\circ \\ \theta &= 37.3 && ^\circ \end{aligned}$$

A suggested procedure is:

- 1) Type in a guess value for  $\beta$
- 2) Compute  $\theta$  from Eq. 13.49  
(using built-in function  $\Theta(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

- 3) Use *Solver* to maximize  $\theta$  by varying  $\beta$

For a deflection angle  $\theta$  the angle of attack  $\alpha$  is

$$\begin{aligned} \alpha &= \theta - \delta/2 \\ \alpha &= 7.31 && ^\circ \end{aligned}$$



Computed results:

$\alpha$ (°)	$\beta$ (°)	$\theta$ (°) Needed	$\theta$ (°)	Error	$M_{1n}$	$p_2$ (kPa)	$T_2$ (°C)
0.00	47.1	30.0	30.0	0.0%	2.64	597	357
1.00	48.7	31.0	31.0	0.0%	2.71	628	377
2.00	50.4	32.0	32.0	0.0%	2.77	660	397
3.00	52.1	33.0	33.0	0.0%	2.84	695	418
4.00	54.1	34.0	34.0	0.0%	2.92	731	441
5.50	57.4	35.5	35.5	0.0%	3.03	793	479
5.75	58.1	35.8	35.7	0.0%	3.06	805	486
6.00	58.8	36.0	36.0	0.0%	3.08	817	494
6.25	59.5	36.3	36.2	0.0%	3.10	831	502
6.50	60.4	36.5	36.5	0.0%	3.13	845	511
6.75	61.3	36.8	36.7	0.0%	3.16	861	521
7.00	62.5	37.0	37.0	0.0%	3.19	881	533
7.25	64.4	37.3	37.2	0.0%	3.25	910	551
7.31	65.8	37.3	37.3	0.0%	3.28	931	564

Sum:  Max:

To compute this table:

- 1) Type the range of  $\alpha$
- 2) Type in guess values for  $\beta$
- 3) Compute  $\theta_{\text{Needed}}$  from  $\theta = \alpha + \delta/2$
- 4) Compute  $\theta$  from Eq. 13.49  
(using built-in function *Theta* ( $M, \beta, k$ ))
- 5) Compute the absolute error between each  $\theta$  and  $\theta_{\text{Needed}}$
- 6) Compute the sum of the errors
- 7) Use *Solver* to minimize the sum by varying the  $\beta$  values  
(Note: You may need to interactively type in new  $\beta$  values if *Solver* generates  $\beta$  values that lead to no  $\theta$ )
- 8) For each  $\alpha$ ,  $M_{1n}$  is obtained from  $M_1$ , and Eq. 13.47a
- 9) For each  $\alpha$ ,  $p_2$  is obtained from  $p_1$ ,  $M_{1n}$ , and Eq. 13.48d  
(using built-in function *NormpfromM* ( $M, k$ ))
- 10) For each  $\alpha$ ,  $T_2$  is obtained from  $T_1$ ,  $M_{1n}$ , and Eq. 13.48c  
(using built-in function *NormTfromM* ( $M, k$ ))



## Problem 13.190

[Difficulty: 3]

**13.190** An oblique shock causes a flow that was at  $M = 4$  and a static pressure of 75 kPa to slow down to  $M = 2.5$ . Find the deflection angle and the static pressure after the shock.

**Given:** Oblique shock Mach numbers

**Find:** Deflection angle; Pressure after shock

**Solution:**

The given or available data is:

$$\begin{aligned}k &= 1.4 \\p_1 &= 75 \quad \text{kPa} \\M_1 &= 4 \\M_2 &= 2.5\end{aligned}$$

Equations and Computations:

We make a guess for  $\beta$ :  $\beta = 33.6^\circ$

From  $M_1$  and  $\beta$ , and Eq. 13.49 (using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

$$\theta = 21.0^\circ$$

From  $M_1$  and  $\beta$

$$M_{1n} = 2.211$$

From  $M_2$ ,  $\theta$ , and  $\beta$

$$M_{2n} = 0.546 \quad (1)$$

We can also obtain  $M_{2n}$  from Eq. 13.48a (using built-in function  $\text{normM2fromM}(M, k)$ )

$$M_{2n}^2 = \frac{M_{1n}^2 + \frac{2}{k-1}}{\frac{2k}{k-1} M_{1n}^2 - 1} \quad (13.48a)$$

$$M_{2n} = 0.546 \quad (2)$$

We need to manually change  $\beta$  so that Eqs. 1 and 2 give the same answer.

Alternatively, we can compute the difference between 1 and 2, and use *Solver* to vary  $\beta$  to make the difference zero

$$\text{Error in } M_{2n} = 0.00\%$$

Then  $p_2$  is obtained from Eq. 13.48d (using built-in function  $\text{normpfromm}(M, k)$ )


$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

$$p_2 = 415 \quad \text{kPa}$$

## Problem 13.191

[Difficulty: 3]

**13.191** The wedge-shaped airfoil shown has chord  $c = 2$  m and angles  $\delta_{\text{lower}} = 15^\circ$  and  $\delta_{\text{upper}} = 5^\circ$ . Find the lift per unit span at a Mach number of 2.75 in air at a static pressure of 75 kPa.



**Given:** Data on airfoil flight

**Find:** Lift per unit span

**Solution:**

The given or available data is:

$R =$	286.9	J/kg.K
$k =$	1.4	
$p_1 =$	75	kPa
$M_1 =$	2.75	
$\delta_U =$	5	$^\circ$
$\delta_L =$	15	$^\circ$
$c =$	2	m

Equations and Computations:

The lift per unit span is

$$L = (p_L - p_U)c \quad (1)$$

(Note that each  $p$  acts on area  $c/\cos(\delta)$ , but its normal component is multiplied by  $\cos(\delta)$ )

**For the upper surface:**

We need to find  $M_{1n(U)}$

The deflection angle is

$$\theta_U = \delta_U$$

$$\theta_U = 5 \quad ^\circ$$

From  $M_1$  and  $\theta_U$ , and Eq. 13.49

(using built-in function  $\theta(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

For  $\theta_U = 5.00 \quad ^\circ$

$\beta_U = 25.1 \quad ^\circ$

(Use *Goal Seek* to vary  $\beta_U$  so that  $\theta_U = \delta_U$ )

From  $M_1$  and  $\beta_U$   $M_{1n(U)} = 1.16$

From  $M_{1n(U)}$  and  $p_1$ , and Eq. 13.48d  
(using built-in function *NormpfromM(M,k)*)

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

$$p_2 = 106 \quad \text{kPa}$$

$$p_U = p_2$$

$$p_U = 106 \quad \text{kPa}$$

**For the lower surface:**

We need to find  $M_{1n(L)}$

The deflection angle is  $\theta_L = \delta_L$

$$\theta_L = 15 \quad ^\circ$$

From  $M_1$  and  $\theta_L$ , and Eq. 13.49  
(using built-in function *Theta(M, beta,k)*)

$$\text{For } \theta_L = 15.00 \quad ^\circ$$

$$\beta_L = 34.3 \quad ^\circ$$

(Use *Goal Seek* to vary  $\beta_L$  so that  $\theta_L = \delta_L$ )

From  $M_1$  and  $\beta_L$   $M_{1n(L)} = 1.55$

From  $M_{1n(L)}$  and  $p_1$ , and Eq. 13.48d  
(using built-in function *NormpfromM(M,k)*)

$$p_2 = 198 \quad \text{kPa}$$

$$p_L = p_2$$

$$p_L = 198 \quad \text{kPa}$$

From Eq 1  $L = 183 \quad \text{kN/m}$

## Problem 13.192

[Difficulty: 3]

**13.192** Air flows at a Mach number of 3.3, with static conditions of 100°F and 20 psia. An oblique shock is observed at an angle of 45° relative to the flow. Calculate the post-shock conditions (pressure, temperature, Mach number). What is the deflection angle for the flow? Is this a strong or a weak shock?

**Given:** Air deflected at an angle, causing an oblique shock

**Find:** Post shock pressure, temperature, and Mach number, deflection angle, strong or weak

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.4 \\M_1 &= 3.3 \\T_1 &= 100 && ^\circ\text{F} \\T_1 &= 560 && ^\circ\text{R} \\p_1 &= 20 && \text{psia} \\\beta &= 45 && ^\circ\end{aligned}$$

Equations and Computations:

The pre-shock Mach numbers normal and parallel to the wave are:

$$\begin{aligned}M_{1n} &= 2.3335 \\M_{1t} &= 2.3335\end{aligned}$$

The sound speed upstream of the shock is:

$$c_1 = 1160.30 \quad \text{ft/s}$$

Therefore, the speed of the flow parallel to the wave is:

$$V_{1t} = 2707.51 \quad \text{ft/s}$$

The post-shock Mach number normal to the wave is:

$$M_{2n} = 0.5305$$

The pressure and temperature ratios across the shock wave are:

$$\begin{aligned}p_2/p_1 &= 6.1858 \\T_2/T_1 &= 1.9777\end{aligned}$$

Therefore, the post-shock temperature and pressure are:

$$\begin{aligned}p_2 &= 124 && \text{psia} \\T_2 &= 1108 && ^\circ\text{R} \\T_2 &= 648 && ^\circ\text{F}\end{aligned}$$

The sound speed downstream of the shock is:

$$c_2 = 1631.74 \quad \text{ft/s}$$

So the speed of the flow normal to wave is:

$$V_{2n} = 865.63 \quad \text{ft/s}$$

The speed of the flow parallel to the wave is preserved through the shock:

$$V_{2t} = 2707.51 \quad \text{ft/s}$$

Therefore the flow speed after the shock is:

$$V_2 = 2842.52 \quad \text{ft/s}$$

and the Mach number is:

$$M_2 = 1.742$$

Based on the Mach number and shock angle, the deflection angle is:

$$\theta = 27.3 \quad ^\circ$$

Since the Mach number at 2 is supersonic, this is a **weak** wave. This can be confirmed by inspecting Fig. 13.29 in the text.

## Problem 13.193

[Difficulty: 3]

**13.193** Air entering the inlet of a jet engine is turned through an angle of  $8^\circ$ , creating an oblique shock. If the freestream flow of air is at Mach 4 and 8 psia, what is the pressure after the oblique shock? What would the pressure be if the flow were through two separate  $4^\circ$  wedges instead of a single  $8^\circ$  wedge?

**Given:** Air passing through jet inlet

**Find:** Pressure after one oblique shock; pressure after two shocks totaling same overall turn

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.4 \\M_1 &= 4 \\p_1 &= 8 && \text{psia} \\ \theta &= 8 && ^\circ\end{aligned}$$

Equations and Computations:

To find the shock angle, we have to iterate on the shock angle until we match the deflection angle, which is a function of Mach number, specific heat ratio, and shock angle.

$$\begin{aligned}\beta &= 20.472 && ^\circ \\ \theta &= 8.0000 && ^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach number normal to the wave is:

$$M_{1n} = 1.3990$$

The pressure ratio across the shock wave is:

$$p_2/p_1 = 2.1167$$

Therefore, the post-shock pressure is:

$$p_2 = 16.93 \text{ psia}$$

Now if we use two 4-degree turns, we perform two oblique-shock calculations.

For the first turn:

$$\begin{aligned}\beta_{1-2a} &= 17.258 && ^\circ \\ \theta &= 4.0000 && ^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach number normal to the wave is:

$$M_{1n} = 1.1867$$

The post-shock Mach number normal to the wave is:

$$M_{2an} = 0.8506$$

The pressure ratio across the shock wave is:

$$p_{2a}/p_1 = 1.4763$$

Therefore, the post-shock pressure is:

$$p_{2a} = 11.8100 \text{ psia}$$

So the Mach number after the first shock wave is:

$$M_{2a} = 3.7089$$

For the second turn:

$$\beta_{2a-2b} = 18.438^\circ$$
$$\theta = 4.0000^\circ$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach number normal to the wave is:

$$M_{2an} = 1.1731$$

The post-shock Mach number normal to the wave is:

$$M_{2bn} = 0.8594$$

The pressure ratio across the shock wave is:

$$p_{2b}/p_{2a} = 1.4388$$

Therefore, the post-shock pressure is:

$$p_{2b} = 16.99 \text{ psia}$$

The pressure recovery is slightly better for two weaker shocks than a single stronger one!

## Problem 13.194

[Difficulty: 4]

**13.194** Air having an initial Mach number of 2.3 and static conditions of 14.7 psia and 80°F is turned through an angle of 10°. The resulting shock at the corner is reflected from the opposite wall, turning the flow back 10° to its original direction. Calculate the pressure, temperature, and Mach number after the initial and reflected shock waves.

**Given:** Air turning through an incident and reflected shock wave

**Find:** Pressure, temperature, and Mach number after each wave

**Solution:**

The given or available data is:

$R =$	53.33	ft-lbf/lbm-°R
$k =$	1.4	
$M_1 =$	2.3	
$p_1 =$	14.7	psia
$T_1 =$	80	°F
$T_1 =$	540	°R
$\theta =$	10	°

Equations and Computations:

To find the shock angle, we have to iterate on the shock angle until we match the deflection angle, which is a function of Mach number, specific heat ratio, and shock angle.

For the first turn:

$$\begin{aligned}\beta_{1-2} &= 34.326 \text{ }^\circ \\ \theta &= 10.0000 \text{ }^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach numbers normal and parallel to the wave are:

$$\begin{aligned}M_{1n} &= 1.2970 \\ M_{1t} &= 1.8994\end{aligned}$$

The post-shock Mach number normal to the wave is:

$$M_{2n} = 0.7875$$

The pressure and temperature ratios across the shock wave are:

$$\begin{aligned}p_2/p_1 &= 1.7959 \\ T_2/T_1 &= 1.1890\end{aligned}$$

Therefore, the post-shock pressure and temperature are:

$$\begin{aligned}p_2 &= 26.4 \text{ psia} \\ T_2 &= 642 \text{ }^\circ\text{R}\end{aligned}$$

Since the parallel component of velocity is preserved across the shock and the Mach number is related to the square root of temperature, the new parallel component of Mach number is:

$$M_{2t} = 1.7420$$

So the Mach number after the first shock wave is:

$$M_2 = 1.912$$

For the second turn:

$$\begin{aligned}\beta_{2-3} &= 41.218 \text{ }^\circ \\ \theta &= 10.0000 \text{ }^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach numbers normal and parallel to the wave are:

$$M_{1n} = 1.2597$$

$$M_{1t} = 1.4380$$

The post-shock Mach number normal to the wave is:

$$M_{2an} = 0.8073$$

The pressure and temperature ratios across the shock wave are:

$$p_3/p_2 = 1.6845$$

$$T_2/T_1 = 1.1654$$

Therefore, the post-shock pressure is:

$$p_3 = 44.5 \text{ psia}$$

$$T_3 = 748 \text{ }^\circ\text{R}$$

Since the parallel component of velocity is preserved across the shock and the Mach number is related to the square root of temperature, the new parallel component of Mach number is:

$$M_{2t} = 1.3320$$

So the Mach number after the second shock wave is:

$$M_2 = 1.558$$

## Problem 13.195

[Difficulty: 3]

---

**13.195** A wedge-shaped projectile (half angle is  $10^\circ$ ) is launched through air at 1 psia and  $10^\circ\text{F}$ . If the static pressure measurement on the surface of the wedge is 3 psia, calculate the speed at which the projectile is moving through the air.

---

**Given:** Wedge-shaped projectile

**Find:** Speed at which projectile is traveling through the air

**Solution:**

The given or available data is:

$R =$	53.33	ft-lbf/lbm- $^\circ\text{R}$
$k =$	1.4	
$p_1 =$	1	psia
$T_1 =$	10	$^\circ\text{F}$
$T_1 =$	470	$^\circ\text{R}$
$\theta =$	10	$^\circ$
$p_2 =$	3	psia

Equations and Computations:

The pressure ratio across the shock wave is:

$$p_2/p_1 = 3.0000$$

For this pressure ratio, we can iterate to find the Mach number of the flow normal to the shock wave:

$$\begin{aligned}M_{1n} &= 1.6475 \\ p_2/p_1 &= 3.0000\end{aligned}$$

We used *Solver* in *Excel* to iterate on the Mach number.

With the normal Mach number, we can iterate on the incident Mach number to find the right combination of Mach number and shock angle to match the turning angle of the flow and normal Mach number:

$$\begin{aligned}M_1 &= 4.9243 \\ \beta_{1-2} &= 19.546^\circ \\ \theta &= 10.0000^\circ\end{aligned}$$

The pre-shock Mach numbers normal and parallel to the wave are:

$$\begin{aligned}M_{1n} &= 1.6475 \\ M_{1t} &= 4.6406\end{aligned}$$

We used *Solver* in *Excel* to iterate on the Mach number and shock angle.

Now that we have the upstream Mach number, we can find the speed. The sound speed upstream of the shock wave is:

$$c_1 = 1062.9839 \text{ ft/s}$$

Therefore, the speed of the flow relative to the wedge is:

$$V_1 = 5234 \text{ ft/s}$$

## Problem 13.196

[Difficulty: 4]

---

**13.196** Air at Mach 2 and 1 atmosphere is turned through an expansion of  $16^\circ$ , followed by another turn of  $16^\circ$ , causing an oblique shock wave. Calculate the Mach number and pressure downstream of the oblique shock.

---

**Given:** Flow turned through an expansion followed by a oblique shock wave

**Find:** Mach number and pressure downstream of the shock wave

**Solution:**

The given or available data is:

$R =$	53.33	ft-lbf/lbm-°R
$k =$	1.4	
$M_1 =$	2	
$p_1 =$	1	atm
$\theta =$	16	°

Equations and Computations:

The Prandtl-Meyer function of the flow before the expansion is:

$$\omega_1 = 26.380^\circ$$

Since we know the turning angle of the flow, we know the Prandtl-Meyer function after the expansion:

$$\omega_2 = 42.380^\circ$$

We can iterate to find the Mach number after the expansion:

$$M_2 = 2.6433$$
$$\omega_2 = 42.380^\circ$$

The pressure ratio across the expansion wave is:

$$p_2/p_1 = 0.3668$$

Therefore the pressure after the expansion is:

$$p_2 = 0.3668 \text{ atm}$$

We can iterate on the shock angle to find the conditions after the oblique shock:

$$\beta_{2-3} = 36.438^\circ$$
$$\theta = 16.0000^\circ$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach numbers normal and parallel to the wave are:

$$M_{2n} = 1.5700$$
$$M_{2t} = 2.1265$$

The post-shock Mach number normal to the wave is:

$$M_{3n} = 0.6777$$

The pressure and temperature ratios across the shock are:

$$p_3/p_2 = 2.7090$$
$$T_3/T_2 = 1.3674$$

The pressure after the shock wave is:

$$p_3 = 0.994 \text{ atm}$$

We can get the post-shock Mach number parallel to the shock from the temperature ratio:

$$M_{3t} = 1.8185$$

So the post-shock Mach number is:

$$M_3 = 1.941$$

## Problem 13.197

[Difficulty: 4]

**13.197** Air at Mach 2.0 and 5 psia static pressure is turned through an angle of  $20^\circ$ . Determine the resulting static pressure and stagnation pressure when the turning is achieved through (a) a single oblique shock, (b) two oblique shocks, each turning the flow  $10^\circ$ , and (c) an isentropic compression wave system.

**Given:** Air passing through jet inlet

**Find:** Pressure after one oblique shock; after two shocks totaling same overall turn, after isentropic compression

**Solution:**

The given or available data is:

$$\begin{aligned}R &= 53.33 && \text{ft-lbf/lbm-}^\circ\text{R} \\k &= 1.4 \\M_1 &= 2 \\p_1 &= 5 && \text{psia} \\ \theta &= 20 && ^\circ\end{aligned}$$

Equations and Computations:

To find the shock angle, we have to iterate on the shock angle until we match the deflection angle, which is a function of Mach number, specific heat ratio, and shock angle.

$$\begin{aligned}\beta &= 53.423 && ^\circ \\ \theta &= 20.0000 && ^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach number normal to the wave is:

$$M_{1n} = 1.6061$$

The pressure ratio across the shock wave is:

$$p_2/p_1 = 2.8429$$

Therefore, the post-shock pressure is:

$$p_2 = 14.21 \text{ psia}$$

Now if we use two 10-degree turns, we perform two oblique-shock calculations.

For the first turn:

$$\begin{aligned}\beta_{1-2a} &= 39.314 && ^\circ \\ \theta &= 10.0000 && ^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach number normal to the wave is:

$$M_{1n} = 1.2671$$

The post-shock Mach number normal to the wave is:

$$M_{2an} = 0.8032$$

The pressure ratio across the shock wave is:

$$p_{2a}/p_1 = 1.7066$$

Therefore, the post-shock pressure is:

$$p_{2a} = 8.5329 \text{ psia}$$

So the Mach number after the first shock wave is:

$$M_{2a} = 1.6405$$

For the second turn:

$$\begin{aligned}\beta_{2a-2b} &= 49.384 && ^\circ \\ \theta &= 10.0000 && ^\circ\end{aligned}$$

We used *Solver* in *Excel* to iterate on the shock angle.

The pre-shock Mach number normal to the wave is:

$$M_{2an} = 1.2453$$

The post-shock Mach number normal to the wave is:

$$M_{2bn} = 0.8153$$

The pressure ratio across the shock wave is:

$$p_{2b}/p_{2a} = 1.6426$$

Therefore, the post-shock pressure is:

$$p_{2b} = 14.02 \text{ psia}$$

For the isentropic compression, we need to calculate the Prandtl-Meyer function for the incident flow:

$$\omega_1 = 26.3798^\circ$$

The flow out of the compression will have a Prandtl-Meyer function of:

$$\omega_{2i} = 6.3798^\circ$$

To find the exit Mach number, we need to iterate on the Mach number to match the Prandtl-Meyer function:

$$M_{2i} = 1.3076$$

$$\omega_{2i} = 6.3798^\circ$$

The pressure ratio across the compression wave is:

$$p_{2i}/p_1 = 2.7947$$


Therefore, the exit pressure is:

$$p_{2i} = 13.97 \text{ psia}$$

## Problem 13.198

[Difficulty: 3]

**13.198** Air flows isentropically at  $M = 2.5$  in a duct. There is a  $7.5^\circ$  contraction that triggers an oblique shock, which in turn reflects off a wall generating a second oblique shock. This second shock is necessary so the flow ends up flowing parallel to the channel walls after the two shocks. Find the Mach number and pressure in the contraction and downstream of the contraction. (Note that the convex corner will have expansion waves to redirect the flow along the upper wall.)



**Given:** Air flow in a duct

**Find:** Mach number and pressure at contraction and downstream;

**Solution:**

The given or available data is:

$$\begin{aligned} k &= 1.4 \\ M_1 &= 2.5 \\ \theta &= 7.5^\circ \\ p_1 &= 50 \text{ kPa} \end{aligned}$$

Equations and Computations:

For the first oblique shock (1 to 2) we need to find  $\beta$  from Eq. 13.49

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

We choose  $\beta$  by iterating or by using *Goal Seek* to target  $\theta$  (below) to equal the given  $\theta$   
Using built-in function *theta* ( $M, \beta, k$ )

$$\begin{aligned} \theta &= 7.50^\circ \\ \beta &= 29.6^\circ \end{aligned}$$

Then  $M_{1n}$  can be found from geometry (Eq. 13.47a)

$$M_{1n} = 1.233$$

Then  $M_{2n}$  can be found from Eq. 13.48a)

Using built-in function *NormM2fromM* ( $M, k$ )

$$M_{2n} = f(M_{1n}) \quad (13.48a)$$

$$M_{2n} = 0.822$$

Then, from  $M_{2n}$  and geometry (Eq. 13.47b)

$$M_2 = 2.19$$

From  $M_{1n}$  and Eq. 13.48d (using built-in function *NormpfromM(M,k)*)

$$\frac{p_2}{p_1} = f(M_{1n}) \quad (13.48d)$$

$$\begin{aligned} p_2/p_1 &= 1.61 && \text{Pressure ratio} \\ p_2 &= 80.40 \end{aligned}$$

We repeat the analysis of states 1 to 2 for states 2 to 3, to analyze the second oblique shock

We choose  $\beta$  for  $M_2$  by iterating or by using *Goal Seek* to target  $\theta$  (below) to equal the given  $\theta$   
Using built-in function *theta(M,  $\beta$ , k)*

$$\begin{aligned} \theta &= 7.50 && ^\circ \\ \beta &= 33.5 && ^\circ \end{aligned}$$

Then  $M_{2n}$  (normal to second shock!) can be found from geometry (Eq. 13.47a)

$$M_{2n} = 1.209$$

Then  $M_{3n}$  can be found from Eq. 13.48a)

Using built-in function *NormM2fromM(M,k)*

$$M_{3n} = 0.837$$

Then, from  $M_{3n}$  and geometry (Eq. 13.47b)

$$M_3 = 1.91$$

From  $M_{2n}$  and Eq. 13.48d (using built-in function *NormpfromM(M,k)*)

$$\begin{aligned} p_3/p_2 &= 1.54 && \text{Pressure ratio} \\ p_3 &= 124 \end{aligned}$$

## Problem 13.199

[Difficulty: 4]

**13.199** The geometry of the fuselage and engine cowling near the inlet to the engine of a supersonic fighter aircraft is designed so that the incoming air at  $M = 3$  is deflected 7.5 degrees, and then experiences a normal shock at the engine entrance. If the incoming air is at 50 kPa, what is the pressure of the air entering the engine? What would be the pressure if the incoming air was slowed down by only a normal shock?

**Given:** Air flow into engine

**Find:** Pressure of air in engine; Compare to normal shock

**Solution:**

The given or available data is:

$$\begin{aligned}k &= 1.4 \\p_1 &= 50 \quad \text{kPa} \\M_1 &= 3 \\ \theta &= 7.5 \quad ^\circ\end{aligned}$$

Equations and Computations:

Assuming isentropic flow deflection

$$p_0 = \text{constant}$$

$$p_{02} = p_{01}$$

For  $p_{01}$  we use Eq. 13.7a (using built-in function  $I_{senp}(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$p_{01} = 1837 \quad \text{kPa}$$

$$p_{02} = 1837 \quad \text{kPa}$$

For the deflection

$$\theta = 7.5 \quad ^\circ$$

From  $M_1$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

$$\omega_1 = 49.8 \quad ^\circ$$

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (1)$$

$$\text{Applying Eq. 1} \quad \omega_2 = \omega_1 - \theta \quad (\text{Compression!})$$

$$\omega_2 = 42.3 \quad ^\circ$$

From  $\omega_2$ , and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\begin{aligned}\text{For} \quad \omega_2 &= 42.3 \quad ^\circ \\ M_2 &= 2.64\end{aligned}$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2$  is correct)

Hence for  $p_2$  we use Eq. 13.7a

(using built-in function  $\text{Isenp}(M, k)$ )

$$p_2 = p_{02}/(p_{02}/p_2)$$

$$p_2 = 86.8 \quad \text{kPa}$$

$$\text{For the normal shock (2 to 3)} \quad M_2 = 2.64$$

From  $M_2$  and  $p_2$ , and Eq. 13.41d (using built-in function  $\text{NormpfromM}(M, k)$ )

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_1^2 - \frac{k-1}{k+1} \quad (13.41d)$$

$$p_3 = 690 \quad \text{kPa}$$

For slowing the flow down from  $M_1$  with only a normal shock, using Eq. 13.41d

$$p = 517 \quad \text{kPa}$$

## Problem 13.200


[Difficulty: 3]

**13.200** Air flows at Mach number of 1.5, static pressure 95 kPa, and is expanded by angles  $\theta_1 = 15^\circ$  and  $\theta_2 = 15^\circ$ , as shown. Find the pressure changes.

**Given:** Deflection of air flow

**Find:** Pressure changes

**Solution:**



The given or available data is:

$R =$	286.9	J/kg.K
$k =$	1.4	
$p =$	95	kPa
$M =$	1.5	
$\theta_1 =$	15	$^\circ$
$\theta_2 =$	15	$^\circ$

Equations and Computations:

We use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_a - \omega_b = \omega(M_a) - \omega(M_b) \quad (1)$$

From  $M$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega = 11.9 \quad ^\circ$$

**For the first deflection:**

Applying Eq. 1

$$\theta_1 = \omega_1 - \omega$$

$$\omega_1 = \theta_1 + \omega$$

$$\omega_1 = 26.9 \quad ^\circ$$

From  $\omega_1$ , and Eq. 13.55

(using built-in function  $\Omega(M, k)$ )

$$\text{For } \omega_1 = 26.9 \quad ^\circ$$

$$M_1 = 2.02$$

(Use *Goal Seek* to vary  $M_1$  so that  $\omega_1$  is correct)

Hence for  $p_1$  we use Eq. 13.7a

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

The approach is to apply Eq. 13.7a twice, so that  
(using built-in function *Isenp*( $M, k$ ))

$$p_1 = p(p_0/p)/(p_0/p_1)$$

$$p_1 = 43.3 \text{ kPa}$$

**For the second deflection:**

We repeat the analysis of the first deflection

Applying Eq. 1

$$\theta_2 + \theta_1 = \omega_2 - \omega$$

$$\omega_2 = \theta_2 + \theta_1 + \omega$$

$$\omega_2 = 41.9^\circ$$

(Note that instead of working from the initial state to state 2 we could have worked from state 1 to state 2 because the entire flow is isentropic)

From  $\omega_2$ , and Eq. 13.55

(using built-in function *Omega*( $M, k$ ))

$$\text{For } \omega_2 = 41.9^\circ$$

$$M_2 = 2.62$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2$  is correct)

Hence for  $p_2$  we use Eq. 13.7a

(using built-in function *Isenp*( $M, k$ ))


$$p_2 = p(p_0/p)/(p_0/p_2)$$

$$p_2 = 16.9 \text{ kPa}$$

## Problem 13.201

[Difficulty: 3]

**13.201** A flow at  $M = 2.5$  is deflected by a combination of interacting oblique shocks as shown. The first shock pair is aligned at  $30^\circ$  to the flow. A second oblique shock pair deflects the flow again so it ends up parallel to the original flow. If the pressure before any deflections is 50 kPa, find the pressure after two deflections.



**Given:** Air flow in a duct

**Find:** Mach number and pressure at contraction and downstream;

**Solution:**

The given or available data is:

$$\begin{aligned} k &= 1.4 \\ M_1 &= 2.5 \\ \beta &= 30^\circ \\ p_1 &= 50 \text{ kPa} \end{aligned}$$

Equations and Computations:

For the first oblique shock (1 to 2) we find  $\theta$  from Eq. 13.49

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

Using built-in function *theta* ( $M, \beta, k$ )

$$\theta = 7.99^\circ$$

Also,  $M_{1n}$  can be found from geometry (Eq. 13.47a)

$$M_{1n} = 1.250$$

Then  $M_{2n}$  can be found from Eq. 13.48a)

Using built-in function *NormM2fromM* ( $M, k$ )

$$M_{2n} = f(M_{1n}) \quad (13.48a)$$

$$M_{2n} = 0.813$$

Then, from  $M_{2n}$  and geometry (Eq. 13.47b)

$$M_2 = 2.17$$

From  $M_{1n}$  and Eq. 13.48d (using built-in function  $NormpfromM(M,k)$ )

$$\frac{p_2}{p_1} = f(M_{1n}) \quad (13.48d)$$

$$\begin{aligned} p_2/p_1 &= 1.66 && \text{Pressure ratio} \\ p_2 &= 82.8 \end{aligned}$$

We repeat the analysis for states 1 to 2 for 2 to 3, for the second oblique shock

We choose  $\beta$  for  $M_2$  by iterating or by using *Goal Seek* to target  $\theta$  (below) to equal the previous  $\theta$ , using built-in function  $theta(M, \beta, k)$

$$\begin{aligned} \theta &= 7.99 && ^\circ \\ \beta &= 34.3 && ^\circ \end{aligned}$$

Then  $M_{2n}$  (normal to second shock!) can be found from geometry (Eq. 13.47a)

$$M_{2n} = 1.22$$

Then  $M_{3n}$  can be found from Eq. 13.48a)

Using built-in function  $NormM2fromM(M,k)$

$$M_{3n} = 0.829$$

Then, from  $M_{3n}$  and geometry (Eq. 13.47b)

$$M_3 = 1.87$$

From  $M_{2n}$  and Eq. 13.48d (using built-in function  $NormpfromM(M,k)$ )

$$\begin{aligned} p_3/p_2 &= 1.58 && \text{Pressure ratio} \\ p_3 &= 130 \end{aligned}$$

## Problem 13.202

[Difficulty: 4]

---

**13.202** Compare the static and stagnation pressures produced by (a) an oblique shock and (b) isentropic *compression* waves as they each deflect a flow at a Mach number of 3.5 through a deflection angle of  $35^\circ$  in air for which the static pressure is 50 kPa.

---

**Given:** Mach number and deflection angle

**Find:** Static and stagnation pressures due to: oblique shock; compression wave

**Solution:**

The given or available data is:

$R =$	286.9	J/kg.K
$k =$	1.4	
$p_1 =$	50	kPa
$M_1 =$	3.5	
$\theta =$	35	$^\circ$

Equations and Computations:

**For the oblique shock:**

We need to find  $M_{1n}$

The deflection angle is  $\theta = 35^\circ$

From  $M_1$  and  $\theta$ , and Eq. 13.49

(using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

For  $\theta = 35.0^\circ$   
 $\beta = 57.2^\circ$

(Use *Goal Seek* to vary  $\beta$  so that  $\theta = 35^\circ$ )

From  $M_1$  and  $\beta$   $M_{1n} = 2.94$

From  $M_{1n}$  and  $p_1$ , and Eq. 13.48d

(using built-in function  $\text{NormpfromM}(M, k)$ )

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

$p_2 = 496 \text{ kPa}$

To find  $M_2$  we need  $M_{2n}$ . From  $M_{1n}$ , and Eq. 13.48a  
(using built-in function  $NormM2fromM(M, k)$ )

$$M_{2n}^2 = \frac{M_{1n}^2 + \frac{2}{k-1}}{\frac{2k}{k-1} M_{1n}^2 - 1} \quad (13.48a)$$

$$M_{2n} = 0.479$$

The downstream Mach number is then obtained from  
from  $M_{2n}$ ,  $\theta$  and  $\beta$ , and Eq. 13.47b

$$M_2 = M_{2n} \sin(\beta - \theta) \quad (13.47b)$$

Hence  $M_2 = 1.27$

For  $p_{02}$  we use Eq. 12.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$p_{02} = p_2 / (p_{02}/p_2)$$

$$p_{02} = 1316 \text{ kPa}$$

**For the isentropic compression wave:**

For isentropic flow  $p_0 = \text{constant}$

$$p_{02} = p_{01}$$

For  $p_{01}$  we use Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$p_{01} = 3814 \text{ kPa}$$

$$p_{02} = 3814 \text{ kPa}$$

(Note that for the oblique shock, as required by Eq. 13.48b

$$\frac{p_{02}}{p_{01}} = \frac{\left[ \frac{\frac{k+1}{2} M_{1n}^2}{1 + \frac{k-1}{2} M_{1n}^2} \right]^{k/(k-1)}}{\left[ \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \right]^{1/(k-1)}} \quad (13.48b)$$

$$p_{02}/p_{01} = 0.345$$

(using built-in function  $Normp0fromM(M, k)$ )

$$p_{02}/p_{01} = 0.345$$

(using  $p_{02}$  from the shock and  $p_{01}$ )

For the deflection  $\theta = -\theta$  (Compression)

$$\theta = -35.0^\circ$$

We use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (1)$$

From  $M_1$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega_1 = 58.5^\circ$$

Applying Eq. 1

$$\omega_2 = \omega_1 + \theta$$

$$\omega_2 = 23.5^\circ$$

From  $\omega_2$ , and Eq. 13.55

(using built-in function  $\Omega(M, k)$ )

For

$$\omega_2 = 23.5^\circ$$

$$M_2 = 1.90$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2 = 23.5^\circ$ )

Hence for  $p_2$  we use Eq. 13.7a

(using built-in function  $\text{Isenp}(M, k)$ )

$$p_2 = p_{02}/(p_{02}/p_2)$$

$$p_2 = 572 \text{ kPa}$$

## Problem 13.203


[Difficulty: 3]

**13.203** Find the incoming and intermediate Mach numbers and static pressures if, after two expansions of  $\theta_1 = 15^\circ$  and  $\theta_2 = 15^\circ$ , the Mach number is 4, and static pressure is 10 kPa.

**Given:** Deflection of air flow

**Find:** Mach numbers and pressures

**Solution**



The given or available data is:

$$\begin{aligned}
 R &= 286.9 && \text{J/kg.K} \\
 k &= 1.4 \\
 p_2 &= 10 && \text{kPa} \\
 M_2 &= 4 \\
 \theta_1 &= 15 && ^\circ \\
 \theta_2 &= 15 && ^\circ
 \end{aligned}$$

Equations and Computations:

We use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_a - \omega_b = \omega(M_a) - \omega(M_b) \quad (1)$$

From  $M$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega_2 = 65.8 \quad ^\circ$$

**For the second deflection:**

Applying Eq. 1

$$\begin{aligned}
 \omega_1 &= \omega_2 - \theta_2 \\
 \omega_1 &= 50.8 \quad ^\circ
 \end{aligned}$$

From  $\omega_1$ , and Eq. 13.55

(using built-in function  $\Omega(M, k)$ )

$$\begin{aligned}
 \text{For } \omega_1 &= 50.8 \quad ^\circ \\
 M_1 &= 3.05
 \end{aligned}$$

(Use *Goal Seek* to vary  $M_1$  so that  $\omega_1$  is correct)

Hence for  $p_1$  we use Eq. 13.7a

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

The approach is to apply Eq. 13.7a twice, so that  
(using built-in function  $Isenp(M, k)$ )

$$p_1 = p_2(p_0/p_2)/(p_0/p_1)$$

$$p_1 = 38.1 \text{ kPa}$$

**For the first deflection:**

We repeat the analysis of the second deflection

Applying Eq. 1

$$\theta_2 + \theta_1 = \omega_2 - \omega$$

$$\omega = \omega_2 - (\theta_2 + \theta_1)$$

$$\omega = 35.8^\circ$$

(Note that instead of working from state 2 to the initial state we could have worked from state 1 to the initial state because the entire flow is isentropic)

From  $\omega$ , and Eq. 13.55

(using built-in function  $Omega(M, k)$ )

$$\text{For } \omega = 35.8^\circ$$

$$M = 2.36$$

(Use *Goal Seek* to vary  $M$  so that  $\omega$  is correct)

Hence for  $p$  we use Eq. 13.7a

(using built-in function  $Isenp(M, k)$ )

$$p = p_2(p_0/p_2)/(p_0/p)$$

$$p = 110 \text{ kPa}$$

## Problem 13.204


[Difficulty: 4]

**13.204** Find the lift and drag per unit span on the airfoil shown for flight at a Mach number of 1.75 in air for which the static pressure is 50 kPa. The chord length is 1 m.

**Given:** Mach number and airfoil geometry

**Find:** Lift and drag per unit span

**Solution:**



The given or available data is:

$R =$	286.9	J/kg.K
$k =$	1.4	
$p_1 =$	50	kPa
$M_1 =$	1.75	
$\alpha =$	18	$^\circ$
$c =$	1	m

Equations and Computations:

The net force per unit span is  $F = (p_L - p_U)c$

Hence, the lift force per unit span is  $L = (p_L - p_U)c \cos(\alpha)$  (1)

The drag force per unit span is  $D = (p_L - p_U)c \sin(\alpha)$  (2)

**For the lower surface (oblique shock):**

We need to find  $M_{1n}$

The deflection angle is  $\theta = \alpha$   
 $\theta = 18 \quad ^\circ$

From  $M_1$  and  $\theta$ , and Eq. 13.49

(using built-in function  $\theta(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

For  $\theta = 18.0 \quad ^\circ$   
 $\beta = 62.9 \quad ^\circ$

(Use *Goal Seek* to vary  $\beta$  so that  $\theta$  is correct)

From  $M_1$  and  $\beta$   $M_{1n} = 1.56$

From  $M_{1n}$  and  $p_1$ , and Eq. 13.48d  
(using built-in function *NormpfromM(M,k)*)

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

$$p_2 = 133.2 \text{ kPa}$$

$$p_L = p_2$$

$$p_L = 133.2 \text{ kPa}$$

**For the upper surface (isentropic expansion wave):**

For isentropic flow  $p_0 = \text{constant}$

$$p_{02} = p_{01}$$

For  $p_{01}$  we use Eq. 13.7a  
(using built-in function *Isenp(M,k)*)

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$p_{01} = 266 \text{ kPa}$$

$$p_{02} = 266 \text{ kPa}$$

For the deflection  $\theta = \alpha$  (*Compression*)

$$\theta = 18.0^\circ$$

We use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (3)$$

From  $M_1$  and Eq. 13.55 (using built-in function *Omega(M,k)*)

$$\omega_1 = 19.3^\circ$$

Applying Eq. 3

$$\omega_2 = \omega_1 + \theta$$

$$\omega_2 = 37.3^\circ$$

From  $\omega_2$ , and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\begin{aligned} \text{For} \quad \omega_2 &= 37.3 \quad ^\circ \\ M_2 &= 2.42 \end{aligned}$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2$  is correct)

Hence for  $p_2$  we use Eq. 13.7a  
(using built-in function  $I_{senp}(M, k)$ )

$$p_2 = p_{02}/(p_{02}/p_2)$$

$$p_2 = 17.6 \quad \text{kPa}$$

$$p_U = p_2$$

$$p_U = 17.6 \quad \text{kPa}$$


$$\text{From Eq. 1} \quad L = 110.0 \quad \text{kN/m}$$

$$\text{From Eq. 2} \quad D = 35.7 \quad \text{kN/m}$$

## Problem 13.205

[Difficulty: 3]

**13.205** Consider the wedge-shaped airfoil of Problem 13.188. Suppose the oblique shock could be replaced by isentropic *compression* waves. Find the lift per unit span at the Mach number of 2.75 in air for which the static pressure is 70 kPa.



**Given:** Wedge-shaped airfoil

**Find:** Lift per unit span assuming isentropic flow

**Solution:**

The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg}\cdot\text{K} \\ k &= 1.4 \\ p &= 70 && \text{kPa} \\ M &= 2.75 \\ \delta &= 7 && ^\circ \\ c &= 1.5 && \text{m} \end{aligned}$$

Equations and Computations:

The lift per unit span is

$$L = (p_L - p_U)c \quad (1)$$

(Note that  $p_L$  acts on area  $c/\cos(\delta)$ , but its normal component is multiplied by  $\cos(\delta)$ )

**For the upper surface:**

$$\begin{aligned} p_U &= p \\ p_U &= 70 && \text{kPa} \end{aligned}$$

**For the lower surface:**

$$\theta = -\delta$$

$$\theta = -7.0^\circ$$

We use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_L - \omega = \omega(M_L) - \omega(M) \quad (2)$$

From  $M$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega = 44.7^\circ$$

Applying Eq. 2

$$\theta = \omega_L - \omega$$

$$\omega_L = \theta + \omega$$

$$\omega_L = 37.7^\circ$$

From  $\omega_L$ , and Eq. 13.55

(using built-in function  $\Omega(M, k)$ )

$$\begin{aligned} \text{For } \omega_L &= 37.7^\circ \\ M_L &= 2.44 \end{aligned}$$

(Use *Goal Seek* to vary  $M_L$  so that  $\omega_L$  is correct)

Hence for  $p_L$  we use Eq. 13.7a

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

The approach is to apply Eq. 13.7a twice, so that  
(using built-in function  $Isenp(M, k)$ )

$$p_L = p(p_0/p)/(p_0/p_L)$$

$$p_L = 113 \quad \text{kPa}$$

From Eq 1

$$L = 64.7 \quad \text{kN/m}$$

## Problem 13.206


[Difficulty: 4]

**13.206** Find the drag coefficient of the symmetric, zero angle of attack airfoil shown for a Mach number of 2.0 in air for which the static pressure is 95 kPa and temperature is 0°C. The included angles at the nose and tail are each 10°.

**Given:** Mach number and airfoil geometry

**Find:** Drag coefficient

**Solution:**



The given or available data is:

$$\begin{aligned} R &= 286.9 && \text{J/kg.K} \\ k &= 1.4 \\ p_1 &= 95 && \text{kPa} \\ M_1 &= 2 \\ \alpha &= 0 && ^\circ \\ \delta &= 10 && ^\circ \end{aligned}$$

Equations and Computations:

The drag force is

$$D = (p_F - p_R)cs \tan(\delta/2) \quad (1)$$

( $s$  and  $c$  are the span and chord)

This is obtained from the following analysis

$$\text{Airfoil thickness (frontal area)} = 2s(c/2\tan(\delta/2))$$

$$\text{Pressure difference acting on frontal area} = (p_F - p_R)$$

( $p_F$  and  $p_R$  are the pressures on the front and rear surfaces)

$$\text{The drag coefficient is} \quad C_D = D/(1/2\rho V^2 A) \quad (2)$$

But it can easily be shown that

$$\rho V^2 = p k M^2$$

Hence, from Eqs. 1 and 2

$$C_D = (p_F - p_R) \tan(\delta/2) / (1/2 \rho k M^2) \quad (3)$$

**For the frontal surfaces (oblique shocks):**

We need to find  $M_{1n}$

The deflection angle is  $\theta = \delta/2$

$$\theta = 5^\circ$$

From  $M_1$  and  $\theta$ , and Eq. 13.49

(using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

$$\begin{aligned} \text{For } \theta &= 5.0^\circ \\ \beta &= 34.3^\circ \end{aligned}$$

(Use *Goal Seek* to vary  $\beta$  so that  $\theta = 5^\circ$ )

From  $M_1$  and  $\beta$   $M_{1n} = 1.13$

From  $M_{1n}$  and  $p_1$ , and Eq. 13.48d

(using built-in function  $\text{NormpfromM}(M, k)$ )

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

$$p_2 = 125.0 \text{ kPa}$$

$$p_F = p_2$$

$$p_F = 125.0 \text{ kPa}$$

To find  $M_2$  we need  $M_{2n}$ . From  $M_{1n}$ , and Eq. 13.48a  
(using built-in function  $NormM2fromM(M, k)$ )

$$M_{2n}^2 = \frac{M_{1n}^2 + \frac{2}{k-1}}{\frac{2k}{k-1} M_{1n}^2 - 1} \quad (13.48a)$$

$$M_{2n} = 0.891$$

The downstream Mach number is then obtained from  
from  $M_{2n}$ ,  $\theta$  and  $\beta$ , and Eq. 13.47b

$$M_2 = M_{2n} \sin(\beta - \theta) \quad (13.47b)$$

Hence  $M_2 = 1.82$

For  $p_{02}$  we use Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$p_{02} = 742 \text{ kPa}$$

#### **For the rear surfaces (isentropic expansion waves):**

Treating as a new problem

Here:  $M_1$  is the Mach number after the shock  
and  $M_2$  is the Mach number after the expansion wave  
 $p_{01}$  is the stagnation pressure after the shock  
and  $p_{02}$  is the stagnation pressure after the expansion wave

$$M_1 = M_2 \text{ (shock)}$$

$$M_1 = 1.82$$

$$p_{01} = p_{02} \text{ (shock)}$$

$$p_{01} = 742 \text{ kPa}$$

For isentropic flow

$$p_0 = \text{constant}$$

$$p_{02} = p_{01}$$

$$p_{02} = 742 \text{ kPa}$$

For the deflection

$$\theta = \delta$$

$$\theta = 10.0^\circ$$

We use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (3)$$

From  $M_1$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega_1 = 21.3^\circ$$

Applying Eq. 3

$$\omega_2 = \omega_1 + \theta$$

$$\omega_2 = 31.3^\circ$$

From  $\omega_2$ , and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

For

$$\omega_2 = 31.3^\circ$$

$$M_2 = 2.18$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2 = 31.3^\circ$ )

Hence for  $p_2$  we use Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$p_2 = p_{02}/(p_{02}/p_2)$$

$$p_2 = 71.2 \text{ kPa}$$

$$p_R = p_2$$

$$p_R = 71.2 \text{ kPa}$$

Finally, from Eq. 1

$$C_D = 0.0177$$

## Problem 13.207

[Difficulty: 4]

**13.207** Plot the lift and drag per unit span, and the lift/drag ratio, as functions of angle of attack for  $\alpha = 0^\circ$  to  $18^\circ$ , for the airfoil shown, for flight at a Mach number of 1.75 in air for which the static pressure is 50 kPa. The chord length is 1 m.

**Given:** Mach number and airfoil geometry

**Find:** Plot of lift and drag and lift/drag versus angle of attack

**Solution:**

The given or available data is:

$$\begin{aligned}k &= 1.4 \\p_1 &= 50 \text{ kPa} \\M_1 &= 1.75 \\ \alpha &= 12^\circ \\c &= 1 \text{ m}\end{aligned}$$

Equations and Computations:

The net force per unit span is

$$F = (p_L - p_U)c$$


Hence, the lift force per unit span is

$$L = (p_L - p_U)c \cos(\alpha) \quad (1)$$

The drag force per unit span is

$$D = (p_L - p_U)c \sin(\alpha) \quad (2)$$

**For each angle of attack the following needs to be computed:**



**For the lower surface (oblique shock):**

We need to find  $M_{1n}$

Deflection  $\theta = \alpha$

From  $M_1$  and  $\theta$ , and Eq. 13.49

(using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

find  $\beta$

(Use *Goal Seek* to vary  $\beta$  so that  $\theta$  is the correct value)

From  $M_1$  and  $\beta$  find  $M_{1n}$

From  $M_{1n}$  and  $p_1$ , and Eq. 13.48d

(using built-in function  $\text{NormpfromM}(M, k)$ )

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

find  $p_2$

and  $p_L = p_2$

**For the upper surface (isentropic expansion wave):**

For isentropic flow  $p_0 = \text{constant}$

$$p_{02} = p_{01}$$

For  $p_{01}$  we use Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$\text{find } p_{02} = 266 \text{ kPa}$$

Deflection  $\theta = \alpha$

we use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (3)$$

From  $M_1$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\text{find } \omega_1 = 19.3^\circ$$

Applying Eq. 3  $\omega_2 = \omega_1 + \theta$  (4)

From  $\omega_2$ , and Eq. 12.55 (using built-in function  $\Omega(M, k)$ )

$$\text{From } \omega_2 \text{ find } M_2$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2$  is the correct value)

Hence for  $p_2$  we use Eq. 13.7a  
 (using built-in function  $I_{senp}(M, k)$ )

$$p_2 = p_{02}/(\rho_{02}/\rho_2)$$

$$p_U = p_2$$

Finally, from Eqs. 1 and 2, compute  $L$  and  $D$

Computed results:

$\alpha$ (°)	$\beta$ (°)	$\theta$ (°)	Error	$M_{1n}$	$p_L$ (kPa)	$\omega_2$ (°)	$\omega_2$ from $M_2$ (°)	Error	$M_2$	$p_U$ (kPa)	$L$ (kN/m)	$D$ (kN/m)	$L/D$
0.50	35.3	0.50	0.0%	1.01	51.3	19.8	19.8	0.0%	1.77	48.7	2.61	0.0227	115
1.00	35.8	1.00	0.0%	1.02	52.7	20.3	20.3	0.0%	1.78	47.4	5.21	0.091	57.3
1.50	36.2	1.50	0.0%	1.03	54.0	20.8	20.8	0.0%	1.80	46.2	7.82	0.205	38.2
2.00	36.7	2.00	0.0%	1.05	55.4	21.3	21.3	0.0%	1.82	45.0	10.4	0.364	28.6
4.00	38.7	4.00	0.0%	1.09	61.4	23.3	23.3	0.0%	1.89	40.4	20.9	1.46	14.3
5.00	39.7	5.00	0.0%	1.12	64.5	24.3	24.3	0.0%	1.92	38.3	26.1	2.29	11.4
10.00	45.5	10.0	0.0%	1.25	82.6	29.3	29.3	0.0%	2.11	28.8	53.0	9.35	5.67
15.00	53.4	15.0	0.0%	1.41	106.9	34.3	34.3	0.0%	2.30	21.3	82.7	22.1	3.73
16.00	55.6	16.0	0.0%	1.44	113.3	35.3	35.3	0.0%	2.34	20.0	89.6	25.7	3.49
16.50	56.8	16.5	0.0%	1.47	116.9	35.8	35.8	0.0%	2.36	19.4	93.5	27.7	3.38
17.00	58.3	17.0	0.0%	1.49	121.0	36.3	36.3	0.0%	2.38	18.8	97.7	29.9	3.27
17.50	60.1	17.5	0.0%	1.52	125.9	36.8	36.8	0.0%	2.40	18.2	102.7	32.4	3.17
18.00	62.9	18.0	0.0%	1.56	133.4	37.3	37.3	0.0%	2.42	17.6	110	35.8	3.08


Sum: 0.0%

Sum: 0.0%


To compute this table:

- 1) Type the range of  $\alpha$
- 2) Type in guess values for  $\beta$
- 3) Compute  $\theta$  from Eq. 13.49  
(using built-in function  $Theta(M, \beta, k)$ )
- 4) Compute the absolute error between each  $\theta$  and  $\alpha$
- 5) Compute the sum of the errors
- 6) Use *Solver* to minimize the sum by varying the  $\beta$  values  
(Note: You may need to interactively type in new  $\beta$  values if *Solver* generates  $\beta$  values that lead to no  $\theta$ )
- 7) For each  $\alpha$ ,  $M_{1n}$  is obtained from  $M_1$ , and Eq. 13.47a
- 8) For each  $\alpha$ ,  $p_L$  is obtained from  $p_1$ ,  $M_{1n}$ , and Eq. 13.48d  
(using built-in function  $NormpfromM(M, k)$ )
- 9) For each  $\alpha$ , compute  $\omega_2$  from Eq. 4
- 10) For each  $\alpha$ , compute  $\omega_2$  from  $M_2$ , and Eq. 13.55  
(using built-in function  $Omega(M, k)$ )
- 11) Compute the absolute error between the two values of  $\omega_2$
- 12) Compute the sum of the errors
- 13) Use *Solver* to minimize the sum by varying the  $M_2$  values  
(Note: You may need to interactively type in new  $M_2$  values if *Solver* generates  $\beta$  values that lead to no  $\theta$ )
- 14) For each  $\alpha$ ,  $p_U$  is obtained from  $p_{02}$ ,  $M_2$ , and Eq. 13.47a  
(using built-in function  $Isenp(M, k)$ )
- 15) Compute  $L$  and  $D$  from Eqs. 1 and 2

**Lift and Drag of an Airfoil  
as a Function of Angle of Attack**



**Lift/Drag of an Airfoil  
as a Function of Angle of Attack**



## Problem 13.208


[Difficulty: 4]

**13.208** Find the lift and drag coefficients of the airfoil of Problem 13.206 if the airfoil now has an angle of attack of  $12^\circ$ .

**Given:** Mach number and airfoil geometry

**Find:** Lift and Drag coefficients

**Solution:**



The given or available data is:

$$\begin{aligned}
 R &= 286.9 && \text{J/kg.K} \\
 k &= 1.4 \\
 p_1 &= 95 && \text{kPa} \\
 M_1 &= 2 \\
 \alpha &= 12 && ^\circ \\
 \delta &= 10 && ^\circ
 \end{aligned}$$

Equations and Computations:

Following the analysis of Example 13.14 the force component perpendicular to the major axis, per area, is

$$F_{V/sc} = 1/2 \{ (p_{FL} + p_{RL}) - (p_{FU} + p_{RU}) \} \quad (1)$$

and the force component parallel to the major axis, per area, is

$$F_{H/sc} = 1/2 \tan(\delta/2) \{ (p_{FU} + p_{FL}) - (p_{RU} + p_{RL}) \} \quad (2)$$

using the notation of the figure above.  
( $s$  and  $c$  are the span and chord)

The lift force per area is

$$F_L/sc = (F_V \cos(\alpha) - F_H \sin(\alpha))/sc \quad (3)$$

The drag force per area is

$$F_D/sc = (F_V \sin(\alpha) + F_H \cos(\alpha))/sc \quad (4)$$

The lift coefficient is  $C_L = F_L / (1/2 \rho V^2 A) \quad (5)$

But it can be shown that

$$\rho V^2 = p k M^2 \quad (6)$$

Hence, combining Eqs. 3, 4, 5 and 6

$$C_L = (F_V/sc \cos(\alpha) - F_H/sc \sin(\alpha)) / (1/2 p k M^2) \quad (7)$$

Similarly, for the drag coefficient

$$C_D = (F_V/sc \sin(\alpha) + F_H/sc \cos(\alpha))/(1/2\rho k M^2) \quad (8)$$

**For surface FL (oblique shock):**

We need to find  $M_{1n}$

The deflection angle is  $\theta = \alpha + \delta/2$

$$\theta = 17^\circ$$

From  $M_1$  and  $\theta$ , and Eq. 13.49

(using built-in function  $\text{Theta}(M, \beta, k)$ )

$$\tan \theta = \frac{2 \cot \beta (M_1^2 \sin^2 \beta - 1)}{M_1^2 (k + \cos 2\beta) + 2} \quad (13.49)$$

$$\begin{aligned} \text{For } \theta &= 17.0^\circ \\ \beta &= 48.2^\circ \end{aligned}$$

(Use *Goal Seek* to vary  $\beta$  so that  $\theta = 17^\circ$ )

From  $M_1$  and  $\beta$   $M_{1n} = 1.49$

From  $M_{1n}$  and  $p_1$ , and Eq. 13.48d

(using built-in function  $\text{NormpfromM}(M, k)$ )

$$\frac{p_2}{p_1} = \frac{2k}{k+1} M_{1n}^2 - \frac{k-1}{k+1} \quad (13.48d)$$

$$p_2 = 230.6 \text{ kPa}$$

$$p_{FL} = p_2$$

$$p_{FL} = 230.6 \text{ kPa}$$

To find  $M_2$  we need  $M_{2n}$ . From  $M_{1n}$ , and Eq. 13.48a

(using built-in function  $\text{NormM2fromM}(M, k)$ )

$$M_{2n}^2 = \frac{M_{1n}^2 + \frac{2}{k-1}}{\frac{2k}{k-1} M_{1n}^2 - 1} \quad (13.48a)$$

$$M_{2n} = 0.704$$

The downstream Mach number is then obtained from  
from  $M_{2n}$ ,  $\theta$  and  $\beta$ , and Eq. 13.47b

$$M_{2n} = M_2 \sin(\beta - \theta) \quad (13.47b)$$

Hence  $M_2 = 1.36$

For  $p_{02}$  we use Eq. 13.7a  
(using built-in function  $Isenp(M, k)$ )

$$\frac{p_0}{p} = \left[ 1 + \frac{k-1}{2} M^2 \right]^{k/(k-1)} \quad (13.7a)$$

$$p_{02} = 693 \text{ kPa}$$

**For surface RL (isentropic expansion wave):**

Treating as a new problem

Here:  $M_1$  is the Mach number after the shock  
and  $M_2$  is the Mach number after the expansion wave  
 $p_{01}$  is the stagnation pressure after the shock  
and  $p_{02}$  is the stagnation pressure after the expansion wave

$$M_1 = M_2 \text{ (shock)}$$

$$M_1 = 1.36$$

$$p_{01} = p_{02} \text{ (shock)}$$

$$p_{01} = 693 \text{ kPa}$$

For isentropic flow

$$p_0 = \text{constant}$$

$$p_{02} = p_{01}$$

$$p_{02} = 693 \text{ kPa}$$

For the deflection

$$\theta = \delta$$

$$\theta = 10.0^\circ$$

We use Eq. 13.55

$$\omega = \sqrt{\frac{k+1}{k-1}} \tan^{-1} \left( \sqrt{\frac{k-1}{k+1}} (M^2 - 1) \right) - \tan^{-1} \left( \sqrt{M^2 - 1} \right) \quad (13.55)$$

and

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (3)$$

From  $M_1$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega_1 = 7.8^\circ$$

Applying Eq. 3

$$\omega_2 = \omega_1 + \theta$$

$$\omega_2 = 17.8^\circ$$

From  $\omega_2$ , and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

For

$$\omega_2 = 17.8^\circ$$

$$M_2 = 1.70$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2 = 17.8^\circ$ )

Hence for  $p_2$  we use Eq. 13.7a

(using built-in function  $\text{Isenp}(M, k)$ )

$$p_2 = p_{02}/(p_{02}/p_2)$$

$$p_2 = 141 \text{ kPa}$$

$$p_{RL} = p_2$$

$$p_{RL} = 141 \text{ kPa}$$

**For surface FU (isentropic expansion wave):**

$$M_1 = 2.0$$

For isentropic flow

$$p_0 = \text{constant}$$

$$p_{02} = p_{01}$$

For  $p_{01}$  we use Eq. 13.7a

(using built-in function  $\text{Isenp}(M, k)$ )

$$p_{01} = 743$$

$$p_{02} = 743 \text{ kPa}$$

For the deflection

$$\theta = \alpha - \delta/2$$

$$\theta = 7.0^\circ$$

We use Eq. 13.55

and

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (3)$$

From  $M_1$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega_1 = 26.4^\circ$$

Applying Eq. 3

$$\omega_2 = \omega_1 + \theta$$

$$\omega_2 = 33.4^\circ$$

From  $\omega_2$ , and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

For

$$\omega_2 = 33.4^\circ$$

$$M_2 = 2.27$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2 = 33.4^\circ$ )

Hence for  $p_2$  we use Eq. 13.7a

(using built-in function  $I_{senp}(M, k)$ )

$$p_2 = p_{02}/(p_{02}/p_2)$$

$$p_2 = 62.8 \text{ kPa}$$

$$p_{FU} = p_2$$

$$p_{FU} = 62.8 \text{ kPa}$$

**For surface RU (isentropic expansion wave):**

Treat as a new problem.

Flow is isentropic so we could analyse from region FU to RU but instead analyse from region 1 to region RU.

$$M_1 = 2.0$$

For isentropic flow

$$p_0 = \text{constant}$$

$$p_{02} = p_{01}$$

$$p_{01} = 743 \text{ kPa}$$

$$p_{02} = 743 \text{ kPa}$$

TOTAL deflection

$$\theta = \alpha + \delta/2$$

$$\theta = 17.0^\circ$$

We use Eq. 13.55

and

$$\text{Deflection} = \omega_2 - \omega_1 = \omega(M_2) - \omega(M_1) \quad (3)$$

From  $M_1$  and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

$$\omega_1 = 26.4^\circ$$

Applying Eq. 3

$$\omega_2 = \omega_1 + \theta$$

$$\omega_2 = 43.4^\circ$$

From  $\omega_2$ , and Eq. 13.55 (using built-in function  $\Omega(M, k)$ )

For

$$\omega_2 = 43.4^\circ$$

$$M_2 = 2.69$$

(Use *Goal Seek* to vary  $M_2$  so that  $\omega_2 = 43.4^\circ$ )

Hence for  $p_2$  we use Eq. 13.7a

(using built-in function  $\text{Isenp}(M, k)$ )

$$p_2 = p_{02}/(p_{02}/p_2)$$

$$p_2 = 32.4 \text{ kPa}$$

$$p_{RU} = p_2$$

$$p_{RU} = 32.4 \text{ kPa}$$

The four pressures are:

$$p_{FL} = 230.6 \text{ kPa}$$

$$p_{RL} = 140.5 \text{ kPa}$$

$$p_{FU} = 62.8 \text{ kPa}$$

$$p_{RU} = 32.4 \text{ kPa}$$

From Eq 1

$$F_{V/sc} = 138 \text{ kPa}$$

From Eq 2

$$F_{H/sc} = 5.3 \text{ kPa}$$

From Eq 7

$$C_L = 0.503$$


From Eq 8

$$C_D = 0.127$$

## Problem 13.209

[Difficulty: 3]

**13.209** An airplane is flying at Mach 5 at an altitude of 16,764 m, where  $T_1 = 216.67$  K and  $p_1 = 9.122$  kPa. The airplane uses a scramjet engine. Two oblique shocks are formed in the intake (2) prior to entering the combustion chamber (3) at supersonic speed. The inlet and exit areas are equal,  $A_1 = A_5 = 0.2$  m<sup>2</sup>. Calculate the stagnation temperature,  $T_2/T_1$ , and the Mach number in the intake (2).



**Given:** The gas dynamic relations for compressible flow

**Find:** The shock values and angles in each region

**Solution:** Begin with the 1-D gas dynamic relations for compressible flow

**Governing equations:**

$$V_1 = M_1 \sqrt{kRT_1}; T_{0_1} = T_1 \left( 1 + \frac{k-1}{2} M_1^2 \right)$$

**Assumption:** The flow is compressible and supersonic

$$V_1 = M_1 \sqrt{kRT_a} = 5 \sqrt{1.4 \times 287 \times 216.7} = 1475.4 \frac{\text{m}}{\text{s}}$$

$$V_f = V_1 = 1475.4 \frac{\text{m}}{\text{s}}$$

$$T_{0_1} = T_1 \left( 1 + \frac{k-1}{2} M_1^2 \right) = 1300 \text{ K}$$


From (1) to (2) there is an oblique shock with  $M_1=5$  and  $\delta=10^\circ$

From the oblique shock figure (or tables)

$$\therefore \sigma_1 = 19.38^\circ$$

$$M_{1n} = M_1 \sin(\sigma)$$

$$M_{1n} = 1.659$$




From Normal Shock Tables

$$M_{1n} = 1.659$$

$$\therefore M_{2n} = 0.65119$$

$$\frac{T_2}{T_1} = 1.429$$


$$M_2 = \frac{M_{2n}}{\sin(\sigma - \delta)} = 4.0$$



## Problem 13.210

[Difficulty: 3]

**13.210** Two oblique shocks are formed in a scramjet engine intake prior to entering the combustion chamber. The inlet Mach number is  $M_1 = 5$ , the incoming air temperature is  $T_1 = 216.67 \text{ K}$ ,  $p_1 = 9.122 \text{ kPa}$ , and  $A_1 = 0.2 \text{ m}^2$ . Calculate  $M_3$  in the combustion chamber (3) if  $M_2 = 4.0$ .



**Given:** The gas dynamic relations for compressible flow

**Find:** The shock values and angles in each region

**Solution:** Begin with the 1-D gas dynamic relations for compressible flow

**Governing equations:**

$$V_1 = M_1 \sqrt{kRT_1}; T_{0_1} = T_1 \left( 1 + \frac{k-1}{2} M_1^2 \right)$$

**Assumption:** The flow is compressible and supersonic

$$V_1 = M_1 \sqrt{kRT_a} = 5 \sqrt{1.4 \times 287 \times 216.7} = 1475.4 \frac{\text{m}}{\text{s}}$$

$$V_f = V_1 = 1475.4 \frac{\text{m}}{\text{s}}$$

$$T_{0_1} = T_1 \left( 1 + \frac{k-1}{2} M_1^2 \right) = 1300 \text{ K}$$

From (2) to (3) A second oblique shock with  $M_2 = 4.0$  and  $\delta = 10^\circ$

$\therefore$  From the oblique shock tables

$$\therefore \sigma_2 = 22.23^\circ$$

and



$$M_{2n} = M_2 \sin \sigma = 1.513$$

From normal shock tables

$$\therefore M_{3n} = 0.698$$

$$M_3 = \frac{M_{3n}}{\sin(\sigma - \delta)} = \frac{0.698}{\sin 12.23}$$


$$M_3 = 3.295$$



## Problem 13.211

[Difficulty: 4]

**13.211** An airplane is flying at Mach 5, where  $T_1 = 216.67$  K. Oblique shocks form in the intake prior to entering the combustion chamber (3). The nozzle expansion ratio is  $A_5/A_4 = 5$ . The inlet and exit areas are equal,  $A_1 = A_5 = 0.2$  m<sup>2</sup>. Assuming isentropic flow with  $M_2 = 4$ ,  $M_3 = 3.295$ , and  $M_4 = 1.26$ , calculate the exit Mach number and the exhaust jet velocity (5). *Hint*: Calculate the temperature ratios in each section.



**Given:** The gas dynamic relations for compressible flow

**Find:** Exit Mach number and velocity

**Solution:** Begin with the 1-D gas dynamic relations for compressible flow

**Governing equations:**

$$V_1 = M_1 \sqrt{kRT_1}; T_{0_1} = T_1 \left( 1 + \frac{k-1}{2} M_1^2 \right)$$

**Assumption:** The flow is compressible and supersonic

$$V_1 = M_1 \sqrt{kRT_a} = 5 \sqrt{1.4 \times 287 \times 216.7} = 1475.4 \frac{\text{m}}{\text{s}}$$

Assuming  $M_2 = 4.0$ ,  $M_3 = 3.295$ , and  $M_4 = 1.26$

$$\therefore \frac{A_4}{A^*} = 1.05$$

$$\text{and } \frac{T_{04}}{T_4} = 1.317$$

$$\text{With } \frac{A_5}{A^*} = \frac{A_5}{A_4} \frac{A_4}{A^*} = 5 \times 1.05 = 5.25$$

$$M_5 = 3.23$$

$$\frac{T_{0_5}}{T_5} = 1 + \frac{k-1}{2} M_5^2 = 3.11$$

To find the temperature at state 5, we need to express the temperature in terms of the entrance temperature and known temperature ratios:

$$T_5 = T_1 \frac{T_2}{T_1} \frac{T_3}{T_2} \frac{T_4}{T_3} \frac{T_{0_4}}{T_4} \frac{T_{0_5}}{T_4} \frac{T_5}{T_{0_5}}$$

Now since the stagnation temperatures at 4 and 5 are equal (isentropic flow through the nozzle):

$$T_5 = 216.7 \text{ K} \times 1.429 \times 1.333 \times 3.744 \times 1.317 \times 1 \times \frac{1}{3.11}$$

$$T_5 = 654.5 \text{ K}$$

Therefore, the exhaust velocity is:

$$V_5 = M_5 \sqrt{kRT_5} = 3.23 \sqrt{1.4 \times 287 \times 654.5} = 1656 \frac{\text{m}}{\text{s}}$$